Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
05	SB	101	45.6/46.4	47	66

Linda Baker
LICENSED LANDSCAPE ARCHITECT

09-28-15
PLANS APPROVAL DATE

LICENSED LANDSCAPE ARCHITECT
Linda S. Baker Lic. 4407
Linda Baker
Signature
06/30/16
Renewal Date
09/28/15
Date
STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

EROSION CONTROL TYPE 1

SEQUENCE	ITEM	MATERIAL		APPLICATION RATE	DEPTH
		DESCRIPTION	TYPE		
STEP 1	COMPOST	COMPOST	MEDIUM	201 CY/ACRE	1.5"
STEP 2	HYDROSEED	SEED	MIX 4	53 LB/ACRE	
		FIBER	WOOD	500 LB/ACRE	
		TACKIFIER	PSYLLIUM	125 LB/ACRE	
STEP 3	RECP (NETTING)	NETTING	TYPE A		

EROSION CONTROL TYPE 2

SEQUENCE	ITEM	MATERIAL		APPLICATION RATE	DEPTH
		DESCRIPTION	TYPE		
STEP 1	COMPOST	COMPOST	MEDIUM	201 CY/ACRE	1.5"
STEP 2	HYDROSEED	SEED	MIX 1	43 LB/ACRE	
		FIBER	WOOD	1,500 LB/ACRE	
		TACKIFIER	PSYLLIUM	125 LB/ACRE	

EROSION CONTROL TYPE 3

SEQUENCE	ITEM	MATERIAL		APPLICATION RATE	DEPTH
		DESCRIPTION	TYPE		
STEP 1	COMPOST	COMPOST	MEDIUM	405 CY/ACRE	3"
STEP 2	INCORPORATE MATERIALS	COMPOST			8"
STEP 3	HYDROSEED	SEED	MIX 1	43 LB/ACRE	
		FIBER	WOOD	1,500 LB/ACRE	
		TACKIFIER	PSYLLIUM	125 LB/ACRE	

EROSION CONTROL TYPE 4

SEQUENCE	ITEM	MATERIAL		APPLICATION RATE
		DESCRIPTION	TYPE	
STEP 1	HYDROSEED	SEED	MIX 3	41.5 LB/ACRE
		FIBER	WOOD	1,500 LB/ACRE
		TACKIFIER	PSYLLIUM	125 LB/ACRE

EROSION CONTROL TYPE 5

SEQUENCE	ITEM	MATERIAL		APPLICATION RATE	DEPTH
		DESCRIPTION	TYPE		
STEP 1	COMPOST	COMPOST	MEDIUM	201 CY/ACRE	1.5"
STEP 2	HYDROSEED	SEED	MIX 2	25 LB/ACRE	
		FIBER	WOOD	1,500 LB/ACRE	
		TACKIFIER	PSYLLIUM	125 LB/ACRE	

EROSION CONTROL TYPE 6

SEQUENCE	ITEM	MATERIAL		APPLICATION RATE	DEPTH
		DESCRIPTION	TYPE		
STEP 1	COMPOST	COMPOST	MEDIUM	405 CY/ACRE	3"
STEP 2	INCORPORATE MATERIALS	COMPOST			8"
STEP 3	HYDROSEED	SEED	MIX 4	53 LB/ACRE	
		FIBER	WOOD	1,500 LB/ACRE	
		TACKIFIER	PSYLLIUM	125 LB/ACRE	

COMPOST SOCK 1

SEQUENCE	ITEM	MATERIAL		REMARKS
		DESCRIPTION	TYPE	
INSTALL COMPOST SOCKS AFTER RECP (NETTING)	COMPOST SOCK	MESH TUBE	8" Dia ~~BURLAP~~	INSTALL PER PLAN

1 REPLACED PER ADDENDUM No. 1 DATED JANUARY 21, 2016

EROSION CONTROL LEGEND
ECL-2

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans® LANDSCAPE ARCHITECTURE
SENIOR LANDSCAPE ARCHITECT: DENNIS REEVES
CALCULATED-DESIGNED BY: LINDA BAKER
CHECKED BY: SCOTT DOWLAN
REVISED BY: 00/00/00
DATE REVISED: 00/00/00

LAST REVISION 09-28-15
DATE PLOTTED => 20-JAN-2016
TIME PLOTTED => 12:53