

**DEPARTMENT OF TRANSPORTATION**

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30<sup>th</sup> Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

www.dot.ca.gov/hq/esc/oe



*Serious Drought.  
Help save water!*

March 24, 2015

05-SB-101-21.0/27.1  
05-1A7204  
Project ID 0512000012  
ACNHP-Q101(262)E

Addendum No. 4

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN SANTA BARBARA COUNTY IN AND NEAR GOLETA FROM MARIA YGNACIO CREEK BRIDGE TO 0.2 MILE NORTH OF CATHEDRAL OAKS OVERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Wednesday, April 1, 2015, instead of the original date of Thursday, March 26, 2015.

This addendum is being issued to set a new bid open date as shown herein, revise the project plans, the *Notice to Bidders and Special Provisions* and the *Bid book*.

Project plan sheets 23, 34, 35, 36 and 39 are replaced and attached for substitution for the like-numbered sheets.

In the Special Provisions, Section 14-11.07, is deleted.

In the Special Provisions, Section 15-1.03B, is added as attached.

In the Special Provisions, Section 15-2.02C(2), is added as attached.

In the *Bid book*, in the "Bid Item List," Items 61 and 62 are replaced.

In the *Bid book*, in the "Bid Item List," Items 77 and 78 are added.

In the *Bid book*, in the "Bid Item List," Items 14 and 76 are deleted.

Addendum No. 4  
Page 2  
March 24, 2015

05-SB-101-21.0/27.1  
05-1A7204  
Project ID 0512000012  
ACNHP-Q101(262)E

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

**[http://www.dot.ca.gov/hq/esc/oe/electronic\\_bidding/electronic\\_bidding.html](http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html)**

Inform subcontractors and suppliers as necessary.

This addendum, EBS addendum file and attachments are available for the Contractors' download on the Web site:

**[http://www.dot.ca.gov/hq/esc/oe/project\\_ads\\_addenda/05/05-1A7204](http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/05/05-1A7204)**

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

*for* 

SHARRI BENDER EHLERT  
District Director  
District 6 Central Region

Attachments

**Replace section 15-1.03B with:**

**15-1.03B Residue Containing Lead from Paint and Thermoplastic**

Residue from grinding or cold planing contains lead from paint and thermoplastic. The average lead concentrations are less than 1,000 mg/kg total lead and 5 mg/L soluble lead. This residue:

1. Is a nonhazardous waste
2. Does not contain heavy metals in concentrations that exceed thresholds established by the Health and Safety Code and 22 CA Code of Regs
3. Is not regulated under the Federal Resource Conservation and Recovery Act (RCRA), 42 USC § 6901 et seq.

Submit a lead compliance plan under section 7-1.02K(6)(j)(ii).

Payment for a lead compliance plan is not included in the payment for existing facilities work.

Payment for handling, removal, and disposal of grinding or cold planing residue that is a nonhazardous waste is included in the payment for the type of removal work involved.

**Replace section 15-2.02C(2) with:**

**15-2.02C(2) Remove Traffic Stripes and Pavement Markings Containing Lead**

Residue from removing traffic stripes and pavement markings contains lead from the paint or thermoplastic. The average lead concentrations are less than 1,000 mg/kg total lead and 5 mg/L soluble lead. This residue:

1. Is a nonhazardous waste
2. Does not contain heavy metals in concentrations that exceed thresholds established by the Health and Safety Code and 22 CA Code of Regs
3. Is not regulated under the Federal Resource Conservation and Recovery Act (RCRA), 42 USC § 6901 et seq.

Submit a lead compliance plan under section 7-1.02K(6)(j)(ii).

Payment for a lead compliance plan is not included in the payment for existing facilities work.

Payment for handling, removal, and disposal of pavement residue that is a nonhazardous waste is included in the payment for the type of removal work involved.

**BID ITEM LIST**  
**05-1A7204**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	070030	LEAD COMPLIANCE PLAN	LS	LUMP SUM	LUMP SUM	
2	080050	PROGRESS SCHEDULE (CRITICAL PATH METHOD)	LS	LUMP SUM	LUMP SUM	
3	090100	TIME-RELATED OVERHEAD (WDAY)	WDAY	160		
4	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
5	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
6	120165	CHANNELIZER (SURFACE MOUNTED)	EA	40		
7	028585	TEMPORARY ALTERNATIVE CRASH CUSHION	EA	4		
8	028586	TEMPORARY SIGNAL POWER	LS	LUMP SUM	LUMP SUM	
9	128652	PORTABLE CHANGEABLE MESSAGE SIGN (LS)	LS	LUMP SUM	LUMP SUM	
10	129000	TEMPORARY RAILING (TYPE K)	LF	500		
11	130100	JOB SITE MANAGEMENT	LS	LUMP SUM	LUMP SUM	
12	130200	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM	LUMP SUM	
13	130900	TEMPORARY CONCRETE WASHOUT	LS	LUMP SUM	LUMP SUM	
14	BLANK					
15	141120	TREATED WOOD WASTE	LB	119,000		
16	150661	REMOVE GUARDRAIL	LF	28,200		
17	150715	REMOVE THERMOPLASTIC PAVEMENT MARKING	SQFT	4,530		
18	150722	REMOVE PAVEMENT MARKER	EA	8,620		
19	150770	REMOVE ASPHALT CONCRETE PAVEMENT (SQFT)	SQFT	3,110		
20	150771	REMOVE ASPHALT CONCRETE DIKE	LF	48,700		

**BID ITEM LIST**  
**05-1A7204**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
61	832006	MIDWEST GUARDRAIL SYSTEM (STEEL POST)	LF	23,400		
62	832017	MIDWEST GUARDRAIL SYSTEM (8' POST)	LF	2,700		
63	028587	CONCRETE BARRIER (TRANSITION)	LF	11		
64 (F)	833142	CONCRETE BARRIER (TYPE 26 MODIFIED)	LF	41		
65	839543	TRANSITION RAILING (TYPE WB-31)	EA	12		
66	839581	END ANCHOR ASSEMBLY (TYPE SFT)	EA	28		
67	839584	ALTERNATIVE IN-LINE TERMINAL SYSTEM	EA	10		
68	839585	ALTERNATIVE FLARED TERMINAL SYSTEM	EA	19		
69	840515	THERMOPLASTIC PAVEMENT MARKING	SQFT	4,530		
70	840560	THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	LF	220,000		
71	850101	PAVEMENT MARKER (NON-REFLECTIVE)	EA	4,820		
72	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	3,810		
73	860090	MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION	LS	LUMP SUM	LUMP SUM	
74	028588	MODIFY WIRELESS VEHICLE DETECTOR SYSTEM	LS	LUMP SUM	LUMP SUM	
75	861502	MODIFY SIGNAL	LS	LUMP SUM	LUMP SUM	
76	BLANK					
77	150714	REMOVE THERMPLASTIC TRAFFIC STRIPE	LF	21,600		
78	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

**TOTAL BID:**

**\$**

---