Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
05	SLO	101	12.4/29.7	30	54

REGISTERED CIVIL ENGINEER 3-18-16 DATE

3-21-16
PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER JACKSON S.L. HO No. 75625 Exp 6-30-16 CIVIL STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

PAVEMENT STRUCTURE

SHEET No.	Loc No.	MINOR CONCRETE (EXPOSED AGGREGATE CONCRETE)	MINOR CONCRETE (STAMPED CONCRETE)	CLASS 2 AGGREGATE BASE (CY)	MINOR HOT MIX ASPHALT	(N) MINOR CONCRETE (POST SLEEVE)	(N) CLASS II PERMEABLE MATERIAL (POST SLEEVE)	REMOVE CONCRETE CURB (LF)
		SQFT	SQFT	CY	TON	CY	CY	LF
C-4	1		2,625	16.5	7.5	0.68	0.08	
C-4	2		1,399	8.8	~~7.2~~ 7.3	0.34	0.04	
C-4	3		644	4.1	2.2	1.36	0.16	
C-5	4		5,360	33.7	16.3	2.38	0.28	
C-5	5		2,434	15.3	7.5	0.34	0.04	
C-6	6		2,287	14.4	~~11.4~~ 11.6	0.34	0.04	
C-6	7		506	3.2	2.6	0.68	0.08	
C-6	8		840	5.3	5.2			
C-7	9		5,114	32.2	23.9	0.34	0.04	
C-7	10		2,551	16.1	12.3	0.34	0.04	
C-8	11		2,359	14.9	11.4	0.34	0.04	
C-8	12		981	6.2	6.1	0.34	0.04	
C-8	13		1,764	11.1	8.2	0.34	0.04	
C-9	14		1,459	9.2	7.4			
C-9	15		374	2.4	3.1	0.34	0.04	
C-9	16		1,995	12.6	11.4	0.34	0.04	
C-10	17		3,457	21.8	10.7	0.34		
C-10	18		~~3,176~~ 931	~~20.0~~ 5.9	~~15.6~~ 6.4	0.34	0.04	
C-11	19		1,918	12.1	11.0	0.34	0.04	
C-11	20		4,109	25.9	19.9	0.68	0.08	
C-12	21	1,345		8.5	12.0	0.34	0.04	
C-12	22	2,331		14.7	20.6			
C-13	23	1,749		11.0	8.4	0.34	0.04	4.0
C-13	24	1,224		7.7	11.5	0.34	0.04	
C-14	25	1,001		6.3	15.8	0.34	0.04	
C-14	26	478		3.0	9.0	0.68	0.08	
C-14	27	1,925		12.1	23.1	0.34	0.04	
C-15	28	788		5.0	11.8	0.34	0.04	
C-15	29	2,705		17.0	~~12.3~~ 12.6	0.34	0.04	
C-15	30	2,366		14.9	~~9.5~~ 9.7	0.34	0.04	
C-16	31	2,032		12.8	~~48.5~~ 28.9	0.34	0.04	
C-16	32	2,612		16.4	~~11.5~~ 11.7	0.34	0.04	
C-16	33	1,099		6.9	~~5.9~~ 6.0	0.34	0.04	
Q-1	Var				0.2			
TOTAL		21,655	~~45,352~~ 43,107	~~421.9~~ 408.0	~~401.0~~ 373.3			4.0

(N) - NOT A SEPARATE PAY ITEM, FOR INFORMATION ONLY

2

EARTHWORK

SHEET No.	Loc No.	ROADWAY EXCAVATION	(N) EMBANKMENT	ROADWAY EXCAVATION (TYPE Z-2) (AERIALLY DEPOSITED LEAD)
		CY	CY	CY
C-4	1	44.0		21.2
C-4	2	15.1		13.2
C-4	3	7.6		4.9
C-5	4	131.8		
C-5	5	53.0		21.6
C-6	6	48.1		
C-6	7	7.7		6.0
C-6	8	21.7	3.3	
C-7	9	191.9		
C-7	10	99.8		
C-8	11	117.4		
C-8	12	20.9		
C-8	13	31.3		15.3
C-9	14	72.7		
C-9	15	8.2		
C-9	16	42.3		
C-10	17	128.1		
C-10	18	21.5		10.2
C-11	19	67.8	0.5	
C-11	20	~~37.7~~ 104.7		~~101.5~~ 34.5
C-12	21	27.9		12.6
C-12	22	90.9		25.7
C-13	23	37.6		~~14.7~~ 14.6
C-13	24	36.0		
C-14	25	32.4		
C-14	26	10.7		
C-14	27	63.0		
C-15	28	6.1	0.5	7.5
C-15	29	55.9		
C-15	30	~~69.9~~ 67.9		
C-16	31	68.4		
C-16	32	71.2		21.4
C-16	33	29.0		10.3
TOTAL		~~1,767.4~~ 1,832.6		~~286.2~~ 219.0

(N) - NOT A SEPARATE PAY ITEM, FOR INFORMATION ONLY

2

DRAINAGE INLET

SHEET No.	Loc No.	ADJUST INLET	MISCELLANEOUS IRON AND STEEL	(N) TYPE 24-12X GRATE	TEMPORARY DRAINAGE INLET PROTECTION
		EA	LB	EA	EA
C-4	1				1
C-5	4				1
C-5	5				1
C-6	7				1
C-6	8				1
C-7	9	1	239	1	1
C-7	10				1
C-8	11				1
C-8	12				1
C-8	13				1
C-9	14				1
C-9	15				1
C-10	17				1
C-10	18				1
C-11	20				3
C-12	21				2
C-12	22				1
C-13	23				1
C-13	24				1
C-15	30				1
C-16	31				1
C-16	32				1
C-16	33				1
TOTAL		1	239		26

(N) - NOT A SEPARATE PAY ITEM, FOR INFORMATION ONLY

VEGETATION CONTROL

SHEET No.	Loc No.	VEGETATION CONTROL (MINOR CONCRETE)
		SQYD
C-4	3	105
TOTAL		105

ADJUST PULLBOX

SHEET No.	Loc No.	ADJUST PULL BOX
		EA
C-9	16	1
C-15	30	3
TOTAL		4

HOT MIX ASPHALT DIKE TRANSITION

SHEET No.	Loc No.	PLACE HOT MIX ASPHALT DIKE (TYPE A)	MINOR HOT MIX ASPHALT
		LF	TON
C-7	10	5.0	0.06
C-9	14	5.0	0.06
C-10	17	5.0	0.06
C-12	22	5.0	0.06
TOTAL		20.0	0.24 *

* QUANTITIES INCLUDED IN PAVEMENT STRUCTURE QUANTITY

2 **REPLACED PER ADDENDUM No. 2 DATED AUGUST 18, 2016**

SUMMARY OF QUANTITIES

Q-1

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans DESIGN
FUNCTIONAL SUPERVISOR: DAVID BEARD
CALCULATED-DESIGNED BY: JACKSON HO
CHECKED BY: STEVE SENET
REVISED BY
DATE REVISED

LAST REVISION 03-18-16
DATE PLOTTED => 15-AUG-2016
TIME PLOTTED => 15:57