

**DEPARTMENT OF TRANSPORTATION**

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30<sup>th</sup> Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

www.dot.ca.gov/hq/esc/oe



*Serious Drought.  
Help save water!*

February 12, 2016

05-Mon,SLO-41, 101-Var

05-1G3204

Project ID 0514000141

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN MONTEREY AND SAN LUIS OBISPO COUNTIES AT VARIOUS LOCATIONS, and to revise the *Notice to Bidders and Special Provisions*.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Thursday, February 18, 2016.

In the Special Provisions, Section 15-5.06A(2) and Section 15-5.06A(3) are added as follows:

**“Replace the 3rd paragraph of section 15-5.06A(2) with:**

Submit test samples of methacrylate resins, polyester resins, and aggregates with a certificate of compliance and manufacturer’s test results 15 days before use.

**Add to section 15-5.06A(3):**

Place polyester concrete overlay:

1. On Portland cement concrete no sooner than 28 days after concrete placement.
2. On Portland cement based RSC no sooner than 14 days after concrete placement and your test results for prequalification of RSC show that the concrete attained at least 3,500 psi compressive strength.
3. On RSC using hydraulic cement other than Portland cement no sooner than 72 hours after concrete placement and your test results for prequalification of RSC show that the concrete attained at least 3,500 psi compressive strength.

In the Special Provisions, Section 15-5.06C(1) is added as follows:

**Replace the 11th paragraph of section 15-5.06C(1) with:**

Clean the deck by vacuuming, then blow the deck clean with oil-free compressed air. Dust must not be blown into the air while blowing deck.

**Delete the 14th paragraph of section 15-5.06C(1).”**

*“Provide a safe, sustainable, integrated and efficient transportation system  
to enhance California’s economy and livability”*

Addendum No.1  
Page 2  
February 12, 2016

05-Mon,SLO-41, 101-Var  
05-1G3204  
Project ID 0514000141

In the Special Provisions, Section 51-1.01A is added as follows:

**"Add to section 51-1.01A.**

Concrete for Nacimiento River Bridge, bridge no. 44-0139R, Span 3 hinge, and Curbaril Avenue OC. Bent 4, must comply with one of the following:

1. Cure for at least 5 days before opening to traffic
2. Comply with the specifications for RSC"

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

**[http://www.dot.ca.gov/hq/esc/oe/electronic\\_bidding/electronic\\_bidding.html](http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html)**

Inform subcontractors and suppliers as necessary.

This addendum and EBS addendum file are available for the Contractors' download on the Web site:

**[http://www.dot.ca.gov/hq/esc/oe/project\\_ads\\_addenda/05/05-1G3204](http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/05/05-1G3204)**

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

SHARRI BENDER EHLERT  
District Director  
District 6 Central Region