

**\*\* WARNING \*\* WARNING \*\* WARNING \*\* WARNING \*\***  
**This document is intended for informational purposes only.**

Users are cautioned that Caltrans does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders and non-bidder packages, write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone and fax number, P.O. Box and street address so that you can receive addenda.

Note: Addenda information is NOT included with the electronic documents available via electronic file transfer. Only bidder or non-bidder package holders listed with the Caltrans Plans and Bid Documents section as described above will receive addenda information.



**STATE OF CALIFORNIA**  
**DEPARTMENT OF TRANSPORTATION**

---

**NOTICE TO CONTRACTORS**  
**AND**  
**SPECIAL PROVISIONS**  
**FOR HIGHWAY PLANTING ON STATE HIGHWAY IN**  
**SAN LUIS OBISPO COUNTY IN AND NEAR ATASCADERO FROM 0.1 km**  
**WEST OF ROUTE 101 TO 1.9 km EAST OF SALINAS RIVER VIADUCT**

**DISTRICT 05, ROUTE 41**

---

**For Use in Connection with Standard Specifications Dated JULY 1999, Standard Plans Dated JULY 1999, and Labor Surcharge and Equipment Rental Rates.**

---

**CONTRACT NO. 05-345224**  
**05-SLO-41-25.5/31.7**

**Bids Open: September 19, 2000**  
**Dated: August 21, 2000**

\*\*\*\*\*

# IMPORTANT SPECIAL NOTICES

\*\*\*\*\*

- **SURETY 2000**

Caltrans is conducting a pilot program in cooperation with Surety 2000, to test electronic bond verification systems. The purpose of the pilot program is to test the use of Surety 2000 for verifying a bidder's bond electronically.

Surety 2000 is an Internet-based surety verification and security system, developed in conjunction with the surety industry. Surety agents may contact Surety 2000 at 1-800-660-3263.

Bidders are encouraged to participate in the pilot program. To participate, the bidder is asked to provide the "Authorization Code" provided by Surety 2000, on a separate sheet, together with the standard bidder's bond required by the specifications. The bidder's surety agent may obtain the "Authorization Code" from Surety 2000.

The Department will use the "Authorization Code" to access the Surety 2000 database, and independently verify the actual bidder's bond and document the functioning of the Surety 2000 system.

"Authorization Codes" will be used only to verify bidder's bonds, and only as part of the pilot program. The use of "Authorization Codes" will not be accepted in lieu of the bidder's bond or other bidder's security required in the specifications during the pilot study.

The function of the Surety 2000 system is to provide an easier way for Contractors to protect their bid security, and to discourage fraud. This system is available to all California admitted sureties and surety agents.

The results of the pilot study will be tabulated, and at some time in the future, the Department may consider accepting electronic bidder's bond verification in lieu of the bidder's bond specified.



# TABLE OF CONTENTS

NOTICE TO CONTRACTORS.....	1
COPY OF ENGINEER'S ESTIMATE .....	3
SPECIAL PROVISIONS .....	5
SECTION 1. SPECIFICATIONS AND PLANS.....	5
SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS.....	5
2-1.01 GENERAL.....	5
2-1.02 DISABLED VETERAN BUSINESS ENTERPRISE (DVBE).....	5
2-1.03 DVBE GOAL FOR THIS PROJECT .....	6
2-1.04 SUBMISSION OF DVBE INFORMATION .....	7
2-1.05 SMALL BUSINESS PREFERENCE.....	7
2-1.06 CALIFORNIA COMPANY PREFERENCE .....	8
SECTION 3. AWARD AND EXECUTION OF CONTRACT.....	8
SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES .....	9
SECTION 5. GENERAL .....	9
SECTION 5-1. MISCELLANEOUS .....	9
5-1.01 PLANS AND WORKING DRAWINGS .....	9
5-1.015 LABORATORY .....	9
5-1.02 LABOR NONDISCRIMINATION .....	9
5-1.03 INTEREST ON PAYMENTS .....	10
5-1.04 PUBLIC SAFETY .....	10
5-1.05 SURFACE MINING AND RECLAMATION ACT.....	11
5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES.....	11
5-1.07 YEAR 2000 COMPLIANCE.....	11
5-1.08 SUBCONTRACTOR AND DVBE RECORDS.....	12
5-1.086 PERFORMANCE OF DVBE SUBCONTRACTORS AND SUPPLIERS .....	12
5-1.09 SUBCONTRACTING .....	12
5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS .....	13
5-1.11 PAYMENTS .....	13
SECTION 6. (BLANK).....	13
SECTION 7. (BLANK).....	13
SECTION 8. MATERIALS .....	13
SECTION 8-1. MISCELLANEOUS .....	13
8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS .....	13
8-1.02 APPROVED TRAFFIC PRODUCTS.....	20
PAVEMENT MARKERS, PERMANENT TYPE .....	20
PAVEMENT MARKERS, TEMPORARY TYPE.....	20
STRIPING AND PAVEMENT MARKING MATERIALS .....	21
CLASS 1 DELINEATORS.....	21
CHANNELIZERS .....	21
CONICAL DELINEATORS, 1070 mm (For 700 mm Traffic Cones, see Standard Specifications) .....	22
OBJECT MARKERS.....	22
TEMPORARY RAILING (TYPE K) REFLECTORS AND CONCRETE BARRIER MARKERS .....	22
THRIE BEAM BARRIER MARKERS (For use to the left of traffic).....	22
CONCRETE BARRIER DELINEATORS, 400 mm (For use to the right of traffic. When mounted on top of barrier, places top of reflective element at 1200 mm) .....	22
CONCRETE BARRIER-MOUNTED MINI-DRUM (260 mm x 360 mm x 570 mm) .....	22
SOUND WALL DELINEATOR (Applied to a vertical surface. Top of reflective element at 1200 mm) .....	22
GUARD RAILING DELINEATOR (Top of reflective element at 1200 mm above plane of roadway) .....	23
RETROREFLECTIVE SHEETING .....	23
SIGN SUBSTRATE FOR CONSTRUCTION AREA SIGNS .....	24

SECTION 9. (BLANK).....	24
SECTION 10. CONSTRUCTION DETAILS.....	24
SECTION 10-1. GENERAL.....	24
10-1.01 ORDER OF WORK.....	24
10-1.02 WATER POLLUTION CONTROL.....	24
WATER POLLUTION CONTROL PROGRAM PREPARATION, APPROVAL AND UPDATES.....	25
WPCP IMPLEMENTATION.....	26
MAINTENANCE.....	27
PAYMENT.....	27
10-1.03 PRESERVATION OF PROPERTY.....	27
10-1.04 DAMAGE REPAIR.....	27
10-1.05 OBSTRUCTIONS.....	28
10-1.06 CONSTRUCTION AREA SIGNS.....	28
10-1.07 MAINTAINING TRAFFIC.....	29
SECTION 10-2. HIGHWAY PLANTING AND IRRIGATION SYSTEMS.....	29
10-2.01 GENERAL.....	29
10-2.02 EXISTING HIGHWAY IRRIGATION FACILITIES.....	29
LOCATE EXISTING CROSSEOVERS AND CONDUITS.....	29
CHECK AND TEST EXISTING IRRIGATION FACILITIES.....	30
10-2.03 HIGHWAY PLANTING.....	30
HIGHWAY PLANTING MATERIALS.....	30
ROADSIDE CLEARING.....	30
PESTICIDES.....	31
PLANTING.....	31
FOLIAGE PROTECTOR.....	32
WILD FLOWER SEEDING.....	32
MEASUREMENT AND PAYMENT.....	33
PLANT ESTABLISHMENT WORK.....	33
10-2.04 IRRIGATION SYSTEMS.....	34
VALVE BOXES.....	34
ELECTRIC AUTOMATIC IRRIGATION COMPONENTS.....	34
IRRIGATION SYSTEMS FUNCTIONAL TEST.....	35
BACKFLOW PREVENTER ASSEMBLIES.....	35
TESTING BACKFLOW PREVENTERS.....	36
SPRINKLERS.....	36
SPRINKLER (TYPE D).....	36
WYE STRAINERS.....	36
VALVE ASSEMBLY UNIT.....	36
BALL VALVE.....	37
FINAL IRRIGATION SYSTEM CHECK.....	37
SECTION 10-3. ELECTRICAL SYSTEMS.....	37
10-3.01 DESCRIPTION.....	37
10-3.02 COST BREAK-DOWN.....	37
10-3.03 CONDUIT.....	38
10-3.04 PULL BOXES.....	38
10-3.05 CONDUCTORS AND WIRING.....	38
10-3.06 ELECTRIC SERVICE (IRRIGATION).....	38
10-3.07 IRRIGATION CONTROLLER ENCLOSURE CABINET.....	39
SECTION 11. (BLANK).....	39
SECTION 12. (BLANK).....	39
SECTION 13. RELATIONS WITH RAILROAD.....	39

# STANDARD PLANS LIST

The Standard Plan sheets applicable to this contract include, but are not limited to those indicated below. The Revised Standard Plans (RSP) and New Standard Plans (NSP) which apply to this contract are included as individual sheets of the project plans.

A10A	Abbreviations
A10B	Symbols
H1	Planting and Irrigation - Abbreviations
H2	Planting and Irrigation - Symbols
H3	Planting and Irrigation Details
H4	Planting and Irrigation Details
H5	Planting and Irrigation Details
H7	Planting and Irrigation Details
H8	Planting and Irrigation Details
RS1	Roadside Signs, Typical Installation Details No. 1
RS2	Roadside Signs - Wood Post, Typical Installation Details No. 2
ES-1A	Signal, Lighting and Electrical Systems - Symbols and Abbreviations
ES-1B	Signal, Lighting and Electrical Systems - Symbols and Abbreviations
ES-2C	Signal, Lighting and Electrical Systems - Service Equipment Notes, Type III Series
ES-2E	Signal, Lighting and Electrical Systems - Service Equipment and Typical Wiring Diagram Type III-B Series
ES-3A	Signal, Lighting and Electrical Systems - Controller Cabinet Details
ES-3C	Signal, Lighting and Electrical Systems - Controller Cabinet Details
ES-3H	Signal, Lighting and Electrical Systems – Irrigation Controller Enclosure Cabinet
ES-8	Signal, Lighting and Electrical Systems - Pull Box Details
ES-13A	Signal, Lighting and Electrical Systems - Splicing Details





## DEPARTMENT OF TRANSPORTATION

---

### NOTICE TO CONTRACTORS

---

**CONTRACT NO. 05-345224**

**05-SLO-41-25.5/31.7**

Sealed proposals for the work shown on the plans entitled:

**STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROJECT PLANS FOR HIGHWAY  
PLANTING ON STATE HIGHWAY IN SAN LUIS OBISPO COUNTY IN AND NEAR ATASCADERO FROM  
0.1 km WEST OF ROUTE 101 TO 1.9 km EAST OF SALINAS RIVER VIADUCT**

will be received at the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, CA 95814, until 2 o'clock p.m. on September 19, 2000, at which time they will be publicly opened and read in Room 0100 at the same address.

Proposal forms for this work are included in a separate book entitled:

**STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROPOSAL AND CONTRACT FOR  
HIGHWAY PLANTING ON STATE HIGHWAY IN SAN LUIS OBISPO COUNTY IN AND NEAR ATASCADERO  
FROM 0.1 km WEST OF ROUTE 101 TO 1.9 km EAST OF SALINAS RIVER VIADUCT**

General work description: Highway Planting and Irrigation System to be Installed.

This project has a goal of 3 percent disabled veteran business enterprise (DVBE) participation.

No prebid meeting is scheduled for this project.

Bids are required for the entire work described herein.

At the time this contract is awarded, the Contractor shall possess either a Class A license or a Class C-27 license.

The Contractor must also be properly licensed at the time the bid is submitted, except that on a joint venture bid a joint venture license may be obtained by a combination of licenses after bid opening but before award in conformance with Business and Professions Code, Section 7029.1.

This contract is subject to state contract nondiscrimination and compliance requirements pursuant to Government Code, Section 12990.

Preference will be granted to bidders properly certified as a "Small Business" as determined by the Department of General Services, Office of Small Business Certification and Resources at the time of bid opening in conformance with the provisions in Section 2-1.05, "Small Business Preference," of the special provisions, and Section 1896 et seq, Title 2, California Code of Regulations. A form for requesting a "Small Business" preference is included with the bid documents. Applications for status as a "Small Business" must be submitted to the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814, Telephone No. (916) 322-5060.

A reciprocal preference will be granted to "California company" bidders in conformance with Section 6107 of the Public Contract Code. (See Sections 2 and 3 of the special provisions.) A form for indicating whether bidders are or are not a "California company" is included in the bid documents and is to be filled in and signed by all bidders.

The Caltrans Central Region Construction Office is located at 850 L Street, Fresno, CA 93721-2615. The District 05 Duty Senior for this project can be reached at (805) 549-3481, or by fax at (805) 549-3523. The Department will consider bidder inquiries only when a completed Bidder Inquiry Form is submitted. The Bidder Inquiry Form is available on the Internet at <http://www.dot.ca.gov/dist6/construction>. To the extent feasible and at the discretion of the Department, completed Bidder Inquiry Forms submitted for consideration will be investigated, and responses will be posted on the Internet at <http://www.dot.ca.gov/dist6/construction>.

Project plans, special provisions, and proposal forms for bidding this project can only be obtained at the Department of Transportation, Plans and Bid Documents, Room 0200, MS #26, Transportation Building, 1120 N Street, Sacramento, California 95814, FAX No. (916) 654-7028, Telephone No. (916) 654-4490. Use FAX orders to expedite orders for project plans, special provisions and proposal forms. FAX orders must include credit card charge number, card expiration date and authorizing signature. Project plans, special provisions, and proposal forms may be seen at the above Department of Transportation office and at the offices of the District Directors of Transportation at Irvine, Oakland, and the district in which the work is situated. Standard Specifications and Standard Plans are available through the State of California, Department of Transportation, Publications Unit, 1900 Royal Oaks Drive, Sacramento, CA 95815, Telephone No. (916) 445-3520.

Cross sections for this project are not available.

The successful bidder shall furnish a payment bond and a performance bond.

Pursuant to Section 1773 of the Labor Code, the general prevailing wage rates in the county, or counties, in which the work is to be done have been determined by the Director of the California Department of Industrial Relations. These wages are set forth in the General Prevailing Wage Rates for this project, available at the Labor Compliance Office at the offices of the District Director of Transportation for the district in which the work is situated, and available from the California Department of Industrial Relations' Internet Web Site at: <http://www.dir.ca.gov>. Future effective general prevailing wage rates which have been predetermined and are on file with the Department of Industrial Relations are referenced but not printed in the general prevailing wage rates.

DEPARTMENT OF TRANSPORTATION

Deputy Director Transportation Engineering

Dated August 21, 2000

LSB

**COPY OF ENGINEER'S ESTIMATE**  
**(NOT TO BE USED FOR BIDDING PURPOSES)**

**05-345224**

Item	Item Code	Item	Unit of Measure	Estimated Quantity
1	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM
2	200002	ROADSIDE CLEARING	LS	LUMP SUM
3	202011	MULCH	M3	310
4	204035	PLANT (GROUP A)	EA	1154
5	204038	PLANT (GROUP U)	EA	40
6	205051	FOLIAGE PROTECTOR	EA	577
7	204036	PLANT (GROUP B)	EA	5
8	204053	WILD FLOWER SEEDING	HA	.3
9	204099	PLANT ESTABLISHMENT WORK	LS	LUMP SUM
10	206560	CONTROL AND NEUTRAL CONDUCTORS	LS	LUMP SUM
11	206611	25 MM ELECTRIC REMOTE CONTROL VALVE	EA	11
12	206612	32 MM ELECTRIC REMOTE CONTROL VALVE	EA	1
13	206613	40 MM ELECTRIC REMOTE CONTROL VALVE	EA	3
14	206749	8 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	EA	1
15	206751	12 STATION IRRIGATION CONTROLLER (WALL MOUNTED)	EA	1
16 (F)	208214	15 MM PLASTIC PIPE (IRRIGATION LINE)	M	4470
17 (F)	208249	20 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	4790
18 (F)	208250	25 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	740
19 (F)	208251	32 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	400
20 (F)	208252	40 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	750

Item	Item Code	Item	Unit of Measure	Estimated Quantity
21 (F)	208253	50 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	440
22 (F)	208255	75 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	30
23	208434	40 MM BACKFLOW PREVENTER ASSEMBLY	EA	2
24	208482	SPRINKLER (TYPE C-2)	EA	602
25	208488	25 MM GATE VALVE	EA	1
26	208490	40 MM GATE VALVE	EA	1
27	208491	50 MM GATE VALVE	EA	2
28	208505	25 MM MANUAL CONTROL VALVE	EA	1
29	208509	25 MM WYE STRAINER	EA	2
30	208526	SPRINKLER (TYPE D-1)	EA	585
31	019644	VALVE ASSEMBLY UNIT	EA	3
32	019645	CAM COUPLER ASSEMBLY	EA	2
33	208683	BALL VALVE	EA	6
34	860640	IRRIGATION CONTROLLER ENCLOSURE CABINET	EA	2
35 (S)	860797	ELECTRIC SERVICE (IRRIGATION)	LS	LUMP SUM

**STATE OF CALIFORNIA**  
**DEPARTMENT OF TRANSPORTATION**

---

**SPECIAL PROVISIONS**

**Annexed to Contract No. 05-345224**

**SECTION 1. SPECIFICATIONS AND PLANS**

The work embraced herein shall conform to the provisions in the Standard Specifications dated July 1999, and the Standard Plans dated July 1999, of the Department of Transportation insofar as the same may apply, and these special provisions.

Amendments to the Standard Specifications set forth in these special provisions shall be considered as part of the Standard Specifications for the purposes set forth in Section 5-1.04, "Coordination and Interpretation of Plans, Standard Specifications and Special Provisions," of the Standard Specifications. Whenever either the term "Standard Specifications is amended" or the term "Standard Specifications are amended" is used in the special provisions, the indented text or table following the term shall be considered an amendment to the Standard Specifications. In case of conflict between such amendments and the Standard Specifications, the amendments shall take precedence over and be used in lieu of the conflicting portions.

In case of conflict between the Standard Specifications and these special provisions, the special provisions shall take precedence over and shall be used in lieu of the conflicting portions.

**SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS**

**2-1.01 GENERAL**

The bidder's attention is directed to the provisions in Section 2, "Proposal Requirements and Conditions," of the Standard Specifications and these special provisions for the requirements and conditions which the bidder must observe in the preparation of the proposal form and the submission of the bid.

In addition to the subcontractors required to be listed in conformance with Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications, each proposal shall have listed therein the name and address of each DVBE subcontractor to be used for credit in meeting the goal, and to whom the bidder proposes to directly subcontract portions of the work. The list of subcontractors shall also set forth the portion of work that will be performed by each subcontractor listed. A sheet for listing the subcontractors is included in the Proposal.

The Bidder's Bond form mentioned in the last paragraph in Section 2-1.07, "Proposal Guaranty," of the Standard Specifications will be found following the signature page of the Proposal.

In conformance with Public Contract Code Section 7106, a Noncollusion Affidavit is included in the Proposal. Signing the Proposal shall also constitute signature of the Noncollusion Affidavit.

Submit request for substitution of an "or equal" item, and the data substantiating the request to the Department of Transportation, Central Region Construction, P.O. Box 12616, Fresno, CA 93778, so that the request is received by the Department by close of business on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening.

**2-1.02 DISABLED VETERAN BUSINESS ENTERPRISE (DVBE)**

Section 10115 of the Public Contract Code requires the Department to implement provisions to establish a goal for Disabled Veterans Business Enterprise (DVBE) in contracts.

It is the policy of the Department that Disabled Veteran Business Enterprise (DVBE) shall have the maximum opportunity to participate in the performance of contracts financed solely with state funds. The Contractor shall ensure that DVBEs have the maximum opportunity to participate in the performance of this contract and shall take all necessary and reasonable steps for this assurance. The Contractor shall not discriminate on the basis of race, color, national origin, or sex in the award and performance of subcontracts. Failure to carry out the requirements of this paragraph shall constitute a breach of contract and may result in termination of this contract or other remedy the Department may deem appropriate.

Bidder's attention is directed to the following:

- A. "Disabled Veteran Business Enterprise" (DVBE) means a business concern certified as a DVBE by the Office of Small Business Certification and Resources, Department of General Services.
- B. A DVBE may participate as a prime contractor, subcontractor, joint venture partner with a prime or subcontractor, or vendor of material or supplies.
- C. Credit for DVBE prime contractors will be 100 percent.
- D. A DVBE joint venture partner must be responsible for specific contract items of work, or portions thereof. Responsibility means actually performing, managing and supervising the work with its own forces. The DVBE joint venture partner must share in the ownership, control, management responsibilities, risks and profits of the joint venture. The DVBE joint venturer must submit the joint venture agreement with the Caltrans Bidder DVBE Information form required in Section 2-1.04, "Submission of DVBE Information," elsewhere in these special provisions.
- E. A DVBE must perform a commercially useful function, i.e., must be responsible for the execution of a distinct element of the work and must carry out its responsibility by actually performing, managing and supervising the work.
- F. Credit for DVBE vendors of materials or supplies is limited to 60 percent of the amount to be paid to the vendor for the material unless the vendor manufactures or substantially alters the goods.
- G. Credit for trucking by DVBEs will be as follows:
  - 1. One hundred percent of the amount to be paid when a DVBE trucker will perform the trucking with his/her own trucks, tractors and employees.
  - 2. Twenty percent of the amount to be paid to DVBE trucking brokers who do not have a "certified roster."
  - 3. One hundred percent of the amount to be paid to DVBE trucking brokers who have signed agreements that all trucking will be performed by DVBE truckers if credit is toward the DVBE goal, a "certified roster" showing that all trucks are owned by DVBEs, and a signed statement on the "certified roster" that indicates that 100 percent of revenue paid by the broker will be paid to the DVBEs listed on the "certified roster."
  - 4. Twenty percent of the amount to be paid to trucking brokers who are not a DVBE but who have signed agreements with DVBE truckers assuring that at least 20 percent of the trucking will be performed by DVBE truckers if credit is toward the DVBE goal, a "certified roster" showing that at least 20 percent of the number of trucks are owned by DVBE truckers, and a signed statement on the "certified roster" that indicates that at least 20 percent of the revenue paid by the broker will be paid to the DVBEs listed on the "certified roster."

The "certified roster" referred to herein shall conform to the requirements in Section 2-1.04, "Submission Of DVBE Information," elsewhere in these special provisions.

- H. DVBEs and DVBE joint venture partners must be certified DVBEs as determined by the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814, on the date bids for the project are opened before credit may be allowed toward the DVBE goal. It is the Contractor's responsibility to verify that DVBEs are certified.
- I. Noncompliance by the Contractor with these requirements constitutes a breach of this contract and may result in termination of the contract or other appropriate remedy for a breach of this contract.

### **2-1.03 DVBE GOAL FOR THIS PROJECT**

The Department has established the following goal for Disabled Veteran Business Enterprise (DVBE) participation for this project:

Disabled Veteran Business Enterprise (DVBE): 3 percent.

It is the bidder's responsibility to make a sufficient portion of the work available to subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DVBE subcontractors and suppliers, so as to assure meeting the goal for DVBE participation.

The Office of Small Business Certification and Resources, Department of General Services, may be contacted at (916) 322-5060 or visit their internet web site at <http://www.osmb.dgs.ca.gov/> for program information and certification status. The Department's Business Enterprise Program may also be contacted at (916) 227-9599 or the internet web site at <http://www.dot.ca.gov/hq/bep/>.

## **2-1.04 SUBMISSION OF DVBE INFORMATION**

The required DVBE information shall be submitted on the "CALTRANS BIDDER - DVBE INFORMATION" form included in the Proposal. If this information is not submitted with the bid, the DVBE information forms shall be removed from the documents prior to submitting the bid.

It is the bidder's responsibility to make enough work available to DVBEs and to select those portions of the work or material needs consistent with the available DVBEs to meet the goal for DVBE participation or to provide information to establish that, prior to bidding, the bidder made adequate good faith efforts to do so.

If the DVBE information is not submitted with the bid, the apparent successful bidder (low bidder), the second low bidder and the third low bidder shall submit the DVBE information to the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, California 95814 so the information is received by the Department no later than 4:00 p.m. on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening. DVBE information sent by U.S. Postal Service certified mail with return receipt and certificate of mailing and mailed on or before the third day, not including Saturdays, Sundays and legal holidays, following bid opening will be accepted even if it is received after the fourth day following bid opening. Failure to submit the required DVBE information by the time specified will be grounds for finding the bid or proposal nonresponsive. Other bidders need not submit DVBE information unless requested to do so by the Department.

The bidder's DVBE information shall establish that good faith efforts to meet the DVBE goal have been made. To establish good faith efforts, the bidder shall demonstrate that the goal will be met or that, prior to bidding, adequate good faith efforts to meet the goal were made.

Bidders are cautioned that even though their submittal indicates they will meet the stated DVBE goal, their submittal should also include their adequate good faith efforts information along with their DVBE goal information to protect their eligibility for award of the contract in the event the Department, in its review, finds that the goal has not been met.

The bidder's DVBE information shall include the names of DVBE firms that will participate, with a complete description of work or supplies to be provided by each, the dollar value of each DVBE transaction, and a written confirmation from the DVBE that it is participating in the contract. A copy of the DVBE's quote will serve as written confirmation that the DVBE is participating in the contract. When 100 percent of a contract item of work is not to be performed or furnished by a DVBE, a description of the exact portion of that work to be performed or furnished by that DVBE shall be included in the DVBE information, including the planned location of that work. The work that a DVBE prime contractor has committed to performing with its own forces as well as the work that it has committed to be performed by DVBE subcontractors, suppliers and trucking companies will count toward the goal.

If credit for trucking by a DVBE trucking broker is shown on the bidder's information as 100 percent of the revenue to be paid by the broker is to be paid to DVBE truckers, a "certified roster" of the broker's trucks to be used must be included. The "certified roster" must indicate that all the trucks are owned by certified DVBEs and must show the DVBE truck numbers, owner's name, Public Utilities Commission Cal-T numbers, and the DVBE certification numbers. The roster must indicate that all revenue paid by the broker will be paid to DVBEs listed on the "certified roster".

If credit for trucking by a trucking broker who is not a DVBE is shown in the bidder's information, a "certified roster" of the broker's trucks to be used must be included. The "certified roster" must indicate that at least 20 percent of the broker's trucks are owned by certified DVBEs and must show the DVBE truck numbers, owner's name, Public Utilities Commission Cal-T numbers, and the DVBE certification number. The roster must indicate that at least 20 percent of the revenue paid by the broker will be paid to DVBEs listed on the "certified roster".

A bidder shall be deemed to have made good faith efforts upon submittal, within time limits specified by the Department, of documentary evidence that all of the following actions were taken:

- A. Contact was made with the Office of Small Business Certification and Resources (OSBCR), Department of General Services or their web site at <http://www.osmb.dgs.ca.gov/> to identify Disabled Veteran Business Enterprises.
- B. Advertising was published in trade media and media focusing on Disabled Veteran Business Enterprises, unless time limits imposed by the Department do not permit that advertising.
- C. Invitations to bid were submitted to potential Disabled Veteran Business Enterprise contractors.
- D. Available Disabled Veteran Business Enterprises were considered.

## **2-1.05 SMALL BUSINESS PREFERENCE**

Attention is directed to "Award and Execution of Contract" of these special provisions.

Attention is also directed to the Small Business Procurement and Contract Act, Government Code Section 14835, et seq and Title 2, California Code of Regulations, Section 1896, et seq.

Bidders who wish to be classified as a Small Business under the provisions of those laws and regulations, shall be certified as Small Business by the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814.

To request Small Business Preference, bidders shall fill out and sign the Request for Small Business Preference form in the Proposal and shall attach a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form. The bidder's signature on the Request for Small Business Preference certifies, under penalty of perjury, that the bidder is certified as Small Business at the time of bid opening and further certifies, under penalty of perjury, that under the following conditions, at least 50 percent of the subcontractors to be utilized on the project are either certified Small Business or have applied for Small Business certification by bid opening date and are subsequently granted Small Business certification.

The conditions requiring the aforementioned 50 percent level of subcontracting by Small Business subcontractors apply if:

- A. The lowest responsible bid for the project exceeds \$100,000; and
- B. The project work to be performed requires a Class A or a Class B contractor's license; and
- C. Two or more subcontractors will be used.

If the above conditions apply and Small Business Preference is granted in the award of the contract, the 50 percent Small Business subcontractor utilization level shall be maintained throughout the life of the contract.

## **2-1.06 CALIFORNIA COMPANY PREFERENCE**

Attention is directed to "Award and Execution of Contract" of these special provisions.

In conformance with the requirements of Section 6107 of the Public Contract Code, a "California company" will be granted a reciprocal preference for bid comparison purposes as against a nonresident contractor from any state that gives or requires a preference to be given contractors from that state on its public entity construction contracts.

A "California company" means a sole proprietorship, partnership, joint venture, corporation, or other business entity that was a licensed California contractor on the date when bids for the public contract were opened and meets one of the following:

- A. Has its principal place of business in California.
- B. Has its principal place of business in a state in which there is no local contractor preference on construction contracts.
- C. Has its principal place of business in a state in which there is a local contractor construction preference and the contractor has paid not less than \$5000 in sales or use taxes to California for construction related activity for each of the five years immediately preceding the submission of the bid.

To carry out the "California company" reciprocal preference requirements of Section 6107 of the Public Contract Code, all bidders shall fill out and sign the California Company Preference form in the Proposal. The bidder's signature on the California Company Preference form certifies, under penalty of perjury, that the bidder is or is not a "California company" and if not, the amount of the preference applied by the state of the nonresident Contractor.

A nonresident Contractor shall disclose any and all bid preferences provided to the nonresident Contractor by the state or country in which the nonresident Contractor has its principal place of business.

Proposals without the California Company Preference form filled out and signed may be rejected.

## **SECTION 3. AWARD AND EXECUTION OF CONTRACT**

The bidder's attention is directed to the provisions in Section 3, "Award and Execution of Contract," of the Standard Specifications and these special provisions for the requirements and conditions concerning award and execution of contract.

The award of the contract, if it be awarded, will be to the lowest responsible bidder whose proposal complies with all the requirements prescribed and who has met the goal for DVBE participation or has demonstrated, to the satisfaction of the Department, adequate good faith efforts to do so. Meeting the goal for DVBE participation or demonstrating, to the satisfaction of the Department, adequate good faith efforts to do so is a condition for being eligible for award of contract.

A "Payee Data Record" form will be included in the contract documents to be executed by the successful bidder. The purpose of the form is to facilitate the collection of taxpayer identification data. The form shall be completed and returned to the Department by the successful bidder with the executed contract and contract bonds. For the purposes of the form, payee shall be deemed to mean the successful bidder. The form is not to be completed for subcontractors or suppliers. Failure to complete and return the "Payee Data Record" form to the Department as provided herein will result in the retention of 20 percent of payments due the contractor and penalties of up to \$20,000. This retention of payments for failure to complete the "Payee Data Record" form is in addition to any other retention of payments due the Contractor.

Attention is also directed to "Small Business Preference" of these special provisions. Any bidder who is certified as a Small Business by the Department of General Services, Office of Small Business Certification and Resources will be allowed a preference in the award of this contract, if it be awarded, under the following conditions:



- A. The apparent low bidder is not certified as a Small Business, or has not filled out and signed the Request for Small Business Preference included with the bid documents and attached a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form; and
- B. The bidder filled out and signed the Request for Small Business Preference form included with the bid documents and attached a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form.

The small business preference will be a reduction in the bid submitted by the small business contractor, for bid comparison purposes, by an amount equal to 5 percent of the amount bid by the apparent low bidder, the amount not to exceed \$50,000. If this reduction results in the small business contractor becoming the low bidder, then the contract will be awarded to the small business contractor on the basis of the actual bid of the small business contractor notwithstanding the reduced bid price used for bid comparison purposes.

Attention is also directed to "California Company Preference" of these special provisions.

The amount of the California company reciprocal preference shall be equal to the amount of the preference applied by the state of the nonresident contractor with the lowest responsive bid, except where the "California company" is eligible for a California Small Business Preference, in which case the preference applied shall be the greater of the two, but not both.

If the bidder submitting the lowest responsive bid is not a "California company" and with the benefit of the reciprocal preference, a "California company's" responsive bid is equal to or less than the original lowest responsive bid, the "California company" will be awarded the contract at its submitted bid price except as provided below.

Small business bidders shall have precedence over nonsmall business bidders in that the application of the "California company" preference for which nonsmall business bidders may be eligible shall not result in the denial of the award to a small business bidder.

#### **SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES**

Attention is directed to the provisions in Section 8-1.03, "Beginning of Work," in Section 8-1.06, "Time of Completion," and in Section 8-1.07, "Liquidated Damages," of the Standard Specifications and these special provisions.

The Contractor shall begin work within 15 calendar days after the contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department of Transportation.

This work shall be diligently prosecuted to completion before the expiration of **815 WORKING DAYS** beginning on the fifteenth calendar day after approval of the contract.

The Contractor shall pay to the State of California the sum of \$250 per day, for each and every calendar day's delay in finishing the work in excess of the number of working days prescribed above.

#### **SECTION 5. GENERAL**

##### **SECTION 5-1. MISCELLANEOUS**

###### **5-1.01 PLANS AND WORKING DRAWINGS**

When the specifications require working drawings to be submitted to the Division of Structure Design, the drawings shall be submitted to: Division of Structure Design, Documents Unit, Mail Station 9, 1801 30th Street, Sacramento, CA 95816, Telephone 916 227-8252.

###### **5-1.015 LABORATORY**

When a reference is made in the specifications to the "Laboratory," the reference shall mean the Division of Materials Engineering and Testing Services and the Division of Structural Foundations of the Department of Transportation, or established laboratories of the various Districts of the Department, or other laboratories authorized by the Department to test materials and work involved in the contract. When a reference is made in the specifications to the "Transportation Laboratory," the reference shall mean the Division of Materials Engineering and Testing Services and the Division of Structural Foundations, located at 5900 Folsom Boulevard, Sacramento, CA 95819, Telephone (916) 227-7000.

###### **5-1.02 LABOR NONDISCRIMINATION**

Attention is directed to the following Notice that is required by Chapter 5 of Division 4 of Title 2, California Code of Regulations.

**NOTICE OF REQUIREMENT FOR NONDISCRIMINATION PROGRAM  
(GOV. CODE, SECTION 12990)**

Your attention is called to the "Nondiscrimination Clause", set forth in Section 7-1.01A(4), "Labor Nondiscrimination," of the Standard Specifications, which is applicable to all nonexempt State contracts and subcontracts, and to the "Standard California Nondiscrimination Construction Contract Specifications" set forth therein. The specifications are applicable to all nonexempt State construction contracts and subcontracts of \$5000 or more.

**5-1.03 INTEREST ON PAYMENTS**

Interest shall be payable on progress payments, payments after acceptance, final payments, extra work payments, and claim payments as follows:

- A. Unpaid progress payments, payment after acceptance, and final payments shall begin to accrue interest 30 days after the Engineer prepares the payment estimate.
- B. Unpaid extra work bills shall begin to accrue interest 30 days after preparation of the first pay estimate following receipt of a properly submitted and undisputed extra work bill. To be properly submitted, the bill must be submitted within 7 days of the performance of the extra work and in conformance with the provisions in Section 9-1.03C, "Records," and Section 9-1.06, "Partial Payments," of the Standard Specifications. An undisputed extra work bill not submitted within 7 days of performance of the extra work will begin to accrue interest 30 days after the preparation of the second pay estimate following submittal of the bill.
- C. The rate of interest payable for unpaid progress payments, payments after acceptance, final payments, and extra work payments shall be 10 percent per annum.
- D. The rate of interest payable on a claim, protest or dispute ultimately allowed under this contract shall be 6 percent per annum. Interest shall begin to accrue 61 days after the Contractor submits to the Engineer information in sufficient detail to enable the Engineer to ascertain the basis and amount of said claim, protest or dispute.

The rate of interest payable on any award in arbitration shall be 6 percent per annum if allowed under the provisions of Civil Code Section 3289.

**5-1.04 PUBLIC SAFETY**

The Contractor shall provide for the safety of traffic and the public in conformance with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications and these special provisions.

The Contractor shall install temporary railing (Type K) between a lane open to public traffic and an excavation, obstacle or storage area when the following conditions exist:

- A. Excavations.—The near edge of the excavation is 3.6 m or less from the edge of the lane, except:
  - 1. Excavations covered with sheet steel or concrete covers of adequate thickness to prevent accidental entry by traffic or the public.
  - 2. Excavations less than 0.3-m deep.
  - 3. Trenches less than 0.3-m wide for irrigation pipe or electrical conduit, or excavations less than 0.3-m in diameter.
  - 4. Excavations parallel to the lane for the purpose of pavement widening or reconstruction.
  - 5. Excavations in side slopes, where the slope is steeper than 1:4 (vertical:horizontal).
  - 6. Excavations protected by existing barrier or railing.
- B. Temporarily Unprotected Permanent Obstacles.—The work includes the installation of a fixed obstacle together with a protective system, such as a sign structure together with protective railing, and the Contractor elects to install the obstacle prior to installing the protective system; or the Contractor, for the Contractor's convenience and with permission of the Engineer, removes a portion of an existing protective railing at an obstacle and does not replace such railing complete in place during the same day.
- C. Storage Areas.—Material or equipment is stored within 3.6 m of the lane and the storage is not otherwise prohibited by the provisions of the Standard Specifications and these special provisions.

The approach end of temporary railing (Type K), installed in conformance with the provisions in this section "Public Safety" and in Section 7-1.09, "Public Safety," of the Standard Specifications, shall be offset a minimum of 4.6 m from the edge of the traffic lane open to public traffic. The temporary railing shall be installed on a skew toward the edge of the traffic lane of not more than 0.3-m transversely to 3 m longitudinally with respect to the edge of the traffic lane. If the 4.6-m

minimum offset cannot be achieved, the temporary railing shall be installed on the 10 to 1 skew to obtain the maximum available offset between the approach end of the railing and the edge of the traffic lane, and an array of temporary crash cushion modules shall be installed at the approach end of the temporary railing.

Temporary railing (Type K) shall conform to the provisions in Section 12-3.08, "Temporary Railing (Type K)," of the Standard Specifications. Temporary railing (Type K), conforming to the details shown on 1999 Standard Plan T3, may be used. Temporary railing (Type K) fabricated prior to January 1, 1993, and conforming to 1988 Standard Plan B11-30 may be used, provided the fabrication date is printed on the required Certificate of Compliance.

Temporary crash cushion modules shall conform to the provisions in "Temporary Crash Cushion Module" of these special provisions.

Except for installing, maintaining and removing traffic control devices, whenever work is performed or equipment is operated in the following work areas, the Contractor shall close the adjacent traffic lane unless otherwise provided in the Standard Specifications and these special provisions:

Approach Speed of Public Traffic (Posted Limit) (Kilometers Per Hour)	Work Areas
Over 72 (45 Miles Per Hour)	Within 1.8 m of a traffic lane but not on a traffic lane
56 to 72 (35 to 45 Miles Per Hour)	Within 0.9-m of a traffic lane but not on a traffic lane

The lane closure provisions of this section shall not apply if the work area is protected by permanent or temporary railing or barrier.

When traffic cones or delineators are used to delineate a temporary edge of a traffic lane, the line of cones or delineators shall be considered to be the edge of the traffic lane, however, the Contractor shall not reduce the width of an existing lane to less than 3 m without written approval from the Engineer.

When work is not in progress on a trench or other excavation that required closure of an adjacent lane, the traffic cones or portable delineators used for the lane closure shall be placed off of and adjacent to the edge of the traveled way. The spacing of the cones or delineators shall be not more than the spacing used for the lane closure.

Suspended loads or equipment shall not be moved nor positioned over public traffic or pedestrians.

Full compensation for conforming to the provisions in this section "Public Safety," including furnishing and installing temporary railing (Type K) and temporary crash cushion modules, shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

#### **5-1.05 SURFACE MINING AND RECLAMATION ACT**

Attention is directed to the Surface Mining and Reclamation Act of 1975, commencing in Public Resources Code, Mining and Geology, Section 2710, which establishes regulations pertinent to surface mining operations.

Material from mining operations furnished for this project shall only come from permitted sites in compliance with the Surface Mining and Reclamation Act of 1975.

The requirements of this section shall apply to materials furnished for the project, except for acquisition of materials in conformance with the provisions in Section 4-1.05, "Use of Materials Found on the Work," of the Standard Specifications.

#### **5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES**

When the presence of asbestos or hazardous substances are not shown on the plans or indicated in the specifications and the Contractor encounters materials which the Contractor reasonably believes to be asbestos or a hazardous substance as defined in Section 25914.1 of the Health and Safety Code, and the asbestos or hazardous substance has not been rendered harmless, the Contractor may continue work in unaffected areas reasonably believed to be safe. The Contractor shall immediately cease work in the affected area and report the condition to the Engineer in writing.

In conformance with Section 25914.1 of the Health and Safety Code, removal of asbestos or hazardous substances including exploratory work to identify and determine the extent of the asbestos or hazardous substance will be performed by separate contract.

If delay of work in the area delays the current controlling operation, the delay will be considered a right of way delay and the Contractor will be compensated for the delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

#### **5-1.07 YEAR 2000 COMPLIANCE**

This contract is subject to Year 2000 Compliance for automated devices in the State of California.

Year 2000 compliance for automated devices in the State of California is achieved when embedded functions have or create no logical or mathematical inconsistencies when dealing with dates prior to and beyond 1999. The year 2000 is

recognized and processed as a leap year. The product shall operate accurately in the manner in which the product was intended for date operation without requiring manual intervention.

The Contractor shall provide the Engineer a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for all automated devices furnished for the project.

#### **5-1.08 SUBCONTRACTOR AND DVBE RECORDS**

The Contractor shall maintain records of all subcontracts entered into with certified DVBE subcontractors and records of materials purchased from certified DVBE suppliers. The records shall show the name and business address of each DVBE subcontractor or vendor and the total dollar amount actually paid each DVBE subcontractor or vendor.

Upon completion of the contract, a summary of these records shall be prepared on Form CEM-2402 (S) and certified correct by the Contractor or the Contractor's authorized representative, and shall be furnished to the Engineer.

#### **5-1.086 PERFORMANCE OF DVBE SUBCONTRACTORS AND SUPPLIERS**

The DVBEs listed by the Contractor in response to the provisions in Section 2-1.04, "Submission of DVBE Information," and Section 3, "Award and Execution of Contract," of these special provisions, which are determined by the Department to be certified DVBEs, shall perform the work and supply the materials for which they are listed, unless the Contractor has received prior written authorization to perform the work with other forces or to obtain the materials from other sources.

Authorization to utilize other forces or sources of materials may be requested for the following reasons:

- A. The listed DVBE, after having had a reasonable opportunity to do so, fails or refuses to execute a written contract, when the written contract, based upon the general terms, conditions, plans and specifications for the project, or on the terms of the subcontractor's or supplier's written bid, is presented by the Contractor.
- B. The listed DVBE becomes bankrupt or insolvent.
- C. The listed DVBE fails or refuses to perform the subcontract or furnish the listed materials.
- D. The Contractor stipulated that a bond was a condition of executing a subcontract and the listed DVBE subcontractor fails or refuses to meet the bond requirements of the Contractor.
- E. The work performed by the listed subcontractor is substantially unsatisfactory and is not in substantial conformance with the plans and specifications or the subcontractor is substantially delaying or disrupting the progress of the work.
- F. The listed DVBE subcontractor is not licensed pursuant to the Contractor's License Law.
- G. It would be in the best interest of the State.

The Contractor shall not be entitled to payment for the work or material unless it is performed or supplied by the listed DVBE or by other forces (including those of the Contractor) pursuant to prior written authorization of the Engineer.

#### **5-1.09 SUBCONTRACTING**

Attention is directed to the provisions in Section 8-1.01, "Subcontracting," of the Standard Specifications, Section 2, "Proposal Requirements and Conditions," Section 2-1.04, "Submission of DVBE Information," and Section 3, "Award and Execution of Contract," of these special provisions and these special provisions.

Pursuant to the provisions in Section 1777.1 of the Labor Code, the Labor Commissioner publishes and distributes a list of contractors ineligible to perform work as a subcontractor on a public works project. This list of debarred contractors is available from the Department of Industrial Relations web site at:

<http://www.dir.ca.gov/DLSE/Debar.html>.

The DVBE information furnished under Section 3-1.01A, "DVBE Information," of these special provisions is in addition to the subcontractor information required to be furnished in Section 8-1.01, "Subcontracting," and Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications.

Section 10115 of the Public Contract Code requires the Department to implement provisions to establish a goal for Disabled Veteran Business Enterprise (DVBE) participation in highway contracts that are State funded. As a part of this requirement:

- A. No substitution of a DVBE subcontractor shall be made at any time without the written consent of the Department, and
- B. If a DVBE subcontractor is unable to perform successfully and is to be replaced, the Contractor shall make good faith efforts to replace the original DVBE subcontractor with another DVBE subcontractor.

The provisions in Section 2-1.02, "Disabled Veteran Business Enterprise (DVBE)," of these special provisions that DVBEs shall be certified on the date bids are opened does not apply to DVBE substitutions after award of the contract.

#### **5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS**

Attention is directed to the provisions in Sections 10262 and 10262.5 of the Public Contract Code and Section 7108.5 of the Business and Professions Code concerning prompt payment to subcontractors.

#### **5-1.11 PAYMENTS**

Attention is directed to Sections 9-1.06, "Partial Payments," and 9-1.07, "Payment After Acceptance," of the Standard Specifications and these special provisions.

For the purpose of making partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications, the amount set forth for the contract items of work hereinafter listed shall be deemed to be the maximum value of the contract item of work which will be recognized for progress payment purposes:

A. Roadside Clearing	\$5,000.00
----------------------	------------

After acceptance of the contract pursuant to the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, the amount, if any, payable for a contract item of work in excess of the maximum value for progress payment purposes hereinabove listed for the item, will be included for payment in the first estimate made after acceptance of the contract.

No partial payment will be made for any materials on hand which are furnished but not incorporated in the work.

### **SECTION 6. (BLANK)**

### **SECTION 7. (BLANK)**

### **SECTION 8. MATERIALS**

#### **SECTION 8-1. MISCELLANEOUS**

##### **8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS**

Only materials and products conforming to the requirements of the specifications shall be incorporated in the work. When metric materials and products are not available, and when approved by the Engineer, and at no cost to the State, materials and products in the inch-pound (Imperial) system which are of equal quality and of the required properties and characteristics for the purpose intended, may be substituted for the equivalent metric materials and products, subject to the following provisions:

- A. Materials and products shown on the plans or in the special provisions as being equivalent may be substituted for the metric materials and products specified or detailed on the plans.
- B. Before other non-metric materials and products will be considered for use the Contractor shall furnish, at the Contractor's expense, evidence satisfactory to the Engineer that the materials and products proposed for use are equal to or better than the materials and products specified or detailed on the plans. The burden of proof as to the quality and suitability of substitutions shall be upon the Contractor and the Contractor shall furnish necessary information as required by the Engineer. The Engineer will be the sole judge as to the quality and suitability of the substituted materials and products and the Engineer's decision will be final.
- C. When the Contractor elects to substitute non-metric materials and products, including materials and products shown on the plans or in the special provisions as being equivalent, the list of sources of material as specified in Section 6-1.01, "Source of Supply and Quality of Materials," of the Standard Specification shall include a list of substitutions to be made and contract items involved. In addition, for a change in design or details the Contractor shall submit plans and working drawings in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications.

Unless otherwise specified, the following substitutions of materials and products will be allowed:

**SUBSTITUTION TABLE FOR SIZES OF HIGH STRENGTH STEEL FASTENERS**

ASTM Designation: A 325M

METRIC SIZE SHOWN ON THE PLANS mm x thread pitch	IMPERIAL SIZE TO BE SUBSTITUTED inch
M16 x 2	5/8
M20 x 2.5	3/4
M22 x 2.5	7/8
M24 x 3	1
M27 x 3	1-1/8
M30 x 3.5	1-1/4
M36 x 4	1-1/2

**SUBSTITUTION TABLE FOR PLAIN WIRE REINFORCEMENT, ASTM Designation: A 82**

METRIC SIZE SHOWN ON THE PLANS mm <sup>2</sup>	US CUSTOMARY UNITS SIZE TO BE SUBSTITUTED inch <sup>2</sup> x 100
MW9	W1.4
MW10	W1.6
MW13	W2.0
MW15	W2.3
MW19	W2.9
MW20	W3.1
MW22	W3.5
MW25	W3.9, except W3.5 in piles only
MW26	W4.0
MW30	W4.7
MW32	W5.0
MW35	W5.4
MW40	W6.2
MW45	W6.5
MW50	W7.8
MW55	W8.5, except W8.0 in piles only
MW60	W9.3
MW70	W10.9, except W11.0 in piles only
MW80	W12.4
MW90	W14.0
MW100	W15.5

**SUBSTITUTION TABLE FOR BAR REINFORCEMENT**

METRIC BAR DESIGNATION NUMBER SHOWN ON THE PLANS	EQUIVALENT IMPERIAL BAR DESIGNATION NUMBER TO BE SUBSTITUTED
13	4
16	5
19	6
22	7
25	8
29	9
32	10
36	11
43	14
57	18

No adjustment will be required in spacing or total number of reinforcing bars due to a difference in minimum yield strength between metric and non-metric bars.

The sizes in the following tables of materials and products are exact conversions of metric sizes of materials and products and are listed as acceptable equivalents:

CONVERSION TABLE FOR SIZES OF:

- (1) STEEL FASTENERS FOR GENERAL APPLICATIONS, ASTM Designation: A 307 or AASHTO Designation: M 314, Grade 36 or 55, and  
 (2) HIGH STRENGTH STEEL FASTENERS, ASTM Designation: A 325 or A 449

METRIC SIZE SHOWN ON THE PLANS mm	EQUIVALENT IMPERIAL SIZE inch
6, or 6.35	1/4
8 or 7.94	5/16
10, or 9.52	3/8
11, or 11.11	7/16
13 or 12.70	1/2
14, or 14.29	9/16
16, or 15.88	5/8
19, or 19.05	3/4
22, or 22.22	7/8
24, 25, or 25.40	1
29, or 28.58	1-1/8
32, or 31.75	1-1/4
35, or 34.93	1-3/8
38 or 38.10	1-1/2
44, or 44.45	1-3/4
51, or 50.80	2
57, or 57.15	2-1/4
64, or 63.50	2-1/2
70 or 69.85	2-3/4
76, or 76.20	3
83, or 82.55	3-1/4
89 or 88.90	3-1/2
95, or 95.25	3-3/4
102, or 101.60	4

**CONVERSION TABLE FOR NOMINAL THICKNESS OF SHEET METAL**

UNCOATED HOT AND COLD ROLLED SHEETS		HOT-DIPPED ZINC COATED SHEETS (GALVANIZED)	
METRIC THICKNESS SHOWN ON THE PLANS	EQUIVALENT US STANDARD GAGE	METRIC THICKNESS SHOWN ON THE PLANS	EQUIVALENT GALVANIZED SHEET GAGE
mm	inch	mm	inch
7.94	0.3125	4.270	0.1681
6.07	0.2391	3.891	0.1532
5.69	0.2242	3.510	0.1382
5.31	0.2092	3.132	0.1233
4.94	0.1943	2.753	0.1084
4.55	0.1793	2.372	0.0934
4.18	0.1644	1.994	0.0785
3.80	0.1495	1.803	0.0710
3.42	0.1345	1.613	0.0635
3.04	0.1196	1.461	0.0575
2.66	0.1046	1.311	0.0516
2.28	0.0897	1.158	0.0456
1.90	0.0747	1.006 or 1.016	0.0396
1.71	0.0673	0.930	0.0366
1.52	0.0598	0.853	0.0336
1.37	0.0538	0.777	0.0306
1.21	0.0478	0.701	0.0276
1.06	0.0418	0.627	0.0247
0.91	0.0359	0.551	0.0217
0.84	0.0329	0.513	0.0202
0.76	0.0299	0.475	0.0187
0.68	0.0269	-----	-----
0.61	0.0239	-----	-----
0.53	0.0209	-----	-----
0.45	0.0179	-----	-----
0.42	0.0164	-----	-----
0.38	0.0149	-----	-----



**CONVERSION TABLE FOR WIRE**

METRIC THICKNESS SHOWN ON THE PLANS mm	EQUIVALENT USA STEEL WIRE THICKNESS inch	GAGE NO.
6.20	0.244	3
5.72	0.225	4
5.26	0.207	5
4.88	0.192	6
4.50	0.177	7
4.11	0.162	8
3.76	0.148	9
3.43	0.135	10
3.05	0.120	11
2.69	0.106	12
2.34	0.092	13
2.03	0.080	14
1.83	0.072	15
1.57	0.062	16
1.37	0.054	17
1.22	0.048	18
1.04	0.041	19
0.89	0.035	20

**CONVERSION TABLE FOR PIPE PILES**

METRIC SIZE SHOWN ON THE PLANS mm x mm	EQUIVALENT IMPERIAL SIZE inch x inch
PP 360 x 4.55	NPS 14 x 0.179
PP 360 x 6.35	NPS 14 x 0.250
PP 360 x 9.53	NPS 14 x 0.375
PP 360 x 11.12	NPS 14 x 0.438
PP 406 x 12.70	NPS 16 x 0.500
PP 460 x T	NPS 18 x T"
PP 508 x T	NPS 20 x T"
PP 559 x T	NPS 22 x T"
PP 610 x T	NPS 24 x T"
PP 660 x T	NPS 26 x T"
PP 711 x T	NPS 28 x T"
PP 762 x T	NPS 30 x T"
PP 813 x T	NPS 32 x T"
PP 864 x T	NPS 34 x T"
PP 914 x T	NPS 36 x T"
PP 965 x T	NPS 38 x T"
PP 1016 x T	NPS 40 x T"
PP 1067 x T	NPS 42 x T"
PP 1118 x T	NPS 44 x T"
PP 1219 x T	NPS 48 x T"
PP 1524 x T	NPS 60 x T"

The thickness in inches (T") represents an exact conversion of the metric thickness in millimeters (T).

**CONVERSION TABLE FOR STRUCTURAL TIMBER AND LUMBER**

METRIC MINIMUM DRESSED DRY, SHOWN ON THE PLANS mm x mm	METRIC MINIMUM DRESSED GREEN, SHOWN ON THE PLANS mm x mm	EQUIVALENT NOMINAL US SIZE inch x inch
19x89	20x90	1x4
38x89	40x90	2x4
64x89	65x90	3x4
89x89	90x90	4x4
140x140	143x143	6x6
140x184	143x190	6x8
184x184	190x190	8x8
235x235	241x241	10x10
286x286	292x292	12x12

**CONVERSION TABLE FOR NAILS AND SPIKES**

METRIC COMMON NAIL, SHOWN ON THE PLANS  Length, mm Diameter, mm	METRIC BOX NAIL, SHOWN ON THE PLANS  Length, mm Diameter, mm	METRIC SPIKE, SHOWN ON THE PLANS Length, mm Diameter, mm	EQUIVALENT IMPERIAL SIZE  Penny-weight
50.80 2.87	50.80 2.51	————	6d
63.50 3.33	63.50 2.87	————	8d
76.20 3.76	76.20 3.25	76.20 4.88	10d
82.55 3.76	82.55 3.25	82.55 4.88	12d
88.90 4.11	88.90 3.43	88.90 5.26	16d
101.60 4.88	101.60 3.76	101.60 5.72	20d
114.30 5.26	114.30 3.76	114.30 6.20	30d
127.00 5.72	127.00 4.11	127.00 6.68	40d
————	————	139.70 7.19	50d
————	————	152.40 7.19	60d

CONVERSION TABLE FOR IRRIGATION COMPONENTS

METRIC WATER METERS, TRUCK LOADING STANDPIPES, VALVES, BACKFLOW PREVENTERS, FLOW SENSORS, WYE STRAINERS, FILTER ASSEMBLY UNITS, PIPE SUPPLY LINES, AND PIPE IRRIGATION SUPPLY LINES SHOWN ON THE PLANS DIAMETER NOMINAL (DN) mm	EQUIVALENT NOMINAL US SIZE inch
15	1/2
20	3/4
25	1
32	1-1/4
40	1-1/2
50	2
65	2-1/2
75	3
100	4
150	6
200	8
250	10
300	12
350	14
400	16

## **8-1.02 APPROVED TRAFFIC PRODUCTS**

The Department maintains the following List of Approved Traffic Products. The Engineer shall not be precluded from sampling and testing products on the List of Approved Traffic Products.

The manufacturer of products on the List of Approved Traffic Products shall furnish the Engineer a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each type of traffic product supplied.

### **PAVEMENT MARKERS, PERMANENT TYPE**

#### **Retroreflective**

- A. Apex, Model 921 (100 mm x 100 mm)
- B. Ray-O-Lite, Models SS (100 mm x 100 mm), RS (100 mm x 100 mm) and AA (100 mm x 100 mm)
- C. Stimsonite, Models 88 (100 mm x 100 mm), 911 (100 mm x 100 mm), 953 (70 mm x 114 mm)
- D. 3M Series 290 (89 mm x 100 mm)

#### **Retroreflective With Abrasion Resistant Surface (ARS)**

- A. Ray-O-Lite "AA" ARS (100 mm x 100 mm)
- B. Stimsonite, Models 911 (100 mm x 100 mm), 953 (70 mm x 114 mm)
- C. 3M Series 290 (89 mm x 100 mm)

#### **Retroreflective With Abrasion Resistant Surface (ARS) (Used for recessed applications)**

- A. Stimsonite, Model 948 (58 mm x 119 mm)
- B. Ray-O-Lite, Model 2002 (58 mm x 117 mm)
- C. Stimsonite, Model 944SB (51 mm x 100 mm)\*
- D. Ray-O-Lite, Model 2004 ARS (51 mm x 100 mm)\*

\*For use only in 114 mm wide (older) recessed slots

#### **Non-Reflective For Use With Epoxy Adhesive, 100 mm Round**

- A. Apex Universal (Ceramic)
- B. Highway Ceramics, Inc. (Ceramic)

#### **Non-Reflective For Use With Bitumen Adhesive, 100 mm Round**

- A. Apex Universal (Ceramic)
- B. Apex Universal, Model 929 (ABS)
- C. Elgin Molded Plastics, "Empco-Lite" Model 900 (ABS)
- D. Highway Ceramics, Inc. (Ceramic)
- E. Hi-Way Safety, Inc., Models P20-2000W and 2001Y (ABS)
- F. Interstate Sales, "Diamond Back" (ABS) and (Polypropylene)
- G. Alpine Products, D-Dot (ABS)
- H. Road Creations, Model RCB4NR (Acrylic)

### **PAVEMENT MARKERS, TEMPORARY TYPE**

#### **Temporary Markers For Long Term Day/Night Use (6 months or less)**

- A. Apex Universal, Model 924 (100 mm x 100 mm)
- B. Davidson Plastics Corp., Model 3.0 (100 mm x 100 mm)
- C. Elgin Molded Plastics, "Empco-Lite" Model 901 (100 mm x 100 mm)
- D. Road Creations, Model R41C (100 mm x 100 mm)
- E. Vega Molded Products "Temporary Road Marker" (75 mm x 100 mm)

#### **Temporary Markers For Short Term Day/Night Use (14 days or less) (For seal coat or chip seal applications, clear protective covers are required)**

- A. Apex Universal, Model 932
- B. Davidson Plastics, Models T.O.M., T.R.P.M., and "HH" (High Heat)
- C. Hi-Way Safety, Inc., Model 1280/1281

## **STRIPING AND PAVEMENT MARKING MATERIALS**

### **Permanent Traffic Striping And Pavement Marking Tape**

- A. Advanced Traffic Marking, Series 300 and 400
- B. Brite-Line, Series 1000
- C. Swarco Industries, "Director 35" (For transverse application only)
- D. Swarco Industries, "Director 60"
- E. 3M, "Stamark" Series 380 and 5730
- F. 3M, "Stamark" Series A320 Bisymmetric (For use on low-volume roadways only)
- G. 3M, "Stamark" Series A420, A440, N420, and N440 (For transverse application only)

### **Temporary (Removable) Striping And Pavement Marking Tape (6 months or less)**

- A. Brite-Line, Series 100
- B. P.B. Laminations, Aztec, Grade 102
- C. Swarco Industries, "Director-2"
- D. 3M, "Stamark," Series A620
- E. 3M Series A145 Removable Black Line Mask  
(Black Tape: For use only on Asphalt Concrete Surfaces)
- F. Advanced Traffic Marking Black "Hide-A-Line"  
(Black Tape: For use only on Asphalt Concrete Surfaces)

### **Preformed Thermoplastic (Heated in place)**

- A. Flint Trading, "Premark" and "Premark 20/20 Flex"
- B. Pavemark, "Hotape"

### **Removable Traffic Paint**

- A. Belpro, Series 250/252 and No. 93 Remover

## **CLASS 1 DELINEATORS**

### **One Piece Driveable Flexible Type, 1700 mm**

- A. Carsonite, Curve-Flex CFRM-400
- B. Carsonite, Roadmarker CRM-375
- C. Davidson Plastics, "Flexi-Guide Models 400 and 566"
- D. FlexStake, Model 654TM
- E. GreenLine Models HWD1-66 and CGD1-66
- F. J. Miller Industries, Model JMI-375 (with soil anchor)

### **Special Use Flexible Type, 1700 mm**

- A. Carsonite, "Survivor" with 450 mm U-Channel base
- B. FlexStake, Model 604
- C. GreenLine Models HWD and CGD (with 450 mm U-Channel base)
- D. Safe-Hit with 200 mm pavement anchor (SH248-GP1)
- E. Safe-Hit with 380 mm soil anchor (SH248-GP2) and with 450 mm soil anchor (SH248-GP3)

### **Surface Mount Flexible Type, 1200 mm**

- A. Bent Manufacturing Company, "Masterflex" Model MF-180EX-48
- B. Carsonite, "Super Duck II"
- C. FlexStake, Surface Mount, Models 704 and 754TM

## **CHANNELIZERS**

### **Surface Mount Type, 900 mm**

- A. Bent Manufacturing Company, "Masterflex" Models MF-360-36 (Round) and MF-180-36 (Flat)
- B. Carsonite, "Super Duck" (Flat SDF-436, Round SDR-336)
- C. Carsonite, Super Duck II Model SDCF203601MB "The Channelizer"
- D. Davidson Plastics, Flex-Guide Models FG300LD and FG300UR
- E. FlexStake, Surface Mount, Models 703 and 753TM
- F. GreenLine, Model SMD-36

- G. The Line Connection, "Dura-Post" Model DP36-3 (Permanent)
- H. The Line Connection, "Dura-Post" Model DP36-3C (Temporary)
- I. Repo, Models 300 and 400
- J. Safe-Hit, Guide Post, Model SH236SMA

**CONICAL DELINEATORS, 1070 mm (For 700 mm Traffic Cones, see Standard Specifications)**

- A. Bent Manufacturing Company "T-Top"
- B. Plastic Safety Systems "Navigator-42"
- C. Roadmaker Company "Stacker"
- D. Traffix Devices "Grabber"

**OBJECT MARKERS**

**Type "K", 450 mm**

- A. Carsonite, Model SMD-615
- B. FlexStake, Model 701KM
- C. Repo, Models 300 and 400
- D. Safe-Hit, Model SH718SMA
- E. The Line Connection, Model DP21-4K

**Type "K-4", 450-600 mm (Shown as Type "Q" in the Traffic Manual)**

- A. Carsonite, Super Duck II
- B. FlexStake, Model 701KM
- C. Repo, Models 300 and 400
- D. Safe-Hit, Models SH8 24SMA\_WA and SH8 24GP3\_WA
- E. The Line Connection, Model DP21-4Q

**TEMPORARY RAILING (TYPE K) REFLECTORS AND CONCRETE BARRIER MARKERS**

**Impactable Type**

- A. ARTUK, "FB"
- B. Davidson Plastics, Model PCBM-12
- C. Duraflex Corp., "Flexx 2020" and "Electriflexx"

**Non-Impactable Type**

- A. ARTUK, JD Series
- B. Stimsonite, Model 967 (with 83 mm Acrylic cube corner reflector)
- C. Stimsonite, Model 967LS
- D. Vega Molded Products, Models GBM and JD

**THREE BEAM BARRIER MARKERS (For use to the left of traffic)**

- A. Duraflex Corp., "Railrider"
- B. Davidson Plastics, "Mini" (75 mm x 254 mm)

**CONCRETE BARRIER DELINEATORS, 400 mm (For use to the right of traffic. When mounted on top of barrier, places top of reflective element at 1200 mm)**

- A. Davidson Plastics, Model PCBM T-16
- B. Safe-Hit, Model SH216RBM

**CONCRETE BARRIER-MOUNTED MINI-DRUM (260 mm x 360 mm x 570 mm)**

- A. Stinson Equipment Company "SaddleMarker"

**SOUND WALL DELINEATOR (Applied to a vertical surface. Top of reflective element at 1200 mm)**

- A. Davidson Plastics, PCBM S-36

## **GUARD RAILING DELINEATOR (Top of reflective element at 1200 mm above plane of roadway)**

### **Wood Post Type, 686 mm**

- A. Carsonite, Model 427
- B. Davidson Plastics FG 427 and FG 527
- C. FlexStake, Model 102 GR
- D. GreenLine GRD 27
- E. J. Miller Model JMI-375G
- F. Safe-Hit, Model SH227GRD

### **Steel Post Type**

- A. Carsonite, Model CFGR-327 with CFGRBK300 Mounting Bracket

## **RETROREFLECTIVE SHEETING**

### **Channelizers, Barrier Markers, And Delineators**

- A. 3M, High Intensity
- B. Reflexite, PC-1000 Metalized Polycarbonate
- C. Reflexite, AC-1000 Acrylic
- D. Reflexite, AP-1000 Metalized Polyester
- E. Reflexite, AR-1000 Abrasion Resistant Coating
- F. Stimsonite, Series 6200 (For rigid substrate devices only)

### **Traffic Cones, 330 mm Sleeves**

- A. Reflexite SB (Polyester), Vinyl or "TR" (Semi-transparent)

### **Traffic Cones, 100 mm and 150 mm Sleeves**

- A. 3M Series 3840
- B. Reflexite Vinyl, "TR" (Semi-transparent) or "Conformalite"

### **Barrels And Drums**

- A. Reflexite, "Super High Intensity" or "High Impact Drum Sheeting"
- B. 3M Series 3810

### **Barricades: Type I, Engineering Grade**

- A. American Decal, Adcolite
- B. Avery Dennison, 1500 and 1600
- C. 3M, Scotchlite, Series CW

### **Barricades: Type II, Super Engineering Grade**

- A. Avery Dennison, "Fasign" 2500 Series
- B. Kiwalite Type II
- C. Nikkalite 1800 Series

### **Signs: Type II, Super Engineering Grade**

- A. Avery Dennison, "Fasign" 2500 Series
- B. Kiwalite, Type II
- C. Nikkalite 1800 Series

### **Signs: Type III, High-Intensity Grade**

- A. 3M Series 3800
- B. Nippon Carbide, Nikkalite Brand Ultralite Grade II

### **Signs: Type IV, High-Intensity Prismatic Grade**

- A. Stimsonite Series 6200

**Signs: Type VII, High-Intensity Prismatic Grade**

- A. 3M Series 3900

**Signs: Type VI, Roll-Up Signs**

- A. Reflexite, Vinyl (Orange), Reflexite "SuperBright" (Fluorescent orange)
- B. 3M Series RS34 (Orange) and RS20 (Fluorescent orange)

**SIGN SUBSTRATE FOR CONSTRUCTION AREA SIGNS**

**Aluminum**

**Fiberglass Reinforced Plastic (FRP)**

- A. Sequentia, "Polyplate"
- B. Fiber-Brite

**SECTION 9. (BLANK)**

**SECTION 10. CONSTRUCTION DETAILS**

**SECTION 10-1. GENERAL**

**10-1.01 ORDER OF WORK**

Order of work shall conform to the provisions in Section 5-1.05, "Order of Work," of the Standard Specifications and these special provisions.

Within 15 days after the contract has been approved, the Contractor shall furnish the Engineer a statement from the vendor that the order for the plants required for this contract, including inspection plants, has been received and accepted by the vendor. The statement from the vendor shall include the names, sizes, and quantities of plants ordered and the anticipated date of delivery.

The Contractor shall place orders for replacement plants with the vendor at the appropriate time so that the roots of the replacement plants are not in a root-bound condition.

Attention is directed to Section 9-1.06, "Partial Payments," of the Standard Specifications. For progress payment purposes, the Department will retain 50 percent of the estimated value of highway planting work done until a statement from the vendor that the order for the plants required for this contract has been submitted to the Engineer.

Not less than 60 days prior to applying seeds, the Contractor shall furnish the Engineer a statement from the vendor that the order for the seed required for this contract has been received and accepted by the vendor. The statement from the vendor shall include the names and quantity of seed ordered and the anticipated date of delivery.

Attention is directed to "Irrigation Systems Functional Test" of these special provisions, regarding restrictions for planting operations.

Attention is directed to "Locate Existing Crossovers and Conduits" of these special provisions regarding locating existing irrigation water line crossovers and conduits shown on the plans to be incorporated in the new work. Existing irrigation water line crossovers and conduits shall be located prior to performing work on the irrigation system.

Attention is directed to "Existing Highway Irrigation Facilities" of these special provisions regarding the checking of existing irrigation facilities that are to remain in place, prior to the start of any irrigation work.

Attention is directed to Section 20-5.027B, "Wiring Plans and Diagrams," of the Standard Specifications regarding submittal of working drawings.

**10-1.02 WATER POLLUTION CONTROL**

Water pollution control work shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications and these special provisions.

Water pollution control work shall conform to the requirements in the Construction Contractor's Guide and Specifications of the Caltrans Storm Water Quality Handbooks, dated April 1997, and addenda thereto issued up to and including the date of advertisement of the project, hereafter referred to as the "Handbook." Copies of the Handbook may be obtained from the Department of Transportation, Material Operations Branch, Publication Distribution Unit, 1900 Royal Oaks Drive, Sacramento, California 95815, Telephone: (916) 445-3520.

The Contractor shall know and fully comply with the applicable provisions of the Handbook and Federal, State, and local regulations that govern the Contractor's operations and storm water discharges from both the project site and areas of disturbance outside the project limits during construction.



Unless arrangements for disturbance of areas outside the project limits are made by the Department and made part of the contract, it is expressly agreed that the Department assumes no responsibility whatsoever to the Contractor or property owner with respect to any arrangements made between the Contractor and property owner to allow disturbance of areas outside the project limits.

The Contractor shall be responsible for the costs and for liabilities imposed by law as a result of the Contractor's failure to comply with the requirements set forth in this section "Water Pollution Control" including, but not limited to, compliance with the applicable provisions of the Handbook and Federal, State, and local regulations. For the purposes of this paragraph, costs and liabilities include, but are not limited to, fines, penalties, and damages whether assessed against the State or the Contractor, including those levied under the Federal Clean Water Act and the State Porter Cologne Water Quality Act.

In addition to the remedies authorized by law, an amount of the money due the Contractor under the contract, as determined by the Department, may be retained by the State of California until disposition has been made of the costs and liabilities.

The retention of money due the Contractor shall be subject to the following:

- A. The Department will give the Contractor 30 days notice of the Department's intention to retain funds from partial payments which may become due to the Contractor prior to acceptance of the contract. Retention of funds from payments made after acceptance of the contract may be made without prior notice to the Contractor.
- B. No retention of additional amounts out of partial payments will be made if the amount to be retained does not exceed the amount being withheld from partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications.
- C. If the Department has retained funds and it is subsequently determined that the State is not subject to the costs and liabilities in connection with the matter for which the retention was made, the Department shall be liable for interest on the amount retained at the legal rate of interest for the period of the retention.

Conformance with the provisions in this section "Water Pollution Control" shall not relieve the Contractor from the Contractor's responsibilities as provided in Section 7, "Legal Relations and Responsibilities," of the Standard Specifications.

#### **WATER POLLUTION CONTROL PROGRAM PREPARATION, APPROVAL AND UPDATES**

As part of the water pollution control work, a Water Pollution Control Program, hereafter referred to as the "WPCP," is required for this contract. The WPCP shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications, the requirements in the Handbook, and these special provisions.

No work having potential to cause water pollution, as determined by the Engineer, shall be performed until the WPCP has been approved by the Engineer.

Within 20 days after the approval of the contract, the Contractor shall submit 3 copies of the WPCP to the Engineer. The Engineer will have 5 days to review the WPCP. If revisions are required, as determined by the Engineer, the Contractor shall revise and resubmit the WPCP within 5 days of receipt of the Engineer's comments. The Engineer will have 5 days to review the revisions. Upon the Engineer's approval of the WPCP, 3 additional copies of the WPCP incorporating the required changes shall be submitted to the Engineer. Minor changes or clarifications to the initial submittal may be made and attached as amendments to the WPCP. In order to allow construction activities to proceed, the Engineer may conditionally approve the WPCP while minor revisions or amendments are being completed.

The WPCP shall identify pollution sources that may adversely affect the quality of storm water discharges associated with the project and shall identify water pollution control measures, hereafter referred to as control measures, to be constructed, implemented, and maintained in order to reduce to the extent feasible pollutants in storm water discharges from the construction site during construction under this contract.

The WPCP shall incorporate control measures in the following categories:

- A. Soil stabilization practices;
- B. Sediment control practices;
- C. Sediment tracking control practices;
- D. Wind erosion control practices; and
- E. Nonstorm water management and waste management and disposal control practices.

Specific objectives and minimum requirements for each category of control measures are contained in the Handbook.

The Contractor shall consider the objectives and minimum requirements presented in the Handbook for each of the above categories. When minimum requirements are listed for any category, the Contractor shall incorporate into the WPCP and implement on the project, one or more of the listed minimum controls required in order to meet the pollution control objectives for the category. In addition, the Contractor shall consider other control measures presented in the Handbook and

shall incorporate into the WPCP and implement on the project the control measures necessary to meet the objectives of the WPCP. The Contractor shall document the selection process in conformance with the procedure specified in the Handbook.

The WPCP shall include, but not be limited to, the following items as described in the Handbook:

- A. Project description and Contractor's certification;
- B. Project information;
- C. Pollution sources, control measures, and water pollution control drawings; and
- D. Amendments, if any.

The Contractor shall amend the WPCP, graphically and in narrative form, whenever there is a change in construction activities or operations which may affect the discharge of significant quantities of pollutants to surface waters, ground waters, municipal storm drain systems or when deemed necessary by the Engineer. The WPCP shall be amended if the WPCP has not achieved the objective of reducing pollutants in storm water discharges. Amendments shall show additional control measures or revised operations, including those in areas not shown in the initially approved WPCP, which are required on the project to control water pollution effectively. Amendments to the WPCP shall be submitted for review and approval by the Engineer in the same manner specified for the initially approved WPCP. Amendments shall be dated and attached to the on-site WPCP document.

The Contractor shall keep a copy of the WPCP, together with updates, revisions and amendments at the project site.

### **WPCP IMPLEMENTATION**

Upon approval of the WPCP, the Contractor shall be responsible throughout the duration of the project for installing, constructing, inspecting, and maintaining the control measures included in the WPCP and any amendments thereto and for removing and disposing of temporary control measures. Unless otherwise directed by the Engineer or specified in these special provisions, the Contractor's responsibility for WPCP implementation shall continue throughout any temporary suspension of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications. Requirements for installation, construction, inspection, maintenance, removal, and disposal of control measures are specified in the Handbook and these special provisions.

Soil stabilization practices and sediment control measures, including minimum requirements, shall be provided throughout the winter season, defined as between October 15 and April 1.

Implementation of soil stabilization practices and sediment control measures for soil-disturbed areas on the project site shall be completed, except as provided for below, not later than 20 days prior to the beginning of the winter season or upon start of applicable construction activities for projects which begin either during or within 20 days of the winter season.

Throughout the winter season, the active, soil-disturbed area of the project site shall be not more than 1.9 hectares. The Engineer may approve, on a case-by-case basis, expansions of the active, soil-disturbed area limit. The Contractor shall demonstrate the ability and preparedness to fully deploy soil stabilization practices and sediment control measures to protect soil-disturbed areas on the project site before the onset of precipitation. A quantity of soil stabilization and sediment control materials shall be maintained on site equal to 100 percent of that sufficient to protect unprotected, soil-disturbed areas on the project site. A detailed plan for the mobilization of sufficient labor and equipment shall be maintained to fully deploy control measures required to protect unprotected, soil-disturbed areas on the project site prior to the onset of precipitation. A current inventory of control measure materials and the detailed mobilization plan shall be included as part of the WPCP.

Throughout the winter season, soil-disturbed areas on the project site shall be considered to be nonactive whenever soil disturbing activities are expected to be discontinued for a period of 20 or more days and the areas are fully protected. Areas that will become nonactive either during the winter season or within 20 days thereof shall be fully protected with soil stabilization practices and sediment control measures within 10 days of the discontinuance of soil disturbing activities or prior to the onset of precipitation, whichever is first to occur.

Throughout the winter season, active soil-disturbed areas of the project site shall be fully protected at the end of each day with soil stabilization practices and sediment control measures unless fair weather is predicted through the following work day. The weather forecast shall be monitored by the Contractor on a daily basis. The National Weather Service forecast shall be used. An alternative weather forecast proposed by the Contractor may be used if approved by the Engineer. If precipitation is predicted prior to the end of the following work day, construction scheduling shall be modified, as required, and functioning control measures shall be deployed prior to the onset of the precipitation.

The Contractor shall implement, year-round and throughout the duration of the project, control measures included in the WPCP for sediment tracking, wind erosion, nonstorm water management, and waste management and disposal.

The Engineer may order the suspension of construction operations which create water pollution if the Contractor fails to conform to the provisions in this section "Water Pollution Control" as determined by the Engineer.

## **MAINTENANCE**

To ensure the proper implementation and functioning of control measures, the Contractor shall regularly inspect and maintain the construction site for the control measures identified in the WPCP. The Contractor shall identify corrective actions and time needed to address any deficient measures or reinitiate any measures that have been discontinued.

The construction site inspection checklist provided in the Handbook shall be used to ensure that the necessary measures are being properly implemented, and to ensure that the control measures are functioning adequately. One copy of each site inspection record shall be submitted to the Engineer.

During the winter season, inspections of the construction site shall be conducted by the Contractor to identify deficient measures, as follows:

- A. Prior to a forecast storm;
- B. After all precipitation which causes runoff capable of carrying sediment from the construction site;
- C. At 24-hour intervals during extended precipitation events; and
- D. Routinely, at a minimum of once every 2 weeks.

If the Contractor or the Engineer identifies a deficiency in the deployment or functioning of an identified control measure, the deficiency shall be corrected immediately. The deficiency may be corrected at a later date and time if requested by the Contractor and approved by the Engineer in writing, but not later than the onset of subsequent precipitation events. The correction of deficiencies shall be at no additional cost to the State.

## **PAYMENT**

Full compensation for conforming to the provisions in this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

Those control measures which are shown on the plans and for which there is a contract item of work will be measured and paid for as that contract item of work.

The Engineer will retain an amount equal to 25 percent of the estimated value of the contract work performed during estimate periods in which the Contractor fails to conform to the provisions in this section "Water Pollution Control" as determined by the Engineer.

Retentions for failure to conform to the provisions in this section "Water Pollution Control" shall be in addition to the other retentions provided for in the contract. The amounts retained for failure of the Contractor to conform to the provisions in this section will be released for payment on the next monthly estimate for partial payment following the date that a WPCP has been implemented and maintained and water pollution is adequately controlled, as determined by the Engineer.

### **10-1.03 PRESERVATION OF PROPERTY**

Attention is directed to Section 7-1.11, "Preservation of Property," of the Standard Specifications and these special provisions.

Existing trees, shrubs and other plants, that are not to be removed as shown on the plans or specified in these special provisions, and are injured or damaged by reason of the Contractor's operations, shall be replaced by the Contractor. The minimum size of tree replacement shall be 600 mm box and the minimum size of shrub replacement shall be No. 15 container. Replacement planting shall conform to the requirements in Section 20-4.07, "Replacement," of the Standard Specifications. The Contractor shall water replacement plants in conformance with the provisions in Section 20-4.06, "Watering," of the Standard Specifications.

Damaged or injured plants shall be removed and disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13 of the Standard Specifications. At the option of the Contractor, removed trees and shrubs may be reduced to chips. The chipped material shall be spread within the highway right of way at locations designated by the Engineer.

Replacement planting of injured or damaged trees, shrubs, and other plants shall be completed prior to the start of the plant establishment period. Replacement planting shall conform to the provisions in Section 20-4.05, "Planting," of the Standard Specifications.

### **10-1.04 DAMAGE REPAIR**

Attention is directed to Section 7-1.16, "Contractor's Responsibility for the Work and Materials," and Section 7-1.165, "Damage by Storm, Flood, Tsunami or Earthquake," of the Standard Specifications and these special provisions.

Damage to slopes or other existing facilities occurring prior to the performance of the work provided for in this contract shall be repaired or reconstructed by the Contractor, as directed by the Engineer. Damage repair will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Storm damage caused by a change in the runoff pattern from that which existed on the day the Notice to Contractors for this project is dated and was the result of work by others within the right of way shall be repaired as directed by the Engineer. The total cost of ordered repair work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Damage to slopes or other facilities occurring after start of work and before start of plant establishment period shall be repaired or reconstructed by the Contractor in conformance with the provisions in Section 7-1.16, "Contractor's Responsibility for the Work and Materials," of the Standard Specifications.

Damage to slopes, plants, irrigation systems and other highway facilities occurring as a result of rain during the plant establishment period shall be repaired by the Contractor, when directed by the Engineer. The cost of the repairs which exceed the accumulated sum of \$4500 will be borne equally by the State and the Contractor. The division of cost will be made by determining the cost of repairs in conformance with the provisions in Section 9-1.03, "Force Account Payment," of the Standard Specifications, and paying to the Contractor one-half of the cost which exceeds the sum of \$4500.

When as a result of freezing conditions (as defined herein) during the plant establishment period, plants have died or, in the opinion of the Engineer, have deteriorated to a point beyond which the plants will not mature as typical examples of their species, the Engineer may direct replacement of the affected plants. The total cost of ordered plant replacement work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. A freezing condition, for the purpose of this specification, occurs when the temperature at or near the affected area has been officially recorded below 0°C and plants have been killed or damaged to the degree described above.

When the provisions in Section 7-1.165, "Damage by Storm, Flood, Tsunami or Earthquake," of the Standard Specifications are applicable, the provisions above for payment of costs for repair of damage due to rain, freezing conditions and drought shall not apply.

#### **10-1.05 OBSTRUCTIONS**

Attention is directed to Section 8-1.10, "Utility and Non-Highway Facilities," and Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Attention is directed to the existence of certain underground facilities that may require special precautions be taken by the Contractor to protect the health, safety and welfare of workers and of the public. Facilities requiring special precautions include, but are not limited to: conductors of petroleum products, oxygen, chlorine, and toxic or flammable gases; natural gas in pipelines greater than 150 mm in diameter or pipelines operating at pressures greater than 415 kPa (gage); underground electric supply system conductors or cables, with potential to ground of more than 300 V, either directly buried or in a duct or conduit which do not have concentric grounded or other effectively grounded metal shields or sheaths.

The Contractor shall notify the Engineer and the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to performing any excavation or other work close to any underground pipeline, conduit, duct, wire or other structure. Regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	1-800-642-2444 1-800-227-2600
Underground Service Alert-Southern California (USA)	1-800-422-4133 1-800-227-2600

If these facilities are not located on the plans in both alignment and elevation, no work shall be performed in the vicinity of the facilities, except as provided herein for conduit to be placed under pavement, until the owner, or the owner's representative, has located the facility by potholing, probing or other means that will locate and identify the facility. Conduit to be installed under pavement in the vicinity of these facilities shall be placed by the trenching method in conformance with the provisions in "Conduit" of these special provisions. If, in the opinion of the Engineer, the Contractor's operations are delayed or interfered with by reason of the utility facilities not being located by the owner or the owner's representative, the State will compensate the Contractor for the delays to the extent provided in Section 8-1.09, "Right of Way Delays," of the Standard Specifications, and not otherwise, except as provided in Section 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications.

#### **10-1.06 CONSTRUCTION AREA SIGNS**

Construction area signs shall be furnished, installed, maintained, and removed when no longer required in conformance with the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to the provisions in "Approved Traffic Products" of these special provisions. Type II retroreflective sheeting shall not be used on construction area sign panels.

The Contractor shall notify the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to commencing excavation for construction area sign posts. The regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	1-800-642-2444 1-800-227-2600
Underground Service Alert-Southern California (USA)	1-800-422-4133 1-800-227-2600

Excavations required to install construction area signs shall be performed by hand methods without the use of power equipment, except that power equipment may be used if it is determined there are no utility facilities in the area of the proposed post holes.

Sign substrates for stationary mounted construction area signs may be fabricated from fiberglass reinforced plastic as specified under "Approved Traffic Products" of these special provisions.

#### **10-1.07 MAINTAINING TRAFFIC**

Attention is directed to Sections 7-1.08, "Public Convenience," 7-1.09, "Public Safety," and 12, "Construction Area Traffic Control Devices," of the Standard Specifications and to the provisions in "Public Safety" of these special provisions and these special provisions. Nothing in these special provisions shall be construed as relieving the Contractor from the responsibilities specified in Section 7-1.09.

No work that would require a lane closure shall be performed.

Personal vehicles of the Contractor's employees shall not be parked on the traveled way or shoulders including any section closed to public traffic.

Whenever vehicles or equipment are parked on the shoulder within 1.8 m of a traffic lane, the shoulder area shall be closed with fluorescent traffic cones or portable delineators placed on a taper in advance of the parked vehicles or equipment and along the edge of the pavement at 7.5 m intervals to a point not less than 7.5 m past the last vehicle or piece of equipment. A minimum of 9 cones or portable delineators shall be used for the taper. A C23 (Road Work Ahead) or C24 (Shoulder Work Ahead) sign shall be mounted on a portable sign stand with flags. The sign shall be placed where designated by the Engineer.

### **SECTION 10-2. HIGHWAY PLANTING AND IRRIGATION SYSTEMS**

#### **10-2.01 GENERAL**

The work performed in connection with highway planting and irrigation systems shall conform to the provisions in Section 20, "Erosion Control and Highway Planting," of the Standard Specifications and these special provisions.

Plants located on the right side of Route 41 at Sta 336 shall be hand watered in conformance with Section 20-4.06, "Watering," of the Standard Specifications.

#### **10-2.02 EXISTING HIGHWAY IRRIGATION FACILITIES**

In addition to the provisions in Section 20, "Erosion Control and Highway Planting," of the Standard Specifications, the work performed in connection with the various existing highway irrigation system facilities shall conform to the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Water shall be maintained in conformance with the provisions in Section 20-5.025, "Maintain Existing Water Supply," of the Standard Specifications.

#### **LOCATE EXISTING CROSSOVERS AND CONDUITS**

Existing crossovers and conduits shown on the plans to be incorporated in the new work shall be located in conformance with the provisions for locating conduits in Section 20-5.03B, "Conduit for Irrigation Crossovers," of the Standard Specifications.

Unless otherwise directed by the Engineer, existing crossovers and conduits shown on the plans to be incorporated in the new work shall be located prior to performing work on irrigation systems.

If debris is encountered in the ends of conduits, the debris shall be removed prior to performing other work in the conduits. Removal of debris within the first one meter in these conduits shall be at the Contractor's expense. If debris is encountered in the conduits more than one meter from the ends of the conduits, the additional debris shall be removed as directed by the Engineer and the removal work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

## CHECK AND TEST EXISTING IRRIGATION FACILITIES

Existing irrigation facilities that are to remain or to be relocated, and that are to be part of the new irrigation system, shall be checked for missing or damaged components, and for proper operation prior to performing irrigation system work.

A written list of existing irrigation system deficiencies shall be submitted to the Engineer within 5 working days after checking the existing facilities.

Deficiencies found during checking of the existing facilities shall be corrected as directed by the Engineer. Corrective work ordered by the Engineer will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Existing backflow preventers shall be tested in conformance with the provisions in "Irrigation Systems" of these special provisions.

Repairs to the existing irrigation facilities ordered by the Engineer after checking and testing the facilities, and further repairs required thereafter as ordered by the Engineer, except as otherwise provided under "Existing Highway Irrigation Facilities" of these special provisions, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Full compensation for checking and testing existing irrigation facilities, including testing existing backflow preventers, shall be considered as included in the contract prices paid per meter for the various sizes of plastic pipe (supply line) and no additional compensation will be allowed therefor.

## 10-2.03 HIGHWAY PLANTING

The work performed in connection with highway planting shall conform to the provisions in Section 20-4, "Highway Planting," of the Standard Specifications and these special provisions.

### HIGHWAY PLANTING MATERIALS

#### Mulch

Mulch shall consist of either wood chips or tree bark or a combination of both.

#### Commercial Fertilizer

Commercial fertilizer (tablet) shall be slow release and shall be in tablet form. Each tablet, as shown in the Plant List of the plans, shall have a mass of  $21 \text{ g} \pm 1 \text{ g}$ , and shall have the following guaranteed chemical analysis:

Ingredient	Percentage
Nitrogen	20
Phosphoric Acid	10
Water Soluble Potash	5

At the option of the Contractor, two 10.5-g tablets may be used in place of each 21-g tablet designated on the plans or specified in these special provisions. Regardless of the tablet size used, each tablet shall be the slow release type and shall have the same guaranteed chemical analysis as specified for the 21-g tablets. Each 10.5-g tablet shall have a mass of  $10.5 \text{ g} \pm 0.5\text{-g}$ .

### ROADSIDE CLEARING

Prior to preparing planting areas and wild flower seeding areas, or commencing irrigation trenching operations for planting areas, trash and debris shall be removed from these areas and a distance of 3 m beyond the edges of those areas. At locations where proposed planting areas are 3.6 m or more from the edges of dikes, curbs, sidewalks, fences, walls, paved shoulders and existing planting to remain or to be maintained, the clearing limit shall be 2 m beyond the outer limits of the proposed planting area.

In addition to removing trash and debris, the project area shall be cleared as specified herein:

- A. Weeds shall be killed and removed within planting areas where plants are to be planted in groups or rows 4.6 m or less apart and from within an area extending 2 m beyond the outer limits of the groups or rows of plants.
- B. Weeds shall be killed and removed within an area 2 m in diameter centered at each plant location where the plants are to be planted more than 4.6 m apart.

After the initial roadside clearing is complete, additional roadside clearing work shall be performed as necessary to maintain the areas, as specified above, in a neat appearance until the start of the plant establishment period. This work shall include the following:

- A. Trash and debris shall be removed.
- B. Rodents shall be controlled.
- C. Weed growth shall be killed before the weeds reach the seed stage of growth or exceed 150 mm in length, except for weeds in wild flower seeding areas to be mowed.
- D. Weeds in plant basins, including basin walls, shall be removed by hand pulling, after the plants have been planted.

### **Weed Control**

Weed control shall also conform to the following:

- A. Stolon type weeds shall be killed with glyphosate.
- B. Disposal of mowed material and killed weeds after initial roadside clearing will not be required, unless otherwise directed by the Engineer. When directed by the Engineer, mowed material and killed weeds shall be disposed of and the disposal will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

### **PESTICIDES**

Pesticides used to control weeds shall conform to the provisions in Section 20-4.026, "Pesticides," of the Standard Specifications. Except as otherwise provided in these special provisions, pesticide use shall be limited to the following materials:

Cacodylic Acid  
 Dichlobenil (Preemergent)  
 Fluazifop-butyl  
 Glyphosate  
 Isoxaben (Preemergent)  
 Sethoxydim  
 Oxadiazon - 50 percent WP (Preemergent)  
 Oryzalin (Preemergent)  
 Pendimethalin (Preemergent)  
 Proflam (Preemergent)  
 Trifluralin (Preemergent)  
 Napropamide (Preemergent)

Granular forms of Oxadiazon or Dichlobenil shall be applied in areas to be covered with mulch.

Preemergents shall be applied prior to the application of mulch. Once the preemergent is applied to the mulch areas, mulch applications shall be completed in that area on the same working day.

Glyphosate shall be used to kill stolon type weeds.

Oxadiazon shall be of the emulsifiable concentration or wettable powder type, except when Oxadiazon is used under mulch in conformance with these special provisions.

A minimum of 100 days shall elapse between applications of preemergents.

Preemergents shall not be applied within 450 mm of plants or within wild flower seeding areas.

If the Contractor elects to request the use of other pesticides on this project, the request shall be submitted, in writing, to the Engineer not less than 10 working days prior to the intended use of the other pesticides. Except for the pesticides listed in these special provisions, no pesticides shall be used or applied without prior written approval of the Engineer.

Pesticides shall not be applied within the limits of the plant basins. Pesticides shall not be applied in a manner that allows the pesticides to come in contact with the foliage and woody parts of the plants.

### **PLANTING**

Where removal of existing erosion control blanket is necessary for plant installation, prior to excavation, existing erosion control blanket shall be cut with a sharp knife or shears to prevent tearing. Erosion control blanket shall not be removed beyond the outer perimeter of the plant basin. Cut edges of the erosion control blanket to remain shall be secured in place with wire staples. Staples for erosion control blanket shall be made of 11-gage minimum steel wire and shall be U-shaped with 200-mm legs and 50-mm crown.

Commercial fertilizer shall be applied or placed at the time of planting and at the rates shown on the plans.

A granular preemergent shall be applied to areas to be covered with mulch outside of plant basins in conformance with the provisions in "Pesticides" of these special provisions.

Mulch placed in areas outside of plant basins shall be spread to a depth of not less than 100 mm.

Mulch shall not be placed within one meter of the center line of earthen drainage ditches, within one meter of the edge of paved ditches, and within one meter of the center line of drainage flow lines.

Attention is directed to "Irrigation Systems Functional Test" of these special provisions regarding functional tests of the irrigation systems. Planting shall not be performed in an area until the functional test has been completed for the irrigation system serving that area.

Full compensation for furnishing and applying commercial fertilizer (tablet) and pesticides shall be considered as included in the contract unit prices paid for the various items of plants involved and no separate payment will be made therefor.

Cutting and removing of erosion control blanket will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

### **FOLIAGE PROTECTOR**

Foliage protectors shall be installed in conformance with the details shown on the plans, the provisions in Section 20-2.14, "Foliage Protector," and Section 20-4, "Highway Planting," of the Standard Specifications and these special provisions.

Each foliage protector shall be held in place with two 13-mm steel reinforcing bar support stakes, a minimum of 1.5 m long. Support stakes shall be installed vertically a minimum of 0.3-m deep on the opposite sides of the plant in a direction transverse to the prevailing winds.

### **WILD FLOWER SEEDING**

Wild flower seeding shall conform to the provisions in Section 20-3, "Erosion Control," of the Standard Specifications and these special provisions.

Wild flower seeding work shall consist of mowing weeds, scarifying the soil, and dry applying seed to areas shown on the plans as "Wild Flower Seeding."

Wild flower seeding materials shall not be applied prior to October 15 or after January 1. If wild flower seeding work cannot be performed prior to the start of plant establishment and within the above specified time limit, then the work shall be performed during the plant establishment period when directed by the Engineer.

Pesticides shall not be used on wild flower seeding areas after the seed has been applied.

### **Site Preparation**

Immediately prior to planting wild flower seeding areas, trash and debris shall be removed, and weeds shall be mowed as close to the ground as possible. Removal of mowed material will not be required. After mowing and just prior to seed application, wild flower seeding areas shall be scarified to a minimum depth of 25 mm.

Removed trash and debris shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Materials shall conform to the provisions in Section 20-2, "Materials," of the Standard Specifications and these special provisions.

### **Seed**

Seed shall conform to the provisions in Section 20-2.10, "Seed," of the Standard Specifications. Individual seed species shall be measured and mixed in the presence of the Engineer.

Seed shall be delivered to the job site in unopened separate containers with the seed tag attached. Containers without a seed tag will not be accepted.

A sample of approximately 30 g of seed will be taken from each seed container by the Engineer.

Seed shall consist of the following:

#### **NON-LEGUME SEED**

Botanical Name (Common Name)	Percent Germination (Minimum)	Kilograms Pure Live Seed Per Hectare (Slope Measurement)
Clarkia amoena Farewell-to-Spring	50	3.0
Eschscholzia californica California Poppy	50	8.0



## **Commercial Fertilizer**

### **Application**

Wild flower seed shall be applied at the rate of 11.0 kg per hectare (slope measurement).

Seed shall be incorporated into the soil to a maximum depth of 6 mm by raking, dragging or drilling.

### **MEASUREMENT AND PAYMENT**

Quantities of wild flower seeding will be measured by the hectare.

The contract price paid per hectare for wild flower seeding shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in performing wild flower seeding, complete in place, including removing trash and debris, mowing weeds, scarifying the soil, , as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **PLANT ESTABLISHMENT WORK**

The plant establishment period shall be Type 1 and shall be 750 working days.

If wild flower seeding cannot be performed within the time limits specified under "Wild Flower Seeding" of these special provisions and the Engineer determines that the work except wild flower seeding and plant establishment work has been completed, the Engineer will notify the Contractor in writing of the start of the plant establishment period.

Wild flower seeding not performed prior to the start of the plant establishment period shall be performed during the plant establishment period. The work involved in preparing areas to receive wild flower seeding and applying seed shall be in conformance with the provisions in "Wild Flower Seeding" of these special provisions.

After sowing wild flower seed, plant establishment work for the wild flower seeding areas will not be required except for removing trash and debris and mowing. Mowing shall be performed after the wild flower seeds have set and the wild flowers have begun to die back.

Weeds within plant basins, including basin walls, shall be controlled by hand pulling.

Weeds within mulched areas , but outside of plant basins, shall be controlled by killing.

Weeds outside of mulched areas, plant basins, and paved areas shall be controlled by mowing. At locations where proposed planting areas are 3.6 m or more from the edges of existing plantings to remain and from shoulders, dikes, curbs, sidewalks, fences, and walls, the mowing limit shall be 2 m beyond the outer limits of the proposed planting area.

Vines shall be trained onto walls.

Except as specified in these special provisions, disposal of mowed material will not be required unless ordered by the Engineer. Disposal of mowed material, as directed by the Engineer, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

At the option of the Contractor, plants of a larger container size than those originally specified may be used for replacement plants during the first 125 working days of the plant establishment period. The use of plants of a larger container size than those originally specified for replacement plants shall be at the Contractor's expense.

After 125 working days of the plant establishment period have been completed, replacement of plants shall be No. 5 size for No. one size plants; and other plant replacement plants shall be the same size as originally specified.

During the plant establishment period, if plants become restricted by foliage protectors, the tops of foliage protectors shall be removed. Foliage protectors shall be completely removed, including the support stakes, within 15 working days prior to completion of the plant establishment period.

Wye strainers and wye filters in valve assembly units shall be cleaned at least 15 days prior to the completion of the plant establishment period.

Plastic pipe irrigation line shall be removed and disposed of at least 5 days prior to the completion of the plant establishment period. Removed plastic pipe irrigation line shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The final inspection shall be performed in conformance with the provisions in Section 5-1.13, "Final Inspection," of the Standard Specifications and shall be completed a minimum of 20 working days before the estimated completion of the contract.

Full compensation for weed control, rodent control, cleaning of wye filters, removing foliage protectors, and removing and disposing of plastic pipe irrigation line during the plant establishment period shall be considered as included in the contract lump sum price paid for plant establishment work and no additional compensation will be allowed therefor.

#### **10-2.04 IRRIGATION SYSTEMS**

Irrigation systems shall be furnished and installed in conformance with the provisions in Section 20-5, "Irrigation Systems," of the Standard Specifications, except materials containing asbestos fibers shall not be used.

Attention is directed to the provisions in "Obstructions" of these special provisions, regarding work over or adjacent to existing underground facilities. Excavation for proposed irrigation facilities shall not be started until the existing underground facilities have been located.

Pipe supply lines shall be pressure tested in conformance with the provisions in Section 20-5.03H, "Pressure Testing," of the Standard Specifications, except the pipe (supply line) on the discharge side of the control valve shall be tested by Method B as specified in Section 20-5.03H(2), "Method B," of the Standard Specifications.

Only pipeline trenches and excavation pits for supply lines being supplied from one water service point shall be open at one time. After pressure testing is complete, trenches and pits excavated for pipe supply lines, being supplied from one water service point, shall be backfilled prior to commencing excavations for pipe supply lines being supplied from another water service point.

Where removal of existing erosion control blanket is necessary for excavation of pipe supply line trenches, prior to excavation, existing erosion control blanket shall be cut with a sharp knife or shears to prevent tearing. Erosion control blanket shall be removed only to the minimum extent necessary for trench construction. Cut edges of the erosion control blanket to remain shall be secured in place with wire staples. Staples for erosion control blanket shall be made of 11-gage minimum steel wire and shall be U-shaped with 200-mm legs and 50-mm crown.

Cutting and removing of erosion control blanket will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

#### **VALVE BOXES**

Valve boxes shall conform to the provisions in Section 20-2.24, "Valve Boxes," of the Standard Specifications, except as otherwise provided herein.

Valve boxes shall be fiberglass or reinforced plastic.

Covers for glass fiber reinforced plastic or plastic valve boxes shall be glass fiber reinforced plastic or plastic.

Valve boxes shall be identified on the top surface of the covers by stenciling with paint the appropriate abbreviations for the irrigation facilities contained in the valve boxes as shown on the plans. Valve boxes that contain remote control valves shall be identified by the appropriate letters and numbers (controller and station numbers). The letters and numbers shall be 50 mm in height. The stenciling paint shall be a commercial quality, epoxy resin base paint of a color which contrasts with the valve box covers.

#### **ELECTRIC AUTOMATIC IRRIGATION COMPONENTS**

##### **Irrigation Controllers**

Irrigation controllers shall be single, solid-state independent controllers conforming to the following:

- A. Irrigation controllers shall be fully automatic and shall operate a complete 14-day or longer irrigation program.
- B. A switch or switches shall be provided on the face of the control panel that will turn the irrigation controller "on" or "off" and provide for automatic or manual operation. Manual operation shall allow cycle start at the desired station and shall allow activation of a single station.
- C. The watering time of each station shall be displayed on the face of the control panel.
- D. The irrigation controller and the low voltage output source shall be protected by fuses or circuit breakers.
- E. The irrigation controller mechanism, panel and circuit board shall be connected to the low voltage control and neutral conductors by means of plug and receptacle connectors located in the irrigation controller enclosure.
- F. Each station shall have a variable or incremental timing adjustment with a range of 12 hours to a minimum of one minute.
- G. Irrigation controllers shall be capable of a minimum of 2 program schedules.
- H. Irrigation controllers shall have an output that can energize a pump start circuit or a remote control valve (master).
- I. Irrigation controllers shall be manufactured by the same company.
- J. Where direct burial conductors are to be connected to the terminals strip, the conductors shall be connected with the proper size open-end crimp-on wire terminals. No exposed wire shall extend beyond the crimp of the terminal and the wires shall be parallel on the terminal strip.

Attention is directed to the provisions in Section 10-3, "Signals, Lighting and Electrical Systems," of these special provisions, regarding electrical power for irrigation controllers and irrigation controller enclosure cabinets.

### **Electric Remote Control Valves**

Electric remote control valves shall conform to the provisions in Section 20-2.23, "Control Valves," of the Standard Specifications and the following:

- A. Valves shall be brass construction.
- B. Valves shall be angle pattern (bottom inlet) or straight pattern (side inlet) as shown on the plans.
- C. Valves shall be pressure regulating. Valves shall have an adjustable discharge pressure range of 103 kPa to 862 kPa. Valves shall have an operating inlet pressure range of 172 kPa to 1034 kPa.
- D. Valves shall have removable self-flushing filter screens.

### **Pull Boxes**

Pull box installations shall conform to the provisions in Section 20-5.027I, "Conductors, Electrical Conduits and Pull Boxes," of the Standard Specifications.

### **Conductors**

Low voltage, as used in this section "Conductors," shall mean 36 V or less.

Low voltage control and neutral conductors in pull boxes and valve boxes, at irrigation controller terminals, and at splices shall be marked as follows:

- A. Conductor terminations and splices shall be marked with adhesive backed paper markers or adhesive cloth wrap-around markers, with clear, heat-shrinkable sleeves sealed over the markers.
- B. Non-spliced conductors in pull boxes and valve boxes shall be marked with clip-on, "C" shaped, white extruded polyvinyl chloride sleeves. Marker sleeves shall have black, indented legends of uniform depth with transparent overlays over the legends and "chevron" cuts for alignment of 2 or more sleeves.

Markers for the control conductors shall be identified with the appropriate number or letter designations of irrigation controllers and station numbers. Markers for neutral conductors shall be identified with the appropriate number or letter designations of the irrigation controllers.

The color of low voltage neutral and control conductor insulation, except for the striped portions, shall be homogeneous throughout the entire thickness of the insulation.

Insulation for conductors may be UL listed polyethylene conforming to UL44 test standards with a minimum insulation thickness of 1.05 mm for wire sizes 10AWG and smaller.

### **IRRIGATION SYSTEMS FUNCTIONAL TEST**

Functional tests for the irrigation controllers and associated automatic irrigation systems shall conform to the provisions in Section 20-5.027J, "Testing," of the Standard Specifications and these special provisions.

Tests shall demonstrate to the Engineer, through one complete cycle of the irrigation controllers in the automatic mode, that the associated automatic components of the irrigation systems operate properly. If automatic components of the irrigation systems fail a functional test, these components shall be repaired at the Contractor's expense and the testing repeated until satisfactory operation is obtained.

Associated automatic components shall include, but not be limited to remote control valves.

Upon completion of work on an irrigation system, including correction of deficiencies and satisfactory functional tests for the systems involved, the plants to be planted in the area watered by the irrigation system may be planted provided the planting areas have been prepared as specified in these special provisions.

### **BACKFLOW PREVENTER ASSEMBLIES**

Backflow preventers shall conform to the provisions in Section 20-2.25, "Backflow Preventers," of the Standard Specifications and these special provisions.

Pressure loss through the backflow preventers shall not exceed the following:

BACKFLOW PREVENTER SIZE (millimeters)	FLOW RATE (Liters per minute)	PRESSURE LOSS (kPa)
40	610	120

Backflow preventer assemblies shall be painted with a minimum of 2 applications of a commercial quality enamel paint. The color of the paint shall be light brown.

Backflow preventer assemblies shall include a reusable pre-manufactured frost blanket cover. The blanket fabric shall be water, mildew and flame resistant polymeric resin coated polyester. Blankets shall have compression packaged fiberglass insulation with a minimum insulating value of R-13 and shall include a metal grommet for installation of a padlock. The blanket shall be of sufficient size to completely enclose the backflow preventer, wye strainer, and all associated above-ground pipe and fittings.

### **TESTING BACKFLOW PREVENTERS**

New backflow preventers installed by the Contractor shall be tested for proper operation in conformance with the provisions in Section 20-5.03J, "Check and Test Backflow Preventers," of the Standard Specifications and these special provisions.

Tests for new backflow preventers shall be satisfactorily completed after installation of the backflow preventer assembly and before operation of the irrigation systems.

New backflow preventers shall be retested one year after the satisfactory completion of the previous test or 10 days prior to completion of the plant establishment period, whichever occurs first.

Testing existing and relocated backflow preventers will be paid for in conformance with the provisions in "Checking and Testing Existing Irrigation Facilities" of these special provisions.

### **SPRINKLERS**

Sprinklers shall conform to the type, pattern, material, and operating characteristics listed in the "Sprinkler Schedule" shown on the plans.

#### **SPRINKLER (TYPE D)**

Type D sprinklers shall be plastic, nonadjustable, pressure compensating emitters with automatic flushing action. Emitters shall have the flow rate and operating pressure range shown on the plans.

Emitters shall be installed as shown on the plans and in conformance with the manufacturer's written instructions. Two copies of the written instructions shall be furnished to the Engineer prior to installation.

One emitter shall be installed per plant. Emitters shall be installed on the up-slope side of the plants such that water thoroughly moistens the plant roots.

Emitters shall be equipped with a single barb.

Flexible tubing for the emitters shall be virgin polyethylene plastic containing 2 percent to 3 percent carbon black. The size of the tubing shall be as recommended by the manufacturer of the emitter.

Discharge ends of tubing shall be held in place, within the basin and approximately 50 mm above grade, by plastic or metal stakes. Stakes shall be as recommended by the manufacturer of the emitter.

### **WYE STRAINERS**

Wye strainers shall consist of a wye filter, valve box, wire mesh and gravel or crushed rock as shown on the plans.

Wye strainers shall be installed on the downstream side of the cam coupler assemblies as shown on the plans.

Wye filters shall withstand a cold water working pressure of 1034 kPa.

Wye filter housings shall be manufactured of brass, bronze, reinforced polypropylene plastic or glass-filled nylon.

Wye filter cartridges shall be reusable stainless steel or polyester mesh and shall be capable of 75 µm size mesh filtration.

Full compensation for wye filter, valve box, wire mesh, gravel or crushed rock, and pipe fittings shall be considered as included in the contract unit price paid for the size of wye strainer involved and no separate payment will be allowed therefor.

### **VALVE ASSEMBLY UNIT**

A valve assembly unit shall consist of an electric remote control valve, wye filter, pipe, fittings, valve box, wire mesh and gravel or crushed rock as shown on plans.

Electric remote control valves shall conform to the provisions in "Electric Automatic Irrigation Components" of these special provisions.

Wye filters shall be installed on the upstream side of the electric remote control valves.

Wye filters shall withstand a cold water working pressure of 1034 kPa.

Wye filter housings shall be manufactured of brass, bronze, reinforced polypropylene plastic or glass-filled nylon.

Wye filter cartridges shall be reusable stainless steel or polyester mesh and shall be capable of 75 µm size mesh filtration.

Pipe used for valve assembly units shall be Schedule 80 polyvinyl chloride (PVC) and shall conform to the provisions in Section 20-2.15, "Pipe," of the Standard Specifications. Fittings shall be injection molded polyvinyl chloride (PVC), Schedule 80, conforming to the requirements in ASTM Designation: D 2467.

The quantity of valve assembly units will be measured by the unit as determined from actual count in place.

The contract unit price paid for valve assembly unit shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the valve assembly units, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **BALL VALVE**

Ball Valves shall be polyvinyl chloride (PVC). The ball seats shall be high molecular weight high density polyethylene.

Ball valves shall be installed in a valve box as shown on the plans.

The contract unit price paid for ball valves shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in ball valves, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **CAM COUPLER ASSEMBLY**

Cam coupler assembly shall consist of a cam coupler with dust cap, galvanized steel nipples, galvanized and plastic pipe fittings, concrete support and valve box as shown on the plans.

Cam couplers shall be manufactured of brass or bronze.

The quantity of cam coupler assemblies will be measured by the unit as determined from actual count in place.

The contract unit price paid for cam coupler assembly shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in installing cam coupler assembly, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **FINAL IRRIGATION SYSTEM CHECK**

A final check of new irrigation facilities shall be performed not more than 20 working days prior to acceptance of the contract.

The length of watering cycles using potable water measured by water meters for the final check of irrigation facilities will be determined by the Engineer.

Remote control valves connected to new irrigation controllers shall be checked for automatic performance when the controllers are in automatic mode.

Unsatisfactory performance of irrigation facilities installed or modified by the Contractor shall be repaired and rechecked at the Contractor's expense until satisfactory performance is obtained, as determined by the Engineer.

Nothing in this section "Final Irrigation System Check" shall relieve the Contractor of full responsibility for making good or repairing defective work or materials found before the formal written acceptance of the entire contract by the Director.

Full compensation for checking the irrigation systems prior to the acceptance of the contract shall be considered as included in the contract lump sum price paid for plant establishment work and no additional compensation will be allowed therefor.

## **SECTION 10-3. ELECTRICAL SYSTEMS**

### **10-3.01 DESCRIPTION**

Irrigation controller enclosure cabinet and electric service (irrigation) shall conform to the provisions in Section 86, "Signals, Lighting and Electrical Systems," of the Standard Specifications and these special provisions.

### **10-3.02 COST BREAK-DOWN**

Cost break-downs shall conform to the provisions in Section 86-1.03, "Cost Break-Down," of the Standard Specifications and these special provisions.

The Engineer shall be furnished a cost break-down for each contract lump sum item of work described in this Section 10-3.

The cost break-down shall be submitted to the Engineer for approval within 15 days after the contract has been approved. The cost break-down shall be approved, in writing, by the Engineer before any partial payment for the items of electrical work will be made.

### 10-3.03 CONDUIT

Conduit to be installed underground shall be Type 1 or Type 3 unless otherwise specified. Detector termination conduits shall be Type 3 or Type 4.

The conduit in a foundation and between a foundation and the nearest pull box shall be Type 1.

Conduit sizes shown on the plans and specified in the Standard Specifications and these special provisions are referenced to metallic type conduit. When rigid non-metallic conduit is required or allowed, the nominal equivalent industry size shall be used as shown in the following table:

Size Designation for Metallic Type Conduit	Equivalent Size for Rigid Non-metallic Conduit
21	20
27	25
41	40
53	50
63	65
78	75
103	100

When a standard coupling cannot be used for joining Type 1 conduit, a UL listed threaded union coupling conforming to the provisions in Section 86-2.05C, "Installation," of the Standard Specifications shall be used.

When Type 3 conduit is placed in a trench (not in pavement or under portland cement concrete sidewalk), after the bedding material is placed and the conduit is installed, the trench shall be backfilled with commercial quality concrete, containing not less than 250 kg of portland cement per cubic meter, to not less than 100 mm above the conduit before additional backfill material is placed.

After conductors have been installed, the ends of conduits terminating in pull boxes, service equipment enclosures, and controller cabinets shall be sealed with an approved type of sealing compound.

At those locations where conduit is required to be installed under pavement and existing underground facilities require special precautions in conformance with the provisions in "Obstructions" of these special provisions, conduit shall be placed by the "Trenching in Pavement Method" in conformance with the provisions in Section 86-2.05C, "Installation," of the Standard Specifications.

### 10-3.04 PULL BOXES

Grout shall be placed in the bottom of pull boxes.

### 10-3.05 CONDUCTORS AND WIRING

Splices shall be insulated by "Method B" or, at the Contractor's option, splices of conductors shall be insulated with heat-shrink tubing of the appropriate size after thoroughly painting the spliced conductors with electrical insulating coating.

The minimum insulation thickness, at any point, for Type USE, RHH or RHW wire shall be 1.0 mm for conductor sizes No. 14 to No. 10, inclusive, and 1.3 mm for No. 8 to No. 2, inclusive. The minimum insulation thickness, at any point, for Type THW and TW wires shall be 0.69 mm for conductor sizes No. 14 to No. 10, inclusive, 1.02 mm for No. 8, and 1.37 mm for No. 6 to No. 2, inclusive.

### 10-3.06 ELECTRIC SERVICE (IRRIGATION)

Electric service (irrigation) shall be from the service points to the irrigation controllers (IC) and to the spaces provided in the irrigation controller enclosure cabinets (CEC) for irrigation controllers as shown on the plans.

Irrigation Controller (IC) A and B: A single-pole, 20-A circuit breaker shall be installed in the existing service equipment enclosure cabinet. The circuit breaker shall be of the same manufacturer and model and interrupting capacity as the existing circuit breakers.

Electric service (irrigation) will be paid for on a lump sum basis.

The contract lump sum price paid for electric service (irrigation) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing electric service (irrigation) for irrigation controllers, complete in place, including conductors, conduit and pull boxes to the pull box adjacent to irrigation controller enclosure cabinets and irrigation controllers, as shown on the plans, as specified in these special provisions, and as directed by the Engineer.

### **10-3.07 IRRIGATION CONTROLLER ENCLOSURE CABINET**

Irrigation controller enclosure cabinets (CEC) shall be constructed and the equipment within the cabinets shall be installed in conformance with the details shown on the plans, the provisions in the Standard Specifications, and these special provisions.

Irrigation controller enclosure cabinets shall be of metal construction conforming to the details for empty Type P signal cabinets shown on Standard Plans ES-3A and ES-3C, except that the fluorescent interior light, police panels, and shelves shall not be provided, unless otherwise shown on the plans. Cabinets shall be provided with cross ventilation, roof ventilation or a combination of both. The anchorage arrangement shall be inside the cabinet as shown on the plans. Dimensions of the cabinet shall be suitable for the equipment to be installed as shown on the plans and specified in these special provisions.

Irrigation controller enclosure cabinets shall be fabricated in conformance with the provisions in Section 86-3.04A, "Cabinet Construction," of the Standard Specifications.

Irrigation controller enclosure cabinets shall be fabricated of cold rolled steel.

Irrigation controller enclosure cabinets fabricated of cold rolled steel shall be cleaned and painted in conformance with the provisions in Section 86-3.04A, "Cabinet Construction," of the Standard Specifications, except the finish color of the irrigation controller enclosure cabinets shall be light brown conforming to Federal Standard 595B, Color No. 20450.

Door locks for the irrigation controller enclosure cabinets shall be a removable-core mortise cam cylinder door lock that receives the State's lock core. The State's lock core is a "Best" construction core. Keys shall be removable from the locks in the locked position only. Door locks shall be installed in conformance with the manufacturer's written instructions and recommendations. Two keys for each door lock shall be delivered to the Engineer.

Inside of the doors shall have provisions for storage of the irrigation plans.

Duplex convenience receptacles shall have ground-fault circuit interruption as defined by the Code. Circuit interruption shall occur on 6 mA of ground-fault current and shall not occur on less than 4 mA. Receptacles shall be installed in a weatherproof housing with rainproof lift covers.

Equipment, except for field wiring, shall be installed in the cabinet in a shop prior to field installation.

Irrigation controller enclosure cabinets will be measured by the unit as determined from actual count in place.

The contract unit price paid for irrigation controller enclosure cabinet shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in fabricating and installing irrigation controller enclosure cabinets, complete in place, including constructing foundations, pads and conduits to pull box adjacent to cabinets, and installing equipment within the cabinets, except controllers, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **SECTION 11. (BLANK)**

### **SECTION 12. (BLANK)**

### **SECTION 13. RELATIONS WITH RAILROAD**

**13-1.01 GENERAL.**--The Contractor's attention is directed to the track and right of way of the Union Pacific Railroad Company at Salinas River Viaduct, State Bridge No. 49-219, PUC No. E-226.7-A, Route 41, within the limits of the project.

No work is to be performed within 50 feet of tracks.

In accordance with Section 7-1.12, "Responsibility for Damage" of the Standard Specifications, the Contractor shall be responsible for all damage to Railroad tracks, appurtenances and facilities thereto and to Railroad equipment operating on such track, resulting from his operations.

No men or equipment are to trespass on Railroad right of way at track levels at Salinas River Viaduct.