

DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30th Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

www.dot.ca.gov/hq/esc/oe



*Serious Drought.
Help save water!*

June 24, 2015

06-Mad-41-11.7/13.4

06-OG9004

Project ID 0600000112

ACNHP-P041(128)E

Addendum No. 2

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN MADERA COUNTY NEAR COARSEGOLD FROM 0.3 MILE NORTH OF ROAD 208 TO 2.0 MILES NORTH OF ROAD 208.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Thursday, July 2, 2015.

This addendum is being issued to revise the project plans, the *Notice to Bidders and Special Provisions*, the *Bid book*, and *Information Handout*.

Project plan sheet 45 is replaced and attached for substitution for the like-numbered sheet.

In the Special Provisions, Section 1-1.01, is replaced as attached.

In the Special Provisions, Section 8-1.04C, is replaced as attached.

In the Special Provisions, Section 13-11.01, is replaced as attached.

In the Special Provisions, Section 17-1.02, is added as attached.

The *Information Handout* "Water Source Information" is replaced as attached.

In the *Bid book*, in the "Bid Item List," Items 77, and 78 are added.

In the *Bid book*, in the "Bid Item List," Items 3, and 76 are deleted.

Addendum No. 2
Page 2
June 24, 2015

06-Mad-41-11.7/13.4
06-0G9004
Project ID 0600000112
ACNHP-P041(128)E

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html

Inform subcontractors and suppliers as necessary.

This addendum, EBS addendum file, and attachments are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/06/06-0G9004

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



SHARRI BENDER EHLERT
District Director
District 6 Central Region

Attachments

Add to section 1-1.01:

Bid Items and Applicable Sections

| Item code | Item description | Applicable section |
|-----------|---|--------------------|
| 029111 | CENTERLINE RUMBLE STRIP(RHMA,GROUND-INDENTATION | 39 |
| 029112 | 102" Corrugated Steel Pipe(0.168" Thick) | 66 |

Replace "Reserved" in section 8-1.04C with:

Section 8-1.04B does not apply.

Start job site activities within 55 days after receiving notice that the Contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department.

Do not start job site activities until the Department authorizes or accepts your submittal for:

1. CPM baseline schedule
2. WPCP or SWPPP, whichever applies
3. Notification of DRA or DRB nominee and disclosure statement

You may enter the job site only to measure controlling field dimensions and locate utilities.

Do not start other job site activities until all the submittals from the above list are authorized or accepted and the following information is received by the Engineer:

1. *Notice of Materials To Be Used* form.
2. Written statement from the vendor that the order for the sign panels has been received and accepted by the vendor. The statement must show the dates that the materials will be shipped.

You may start job site activities before the 55th day after Contract approval if you:

1. Obtain specified authorization or acceptance for each submittal before the 55th day
2. Receive authorization to start

Submit a notice 72 hours before starting job site activities. If the project has more than 1 location of work, submit a separate notice for each location.

13-11.01 GENERAL

Section 13-11 includes specifications for monitoring water quality during the following construction activities:

1. Wetland swale and Vernal pools.

The receiving water for this project is ephemeral pools and swales, tributary to Hildreth Creek.

Replace the 1st sentence of the paragraph in section 17-1.02 with:

Water must be nonpotable.

BID ITEM LIST**06-0G9004**

| Item No. | Item Code | Item Description | Unit of Measure | Estimated Quantity | Unit Price | Item Total |
|----------|-----------|---|-----------------|--------------------|------------|------------|
| 1 | 070030 | LEAD COMPLIANCE PLAN | LS | LUMP SUM | LUMP SUM | |
| 2 | 080050 | PROGRESS SCHEDULE (CRITICAL PATH METHOD) | LS | LUMP SUM | LUMP SUM | |
| 3 | BLANK | | | | | |
| 4 | 120090 | CONSTRUCTION AREA SIGNS | LS | LUMP SUM | LUMP SUM | |
| 5 | 120100 | TRAFFIC CONTROL SYSTEM | LS | LUMP SUM | LUMP SUM | |
| 6 | 120159 | TEMPORARY TRAFFIC STRIPE (PAINT) | LF | 50,700 | | |
| 7 | 120165 | CHANNELIZER (SURFACE MOUNTED) | EA | 36 | | |
| 8 | 120300 | TEMPORARY PAVEMENT MARKER | EA | 1,420 | | |
| 9 | 128652 | PORTABLE CHANGEABLE MESSAGE SIGN (LS) | LS | LUMP SUM | LUMP SUM | |
| 10 | 129000 | TEMPORARY RAILING (TYPE K) | LF | 11,100 | | |
| 11 | 129100 | TEMPORARY CRASH CUSHION MODULE | EA | 84 | | |
| 12 | 130100 | JOB SITE MANAGEMENT | LS | LUMP SUM | LUMP SUM | |
| 13 | 130300 | PREPARE STORM WATER POLLUTION PREVENTION PLAN | LS | LUMP SUM | LUMP SUM | |
| 14 | 130330 | STORM WATER ANNUAL REPORT | EA | 2 | 2,000.00 | 4,000.00 |
| 15 | 130505 | MOVE-IN/MOVE-OUT (TEMPORARY EROSION CONTROL) | EA | 6 | | |
| 16 | 130520 | TEMPORARY HYDRAULIC MULCH | SQYD | 19,800 | | |
| 17 | 130640 | TEMPORARY FIBER ROLL | LF | 1,030 | | |
| 18 | 130680 | TEMPORARY SILT FENCE | LF | 7,420 | | |
| 19 | 130710 | TEMPORARY CONSTRUCTION ENTRANCE | EA | 4 | | |
| 20 | 130730 | STREET SWEEPING | LS | LUMP SUM | LUMP SUM | |

BID ITEM LIST
06-0G9004

| Item No. | Item Code | Item Description | Unit of Measure | Estimated Quantity | Unit Price | Item Total |
|----------|-----------|---|-----------------|--------------------|------------|------------|
| 61 | 029112 | 102" CORRUGATED STEEL PIPE (0.168" THICK) | LF | 71 | | |
| 62 | 690110 | 12" CORRUGATED STEEL PIPE DOWNDRAIN | LF | 200 | | |
| 63 | 692005 | 12" ENTRANCE TAPER | EA | 4 | | |
| 64 | 705007 | 12" STEEL FLARED END SECTION | EA | 4 | | |
| 65 | 705015 | 24" STEEL FLARED END SECTION | EA | 11 | | |
| 66 | 705031 | 48" STEEL FLARED END SECTION | EA | 1 | | |
| 67 | 721028 | ROCK SLOPE PROTECTION (NO. 2, METHOD B) (CY) | CY | 250 | | |
| 68 | 729011 | ROCK SLOPE PROTECTION FABRIC (CLASS 8) | SQYD | 1,190 | | |
| 69 | 800007 | FENCE (TYPE BW, 5-STRAND, METAL POST) | LF | 15,900 | | |
| 70 | 820107 | DELINEATOR (CLASS 1) | EA | 9 | | |
| 71 | 840504 | 4" THERMOPLASTIC TRAFFIC STRIPE | LF | 50,200 | | |
| 72 | 840515 | THERMOPLASTIC PAVEMENT MARKING | SQFT | 260 | | |
| 73 | 840525 | 4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12) | LF | 10,800 | | |
| 74 | 850111 | PAVEMENT MARKER (RETROREFLECTIVE) | EA | 950 | | |
| 75 | 860090 | MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION | LS | LUMP SUM | LUMP SUM | |
| 76 | BLANK | | | | | |
| 77 | 090105 | TIME-RELATED OVERHEAD (LS) | LS | LUMP SUM | LUMP SUM | |
| 78 | 999990 | MOBILIZATION | LS | LUMP SUM | LUMP SUM | |

BID ITEM LIST
06-0G9004

TOTAL BID
FOR BID ITEMS: \$ _____

TOTAL BID
FOR TIME: _____ X \$14,000.00 = \$ _____
WORKING DAYS BID COST PER DAY
(Not to exceed 160 Days)

TOTAL BID FOR COMPARISON (COST PLUS TIME): \$ _____