

DEPARTMENT OF TRANSPORTATION
DIVISION OF ENGINEERING SERVICES
OFFICE ENGINEER, MS 43
1727 30TH STREET
P.O. BOX 168041
SACRAMENTO, CA 95816-8041
PHONE (916) 227-6230
FAX (916) 227-6214
TTY (916) 227-8454



Flex your power!
Be energy efficient!

**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

November 2, 2004

06-Fre-180-87.4/88.3
06-303704
ACSTPH-P180(050)E

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in FRESNO COUNTY IN FRESNO FROM 0.5 KM EAST OF MARKS AVENUE TO 0.5 KM WEST OF MARKS AVENUE.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on November 9, 2004.

This addendum is being issued to revise the Project Plans, the Notice to Contractors and Special Provisions, and the Proposal and Contract.

Project Plan Sheets 2, 3, 4, 5, 6, 7, 8, 10, 16, 19, 24 and 26 are revised. Half-sized copies of the revised sheets are attached for substitution for the like-numbered sheets.

Project Plan Sheet 10A is added. Half-sized copy of the added sheet is attached for addition to the project plans.

In the Special Provisions, Section 4, "BEGINNING OF WORK, TIME OF COMPLETION, AND LIQUIDATED DAMAGES," is revised as attached.

In the Special Provisions, Section 5-1.12A, "PROJECT INFORMATION," is added as attached.

Addendum No. 1
Page 2
November 2, 2004

06-Fre-180-87.4/88.3
06-303704
ACSTPH-P180(050)E

In the Proposal and Contract, the Engineer's Estimate Items 8, 15, 16, 17, 29, 32, and 34 are revised. Items 9, 31, and 42 are deleted. Items 43 and 44 are added as attached.

To Proposal and Contract book holders:

Replace pages 3, 4, and 5 of the Engineer's Estimate in the Proposal with the attached revised pages 3, 4, and 5 of the Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by UPS overnight mail to Proposal and Contract book holders to ensure that each receives it. A copy of this addendum and the modified wage rates are available for the contractor's use on the Internet Site:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief
Office of Plans, Specifications & Estimates
Office Engineer

Attachments

SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES

Attention is directed to the provisions in Section 8-1.03, "Beginning of Work," in Section 8-1.06, "Time of Completion," and in Section 8-1.07, "Liquidated Damages," of the Standard Specifications and these special provisions.

The Contractor shall furnish the Engineer with a statement from the vendor that the order for the electrical materials required for this contract has been received and accepted by the vendor; and the statement shall be furnished within 15 calendar days after the contract has been approved by the Attorney General, or the attorney appointed and authorized to represent the Department of Transportation. The statement shall give the date that the electrical materials will be shipped. If the Contractor has the necessary materials on hand, the Contractor will not be required to furnish the vendor's statement.

The Contractor shall begin work within 90 calendar days after the contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department of Transportation.

The work shall be diligently prosecuted to completion before the expiration of **90 WORKING DAYS** beginning on the date that work begins, or beginning on the ninetieth calendar day after approval of the contract, whichever occurs first.

The Contractor shall pay to the State of California the sum of \$ 1,600 per day, for each and every calendar day's delay in finishing the work in excess of **90 WORKING DAYS**.

The 72 hours advance notice before beginning work specified in Section 8-1.03, "Beginning of Work," of the Standard Specifications is changed to 5 days advance notice for this project.

5-1.12A PROJECT INFORMATION

The information in this section has been compiled specifically for this project and is made available for bidders and Contractors. Other information referenced in the Standard Specifications and these special provisions do not appear in this section. The information is subject to the conditions and limitations set forth in Section 2-1.03, "Examination of Plans, Specifications, Contract, and Site of Work," and Section 6-2, "Local Materials," of the Standard Specifications. Bidders and Contractors shall be responsible for knowing the procedures for obtaining information.

Information available for inspection at the District Construction Office is as follows:

A. Cross section.

The District Construction Office in which the work is situated is located at 855 M Street, Suite 200, Fresno, CA 93721. Tel (559)445-6360 or Fax (559) 445-6445.

ENGINEER'S ESTIMATE

06-303704

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	074019	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	LUMP SUM	LUMP SUM	
2	074020	WATER POLLUTION CONTROL	LS	LUMP SUM	LUMP SUM	
3 (S)	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
4 (S)	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
5 (S)	128650	PORTABLE CHANGEABLE MESSAGE SIGN	LS	LUMP SUM	LUMP SUM	
6 (S)	150715	REMOVE THERMOPLASTIC PAVEMENT MARKING	M2	19		
7	150744	REMOVE ROADSIDE SIGN (WOOD POST)	EA	6		
8	150771	REMOVE ASPHALT CONCRETE DIKE	M	73		
9	BLANK					
10	033659	REMOVE STANDPIPE	EA	1		
11	150820	REMOVE INLET	EA	1		
12	150821	REMOVE HEADWALL	EA	1		
13	152255	RESET MAILBOX	EA	4		
14	152386	RELOCATE ROADSIDE SIGN-ONE POST	EA	7		
15	152439	ADJUST FRAME AND GRATE TO GRADE	EA	6		
16 (S)	153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	M2	3760		
17	153216	REMOVE CONCRETE CURB AND SIDEWALK	M3	60		
18	160101	CLEARING AND GRUBBING	LS	LUMP SUM	LUMP SUM	
19	190101	ROADWAY EXCAVATION	M3	2260		
20 (S)	202011	MULCH	M3	4		

ENGINEER'S ESTIMATE

06-303704

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
21 (S)	203003	STRAW (EROSION CONTROL)	TONN	3		
22 (S)	203014	FIBER (EROSION CONTROL)	KG	220		
23 (S)	203024	COMPOST (EROSION CONTROL)	M3	4.2		
24 (S)	203045	PURE LIVE SEED (EROSION CONTROL)	KG	18		
25 (S)	203056	COMMERCIAL FERTILIZER (EROSION CONTROL)	KG	110		
26 (S)	203061	STABILIZING EMULSION (EROSION CONTROL)	KG	97		
27 (S)	204031	TRANSPLANT PALM TREE	EA	5		
28	260201	CLASS 2 AGGREGATE BASE	M3	550		
29	390155	ASPHALT CONCRETE (TYPE A)	TONN	6220		
30	394002	PLACE ASPHALT CONCRETE (MISCELLANEOUS AREA)	M2	1200		
31	BLANK					
32	397001	ASPHALTIC EMULSION (PAINT BINDER)	TONN	32		
33	566011	ROADSIDE SIGN - ONE POST	EA	2		
34	731502	MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION)	M3	70		
35	820107	DELINEATOR (CLASS 1)	EA	10		
36 (S)	840515	THERMOPLASTIC PAVEMENT MARKING	M2	120		
37 (S)	840560	THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	M	1770		
38 (S)	840561	100 MM THERMOPLASTIC TRAFFIC STRIPE	M	810		
39 (S)	840563	200 MM THERMOPLASTIC TRAFFIC STRIPE	M	220		
40 (S)	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	230		

ENGINEER'S ESTIMATE

06-303704

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
41 (S)	860201	SIGNAL AND LIGHTING	LS	LUMP SUM	LUMP SUM	
42	BLANK					
43	394048	PLACE ASPHALT CONCRETE DIKE (TYPE E)	M	170		
44	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

TOTAL BID: _____