

**DEPARTMENT OF TRANSPORTATION**

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30<sup>th</sup> Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

www.dot.ca.gov/hq/esc/oe



*Serious Drought.  
Help save water!*

August 28, 2015

06-Tul-99-35.2/R37.3

06-360234

Project ID 0612000241

ACNH-P099(587)E

Addendum No. 2

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN TULARE COUNTY IN AND NEAR VISALIA FROM 1.2 MILES SOUTH OF AVENUE 280 OVERCROSSING TO 0.9 MILE SOUTH OF WEST VISALIA OVERHEAD.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Wednesday, September 9, 2015.

This addendum is being issued to revise the project plans, the *Notice to Bidders and Special Provisions*, the *Bid book*, *Information Handout*, and the Federal Minimum Wages with Modification Number 9 dated 08/14/15.

Project plan sheets 42 and 82, are replaced and attached for substitution for the like-numbered sheets.

Project plan sheet 44A is added and attached for addition to the project plans.

In the Special Provisions, Section 2-1.06B, "Supplemental Project Information" table, in "Included in the Information Handout section," Item 3 "Geotechnical Design Report, Dated January 26, 2012" is added.

In the Special Provisions, Section 8-1.04C, is added as attached.

In the Special Provisions, Section 10-1.02, the following paragraph is added after the second paragraph.

"If you completely close the ramp to through public traffic utilizing Lane Closure Charts No.E-2 and E-3, construction of the entire ramp roadway except the top lift of hot mix asphalt pavement must be completed within the allotted time specified for the closure hours."

In the Special Provisions, Section 12-4.02A is replaced as attached.

In the Special Provisions, Section 12-4.05B, "Lane Closure Chart No. B-1," is replaced as attached.

Addendum No. 2  
Page 2  
August 28, 2015

06-Tul-99-35.2/R37.3  
06-360234  
Project ID 0612000241  
ACNH-P099(587)E

In the Special Provisions, Section 12-4.05E, "Lane Closure Chart No.E-1," is replaced as attached.

In the Special Provisions, Section 12-4.05E, "Lane Closure Chart No. E-2 and E-3," are added as attached.

The *Information Handout* is replaced as attached.

In the *Bid* book, in the "Bid Item List," Items 64 and 65 are deleted.

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

[http://www.dot.ca.gov/hq/esc/oe/electronic\\_bidding/electronic\\_bidding.html](http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html)

Inform subcontractors and suppliers as necessary.

This addendum, EBS addendum file, attachments and the modified wage rates are available for the Contractors' download on the Web site:

[http://www.dot.ca.gov/hq/esc/oe/project\\_ads\\_addenda/06/06-360234](http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/06/06-360234)

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



SHARRI BENDER EHLERT  
District Director  
District 6 Central Region

Attachments

## 8 PROSECUTION AND PROGRESS

Replace "Reserved" in section 8-1.04C with:

Section 8-1.04B does not apply.

Start job site activities within 55 days after receiving notice that the Contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department.

Do not start job site activities until the Department authorizes or accepts your submittal for:

1. Biological resource information program
2. CPM baseline schedule
3. WPCP or SWPPP, whichever applies

If the submittal for biological resource information program is authorized, you may enter the job site only to measure controlling field dimensions and locate utilities.

Do not start other job site activities until all the submittals from the above list are authorized or accepted and the following information is received by the Engineer:

1. *Notice of Materials To Be Used* form.
2. Written statement from the vendor that the order for the sign panels has been received and accepted by the vendor. The statement must show the dates that the materials will be shipped.
3. Written statement from the vendor that the order for electrical material has been received and accepted by the vendor. The statement must show the dates that the materials will be shipped.

You may start job site activities before the 55th day after Contract approval if you:

1. Obtain specified authorization or acceptance for each submittal before the 55th day
2. Receive authorization to start

Submit a notice 72 hours before starting job site activities. If the project has more than 1 location of work, submit a separate notice for each location.

AA

**Add to section 12-4.02A:**

If work including installing, maintaining, and removing Type K temporary railing is to be performed within 6 feet of the adjacent traffic lane, close the adjacent traffic lane.

Except as listed above, closure of the adjacent traffic lane is not required for installing, maintaining, and removing traffic control devices.

For grinding and grooving operations, saw cutting concrete slabs, and installing loop detectors, closure of the adjacent traffic lane is not required if an impact attenuator vehicle is used as a shadow vehicle.

Designated holidays are shown in the following table:

**Designated Holidays**

Holiday	Date observed
New Year's Day	January 1st
Washington's Birthday	3rd Monday in February
Memorial Day	Last Monday in May
Independence Day	July 4th
Labor Day	1st Monday in September
Veterans Day	November 11th
Thanksgiving Day	4th Thursday in November
Christmas Day	December 25th

If a designated holiday falls on a Saturday or Sunday, the following Monday is a designated holiday. If November 11th falls on a Saturday, the preceding Friday is a designated holiday.

Special days are: Martin Luther King Day, Cesar Chavez Day, and Easter Sunday including the Friday prior.

The maximum length of the work area inside a lane closure other than one-way reversing traffic-control lane closure is 0.5 miles. Work area is as shown.

Not more than 1 stationary lane closure will be allowed at one time.

Personal vehicles of your employees must not be parked on the traveled way or shoulders, including sections closed to traffic.

If work vehicles or equipment are parked within 6 feet of a traffic lane, close the shoulder area as shown.

If a connector closure is required within the limits of a freeway lane closure, complete the work on the connector first. Then, complete the work on the freeway traveled way necessary to ensure safe passage of traffic between the connector and open freeway lanes. Complete the remaining work only after reopening the connector.

When the ramp is closed, place a PCMS for the entire closure duration at least 1,500 feet in advance of the off-ramp upstream from the ramp being closed with the message: "<Name of ramp> / Exit / Closed." Place a PCMS at a location on the ramp 7 continuous days before the date of planned closure with the following message:

Message type	Message
Weekend	Ramp / Will Be / Closed – Next / Weekend
Weekday	Ramp / Will Be / Closed – This / Weekend

Note:

"/" separates each line of text on the PCMS display.

"-" denotes where the PCMS display flashes the next line of text.

From 3 hours before to 2 hours after events at the venues or special events shown in the table titled "Special Events and Venues," work listed below that is on the highway and/or encroaches onto the freeway will not be allowed:

1. Route 99 PM 35.2 to PM R37.3
2. Northbound on-ramp and off-ramp to Avenue 280
3. Southbound on-ramp and off-ramp to Avenue 280

Special events and venues are as follows:

**Special Events and Venues**

Venue/Special event	Affected routes	Route limits
International Agri-Center/ World Ag Expo	99	Route 99 in Madera, Fresno, Tulare, and Kern Counties

Replace "Reserved" in section 12-4.05B with:

Chart no. B-1 Freeway Lane Requirements																										
County: Tul							Route/Direction: 99/NB&SB							PM: 35.2/R37.3												
Closure limits: From Avenue 272 to 0.9 mile south of west Visalia Overhead (Br. No. 46-226)																										
Hour	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	
Mon-Thu	1	1	1	1	1	1														1	1	1	1	1		
Fri	1	1	1	1	1	1																				
Sat																										
Sun																								1	1	

Legend:

1 Provide at least 1 through freeway lane open in direction of travel

Work allowed within the highway where shoulder or lane closure is not required

REMARKS:

1. The full width of the traveled way must be open to traffic when construction activities are not actively in progress.

Replace "Reserved" in section 12-4.05E with:

<b>Chart no. E-1 Ramp Lane Requirements</b>																									
County: Tul							Route/Direction: 99/NB&SB							PM: 36.2, 36.3, 36.4, 36.6											
Closure limits: Northbound off-ramp to Avenue 280 (PM 36.2) Southbound on-ramp from Avenue 280 (PM 36.3) Northbound on-ramp from Avenue 280 (PM 36.4) Southbound off-ramp to Avenue 280 (PM 36.6)																									
Hour	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mon-Thu	C	C	C	C	C	C														C	C	C	C	C	
Fri	C	C	C	C	C	C																			
Sat																									
Sun																								C	C
<b>Legend:</b> <input type="checkbox"/> C Ramp may be closed completely <input type="checkbox"/> Work allowed within the highway where shoulder or lane closure is not required																									
<b>REMARKS:</b> 1. Complete interchange closure shall not be permitted. 2. The full width of the traveled way must be open to traffic when construction activities are not actively in progress.																									

**Chart no. E-2  
Complete Ramp Closure Hours Requirements**

County: Tul		Route/Direction: 99/NB&SB										PM: 36.2, 36.4													
Closure limits: Northbound off-ramp to Avenue 280 (PM 36.2) Northbound on-ramp from Avenue 280 (PM 36.4)																									
Hour	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Tues-Thu																									
Fri																							C	C	C
Sat	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Sun	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Mon	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C				

**Legend:**  
 C Ramp may be closed completely  
 Work allowed within the highway where shoulder or lane closure is not required

**REMARKS:**  
 1. Complete interchange closure shall not be permitted.  
 2. The full width of the traveled way must be open to traffic when construction activities are not actively in progress.  
 3. E2 and E3 shall not occur concurrently.  
 4. This lane requirement chart valid for a one-time 72 hour maximum closure of both ramps simultaneously.

Chart no. E-3 Complete Ramp Closure Hours Requirements																									
County: Tul							Route/Direction: 99/NB&SB							PM: 36.2											
Closure limits: Southbound off-ramp to Avenue 280 (PM 36.2)																									
Hour	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mon-Thu																									
Fri																							C	C	C
Sat	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Sun	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C				

Legend:

C Ramp may be closed completely

Work allowed within the highway where shoulder or lane closure is not required

REMARKS:

1. Complete interchange closure shall not be permitted.
2. The full width of the traveled way must be open to traffic when construction activities are not actively in progress.
3. E2 and E3 shall not occur concurrently.
4. This lane requirement chart valid for a one-time 48 hour maximum closure.

CONTRACT NO. 06-360234  
 ADDED PER ADDENDUM NO. 2 DATED AUGUST 28, 2015

**BID ITEM LIST****06-360234**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
61	394090	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREA)	SQYD	15		
62	397005	TACK COAT	TON	160		
63	401050	JOINTED PLAIN CONCRETE PAVEMENT	CY	8,900		
64	BLANK					
65	BLANK					
66	498052	60" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	LF	160		
67	510502	MINOR CONCRETE (MINOR STRUCTURE)	CY	82		
68	520101	BAR REINFORCING STEEL	LB	240		
69	560218	FURNISH SIGN STRUCTURE (TRUSS)	LB	109,000		
70	560219	INSTALL SIGN STRUCTURE (TRUSS)	LB	109,000		
71	560251	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-FRAMED)	SQFT	22		
72	566011	ROADSIDE SIGN - ONE POST	EA	2		
73	566012	ROADSIDE SIGN - TWO POST	EA	7		
74	568001	INSTALL SIGN (STRAP AND SADDLE BRACKET METHOD)	EA	2		
75	029336	FURNISH LAMINATED SIGN PANEL (1" TYPE A)FOR RETROREFLECTIVE SHEETING (TYPE XI)	SQFT	840		
76	029337	FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-UNFRAMED) FOR RETROREFLECTIVE SHEETING (TYPE XI)	SQFT	130		
77	029338	FURNISH SINGLE SHEET ALUMINUM SIGN (0.063"-FRAMED) FOR RETROREFLECTIVE SHEETING (TYPE XI)	SQFT	60		
78	029339	RETROREFLECTIVE SHEETING (TYPE XI)	SQFT	1,030		
79	650014	18" REINFORCED CONCRETE PIPE	LF	1,440		
80	650018	24" REINFORCED CONCRETE PIPE	LF	2,120		