


**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that Caltrans does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders and non-bidder packages, write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone and fax number, P.O. Box and street address so that you can receive addenda.

Note: Addenda information is NOT included with the electronic documents available via electronic file transfer. Only bidder or non-bidder package holders listed with the Caltrans Plans and Bid Documents section as described above will receive addenda information.



STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS
AND
SPECIAL PROVISIONS
FOR BUILDING CONSTRUCTION IN

MADERA COUNTY IN MADERA AT THE MADERA MAINTENANCE STATION AT 125 ALMOND AVENUE

DISTRICT 06, ROUTE 5714

For Use in Connection with Standard Specifications Dated JULY 1999, Standard Plans Dated JULY 1999, and Labor Surcharge and Equipment Rental Rates.

CONTRACT NO. 06-378604
06-Mad-5714-13.7

Bids Open: January 10, 2001
Dated: December 4, 2000

OSD

IMPORTANT SPECIAL NOTICES

- **SURETY 2000**

Caltrans is conducting a pilot program in cooperation with Surety 2000, to test electronic bond verification systems. The purpose of the pilot program is to test the use of Surety 2000 for verifying a bidder's bond electronically.

Surety 2000 is an Internet-based surety verification and security system, developed in conjunction with the surety industry. Surety agents may contact Surety 2000 at 1-800-660-3263.

Bidders are encouraged to participate in the pilot program. To participate, the bidder is asked to provide the "Authorization Code" provided by Surety 2000, on a separate sheet, together with the standard bidder's bond required by the specifications. The bidder's surety agent may obtain the "Authorization Code" from Surety 2000.

The Department will use the "Authorization Code" to access the Surety 2000 database, and independently verify the actual bidder's bond and document the functioning of the Surety 2000 system.

"Authorization Codes" will be used only to verify bidder's bonds, and only as part of the pilot program. The use of "Authorization Codes" will not be accepted in lieu of the bidder's bond or other bidder's security required in the specifications during the pilot study.

The function of the Surety 2000 system is to provide an easier way for Contractors to protect their bid security, and to discourage fraud. This system is available to all California admitted sureties and surety agents.

The results of the pilot study will be tabulated, and at some time in the future, the Department may consider accepting electronic bidder's bond verification in lieu of the bidder's bond specified.

TABLE OF CONTENTS

NOTICE TO CONTRACTORS.....	1
COPY OF ENGINEER'S ESTIMATE	3
SPECIAL PROVISIONS	4
SECTION 1. SPECIFICATIONS AND PLANS.....	4
SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS.....	4
2-1.01 GENERAL.....	4
2-1.02 DISABLED VETERAN BUSINESS ENTERPRISE (DVBE).....	4
2-1.03 DVBE GOAL FOR THIS PROJECT	5
2-1.04 SUBMISSION OF DVBE INFORMATION	6
2-1.05 SMALL BUSINESS PREFERENCE.....	6
2-1.06 CALIFORNIA COMPANY PREFERENCE	7
SECTION 3. AWARD AND EXECUTION OF CONTRACT.....	7
SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES	8
SECTION 5. GENERAL	8
SECTION 5-1. MISCELLANEOUS	8
5-1.01 PLANS AND WORKING DRAWINGS	8
5-1.011 EXAMINATION OF PLANS, SPECIFICATIONS, CONTRACT, AND SITE OF WORK	8
5-1.012 DIFFERING SITE CONDITIONS.....	9
5-1.015 LABORATORY	9
5-1.017 CONTRACT BONDS	9
5-1.018 EXCAVATION SAFETY PLANS	9
5-1.02 LABOR NONDISCRIMINATION	10
5-1.03 INTEREST ON PAYMENTS	10
5-1.031 FINAL PAYMENT AND CLAIMS.....	10
5-1.04 PUBLIC SAFETY	11
5-1.05 SURFACE MINING AND RECLAMATION ACT.....	12
5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES.....	12
5-1.07 YEAR 2000 COMPLIANCE.....	12
5-1.08 SUBCONTRACTOR AND DVBE RECORDS.....	12
5-1.086 PERFORMANCE OF DVBE SUBCONTRACTORS AND SUPPLIERS	12
5-1.09 SUBCONTRACTING.....	13
5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS	13
5-1.11 AREAS FOR CONTRACTOR'S USE	13
5-1.12 PAYMENTS	13
5-1.13 PRESERVATION OF PROPERTY	14
5-1.14 COOPERATION	14
5-1.15 OBSTRUCTIONS	14
SECTION 6. (BLANK).....	15
SECTION 7. (BLANK).....	15
SECTION 8. MATERIALS	15
SECTION 8-1. MISCELLANEOUS	15
8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS	15
8-1.02 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS	21
PAVEMENT MARKERS, PERMANENT TYPE	22
PAVEMENT MARKERS, TEMPORARY TYPE.....	22
STRIPING AND PAVEMENT MARKING MATERIAL	23
CLASS 1 DELINEATORS.....	23
CHANNELIZERS	24
CONICAL DELINEATORS, 1070 mm	24
OBJECT MARKERS.....	24
TEMPORARY RAILING (TYPE K) REFLECTORS AND CONCRETE BARRIER MARKERS	24
THREE BEAM BARRIER MARKERS.....	24
CONCRETE BARRIER DELINEATORS, 400 mm	25
CONCRETE BARRIER-MOUNTED MINI-DRUM (260 mm x 360 mm x 570 mm).....	25

SOUND WALL DELINEATOR.....	25
GUARD RAILING DELINEATOR.....	25
RETROREFLECTIVE SHEETING.....	25
SPECIALTY SIGN (All Plastic)	26
SIGN SUBSTRATE FOR CONSTRUCTION AREA SIGNS	26
SECTION 8-2. (BLANK)	26
SECTION 9. (BLANK).....	26
SECTION 10. CONSTRUCTION DETAILS.....	26
SECTION 10-1. GENERAL	26
10-1.01 WATER POLLUTION CONTROL.....	26
WATER POLLUTION CONTROL PROGRAM PREPARATION, APPROVAL AND UPDATES	27
WPCP IMPLEMENTATION	28
MAINTENANCE	29
PAYMENT	29
10-1.02 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES	29
10-1.03 CONSTRUCTION AREA SIGNS	30
10-1.04 MAINTAINING TRAFFIC.....	30
10-1.05 TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE.....	30
STATIONARY LANE CLOSURE	31
PAYMENT	31
10-1.06 TEMPORARY CRASH CUSHION MODULE.....	31
GENERAL	31
MATERIALS.....	31
INSTALLATION	32
MEASUREMENT AND PAYMENT	32
10-1.07 AGGREGATE BASE.....	32
10-1.08 ASPHALT CONCRETE	32
10-1.09 PAINT TRAFFIC STRIPE.....	33
10-1.10 PAVEMENT MARKERS	33
SECTION 10-2. (BLANK)	33
SECTION 10-3. (BLANK)	33
SECTION 10-4. CITY OF MADERA SEWER	33
10-4.01 SEWER PLASTIC PIPE (300 MM PIPE)	33
10-4.02 SEWER MANHOLE AND COVER.....	34
SECTION 11. (BLANK).....	34
SECTION 12. BUILDING WORK.....	34
SECTION 12-1. GENERAL REQUIREMENTS	34
12-1.01 SCOPE.....	34
12-1.02 ABBREVIATIONS	35
12-1.03 GUARANTEE.....	35
12-1.04 SUBMITTALS	36
12-1.05 PROGRESS SCHEDULE	36
12-1.06 SCHEDULE OF VALUES.....	36
12-1.07 INSPECTION	36
12-1.08 UTILITY CONNECTION.....	37
12-1.09 TEMPORARY UTILITIES.....	37
12-1.10 SANITARY FACILITIES	37
12-1.11 MEASUREMENT AND PAYMENT	37
12-1.12 FIELD ENGINEERING.....	37
12-1.13 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS	38
SECTION 12-2. SITEWORK	48
12-2.01 REMOVING PORTIONS OF EXISTING FACILITIES	48
12-2.02 RELOCATING MATERIALS AND EQUIPMENT	49
12-2.03 ABANDON PORTIONS OF WASTE DISPOSAL SYSTEM	50
12-2.04 EARTHWORK FOR BUILDING WORK.....	50
12-2.05 AGGREGATE BASE.....	53
12-2.06 FREE DRAINING GRANULAR MATERIAL	54
12-2.07 ASPHALT CONCRETE	54
12-2.08 CORE CONCRETE.....	56

12-2.09 LIFT STATION	56
12-2.10 WASH WATER SYSTEM.....	58
12-2.11 GUARD POSTS	62
SECTION 12-3. CONCRETE AND REINFORCEMENT	63
12-3.01 CAST-IN-PLACE CONCRETE.....	63
SECTION 12-4. MASONRY (BLANK)	67
SECTION 12-5. METALS.....	67
12-5.01 BUILDING MISCELLANEOUS METAL.....	67
SECTION 12-6. (BLANK)	69
SECTION 12-7 THERMAL AND MOISTURE PROTECTION	69
12-7.01 JOINT SEALANT	69
SECTION 12-8. THROUGH AND 12-9. BLANK	70
SECTION 12-10. SPECIALTIES	70
12-10.01 METAL SIGNS	70
SECTION 12-11 EQUIPMENT.....	70
12-11.01 OIL/WATER SEPARATOR SYSTEM	70
SECTION 12-12. THROUGH 12-15. BLANK	72
SECTION 12-16. ELECTRICAL	72
12-16.01 ELECTRICAL WORK.....	72
12-16.02 BASIC MATERIALS AND METHODS.....	73
12-16.03 ELECTRICAL EQUIPMENT.....	76
12-16.04 VALVE CONTROL PANEL	77

STANDARD PLANS LIST

The Standard Plan sheets applicable to this contract include, but are not limited to those indicated below. The Revised Standard Plans (RSP) and New Standard Plans (NSP) which apply to this contract are included as individual sheets of the project plans.

A10A	Abbreviations
A10B	Symbols
T1A	Temporary Crash Cushion, Sand Filled (Unidirectional)
T1B	Temporary Crash Cushion, Sand Filled (Bidirectional)
T11	Traffic Control System for Lane Closure On Multilane Conventional Highways
T13	Traffic Control System for Lane Closure On Two Lane Conventional Highways
T17	Traffic Control System for Moving Lane Closure On Two Lane Highways
RS1	Roadside Signs, Typical Installation Details No. 1
RS2	Roadside Signs - Wood Post, Typical Installation Details No. 2

State Project with DVBE Goals (06-14-00)

DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS

CONTRACT NO. 06-378604

06-Mad-5714-13.7

Sealed proposals for the work shown on the plans entitled:

**STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROJECT PLANS FOR BUILDING
CONSTRUCTION IN MADERA COUNTY IN MADERA AT THE MADERA MAINTENANCE STATION AT 125
ALMOND AVENUE**

will be received at the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, CA 95814, until 2 o'clock p.m. on January 10, 2001, at which time they will be publicly opened and read in Room 0100 at the same address.

Proposal forms for this work are included in a separate book entitled:

**STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROPOSAL AND CONTRACT FOR
BUILDING CONSTRUCTION IN MADERA COUNTY IN MADERA AT THE MADERA MAINTENANCE
STATION AT 125 ALMOND AVENUE**

General work description: Install washrack and sewer piping.

This project has a goal of 3 percent disabled veteran business enterprise (DVBE) participation.

No prebid meeting is scheduled for this project.

Bids are required for the entire work described herein.

At the time this contract is awarded, the Contractor shall possess either a Class A license or a combination of Class C licenses which constitutes a majority of the work.

The Contractor must also be properly licensed at the time the bid is submitted, except that on a joint venture bid a joint venture license may be obtained by a combination of licenses after bid opening but before award in conformance with Business and Professions Code, Section 7029.1.

This contract is subject to state contract nondiscrimination and compliance requirements pursuant to Government Code, Section 12990.

Preference will be granted to bidders properly certified as a "Small Business" as determined by the Department of General Services, Office of Small Business Certification and Resources at the time of bid opening in conformance with the provisions in Section 2-1.05, "Small Business Preference," of the special provisions, and Section 1896 et seq, Title 2, California Code of Regulations. A form for requesting a "Small Business" preference is included with the bid documents. Applications for status as a "Small Business" must be submitted to the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814, Telephone No. (916) 322-5060.

A reciprocal preference will be granted to "California company" bidders in conformance with Section 6107 of the Public Contract Code. (See Sections 2 and 3 of the special provisions.) A form for indicating whether bidders are or are not a "California company" is included in the bid documents and is to be filled in and signed by all bidders.

Project plans, special provisions, and proposal forms for bidding this project can only be obtained at the Department of Transportation, Plans and Bid Documents, Room 0200, MS #26, Transportation Building, 1120 N Street, Sacramento, California 95814, FAX No. (916) 654-7028, Telephone No. (916) 654-4490. Use FAX orders to expedite orders for project plans, special provisions and proposal forms. FAX orders must include credit card charge number, card expiration date and authorizing signature. Project plans, special provisions, and proposal forms may be seen at the above Department of

Transportation office and at the offices of the District Directors of Transportation at Irvine, Oakland, and the district in which the work is situated. Standard Specifications and Standard Plans are available through the State of California, Department of Transportation, Publications Unit, 1900 Royal Oaks Drive, Sacramento, CA 95815, Telephone No. (916) 445-3520.

Cross sections for this project are not available.

The successful bidder shall furnish a payment bond and a performance bond.

Pursuant to Section 1773 of the Labor Code, the general prevailing wage rates in the county, or counties, in which the work is to be done have been determined by the Director of the California Department of Industrial Relations. These wages are set forth in the General Prevailing Wage Rates for this project, available at the Labor Compliance Office at the offices of the District Director of Transportation for the district in which the work is situated, and available from the California Department of Industrial Relations' Internet Web Site at: <http://www.dir.ca.gov>. Future effective general prevailing wage rates which have been predetermined and are on file with the Department of Industrial Relations are referenced but not printed in the general prevailing wage rates.

DEPARTMENT OF TRANSPORTATION

Deputy Director Transportation Engineering

Dated December 4, 2000

MAG/TLV

COPY OF ENGINEER'S ESTIMATE
(NOT TO BE USED FOR BIDDING PURPOSES)

06-378604

Item	Item Code	Item	Unit of Measure	Estimated Quantity
1	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM
2	260201	CLASS 2 AGGREGATE BASE	M3	40
3	390103	ASPHALT CONCRETE (TYPE B)	TONN	60
4	020196	300 MM PVC SEWER PIPE	M	250
5	719362	1200 MM PRECAST CONCRETE PIPE SEWER MANHOLE	EA	2
6	994650	BUILDING WORK	LS	LUMP SUM

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISIONS

Annexed to Contract No. 06-378604

SECTION 1. SPECIFICATIONS AND PLANS

The work embraced herein shall conform to the provisions in the Standard Specifications dated July 1999, and the Standard Plans dated July 1999, of the Department of Transportation insofar as the same may apply, and these special provisions.

Amendments to the Standard Specifications set forth in these special provisions shall be considered as part of the Standard Specifications for the purposes set forth in Section 5-1.04, "Coordination and Interpretation of Plans, Standard Specifications and Special Provisions," of the Standard Specifications. Whenever either the term "Standard Specifications is amended" or the term "Standard Specifications are amended" is used in the special provisions, the indented text or table following the term shall be considered an amendment to the Standard Specifications. In case of conflict between such amendments and the Standard Specifications, the amendments shall take precedence over and be used in lieu of the conflicting portions.

In case of conflict between the Standard Specifications and these special provisions, the special provisions shall take precedence over and shall be used in lieu of the conflicting portions.

SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS

2-1.01 GENERAL

The bidder's attention is directed to the provisions in Section 2, "Proposal Requirements and Conditions," of the Standard Specifications and these special provisions for the requirements and conditions which the bidder must observe in the preparation of the proposal form and the submission of the bid.

In addition to the subcontractors required to be listed in conformance with Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications, each proposal shall have listed therein the name and address of each DVBE subcontractor to be used for credit in meeting the goal, and to whom the bidder proposes to directly subcontract portions of the work. The list of subcontractors shall also set forth the portion of work that will be performed by each subcontractor listed. A sheet for listing the subcontractors is included in the Proposal.

The Bidder's Bond form mentioned in the last paragraph in Section 2-1.07, "Proposal Guaranty," of the Standard Specifications will be found following the signature page of the Proposal.

In conformance with Public Contract Code Section 7106, a Noncollusion Affidavit is included in the Proposal. Signing the Proposal shall also constitute signature of the Noncollusion Affidavit.

Submit request for substitution of an "or equal" item, and the data substantiating the request to the Department of Transportation, Central Region Construction, P.O. Box 12616, Fresno, CA 93778, so that the request is received by the Department by close of business on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening.

2-1.02 DISABLED VETERAN BUSINESS ENTERPRISE (DVBE)

Section 10115 of the Public Contract Code requires the Department to implement provisions to establish a goal for Disabled Veterans Business Enterprise (DVBE) in contracts.

It is the policy of the Department that Disabled Veteran Business Enterprise (DVBE) shall have the maximum opportunity to participate in the performance of contracts financed solely with state funds. The Contractor shall ensure that DVBEs have the maximum opportunity to participate in the performance of this contract and shall take all necessary and reasonable steps for this assurance. The Contractor shall not discriminate on the basis of race, color, national origin, or sex in the award and performance of subcontracts. Failure to carry out the requirements of this paragraph shall constitute a breach of contract and may result in termination of this contract or other remedy the Department may deem appropriate.

Bidder's attention is directed to the following:

- A. "Disabled Veteran Business Enterprise" (DVBE) means a business concern certified as a DVBE by the Office of Small Business Certification and Resources, Department of General Services.
- B. A DVBE may participate as a prime contractor, subcontractor, joint venture partner with a prime or subcontractor, or vendor of material or supplies.
- C. Credit for DVBE prime contractors will be 100 percent.
- D. A DVBE joint venture partner must be responsible for specific contract items of work, or portions thereof. Responsibility means actually performing, managing and supervising the work with its own forces. The DVBE joint venture partner must share in the ownership, control, management responsibilities, risks and profits of the joint venture. The DVBE joint venturer must submit the joint venture agreement with the Caltrans Bidder DVBE Information form required in Section 2-1.04, "Submission of DVBE Information," elsewhere in these special provisions.
- E. A DVBE must perform a commercially useful function, i.e., must be responsible for the execution of a distinct element of the work and must carry out its responsibility by actually performing, managing and supervising the work.
- F. Credit for DVBE vendors of materials or supplies is limited to 60 percent of the amount to be paid to the vendor for the material unless the vendor manufactures or substantially alters the goods.
- G. Credit for trucking by DVBEs will be as follows:
 - 1. One hundred percent of the amount to be paid when a DVBE trucker will perform the trucking with his/her own trucks, tractors and employees.
 - 2. Twenty percent of the amount to be paid to DVBE trucking brokers who do not have a "certified roster."
 - 3. One hundred percent of the amount to be paid to DVBE trucking brokers who have signed agreements that all trucking will be performed by DVBE truckers if credit is toward the DVBE goal, a "certified roster" showing that all trucks are owned by DVBEs, and a signed statement on the "certified roster" that indicates that 100 percent of revenue paid by the broker will be paid to the DVBEs listed on the "certified roster."
 - 4. Twenty percent of the amount to be paid to trucking brokers who are not a DVBE but who have signed agreements with DVBE truckers assuring that at least 20 percent of the trucking will be performed by DVBE truckers if credit is toward the DVBE goal, a "certified roster" showing that at least 20 percent of the number of trucks are owned by DVBE truckers, and a signed statement on the "certified roster" that indicates that at least 20 percent of the revenue paid by the broker will be paid to the DVBEs listed on the "certified roster."

The "certified roster" referred to herein shall conform to the requirements in Section 2-1.04, "Submission Of DVBE Information," elsewhere in these special provisions.

- H. DVBEs and DVBE joint venture partners must be certified DVBEs as determined by the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814, on the date bids for the project are opened before credit may be allowed toward the DVBE goal. It is the Contractor's responsibility to verify that DVBEs are certified.
- I. Noncompliance by the Contractor with these requirements constitutes a breach of this contract and may result in termination of the contract or other appropriate remedy for a breach of this contract.

2-1.03 DVBE GOAL FOR THIS PROJECT

The Department has established the following goal for Disabled Veteran Business Enterprise (DVBE) participation for this project:

Disabled Veteran Business Enterprise (DVBE): 3 percent.

It is the bidder's responsibility to make a sufficient portion of the work available to subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DVBE subcontractors and suppliers, so as to assure meeting the goal for DVBE participation.

The Office of Small Business Certification and Resources, Department of General Services, may be contacted at (916) 322-5060 or visit their internet web site at <http://www.osmb.dgs.ca.gov/> for program information and certification status. The Department's Business Enterprise Program may also be contacted at (916) 227-9599 or the internet web site at <http://www.dot.ca.gov/hq/bep/>.

2-1.04 SUBMISSION OF DVBE INFORMATION

The required DVBE information shall be submitted on the "CALTRANS BIDDER - DVBE INFORMATION" form included in the Proposal. If this information is not submitted with the bid, the DVBE information forms shall be removed from the documents prior to submitting the bid.

It is the bidder's responsibility to make enough work available to DVBEs and to select those portions of the work or material needs consistent with the available DVBEs to meet the goal for DVBE participation or to provide information to establish that, prior to bidding, the bidder made adequate good faith efforts to do so.

If the DVBE information is not submitted with the bid, the apparent successful bidder (low bidder), the second low bidder and the third low bidder shall submit the DVBE information to the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, California 95814 so the information is received by the Department no later than 4:00 p.m. on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening. DVBE information sent by U.S. Postal Service certified mail with return receipt and certificate of mailing and mailed on or before the third day, not including Saturdays, Sundays and legal holidays, following bid opening will be accepted even if it is received after the fourth day following bid opening. Failure to submit the required DVBE information by the time specified will be grounds for finding the bid or proposal nonresponsive. Other bidders need not submit DVBE information unless requested to do so by the Department.

The bidder's DVBE information shall establish that good faith efforts to meet the DVBE goal have been made. To establish good faith efforts, the bidder shall demonstrate that the goal will be met or that, prior to bidding, adequate good faith efforts to meet the goal were made.

Bidders are cautioned that even though their submittal indicates they will meet the stated DVBE goal, their submittal should also include their adequate good faith efforts information along with their DVBE goal information to protect their eligibility for award of the contract in the event the Department, in its review, finds that the goal has not been met.

The bidder's DVBE information shall include the names of DVBE firms that will participate, with a complete description of work or supplies to be provided by each, the dollar value of each DVBE transaction, and a written confirmation from the DVBE that it is participating in the contract. A copy of the DVBE's quote will serve as written confirmation that the DVBE is participating in the contract. When 100 percent of a contract item of work is not to be performed or furnished by a DVBE, a description of the exact portion of that work to be performed or furnished by that DVBE shall be included in the DVBE information, including the planned location of that work. The work that a DVBE prime contractor has committed to performing with its own forces as well as the work that it has committed to be performed by DVBE subcontractors, suppliers and trucking companies will count toward the goal.

If credit for trucking by a DVBE trucking broker is shown on the bidder's information as 100 percent of the revenue to be paid by the broker is to be paid to DVBE truckers, a "certified roster" of the broker's trucks to be used must be included. The "certified roster" must indicate that all the trucks are owned by certified DVBEs and must show the DVBE truck numbers, owner's name, Public Utilities Commission Cal-T numbers, and the DVBE certification numbers. The roster must indicate that all revenue paid by the broker will be paid to DVBEs listed on the "certified roster".

If credit for trucking by a trucking broker who is not a DVBE is shown in the bidder's information, a "certified roster" of the broker's trucks to be used must be included. The "certified roster" must indicate that at least 20 percent of the broker's trucks are owned by certified DVBEs and must show the DVBE truck numbers, owner's name, Public Utilities Commission Cal-T numbers, and the DVBE certification number. The roster must indicate that at least 20 percent of the revenue paid by the broker will be paid to DVBEs listed on the "certified roster".

A bidder shall be deemed to have made good faith efforts upon submittal, within time limits specified by the Department, of documentary evidence that all of the following actions were taken:

- A. Contact was made with the Office of Small Business Certification and Resources (OSBCR), Department of General Services or their web site at <http://www.osmb.dgs.ca.gov/> to identify Disabled Veteran Business Enterprises.
- B. Advertising was published in trade media and media focusing on Disabled Veteran Business Enterprises, unless time limits imposed by the Department do not permit that advertising.
- C. Invitations to bid were submitted to potential Disabled Veteran Business Enterprise contractors.
- D. Available Disabled Veteran Business Enterprises were considered.

2-1.05 SMALL BUSINESS PREFERENCE

Attention is directed to "Award and Execution of Contract" of these special provisions.

Attention is also directed to the Small Business Procurement and Contract Act, Government Code Section 14835, et seq and Title 2, California Code of Regulations, Section 1896, et seq.

Bidders who wish to be classified as a Small Business under the provisions of those laws and regulations, shall be certified as Small Business by the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814.

To request Small Business Preference, bidders shall fill out and sign the Request for Small Business Preference form in the Proposal and shall attach a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form. The bidder's signature on the Request for Small Business Preference certifies, under penalty of perjury, that the bidder is certified as Small Business at the time of bid opening and further certifies, under penalty of perjury, that under the following conditions, at least 50 percent of the subcontractors to be utilized on the project are either certified Small Business or have applied for Small Business certification by bid opening date and are subsequently granted Small Business certification.

The conditions requiring the aforementioned 50 percent level of subcontracting by Small Business subcontractors apply if:

- A. The lowest responsible bid for the project exceeds \$100,000; and
- B. The project work to be performed requires a Class A or a Class B contractor's license; and
- C. Two or more subcontractors will be used.

If the above conditions apply and Small Business Preference is granted in the award of the contract, the 50 percent Small Business subcontractor utilization level shall be maintained throughout the life of the contract.

2-1.06 CALIFORNIA COMPANY PREFERENCE

Attention is directed to "Award and Execution of Contract" of these special provisions.

In conformance with the requirements of Section 6107 of the Public Contract Code, a "California company" will be granted a reciprocal preference for bid comparison purposes as against a nonresident contractor from any state that gives or requires a preference to be given contractors from that state on its public entity construction contracts.

A "California company" means a sole proprietorship, partnership, joint venture, corporation, or other business entity that was a licensed California contractor on the date when bids for the public contract were opened and meets one of the following:

- A. Has its principal place of business in California.
- B. Has its principal place of business in a state in which there is no local contractor preference on construction contracts.
- C. Has its principal place of business in a state in which there is a local contractor construction preference and the contractor has paid not less than \$5000 in sales or use taxes to California for construction related activity for each of the five years immediately preceding the submission of the bid.

To carry out the "California company" reciprocal preference requirements of Section 6107 of the Public Contract Code, all bidders shall fill out and sign the California Company Preference form in the Proposal. The bidder's signature on the California Company Preference form certifies, under penalty of perjury, that the bidder is or is not a "California company" and if not, the amount of the preference applied by the state of the nonresident Contractor.

A nonresident Contractor shall disclose any and all bid preferences provided to the nonresident Contractor by the state or country in which the nonresident Contractor has its principal place of business.

Proposals without the California Company Preference form filled out and signed may be rejected.

SECTION 3. AWARD AND EXECUTION OF CONTRACT

The bidder's attention is directed to the provisions in Section 3, "Award and Execution of Contract," of the Standard Specifications and these special provisions for the requirements and conditions concerning award and execution of contract.

The award of the contract, if it be awarded, will be to the lowest responsible bidder whose proposal complies with all the requirements prescribed and who has met the goal for DVBE participation or has demonstrated, to the satisfaction of the Department, adequate good faith efforts to do so. Meeting the goal for DVBE participation or demonstrating, to the satisfaction of the Department, adequate good faith efforts to do so is a condition for being eligible for award of contract.

A "Payee Data Record" form will be included in the contract documents to be executed by the successful bidder. The purpose of the form is to facilitate the collection of taxpayer identification data. The form shall be completed and returned to the Department by the successful bidder with the executed contract and contract bonds. For the purposes of the form, payee shall be deemed to mean the successful bidder. The form is not to be completed for subcontractors or suppliers. Failure to complete and return the "Payee Data Record" form to the Department as provided herein will result in the retention of 20 percent of payments due the contractor and penalties of up to \$20,000. This retention of payments for failure to complete the "Payee Data Record" form is in addition to any other retention of payments due the Contractor.

Attention is also directed to "Small Business Preference" of these special provisions. Any bidder who is certified as a Small Business by the Department of General Services, Office of Small Business Certification and Resources will be allowed a preference in the award of this contract, if it be awarded, under the following conditions:

- A. The apparent low bidder is not certified as a Small Business, or has not filled out and signed the Request for Small Business Preference included with the bid documents and attached a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form; and
- B. The bidder filled out and signed the Request for Small Business Preference form included with the bid documents and attached a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form.

The small business preference will be a reduction in the bid submitted by the small business contractor, for bid comparison purposes, by an amount equal to 5 percent of the amount bid by the apparent low bidder, the amount not to exceed \$50,000. If this reduction results in the small business contractor becoming the low bidder, then the contract will be awarded to the small business contractor on the basis of the actual bid of the small business contractor notwithstanding the reduced bid price used for bid comparison purposes.

Attention is also directed to "California Company Preference" of these special provisions.

The amount of the California company reciprocal preference shall be equal to the amount of the preference applied by the state of the nonresident contractor with the lowest responsive bid, except where the "California company" is eligible for a California Small Business Preference, in which case the preference applied shall be the greater of the two, but not both.

If the bidder submitting the lowest responsive bid is not a "California company" and with the benefit of the reciprocal preference, a "California company's" responsive bid is equal to or less than the original lowest responsive bid, the "California company" will be awarded the contract at its submitted bid price except as provided below.

Small business bidders shall have precedence over non-small business bidders in that the application of the "California company" preference for which non-small business bidders may be eligible shall not result in the denial of the award to a small business bidder.

SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES

Attention is directed to the provisions in Section 8-1.03, "Beginning of Work," in Section 8-1.06, "Time of Completion," and in Section 8-1.07, "Liquidated Damages," of the Standard Specifications and these special provisions.

The Contractor shall begin work within 15 calendar days after the contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department of Transportation.

This work shall be diligently prosecuted to completion before the expiration of **90 WORKING DAYS** beginning on the fifteenth calendar day after approval of the contract.

The Contractor shall pay to the State of California the sum of \$250 per day, for each and every calendar day's delay in finishing the work in excess of the number of working days prescribed above.

SECTION 5. GENERAL

SECTION 5-1. MISCELLANEOUS

5-1.01 PLANS AND WORKING DRAWINGS

When the specifications require working drawings to be submitted to the Division of Structure Design, the drawings shall be submitted to: Division of Structure Design, Documents Unit, Mail Station 9, 1801 30th Street, Sacramento, CA 95816, Telephone 916 227-8252.

5-1.011 EXAMINATION OF PLANS, SPECIFICATIONS, CONTRACT, AND SITE OF WORK

The second paragraph of Section 2-1.03, "Examination of Plans, Specifications, Contract, and Site of Work," of the Standard Specifications is amended to read:

- Where the Department has made investigations of site conditions, including subsurface conditions in areas where work is to be performed under the contract, or in other areas, some of which may constitute possible local material sources, bidders or Contractors may, upon written request, inspect the records of the Department as to those investigations subject to and upon the conditions hereinafter set forth.

Attention is directed to "Differing Site Conditions" of these special provisions regarding physical conditions at the site which may differ from those indicated in "Materials Information," log of test borings or other geotechnical information obtained by the Department's investigation of site conditions.

5-1.012 DIFFERING SITE CONDITIONS

Attention is directed to Section 5-1.116, "Differing Site Conditions," of the Standard Specifications.

During the progress of the work, if subsurface or latent conditions are encountered at the site differing materially from those indicated in the "Materials Information," log of test borings, other geotechnical data obtained by the Department's investigation of subsurface conditions, or an examination of the conditions above ground at the site, the party discovering those conditions shall promptly notify the other party in writing of the specific differing conditions before they are disturbed and before the affected work is performed.

The Contractor will be allowed 15 days from the notification of the Engineer's determination of whether or not an adjustment of the contract is warranted, in which to file a notice of potential claim in conformance with the provisions of Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications and as specified herein; otherwise the decision of the Engineer shall be deemed to have been accepted by the Contractor as correct. The notice of potential claim shall set forth in what respects the Contractor's position differs from the Engineer's determination and provide any additional information obtained by the Contractor, including but not limited to additional geotechnical data. The notice of potential claim shall be accompanied by the Contractor's certification that the following were made in preparation of the bid: a review of the contract, a review of the "Materials Information," a review of the log of test borings and other records of geotechnical data to the extent they were made available to bidders prior to the opening of bids, and an examination of the conditions above ground at the site. Supplementary information, obtained by the Contractor subsequent to the filing of the notice of potential claim, shall be submitted to the Engineer in an expeditious manner.

5-1.015 LABORATORY

When a reference is made in the specifications to the "Laboratory," the reference shall mean the Division of Materials Engineering and Testing Services and the Division of Structural Foundations of the Department of Transportation, or established laboratories of the various Districts of the Department, or other laboratories authorized by the Department to test materials and work involved in the contract. When a reference is made in the specifications to the "Transportation Laboratory," the reference shall mean the Division of Materials Engineering and Testing Services and the Division of Structural Foundations, located at 5900 Folsom Boulevard, Sacramento, CA 95819, Telephone (916) 227-7000.

5-1.017 CONTRACT BONDS

Attention is directed to Section 3-1.02, "Contract Bonds," of the Standard Specifications and these special provisions.

The payment bond shall be in a sum not less than the following:

- A. One hundred percent of the total amount payable by the terms of the contract when the total amount payable does not equal or exceed five million dollars (\$5,000,000).
- B. Fifty percent of the total amount payable by the terms of the contract when the total amount payable is not less than five million dollars (\$5,000,000) and does not exceed ten million dollars (\$10,000,000).
- C. Twenty-five percent of the total amount payable by the terms of the contract when the total amount payable exceeds ten million dollars (\$10,000,000).

5-1.018 EXCAVATION SAFETY PLANS

Section 5-1.02A, "Trench Excavation Safety Plans," of the Standard Specifications is amended to read:

5-1.02A Excavation Safety Plans

- The Construction Safety Orders of the Division of Occupational Safety and Health shall apply to all excavations. For all excavations 1.5 m or more in depth, the Contractor shall submit to the Engineer a detailed plan showing the design and details of the protective systems to be provided for worker protection from the hazard of caving ground during excavation. The detailed plan shall include any tabulated data and any design calculations used in the preparation of the plan. Excavation shall not begin until the detailed plan has been reviewed and approved by the Engineer.
- Detailed plans of protective systems for which the Construction Safety Orders require design by a registered professional engineer shall be prepared and signed by an engineer who is registered as a Civil Engineer in the State of California, and shall include the soil classification, soil properties, soil design calculations that demonstrate adequate stability of the protective system, and any other design calculations used in the preparation of the plan.

Contract No. «Dist»-«Contract_No»

- No plan shall allow the use of a protective system less effective than that required by the Construction Safety Orders.
- If the detailed plan includes designs of protective systems developed only from the allowable configurations and slopes, or Appendices, contained in the Construction Safety Orders, the plan shall be submitted at least 5 days before the Contractor intends to begin excavation. If the detailed plan includes designs of protective systems developed from tabulated data, or designs for which design by a registered professional engineer is required, the plan shall be submitted at least 3 weeks before the Contractor intends to begin excavation.
- Attention is directed to Section 7-1.01E, "Trench Safety."

The third paragraph of Section 19-1.02, "Preservation of Property," of the Standard Specifications is amended to read:

- In addition to the provisions in Sections 5-1.02, "Plans and Working Drawings," and 5-1.02A, "Excavation Safety Plans," detailed plans of the protective systems for excavations on or affecting railroad property will be reviewed for adequacy of protection provided for railroad facilities, property, and traffic. These plans shall be submitted at least 9 weeks before the Contractor intends to begin excavation requiring the protective systems. Approval by the Engineer of the detailed plans for the protective systems will be contingent upon the plans being satisfactory to the railroad company involved.

5-1.02 LABOR NONDISCRIMINATION

Attention is directed to the following Notice that is required by Chapter 5 of Division 4 of Title 2, California Code of Regulations.

NOTICE OF REQUIREMENT FOR NONDISCRIMINATION PROGRAM (GOV. CODE, SECTION 12990)

Your attention is called to the "Nondiscrimination Clause", set forth in Section 7-1.01A(4), "Labor Nondiscrimination," of the Standard Specifications, which is applicable to all nonexempt State contracts and subcontracts, and to the "Standard California Nondiscrimination Construction Contract Specifications" set forth therein. The specifications are applicable to all nonexempt State construction contracts and subcontracts of \$5000 or more.

5-1.03 INTEREST ON PAYMENTS

Interest shall be payable on progress payments, payments after acceptance, final payments, extra work payments, and claim payments as follows:

- Unpaid progress payments, payment after acceptance, and final payments shall begin to accrue interest 30 days after the Engineer prepares the payment estimate.
- Unpaid extra work bills shall begin to accrue interest 30 days after preparation of the first pay estimate following receipt of a properly submitted and undisputed extra work bill. To be properly submitted, the bill must be submitted within 7 days of the performance of the extra work and in conformance with the provisions in Section 9-1.03C, "Records," and Section 9-1.06, "Partial Payments," of the Standard Specifications. An undisputed extra work bill not submitted within 7 days of performance of the extra work will begin to accrue interest 30 days after the preparation of the second pay estimate following submittal of the bill.
- The rate of interest payable for unpaid progress payments, payments after acceptance, final payments, and extra work payments shall be 10 percent per annum.
- The rate of interest payable on a claim, protest or dispute ultimately allowed under this contract shall be 6 percent per annum. Interest shall begin to accrue 61 days after the Contractor submits to the Engineer information in sufficient detail to enable the Engineer to ascertain the basis and amount of said claim, protest or dispute.

The rate of interest payable on any award in arbitration shall be 6 percent per annum if allowed under the provisions of Civil Code Section 3289.

5-1.031 FINAL PAYMENT AND CLAIMS

Attention is directed to Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications.

The District that administers the contract shall submit a claim position letter to the Contractor within 135 days after acceptance of the contract. After receipt of the claim position letter from the District, or 135 days after acceptance of the contract, whichever occurs first, the Contractor may request a meeting with the person or board designated by the District Director to review claims that remain in dispute. If the Contractor requests a meeting, the review person or board shall meet with the Contractor within 45 days after the request is received.

5-1.04 PUBLIC SAFETY

The Contractor shall provide for the safety of traffic and the public in conformance with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications and these special provisions.

The Contractor shall install temporary railing (Type K) between a lane open to public traffic and an excavation, obstacle or storage area when the following conditions exist:

- A. Excavations.—The near edge of the excavation is 3.6 m or less from the edge of the lane, except:
 - 1. Excavations covered with sheet steel or concrete covers of adequate thickness to prevent accidental entry by traffic or the public.
 - 2. Excavations less than 0.3-m deep.
 - 3. Trenches less than 0.3-m wide for irrigation pipe or electrical conduit, or excavations less than 0.3-m in diameter.
 - 4. Excavations parallel to the lane for the purpose of pavement widening or reconstruction.
 - 5. Excavations in side slopes, where the slope is steeper than 1:4 (vertical:horizontal).
 - 6. Excavations protected by existing barrier or railing.
- B. Temporarily Unprotected Permanent Obstacles.—The work includes the installation of a fixed obstacle together with a protective system, such as a sign structure together with protective railing, and the Contractor elects to install the obstacle prior to installing the protective system; or the Contractor, for the Contractor's convenience and with permission of the Engineer, removes a portion of an existing protective railing at an obstacle and does not replace such railing complete in place during the same day.
- C. Storage Areas.—Material or equipment is stored within 3.6 m of the lane and the storage is not otherwise prohibited by the provisions of the Standard Specifications and these special provisions.

The approach end of temporary railing (Type K), installed in conformance with the provisions in this section "Public Safety" and in Section 7-1.09, "Public Safety," of the Standard Specifications, shall be offset a minimum of 4.6 m from the edge of the traffic lane open to public traffic. The temporary railing shall be installed on a skew toward the edge of the traffic lane of not more than 0.3-m transversely to 3 m longitudinally with respect to the edge of the traffic lane. If the 4.6-m minimum offset cannot be achieved, the temporary railing shall be installed on the 10 to 1 skew to obtain the maximum available offset between the approach end of the railing and the edge of the traffic lane, and an array of temporary crash cushion modules shall be installed at the approach end of the temporary railing.

Temporary railing (Type K) shall conform to the provisions in Section 12-3.08, "Temporary Railing (Type K)," of the Standard Specifications. Temporary railing (Type K), conforming to the details shown on 1999 Standard Plan T3, may be used. Temporary railing (Type K) fabricated prior to January 1, 1993, and conforming to 1988 Standard Plan B11-30 may be used, provided the fabrication date is printed on the required Certificate of Compliance.

Temporary crash cushion modules shall conform to the provisions in "Temporary Crash Cushion Module" of these special provisions.

Except for installing, maintaining and removing traffic control devices, whenever work is performed or equipment is operated in the following work areas, the Contractor shall close the adjacent traffic lane unless otherwise provided in the Standard Specifications and these special provisions:

Approach Speed of Public Traffic (Posted Limit) (Kilometers Per Hour)	Work Areas
Over 72 (45 Miles Per Hour)	Within 1.8 m of a traffic lane but not on a traffic lane
56 to 72 (35 to 45 Miles Per Hour)	Within 0.9-m of a traffic lane but not on a traffic lane

The lane closure provisions of this section shall not apply if the work area is protected by permanent or temporary railing or barrier.

When traffic cones or delineators are used to delineate a temporary edge of a traffic lane, the line of cones or delineators shall be considered to be the edge of the traffic lane, however, the Contractor shall not reduce the width of an existing lane to less than 3 m without written approval from the Engineer.

When work is not in progress on a trench or other excavation that required closure of an adjacent lane, the traffic cones or portable delineators used for the lane closure shall be placed off of and adjacent to the edge of the traveled way. The spacing of the cones or delineators shall be not more than the spacing used for the lane closure.

Suspended loads or equipment shall not be moved nor positioned over public traffic or pedestrians.

Full compensation for conforming to the provisions in this section "Public Safety," including furnishing and installing temporary railing (Type K) and temporary crash cushion modules, shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

5-1.05 SURFACE MINING AND RECLAMATION ACT

Attention is directed to the Surface Mining and Reclamation Act of 1975, commencing in Public Resources Code, Mining and Geology, Section 2710, which establishes regulations pertinent to surface mining operations, and to California Public Contract Code Section 10295.5.

Material from mining operations furnished for this project shall only come from permitted sites in compliance with California Public Contract Code Section 10295.5.

The requirements of this section shall apply to materials furnished for the project, except for acquisition of materials in conformance with the provisions in Section 4-1.05, "Use of Materials Found on the Work," of the Standard Specifications.

5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES

When the presence of asbestos or hazardous substances are not shown on the plans or indicated in the specifications and the Contractor encounters materials which the Contractor reasonably believes to be asbestos or a hazardous substance as defined in Section 25914.1 of the Health and Safety Code, and the asbestos or hazardous substance has not been rendered harmless, the Contractor may continue work in unaffected areas reasonably believed to be safe. The Contractor shall immediately cease work in the affected area and report the condition to the Engineer in writing.

In conformance with Section 25914.1 of the Health and Safety Code, removal of asbestos or hazardous substances including exploratory work to identify and determine the extent of the asbestos or hazardous substance will be performed by separate contract.

If delay of work in the area delays the current controlling operation, the delay will be considered a right of way delay and the Contractor will be compensated for the delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

5-1.07 YEAR 2000 COMPLIANCE

This contract is subject to Year 2000 Compliance for automated devices in the State of California.

Year 2000 compliance for automated devices in the State of California is achieved when embedded functions have or create no logical or mathematical inconsistencies when dealing with dates prior to and beyond 1999. The year 2000 is recognized and processed as a leap year. The product shall operate accurately in the manner in which the product was intended for date operation without requiring manual intervention.

The Contractor shall provide the Engineer a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for all automated devices furnished for the project.

5-1.08 SUBCONTRACTOR AND DVBE RECORDS

The Contractor shall maintain records of all subcontracts entered into with certified DVBE subcontractors and records of materials purchased from certified DVBE suppliers. The records shall show the name and business address of each DVBE subcontractor or vendor and the total dollar amount actually paid each DVBE subcontractor or vendor.

Upon completion of the contract, a summary of these records shall be prepared on Form CEM-2402 (S) and certified correct by the Contractor or the Contractor's authorized representative, and shall be furnished to the Engineer.

5-1.086 PERFORMANCE OF DVBE SUBCONTRACTORS AND SUPPLIERS

The DVBEs listed by the Contractor in response to the provisions in Section 2-1.04, "Submission of DVBE Information," and Section 3, "Award and Execution of Contract," of these special provisions, which are determined by the Department to be certified DVBEs, shall perform the work and supply the materials for which they are listed, unless the Contractor has received prior written authorization to perform the work with other forces or to obtain the materials from other sources.

Authorization to utilize other forces or sources of materials may be requested for the following reasons:

- A. The listed DVBE, after having had a reasonable opportunity to do so, fails or refuses to execute a written contract, when the written contract, based upon the general terms, conditions, plans and specifications for the project, or on the terms of the subcontractor's or supplier's written bid, is presented by the Contractor.
- B. The listed DVBE becomes bankrupt or insolvent.
- C. The listed DVBE fails or refuses to perform the subcontract or furnish the listed materials.

- D. The Contractor stipulated that a bond was a condition of executing a subcontract and the listed DVBE subcontractor fails or refuses to meet the bond requirements of the Contractor.
- E. The work performed by the listed subcontractor is substantially unsatisfactory and is not in substantial conformance with the plans and specifications or the subcontractor is substantially delaying or disrupting the progress of the work.
- F. The listed DVBE subcontractor is not licensed pursuant to the Contractor's License Law.
- G. It would be in the best interest of the State.

The Contractor shall not be entitled to payment for the work or material unless it is performed or supplied by the listed DVBE or by other forces (including those of the Contractor) pursuant to prior written authorization of the Engineer.

5-1.09 SUBCONTRACTING

Attention is directed to the provisions in Section 8-1.01, "Subcontracting," of the Standard Specifications, Section 2, "Proposal Requirements and Conditions," Section 2-1.04, "Submission of DVBE Information," and Section 3, "Award and Execution of Contract," of these special provisions and these special provisions.

Pursuant to the provisions in Section 1777.1 of the Labor Code, the Labor Commissioner publishes and distributes a list of contractors ineligible to perform work as a subcontractor on a public works project. This list of debarred contractors is available from the Department of Industrial Relations web site at:

<http://www.dir.ca.gov/DLSE/Debar.html>.

The first sentence in the third paragraph of Section 8-1.01, "Subcontracting," of the Standard Specifications shall not apply.

The Contractor shall perform with the Contractor's own organization contract work amounting to not less than 30 percent of the original total contract price, except that any designated "Specialty Items" may be performed by subcontract and the amount of "Specialty Items" so performed may be deducted from the original total contract price before computing the amount of work required to be performed by the Contractor with the Contractor's own organization.

The DVBE information furnished under Section 3-1.01A, "DVBE Information," of these special provisions is in addition to the subcontractor information required to be furnished in Section 8-1.01, "Subcontracting," and Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications.

Section 10115 of the Public Contract Code requires the Department to implement provisions to establish a goal for Disabled Veteran Business Enterprise (DVBE) participation in highway contracts that are State funded. As a part of this requirement:

- A. No substitution of a DVBE subcontractor shall be made at any time without the written consent of the Department, and
- B. If a DVBE subcontractor is unable to perform successfully and is to be replaced, the Contractor shall make good faith efforts to replace the original DVBE subcontractor with another DVBE subcontractor.

The provisions in Section 2-1.02, "Disabled Veteran Business Enterprise (DVBE)," of these special provisions that DVBEs shall be certified on the date bids are opened does not apply to DVBE substitutions after award of the contract.

5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS

Attention is directed to the provisions in Sections 10262 and 10262.5 of the Public Contract Code and Section 7108.5 of the Business and Professions Code concerning prompt payment to subcontractors.

5-1.11 AREAS FOR CONTRACTOR'S USE

No area is available within the contract limits for the exclusive use of the Contractor. The Contractor shall arrange with the Engineer for areas to store equipment and materials within the work area.

5-1.12 PAYMENTS

Attention is directed to Sections 9-1.06, "Partial Payments," and 9-1.07, "Payment After Acceptance," of the Standard Specifications and these special provisions.

No partial payment will be made for any materials on hand which are furnished but not incorporated in the work.

5-1.13 PRESERVATION OF PROPERTY

Attention is directed to Section 7-1.11, "Preservation of Property," of the Standard Specifications and these special provisions.

Existing trees, shrubs and other plants, that are not to be removed as shown on the plans or specified in these special provisions, and are injured or damaged by reason of the Contractor's operations, shall be replaced by the Contractor. The minimum size of tree replacement shall be ____ mm box and the minimum size of shrub replacement shall be No. 15 container. Replacement ground cover plants shall be from flats and shall be planted 300 mm on center. Replacement of Carpobrotus ground cover plants shall be from cuttings and shall be planted 300 mm on center. Replacement planting shall conform to the requirements in Section 20-4.07, "Replacement," of the Standard Specifications. The Contractor shall water replacement plants in conformance with the provisions in Section 20-4.06, "Watering," of the Standard Specifications.

Damaged or injured plants shall be removed and disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13 of the Standard Specifications. At the option of the Contractor, removed trees and shrubs may be reduced to chips. The chipped material shall be spread within the highway right of way at locations designated by the Engineer.

Replacement planting of injured or damaged trees, shrubs, and other plants shall be completed prior to the start of the plant establishment period. Replacement planting shall conform to the provisions in Section 20-4.05, "Planting," of the Standard Specifications.

Replacement planting of injured or damaged trees, shrubs and other plants shall be completed not less than 20 working days prior to acceptance of the contract. Replacement plants shall be watered as necessary to maintain the plants in a healthy condition.

5-1.14 COOPERATION

Attention is directed to Section 7-1.14, "Cooperation," and Section 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications and these special provisions.

Work by State forces will be in progress within the contract limits during the working period for this contract.

The Contractor shall comply with all security policies of the State concerning the Madera Maintenance Station.

The Contractor shall plan his work to minimize interference with State forces and the public. Interruptions to any services for the purpose of making or breaking a connection shall be made only after consultation with and for such time periods as directed by the Engineer.

5-1.15 OBSTRUCTIONS

Attention is directed to Section 8-1.10, "Utility and Non-Highway Facilities," and Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Attention is directed to the existence of certain underground facilities that may require special precautions be taken by the Contractor to protect the health, safety and welfare of workers and of the public. Facilities requiring special precautions include, but are not limited to: conductors of petroleum products, oxygen, chlorine, and toxic or flammable gases; natural gas in pipelines greater than 150 mm in diameter or pipelines operating at pressures greater than 415 kPa (gage); underground electric supply system conductors or cables, with potential to ground of more than 300 V, either directly buried or in a duct or conduit which do not have concentric grounded or other effectively grounded metal shields or sheaths.

The Contractor shall notify the Engineer and the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to performing any excavation or other work close to any underground pipeline, conduit, duct, wire or other structure. Regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	1-800-642-2444 1-800-227-2600
Underground Service Alert-Southern California (USA)	1-800-422-4133 1-800-227-2600

SECTION 6. (BLANK)

SECTION 7. (BLANK)

SECTION 8. MATERIALS

SECTION 8-1. MISCELLANEOUS

8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS

Only materials and products conforming to the requirements of the specifications shall be incorporated in the work. When metric materials and products are not available, and when approved by the Engineer, and at no cost to the State, materials and products in the United States Standard Measures which are of equal quality and of the required properties and characteristics for the purpose intended, may be substituted for the equivalent metric materials and products, subject to the following provisions:

- A. Materials and products shown on the plans or in the special provisions as being equivalent may be substituted for the metric materials and products specified or detailed on the plans.
- B. Before other non-metric materials and products will be considered for use, the Contractor shall furnish, at the Contractor's expense, evidence satisfactory to the Engineer that the materials and products proposed for use are equal to or better than the materials and products specified or detailed on the plans. The burden of proof as to the quality and suitability of substitutions shall be upon the Contractor and the Contractor shall furnish necessary information as required by the Engineer. The Engineer will be the sole judge as to the quality and suitability of the substituted materials and products and the Engineer's decision will be final.
- C. When the Contractor elects to substitute non-metric materials and products, including materials and products shown on the plans or in the special provisions as being equivalent, the list of sources of material specified in Section 6-1.01, "Source of Supply and Quality of Materials," of the Standard Specification shall include a list of substitutions to be made and contract items involved. In addition, for a change in design or details, the Contractor shall submit plans and working drawings in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The plans and working drawings shall be submitted at least 7 days before the Contractor intends to begin the work involved.

Unless otherwise specified, the following substitutions of materials and products will be allowed:

SUBSTITUTION TABLE FOR SIZES OF HIGH STRENGTH STEEL FASTENERS
ASTM Designation: A 325M

METRIC SIZE SHOWN ON THE PLANS mm x thread pitch	SIZE TO BE SUBSTITUTED inch
M16 x 2	5/8
M20 x 2.5	3/4
M22 x 2.5	7/8
M24 x 3	1
M27 x 3	1-1/8
M30 x 3.5	1-1/4
M36 x 4	1-1/2

SUBSTITUTION TABLE FOR PLAIN WIRE REINFORCEMENT

ASTM Designation: A 82

METRIC SIZE SHOWN ON THE PLANS mm ²	SIZE TO BE SUBSTITUTED inch ² x 100
MW9	W1.4
MW10	W1.6
MW13	W2.0
MW15	W2.3
MW19	W2.9
MW20	W3.1
MW22	W3.5
MW25	W3.9, except W3.5 in piles only
MW26	W4.0
MW30	W4.7
MW32	W5.0
MW35	W5.4
MW40	W6.2
MW45	W6.5
MW50	W7.8
MW55	W8.5, except W8.0 in piles only
MW60	W9.3
MW70	W10.9, except W11.0 in piles only
MW80	W12.4
MW90	W14.0
MW100	W15.5

SUBSTITUTION TABLE FOR BAR REINFORCEMENT

METRIC BAR DESIGNATION NUMBER ¹ SHOWN ON THE PLANS	BAR DESIGNATION NUMBER ² TO BE SUBSTITUTED
13	4
16	5
19	6
22	7
25	8
29	9
32	10
36	11
43	14
57	18

¹Bar designation numbers approximate the number of millimeters of the nominal diameter of the bars.

²Bar numbers are based on the number of eighths of an inch included in the nominal diameter of the bars.

No adjustment will be required in spacing or total number of reinforcing bars due to a difference in minimum yield strength between metric and non-metric bars.

SUBSTITUTION TABLE FOR SIZES OF:

(1) STEEL FASTENERS FOR GENERAL APPLICATIONS (ASTM Designation: A 307 or AASHTO Designation: M 314, Grade 36 or 55), and

(2) HIGH STRENGTH STEEL FASTENERS (ASTM Designation: A 325 or A 449)

METRIC SIZE SHOWN ON THE PLANS mm	SIZE TO BE SUBSTITUTED inch
6 or 6.35	1/4
8 or 7.94	5/16
10 or 9.52	3/8
11 or 11.11	7/16
13 or 12.70	1/2
14 or 14.29	9/16
16 or 15.88	5/8
19 or 19.05	3/4
22 or 22.22	7/8
24, 25, or 25.40	1
29 or 28.58	1-1/8
32 or 31.75	1-1/4
35 or 34.93	1-3/8
38 or 38.10	1-1/2
44 or 44.45	1-3/4
51 or 50.80	2
57 or 57.15	2-1/4
64 or 63.50	2-1/2
70 or 69.85	2-3/4
76 or 76.20	3
83 or 82.55	3-1/4
89 or 88.90	3-1/2
95 or 95.25	3-3/4
102 or 101.60	4

SUBSTITUTION TABLE FOR NOMINAL THICKNESS OF SHEET METAL

UNCOATED HOT AND COLD ROLLED SHEETS		HOT-DIPPED ZINC COATED SHEETS (GALVANIZED)	
METRIC THICKNESS SHOWN ON THE PLANS mm	GAGE TO BE SUBSTITUTED inch	METRIC THICKNESS SHOWN ON THE PLANS mm	GAGE TO BE SUBSTITUTED inch
7.94	0.3125	4.270	0.1681
6.07	0.2391	3.891	0.1532
5.69	0.2242	3.510	0.1382
5.31	0.2092	3.132	0.1233
4.94	0.1943	2.753	0.1084
4.55	0.1793	2.372	0.0934
4.18	0.1644	1.994	0.0785
3.80	0.1495	1.803	0.0710
3.42	0.1345	1.613	0.0635
3.04	0.1196	1.461	0.0575
2.66	0.1046	1.311	0.0516
2.28	0.0897	1.158	0.0456
1.90	0.0747	1.006 or 1.016	0.0396
1.71	0.0673	0.930	0.0366
1.52	0.0598	0.853	0.0336
1.37	0.0538	0.777	0.0306
1.21	0.0478	0.701	0.0276
1.06	0.0418	0.627	0.0247
0.91	0.0359	0.551	0.0217
0.84	0.0329	0.513	0.0202
0.76	0.0299	0.475	0.0187
0.68	0.0269	-----	-----
0.61	0.0239	-----	-----
0.53	0.0209	-----	-----
0.45	0.0179	-----	-----
0.42	0.0164	-----	-----
0.38	0.0149	-----	-----

SUBSTITUTION TABLE FOR WIRE

METRIC THICKNESS SHOWN ON THE PLANS mm	WIRE THICKNESS TO BE SUBSTITUTED inch	GAGE NO.
6.20	0.244	3
5.72	0.225	4
5.26	0.207	5
4.88	0.192	6
4.50	0.177	7
4.11	0.162	8
3.76	0.148	9
3.43	0.135	10
3.05	0.120	11
2.69	0.106	12
2.34	0.092	13
2.03	0.080	14
1.83	0.072	15
1.57	0.062	16
1.37	0.054	17
1.22	0.048	18
1.04	0.041	19
0.89	0.035	20

SUBSTITUTION TABLE FOR PIPE PILES

METRIC SIZE SHOWN ON THE PLANS mm x mm	SIZE TO BE SUBSTITUTED inch x inch
PP 360 x 4.55	NPS 14 x 0.179
PP 360 x 6.35	NPS 14 x 0.250
PP 360 x 9.53	NPS 14 x 0.375
PP 360 x 11.12	NPS 14 x 0.438
PP 406 x 12.70	NPS 16 x 0.500
PP 460 x T	NPS 18 x T"
PP 508 x T	NPS 20 x T"
PP 559 x T	NPS 22 x T"
PP 610 x T	NPS 24 x T"
PP 660 x T	NPS 26 x T"
PP 711 x T	NPS 28 x T"
PP 762 x T	NPS 30 x T"
PP 813 x T	NPS 32 x T"
PP 864 x T	NPS 34 x T"
PP 914 x T	NPS 36 x T"
PP 965 x T	NPS 38 x T"
PP 1016 x T	NPS 40 x T"
PP 1067 x T	NPS 42 x T"
PP 1118 x T	NPS 44 x T"
PP 1219 x T	NPS 48 x T"
PP 1524 x T	NPS 60 x T"

The thickness in millimeters (T) represents an exact conversion of the thickness in inches (T").

SUBSTITUTION TABLE FOR STRUCTURAL TIMBER AND LUMBER

METRIC MINIMUM DRESSED DRY, SHOWN ON THE PLANS mm x mm	METRIC MINIMUM DRESSED GREEN, SHOWN ON THE PLANS mm x mm	NOMINAL SIZE TO BE SUBSTITUTED inch x inch
19x89	20x90	1x4
38x89	40x90	2x4
64x89	65x90	3x4
89x89	90x90	4x4
140x140	143x143	6x6
140x184	143x190	6x8
184x184	190x190	8x8
235x235	241x241	10x10
286x286	292x292	12x12

SUBSTITUTION TABLE FOR NAILS AND SPIKES

METRIC COMMON NAIL, SHOWN ON THE PLANS Length, mm Diameter, mm	METRIC BOX NAIL, SHOWN ON THE PLANS Length, mm Diameter, mm	METRIC SPIKE, SHOWN ON THE PLANS Length, mm Diameter, mm	SIZE TO BE SUBSTITUTED Penny-weight
50.80 2.87	50.80 2.51	————	6d
63.50 3.33	63.50 2.87	————	8d
76.20 3.76	76.20 3.25	76.20 4.88	10d
82.55 3.76	82.55 3.25	82.55 4.88	12d
88.90 4.11	88.90 3.43	88.90 5.26	16d
101.60 4.88	101.60 3.76	101.60 5.72	20d
114.30 5.26	114.30 3.76	114.30 6.20	30d
127.00 5.72	127.00 4.11	127.00 6.68	40d
————	————	139.70 7.19	50d
————	————	152.40 7.19	60d

**SUBSTITUTION TABLE FOR IRRIGATION
COMPONENTS**

METRIC WATER METERS, TRUCK LOADING STANDPIPES, VALVES, BACKFLOW PREVENTERS, FLOW SENSORS, WYE STRAINERS, FILTER ASSEMBLY UNITS, PIPE SUPPLY LINES, AND PIPE IRRIGATION SUPPLY LINES SHOWN ON THE PLANS DIAMETER NOMINAL (DN) mm	NOMINAL SIZE TO BE SUBSTITUTED inch
15	1/2
20	3/4
25	1
32	1-1/4
40	1-1/2
50	2
65	2-1/2
75	3
100	4
150	6
200	8
250	10
300	12
350	14
400	16

Unless otherwise specified, substitutions of United States Standard Measures standard structural shapes corresponding to the metric designations shown on the plans and in conformance with the requirements in ASTM Designation: A 6/A 6M, Annex 2, will be allowed.

8-1.02 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS

The Department maintains the following list of Prequalified and Tested Signing and Delineation Materials. The Engineer shall not be precluded from sampling and testing products on the list of Prequalified and Tested Signing and Delineation Materials.

The manufacturer of products on the list of Prequalified and Tested Signing and Delineation Materials shall furnish the Engineer a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each type of traffic product supplied.

For those categories of materials included in the list of Prequalified and Tested Signing and Delineation Materials, only those products shown within the listing may be used in the work. Other categories of products, not included in the list of Prequalified and Tested Signing and Delineation Materials, may be used in the work provided they conform to the requirements of the Standard Specifications.

Materials and products may be added to the list of Prequalified and Tested Signing and Delineation Materials if the manufacturer submits a New Product Information Form to the New Product Coordinator at the Transportation Laboratory. Upon a Departmental request for samples, sufficient samples shall be submitted to permit performance of required tests. Approval of materials or products will depend upon compliance with the specifications and tests the Department may elect to perform.

PAVEMENT MARKERS, PERMANENT TYPE

Retroreflective

- A. Apex, Model 921 (100 mm x 100 mm)
- B. Ray-O-Lite, Models SS (100 mm x 100 mm), RS (100 mm x 100 mm) and AA (100 mm x 100 mm)
- C. Stimsonite, Models 88 (100 mm x 100 mm), 911 (100 mm x 100 mm), 953 (70 mm x 114 mm)
- D. 3M Series 290 (89 mm x 100 mm)

Retroreflective With Abrasion Resistant Surface (ARS)

- A. Ray-O-Lite "AA" ARS (100 mm x 100 mm)
- B. Stimsonite, Models 911 (100 mm x 100 mm), 953 (70 mm x 114 mm)
- C. 3M Series 290 (89 mm x 100 mm)

Retroreflective With Abrasion Resistant Surface (ARS)

(Used for recessed applications)

- A. Stimsonite, Model 948 (58 mm x 119 mm)
- B. Ray-O-Lite, Model 2002 (58 mm x 117 mm)
- C. Stimsonite, Model 944SB (51 mm x 100 mm)*
- D. Ray-O-Lite, Model 2004 ARS (51 mm x 100 mm)*

*For use only in 114 mm wide (older) recessed slots

Non-Reflective For Use With Epoxy Adhesive, 100 mm Round

- A. Apex Universal (Ceramic)
- B. Highway Ceramics, Inc. (Ceramic)

Non-Reflective For Use With Bitumen Adhesive, 100 mm Round

- A. Alpine Products, "D-Dot" and "ANR" (ABS)
- B. Apex Universal (Ceramic)
- C. Apex Universal, Model 929 (ABS)
- D. Elgin Molded Plastics, "Empco-Lite" Model 900 (ABS)
- E. Highway Ceramics, Inc. (Ceramic)
- F. Hi-Way Safety, Inc., Models P20-2000W and 2001Y (ABS)
- G. Interstate Sales, "Diamond Back" (ABS) and (Polypropylene)
- H. Road Creations, Model RCB4NR (Acrylic)
- I. Zumar Industries, "Titan TM40A" (ABS)

PAVEMENT MARKERS, TEMPORARY TYPE

Temporary Markers For Long Term Day/Night Use (6 months or less)

- A. Apex Universal, Model 924 (100 mm x 100 mm)
- B. Davidson Plastics Corp., Model 3.0 (100 mm x 100 mm)
- C. Elgin Molded Plastics, "Empco-Lite" Model 901 (100 mm x 100 mm)
- D. Road Creations, Model R41C (100 mm x 100 mm)
- E. Vega Molded Products "Temporary Road Marker" (75 mm x 100 mm)

Temporary Markers For Short Term Day/Night Use (14 days or less)

(For seal coat or chip seal applications, clear protective covers are required)

- A. Apex Universal, Model 932
- B. Davidson Plastics, Models T.O.M., T.R.P.M., and "HH" (High Heat)
- C. Hi-Way Safety, Inc., Model 1280/1281

STRIPING AND PAVEMENT MARKING MATERIAL

Permanent Traffic Striping and Pavement Marking Tape

- A. Advanced Traffic Marking, Series 300 and 400
- B. Brite-Line, Series 1000
- C. Brite-Line "DeltaLine XRP"
- D. Swarco Industries, "Director 35" (For transverse application only)
- E. Swarco Industries, "Director 60"
- F. 3M, "Stamark" Series 380 and 5730
- G. 3M, "Stamark" Series 420 (For transverse application only)

Temporary (Removable) Striping and Pavement Marking Tape (6 months or less)

- A. Advanced Traffic Marking, Series 200
- B. Brite-Line, Series 100
- C. P.B. Laminations, Aztec, Grade 102
- D. Swarco Industries, "Director-2"
- E. 3M, "Stamark," Series 620
- F. 3M Series A145 Removable Black Line Mask
(Black Tape: For use only on Asphalt Concrete Surfaces)
- G. Advanced Traffic Marking Black "Hide-A-Line"
(Black Tape: For use only on Asphalt Concrete Surfaces)
- H. Brite-Line "BTR" Black Removable Tape
(Black Tape: For use only on Asphalt Concrete Surfaces)

Preformed Thermoplastic (Heated in place)

- A. Flint Trading, "Premark" and "Premark 20/20 Flex"
- B. Pavemark, "Hotape"

Removable Traffic Paint

- A. Bepro, Series 250/252 and No. 93 Remover

Ceramic Surfacing Laminate, 150 mm x 150 mm

- A. Safeline Industries/Highway Ceramics, Inc.

CLASS 1 DELINEATORS

One Piece Driveable Flexible Type, 1700 mm

- A. Carsonite, Curve-Flex CFRM-400
- B. Carsonite, Roadmarker CRM-375
- C. Davidson Plastics, "Flexi-Guide Models 400 and 566"
- D. FlexStake, Model 654 TM
- E. GreenLine Models HWD1-66 and CGD1-66
- F. J. Miller Industries, Model JMI-375 (with soil anchor)

Special Use Flexible Type, 1700 mm

- A. Carsonite, "Survivor" (with 450 mm U-Channel base)
- B. FlexStake, Model 604
- C. GreenLine Models HWD and CGD (with 450 mm U-Channel base)
- D. Safe-Hit with 200 mm pavement anchor (SH248-GP1)
- E. Safe-Hit with 380 mm soil anchor (SH248-GP2) and with 450 mm soil anchor (SH248-GP3)

Surface Mount Flexible Type, 1200 mm

- A. Bent Manufacturing Company, Masterflex Model MF-180EX-48
- B. Carsonite, "Super Duck II"
- C. FlexStake, Surface Mount, Models 704 and 754 TM

CHANNELIZERS

Surface Mount Type, 900 mm

- A. Bent Manufacturing Company, Masterflex Models MF-360-36 (Round) and MF-180-36 (Flat)
- B. Carsonite, "Super Duck" (Flat SDF-436, Round SDR-336)
- C. Carsonite, "Super Duck II" Model SDCF203601MB "The Channelizer"
- D. Davidson Plastics, Flex-Guide Models FG300LD and FG300UR
- E. FlexStake, Surface Mount, Models 703 and 753 TM
- F. GreenLine, Model SMD-36
- G. Hi-Way Safety, Inc. "Channel Guide Channelizer" Model CGC36
- H. The Line Connection, "Dura-Post" Model DP36-3 (Permanent)
- I. The Line Connection, "Dura-Post" Model DP36-3C (Temporary)
- J. Repo, Models 300 and 400
- K. Safe-Hit, Guide Post, Model SH236SMA

CONICAL DELINEATORS, 1070 mm

(For 700 mm Traffic Cones, see Standard Specifications)

- A. Bent Manufacturing Company "T-Top"
- B. Plastic Safety Systems "Navigator-42"
- C. Roadmaker Company "Stacker"
- D. Traffix Devices "Grabber"

OBJECT MARKERS

Type "K", 450 mm

- A. Carsonite, Model SMD-615
- B. FlexStake, Model 701 KM
- C. Repo, Models 300 and 400
- D. Safe-Hit, Model SH718SMA
- E. The Line Connection, Model DP21-4K

Type "K-4" / "Q" Object Markers, 600 mm

- A. Bent Manufacturing "Masterflex" Model MF-360-24
- B. Carsonite, Super Duck II
- C. FlexStake, Model 701KM
- D. Repo, Models 300 and 400
- E. Safe-Hit, Models SH8 24SMA_WA and SH8 24GP3_WA
- F. The Line Connection, Model DP21-4Q

TEMPORARY RAILING (TYPE K) REFLECTORS AND CONCRETE BARRIER MARKERS

Impactable Type

- A. ARTUK, "FB"
- B. Davidson Plastics, Model PCBM-12
- C. Duraflex Corp., "Flexx 2020" and "Electriflexx"
- D. Hi-Way Safety, Inc., Model GMKRM100

Non-Impactable Type

- A. ARTUK, JD Series
- B. Stimsonite, Model 967 (with 83 mm Acrylic cube corner reflector)
- C. Stimsonite, Model 967LS
- D. Vega Molded Products, Models GBM and JD

THREE BEAM BARRIER MARKERS

(For use to the left of traffic)

- A. Duraflex Corp., "Railrider"
- B. Davidson Plastics, "Mini" (75 mm x 254 mm)

CONCRETE BARRIER DELINEATORS, 400 mm

(For use to the right of traffic. When mounted on top of barrier, places top of reflective element at 1200 mm)

- A. Davidson Plastics, Model PCBM T-16
- B. Safe-Hit, Model SH216RBM
- C. Sun-Lab Technology, "Safety Guide Light, Model TM," 130 mm x 130 mm x 80 mm

CONCRETE BARRIER-MOUNTED MINI-DRUM (260 mm x 360 mm x 570 mm)

- A. Stinson Equipment Company "SaddleMarker"

SOUND WALL DELINEATOR

(Applied vertically. Place top of 75 mm x 300 mm reflective element at 1200 mm above roadway)

- A. Davidson Plastics, PCBM S-36
- B. Sun-Lab Technology, "Safety Guide Light, Model SM12," 130 mm x 130 mm x 80 mm

GUARD RAILING DELINEATOR

(Top of reflective element at 1200 mm above plane of roadway)

Wood Post Type, 686 mm

- A. Carsonite, Model 427
- B. Davidson Plastics FG 427 and FG 527
- C. FlexStake, Model 102 GR
- D. GreenLine GRD 27
- E. J.Miller Model JMI-375G
- F. Safe-Hit, Model SH227GRD

Steel Post Type

- A. Carsonite, Model CFGR-327 with CFGRBK300 Mounting Bracket

RETROREFLECTIVE SHEETING

Channelizers, Barrier Markers, and Delineators

- A. 3M, High Intensity
- B. Reflexite, PC-1000 Metalized Polycarbonate
- C. Reflexite, AC-1000 Acrylic
- D. Reflexite, AP-1000 Metalized Polyester
- E. Reflexite, AR-1000 Abrasion Resistant Coating
- F. Stimsonite, Series 6200 (For rigid substrate devices only)

Traffic Cones, 330 mm Sleeves

- A. Reflexite SB (Polyester), Vinyl or "TR" (Semi-transparent)

Traffic Cones, 100 mm and 150 mm Sleeves

- A. 3M Series 3840
- B. Reflexite Vinyl, "TR" (Semi-transparent) or "Conformalite"

Barrels and Drums

- A. Reflexite, "Super High Intensity" or "High Impact Drum Sheeting"
- B. 3M Series 3810

Barricades: Type I, Engineer Grade

- A. American Decal, Adcolite
- B. Avery Dennison, 1500 and 1600
- C. 3M, Scotchlite, Series CW

Barricades: Type II, Super Engineer Grade

- A. Avery Dennison, "Fasign" 2500 Series
- B. Kiwalite Type II
- C. Nikkalite 1800 Series

Signs: Type II, Super Engineer Grade

- A. Avery Dennison, "Fasign" 2500 Series
- B. Kiwalite, Type II
- C. Nikkalite 1800 Series

Signs: Type III, High-Intensity Grade

- A. 3M Series 3800
- B. Nippon Carbide, Nikkalite Brand Ultralite Grade II

Signs: Type IV, High-Intensity Prismatic Grade

- A. Avery Dennison T-6500 (Formerly Stimsonite Series 6200)

Signs: Type VII, High-Intensity Prismatic Grade

- A. 3M Series 3900

Signs: Type VI, Roll-Up Signs

- A. Reflexite, Vinyl (Orange), Reflexite "SuperBright" (Fluorescent orange)
- B. 3M Series RS34 (Orange) and RS20 (Fluorescent orange)

SPECIALTY SIGN (All Plastic)

- A. All Sign Products, STOP Sign, 750 mm

SIGN SUBSTRATE FOR CONSTRUCTION AREA SIGNS

Aluminum

Fiberglass Reinforced Plastic (FRP)

- A. Sequentia, "Polyplate"
- B. Fiber-Brite

SECTION 8-2. (BLANK)

SECTION 9. (BLANK)

SECTION 10. CONSTRUCTION DETAILS

SECTION 10-1. GENERAL

10-1.01 WATER POLLUTION CONTROL

Water pollution control work shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications and these special provisions.

Water pollution control work shall conform to the requirements in the Construction Contractor's Guide and Specifications of the Caltrans Storm Water Quality Handbooks, dated April 1997, and addenda thereto issued up to and including the date of advertisement of the project, hereafter referred to as the "Handbook." Copies of the Handbook may be obtained from the Department of Transportation, Material Operations Branch, Publication Distribution Unit, 1900 Royal Oaks Drive, Sacramento, California 95815, Telephone: (916) 445-3520.

The Contractor shall know and fully comply with the applicable provisions of the Handbook and Federal, State, and local regulations that govern the Contractor's operations and storm water discharges from both the project site and areas of disturbance outside the project limits during construction.

Unless arrangements for disturbance of areas outside the project limits are made by the Department and made part of the contract, it is expressly agreed that the Department assumes no responsibility whatsoever to the Contractor or property owner with respect to any arrangements made between the Contractor and property owner to allow disturbance of areas outside the project limits.

The Contractor shall be responsible for the costs and for liabilities imposed by law as a result of the Contractor's failure to comply with the requirements set forth in this section "Water Pollution Control" including, but not limited to, compliance with the applicable provisions of the Handbook and Federal, State, and local regulations. For the purposes of this paragraph, costs and liabilities include, but are not limited to, fines, penalties, and damages whether assessed against the State or the Contractor, including those levied under the Federal Clean Water Act and the State Porter Cologne Water Quality Act.

In addition to the remedies authorized by law, an amount of the money due the Contractor under the contract, as determined by the Department, may be retained by the State of California until disposition has been made of the costs and liabilities.

The retention of money due the Contractor shall be subject to the following:

- A. The Department will give the Contractor 30 days notice of the Department's intention to retain funds from partial payments which may become due to the Contractor prior to acceptance of the contract. Retention of funds from payments made after acceptance of the contract may be made without prior notice to the Contractor.
- B. No retention of additional amounts out of partial payments will be made if the amount to be retained does not exceed the amount being withheld from partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications.
- C. If the Department has retained funds and it is subsequently determined that the State is not subject to the costs and liabilities in connection with the matter for which the retention was made, the Department shall be liable for interest on the amount retained at the legal rate of interest for the period of the retention.

Conformance with the provisions in this section "Water Pollution Control" shall not relieve the Contractor from the Contractor's responsibilities as provided in Section 7, "Legal Relations and Responsibilities," of the Standard Specifications.

WATER POLLUTION CONTROL PROGRAM PREPARATION, APPROVAL AND UPDATES

As part of the water pollution control work, a Water Pollution Control Program, hereafter referred to as the "WPCP," is required for this contract. The WPCP shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications, the requirements in the Handbook, and these special provisions.

No work having potential to cause water pollution, as determined by the Engineer, shall be performed until the WPCP has been approved by the Engineer.

Within 10 days after the approval of the contract, the Contractor shall submit 3 copies of the WPCP to the Engineer. The Engineer will have 3 days to review the WPCP. If revisions are required, as determined by the Engineer, the Contractor shall revise and resubmit the WPCP within 3 days of receipt of the Engineer's comments. The Engineer will have 3 days to review the revisions. Upon the Engineer's approval of the WPCP, 3 additional copies of the WPCP incorporating the required changes shall be submitted to the Engineer. Minor changes or clarifications to the initial submittal may be made and attached as amendments to the WPCP. In order to allow construction activities to proceed, the Engineer may conditionally approve the WPCP while minor revisions or amendments are being completed.

The WPCP shall identify pollution sources that may adversely affect the quality of storm water discharges associated with the project and shall identify water pollution control measures, hereafter referred to as control measures, to be constructed, implemented, and maintained in order to reduce to the extent feasible pollutants in storm water discharges from the construction site during construction under this contract.

The WPCP shall incorporate control measures in the following categories:

- A. Soil stabilization practices;
- B. Sediment control practices;
- C. Sediment tracking control practices;
- D. Wind erosion control practices; and
- E. Nonstorm water management and waste management and disposal control practices.

Specific objectives and minimum requirements for each category of control measures are contained in the Handbook.

The Contractor shall consider the objectives and minimum requirements presented in the Handbook for each of the above categories. When minimum requirements are listed for any category, the Contractor shall incorporate into the WPCP and implement on the project, one or more of the listed minimum controls required in order to meet the pollution control objectives for the category. In addition, the Contractor shall consider other control measures presented in the Handbook and

shall incorporate into the WPCP and implement on the project the control measures necessary to meet the objectives of the WPCP. The Contractor shall document the selection process in conformance with the procedure specified in the Handbook.

The WPCP shall include, but not be limited to, the following items as described in the Handbook:

- A. Project description and Contractor's certification;
- B. Project information;
- C. Pollution sources, control measures, and water pollution control drawings; and
- D. Amendments, if any.

The Contractor shall amend the WPCP, graphically and in narrative form, whenever there is a change in construction activities or operations which may affect the discharge of significant quantities of pollutants to surface waters, ground waters, municipal storm drain systems or when deemed necessary by the Engineer. The WPCP shall be amended if the WPCP has not achieved the objective of reducing pollutants in storm water discharges. Amendments shall show additional control measures or revised operations, including those in areas not shown in the initially approved WPCP, which are required on the project to control water pollution effectively. Amendments to the WPCP shall be submitted for review and approval by the Engineer in the same manner specified for the initially approved WPCP. Amendments shall be dated and attached to the on-site WPCP document.

The Contractor shall keep a copy of the WPCP, together with updates, revisions and amendments at the project site.

WPCP IMPLEMENTATION

Upon approval of the WPCP, the Contractor shall be responsible throughout the duration of the project for installing, constructing, inspecting, and maintaining the control measures included in the WPCP and any amendments thereto and for removing and disposing of temporary control measures. Unless otherwise directed by the Engineer or specified in these special provisions, the Contractor's responsibility for WPCP implementation shall continue throughout any temporary suspension of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications. Requirements for installation, construction, inspection, maintenance, removal, and disposal of control measures are specified in the Handbook and these special provisions.

Soil stabilization practices and sediment control measures, including minimum requirements, shall be provided throughout the winter season, defined as between November 1 and March 15.

Implementation of soil stabilization practices and sediment control measures for soil-disturbed areas on the project site shall be completed, except as provided for below, not later than 20 days prior to the beginning of the winter season or upon start of applicable construction activities for projects which begin either during or within 20 days of the winter season.

Throughout the winter season, the active, soil-disturbed area of the project site shall be not more than 1.9 hectares. The Engineer may approve, on a case-by-case basis, expansions of the active, soil-disturbed area limit. The Contractor shall demonstrate the ability and preparedness to fully deploy soil stabilization practices and sediment control measures to protect soil-disturbed areas on the project site before the onset of precipitation. A quantity of soil stabilization and sediment control materials shall be maintained on site equal to 100 percent of that sufficient to protect unprotected, soil-disturbed areas on the project site. A detailed plan for the mobilization of sufficient labor and equipment shall be maintained to fully deploy control measures required to protect unprotected, soil-disturbed areas on the project site prior to the onset of precipitation. A current inventory of control measure materials and the detailed mobilization plan shall be included as part of the WPCP.

Throughout the winter season, soil-disturbed areas on the project site shall be considered to be nonactive whenever soil disturbing activities are expected to be discontinued for a period of 20 or more days and the areas are fully protected. Areas that will become nonactive either during the winter season or within 20 days thereof shall be fully protected with soil stabilization practices and sediment control measures within 10 days of the discontinuance of soil disturbing activities or prior to the onset of precipitation, whichever is first to occur.

Throughout the winter season, active soil-disturbed areas of the project site shall be fully protected at the end of each day with soil stabilization practices and sediment control measures unless fair weather is predicted through the following work day. The weather forecast shall be monitored by the Contractor on a daily basis. The National Weather Service forecast shall be used. An alternative weather forecast proposed by the Contractor may be used if approved by the Engineer. If precipitation is predicted prior to the end of the following work day, construction scheduling shall be modified, as required, and functioning control measures shall be deployed prior to the onset of the precipitation.

The Contractor shall implement, year-round and throughout the duration of the project, control measures included in the WPCP for sediment tracking, wind erosion, nonstorm water management, and waste management and disposal.

The Engineer may order the suspension of construction operations which create water pollution if the Contractor fails to conform to the provisions in this section "Water Pollution Control" as determined by the Engineer.

MAINTENANCE

To ensure the proper implementation and functioning of control measures, the Contractor shall regularly inspect and maintain the construction site for the control measures identified in the WPCP. The Contractor shall identify corrective actions and time needed to address any deficient measures or reinitiate any measures that have been discontinued.

The construction site inspection checklist provided in the Handbook shall be used to ensure that the necessary measures are being properly implemented, and to ensure that the control measures are functioning adequately. One copy of each site inspection record shall be submitted to the Engineer.

During the winter season, inspections of the construction site shall be conducted by the Contractor to identify deficient measures, as follows:

- A. Prior to a forecast storm;
- B. After all precipitation which causes runoff capable of carrying sediment from the construction site;
- C. At 24-hour intervals during extended precipitation events; and
- D. Routinely, at a minimum of once every 2 weeks.

If the Contractor or the Engineer identifies a deficiency in the deployment or functioning of an identified control measure, the deficiency shall be corrected immediately. The deficiency may be corrected at a later date and time if requested by the Contractor and approved by the Engineer in writing, but not later than the onset of subsequent precipitation events. The correction of deficiencies shall be at no additional cost to the State.

PAYMENT

Full compensation for conforming to the provisions in this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

The Engineer will retain an amount equal to 25 percent of the estimated value of the contract work performed during estimate periods in which the Contractor fails to conform to the provisions in this section "Water Pollution Control" as determined by the Engineer.

Retentions for failure to conform to the provisions in this section "Water Pollution Control" shall be in addition to the other retentions provided for in the contract. The amounts retained for failure of the Contractor to conform to the provisions in this section will be released for payment on the next monthly estimate for partial payment following the date that a WPCP has been implemented and maintained and water pollution is adequately controlled, as determined by the Engineer.

10-1.02 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES

Flagging, signs, and all other traffic control devices furnished, installed, maintained, and removed when no longer required shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Category 1 traffic control devices are defined as those devices that are small and lightweight (less than 45 kg), and have been in common use for many years. The devices shall be known to be crashworthy by crash testing, crash testing of similar devices, or years of demonstrable safe performance. Category 1 traffic control devices include traffic cones, plastic drums, portable delineators, and channelizers.

If requested by the Engineer, the Contractor shall provide written self-certification for crashworthiness of Category 1 traffic control devices. Self-certification shall be provided by the manufacturer or Contractor and shall include the following: date, Federal Aid number (if applicable), expenditure authorization, district, county, route and kilometer post of project limits; company name of certifying vendor, street address, city, state and zip code; printed name, signature and title of certifying person; and an indication of which Category 1 traffic control devices will be used on the project. The Contractor may obtain a standard form for self-certification from the Engineer.

Category 2 traffic control devices are defined as those items that are small and lightweight (less than 45 kg), that are not expected to produce significant vehicular velocity change, but may otherwise be potentially hazardous. Category 2 traffic control devices include: barricades and portable sign supports.

Category 2 devices purchased on or after October 1, 2000 shall be on the Federal Highway Administration (FHWA) Acceptable Crashworthy Category 2 Hardware for Work Zones list. This list is maintained by FHWA and can be located at the following internet address: <http://safety.fhwa.dot.gov/fourthlevel/hardware/listing.cfm?code=workzone>. The Department maintains a secondary list at the following internet address: <http://www.dot.ca.gov/hq/traffops/signtech/signdel/pdf/ffiles.htm>.

Category 2 devices that have not received FHWA acceptance, and were purchased before October 1, 2000, may continue to be used until they complete their useful service life or until January 1, 2003, whichever comes first. Category 2 devices in use that have received FHWA acceptance shall be labeled with the FHWA acceptance letter number and the name of the manufacturer by the start of the project. The label shall be readable. After January 1, 2003, all Category 2 devices without a label shall not be used on the project.

Full compensation for providing self-certification for crashworthiness of Category 1 traffic control devices and labeling Category 2 devices as specified shall be considered as included in the prices paid for the various contract items of work requiring the use of the Category 1 or Category 2 traffic control devices and no additional compensation will be allowed therefor.

10-1.03 CONSTRUCTION AREA SIGNS

Construction area signs shall be furnished, installed, maintained, and removed when no longer required in conformance with the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. Type II retroreflective sheeting shall not be used on construction area sign panels.

The Contractor shall notify the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to commencing excavation for construction area sign posts. The regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	1-800-642-2444 1-800-227-2600
Underground Service Alert-Southern California (USA)	1-800-422-4133 1-800-227-2600

Excavations required to install construction area signs shall be performed by hand methods without the use of power equipment, except that power equipment may be used if it is determined there are no utility facilities in the area of the proposed post holes.

Sign substrates for stationary mounted construction area signs may be fabricated from fiberglass reinforced plastic as specified under "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Full compensation for furnishing, installing, maintaining, removing, and disposing of construction area signs, including lamps, power sources and appurtenances, shall be considered as included in the contract lump sum price paid for traffic control system and no separate payment will be made therefor.

10-1.04 MAINTAINING TRAFFIC

Attention is directed to Sections 7-1.08, "Public Convenience," 7-1.09, "Public Safety," and 12, "Construction Area Traffic Control Devices," of the Standard Specifications and to the provisions in "Public Safety" of these special provisions and these special provisions. Nothing in these special provisions shall be construed as relieving the Contractor from the responsibilities specified in Section 7-1.09.

Lane closures shall conform to the provisions in section "Traffic Control System for Lane Closure" of these special provisions.

Personal vehicles of the Contractor's employees shall not be parked on the traveled way including any section closed to public traffic.

The Contractor shall notify local authorities of the Contractor's intent to begin work at least 5 days before work is begun. The Contractor shall cooperate with local authorities relative to handling traffic through the area and shall make arrangements relative to keeping the working area clear of parked vehicles.

Whenever vehicles or equipment are parked on the shoulder within 1.8 m of a traffic lane, the shoulder area shall be closed with fluorescent traffic cones or portable delineators placed on a taper in advance of the parked vehicles or equipment and along the edge of the pavement at 7.5 m intervals to a point not less than 7.5 m past the last vehicle or piece of equipment. A minimum of 9 cones or portable delineators shall be used for the taper. A C23 (Road Work Ahead) or C24 (Shoulder Work Ahead) sign shall be mounted on a portable sign stand with flags. The sign shall be placed where designated by the Engineer.

A minimum of one paved traffic lane, not less than 3.0 m wide, shall be open for use by public traffic in each direction of travel.

During construction on the city street the road may be closed and public traffic stopped for periods not to exceed 30 minutes. After each closure, accumulated traffic shall pass through the work before another closure is made.

10-1.05 TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE

A traffic control system shall consist of closing traffic lanes in conformance with the details shown on the plans, the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications, the provisions under "Maintaining Traffic" and "Construction Area Signs" of these special provisions, and these special provisions.

The provisions in this section will not relieve the Contractor from the responsibility to provide additional devices or take measures as may be necessary to comply with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications.

During traffic stripe operations and pavement marker placement operations using bituminous adhesive, traffic shall be controlled, at the option of the Contractor, with stationary lane closures. During other operations, traffic shall be controlled with stationary lane closures. Attention is directed to the provisions in Section 84-1.04, "Protection From Damage," and Section 85-1.06, "Placement," of the Standard Specifications.

If components in the traffic control system are displaced or cease to operate or function as specified, from any cause, during the progress of the work, the Contractor shall immediately repair the components to the original condition or replace the components and shall restore the components to the original location.

STATIONARY LANE CLOSURE

When lane closures are made for work periods only, at the end of each work period, all components of the traffic control system, except portable delineators placed along open trenches or excavation adjacent to the traveled way, shall be removed from the traveled way and shoulder. If the Contractor so elects, the components may be stored at selected central locations designated by the Engineer within the limits of the local street right of way.

One-way traffic shall be controlled through the project in conformance with the plan entitled "Traffic Control System for Lane Closure on Two Lane Conventional Highways" and these special provisions.

PAYMENT

The contract lump sum price paid for traffic control system shall include full compensation for furnishing all labor (except for flagging costs), materials (including signs), tools, equipment, and incidentals, and for doing all the work involved in placing, removing, storing, maintaining, replacing, and disposing of the components of the traffic control system and maintaining traffic as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer. Flagging costs will be paid for as provided in Section 12-2.02, "Flagging Costs," of the Standard Specifications.

Traffic control system required by work which is classed as extra work, as provided in Section 4-1.03D of the Standard Specifications, will be paid for as a part of the extra work.

10-1.06 TEMPORARY CRASH CUSHION MODULE

This work shall consist of furnishing, installing, and maintaining sand filled temporary crash cushion modules in groupings or arrays at each location shown on the plans, as specified in these special provisions or where designated by the Engineer. The grouping or array of sand filled modules shall form a complete sand filled temporary crash cushion in conformance with the details shown on the plans and these special provisions.

Attention is directed to "Public Safety" of these special provisions.

GENERAL

Whenever the work or the Contractor's operations establishes a fixed obstacle, the exposed fixed obstacle shall be protected with a sand filled temporary crash cushion. The sand filled temporary crash cushion shall be in place prior to opening the lanes adjacent to the fixed obstacle to public traffic.

Sand filled temporary crash cushions shall be maintained in place at each location, including times when work is not actively in progress. Sand filled temporary crash cushions may be removed during a work period for access to the work provided that the exposed fixed obstacle is 4.6 m or more from a lane carrying public traffic and the temporary crash cushion is reset to protect the obstacle prior to the end of the work period in which the fixed obstacle was exposed. When no longer required, as determined by the Engineer, sand filled temporary crash cushions shall be removed from the site of the work.

MATERIALS

At the Contractor's option, the modules for use in sand filled temporary crash cushions shall be either Energite III Inertial Modules, Fitch Inertial Modules or Traffix Sand Barrels manufactured after March 31, 1997, or equal:

- A. Energite III Inertial Modules, manufactured by Energy Absorption Systems, Inc., One East Wacker Drive, Chicago, IL 60601-2076, Telephone 1-312-467-6750, FAX 1-800-770-6755.
 - 1. Distributor (Northern): Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828, Telephone 1-800-884-8274, FAX 1-916-387-9734
 - 2. Distributor (Southern): Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, CA 92805, Telephone 1-800-222-8274, FAX 1-714-937-1070.

- B. Fitch Inertial Modules, manufactured by Roadway Safety Service, Inc., 1050 North Rand Road, Wauconda, IL 60084, Telephone 1-800-426-0839, FAX 1-847-487-9820.
 - 1.. Distributor (Northern): Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828, Telephone 1-800-884-8274, FAX 1-916-387-9734
 - 2. Distributor (Southern): Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, CA 92805, Telephone 1-800-222-8274, FAX 1-714-937-1070.
- C. Traffix Sand Barrels, manufactured by Traffix Devices, Inc., 220 Calle Pintoresco, San Clemente, CA 92672, Telephone 1-949-361-5663, FAX 1-949-361-9205.
 - 1. Russ Enterprises, Inc., 1533 Berger Drive, San Jose, CA 95112, Telephone 1-408-287-4303, FAX 1-408-287-1929.
 - 2. Statewide Safety, P.O. Box 1440, Pismo Beach, CA 93448, Telephone 1-800-559-7080, FAX 1-805-929-5786.

Modules contained in each temporary crash cushion shall be of the same type at each location. The color of the modules shall be the standard yellow color, as furnished by the vendor, with black lids. The modules shall exhibit good workmanship free from structural flaws and objectionable surface defects. The modules need not be new. Good used undamaged modules conforming to color and quality of the types specified herein may be utilized. If used Fitch modules requiring a seal are furnished, the top edge of the seal shall be securely fastened to the wall of the module by a continuous strip of heavy duty tape.

Modules shall be filled with sand in conformance with the manufacturer's directions, and to the sand capacity in kilograms for each module shown on the plans. Sand for filling the modules shall be clean washed concrete sand of commercial quality. At the time of placing in the modules, the sand shall contain not more than 7 percent water as determined by California Test 226.

Modules damaged due to the Contractor's operations shall be repaired immediately by the Contractor at the Contractor's expense. Modules damaged beyond repair, as determined by the Engineer, due to the Contractor's operations shall be removed and replaced by the Contractor at the Contractor's expense.

INSTALLATION

Temporary crash cushion modules shall be placed on movable pallets or frames conforming to the dimensions shown on the plans. The pallets or frames shall provide a full bearing base beneath the modules. The modules and supporting pallets or frames shall not be moved by sliding or skidding along the pavement or bridge deck.

A Type R or P marker panel shall be attached to the front of the crash cushion as shown on the plans, when the closest point of the crash cushion array is within 3.6 m of the traveled way. The marker panel, when required, shall be firmly fastened to the crash cushion with commercial quality hardware or by other methods determined by the Engineer.

At the completion of the project, temporary crash cushion modules, sand filling, pallets or frames, and marker panels shall become the property of the Contractor and shall be removed from the site of the work. Temporary crash cushion modules shall not be installed in the permanent work.

MEASUREMENT AND PAYMENT

Temporary crash cushion modules placed in conformance with the provisions in "Public Safety" of these special provisions will not be measured nor paid for.

10-1.07 AGGREGATE BASE

Aggregate base shall be Class 2 and shall conform to the provisions in Section 26, "Aggregate Bases," of the Standard Specifications.

10-1.08 ASPHALT CONCRETE

Asphalt concrete shall be Type B and shall conform to the provisions in Section 39, "Asphalt Concrete," of the Standard Specifications and these special provisions.

Asphalt concrete shall be produced from commercial quality asphalt and aggregates. The spreading and compacting provisions in Section 39-6.02, "Spreading," and Section 39-6.03, "Compacting," of the Standard Specifications will not apply.

The asphalt concrete shall conform to the following requirements:

- A. Asphalt concrete shall be produced at a central mixing plant.
- B. Aggregate shall conform to the 12.5 mm, Maximum, coarse grading conforming to the provisions in Section 39-2.02, "Aggregate," of the Standard Specifications.
- C. The amount of asphalt binder to be mixed with the aggregate shall be between 4 percent and 7 percent by mass of the dry aggregate as determined by the Engineer. The fifth through eighth paragraphs in Section 39-3.03, "Proportioning," of the Standard Specifications shall not apply.
- D. Asphalt concrete shall be spread in one operation with a self-propelled spreader ready for compaction without further shaping.
- E. Compaction shall be performed with a tandem roller weighing not less than 7.2 tonnes.
- F. The finished surface shall meet the straightedge provisions in Section 39-6.03, "Compacting," of the Standard Specifications.

Where a portion of the existing surfacing is to be removed, the outline of the area to be removed shall be cut on a neat line with a power-driven saw to a minimum depth of 50 mm before removing the surfacing. Full compensation for cutting the existing surfacing shall be considered as included in the contract price paid per tonne of asphalt concrete (type B) and no additional compensation will be allowed therefor.

Removed or damaged painted traffic stripes and pavement markers shall be replaced in conformance with the requirements specified under "Paint Traffic Stripe" and "Pavement Markers" of these special provisions.

10-1.09 PAINT TRAFFIC STRIPE

Painted traffic stripes shall be applied in conformance with the provisions in Section 84, "Traffic Stripes and Pavement Markings," of the Standard Specifications and these special provisions.

Full compensation for replacing painted traffic stripes shall be considered as included in the contract price paid per tonne for asphalt concrete (type B) and no separate payment will be made therefor.

10-1.10 PAVEMENT MARKERS

Pavement markers shall be placed in conformance with the provisions in Section 85, "Pavement Markers," of the Standard Specifications and these special provisions.

Attention is directed to "Traffic Control System For Lane Closure" of these special provisions regarding the use of moving lane closures during placement of pavement markers with bituminous adhesive.

Full compensation for replacing pavement markers shall be considered as included in the contract price paid per tonne for asphalt concrete and no separate payment will be made therefor.

SECTION 10-2. (BLANK)

SECTION 10-3. (BLANK)

SECTION 10-4. CITY OF MADERA SEWER

10-4.01 SEWER PLASTIC PIPE (300 MM PIPE)

Sewer plastic pipe shall be installed at the locations shown on the plans. and these special provisions.

MATERIALS.--Plastic pipe shall be polyvinyl chloride (PVC) pipe SDR 35 shall conform to ASTM Designation: D 3034.

Sewer plastic pipe shall be accompanied with a Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance" of the Standard Specifications.

JOINTS.--Plastic pipe joints shall be water tight and shall be made in accordance with the pipe manufacturer's recommendations.

EARTHWORK.—Excavation, backfill, and pipe bedding shall conform to the provisions shown on the plans.

Surplus excavated material shall become the property of the Contractor and shall be disposed of outside the right of way.

INSTALLATION.--Plastic pipe shall be installed as shown on the plans. Sewer pipe shall be connected to an existing sewer line, as shown on the plans. Provide sewer pipe stub with plug. Asphalt concrete pavement chunks shall not be use as backfilling material.

MEASUREMENT AND PAYMENT.—

The length of sewer pipe to be paid for will be the slope length designated by the Engineer. Pipe placed in excess of the length designated will not be paid for.

The contract price paid per meter for 300 mm polyvinyl chloride (PVC) sewer pipe shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing PVC sewer pipe, complete in place, including hardware, wye branch connection, connecting to existing sewer line at the manhole, providing stub with plug, shoring, excavating, backfilling, compacting, removing and disposing surplus excavated materials outside the right of way, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-4.02 SEWER MANHOLE AND COVER

Manhole.--

Manhole sections and cones and grade rings shall be precast, reinforced concrete, conforming to ASTM Designation: C 478-72 or precast reinforced concrete pipe conforming to ASTM Designation: C 76.

Manhole frame and cover.--

Manhole frame and cover shall be gray cast iron as shown on the plans. Cover shall be no bolt, and shall be factory marked "SEWER." The bearing surfaces of frames and covers shall be machined, and the cover shall seat firmly into the frame without rocking or sliding. Gray iron castings shall be true to pattern in form, dimensions and thickness; shall be free of surface defects; and shall be free from visible, x-ray, and machine operation defects which would affect the service value of the castings. Castings shall be matched sets in appearance, and lettering and sizing as shown on the plans.

Concrete collar and concrete base shall be constructed as shown on the plans and shall conform to the provisions of Section 90-10 "Minor Concrete" of the Standard Specifications.

Full compensation for concrete collar and concrete base shall be considered as included in the contract unit price paid for 1200 mm precast concrete pipe sewer manhole and no additional compensation will be allowed therefor.

The contract unit price paid for each complete 1200 mm precast concrete pipe sewer manhole shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing manhole, grade rings, manhole frame and cover, including constructing concrete collar and concrete base, complete in place, as specified in the Standard Specifications and these special provisions and as directed by the Engineer.

SECTION 11. (BLANK)

SECTION 12. BUILDING WORK

SECTION 12-1. GENERAL REQUIREMENTS

12-1.01 SCOPE

Building work described herein and as shown on the plans shall conform to the requirements of these special provisions and Sections 1 through 9 of the Standard Specifications. Sections 10 through 95 of the Standard Specifications shall not apply to the work in this Section 12 except when specific reference is made thereto.

The building work to be done consists, in general, of construct wash rack, install oil/water separator, modify sewer system and such other items or details, not mentioned above, that are required by the plans, Standard Specifications, or these special provisions shall be performed, placed, constructed or installed.

12-1.02 ABBREVIATIONS

Section 1-1.02, "Abbreviations," of the Standard Specifications is amended by adding the following:

AAMA	American Architectural Manufacturers' Association
ACI	American Concrete Institute
AGA	American Gas Association
AITC	American Institute of Timber Construction
AMCA	Air Movement and Control Association
APA	American Plywood Association
ARI	American Refrigeration Institute
ASHRAE	American Society of Heating, Refrigeration and Air Conditioning Engineers
CS	Commercial Standards (US Department of Commerce)
ESO	Electrical Safety Orders
FGMA	Flat Glass Marketing Association
FM	Factory Mutual
FS	Federal Specification
ICBO	International Conference of Building Officials
NAAMM	National Association of Architectural Metal Manufacturers
NBFU	National Board Fire Underwriters
NEC	National Electrical Code
NFPA	National Fire Protection Association
PEI	Porcelain Enamel Institute
PS	Product Standard (US Department of Commerce)
RIS	Redwood Inspection Service
SCPI	Structural Clay Products Institute
SMACNA	Sheet Metal and Air Conditioning Contractors' National Association
SSPC	Steel Structures Paint Council
TCA	Tile Council of America
TPI	Truss Plate Institute
UBC	Uniform Building Code
UL	Underwriters Laboratories, Inc.
WCLIB	West Coast Lumber Inspection Bureau (stamped WCLB)
WCLB	Grade stamp for WCLIB
WIC	Woodwork Institute of California
WWPA	Western Wood Products' Association

When reference is made to the Uniform Building Code (UBC) on the plans or in the special provisions, it shall be the 1997 Uniform Building Code as amended by the 1998 Title 24 California Building Standards Code.

12-1.03 GUARANTEE

The Contractor hereby unconditionally guarantees that the building work will be done in accordance with the requirements of the contract, and further guarantees the building work of the contract to be and remain free of defects in workmanship and materials for a period of one year from the date of acceptance of the contract, unless a longer guarantee period is required elsewhere in these special provisions. The Contractor hereby agrees to repair or replace any and all building work, together with any other adjacent work which may be displaced in so doing, that may prove to be not in accordance with the requirements of the contract or that may be defective in its workmanship or material within the guarantee period specified, without any expense whatsoever to the Department, ordinary wear and tear and unusual abuse or neglect excepted.

The performance bond for the contract, or a portion thereof, in the sum equal to one-half the contract price of the building work, shall remain in full force and effect during the guarantee period.

The Contractor further agrees, that within 10 calendar days after being notified in writing by the Department of any building work not in accordance with the requirements of the contract or any defects in the building work, he shall commence and prosecute with due diligence all work necessary to fulfill the terms of this guarantee, and shall complete the work within a reasonable period of time, and, in the event he fails to comply, he does hereby authorize the Department to proceed to have such work done at the Contractor's expense and he shall honor and pay the cost and charges therefor upon demand. The Department shall be entitled to all costs and expenses, including reasonable attorney's fees, necessarily incurred upon the Contractor's refusal to honor and pay the above costs and charges.

12-1.04 SUBMITTALS

Working drawings, material lists, descriptive data, samples and other submittals specified in these special provisions shall be submitted for approval in accordance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications and these special provisions.

Unless otherwise permitted in writing by the Engineer, all submittals required by these special provisions shall be submitted within 35 days after the contract has been approved.

Attention is directed to the provisions in Section 5-1.01, "Authority of Engineer," of the Standard Specifications. The Engineer may request submittals for materials or products where submittals have not been specified in these special provisions, or may request that additional information be included in specified submittals, as necessary to determine the quality or acceptability of such materials or products.

Attention is directed to Section 6-1.05, "Trade Names and Alternatives," of the Standard Specifications. The second indented paragraph of the first paragraph of said Section 6-1.05 is amended to read:

Whenever the specifications permit the substitution of a similar or equivalent material or article, no test or action relating to the approval of such substituted material will be made until the request for substitution is made in writing by the Contractor accompanied by complete data as to the equality of the material or article proposed. Such request shall be made within 35 days after the date the contract has been approved and in ample time to permit approval without delaying the work, but need not be made in less than 35 days after award of the contract.

Work requiring the submittal of working drawings, material lists, descriptive data, samples, or other submittals shall not begin prior to approval of said submittal by the Engineer. Fifteen working days shall be allowed for approval or return for correction of each submittal or resubmittal. Should the Engineer fail to complete his review within the time specified and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in review, an extension of time commensurate with the delay in completion of the work thus caused will be granted as provided in Section 8-1.07, "Liquidated Damages," of the Standard Specifications.

Submittals shall be delivered to the locations indicated in these special provisions. If a specific location is not indicated, the submittal shall be delivered to the Office of Structure Design, Documents Unit, Fourth Floor, Mail Station 9, 1801 30th Street, Sacramento, California 95816, telephone (916) 227-8252, or the submittals shall be mailed to the Office of Structure Design, Documents Unit, Mail Station 9, P. O. Box 942874, Sacramento, California 94274-0001.

Each submission of drawings, material lists and descriptive data shall consist of at least 5 copies. Two copies will be returned to the Contractor either approved for use or returned for correction and resubmittal.

Each separate item submitted shall bear a descriptive title, the name of the project, district, county, and contract number. Plans and detailed drawings shall be not larger than 559 mm x 914 mm.

The material list shall be complete as to name of manufacturer, catalog number, size, capacity, finish, all pertinent ratings, and identification symbols used on the plans and in the special provisions for each unit.

Parts lists and service instructions packaged with or accompanying the equipment installed in the work shall be delivered to the Engineer at the jobsite. Required operating and maintenance instructions shall be submitted in triplicate.

Manufacturer's warranties for products installed in the work shall be delivered to the Engineer at the jobsite.

Unapproved samples and samples not incorporated in the work shall be removed from State property, when directed by the Engineer.

12-1.05 PROGRESS SCHEDULE

A progress schedule shall be submitted in duplicate for the building work in accordance with the requirements in Section 8-1.04, "Progress Schedule," of the Standard Specifications.

12-1.06 SCHEDULE OF VALUES

The Contractor shall prepare and submit to the Engineer 2 copies of a Schedule of Values covering each lump sum item for building work. The Schedule of Values, showing the value of each kind of work, shall be acceptable to the Engineer before any partial payment estimate is prepared.

The sum of the items listed in the Schedule of Values shall equal the contract lump sum price for building work. Overhead, profit, bond premium, temporary construction facilities, and plant shall not be listed.

12-1.07 INSPECTION

All items covered or all stages of work that are not to remain observable must be inspected and approved before progress of work conceals portions to be inspected. The Contractor shall notify the Engineer not less than 72 hours in advance of when such inspection is needed.

12-1.08 UTILITY CONNECTION

The Contractor shall make all arrangements, and obtain all permits and licenses required for the extension of and connection to each utility service applicable to this project, shall furnish all labor and materials necessary for such extensions which are not performed or provided by the utility, and shall furnish and install any intermediate equipment required by the serving utilities.

Upon written request by the Contractor, the State will pay all utility permits, licenses, connection charges, and excess length charges directly to the utility. Such request shall be submitted not less than 15 days before service connections are required.

The costs incurred by the Contractor for the extensions of utilities beyond the limits shown on the plans, and in furnishing and installing any intermediate equipment required by the serving utilities, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Full compensation for any costs incurred by the Contractor to obtain the permits and licenses shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

12-1.09 TEMPORARY UTILITIES

The Contractor may obtain electrical power and water from existing State electrical power and water outlets within the contract limits free of charge for contract operations where such utilities exist, provided that such utility services are in service and are not required by the State for other purposes and subject to the provisions in the section "Cooperation" of these special provisions.

The Contractor shall make his own arrangements to obtain any additional electrical power and water or other utilities required for his operations and shall make and maintain the necessary service connections at his own expense.

When existing utility systems are being modified, periods of shutdown will be determined by the Engineer.

The Contractor shall provide adequate temporary lighting to perform the work and allow the Engineer to inspect the project as each portion is completed.

The Contractor shall provide and pay for telephone service he may require. State telephone facilities shall not be used.

12-1.10 SANITARY FACILITIES

State sanitary facilities will not be available for use by the Contractor's employees. Tools shall not be cleaned nor shall cleaning liquids be disposed of in State sanitary facilities or sewers.

12-1.11 MEASUREMENT AND PAYMENT

The contract lump sum price paid for building work shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the building work, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for any incidental materials and labor, not shown on the plans or specified, which are necessary to complete the buildings and appurtenances shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

12-1.12 FIELD ENGINEERING

This section specifies administrative and procedural requirements for field engineering services to be performed by the Contractor.

Lines and grades.--Attention is directed to Section 5-1.07 "Lines and Grades," of the Standard Specifications.

Such stakes or marks will be set by the Engineer as he determines to be necessary to establish the lines and grades required for the completion of the work shown on the plans and as specified in these special provisions. In general, these will consist of the primary vertical and horizontal control points.

Stakes and marks set by the Engineer shall be carefully preserved by the Contractor. In case such stakes and marks are destroyed or damaged they will be replaced at the Engineer's earliest convenience. The Contractor will be charged for the cost of necessary replacement or restoration of such stakes and marks which in the judgment of the Engineer were carelessly or willfully destroyed or damaged by the Contractor's operations. This charge will be deducted from any moneys due or to become due the Contractor.

All other stakes or marks required to establish the lines and grades required for the completion of the work shall be the responsibility of the Contractor.

Existing utilities and equipment.--The existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning sitework, the Contractor shall investigate and verify the existence and location of underground utilities and other construction.

Prior to construction, the Contractor shall verify the location and invert elevation at points of connection of sanitary and septic sewers, storm sewer, and water or fire service piping.

Surveys for layout and performance.--The Contractor shall perform all surveys for layout and performance, reduce field notes, and make all necessary calculations and drawings necessary to carry out the work.

The Contractor shall locate and layout site improvements, and other work requiring field engineering services, including pavements, stakes for grading, fill and topsoil placement, utility slopes and invert elevations by instrumentation and similar appropriate means.

Batter boards shall be located and laid out for structures, building foundations, column grids and locations, floor levels and, control lines and levels required for mechanical and electrical work.

Survey accuracy and tolerances.--The tolerances generally applicable in setting survey stakes for foundations, slabs, and underground work shall not exceed the following:

Survey Stakes or Markers	Tolerance
Rough grading or excavation	30 mm
Trimming or preparation of subgrade for roadways	15 mm
Roadway surfacing, steel or concrete pipe	6 mm
Structures or building construction	3 mm

Such tolerance shall not supersede stricter tolerances required by the plans or special provisions, and shall not otherwise relieve the Contractor of responsibility for measurements in compliance therein.

12-1.13 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS

Only materials and products conforming to the requirements of the specifications shall be incorporated in the work. When metric materials and products are not available, and when approved by the Engineer, and at no cost to the State, materials and products in the inch-pound (imperial) system which are of equal quality and of the required properties and characteristics for the purpose intended, may be substituted for the equivalent metric materials and products, subject to the following requirements:

Materials and products shown on the plans or in the special provisions as being equivalent may be substituted for the metric materials and products specified or detailed on the plans.

Before other non-metric materials and products will be considered for use the Contractor shall furnish, at the Contractor's expense, evidence satisfactory to the Engineer that the materials and products proposed for use are equal to or better than the materials and products specified or detailed on the plans. The burden of proof as to the quality and suitability of substitutions shall be upon the Contractor and the Contractor shall furnish all information necessary as required to the Engineer. The Engineer will be the sole judge as to the quality and suitability of the substituted materials and products and the Engineer's decision shall be final.

When the Contractor elects to substitute non-metric materials and products, including materials and products shown on the plans or in the special provisions as being equivalent, a list of substitutions to be made shall be submitted for approval.

The following substitutions of materials and products will be allowed:

SUBSTITUTION TABLE FOR SIZES OF HIGH STRENGTH STEEL FASTENERS, ASTM Designation: A 325M	
METRIC SIZE SHOWN ON THE PLANS mm x thread pitch	IMPERIAL SIZE TO BE SUBSTITUTED inch
M16 x 2	5/8
M20 x 2.5	3/4
M22 x 2.5	7/8
M24 x 3	1
M27 x 3	1-1/8
M30 x 3.5	1-1/4
M36 x 4	1-1/2

SUBSTITUTION TABLE FOR REINFORCEMENT	
METRIC BAR DESIGNATION NUMBER AS SHOWN ON THE PLANS	IMPERIAL BAR DESIGNATION NUMBER TO BE SUBSTITUTED
10	3
13	4
16	5
19	6
22	7
25	8
29	9
32	10
36	11
43	14
57	18

SUBSTITUTION TABLE FOR WELDED PLAIN WIRE REINFORCEMENT, ASTM DESIGNATION: A 185	
	US CUSTOMARY UNITS SIZE TO BE SUBSTITUTED inch ² x 100
MW9	W1.4
MW10	W1.6
MW13	W2.0
MW15	W2.3
MW19	W2.9
MW20	W3.1
MW22	W3.5
MW25	W3.9, except W3.5 in piles only
MW26	W4.0
MW30	W4.7
MW32	W5.0

MW35	W5.4
MW40	W6.2
MW45	W6.5
MW50	W7.8
MW55	W8.5, except W8.0 in piles only
MW60	W9.3
MW70	W10.9, except W11.0 in piles only
MW80	W12.4
MW90	W14.0
MW100	W15.5

The sizes in the following tables of materials and products are exact conversions of metric sizes of materials and products and are listed as acceptable equivalents:

CONVERSION TABLE FOR SIZES OF: (1) STEEL FASTENERS FOR GENERAL APPLICATIONS, ASTM Designation: A 307 or AASHTO Designation: M 314, Grade 36 or 55, and (2) HIGH STRENGTH STEEL FASTENERS, ASTM Designation: A 325 or A 449 DIAMETER	
METRIC SIZE SHOWN ON THE PLANS mm	EQUIVALENT IMPERIAL SIZE inch
6, or 6.35	1/4
8 or 7.94	5/16
10, or 9.52	3/8
11, or 11.11	7/16
13 or 12.70	1/2
14, or 14.29	9/16
16, or 15.88	5/8
19, or 19.05	3/4
22, or 22.22	7/8
24, 25, or 25.40	1
29, or 28.58	1-1/8
32, or 31.75	1-1/4
35, or 34.93	1-3/8
38 or 38.10	1-1/2
44, or 44.45	1-3/4
51, or 50.80	2
57, or 57.15	2-1/4
64, or 63.50	2-1/2
70 or 69.85	2-3/4
76, or 76.20	3
83, or 82.55	3-1/4
89 or 88.90	3-1/2
95, or 95.25	3-3/4
102, or 101.60	4

CONVERSION TABLE FOR NOMINAL THICKNESS OF SHEET METAL			
UNCOATED HOT AND COLD ROLLED SHEETS		HOT-DIPPED ZINC COATED (GALVANIZED) SHEETS	
METRIC THICK- NESS SHOWN ON THE PLANS mm	EQUIVA- LENT US STAND- ARD GAGE inch	METRIC THICK- NESS SHOWN ON THE PLANS mm	EQUIVA- LENT GALVAN- IZED SHEET GAGE inch
7.94	0.3125		
6.07	0.2391		
5.69	0.2242		
5.31	0.2092		
4.94	0.1943		
4.55	0.1793		
4.18	0.1644	4.270	0.1681
3.80	0.1495	3.891	0.1532
3.42	0.1345	3.510	0.1382
3.04	0.1196	3.132	0.1233
2.66	0.1046	2.753	0.1084
2.28	0.0897	2.372	0.0934
1.90	0.0747	1.994	0.0785
1.71	0.0673	1.803	0.0710
1.52	0.0598	1.613	0.0635
1.37	0.0538	1.461	0.0575
1.21	0.0478	1.311	0.0516
1.06	0.0418	1.158	0.0456
0.91	0.0359	1.006 or 1.016	0.0396
0.84	0.0329	0.930	0.0366
0.76	0.0299	0.853	0.0336
0.68	0.0269	0.777	0.0306
0.61	0.0239	0.701	0.0276
0.53	0.0209	0.627	0.0247
0.45	0.0179	0.551	0.0217
0.42	0.0164	0.513	0.0202
0.38	0.0149	0.475	0.0187

CONVERSION TABLE FOR WIRE		
METRIC THICKNESS SHOWN ON THE PLANS	EQUIVALENT USA STEEL WIRE THICKNESS	GAGE NO.
mm	inch	
6.20	0.244	3
5.72	0.225	4
5.26	0.207	5
4.88	0.192	6
4.50	0.177	7
4.11	0.162	8
3.76	0.148	9
3.43	0.135	10
3.05	0.120	11
2.69	0.106	12
2.34	0.092	13
2.03	0.080	14
1.83	0.072	15
1.57	0.062	16
1.37	0.054	17
1.22	0.048	18
1.04	0.041	19
0.89	0.035	20

CONVERSION TABLE FOR COMMON NAILS				
NAIL SIZE	METRIC		ENGLISH	
	mm		inch	
	Length	Diameter	Length	Diameter
8d	63.5	3.33	2 1/2	0.131
10d	76.2	3.76	3	0.148
16d	88.9	4.11	3 1/2	0.162

CONVERSION TABLE FOR LUMBER	
METRIC NOMINAL SURFACE DRY SIZE	EQUIVALENT NOMINAL SURFACE DRY U S SIZE
mm	inch
51	2
102	4
152	6
203	8
254	10
305	12

CONVERSION TABLE FOR PLYWOOD	
METRIC mm	ENGLISH inch
6.4	1/4
7.9	5/16
9.5	3/8
11.1	7/16
11.9	15/32
12.7	1/2
15.1	19/32
15.9	5/8
18.3	23/32
19.1	3/4
22.2	7/8
25.4	1
28.6	1 1/8

CONVERSION TABLE FOR INSULATION R-VALUE	
METRIC (m ² K/W)	ENGLISH (HR FT ² F/BTU)
0.5	3
0.7	4
1.4	8
1.9	11
2.3	13
2.5	14
3.3	19
5.3	30

CONVERSION TABLE FOR VAPOR TRANSMISSION RATING	
METRIC (Perm-m)	ENGLISH (perm-inch)
0.29	0.02

CONVERSION TABLE FOR LOW PRESSURE	
METRIC (Pa)	ENGLISH (Inches of Water Column)
30	0.125
60	0.25
90	0.375
120	0.50
150	0.60
155	0.625
175	0.70
185	0.75
200	0.80
250	1.00
310	1.25

CONVERSION TABLE FOR PRESSURE	
METRIC (kPa)	ENGLISH (psi)
10	1.5
210	30
280	40
350	50
690	100
860	125
1040	150
1100	160
1210	175
1380	200
1730	250
2070	300
2170	315
2410	350
2590	375
2760	400
4830	700
5170	750
5520	800
13800	2000
17200	2500
20700	3000
27600	4000
34500	5000
137900	20000

CONVERSION TABLE FOR MIL THICKNESS	
METRIC (mm)	ENGLISH (inch/1000)
0.10	4
0.10	5
0.50	20
0.75	30
1.00	40

CONVERSION TABLE FOR HVAC DUCTING.	
METRIC (mm)	ENGLISH (inch)
100	4
125	5
150	6
175	7
200	8
225	9
250	10
300	12
360	14
410	16
460	18
510	20
560	22
610	24
660	26
710	28
760	30

CONVERSION TABLE FOR MECHANICAL PIPING		
METRIC (GSP, PVC, BSP, DUCTILE IRON)	METRIC (mm)	ENGLISH (inch)
NPS 1/2	15	1/2
NPS 3/4	20	3/4
NPS 1	25	1
NPS 1 1/4	32	1 1/4
NPS 1 1/2	40	1 1/2
NPS 2	50	2
NPS 2 1/2	65	2 1/2
NPS 3	75	3
NPS 4	100	4
NPS 6	150	6

CONVERSION TABLE FOR LUBRICATION PIPING TUBING WALL THICKNESS	
METRIC (mm)	ENGLISH (inch)
2.1	0.083
0.9	0.035

CONVERSION TABLE FOR HOSE/TUBING SIZES O. D.	
METRIC (mm)	ENGLISH (inch)
6	1/4
10	3/8
13	1/2
16	5/8
19	3/4
22	7/8
25	1

CONVERSION TABLE FOR DRUM SIZES			
METRIC		ENGLISH	
L	kg	gallons	pounds
205	180	55	400
60	55	16	120
19	16	5	35

CONVERSION TABLE FOR POWER	
METRIC (kW)	ENGLISH (HP)
0.037	1/20
0.075	1/10
0.18	1/4
0.25	1/3
0.37	1/2
0.55	3/4
0.75	1
1.1	1 1/2
1.5	2
2.2	3
3.7	5
5.5	7 1/2
7.5	10
11	15
15	20
18.5	25
22	30
30	40
37	50
45	60
55	75
75	100
90	120
110	150

CONVERSION TABLE FOR IMPELLER BALANCE		
SYNCHRONOUS RPM	METRIC (g mm/kg)	ENGLISH (ounce- inch/pound)
720	94	0.059
900	73	0.046
1200	54	0.034
1800	41	0.026
3600	17	0.011

CONVERSION TABLE FOR ELECTRICAL CONDUIT	
METRIC SIZE SHOWN ON THE PLANS mm	EQUIVALENT IMPERIAL SIZE inch
16	1/2
21	3/4
27	1
35	1 1/4
41	1 1/2
53	2
103	4

SECTION 12-2. SITEWORK

12-2.01 REMOVING PORTIONS OF EXISTING FACILITIES

PART 1.- GENERAL

Scope.--This work shall consist of removing portions of the existing facilities, including removal of existing work to gain access to or for new work, in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS (Not applicable)

PART 3.- EXECUTION

PREPARATION.--

General.--The limits of removal shall be located and identified. Items to be removed and the interface of items to be removed and items to remain intact shall be identified and marked.

Prior to removing concrete or asphalt concrete , a saw cut approximately 25 mm deep shall be made along the limits of removal on all faces that will be visible in the completed work.

REMOVAL.--

General.--Removal shall be to the limits shown on the plans. Removal shall be done carefully to minimize damage to the portions to remain. Remaining portions that are damaged by the Contractor's operation shall be restored to original condition at the Contractor's expense.

Existing apparatuses, devices, or accessories which would be functionally impaired by new construction or remodeling shall be moved, brought out to new surfaces, or provided with new access covers, as necessary to restore apparatuses, devices, or accessories to their original usefulness.

Piping and conduits to be abandoned shall be capped or plugged.

Surfaces that are exposed to view at the limits of removal work shall be patched, bumps shall be removed and depressions filled, and the surface shall be finished to match the existing surrounding surfaces. Depressions in concrete less than 25 mm deep shall be deepened to 25 mm minimum depth before filling with cement mortar.

Anchor bolts and reinforcement shall be removed at least 25 mm below the surrounding surfaces, and the resulting hole shall be patched with cement mortar.

Existing reinforcement that is to be incorporated into the new work shall be protected from damage and thoroughly cleaned before being embedded in new concrete.

DISPOSAL.--

General.--Materials that are to be removed, shall become the property of the Contractor and shall be disposed of outside the highway right of way in accordance with the requirements in Section 7-1.13, "Disposal of Material Outside of the Highway Right of Way," of the Standard Specifications.

12-2.02 RELOCATING MATERIALS AND EQUIPMENT

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of relocating existing materials and equipment in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS (Not applicable)

PART 3.- EXECUTION

RELOCATION.--

General.--Materials or equipment to be relocated shall be removed carefully to avoid damage to the materials or equipment or to the materials or equipment which are to remain. Assemblies to be relocated which require dismantling for removal shall be matchmarked before dismantling.

The Contractor shall notify the Engineer prior to the relocation work in order that the materials or equipment may be inspected for existing damage.

Materials or equipment to be relocated shall have all adhering concrete, mastics, earth or other deleterious materials removed and shall have all exterior surfaces cleaned.

Materials or equipment which are damaged by the Contractor's operations shall be replaced or restored to match the condition of the materials or equipment prior to the beginning of the Contractor's operations. Replacement or restoration of damaged materials or equipment shall be at the Contractor's expense.

Connections, anchorages and fasteners for relocated materials and equipment shall match existing and shall be furnished and installed by the Contractor. Assemblies which have been dismantled shall be reassembled to match the existing installation. Relocated materials and equipment shall be installed as required for new work.

Modifications to wiring and plumbing to accommodate relocated items shall be as shown on the plans. Ends of piping and conduits to be abandoned shall be capped.

Surfaces that are exposed to view upon removal or relocation of materials or equipment shall be patched. Bumps shall be removed and depressions filled, and the surface finished to match the existing surfaces. Depressions in concrete less than 25 mm deep shall be deepened to 25 mm minimum depth before filling with cement mortar.

DISPOSAL.--

General.--Materials from existing facilities to be reused in the work, in the opinion of the Engineer, is unsuitable for use shall become the property of the Contractor and disposed of as provided in Section 7-1.13, "Disposal of Material Outside of the Highway Right of Way," of the Standard Specifications. The unsuitable material shall be replaced as ordered by the Engineer and will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

12-2.03 ABANDON PORTIONS OF WASTE DISPOSAL SYSTEM

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of abandoning portions of the existing waste disposal system in accordance with the details shown on the plans and these special provisions.

Codes and standards.--Attention is directed to Section 7-1.01, "Laws to be Observed," of the Standard Specifications.

PART 2.- PRODUCTS (Not applicable)

PART 3.- EXECUTION

Staging of work.--Work that will curtail the use of the waste disposal system shall not be done until the facilities utilizing the system are closed and are no longer required.

Disposal.--Sewage facilities to be abandoned shall be pumped out and the sewage and sediment removed from such facilities shall be disposed of away from the premises. Disposal shall conform to the laws, rules and regulations of the agency having jurisdiction of the disposal site.

Abandoning facilities.--Each pipe entering or exiting the sewage disposal system to be abandoned shall be closed by a tight fitting plug or wall of concrete not less than 150 mm thick. Such concrete shall be commercial quality concrete and shall contain not less than 300 kilograms of cement per cubic meter of concrete.

The top cover of the structure shall be removed and the bases shall be broken to prevent entrapment of water. The sewage structures to be abandoned shall be backfilled with sand, unless otherwise shown on the plans. Sand backfill shall be consolidated by vibrating or other methods.

Manhole frames and covers.--Manhole frames and covers which are to be removed shall become the property of the Contractor and disposed of away from the premises. Such disposal shall conform to the laws, rules, and regulations of all agencies having jurisdiction at the disposal site.

12-2.04 EARTHWORK FOR BUILDING WORK

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of performing earthwork for building work in accordance with the details shown on the plans and these special provisions.

Earthwork for building work shall consist of excavation for footings, foundations, slabs, lift station; filling under slabs; backfilling; trenching and backfilling for pipes and conduits; backfilling holes resulting from removal of existing facilities; and any other earthwork, not mentioned, but necessary to complete the building work.

Attention is directed to the requirements of "Field Engineering" in Section 12-1, "General Requirements," of these special provisions.

QUALITY ASSURANCE.--

Samples.--Samples of sand and pea gravel, weighing not less than 11 kg, shall be submitted to the Engineer at the jobsite for approval.

SITE CONDITIONS.--

Existing underground piping and conduit.--The location of existing underground piping and conduit is based on the best records available. Before beginning work, the Contractor shall accurately locate the piping and conduit involved in the work. If the location of the existing piping or conduit deviates from the location shown on the plans by more than 1.5 meters, or, if no elevations are indicated and the piping or conduit is more than 0.9 meter below grade, the cost of the additional excavation, backfill, piping or conduit, and removal and replacement of concrete, if any, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Existing surfaced or planted areas.--Existing surfaced or planted areas that are removed, broken or damaged by the Contractor's operations shall be restored to their original condition except as otherwise shown on the plans or specified herein. Restoration materials shall be equal to or better than the original materials.

PART 2.- PRODUCTS

BACKFILL MATERIALS.--

Structure backfill.--

Structure and trench backfill shall be free of organic and other deleterious material and shall be suitable for the required compaction. Gravel without sand matrix shall not be used except as free draining granular material beneath slabs and footings.

Sand.--

Sand shall be clean, washed sand, free from clay or organic material graded such that 100 percent passes the 6 mm sieve, 90 percent to 100 percent passes the 4.75 mm sieve and not more than 5 percent passes the 75 μ m sieve size.

Pea gravel (naturally rounded).--

Pea gravel (naturally rounded) shall be clean, washed, dry density of not less than 1522 kg/m³, free from clay or organic material and shall conform to the following grading as determined by California Test 202:

Sieve or Screen Size	Percentage Passing
19 mm	100
13 mm	90-100
9.5 mm	40-70
4.75 mm	0-15
2.36 mm	0-3

Pea gravel shall conform to the following requirements:

Test	California Test No.	Test Requirements
Durability Index	229	35 Min.

PART 3.- EXECUTION

PREPARATION.--

Sawcutting.--Prior to excavation or trenching, existing surfacing shall be removed to saw cut lines, or to existing wood dividers or expansion joints, if any. The saw cut shall be to a neat line and have a depth not less than 25 mm. Surfacing shall be replaced to match the thickness, grades and finish of the adjacent surrounding surfaces.

EXCAVATION.--

Footing excavation.--The footing depths shown on the plans shall be changed to suit field conditions when directed by the Engineer. Solid rock at or near required depths shall not be disturbed. Unsuitable material shall be excavated down to firm bearing as directed by the Engineer. Work and materials required because of excavation in excess of the depths shown on the plans, when such excavation has been ordered by the Engineer, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Limits of the excavation shall allow for adequate working space for installing materials and as required for safety of personnel. Such working space excavation shall be replaced in kind and compacted at the Contractor's expense.

Overdepth excavation for footings shall be backfilled with concrete or such other material recommended by the Contractor and approved by the Engineer. Relative compaction shall be not less than 95 percent.

At locations and to the limits shown on the plans, material below the bottom of the foundation or footing shall be removed and replaced with select backfill in accordance with the placing and compacting requirements for backfill.

Excavation for pipes and conduits.--Pipes or conduits in the same trench shall have a minimum clear distance between pipes or conduits of 150 mm. Pipes or conduits shall have not less than 0.75 meter of cover from top of pipes or conduits to finished grade unless otherwise shown on the plans or specified.

Trenching shall be of sufficient depth to permit placing a minimum depth of 100 mm of compacted sand under all pipes and conduits.

Excavation adjacent to trees shall be performed by hand methods where necessary to avoid injury to trees and roots. Roots 50 mm in diameter and larger shall be protected with heavy burlap. Roots smaller than 50 mm in diameter adjacent to trees shall be hand trimmed. Cuts through roots 13 mm in diameter and larger shall be sealed with tree trimmers' asphaltic emulsion. If trenches remain open more than 24 hours, the side of the trench adjacent to the tree shall be shaded with burlap and kept damp. Materials shall not be stockpiled within the drip line of trees.

Dewatering.--Excavations shall be kept clear of standing water. Water shall be removed by pumping if necessary. Water removed from excavation shall be carried away from the building site and disposed of in a manner that will not harm State or adjacent property.

BACKFILLING.--

General.--Backfill shall be placed and compacted in horizontal layers, not more than 150 mm thick prior to compaction, and to the lines and grades shown on the plans or to original ground.

Structure backfill.--After structures are in place and forms are removed, wood and other debris shall be removed from excavations before placing backfill.

Unless approved in writing by the Engineer, compaction of structure backfill by jetting or ponding shall not be permitted.

Backfilling pipes and conduits.--Unless otherwise shown on the plans, backfill placed under pipe and conduits shall be compacted sand, 100 mm minimum depth. Backfill material placed to a level 150 mm above tops of pipes and conduits shall be sand or fine earth and particles shall not exceed 13 mm in greatest dimension. For wrapped, coated, or plastic pipe or conduits, sand shall be used for backfill. Backfill material placed higher than 150 mm above tops of pipes or conduits shall consist of material free of stones or lumps exceeding 100 mm in greatest dimension except:

- (a) The top 300 mm of backfill under roads, walks or paving shall consist of aggregate base material.
- (b) The top 150 mm of backfill in planted areas shall consist of topsoil.

Unless otherwise shown on the plans, pipe under roads, with less than 0.75 m of cover over the top of pipe, shall be backfilled with concrete to a level 100 mm above the top of pipe. Concrete for backfill shall be commercial quality concrete containing not less than 350 kg/m³ of cement.

COMPACTION.--

General.--Relative compaction shall be determined in accordance with California Test 216 or 231.

Unless otherwise noted below, all backfill shall be compacted to a relative compaction of 90 percent.

Compact original ground.--Original ground within 400 mm of the top of concrete slabs and asphalt concrete surfacing shall be compacted to a relative compaction of not less than 95 percent.

Structure backfill.--Structure backfill shall be compacted to a relative compaction of not less than 95 percent.

Trench backfill.--Trench backfill placed beneath slabs or paved areas shall be compacted to a relative compaction of not less than 95 percent.

DISPOSAL.--

Surplus material.--Surplus material from the excavation shall be removed and disposed of outside the right-of-way in accordance with Section 7-1.13 of the Standard Specifications.

FIELD QUALITY CONTROL.--

Inspection.--When the excavation is substantially completed to grade, the Contractor shall notify the Engineer. No concrete shall be placed until the foundation has been approved by the Engineer.

Testing.--The State will conduct compaction tests during the backfilling and compacting operations.

12-2.05 AGGREGATE BASE

PART 1.-GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing, spreading and compacting aggregate base in accordance with the details shown on the plans and these special provisions.

PART 2.-PRODUCTS

Aggregate base.--

Aggregate base shall be commercial quality aggregates consisting of broken stone; crushed gravel; natural, clean, rough-surfaced gravel and sand; or a combination thereof.

Aggregate base shall conform to the following grading as determined by California Test 202:

Sieve or Screen Size	Percentage Passing
25 mm	100
19 mm	90 - 100
4.75 mm	35 - 60
6 µm	10 - 30
75 µm	2 - 9

Aggregate base shall also conform to the following quality requirements:

Tests	California Test No.	Test Requirement s
Durability Index	229	35 Min.
Resistance (R-Value)	301	78 Min.
Sand Equivalent	217	22 Min.

PART 3.-EXECUTION

SPREADING AND COMPACTING.--

Spreading.--Aggregate base shall be placed and compacted to the lines and grades shown on the plans.

Spreading and compacting shall be performed by methods that will produce a uniform base, free from pockets of coarse or fine material.

Compaction.--Relative compaction of each layer of compacted base material shall be not less than 95 percent, as determined by California Test 216 or 231.

12-2.06 FREE DRAINING GRANULAR MATERIAL

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and placing free draining granular material beneath slabs in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS

Free draining granular material.--

Free draining granular material shall be clean, hard, durable, free-draining rock. The material gradation shall be such that all passes the 25 mm screen, and not more than 5 percent passes the 4.75 mm sieve as determined by California Test 202. Granular material shall be free from organic material, clay balls or other deleterious substances.

PART 3.- EXECUTION.--

SPREADING AND CONSOLIDATING.--

General.--Free draining granular material shall be placed, spread and consolidated by tamping or vibrating.

12-2.07 ASPHALT CONCRETE

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing, spreading, placing and compacting asphalt concrete for asphalt concrete surfacing, applying asphaltic emulsion paint binder and fog seal coat, in accordance with the details shown on the plans and these special provisions.

Asphalt concrete shall be commercial quality, produced at a central mixing plant, 13 mm maximum, medium grade, as specified herein.

Areas to be surfaced with asphalt concrete shall be as shown on the plans and shall include those locations where existing bituminous surfacing has been removed to facilitate the required work.

QUALITY ASSURANCE.--

Certificates of Compliance.--Certificates of Compliance shall be furnished for asphalt concrete and asphaltic emulsion in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

PART 2.- PRODUCTS

MATERIALS.--

Asphalts.--

Asphalt binder for asphalt concrete shall be steam-refined paving asphalt Grade AR-4000 (asphalt graded by viscosity), conforming to the requirements in AASHTO Designation: M 226.

Asphalt emulsion for paint binder and fog seal coat shall be asphaltic emulsion Grade SS1h conforming to the requirements in AASHTO Designation: M 140.

Aggregates.--

Aggregate for asphalt concrete shall be commercial quality asphalt concrete aggregate, and shall have a Sand Equivalent value of 30 minimum, when determined by California Test 217.

The combined aggregate gradings for the respective asphalt concrete mixture shall conform to the following gradations when determined by California Test 202:

13 mm Maximum Grading	
Sieve Sizes	Percentage Passing
19 mm	100
13 mm	95 - 100
4.75 mm	55 - 72
600 µm	18 - 33
75 µm	4 - 8

MIXING.--

General.--Asphalt binder to be mixed with the aggregate shall be between 5 percent and 8 percent by weight of the dry aggregate as determined by the Engineer.

PART 3.- EXECUTION

PREPARATION.--

Subgrade.--Immediately prior to placing asphalt concrete thereon, the surface of the grading plane shall not vary more than 0.015 meter above or below the grade established by the Engineer.

At the time of placing the asphalt concrete material thereon, the moisture content of the subgrade shall not be more than 3 percent above or below the optimum moisture content of the subgrade material as determined by California Test 216.

Paint binder.--Paint binder shall be furnished and applied to all existing surfacing upon which asphalt concrete is to be placed, vertical surfaces against which additional asphalt concrete material is to be placed and other surfaces designated by the Engineer.

SPREADING AND COMPACTING.--

Spreading.--The mixture shall be spread at a temperature of not less than 121°C. Spreading shall be performed by methods that will produce an asphalt concrete surfacing of uniform smoothness and texture. Asphalt concrete shall be placed only when the atmospheric temperature is above 10°C.

Asphalt concrete for surfacing more than 1.5 meters in width shall be spread in one operation with an approved spreader and be ready for compaction without further shaping.

Compacting.--Asphalt concrete shall be placed in one or more layers of 0.04 meter or less in compacted thickness to match the thickness as shown on the plans. The first coverage of initial or breakdown compaction shall be performed when the temperature of the mixture is not less than 121°C, and all breakdown compaction shall be completed before the temperature of the mixture drops below 93°C.

Asphalt concrete shall be thoroughly compacted with a self-propelled tandem roller, weighing not less than 7260 kg. At locations where asphalt concrete is to be placed and which are inaccessible to rolling equipment, compaction shall be obtained by hand rollers, vibrating plates, impactors or other methods approved by the Engineer.

12-2.08 CORE CONCRETE

GENERAL.--This work shall consist of coring holes through existing concrete or masonry surfaces in accordance with the details shown on the plans and these special provisions.

EXECUTION.--

Holes shall be cored by methods that will not shatter or damage the concrete adjacent to the holes.

Water for the core drilling operations shall be from the domestic water supply, and shall not contain more than 1,000 parts per million of chlorides as Cl, nor more than 1,300 parts per million of sulfates as SO₄, nor shall it contain any impurities in a sufficient amount to cause discoloration or etching of the surface.

Water from the core drilling operations shall not be permitted to flow into sewers or other drainage facilities.

12-2.09 LIFT STATION

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and constructing a lift station in accordance with the details shown on the plans and these special provisions.

Lift station shall consist of precast concrete manhole base and riser, cast-in-place concrete top slab, access door, and other work as necessary for a complete installation.

Earthwork, including excavation and backfill, shall conform to the requirements in "Earthwork for Building Work," in this Section 12-2.

Cast-in-place concrete shall conform to the requirements for structural work in "Cast-In-Place Concrete" in Section 12-3, "Concrete and Reinforcement" in these special provisions.

Bar reinforcing steel shall conform to the requirements in "Cast-In-Place Concrete," in Section 12-3, "Concrete and Reinforcement" in these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data for access door, precast manhole base and riser sections, and waterproofing membrane including Material Safety Data Sheet (MSDS) shall be submitted for approval.

QUALITY ASSURANCE.--

Certificates of Compliance.--Certificates of Compliance shall be furnished for precast manhole base and risers in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

PART 2.- PRODUCTS

MANUFACTURED UNITS.--

Precast manhole riser sections.--

Precast reinforced concrete manholes shall conform to the requirements in ASTM Designation: C 478M.

Precast manhole base section.--

Precast manhole base section shall be integral with sidewalk.

MATERIALS.--

Waterproofing membrane.--

Waterproofing membrane shall be a liquid, cold applied, seamless, single component, bitumen modified polyurethane formulated for airless spraying surfaces.

A wet mil thickness gage shall be supplied by the Contractor for use by the Engineer.

Properties shall be as follows:

Property	Value	Test Designation
Shore A hardness	10 min.	ASTM D 2240
Elongation, %	350 min.	ASTM D 412
Tensile strength (kPa)	550 min.	ASTM D 412
Application rate, approximate	3 liters per square meter	Inspection, wet 1.27 mm thickness

Waterproofing membrane shall be Rexnord Chemical Products, HLM 500; Polycoat Products, Aquaseal; Select Products Company, Select Poly-Kote LM; or equal.

Epoxy mortar.--

Epoxy mortar shall be a commercial quality, trowelable, 3-component epoxy mortar consisting of 2 pourable epoxy components and a chemically resistant aggregate filler of silica quartz sand with a maximum water absorption of 0.1 percent. Epoxy shall have a pull-off strength of not less than 6900 kPa and a 90 percent cure in 24 hours. Epoxy mortar shall be the type that requires no primer as a bonding agent.

ACCESSORIES.--

Access door.--

Access door shall be single or double leaf, 6 mm minimum extruded aluminum frame with built-in neoprene cushion and strap anchors suitable for installation in concrete. Door or doors shall be aluminum diamond plate reinforced with aluminum stiffeners as required. Steel hinges shall be bolted to underside and pivot on tension bars for easy opening. Cover to withstand a load of not less than 7182 Pa, open to 90 degrees and lock open in that position, and equipped with snap lock and removable handle. Door hardware shall be corrosion resistant. Aluminum shall be mill finish and bituminous coating shall be applied to exterior of frame by manufacturer.

The clear door opening shall be as shown on the plans,

Access door shall be Babcock-Davis Hatchways, Inc., Type FB; Bilco Co., Type K or KD; or equal.

PART 3.- EXECUTION

INSTALLATION.--

Precast manhole base and risers.--Ends of riser sections shall be thoroughly cleaned and wetted prior to placing epoxy mortar.

Joint in lower section shall be completely filled with mortar prior to setting next section in place. Interior surfaces of joints shall be trowelled smooth.

All joints and penetrations of manholes shall be sealed watertight with epoxy mortar.

Application of coating.--The interior surfaces of the enclosure shall be prepared and coated with waterproofing membrane in accordance with the manufacturer's recommendations.

FIELD QUALITY CONTROL.--

Testing.--When, in the opinion of the Engineer, the groundwater table is too low to permit visual detection of leaks, pumping station enclosure shall be hydrostatically tested.

Inlets and outlets shall be plugged and the enclosure filled to the height determined by the Engineer.

Enclosure may be filled 24 hours prior to testing to permit normal absorption into the walls to take place.

There shall be no visible leakage from the enclosure.

Enclosures that do not meet the hydrostatic test shall be repaired or replaced.

12-2.10 WASH WATER SYSTEM

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing, installing and constructing a sanitary wash water system and modifying portions of existing water and sewer systems in accordance with the details shown on the plans and these special provisions.

Sanitary wash water system shall include drain pipe, sewer pipe, valves, cleanouts and other fittings and appurtenances, not mentioned, which are required for the complete installation and proper operation of the system.

Earthwork for installation of pipes, valves, cleanouts and other appurtenances shall be as specified under "Earthwork for Building Work" in this Section 12-2 of these special provisions.

Concrete and reinforcement shall conform to the requirements specified under "Cast-in-place Concrete" in Section 12-3, "Concrete and Reinforcement," of these special provisions.

Order of work.--Work which will curtail the use of the existing sewage system shall not be done until the facilities utilizing the system are closed and are no longer required.

SUBMITTALS.--

Product data.--Materials list for materials to be used shall be submitted for approval and shall include the name of the manufacturer and the source, model number, description, and standard of manufacture.

Manufacturer's descriptive data and catalog cuts to be submitted for approval are as follows:

- Cleanouts
- Drain pipe and sewer pipe and fittings/adaptor coupling
- Schedule 80 pipe
- Schedule 80 PVC flange, adaptor couplings and fittings
- Motorized valve
- Ball valve
- Electric valve actuator
- Galvanized steel pipe/adaptor coupling and fittings
- Valve box and cover
- Meter box and cover
- Underground tracer tape
- Pipe wrapping and primer
- Pipe supports
- Flexible discharge pipe
- Quick disconnect
- Check Valve
- Gate valve
- Yard hydrant
- Hose faucet

QUALITY ASSURANCE.--

Codes and standards.--Work shall conform to the applicable portions of the current approved Uniform Plumbing Code as amended by the applicable portions of current approved Title 24 California Building Standards Code.

PART 2.- PRODUCTS

IDENTIFICATION.--

Underground tracer tape.--

Underground tracer tape shall be permanent, bright colored, continuous printed plastic tape with copper wire or aluminum foil intended for direct burial service; not less than 50 mm wide x 0.1 mm thick; lettering shall read "CAUTION SEWER BURIED BELOW" or "CAUTION WATER PIPE BURIED BELOW."

PIPES AND PIPE FITTINGS.--

General.--Provide pipes of one of the following materials, of weight and class indicated. Provide pipe fittings and accessories of same material and weight and class as pipes, with joining method as indicated.

Drain and sewer pipe and fittings (for pipe 100 mm and smaller).--

Drain and sewer pipe and fittings (below grade) shall be polyvinyl chloride, (PVC) plastic sewer pipe and fittings, Standard Dimension Ratio (SDR) 35, conforming to ASTM Designation: D 3034; or PVC drain waste and vent pipe (PVC-DWV) and fittings conforming to ASTM Designation: D 2665;

Drain and sewer pipe adapters.--

Drain and sewer pipe adapters for PVC to cast iron soil pipe shall be appropriately sized flexible PVC connector with stainless steel band coupler with hex tightening screws. Rubber couplings will not be allowed. Connectors shall be Indiana Seal; Fernco; or equal.

Hose faucet risers.--

Galvanized steel pipe shall be Schedule 40 conforming to ASTM Designation: A 53, with threaded ends for connection to Schedule 80 pipe fittings. The weight of the zinc coating shall be not less than 90 percent of that specified in ASTM Designation: A 53.

Water pipe.--

Schedule 80 pipe, pipe sleeves, and fittings shall be polyvinyl chloride (PVC) plastic pipe, Schedule 80, conforming to ASTM Designation: D 1785. Connections shall be threaded and/or slip pipe.

VALVE BOX AND COVER.--

Meter box and cover (for gate valves).--

Traffic rated meter box and cover shall be precast concrete meter box and cast iron cover with no holes and high solids epoxy enamel coatings. Cover shall be factory marked "WATER." Meter box and cover shall be Bes Concrete Products, Christy Concrete Products, Cook Concrete Products, or equal with extensions as required by plan dimension.

Valve box and cover (for COTG's).--

Traffic rated valve box and cover with no holes and high solids epoxy enamel coatings shall be precast concrete box with cast iron cover. Cover shall be factory marked "SEWER," "SS," or "SANITARY SEWER". Valve box and cover shall be Cook Concrete Products, Christy Concrete Products, Best Concrete products, or equal with extensions as required.

VALVES.--

Motorized valve (ball type).--

Motorized valve (ball type) shall be minimum 1550 kPa, polyvinyl chloride, body ball and components, fluorocarbon rubber o-rings, polytetrafluoroethylene (PTFE) seals, true union, factory mounted flanged, true block valve. Valve shall be supplied with mounting kit for electric valve actuator. Valve shall be Hayward, Asahi, or equal.

Ball valve.--

Ball valve shall be two piece, minimum 2760 kPa WOG, bronze body and chrome plated or brass ball with full size port. Valve shall be Nibco Scott, T-580; Watts, B-6000; Kitz, 56; or equal.

Gate valve.--

Gate valve shall be bronze body and trim, removable bonnet and non-rising stem, Class 125, and same size as pipe in which installed. Valve shall be Crane, 428; Nibco Scott, T-113; Jenkins, 370; or equal.

Electric valve actuator.--

Electric valve actuator (for motorized valve, ball type) shall be NEMA 4, UL listed, with 115 VAC split-capacitor type reversible electric motor with compound gear drive. Actuator shall have factory set full open/close stroke limiting switches, manual override shaft, and visual position indicator. Actuator shall be capable of 25 seconds at locked rotor without overheating. Actuator shall be rated for 1.5 times the listed opening torque of the valve. Valve actuator shall be Hayward, EVS6L2T; Valvcon, TW600L2R; or equal.

Check valve.--

Check valve shall be polyvinyl chloride (PVC), socket by socket, full flow design, nonmetallic parts, pressure rated to 860 kPa, Buna-N seal and shielded clapper.

CLEANOUTS.--**Cleanout to grade.--**

Cleanout to grade shall be as shown on the plans. Piping and fittings for NPS 4 pipe shall be PVC sewer pipe, SDR 35, conforming to ASTM Designation: D 3034. Cleanout piping shall terminate below grade and in a traffic rated valve box with traffic treated cast iron cover. Cleanout piping shall terminate with an appropriately sized flexible PVC access cap and stainless steel band coupler with hex tightening screw. Rubber coupling or cap will not be allowed. Access cap shall be Indiana Seal; Fernco; or equal.

HYDRANTS AND FAUCETS.--**Yard hydrant.--****57a**

Yard hydrant shall have the shut off valve seat below frost grade depth, NPS 1 1/2 inlet and outlet, one piece corrosion resistant brass casting valve body, brass plunger, rubber seal, wheel handle, rated 825 kPa and weep drain hole connectors.

Hose faucet.--

Hose faucet shall be compression type, angle pattern, tee handle, NPS 3/4 female thread with hose end, rough brass finish. Hose faucet shall be supplied with an integral or nonremovable threaded outlet vacuum breaker which meets the requirements of the American Society of Sanitary Engineering (ASSE) Standard: 1011. Hose faucet shall be Nibco, No. 63VB; Chicago, No. 13T; or equal.

MISCELLANEOUS MATERIALS.--**Pipe wrapping tape and primer.--**

Pipe wrapping tape shall be pressure sensitive polyvinyl chloride or pressure sensitive polyethylene tape having nominal thickness of 0.50 mm. Wrapping tape shall be Polyken, 922; Manville, Trantex VID-20; Scotchrap, 51; or equal.

Pipe wrapping primer shall be compatible with the pipe wrapping tape used.

Pipe supports.--

Pipe supports shall consist of non-metallic or metallic channel framing system of anchor chair, brackets, anchor rods, fittings and fasteners, yoke and nuts as required. Supports shall meet the requirements of Federal Specification WW-H-171 for pipe hangers and supports. The maximum rated loads for supports shall have a minimum safety factor of 5 or the allowable stress values as set forth in Manufacturer's Standardization Society Standards MSS SP-58. Non-metallic channel framing products shall have a flame spread rating of 25 or less when tested per ASTM Designation: E-84 and be rated Class-1.

Flexible discharge pipe.--

Flexible discharge pipe shall be heavy duty flexible hose of nitrile rubber tube, synthetic fabric reinforcement and carbon steel wire helix, resistant to oil, detergents, ozone and heat; minimum working pressure 1380 kPa, temperature range -6°C to 104°C.

Quick Disconnect.--

Quick disconnect shall be corrosion resistant cam type couplings manufactured of glass filled polypropylene or glass filled nylon. Couplers shall have a minimum working pressure of 690 kPa, temperature rated -12°C to 82°C. Dimensions conforming to MIL-C-27487 and gaskets of nitrile compound of rubber. Couplers shall be a workable combination of fittings as shown on the plans. Hayward, Banji Flo-Control Inc., or equal.

PART 3.- EXECUTION**INSTALLATION OF IDENTIFICATION.--**

General.--Continuous underground tracer tape shall be installed directly above buried line and 150 mm to 200 mm below finished grade during backfilling operations.

INSTALLATION OF DRAIN, SEWER, AND WATER PIPE AND FITTINGS.--

General.--Drain and sewer pipe shall be installed upgrade unless otherwise permitted by the Engineer. Pipe slopes shall be as shown on the plans.

Joints shall be cleaned and sealed with the type of materials required by the pipe manufacturer. The joint sealing operation shall make the joints watertight and shall prevent leakage and infiltration under all conditions of expansion, contraction, and settlement. Joints shall be carefully cleaned before assembly. Completed joints shall be finished smooth on the inside.

Wall, footing and slab penetrations.--Wall, footing and slab penetrations shall consist of coring holes through existing walls and reinforced footings and slabs for the passage of sleeved pipe(s) and electrical conduit(s). The sleeve shall be set with epoxy mortar.

Coring holes shall conform to the requirements under "Cored Holes" in this Section 12-2 of these special provisions.

The annular gap between the pipe and sleeve shall be filled with silicone sealant.

Cleaning and closing pipe.--The interior of all pipe shall be cleaned before installation. All openings shall be capped or plugged as soon as the pipe is installed to prevent the entrance of any materials. The caps or plugs shall remain in place until their removal is necessary for completion of the installation.

Interior inspection.--Interiors of pipes shall be inspected to determine displacement or damage during installation or backfilling.

Damaged pipe shall be replaced.

Misaligned pipe shall be corrected prior to use.

Wrapping PVC and steel pipe.--Exposed PVC pipe and steel pipe buried in the ground shall be wrapped as specified herein:

1. Wrapped pipe shall be thoroughly cleaned and primed as recommended by the tape manufacturer.
2. Tapes shall be tightly applied with 1/2 uniform lap, free from wrinkles and voids with approved wrapping machines and experienced operators to provide not less than 1.00 mm thickness.
3. Field joints, fittings and valves for wrapped and plastic coated steel pipe shall be covered to provide continuous protection by puttying and double wrapping with 0.50 mm thick tape. Wrapping at joints shall extend a minimum of 150 mm over the adjacent pipe covering. Width of tape for wrapping fittings shall not exceed 50 mm. Adequate tension shall be applied so tape will conform closely to contours of fittings. Putty tape insulation compounds approved by the Engineer shall be used to fill voids and provide a smooth even surface for the application of the tape wrap.

INSTALLATION OF MISCELLANEOUS ITEMS.--

Installing pipe supports.--Pipe supports shall allow free axial movement between anchor points without abrasion, cutting or restricting of the pipe. Sleeve plastic piping at support points with a plastic pipe one pipe size larger which will allow unrestricted movement.

Pipe support anchors shall be placed at tees, valves, equipment and detailed locations to create sections of predictable expansion and contraction in the piping system. The pipe supports shall prevent transverse movement, and in conjunction with anchors, prevent point loading of the pipe.

Vertical runs of force main pipe shall be supported just below a coupling or other fitting so that the shoulder of the coupling provides bearing support to the clamp.

Flushing completed systems.--All completed systems shall be flushed and blown out.

Chlorination.--All domestic water piping and facilities shall be flushed and chlorinated by disinfecting solutions.

Calcium hypochlorite granules or tablets, if used, shall not be applied in the dry form, but shall first be dissolved into a solution before application.

The Contractor shall take adequate precautions in handling chlorine so as not to endanger workmen or damage materials. All pipes and fittings shall be completely filled with water containing a minimum of 50 ppm available chlorine. Each outlet in the system shall be opened and water run to waste until a strong chlorine test is obtained. The line shall then be closed and the chlorine solution allowed to remain in the system for a minimum of 24 hours so that the line shall contain no less than 25 ppm chlorine throughout. After the retention period, the system shall be drained, flushed and refilled with fresh water.

FIELD QUALITY CONTROL.--

Testing pipes.--Drain and sewer pipes shall be tested for obstructions before covering the pipes by balling and flushing the pipes with an approved commercial sewer cleaning ball. The ball shall be moved slowly through the pipes with a tag line. NPS 4 drain and sewer pipe shall be tested by pulling an appropriate sized inflatable plug through the pipe. Obstructions or irregularities shall be removed or repaired.

All pipes shall be tested for leakage for a minimum period of 4 hours. Drain and sewer pipes shall be tested by filling with water to an elevation of 1.2 m above the average invert of pipe, or to the top of the manhole where less than 1.2 m deep. Water pipes shall be tested at line pressure. The system shall show no visible leaks. Drain and sewer pipe may be tested in sections with the test water progressively passed down the pipes if feasible. Water shall be released at a rate which will not create water hammer or surge in the plugged section of drain, air vent and sewer pipe.

Repairs, if necessary, shall be made at the Contractor's expense.

12-2.11 GUARD POSTS

PART 1.- GENERAL

Scope.--This work shall consist of constructing guard posts in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS

Steel posts.--

Steel posts for guard posts shall be standard weight, galvanized steel pipe conforming to the details shown on the plans.

Concrete.--

Concrete for guard posts shall be commercial quality concrete, proportioned to provide a workable mix suitable for the intended use, with not less than 300 kilograms of cement per cubic meter.

PART 3.- EXECUTION

Installation.--The length and diameter of the guard posts shall conform to the details shown on the plans.

Guard posts shall be placed in holes excavated to the depth and cross section shown on the plans, and shall be installed plumb.

Guard posts shall be backfilled with concrete as shown on the plans.

SECTION 12-3. CONCRETE AND REINFORCEMENT

12-3.01 CAST-IN-PLACE CONCRETE

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of constructing cast-in-place concrete facilities in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data for admixtures, expansion joint material, vapor barrier, hardener, and sealer shall be submitted for approval.

Descriptive data shall be delivered to the Engineer at the jobsite.

QUALITY ASSURANCE.--

Certificates of Compliance.--Certificates of Compliance shall be furnished for cement, reinforcement, admixtures, freeze-thaw aggregates and epoxy products in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

PART 2.- PRODUCTS

CONCRETE MIXES.--

Concrete (structural work).--

Commercial quality concrete shall be proportioned to provide a workable mix suitable for the intended use; shall have not less than 350 kg/m³ of cement; 0 to 50 mm penetration, inclusive, as determined by California Test 533.

Concrete (minor work).--

Commercial quality concrete for concrete collars shall be proportioned to provide a workable mix suitable for the intended use; shall have not less than 300 kg/m³ of cement; 0 to 50 mm penetration, inclusive, as determined by California Test 533.

Concrete (sewer structures).--

Commercial quality concrete for sewer structures, vehicle washracks and mudrinse slabs, shall be proportioned to provide a workable mix suitable for the intended use; shall have not less than 400 kg/m³ of a mixture of Type II cement and 15 percent by weight of a mineral admixture or Type IP (MS) Modified cement; 0 to 50 mm penetration, inclusive, as determined by California Test 533.

CONCRETE MATERIALS.--

Cement.--

Cement shall conform to ASTM Designation: C 150, Types II, or III portland cement; or Type IP (MS) Modified cement. Type IP (MS) Modified shall conform to ASTM Designation: C 595 and shall be comprised of an intimate mixture of Type II Modified cement and not more than 20 percent of a pozzolanic material.

Aggregates.--

Aggregates shall be free from deleterious coatings, clay balls and other extraneous materials.

Admixtures.--

Admixtures used in portland cement concrete shall be included on the Department's current list of approved admixtures, and shall conform to ASTM Designation: C 494, Types A, B, D, F or G for chemical admixtures; ASTM Designation: C 260 for air-entraining admixtures; and ASTM Designation: C 618 for mineral admixtures, except loss on ignition shall not exceed 4 percent. Properties of admixtures shall be uniform in each lot.

FORM MATERIALS.--

Forms for unexposed finish concrete.--

Forms for unexposed finish concrete surfaces shall be plywood, lumber, metal or other acceptable material.

Form ties.--

Form ties shall be factory fabricated, removable or snapoff metal ties for use as necessary to prevent spreading of forms during concrete placement.

Form oil.--

Form oil shall be commercial quality form oil which will permit the ready release of the forms and will not discolor the concrete.

REINFORCING MATERIALS.--

Bar reinforcement.--

Bar reinforcement shall conform to ASTM Designation: A 615/A 615M, Grade 420, or ASTM Designation: A 706/A 706M.

Bar supports.--

Bar supports for reinforcement shall be precast mortar blocks or ferrous metal chairs, spacers, metal hangers, supporting wires, and other approved devices of sufficient strength to resist crushing under applied loads.

EPOXY.--

General.--Epoxy shall be furnished as 2 components which shall be mixed together at the site of the work.

Epoxy mortars.--

Epoxy mortar and epoxy mortar surface treatment shall consist of a commercial quality, trowelable mixture consisting of epoxy and sand. Epoxy shall have a pull-off strength of not less than 6895 MPa and a 90-percent cure in 24 hours. Epoxy shall be of the type that requires no primer as a bonding agent.

Sand.--

Sand for use in epoxy mortars shall be clean and shall have a moisture content of not more than 0.50-percent when tested in accordance with California Test 226.

Sand for epoxy mortar surface treatment shall be graded such that 100-percent passes the 150 μ m sieve.

RELATED MATERIALS.--

Anchor bolts, nuts, and washers.--

Nonheaded anchor bolts shall conform to ASTM Designation: A 36M, with a minimum hook length of 6.2 diameters.

Headed anchor bolts shall conform to ASTM Designation: A 307.

Nuts shall conform to ASTM Designation: A 563M, Grade A.

Washers for anchor bolts shall be commercial quality.

Mortar.--

Mortar shall consist of one part cement to 2 parts clean sand and only enough water to permit placing and packing.

Curing compound.--

Curing compound shall be a non-pigmented curing compound with fugitive dye conforming to the requirements of ASTM Designation: C 309, Type 1-D, Class A.

Concrete sealer.--

Concrete sealer shall be commercial quality VOC-compliant, silane type sealer with hydrophobic and oleophobic properties. Concrete sealer shall be Tamms Industries, Hey'Di H.O.S.; Textured Coatings of America, Inc., Rainstopper 1750W-Clear; or equal.

ADMIXTURES.--

General.--Admixtures shall be used when specified or ordered by the Engineer and may be used at the Contractor's option to conserve cement or to facilitate any construction operation.

Calcium chloride shall not be used in any concrete containing reinforcement or other embedded items.

Admixtures shall be combined with concrete materials by methods that produce uniform properties throughout the concrete.

If more than one admixture is used, said admixtures shall be compatible with each other so that the desirable effects of all admixtures will be realized.

Mineral admixtures may be used to replace up to 15 percent of Type II portland cement provided the weight of mineral admixture used is not less than the weight of cement replaced. Mineral admixtures shall not be used to replace Type IP (MS) Modified or Type III cements. Chemical admixtures may be used to reduce up to 5 percent of the portland cement except that the cement content shall not be less than 300 kg/m³. When both chemical and mineral admixtures are used with Type II cement, the weight of cement replaced by mineral admixture may be considered as cement in determining the resulting cement content.

Mineral admixtures will be required in the manufacture of concrete containing aggregates that are determined to be "deleterious" or "potentially deleterious" when tested in accordance with ASTM Designation: C 289. The use of mineral admixture in such concrete shall conform to the requirements in this section except that the use of set retarding admixtures will not be permitted.

When the use of a chemical admixture is specified or is ordered by the Engineer, the admixture shall be used at the rate specified or ordered. If no rate is specified or ordered, or if the Contractor uses a chemical admixture for his own convenience, the admixture shall be used at the dosage normally recommended by the admixture manufacturer.

When air-entrainment is specified or is ordered by the Engineer, the air-entraining admixture shall be used in amounts to produce concrete having the specified or ordered air content as determined by California Test 504. If the Contractor uses air-entrainment for his own convenience, the average air content shall not exceed 4 percent and no single test shall exceed 5 1/2 percent.

Chemical admixtures and air-entraining admixtures shall be dispensed in liquid form. Dispensers shall have sufficient capacity to measure at one time the total quantity required for each batch. If more than one liquid admixture is used in the concrete, a separate measuring unit shall be provided for each liquid admixture and dispensing shall be such that the admixtures are not mixed at high concentrations. When air-entraining admixtures are used with other liquid admixtures, the air-entraining admixtures shall be the first to be incorporated into the mix. Unless liquid admixtures are added to premeasured water for the batch, they shall be discharged to flow into the stream of water so that the admixtures are well dispersed throughout the batch.

BAR REINFORCING STEEL.--

Bending.--Reinforcing steel bars shall accurately conform to the dimensions shown on the plans.

Bars shall be bent or straightened in a manner that will not crack or break the material. Bars with kinks or improper bends shall not be used.

Hooks, bends and splices shall conform to the provisions of the Building Code Requirements for Reinforced Concrete of the American Concrete Institute.

MIXING AND TRANSPORTING CONCRETE.--

General.--When a truck mixer or agitator is used for transporting concrete to the delivery point, discharge shall be complete within 1 1/2 hours, or before 250 revolutions of the drum or blades, whichever comes first, after the introduction of cement to the aggregates.

Truck mixers or agitator shall be equipped with electrically or mechanically actuated revolution counters by which the number of revolutions of the drum or blades may readily be verified. The counters shall be of the continuous-registering type, which accurately register the number of revolutions and shall be mounted on the truck so that the Engineer may safely and conveniently inspect them from alongside the truck. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C or above, a time less than 1 1/2 hours may be required.

When non-agitating hauling equipment is used for transporting concrete to the delivery point, discharge shall be complete within one hour after the introduction of cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C, or above, the time between the introduction of cement to the aggregates and discharge shall not exceed 45 minutes.

Each load of concrete for the work shall be accompanied by a trip ticket, a copy of which shall be delivered to the Engineer at the jobsite. The trip ticket shall show volume of concrete, weight of cement and aggregates, quantity of each admixture, quantity of water including water added at the jobsite, time of day the concrete is batched, and revolution counter readings on transit mix trucks at the times the truck is charged and unloaded.

PART 3.- EXECUTION

PREPARATION.--

Forms.--Forms shall be mortar tight, true to the dimensions, lines, and grades shown on the plans, securely fastened and supported, and of adequate rigidity to prevent distortion during placing of concrete.

Forms for exposed surfaces shall be constructed with triangular fillets not less than 19 mm x 19 mm attached so as to prevent mortar runs and to produce smooth straight chamfers at all sharp edges of the concrete.

Form fasteners shall be removable without chipping, spalling, heating or otherwise damaging the concrete surface. Form ties shall be removed to a depth of at least 25 mm below the surface of the concrete.

The inside surfaces of forms shall be cleaned of all dirt, mortar and foreign material. Forms shall be thoroughly coated with form oil prior to use.

Forms shall not be stripped until at least 40 hours after placing concrete.

Anchorage and embedded items shall be placed and rigidly secured at their planned locations prior to placing concrete.

Placing reinforcing steel.--Reinforcing steel bars shall be accurately placed to the dimensions shown on the plans.

Bar reinforcement conforming to ASTM Designation: A 615/A 615M, Grade 420, or A 706/A 706M shall be lapped at least 45 diameters.

Bars shall be firmly and securely held in position by means of wiring and approved bar supports. The spacing of supports and ties shall prevent displacement of the reinforcing or crushing of supports.

Tie wire shall be clear of concrete formwork and concrete surfaces.

All reinforcing steel shall be in place and inspected before concrete placement begins. Placing of bars on fresh layers of concrete will not be permitted.

PLACING CONCRETE.--

General.--Concrete shall be placed and consolidated by means of internal vibrators to form dense, homogeneous concrete free of voids and rock pockets.

Forms and subgrade shall be thoroughly moistened with water immediately before placing concrete.

Concrete shall be placed as nearly as possible to its final location and the use of vibrators for extensive shifting of the concrete will not be permitted.

Concrete shall be deposited and consolidated in a continuous operation within limits of construction joints, until the placing of the panel or section is completed.

When concrete is to be placed in large areas requiring more than two pours, concrete shall be placed in alternate long strips between construction joints and the final slab infilled.

FINISHING CONCRETE SURFACES.--

Finishing unformed surfaces.--Slabs shall be placed full thickness to finish elevation and leveled to screeds by use of long straightedges. The screeds shall be set to grade at approximately 1.8 meter centers. After leveling, screeds shall be removed and the surface shall be floated with wooden floats.

The floated surface shall be trowelled with steel trowels. Troweling shall form a dense, smooth and true finish. Slabs shall be given a non-slip broom finish unless a different finish is called for on the plans or in these special provisions.

The application of cement dust coat will not be permitted.

Finished surfaces of floor slabs shall not deviate more than 3 mm from the lower edge of a 3-meter long straight edge.

Finishing formed surfaces.--Formed concrete surfaces shall be finished by filling holes or depressions in the surface, repairing all rock pockets, and removing fins. All surfaces of formed concrete exposed to view shall have stains and discolorations removed, unsightly bulges removed, and all areas which do not exhibit the required smooth, even surface of uniform texture and appearance shall be sanded with power sanders or other approved abrasive means until smooth, even surfaces of uniform texture and appearance are obtained.

Cement mortar, patching and finishing materials used to finish exposed surfaces of concrete shall closely match the color of surrounding surfaces.

CURING CONCRETE.--

General.--Freshly placed concrete shall be protected from premature drying and excessive cold or hot temperatures.

Initial curing of floor slabs shall start as soon as free water has disappeared from the concrete surface. The concrete shall be kept continuously moist for not less than 7 days after the concrete has been placed.

Cotton mats, rugs, carpets, or sand blankets may be used as a curing medium to retain the moisture during the curing period. Curing materials that will stain or discolor concrete shall not be used on surfaces exposed to view.

Prior to placing the curing medium, the entire surface of the concrete shall be kept damp by applying water with a nozzle that so atomizes the flow that a mist and not a spray is formed, until the surface of the concrete is covered with the curing medium. At the expiration of the curing period, the concrete surfaces shall be cleared of all curing mediums.

Concrete surfaces, other than floor slabs, shall be kept moist for a period of at least 5 days by leaving the forms in place or by covering the exposed surfaces using moist rugs, cotton mats or other curing materials approved by the Engineer.

Concrete collars shall be cured with a curing compound.

PROTECTING CONCRETE.--

General.--Concrete shall not be placed on frozen or frost covered surfaces.

Concrete shall be protected from damage due to rain, freezing or inclement weather, and shall be maintained at a temperature of not less than 4°C for 72 hours. When required by the Engineer, the Contractor shall provide a written outline of his proposed methods of protecting concrete.

Vehicles, equipment, or concentrated loads weighing more than 140 kg individually and material stockpiles weighing more than 240 kg/m² will not be permitted on the concrete within 10 calendar days after placing.

SPECIAL TREATMENTS.--

Concrete sealer.--Concrete sealer shall be applied to the concrete surfaces of mud rinse and wash rack slab. in accordance with the manufacturer's instructions for heavy duty use. The sealer shall be applied to dry concrete surfaces.

Epoxy mortars.--Epoxy for use as a binder in epoxy mortars shall be thoroughly mixed together before the aggregate is added, and unless otherwise specified, the mix proportions shall consist of one part binder to approximately 4 parts of aggregate, by volume.

All surfaces against which epoxy mortars are to be applied shall be free of rust, paint, grease, asphalt, and loose or deleterious material.

SECTION 12-4. MASONRY (BLANK)

SECTION 12-5. METALS

12-5.01 BUILDING MISCELLANEOUS METAL

PART 1.- GENERAL

Scope.--This work shall consist of fabricating, furnishing and installing building miscellaneous metal in accordance with the details shown on the plans and these special provisions.

Building miscellaneous metal shall consist of the following:

Mud rinse interceptor grate and frame

Wash rack sump grate and frame

including all anchors, fastenings, hardware, accessories and other supplementary parts necessary to complete the work.

REFERENCES.--

Codes and standards.--Welding of steel shall be in accordance with American Welding Society (AWS) D 1.1, "Structural Welding Code-Steel" and D 1.3, "Structural Welding Code-Sheet Steel."

SUBMITTALS.--

Product data.--Submit manufacturer's specifications, anchor details and installation instructions for interceptor grate and frame.

Working drawings.--Working drawings of fabricated items shall be submitted for approval.

QUALITY ASSURANCE.--

Shop assembly.--Preassemble items in shop to the greatest extent possible to minimize field splicing and assembly. Disassemble units only as necessary for shipping and handling limitations. Clearly mark all units for reassembly and installation.

Inspection and tests.--Materials and fabrication procedures shall be subject to inspection and tests by the Engineer, in mill, shop and field. Such tests will not relieve the Contractor of responsibility of providing materials and fabrication procedures in compliance with specified requirements.

PART 2.- PRODUCTS

MATERIALS.--

Interceptor grate and frame.--

Interceptor grate and frame shall be galvanized and traffic rated. Grate and frame shall be Neenah, R4990CX with Type A grate; AFC, A-2422; or equal.

Steel bars, plates and hot-rolled shapes.--

Steel bars, plates and hot-rolled shapes shall conform to ASTM Designation: A 36/A 36M.

Bolts, studs, threaded rods, nuts and washers.--

Bolts, studs, threaded rods, and nuts for general application shall conform to ASTM Designation: A 307.

Washers shall be commercial quality.

Mortar.--

Mortar shall consist of one part cement, measured by volume, to 2 parts clean sand and only enough water to permit placing and packing.

FABRICATION.--

Workmanship and finish.--Workmanship and finish shall be equal to the best general practice in modern shops.

Miscellaneous metal shall be clean and free from loose mill scale, flake rust and rust pitting, and shall be well formed and finished to shape and size with sharp lines and angles. Bends from shearing or punching shall be straightened.

The thickness of metal and details of assembly and support shall give ample strength and stiffness.

Built-up parts shall be true to line and without sharp bends, twists and kinks. Exposed ends and edges of metal shall be milled or ground smooth, with corners slightly rounded.

Joints exposed to the weather shall be made up to exclude water.

Galvanizing.--Items indicated on the plans to be galvanized shall be hot-dip galvanized after fabrication. The weight of galvanized coating shall be at least 460 grams per square meter of surface area, except drainage grates shall have at least 610 grams per square meter of surface area.

PART 3.- EXECUTION

GENERAL.--

Anchorage.--Anchorage devices and fasteners shall be provided for securing miscellaneous metal in-place construction; including threaded fasteners for concrete and masonry inserts, toggle bolts, through bolts, lag bolts, wood screws and other connectors.

Cutting, drilling and fitting shall be performed as required for installation of miscellaneous metal fabrications. Work is to set accurately in location, alignment and elevation, plumb, level, true and free of rack, measured from established lines and levels.

SECTION 12-6. (BLANK)

SECTION 12-7 THERMAL AND MOISTURE PROTECTION

12-7.01 JOINT SEALANT

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of preparing and placing joint sealant in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data, specifications and installation instructions shall be submitted to the Engineer at the jobsite for approval.

PART 2.- PRODUCTS

Primer.--

Primer shall be as recommended by the sealant manufacturer.

Joint sealant.--

Joint sealant shall be a commercial quality, 2 component polyurethane sealant, which shall be self-leveling and withstand up to 25 percent movement.

PART 3.- EXECUTION

PREPARATION.--

Forming.--Groove for joint sealant shall be formed to a uniform width and depth and to the alignment shown on the plans or as ordered by the Engineer. The completed groove shall have a top width within 3 mm of the width shown on the plans and the bottom width shall not vary from the top width by more than 2 mm.

At least 24 hours prior to installing the joint sealant, the Contractor shall repair all spalls, fractures, breaks, or voids in the concrete surfaces of the joint groove.

Cleaning.--Prior to placing the joint sealant, the joint shall be cleaned by a method which shall include abrasive blast cleaning and then be cleaned with a high pressure air jets to remove all residue and foreign material.

INSTALLATION.--

Materials.--No material shall be used which has skinned over or which has settled in the container to the extent that it cannot be easily redispersed by hand stirring to form a smooth uniform product.

Each container of material shall be clearly labeled or each delivery of material in the tanks of 2-component equipment shall be accompanied with a ticket showing designation (Component A or B), the manufacturer's name, lot or batch number, date of manufacture, date of packaging, and date, if any, beyond which the sealant shall not be used.

Primer.--A primer shall be applied to the sides of the groove and all exposed vertical surfaces in the joint prior to placing the sealant. Primer shall be dry at the time of placing the sealant. Contaminated primer shall be removed and replaced.

Joint sealant.--The 2-component sealant shall be mixed and placed in the groove in accordance with manufacturer's instructions. Unmixed liquid components which have been exposed to the atmosphere for more than 24 hours, shall not be used.

SECTION 12-8. THROUGH AND 12-9. BLANK

SECTION 12-10. SPECIALTIES

12-10.01 METAL SIGNS

GENERAL.--This work shall consist of furnishing and installing signs in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive data, colors, graphics and fastening details shall be submitted for approval.

PRODUCTS.--

Signs.--

Signs shall be sheet steel, not less than 1.22 mm thick (18-gage) with a baked-on enamel coating. Decals are not allowed and shall not be submitted for approval.

See plans for letter size, color and background color.

Fasteners.--

Fasteners shall be galvanized expansion anchors as recommended by the sign manufacturer.

EXECUTION.--Sign inscriptions shall read as shown on the plans.

Each sign shall be located as shown on the plans and shall be fastened in place with a minimum of 4 fasteners for each sign.

SECTION 12-11 EQUIPMENT

12-11.01 OIL/WATER SEPARATOR SYSTEM

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing an above ground oil/water separator system and appurtenances in accordance with the details shown on the plans and these special provisions.

Oil/water separator system and appurtenances shall include products and other fittings and appurtenances, not mentioned, which are required for the complete installation and proper operation of the system.

Earthwork for installation of pipes, cleanouts and other appurtenances shall be as specified under "Earthwork for Building Work" in this Section 12-2 of these special provisions.

Concrete and reinforcement shall conform to the requirements specified under "Cast-in-place Concrete" in Section 12-3, "Concrete and Reinforcement," of these special provisions.

Wash Water System shall conform to the requirements specified under "Wash Water System" in this Section 12-2 of these special provisions.

SUBMITTALS.--

Working drawing and seismic design.--Working drawings for oil/water separator used in the work shall be submitted for approval. Seismic design calculations for anchor supports and slab dimensions and details shall be submitted for approval. Calculations shall be based on the latest edition of the Title 24 California Building Standards Code. The drawing and calculations shall be stamped and signed by an engineer who is registered as a Civil or Structural Engineer in the State of California.

Product data.--Materials list for materials to be used shall be submitted for approval and shall include the name of the manufacturer and the source, model number, description, and standard of manufacture.

The following is a list of the required data and catalog cuts:

Oil/water separator and components

OPERATION AND MAINTENANCE MANUALS.--

Operation and maintenance manuals.--Prior to the completion of the contract, 3 identical copies of the operation, electrical control schematics, and maintenance instructions with parts lists for the equipment specified herein shall be delivered to the Engineer at the jobsite. The instruction and parts lists shall be indexed and bound in a manual form and shall be complete and adequate for the equipment installed. Inadequate or incomplete material shall be returned. The Contractor shall resubmit adequate and complete manuals at no expense to the State.

WARRANTIES AND GUARANTEES.--

Warranties and Guarantees.--Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract. Manufacturer's warranties and guarantees shall be in a bound manual form. .

PART 2.- PRODUCTS

Oil/water separator.--

The above ground oil/water separator shall be a preassembled, oil-water separation unit. All components shall be supplied by one supplier as a package system. The oil/water separator unit shall be designed for installation in outdoor locations, and shall be supplied with drain lines and submersible heaters, and valves to prevent freeze damage.

Control panel enclosure shall be a NEMA 3R, lockable enclosure, containing an electrical mounting panel, hinged interior door and exterior deadfront door with window(s) properly located to observe necessary controls and gauges. The oil/water separator system shall be suitable for operation on a nominal input voltage of 120-volts, 60 hertz, single phase, with a maximum input of 24-amperes.

Oil/water separator control shall incorporate intrinsically safe circuitry (suitable for Class 1, Division 1 locations) for detecting water level in the pump sump. Intrinsically safe circuitry shall be housed in a separate compartment with metal barriers to separate low voltage from higher voltages within the control panel. Metal barrier shall extend all the way from back mounting panel to the interior hinged door. Control panel shall be factory assembled control panel.

The oil/water separator unit shall be capable of processing up to 55 liters per minute. The unit shall have a discharge of oil and grease not to exceed 10 mg/l of 20 micron size and larger.

The oil/water separator unit and pump shall be designed and sized to deliver sufficient and adequate quantities and pressures that are required to satisfy all operating conditions.

The oil/water separator unit shall consist of at least the following components:

1. Water level activated sump pump with float(s). Pumps shall be explosion proof suitable for Class I, Division I locations.
2. Above ground oil-water solids coalescing separator having a minimum of 51 square meters of coalescing surface area.
3. Floating oil skimmer system with covered waste oil storage container.
4. A continuous ozone disinfection system with dedicated pump and adjustable 24 hour timer.
5. All electrical controls
6. All necessary piping, valves and miscellaneous equipment that are necessary for a complete operating system.

PART 3.- EXECUTION

INSTALLATION OF OIL/WATER SEPARATOR UNIT

General.--Manufactured oil/water separator unit and appurtenances shall be installed in accordance with the approved drawings, these specifications, applicable codes and standards and the manufacturer's recommendations where applicable, as approved by the Engineer.

A manufacturers representative shall be present during the installation and during the testing of the oil/water process unit system. A two hour operational and maintenance demonstration shall be conducted by the manufacturer's representative. The Engineer shall be given a 5-day notice prior to the demonstration.

Oil/water separator control panel shall be mounted on the unit with proper working clearances in front of and around the electrical equipment. Low voltage conduit shall be terminated in the intrinsically safe compartment and other conduits shall be terminated elsewhere as required. All wires entering and leaving the control panel must be terminated on terminal blocks. Wires shall be neatly trained and bundled, and wiring troughs shall be provided in the enclosure as necessary. Wiring shall be arranged so that any piece of equipment/apparatus may be removed without disconnecting any wires except leads to that piece of apparatus. A schematic diagram encased between 2 heat-fused laminated plastic sheets shall be provided with brass mounting eyelets and attached to the inside of the enclosure,

FIELD QUALITY CONTROL.--

Testing.--Testing of the oil water separator unit shall be conducted by the Contractor in the presence of the Engineer. Any repairs shall be corrected by the Contractor at no cost to the State.

The Contractor shall notify the Engineer in writing not less than 5 days prior to the time that testing is to be conducted.

The unit shall be tested for 3 hours a day for 3 days. The oil water separator shall be tested at various flow rates during the test period. Any repairs or adjustments shall be made by the Contractor at no additional cost to the State. Upon completion of any repair work, the test period shall be restarted.

SECTION 12-12. THROUGH 12-15. BLANK

SECTION 12-16. ELECTRICAL

12-16.01 ELECTRICAL WORK

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of performing electrical work in accordance with the details shown on the plans and these special provisions.

Electrical work shall include furnishing all labor, materials, equipment and services required to construct and install the complete electrical system shown on the plans and the work of installing electrical connections for the oil/water separator system, motorized valve, rain sensor, lift station, and controls specified elsewhere in these special provisions.

System layouts are generally diagrammatic and location of equipment is approximate. Exact routing of conduits and other facilities and location of equipment is to be governed by structural conditions and other obstructions, and shall be coordinated with the work of other trades. Equipment requiring maintenance and inspection shall be located where it is readily accessible for the performance of such maintenance and inspection.

Related work.--Earthwork, foundations, sheet metal, painting, mechanical and such other work incidental to and necessary for the proper installation and operation of the electrical work shall be done in accordance with the requirements specified for similar work elsewhere in these special provisions.

QUALITY ASSURANCE.--

Codes and standards.--All work performed and materials installed shall be in accordance with the National Electrical Code; the California Building Standards Code, Title 24, Part 3, "California Electrical Code," and the California Code of Regulations, Title 8, Chapter 4, "Electrical Safety Orders," and all local ordinances.

Warranties and guarantees.--Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

TESTING.--

After the electrical system installation work has been completed, the electrical system shall be tested in the presence of the Engineer to demonstrate that the electrical system functions properly. The Contractor shall make necessary repairs, replacements, adjustments and retests at his expense.

12-16.02 BASIC MATERIALS AND METHODS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing conduits, conductors, fittings, and wiring devices in accordance with the details shown on the plans and these special provisions.

Conduits, conductors, fittings, and wiring devices shall include those accessories and appurtenances, not mentioned, that are required for the proper installation and operation of the electrical system.

Related work.--Roof penetrations shall be flashed and sealed watertight conforming to the requirements specified under "Sheet Metal Flashing" in Division 7, "Thermal and Moisture Protection," of these special provisions.

Where conduits pass through fire rated wall, floor or ceiling assemblies, the penetrations shall be protected in accordance with the requirements specified under "Through-Penetration Firestopping" in Division 7, "Thermal and Moisture Protection," of these special provisions.

SUBMITTALS.--

Product data.--A list of materials and equipment to be installed, manufacturer's descriptive data, and such other data as may be requested by the Engineer shall be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions for recessed junction and pull boxes, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

PART 2.- PRODUCTS

CONDUITS AND FITTINGS.--

Rigid steel conduit and fittings.--

Rigid steel conduit shall be threaded, full weight rigid steel, hot-dip galvanized inside and outside with steel or malleable iron fittings. Fittings shall be threaded unless otherwise specified or shown on the plans.

Split or three-piece couplings shall be electroplated, malleable cast iron couplings.

Insulated grounding bushings shall be threaded malleable cast iron body with plastic insulated throat and steel, lay-in ground lug with compression screw.

Insulated metallic bushings shall be threaded malleable cast iron body with plastic insulated throat.

Electrical metallic tubing (EMT) and fittings.--

Electrical metallic tubing shall be formed of cold rolled strip steel, electrical resistance welded continuously along the longitudinal seam with zinc coating outside and enamel or lacquer coating inside.

Couplings shall be electroplated, rain and concrete tight, gland compression type, steel body couplings with malleable iron nuts.

Connectors shall be electroplated, rain and concrete tight, gland compression type, steel body connectors with male hub, malleable iron nut and insulated plastic throat.

Liquid tight flexible metallic conduit and fittings.--

Liquid tight flexible metallic conduit shall be fabricated in continuous length from galvanized sheet steel, spirally wound and formed to provide an interlocking design with an extruded polyvinyl chloride cover.

Fittings shall be electroplated, malleable cast iron body, with cap nut, grounding ferrule, and connector body with insulated throat.

CABLES AND CONDUCTORS.--**Conductors.--**

Conductors shall be stranded copper wire.

Conductor insulation types unless otherwise shown or specified, shall be as follows:

1. Conductors across hinges of control panel enclosures shall be Type MTW.
2. Conductors shall be type XHHW in wet and outdoor locations.
3. Conductors shall be type THHN in dry locations.

Wire connections and devices.--

Wire connections and devices shall be pressure or compression type, except that connectors for No. 10 AWG and smaller conductors in dry locations may be preinsulated spring-pressure type.

ELECTRICAL BOXES.--**Outlet, device and junction boxes.--**

Unless otherwise shown or specified, boxes shall be galvanized steel boxes with knock-outs and shall be the size and configuration best suited to the application indicated on the plans. Minimum size of outlet, receptacle, switch or junction boxes shall be 100 mm square by 40 mm deep, except that switch boxes for the installation of single switches and outlet boxes for flush-mounted light fixtures shall be 50 mm by 75 mm by 40 mm deep.

Cast metal boxes shall be cast iron boxes with threaded hubs and shall be of the size and configuration best suited to the application shown on the plans.

Weatherproof junction boxes shall have cast metal covers with gaskets.

Weatherproof switch and receptacle boxes shall have gasketed covers with gasketed hinged flaps to cover switches and receptacles.

RECEPTACLES AND SWITCHES.--**Ground fault circuit interrupter receptacles, (GFCI).--**

Ground fault circuit interrupter receptacles shall be NEMA Type 5-20R, feed-through type, ivory color, 3-wire, 20-ampere, 125-volt AC, grounding type, specification grade, duplex receptacle with ground fault interruption. Receptacle shall detect and trip at current leakage of 5 milliamperes and shall have front mounted test and reset buttons.

MISCELLANEOUS MATERIALS.--**Warning Tape.--**

Warning tape shall be 100 mm wide and contain the printed warning "CAUTION ELECTRICAL CONDUIT" in bold 19 mm black letters at 760 mm intervals on bright orange or yellow background. The printed warning shall be non-erasable when submerged under water and resistant to insects, acids, alkali, and other corrosive elements in the soil. The tape shall have a tensile strength of not less than 70 kg per 100 mm wide strip and shall have a minimum elongation of 700 percent before breaking.

Anchorage devices.--

Anchorage devices shall be corrosion resistant, toggle bolts, wood screws, bolts, machine screws, studs, expansion shields, and expansion anchors and inserts.

Electrical supporting devices.--

Electrical supporting devices shall be one hole conduit clamps with clamp backs, hot-dipped galvanized, malleable cast iron.

PART 3.- EXECUTION

INSTALLATION.--

Conduit, general.--Rigid steel conduit shall be used unless otherwise shown on the plans or specified in these special provisions.

Electrical metallic tubing may be used in furred spaces and for exposed work indoors above the switch height.

Unless otherwise specified or shown on the plans, liquid-tight flexible metal conduit shall be used to connect motors, and other equipment subject to vibration in wet locations.

Conduit installation.--Conduit trade sizes are shown on the plans. No deviation from the conduit size shown on the plans will be permitted without written permission from the Engineer.

Conduit shall be concealed unless otherwise shown on the plans.

Exposed conduit shall be installed parallel and at right angles to the building lines.

All raceway systems shall be secured to the building structures using specified fasteners, clamps and hangers.

Single conduit runs shall be supported by using one hole pipe clamps. Where run horizontally on walls in damp or wet locations, conduit shall be installed with "clamp backs" to space conduit off the surface.

Multiple conduit runs shall be supported with construction channel secured to the building structure. Conduits shall be fastened to construction channel with channel compatible pipe clamps.

All floor and wall penetrations shall be sealed water-tight.

Conduit terminations.--Rigid steel conduits shall be securely fastened to cabinets, boxes and gutters using 2 locknuts and specified insulating metallic bushing. Electrical metallic tubing shall be securely fastened to cabinets, boxes and gutters using specified connectors. Conduit terminations at exposed weatherproof enclosures and cast outlet boxes shall be made watertight using specified hubs.

Grounding bushings with bonding jumpers shall be installed on all type of conduits terminating at concentric knockouts and on all conduits containing service conductors, grounding electrode conductor, and conductors feeding separate buildings.

Warning Tape.--Warning tape shall be placed over each conduit in a trench. Each warning tape shall be centered over the conduit and shall be placed over the 150 mm layer of sand covering the conduit as described elsewhere in these special provisions.

Conductor and cable installation.--Conductors shall not be installed in conduit until all work of any nature that may cause injury is completed. Care shall be taken in pulling conductors that insulation is not damaged. An approved non-petroleum base and insulating type pulling compound shall be used as needed.

All cables shall be installed and tested in accordance with manufacturer's recommendations.

Splices and joints shall be insulated with insulation equivalent to that of the conductor.

Provide 155 mm of slack at each outlet and device connection. If the outlet or device is not at the end of a run of wire, connection shall be made with correctly colored pigtails tapped to the runs with splices as specified herein.

Branch circuit conductors in panelboards and load centers shall be neatly trained along a path from the breaker terminals to their exit point. The conductors shall have ample length to transverse the path without strain, but shall not be so long as to require coiling, doubling back, or cramming. The path shall transverse the panelboard gutter spaces without entering a gutter containing service conductors and, unless otherwise shown on the plans, without entering the gutter space of any panelboard feeder.

All pressure type connectors and lugs shall be retightened after the initial set.

Splices in underground pull boxes and similar locations shall be made watertight.

Junction boxes in furred or accessible ceiling spaces shall be identified with felt-tip pen denoting the circuits contained in the box.

Conductor identification.--The neutral and equipment grounding conductors shall be identified as follows:

Neutral conductor shall have a white or natural gray insulation except that conductors No. 4 and larger may be identified by distinctive white marker such as paint or white tape at each termination.

Equipment grounding conductor shall be bare or insulated. If insulated, equipment grounding conductors shall have green or green with one or more yellow stripes insulation over its entire length except that conductors No. 4 and larger may be permanently identified by distinctive green markers such as paint or green tape over its entire exposed insulation.

Feeder and branch circuit ungrounded conductors shall be color coded by continuously colored insulation, except

Contract No. «Dist»-«Contract_No»

conductors No. 6 AWG or larger may be color coded by colored tape at each connection and where accessible. Ungrounded conductor color coding shall be as follows:

SYSTEM	COLOR CODE
120/240V-Single phase	Black, blue (Oil/Water System)
120/240V-Single phase	Black, orange, blue

Where more than one branch circuit enters or leaves a conduit, panel, gutter, or junction box, each conductor shall be identified by its panelboard and circuit number. All control conductors including control conductors of manufacturer supplied and field wired control devices shall be identified at each termination with the wire numbers shown on the plans, approved shop drawings, and as directed by the Engineer where deemed necessary. Identification shall be made with one of the following:

1. Adhesive backed paper or cloth wrap-around markers with clear, heat shrinkable tubing sealed over either type of marker.
2. Self-laminating wrap around type, printable, transparent, permanent heat bonding type thermoplastic film markers.
3. Pre-printed, white, heat-shrinkable tubing.

Each terminal block shall have a molded marking strip attached with screws. The identifying numbers of the terminating conductors, as shown on the plans or on the submittal drawings, shall be engraved in the marking strip.

Outlet, device and junction box installation.--Where one or more threaded steel conduits are required to connect to an outlet, device, or junction box, the box shall be a cast metal box with threaded hubs. Unless otherwise shown on the plans or specified in these special provisions, all other boxes shall be sheet steel boxes. Weatherproof outlet, device and junction boxes shall have cast metal covers with gaskets. Unless otherwise shown on the plans or specified in these special provisions, all other boxes shall have standard galvanized covers.

No unused openings shall be left in any box. Knockout seals shall be installed as required to close openings.

Outlet, device, and junction boxes shall be installed at the locations and elevations shown on the plans or specified herein. Adjustments to locations may be made as required by structural conditions and to suit coordination requirements of other trades.

Anchorage.--Hangers, brackets, conduit straps, supports, and electrical equipment shall be rigidly and securely fastened to surfaces by means of toggle bolts on hollow masonry; expansion shields and machine screws, or expansion anchors and studs or standard preset inserts on concrete or solid masonry; machine screws or bolts on metal surfaces; and wood or lag screws on wood construction.

Anchorage devices shall be installed in accordance with the anchorage manufacturer's recommendations.

Mounting heights.--Electrical system components shall be mounted at the mounting heights, shown on the plans. The mounting height dimensions shall be measured above the finished floor to the bottom of the device or component.

12-16.03 ELECTRICAL EQUIPMENT

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of replacing and upgrading existing load center and related accessories in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

PART 2.- PRODUCTS

Panel 2B.--

Panel 2B shall be indoor type, surface-mounted, factory assembled, 3-phase, 4-wire, 120/240-volt, AC load center with 100-ampere main circuit breaker, insulated groundable neutral, hinged door and molded case branch circuit breakers as shown on the plans. Load center size shall be at most 510 mm wide and 865 mm high. Load center shall be Westinghouse; Cutler-Hammer; or equal.

Warning plates.--

33a

Warning plates shall be laminated phenolic plastic with white core and red front and back. Warning plates inscription shall be in capitals letters etched through the outer layer of the nameplate material.

PART 3.- EXECUTION

INSTALLATION.--

Panelboard installation.--Set cabinets plumb and symmetrical with building lines. Train interior wiring as specified under "Conductor and Cable Installation" in "Basic Materials and Methods" of these special provisions. Touch-up paint any marks, blemishes, or other finish damage suffered during installation. Replace cabinets, doors or trim exhibiting dents, bends, warps or poor fit which may impede ready access, security or integrity.

Mounting height shall be as shown on the plans.

A typewritten directory under transparent protective cover shall be provided and set in metal frame inside each cabinet door. Directory panel designation for each circuit breaker shall include complete information concerning equipment controlled, including room number or area designated on the plans.

Equipment identification.--Equipment shall be identified with nameplates fastened with self-tapping, cadmium-plated screws or nickel-plated bolts.

Nameplate inscriptions shall read as follows:

Item	Letter height, mm	Inscription
Oil/water separator Control panel	6.0	OIL/WATER SEPARATOR CONTROL PANEL

Warning plates.-- Warning plates shall be attached to the wall and/or near the designated equipment with self-tapping cadmium-plated screws or nickel-plated bolts.

Warning plate inscriptions shall read as follows:

Item	Letter height, mm	Inscription
Water diverted alarm	25	WATER DIVERTED

12-16.04 VALVE CONTROL PANEL

GENERAL.--This work shall consist of furnishing and installing valve control panel in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--Manufacturer's descriptive information, catalog cuts and installation instructions shall be submitted for approval.

PRODUCTS.--

Valve control panel.--

Valve control panel shall be single exterior hinged door, dust tight NEMA Type 3R enclosure, containing an electrical mounting panel and hinged interior door and exterior deadfront door. The enclosure shall be made of 14-gage steel minimum with all seams continuously welded. The enclosure shall be sized to fit in all power and control appurtenances. A rolled lip shall be provided around three sides of the hinged door and around all sides of the enclosure opening. The door shall be provided with a neoprene gasket that is attached with an oil-resistant adhesive. The door shall be maintained closed with door clamps. Security shall be provided by a hasp and staple for padlocking.

The enclosure shall be factory prewired in conformance with NEMA Class IIC wiring. All wires entering the enclosure shall terminate on terminal blocks. All interior control wires shall be 19-strand No. 14 MTW. Wires shall be neatly trained and bundled, and wiring troughs shall be provided in the enclosure as necessary. Wiring shall be arranged so that any piece of apparatus may be removed without disconnecting any wires except the leads to that piece of apparatus.

A wiring diagram encased between 2 heat-fused laminated plastic sheets shall be provided with brass mounting eyelets and attached to the inside of the enclosure.

Panel main breaker, PMB.--

Panel main breaker, PMB, shall be single-pole, 120-volt, AC, molded case circuit breaker with 100-ampere frame, 40-ampere trip, and interrupting capacity of 10,000 amperes (symmetrical) at 120 volts.

Oil/Water separator disconnect, O/WD.--

Oil/water separator disconnect, O/WD, shall be single-pole, 120-volt, AC, molded case circuit breaker with 100-ampere frame, 30-ampere trip, and interrupting capacity of 10,000 amperes (symmetrical) at 120 volts.

Receptacle disconnect, RD.--

Receptacle disconnect, RD, shall be single-pole, 120-volt, AC, molded case circuit breaker with 100-ampere frame, 15-ampere trip, and interrupting capacity of 10,000 amperes (symmetrical) at 120 volts.

Valve control disconnect, VCD.--

Valve control disconnect, VCD, shall be single-pole, 120-volt, AC, molded case circuit breaker with 100-ampere frame, 15-ampere trip, and interrupting capacity of 10,000 amperes (symmetrical) at 120 volts.

Pilot light, PL1 and PL2.--

Pilot light shall be panel-mounted pilot light with 120-volt direct incandescent replacement type LED lamp, amber lens, and screw cap. Pilot light shall be bright enough to be readily visible during daylight hours.

Fuse.--

Fuse shall be 120-volt, dual-element glass tube fuse and 1-pole barrier type fuse base. The fuse shall be sized to prevent an overcurrent in the control transformer primary from exceeding 300 percent of its respective rating. Provide five extra spare fuses within the control enclosure for future use.

Control transformer, CT.--

Control transformer, CT, shall be double-wound, 0.200 KVA, 120-volt primary, 24-volt secondary, 60Hz, dry type transformer.

Power distribution block, PDB.--

Power distribution block, PDB, shall be 50-ampere, 300-volt, molded plastic with two or more mounting holes and two or more branch openings in each pole. The molded plastic shall have a high resistance to heat, moisture, mechanical shock, and electric potential and shall have a smooth even finish. Each block shall have a molded marking strip attached with screws. Terminal blocks shall have tubular, high pressure clamp connectors.

Terminal block, TB.--

Terminal block, TB, shall be 20-ampere, 300-volt, molded plastic with two or more mounting holes and two or more terminals in each cast block. The molded plastic shall have a high resistance to heat, moisture, mechanical shock, and electric potential and shall have a smooth even finish. Each block shall have a molded marking strip attached with screws. Terminal blocks shall have tubular, high pressure clamp connectors.

Bypass selector switch, SS.--

Bypass selector switch, SS, shall be heavy duty oil-tight selector switch with double-pole, double-throw contact. The contact shall have an inductive pilot duty rating of 60-amperes (make), 6-amperes (break) and 10-amperes (continuous) at 120-volts and 35 percent power factor. Selector switch shall have legend plate marked "AUTO-TEST."

Alarm light, AL.--

Alarm light, AL, shall be fluorescent, weatherproof cast-metal light fixture for use with threaded rigid conduit. Light fixture shall have guard and red globe, and 15-watt, 120-volt standard service fluorescent lamp complete with ballast and screw-on type base.

Rain sensor.--

Rain sensor shall be 24-volt, AC, sealed with solid state electronic components. The rain sensor shall energize the normally open (NO) contact after approximately 3 mm rain has fallen. The level of rain water in the rain sensor container shall not exceed 6.3 mm.

Control relays, CR1, CR2.--

Control relays, CR1 and CR2, shall be 24-volt AC coil, general purpose relay with three-pole, double-throw, 10-ampere, 120-volt, AC, contacts. Relay shall be enclosed in clear plastic with 11-pin tube type plug base. Sockets shall be barrier type, 11-contact relay socket with 10-ampere contacts and screw terminals.

Ground fault circuit interrupter receptacles, (GFCI).--

Ground fault circuit interrupter receptacles shall be NEMA Type 5-20R, feed-through type, ivory color, 3-wire, 20-ampere, 125-volt AC, grounding type, specification grade, duplex receptacle with ground fault interruption. Receptacle shall detect and trip at current leakage of 5 milliamperes and shall have front mounted test and reset buttons.

Nameplates.--

Nameplates shall be laminated phenolic plastic with white core and black front and back. Nameplate inscription shall be in capitals letters etched through the outer layer of the nameplate material.

EXECUTION.--

EQUIPMENT IDENTIFICATION.--Equipment shall be identified with nameplates fastened with self-tapping, cadmium-plated screws or nickel-plated bolts.

Nameplate inscriptions shall read as shown on the plans.

COMPONENT MOUNTING.--The following electrical components shall be mounted on the back mounting panel of the Valve Control Enclosure: Panel main breaker, PMB; Oil/water separator disconnect; Receptacle disconnect, RD; Valve control disconnect, VCD; Fuse base with fuse; Control transformer, CT; Control relays, CR1 and CR2; Power distribution block, PDB; Terminal block, TB; Neutral bar; Ground Bus; and nameplates as shown on the plans.

The following electrical components shall be mounted on the interior door of the Valve Control Enclosure: Selector switch, SS; Pilot Light, PL1 and PL2; Indicating light, IL; GFCI receptacle outlet; and nameplates as shown on the plans.

Alarm lights, AL, shall be mounted on the top of the Valve Control Panel cabinet as shown on the plans.

OPERATION.--The automatic operation of the motorized valve shall be controlled by the rain sensor. When the rain sensor is actuated by the rain, the motorized valve shall go to the diverted position and shall energize the pilot light, PL2 and alarm light, AL. Once the rain stops, water in rain sensor shall keep the electric actuator in the diverted position until the rain sensor is deactivated.