


**\*\* WARNING \*\* WARNING \*\* WARNING \*\* WARNING \*\***  
**This document is intended for informational purposes only.**

Users are cautioned that Caltrans does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders and non-bidder packages, write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone and fax number, P.O. Box and street address so that you can receive addenda.

Note: Addenda information is NOT included with the electronic documents available via electronic file transfer. Only bidder or non-bidder package holders listed with the Caltrans Plans and Bid Documents section as described above will receive addenda information.



**STATE OF CALIFORNIA**

**DEPARTMENT OF TRANSPORTATION**

---

**NOTICE TO CONTRACTORS  
AND**

**SPECIAL PROVISIONS**

**FOR HIGHWAY PLANTING ON STATE HIGHWAY IN**

**FRESNO COUNTY IN FRESNO FROM CALIFORNIA AVENUE**

**OVERCROSSING TO NORTH FRESNO UNDERCROSSING**

**DISTRICT 06, ROUTE 99**

---

**For Use in Connection with Standard Specifications Dated JULY 1999, Standard Plans Dated JULY 1999, and Labor  
Surcharge and Equipment Rental Rates.**

---

**CONTRACT NO. 06-404104**

**06-Fre-99-31.8/38.9**

**Federal Aid Project  
ACNH-P099(418)E**

**Bids Open: May 9, 2001  
Dated: April 2, 2001**

**OSD**

\*\*\*\*\*

# IMPORTANT SPECIAL NOTICES

\*\*\*\*\*

- The Special Provisions for Federal-aid projects (with and without DBE goals) have been revised to incorporate changes made by new regulations governing the DBE Program (49 CFR Part 26).

Sections 2 and 5 incorporate the changes. Bidders should read these sections to become familiar with them. Attention is directed to the following significant changes:

Section 2, "Disadvantaged Business Enterprise (DBE)" revises the counting of participation by DBE primes, and the counting of trucking performed by DBE firms. The section also revises the information that must be submitted to the Department in order to receive credit for trucking.

Section 2, "Submission of DBE Information" revises the information required to be submitted to the Department to receive credit toward the DBE goal. It also revises the criteria to demonstrate good faith efforts.

Section 5, "Subcontractor and DBE Records" revises the information required to be reported at the end of the project, and information related to trucking that must be submitted throughout the project.

Section 5, "DBE Certification Status" adds new reporting requirements related to DBE certification.

Section 5, "Subcontracting" describes the efforts that must be made in the event a DBE subcontractor is terminated or fails to complete its work for any reason.

Section 5, "Prompt Progress Payment to Subcontractors" requires prompt payment to all subcontractors.

Section 5, "Prompt Payment of Withheld Funds to Subcontractors" requires the prompt payment of retention to all subcontractors.

- **Payment Bonds**  
Attention is directed to Section 5 of the Special Provisions, regarding contract bonds. The payment bond shall be in a sum not less than one hundred percent of the total amount payable by the terms of the contract.



# TABLE OF CONTENTS

NOTICE TO CONTRACTORS.....	1
COPY OF ENGINEER'S ESTIMATE .....	3
SPECIAL PROVISIONS .....	6
SECTION 1. SPECIFICATIONS AND PLANS .....	6
SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS.....	6
2-1.01 GENERAL.....	6
2-1.015 FEDERAL LOBBYING RESTRICTIONS.....	6
2-1.02 DISADVANTAGED BUSINESS ENTERPRISE (DBE).....	7
2-1.02A DBE GOAL FOR THIS PROJECT.....	8
2-1.02B SUBMISSION OF DBE INFORMATION .....	9
SECTION 3. AWARD AND EXECUTION OF CONTRACT.....	10
SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES .....	10
SECTION 5. GENERAL .....	10
SECTION 5-1. MISCELLANEOUS .....	10
5-1.01 PLANS AND WORKING DRAWINGS .....	10
5-1.011 EXAMINATION OF PLANS, SPECIFICATIONS, CONTRACT, AND SITE OF WORK .....	11
5-1.012 DIFFERING SITE CONDITIONS.....	11
5-1.015 LABORATORY .....	11
5-1.017 CONTRACT BONDS .....	11
5-1.018 EXCAVATION SAFETY PLANS .....	11
5-1.019 COST REDUCTION INCENTIVE.....	12
5-1.02 LABOR NONDISCRIMINATION.....	12
5-1.03 INTEREST ON PAYMENTS .....	12
5-1.031 FINAL PAYMENT AND CLAIMS.....	13
5-1.04 PUBLIC SAFETY .....	13
5-1.05 SURFACE MINING AND RECLAMATION ACT.....	14
5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES.....	14
5-1.07 YEAR 2000 COMPLIANCE.....	14
5-1.075 BUY AMERICA REQUIREMENTS.....	14
5-1.08 SUBCONTRACTOR AND DBE RECORDS .....	15
5-1.083 DBE CERTIFICATION STATUS .....	15
5-1.086 PERFORMANCE OF DBE SUBCONTRACTORS AND SUPPLIERS .....	15
5-1.09 SUBCONTRACTING.....	16
5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS .....	16
5-1.102 PROMPT PAYMENT OF WITHHELD FUNDS TO SUBCONTRACTORS .....	16
5-1.11 PARTNERING .....	17
5-1.12 AREAS FOR CONTRACTOR'S USE.....	17
5-1.13 PAYMENTS.....	17
5-1.14 AERIALY DEPOSITED LEAD.....	17
SECTION 6. (BLANK).....	18
SECTION 7. (BLANK).....	18
SECTION 8. MATERIALS .....	18
SECTION 8-1. MISCELLANEOUS .....	18
8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS .....	18
8-1.02 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS .....	24
SECTION 8-2. CONCRETE.....	29
8-2.01 PORTLAND CEMENT CONCRETE.....	29
SECTION 8-3. (BLANK) .....	39
SECTION 9. (BLANK).....	39
SECTION 10. CONSTRUCTION DETAILS.....	39
SECTION 10-1. GENERAL .....	39
10-1.00 CONSTRUCTION PROJECT INFORMATION SIGNS .....	39
10-1.01 ORDER OF WORK.....	40
10-1.02 WATER POLLUTION CONTROL (STORM WATER POLLUTION PREVENTION PLAN) .....	40

STORM WATER POLLUTION PREVENTION PLAN PREPARATION, APPROVAL AND AMENDMENTS .....	41
COST BREAK-DOWN .....	42
SWPPP IMPLEMENTATION .....	43
MAINTENANCE .....	44
PAYMENT .....	45
10-1.03 PRESERVATION OF PROPERTY .....	46
10-1.04 DAMAGE REPAIR.....	46
10-1.05 COOPERATION .....	47
10-1.06 OBSTRUCTIONS .....	47
10-1.07 DUST CONTROL .....	47
10-1.08 MOBILIZATION .....	47
10-1.09 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES .....	47
10-1.10 CONSTRUCTION AREA SIGNS .....	48
10-1.11 MAINTAINING TRAFFIC.....	48
10-1.12 TEMPORARY CRASH CUSHION MODULE.....	49
GENERAL .....	49
MATERIALS.....	49
INSTALLATION .....	50
MEASUREMENT AND PAYMENT .....	50
10-1.13 EXISTING HIGHWAY FACILITIES .....	50
REMOVE ASPHALT CONCRETE DIKE .....	50
REMOVE CONCRETE CURB.....	50
10-1.14 EARTHWORK.....	50
10-1.15 MATERIAL CONTAINING AERIALY DEPOSITED LEAD .....	50
LEAD COMPLIANCE PLAN .....	51
EXCAVATION AND TRANSPORTATION PLAN .....	51
DUST CONTROL .....	52
MATERIAL TRANSPORTATION .....	52
MEASUREMENT AND PAYMENT .....	52
10-1.16 IRRIGATION CROSSOVERS .....	52
10-1.17 EXTEND IRRIGATION CROSSOVERS .....	52
10-1.18 MAINTENANCE VEHICLE PULLOUT.....	53
EARTHWORK.....	53
AGGREGATE BASE.....	53
MINOR CONCRETE (TEXTURE PAVING).....	53
MEASUREMENT .....	53
PAYMENT .....	54
10-1.19 ASPHALT CONCRETE .....	54
10-1.20 CHAIN LINK WALK GATE.....	54
SECTION 10-2. HIGHWAY PLANTING AND IRRIGATION SYSTEMS .....	54
10-2.01 GENERAL.....	54
PROGRESS INSPECTIONS.....	54
10-2.02 EXISTING HIGHWAY PLANTING .....	55
REMOVE EXISTING PLANTS FOR TRENCHING .....	55
PRUNE EXISTING PLANTS .....	55
10-2.03 EXISTING HIGHWAY IRRIGATION FACILITIES.....	56
LOCATE EXISTING CROSSOVERS AND CONDUITS.....	56
REMOVE EXISTING IRRIGATION FACILITIES.....	56
RELOCATE EXISTING IRRIGATION FACILITIES.....	56
10-2.04 HIGHWAY PLANTING.....	57
HIGHWAY PLANTING MATERIALS .....	57
ROADSIDE CLEARING .....	57
PESTICIDES .....	58
PREPARING PLANTING AREAS .....	58
PREPARE HOLES .....	59
PLANTING.....	59
ROOT PROTECTOR .....	59
PLANT ESTABLISHMENT WORK.....	59

10-2.05	IRRIGATION SYSTEMS .....	60
	VALVE BOXES.....	60
	IRRIGATION CONTROLLER.....	60
	FLOW SENSOR.....	62
	ARMOR-CLAD CONDUCTORS.....	62
	IRRIGATION SYSTEMS FUNCTIONAL TEST .....	62
	PIPE .....	63
	WATER METER.....	63
	BACKFLOW PREVENTER ASSEMBLIES.....	63
	BACKFLOW PREVENTER ASSEMBLY INSULATING BLANKET.....	64
	BACKFLOW PREVENTER ASSEMBLY ENCLOSURE .....	64
	SPRINKLERS.....	64
	FILTER ASSEMBLY UNIT .....	64
	BALL VALVE.....	65
	COMBINATION AIR AND VACUUM RELIEF VALVE.....	65
10-2.06	CHECK VALVES .....	65
	SPRING CHECK VALVES .....	65
	SWING CHECK VALVE .....	65
	FINAL IRRIGATION SYSTEM CHECK .....	65
10-2.07	BOOSTER PUMP .....	66
	MATERIALS LIST AND DRAWINGS .....	66
	PUMP PERFORMANCE REQUIREMENTS .....	66
	PUMP AND MOTOR.....	66
	PIPE, JOINTS AND FITTINGS.....	66
	FOUNDATIONS .....	66
	PRESSURE GAGES .....	67
	PUMP ENCLOSURE.....	67
	PUMP CONTROL.....	67
	PAYMENT .....	67
SECTION 10-3.	ELECTRICAL SYSTEMS .....	67
10-3.01	DESCRIPTION .....	67
10-3.02	COST BREAK-DOWN.....	67
10-3.03	CONDUIT .....	67
10-3.04	CONDUCTORS AND WIRING.....	68
10-3.05	SERVICE.....	68
	ELECTRIC SERVICE (IRRIGATION).....	68
10-3.06	IRRIGATION CONTROLLER ENCLOSURE CABINET.....	68
10-3.07	BOOSTER PUMP ELECTRICAL SYSTEM .....	69
	MATERIALS LIST AND DRAWINGS .....	69
	CONDUIT.....	69
	PULL BOXES .....	69
	CONDUCTORS AND WIRING.....	69
	BOOSTER PUMP CONTROL PANEL ENCLOSURE .....	70
	PAYMENT .....	72
SECTION 11.	(BLANK).....	72
SECTION 12.	(BLANK).....	72
SECTION 13.	RELATIONS WITH RAILROAD.....	72
SECTION 14	FEDERAL REQUIREMENTS FOR FEDERAL-AID CONSTRUCTION PROJECTS.....	73

# STANDARD PLANS LIST

The Standard Plan sheets applicable to this contract include, but are not limited to those indicated below. The Revised Standard Plans (RSP) and New Standard Plans (NSP) which apply to this contract are included as individual sheets of the project plans.

A10A	Abbreviations
A10B	Symbols
A20A	Pavement Markers and Traffic Lines, Typical Details
A85	Chain Link Fence
A87	Curbs, Dikes and Driveways
H1	Planting and Irrigation - Abbreviations
H2	Planting and Irrigation - Symbols
H8	Planting and Irrigation Details
T7	Construction Project Funding Identification Signs
T10	Traffic Control System for Lane Closure On Freeways and Expressways
RS1	Roadside Signs, Typical Installation Details No. 1
RS2	Roadside Signs - Wood Post, Typical Installation Details No. 2
ES-1A	Signal, Lighting and Electrical Systems - Symbols and Abbreviations
ES-1B	Signal, Lighting and Electrical Systems - Symbols and Abbreviations
ES-2A	Signal, Lighting and Electrical Systems - Service Equipment
ES-2C	Signal, Lighting and Electrical Systems - Service Equipment Notes, Type III Series
ES-2D	Signal, Lighting and Electrical Systems - Service Equipment and Typical Wiring Diagram Type III-A Series
ES-3H	Signal, Lighting and Electrical Systems – Irrigation Controller Enclosure Cabinet
ES-8	Signal, Lighting and Electrical Systems - Pull Box Details
ES-11	Signal, Lighting and Electrical Systems - Foundation Installations
ES-13A	Signal, Lighting and Electrical Systems - Splicing Details
ES-13B	Signal, Lighting and Electrical Systems - Wiring Details and Fuse Ratings

DEPARTMENT OF TRANSPORTATION

---

**NOTICE TO CONTRACTORS**

---

**CONTRACT NO. 06-404104**

**06-Fre-99-31.8/38.9**

Sealed proposals for the work shown on the plans entitled:

**STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROJECT PLANS FOR HIGHWAY PLANTING ON STATE HIGHWAY IN FRESNO COUNTY IN FRESNO FROM CALIFORNIA AVENUE OVERCROSSING TO NORTH FRESNO UNDERCROSSING**

will be received at the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, CA 95814, until 2 o'clock p.m. on May 9, 2001, at which time they will be publicly opened and read in Room 0100 at the same address.

Proposal forms for this work are included in a separate book entitled:

**STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROPOSAL AND CONTRACT FOR HIGHWAY PLANTING ON STATE HIGHWAY IN FRESNO COUNTY IN FRESNO FROM CALIFORNIA AVENUE OVERCROSSING TO NORTH FRESNO UNDERCROSSING**

General work description: Highway Planting to be performed and Irrigation System to be installed.

This project has a goal of 6 percent disadvantaged business enterprise (DBE) participation.

No prebid meeting is scheduled for this project.

**THIS PROJECT IS SUBJECT TO THE "BUY AMERICA" PROVISIONS OF THE SURFACE TRANSPORTATION ASSISTANCE ACT OF 1982 AS AMENDED BY THE INTERMODAL SURFACE TRANSPORTATION EFFICIENCY ACT OF 1991.**

Bids are required for the entire work described herein.

At the time this contract is awarded, the Contractor shall possess either a Class A license or one of the following Class C licenses: C-27.

This contract is subject to state contract nondiscrimination and compliance requirements pursuant to Government Code, Section 12990.

The Caltrans Central Region Construction Office is located at 850 L Street, Fresno, CA 93721-2615. The District Duty Senior for this project can be reached at (559) 445-6360, or by fax at (559) 445-6350. The Department will consider bidder inquiries only when a completed Bidder Inquiry Form is submitted. The Bidder Inquiry Form is available on the Internet at <http://www.dot.ca.gov/dist6/construction>. To the extent feasible and at the discretion of the Department, completed Bidder Inquiry Forms submitted for consideration will be investigated, and responses will be posted on the Internet at <http://www.dot.ca.gov/dist6/construction>.

Project plans, special provisions, and proposal forms for bidding this project can only be obtained at the Department of Transportation, Plans and Bid Documents, Room 0200, MS #26, Transportation Building, 1120 N Street, Sacramento, California 95814, FAX No. (916) 654-7028, Telephone No. (916) 654-4490. Use FAX orders to expedite orders for project plans, special provisions and proposal forms. FAX orders must include credit card charge number, card expiration date and authorizing signature. Project plans, special provisions, and proposal forms may be seen at the above Department of Transportation office and at the offices of the District Directors of Transportation at Irvine, Oakland, and the district in which the work is situated. Standard Specifications and Standard Plans are available through the State of California, Department of Transportation, Publications Unit, 1900 Royal Oaks Drive, Sacramento, CA 95815, Telephone No. (916) 445-3520.

Cross sections for this project are not available.

The successful bidder shall furnish a payment bond and a performance bond.

The Department of Transportation hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, disadvantaged business enterprises will be afforded full opportunity to submit bids in response to this invitation.

The U.S. Department of Transportation (DOT) provides a toll-free "hotline" service to report bid rigging activities. Bid rigging activities can be reported Mondays through Fridays, between 8:00 a.m. and 5:00 p.m., eastern time, Telephone No. 1-800-424-9071. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the "hotline" to report these activities. The "hotline" is part of the DOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

Pursuant to Section 1773 of the Labor Code, the general prevailing wage rates in the county, or counties, in which the work is to be done have been determined by the Director of the California Department of Industrial Relations. These wages are set forth in the General Prevailing Wage Rates for this project, available at the Labor Compliance Office at the offices of the District Director of Transportation for the district in which the work is situated, and available from the California Department of Industrial Relations' Internet Web Site at: <http://www.dir.ca.gov>. The Federal minimum wage rates for this project as predetermined by the United States Secretary of Labor are set forth in the books issued for bidding purposes entitled "Proposal and Contract," and in copies of this book that may be examined at the offices described above where project plans, special provisions, and proposal forms may be seen. Addenda to modify the Federal minimum wage rates, if necessary, will be issued to holders of "Proposal and Contract" books. Future effective general prevailing wage rates which have been predetermined and are on file with the California Department of Industrial Relations are referenced but not printed in the general prevailing wage rates.

Attention is directed to the Federal minimum wage rate requirements in the books entitled "Proposal and Contract." If there is a difference between the minimum wage rates predetermined by the Secretary of Labor and the general prevailing wage rates determined by the Director of the California Department of Industrial Relations for similar classifications of labor, the Contractor and subcontractors shall pay not less than the higher wage rate. The Department will not accept lower State wage rates not specifically included in the Federal minimum wage determinations. This includes "helper" (or other classifications based on hours of experience) or any other classification not appearing in the Federal wage determinations. Where Federal wage determinations do not contain the State wage rate determination otherwise available for use by the Contractor and subcontractors, the Contractor and subcontractors shall pay not less than the Federal minimum wage rate which most closely approximates the duties of the employees in question.

DEPARTMENT OF TRANSPORTATION

Deputy Director Transportation Engineering

Dated April 2, 2001

LSB

**COPY OF ENGINEER'S ESTIMATE  
(NOT TO BE USED FOR BIDDING PURPOSES)**

**06-404104**

Item	Item Code	Item	Unit of Measure	Estimated Quantity
1	074019	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	LUMP SUM
2	074020	WATER POLLUTION CONTROL	LS	LUMP SUM
3 (S)	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM
4 (S)	150771	REMOVE ASPHALT CONCRETE DIKE	M	26
5 (S)	153214	REMOVE CONCRETE CURB	M	420
6	021067	REMOVE EXISTING PLANTS	LS	LUMP SUM
7	190103	ROADWAY EXCAVATION (TYPE Y) (AERIALY DEPOSITED LEAD	M3	316
8	190110	LEAD COMPLIANCE PLAN	LS	LUMP SUM
9	200002	ROADSIDE CLEARING	LS	LUMP SUM
10	200052	PRUNE EXISTING PLANTS	LS	LUMP SUM
11	205061	ROOT PROTECTOR	EA	230
12	202011	MULCH	M3	830
13	021068	COMMERCIAL FERTILIZER (PACKET)	EA	4310
14	204008	PLANT (GROUP H)	EA	3860
15	204035	PLANT (GROUP A)	EA	2360
16	204036	PLANT (GROUP B)	EA	650
17	204099	PLANT ESTABLISHMENT WORK	LS	LUMP SUM
18	206560	CONTROL AND NEUTRAL CONDUCTORS	LS	LUMP SUM
19	206614	50 MM ELECTRIC REMOTE CONTROL VALVE	EA	33
20	206616	75 MM ELECTRIC REMOTE CONTROL VALVE	EA	2

Item	Item Code	Item	Unit of Measure	Estimated Quantity
21	021069	50 MM PRESSURE REDUCING VALVE	EA	20
22	021070	24 STATION EICON SATELLITE FIELD UNIT	EA	2
23 (F)	208249	20 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	7199
24 (F)	208250	25 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	2553
25 (F)	208251	32 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	1980
26 (F)	208252	40 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	1156
27 (F)	208253	50 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	2927
28 (F)	208254	65 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	1310
29 (F)	208255	75 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	2275
30 (F)	208288	50 MM PLASTIC PIPE (PR 315) (SUPPLY LINE)	M	30
31 (F)	208291	75 MM PLASTIC PIPE (PR 315) (SUPPLY LINE)	M	143
32	208304	WATER METER	EA	2
33	208420	BACKFLOW PREVENTER ASSEMBLY	EA	2
34	208421	BACKFLOW PREVENTER ASSEMBLY ENCLOSURE	EA	2
35	208461	SPRINKLER (TYPE A-1)	EA	160
36	208471	SPRINKLER (TYPE B-1)	EA	210
37	208483	SPRINKLER (TYPE C-3)	EA	3230
38	208493	75 MM GATE VALVE	EA	14
39	021071	COMBINATION AIR AND VACUUM RELIEF VALVE	EA	1
40	208560	FILTER ASSEMBLY UNIT	EA	13

Item	Item Code	Item	Unit of Measure	Estimated Quantity
41	021072	FLOW SENSOR	EA	5
42	208670	CHECK VALVE	EA	35
43	208683	BALL VALVE	EA	15
44	208798	200 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	M	10
45	208800	300 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	M	150
46	021073	EXTEND 300 MM CONDUIT	M	7
47 (S)	209503	BOOSTER PUMP SYSTEM	EA	10
48 (S)	209801	MAINTENANCE VEHICLE PULLOUT	M2	1051
49 (S)	390101	ASPHALT CONCRETE	TONN	28
50 (S)	394001	PLACE ASPHALT CONCRETE DIKE	M	450
51 (S)	802590	1.8 M CHAIN LINK GATE (TYPE CL-1.8)	EA	4
52 (S)	860640	IRRIGATION CONTROLLER ENCLOSURE CABINET	EA	2
53 (S)	860797	ELECTRIC SERVICE (IRRIGATION)	LS	LUMP SUM
54 (S)	860798	BOOSTER PUMP ELECTRICAL SYSTEM	LS	LUMP SUM
55	999990	MOBILIZATION	LS	LUMP SUM

**STATE OF CALIFORNIA**  
**DEPARTMENT OF TRANSPORTATION**

---

**SPECIAL PROVISIONS**

**Annexed to Contract No. 06-404104**

**SECTION 1. SPECIFICATIONS AND PLANS**

The work embraced herein shall conform to the provisions in the Standard Specifications dated July 1999, and the Standard Plans dated July 1999, of the Department of Transportation insofar as the same may apply, and these special provisions.

Amendments to the Standard Specifications set forth in these special provisions shall be considered as part of the Standard Specifications for the purposes set forth in Section 5-1.04, "Coordination and Interpretation of Plans, Standard Specifications and Special Provisions," of the Standard Specifications. Whenever either the term "Standard Specifications is amended" or the term "Standard Specifications are amended" is used in the special provisions, the indented text or table following the term shall be considered an amendment to the Standard Specifications. In case of conflict between such amendments and the Standard Specifications, the amendments shall take precedence over and be used in lieu of the conflicting portions.

In case of conflict between the Standard Specifications and these special provisions, the special provisions shall take precedence over and shall be used in lieu of the conflicting portions.

**SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS**

**2-1.01 GENERAL**

The bidder's attention is directed to the provisions in Section 2, "Proposal Requirements and Conditions," of the Standard Specifications and these special provisions for the requirements and conditions which the bidder must observe in the preparation of the Proposal form and the submission of the bid.

In addition to the subcontractors required to be listed in conformance with Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications, each proposal shall have listed therein the portion of work that will be performed by each subcontractor listed.

The Bidder's Bond form mentioned in the last paragraph in Section 2-1.07, "Proposal Guaranty," of the Standard Specifications will be found following the signature page of the Proposal.

Submit request for substitution of an "or equal" item, and the data substantiating the request to the Department of Transportation, Central Region Construction, P.O. Box 12616, Fresno, CA 93778, so that the request is received by the Department by close of business on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening.

In conformance with Public Contract Code Section 7106, a Noncollusion Affidavit is included in the Proposal. Signing the Proposal shall also constitute signature of the Noncollusion Affidavit.

The contractor, sub recipient or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR part 26 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate. Each subcontract signed by the bidder must include this assurance.

**2-1.015 FEDERAL LOBBYING RESTRICTIONS**

Section 1352, Title 31, United States Code prohibits Federal funds from being expended by the recipient or any lower tier subrecipient of a Federal-aid contract to pay for any person for influencing or attempting to influence a Federal agency or Congress in connection with the awarding of any Federal-aid contract, the making of any Federal grant or loan, or the entering into of any cooperative agreement.

If any funds other than Federal funds have been paid for the same purposes in connection with this Federal-aid contract, the recipient shall submit an executed certification and, if required, submit a completed disclosure form as part of the bid documents.

A certification for Federal-aid contracts regarding payment of funds to lobby Congress or a Federal agency is included in the Proposal. Standard Form - LLL, "Disclosure of Lobbying Activities," with instructions for completion of the Standard Form is also included in the Proposal. Signing the Proposal shall constitute signature of the Certification.

The above-referenced certification and disclosure of lobbying activities shall be included in each subcontract and any lower-tier contracts exceeding \$100,000. All disclosure forms, but not certifications, shall be forwarded from tier to tier until received by the Engineer.

The Contractor, subcontractors and any lower-tier contractors shall file a disclosure form at the end of each calendar quarter in which there occurs any event that requires disclosure or that materially affects the accuracy of the information contained in any disclosure form previously filed by the Contractor, subcontractors and any lower-tier contractors. An event that materially affects the accuracy of the information reported includes:

- A. A cumulative increase of \$25,000 or more in the amount paid or expected to be paid for influencing or attempting to influence a covered Federal action; or
- B. A change in the person(s) or individual(s) influencing or attempting to influence a covered Federal action; or,
- C. A change in the officer(s), employee(s), or Member(s) contacted to influence or attempt to influence a covered Federal action.

### **2-1.02 DISADVANTAGED BUSINESS ENTERPRISE (DBE)**

This project is subject to Part 26, Title 49, Code of Federal Regulations entitled "Participation by Disadvantaged Business Enterprises in Department of Transportation Financial Assistance Programs." The Regulations in their entirety are incorporated herein by this reference.

Bidders shall be fully informed respecting the requirements of the Regulations and the Department's Disadvantaged Business Enterprise (DBE) program developed pursuant to the Regulations; particular attention is directed to the following matters:

- A. A DBE must be a small business concern as defined pursuant to Section 3 of U.S. Small Business Act and relevant regulations promulgated pursuant thereto.
- B. A DBE may participate as a prime contractor, subcontractor, joint venture partner with a prime or subcontractor, vendor of material or supplies, or as a trucking company.
- C. A DBE bidder, not bidding as a joint venture with a non-DBE, will be required to document one or a combination of the following:
  - 1. The bidder will meet the goal by performing work with its own forces.
  - 2. The bidder will meet the goal through work performed by DBE subcontractors, suppliers or trucking companies.
  - 3. The bidder, prior to bidding, made adequate good faith efforts to meet the goal.
- D. A DBE joint venture partner must be responsible for specific contract items of work, or portions thereof. Responsibility means actually performing, managing and supervising the work with its own forces. The DBE joint venture partner must share in the capital contribution, control, management, risks and profits of the joint venture. The DBE joint venturer must submit the joint venture agreement with the proposal or the DBE Information form required in the Section entitled "Submission of DBE Information" of these special provisions.
- E. A DBE must perform a commercially useful function, i.e., must be responsible for the execution of a distinct element of the work and must carry out its responsibility by actually performing, managing and supervising the work.
- F. DBEs must be certified by either the California Department of Transportation, or by a participating State of California or local agency which certifies in conformance with Title 49, Code of Federal Regulations, Part 26, as of the date of bid opening. It is the Contractor's responsibility to verify that DBEs are certified. Listings of DBEs certified by the Department are available from the following sources:
  - 1. The Department's DBE Directory, which is published quarterly. This Directory may be obtained from the Department of Transportation, Materiel Operations Branch, Publication Distribution Unit, 1900 Royal Oaks Drive, Sacramento, California 95815, Telephone: (916) 445-3520.
  - 2. The Department's Electronic Information Bulletin Board Service, which is accessible by modem and is updated weekly. The Bulletin Board may be accessed by first contacting the Department's Business Enterprise Program at Telephone: (916) 227-8937 and obtaining a user identification and password.
  - 3. The Department's web site at <http://www.dot.ca.gov/hq/bep/index.htm>.
  - 4. The organizations listed in the Section entitled "DBE Goal for this Project" of these special provisions.

G. Credit for materials or supplies purchased from DBEs will be as follows:

1. If the materials or supplies are obtained from a DBE manufacturer, 100 percent of the cost of the materials or supplies will count toward the DBE goal. A DBE manufacturer is a firm that operates or maintains a factory or establishment that produces, on the premises, the materials, supplies, articles, or equipment required under the contract and of the general character described by the specifications.
2. If the materials or supplies are purchased from a DBE regular dealer, 60 percent of the cost of the materials or supplies will count toward the DBE goal. A DBE regular dealer is a firm that owns, operates, or maintains a store, warehouse, or other establishment in which the materials, supplies, articles or equipment of the general character described by the specifications and required under the contract are bought, kept in stock, and regularly sold or leased to the public in the usual course of business. To be a DBE regular dealer, the firm must be an established, regular business that engages, as its principal business and under its own name, in the purchase and sale or lease of the products in question. A person may be a DBE regular dealer in such bulk items as petroleum products, steel, cement, gravel, stone, or asphalt without owning, operating, or maintaining a place of business as provided in this paragraph G.2. if the person both owns and operates distribution equipment for the products. Any supplementing of regular dealers' own distribution equipment shall be by a long-term lease agreement and not on an ad hoc or contract-by-contract basis. Packagers, brokers, manufacturers' representatives, or other persons who arrange or expedite transactions are not DBE regular dealers within the meaning of this paragraph G.2.
3. Credit for materials or supplies purchased from a DBE which is neither a manufacturer nor a regular dealer will be limited to the entire amount of fees or commissions charged for assistance in the procurement of the materials and supplies, or fees or transportation charges for the delivery of materials or supplies required on a job site, provided the fees are reasonable and not excessive as compared with fees charged for similar services.

H. Credit for DBE trucking companies will be as follows:

1. The DBE must be responsible for the management and supervision of the entire trucking operation for which it is responsible on a particular contract, and there cannot be a contrived arrangement for the purpose of meeting the DBE goal.
2. The DBE must itself own and operate at least one fully licensed, insured, and operational truck used on the contract.
3. The DBE receives credit for the total value of the transportation services it provides on the contract using trucks it owns, insures, and operates using drivers it employs.
4. The DBE may lease trucks from another DBE firm, including an owner-operator who is certified as a DBE. The DBE who leases trucks from another DBE receives credit for the total value of the transportation services the lessee DBE provides on the contract.
5. The DBE may also lease trucks from a non-DBE firm, including an owner-operator. The DBE who leases trucks from a non-DBE is entitled to credit only for the fee or commission it receives as a result of the lease arrangement. The DBE does not receive credit for the total value of the transportation services provided by the lessee, since these services are not provided by a DBE.
6. For the purposes of this paragraph H, a lease must indicate that the DBE has exclusive use of and control over the truck. This does not preclude the leased truck from working for others during the term of the lease with the consent of the DBE, so long as the lease gives the DBE absolute priority for use of the leased truck. Leased trucks must display the name and identification number of the DBE.

I. Noncompliance by the Contractor with the requirements of the regulations constitutes a breach of this contract and may result in termination of the contract or other appropriate remedy for a breach of this contract.

J. Bidders are encouraged to use services offered by financial institutions owned and controlled by DBEs.

#### **2-1.02A DBE GOAL FOR THIS PROJECT**

The Department has established the following goal for Disadvantaged Business Enterprise (DBE) participation for this project:

Disadvantaged Business Enterprise (DBE): 6 percent

Bidders may use the services of the following firms to contact interested DBEs. These firms are available to assist DBEs in preparing bids for subcontracting or supplying materials.

The following firms may be contacted for projects in the following locations:

Districts 04, 05 (except San Luis Obispo and Santa Barbara Counties), 06 (except Kern County) and 10:
Triaxial Management Services, Inc. - Oakland  1545 Willow Street, 1st Floor Oakland, CA 94607 Telephone - (510) 286-1313 FAX No. - (510) 286-6792

Districts 08, 11 and 12:
Triaxial Management Services, Inc. - San Diego 2725 Congress Street, Suite 1-D San Diego, CA 92110 Telephone - (619) 543-5109 FAX No. - (619) 543-5108

Districts 07 and 08; in San Luis Obispo and Santa Barbara Counties in District 05; and in Kern County in District 06:
Triaxial Management Services, Inc. - Los Angeles 2594 Industry Way, Suite 101 Lynwood, CA 90262 Telephone - (310) 537-6677 FAX No. - (310) 637-0128

Districts 01, 02, 03 and 09:
Triaxial Management Services, Inc. - Sacramento 930 Alhambra Blvd., #205 Sacramento, CA 95816 Telephone - (916) 553-4172 FAX No. - (916) 553-4173

**2-1.02B SUBMISSION OF DBE INFORMATION**

The required DBE information shall be submitted on the "CALTRANS BIDDER - DBE INFORMATION" form included in the Proposal. If the DBE information is not submitted with the bid, the DBE Information form shall be removed from the documents prior to submitting the bid.

It is the bidder's responsibility to make enough work available to DBEs and to select those portions of the work or material needs consistent with the available DBEs to meet the goal for DBE participation or to provide information to establish that, prior to bidding, the bidder made adequate good faith efforts to do so.

If DBE information is not submitted with the bid, the apparent successful bidder (low bidder), the second low bidder and the third low bidder shall submit DBE information to the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, California 95814 so the information is received by the Department no later than 4:00 p.m. on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening. DBE information sent by U.S. Postal Service certified mail with return receipt and certificate of mailing and mailed on or before the third day, not including Saturdays, Sundays and legal holidays, following bid opening will be accepted even if it is received after the fourth day following bid opening. Failure to submit the required DBE information by the time specified will be grounds for finding the bid or proposal nonresponsive. Other bidders need not submit DBE information unless requested to do so by the Department.

The bidder's DBE information shall establish that good faith efforts to meet the DBE goal have been made. To establish good faith efforts, the bidder shall demonstrate that the goal will be met or that, prior to bidding, adequate good faith efforts to meet the goal were made.

Bidders are cautioned that even though their submittal indicates they will meet the stated DBE goal, their submittal should also include their adequate good faith efforts information along with their DBE goal information to protect their eligibility for award of the contract in the event the Department, in its review, finds that the goal has not been met.

The bidder's DBE information shall include the names, addresses and phone numbers of DBE firms that will participate, with a complete description of work or supplies to be provided by each, the dollar value of each DBE transaction, and a written confirmation from the DBE that it is participating in the contract. A copy of the DBE's quote will serve as written confirmation that the DBE is participating in the contract. When 100 percent of a contract item of work is not to be performed or furnished by a DBE, a description of the exact portion of that work to be performed or furnished by that DBE shall be included in the DBE information, including the planned location of that work. The work that a DBE prime contractor has committed to performing with its own forces as well as the work that it has committed to be performed by DBE subcontractors, suppliers and trucking companies will count toward the goal.

The information necessary to establish the bidder's adequate good faith efforts to meet the DBE goal should include:

- A. The names and dates of each publication in which a request for DBE participation for this project was placed by the bidder.
- B. The names and dates of written notices sent to certified DBEs soliciting bids for this project and the dates and methods used for following up initial solicitations to determine with certainty whether the DBEs were interested.
- C. The items of work which the bidder made available to DBE firms, including, where appropriate, any breaking down of the contract work items (including those items normally performed by the bidder with its own forces) into economically feasible units to facilitate DBE participation. It is the bidder's responsibility to demonstrate that sufficient work to meet the DBE goal was made available to DBE firms.
- D. The names, addresses and phone numbers of rejected DBE firms, the firms selected for that work, and the reasons for the bidder's choice.
- E. Efforts made to assist interested DBEs in obtaining bonding, lines of credit or insurance, and any technical assistance or information related to the plans, specifications and requirements for the work which was provided to DBEs.
- F. Efforts made to assist interested DBEs in obtaining necessary equipment, supplies, materials, or related assistance or services, excluding supplies and equipment the DBE subcontractor purchases or leases from the prime contractor or its affiliate.
- G. The names of agencies contacted to provide assistance in contacting, recruiting and using DBE firms.
- H. Any additional data to support a demonstration of good faith efforts.

### **SECTION 3. AWARD AND EXECUTION OF CONTRACT**

The bidder's attention is directed to the provisions in Section 3, "Award and Execution of Contract," of the Standard Specifications and these special provisions for the requirements and conditions concerning award and execution of contract.

The award of the contract, if it be awarded, will be to the lowest responsible bidder whose proposal complies with all the requirements prescribed and who has met the goal for DBE participation or has demonstrated, to the satisfaction of the Department, adequate good faith efforts to do so. Meeting the goal for DBE participation or demonstrating, to the satisfaction of the Department, adequate good faith efforts to do so is a condition for being eligible for award of contract.

A "Payee Data Record" form will be included in the contract documents to be executed by the successful bidder. The purpose of the form is to facilitate the collection of taxpayer identification data. The form shall be completed and returned to the Department by the successful bidder with the executed contract and contract bonds. For the purposes of the form, payee shall be deemed to mean the successful bidder. The form is not to be completed for subcontractors or suppliers. Failure to complete and return the "Payee Data Record" form to the Department as provided herein will result in the retention of 31 percent of payments due the contractor and penalties of up to \$20,000. This retention of payments for failure to complete the "Payee Data Record" form is in addition to any other retention of payments due the Contractor.

### **SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES**

Attention is directed to the provisions in Section 8-1.03, "Beginning of Work," in Section 8-1.06, "Time of Completion," and in Section 8-1.07, "Liquidated Damages," of the Standard Specifications and these special provisions.

The Contractor shall begin work within 15 calendar days after the contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department of Transportation.

This work shall be diligently prosecuted to completion before the expiration of **900 WORKING DAYS** beginning on the fifteenth calendar day after approval of the contract.

The Contractor shall pay to the State of California the sum of \$250 per day, for each and every calendar day's delay in finishing the work in excess of the number of working days prescribed above.

### **SECTION 5. GENERAL**

#### **SECTION 5-1. MISCELLANEOUS**

##### **5-1.01 PLANS AND WORKING DRAWINGS**

When the specifications require working drawings to be submitted to the Division of Structure Design, the drawings shall be submitted to: Division of Structure Design, Documents Unit, Mail Station 9, 1801 30th Street, Sacramento, CA 95816, Telephone 916 227-8252.

### **5-1.011 EXAMINATION OF PLANS, SPECIFICATIONS, CONTRACT, AND SITE OF WORK**

The second paragraph of Section 2-1.03, "Examination of Plans, Specifications, Contract, and Site of Work," of the Standard Specifications is amended to read:

- Where the Department has made investigations of site conditions, including subsurface conditions in areas where work is to be performed under the contract, or in other areas, some of which may constitute possible local material sources, bidders or Contractors may, upon written request, inspect the records of the Department as to those investigations subject to and upon the conditions hereinafter set forth.

Attention is directed to "Differing Site Conditions" of these special provisions regarding physical conditions at the site which may differ from those indicated in "Materials Information," log of test borings or other geotechnical information obtained by the Department's investigation of site conditions.

### **5-1.012 DIFFERING SITE CONDITIONS**

Attention is directed to Section 5-1.116, "Differing Site Conditions," of the Standard Specifications.

During the progress of the work, if subsurface or latent conditions are encountered at the site differing materially from those indicated in the "Materials Information," log of test borings, other geotechnical data obtained by the Department's investigation of subsurface conditions, or an examination of the conditions above ground at the site, the party discovering those conditions shall promptly notify the other party in writing of the specific differing conditions before they are disturbed and before the affected work is performed.

The Contractor will be allowed 15 days from the notification of the Engineer's determination of whether or not an adjustment of the contract is warranted, in which to file a notice of potential claim in conformance with the provisions of Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications and as specified herein; otherwise the decision of the Engineer shall be deemed to have been accepted by the Contractor as correct. The notice of potential claim shall set forth in what respects the Contractor's position differs from the Engineer's determination and provide any additional information obtained by the Contractor, including but not limited to additional geotechnical data. The notice of potential claim shall be accompanied by the Contractor's certification that the following were made in preparation of the bid: a review of the contract, a review of the "Materials Information," a review of the log of test borings and other records of geotechnical data to the extent they were made available to bidders prior to the opening of bids, and an examination of the conditions above ground at the site. Supplementary information, obtained by the Contractor subsequent to the filing of the notice of potential claim, shall be submitted to the Engineer in an expeditious manner.

### **5-1.015 LABORATORY**

When a reference is made in the specifications to the "Laboratory," the reference shall mean the Division of Materials Engineering and Testing Services and the Division of Structural Foundations of the Department of Transportation, or established laboratories of the various Districts of the Department, or other laboratories authorized by the Department to test materials and work involved in the contract. When a reference is made in the specifications to the "Transportation Laboratory," the reference shall mean the Division of Materials Engineering and Testing Services and the Division of Structural Foundations, located at 5900 Folsom Boulevard, Sacramento, CA 95819, Telephone (916) 227-7000.

### **5-1.017 CONTRACT BONDS**

Attention is directed to Section 3-1.02, "Contract Bonds," of the Standard Specifications and these special provisions.

The payment bond shall be in a sum not less than one hundred percent of the total amount payable by the terms of the contract.

### **5-1.018 EXCAVATION SAFETY PLANS**

Section 5-1.02A, "Trench Excavation Safety Plans," of the Standard Specifications is amended to read:

#### **5-1.02A Excavation Safety Plans**

- The Construction Safety Orders of the Division of Occupational Safety and Health shall apply to all excavations. For all excavations 1.5 m or more in depth, the Contractor shall submit to the Engineer a detailed plan showing the design and details of the protective systems to be provided for worker protection from the hazard of caving ground during excavation. The detailed plan shall include any tabulated data and any design calculations used in the preparation of the plan. Excavation shall not begin until the detailed plan has been reviewed and approved by the Engineer.

- Detailed plans of protective systems for which the Construction Safety Orders require design by a registered professional engineer shall be prepared and signed by an engineer who is registered as a Civil Engineer in the State of California, and shall include the soil classification, soil properties, soil design calculations that demonstrate adequate stability of the protective system, and any other design calculations used in the preparation of the plan.
- No plan shall allow the use of a protective system less effective than that required by the Construction Safety Orders.
- If the detailed plan includes designs of protective systems developed only from the allowable configurations and slopes, or Appendices, contained in the Construction Safety Orders, the plan shall be submitted at least 5 days before the Contractor intends to begin excavation. If the detailed plan includes designs of protective systems developed from tabulated data, or designs for which design by a registered professional engineer is required, the plan shall be submitted at least 3 weeks before the Contractor intends to begin excavation.
- Attention is directed to Section 7-1.01E, "Trench Safety."

The third paragraph of Section 19-1.02, "Preservation of Property," of the Standard Specifications is amended to read:

- In addition to the provisions in Sections 5-1.02, "Plans and Working Drawings," and 5-1.02A, "Excavation Safety Plans," detailed plans of the protective systems for excavations on or affecting railroad property will be reviewed for adequacy of protection provided for railroad facilities, property, and traffic. These plans shall be submitted at least 9 weeks before the Contractor intends to begin excavation requiring the protective systems. Approval by the Engineer of the detailed plans for the protective systems will be contingent upon the plans being satisfactory to the railroad company involved.

#### **5-1.019 COST REDUCTION INCENTIVE**

Attention is directed to Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications.

Prior to preparing a cost reduction proposal, the Contractor shall request a meeting with the Engineer to discuss the proposal in concept and to determine the merit of the cost reduction proposal. Items of discussion will also include permit issues, impact on other projects, impact on the project schedule, peer reviews, and review times required by the Department and other agencies.

#### **5-1.02 LABOR NONDISCRIMINATION**

Attention is directed to the following Notice that is required by Chapter 5 of Division 4 of Title 2, California Code of Regulations.

### **NOTICE OF REQUIREMENT FOR NONDISCRIMINATION PROGRAM**

#### **(GOV. CODE, SECTION 12990)**

Your attention is called to the "Nondiscrimination Clause", set forth in Section 7-1.01A(4), "Labor Nondiscrimination," of the Standard Specifications, which is applicable to all nonexempt State contracts and subcontracts, and to the "Standard California Nondiscrimination Construction Contract Specifications" set forth therein. The specifications are applicable to all nonexempt State construction contracts and subcontracts of \$5000 or more.

#### **5-1.03 INTEREST ON PAYMENTS**

Interest shall be payable on progress payments, payments after acceptance, final payments, extra work payments, and claim payments as follows:

- A. Unpaid progress payments, payment after acceptance, and final payments shall begin to accrue interest 30 days after the Engineer prepares the payment estimate.
- B. Unpaid extra work bills shall begin to accrue interest 30 days after preparation of the first pay estimate following receipt of a properly submitted and undisputed extra work bill. To be properly submitted, the bill must be submitted within 7 days of the performance of the extra work and in conformance with the provisions in Section 9-1.03C, "Records," and Section 9-1.06, "Partial Payments," of the Standard Specifications. An undisputed extra work bill not submitted within 7 days of performance of the extra work will begin to accrue interest 30 days after the preparation of the second pay estimate following submittal of the bill.
- C. The rate of interest payable for unpaid progress payments, payments after acceptance, final payments, and extra work payments shall be 10 percent per annum.
- D. The rate of interest payable on a claim, protest or dispute ultimately allowed under this contract shall be 6 percent per annum. Interest shall begin to accrue 61 days after the Contractor submits to the Engineer information in sufficient detail to enable the Engineer to ascertain the basis and amount of said claim, protest or dispute.

The rate of interest payable on any award in arbitration shall be 6 percent per annum if allowed under the provisions of Civil Code Section 3289.

#### **5-1.031 FINAL PAYMENT AND CLAIMS**

Attention is directed to Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications.

The District that administers the contract shall submit a claim position letter to the Contractor within 135 days after acceptance of the contract. After receipt of the claim position letter from the District, or 135 days after acceptance of the contract, whichever occurs first, the Contractor may request a meeting with the person or board designated by the District Director to review claims that remain in dispute. If the Contractor requests a meeting, the review person or board shall meet with the Contractor within 45 days after the request is received.

#### **5-1.04 PUBLIC SAFETY**

The Contractor shall provide for the safety of traffic and the public in conformance with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications and these special provisions.

The Contractor shall install temporary railing (Type K) between a lane open to public traffic and an excavation, obstacle or storage area when the following conditions exist:

- A. Excavations.—The near edge of the excavation is 3.6 m or less from the edge of the lane, except:
  - 1. Excavations covered with sheet steel or concrete covers of adequate thickness to prevent accidental entry by traffic or the public.
  - 2. Excavations less than 0.3-m deep.
  - 3. Trenches less than 0.3-m wide for irrigation pipe or electrical conduit, or excavations less than 0.3-m in diameter.
  - 4. Excavations parallel to the lane for the purpose of pavement widening or reconstruction.
  - 5. Excavations in side slopes, where the slope is steeper than 1:4 (vertical:horizontal).
  - 6. Excavations protected by existing barrier or railing.
- B. Temporarily Unprotected Permanent Obstacles.—The work includes the installation of a fixed obstacle together with a protective system, such as a sign structure together with protective railing, and the Contractor elects to install the obstacle prior to installing the protective system; or the Contractor, for the Contractor's convenience and with permission of the Engineer, removes a portion of an existing protective railing at an obstacle and does not replace such railing complete in place during the same day.
- C. Storage Areas.—Material or equipment is stored within 3.6 m of the lane and the storage is not otherwise prohibited by the provisions of the Standard Specifications and these special provisions.

The approach end of temporary railing (Type K), installed in conformance with the provisions in this section "Public Safety" and in Section 7-1.09, "Public Safety," of the Standard Specifications, shall be offset a minimum of 4.6 m from the edge of the traffic lane open to public traffic. The temporary railing shall be installed on a skew toward the edge of the traffic lane of not more than 0.3-m transversely to 3 m longitudinally with respect to the edge of the traffic lane. If the 4.6-m minimum offset cannot be achieved, the temporary railing shall be installed on the 10 to 1 skew to obtain the maximum available offset between the approach end of the railing and the edge of the traffic lane, and an array of temporary crash cushion modules shall be installed at the approach end of the temporary railing.

Temporary railing (Type K) shall conform to the provisions in Section 12-3.08, "Temporary Railing (Type K)," of the Standard Specifications. Temporary railing (Type K), conforming to the details shown on 1999 Standard Plan T3, may be used. Temporary railing (Type K) fabricated prior to January 1, 1993, and conforming to 1988 Standard Plan B11-30 may be used, provided the fabrication date is printed on the required Certificate of Compliance.

Temporary crash cushion modules shall conform to the provisions in "Temporary Crash Cushion Module" of these special provisions.

Except for installing, maintaining and removing traffic control devices, whenever work is performed or equipment is operated in the following work areas, the Contractor shall close the adjacent traffic lane unless otherwise provided in the Standard Specifications and these special provisions:

Approach Speed of Public Traffic (Posted Limit) (Kilometers Per Hour)	Work Areas
Over 72 (45 Miles Per Hour)	Within 1.8 m of a traffic lane but not on a traffic lane
56 to 72 (35 to 45 Miles Per Hour)	Within 0.9-m of a traffic lane but not on a traffic lane

The lane closure provisions of this section shall not apply if the work area is protected by permanent or temporary railing or barrier.

When traffic cones or delineators are used to delineate a temporary edge of a traffic lane, the line of cones or delineators shall be considered to be the edge of the traffic lane, however, the Contractor shall not reduce the width of an existing lane to less than 3 m without written approval from the Engineer.

When work is not in progress on a trench or other excavation that required closure of an adjacent lane, the traffic cones or portable delineators used for the lane closure shall be placed off of and adjacent to the edge of the traveled way. The spacing of the cones or delineators shall be not more than the spacing used for the lane closure.

Suspended loads or equipment shall not be moved nor positioned over public traffic or pedestrians.

Full compensation for conforming to the provisions in this section "Public Safety," including furnishing and installing temporary railing (Type K) and temporary crash cushion modules, shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

#### **5-1.05 SURFACE MINING AND RECLAMATION ACT**

Attention is directed to the Surface Mining and Reclamation Act of 1975, commencing in Public Resources Code, Mining and Geology, Section 2710, which establishes regulations pertinent to surface mining operations, and to California Public Contract Code Section 10295.5.

Material from mining operations furnished for this project shall only come from permitted sites in compliance with California Public Contract Code Section 10295.5.

The requirements of this section shall apply to materials furnished for the project, except for acquisition of materials in conformance with the provisions in Section 4-1.05, "Use of Materials Found on the Work," of the Standard Specifications.

#### **5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES**

When the presence of asbestos or hazardous substances are not shown on the plans or indicated in the specifications and the Contractor encounters materials which the Contractor reasonably believes to be asbestos or a hazardous substance as defined in Section 25914.1 of the Health and Safety Code, and the asbestos or hazardous substance has not been rendered harmless, the Contractor may continue work in unaffected areas reasonably believed to be safe. The Contractor shall immediately cease work in the affected area and report the condition to the Engineer in writing.

In conformance with Section 25914.1 of the Health and Safety Code, removal of asbestos or hazardous substances including exploratory work to identify and determine the extent of the asbestos or hazardous substance will be performed by separate contract.

If delay of work in the area delays the current controlling operation, the delay will be considered a right of way delay and the Contractor will be compensated for the delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

#### **5-1.07 YEAR 2000 COMPLIANCE**

This contract is subject to Year 2000 Compliance for automated devices in the State of California.

Year 2000 compliance for automated devices in the State of California is achieved when embedded functions have or create no logical or mathematical inconsistencies when dealing with dates prior to and beyond 1999. The year 2000 is recognized and processed as a leap year. The product shall operate accurately in the manner in which the product was intended for date operation without requiring manual intervention.

The Contractor shall provide the Engineer a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for all automated devices furnished for the project.

#### **5-1.075 BUY AMERICA REQUIREMENTS**

Attention is directed to the "Buy America" requirements of the Surface Transportation Assistance Act of 1982 (Section 165) and the Intermodal Surface Transportation Efficiency Act of 1991 (ISTEA) Sections 1041(a) and 1048(a), and the regulations adopted pursuant thereto. In conformance with the law and regulations, all manufacturing processes for steel and iron materials furnished for incorporation into the work on this project shall occur in the United States; with the exception that pig iron and processed, pelletized and reduced iron ore manufactured outside of the United States may be used in the domestic manufacturing process for such steel and iron materials. The application of coatings, such as epoxy coating,

galvanizing, painting, and other coatings that protect or enhance the value of steel or iron materials shall be considered a manufacturing process subject to the "Buy America" requirements.

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications shall be furnished for steel and iron materials. The certificates, in addition to certifying that the materials comply with the specifications, shall specifically certify that all manufacturing processes for the materials occurred in the United States, except for the above exceptions.

The requirements imposed by the law and regulations do not prevent a minimal use of foreign steel and iron materials if the total combined cost of the materials used does not exceed one-tenth of one percent (0.1 percent) of the total contract cost or \$2500, whichever is greater. The Contractor shall furnish the Engineer acceptable documentation of the quantity and value of the foreign steel and iron prior to incorporating the materials into the work.

#### **5-1.08 SUBCONTRACTOR AND DBE RECORDS**

The Contractor shall maintain records showing the name and business address of each first-tier subcontractor. The records shall also show the name and business address of every DBE subcontractor, DBE vendor of materials and DBE trucking company, regardless of tier. The records shall show the date of payment and the total dollar figure paid to all of these firms. DBE prime contractors shall also show the date of work performed by their own forces along with the corresponding dollar value of the work.

Upon completion of the contract, a summary of these records shall be prepared on Form CEM-2402 (F) and certified correct by the Contractor or the Contractor's authorized representative, and shall be furnished to the Engineer. The form shall be furnished to the Engineer within 90 days from the date of contract acceptance. \$10,000 will be withheld from payment until the Form CEM-2402 (F) is submitted. The amount will be returned to the Contractor when a satisfactory Form CEM-2402 (F) is submitted.

Prior to the fifteenth of each month, the Contractor shall submit documentation to the Engineer showing the amount paid to DBE trucking companies listed in the Contractor's DBE information. This monthly documentation shall indicate the portion of the revenue paid to DBE trucking companies which is claimed toward DBE participation. The Contractor shall also obtain and submit documentation to the Engineer showing the amount paid by DBE trucking companies to all firms, including owner-operators, for the leasing of trucks. The DBE who leases trucks from a non-DBE is entitled to credit only for the fee or commission it receives as a result of the lease arrangement. The records must confirm that the amount of credit claimed toward DBE participation conforms with Section 2-1.02, "Disadvantaged Business Enterprise," of these special provisions.

The Contractor shall also obtain and submit documentation to the Engineer showing the truck number, owner's name, California Highway Patrol CA number, and if applicable, the DBE certification number of the owner of the truck for all trucks used during that month for which DBE participation will be claimed. This documentation shall be submitted on Form CEM-2404 (F).

#### **5-1.083 DBE CERTIFICATION STATUS**

If a DBE subcontractor is decertified during the life of the project, the decertified subcontractor shall notify the Contractor in writing with the date of decertification. If a subcontractor becomes a certified DBE during the life of the project, the subcontractor shall notify the Contractor in writing with the date of certification. The Contractor shall furnish the written documentation to the Engineer.

Upon completion of the contract, Form CEM-2403 (F) indicating the DBE's existing certification status shall be signed and certified correct by the Contractor. The certified form shall be furnished to the Engineer within 90 days from the date of contract acceptance.

#### **5-1.086 PERFORMANCE OF DBE SUBCONTRACTORS AND SUPPLIERS**

The DBEs listed by the Contractor in response to the provisions in Section 2-1.02B, "Submission of DBE Information," and Section 3, "Award and Execution of Contract," of these special provisions, which are determined by the Department to be certified DBEs, shall perform the work and supply the materials for which they are listed, unless the Contractor has received prior written authorization to perform the work with other forces or to obtain the materials from other sources.

Authorization to use other forces or sources of materials may be requested for the following reasons:

- A. The listed DBE, after having had a reasonable opportunity to do so, fails or refuses to execute a written contract, when such written contract, based upon the general terms, conditions, plans and specifications for the project, or on the terms of such subcontractor's or supplier's written bid, is presented by the Contractor.
- B. The listed DBE becomes bankrupt or insolvent.
- C. The listed DBE fails or refuses to perform the subcontract or furnish the listed materials.
- D. The Contractor stipulated that a bond was a condition of executing a subcontract and the listed DBE subcontractor fails or refuses to meet the bond requirements of the Contractor.

- E. The work performed by the listed subcontractor is substantially unsatisfactory and is not in substantial conformance with the plans and specifications, or the subcontractor is substantially delaying or disrupting the progress of the work.
- F. It would be in the best interest of the State.

The Contractor shall not be entitled to any payment for such work or material unless it is performed or supplied by the listed DBE or by other forces (including those of the Contractor) pursuant to prior written authorization of the Engineer.

#### **5-1.09 SUBCONTRACTING**

Attention is directed to the provisions in Section 8-1.01, "Subcontracting," of the Standard Specifications, and Section 2, "Proposal Requirements and Conditions," and Section 3, "Award and Execution of Contract," of these special provisions.

Pursuant to the provisions of Section 1777.1 of the Labor Code, the Labor Commissioner publishes and distributes a list of contractors ineligible to perform work as a subcontractor on a public works project. This list of debarred contractors is available from the Department of Industrial Relations web site at:

<http://www.dir.ca.gov/DLSE/Debar.html>.

The provisions in the third paragraph of Section 8-1.01, "Subcontracting," of the Standard Specifications, that the Contractor shall perform with the Contractor's own organization contract work amounting to not less than 50 percent of the original contract price, is not changed by the Federal Aid requirement specified under "Required Contract Provisions Federal-Aid Construction Contracts" in Section 14 of these special provisions that the Contractor perform not less than 30 percent of the original contract work with the Contractor's own organization.

Each subcontract and any lower tier subcontract that may in turn be made shall include the "Required Contract Provisions Federal-Aid Construction Contracts" in Section 14 of these special provisions. This requirement shall be enforced as follows:

- A. Noncompliance shall be corrected. Payment for subcontracted work involved will be withheld from progress payments due, or to become due, until correction is made. Failure to comply may result in termination of the contract.

In conformance with the Federal DBE regulations Sections 26.53(f)(1) and 26.53(f)(2) Part 26, Title 49 CFR:

- A. The Contractor shall not terminate for convenience a DBE subcontractor listed in response to Section 2-1.02B, "Submission of DBE Information," and then perform that work with its own forces, or those of an affiliate without the written consent of the Department, and
- B. If a DBE subcontractor is terminated or fails to complete its work for any reason, the Contractor will be required to make good faith efforts to substitute another DBE subcontractor for the original DBE subcontractor, to the extent needed to meet the contract goal.

The requirement in Section 2-1.02, "Disadvantaged Business Enterprise (DBE)," of these special provisions that DBEs must be certified on the date bids are opened does not apply to DBE substitutions after award of the contract.

#### **5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS**

Attention is directed to the provisions in Sections 10262 and 10262.5 of the Public Contract Code and Section 7108.5 of the Business and Professions Code concerning prompt payment to subcontractors.

#### **5-1.102 PROMPT PAYMENT OF WITHHELD FUNDS TO SUBCONTRACTORS**

The Contractor shall return all moneys withheld in retention from the subcontractor within 30 days after receiving payment for work satisfactorily completed, even if the other contract work is not completed and has not been accepted in conformance with Section 7-1.17, "Acceptance of Contract," of the Standard Specifications. This requirement shall not be construed to limit or impair any contractual, administrative, or judicial remedies otherwise available to the Contractor or subcontractor in the event of a dispute involving late payment or nonpayment by the Contractor or deficient subcontract performance or noncompliance by a subcontractor.



Once the Contractor has completed the placement of material containing aurally deposited lead in conformance with these special provisions and as directed by the Engineer, the Contractor shall have no responsibility for such materials in place. The Department will not consider the Contractor a generator of such contaminated materials. Further cleanup, removal or remedial actions for such materials will not be required if handled or disposed of as specified herein.

Excavation, reuse, and disposal of material with aurally deposited lead shall be in conformance with all rules and regulations including, but not limited to, those of the following agencies:

- United States Department of Transportation (USDOT)
- United States Environmental Protection Agency (USEPA)
- California Environmental Protection Agency (Cal-EPA)
- California Department of Health Services
- Department of Toxic Substances Control (DTSC)
- California Division of Occupational Safety and Health Administration (Cal-OSHA)
- Integrated Waste Management Board
- Regional Water Quality Control Board (RWQCB), Region 5
- State Air Resources Control Board
- San Joaquin Valley Air Quality Management District (AQMD)

Materials containing hazardous levels of lead shall be transported and disposed of in conformance with Federal and State laws and regulations, as amended, and county and municipal ordinances and regulations, as amended. Laws and regulations that govern this work include, but are not limited to:

- Health and Safety Code, Division 20, Chapter 6.5 (California Hazardous Waste Control Act)
- Title 22, California Code of Regulations, Division 4.5 (Environmental Health Standards for the Management of Hazardous Waste)
- Title 8, California Code of Regulations

#### **SECTION 6. (BLANK)**

#### **SECTION 7. (BLANK)**

### **SECTION 8. MATERIALS**

#### **SECTION 8-1. MISCELLANEOUS**

##### **8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS**

Only materials and products conforming to the requirements of the specifications shall be incorporated in the work. When metric materials and products are not available, and when approved by the Engineer, and at no cost to the State, materials and products in the United States Standard Measures which are of equal quality and of the required properties and characteristics for the purpose intended, may be substituted for the equivalent metric materials and products, subject to the following provisions:

- A. Materials and products shown on the plans or in the special provisions as being equivalent may be substituted for the metric materials and products specified or detailed on the plans.
- B. Before other non-metric materials and products will be considered for use, the Contractor shall furnish, at the Contractor's expense, evidence satisfactory to the Engineer that the materials and products proposed for use are equal to or better than the materials and products specified or detailed on the plans. The burden of proof as to the quality and suitability of substitutions shall be upon the Contractor and the Contractor shall furnish necessary information as required by the Engineer. The Engineer will be the sole judge as to the quality and suitability of the substituted materials and products and the Engineer's decision will be final.
- C. When the Contractor elects to substitute non-metric materials and products, including materials and products shown on the plans or in the special provisions as being equivalent, the list of sources of material specified in Section 6-1.01, "Source of Supply and Quality of Materials," of the Standard Specification shall include a list of substitutions to be made and contract items involved. In addition, for a change in design or details, the Contractor shall submit plans and working drawings in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The plans and working drawings shall be submitted at least 7 days before the Contractor intends to begin the work involved.

Unless otherwise specified, the following substitutions of materials and products will be allowed:

**SUBSTITUTION TABLE FOR SIZES OF HIGH STRENGTH STEEL FASTENERS**  
ASTM Designation: A 325M

METRIC SIZE SHOWN ON THE PLANS mm x thread pitch	SIZE TO BE SUBSTITUTED inch
M16 x 2	5/8
M20 x 2.5	3/4
M22 x 2.5	7/8
M24 x 3	1
M27 x 3	1-1/8
M30 x 3.5	1-1/4
M36 x 4	1-1/2

**SUBSTITUTION TABLE FOR PLAIN WIRE REINFORCEMENT**  
ASTM Designation: A 82

METRIC SIZE SHOWN ON THE PLANS <sup>2</sup> mm	SIZE TO BE SUBSTITUTED <sup>2</sup> inch x 100
MW9	W1.4
MW10	W1.6
MW13	W2.0
MW15	W2.3
MW19	W2.9
MW20	W3.1
MW22	W3.5
MW25	W3.9, except W3.5 in piles only
MW26	W4.0
MW30	W4.7
MW32	W5.0
MW35	W5.4
MW40	W6.2
MW45	W6.5
MW50	W7.8
MW55	W8.5, except W8.0 in piles only
MW60	W9.3
MW70	W10.9, except W11.0 in piles only
MW80	W12.4
MW90	W14.0
MW100	W15.5

**SUBSTITUTION TABLE FOR BAR REINFORCEMENT**

METRIC BAR DESIGNATION NUMBER <sup>1</sup> SHOWN ON THE PLANS	BAR DESIGNATION NUMBER <sup>2</sup> TO BE SUBSTITUTED
13	4
16	5
19	6
22	7
25	8
29	9
32	10
36	11
43	14
57	18

<sup>1</sup>Bar designation numbers approximate the number of millimeters of the nominal diameter of the bars.

<sup>2</sup>Bar numbers are based on the number of eighths of an inch included in the nominal diameter of the bars.

No adjustment will be required in spacing or total number of reinforcing bars due to a difference in minimum yield strength between metric and non-metric bars.

**SUBSTITUTION TABLE FOR SIZES OF:**

(1) STEEL FASTENERS FOR GENERAL APPLICATIONS (ASTM Designation: A 307 or AASHTO Designation: M 314, Grade 36 or 55), and

(2) HIGH STRENGTH STEEL FASTENERS (ASTM Designation: A 325 or A 449)

METRIC SIZE SHOWN ON THE PLANS mm	SIZE TO BE SUBSTITUTED inch
6 or 6.35	1/4
8 or 7.94	5/16
10 or 9.52	3/8
11 or 11.11	7/16
13 or 12.70	1/2
14 or 14.29	9/16
16 or 15.88	5/8
19 or 19.05	3/4
22 or 22.22	7/8
24, 25, or 25.40	1
29 or 28.58	1-1/8
32 or 31.75	1-1/4
35 or 34.93	1-3/8
38 or 38.10	1-1/2
44 or 44.45	1-3/4
51 or 50.80	2
57 or 57.15	2-1/4
64 or 63.50	2-1/2
70 or 69.85	2-3/4
76 or 76.20	3
83 or 82.55	3-1/4
89 or 88.90	3-1/2
95 or 95.25	3-3/4
102 or 101.60	4

**SUBSTITUTION TABLE FOR NOMINAL THICKNESS OF SHEET METAL**

UNCOATED HOT AND COLD ROLLED SHEETS		HOT-DIPPED ZINC COATED SHEETS (GALVANIZED)	
METRIC THICKNESS SHOWN ON THE PLANS mm	GAGE TO BE SUBSTITUTED inch	METRIC THICKNESS SHOWN ON THE PLANS mm	GAGE TO BE SUBSTITUTED inch
7.94	0.3125	4.270	0.1681
6.07	0.2391	3.891	0.1532
5.69	0.2242	3.510	0.1382
5.31	0.2092	3.132	0.1233
4.94	0.1943	2.753	0.1084
4.55	0.1793	2.372	0.0934
4.18	0.1644	1.994	0.0785
3.80	0.1495	1.803	0.0710
3.42	0.1345	1.613	0.0635
3.04	0.1196	1.461	0.0575
2.66	0.1046	1.311	0.0516
2.28	0.0897	1.158	0.0456
1.90	0.0747	1.006 or 1.016	0.0396
1.71	0.0673	0.930	0.0366
1.52	0.0598	0.853	0.0336
1.37	0.0538	0.777	0.0306
1.21	0.0478	0.701	0.0276
1.06	0.0418	0.627	0.0247
0.91	0.0359	0.551	0.0217
0.84	0.0329	0.513	0.0202
0.76	0.0299	0.475	0.0187
0.68	0.0269	-----	-----
0.61	0.0239	-----	-----
0.53	0.0209	-----	-----
0.45	0.0179	-----	-----
0.42	0.0164	-----	-----
0.38	0.0149	-----	-----

**SUBSTITUTION TABLE FOR WIRE**

METRIC THICKNESS SHOWN ON THE PLANS mm	WIRE THICKNESS TO BE SUBSTITUTED inch	GAGE NO.
6.20	0.244	3
5.72	0.225	4
5.26	0.207	5
4.88	0.192	6
4.50	0.177	7
4.11	0.162	8
3.76	0.148	9
3.43	0.135	10
3.05	0.120	11
2.69	0.106	12
2.34	0.092	13
2.03	0.080	14
1.83	0.072	15
1.57	0.062	16
1.37	0.054	17
1.22	0.048	18
1.04	0.041	19
0.89	0.035	20

**SUBSTITUTION TABLE FOR PIPE PILES**

METRIC SIZE SHOWN ON THE PLANS mm x mm	SIZE TO BE SUBSTITUTED inch x inch
PP 360 x 4.55	NPS 14 x 0.179
PP 360 x 6.35	NPS 14 x 0.250
PP 360 x 9.53	NPS 14 x 0.375
PP 360 x 11.12	NPS 14 x 0.438
PP 406 x 12.70	NPS 16 x 0.500
PP 460 x T	NPS 18 x T"
PP 508 x T	NPS 20 x T"
PP 559 x T	NPS 22 x T"
PP 610 x T	NPS 24 x T"
PP 660 x T	NPS 26 x T"
PP 711 x T	NPS 28 x T"
PP 762 x T	NPS 30 x T"
PP 813 x T	NPS 32 x T"
PP 864 x T	NPS 34 x T"
PP 914 x T	NPS 36 x T"
PP 965 x T	NPS 38 x T"
PP 1016 x T	NPS 40 x T"
PP 1067 x T	NPS 42 x T"
PP 1118 x T	NPS 44 x T"
PP 1219 x T	NPS 48 x T"
PP 1524 x T	NPS 60 x T"

The thickness in millimeters (T) represents an exact conversion of the thickness in inches (T").

**SUBSTITUTION TABLE FOR STRUCTURAL TIMBER AND LUMBER**

METRIC MINIMUM DRESSED DRY, SHOWN ON THE PLANS mm x mm	METRIC MINIMUM DRESSED GREEN, SHOWN ON THE PLANS mm x mm	NOMINAL SIZE TO BE SUBSTITUTED inch x inch
19x89	20x90	1x4
38x89	40x90	2x4
64x89	65x90	3x4
89x89	90x90	4x4
140x140	143x143	6x6
140x184	143x190	6x8
184x184	190x190	8x8
235x235	241x241	10x10
286x286	292x292	12x12

**SUBSTITUTION TABLE FOR NAILS AND SPIKES**

METRIC COMMON NAIL, SHOWN ON THE PLANS  Length, mm Diameter, mm	METRIC BOX NAIL, SHOWN ON THE PLANS  Length, mm Diameter, mm	METRIC SPIKE, SHOWN ON THE PLANS Length, mm Diameter, mm	SIZE TO BE SUBSTITUTED Penny-weight
50.80 2.87	50.80 2.51	————	6d
63.50 3.33	63.50 2.87	————	8d
76.20 3.76	76.20 3.25	76.20 4.88	10d
82.55 3.76	82.55 3.25	82.55 4.88	12d
88.90 4.11	88.90 3.43	88.90 5.26	16d
101.60 4.88	101.60 3.76	101.60 5.72	20d
114.30 5.26	114.30 3.76	114.30 6.20	30d
127.00 5.72	127.00 4.11	127.00 6.68	40d
————	————	139.70 7.19	50d
————	————	152.40 7.19	60d

SUBSTITUTION TABLE FOR IRRIGATION  
COMPONENTS

METRIC WATER METERS, TRUCK LOADING STANDPIPES, VALVES, BACKFLOW PREVENTERS, FLOW SENSORS, WYE STRAINERS, FILTER ASSEMBLY UNITS, PIPE SUPPLY LINES, AND PIPE IRRIGATION SUPPLY LINES SHOWN ON THE PLANS DIAMETER NOMINAL (DN) mm	NOMINAL SIZE TO BE SUBSTITUTED  inch
15	1/2
20	3/4
25	1
32	1-1/4
40	1-1/2
50	2
65	2-1/2
75	3
100	4
150	6
200	8
250	10
300	12
350	14
400	16

Unless otherwise specified, substitutions of United States Standard Measures standard structural shapes corresponding to the metric designations shown on the plans and in conformance with the requirements in ASTM Designation: A 6/A 6M, Annex 2, will be allowed.

**8-1.02 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS**

The Department maintains the following list of Prequalified and Tested Signing and Delineation Materials. The Engineer shall not be precluded from sampling and testing products on the list of Prequalified and Tested Signing and Delineation Materials.

The manufacturer of products on the list of Prequalified and Tested Signing and Delineation Materials shall furnish the Engineer a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each type of traffic product supplied.

For those categories of materials included in the list of Prequalified and Tested Signing and Delineation Materials, only those products shown within the listing may be used in the work. Other categories of products, not included in the list of Prequalified and Tested Signing and Delineation Materials, may be used in the work provided they conform to the requirements of the Standard Specifications.

Materials and products may be added to the list of Prequalified and Tested Signing and Delineation Materials if the manufacturer submits a New Product Information Form to the New Product Coordinator at the Transportation Laboratory. Upon a Departmental request for samples, sufficient samples shall be submitted to permit performance of required tests. Approval of materials or products will depend upon compliance with the specifications and tests the Department may elect to perform.

## **PAVEMENT MARKERS, PERMANENT TYPE**

### **Retroreflective**

- A. Apex, Model 921 (100 mm x 100 mm)
- B. Ray-O-Lite, Models SS (100 mm x 100 mm), RS (100 mm x 100 mm) and AA (100 mm x 100 mm)
- C. Stimsonite, Models 88 (100 mm x 100 mm), 911 (100 mm x 100 mm), 953 (70 mm x 114 mm)
- D. 3M Series 290 (89 mm x 100 mm)

### **Retroreflective With Abrasion Resistant Surface (ARS)**

- A. Apex, Model 921AR (100 mm x 100 mm)
- B. Ray-O-Lite "AA" ARS (100 mm x 100 mm)
- C. Stimsonite, Models 911 (100 mm x 100 mm), 953 (70 mm x 114 mm)
- D. 3M Series 290 (89 mm x 100 mm)

### **Retroreflective With Abrasion Resistant Surface (ARS)**

(Used for recessed applications)

- A. Stimsonite, Model 948 (58 mm x 119 mm)
- B. Ray-O-Lite, Model 2002 (58 mm x 117 mm)
- C. Stimsonite, Model 944SB (51 mm x 100 mm)\*
- D. Ray-O-Lite, Model 2004 ARS (51 mm x 100 mm)\*

\*For use only in 114 mm wide (older) recessed slots

### **Non-Reflective For Use With Epoxy Adhesive, 100 mm Round**

- A. Apex Universal (Ceramic)
- B. Highway Ceramics, Inc. (Ceramic)

### **Non-Reflective For Use With Bitumen Adhesive, 100 mm Round**

- A. Alpine Products, "D-Dot" and "ANR" (ABS)
- B. Apex Universal (Ceramic)
- C. Apex Universal, Model 929 (ABS)
- D. Elgin Molded Plastics, "Empco-Lite" Model 900 (ABS)
- E. Highway Ceramics, Inc. (Ceramic)
- F. Hi-Way Safety, Inc., Models P20-2000W and 2001Y (ABS)
- G. Interstate Sales, "Diamond Back" (ABS) and (Polypropylene)
- H. Novabrite Models Adot-w (White) Adot-y (Yellow), (ABS)
- I. Road Creations, Model RCB4NR (Acrylic)
- J. Zumar Industries, "Titan TM40A" (ABS)

## **PAVEMENT MARKERS, TEMPORARY TYPE**

### **Temporary Markers For Long Term Day/Night Use (6 months or less)**

- A. Apex Universal, Model 924 (100 mm x 100 mm)
- B. Elgin Molded Plastics, "Empco-Lite" Model 901 (100 mm x 100 mm)
- C. Road Creations, Model R41C (100 mm x 100 mm)
- D. Vega Molded Products "Temporary Road Marker" (75 mm x 100 mm)

### **Temporary Markers For Short Term Day/Night Use (14 days or less)**

(For seal coat or chip seal applications, clear protective covers are required)

- A. Apex Universal, Model 932
- B. Davidson Plastics, Models T.O.M., T.R.P.M., and "HH" (High Heat)
- C. Hi-Way Safety, Inc., Model 1280/1281

## **STRIPING AND PAVEMENT MARKING MATERIAL**

### **Permanent Traffic Striping and Pavement Marking Tape**

- A. Advanced Traffic Marking, Series 300 and 400
- B. Brite-Line, Series 1000
- C. Brite-Line "DeltaLine XRP"
- D. Swarco Industries, "Director 35" (For transverse application only)

- E. Swarco Industries, "Director 60"
- F. 3M, "Stamark" Series 380 and 5730
- G. 3M, "Stamark" Series 420 (For transverse application only)

**Temporary (Removable) Striping and Pavement Marking Tape (6 months or less)**

- A. Advanced Traffic Marking, Series 200
- B. Brite-Line, Series 100
- C. P.B. Laminations, Aztec, Grade 102
- D. Swarco Industries, "Director-2"
- E. 3M, "Stamark," Series 620
- F. 3M Series A145 Removable Black Line Mask  
(Black Tape: For use only on Asphalt Concrete Surfaces)
- G. Advanced Traffic Marking Black "Hide-A-Line"  
(Black Tape: For use only on Asphalt Concrete Surfaces)
- H. Brite-Line "BTR" Black Removable Tape  
(Black Tape: For use only on Asphalt Concrete Surfaces)

**Preformed Thermoplastic (Heated in place)**

- A. Flint Trading, "Premark" and "Premark 20/20 Flex"
- B. Pavemark, "Hotape"

**Removable Traffic Paint**

- A. Belpro, Series 250/252 and No. 93 Remover

**Ceramic Surfacing Laminate, 150 mm x 150 mm**

- A. Safeline Industries/Highway Ceramics, Inc.

**CLASS 1 DELINEATORS**

**One Piece Driveable Flexible Type, 1700 mm**

- A. Carsonite, Curve-Flex CFRM-400
- B. Carsonite, Roadmarker CRM-375
- C. Davidson Plastics, "Flexi-Guide Models 400 and 566"
- D. FlexStake, Model 654 TM
- E. GreenLine Models HWD1-66 and CGD1-66
- F. J. Miller Industries, Model JMI-375 (with soil anchor)

**Special Use Flexible Type, 1700 mm**

- A. Carsonite, "Survivor" (with 450 mm U-Channel base)
- B. FlexStake, Model 604
- C. GreenLine Models HWD and CGD (with 450 mm U-Channel base)
- D. Safe-Hit with 200 mm pavement anchor (SH248-GP1)
- E. Safe-Hit with 380 mm soil anchor (SH248-GP2) and with 450 mm soil anchor (SH248-GP3)

**Surface Mount Flexible Type, 1200 mm**

- A. Bent Manufacturing Company, Masterflex Model MF-180EX-48
- B. Carsonite, "Super Duck II"
- C. FlexStake, Surface Mount, Models 704 and 754 TM

**CHANNELIZERS**

**Surface Mount Type, 900 mm**

- A. Bent Manufacturing Company, Masterflex Models MF-360-36 (Round) and MF-180-36 (Flat)
- B. Carsonite, "Super Duck" (Flat SDF-436, Round SDR-336)
- C. Carsonite, "Super Duck II" Model SDCF203601MB "The Channelizer"
- D. Davidson Plastics, Flex-Guide Models FG300LD and FG300UR
- E. FlexStake, Surface Mount, Models 703 and 753 TM
- F. GreenLine, Model SMD-36

- G. Hi-Way Safety, Inc. "Channel Guide Channelizer" Model CGC36
- H. The Line Connection, "Dura-Post" Model DP36-3 (Permanent)
- I. The Line Connection, "Dura-Post" Model DP36-3C (Temporary)
- J. Repo, Models 300 and 400
- K. Safe-Hit, Guide Post, Model SH236SMA

### **CONICAL DELINEATORS, 1070 mm**

(For 700 mm Traffic Cones, see Standard Specifications)

- A. Bent Manufacturing Company "T-Top"
- B. Plastic Safety Systems "Navigator-42"
- C. Roadmaker Company "Stacker"
- D. Traffix Devices "Grabber"

### **OBJECT MARKERS**

#### **Type "K", 450 mm**

- A. Carsonite, Model SMD-615
- B. FlexStake, Model 701 KM
- C. Repo, Models 300 and 400
- D. Safe-Hit, Model SH718SMA
- E. The Line Connection, Model DP21-4K

#### **Type "K-4" / "Q" Object Markers, 600 mm**

- A. Bent Manufacturing "Masterflex" Model MF-360-24
- B. Carsonite, Super Duck II
- C. FlexStake, Model 701KM
- D. Repo, Models 300 and 400
- E. Safe-Hit, Models SH8 24SMA\_WA and SH8 24GP3\_WA
- F. The Line Connection, Model DP21-4Q

### **TEMPORARY RAILING (TYPE K) REFLECTORS AND CONCRETE BARRIER MARKERS**

#### **Impactable Type**

- A. ARTUK, "FB"
- B. Davidson Plastics, Model PCBM-12
- C. Duraflex Corp., "Flexx 2020" and "Electriflexx"
- D. Hi-Way Safety, Inc., Model GMKRM100

#### **Non-Impactable Type**

- A. ARTUK, JD Series
- B. Stimsonite, Model 967 (with 83 mm Acrylic cube corner reflector)
- C. Stimsonite, Model 967LS
- D. Vega Molded Products, Models GBM and JD

### **THREE BEAM BARRIER MARKERS**

(For use to the left of traffic)

- A. Duraflex Corp., "Railrider"
- B. Davidson Plastics, "Mini" (75 mm x 254 mm)

### **CONCRETE BARRIER DELINEATORS, 400 mm**

(For use to the right of traffic. When mounted on top of barrier, places top of reflective element at 1200 mm)

- A. Davidson Plastics, Model PCBM T-16
- B. Safe-Hit, Model SH216RBM
- C. Sun-Lab Technology, "Safety Guide Light, Model TM," 130 mm x 130 mm x 80 mm

### **CONCRETE BARRIER-MOUNTED MINI-DRUM (260 mm x 360 mm x 570 mm)**

- A. Stinson Equipment Company "SaddleMarker"

## **SOUND WALL DELINEATOR**

(Applied vertically. Place top of 75 mm x 300 mm reflective element at 1200 mm above roadway)

- A. Davidson Plastics, PCBM S-36
- B. Sun-Lab Technology, "Safety Guide Light, Model SM12," 130 mm x 130 mm x 80 mm

## **GUARD RAILING DELINEATOR**

(Top of reflective element at 1200 mm above plane of roadway)

### **Wood Post Type, 686 mm**

- A. Carsonite, Model 427
- B. Davidson Plastics FG 427 and FG 527
- C. FlexStake, Model 102 GR
- D. GreenLine GRD 27
- E. J. Miller Model JMI-375G
- F. Safe-Hit, Model SH227GRD

### **Steel Post Type**

- A. Carsonite, Model CFGR-327 with CFGRBK300 Mounting Bracket

## **RETROREFLECTIVE SHEETING**

### **Channelizers, Barrier Markers, and Delineators**

- A. 3M, High Intensity
- B. Reflexite, PC-1000 Metalized Polycarbonate
- C. Reflexite, AC-1000 Acrylic
- D. Reflexite, AP-1000 Metalized Polyester
- E. Reflexite, AR-1000 Abrasion Resistant Coating
- F. Avery Dennison T-6500 Series (Formerly Stimsonite, Series 6200) (For rigid substrate devices only)

### **Traffic Cones, 330 mm Sleeves**

- A. Reflexite SB (Polyester), Vinyl or "TR" (Semi-transparent)

### **Traffic Cones, 100 mm and 150 mm Sleeves**

- A. 3M Series 3840
- B. Reflexite Vinyl, "TR" (Semi-transparent) or "Conformalite"

### **Barrels and Drums**

- A. Reflexite, "Super High Intensity" or "High Impact Drum Sheeting"
- B. 3M Series 3810

### **Barricades: Type I, Engineer Grade**

- A. American Decal, Adcolite
- B. Avery Dennison, T-1500 and T-1600
- C. 3M, Scotchlite, Series CW

### **Barricades: Type II, Super Engineer Grade**

- A. Avery Dennison, T-2500 Series
- B. Kiwalite Type II
- C. Nikkalite 1800 Series

### **Signs: Type II, Super Engineer Grade**

- A. Avery Dennison, T-2500 Series
- B. Kiwalite, Type II
- C. Nikkalite 1800 Series

### **Signs: Type III, High-Intensity Grade**

- A. 3M Series 3800
- B. Nippon Carbide, Nikkalite Brand Ultralite Grade II

**Signs: Type IV, High-Intensity Prismatic Grade**

- A. Avery Dennison T-6500 (Formerly Stimsonite Series 6200)

**Signs: Type VII, High-Intensity Prismatic Grade**

- A. 3M Series 3900

**Signs: Type VI, Roll-Up Signs**

- A. Reflexite, Vinyl (Orange)
- B. Reflexite "SuperBright" (Fluorescent orange)
- C. Reflexite "Marathon" (Fluorescent orange)
- D. 3M Series RS34 (Orange) and RS20 (Fluorescent orange)

**SPECIALTY SIGN (All Plastic)**

- A. All Sign Products, STOP Sign, 750 mm

**SIGN SUBSTRATE FOR CONSTRUCTION AREA SIGNS**

**Aluminum**

**Fiberglass Reinforced Plastic (FRP)**

- A. Sequentia, "Polyplate"
- B. Fiber-Brite

**SECTION 8-2. CONCRETE**

**8-2.01 PORTLAND CEMENT CONCRETE**

Portland cement concrete shall conform to the provisions in Section 90, "Portland Cement Concrete," of the Standard Specifications and these special provisions.

Unless the use of a mineral admixture is prohibited, whenever the word "cement" is used in the Standard Specifications or the special provisions, it shall be understood to mean "cementitious material" when both of the following conditions are met:

- A. The cement content of portland cement concrete is specified, and
- B. Section 90, "Portland Cement Concrete," of the Standard Specifications is referenced.

Section 90-1.01, "Description," of the Standard Specifications is amended to read:

**90-1.01 DESCRIPTION**

- Portland cement concrete shall be composed of cementitious material, fine aggregate, coarse aggregate, admixtures if used, and water, proportioned and mixed as specified in these specifications.
- Unless otherwise specified, cementitious material to be used in portland cement concrete shall conform to the provisions for cement and mineral admixtures in Section 90-2, "Materials," and shall be either: 1) "Type IP (MS) Modified" cement or 2) a combination of "Type II Modified" portland cement and mineral admixture.
- Concrete for each portion of the work shall comply with the provisions for the Class, cementitious material content in kilograms per cubic meter, 28-day compressive strength, minor concrete or commercial quality concrete, as shown on the plans or specified in these specifications or the special provisions.
  - Class 1 concrete shall contain not less than 400 kg of cementitious material per cubic meter.
  - Class 2 concrete shall contain not less than 350 kg of cementitious material per cubic meter.
  - Class 3 concrete shall contain not less than 300 kg of cementitious material per cubic meter.
  - Class 4 concrete shall contain not less than 250 kg of cementitious material per cubic meter.
  - Minor concrete shall contain not less than 325 kg of cementitious material per cubic meter unless otherwise specified in these specifications or the special provisions.
- Unless otherwise designated on the plans or specified in these specifications or the special provisions, the amount of cementitious material used per cubic meter of concrete in structures or portions of structures shall conform to the following:

Use	Cementitious Material Content (kg/m <sup>3</sup> )
Concrete which is designated by compressive strength:	
Deck slabs and slab spans of bridges	400 min., 475 max.
Roof sections of exposed top box culverts	400 min., 475 max.
Other portions of structures	350 min., 475 max.
Concrete not designated by compressive strength:	
Deck slabs and slab spans of bridges	400 min.
Roof sections of exposed top box culverts	400 min.
Prestressed members	400 min.
Seal courses	400 min.
Other portions of structures	350 min.
Concrete for precast members	350 min., 550 max.

• Whenever the 28-day compressive strength shown on the plans is greater than 25 MPa, the concrete shall be considered to be designated by compressive strength. If the plans show a 28-day compressive strength which is 31 MPa or greater, an additional 7 days will be allowed to obtain the specified strength. The 28-day compressive strengths shown on the plans which are 25 MPa or less are shown for design information only and are not to be considered a requirement for acceptance of the concrete.

• Concrete designated by compressive strength shall be proportioned such that the concrete will conform to the strength shown on the plans or specified in the special provisions.

• The Contractor shall determine the mix proportions for all concrete except pavement concrete. The Engineer will determine the mix proportions for pavement concrete.

• Before using concrete for which the mix proportions have been determined by the Contractor, or in advance of revising those mix proportions, the Contractor shall submit in writing to the Engineer a copy of the mix design.

• Compliance with cementitious material content requirements will be verified in conformance with procedures described in California Test 518 for cement content. For testing purposes, mineral admixture shall be considered to be cement. Batch proportions shall be adjusted as necessary to produce concrete having the specified cementitious material content.

• If any concrete used in the work has a cementitious material content, consisting of cement, mineral admixture, or cement plus mineral admixture, which is less than the minimum required for the work, the concrete shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place and the Contractor shall pay to the State \$0.55 for each kilogram of cement, mineral admixture, or cement plus mineral admixture which is less than the minimum required for the work. The Department may deduct the amount from moneys due, or that may become due, the Contractor under the contract. The deductions will not be made unless the difference between the contents required and those actually provided exceeds the batching tolerances permitted by Section 90-5, "Proportioning." No deductions for cementitious material content will be made based on the results of California Test 518.

• The requirements of the preceding paragraph shall not apply to minor concrete or commercial quality concrete.

• Concrete for which the mix proportions are determined either by the Contractor or the Engineer shall conform to the requirements of this Section 90.

The first paragraph in Section 90-2.01, "Portland Cement," of the Standard Specifications is amended to read:

**90-2.01 PORTLAND CEMENT**

• Unless otherwise specified, portland cement shall be either "Type IP (MS) Modified" cement or "Type II Modified" portland cement.

• "Type IP (MS) Modified" cement shall conform to the specifications for Type IP (MS) cement in ASTM Designation: C 595, and shall be comprised of an intimate mixture of Type II cement and not more than 25 percent of a mineral admixture. The type and minimum amount of mineral admixture used in the manufacture of "Type IP (MS) Modified" cement shall be in conformance with the provisions in Section 90-4.08, "Required Use of Mineral Admixtures."

• "Type II Modified" portland cement shall conform to the requirements for Type II portland cement in ASTM Designation: C 150.

• In addition, "Type IP (MS) Modified" cement and "Type II Modified" portland cement shall conform to the following requirements:

- A. The cement shall not contain more than 0.60 percent by mass of alkalis, calculated as the percentage of Na<sub>2</sub>O plus 0.658 times the percentage of K<sub>2</sub>O, when determined by either direct intensity flame photometry or by the atomic absorption method. The instrument and procedure used shall be qualified as to precision and accuracy in conformance with the requirements in ASTM Designation: C 114.
- B. The autoclave expansion shall not exceed 0.50 percent.
- C. Mortar, containing the cement to be used and Ottawa sand, when tested in conformance with California Test 527, shall not expand in water more than 0.010 percent and shall not contract in air more than 0.048 percent except that when cement is to be used for precast prestressed concrete piling, precast prestressed concrete members or steam cured concrete products, the mortar shall not contract in air more than 0.053 percent.

The second paragraph in Section 90-2.01, "Portland Cement," of the Standard Specifications is amended to read:

- Type III and Type V portland cements shall conform to the requirements in ASTM Designation: C 150, and the additional requirements listed above for Type II Modified portland cement, except that when tested in conformance with California Test 527, mortar containing Type III portland cement shall not contract in air more than 0.075 percent.

The third paragraph in Section 90-2.01, "Portland Cement," of the Standard Specifications is deleted.

The twelfth paragraph in Section 90-2.02, "Aggregates," of the Standard Specifications is deleted.

The first paragraph in Section 90-2.03, "Water," of the Standard Specifications is amended to read:.

### **90-2.03 WATER**

- In conventionally reinforced concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 1,000 parts per million of chlorides as Cl, nor more than 1,300 parts per million of sulfates as SO<sub>4</sub>. In prestressed concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 650 parts per million of chlorides as Cl, nor more than 1,300 parts per million of sulfates as SO<sub>4</sub>. In no case shall the water contain an amount of impurities that will cause either: 1) a change in the setting time of cement of more than 25 percent when tested in conformance with the requirements in ASTM Designation: C 191 or ASTM Designation: C 266 or 2) a reduction in the compressive strength of mortar at 14 days of more than 5 percent, when tested in conformance with the requirements in ASTM Designation: C 109, when compared to the results obtained with distilled water or deionized water, tested in conformance with the requirements in ASTM Designation: C 109.

The following section is added to Section 90-2, "Materials," of the Standard Specifications:

### **90-2.04 ADMIXTURE MATERIALS**

- Admixture materials shall conform to the requirements in the following ASTM Designations:
  - A. Chemical Admixtures—ASTM Designation: C 494.
  - B. Air-entraining Admixtures—ASTM Designation: C 260.
  - C. Calcium Chloride—ASTM Designation: D 98.
  - D. Mineral Admixtures—Coal fly ash, raw or calcined natural pozzolan as specified in ASTM Designation: C618. Silica fume conforming to the requirements in ASTM Designation: C1240, with reduction of mortar expansion of 80 percent, minimum, using the cement from the proposed mix design.
- Mineral admixtures shall be used in conformance with the provisions in Section 90-4.08, "Required Use of Mineral Admixtures."

The first paragraph in Section 90-3.03, "Fine Aggregate Grading," is amended to read:

Fine aggregate shall be graded within the following limits:

Sieve Sizes	Percentage Passing	
	Operating Range	Contract Compliance
9.5-mm	100	100
4.75-mm	95-100	93-100
2.36-mm	65-95	61-99
1.18-mm	X ± 10	X ± 13
600-µm	X ± 9	X ± 12
300-µm	X ± 6	X ± 9
150-µm	2-12	1-15
75-µm	0-8	0-10

Section 90-4.02, "Materials," of the Standard Specifications is amended to read:

**90-4.02 MATERIALS**

- Admixture materials shall conform to the provisions in Section 90-2.04, "Admixture Materials."

Section 90-4.05, "Optional Use of Chemical Admixtures," of the Standard Specifications is amended to read:

**90-4.05 OPTIONAL USE OF CHEMICAL ADMIXTURES**

- The Contractor will be permitted to use Type A or F, water-reducing; Type B, retarding; or Type D or G, water-reducing and retarding admixtures as described in ASTM Designation: C 494 to conserve cementitious material or to facilitate concrete construction application subject to the following conditions:
  - A. When a water-reducing admixture or a water-reducing and retarding admixture is used, the cementitious material content specified or ordered may be reduced by a maximum of 5 percent by mass except that the resultant cementitious material content shall be not less than 300 kilograms per cubic meter.
  - B. When a reduction in cementitious material content is made, the dosage of admixture used shall be the dosage used in determining approval of the admixture.

Section 90-4.07, "Optional Use of Air-entraining Admixtures," of the Standard Specifications is amended to read:

**90-4.07 OPTIONAL USE OF AIR-ENTRAINING ADMIXTURES**

- When air-entrainment has not been specified or ordered by the Engineer, the Contractor will be permitted to use an air-entraining admixture to facilitate the use of any construction procedure or equipment provided that the average air content, as determined by California Test 504, of 3 successive tests does not exceed 4 percent and no single test value exceeds 5.5 percent. If the Contractor elects to use an air-entraining admixture in concrete for pavement, the Contractor shall so indicate at the time the Contractor designates the source of aggregate as provided in Section 40-1.015, "Cement Content."

Section 90-4.08, "Required Use of Mineral Admixtures," of the Standard Specifications is amended to read:

**90-4.08 REQUIRED USE OF MINERAL ADMIXTURES**

- Unless otherwise specified, mineral admixture shall be combined with cement to make cementitious material for use in portland cement concrete.
  - The calcium oxide content of mineral admixtures shall not exceed 10 percent and the available alkali, as sodium oxide equivalent, shall not exceed 1.5 percent when determined in conformance with the requirements in ASTM Designation: C618.
  - The amounts of cement and mineral admixture used in cementitious material for portland cement concrete shall be sufficient to satisfy the minimum cementitious material content requirements specified in Section 90-1.01, "Description," or Section 90-4.05, "Optional Use of Chemical Admixtures," and shall conform to the following:
    - A. The minimum amount of cement shall not be less than 75 percent by mass of the specified minimum cementitious material content.
    - B. The minimum amount of mineral admixture to be combined with cement shall be determined using one of the following criteria:

1. When the calcium oxide content of a mineral admixture, as determined in conformance with the requirements in ASTM Designation: C618 and the provisions in Section 90-2.04, "Admixture Materials," is equal to or less than 2 percent by mass, the amount of mineral admixture shall not be less than 15 percent by mass of the total amount of cementitious material to be used in the mix.
  2. When the calcium oxide content of a mineral admixture, as determined in conformance with the requirements in ASTM Designation: C618 and the provisions in Section 90-2.04, "Admixture Materials," is greater than 2 percent, the amount of mineral admixture shall not be less than 25 percent by mass of the total amount of cementitious material to be used in the mix.
  3. When a mineral admixture is used, which conforms to the provisions for silica fume in Section 90-2.04, "Admixture Materials," the amount of mineral admixture shall not be less than 10 percent by mass of the total amount of cementitious material to be used in the mix.
- C. If more than the required amount of cementitious material is used, the additional cementitious material in the mix may be either cement, a mineral admixture conforming to the provisions in Section 90-2.04, "Admixture Materials," or a combination of both; however, the maximum total amount of mineral admixture shall not exceed 35 percent by mass of the total amount of cementitious material to be used in the mix. Where Section 90-1.01, "Description," specifies a maximum cementitious content in kilograms per cubic meter, the total mass of cement and mineral admixture per cubic meter shall not exceed the specified maximum cementitious material content.

Section 90-4.09, "Optional Use of Mineral Admixtures," of the Standard Specifications is deleted.

Section 90-4.11, "Storage, Proportioning, and Dispensing of Mineral Admixtures," of the Standard Specifications is amended to read:

#### **90-4.11 STORAGE, PROPORTIONING, AND DISPENSING OF MINERAL ADMIXTURES**

- Mineral admixtures shall be protected from exposure to moisture until used. Sacked material shall be piled to permit access for tally, inspection, and identification for each shipment.
- Adequate facilities shall be provided to assure that mineral admixtures meeting the specified requirements are kept separate from other mineral admixtures in order to prevent any but the specified mineral admixtures from entering the work. Safe and suitable facilities for sampling mineral admixtures shall be provided at the weigh hopper or in the feed line immediately in advance of the hopper.
- Mineral admixtures shall be incorporated into concrete using equipment conforming to the requirements for cement weigh hoppers, and charging and discharging mechanisms in ASTM Designation: C 94, in Section 90-5.03, "Proportioning," and in this Section 90-4.11.
- When interlocks are required for cement and mineral admixture charging mechanisms by Section 90-5.03A, "Proportioning for Pavement," and cement and mineral admixtures are weighed cumulatively, their charging mechanisms shall be interlocked to prevent the introduction of mineral admixture until the mass of cement in the cement weigh hopper is within the tolerances specified in Section 90-5.02, "Proportioning Devices."
- Mineral admixture used in concrete for exposed surfaces of like elements of a structure shall be from the same source and of the same percentage.

Section 90-5.02, "Proportioning Devices," of the Standard Specifications is amended to read:

#### **90-5.02 PROPORTIONING DEVICES**

- Weighing, measuring or metering devices used for proportioning materials shall conform to the provisions in Section 9-1.01, "Measurement of Quantities," and this Section 90-5.02. In addition, automatic weighing systems used shall comply with the provisions for automatic proportioning devices in Section 90-5.03A, "Proportioning for Pavement." These automatic devices shall be automatic to the extent that the only manual operation required for proportioning the aggregates, cement, and mineral admixture for one batch of concrete is a single operation of a switch or starter.
- Proportioning devices shall be tested at the expense of the Contractor as frequently as the Engineer may deem necessary to insure their accuracy.
- Weighing equipment shall be insulated against vibration or movement of other operating equipment in the plant. When the plant is in operation, the mass of each batch of material shall not vary from the mass designated by the Engineer by more than the tolerances specified herein.
- Equipment for cumulative weighing of aggregate shall have a zero tolerance of  $\pm 0.5$  percent of the designated total batch mass of the aggregate. For systems with individual weigh hoppers for the various sizes of aggregate, the zero tolerance shall be  $\pm 0.5$  percent of the individual batch mass designated for each size of aggregate. Equipment for cumulative weighing of cement and mineral admixtures shall have a zero tolerance of  $\pm 0.5$  percent of the designated total batch mass of the cement and mineral admixture. Equipment for weighing cement or mineral admixture separately shall have a zero tolerance of  $\pm 0.5$

percent of their designated individual batch masses. Equipment for measuring water shall have a zero tolerance of  $\pm 0.5$  percent of its designated mass or volume.

- The mass indicated for a batch of material shall not vary from the preselected scale setting by more than the following:

- A. Aggregate weighed cumulatively shall be within 1.0 percent of the designated total batch mass of the aggregate. Aggregates weighed individually shall be within 1.5 percent of their respective designated batch masses.
- B. Cement shall be within 1.0 percent of its designated batch mass. When weighed individually, mineral admixture shall be within 1.0 percent of its designated batch mass. When mineral admixture and cement are permitted to be weighed cumulatively, cement shall be weighed first to within 1.0 percent of its designated batch mass, and the total for cement and mineral admixture shall be within 1.0 percent of the sum of their designated batch masses.
- C. Water shall be within 1.5 percent of its designated mass or volume.

- Each scale graduation shall be approximately 0.001 of the total capacity of the scale. The capacity of scales for weighing cement, mineral admixture, or cement plus mineral admixture and aggregates shall not exceed that of commercially available scales having single graduations indicating a mass not exceeding the maximum permissible mass variation above, except that no scale shall be required having a capacity of less than 500 kg, with 0.5 kg graduations.

Section 90-5.03, "Proportioning," excluding Section 90-5.03A, "Proportioning for Pavement," of the Standard Specifications is amended to read:

### **90-5.03 PROPORTIONING**

- Proportioning shall consist of dividing the aggregates into the specified sizes, each stored in a separate bin, and combining them with cement, mineral admixture, and water as provided in these specifications. Aggregates shall be proportioned by mass.

- At the time of batching, aggregates shall have been dried or drained sufficiently to result in a stable moisture content such that no visible separation of water from aggregate will take place during transportation from the proportioning plant to the point of mixing. In no event shall the free moisture content of the fine aggregate at the time of batching exceed 8 percent of its saturated, surface-dry mass.

- Should separate supplies of aggregate material of the same size group, but of different moisture content or specific gravity or surface characteristics affecting workability, be available at the proportioning plant, withdrawals shall be made from one supply exclusively and the materials therein completely exhausted before starting upon another.

- Bulk "Type IP (MS) Modified" cement that conforms to the provisions in Section 90-2.01, "Portland Cement," shall be weighed in an individual hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer.

- Bulk cement to be blended with mineral admixture for use in portland cement concrete for pavement and structures may be weighed in separate, individual weigh hoppers or may be weighed in the same weigh hopper with mineral admixture and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer. If the cement and mineral admixture are weighed cumulatively, the cement shall be weighed first.

- When cement and mineral admixtures are weighed in separate weigh hoppers, the weigh systems for the proportioning of the aggregate, the cement, and the mineral admixture shall be individual and distinct from other weigh systems. Each weigh system shall be equipped with a hopper, a lever system, and an indicator to constitute an individual and independent material weighing device. The cement and the mineral admixture shall be discharged into the mixer simultaneously with the aggregate.

- The scale and weigh hopper for bulk weighing cement, mineral admixture, and cement plus mineral admixture shall be separate and distinct from the aggregate weighing equipment.

- When the source of an aggregate is changed for concrete structures, the Contractor shall adjust the mix proportions and submit in writing to the Engineer a copy of the mix design before using such aggregates. When the source of an aggregate is changed for other concrete, the Engineer shall be allowed sufficient time to adjust the mix and such aggregates shall not be used until necessary adjustments are made.

- For batches with a volume of one cubic meter or more, the batching equipment shall conform to one of the following combinations:

- A. Separate boxes and separate scale and indicator for weighing each size of aggregate.
- B. Single box and scale indicator for all aggregates.
- C. Single box or separate boxes and automatic weighing mechanism for all aggregates.

- In order to check the accuracy of batch masses, the gross mass and tare mass of batch trucks, truck mixers, truck agitators, and non-agitating hauling equipment shall be determined when ordered by the Engineer. The equipment shall be weighed at the Contractor's expense on scales designated by the Engineer.

Section 90-5.03A, "Proportioning for Pavement," of the Standard Specifications is amended to read:

#### **90-5.03A PROPORTIONING FOR PAVEMENT**

- Aggregates and bulk cement, mineral admixture, and cement plus mineral admixture for use in pavement shall be proportioned by mass by means of automatic proportioning devices of approved type conforming to the provisions in this Section 90-5.03A.
  - The Contractor shall install and maintain in operating condition an electrically actuated moisture meter that will indicate, on a readily visible scale, changes in the moisture content of the fine aggregate as it is batched within a sensitivity of 0.5 percent by mass of the fine aggregate.
    - The batching of cement, mineral admixture, or cement plus mineral admixture and aggregate shall be interlocked so that a new batch cannot be started until all weigh hoppers are empty, the proportioning devices are within zero tolerance, and the discharge gates are closed. The interlock shall permit no part of the batch to be discharged until all aggregate hoppers and the cement and mineral admixture hoppers or the cement plus mineral admixture hopper are charged with masses which are within the tolerances specified in Section 90-5.02, "Proportioning Devices."
      - The discharge gate on the cement and mineral admixture hoppers or the cement plus mineral admixture hopper shall be designed to permit regulating the flow of cement, mineral admixture or cement plus mineral admixture into the aggregate as directed by the Engineer.
        - When separate weigh boxes are used for each size of aggregate, the discharge gates shall permit regulating the flow of each size of aggregate as directed by the Engineer.
          - Material discharged from the several bins shall be controlled by gates or by mechanical conveyors. The means of withdrawal from the several bins, and of discharge from the weigh box, shall be interlocked so that not more than one bin can discharge at a time, and that the weigh box cannot be tripped until the required quantity from each of the several bins has been deposited therein. Should a separate weigh box be used for each size of aggregate, all may be operated and discharged simultaneously.
            - When the discharge from the several bins is controlled by gates, each gate shall be actuated automatically so that the required mass is discharged into the weigh box, after which the gate shall automatically close and lock.
              - The automatic weighing system shall be designed so that all proportions required may be set on the weighing controller at the same time.

The third paragraph in Section 90-6.01, "General," of the Standard Specifications is amended to read:

- Concrete shall be homogeneous and thoroughly mixed. There shall be no lumps or evidence of undispersed cement, mineral admixture, or cement plus mineral admixture.

The third and fourth paragraphs in Section 90-6.02, "Machine Mixing," of the Standard Specifications are amended to read:

- The batch shall be so charged into the mixer that some water will enter in advance of cementitious materials and aggregates. All water shall be in the drum by the end of the first one-fourth of the specified mixing time.
  - Cementitious materials shall be batched and charged into the mixer by means that will not result either in loss of cementitious materials due to the effect of wind, or in accumulation of cementitious materials on surfaces of conveyors or hoppers, or in other conditions which reduce or vary the required quantity of cementitious material in the concrete mixture.

The sixth paragraph in Section 90-6.02, "Machine Mixing," of the Standard Specifications is amended to read:

- The total elapsed time between the intermingling of damp aggregates and all cementitious materials and the start of mixing shall not exceed 30 minutes.

The seventh through tenth paragraphs in Section 90-6.03, "Transporting Mixed Concrete," of the Standard Specifications are amended to read:

- When a truck mixer or agitator is used for transporting concrete to the delivery point, discharge shall be completed within 1.5 hours, or before 250 revolutions of the drum or blades, whichever comes first, after the introduction of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C, or above, a time less than 1.5 hours may be required.
- When non-agitating hauling equipment is used for transporting concrete to the delivery point, discharge shall be completed within one hour after the addition of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C, or above, the time between the introduction of cement to the aggregates and discharge shall not exceed 45 minutes.
- Each load of concrete delivered at the job site shall be accompanied by a weight certificate showing the mix identification number, non-repeating load number, date and time at which the materials were batched, the total amount of water added to the load and for transit-mixed concrete, the reading of the revolution counter at the time the truck mixer is charged with cement. This weight certificate shall also show the actual scale masses (kilograms) for the ingredients batched. Theoretical or target batch masses shall not be used as a substitute for actual scale masses.
- Weight certificates shall be provided in printed form, or if approved by the Engineer, the data may be submitted in electronic media. Electronic media shall be presented in a tab-delimited format on 90 mm diskette with a capacity of at least 1.4 megabytes. Captured data, for the ingredients represented by each batch shall be LFCR (one line, separate record) with allowances for sufficient fields to satisfy the amount of data required by these specifications.
- The Contractor may furnish a weight certificate that is accompanied by a separate certificate which lists the actual batch masses or measurements for a load of concrete provided that both certificates are 1) imprinted with the same non-repeating load number that is unique to the contract and 2) delivered to the job site with the load.
- Weight certificates furnished by the Contractor shall conform to the provisions in Section 9-1.01, "Measurement of Quantities," of the Standard Specifications.

Section 90-6.05, "Hand-Mixing," of the Standard Specifications is amended to read:

**90-6.05 HAND-MIXING**

- Hand-mixed concrete shall be made in batches not more than one-fourth cubic meter and shall be mixed on a watertight, level platform. The proper amount of coarse aggregate shall be measured in measuring boxes and spread on the platform and the fine aggregate shall be spread on this layer, the 2 layers being not more than 0.3 meters in total depth. On this mixture shall be spread the dry cement and mineral admixture and the whole mass turned no fewer than 2 times dry; then sufficient clean water shall be added, evenly distributed, and the whole mass again turned no fewer than 3 times, not including placing in the carriers or forms.

The table in the first paragraph in Section 90-6.06, "Amount of Water and Penetration," of the Standard Specifications is replaced with the following table:

Type of Work	Nominal Penetration (mm)	Maximum Penetration (mm)
Concrete pavement	0-25	40
Non-reinforced concrete facilities	0-35	50
Reinforced concrete structures:		
Sections over 300 mm thick	0-35	65
Sections 300 mm thick or less	0-50	75
Concrete placed under water	75-100	115
Cast-in-place concrete piles	65-90	100

The first paragraph following the table of penetration ranges in Section 90-6.06, "Amount of Water and Penetration," of the Standard Specifications is amended to read:

- The amount of free water used in concrete shall not exceed 183 kg/m<sup>3</sup>, plus 20 kg for each required 100 kg of cementitious material in excess of 325 kg/m<sup>3</sup>.

The fourth paragraph in Section 90-6.06, "Amount of Water and Penetration," of the Standard Specifications is amended to read:

- Where there are adverse or difficult conditions which affect the placing of concrete, the above specified penetration and free water content limitations may be exceeded providing the Contractor is granted permission by the Engineer in writing to increase the cementitious material content per cubic meter of concrete. The increase in water and cementitious material shall be at a ratio not to exceed 30 kg of water per added 100 kg of cementitious material per cubic meter. The cost of additional cementitious material and water added under these conditions shall be at the Contractor's expense and no additional compensation will be allowed therefor.

Section 90-9.01, "General," of the Standard Specifications is amended to read:

#### **90-9.01 GENERAL**

- Concrete compressive strength requirements consist of a minimum strength which must be attained before various loads or stresses are applied to the concrete and, for concrete designated by strength, a minimum strength at the age of 28 days or at the age otherwise allowed in Section 90-1.01, "Description." The various strengths required are specified in these specifications or are shown on the plans.

- The compressive strength of concrete will be determined from test cylinders which have been fabricated from concrete sampled in conformance with California Test 539. Test cylinders will be molded and initial field cured in conformance with California Test 540. Test cylinders will be cured and tested after receipt at the testing laboratory in conformance with California Test 521. A strength test shall consist of the average strength of 2 cylinders fabricated from material taken from a single load of concrete, except that, if any cylinder should show evidence of improper sampling, molding, or testing, that cylinder shall be discarded and the strength test shall consist of the strength of the remaining cylinder.

- When concrete compressive strength is specified as a prerequisite to applying loads or stresses to a concrete structure or member, test cylinders for other than steam cured concrete will be cured in conformance with Method 1 of California Test 540. The compressive strength of concrete determined for these purposes will be evaluated on the basis of individual tests.

- When concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete strength to be used as a basis for acceptance of other than steam cured concrete will be determined from cylinders cured in conformance with Method 1 of California Test 540. If the result of a single compressive strength test at the maximum age specified or allowed is below the specified strength but is 95 percent or more of the specified strength, the Contractor shall, at the Contractor's expense, make corrective changes, subject to approval by the Engineer, in the mix proportions or in the concrete fabrication procedures, before placing additional concrete, and shall pay to the State \$14 for each in-place cubic meter of concrete represented by the deficient test. If the result of a single compressive strength test at the maximum age specified or allowed is below 95 percent of the specified strength, but is 85 percent or more of the specified strength, the Contractor shall make the corrective changes specified above, and shall pay to the State \$20 for each in place cubic meter of concrete represented by the deficient test. In addition, such corrective changes shall be made when the compressive strength of concrete tested at 7 days indicates, in the judgment of the Engineer, that the concrete will not attain the required compressive strength at the maximum age specified or allowed. Concrete represented by a single test which indicates a compressive strength of less than 85 percent of the specified 28-day compressive strength will be rejected in conformance with the provisions in Section 6-1.04, "Defective Materials."

- If the test result indicates that the compressive strength at the maximum curing age specified or allowed is below the specified strength, but 85 percent or more of the specified strength, payments to the State as required above shall be made, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength of the concrete placed in the work meets or exceeds the specified 28-day compressive strength. If the test result indicates a compressive strength at the maximum curing age specified or allowed below 85 percent, the concrete represented by that test will be rejected, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength and quality of the concrete placed in the work are acceptable. If the evidence consists of tests made on cores taken from the work, the cores shall be obtained and tested in conformance with the requirements in ASTM Designation: C 42.

- No single compressive strength test shall represent more than 250 cubic meters.

- When a precast concrete member is steam cured, the compressive strength of the concrete will be determined from test cylinders which have been handled and stored in conformance with Method 3 of California Test 540. The compressive strength of steam cured concrete will be evaluated on the basis of individual tests representing specific portions of production. When the concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete shall be considered to be acceptable whenever its compressive strength reaches the specified 28-day compressive strength provided that strength is reached in not more than the maximum number of days specified or allowed after the member is cast.

- If concrete is specified by compressive strength, then materials, mix proportions, mixing equipment, and procedures proposed for use shall be prequalified prior to placement of the concrete. Prequalification shall be accomplished by the submission of acceptable certified test data or trial batch reports by the Contractor. Prequalification data shall be based on the use of materials, mix proportions, mixing equipment, procedures, and size of batch proposed for use in the work.

- Certified test data, in order to be acceptable, must indicate that not less than 90 percent of at least 20 consecutive tests exceed the specified strength at the maximum number of cure days specified or allowed, and none of those tests are less than 95 percent of specified strength. Strength tests included in the data shall be the most recent tests made on concrete of the proposed mix design and all shall have been made within one year of the proposed use of the concrete.

- Trial batch test reports, in order to be acceptable, must indicate that the average compressive strength of 5 consecutive concrete cylinders, taken from a single batch, at not more than 28 days (or the maximum age allowed) after molding shall be at least 4 MPa greater than the specified 28-day compressive strength, and no individual cylinder shall have a strength less than the specified strength at the maximum age specified or allowed. Data contained in the report shall be from trial batches which were produced within one year of the proposed use of specified strength concrete in the project. Whenever air-entrainment is required, the air content of trial batches shall be equal to or greater than the air content specified for the concrete without reduction due to tolerances.

- Tests shall be performed in conformance with either the appropriate California Test methods or the comparable ASTM test methods. Equipment employed in testing shall be in good condition and shall be properly calibrated. If the tests are performed during the life of the contract, the Engineer shall be notified sufficiently in advance of performing the tests in order to witness the test procedures.

- The certified test data and trial batch test reports shall include the following information:

- A. Date of mixing.
- B. Mixing equipment and procedures used.
- C. The size of batch in cubic meters and the mass, type and source of ingredients used.
- D. Penetration of the concrete.
- E. The air content of the concrete if an air-entraining admixture is used.
- F. The age at time of testing and strength of concrete cylinders tested.

- Certified test data and trial batch test reports shall be signed by an official of the firm which performed the tests.

- When approved by the Engineer, concrete from trial batches may be used in the work at locations where concrete of a lower quality is required and the concrete will be paid for as the type or class of concrete required at that location.

- After materials, mix proportions, mixing equipment, and procedures for concrete have been prequalified for use, additional prequalification by testing of trial batches will be required prior to making changes which, in the judgment of the Engineer, could result in a lowering of the strength of the concrete below that specified.

- The Contractor's attention is directed to the time required to test trial batches. The Contractor shall be responsible for production of trial batches at a sufficiently early date so that the progress of the work is not delayed.

- When precast concrete members are manufactured at the plant of an established manufacturer of precast concrete members, the mix proportions of the concrete shall be determined by the Contractor, and a trial batch and prequalification of the materials, mix proportions, mixing equipment, and procedures will not be required.

Section 90-10.02A, "Portland Cement," of the Standard Specifications is renamed "Cementitious Material" and is amended to read:

#### **90-10.02A CEMENTITIOUS MATERIAL**

- Cementitious material shall conform to the provisions in Section 90-1.01, "Description." Compressive strength requirements consist of a minimum strength which must be attained before various loads or stresses are applied to the concrete and, for concrete designated by strength, a minimum strength at the age of 28 days or at the age otherwise allowed in Section 90-1.01, "Description." The various strengths required are specified in these specifications or are shown on the plans.

The fifth paragraph in Section 90-10.02B, "Aggregate," of the Standard Specifications is deleted.

Section 90-10.03, "Production," of the Standard Specifications is amended to read:

#### **90-10.03 PRODUCTION**

- Cementitious material, water, aggregate, and admixtures shall be stored, proportioned, mixed, transported, and discharged in conformance with recognized standards of good practice, which will result in concrete that is thoroughly and uniformly mixed, which is suitable for the use intended, and which conforms to provisions specified herein. Recognized

standards of good practice are outlined in various industry publications such as those issued by American Concrete Institute, AASHTO, or California Department of Transportation.

- The cementitious material content of minor concrete shall conform to the provisions in Section 90-1.01, "Description."
- The amount of water used shall result in a consistency of concrete conforming to the provisions in Section 90-6.06, "Amount of Water and Penetration." Additional mixing water shall not be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer.
- Discharge of ready-mixed concrete from the transporting vehicle shall be made while the concrete is still plastic and before stiffening occurs. An elapsed time of 1.5 hours (one hour in non-agitating hauling equipment), or more than 250 revolutions of the drum or blades, after the introduction of the cementitious material to the aggregates, or a temperature of concrete of more than 32°C will be considered as conditions contributing to the quick stiffening of concrete. The Contractor shall take whatever action is necessary to eliminate quick stiffening, except that the addition of water will not be permitted.
- The required mixing time in stationary mixers shall be not less than 50 seconds or more than 5 minutes.
- The minimum required revolutions at mixing speed for transit-mixed concrete shall be not less than that recommended by the mixer manufacturer, and shall be increased, if necessary, to produce thoroughly and uniformly mixed concrete.
- Each load of ready-mixed concrete shall be accompanied by a weight certificate which shall be delivered to the Engineer at the discharge location of the concrete, unless otherwise directed by the Engineer. The weight certificate shall be clearly marked with the date and time of day when the load left the batching plant and, if hauled in truck mixers or agitators, the time the mixing cycle started.
- A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," shall be furnished to the Engineer, prior to placing minor concrete from a source not previously used on the contract, stating that minor concrete to be furnished meets contract requirements, including minimum cementitious material content specified.

The third and fourth paragraphs in Section 90-11.02, "Payment," of the Standard Specifications are amended to read:

- Should the Engineer order the Contractor to incorporate admixtures into the concrete when their use is not required by these specifications or the special provisions, furnishing the admixtures and adding them to the concrete will be paid for as extra work as provided in Section 4-1.03D.
- Should the Contractor use admixtures in conformance with the provisions in Section 90-4.05, "Optional Use of Chemical Admixtures," or Section 90-4.07, "Optional Use of Air-entraining Admixtures," or should the Contractor request and obtain permission to use other admixtures for the Contractor's benefit, the Contractor shall furnish those admixtures and incorporate them in the concrete at the Contractor's expense and no additional compensation will be allowed therefor.

### **SECTION 8-3. (BLANK)**

### **SECTION 9. (BLANK)**

## **SECTION 10. CONSTRUCTION DETAILS**

### **SECTION 10-1. GENERAL**

#### **10-1.00 CONSTRUCTION PROJECT INFORMATION SIGNS**

Before any major physical construction work readily visible to highway users is started on this contract, the Contractor shall furnish and erect 2 Type 2 Construction Project Information signs at the locations designated by the Engineer.

The signs and overlays shall be of a type and material consistent with the estimated time of completion of the project and shall conform to the details shown on the plans.

The sign letters, border and the Department's construction logos shall conform to the colors (non-reflective) and details shown on the plans, and shall be on a white background (non-reflective). The colors blue and orange shall conform to PR Color Number 3 and Number 6, respectively, as specified in the Federal Highway Administration's Color Tolerance Chart.

The sign message to be used for fund types shall consist of the following, in the order shown:

FEDERAL HIGHWAY TRUST FUNDS
STATE HIGHWAY FUNDS

The sign message to be used for type of work shall consist of the following:

### ROADSIDE WORK

The sign message to be used for the Year of Completion of Project Construction will be furnished by the Engineer. The Contractor shall furnish and install the "Year" sign overlay within 10 working days of notification of the year date to be used.

The letter sizes to be used shall be as shown on the plans. The information shown on the signs shall be limited to that shown on the plans.

The signs shall be kept clean and in good repair by the Contractor.

Upon completion of the work, the signs shall be removed and disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13 of the Standard Specifications.

Full compensation for furnishing, erecting, maintaining, and removing and disposing of the construction project information signs shall be considered as included in the contract lump sum price paid for construction area signs and no additional compensation will be allowed therefor.

#### **10-1.01 ORDER OF WORK**

Order of work shall conform to the provisions in Section 5-1.05, "Order of Work," of the Standard Specifications and these special provisions.

At the end of each working day if a difference in excess of 450 millimeter exists between the elevation of the existing pavement and the elevation of excavations within 2.4 m of the traveled way, material shall be placed and compacted against the vertical cuts adjacent to the traveled way. During excavation operations, native material may be used for this purpose; however, once placing of the structural section commences, structural material shall be used. The material shall be placed to the level of the elevation of the top of existing pavement and tapered at a slope of 1:4 (vertical:horizontal) or flatter to the bottom of the excavation. Full compensation for placing the material on a 1:4 slope, regardless of the number of times the material is required, and subsequent removing or reshaping of the material to the lines and grades shown on the plans shall be considered as included in the contract price paid for the materials involved and no additional compensation will be allowed therefor. No payment will be made for material placed in excess of that required for the structural section.

Within 30 days after the contract has been approved, the Contractor shall furnish the Engineer a statement from the vendor that the order for the plants required for this contract, including inspection plants, has been received and accepted by the vendor. The statement from the vendor shall include the names, sizes, and quantities of plants ordered and the anticipated date of delivery.

The Contractor shall place orders for replacement plants with the vendor at the appropriate time so that the roots of the replacement plants are not in a root-bound condition.

Attention is directed to Section 9-1.06, "Partial Payments," of the Standard Specifications. For progress payment purposes, the Department will retain 50 percent of the estimated value of highway planting work done until a statement from the vendor that the order for the plants required for this contract has been submitted to the Engineer.

Attention is directed to "Irrigation Systems Functional Test" of these special provisions, regarding restrictions for planting operations.

Attention is directed to "Locate Existing Crossovers and Conduits" of these special provisions regarding locating existing irrigation water line crossovers and conduits shown on the plans to be incorporated in the new work. Existing irrigation water line crossovers and conduits shall be located prior to performing work on the irrigation system.

Unless otherwise shown on the plans or specified in these special provisions, conduits to be jacked or drilled or installed by the open trench method for water line crossovers and sprinkler control crossovers shall be installed prior to the installation of other pipe supply lines.

Attention is directed to "Existing Highway Irrigation Facilities" of these special provisions regarding the checking of existing irrigation facilities that are to remain in place, prior to the start of any irrigation work.

Attention is directed to Section 20-5.027B, "Wiring Plans and Diagrams," of the Standard Specifications regarding submittal of working drawings.

Attention is directed to "Irrigation Controller Enclosure Cabinet" of these special provisions regarding preinstalling irrigation components in the irrigation controller enclosure cabinet prior to field installation.

#### **10-1.02 WATER POLLUTION CONTROL (STORM WATER POLLUTION PREVENTION PLAN)**

Water pollution control work shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications and these special provisions.

This project lies within the boundaries of the San Joaquin Valley Regional Water Quality Control Board and shall conform to the requirements of the National Pollutant Discharge Elimination System (NPDES) Permit for General Construction Activities No. CAS000002, Order No. 99-08-DWQ, and the NPDES Permit for the State of California Department of Transportation Properties, Facilities, and Activities, No. CAS000003, Order No. 99-06-DWQ issued by the

State Water Resources Control Board. These permits, hereafter referred to as the "Permits," regulate storm water discharges associated with construction activities.

Water pollution control work shall conform to the requirements in the "Storm Water Pollution Prevention Plan (SWPPP) and Water Pollution Control Program (WPCP) Preparation Manual" and the "Construction Site Best Management Practices (BMPs) Manual," and addenda thereto issued up to, and including, the date of advertisement of the project, hereafter referred to respectively as the "Preparation Manual" and the "Construction Site BMP Manual" and collectively as the "Manuals." Copies of the Manuals and the Permits may be obtained from the Department of Transportation, Material Operations Branch, Publication Distribution Unit, 1900 Royal Oaks Drive, Sacramento, California 95815, Telephone: (916) 445-3520. Copies of the Manuals may also be obtained from the Department's Internet Web Site at: <http://www.dot.ca.gov/hq/construc/stormwater.html>.

The Contractor shall know and fully comply with the applicable provisions of the Manuals, Permits, and Federal, State, and local regulations that govern the Contractor's operations and storm water discharges from both the project site and areas of disturbance outside the project limits during construction. The Contractor shall maintain copies of the Permits at the project site and shall make the Permits available during construction.

Unless arrangements for disturbance or use of areas outside the project limits are made by the Department and made part of the contract, it is expressly agreed that the Department assumes no responsibility for the Contractor or property owner with respect to any arrangements made between the Contractor and property owner. The Contractor shall implement, inspect and maintain all necessary water pollution control practices to satisfy all applicable Federal, State, and Local laws and regulations that govern water quality for areas used outside of the highway right-of-way or areas arranged for the specific use of the Contractor for this project. Installing, inspecting, and maintaining water pollution control practices on areas outside the highway right-of-way not specifically arranged for and provided for by the Department for the execution of this contract will not be paid for.

The Contractor shall be responsible for the costs and for liabilities imposed by law as a result of the Contractor's failure to comply with the provisions set forth in this section "Water Pollution Control", including but not limited to, compliance with the applicable provisions of the Manuals, Permits and Federal, State and local regulations. Costs and liabilities include, but are not limited to, fines, penalties, and damages whether assessed against the State or the Contractor, including those levied under the Federal Clean Water Act and the State Porter Cologne Water Quality Act.

In addition to the remedies authorized by law, money due the Contractor under the contract, in an amount determined by the Department, may be retained by the State of California until disposition has been made of the costs and liabilities.

When a regulatory agency or other third party identifies a failure to comply with the permit or any other local, State, or federal requirement, the Engineer may retain money due the Contractor, subject to the following:

- A. The Department will give the Contractor 30 days notice of the Department's intention to retain funds from partial payments which may become due to the Contractor prior to acceptance of the contract. Retention of funds from payments made after acceptance of the contract may be made without prior notice to the Contractor.
- B. No retention of additional amounts out of partial payments will be made if the amount to be retained does not exceed the amount being withheld from partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications.
- C. If the Department has retained funds and it is subsequently determined that the State is not subject to the costs and liabilities in connection with the matter for which the retention was made, the Department shall be liable for interest on the amount retained for the period of the retention, and the rate of interest payable shall be 6 percent per annum.

Conformance with the provisions of this section "Water Pollution Control" shall not relieve the Contractor from the Contractor's responsibilities, as provided in Section 7, "Legal Relations and Responsibilities," of the Standard Specifications.

The Contractor shall notify the Engineer immediately upon request from the regulatory agencies to enter, inspect, sample, monitor or otherwise access the project site or the Contractor's records pertaining to water pollution control work.

#### **STORM WATER POLLUTION PREVENTION PLAN PREPARATION, APPROVAL AND AMENDMENTS**

As part of the water pollution control work, a Storm Water Pollution Prevention Plan, hereafter referred to as the "SWPPP," is required for this contract. The SWPPP shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications, the requirements in the Manuals, the requirements of the Permits, and these special provisions. Upon the Engineer's approval of the SWPPP, the SWPPP shall be considered to fulfill the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications for development and submittal of a Water Pollution Control Program.

No work having potential to cause water pollution, as determined by the Engineer, shall be performed until the SWPPP has been approved by the Engineer.

The Contractor shall designate a Water Pollution Control Manager. The Water Pollution Control Manager shall be responsible for the preparation of the SWPPP and any required modifications or amendments and shall be responsible for the implementation and adequate functioning of the various water pollution control practices employed. The Water Pollution Control Manager shall serve as the primary contact for all issues related to the SWPPP or its implementation. The Contractor shall submit to the Engineer a statement of qualifications, describing the training, previous work history and expertise of the individual selected by the Contractor to serve as Water Pollution Control Manager. The Engineer will reject the Contractor's submission of a Water Pollution Control Manager if the submitted qualifications are deemed to be inadequate.

Within 30 days after the approval of the contract, the Contractor shall submit 3 copies of the draft SWPPP to the Engineer. The Engineer will have 15 days to review the SWPPP. If revisions are required, as determined by the Engineer, the Contractor shall revise and resubmit the SWPPP within 15 days of receipt of the Engineer's comments. The Engineer will have 15 days to review the revisions. Upon the Engineer's approval of the SWPPP, 3 approved copies of the SWPPP, incorporating the required changes, shall be submitted to the Engineer. In order to allow construction activities to proceed, the Engineer may conditionally approve the SWPPP while minor revisions are being completed. If the Engineer does not review or approve the SWPPP within the time specified, compensation will be made in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The SWPPP shall apply to all areas that are directly related to construction including, but not limited to, staging areas, storage yards, material borrow areas, and access roads within or outside of the highway right-of-way.

The SWPPP shall incorporate water pollution control practices in the following six categories:

- A. Soil stabilization;
- B. Sediment control;
- C. Wind erosion control;
- D. Tracking control;
- E. Non-storm water control; and
- F. Waste management and material pollution control.

The Contractor shall develop a Water Pollution Control Schedule that shall describe the timing of grading or other work activities that could affect water pollution. The Water Pollution Control Schedule shall be updated by the Contractor to reflect any changes in the Contractor's operations that would affect the necessary implementation of water pollution control practices.

The Contractor shall incorporate the "Minimum Requirements" presented in the Preparation Manual into the SWPPP. In addition to the "Minimum Requirements" presented in the Preparation Manual, the Contractor shall complete the BMP Consideration Checklist presented in the Preparation Manual. The Contractor shall identify and incorporate into the SWPPP the water pollution control practices selected by the Contractor or as directed by the Engineer.

The SWPPP shall include, but not be limited to, the items described in the Manuals, Permits and related information contained in the contract documents. The Contractor shall prepare an amendment to the SWPPP when there is a change in construction activities or operations which may affect the discharge of pollutants to surface waters, ground waters, municipal storm drain systems, or when the Contractor's activities or operations violate any condition of the Permits, or when directed by the Engineer. Amendments shall show additional water pollution control practices or revised operations, including those areas or operations not shown in the initially approved SWPPP. Amendments to the SWPPP shall be prepared, and submitted for review and approval in the same manner as specified for the SWPPP approval. Subsequent amendments shall be submitted within a time approved by the Engineer, but in no case longer than the time specified for the initial submittal and review of the SWPPP.

The Contractor shall keep one copy of the approved SWPPP and approved amendments at the project site. The SWPPP shall be made available upon request of a representative of the Regional Water Quality Control Board, State Water Resources Control Board, United States Environmental Protection Agency or the local storm water management agency. Requests by the public shall be directed to the Engineer.

### **COST BREAK-DOWN**

The Contractor shall submit to the Engineer a cost break-down for the contract lump sum item of water pollution control, together with the SWPPP.

The cost break-down shall be completed and furnished in the format shown in the example of the cost break-down included in this section. Unit descriptions and quantities shall be designated by the Contractor, except for the specified special requirements shown in the example. The units and quantities given in the example, if provided, are special requirements specified for the SWPPP, and shall be included in the cost break-down furnished to the Engineer. The Contractor shall verify the estimated quantities of the special requirements and submit revised quantities in the cost break-down.

The Contractor shall determine the quantities required to complete the work of water pollution control. The quantities and their values shall be included in the cost break-down submitted to the Engineer for approval. The Contractor shall be responsible for the accuracy of the quantities and values used in the cost break-down submitted for approval. The cost break-down shall not include water pollution control practices which are shown on the plans and for which there is a separate contract item.

The sum of the amounts for the units of work listed in the cost break-down shall be equal to the contract lump sum price bid for water pollution control. Overhead and profit shall be included in each individual unit listed in the cost break-down. The cost break-down shall be submitted and approved within the same times specified for the SWPPP. Partial payment for the item of water pollution control will not be made until the cost break-down is approved, in writing, by the Engineer.

Adjustments in the items of work and quantities listed in the approved cost break-down shall be made when required to address amendments to the SWPPP, except when the adjusted items are paid for as extra work.

No adjustment in compensation will be made in the contract lump sum price paid for water pollution control due to differences between the quantities shown in the approved cost break-down and the quantities required to complete the work as shown on the approved SWPPP. No adjustment in compensation will be made for ordered changes to correct SWPPP work resulting from the Contractor's own operations or from the Contractor's negligence.

The approved cost break-down will be used to determine partial payments during the progress of the work and as the basis for calculating the adjustment in compensation for the item of water pollution control due to increases or decreases of quantities ordered by the Engineer. When an ordered change increases or decreases the quantities of an approved cost break-down item, the adjustment in compensation will be determined in the same manner specified for increases and decreases in the quantity of a contract item of work in conformance with the provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications. If an ordered change requires a new item not on the approved cost break-down, the adjustment in compensation will be determined in the same manner specified for extra work in conformance with Section 4-1.03D, "Extra Work," of the Standard Specifications.

If requested by the Contractor and approved by the Engineer, changes to the water pollution control practices listed in the approved cost break-down, including the addition of new water pollution control practices, will be allowed. The changes shall be included in an approved amendment to the SWPPP. If the changes to the water pollution control practices requested by the Contractor would result in a net cost increase to the lump sum price for water pollution control, an adjustment in compensation will be made without change to the item of water pollution control. The net cost increase to the item of water pollution control resulting from changes requested by the Contractor will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

### **SWPPP IMPLEMENTATION**

Upon approval of the SWPPP, the Contractor shall be responsible throughout the duration of the project for installing, constructing, inspecting, maintaining, removing and disposing of the water pollution control practices included in the SWPPP and any amendments. Unless otherwise directed by the Engineer, the Contractor's responsibility for SWPPP implementation shall continue throughout any temporary suspension of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications. Requirements for installation, construction, inspection, maintenance, removal, and disposal of water pollution control practices are specified in the Manuals and these special provisions.

If the Contractor or the Engineer identifies a deficiency in any aspect of the implementation of the approved SWPPP or amendments, the deficiency shall be corrected immediately. The deficiency may be corrected at a later date and time if requested by the Contractor and approved by the Engineer in writing, but not later than the onset of precipitation. If the Contractor fails to correct the identified deficiency by the date agreed or prior to the onset of precipitation the project shall be in noncompliance. Attention is directed to Section 5-1.01, "Authority of the Engineer," of the Standard Specifications and the payment sections of these special provisions for possible noncompliance penalties.

If the Contractor fails to conform to the provisions of "Water Pollution Control," the Engineer may order the suspension of construction operations which create water pollution.

Implementation of water pollution control practices may vary by season. The Construction Site BMP Manual and these special provisions shall be followed for control practice selection of year round, rainy season and non-rainy season water pollution control practices.

### **Year-Round Implementation Requirements**

The Contractor shall have a year-round program for implementing, inspecting and maintaining water pollution control practices for wind erosion control, tracking control, non-storm water control, and waste management and materials pollution control.

The National Weather Service weather forecast shall be monitored and used by the Contractor on a daily basis. An alternative weather forecast proposed by the Contractor may be used if approved by the Engineer. If precipitation is predicted, the necessary water pollution control practices shall be deployed prior to the onset of the precipitation.

Disturbed soil areas shall be considered active whenever the soil disturbing activities have occurred, continue to occur or will occur during the ensuing 21 days. Non-active areas shall be protected as prescribed in the Construction Site BMP Manual within 14 days of cessation of soil disturbing activities or prior to the onset of precipitation, whichever occurs first.

### **Rainy Season Requirements**

Soil stabilization and sediment control practices conforming to the requirements in the Special Requirements and applicable Preparation Manual Minimum Requirements, shall be provided throughout the rainy season, defined as between November 1 and March 15.

Throughout the defined rainy season, the active disturbed soil area of the project site shall be not more than 2 hectares. The Engineer may approve, on a case-by-case basis, expansions of the active disturbed soil area limit. Soil stabilization and sediment control materials shall be maintained on site sufficient to protect the unprotected disturbed soil area. A detailed plan for the mobilization of sufficient labor and equipment shall be maintained to deploy the water pollution control practices required to protect the project site prior to the onset of precipitation events.

### **Non-Rainy Season Requirements**

The non-rainy season shall be defined as all days outside the defined rainy season. The Contractor's attention is directed to the Construction Site BMP Manual for soil stabilization and sediment control implementation requirements on disturbed soil areas during the non-rainy season. Disturbed soil areas within the project shall be protected in conformance with the requirements in the Construction Site BMP Manual with an effective combination of soil stabilization and sediment control.

### **MAINTENANCE**

To ensure the proper implementation and functioning of water pollution control practices, the Contractor shall regularly inspect and maintain the construction site for the water pollution control practices identified in the SWPPP. The construction site shall be inspected by the Contractor as follows:

- A. Prior to a forecast storm;
- B. After a precipitation event which causes site runoff;
- C. At 24 hour intervals during extended precipitation events;
- D. Routinely, a minimum of once every two weeks outside of the defined rainy season;
- E. Routinely, a minimum of once every week during the defined rainy season.

The Contractor shall use the Storm Water Quality Construction Site Inspection Checklist provided in the Preparation Manual or an alternative inspection checklist provided by the Engineer. One copy of each site inspection record shall be submitted to the Engineer within 24 hours of completing the inspection.

### **REPORTING REQUIREMENTS**

#### **Report of Discharges, Notices or Orders**

If the Contractor identifies any discharge into receiving waters in a manner causing, or potentially causing, a condition of pollution, or if the project receives a written notice or order from any regulatory agency, the Contractor shall immediately inform the Engineer. The Contractor shall submit a written report to the Engineer within 7 days of the discharge event, notice, or order. The report shall include the following information:

- A. The date, time, location, nature of the operation, and type of discharge, including the cause or nature of the notice or order.
- B. The water pollution control practices deployed before the discharge event, or prior to receiving the notice or order.
- C. The date of deployment and type of water pollution control practices deployed after the discharge event, or after receiving the notice, or order, including additional measures installed or planned to reduce or prevent reoccurrence.
- D. An implementation and maintenance schedule for any affected water pollution control practices.

#### **Report of First-Time Non-Storm Water Discharge**

The Contractor shall notify the Engineer at least 3 days in advance of each first-time non-storm water discharge event, excluding exempted discharges. The Contractor shall notify the Engineer of each different operation causing a non-storm water discharge and shall obtain field approval for each first-time non-storm water discharge. Non-storm water discharges shall be monitored at each first-time occurrence and routinely thereafter.

## **Annual Certifications**

By June 15 of each year, the Contractor shall complete and submit an Annual Construction Activity Certification as contained in the Preparation Manual to the Engineer.

## **PAYMENT**

The contract lump sum price paid for prepare storm water pollution prevention plan shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals for doing all the work involved in developing, preparing, obtaining approval of, revising, and amending the SWPPP, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Attention is directed to Section 9-1.06, "Partial Payments," and Section 9-1.07, "Payment After Acceptance," of the Standard Specifications. Payments for prepare storm water pollution prevention plan will be made as follows:

- A. After the SWPPP has been approved by the Engineer, 75 percent of the contract item price for prepare storm water pollution prevention plan will be included in the monthly partial payment estimate; and
- B. After acceptance of the contract in conformance with the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, payment for the remaining 25 percent of the contract item price for prepare storm water pollution prevention plan will be made in conformance with the provisions in Section 9-1.07.

The contract lump sum price paid for water pollution control shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing, constructing, removing, and disposing of water pollution control practices, including non-storm water and waste management and materials pollution water pollution control practices except those shown on the plans and for which there is a contract item of work, and excluding developing, preparing, obtaining approval of, revising, and amending the SWPPP, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The cost of maintaining the temporary water pollution control practices shall be divided equally by the State and the Contractor as follows:

### **Soil Stabilization**

All temporary water pollution control practices except:

- SS-1 Scheduling
- SS-2 Preservation of Existing Vegetation

### **Sediment Control**

All temporary water pollution control practices.

### **Tracking Control**

All temporary water pollution control practices except:

- SC-7 Street Sweeping and Vacuuming

### **Wind Erosion Control**

All temporary water pollution control practices.

### **Non-Storm Water Control**

No sharing of maintenance costs will be allowed.

### **Waste Management & Material Control**

No sharing of maintenance costs will be allowed.

The division of cost will be made by determining the cost of maintaining temporary water pollution control practices in conformance with the provisions in Section 9-1.03, "Force Account Payment," of the Standard Specifications and paying to the Contractor one-half of that cost. Clean-up, repair, removal, disposal, improper installation, and replacement of temporary water pollution control practices damaged by the Contractor's negligence shall not be considered as included in the cost for performing maintenance and no additional compensation will be allowed therefor.

The provisions for sharing maintenance costs shall not relieve the Contractor from the responsibility for providing appropriate maintenance on those items where maintenance costs are not shared.

Full compensation for maintenance costs of water pollution control practices not shared, as specified in these special provisions, shall be considered as included in the contract lump sum price paid for water pollution control and no additional compensation will be allowed therefor.

Those water pollution control practices which are shown on the plans and for which there is a contract item of work will be measured and paid for as that contract item of work.

The Engineer will retain an amount equal to 25 percent of the estimated value of the contract work performed during estimate periods in which the Contractor fails to conform to the provisions of this section "Water Pollution Control," as determined by the Engineer.

Retention for failure to conform to the provisions in this section "Water Pollution Control" shall be in addition to the other retention provided for in the contract. The amounts retained for failure of the Contractor to conform to the provisions in this section will be released for payment on the next monthly estimate for partial payment following the date that an approved SWPPP has been implemented and maintained, and water pollution is adequately controlled, as determined by the Engineer.

### **10-1.03 PRESERVATION OF PROPERTY**

Attention is directed to Section 7-1.11, "Preservation of Property," of the Standard Specifications and these special provisions.

Existing trees, shrubs and other plants, that are not to be removed as shown on the plans or specified in these special provisions, and are injured or damaged by reason of the Contractor's operations, shall be replaced by the Contractor. The minimum size of tree replacement shall be 600 mm box and the minimum size of shrub replacement shall be No. 15 container. Replacement ground cover plants shall be from flats and shall be planted 300 mm on center. Replacement of Carpobrotus ground cover plants shall be from cuttings and shall be planted 300 mm on center. Replacement planting shall conform to the requirements in Section 20-4.07, "Replacement," of the Standard Specifications. The Contractor shall water replacement plants in conformance with the provisions in Section 20-4.06, "Watering," of the Standard Specifications.

Damaged or injured plants shall be removed and disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13 of the Standard Specifications. At the option of the Contractor, removed trees and shrubs may be reduced to chips. The chipped material shall be spread within the highway right of way at locations designated by the Engineer.

Replacement planting of injured or damaged trees, shrubs, and other plants shall be completed prior to the start of the plant establishment period. Replacement planting shall conform to the provisions in Section 20-4.05, "Planting," of the Standard Specifications.

### **10-1.04 DAMAGE REPAIR**

Attention is directed to Section 7-1.16, "Contractor's Responsibility for the Work and Materials," and Section 7-1.165, "Damage by Storm, Flood, Tsunami or Earthquake," of the Standard Specifications and these special provisions.

Damage to slopes or other existing facilities occurring prior to the performance of the work provided for in this contract shall be repaired or reconstructed by the Contractor, as directed by the Engineer. Damage repair will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Storm damage caused by a change in the runoff pattern from that which existed on the day the Notice to Contractors for this project is dated and was the result of work by others within the right of way shall be repaired as directed by the Engineer. The total cost of ordered repair work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Damage to slopes or other facilities occurring after start of work and before start of plant establishment period shall be repaired or reconstructed by the Contractor in conformance with the provisions in Section 7-1.16, "Contractor's Responsibility for the Work and Materials," of the Standard Specifications.

Damage to slopes, plants, irrigation systems and other highway facilities occurring as a result of rain during the plant establishment period shall be repaired by the Contractor, when directed by the Engineer. The cost of the repairs which exceed the accumulated sum of \$7000 will be borne equally by the State and the Contractor. The division of cost will be made by determining the cost of repairs in conformance with the provisions in Section 9-1.03, "Force Account Payment," of the Standard Specifications, and paying to the Contractor one-half of the cost which exceeds the sum of \$7000.

When as a result of freezing conditions (as defined herein) during the plant establishment period, plants have died or, in the opinion of the Engineer, have deteriorated to a point beyond which the plants will not mature as typical examples of their species, the Engineer may direct replacement of the affected plants. The total cost of ordered plant replacement work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. A freezing condition, for the purpose of this specification, occurs when the temperature at or near the affected area has been officially recorded below 0°C and plants have been killed or damaged to the degree described above.

When, as a result of drought conditions (as defined herein) during the plant establishment period, plants have died or, in the opinion of the Engineer, have deteriorated to a point beyond which the plants will not mature as typical examples of their species, the Engineer may direct replacement of the affected plants. The total cost of ordered plant replacements, after water has been restricted or stopped, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. Restriction or shutoff of available water shall not relieve the Contractor from performing other contract work. A drought condition occurs when the Department, or its supplier, restricts or stops delivery of water to the Contractor to the degree that plants have died or deteriorated as described above.

When the provisions in Section 7-1.165, "Damage by Storm, Flood, Tsunami or Earthquake," of the Standard Specifications are applicable, the provisions above for payment of costs for repair of damage due to rain, freezing conditions and drought shall not apply.

**10-1.05 COOPERATION**

Attention is directed to Section 7-1.14, "Cooperation," and Section 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications and these special provisions.

It is anticipated that work by the following contractors may be in progress adjacent to or within the limits of this project during progress of the work on this contract:

(Contract No. 06-393304) to rehabilitate roadway in the City of Fresno on Route 99 from Ventura Street Overcrossing to the Fresno/Madera County Line (KP 32.5 to KP 50.9). (Contract No. 06-411804) to construct concrete barrier and double thrie beam barrier on Route 99 from Mountain View Ave. OC to San Joaquin River Bridge at various locations (KP R6.8 to KP 8.6), (KP 12.1 to KP 26.7) and (KP 43.9 to KP 45.7). (Contract No. 06-440104) to enhance the roadway in the City of Fresno on Route 99 from American Avenue Overcrossing to San Joaquin River Bridge (KP 23.3 to KP 50.7).

**10-1.06 OBSTRUCTIONS**

Attention is directed to Section 8-1.10, "Utility and Non-Highway Facilities," and Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Attention is directed to the existence of certain underground facilities that may require special precautions be taken by the Contractor to protect the health, safety and welfare of workers and of the public. Facilities requiring special precautions include, but are not limited to: conductors of petroleum products, oxygen, chlorine, and toxic or flammable gases; natural gas in pipelines greater than 150 mm in diameter or pipelines operating at pressures greater than 415 kPa (gage); underground electric supply system conductors or cables, with potential to ground of more than 300 V, either directly buried or in a duct or conduit which do not have concentric grounded or other effectively grounded metal shields or sheaths.

The Contractor shall notify the Engineer and the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to performing any excavation or other work close to any underground pipeline, conduit, duct, wire or other structure. Regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	1-800-642-2444 1-800-227-2600
Underground Service Alert-Southern California (USA)	1-800-422-4133 1-800-227-2600

**10-1.07 DUST CONTROL**

Dust control shall conform to the provisions in Section 10, "Dust Control," of the Standard Specifications

**10-1.08 MOBILIZATION**

Mobilization shall conform to the provisions in Section 11, "Mobilization," of the Standard Specifications.

**10-1.09 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES**

Flagging, signs, and all other traffic control devices furnished, installed, maintained, and removed when no longer required shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Category 1 traffic control devices are defined as those devices that are small and lightweight (less than 45 kg), and have been in common use for many years. The devices shall be known to be crashworthy by crash testing, crash testing of similar devices, or years of demonstrable safe performance. Category 1 traffic control devices include traffic cones, plastic drums, portable delineators, and channelizers.

If requested by the Engineer, the Contractor shall provide written self-certification for crashworthiness of Category 1 traffic control devices. Self-certification shall be provided by the manufacturer or Contractor and shall include the following: date, Federal Aid number (if applicable), expenditure authorization, district, county, route and kilometer post of project limits; company name of certifying vendor, street address, city, state and zip code; printed name, signature and title of certifying person; and an indication of which Category 1 traffic control devices will be used on the project. The Contractor may obtain a standard form for self-certification from the Engineer.

Category 2 traffic control devices are defined as those items that are small and lightweight (less than 45 kg), that are not expected to produce significant vehicular velocity change, but may otherwise be potentially hazardous. Category 2 traffic control devices include: barricades and portable sign supports.

Category 2 devices purchased on or after October 1, 2000 shall be on the Federal Highway Administration (FHWA) Acceptable Crashworthy Category 2 Hardware for Work Zones list. This list is maintained by FHWA and can be located at the following internet address: <http://safety.fhwa.dot.gov/fourthlevel/hardware/listing.cfm?code=workzone>. The Department maintains a secondary list at the following internet address: <http://www.dot.ca.gov/hq/traffops/signtech/signdel/pdffiles.htm>.

Category 2 devices that have not received FHWA acceptance, and were purchased before October 1, 2000, may continue to be used until they complete their useful service life or until January 1, 2003, whichever comes first. Category 2 devices in use that have received FHWA acceptance shall be labeled with the FHWA acceptance letter number and the name of the manufacturer by the start of the project. The label shall be readable. After January 1, 2003, all Category 2 devices without a label shall not be used on the project.

Full compensation for providing self-certification for crashworthiness of Category 1 traffic control devices and labeling Category 2 devices as specified shall be considered as included in the prices paid for the various contract items of work requiring the use of the Category 1 or Category 2 traffic control devices and no additional compensation will be allowed therefor.

**10-1.10 CONSTRUCTION AREA SIGNS**

Construction area signs shall be furnished, installed, maintained, and removed when no longer required in conformance with the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. Type II retroreflective sheeting shall not be used on construction area sign panels.

Attention is directed to "Construction Project Information Signs" of these special provisions regarding the number and type of construction project information signs to be furnished, erected, maintained, and removed and disposed of.

The Contractor shall notify the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to commencing excavation for construction area sign posts. The regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	1-800-642-2444 1-800-227-2600
Underground Service Alert-Southern California (USA)	1-800-422-4133 1-800-227-2600

Excavations required to install construction area signs shall be performed by hand methods without the use of power equipment, except that power equipment may be used if it is determined there are no utility facilities in the area of the proposed post holes.

Sign substrates for stationary mounted construction area signs may be fabricated from fiberglass reinforced plastic as specified under "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

**10-1.11 MAINTAINING TRAFFIC**

Attention is directed to Sections 7-1.08, "Public Convenience," 7-1.09, "Public Safety," and 12, "Construction Area Traffic Control Devices," of the Standard Specifications and to the provisions in "Public Safety" of these special provisions and these special provisions. Nothing in these special provisions shall be construed as relieving the Contractor from the responsibilities specified in Section 7-1.09.

No work that would require a lane closure shall be performed.

Personal vehicles of the Contractor's employees shall not be parked on the traveled way or shoulders including any section closed to public traffic.

Whenever vehicles or equipment are parked on the shoulder within 1.8 m of a traffic lane, the shoulder area shall be closed as shown on the plans.

### **10-1.12 TEMPORARY CRASH CUSHION MODULE**

This work shall consist of furnishing, installing, and maintaining sand filled temporary crash cushion modules in groupings or arrays at each location shown on the plans, as specified in these special provisions or where designated by the Engineer. The grouping or array of sand filled modules shall form a complete sand filled temporary crash cushion in conformance with the details shown on the plans and these special provisions.

Attention is directed to "Public Safety" of these special provisions.

#### **GENERAL**

Whenever the work or the Contractor's operations establishes a fixed obstacle, the exposed fixed obstacle shall be protected with a sand filled temporary crash cushion. The sand filled temporary crash cushion shall be in place prior to opening the lanes adjacent to the fixed obstacle to public traffic.

Sand filled temporary crash cushions shall be maintained in place at each location, including times when work is not actively in progress. Sand filled temporary crash cushions may be removed during a work period for access to the work provided that the exposed fixed obstacle is 4.6 m or more from a lane carrying public traffic and the temporary crash cushion is reset to protect the obstacle prior to the end of the work period in which the fixed obstacle was exposed. When no longer required, as determined by the Engineer, sand filled temporary crash cushions shall be removed from the site of the work.

#### **MATERIALS**

At the Contractor's option, the modules for use in sand filled temporary crash cushions shall be either Energite III Inertial Modules, Fitch Inertial Modules or Traffix Sand Barrels manufactured after March 31, 1997, or equal:

- A. Energite III Inertial Modules, manufactured by Energy Absorption Systems, Inc., One East Wacker Drive, Chicago, IL 60601-2076, Telephone 1-312-467-6750, FAX 1-800-770-6755.
  - 1. Distributor (Northern): Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828, Telephone 1-800-884-8274, FAX 1-916-387-9734
  - 2. Distributor (Southern): Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, CA 92805, Telephone 1-800-222-8274, FAX 1-714-937-1070.
  
- B. Fitch Inertial Modules, manufactured by Roadway Safety Service, Inc., 1050 North Rand Road, Wauconda, IL 60084, Telephone 1-800-426-0839, FAX 1-847-487-9820.
  - 1.. Distributor (Northern): Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828, Telephone 1-800-884-8274, FAX 1-916-387-9734
  - 2. Distributor (Southern): Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, CA 92805, Telephone 1-800-222-8274, FAX 1-714-937-1070.
  
- C. Traffix Sand Barrels, manufactured by Traffix Devices, Inc., 220 Calle Pintoresco, San Clemente, CA 92672, Telephone 1-949-361-5663, FAX 1-949-361-9205.
  - 1. Russ Enterprises, Inc., 1533 Berger Drive, San Jose, CA 95112, Telephone 1-408-287-4303, FAX 1-408-287-1929.
  - 2. Statewide Safety, P.O. Box 1440, Pismo Beach, CA 93448, Telephone 1-800-559-7080, FAX 1-805-929-5786.

Modules contained in each temporary crash cushion shall be of the same type at each location. The color of the modules shall be the standard yellow color, as furnished by the vendor, with black lids. The modules shall exhibit good workmanship free from structural flaws and objectionable surface defects. The modules need not be new. Good used undamaged modules conforming to color and quality of the types specified herein may be utilized. If used Fitch modules requiring a seal are furnished, the top edge of the seal shall be securely fastened to the wall of the module by a continuous strip of heavy duty tape.

Modules shall be filled with sand in conformance with the manufacturer's directions, and to the sand capacity in kilograms for each module shown on the plans. Sand for filling the modules shall be clean washed concrete sand of commercial quality. At the time of placing in the modules, the sand shall contain not more than 7 percent water as determined by California Test 226.

Modules damaged due to the Contractor's operations shall be repaired immediately by the Contractor at the Contractor's expense. Modules damaged beyond repair, as determined by the Engineer, due to the Contractor's operations shall be removed and replaced by the Contractor at the Contractor's expense.

## **INSTALLATION**

Temporary crash cushion modules shall be placed on movable pallets or frames conforming to the dimensions shown on the plans. The pallets or frames shall provide a full bearing base beneath the modules. The modules and supporting pallets or frames shall not be moved by sliding or skidding along the pavement or bridge deck.

A Type R or P marker panel shall be attached to the front of the crash cushion as shown on the plans, when the closest point of the crash cushion array is within 3.6 m of the traveled way. The marker panel, when required, shall be firmly fastened to the crash cushion with commercial quality hardware or by other methods determined by the Engineer.

At the completion of the project, temporary crash cushion modules, sand filling, pallets or frames, and marker panels shall become the property of the Contractor and shall be removed from the site of the work. Temporary crash cushion modules shall not be installed in the permanent work.

## **MEASUREMENT AND PAYMENT**

Temporary crash cushion modules placed in conformance with the provisions in "Public Safety" of these special provisions will not be measured nor paid for.

### **10-1.13 EXISTING HIGHWAY FACILITIES**

The work performed in connection with various existing highway facilities shall conform to the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

#### **REMOVE ASPHALT CONCRETE DIKE**

Existing asphalt concrete dike, where shown on the plans to be removed, shall be removed.

Prior to removing the dike, the outside edge of the asphalt concrete to remain in place shall be cut on a neat line to a minimum depth of 50 mm.

The dike shall be removed in such a manner that the surfacing which is to remain in place is not damaged.

The dike shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13 of the Standard Specifications.

#### **REMOVE CONCRETE CURB**

Concrete curb, where shown on the plans to be removed, shall be removed.

Removing concrete curb, will be measured by the meter, measured along the curb before removal operations.

Concrete removed shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

### **10-1.14 EARTHWORK**

Earthwork shall conform to the provisions in Section 19, "Earthwork," of the Standard Specifications and these special provisions.

### **10-1.15 MATERIAL CONTAINING AERIALY DEPOSITED LEAD**

Earthwork involving materials containing aerially deposited lead shall conform to the provisions in "Earthwork" and this section "Material Containing Aerially Deposited Lead" of these special provisions.

Attention is directed to "Aerially Deposited Lead" of these special provisions.

Type Y material contains aerially deposited lead in average concentrations greater than or equal to 5.0 mg/L Soluble Lead and between 0 - 350 mg/kg (inclusive) Total Lead, as tested using the California Waste Extraction Test. Type Y material exists between 0.3 m and 2.0 m, measured horizontally from the edges of existing pavement, from Station 11+28.82 to Station 28+43, and from a depth of 0 m to 0.6 m below existing grade, or as shown on the plans. These materials shall be placed as shown on the plans, unless otherwise directed by the Engineer, and covered with a minimum 0.3 m layer of non-hazardous soil or pavement. These materials are hazardous waste regulated by the State of California that may be reused as permitted under the Variance of the Department of Toxic Substances Control. Temporary surplus material may be generated on this project due to the requirements of stage construction. Temporary surplus material shall not be transported outside the project limits. In order to conform to the requirements of these provisions, it may be necessary to stockpile materials for subsequent stages or construct some embankments out of stage or handle temporary surplus material more than once.

## **LEAD COMPLIANCE PLAN**

The Contractor shall prepare a project specific Lead Compliance Plan to prevent or minimize worker exposure to lead while handling material containing aerielly deposited lead. Attention is directed to Title 8, California Code of Regulations, Section 1532.1, "Lead," for specific Cal-OSHA requirements when working with lead.

The Lead Compliance Plan shall contain the elements listed in Title 8, California Code of Regulations, Section 1532.1(e)(2)(B). Before submission to the Engineer, the Lead Compliance Plan shall be approved by an Industrial Hygienist certified in Comprehensive Practice by the American Board of Industrial Hygiene. The Plan shall be submitted to the Engineer for review and acceptance at least 15 days prior to beginning work in areas containing aerielly deposited lead.

The Contractor shall not work in areas containing aerielly deposited lead within the project limits, unless authorized in writing by the Engineer, until the Engineer has accepted the Lead Compliance Plan.

Prior to performing work in areas containing aerielly deposited lead, personnel who have no prior training or are not current in their training status, including State personnel, shall complete a safety training program provided by the Contractor. The safety training program shall meet the requirements of Title 8, California Code of Regulations, Section 1532.1, "Lead."

Personal protective equipment, training, and washing facilities required by the Contractor's Lead Compliance Plan shall be supplied to State personnel by the Contractor. The number of State personnel will be 2.

The Engineer will notify the Contractor of acceptance or rejection of any submitted or revised Lead Compliance Plan not more than 10 days after submittal of the plan.

The contract lump sum price paid for Lead Compliance Plan shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in preparing the Lead Compliance Plan, including paying the Certified Industrial Hygienist, and for providing personal protective equipment, training and medical surveillance, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

## **EXCAVATION AND TRANSPORTATION PLAN**

Within 15 days after approval of the contract, the Contractor shall submit 3 copies of the Excavation and Transportation Plan to the Engineer. The Engineer will have 7 days to review the Excavation and Transportation Plan. If revisions are required, as determined by the Engineer, the Contractor shall revise and resubmit the Excavation and Transportation Plan within 7 days of receipt of the Engineer's comments. The Engineer will have 7 days to review the revisions. Upon the Engineer's approval of the Excavation and Transportation Plan, 3 additional copies of the Excavation and Transportation Plan incorporating the required changes shall be submitted to the Engineer. Minor changes or clarifications to the initial submittal may be made and attached as amendments to the Excavation and Transportation Plan. In order to allow construction to proceed, the Engineer may conditionally approve the Excavation and Transportation Plan while minor revisions or amendments to the Plan are being completed.

The Contractor shall prepare a written, project specific Excavation and Transportation Plan establishing the procedures the Contractor will use to comply with requirements for excavating, transporting, and placing (or disposing) of material containing aerielly deposited lead. The Excavation and Transportation Plan shall conform to the regulations of the Department of Toxic Substance Control and the California Division of Occupational Safety and Health Administration (Cal-OSHA). The sampling and analysis plans shall meet the requirements for the design and development of the sampling plan, statistical analysis, and reporting of test results contained in USEPA, SW 846, "Test Methods for Evaluating Solid Waste," Volume II: Field Manual Physical/Chemical, Chapter Nine, Section 9.1. The plan shall contain, but not be limited to the following elements:

- A. Excavation schedule (by location and date).
- B. Temporary locations of stockpiled material.
- C. Sampling and analysis plans for areas after removal of a stockpile.
  1. Location and number of samples
  2. Analytical laboratory
- . Sampling and analysis plan for post excavation from Station 19 to Station 71 as shown on the plans.
- E. Dust control measures.
- F. Example of Bill of Lading to be carried by trucks transporting Type Y material. The Bill of Lading shall contain: US DOT description including shipping name, hazard class, and ID number; handling codes; quantity of material; volume of material. Copies of the bills of lading shall be provided to the Engineer upon placement of Type Y material in its final location. Trucks carrying Type Y material shall not leave the highway right of way.
- G. Spill Contingency Plan for material containing aerielly deposited lead.

## **DUST CONTROL**

Excavation, transportation, placement, and handling of materials containing aerially deposited lead shall result in no visible dust migration. The Contractor shall have a water truck or tank on the job site at all times while clearing and grubbing and performing earthwork operations in work areas containing aerially deposited lead.

Stockpiles of material containing aerially deposited lead shall not be placed where affected by surface run-on or run-off. Stockpiles shall be covered with plastic sheeting 0.33 mm minimum thickness or 0.3 m of non-hazardous material. Stockpiles shall not be placed in environmentally sensitive areas. Stockpiled material shall not enter storm drains, inlets, or waters of the State.

## **MATERIAL TRANSPORTATION**

Prior to traveling on public roads, loose and extraneous material shall be removed from surfaces outside the cargo areas of the transporting vehicles and the cargo shall be covered with tarpaulins, or other cover, as outlined in the approved Excavation and Transportation Plan. The Contractor shall be responsible for costs due to spillage of material containing lead during transport. The Department will not consider the Contractor a generator of these hazardous materials, and the Contractor will not be obligated for further cleanup, removal, or remedial action for such materials handled or disposed of in conformance with the requirements specified in these special provisions and the appropriate State and Federal laws and regulations and county and municipal ordinances and regulations regarding hazardous waste.

The Engineer will obtain the State of California Board of Equalization Identification Number for hazardous material disposal. The Engineer will sign all hazardous waste manifests. The Contractor shall notify the Engineer five days before the manifests are to be signed.

## **MEASUREMENT AND PAYMENT**

Quantities of roadway excavation (aerially deposited lead) of the types shown in the Engineer's Estimate, will be measured and paid for in the same manner specified for roadway excavation in Section 19, "Earthwork," of the Standard Specifications.

Full compensation for preparing an approved Excavation and Transportation Plan, transporting material containing aerially deposited lead reused in the work from location to location, and transporting and disposing of material containing aerially deposited lead shall be considered as included in the contract prices paid per cubic meter for the items of roadway excavation (aerially deposited lead) involved, and no additional compensation will be allowed therefor.

No payment for stockpiling of material containing aerially deposited lead will be made, unless the stockpiling is ordered by the Engineer.

### **10-1.16 IRRIGATION CROSSOVERS**

Irrigation crossovers shall conform to the provisions in Section 20-5, "Irrigation Systems," of the Standard Specifications and these special provisions.

Conduits shall be installed under existing paving by jacking or drilling methods in conformance with the provisions in Section 20-5.03B, "Conduit for Irrigation Crossovers," of the Standard Specifications.

### **10-1.17 EXTEND IRRIGATION CROSSOVERS**

Extend existing irrigation crossovers shall conform to the provisions in Section 20-5, "Irrigation Systems," of the Standard Specifications and these special provisions.

Extend irrigation crossovers shall include conduit, water line crossover, and sprinkler control crossover extensions and appurtenances, locating existing irrigation crossovers and pressure testing existing and new water line crossovers. The sizes of conduit, water line crossover, and sprinkler control crossover extensions shall be as shown on the plans.

Before work is started in an area where an existing irrigation crossover conduit is to be extended, the existing conduit shall be located by the Contractor. When exploratory holes are used to locate the existing conduit, the exploratory holes shall be excavated in conformance with the provisions in Section 20-5.03B, "Conduit for Irrigation Crossovers," of the Standard Specifications.

If debris is encountered in the ends of conduits to be extended, the debris shall be removed prior to extending conduits. Removal of debris within the first meter in the conduits shall be at the Contractor's expense. If debris is encountered in the conduit more than one meter from the ends of the conduits to be extended, the additional debris shall be removed as directed by the Engineer and will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Conduit extensions shall be corrugated high density polyethylene (CHDPE) pipe.

Water line crossover extensions shall be plastic pipe (PR 315) (supply line).

Sprinkler control crossover extensions shall be Type 3 electrical conduit.

Conduits shall be removed from existing sprinkler control crossovers to be extended.

After installation of the sprinkler control crossover extensions, new conductors shall be installed without splices in existing and extended sprinkler control crossovers. New conductors shall match the removed conductors in color and size and shall be spliced to the existing conductors in adjacent pull boxes. After the new conductors are installed, the conductors shall be tested in the same manner specified for traffic signal, sign illumination, and lighting circuits in conformance with the provisions in Section 86-2.14B, "Field Testing," of the Standard Specifications.

After water line crossover extensions have been installed, existing and extended water line crossovers shall be retested for leakage in conformance with the provisions in Section 20-5.03H, "Pressure Testing," of the Standard Specifications. Leaks that develop shall be repaired at the Contractor's expense and the water line crossovers shall be retested until a satisfactory pressure test is achieved.

#### **10-1.18 MAINTENANCE VEHICLE PULLOUT**

Maintenance vehicle pullouts shall be constructed with minor concrete (texture paving) as shown on the plans and in conformance with these special provisions.

##### **EARTHWORK**

Earthwork shall conform to the provisions in Section 19, "Earthwork," of the Standard Specifications and these special provisions.

The grading plane shall not be more than 15 mm above the grade established by the Engineer.

A relative compaction of not less than 95 percent shall be obtained for a minimum depth of 150 mm below the grading plane.

Attention is directed to "Material Containing Aerially Deposited Lead" elsewhere in these special provisions regarding the handling of soil containing aerial deposited lead.

##### **AGGREGATE BASE**

Aggregate for aggregate base shall conform to the provisions specified for 19-mm, Maximum, aggregate grading in Section 26-1.02A, "Class 2 Aggregate Base," of the Standard Specifications.

Aggregate base shall be a minimum of 150 mm thick. Aggregate base shall be spread and compacted in conformance with the provisions in Section 26-1.04, "Spreading," and Section 26-1.05, "Compacting," of the Standard Specifications.

##### **MINOR CONCRETE (TEXTURE PAVING)**

Portland cement concrete for maintenance vehicle pullouts shall be minor concrete conforming to the provisions in Section 90-10, "Minor Concrete," of the Standard Specifications.

The colors and texture specified for the textured paving shall match existing gore area paving found at Chestnut Avenue off ramp originally installed on EA 06-440104, Sta 271+40 Rt. Portland cement concrete closely conforming to the colors specified for textured paving are available through commercial concrete sources.

A sample of sufficient size to demonstrate the textured paving, including color hardener, release agent, curing and finishing compounds, for ungrouted finishes, shall be submitted to the Engineer for written approval.

Textured paving shall not be placed on the project prior to approval by the Engineer of the samples prepared and submitted by the Contractor. In the event more than one sample of the textured paving to be placed is required by the Engineer, each additional sample will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

The pattern types and colors of concrete for textured paving shall be placed at the locations shown on the plans, struck off and compacted until a layer of mortar is brought to the surface. The concrete shall be screeded to the required grade and cross section and floated to a uniform surface.

Floor color hardener shall be applied to the plastic surface of the concrete by the "dry-shake" method using a minimum of 30 kg of hardener per 10 m<sup>2</sup>. Hardener shall be applied in 2 applications, shall be wood-floated after each application, and shall be trowelled only after the final floating. The resultant color of the floor hardener shall closely conform to the colors specified on the plans for the respective areas.

##### **MEASUREMENT**

Maintenance vehicle pullouts will be measured and paid for by the square meter as determined from the dimensions shown on the plans for the surface area of portland cement concrete, minor concrete (texture paving) in the maintenance vehicle pullouts or from other dimensions that may be ordered in writing by the Engineer.

## **PAYMENT**

The contract price paid per square meter for maintenance vehicle pullout shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing maintenance vehicle pullouts, complete in place, including earthwork minor concrete (texture paving), and color, and aggregate base as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **10-1.19 ASPHALT CONCRETE**

Asphalt concrete shall be Type B and shall conform to the provisions in Section 39, "Asphalt Concrete," of the Standard Specifications and these special provisions.

Asphalt concrete shall be produced from commercial quality asphalt and aggregates. The spreading and compacting provisions in Section 39-6.02, "Spreading," and Section 39-6.03, "Compacting," of the Standard Specifications will not apply.

The asphalt concrete shall conform to the following requirements:

- A. Asphalt concrete shall be produced at a central mixing plant.
- B. Aggregate shall conform to the 19 mm, Maximum, medium grading conforming to the provisions in Section 39-2.02, "Aggregate," of the Standard Specifications.
- C. The amount of asphalt binder to be mixed with the aggregate shall be between 4 percent and 7 percent by mass of the dry aggregate as determined by the Engineer. The amount of asphalt binder used in asphalt concrete placed in dikes shall be increased one percent by mass of the aggregate over the amount of asphalt binder determined for use in asphalt concrete placed on the traveled way. The fifth through eighth paragraphs in Section 39-3.03, "Proportioning," of the Standard Specifications shall not apply.

### **10-1.20 CHAIN LINK WALK GATE**

1.8 m chain link walk gates shall be Type CL-1.8 conforming to the provisions in Section 80, "Fences," of the Standard Specifications and these special provisions.

Gates shall be installed in existing fences at the locations shown on the plans. Gate installations shall be complete with gate post, latch post, concrete footings, braces, truss rods, and hardware. Gate and latch posts shall be braced to the next existing line post as shown on the plans.

At each gate location, an existing line post shall be removed and the new gate installed so that the gate is centered on the post hole of the removed post. Holes resulting from the removal of line posts shall be backfilled.

Gate mounting and latching hardware shall not contain open-end slots for the fastening bolts.

Chain link fabric for gates shall be of the same mesh size as the existing fence in which the gates are installed.

Openings made in existing fences for installation of gates shall be closed during the working day in which the openings are made and when work is not in progress. Temporary closures shall be made with the existing fence fabric or with additional 1.83 m chain link fabric as directed by the Engineer.

Full compensation for making the openings in existing fences, for temporary closing of the openings (including furnishing additional fence fabric if necessary), and for new posts, footings, hardware, braces, and truss rods shall be considered as included in the contract unit price paid for 1.8 m chain link gate (Type CL-1.8) and no additional compensation will be allowed therefor.

## **SECTION 10-2. HIGHWAY PLANTING AND IRRIGATION SYSTEMS**

### **10-2.01 GENERAL**

The work performed in connection with highway planting and irrigation systems shall conform to the provisions in Section 20, "Erosion Control and Highway Planting," of the Standard Specifications and these special provisions.

The Contractor shall notify the Engineer not less than 72 hours prior to requiring initial access to the existing irrigation controllers. When the Engineer determines that access to the controllers is required at other times, arrangements will be made to provide this access.

Full compensation for watering plants outside normal working hours shall be considered as included in the contract unit prices paid for the plants involved and the contract lump sum price paid for plant establishment work and no additional compensation will be allowed therefor.

### **PROGRESS INSPECTIONS**

Progress inspections will be performed by the Engineer for completed highway planting and irrigation system work at designated stages during the life of the contract.

Progress inspections will not relieve the Contractor of responsibility for installation in conformance with the special provisions, plans and Standard Specifications. Work within an area shall not progress beyond each stage until the inspection has been completed, corrective work has been performed, and the work is approved, unless otherwise permitted by the Engineer.

The requirements for progress inspections will not preclude additional inspections of work by the Engineer at other times during the life of the contract.

The Contractor shall notify the Engineer, in writing, at least 4 working days prior to completion of the work for each stage of an area and shall allow a minimum of 3 working days for the inspection.

Progress inspections will be performed at the following stages of work:

- A. During pressure testing of the pipelines on the supply side of control valves.
- B. During testing of low voltage conductors.
- C. Before planting begins and after completion of the work specified for planting in Section 20-4.03, "Preparing Planting Areas," of the Standard Specifications.
- D. Before plant establishment work begins and after completion of the work specified for planting in Section 20-4.05, "Planting," of the Standard Specifications.
- E. At intervals of one month during the plant establishment period.

## **10-2.02 EXISTING HIGHWAY PLANTING**

In addition to the provisions in Section 20 of the Standard Specifications, work performed in connection with existing highway planting shall be in conformance with the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Replacement planting shall conform to the requirements specified under "Preservation of Property" of these special provisions.

### **REMOVE EXISTING PLANTS FOR TRENCHING**

Removing existing plants for trenching shall conform to the provisions in Section 20-5.026, "Remove Existing Plants for Trenching," of the Standard Specifications and these special provisions.

Removing existing plants for trenching work shall consist of removing and replacing ground cover, pruning trees and shrubs within trench locations, applying preemergents and disposing of removed ground cover and prunings.

Replacement of removed ground cover within the maximum 1.8 m width, as specified in Section 20-5.026, "Remove Existing Plants for Trenching," of the Standard Specifications, will be required, except for trenches within 1.8 m of fences, curbs, dikes or shoulders.

Trees and shrubs adjacent to dikes, walks, fences, guard railing, and pavement edges may be pruned back 3 m from these facilities to facilitate trenching work. When trenching is to be performed adjacent to other trees and shrubs that cannot be avoided, the trees and shrubs may be pruned upon receipt of prior written approval of the Engineer.

Pruning shall include removal of deadwood, suckers, and broken or bruised branches 25 mm or larger in diameter. Pruning shall conform to the provisions in Section 20-4.055, "Pruning," of the Standard Specifications.

Removed ground cover and pruned materials shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. At the Contractor's option, removed ground cover and prunings may be reduced to chips. Chipped materials shall be spread within the highway right of way where designated by the Engineer.

Shrubs adjacent to dikes, fences, guard railing, and the edge of pavement within the 3-m pruned area designated above, that in the opinion of the Engineer should be removed after pruning, shall be removed and disposed of. Removing and disposing of the shrubs not otherwise provided for will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

One application of a preemergent pesticide shall be applied to trenched areas in existing ground cover areas and to trenched areas adjacent to fences, curbs, dikes and shoulders. The Engineer will determine when the preemergent pesticide shall be applied.

### **PRUNE EXISTING PLANTS**

Existing plants shown on the plans to be pruned shall be pruned in conformance with the provisions in Section 20-4.055, "Pruning," of the Standard Specifications.

Pruning shall include removal of deadwood, suckers, and broken or bruised branches 25 mm or larger in diameter. Tree seal compounds shall not be used to cover pruning cuts.

Removed pruned materials shall be disposed of outside the highway right of way in conformance to the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. At the

Contractor's option, prunings may be reduced to chips. Chipped materials shall be spread within the highway right of way where designated by the Engineer.

Payment for pruning plants as specified under "Remove Existing Plants for Trenching" shall be in conformance to the provisions in these special provisions and shall not be considered as included in the payment for prune existing plants as provided in this section, "Prune Existing Plants."

The contract lump sum price paid for prune existing plants, except as otherwise provided, shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in pruning existing plants, complete in place, including removing and disposing of pruned materials, or chipping and spreading of chipped materials, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **10-2.03 EXISTING HIGHWAY IRRIGATION FACILITIES**

The work performed in connection with the various existing highway irrigation system facilities shall conform to the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Water shall be maintained in conformance with the provisions in Section 20-5.025, "Maintain Existing Water Supply," of the Standard Specifications.

#### **LOCATE EXISTING CROSSOVERS AND CONDUITS**

Existing crossovers and conduits shown on the plans to be incorporated in the new work shall be located in conformance with the provisions for locating conduits in Section 20-5.03B, "Conduit for Irrigation Crossovers," of the Standard Specifications.

Unless otherwise directed by the Engineer, existing crossovers and conduits shown on the plans to be incorporated in the new work shall be located prior to performing work on irrigation systems.

If debris is encountered in the ends of conduits, the debris shall be removed prior to performing other work in the conduits. Removal of debris within the first one meter in these conduits shall be at the Contractor's expense. If debris is encountered in the conduits more than one meter from the ends of the conduits, the additional debris shall be removed as directed by the Engineer and the removal work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

#### **REMOVE EXISTING IRRIGATION FACILITIES**

Existing irrigation facilities where shown on the plans to be removed, shall be removed. Facilities that are more than 150 mm below finished grade, excluding facilities to be salvaged, may be abandoned in place.

Immediately after disconnecting an existing irrigation facility to be removed or abandoned from an existing facility to remain, the remaining facility shall be capped or plugged, or shall be connected to a new or existing irrigation facility.

Facilities to be removed, excluding facilities to be salvaged, shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

#### **RELOCATE EXISTING IRRIGATION FACILITIES**

Relocate existing irrigation facilities shall consist of relocating existing electric remote control valves, sprinklers, pull boxes gate valves, wye strainers, irrigation controller, and other facilities shown on the plans or specified in these special provisions.

Relocate existing valves shall consist of relocating existing valves, valve boxes and valve box covers. Relocated valve boxes shall be installed with new woven wire cloth and crushed rock bedding as shown on the plans.

Relocate existing sprinklers shall consist of relocating existing sprinklers, risers, riser supports, check valves, and concrete protectors as shown on the plans.

Relocate pull boxes shall consist of relocating existing pull boxes and pull box covers. Relocated pull boxes shall be installed on new woven wire cloth and crushed rock bedding as shown on the plans for valve box installations.

Relocate existing irrigation controllers shall consist of relocating the existing controller, controller enclosure and controller enclosure cabinet; constructing concrete pad; and furnishing and installing anchor bolts, electrical conduits, including control and neutral conductors and electrical power conductors. Conduits for control and neutral conductors and electrical power conductors shall terminate in separate new or relocated pull boxes located within 1.5 m of the new concrete pads.

Relocate existing electrical power (irrigation) for the irrigation controllers shall conform to the provisions in "Electrical Service (Irrigation)" of these special provisions.

Existing irrigation facilities, shown on the plans to be relocated, that are, in the opinion of the Engineer, unsuitable for the purpose intended, shall be replaced in conformance with the provisions in Section 15-2.05, "Reconstruction," of the Standard Specifications.

After irrigation facilities have been relocated, the Contractor shall demonstrate that the relocated facilities function properly in the presence of the Engineer.

**10-2.04 HIGHWAY PLANTING**

The work performed in connection with highway planting shall conform to the provisions in Section 20-4, "Highway Planting," of the Standard Specifications and these special provisions.

**HIGHWAY PLANTING MATERIALS**

**Mulch (Green Material)**

Mulch shall be woody material. Woody materials shall consist of chipped, shredded or ground green materials such as shrubs, tree trimmings or clean processed wood products.

Deleterious materials such as rocks, glass, plastics, metals, clods, weeds, weed seeds, coarse objects, sticks larger than the specified particle size, salts, paint, petroleum products, pesticides or other chemical residues that would be harmful to plant or animal life shall not exceed 0.1-percent of the mulch volume. Chipping shall include shredding, grinding or other methods used to reduce mulch materials to the specified size.

Green materials shall be processed and have reached an internal temperature of 56°C for a minimum of 15 consecutive days. During the processing period, the green material shall have been turned a minimum of 5 times.

Green material shall have a particle size conforming to the provisions for wood chips in Section 20-2.08, "Mulch," of the Standard Specifications.

**Commercial Fertilizer**

Commercial fertilizer (slow release) shall be a pelleted or granular form, shall be slow release, and shall fall within the following guaranteed chemical analysis range:

Ingredient	Percentage
Nitrogen	19
Phosphoric Acid	6
Water Soluble Potash	12

Commercial fertilizer (packet) shall be slow release and shall be in packet form. Each packet, as shown in the Plant List of the plans shall have the following guaranteed chemical analysis:

Ingredient	Percentage
Nitrogen	20
Phosphoric Acid	10
Water Soluble Potash	5

**ROADSIDE CLEARING**

Prior to preparing planting areas or commencing irrigation trenching operations for planting areas, trash and debris shall be removed from these areas and a distance of 3 m beyond the edges of those areas. At locations where proposed planting areas are 3.6 m or more from the edges of dikes, curbs, sidewalks, fences, walls, paved shoulders and existing planting to remain or to be maintained, the clearing limit shall be 2 m beyond the outer limits of the proposed planting area.

In addition to removing trash and debris, the project area shall be cleared as specified herein:

- A. At the option of the Contractor, removed trees and shrubs may be reduced to chips. Chipped material shall be spread within the project limits at locations designated by the Engineer. Chipped material shall not be substituted for mulch, nor shall the chipped material be placed within areas to receive mulch.
- B. Weeds shall be killed and removed within the entire highway right of way, within the project limits, except for existing planting areas to be maintained, and excluding median areas, new and existing pavement, curb, sidewalk and other surfaced areas.

**Weed Control**

Weed control shall also conform to the following:

Stolon type weeds shall be killed with glyphosate.

Disposal of mowed material and killed weeds after initial roadside clearing will not be required, unless otherwise directed by the Engineer. When directed by the Engineer, mowed material and killed weeds shall be disposed of and the disposal will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

### **PESTICIDES**

Pesticides used to control weeds shall conform to the provisions in Section 20-4.026, "Pesticides," of the Standard Specifications. Except as otherwise provided in these special provisions, pesticide use shall be limited to the following materials:

- Cacodylic Acid
- Diquat
- Fluazifop-butyl
- Glyphosate
- Isoxaben (Preemergent)
- Sethoxydim
- Oxadiazon - 50 percent WP (Preemergent)
- Oryzalin (Preemergent)
- Pendimethalin (Preemergent)
- Prodiamine (Preemergent)
- Trifluralin (Preemergent)
- Ammonium Sulfate
- Magnesium Chloride
- Melfluidide (Growth regulator)
- Napropamide (Preemergent)

Granular preemergents may be used when applied to areas that will be covered with mulch, excluding plant basins. Granular preemergents shall be limited to the following materials:

- Dichlobenil (Preemergent)
- Oxadiazon (Preemergent)

Granular preemergents shall be applied prior to the application of mulch. Mulch applications shall be completed in these areas on the same working day. Photosensitive dye will not be required.

Glyphosate shall be used to kill stolon type weeds.

Oxadiazon shall be of the emulsifiable concentration or wettable powder type, except when Oxadiazon is used under mulch in conformance with these special provisions.

Prior to the application of preemergents, ground cover plants shall have been planted a minimum of 3 days and shall have been thoroughly watered.

A minimum of 100 days shall elapse between applications of preemergents.

Except for ground cover plants, preemergents shall not be applied within 450 mm of plants or within wild flower seeding areas.

Growth regulators shall not be applied within 2 m of trees, shrubs or vines.

Ammonium sulfate and magnesium chloride shall be used only in areas planted to *Carpobrotus* or *Delosperma*. Ammonium sulfate and magnesium chloride shall not be applied in a manner that allows the pesticides to come in contact with trees or shrubs.

If the Contractor elects to request the use of other pesticides on this project, the request shall be submitted, in writing, to the Engineer not less than 15 days prior to the intended use of the other pesticides. Except for the pesticides listed in these special provisions, no pesticides shall be used or applied without prior written approval of the Engineer.

Pesticides shall not be applied within the limits of the plant basins. Pesticides shall not be applied in a manner that allows the pesticides to come in contact with the foliage and woody parts of the plants.

### **PREPARING PLANTING AREAS**

Plants adjacent to drainage ditches shall be located so that after construction of the basins, no portion of the basin walls shall be less than the minimum distance shown on the plans for each plant involved.

## PREPARE HOLES

Holes for plants shall be excavated to the minimum dimensions shown on the plans.

Root protectors shall be installed in plant holes in conformance with the details shown on the plans and the provisions in "Root Protectors" of these special provisions and the provisions in Section 20-4.05, "Planting," of the Standard Specifications.

Backfill material for plant holes shall be a mixture of soil and other materials shown on the Plant List. Backfill material shall be thoroughly mixed and uniformly distributed throughout the entire depth of the plant hole without clods and lumps.

Full compensation for preparing holes shall be considered as included in the contract unit prices paid for the plants involved and no separate payment will be made therefor.

## PLANTING

Commercial fertilizer shall be applied or placed at the time of planting and at the rates shown on the plans.

A granular preemergent shall be applied to areas to be covered with mulch outside of plant basins in conformance with the provisions in "Pesticides" of these special provisions.

Mulch placed in areas outside of plant basins shall be spread to a depth of not less than 100 mm.

Mulch shall not be placed within one meter of the center line of earthen drainage ditches, within one meter of the edge of paved ditches, and within one meter of the center line of drainage flow lines.

Attention is directed to "Irrigation Systems Functional Test" of these special provisions regarding functional tests of the irrigation systems. Planting shall not be performed in an area until the functional test has been completed for the irrigation system serving that area.

Quantities of commercial fertilizer packets will be measured by the unit as determined from actual count in place.

The contract unit price paid for commercial fertilizer (packet) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in commercial fertilizer (packet), complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

## ROOT PROTECTOR

Root protectors shall be installed in conformance with the details shown on the plans, the provisions in Section 20-2.13B, "Root Protector," and Section 20-4, "Highway Planting," of the Standard Specifications.

## PLANT ESTABLISHMENT WORK

The plant establishment period shall be Type 1 and shall be 750 working days.

Commercial fertilizer (slow release) shall be applied to trees, shrubs, vines and ground cover during the first week of March and September of each year. Commercial fertilizer shall be applied at the rates shown on the plans and shall be spread with a mechanical spreader wherever possible.

The center to center spacing of replacement plants for unsuitable ground cover plants shall be determined by the number of completed plant establishment working days at the time of replacement and the original spacing in conformance with the following:

ORIGINAL SPACING (Millimeters)	SPACING OF REPLACEMENT GROUND COVER PLANTS (Millimeters)		
	Number of Completed Plant Establishment Working Days		
	1-125	126-190	191-End of Plant Establishment
230	230	150	150
300	300	230	150
460	460	300	230
600	600	460	300
910	910	600	460

During the plant establishment period, the plants shall be watered utilizing the Remote Irrigation Control System (RICS) software program. A watering schedule shall be submitted to the Engineer for use during the plant establishment period.

Weeds within plant basins, including basin walls and ground cover, shall be controlled by hand pulling.

Weeds within mulched and ground cover areas and outside of plant basins shall be controlled by killing.

Weeds outside of mulched areas, plant basins, ground cover, the median, and paved areas shall be controlled by mowing.

Weeds within median areas, pavement, curbs, sidewalk, and other surfaced areas shall be controlled by killing.

Except as specified in these special provisions, disposal of mowed material will not be required unless ordered by the Engineer. Disposal of mowed material, as directed by the Engineer, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

At the option of the Contractor, a growth regulator may be applied to mowed areas, provided the growth regulator is approved in advance by the Engineer and the growth regulator is applied in conformance with these special provisions. If a growth regulator is approved and applied, the growth regulator shall be at the Contractor's expense.

At the option of the Contractor, plants of a larger container size than those originally specified may be used for replacement plants during the first 125 working days of the plant establishment period. The use of plants of a larger container size than those originally specified for replacement plants shall be at the Contractor's expense.

After 125 working days of the plant establishment period have been completed, replacement of plants, except for ground cover plants, shall be No. one size for seedlings, pot and liner size plants; No. 5 size for No. one size plants; No. 15 size for No. 5 size plants; and other plant replacement plants shall be the same size as originally specified.

When ordered by the Engineer, one application of a preemergent pesticide conforming to the provisions in "Pesticides" of these special provisions, shall be applied between 40 and 50 working days prior to completion of the plant establishment period. This work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Previously installed filters shall be removed, cleaned and reinstalled at least 15 days prior to the completion of the plant establishment period.

The final inspection shall be performed in conformance with the provisions in Section 5-1.13, "Final Inspection," of the Standard Specifications and shall be completed a minimum of 20 working days before the estimated completion of the contract.

### 10-2.05 IRRIGATION SYSTEMS

Irrigation systems shall be furnished and installed in conformance with the provisions in Section 20-5, "Irrigation Systems," of the Standard Specifications, except materials containing asbestos fibers shall not be used.

Attention is directed to the provisions in "Obstructions" of these special provisions, regarding work over or adjacent to existing underground facilities. Excavation for proposed irrigation facilities shall not be started until the existing underground facilities have been located.

Only pipeline trenches and excavation pits for supply lines being supplied from one water service point shall be open at one time. After pressure testing is complete, trenches and pits excavated for pipe supply lines, being supplied from one water service point, shall be backfilled prior to commencing excavations for pipe supply lines being supplied from another water service point.

Gate valves, 75 mm and larger in size, shall be furnished with a square lug and shall be operated by use of long shank keys. Prior to acceptance of the contract, 3 long shank keys shall be delivered to the Engineer.

#### VALVE BOXES

Valve boxes shall conform to the provisions in Section 20-2.24, "Valve Boxes," of the Standard Specifications, except as otherwise provided herein.

Valve boxes shall be precast portland cement concrete.

Covers for concrete valve boxes shall be concrete.

Valve boxes shall be identified on the top surface of the covers by labels containing the appropriate abbreviation for the irrigation facility contained in the valve box as shown on the plans. Valve boxes that contain remote control valves shall be identified by the appropriate letters and numbers (controller and station numbers). Labels for valve boxes shall conform to the provisions in Section 20-5.03F, "Valves and Valve Boxes," of the Standard Specifications.

#### IRRIGATION CONTROLLER

Irrigation controller units shall be 24 station and furnished and installed as shown on the plans and as specified in these special provisions. Irrigation controllers shall be installed on a concrete pad in accordance with the details shown on Standard Plan ES-3H.

The price quoted by the supplier for the 24 station irrigation controller (IC) is as follows:

Description - Make/Model	Unit Price	Quantity	Total
Eicon 24 Station Universal Plus satellite, in VIT cold rolled steel strongbox/pedestal with data retrieval board and 800 MHz antenna. (UPN24-TR-CR/P-DR-SP-VRA/800)	\$3,400	2	\$6,800
		<b>TOTAL</b>	<b>\$ 6,800</b>

The above price is guaranteed for all orders placed before September 1, 2001, provided delivery is accepted within 90 days after the order is placed.

Arrangements have been made to insure that any successful bidder can obtain the irrigation controllers from any local authorized Eicon distributor. Information is available from:

United Green Mark Inc.  
143 East Sierra Avenue  
Fresno, CA 93720  
Telephone (559) 431-9220

Door locks for satellite field unit enclosure cabinets shall be a removable-core mortise cam cylinder door lock capable of receiving the State's lock core. The State's lock core is a "Best" construction core. Keys shall be removable from the locks in the locked position only. Door locks shall be installed in accordance with the manufacturer's written instructions and recommendations. Two keys for each door lock shall be delivered to the Engineer.

The quantity of 24 Station Eicon Satellite Field Unit will be measured by the unit as determined from actual count in place.

The contract unit price paid for the 24 Station Eicon Satellite Field Unit shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in 24 Station Eicon Satellite Field Unit, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The irrigation controller unit shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in fabricating and installing 24 station satellite field unit, complete in place including constructing foundations and pads, conduits to pull box adjacent to cabinets, and installing equipment, within the cabinets, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Attention is directed to the requirements specified in Section 10-3, "Electrical Systems," elsewhere in these special provisions, regarding electrical power for irrigation controller units and irrigation controller enclosure cabinets.

Attention is directed to the requirements specified under "Booster Pumps" elsewhere in these special provisions, regarding electrical power for booster pumps controller enclosures irrigation controllers.

#### **Electric Remote Control Valves**

Electric remote control valves shall conform to the provisions in Section 20-2.23, "Control Valves," of the Standard Specifications and the following:

- A. Valves shall be brass, or bronze, construction.
- B. Valves shall be angle pattern (bottom inlet) or straight pattern (side inlet) as shown on the plans.

#### **Electric Remote Control Valve with Pressure Regulator for Type C Sprinklers**

Electric remote control valves with pressure regulator for type C sprinklers shall conform to the provisions in Section 20-2.23, "Control Valves," of the Standard Specifications and the following:

- A. Valve shall be constructed of brass with a glass filled nylon regulator. .
- B. Valve shall be straight pattern (side inlet) as shown on the plans.
- C. Valves shall regulate and maintain a constant outlet pressure between 103 kPa and 690 kPa. Valves shall be set to 260 kPa.
- D. Desired pressure shall be easy to set for optimum performance of type C sprinklers.
- E. Pressure regulator shall be fitted with a schrader valve.
- F. A total of 2 pressure gages shall be provided for this project.

#### **Pull Boxes**

Pull box installations shall conform to the provisions in Section 20-5.027I, "Conductors, Electrical Conduits and Pull Boxes," of the Standard Specifications.

#### **Conductors**

Low voltage, as used in this section "Conductors," shall mean 36 V or less.

Low voltage control and neutral conductors in pull boxes and valve boxes, at irrigation controller terminals, and at splices shall be marked as follows:

- A. Conductor terminations and splices shall be marked with adhesive backed paper markers or adhesive cloth wrap-around markers, with clear, heat-shrinkable sleeves sealed over the markers.
- B. Non-spliced conductors in pull boxes and valve boxes shall be marked with clip-on, "C" shaped, white extruded polyvinyl chloride sleeves. Marker sleeves shall have black, indented legends of uniform depth with transparent overlays over the legends and "chevron" cuts for alignment of 2 or more sleeves.

Markers for the control conductors shall be identified with the appropriate number or letter designations of irrigation controllers and station numbers. Markers for neutral conductors shall be identified with the appropriate number or letter designations of the irrigation controllers.

New control and neutral conductors that are to replace existing control and neutral conductors shall be the same size and color as the existing control and neutral conductors being connected to.

The color of low voltage neutral and control conductor insulation, except for the striped portions, shall be homogeneous throughout the entire thickness of the insulation.

Insulation for conductors may be UL listed polyethylene conforming to UL44 test standards with a minimum insulation thickness of 1.05 mm for wire sizes 10AWG and smaller.

Electric remote control valve with pressure regulator will be measured and paid for as 50 mm pressure reducing valve.

### **FLOW SENSOR**

Flow sensor shall be Data Industrial model 220P, 2".

The quantity of flow sensors will be measured by the unit as determined from actual count in place.

The contract unit price paid for flow sensor shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in flow sensor, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **ARMOR-CLAD CONDUCTORS**

Armor-clad conductors shall be used in direct burial applications from pull boxes adjacent to irrigation controller enclosure cabinets to irrigation facilities in conformance with the details shown on the plans and these special provisions.

Armor-clad conductors shall conform to the following:

- A. Conductors shall be the proper size for the application, and shall be solid, uncoated copper with a conductor size of not less than 90 percent of the AWG diameter required.
- B. Conductor insulation coverings shall be manufactured of polyvinyl chloride (PVC) conforming to UL style, Type UF 60°C, 600 V. Average thickness of insulation shall be not less than 1.52 mm with a minimum thickness of 1.37 mm at any one point.
- C. Armor shall be a minimum of 0.13-mm thick by 12.7 mm wide, Type 304 stainless steel tape that is helically wrapped over each conductor with a 33 percent minimum overlap.
- D. Outer jacket for conductors shall be sunlight resistant PVC and shall conform to the Insulated Power Cable Engineer's Association (ICEA) S-61-402, NEMA Standard WC5, and UL Listing 1263. Nominal thickness of the outer jacket shall be 0.76-mm with a minimum thickness of 0.61 mm at any one point.

At the option of the Contractor, nonarmor-clad conductors conforming to the provisions in Section 20-2.31D, "Conductors," of the Standard Specifications may be used in lieu of armor-clad conductors when the conductors are installed in an electrical conduit.

### **IRRIGATION SYSTEMS FUNCTIONAL TEST**

Functional tests for the remote irrigation controller system (RICS) and associated automatic irrigation systems shall conform to the provisions in Section 20-5.027J, "Testing," of the Standard Specifications and these special provisions.

Two functional tests shall be performed, one without and one with connection to the remote irrigation controller system base station. Both tests shall consist of demonstrating to the Engineer, through one complete cycle of the irrigation controllers in the automatic mode, that the associated automatic components of the irrigation systems operate properly.

The Contractor shall notify the Engineer not less than 2 weeks prior to starting the functional tests for the remote irrigation control system.

The existing remote irrigation controller system base station is located at Fresno North Region Maintenance Station, 1635 West Pine Street, Fresno, California. The Contractor shall operate the irrigation system from the satellite field units and shall not have access to the RICS base station.

Associated automatic components for both tests shall include, but not limited to, new and existing remote control valve actuator systems, booster pump systems, irrigation controllers, remote control valves, conductors, and flow sensors. Associated automatic components for the second test shall include, but not be limited to, new and existing irrigation software programs, cellular phone, existing trunked radio transmission systems, and flow alarms for high, low, zero, and maximum mainline flows.

The first test shall be performed prior to planting the plants and shall consist of testing the irrigation controllers and associated automatic irrigation systems without connection to the remote irrigation controller system base station. Upon completion of a satisfactory functional test, and correction of the deficiencies, the plants to be planted in the areas watered by the irrigation system may be planted, provided the planting areas have been prepared as specified in these special provisions.

A remote irrigation controller system watering schedule shall be submitted for each irrigation controller (field unit) to the Engineer. The Engineer will enter the watering schedule into the irrigation software program, and a computer printout will be made available to the Contractor for verification. If the Engineer determines the submitted watering schedule is unacceptable, a revised watering schedule shall be submitted to the Engineer for approval within 5 working days. Upon completion of a satisfactory test, including correction of deficiencies, the plant establishment period may begin, provided planting work as specified in these special provisions has been completed except for plant establishment work.

If existing and new automatic components of the irrigation systems fail a functional test, the components shall be repaired. Repairs shall be at the Contractor's expense, except for repairs to an existing base station (personal computer, printer, mouse, keyboard, cables, and software) which will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. Testing shall be repeated until satisfactory operation is obtained.

Repair or replacement of existing irrigation facilities due to unsatisfactory performance shall conform to the provisions in Section 20-5.025, "Maintain Existing Water Supply," of the Standard Specifications and "Existing Highway Irrigation Facilities" of these special provisions.

## **PIPE**

### **Plastic Pipe**

Plastic pipe supply lines shall be polyvinyl chloride (PVC) 1120 or 1220 pressure rated pipe with the minimum pressure rating (PR) shown on the plans.

Plastic pipe supply lines less than 100 mm in diameter shall have solvent cemented type joints. Primers shall be used on the solvent cemented type joints.

A nonhardening joint compound shall be used in place of the pipe thread sealant tape conforming to the provisions in Section 20-5.03E, "Pipe," of the Standard Specifications. Joint compounds shall be applied in conformance with the manufacturer's recommendations.

Fittings for plastic pipe supply lines with a pressure rating (PR) of 315 shall be Schedule 80.

## **WATER METER**

Water meters for the irrigation systems will be furnished and installed by the serving utility at the locations shown on the plans.

The Contractor shall make the arrangements and pay the costs and fees required by the serving utility.

The City of Fresno Water Department has established a fee of \$1,500 for furnishing and installing a water meter. If, at the time of installation, this fee has been changed, the State will take a credit for the reduction in the fee, or the State will pay the difference for the increase in the fee. The credit or payment will be taken or paid on the first monthly progress payment made after the meter is installed. The Contractor shall furnish the Engineer with a copy of the invoice for the installation fee.

Attention is directed to Section 20-4.06, "Watering," of the Standard Specifications. The Contractor shall make the arrangements for furnishing and applying water until the water meters have been installed by the serving utility.

The quantity of water meters will be measured by the unit as determined from actual count in place.

The contract unit price paid for water meter shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in furnishing and installing water meters, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

## **BACKFLOW PREVENTER ASSEMBLIES**

Backflow preventers shall conform to the provisions in Section 20-2.25, "Backflow Preventers," of the Standard Specifications and these special provisions.

Pressure loss through the backflow preventers shall not exceed the following:

BACKFLOW PREVENTER SIZE (millimeters)	FLOW RATE (Liters per minute)	PRESSURE LOSS (kPa)
50 mm	302	69

Backflow preventer assemblies shall be painted with a minimum of 2 applications of a commercial quality enamel paint. The color of the paint shall be light brown.

When backflow preventer assembly enclosures are specified, the portland cement concrete pads for the enclosures will be paid for in conformance to the provisions in "Backflow Preventer Assembly Enclosures" of these special provisions.

#### **BACKFLOW PREVENTER ASSEMBLY INSULATING BLANKET**

New and existing backflow preventers shall be provided with an insulating blanket sufficient to protect backflow preventer from damage due to freezing. Full compensation for backflow preventer assembly insulating blanket shall be considered as included in the contract unit price paid for backflow preventer assembly and no separate payment will be made therefor.

#### **BACKFLOW PREVENTER ASSEMBLY ENCLOSURE**

Enclosures shall be fabricated of structural steel angles and flattened expanded metal and shall be installed over backflow preventer assemblies on a portland cement concrete pad in conformance with the details shown on the plans. There shall be 50 mm minimum clearance between the backflow preventer assembly and the backflow preventer assembly enclosure. The concrete pad shall extend a minimum of 75 mm beyond the outer limits of the backflow preventer assembly enclosure, unless otherwise shown on the plans or as specified in these special provisions.

Expanded metal for sides, ends and top panels shall be fabricated from 1.9 mm (14-gage), minimum thickness, sheet steel. The flattened expanded metal openings shall be approximately 20 mm by 45 mm in size.

Expanded metal panels shall be attached to the steel frames by a series of welds, not less than 6.4 mm in length and spaced not more than 100 mm on centers, along the edges of the enclosures.

Enclosure door handles shall have provisions for padlocking in the latched position. Padlocks will be State-furnished as provided under "State-furnished Materials" of these special provisions.

Enclosures shall be galvanized, after fabrication, in conformance with the provisions in Section 75-1.05, "Galvanizing," of the Standard Specifications.

Portland cement concrete for the concrete pad shall be minor concrete conforming to the provisions in Section 90-10, "Minor Concrete," of the Standard Specifications.

Hold down bolt assemblies shall be galvanized and shall be installed when the portland cement concrete pad is still plastic. Nuts shall be hexagonal and washers shall be the lock type.

Enclosures shall be painted with one application of a commercial quality pre-treatment, vinyl wash primer and a minimum of one application of a commercial quality, exterior enamel for metal. The finish color shall be light brown.

Insulating blankets shall be installed over the backflow preventer assemblies and shall conform to the provisions in "Backflow Preventer Assembly Insulating Blanket," elsewhere in these special provisions.

The quantity of backflow preventer assembly enclosures will be measured by the unit as determined from actual count in place.

The contract unit price paid for the backflow preventer assembly enclosure shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in furnishing and installing a backflow preventer assembly enclosure, complete in place, including constructing the portland cement concrete pad, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

#### **SPRINKLERS**

Sprinklers shall conform to the type, pattern, material, and operating characteristics listed in the "Sprinkler Schedule" shown on the plans.

Risers shall be ultraviolet (UV) resistant, brown in color and shall conform to the details shown on the plans.

When required, risers for sprinklers shall contain a device that will automatically and instantly stop the flow of water from a riser when the riser is broken on the downstream side of the device. The device shall be installed as recommended by the manufacturer of the device.

#### **FILTER ASSEMBLY UNIT**

A filter assembly unit shall consist of a filter housing, a reusable filter cartridge, fittings, pipe, and valve box as shown on the plans.

Filter assembly units shall withstand a cold water working pressure of 1034 kPa.

Pressure loss through the filter assembly units shall not exceed the following:

FILTER ELEMENT SIZE (Millimeters)	MAX FLOW RATE (Liters Per Minute)	PRESSURE LOSS AT MAX FLOW (kPa)
40	227	21

Filter housings shall be manufactured of reinforced polypropylene plastic.

Filter cartridges shall be reusable stainless steel and shall be capable of 130 µm size mesh filtration.

### **BALL VALVE**

Ball Valves shall be polyvinyl chloride (PVC). The ball seats shall be high molecular weight high density polyethylene.

Ball valves shall be installed in a valve box as shown on the plans.

The quantity of ball valves will be measured by the unit as determined from actual count in place.

The contract unit price paid for ball valve shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in ball valves, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **COMBINATION AIR AND VACUUM RELIEF VALVE**

Combination air and vacuum relief valves shall have cast iron bodies with stainless steel float, stainless steel needle and linkage, outlets air and vacuum relief valves shall be placed on the mainlines at high points, as shown on the plans and as directed by the Engineer.

The quantity of combination air and vacuum relief valves will be measured by the unit as determined from actual count in place.

The contract unit price paid for combination air and vacuum relief valve shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in combination air and vacuum relief valve, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

## **10-2.06 CHECK VALVES**

### **SPRING CHECK VALVES**

Spring check valves shall be PVC with a solid 18-8 stainless steel spring and valve stem. Spring check valves shall be adjustable from 34 kPa to 96 kPa.

Spring Check valves will be measured and paid for as check valve.

### **SWING CHECK VALVE**

Swing check valves shall be PVC with a pressure rating of 862 kPa. Swing check valves shall retain back pressure at 862 kPa.

Swing Check valves will be measured and paid for as check valve.

### **FINAL IRRIGATION SYSTEM CHECK**

A final check of existing and new irrigation facilities shall be performed not more than 20 working days prior to acceptance of the contract.

The length of watering cycles using potable water measured by water meters for the final check of irrigation facilities will be determined by the Engineer.

Remote control valves connected to existing and new irrigation controllers shall be checked for automatic performance when the controllers are in automatic mode.

Unsatisfactory performance of irrigation facilities installed or modified by the Contractor shall be repaired and rechecked at the Contractor's expense until satisfactory performance is obtained, as determined by the Engineer.

Repair or replacement of existing irrigation facilities due to unsatisfactory performance shall conform to the provisions in "Existing Highway Irrigation Facilities" of these special provisions.

Nothing in this section "Final Irrigation System Check" shall relieve the Contractor of full responsibility for making good or repairing defective work or materials found before the formal written acceptance of the entire contract by the Director.

Full compensation for checking the irrigation systems prior to the acceptance of the contract shall be considered as included in the contract lump sum price paid for plant establishment work and no additional compensation will be allowed therefor.

## **10-2.07 BOOSTER PUMP**

Booster pump systems shall be installed in conformance with the details shown on the plans and these special provisions.

A booster pump system shall consist of a pump, motor, pump enclosure, foundation, pipe, fittings, and appurtenances necessary for the satisfactory operation of the booster pump. Service equipment and booster pump electrical equipment shall conform to the provisions in Section 10-3 of these special provisions. Incidental material or equipment not mentioned in these special provisions or shown on the plans, which may be necessary for completion and satisfactory operation of the booster pump system, shall be furnished and installed.

### **MATERIALS LIST AND DRAWINGS**

In conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, the Contractor shall submit, within 15 days after approval of the contract, a list of materials which the Contractor proposes to install for the booster pump systems together with the drawings and other data as specified below:

- A. The materials list shall be a complete listing of the manufacturer, catalog number, size, and capacity of the manufactured articles. There shall be a working drawing for each pump system showing the pump details, piping, and equipment as planned to be installed and for other materials to be fabricated for the installation. Directions for maintenance and adjustment of the pump shall be furnished to the Engineer as well as a manufacturer's performance characteristics curve diagram for the pump covering the range conforming to the provisions in "Pump Performance Requirements" of these special provisions.
- B. The data submitted shall be labeled with a descriptive title, project description and contract number of the project.

At least 4 copies of the data shall be initially submitted to the Engineer for approval. The Engineer will review the submitted data and will return to the Contractor either one set for correction or 2 sets that have been approved.

The State shall not be liable for materials purchased or labor performed, prior to approval of the drawings and materials list, and will not be responsible for any delay to the Contractor pending review of the drawings and information submitted after the 15-day period mentioned.

### **PUMP PERFORMANCE REQUIREMENTS**

The pumps shall deliver at least the pumping rates in liters per minute at the total head indicated on the plans and shall not load the motors to more than the name plate full load current at the highest flow rate listed for each pump.

### **PUMP AND MOTOR**

The pump shall be a single or multiple stage, horizontal, close coupled, end suction centrifugal pump with mechanical seal. The pump casing shall be close grained cast iron with a bronze wearing ring. The impeller shall statically and dynamically balanced, keyed to the shaft, and held in place by a stainless steel washer and cap screw.

The motor shaft for the close coupled pump shall be steel with a bronze or stainless steel sleeve or be stainless steel with no sleeve.

The pump and motor shall be mounted on the concrete pedestal so that the piping and pump casing are not stressed and as recommended by the manufacturer. The method of mounting shall be submitted to the Engineer and be approved prior to mounting.

The motor shall be totally enclosed fan cooled.

### **PIPE, JOINTS AND FITTINGS**

Pipe, joints and fittings shall conform to the provisions in Section 74-2.04, "Pipe, Joints and Fittings," of the Standard Specifications, except that the amount of the zinc coating for galvanized steel pipe shall be a minimum of 90 percent of that specified in the requirements in ASTM Designation: A 120, standard weight. All pipe threads shall be coated with a zinc-rich primer after fabrication.

Valves shall be the type shown on the plans and shall be Class 125 unless otherwise shown on the plans.

Ball valve shall be two piece, minimum 2760 kPa WOG, bronze body and chrome plated or brass ball with full size port. Valve shall be Nibco Scott, T-580; Watts, B-6000; Kitz, 56; or equal.

### **FOUNDATIONS**

Concrete for foundations and pads shall be minor concrete and shall contain not less than 325 kg of portland cement per cubic meter.

## **PRESSURE GAGES**

Pressure gages shall be the dial type, shall be clear glycerin filled with a 65-mm minimum diameter weathertight epoxy case, and shall have an accuracy within 1 percent of the full scale reading. The pressure gages shall have both metric and English scales and have ranges of 0 kPa to 410 kPa and 0 kPa to 690 kPa on the intake and discharge sides of the pump, respectively.

## **PUMP ENCLOSURE**

The pump enclosure shall be fabricated from 12 gauge cold rolled steel. The enclosure shall be cleaned and painted with a two part epoxy paint and baked until thoroughly dried. The enclosure shall have two latches which will lock the lid both open and shut. Above ground accessories to the pumps, including valves and galvanized pipe, shall be painted with one application of commercial quality pre-treatment, vinyl wash primer and a minimum of one application of commercial quality fast drying exterior enamel. The finish color shall be light brown closely matching Federal Standard No. 595B, Color No. 20450.

The Contractor shall provide the primers and paints.

## **PUMP CONTROL**

The pump shall operate on a manual and an automatic mode of operation as follows:

- A. The manual mode of operation shall start the pump motor by bypassing the irrigation controller pump start circuit.
- B. The automatic mode of operation shall start the pump motor when an irrigation controller is in operation.
- C. Both modes of operation shall keep the pump motor running should the flow of water fluctuate between the changing of stations.

## **PAYMENT**

Quantities of booster pumps will be measured by the unit as determined from actual count in place.

The contract unit price paid for booster pump system shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing booster pump systems, complete in place, including foundations, pump enclosures, and excavation and backfill, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

## **SECTION 10-3. ELECTRICAL SYSTEMS**

### **10-3.01 DESCRIPTION**

Irrigation controller enclosure, electric service (irrigation) and booster pump electrical system shall conform to the provisions in Section 86, "Signals, Lighting and Electrical Systems," of the Standard Specifications and these special provisions.

### **10-3.02 COST BREAK-DOWN**

Cost break-downs shall conform to the provisions in Section 86-1.03, "Cost Break-Down," of the Standard Specifications and these special provisions.

The Engineer shall be furnished a cost break-down for each contract lump sum item of work described in this Section 10-3.

The cost break-down shall be submitted to the Engineer for approval within 15 days after the contract has been approved. The cost break-down shall be approved, in writing, by the Engineer before any partial payment for the items of electrical work will be made.

The cost breakdown shall include the following items in addition to those listed in the Standard Specifications:

- A. Booster Pump Control Panel Enclosure

### **10-3.03 CONDUIT**

Conduit to be installed underground shall be Type 3 unless otherwise specified. The conduit in a foundation and between a foundation and the nearest pull box shall be Type 1.

Conduit sizes shown on the plans and specified in the Standard Specifications and these special provisions are referenced to metallic type conduit. When rigid non-metallic conduit is required or allowed, the nominal equivalent industry size shall be used as shown in the following table:

Size Designation for Metallic Type Conduit	Equivalent Size for Rigid Non-metallic Conduit
21	20
27	25
41	40
53	50
63	65
78	75
103	100

After conductors have been installed, the ends of conduits terminating in pull boxes, service equipment enclosures, booster pump control panel enclosure and controller cabinets shall be sealed with an approved type of sealing compound.

**10-3.04 CONDUCTORS AND WIRING**

Splices shall be insulated by "Method B" or, at the Contractor's option, splices of conductors shall be insulated with heat-shrink tubing of the appropriate size after thoroughly painting the spliced conductors with electrical insulating coating.

The minimum insulation thickness, at any point, for Type USE, RHH or RHW wire shall be 1.0 mm for conductor sizes No. 14 to No. 10, inclusive, and 1.3 mm for No. 8 to No. 2, inclusive. The minimum insulation thickness, at any point, for Type THW and TW wires shall be 0.69 mm for conductor sizes No. 14 to No. 10, inclusive, 1.02 mm for No. 8, and 1.37 mm for No. 6 to No. 2, inclusive.

All conductors shall be type THW except irrigation control, control wiring in booster pump control panel enclosure and directly buried low voltage conductors.

**10-3.05 SERVICE**

Type III service equipment enclosures shall be the aluminum type.

**ELECTRIC SERVICE (IRRIGATION)**

Electric service (irrigation) shall be from the service points to the booster pump control panel enclosure and to the irrigation controller enclosure cabinets as shown on the plans.

Electric service (irrigation) and service disconnects in service equipment enclosures shall be as shown on the plans.

The inscription on all nameplates shall be the identifying letter designation used on the plans and in these special provisions, or shall be as directed by the Engineer.

Electric service (irrigation) will be paid for on a lump sum basis.

The contract lump sum price paid for electric service (irrigation) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing electric service (irrigation) for booster control panel enclosures, complete in place, including conductors, conduit and pull boxes to irrigation controllers and conduits and conductors to the booster pump control panel enclosure, as shown on the plans, as specified in these special provisions, and as directed by the Engineer.

**10-3.06 IRRIGATION CONTROLLER ENCLOSURE CABINET**

Irrigation controller enclosure cabinets (CEC) shall be constructed and the equipment within the cabinets shall be installed in conformance with the details shown on the plans, the provisions in the Standard Specifications, and these special provisions.

Irrigation controller enclosure cabinets shall be of metal construction conforming to the details for empty Type P signal cabinets shown on Standard Plans ES-3A and ES-3C, except that the fluorescent interior light, police panels, and shelves shall not be provided, unless otherwise shown on the plans. Cabinets shall be provided with cross ventilation, roof ventilation or a combination of both. The anchorage arrangement shall be inside the cabinet as shown on the plans. Dimensions of the cabinet shall be suitable for the equipment to be installed as shown on the plans and specified in these special provisions.

Irrigation controller enclosure cabinets shall be fabricated in conformance with the provisions in Section 86-3.04A, "Cabinet Construction," of the Standard Specifications.

Irrigation controller enclosure cabinets shall be fabricated of cold rolled steel.

Irrigation controller enclosure cabinets fabricated of cold rolled steel shall be cleaned and painted in conformance with the provisions in Section 86-3.04A, "Cabinet Construction," of the Standard Specifications, except the finish color of the irrigation controller enclosure cabinets shall be light brown conforming to Federal Standard 595B, Color No. 20450.

Door locks for the irrigation controller enclosure cabinets shall be a removable-core mortise cam cylinder door lock that receives the State's lock core. The State's lock core is a "Best" construction core. Keys shall be removable from the locks in

the locked position only. Door locks shall be installed in conformance with the manufacturer's written instructions and recommendations. Two keys for each door lock shall be delivered to the Engineer.

The plywood mounting panel shall be 19-mm exterior AC grade veneer plywood. The panel shall be painted with one application of an exterior, latex based, wood primer and 2 applications of an exterior, vinyl acrylic enamel, white in color. The plywood panel shall be painted on all sides and edges prior to installation of the panel in the cabinet and equipment on the panel.

Inside of the doors shall have provisions for storage of the irrigation plans.

Duplex convenience receptacles shall have ground-fault circuit interruption as defined by the Code. Circuit interruption shall occur on 6 mA of ground-fault current and shall not occur on less than 4 mA. Receptacles shall be installed in a weatherproof housing with rainproof lift covers.

Equipment, except for field wiring, shall be installed in the cabinet in a shop by the equipment manufacturer's representative or distributor prior to field installation.

Irrigation controller enclosure cabinets will be measured by the unit as determined from actual count in place.

The contract unit price paid for irrigation controller enclosure cabinet shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in fabricating and installing irrigation controller enclosure cabinets, complete in place, including constructing foundations, pads and conduits to pull box adjacent to cabinets, and installing equipment within the cabinets, except controllers, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **10-3.07 BOOSTER PUMP ELECTRICAL SYSTEM**

Booster pump electrical system includes pump control equipment as shown on the plans and as specified herein. The Contractor's attention is directed to "Booster Pumps" of these special provisions, regarding the equipment to be operated and served by the booster pump electrical system.

#### **MATERIALS LIST AND DRAWINGS**

A list of materials which the Contractor proposes to install for the booster pump electrical systems together with the drawings and other data shall be submitted to the Engineer in conformance with the provisions in Section 86-1.04, "Equipment List and Drawings," of the Standard Specifications.

The working drawings shall include a wiring diagram for the booster pump system showing service and pump control details.

Before the completion of the contract, one set of the approved wiring diagram for each booster pump system shall be covered separately on each side with clear, self-adhesive plastic and placed in a heavy-duty plastic envelope. The envelope shall be attached securely to the inside of the electrical equipment enclosure exterior door or at a convenient location designated by the Engineer.

The Contractor shall be responsible for the compatibility and adjustment of components as necessary for the successful operation of the completed installation.

#### **CONDUIT**

Type 3 conduit shall not be used.

After conductors have been installed, the ends of conduits terminating in pull boxes and booster pump control panel enclosures shall be sealed with a sealing compound.

Short loops of Type 4 conduit may be used for connecting the pump motor to the junction box. Type 4 conduit shall be no longer than is necessary for the purpose of looping from the junction box to the motor connection box.

#### **PULL BOXES**

Covers of pull boxes installed shall be inscribed "ELECTRICAL BOOSTER PUMP."

#### **CONDUCTORS AND WIRING**

Control wiring in the booster pump control panel enclosure shall be 7-strand No. 14 with Type TW insulation, except for hinge wiring which shall be 19-strand No. 14 with THHN insulation.

Splices shall be avoided wherever possible and those required shall occur only in fixtures, junction boxes, or pull boxes. Splices shall operate satisfactorily when continuously submerged under 0.6-m of water.

Conductor terminations and splices shall be marked with adhesive backed paper markers or cloth wrap-around markers. Clear heat-shrinkable sleeves shall be applied over the markers.

Non-spliced conductors in junction and pull boxes shall be marked with clip-on, "C" shaped, white extruded polyvinyl chloride sleeves. Marker sleeves shall have a black indented legend of uniform depth with a transparent overlay over the legend and a "chevron" cut for alignment of 2 or more sleeves.

Each conductor shall be marked with the same identification number at each termination, each junction box, and each pull box.

**BOOSTER PUMP CONTROL PANEL ENCLOSURE**

Booster pump control panel enclosure shall be of welded construction and shall be fabricated from 2.66 mm (12-gage) cold rolled sheet steel. The enclosure shall conform to the details shown on the plans for Type III-A service equipment enclosure except that the metering section and the associated metering equipment shall not be furnished.

Circuit breakers, overload reset button and switches shall be externally operable after the exterior door is opened.

The enclosure shall be factory pre-wired in conformance with NEMA Class IIC wiring. Wires entering or leaving the enclosure shall terminate on terminal blocks.

The wiring shall be arranged so that any piece of equipment may be removed without disconnecting any wiring except the leads to that piece of equipment.

The booster pump control panel enclosure shall be finished in conformance with the provisions for painting Type III steel service equipment enclosures in Section 86-2.16, "Painting," of the Standard Specifications, except the finish color shall be a light brown color closely matching Federal Standard No. 595B, Color No. 20450.

Equipment shall be furnished and installed in the booster pump control panel enclosure as shown on the plans and specified in these special provisions.

**Main Disconnect (MD)**

Main Disconnect (MD) shall be a molded case circuit breaker with adjustable magnetic trip. The Main Disconnect shall have the following voltage rating, trip rating, number of poles and interrupting capacity:

Location	Voltage [V(ac)]	Trip (A)	Number Of poles	Interrupting Capacity (A, Symmetrical)
EP1	240	70	3	10,000
EP2, EP3, EP4, EP5, EP6 and EP7	240	50	3	10,000
EP8	480	40	3	10,000
NP-1 and NP-2	240	60	2	10,000

**Pump Disconnect (PD)**

Each Pump Disconnect , shall be a molded case circuit breaker with the following voltage rating, trip rating, number of poles and interrupting capacity:

Location	Voltage [V(ac)]	Trip (A)	Number of poles	Interrupting Capacity (A, Symmetrical)
EP1	240	60	3	10,000
EP2, EP3, EP4, EP5, EP6 and EP7	240	40	3	10,000
EP-8	480	20	3	10,000
NP-1 and NP-2	240	50	2	10,000

**Circuit Breaker (CD, PCD, PCD1, PCD2, TSD, RD, ICD1, ICD2 and SD)**

Circuit breakers shall be molded case circuit breakers 120 V(ac) with ampere rating and number of poles as shown on the plans. Interrupting capacity shall be 10,000 A (symmetrical) at 240 V(ac).

**Motor Starter (ST)**

Booster pump motor starters shall be line voltage starters with 120 V(ac) coils, double break silver contacts, and bimetallic, manual reset thermal overloads set to trip between 115 and 125 percent of full load motor current as shown on the nameplate. Each starter shall conform to the following:

Location	NEMA Size	Voltage [V(ac)]	Contactor Auxiliary Contacts	No. of Poles	No. of Overloads
EP8	0	480	1 N.O. & 1 N.C.	3	3
EP1, EP2, EP3, EP4, EP5, EP6 and EP7	1	240	1 N.O. & 1 N.C.	3	3
NP-1 and NP-2	1	240	1 N.O. & 1 N.C.	2	2

#### **Motor Saver (MS)**

The motor saver shall be an electric motor protector complete with integral current transformers to suit the motor sizes and voltages as shown on the plans. The motor saver shall measure power consumed by the booster pump and shall shut off the pump whenever the measured power differs from the normal running value to protect the pump from running dry or overloading. The motor saver shall protect the pump from current unbalance, phase loss, reverse phasing and rapid cycling. The motor saver shall have one single pole double throw auxiliary contact rated at not less than 480 VA at 240 V(ac).

#### **Selector Switch (SS)**

The selector switch shall be a rotary action, single pole, 3-position, 10 A, 120 V(ac) switch. Switch contacts shall have an inductive pilot duty rating of 60 A (make), 6 A (break), and 10 A (continuous) at 120 V(ac) and 35 percent power factor.

#### **Duplex Receptacle Outlet (DP)**

Duplex receptacle outlet shall be the 3-wire, 20 A, 120 V(ac) grounded type and ground fault protection. Circuit interruption shall occur on 6 mA of ground-fault current and shall not occur on less than 4 mA of ground-fault current.

#### **Transformer Primary Disconnect (TPD)**

The transformer primary disconnect shall be a 2-pole, 480 V(ac), 15-A trip, molded case circuit breaker. Breaker shall have an interrupting capacity of not less than 18 000 A (symmetrical) at 480 V(ac).

#### **Transformer (T)**

The transformer shall be a double-wound, 3-kVA, 60 Hz, dry type transformer with a 480 V(ac) primary and 120 V(ac) secondary.

#### **Control Relay (CR1, CR2)**

The control relay shall be 120 V(ac), 10 A, 2-pole, double-throw, 24 V(ac) coil, general purpose type with an enclosed clear plastic cover and 8-pin plug base. The socket for the relay shall be the barrier type, 8-contact relay socket with 10 A contacts and screw terminals.

#### **Terminal Blocks (TB)**

Terminal blocks shall be rated 600 volt, 30 A and shall be molded plastic with 2 or more mounting holes and 2 or more terminals in each cast block. The molded plastic shall have high resistance to heat, electrical potential, moisture, and mechanical shock and shall have a smooth even finish. Each block shall have a molded marking strip attached with screws. The identifying numbers of the terminating wires as shown on the Contractor's working drawings shall be engraved in the marking strip. Terminal blocks shall have tubular, high pressure clamp connectors.

#### **Time Meter (TM)**

Time meters shall be 240 V(ac), 60 Hz for all locations, except at location EP8, panel mounted, elapsed-time meters with a range of 0 to 99 999.9 hours. Time meters shall be completely enclosed for dust protection and shall have the terminals on the back of the enclosure.

Time meter for location EP8 shall be similar except it shall be 480 V(ac).

#### **Alarm Light (AL)**

Alarm light shall be incandescent, 60 W, 120 V(ac), weatherproof light fixture for use with cast metal box. Light fixture shall have guard and red globe.

**Identification Of Units**

Units shall be identified in conformance with the provisions in Section 74-3.09, "Identification of Units and Conductors," of the Standard Specifications and these special provisions. Inscriptions on nameplates for devices and switches shall be as shown on the plans.

**PAYMENT**

Booster pump electrical system will be paid for on a lump sum basis.

The contract lump sum price paid for booster pump electrical system shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing a booster pump electrical system, complete in place, including foundations, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

**SECTION 11. (BLANK)**

**SECTION 12. (BLANK)**

06-404104  
01-09-01

**SECTION 13. RELATIONS WITH RAILROAD**

**13-1.01 GENERAL**--The Contractor's attention is directed to the tracks and right of way of the Union Pacific Railroad Company, hereinafter referred to as "Railroad," on State Route 99 from California Ave Overcrossing to North Fresno Undercrossing in Fresno County, within the limits of the project.

In accordance with the provisions in Section 7-1.12, "Responsibility for Damage," of the Standard Specifications, the Contractor shall be responsible for all damages to Railroad tracks and appurtenances thereto and to Railroad equipment operating on such track, resulting from his operations.

The Contractor shall not allow any personnel or equipment on Railroad right of way.

The Contractor shall conduct his operation in a manner that shall have no impact on the tracks and right of way of the Railroad.

**SECTION 14 FEDERAL REQUIREMENTS FOR FEDERAL-AID CONSTRUCTION PROJECTS**

**GENERAL.**—The work herein proposed will be financed in whole or in part with Federal funds, and therefore all of the statutes, rules and regulations promulgated by the Federal Government and applicable to work financed in whole or in part with Federal funds will apply to such work. The "Required Contract Provisions, Federal-Aid Construction Contracts, "Form FHWA 1273, are included in this Section 14. Whenever in said required contract provisions references are made to "SHA contracting officer", "SHA resident engineer", or "authorized representative of the SHA", such references shall be construed to mean "Engineer" as defined in Section 1-1.18 of the Standard Specifications.

**PERFORMANCE OF PREVIOUS CONTRACT.**—In addition to the provisions in Section II, "Nondiscrimination," and Section VII, "Subletting or Assigning the Contract," of the required contract provisions, the Contractor shall comply with the following:

The bidder shall execute the CERTIFICATION WITH REGARD TO THE PERFORMANCE OF PREVIOUS CONTRACTS OR SUBCONTRACTS SUBJECT TO THE EQUAL OPPORTUNITY CLAUSE AND THE FILING OF REQUIRED REPORTS located in the proposal. No request for subletting or assigning any portion of the contract in excess of \$10,000 will be considered under the provisions of Section VII of the required contract provisions unless such request is accompanied by the CERTIFICATION referred to above, executed by the proposed subcontractor.

**NON-COLLUSION PROVISION.**—The provisions in this section are applicable to all contracts except contracts for Federal Aid Secondary projects.

Title 23, United States Code, Section 112, requires as a condition precedent to approval by the Federal Highway Administrator of the contract for this work that each bidder file a sworn statement executed by, or on behalf of, the person, firm, association, or corporation to whom such contract is to be awarded, certifying that such person, firm, association, or corporation has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with the submitted bid. A form to make the non-collusion affidavit statement required by Section 112 as a certification under penalty of perjury rather than as a sworn statement as permitted by 28, USC, Sec. 1746, is included in the proposal.

**PARTICIPATION BY MINORITY BUSINESS ENTERPRISES IN SUBCONTRACTING.**—Part 23, Title 49, Code of Federal Regulations applies to this Federal-aid project. Pertinent sections of said Code are incorporated in part or in its entirety within other sections of these special provisions.

Schedule B—Information for Determining Joint Venture Eligibility

(This form need not be filled in if all joint venture firms are minority owned.)

1. Name of joint venture \_\_\_\_\_
2. Address of joint venture \_\_\_\_\_
3. Phone number of joint venture \_\_\_\_\_
4. Identify the firms which comprise the joint venture. (The MBE partner must complete Schedule A.) \_\_\_\_\_  
\_\_\_\_\_  
  - a. Describe the role of the MBE firm in the joint venture. \_\_\_\_\_
  - b. Describe very briefly the experience and business qualifications of each non-MBE joint venturer: \_\_\_\_\_  
\_\_\_\_\_
5. Nature of the joint venture's business \_\_\_\_\_  
\_\_\_\_\_
6. Provide a copy of the joint venture agreement.
7. What is the claimed percentage of MBE ownership? \_\_\_\_\_
8. Ownership of joint venture: (This need not be filled in if described in the joint venture agreement, provided by question 6.).
  - a. Profit and loss sharing.
  - b. Capital contributions, including equipment.
  - c. Other applicable ownership interests.

9. Control of and participation in this contract. Identify by name, race, sex, and "firm" those individuals (and their titles) who are responsible for day-to-day management and policy decision making, including, but not limited to, those with prime responsibility for:

a. Financial decisions \_\_\_\_\_

b. Management decisions, such as:

(1) Estimating \_\_\_\_\_

(2) Marketing and sales \_\_\_\_\_

(3) Hiring and firing of management personnel \_\_\_\_\_

(4) Purchasing of major items or supplies \_\_\_\_\_

c. Supervision of field operations \_\_\_\_\_

Note.—If, after filing this Schedule B and before the completion of the joint venture's work on the contract covered by this regulation, there is any significant change in the information submitted, the joint venture must inform the grantee, either directly or through the prime contractor if the joint venture is a subcontractor.

**Affidavit**

"The undersigned swear that the foregoing statements are correct and include all material information necessary to identify and explain the terms and operation of our joint venture and the intended participation by each joint venturer in the undertaking. Further, the undersigned covenant and agree to provide to grantee current, complete and accurate information regarding actual joint venture work and the payment therefor and any proposed changes in any of the joint venture arrangements and to permit the audit and examination of the books, records and files of the joint venture, or those of each joint venturer relevant to the joint venture, by authorized representatives of the grantee or the Federal funding agency. Any material misrepresentation will be grounds for terminating any contract which may be awarded and for initiating action under Federal or State laws concerning false statements."

_____ Name of Firm	_____ Name of Firm
_____ Signature	_____ Signature
_____ Name	_____ Name
_____ Title	_____ Title
_____ Date	_____ Date

Date \_\_\_\_\_

State of \_\_\_\_\_

County of \_\_\_\_\_

On this \_\_\_\_ day of \_\_\_\_\_, 19 \_\_, before me appeared (Name) \_\_\_\_\_, to me personally known, who, being duly sworn, did execute the foregoing affidavit, and did state that he or she was properly authorized by (Name of firm) \_\_\_\_\_ to execute the affidavit and did so as his or her free act and deed.

Notary Public \_\_\_\_\_

Commission expires \_\_\_\_\_

[Seal]

Date \_\_\_\_\_

State of \_\_\_\_\_

County of \_\_\_\_\_

On this \_\_\_\_ day of \_\_\_\_\_, 19 \_\_, before me appeared (Name) \_\_\_\_\_ to me personally known, who, being duly sworn, did execute the foregoing affidavit, and did state that he or she was properly authorized by (Name of firm) \_\_\_\_\_ to execute the affidavit and did so as his or her free act and deed.

Notary Public \_\_\_\_\_

Commission expires \_\_\_\_\_

[Seal]

**REQUIRED CONTRACT PROVISIONS  
FEDERAL-AID CONSTRUCTION CONTRACTS**

**I. GENERAL**

1. These contract provisions shall apply to all work performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.
2. Except as otherwise provided for in each section, the contractor shall insert in each subcontract all of the stipulations contained in these Required Contract Provisions, and further require their inclusion in any lower tier subcontract or purchase order that may in turn be made. The Required Contract Provisions shall not be incorporated by reference in any case. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with these Required Contract Provisions.
3. A breach of any of the stipulations contained in these Required Contract Provisions shall be sufficient grounds for termination of the contract.
4. A breach of the following clauses of the Required Contract Provisions may also be grounds for debarment as provided in 29 CFR 5.12:

Section I, paragraph 2;  
Section IV, paragraphs 1, 2, 3, 4, and 7;  
Section V, paragraphs 1 and 2a through 2g.

5. Disputes arising out of the labor standards provisions of Section IV (except paragraph 5) and Section V of these Required Contract Provisions shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the U.S. Department of Labor (DOL) as set forth in 29 CFR 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the DOL, or the contractor's employees or their representatives.
6. **Selection of Labor:** During the performance of this contract, the contractor shall not:
  - a. discriminate against labor from any other State, possession, or territory of the United States (except for employment preference for Appalachian contracts, when applicable, as specified in Attachment A), or
  - b. employ convict labor for any purpose within the limits of the project unless it is labor performed by convicts who are on parole, supervised release, or probation.

**II. NONDISCRIMINATION**

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$10,000 or more.)

1. **Equal Employment Opportunity:** Equal employment opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (28 CFR 35, 29 CFR 1630, and 41 CFR 60) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140 shall constitute the EEO and specific affirmative action standards for the contractor's project activities under this contract. The Equal Opportunity Construction Contract Specifications set forth under 41 CFR 60-4.3 and the provisions of the American Disabilities Act of 1990 (42 U.S.C. 12101 et seq.) set forth under 28 CFR 35 and 29 CFR 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:
  - a. The contractor will work with the State highway agency (SHA) and the Federal Government in carrying out EEO obligations and in their review of his/her activities under the contract.
  - b. The contractor will accept as his operating policy the following statement:

"It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age or disability. Such action shall

include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, preapprenticeship, and/or on-the-job training."

2. **EEO Officer:** The contractor will designate and make known to the SHA contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active contractor program of EEO and who must be assigned adequate authority and responsibility to do so.
3. **Dissemination of Policy:** All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:
  - a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.
  - b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.
  - c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minority group employees.
  - d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.
  - e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.
4. **Recruitment:** When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minority groups in the area from which the project work force would normally be derived.
  - a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minority group applicants. To meet this requirement, the contractor will identify sources of potential minority group employees, and establish with such identified sources procedures whereby minority group applicants may be referred to the contractor for employment consideration.
  - b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, he is expected to observe the provisions of that agreement to the extent that the system permits the contractor's compliance with EEO contract provisions. (The DOL has held that where implementation of such agreements have the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Executive Order 11246, as amended.)
  - c. The contractor will encourage his present employees to refer minority group applicants for employment. Information and procedures with regard to referring minority group applicants will be discussed with employees.
5. **Personnel Actions:** Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, national origin, age or disability. The following procedures shall be followed:
  - a. The contractor will conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.

- b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.
  - c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.
  - d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with his obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of his avenues of appeal.
6. Training and Promotion:
- a. The contractor will assist in locating, qualifying, and increasing the skills of minority group and women employees, and applicants for employment.
  - b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance. Where feasible, 25 percent of apprentices or trainees in each occupation shall be in their first year of apprenticeship or training. In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision.
  - c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.
  - d. The contractor will periodically review the training and promotion potential of minority group and women employees and will encourage eligible employees to apply for such training and promotion.
7. **Unions:** If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use his/her best efforts to obtain the cooperation of such unions to increase opportunities for minority groups and women within the unions, and to effect referrals by such unions of minority and female employees. Actions by the contractor either directly or through a contractor's association acting as agent will include the procedures set forth below:
- a. The contractor will use best efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minority group members and women for membership in the unions and increasing the skills of minority group employees and women so that they may qualify for higher paying employment.
  - b. The contractor will use best efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age or disability.
  - c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the SHA and shall set forth what efforts have been made to obtain such information.
  - d. In the event the union is unable to provide the contractor with a reasonable flow of minority and women referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age or disability; making full efforts to obtain qualified and/or qualifiable minority group persons and women. (The DOL has held that it shall be no excuse that the union with which the contractor has a collective bargaining agreement providing for exclusive referral failed to refer minority employees.) In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these special provisions, such contractor shall immediately notify the SHA.

- 8. Selection of Subcontractors, Procurement of Materials and Leasing of Equipment:** The contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment.
- a. The contractor shall notify all potential subcontractors and suppliers of his/her EEO obligations under this contract.
  - b. Disadvantaged business enterprises (DBE), as defined in 49 CFR 23, shall have equal opportunity to compete for and perform subcontracts which the contractor enters into pursuant to this contract. The contractor will use his best efforts to solicit bids from and to utilize DBE subcontractors or subcontractors with meaningful minority group and female representation among their employees. Contractors shall obtain lists of DBE construction firms from SHA personnel.
  - c. The contractor will use his best efforts to ensure subcontractor compliance with their EEO obligations.
- 9. Records and Reports:** The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following completion of the contract work and shall be available at reasonable times and places for inspection by authorized representatives of the SHA and the FHWA.
- a. The records kept by the contractor shall document the following:
    - (1) The number of minority and non-minority group members and women employed in each work classification on the project;
    - (2) The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women;
    - (3) The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minority and female employees; and
    - (4) The progress and efforts being made in securing the services of DBE subcontractors or subcontractors with meaningful minority and female representation among their employees.
  - b. The contractors will submit an annual report to the SHA each July for the duration of the project, indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on Form FHWA-1391. If on-the-job training is being required by special provision, the contractor will be required to collect and report training data.

### **III. NONSEGREGATED FACILITIES**

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$10,000 or more.)

- a. By submission of this bid, the execution of this contract or subcontract, or the consummation of this material supply agreement or purchase order, as appropriate, the bidder, Federal-aid construction contractor, subcontractor, material supplier, or vendor, as appropriate, certifies that the firm does not maintain or provide for its employees any segregated facilities at any of its establishments, and that the firm does not permit its employees to perform their services at any location, under its control, where segregated facilities are maintained. The firm agrees that a breach of this certification is a violation of the EEO provisions of this contract. The firm further certifies that no employee will be denied access to adequate facilities on the basis of sex or disability.
- b. As used in this certification, the term "segregated facilities" means any waiting rooms, work areas, restrooms and washrooms, restaurants and other eating areas, time clocks, locker rooms, and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are segregated by explicit directive, or are, in fact, segregated on the basis of race, color, religion, national origin, age or disability, because of habit, local custom, or otherwise. The only exception will be for the disabled when the demands for accessibility override (e.g. disabled parking).

- c. The contractor agrees that it has obtained or will obtain identical certification from proposed subcontractors or material suppliers prior to award of subcontracts or consummation of material supply agreements of \$10,000 or more and that it will retain such certifications in its files.

#### **IV. PAYMENT OF PREDETERMINED MINIMUM WAGE**

(Applicable to all Federal-aid construction contracts exceeding \$2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural minor collectors, which are exempt.)

##### **1. General:**

- a. All mechanics and laborers employed or working upon the site of the work will be paid unconditionally and not less often than once a week and without subsequent deduction or rebate on any account [except such payroll deductions as are permitted by regulations (29 CFR 3)] issued by the Secretary of Labor under the Copeland Act (40 U.S.C. 276c) the full amounts of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment. The payment shall be computed at wage rates not less than those contained in the wage determination of the Secretary of Labor (hereinafter "the wage determination") which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor or its subcontractors and such laborers and mechanics. The wage determination (including any additional classifications and wage rates conformed under paragraph 2 of this Section IV and the DOL poster (WH-1321) or Form FHWA-1495) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers. For the purpose of this Section, contributions made or costs reasonably anticipated for bona fide fringe benefits under Section 1(b)(2) of the Davis-Bacon Act (40 U.S.C. 276a) on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of Section IV, paragraph 3b, hereof. Also, for the purpose of this Section, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs, which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in paragraphs 4 and 5 of this Section IV.
- b. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein, provided, that the employer's payroll records accurately set forth the time spent in each classification in which work is performed.
- c. All rulings and interpretations of the Davis-Bacon Act and related acts contained in 29 CFR 1, 3, and 5 are herein incorporated by reference in this contract.

##### **2. Classification:**

- a. The SHA contracting officer shall require that any class of laborers or mechanics employed under the contract, which is not listed in the wage determination, shall be classified in conformance with the wage determination.
- b. The contracting officer shall approve an additional classification, wage rate and fringe benefits only when the following criteria have been met:
  - (1) the work to be performed by the additional classification requested is not performed by a classification in the wage determination;
  - (2) the additional classification is utilized in the area by the construction industry;
  - (3) the proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination; and
  - (4) with respect to helpers, when such a classification prevails in the area in which the work is performed.
- c. If the contractor or subcontractors, as appropriate, the laborers and mechanics (if known) to be employed in the additional classification or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the DOL, Administrator of the Wage and Hour Division, Employment Standards Administration, Washington, D.C. 20210. The Wage and Hour Administrator, or an authorized

representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.

- d. In the event the contractor or subcontractors, as appropriate, the laborers or mechanics to be employed in the additional classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Wage and Hour Administrator for determination. Said Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary
- e. The wage rate (including fringe benefits where appropriate) determined pursuant to paragraph 2c or 2d of this Section IV shall be paid to all workers performing work in the additional classification from the first day on which work is performed in the classification.

### **3. Payment of Fringe Benefits:**

- a. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor or subcontractors, as appropriate, shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly case equivalent thereof.
- b. If the contractor or subcontractor, as appropriate, does not make payments to a trustee or other third person, he/she may consider as a part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, provided, that the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

### **4. Apprentices and Trainees (Programs of the U.S. DOL) and Helpers:**

- a. Apprentices:
  - (1) Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the DOL, Employment and Training Administration, Bureau of Apprenticeship and Training, or with a State apprenticeship agency recognized by the Bureau, or if a person is employed in his/her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Bureau of Apprenticeship and Training or a State apprenticeship agency (where appropriate) to be eligible for probationary employment as an apprentice.
  - (2) The allowable ratio of apprentices to journeyman-level employees on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any employee listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate listed in the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor or subcontractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman-level hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.
  - (3) Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator for the Wage and Hour Division determines that a different

practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.

- (4) In the event the Bureau of Apprenticeship and Training, or a State apprenticeship agency recognized by the Bureau, withdraws approval of an apprenticeship program, the contractor or subcontractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the comparable work performed by regular employees until an acceptable program is approved.

b. Trainees:

- (1) Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the DOL, Employment and Training Administration.
- (2) The ratio of trainees to journeyman-level employees on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.
- (3) Every trainee must be paid at not less than the rate specified in the approved program for his/her level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman-level wage rate on the wage determination which provides for less than full fringe benefits for apprentices, in which case such trainees shall receive the same fringe benefits as apprentices.
- (4) In the event the Employment and Training Administration withdraws approval of a training program, the contractor or subcontractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

c. Helpers:

Helpers will be permitted to work on a project if the helper classification is specified and defined on the applicable wage determination or is approved pursuant to the conformance procedure set forth in Section IV.2. Any worker listed on a payroll at a helper wage rate, who is not a helper under an approved definition, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed.

**5. Apprentices and Trainees (Programs of the U.S. DOT):**

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.

**6. Withholding:**

The SHA shall upon its own action or upon written request of an authorized representative of the DOL withhold, or cause to be withheld, from the contractor or subcontractor under this contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to Davis-Bacon prevailing wage requirements which is held by the same prime contractor, as much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or

part of the wages required by the contract, the SHA contracting officer may, after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

**7. Overtime Requirements:**

No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers, mechanics, watchmen, or guards (including apprentices, trainees, and helpers described in paragraphs 4 and 5 above) shall require or permit any laborer, mechanic, watchman, or guard in any workweek in which he/she is employed on such work, to work in excess of 40 hours in such workweek unless such laborer, mechanic, watchman, or guard receives compensation at a rate not less than one-and-one-half times his/her basic rate of pay for all hours worked in excess of 40 hours in such workweek.

**8. Violation:**

**Liability for Unpaid Wages; Liquidated Damages:** In the event of any violation of the clause set forth in paragraph 7 above, the contractor and any subcontractor responsible thereof shall be liable to the affected employee for his/her unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory) for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer, mechanic, watchman, or guard employed in violation of the clause set forth in paragraph 7, in the sum of \$10 for each calendar day on which such employee was required or permitted to work in excess of the standard work week of 40 hours without payment of the overtime wages required by the clause set forth in paragraph 7.

**9. Withholding for Unpaid Wages and Liquidated Damages:**

The SHA shall upon its own action or upon written request of any authorized representative of the DOL withhold, or cause to be withheld, from any monies payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph 8 above.

## **V. STATEMENTS AND PAYROLLS**

(Applicable to all Federal-aid construction contracts exceeding \$2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural collectors, which are exempt.)

1. Compliance with Copeland Regulations (29 CFR 3):

The contractor shall comply with the Copeland Regulations of the Secretary of Labor which are herein incorporated by reference.

2. Payrolls and Payroll Records:

a. Payrolls and basic records relating thereto shall be maintained by the contractor and each subcontractor during the course of the work and preserved for a period of 3 years from the date of completion of the contract for all laborers, mechanics, apprentices, trainees, watchmen, helpers, and guards working at the site of the work.

b. The payroll records shall contain the name, social security number, and address of each such employee; his or her correct classification; hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalent thereof the types described in Section 1(b)(2)(B) of the Davis Bacon Act); daily and weekly number of hours worked; deductions made; and actual wages paid. In addition, for Appalachian contracts, the payroll records shall contain a notation indicating whether the employee does, or does not, normally reside in the labor area as defined in Attachment A, paragraph 1. Whenever the Secretary of Labor, pursuant to Section IV, paragraph 3b, has found that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in Section 1(b)(2)(B) of the Davis Bacon Act, the contractor and each subcontractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, that the plan or program has been communicated in writing to the laborers or mechanics affected, and show the cost anticipated or the actual cost incurred in providing benefits. Contractors or subcontractors employing

apprentices or trainees under approved programs shall maintain written evidence of the registration of apprentices and trainees, and ratios and wage rates prescribed in the applicable programs.

- c. Each contractor and subcontractor shall furnish, each week in which any contract work is performed, to the SHA resident engineer a payroll of wages paid each of its employees (including apprentices, trainees, and helpers, described in Section IV, paragraphs 4 and 5, and watchmen and guards engaged on work during the preceding weekly payroll period). The payroll submitted shall set out accurately and completely all of the information required to be maintained under paragraph 2b of this Section V. This information may be submitted in any form desired. Optional Form WH-347 is available for this purpose and may be purchased from the Superintendent of Documents (Federal stock number 029-005-0014-1), U.S. Government Printing Office, Washington, D.C. 20402. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors.
- d. Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor or his/her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:
  - (1) that the payroll for the payroll period contains the information required to be maintained under paragraph 2b of this Section V and that such information is correct and complete;
  - (2) that such laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in the Regulations, 29 CFR 3;
  - (3) that each laborer or mechanic has been paid not less than the applicable wage rate and fringe benefits or cash equivalent for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.
- e. The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 2d of this Section V.
- f. The falsification of any of the above certifications may subject the contractor to civil or criminal prosecution under 18 U.S.C. 1001 and 31 U.S.C. 231.
- g. The contractor or subcontractor shall make the records required under paragraph 2b of this Section V available for inspection, copying, or transcription by authorized representatives of the SHA, the FHWA, or the DOL, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the SHA, the FHWA, the DOL, or all may, after written notice to the contractor, sponsor, applicant, or owner, take such actions as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

## **VI. RECORD OF MATERIALS, SUPPLIES, AND LABOR**

1. On all Federal-aid contracts on the National Highway System, except those which provide solely for the installation of protective devices at railroad grade crossings, those which are constructed on a force account or direct labor basis, highway beautification contracts, and contracts for which the total final construction cost for roadway and bridge is less than \$1,000,000 (23 CFR 635) the contractor shall:
  - a. Become familiar with the list of specific materials and supplies contained in Form FHWA-47, "Statement of Materials and Labor Used by Contractor of Highway Construction Involving Federal Funds," prior to the commencement of work under this contract.
  - b. Maintain a record of the total cost of all materials and supplies purchased for and incorporated in the work, and also of the quantities of those specific materials and supplies listed on Form FHWA-47, and in the units shown on Form FHWA-47.

- c. Furnish, upon the completion of the contract, to the SHA resident engineer on Form FHWA-47 together with the data required in paragraph 1b relative to materials and supplies, a final labor summary of all contract work indicating the total hours worked and the total amount earned.
2. At the prime contractor's option, either a single report covering all contract work or separate reports for the contractor and for each subcontract shall be submitted.

#### **VII. SUBLETTING OR ASSIGNING THE CONTRACT**

1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the State. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635).
  - a. "Its own organization" shall be construed to include only workers employed and paid directly by the prime contractor and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor, assignee, or agent of the prime contractor.
  - b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid on the contract as a whole and in general are to be limited to minor components of the overall contract.
2. The contract amount upon which the requirements set forth in paragraph 1 of Section VII is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.
3. The contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the SHA contracting officer determines is necessary to assure the performance of the contract.
4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the SHA contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the SHA has assured that each subcontract is evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract.

#### **VIII. SAFETY: ACCIDENT PREVENTION**

1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the SHA contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.
2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).
3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).

## **IX. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS**

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, the following notice shall be posted on each Federal-aid highway project (23 CFR 635) in one or more places where it is readily available to all persons concerned with the project:

### **Notice To All Personnel Engaged On Federal-Aid Highway Projects**

18 U.S.C. 1020 READS AS FOLLOWS:

"Whoever being an officer, agent, or employee of the United States, or any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 1, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined not more than \$10,000 or imprisoned not more than 5 years or both."

## **X. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT**

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$100,000 or more.)

By submission of this bid or the execution of this contract, or subcontract, as appropriate, the bidder, Federal-aid construction contractor, or subcontractor, as appropriate, will be deemed to have stipulated as follows:

1. That any facility that is or will be utilized in the performance of this contract, unless such contract is exempt under the Clean Air Act, as amended (42 U.S.C. 1857 et seq., as amended by Pub.L. 91-604), and under the Federal Water Pollution Control Act, as amended (33 U.S.C. 1251 et seq., as amended by Pub.L. 92-500), Executive Order 11738, and regulations in implementation thereof (40 CFR 15) is not listed, on the date of contract award, on the U.S. Environmental Protection Agency (EPA) List of Violating Facilities pursuant to 40 CFR 15.20.
2. That the firm agrees to comply and remain in compliance with all the requirements of Section 114 of the Clean Air Act and Section 308 of the Federal Water Pollution Control Act and all regulations and guidelines listed thereunder.
3. That the firm shall promptly notify the SHA of the receipt of any communication from the Director, Office of Federal Activities, EPA, indicating that a facility that is or will be utilized for the contract is under consideration to be listed on the EPA List of Violating Facilities.
4. That the firm agrees to include or cause to be included the requirements of paragraph 1 through 4 of this Section X in every nonexempt subcontract, and further agrees to take such action as the government may direct as a means of enforcing such requirements.

## **XI. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION**

### **1. Instructions for Certification - Primary Covered Transactions:**

(Applicable to all Federal-aid contracts - 49 CFR 29)

- a. By signing and submitting this proposal, the prospective primary participant is providing the certification set out below.
- b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this covered transaction. The prospective participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective primary participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction.
- c. The certification in this clause is a material representation of fact upon which reliance was placed when the department or agency determined to enter into this transaction. If it is later determined that the prospective primary participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause of default.
- d. The prospective primary participant shall provide immediate written notice to the department or agency to whom this proposal is submitted if any time the prospective primary participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- e. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the department or agency to which this proposal is submitted for assistance in obtaining a copy of those regulations.
- f. The prospective primary participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction.
- g. The prospective primary participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," provided by the department or agency entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.
- h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the nonprocurement portion of the "Lists of Parties Excluded From Federal Procurement or Nonprocurement Programs" (Nonprocurement List) which is compiled by the General Services Administration.
- i. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- j. Except for transactions authorized under paragraph f of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

**Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion — Primary Covered Transactions**

1. The prospective primary participant certifies to the best of its knowledge and belief, that it and its principals:

- a. Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
  - b. Have not within a 3-year period preceding this proposal been convicted of or had a civil judgement rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;
  - c. Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph 1b of this certification; and
  - d. Have not within a 3-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
2. Where the prospective primary participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

## **2. Instructions for Certification - Lower Tier Covered Transactions:**

(Applicable to all subcontracts, purchase orders and other lower tier transactions of \$25,000 or more - 49 CFR 29)

- a. By signing and submitting this proposal, the prospective lower tier is providing the certification set out below.
- b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.
- c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances.
- d. The terms "covered transaction," "debarred," "suspended," "ineligible," "primary covered transaction," "participant," "person," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations.
- e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.
- f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.
- g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the Nonprocurement List.
- h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is

not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

- i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

**Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion — Lower Tier Covered Transactions**

1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.
2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

**XII. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING**

(Applicable to all Federal-aid construction contracts and to all related subcontracts which exceed \$100,000 - 49 CFR 20)

1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:
  - a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
  - b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.
2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.
3. The prospective participant also agrees by submitting his or her bid or proposal that he or she shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such recipients shall certify and disclose accordingly.

**FEDERAL-AID FEMALE AND MINORITY GOALS**

In accordance with Section II, "Nondiscrimination," of "Required Contract Provisions Federal-aid Construction Contracts" the following are the goals for female utilization:

Goal for Women (applies nationwide).....(percent) 6.9

The following are goals for minority utilization:

**CALIFORNIA ECONOMIC AREA**

		<b>Goal (Percent)</b>
<b>174</b>	<b>Redding, CA:</b> Non-SMSA Counties CA Lassen; CA Modoc;CA Plumas;CA Shasta; CA Siskiyou; CA Tehama.	6.8
<b>175</b>	<b>Eureka, CA</b> Non-SMSA Counties CA Del Norte; CA Humboldt; CA Trinity.	6.6
<b>176</b>	<b>San Francisco-Oakland-San Jose, CA:</b> SMSA Counties: 7120 Salinas-Seaside-Monterey, CA CA Monterey. 7360 San Francisco-Oakland CA Alameda; CA Contra Costa; CA Marin; CA San Francisco; CA San Mateo. 7400 San Jose, CA CA Santa Clara. 7485 Santa Cruz, CA. CA Santa Cruz. 7500 Santa Rosa, CA CA Sonoma. 8720 Vallejo-Fairfield- Napa, CA CA Napa; CA Solano Non-SMSA Counties CA Lake; CA Mendocino; CA San Benito	28.9 25.6 19.6 14.9 9.1 17.1 23.2
<b>177</b>	<b>Sacramento, CA:</b> SMSA Counties: 6920 Sacramento, CA CA Placer; CA Sacramento; CA Yolo. Non-SMSA Counties CA Butte; CA Colusa; CA El Dorado; CA Glenn; CA Nevada; CA Sierra; CA Sutter; CA Yuba.	16.1 14.3
<b>178</b>	<b>Stockton-Modesto, CA:</b> SMSA Counties: 5170 Modesto, CA CA Stanislaus. 8120 Stockton, CA CA San Joaquin. Non-SMSA Counties CA Alpine; CA Amador; CA Calaveras; CA Mariposa;CA Merced; CA Tuolumne.	12.3 24.3 19.8

		<b>Goal (Percent)</b>
<b>179</b>	<b>Fresno-Bakersfield, CA</b>	
	SMSA Counties:	
	0680 Bakersfield, CA	19.1
	CA Kern.	
	2840 Fresno, CA	26.1
	CA Fresno.	
	Non-SMSA Counties	23.6
	CA Kings; CA Madera; CA Tulare.	
<b>180</b>	<b>Los Angeles, CA:</b>	
	SMSA Counties:	
	0360 Anaheim-Santa Ana-Garden Grove, CA	11.9
	CA Orange.	
	4480 Los Angeles-Long Beach, CA	28.3
	CA Los Angeles.	
	6000 Oxnard-Simi Valley-Ventura, CA	21.5
	CA Ventura.	
	6780 Riverside-San Bernardino-Ontario, CA.	19.0
	CA Riverside; CA San Bernardino.	
	7480 Santa Barbara-Santa Maria-Lompoc, CA	19.7
	CA Santa Barbara.	
	Non-SMSA Counties	24.6
	CA Inyo; CA Mono; CA San Luis Obispo.	
<b>181</b>	<b>San Diego, CA:</b>	
	SMSA Counties	
	7320 San Diego, CA.	16.9
	CA San Diego.	
	Non-SMSA Counties	18.2
	CA Imperial.	

In addition to the reporting requirements set forth elsewhere in this contract the Contractor and subcontractors holding subcontracts, not including material suppliers, of \$10,000 or more, shall submit for every month of July during which work is performed, employment data as contained under Form FHWA PR-1391 (Appendix C to 23 CFR, Part 230), and in accordance with the instructions included thereon.