

DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30th Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

www.dot.ca.gov/hq/esc/oe



*Flex your power!
Be energy efficient!*

March 19, 2014

06-Kin-198-R16.5/R17.2

06-487504

Project ID 0600000488

Addendum No. 4

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN KINGS COUNTY IN HANFORD FROM 0.4 MILE WEST OF 12TH AVENUE OVERCROSSING TO 0.3 MILE EAST OF 12TH AVENUE OVERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Wednesday, March 26, 2014.

This addendum is being issued to revise the project plans, the *Notice to Bidders and Special Provisions*, the *Bid* book, and *Information Handout*.

Project plan sheets 1, 9, 39, 120, 121, 216 and 224 are replaced and attached for substitution for the like-numbered sheets.

Project plan sheets 247A, 247B, 247C, 247D, 247E, 247F, 247G, 247H, 247I and 247J are added and attached for addition to the project plans.

In the Special Provisions, Section 2 BIDDING, 2-1.06B Supplemental Project Information, is replaced as follows:

"Add to section 2-1.06B:

The Department makes the following supplemental project information available:

Supplemental Project Information

Means	Description
Included in the <i>Information Handout</i>	Railroad relations and insurance requirements Foundation Report (Br. No. 45-0099), March 22, 2011 Geotechnical Recommendation (Overhead Signs)
Available as specified in the <i>Standard Specifications</i>	Cross sections and Other Electronic Files Bridge as built drawings

Addendum No. 4
Page 2
March 19, 2014

06-Kin-198-R16.5/R17.2
06-487504
Project ID 0600000488

In the Special Provisions, Section 80-3.02C, is replaced as follows:

"80 FENCES

Replace the 1st paragraph in section 80-3.02C with:

Chain link fabric must comply with AASHTO M181 for Type IV fabric with a black lusterless Class A coating that must match color no. 37030 of the FED-STD-595."

The Materials Information, "GEOTECHNICAL RECOMMENDATION (OVERHEAD SIGNS)" is added to Information Handout as attached.

In the *Bid* book, in the "Bid Item List," Items 48 and 51 are replaced.

In the *Bid* book, in the "Bid Item List," Item 140 is deleted.

In the *Bid* book, in the "Bid Item List," Items 141 and 142 are added.

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html

Inform subcontractors and suppliers as necessary.

This addendum, EBS addendum file and attachments are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/06/06-487504

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



MOHSEN SULTAN
Chief, Office of Plans, Specifications & Estimates
Office Engineer
Division of Engineering Services

Attachments

**BID ITEM LIST
06-487504**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
41 (F)	153225	PREPARE CONCRETE BRIDGE DECK SURFACE	SQFT	10,555		
42	153226	REFINISH BRIDGE DECK	SQFT	980		
43 (F)	153233	TREAT BRIDGE DECK	SQFT	10,555		
44	153234	FURNISH BRIDGE DECK TREATMENT MATERIAL	GAL	106		
45	157560	BRIDGE REMOVAL (PORTION)	LS	LUMP SUM	LUMP SUM	
46	160102	CLEARING AND GRUBBING (LS)	LS	LUMP SUM	LUMP SUM	
47	190101	ROADWAY EXCAVATION	CY	43,500		
48 (F)	192003	STRUCTURE EXCAVATION (BRIDGE)	CY	261		
49 (F)	192037	STRUCTURE EXCAVATION (RETAINING WALL)	CY	148		
50 (F)	192060	STRUCTURE EXCAVATION (GROUND ANCHOR WALL)	CY	171		
51 (F)	193003	STRUCTURE BACKFILL (BRIDGE)	CY	147		
52 (F)	193013	STRUCTURE BACKFILL (RETAINING WALL)	CY	180		
53 (F)	193027	STRUCTURE BACKFILL (GROUND ANCHOR WALL)	CY	9		
54 (F)	193030	PERVIOUS BACKFILL MATERIAL	CY	30		
55	198010	IMPORTED BORROW (CY)	CY	57,900		
56	208304	WATER METER	EA	2		
57	208562	CAM COUPLER ASSEMBLY	EA	2		
58	208740	12" CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	LF	840		
59	025152	TRUCK WATER (CAM COUPLER ASSEMBLY)	LS	LUMP SUM	LUMP SUM	
60	210010	MOVE-IN/MOVE-OUT (EROSION CONTROL)	EA	6		

**BID ITEM LIST
06-487504**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
121 (F)	833142	CONCRETE BARRIER (TYPE 26 MODIFIED)	LF	365		
122 (F)	839521	CABLE RAILING	LF	202		
123	839543	TRANSITION RAILING (TYPE WB-31)	EA	1		
124	839581	END ANCHOR ASSEMBLY (TYPE SFT)	EA	4		
125	839584	ALTERNATIVE IN-LINE TERMINAL SYSTEM	EA	4		
126	839585	ALTERNATIVE FLARED TERMINAL SYSTEM	EA	1		
127	839700	CONCRETE BARRIER (TYPE 60F)	LF	190		
128	044144	CONCRETE BARRIER (TYPE 60D) (MODIFIED)	LF	200		
129	840504	4" THERMOPLASTIC TRAFFIC STRIPE	LF	12,400		
130	840506	8" THERMOPLASTIC TRAFFIC STRIPE	LF	4,590		
131	840508	8" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3)	LF	440		
132	840515	THERMOPLASTIC PAVEMENT MARKING	SQFT	4,490		
133	840521	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 6-1)	LF	350		
134	840525	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12)	LF	4,520		
135	840526	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 17-7)	LF	8,760		
136	840656	PAINT TRAFFIC STRIPE (2-COAT)	LF	6,620		
137	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	890		
138	860090	MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION	LS	LUMP SUM	LUMP SUM	
139	025155	ELECTRICAL SYSTEM	LS	LUMP SUM	LUMP SUM	
140	BLANK					

**BID ITEM LIST
06-487504**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
141	153221	REMOVE CONCRETE BARRIER	LF	190		
142	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

TOTAL BID:

\$
