



STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION

**NOTICE TO BIDDERS  
AND  
SPECIAL PROVISIONS**

**FOR CONSTRUCTION ON STATE HIGHWAY IN LOS ANGELES COUNTY IN GLENDALE  
FROM SONORA AVENUE UNDERCROSSING TO ALLEN AVENUE UNDERCROSSING**

**In District 07 On Route 5**

**Under**

---

Bid book dated March 22, 2010

Standard Specifications dated 1999

Project Plans approved June 22, 2009

Standard Plans dated 2004

---

**Identified by**

**Contract No. 07-1786A4**

**07-LA-5-44.2/45.2**

Bids open Thursday, May 13, 2010  
Dated March 22, 2010

OSD  
IH

\*\*\*\*\*

# SPECIAL NOTICES

\*\*\*\*\*

- The Subcontractor List form in the Bid book and Section 2-1.12, "Bid Document Completion," of the Amendments to the Standard Specifications have been revised.
- The Department has changed its DVBE requirements, including an increased maximum incentive amount. Refer to section titled "Disabled Veteran Business Enterprises" in Section 2, "Bidding," of these special provisions.
- Effective August 1, 2009, the Department is implementing electronic notification of construction contract addenda for all projects. For addenda information, go to:

<http://www.dot.ca.gov/addenda/>

- The Department is providing an electronic Information Handout for this project. Refer to Section 2-1.03B, "Supplemental Project Information," in the Amendments to the Standard Specifications for the location of this information.
- The contract award period has been extended for this project.
- The Department has revised its specifications for compensation adjustments for price index fluctuations. Refer to section titled "Payment Adjustments for Price Index Fluctuations" in Section 5, "General," of the special provisions. The following list summarizes the main revisions:
  1. The new index is based on the average of the previous month's crude oil prices.
  2. There is a new Web site address.
  3. The 90/10 cost sharing provision was removed.
  4. Sales tax is included in the adjustments.
  5. All paving materials that include asphalt are subject to the adjustments.
  6. Formulas for calculating asphalt quantities for various materials are included.
  7. Bidders may opt out of payment adjustments for price index fluctuations at the time of bid.
- The Department is allowing contractors to submit electronic payroll records to the District Labor Compliance Office. Refer to section titled "Electronic Submission of Payroll Records" under Section 5, "General," of these special provisions.

# CONTRACT NO. 07-1786A4

The special provisions contained herein have been prepared by or under the direction of the following Registered Persons.

## HIGHWAYS

*Paul H. Hsu*  
REGISTERED CIVIL ENGINEER



## MAINTAINING TRAFFIC

*Mart Oregel*  
REGISTERED CIVIL ENGINEER



## ELECTRICAL (ITS)

*Jacqueline Tan*  
REGISTERED ELECTRICAL ENGINEER



# TABLE OF CONTENTS

NOTICE TO BIDDERS .....	1
COPY OF BID ITEM LIST.....	3
SPECIAL PROVISIONS.....	12
SECTION 1 (BLANK).....	12
SECTION 2 BIDDING.....	12
2-1.01 SMALL BUSINESS AND NON-SMALL BUSINESS SUBCONTRACTOR PREFERENCES .....	12
2-1.02 DISABLED VETERAN BUSINESS ENTERPRISES .....	13
2-1.03 CALIFORNIA COMPANIES .....	13
2-1.04 TIE BID RESOLUTION.....	13
2-1.05 OPT OUT OF PAYMENT ADJUSTMENTS FOR PRICE INDEX FLUCTUATIONS .....	14
SECTION 3 CONTRACT AWARD AND EXECUTION.....	14
3-1.01 CONTRACT AWARD.....	14
3-1.02 SMALL BUSINESS PARTICIPATION REPORT .....	14
SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION, AND LIQUIDATED DAMAGES .....	14
SECTION 5 GENERAL.....	14
5-1.01 EMISSIONS REDUCTION .....	14
5-1.02 NON-SMALL BUSINESSES .....	15
5-1.03 DISABLED VETERAN BUSINESS ENTERPRISES .....	15
5-1.04 PAYMENT ADJUSTMENTS FOR PRICE INDEX FLUCTUATIONS .....	15
5-1.05 SURFACE MINING AND RECLAMATION ACT.....	18
5-1.06 ELECTRONIC SUBMISSION OF PAYROLL RECORDS.....	19
5-1.07 FORCE ACCOUNT PAYMENT .....	19
5-1.08 AREAS FOR CONTRACTOR'S USE .....	20
5-1.09 PAYMENTS .....	20
5-1.10 SUPPLEMENTAL PROJECT INFORMATION .....	21
5-1.11 SOUND CONTROL REQUIREMENTS .....	21
5-1.12 BIRD PROTECTION .....	22
5-1.13 RELATIONS WITH CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD .....	22
5-1.14 AERIALY DEPOSITED LEAD .....	23
5-1.15 PRESERVATION OF PROPERTY .....	24
5-1.16 NONHIGHWAY FACILITIES (INCLUDING UTILITIES).....	24
5-1.17 DAMAGE REPAIR .....	24
5-1.18 RELIEF FROM MAINTENANCE AND RESPONSIBILITY .....	25
5-1.19 AIR QUALITY – BASIC NESHAP ASBESTOS NOTIFICATION.....	25
SECTION 6. (BLANK).....	25
SECTION 7. (BLANK).....	25
SECTION 8. MATERIALS.....	25
SECTION 8-1. MISCELLANEOUS.....	25
8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS .....	25
8-1.02 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS .....	32
8-1.03 STATE-FURNISHED MATERIALS.....	37
8-1.04 SLAG AGGREGATE .....	38
8-1.05 ENGINEERING FABRICS .....	39
SECTION 8-2. CONCRETE .....	39
8-2.01 PORTLAND CEMENT CONCRETE.....	39
8-2.02 PRECAST CONCRETE QUALITY CONTROL.....	40
SECTION 8-3. WELDING.....	42
8-3.01 WELDING.....	42
WELDING QUALITY CONTROL.....	44
WELDING FOR OVERHEAD SIGN AND POLE STRUCTURES.....	47
PAYMENT.....	48
SECTION 9. DESCRIPTION OF BRIDGE WORK.....	48
SECTION 10. CONSTRUCTION DETAILS .....	48

SECTION 10-1. GENERAL.....	48
10-1.01 CONSTRUCTION PROJECT INFORMATION SIGNS.....	48
10-1.02 ORDER OF WORK.....	48
10-1.03 WATER POLLUTION CONTROL.....	50
10-1.04 CONSTRUCTION SITE MANAGEMENT.....	56
10-1.05 STREET SWEEPING.....	64
10-1.06 TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX).....	65
10-1.07 TEMPORARY EROSION CONTROL BLANKET.....	67
10-1.08 TEMPORARY CONCRETE WASHOUT FACILITY.....	69
10-1.09 TEMPORARY CONCRETE WASHOUT (PORTABLE).....	71
10-1.10 TEMPORARY FIBER ROLL.....	71
10-1.11 TEMPORARY GRAVEL BAG BERM.....	73
10-1.12 TEMPORARY CONSTRUCTION ENTRANCE.....	74
10-1.13 TEMPORARY DRAINAGE INLET PROTECTION.....	76
10-1.14 SCAFFOLDING.....	80
10-1.15 COOPERATION.....	80
10-1.16 PROGRESS SCHEDULE (CRITICAL PATH METHOD).....	80
10-1.17 TIME-RELATED OVERHEAD.....	86
10-1.18 SMALL BUSINESS UTILIZATION REPORT.....	88
10-1.19 RIGHT OF WAY OBSTRUCTIONS.....	88
10-1.20 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES.....	89
10-1.21 CONSTRUCTION AREA SIGNS.....	90
10-1.22 MAINTAINING TRAFFIC.....	90
10-1.23 CLOSURE REQUIREMENTS AND CONDITIONS.....	97
10-1.24 IMPACT ATTENUATOR VEHICLE.....	98
10-1.25 TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE.....	99
10-1.26 TEMPORARY PAVEMENT DELINEATION.....	100
10-1.27 BARRICADE.....	102
10-1.28 PORTABLE CHANGEABLE MESSAGE SIGN.....	102
10-1.29 CHANNELIZER.....	102
10-1.30 TEMPORARY TRAFFIC SCREEN.....	103
10-1.31 TEMPORARY CRASH CUSHION MODULE.....	103
10-1.32 EXISTING HIGHWAY FACILITIES.....	104
ABANDON PIPE LINE.....	104
REMOVE METAL BEAM GUARD RAILING.....	105
REMOVE SIGN STRUCTURE.....	105
REMOVE PAVEMENT MARKER.....	105
REMOVE CHAIN LINK FENCE.....	105
REMOVE TRAFFIC STRIPE AND PAVEMENT MARKING.....	105
REMOVE DRAINAGE FACILITY.....	107
REMOVE ROADSIDE SIGN.....	107
ADJUST INLET.....	107
COLD PLANE ASPHALT CONCRETE PAVEMENT.....	107
CAP INLET.....	108
EXISTING HIGHWAY IRRIGATION FACILITIES.....	108
BRIDGE REMOVAL.....	108
REMOVE CONCRETE.....	110
10-1.33 CLEARING AND GRUBBING.....	110
10-1.34 EARTHWORK.....	110
10-1.35 CONTROLLED LOW STRENGTH MATERIAL.....	111
10-1.36 SAND BEDDING (AUSTIN VAULT).....	112
MATERIALS.....	112
PLACEMENT.....	112
MEASUREMENT.....	112
PAYMENT.....	112
10-1.37 MATERIAL CONTAINING AERIALY DEPOSITED LEAD.....	112
10-1.38 IRRIGATION CROSSOVERS.....	115
10-1.39 WATER SUPPLY LINE (BRIDGE).....	115

10-1.40	AGGREGATE BASE.....	117
10-1.41	PERMEABLE MATERIAL (AUSTIN VAULT).....	118
	MATERIALS.....	118
	PLACEMENT.....	118
	MEASUREMENT.....	118
	PAYMENT.....	118
10-1.42	LEAN CONCRETE BASE.....	118
10-1.43	HOT MIX ASPHALT.....	119
10-1.44	HOT MIX ASPHALT AGGREGATE LIME TREATMENT - SLURRY METHOD.....	120
10-1.45	HOT MIX ASPHALT AGGREGATE LIME TREATMENT - DRY LIME METHOD.....	123
10-1.46	LIQUID ANTISTRIP TREATMENT.....	125
10-1.47	EXIT RAMP TERMINI.....	127
10-1.48	PILING.....	127
	CAST-IN-DRILLED-HOLE CONCRETE PILES.....	130
10-1.49	CONCRETE STRUCTURES.....	142
	GENERAL.....	142
	DECK CRACK TREATMENT.....	142
	FALSEWORK.....	143
	DECK CLOSURE POURS.....	143
	ELASTOMERIC BEARING PADS.....	143
	MEASUREMENT AND PAYMENT.....	144
10-1.50	PRECAST CONCRETE BOX CULVERTS.....	144
10-1.51	DRILL AND BOND DOWEL (CHEMICAL ADHESIVE).....	145
10-1.52	DRILL AND BOND DOWELS.....	146
10-1.53	CORE CONCRETE.....	146
10-1.54	SEALING JOINTS.....	146
10-1.55	ARCHITECTURAL SURFACE (TEXTURED CONCRETE).....	146
	TEST PANEL.....	147
	FORM LINERS.....	147
	RELEASING FORM LINERS.....	148
	CURING.....	148
	MEASUREMENT AND PAYMENT.....	148
10-1.56	REINFORCEMENT.....	148
10-1.57	STEEL STRUCTURES.....	148
	GENERAL.....	148
	MATERIALS.....	149
	ROTATIONAL CAPACITY TESTING PRIOR TO SHIPMENT TO JOB SITE.....	149
	INSTALLATION TENSION TESTING AND ROTATIONAL CAPACITY TESTING AFTER ARRIVAL ON THE JOB SITE.....	153
	SURFACE PREPARATION.....	154
	SEALING.....	154
	WELDING.....	154
10-1.58	SIGN STRUCTURES.....	154
10-1.59	ROADSIDE SIGNS.....	155
10-1.60	FURNISH SIGN.....	156
	SHEET ALUMINUM.....	157
	RETROREFLECTIVE SHEETING.....	157
	PROCESS COLOR AND FILM.....	158
	SINGLE SHEET ALUMINUM SIGN.....	158
	FIBERGLASS REINFORCED PLASTIC PANEL SIGN.....	158
	FORMED PANEL SIGN.....	158
	MEASUREMENT AND PAYMENT.....	159
10-1.61	CLEAN AND PAINT STRUCTURAL STEEL.....	159
	GENERAL.....	159
	CLEANING.....	160
	PAINTING.....	160
10-1.62	PLASTIC PIPE.....	163
10-1.63	REINFORCED CONCRETE PIPE.....	163

10-1.64	CORRUGATED METAL PIPE .....	163
10-1.65	PLASTIC PIPE UNDERDRAIN (AUSTIN VAULT) .....	163
	MEASUREMENT.....	163
	PAYMENT.....	163
10-1.66	EMERGENCY DRAIN VALVE.....	164
	MATERIALS .....	164
	MEASUREMENT.....	164
	PAYMENT.....	164
10-1.67	MISCELLANEOUS FACILITIES.....	165
10-1.68	SLOPE PROTECTION .....	165
10-1.69	GABIONS .....	165
	MATERIALS .....	165
	GRADING, EXCAVATION AND BACKFILL.....	167
	CONSTRUCTION .....	167
	ASSEMBLY OF SUCCESSIVE GABION BASKETS (GABION-TO-GABION JOINTS).....	167
	ASSEMBLY OF MULTIPLE LAYERED GABIONS.....	167
	FILLING WITH ROCK .....	168
	CLOSURE OF LIDS .....	168
	MEASUREMENT.....	168
	PAYMENT.....	168
10-1.70	MISCELLANEOUS CONCRETE CONSTRUCTION .....	168
10-1.71	MISCELLANEOUS IRON AND STEEL .....	169
10-1.72	MISCELLANEOUS METAL (AUSTIN VAULT).....	169
10-1.73	BRIDGE DECK DRAINAGE SYSTEM.....	169
10-1.74	CHAIN LINK FENCE.....	170
10-1.75	CHAIN LINK WALK GATE.....	170
10-1.76	DELINEATORS .....	170
10-1.77	METAL BEAM GUARD RAILING.....	170
	ALTERNATIVE FLARED TERMINAL SYSTEM.....	170
10-1.78	CHAIN LINK RAILING.....	171
10-1.79	CABLE RAILING.....	171
10-1.80	CONCRETE BARRIER.....	171
10-1.81	TRANSITION RAILING (TYPE WB).....	172
10-1.82	THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING .....	172
10-1.83	PAINT TRAFFIC STRIPE AND PAVEMENT MARKING .....	172
10-1.84	PAVEMENT MARKERS .....	173
SECTION 10-2	HIGHWAY PLANTING AND IRRIGATION SYSTEMS .....	173
10-2.01	GENERAL .....	173
	PROGRESS INSPECTIONS .....	173
	COST BREAK-DOWN.....	173
10-2.02	EXISTING HIGHWAY PLANTING.....	176
10-2.03	EXISTING HIGHWAY IRRIGATION FACILITIES .....	176
	CHECK AND TEST EXISTING IRRIGATION FACILITIES.....	176
	MAINTAIN EXISTING IRRIGATION FACILITIES .....	176
10-2.04	HIGHWAY PLANTING.....	177
	HIGHWAY PLANTING MATERIALS.....	177
	PESTICIDES.....	180
	PLANTING.....	180
	PLANT ESTABLISHMENT WORK .....	180
10-2.05	IRRIGATION SYSTEMS.....	181
	PIPE AND CONDUIT ANCHORS .....	181
	VALVE BOXES .....	182
	BALL VALVES.....	182
	GATE VALVES.....	182
	ELECTRIC AUTOMATIC IRRIGATION COMPONENTS .....	182
	IRRIGATION CONTROLLER ENCLOSURE CABINET.....	184
	IRRIGATION SYSTEMS FUNCTIONAL TEST .....	184
	PIPE.....	184

SPRINKLERS .....	185
RECYCLED WATER WARNING SIGNS .....	185
FINAL IRRIGATION SYSTEM CHECK .....	186
SECTION 10-3. SIGNALS, LIGHTING AND ELECTRICAL SYSTEMS .....	186
10-3.01 DESCRIPTION .....	186
10-3.02 ABBREVIATIONS AND GLOSSARY .....	186
10-3.03 COST BREAK-DOWN .....	190
10-3.04 MAINTAINING EXISTING AND TEMPORARY ELECTRICAL SYSTEMS .....	190
10-3.05 MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION .....	190
10-3.06 CAST-IN-DRILLED-HOLE CONCRETE PILE FOUNDATIONS .....	191
10-3.07 STANDARDS, STEEL PEDESTALS, AND POSTS .....	192
10-3.08 CONDUIT .....	192
COMMUNICATION CONDUIT .....	193
SIZE 25 INNERDUCT .....	193
10-3.09 PULL BOXES .....	194
10-3.10 ELECTRONIC MARKERS .....	194
GENERAL .....	194
MATERIALS LIST AND DRAWINGS .....	194
FUNCTIONAL REQUIREMENTS .....	195
WARRANTY .....	195
PAYMENT .....	195
10-3.11 COMMUNICATION PULL BOXES .....	195
10-3.12 CONDUCTORS AND WIRING .....	196
FIBER OPTIC CABLE .....	196
LABELING .....	199
CABLE INSTALLATION .....	201
SPLICING .....	202
PASSIVE CABLE ASSEMBLIES AND COMPONENTS .....	202
FIBER OPTIC CABLE TERMINATIONS .....	202
FIBER OPTIC TESTING .....	203
TWISTED PAIR CABLE .....	207
10-3.13 BONDING AND GROUNDING .....	208
10-3.14 SERVICE .....	209
ELECTRIC SERVICE (IRRIGATION) .....	209
10-3.15 NUMBERING ELECTRICAL EQUIPMENT .....	209
10-3.16 STATE-FURNISHED CONTROLLER ASSEMBLIES .....	209
10-3.17 TRAFFIC SIGNAL INTERCONNECT AND WIRELESS DATA SERVICE EQUIPMENT .....	210
10-3.18 VEHICLE SIGNAL FACES AND SIGNAL HEADS .....	216
10-3.19 LIGHT EMITTING DIODE SIGNAL MODULE .....	216
10-3.20 PROGRAMMED VISIBILITY VEHICLE TRAFFIC SIGNAL HEADS .....	221
10-3.21 BATTERY BACKUP SYSTEM .....	221
10-3.22 LIGHT EMITTING DIODE PEDESTRIAN SIGNAL FACE MODULES .....	223
10-3.23 DETECTORS .....	225
10-3.24 MICROWAVE VEHICLE DETECTION SYSTEM - SIDE FIRE .....	225
10-3.25 PEDESTRIAN PUSH BUTTONS .....	229
10-3.26 LUMINAIRES .....	229
10-3.27 PEDESTRIAN UNDERCROSSING FIXTURES .....	229
10-3.28 SIGN LIGHTING FIXTURES-INDUCTION .....	230
10-3.29 INTERNALLY ILLUMINATED SIGN LIGHT EMITING DIODE .....	231
10-3.30 INTERNALLY ILLUMINATED STREET NAME SIGNS .....	234
10-3.31 PHOTOELECTRIC CONTROLS .....	234
10-3.32 MODIFY COMMUNICATION SYSTEM .....	234
10-3.33 REMOVING, REINSTALLING OR SALVAGING ELECTRICAL EQUIPMENT .....	234
10-3.34 DISPOSING OF ELECTRICAL EQUIPMENT .....	234
10-3.35 PAYMENT .....	234
AMENDMENTS TO THE STANDARD SPECIFICATIONS .....	236

# STANDARD PLANS LIST

The Standard Plan sheets applicable to this contract include, but are not limited to, those indicated below. Applicable Revised Standard Plans (RSP) and New Standard Plans (NSP) indicated below are included in the project plans as Standard Plan sheets.

A10A	Acronyms and Abbreviations (A-L)
A10B	Acronyms and Abbreviations (M-Z)
A10C	Symbols (Sheet 1 of 2)
A10D	Symbols (Sheet 2 of 2)
A20A	Pavement Markers and Traffic Lines, Typical Details
A20B	Pavement Markers and Traffic Lines, Typical Details
A20C	Pavement Markers and Traffic Lines, Typical Details
A20D	Pavement Markers and Traffic Lines, Typical Details
A24A	Pavement Markings - Arrows
A24B	Pavement Markings - Arrows
RSP A24C	Pavement Markings – Symbols and Numerals
A24D	Pavement Markings – Words
A24E	Pavement Markings – Words and Crosswalks
A62A	Excavation and Backfill – Miscellaneous Details
A62B	Limits of Payment for Excavation and Backfill – Bridge Surcharge and Wall
A62C	Limits of Payment for Excavation and Backfill - Bridge
A62D	Excavation and Backfill – Concrete Pipe Culverts
A62DA	Excavation and Backfill – Concrete Pipe Culverts
A62F	Excavation and Backfill – Metal and Plastic Culverts
A73B	Markers
A73C	Delineators, Channelizers and Barricades
A77A1	Metal Beam Guard Railing – Standard Railing Section (Wood Post with Wood Block)
A77B1	Metal Beam Guard Railing – Standard Hardware
A77C1	Metal Beam Guard Railing – Wood Post and Wood Block Details
A77C3	Metal Beam Guard Railing – Typical Line Post Embedment and Hinge Point Offset Details
A77C4	Metal Beam Guard Railing – Typical Railing Delineation and Dike Positioning Details
A77H1	Metal Railing End Anchor Assembly (Type SFT)
A77H3	Metal Railing Anchor Cable and Anchor Plate Details
A77I1	Metal Railing End Anchor Assembly (Type CA)
A77J1	Metal Beam Guard Railing Connections to Bridge Railings without Sidewalks Details No. 1
A77J4	Metal Beam Guard Railing Transition Railing (Type WB)
A77L1	Metal Beam Railing Terminal System (Type SRT)
A85	Chain Link Fence
RSP A87A	Curbs and Driveways
A87B	Asphalt Concrete Dikes
RSP A88A	Curb Ramp Details
RSP A88B	Curb Ramp and Island Passageway Details
D72	Drainage Inlets
D73	Drainage Inlets
D74B	Drainage Inlets
D74C	Drainage Inlets Details
D75A	Pipe Inlets
RSP D77A	Grate Details
D77B	Bicycle Proof Grate Details
D79	Precast Reinforced Concrete Pipe – Direct Design Method
D84	Box Culvert Wingwalls-Types A, B and C

D87A	Corrugated Metal Pipe Downdrain Details
D88	Construction Loads on Culverts
D93A	Pipe Riser Connections
D93B	Drainage Inlet Riser Connections
D94A	Metal and Plastic Flared End Sections
D97A	Corrugated Metal Pipe Coupling Details No. 1- Annular Coupling Band Bar And Strap and Angle Connections
D97D	Corrugated Metal Pipe Coupling Details No. 4- Hugger Coupling Bands
RSP D97F	Corrugated Metal Pipe Coupling Details No. 6- Positive Joint
RSP D97G	Corrugated Metal Pipe Coupling Details No. 7- Downdrain
D97H	Reinforced Concrete Pipe or Non-Reinforced Concrete Pipe-Standard and Positive Joints
D98C	Grated Line Drain Details
D100A	Gabion Basket Details No. 1
D100B	Gabion Basket Details No. 2
H1	Planting and Irrigation – Abbreviations
RSP H2	Planting and Irrigation – Symbols
H3	Planting and Irrigation Details
H4	Planting and Irrigation Details
H5	Planting and Irrigation Details
H6	Planting and Irrigation Details
H7	Planting and Irrigation Details
H9	Planting and Irrigation Details
H10	Irrigation Controller Enclosure Cabinet
RSP T1A	Temporary Crash Cushion, Sand Filled (Unidirectional)
RSP T1B	Temporary Crash Cushion, Sand Filled (Bidirectional)
RSP T2	Temporary Crash Cushion, Sand Filled (Shoulder Installations)
T3	Temporary Railing (Type K)
T4	Temporary Traffic Screen
RSP T7	Construction Project Funding Identification Signs
RSP T10	Traffic Control System for Lane Closure on Freeways and Expressways
RSP T11	Traffic Control System for Lane Closure on Multilane Conventional Highways
RSP T12	Traffic Control System for Lane Closure on Multilane Conventional Highways
RSP T14	Traffic Control System for Ramp Closure
RSP T15	Traffic Control System for Moving Lane Closure on Multilane Highways
RSP T16	Traffic Control System for Moving Lane Closure on Multilane Highways
T54	Temporary Water Pollution Control Details (Temporary Erosion Control Blanket)
T55	Temporary Water Pollution Control Details (Temporary Erosion Control Blanket)
T56	Temporary Water Pollution Control Details (Temporary Fiber Roll)
T58	Temporary Water Pollution Control Details (Temporary Construction Entrance)
T59	Temporary Water Pollution Control Details (Temporary Concrete Washout Facility)
B0-1	Bridge Details
B0-3	Bridge Details
B0-5	Bridge Details
B0-13	Bridge Details
B2-5	Pile Details-Class 400 And Class 625
B3-1	Retaining Wall Type 1 – H=1200 Through 9100 mm
B3-5	Counterfort Retaining Wall Type 3
B3-8	Retaining Wall Details No. 1
B6-10	Utility Opening, T-Beam
RSP B6-21	Joint Seals (Maximum Movement Rating = 50 mm)
B7-5	Deck Drains
B7-11	Utility Details
B11-47	Cable Railing
B11-52	Chain Link Railing Type 7
B11-56	Concrete Barrier Type 736

B14-3	Communication and Sprinkler Control Conduits (Conduit Less Than Size 103)
B14-4	Water Supply Line (Bridge) (Pipe Sizes Less Than NPS 4)
B14-5	Water Supply Line (Details) (Pipe Sizes Less Than NPS 4)
RS1	Roadside Signs, Typical Installation Details No. 1
RS2	Roadside Signs - Wood Post, Typical Installation Details No. 2
RS4	Roadside Signs, Typical Installation Details No. 4
RSP S1	Overhead Signs – Truss, Instructions and Examples
RSP S2	Overhead Signs – Truss, Single Post Type – Post Type II Thru IX
RSP S3	Overhead Signs – Truss, Single Post Type – Base Plate and Anchorage Details
RSP S4	Overhead Signs – Truss, Single Post Type – Structural Frame Members Details No. 1
S5	Overhead Signs – Truss, Single Post Type – Structural Frame Members Details No. 2
RSP S6	Overhead Signs – Truss, Gusset Plate Details
RSP S7	Overhead Signs – Truss, Single Post Type – Square Pedestal Foundation
RSP S12	Overhead Signs – Truss, Structural Frame Details
RSP S13	Overhead Signs – Truss, Frame Juncture Details
RSP S16	Overhead Signs – Walkway Details No. 1
RSP S17	Overhead Signs – Walkway Details No. 2
NSP S17A	Overhead Signs – Walkway Details No. 3
RSP S18	Overhead Signs – Walkway Safety Railing Details
RSP S20	Overhead Signs – Steel Frames – Removable Sign Panel Frames
S21	Overhead Signs – Removable Sign Panel Frames Mounting Details
RSP S22	Overhead Signs – Truss, Removable Sign Panel Frames – 2794 mm and 3048 mm Sign Panels
RSP S42	Overhead Signs – Lightweight Balanced – Single Steel Post Details
RSP S43	Overhead Signs – Lightweight, Type A, Connection Details
S46	Overhead Signs – Lightweight, Sign Panel Mounting Details, Laminated Panel – Type A
S47	Overhead Signs – Lightweight, Light Fixture Mounting Details
RSP S48	Overhead Signs – Lightweight Post Details
S49	Overhead Signs – Lightweight Foundation Details
S88	Type A – 2 Mounting Hardware – Overhead Laminated Type A Panel, Box Beam Closed Truss, Bridge Mounted and Tubular Sign Structures
S89	Roadside Formed Single Sheet Aluminum Panel
S90	Channel and Bolt Hole Location, Overhead Formed Sign Panel
S92	Overhead Formed Sign Panel
S93	Framing Details for Framed Single Sheet Aluminum Signs, Rectangular Shape
S94	Roadside Single Sheet Aluminum Signs, Rectangular Shape
S95	Roadside Single Sheet Aluminum Signs, Diamond Shape
RSP ES-1A	Electrical Systems (Symbols And Abbreviations)
RSP ES-1B	Electrical Systems (Symbols And Abbreviations)
RSP ES-1C	Electrical Systems (Symbols And Abbreviations)
RSP ES-2A	Electrical Systems (Service Equipment)
RSP ES-2C	Electrical Systems (Service Equipment Notes, Type III Series)
RSP ES-2E	Electrical Systems (Service Equipment and Typical Wiring Diagram, Type III – B Series)
RSP ES-2F	Electrical Systems (Service Equipment and Typical Wiring Diagram Type III – C Series)
ES-3A	Electrical Systems (Controller Cabinet Details)
RSP ES-3B	Electrical Systems (Controller Cabinet Details)
RSP ES-3C	Electrical Systems (Controller Cabinet Details)
RSP ES-3F	Electrical Systems (Telephone Demarcation Cabinet, Type C)
RSP ES-3G	Electrical Systems (Telephone Demarcation Cabinet, Type C Details)
RSP ES-3H	Electrical Systems (Irrigation Controller Enclosure Cabinet)
ES-4A	Electrical Systems (Signal Heads and Mountings)
ES-4B	Electrical Systems (Signal Heads and Mountings)
RSP ES-4C	Electrical Systems (Signal Heads and Mountings)
RSP ES-4D	Electrical Systems (Signal Heads and Mountings)
ES-4E	Electrical Systems (Signal Faces and Mountings)

RSP ES-5A	Electrical Systems (Detectors)
ES-5B	Electrical Systems (Detectors)
ES-5C	Electrical Systems (Detectors)
RSP ES-5D	Electrical Systems (Detectors)
RSP ES-6A	Electrical Systems (Lighting Standard Types 15 and 21)
ES-6B	Electrical Systems (Lighting Standards Types 15 and 21, Barrier Rail Mounted Details)
RSP ES-6E	Electrical Systems (Lighting Standards Types 30 and 31)
ES-6F	Electrical Systems (Lighting Standards Types 30 and 31, Base Plate Details)
RSP ES-7A	Electrical Systems (Signal Standards Push Button Posts and Type 15TS Standard))
RSP ES-7B	Electrical Systems (Signal And Lighting Standard – Type 1 Standard and Equipment Numbering)
RSP ES-7E	Electrical Systems (Signal and Lighting Standard – Case 3 Arm Loading, Wind Velocity = 161 km/h, Arm Lengths 4.6 m to 13.7 m)
RSP ES-7F	Electrical Systems (Signal and Lighting Standard – Case 4 Arm Loading, Wind Velocity = 161 km/h, Arm Lengths 7.6 m to 13.7 m)
RSP ES-7G	Electrical Systems (Signal and Lighting Standard – Case 5 Arm Loading, Wind Velocity = 161 km/h, Arm Lengths 15.2 m to 16.8 m)
RSP ES-7M	Electrical Systems (Signal and Lighting Standards – Details No. 1)
ES-7N	Electrical Systems (Signal and Lighting Standards – Details No. 2)
ES-7O	Electrical Systems (Sign Illumination – Internally Illumination Street Name Sign)
RSP ES-8	Electrical Systems (Pull Box Details)
RSP ES-9A	Electrical Systems (Electrical Details, Structure Installations)
RSP ES-9B	Electrical Systems (Electrical Details, Structure Installations)
RSP ES-9C	Electrical Systems (Electrical Details, Structure Installations)
ES-9D	Electrical Systems (Electrical Details, Structure Installations)
RSP ES-10	Electrical Systems (Isolux Diagrams)
RSP ES-11	Electrical Systems (Foundation Installations)
ES-12B	Electrical Systems (Pedestrian Undercrossing Fluorescent Lighting Fixture)
RSP ES-13A	Electrical Systems (Splicing Details)
RSP ES-13B	Electrical Systems (Wiring Details and Fuse Ratings)
ES-15A	Electrical Systems (Sign Illumination Equipment)
RSP ES-15C	Electrical Systems (Sign Illumination Equipment)
RSP ES-15D	Electrical Systems (Lighting and Sign Illumination Control)

# NOTICE TO BIDDERS

Bids open Thursday, May 13, 2010

Dated March 22, 2010

General work description: Modify and Realign On and Off Ramps with HMA and Retaining Walls.

The Department will receive sealed bids for CONSTRUCTION ON STATE HIGHWAY IN LOS ANGELES COUNTY IN GLENDALE FROM SONORA AVENUE UNDERCROSSING TO ALLEN AVENUE UNDERCROSSING.

District-County-Route-Kilometer Post: 07-LA-5-44.2/45.2

Contract No. 07-1786A4

The Contractor must have either a Class A license or any combination of the following Class C licenses which constitutes a majority of the work: C-8, C-12.

The Department establishes no DVBE Contract goal but encourages bidders to obtain DVBE participation.

Bids must be on a unit price basis.

Complete the work, including plant establishment work, within 490 working days.

The estimated cost of the project is \$9,000,000.

No prebid meeting is scheduled for this project.

The Department will receive bids until 2:00 p.m. on the bid open date at 3347 Michelson Drive, Suite 100, Irvine, CA 92612-1692. Bids received after this time will not be accepted.

The Department will open and publicly read the bids at the above location immediately after the specified closing time.

District office addresses are provided in the Standard Specifications.

Bidders' inquiries may be presented to the Department by following the instructions at:

[http://www.dot.ca.gov/hq/esc/oe/project\\_status/bid\\_inq.html](http://www.dot.ca.gov/hq/esc/oe/project_status/bid_inq.html)

The Department posts responses to the questions at the District Web sites.

Questions about alleged patent ambiguity of the plans, specifications, or estimate must be asked before bid opening. After bid opening, such questions will not be treated as bid protests.

Submit your bid with bidder's security equal to at least 10 percent of the bid.

Under Govt Code § 14835 et seq. and 2 CA Code of Regs § 1896 et seq., the Department gives preference to certified small businesses and non-small businesses who commit to 25 percent certified small business participation.

Under Pub Cont Code § 6107, the Department gives a reciprocal preference to a California company for bid comparison purposes over a nonresident contractor from any state that provides a preference to contractors from that state on construction contracts.

Prevailing wages are required on this Contract. The Director of the California Department of Industrial Relations determines the general prevailing wage rates. Obtain the wage rates at the DIR Web site, <http://www.dir.ca.gov>, or from the Department's Labor Compliance Office of the district in which the work is located.

The Department has made available Notices of Suspension and Proposed Debarment from the Federal Highway Administration. For a copy of the notices go to [http://www.dot.ca.gov/hq/esc/oe/contractor\\_info](http://www.dot.ca.gov/hq/esc/oe/contractor_info). Additional information is listed in the Excluded Parties List System at <https://www.epls.gov>.

DEPARTMENT OF TRANSPORTATION

NT

**COPY OF BID ITEM LIST**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
1	070012	PROGRESS SCHEDULE (CRITICAL PATH METHOD)	LS	LUMP SUM
2	070013	SMALL BUSINESS UTILIZATION REPORT	EA	5
3	070018	TIME-RELATED OVERHEAD	WDAY	240
4	074016	CONSTRUCTION SITE MANAGEMENT	LS	LUMP SUM
5	074019	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	LUMP SUM
6	074027	TEMPORARY EROSION CONTROL BLANKET	M2	410
7	074028	TEMPORARY FIBER ROLL	M	540
8	074031	TEMPORARY GRAVEL BAG BERM	M	2300
9	074032	TEMPORARY CONCRETE WASHOUT FACILITY	EA	1
10	074033	TEMPORARY CONSTRUCTION ENTRANCE	EA	3
11	074038	TEMPORARY DRAINAGE INLET PROTECTION	EA	14
12	074040	TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX)	M2	5000
13	074041	STREET SWEEPING	LS	LUMP SUM
14	074042	TEMPORARY CONCRETE WASHOUT (PORTABLE)	LS	LUMP SUM
15	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM
16	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM
17	120120	TYPE III BARRICADE	EA	21
18	120149	TEMPORARY PAVEMENT MARKING (PAINT)	M2	250
19	120151	TEMPORARY TRAFFIC STRIPE (TAPE)	M	3230
20	120152	TEMPORARY PAVEMENT MARKING (TAPE)	M2	17

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
21	120165	CHANNELIZER (SURFACE MOUNTED)	EA	220
22	129000	TEMPORARY RAILING (TYPE K)	M	1800
23	129100	TEMPORARY CRASH CUSHION MODULE	EA	93
24	150227	ABANDON PIPELINE	M	64
25	150608	REMOVE CHAIN LINK FENCE	M	180
26	150662	REMOVE METAL BEAM GUARD RAILING	M	130
27	150704	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE	M	86
28	150714	REMOVE THERMOPLASTIC TRAFFIC STRIPE	M	810
29	150715	REMOVE THERMOPLASTIC PAVEMENT MARKING	M2	27
30	150722	REMOVE PAVEMENT MARKER	EA	1360
31	150742	REMOVE ROADSIDE SIGN	EA	34
32	150760	REMOVE SIGN STRUCTURE	EA	1
33	150806	REMOVE PIPE	M	380
34	150820	REMOVE INLET	EA	14
35	152430	ADJUST INLET	EA	2
36	153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	M2	120
37	153210	REMOVE CONCRETE	M3	590
38	155003	CAP INLET	EA	1
39	157551	BRIDGE REMOVAL, LOCATION A	LS	LUMP SUM
40	157552	BRIDGE REMOVAL, LOCATION B	LS	LUMP SUM

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
41	160101	CLEARING AND GRUBBING	LS	LUMP SUM
42	190101	ROADWAY EXCAVATION	M3	6630
43	190106	ROADWAY EXCAVATION (TYPE Z-3) (AERIALY DEPOSITED LEAD)	M3	1440
44	190108	ROADWAY EXCAVATION (TYPE Y-2) (AERIALY DEPOSITED LEAD)	M3	2430
45	190110	LEAD COMPLIANCE PLAN	LS	LUMP SUM
46 (F)	192001	STRUCTURE EXCAVATION	M3	1301
47 (F)	192003	STRUCTURE EXCAVATION (BRIDGE)	M3	273
48 (F)	192037	STRUCTURE EXCAVATION (RETAINING WALL)	M3	1915
49	017093	SAND BEDDING (AUSTIN VAULT)	M3	100
50 (F)	192054	STRUCTURE EXCAVATION (TYPE Z-3) (AERIALY DEPOSITED LEAD)	M3	120
51 (F)	192058	STRUCTURE EXCAVATION (TYPE Y-2) (AERIALY DEPOSITED LEAD)	M3	480
52 (F)	193001	STRUCTURE BACKFILL	M3	312.2
53 (F)	193003	STRUCTURE BACKFILL (BRIDGE)	M3	300
54 (F)	193013	STRUCTURE BACKFILL (RETAINING WALL)	M3	2715
55	193114	SAND BACKFILL	M3	11
56	198001	IMPORTED BORROW	M3	5750
57	200001	HIGHWAY PLANTING	LS	LUMP SUM
58	204099	PLANT ESTABLISHMENT WORK	LS	LUMP SUM
59	206401	MAINTAIN EXISTING IRRIGATION FACILITIES	LS	LUMP SUM
60	208000	IRRIGATION SYSTEM	LS	LUMP SUM

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
61	208038	NPS 3 SUPPLY LINE (BRIDGE)	M	33
62	208732	250 MM CORRUGATED HIGH DENSITY POLYETHYLENE PIPE CONDUIT	M	30
63	208798	200 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	M	15
64	260201	CLASS 2 AGGREGATE BASE	M3	6
65	260301	CLASS 3 AGGREGATE BASE	M3	4360
66	017094	PERMEABLE MATERIAL (AUSTIN VAULT)	M3	85
67	280000	LEAN CONCRETE BASE	M3	2300
68	390133	HOT MIX ASPHALT (TYPE B)	TONN	5660
69	393003	GEOSYNTHETIC PAVEMENT INTERLAYER	M2	570
70	394060	DATA CORE	LS	LUMP SUM
71	394073	PLACE HOT MIX ASPHALT DIKE (TYPE A)	M	220
72	394076	PLACE HOT MIX ASPHALT DIKE (TYPE E)	M	30
73	394077	PLACE HOT MIX ASPHALT DIKE (TYPE F)	M	230
74	397005	TACK COAT	TONN	11
75	401066	CONCRETE PAVEMENT (RAMP TERMINI)	M3	270
76	490753	FURNISH PILING (CLASS 625)	M	609
77	490754	DRIVE PILE (CLASS 625)	EA	40
78 (F)	510051	STRUCTURAL CONCRETE, BRIDGE FOOTING	M3	60
79 (F)	510053	STRUCTURAL CONCRETE, BRIDGE	M3	111
80 (F)	510060	STRUCTURAL CONCRETE, RETAINING WALL	M3	99

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
81 (F)	017095	STRUCTURE CONCRETE (AUSTIN VAULT)	M3	251.4
82 (F)	017096	CLASS 2 CONCRETE (RETAINING WALL)	M3	850
83 (F)	017097	CLASS 1 CONCRETE (BOX CULVERT)	M3	6.8
84 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	M3	41.6
85 (F)	511064	FRACTURED RIB TEXTURE	M2	64
86	511106	DRILL AND BOND DOWEL	M	18
87	511110	DRILL AND BOND DOWEL (CHEMICAL ADHESIVE)	EA	109
88	042121	PRECAST REINFORCED BOX CULVERT (2.44 X 3.0)	M	6.5
89	042122	JOINT SEAL (MR 13 MM)	M	10
90	042123	JOINT SEAL (MR 25 MM)	M	5
91 (F)	520101	BAR REINFORCING STEEL	KG	27 844
92 (F)	520102	BAR REINFORCING STEEL (BRIDGE)	KG	18 100
93 (F)	520103	BAR REINFORCING STEEL (RETAINING WALL)	KG	92 500
94 (F)	520107	BAR REINFORCING STEEL (BOX CULVERT)	KG	695.8
95 (F)	550203	FURNISH STRUCTURAL STEEL (BRIDGE)	KG	28 900
96 (F)	550204	ERECT STRUCTURAL STEEL (BRIDGE)	KG	28 900
97 (F)	560213	FURNISH SIGN STRUCTURE (LIGHTWEIGHT)	KG	3880
98 (F)	560214	INSTALL SIGN STRUCTURE (LIGHTWEIGHT)	KG	3880
99 (F)	560218	FURNISH SIGN STRUCTURE (TRUSS)	KG	10 350
100 (F)	560219	INSTALL SIGN STRUCTURE (TRUSS)	KG	10 350

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
101	560233	FURNISH FORMED PANEL SIGN (OVERHEAD)	M2	16
102	560238	FURNISH SINGLE SHEET ALUMINUM SIGN (1.6 MM-UNFRAMED)	M2	36
103	560239	FURNISH SINGLE SHEET ALUMINUM SIGN (2.0 MM-UNFRAMED)	M2	13
104	560242	FURNISH SINGLE SHEET ALUMINUM SIGN (2.0 MM-FRAMED)	M2	5
105	017098	914 MM CAST-IN-DRILLED-HOLE CONCRETE PIPE (SIGN FOUNDATION)	M	8
106	561015	1524 MM CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	M	8
107 (F)	562002	METAL (BARRIER MOUNTED SIGN)	KG	110
108	566011	ROADSIDE SIGN - ONE POST	EA	34
109	566012	ROADSIDE SIGN - TWO POST	EA	2
110	568001	INSTALL SIGN (STRAP AND SADDLE BRACKET METHOD)	EA	2
111	590115	CLEAN AND PAINT STRUCTURAL STEEL	LS	LUMP SUM
112	641132	300 MM PLASTIC PIPE	M	14
113	650069	450 MM REINFORCED CONCRETE PIPE	M	47
114	650075	600 MM REINFORCED CONCRETE PIPE	M	440
115	664019	600 MM CORRUGATED STEEL PIPE (1.63 MM THICK)	M	14
116	017099	EMERGENCY DRAIN VALVE	EA	1
117	017100	150 MM PERFORATED PLASTIC PIPE UNDERDRAIN (AUSTIN VALVE)	M	110
118	017101	150 MM NON-PERFORATED PLASTIC PIPE UNDERDRAIN (AUSTIN VALVE)	M	23
119	681990	FILTER FABRIC	M2	240
120	703288	1200 MM CORRUGATED STEEL PIPE RISER (2.77 MM THICK)	M	2

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
121	707244	900 MM PRECAST CONCRETE PIPE MANHOLE	M	2
122	721009	ROCK SLOPE PROTECTION (FACING, METHOD B)	M3	3
123	722020	GABION	M3	14
124	727906	MINOR CONCRETE (GUTTER LINING)	M3	6
125	729010	ROCK SLOPE PROTECTION FABRIC	M2	10
126	731502	MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION)	M3	190
127	731530	MINOR CONCRETE (TEXTURED PAVING)	M2	1160
128 (F)	750001	MISCELLANEOUS IRON AND STEEL	KG	2716
129 (F)	017102	MISCELLANEOUS METAL (AUSTIN VALVE)	KG	50
130 (F)	017103	MISCELLANEOUS METAL (WATER QUALITY OUTLET RISER)	KG	169
131	800391	CHAIN LINK FENCE (TYPE CL-1.8)	M	230
132	802589	1.5 M CHAIN LINK GATE (TYPE CL-1.8)	EA	2
133	820107	DELINEATOR (CLASS 1)	EA	21
134	832003	METAL BEAM GUARD RAILING (WOOD POST)	M	330
135	833032	CHAIN LINK RAILING (TYPE 7)	M	66
136	833080	CONCRETE BARRIER (TYPE K)	M	18
137	839521	CABLE RAILING	M	73
138	839541	TRANSITION RAILING (TYPE WB)	EA	2
139	839568	TERMINAL ANCHOR ASSEMBLY (TYPE SFT)	EA	1
140	839569	TERMINAL ANCHOR ASSEMBLY (TYPE CA)	EA	1

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
141	839585	ALTERNATIVE FLARED TERMINAL SYSTEM	EA	2
142	839703	CONCRETE BARRIER (TYPE 60C)	M	30
143 (F)	839726	CONCRETE BARRIER (TYPE 736A)	M	319
144 (F)	839727	CONCRETE BARRIER (TYPE 736 MODIFIED)	M	55
145	840515	THERMOPLASTIC PAVEMENT MARKING	M2	200
146	840561	100 MM THERMOPLASTIC TRAFFIC STRIPE	M	2160
147	840563	200 MM THERMOPLASTIC TRAFFIC STRIPE	M	1110
148	840564	200 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 3.66 M - 0.92 M)	M	120
149	840570	100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 10.98 M - 3.66 M)	M	1000
150	840571	100 MM THERMOPLASTIC TRAFFIC STRIPE (BROKEN 5.18 M - 2.14 M)	M	690
151	850101	PAVEMENT MARKER (NON-REFLECTIVE)	EA	770
152	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	750
153	860090	MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION	LS	LUMP SUM
154	860201	SIGNAL AND LIGHTING	LS	LUMP SUM
155	860400	LIGHTING (TEMPORARY)	LS	LUMP SUM
156	017104	MODIFY LIGHTING (PEDESTRIAN UNDERCROSSING)	LS	LUMP SUM
157 (F)	860792	COMMUNICATION CONDUIT (BRIDGE)	M	66
158	017105	MODIFY COMMUNICATION SYSTEM	LS	LUMP SUM
159 (F)	860796	SPRINKLER CONTROL CONDUIT (BRIDGE)	M	33
160	861088	MODIFY RAMP METERING SYSTEM	LS	LUMP SUM

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
161	861501	MODIFY SIGNAL AND LIGHTING	LS	LUMP SUM
162	861504	MODIFY LIGHTING AND SIGN ILLUMINATION	LS	LUMP SUM
163	999990	MOBILIZATION	LS	LUMP SUM

# SPECIAL PROVISIONS

## SECTION 1 (BLANK)

## SECTION 2 BIDDING

### 2-1.01 SMALL BUSINESS AND NON–SMALL BUSINESS SUBCONTRACTOR PREFERENCES

#### General

The Department applies Small Business Preference or Non–Small Business Preference under Govt Code § 14835 et seq. and 2 CA Code of Regs § 1896 et seq.

Contractors, subcontractors, suppliers, and service providers who qualify as small businesses are encouraged to apply for certification as a small business by submitting their application to the Department of General Services, Office of Small Business and DVBE Services.

Contract award is based on the total bid, not the reduced bid.

#### Small Business Preference

The Department allows a bidder certified as a small business by the Office of Small Business and DVBE Services, Department of General Services, a preference if:

1. The bidder submitted a completed Request for Small Business Preference or Non–Small Business Preference form with its bid
2. The low bidder did not request the preference or is not certified as a small business

The bidder's signature on the Request for Small Business Preference or Non–Small Business Preference form certifies that the bidder is certified as a small business at the time and day of bid or has submitted a complete application to the Department of General Services. The complete application and any required substantiating documentation must be received by the Department of General Services by 5:00 p.m. on bid opening date.

The Department of General Services determines if a bidder was certified on bid opening date. The Department confirms the bidder's status as a small business before applying the small business preference.

The small business preference is a reduction for bid comparison in the total bid submitted by the small business contractor by the lesser of:

1. 5 percent of the verified total bid of the low bidder
2. \$50,000

If after the application of the small business preference the Department determines that a certified small business bidder is the low bidder, the Department does not consider a request for non–small business preference.

#### Non–Small Business Subcontractor Preference

The Department allows a bidder not certified as a small business by the Office of Small Business and DVBE Services, Department of General Services, a preference if:

1. The bidder submitted a completed Request for Small Business Preference or Non–Small Business Preference form with its bid.
2. The Certified Small Business Listing for the Non–Small Business Preference form shows that you are subcontracting at least 25 percent to certified small businesses. You may submit this information with your bid. If you do not, submit it so that it is received at the Office Engineer no later than 4:00 p.m. on the 2nd business day after bid opening.

Each listed subcontractor and supplier must be certified as a small business at the time and day of bid or must have submitted a complete application to the Department of General Services. The complete application and any required substantiating documentation must be received by the Department of General Services by 5:00 p.m. on bid opening date.

The non–small business subcontractor preference is a reduction for bid comparison in the total bid submitted by the non–small business contractor requesting the preference by the lesser of:

1. 5 percent of the verified total bid of the low bidder
2. \$50,000

## **2-1.02 DISABLED VETERAN BUSINESS ENTERPRISES**

### **General**

Take necessary and reasonable steps to ensure that DVBEs have opportunity to participate in the contract.

Comply with Mil & Vet Code § 999 et seq.

The Department encourages bidders to obtain DVBE participation in order to ensure the Department achieves its State-mandated overall DVBE goal.

If you obtain DVBE participation:

1. Complete and submit the Certified DVBE Summary form. List all DVBE participation on this form.
2. List each 1st tier DVBE subcontractor in the Subcontractor List form regardless of percentage of the total bid.

### **DVBE Incentive**

The Department grants a DVBE incentive to each bidder who achieves a DVBE participation of 1 percent or greater (Mil & Vet Code 999.5 and Code of Regs § 1896.98 et seq).

To receive this incentive, submit the Certified DVBE Summary form. If you do not submit this form with your bid and you are the low bidder or the 2nd or 3rd low bidder, submit it so that it is received at the Office Engineer no later than 4:00 p.m. on the 4th business day after bid opening. If a DVBE joint venture is used, submit the joint venture agreement with the Certified DVBE Summary form. Other bidders may be required to submit this form if bid ranking changes.

### **Incentive Evaluation**

The Department applies the Small Business and Non-Small Business preference during bid verification and proceeds with the following evaluation for DVBE incentive.

The DVBE incentive is a reduction, for bid comparison only, in the total bid submitted by the lesser of:

1. Percentage of DVBE achievement, rounded to 2 decimal places, of the verified total bid of the low bidder
2. 5 percent of the verified total bid of the low bidder
3. \$250,000

The Department applies DVBE incentive and determines if bid ranking changes.

A non-small business bidder cannot displace a small business bidder. However, a small business bidder with higher DVBE achievement can displace another small business bidder.

The Department proceeds with awarding the contract to the new low bidder and posts the new verified bid results at its Office Engineer Web site.

## **2-1.03 CALIFORNIA COMPANIES**

Under Pub Cont Code § 6107, the Department gives preference to a "California company," as defined, for bid comparison purposes over a nonresident contractor from any state that gives or requires a preference to be given to contractors from that state on its public entity construction contracts.

Complete a California Company Preference form.

The California company reciprocal preference amount is equal to the preference amount applied by the state of the nonresident contractor with the lowest responsive bid unless the California company is eligible for a small business preference or a non-small business subcontractor preference; in which case the preference amount is the greater of the two, but not both.

If the low bidder is not a California company and a California company's bid with reciprocal preference is equal to or less than the lowest bid, the Department awards the contract to the California company on the basis of its total bid.

## **2-1.04 TIE BID RESOLUTION**

If a small business bidder and a non-small business bidder request preferences and the reductions result in a tied bid, the Department awards the contract to the small business bidder.

If a DVBE small business bidder and a non-DVBE small business bidder request preferences and the reduction results in a tied bid, the Department awards the contract to the DVBE small business bidder.

After bid verification, if there is a tie between 2 or more bidders, the Department breaks the tie by tossing a coin.

## **2-1.05 OPT OUT OF PAYMENT ADJUSTMENTS FOR PRICE INDEX FLUCTUATIONS**

You may opt out of the payment adjustments for price index fluctuations as specified in "Payment Adjustments for Price Index Fluctuations" of these special provisions. If you elect to opt out of the provisions of this specification, you must complete the "Opt Out of Payment Adjustments for Price Index Fluctuations" form. The completed form must be submitted with your bid.

## **SECTION 3 CONTRACT AWARD AND EXECUTION**

### **3-1.01 CONTRACT AWARD**

If the Department awards the Contract, the award is made to the lowest responsible bidder within 60 days.

### **3-1.02 SMALL BUSINESS PARTICIPATION REPORT**

The Department has established an overall 25 percent small business participation goal. To determine if the goal is achieved, the Department is tracking small business participation on all contracts.

Complete and sign the Small Business (SB) Participation Report form included in the contract documents even if no small business participation is reported. Submit it with the executed contract.

## **SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION, AND LIQUIDATED DAMAGES**

The 1st working day is the 15th day after contract approval.

Do not start work at the job site, except for measuring controlling field dimensions and locating utilities, until the Engineer approves your submittal for:

1. Baseline Progress Schedule (Critical Path Method)
2. Storm Water Pollution Prevention Plan (SWPPP)
3. Notification of Dispute Review Board (DRB) nominee and disclosure statement

In addition to the above submittals, do not start work at the job site, except for measuring controlling field dimensions and locating utilities, until you submit:

1. Notice of Materials To Be Used.
2. Contingency plan for reopening closures to public traffic.
3. Written statement from the vendor that the order for the sign panels has been received and accepted by the vendor. The statement must show the dates that the materials will be shipped.
4. Written statement from the vendor that the order for electrical material has been received and accepted by the vendor. The statement must show the dates that the materials will be shipped.
5. Written statement from the vendor that the order for structural steel has been received and accepted by the vendor. The statement must show the dates that the materials will be shipped.

You may start work at the job site before the 15th day after contract approval if:

1. You obtain required approval for each submittal before the 15th day
2. The Engineer authorizes it in writing

The Department grants a time extension if a delay is beyond your control and prevents you from starting work at the job site on the 1st working day.

Complete the work, except plant establishment work, within 240 working days.

Liquidated damages are \$5,400 per day starting on the 1st day after exceeding 240 working days.

Complete the work, including plant establishment work, within 490 working days.

The Department reduces liquidated damages to \$950 per day if all the work, except plant establishment work, is complete and 490 working days have expired.

The Department does not simultaneously assess damages for untimely completion of work and plant establishment work.

## **SECTION 5 GENERAL**

### **5-1.01 EMISSIONS REDUCTION**

Contract execution constitutes submittal of the following certification:

I am aware of the emissions reduction regulations being mandated by the California Air Resources Board. I will comply with such regulations before commencing the performance of the work and maintain compliance throughout the duration of this contract.

### **5-1.02 NON-SMALL BUSINESSES**

Use each subcontractor as shown on the Certified Small Business Listing for the Non-Small Business Preference form unless you receive authorization for a substitution.

The requirement that small businesses be certified by the bid opening date does not apply to small business substitutions after contract award.

Maintain records of subcontracts made with certified small business subcontractors and records of materials purchased from certified small business suppliers. Include in the records:

1. Name and business address of each business
2. Total amount paid to each business

For the purpose of determining compliance with 2 CA Code of Regs § 1896 et seq.:

1. Provide the Department relevant information requested.
2. Upon reasonable notice and during normal business hours, permit access to its premises for the purpose of:
  - 2.1. Interviewing employees
  - 2.2. Inspecting and copying books, records, accounts and other material that may be relevant to a matter under investigation

### **5-1.03 DISABLED VETERAN BUSINESS ENTERPRISES**

Use each DVBE as shown on the Certified DVBE Summary form unless you receive authorization for a substitution.

The requirement that DVBEs be certified by the bid opening date does not apply to DVBE substitutions after contract award.

Maintain records of subcontracts made with certified DVBEs. Include in the records:

1. Name and business address of each business
2. Total amount paid to each business

For the purpose of determining compliance with Pub Cont Code § 10115 et seq.:

1. Upon contract completion, complete and submit Final Report - Utilization of Disabled Veteran Business Enterprises (DVBE) State Funded Projects Only form
2. Upon reasonable notice and during normal business hours, permit access to its premises for the purpose of:
  - 2.1. Interviewing employees
  - 2.2. Inspecting and copying books, records, accounts and other material that may be relevant to a matter under investigation

### **5-1.04 PAYMENT ADJUSTMENTS FOR PRICE INDEX FLUCTUATIONS**

#### **GENERAL**

#### **Summary**

This section applies to asphalt contained in materials for pavement structural sections and pavement surface treatments such as hot mix asphalt (HMA), tack coat, asphaltic emulsions, bituminous seals, asphalt binders, and modified asphalt binders placed in the work. This section does not apply if you opted out of payment adjustment for price index fluctuations at the time of bid.

The Engineer adjusts payment if the California Statewide Crude Oil Price Index for the month the material is placed is more than 5 percent higher or lower than the price index at the time of bid.

The California Statewide Crude Oil Price Index is determined each month on or about the 1st business day of the month by the Department using the average of the posted prices in effect for the previous month as posted by Chevron, ExxonMobil, and ConocoPhillips for the Buena Vista, Huntington Beach, and Midway Sunset fields.

If a company discontinues posting its prices for a field, the Department determines the index from the remaining posted prices. The Department may include additional fields to determine the index.

For the California Statewide Crude Oil Price Index, go to:

<http://www.dot.ca.gov/hq/construc/crudeoilindex/>

If the adjustment is a decrease in payment, the Department deducts the amount from the monthly progress payment.

The Department includes payment adjustments for price index fluctuations when making adjustments under Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications.

If you do not complete the work within the contract time, payment adjustments during the overrun period are determined using the California Statewide Crude Oil Price Index in effect for the month in which the overrun period began.

If the price index at the time of placement increases:

1. 50 percent or more over the price index at bid opening, notify the Engineer.
2. 100 percent or more over the price index at bid opening, do not furnish material containing asphalt until the Engineer authorizes you to proceed with that work. The Department may decrease Bid item quantities, eliminate Bid items, or terminate the contract.

### **Submittals**

Before placing material containing asphalt, submit the current sales and use tax rate in effect in the tax jurisdiction where the material is to be placed.

Submit certified weight slips for HMA, tack coat, asphaltic emulsions, and modified asphalt binders, including those materials not paid for by weight, as specified in Section 9-1.01, "Measurement of Quantities," of the Standard Specifications. For slurry seals, submit certified weight slips separately for the asphaltic emulsion.

## **ASPHALT QUANTITIES**

### **General**

Interpret the term "ton" as "tonne" for projects using metric units.

### **Hot Mix Asphalt**

The Engineer calculates the quantity of asphalt in HMA using the following formula:

$$Q_h = \text{HMATT} \times [X_a / (100 + X_a)]$$

where:

$Q_h$  = quantity in tons of asphalt used in HMA  
 $\text{HMATT}$  = HMA total tons placed  
 $X_a$  = theoretical asphalt content from job mix formula expressed as percentage of the weight of dry aggregate

### **Rubberized Hot Mix Asphalt**

The Engineer calculates the quantity of asphalt in rubberized HMA (RHMA) using the following formula:

$$Q_{rh} = \text{RHMATT} \times 0.80 \times [X_{arb} / (100 + X_{arb})]$$

where:

$Q_{rh}$  = quantity in tons of asphalt in asphalt rubber binder used in RHMA  
 $\text{RHMATT}$  = RHMA total tons placed  
 $X_{arb}$  = theoretical asphalt rubber binder content from the job mix formula expressed as percentage of the weight of dry aggregate

### **Modified Asphalt Binder in Hot Mix Asphalt**

The Engineer calculates the quantity of asphalt in modified asphalt binder using the following formula:

$$Q_{mh} = \text{MHMATT} \times [(100 - X_{am}) / 100] \times [X_{mab} / (100 + X_{mab})]$$

where:

$Q_{mh}$  = quantity in tons of asphalt in modified asphalt binder used in HMA  
 $M_{HMATT}$  = modified asphalt binder HMA total tons placed  
 $X_{am}$  = specified percentage of asphalt modifier  
 $X_{mab}$  = theoretical modified asphalt binder content from the job mix formula expressed as percentage of the weight of dry aggregate

### Hot Mix Asphalt Containing Reclaimed Asphalt Pavement (RAP)

The Engineer calculates the quantity of asphalt in HMA containing RAP using the following formulas:

$$Q_{rap} = M_{HMATT} \times [X_{aa} / (100 + X_{aa})]$$

where:

$$X_{aa} = X_{ta} - [(100 - X_{new}) \times (X_{ra} / 100)]$$

and

$Q_{rap}$  = quantity in tons of asphalt used in HMA containing RAP  
 $M_{HMATT}$  = HMA total tons placed  
 $X_{aa}$  = asphalt content of HMA adjusted to account for the asphalt content in RAP expressed as percentage of the weight of dry aggregate  
 $X_{ta}$  = total asphalt content of HMA expressed as percentage of the weight of dry aggregate  
 $X_{new}$  = theoretical percentage of new aggregate in the HMA containing RAP determined from RAP percentage in the job mix formula  
 $X_{ra}$  = asphalt content of RAP expressed as percentage

### Tack Coat

The Engineer calculates the quantity of asphalt in tack coat ( $Q_{tc}$ ) as either:

1. Asphalt binder using the asphalt binder total tons placed as tack coat
2. Asphaltic emulsion by applying the formula in "Asphaltic Emulsion" to the asphaltic emulsion total tons placed as tack coat

### Asphaltic Emulsion

The Engineer calculates the quantity of asphalt in asphaltic emulsions, including fog seals and tack coat, using the following formula:

$$Q_e = A_{ETT} \times X_e$$

where:

$Q_e$  = quantity in tons of asphalt used in asphaltic emulsions  
 $A_{ETT}$  = undiluted asphaltic emulsions total tons placed  
 $X_e$  = minimum percent residue specified in Section 94, "Asphaltic Emulsions," of the Standard Specifications based on the type of emulsion used

You may, as an option, determine " $X_e$ " by submitting actual daily test results for asphalt residue for the asphaltic emulsion used. If you choose this option, you must:

1. Take 1 sample every 200 tons but not less than 1 sample per day in the presence of the Engineer from the delivery truck, at midload from a sampling tap or thief, and in the following order:
  - 1.1. Draw and discard the 1st gallon
  - 1.2. Take two separate 1/2-gallon samples
2. Submit 1st sample at the time of sampling
3. Provide 2nd sample within 3 business days of sampling to an independent testing laboratory that participates in the AASHTO Proficiency Sample Program
4. Submit test results from independent testing laboratory within 10 business days of sample date

### **Slurry Seal**

The Engineer calculates the quantity of asphalt in slurry seals (Qss) by applying the formula in "Asphaltic Emulsion" to the actual quantity of asphaltic emulsion used in producing the slurry seal mix.

### **Modified Asphalt Binder**

The Engineer calculates the quantity of asphalt in modified asphalt binder using the following formula:

$$Q_{mab} = MABTT \times [(100 - X_{am}) / 100]$$

where:

$$\begin{aligned} Q_{mab} &= \text{quantity in tons of asphalt used in modified asphalt binder} \\ MABTT &= \text{modified asphalt binder total tons placed} \\ X_{am} &= \text{specified percentage of asphalt modifier} \end{aligned}$$

### **Other Materials**

For other materials containing asphalt not covered above, the Engineer determines the quantity of asphalt (Qo).

### **PAYMENT ADJUSTMENTS**

The Engineer includes payment adjustments for price index fluctuations in progress pay estimates. If material containing asphalt is placed within 2 months during 1 estimate period, the Engineer calculates 2 separate adjustments. Each adjustment is calculated using the price index for the month in which the quantity of material containing asphalt subject to adjustment is placed in the work. The sum of the 2 adjustments is used for increasing or decreasing payment in the progress pay estimate.

The Engineer calculates each payment adjustment as follows:

$$PA = Q_t \times A$$

where:

PA = Payment adjustment in dollars for asphalt contained in materials placed in the work for a given month.

Q<sub>t</sub> = Sum of all quantities of asphalt-contained materials in pavement structural sections and pavement surface treatments placed (Q<sub>h</sub> + Q<sub>rh</sub> + Q<sub>mh</sub> + Q<sub>rap</sub> + Q<sub>tc</sub> + Q<sub>e</sub> + Q<sub>ss</sub> + Q<sub>mab</sub> + Q<sub>o</sub>).

A = Adjustment in dollars per ton of asphalt used to produce materials placed in the work rounded to the nearest \$0.01.

For US Customary projects, use:

$$\begin{aligned} A &= [(I_u / I_b) - 1.05] \times I_b \times [1 + (T / 100)] \text{ for an increase in the crude oil price index exceeding 5 percent} \\ A &= [(I_u / I_b) - 0.95] \times I_b \times [1 + (T / 100)] \text{ for a decrease in the crude oil price index exceeding 5 percent} \end{aligned}$$

For metric projects, use:

$$\begin{aligned} A &= 1.1023 \times [(I_u / I_b) - 1.05] \times I_b \times [1 + (T / 100)] \text{ for an increase in the crude oil price index exceeding 5 percent} \\ A &= 1.1023 \times [(I_u / I_b) - 0.95] \times I_b \times [1 + (T / 100)] \text{ for a decrease in the crude oil price index exceeding 5 percent} \end{aligned}$$

I<sub>u</sub> = California Statewide Crude Oil Price Index for the month in which the quantity of asphalt subject to adjustment was placed in the work.

I<sub>b</sub> = California Statewide Crude Oil Price Index for the month in which the bid opening for the project occurred

T = Sales and use tax rate, expressed as a percent, currently in effect in the tax jurisdiction where the material is placed.

If the tax rate information is not submitted timely, the statewide sales and use tax rate is used in the payment adjustment calculations until the tax rate information is submitted.

### **5-1.05 SURFACE MINING AND RECLAMATION ACT**

Imported borrow or aggregate material must come from a surface mine permitted under the Surface Mining and Reclamation Act of 1975 (SMARA), Pub Res Code § 2710, et seq., or from an exempt site.

The Department of Conservation, Office of Mine Reclamation maintains a list of permitted mine sites. For the list of permitted sites, go to:

If you import borrow or aggregate material from a surface mine not on this list, submit proof the mine is exempt from SMARA.

#### 5-1.06 ELECTRONIC SUBMISSION OF PAYROLL RECORDS

In lieu of submitting weekly payroll records to the Engineer as specified in Section 7-1.01A(3), "Payroll Records," of the Standard Specifications, you may submit weekly payroll records electronically.

Before submitting payroll records electronically, you must complete and sign the Contractor's Acknowledgement and submit it to the District where your project is located. Submit your signed acknowledgement to the corresponding District electronic mailbox shown in the following table:

District	Address
1	district1.payrolls@dot.ca.gov
2	district2.payrolls@dot.ca.gov
3	district3.payrolls@dot.ca.gov
4	district4.payrolls@dot.ca.gov
5	district5.payrolls@dot.ca.gov
6	district6.payrolls@dot.ca.gov
7	district7.payrolls@dot.ca.gov
8	district8.payrolls@dot.ca.gov
9	district9.payrolls@dot.ca.gov
10	district10.payrolls@dot.ca.gov
11	district11.payrolls@dot.ca.gov
12	district12.payrolls@dot.ca.gov

The Department responds with an e-mail containing a Caltrans Internet Certificate to be used for the electronic submission of payroll records. You must agree to accept this certificate and reply to the e-mail. After you accept the certificate and reply to the e-mail, the Department is ready to accept your electronic submissions.

Each electronic submission must:

1. Include payroll records in a nonmodifiable PDF image format. No spreadsheets, word documents, or password protected documents are accepted.
2. Include payroll records with all data elements required by the Labor Code § 1776.
3. Include a signed Statement of Compliance form with each weekly record.
4. Be received by the Department by close of business on the 15th day of the month for the prior month's work.
5. Be encrypted before submission.
6. Contain the following information in the subject line:
  - 6.1. Contract number
  - 6.2. Week ending date as W/E mm/dd/yy
7. Contain 1 contract number and week ending date per submission.

For additional information on electronic submission of payroll records, go to:

<http://www.dot.ca.gov/hq/construc/LaborCompliance/index.htm>

#### 5-1.07 FORCE ACCOUNT PAYMENT

Payment for extra work at force account will be determined by either non-subcontracted or subcontracted force account payment unless otherwise specified.

##### **Non-Subcontracted Force Account Payment**

When extra work to be paid for on a force account basis is performed by the Contractor, compensation will be determined in accordance with Section 9-1.03, "Force Account Payment," of the Standard Specifications and these special provisions.

The second, third and fourth paragraphs of Section 9-1.03A, "Work Performed by Contractor," of the Standard Specifications shall not apply.

Attention is directed to "Time-Related Overhead" of these special provisions.

To the total of the direct costs for work performed on a force account basis, computed as provided in Section 9-1.03A(1), "Labor," Section 9-1.03A(2), "Materials," and Section 9-1.03A(3), "Equipment Rental," of the Standard Specifications, there will be added the following markups:

Cost	Percent Markup
Labor	30
Materials	10
Equipment Rental	10

The above markups shall be applied to work performed on a force account basis, regardless of whether the work revises the current contract completion date.

The above markups, together with payments made for time-related overhead pursuant to "Time-Related Overhead" of these special provisions, shall constitute full compensation for all overhead costs for work performed on a force account basis. These overhead costs shall be deemed to include all items of expense not specifically designated as cost or equipment rental in conformance with the provisions in Section 9-1.03A(1), "Labor," Section 9-1.03A(2), "Materials," and Section 9-1.03A(3), "Equipment Rental," of the Standard Specifications. The total payment made as provided above and in the first paragraph of Section 9-1.03A, "Work Performed by Contractor," of the Standard Specifications shall be deemed to be the actual cost of the work performed on a force account basis, and shall constitute full compensation therefor.

Full compensation for overhead costs for work performed on a force account basis, and for which no adjustment is made to the quantity for time-related overhead conforming to the provisions in "Time-Related Overhead" of these special provisions, shall be considered as included in the markups specified above, and no additional compensation will be allowed therefor.

#### **Subcontracted Force Account Payment**

When extra work to be paid for on a force account basis is performed by a subcontractor approved in conformance with the provisions in Section 5-1.055, "Subcontracting," of the Standard Specifications, compensation will be determined in accordance with the provisions in Section 9-1.03, "Force Account Payment," of the Standard Specifications.

#### **5-1.08 AREAS FOR CONTRACTOR'S USE**

Attention is directed to the provisions in Section 7-1.19, "Rights in Land and Improvements," of the Standard Specifications and these special provisions.

The highway right of way shall be used only for purposes that are necessary to perform the required work. The Contractor shall not occupy the right of way, or allow others to occupy the right of way, for purposes which are not necessary to perform the required work.

No State-owned parcels adjacent to the right of way are available for the exclusive use of the Contractor within the contract limits. The Contractor shall secure, at the Contractor's own expense, areas required for plant sites, storage of equipment or materials, or for other purposes.

No area is available within the contract limits for the exclusive use of the Contractor. However, temporary storage of equipment and materials on State property may be arranged with the Engineer, subject to the prior demands of State maintenance forces and to other contract requirements. Use of the Contractor's work areas and other State-owned property shall be at the Contractor's own risk, and the State shall not be held liable for damage to or loss of materials or equipment located within such areas.

#### **5-1.09 PAYMENTS**

In determining the partial payments to be made to the Contractor, only the following listed materials will be considered for inclusion in the payment as materials furnished but not incorporated in the work:

- A. Lead Compliance Plan
- B. Progress Schedule (Critical Path Method)
- C. Control and Neutral Conductors
- D. Sprinklers and Valves
- E. Irrigation Controller Enclosure Cabinets
- F. Pipe (Irrigation System)
- G. Bar Reinforcing Steel
- H. Culvert Pipe and appurtenance

- I. Piling
- J Reinforced Concrete Pipe
- K. Corrugated Steel Pipe
- L. Underdrain Plastic Pipe
- M Filter Fabric
- N. Miscellaneous Iron and Steel
- O. Metal Sign Structures
- P. Frame and grate
- Q. Structural Steel
- R. Metal beam guard railing and terminal system
- S. Cable railing
- T. Pavement markers
- U. Signal and Lighting Standards
- V. Luminaires
- W. Signal Heads and Mounting Brackets
- X. Twisted Pair Cables
- Y. Lighting Fixtures

**5-1.10 SUPPLEMENTAL PROJECT INFORMATION**

The Department makes the following supplemental project information available:

**Supplemental Project Information**

Means	Description
Included in the Information Handout	<ul style="list-style-type: none"> <li>• Portion of Site Investigation Private Property – 1619 Cosmic Way, APN 5627-008-013, Parcel No. 77407-, I-5 Western Avenue Interchange, Task Order No. 14, EA 1786A1, prepared by Ninyo &amp; Moore dated February 25, 2009;</li> <li>• Portion of Site Investigation – 1620 Flower Street, I-5 at Western Avenue, Task Order No. 12, EA 1786A1, prepared by Ninyo &amp; Moore dated April 16, 2009;</li> <li>• Portion of Site Investigation – 1648-1650 Flower and 640 Western Avenue, I-5 at Western Avenue, Task Order No. 12, EA 1786A1, prepared by Ninyo &amp; Moor dated April 16, 2009;</li> <li>• Portion of Lead Site Investigation Report, Interstate 5 Western Avenue Interchange, Los Angeles, California, Task Order 07-1786A1, Statewide Contract 43A0078, Prepared by Ninyo &amp; Moore, January 20, 2003</li> <li>• Revised Getechnical Investigation Western Avenue Undercrossing (53-1079S) Part 1 of 2 and Part 2 of 2</li> <li>• Response to Caltrans Review Comments</li> <li>• Update to the Western Avenue Undercrossing (53-1079S) Geotechnical Investigation</li> <li>• Battery Backup system connection diagrams</li> </ul>
Available for inspection at the District Office	Complete lead site investigation report
Available as specified in the Standard Specifications	Bridge as-built drawings
Available at: <a href="http://www.dot.ca.gov/hq/esc/oe/weekly_ads/index.php">http://www.dot.ca.gov/hq/esc/oe/weekly_ads/index.php</a>	Cross sections

**5-1.11 SOUND CONTROL REQUIREMENTS**

Sound control shall conform to the provisions in Section 7-1.01I, "Sound Control Requirements," of the Standard Specifications and these special provisions.

The noise level from the Contractor's operations, between the hours of 9:00 p.m. and 7:00 a.m., shall not exceed 86 dBa at a distance of 15 m. This requirement shall not relieve the Contractor from responsibility for complying with local ordinances regulating noise level.

The noise level requirement shall apply to the equipment on the job or related to the job, including but not limited to trucks, transit mixers or transient equipment that may or may not be owned by the Contractor. The use of loud sound signals shall be avoided in favor of light warnings except those required by safety laws for the protection of personnel.

Full compensation for conforming to the requirements of this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

## **5-1.12 BIRD PROTECTION**

### **GENERAL**

This work includes protecting migratory and nongame birds, their occupied nests, and their eggs.

Nesting or attempted nesting by migratory and nongame birds is anticipated to occur but is not limited to February 15 through August 31.

### **QUALITY ASSURANCE**

#### **Regulatory requirements**

The Federal Migratory Bird Treaty Act (16 USC §703-711.), 50 CFR 10, and Fish & Game Code §3503, §3513, and §3800, protect migratory and nongame birds, their occupied nests, and their eggs.

The Federal Endangered Species Act of 1973 (16 USC §1531,§1543) and California Endangered Species Act (Fish & Game Code §2050-§2115.5) prohibit the take of listed species and protect occupied and unoccupied nests of threatened and endangered bird species.

The Bald Eagle Protection Act (16 USC §668) prohibits the destruction of bald and golden eagles occupied and unoccupied nests.

### **CONSTRUCTION**

When migratory or nongame bird nests are discovered which may be adversely affected by construction activity, or when a bird is found injured or killed as a result of construction activity, immediately stop work within 30.5 meters of the nest or bird and notify the Engineer. Work must not resume until the Engineer provides written notification that work may resume at that location.

When ordered by the Engineer, use exclusion devices, nesting prevention measures or remove and dispose of partially constructed and unoccupied nests of migratory or nongame birds on a regular basis to prevent their occupation.

Nest removal activities must not result in depositing into or allowing materials to enter waters of this state.

### **MEASUREMENT AND PAYMENT**

Exclusion devices, nesting prevention measures and nest removal that are ordered by the Engineer will be paid for as extra work as specified in Section 4-1.03D, "Extra Work," of the Standard Specifications.

A delay to the controlling operation due to migratory or nongame birds or their nests will be considered a temporary suspension of work under Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications. Adjustments will be made for delays that the Engineer determines are not due to the Contractor's failure to perform the provision of the contract in the same manner as for suspensions due to unsuitable weather in Section 8-1.05.

## **5-1.13 RELATIONS WITH CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD**

This project lies within the boundaries of the Los Angeles Regional Water Quality Control Board (RWQCB).

The State Water Resources Control Board (SWRCB) has issued to the Department a permit that governs storm water and non-storm water discharges from the Department's properties, facilities, and activities. The Department's permit is entitled "Order No. 99 - 06 - DWQ, NPDES No. CAS000003, National Pollutant Discharge Elimination System (NPDES) Permit, Statewide Storm Water Permit and Waste Discharge Requirements (WDRs) for the State of California, Department of Transportation (Caltrans)." Copies of the Department's permit are available for review from the SWRCB, Storm Water Permit Unit, 1001 "I" Street, P.O. Box 1977, Sacramento, California 95812-1977, Telephone: (916) 341-5254, and may also be obtained at:

[http://www.waterboards.ca.gov/water\\_issues/programs/stormwater/](http://www.waterboards.ca.gov/water_issues/programs/stormwater/)

The Department's permit references and incorporates by reference the current statewide general permit issued by the SWRCB entitled "Order No. 99-08-DWQ, National Pollutant Discharge Elimination System (NPDES) General Permit No. CAS000002, Waste Discharge Requirements (WDRs) for Discharges of Storm Water Runoff Associated with

Construction Activity" that regulates discharges of storm water and non-storm water from construction activities disturbing one acre or more of soil in a common plan of development. Sampling and analysis requirements as specified in SWRCB Resolution No. 2001-46 are added to the statewide general permit. Copies of the statewide permit and modifications thereto are available for review from the SWRCB, Storm Water Permit Unit, 1001 "I" Street, P.O. Box 1977, Sacramento, California 95812-1977, Telephone: (916) 341-5254 and may also be obtained at:

[http://www.waterboards.ca.gov/water\\_issues/programs/stormwater/](http://www.waterboards.ca.gov/water_issues/programs/stormwater/)

The NPDES permits that regulate this project, as referenced above, are collectively referred to in this section as the "permits."

This project shall conform to the permits and modifications thereto. The Contractor shall maintain copies of the permits at the project site and shall make them available during construction.

The Contractor shall know and comply with provisions of Federal, State, and local regulations and requirements that govern the Contractor's operations and storm water and non-storm water discharges from the project site and areas of disturbance outside the project limits during construction. Attention is directed to Sections 7-1.01, "Laws to be Observed," 7-1.11, "Preservation of Property," 7-1.12, "Indemnification and Insurance," and 9-1.055, "Penalty Withholds," of the Standard Specifications.

The Contractor shall notify the Engineer immediately upon request from the regulatory agencies to enter, inspect, sample, monitor, or otherwise access the project site or the Contractor's records pertaining to water pollution control work. The Contractor and the Department shall provide copies of correspondence, notices of violation, enforcement actions, or proposed fines by regulatory agencies to the requesting regulatory agency.

#### **5-1.14 AERIALY DEPOSITED LEAD**

Aerially deposited lead is present within the project limits. Aerially deposited lead is lead deposited within unpaved areas or formerly unpaved areas, primarily due to vehicle emissions.

Attention is directed to "Material Containing Aerially Deposited Lead" and "Supplemental Project Information" of these special provisions.

Portions of the site investigation report are included in the "Material Information" handout. The complete reports, entitled "(1) Site Investigation Private Property – 1619 Cosmic Way, APN 5627-008-013, Parcel No. 77407-, I-5 Western Avenue Interchange, Task Order No. 14, EA 1786A1, prepared by Ninyo & Moore dated February 25, 2009; (2) Site Investigation – 1620 Flower Street, I-5 at Western Avenue, Task Order No. 12, EA 1786A1, prepared by Ninyo & Moore dated April 16, 2009; (3) Site Investigation – 1648-1650 Flower and 640 Western Avenue, I-5 at Western Avenue, Task Order No. 12, EA 1786A1, prepared by Ninyo & Moor dated April 16, 2009; and (4) Lead Site Investigation Report, Interstate 5 Western Avenue Interchange, Los Angeles, California, Task Order 07-1786A1, Statewide Contract 43A0078, Prepared by Ninyo & Moore, January 20, 2003," are available for inspection at the Department of Transportation, Division of Construction, CCO Unit, Los Angeles, 100 S. Main Street, Los Angeles, California 90012.

The Department has received from the California Department of Toxic Substances Control (DTSC) a Variance regarding the use of material containing aerially deposited lead. This project is subject to the conditions of the Variance, as amended. The Variance is available for inspection at the Department of Transportation, District 7, 100 S. Main Street, Los Angeles, CA 90012.

Once the Contractor has completed the placement of material containing aerially deposited lead in conformance with these special provisions and as directed by the Engineer, the Contractor shall have no responsibility for such materials. The Department will not consider the Contractor a generator of such contaminated materials.

Excavation, reuse, and disposal of material with aerially deposited lead shall be in conformance with all rules and regulations including, but not limited to, those of the following agencies:

- A. United States Department of Transportation,
- B. United States Environmental Protection Agency,
- C. California Environmental Protection Agency,
- D. California Department of Health Services,
- E. Department of Toxic Substances Control,
- F. California Division of Occupational Safety and Health Administration,
- G. Integrated Waste Management Board,
- H. Regional Water Quality Control Board, Region 4, Los Angeles,
- I. State Air Resources Control Board, and
- J. South Coast Air Quality Management District.

Materials containing hazardous levels of lead shall be transported and disposed of in conformance with Federal and State laws and regulations, as amended, and county and municipal ordinances and regulations, as amended. Laws and regulations that govern this work include, but are not limited to:

- A. Health and Safety Code, Division 20, Chapter 6.5 (California Hazardous Waste Control Act),
- B. Title 22, California Code of Regulations, Division 4.5 (Environmental Health Standards for the Management of Hazardous Waste), and
- C. Title 8, California Code of Regulations.

**5-1.15 PRESERVATION OF PROPERTY**

Attention is directed to Section 7-1.11, "Preservation of Property," of the Standard Specifications and these special provisions.

Existing trees, shrubs and other plants, that are not to be removed as shown on the plans or specified in these special provisions, and are injured or damaged by reason of the Contractor's operations, shall be replaced by the Contractor. The minimum size of tree replacement shall be 600 mm box and the minimum size of shrub replacement shall be No. 15 container. Replacement ground cover plants shall be from flats and shall be planted 300 mm on center. Replacement of Carpobrotus ground cover plants shall be from cuttings and shall be planted 300 mm on center. Replacement planting shall conform to the requirements in Section 20-4.07, "Replacement," of the Standard Specifications. The Contractor shall water replacement plants in conformance with the provisions in Section 20-4.06, "Watering," of the Standard Specifications.

Damaged or injured plants shall be removed and disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13 of the Standard Specifications. At the option of the Contractor, removed trees and shrubs may be reduced to chips. The chipped material shall be spread within the highway right of way at locations designated by the Engineer.

Replacement planting of injured or damaged trees, shrubs, and other plants shall be completed prior to the start of the plant establishment period. Replacement planting shall conform to the provisions in Section 20-4.05, "Planting," of the Standard Specifications.

**5-1.16 NONHIGHWAY FACILITIES (INCLUDING UTILITIES)**

The utility owner will relocate a utility shown in the following table before the corresponding date shown:

<b>Utility Relocation and Date of the Relocation</b>		
Utility	Location	Date
Abandon 200 mm City of Glendale water line	WCL of Winchester	Prior to construction
Abandon 50 mm Southern California Gas line	On Winchester Ave 11' EW	Prior to construction
City of Glendale power poles	South of Flower Street	Prior to construction
ATT OH line	South of Flower Street	Prior to construction
Time Warner	South of Flower Street	Prior to construction

During the progress of the work under this Contract, the utility owner will relocate a utility shown in the following table within the corresponding number of days shown. Notify the Engineer before you work within the approximate location of a utility shown. The days start on the notification date.

<b>Utility Relocation and Department-Arranged Time for the Relocation</b>		
Utility	Location	Days
City of Glendale power poles No. 24851-A and 24852-A	South of Flower Street	10
Time Warner on Glendale power poles No. 24851-A and 24852-A	South of Flower Street	10

**5-1.17 DAMAGE REPAIR**

Attention is directed to Section 7-1.16, "Contractor's Responsibility for the Work and Materials," and Section 7-1.165, "Damage by Storm, Flood, Tsunami or Earthquake," of the Standard Specifications and these special provisions.

When as a result of freezing conditions (as defined herein) during the plant establishment period, plants have died or, in the opinion of the Engineer, have deteriorated to a point beyond which the plants will not mature as typical examples of their species, the Engineer may direct replacement of the affected plants. The total cost of ordered plant replacement work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. A freezing condition, for the purpose

of this specification, occurs when the temperature at or near the affected area has been officially recorded below 0°C and plants have been killed or damaged to the degree described above.

When, as a result of drought conditions (as defined herein) during the plant establishment period, plants have died or, in the opinion of the Engineer, have deteriorated to a point beyond which the plants will not mature as typical examples of their species, the Engineer may direct replacement of the affected plants. The total cost of ordered plant replacements, after water has been restricted or stopped, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. Restriction or shutoff of available water shall not relieve the Contractor from performing other contract work. A drought condition occurs when the Department, or its supplier, restricts or stops delivery of water to the Contractor to the degree that plants have died or deteriorated as described above.

When the provisions in Section 7-1.165, "Damage by Storm, Flood, Tsunami or Earthquake," of the Standard Specifications are applicable, the provisions above for payment of costs for repair of damage due to rain, freezing conditions and drought shall not apply.

#### **5-1.18 RELIEF FROM MAINTENANCE AND RESPONSIBILITY**

The Contractor may be relieved of the duty of maintenance and protection for those items not directly connected with plant establishment work in conformance with the provisions in Section 7-1.15, "Relief From Maintenance and Responsibility," of the Standard Specifications. Water pollution control, maintain existing planted areas, maintain existing irrigation facilities, transplant trees, and transplant palm trees shall not be relieved of maintenance.

#### **5-1.19 AIR QUALITY – BASIC NESHAP ASBESTOS NOTIFICATION**

In compliance with Standard Specifications Section 7-1.01F, the Contractor shall notify the air pollution control district or air quality management district identified below as required by the National Emission Standards for Hazardous Air Pollutants (NESHAP) at 40 CFR Part 61, Subpart M, and California Health and Safety Code section 39658(b)(1). A copy of the notification form and attachments shall be provided to the Engineer prior to submittal. Notification shall take place a minimum of 10 working days prior to starting demolition or renovation activities as defined in the NESHAP regulations.

The contractor shall mail or otherwise deliver the original notification form with any necessary attachments to:

South Coast Air Quality Management District  
21865 E. Copley Dr.  
Diamond Bar, CA 91765-4182

The contractor shall also notify other local permit agencies and utility companies prior to starting any demolition activities.

Full compensation for complying with requirements of this section shall be considered as included in the contract price paid for the items involved, and no additional compensation will be allowed therefor.

#### **SECTION 6. (BLANK)**

#### **SECTION 7. (BLANK)**

#### **SECTION 8. MATERIALS**

#### **SECTION 8-1. MISCELLANEOUS**

#### **8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS**

Only materials and products conforming to the requirements of the specifications shall be incorporated in the work. When metric materials and products are not available, and when approved by the Engineer, and at no cost to the State, materials and products in the United States Standard Measures which are of equal quality and of the required properties and characteristics for the purpose intended, may be substituted for the equivalent metric materials and products, subject to the following provisions:

- A. Materials and products shown on the plans or in the special provisions as being equivalent may be substituted for the metric materials and products specified or detailed on the plans.
- B. Before other non-metric materials and products will be considered for use, the Contractor shall furnish, at the Contractor's expense, evidence satisfactory to the Engineer that the materials and products proposed for use are equal to or better than the materials and products specified or detailed on the plans. The burden of proof as to the quality and suitability of substitutions shall be upon the Contractor and the Contractor shall furnish necessary

information as required by the Engineer. The Engineer will be the sole judge as to the quality and suitability of the substituted materials and products and the Engineer's decision will be final.

- C. When the Contractor elects to substitute non-metric materials and products, including materials and products shown on the plans or in the special provisions as being equivalent, the list of sources of material specified in Section 6-1.01, "Source of Supply and Quality of Materials," of the Standard Specification shall include a list of substitutions to be made and contract items involved. In addition, for a change in design or details, the Contractor shall submit plans and working drawings in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The plans and working drawings shall be submitted at least 7 days before the Contractor intends to begin the work involved.

Unless otherwise specified, the following substitutions of materials and products will be allowed:

SUBSTITUTION TABLE FOR PLAIN WIRE REINFORCEMENT  
ASTM Designation: A 82

METRIC SIZE SHOWN ON THE PLANS <sup>2</sup> mm	SIZE TO BE SUBSTITUTED <sup>2</sup> inch x 100
MW9	W1.4
MW10	W1.6
MW13	W2.0
MW15	W2.3
MW19	W2.9
MW20	W3.1
MW22	W3.5
MW25	W3.9, except W3.5 in piles only
MW26	W4.0
MW30	W4.7
MW32	W5.0
MW35	W5.4
MW40	W6.2
MW45	W6.5
MW50	W7.8
MW55	W8.5, except W8.0 in piles only
MW60	W9.3
MW70	W10.9, except W11.0 in piles only
MW80	W12.4
MW90	W14.0
MW100	W15.5

**SUBSTITUTION TABLE FOR BAR REINFORCEMENT**

METRIC BAR DESIGNATION NUMBER <sup>1</sup> SHOWN ON THE PLANS	BAR DESIGNATION NUMBER <sup>2</sup> TO BE SUBSTITUTED
10	3
13	4
16	5
19	6
22	7
25	8
29	9
32	10
36	11
43	14
57	18

<sup>1</sup>Bar designation numbers approximate the number of millimeters of the nominal diameter of the bars.

<sup>2</sup>Bar numbers are based on the number of eighths of an inch included in the nominal diameter of the bars.

No adjustment will be required in spacing or total number of reinforcing bars due to a difference in minimum yield strength between metric and non-metric bars.

**SUBSTITUTION TABLE FOR SIZES OF:**

(1) STEEL FASTENERS FOR GENERAL APPLICATIONS (ASTM Designation: A 307 or AASHTO Designation: M 314, Grade 36 or 55), and

(2) HIGH STRENGTH STEEL FASTENERS (ASTM Designation: A 325 or A 449)

METRIC SIZE SHOWN ON THE PLANS mm	SIZE TO BE SUBSTITUTED inch
6 or 6.35	1/4
8 or 7.94	5/16
10 or 9.52	3/8
11 or 11.11	7/16
13, 12.70, or M12	1/2
14 or 14.29	9/16
16, 15.88, or M16	5/8
19, 19.05, or M20	3/4
22, 22.22, or M22	7/8
24, 25, 25.40, or M24	1
29, 28.58, or M27	1-1/8
32, 31.75, or M30	1-1/4
35 or 34.93	1-3/8
38, 38.10, or M36	1-1/2
44 or 44.45	1-3/4
51 or 50.80	2
57 or 57.15	2-1/4
64 or 63.50	2-1/2
70 or 69.85	2-3/4
76 or 76.20	3
83 or 82.55	3-1/4
89 or 88.90	3-1/2
95 or 95.25	3-3/4
102 or 101.60	4

SUBSTITUTION TABLE FOR NOMINAL THICKNESS OF SHEET METAL

UNCOATED HOT AND COLD ROLLED SHEETS		HOT-DIPPED ZINC COATED SHEETS (GALVANIZED)	
METRIC THICKNESS SHOWN ON THE PLANS mm	GAGE TO BE SUBSTITUTED inch	METRIC THICKNESS SHOWN ON THE PLANS mm	GAGE TO BE SUBSTITUTED inch
7.94	0.3125	4.270	0.1681
6.07	0.2391	3.891	0.1532
5.69	0.2242	3.510	0.1382
5.31	0.2092	3.132	0.1233
4.94	0.1943	2.753	0.1084
4.55	0.1793	2.372	0.0934
4.18	0.1644	1.994	0.0785
3.80	0.1495	1.803	0.0710
3.42	0.1345	1.613	0.0635
3.04	0.1196	1.461	0.0575
2.66	0.1046	1.311	0.0516
2.28	0.0897	1.158	0.0456
1.90	0.0747	1.006 or 1.016	0.0396
1.71	0.0673	0.930	0.0366
1.52	0.0598	0.853	0.0336
1.37	0.0538	0.777	0.0306
1.21	0.0478	0.701	0.0276
1.06	0.0418	0.627	0.0247
0.91	0.0359	0.551	0.0217
0.84	0.0329	0.513	0.0202
0.76	0.0299	0.475	0.0187
0.68	0.0269	-----	-----
0.61	0.0239	-----	-----
0.53	0.0209	-----	-----
0.45	0.0179	-----	-----
0.42	0.0164	-----	-----
0.38	0.0149	-----	-----

**SUBSTITUTION TABLE FOR WIRE**

METRIC THICKNESS SHOWN ON THE PLANS mm	WIRE THICKNESS TO BE SUBSTITUTED inch	GAGE NO.
6.20	0.244	3
5.72	0.225	4
5.26	0.207	5
4.88	0.192	6
4.50	0.177	7
4.11	0.162	8
3.76	0.148	9
3.43	0.135	10
3.05	0.120	11
2.69	0.106	12
2.34	0.092	13
2.03	0.080	14
1.83	0.072	15
1.57	0.062	16
1.37	0.054	17
1.22	0.048	18
1.04	0.041	19
0.89	0.035	20

**SUBSTITUTION TABLE FOR PIPE PILES**

METRIC SIZE SHOWN ON THE PLANS mm x mm	SIZE TO BE SUBSTITUTED inch x inch
PP 360 x 4.55	NPS 14 x 0.179
PP 360 x 6.35	NPS 14 x 0.250
PP 360 x 9.53	NPS 14 x 0.375
PP 360 x 11.12	NPS 14 x 0.438
PP 406 x 12.70	NPS 16 x 0.500
PP 460 x T	NPS 18 x T"
PP 508 x T	NPS 20 x T"
PP 559 x T	NPS 22 x T"
PP 610 x T	NPS 24 x T"
PP 660 x T	NPS 26 x T"
PP 711 x T	NPS 28 x T"
PP 762 x T	NPS 30 x T"
PP 813 x T	NPS 32 x T"
PP 864 x T	NPS 34 x T"
PP 914 x T	NPS 36 x T"
PP 965 x T	NPS 38 x T"
PP 1016 x T	NPS 40 x T"
PP 1067 x T	NPS 42 x T"
PP 1118 x T	NPS 44 x T"
PP 1219 x T	NPS 48 x T"
PP 1524 x T	NPS 60 x T"

The thickness in millimeters (T) represents an exact conversion of the thickness in inches (T").

**SUBSTITUTION TABLE FOR CIDH CONCRETE PILING**

METRIC SIZE SHOWN ON THE PLANS	ACTUAL AUGER SIZE TO BE SUBSTITUTED inches
350 mm	14
400 mm	16
450 mm	18
600 mm	24
750 mm	30
900 mm	36
1.0 m	42
1.2 m	48
1.5 m	60
1.8 m	72
2.1 m	84
2.4 m	96
2.7 m	108
3.0 m	120
3.3 m	132
3.6 m	144
4.0 m	156

**SUBSTITUTION TABLE FOR STRUCTURAL TIMBER AND LUMBER**

METRIC MINIMUM DRESSED DRY, SHOWN ON THE PLANS mm x mm	METRIC MINIMUM DRESSED GREEN, SHOWN ON THE PLANS mm x mm	NOMINAL SIZE TO BE SUBSTITUTED inch x inch
19x89	20x90	1x4
38x89	40x90	2x4
64x89	65x90	3x4
89x89	90x90	4x4
140x140	143x143	6x6
140x184	143x190	6x8
184x184	190x190	8x8
235x235	241x241	10x10
286x286	292x292	12x12

SUBSTITUTION TABLE FOR NAILS AND SPIKES

METRIC COMMON NAIL, SHOWN ON THE PLANS	METRIC BOX NAIL, SHOWN ON THE PLANS	METRIC SPIKE, SHOWN ON THE PLANS	SIZE TO BE SUBSTITUTED Penny-weight
Length, mm Diameter, mm	Length, mm Diameter, mm	Length, mm Diameter, mm	
50.80 2.87	50.80 2.51	————	6d
63.50 3.33	63.50 2.87	————	8d
76.20 3.76	76.20 3.25	76.20 4.88	10d
82.55 3.76	82.55 3.25	82.55 4.88	12d
88.90 4.11	88.90 3.43	88.90 5.26	16d
101.60 4.88	101.60 3.76	101.60 5.72	20d
114.30 5.26	114.30 3.76	114.30 6.20	30d
127.00 5.72	127.00 4.11	127.00 6.68	40d
————	————	139.70 7.19	50d
————	————	152.40 7.19	60d

SUBSTITUTION TABLE FOR IRRIGATION  
COMPONENTS

METRIC WATER METERS, TRUCK LOADING STANDPIPES, VALVES, BACKFLOW PREVENTERS, FLOW SENSORS, WYE STRAINERS, FILTER ASSEMBLY UNITS, PIPE SUPPLY LINES, AND PIPE IRRIGATION SUPPLY LINES SHOWN ON THE PLANS DIAMETER NOMINAL (DN) mm	NOMINAL SIZE TO BE SUBSTITUTED inch
15	1/2
20	3/4
25	1
32	1-1/4
40	1-1/2
50	2
65	2-1/2
75	3
100	4
150	6
200	8
250	10
300	12
350	14
400	16

Unless otherwise specified, substitutions of United States Standard Measures standard structural shapes corresponding to the metric designations shown on the plans and in conformance with the requirements in ASTM Designation: A 6/A 6M, Annex 2, will be allowed.

**8-1.02 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS**

The Department maintains the following list of Prequalified and Tested Signing and Delineation Materials. The Engineer shall not be precluded from sampling and testing products on the list of Prequalified and Tested Signing and Delineation Materials.

The manufacturer of products on the list of Prequalified and Tested Signing and Delineation Materials shall furnish the Engineer a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each type of traffic product supplied.

For those categories of materials included on the list of Prequalified and Tested Signing and Delineation Materials, only those products shown within the listing may be used in the work. Other categories of products, not included on the list of Prequalified and Tested Signing and Delineation Materials, may be used in the work provided they conform to the requirements of the Standard Specifications.

Materials and products may be added to the list of Prequalified and Tested Signing and Delineation Materials if the manufacturer submits a New Product Information Form to the New Product Coordinator at the Transportation Laboratory. Upon a Departmental request for samples, sufficient samples shall be submitted to permit performance of required tests. Approval of materials or products will depend upon compliance with the specifications and tests the Department may elect to perform.

**PAVEMENT MARKERS, PERMANENT TYPE**

**Retroreflective With Abrasion Resistant Surface (ARS)**

1. Apex, Model 921AR (100 mm x 100 mm)
2. Ennis Paint, Models C88 (100 mm x 100 mm), 911 (100 mm x 100 mm) and C80FH

3. Ray-O-Lite, Model "AA" ARS (100 mm x 100 mm) and ARC Round Shoulder (100 mm x 100 mm)
4. 3M Series 290 (89 mm x 100 mm)
5. 3M Series 290 PSA
6. Glowlite, Inc Model 988AR (100 mm x 100 mm)

**Retroreflective With Abrasion Resistant Surface (ARS)**

(for recessed applications only)

1. Ennis Paint, Model 948 (58 mm x 119 mm)
  2. Ennis Paint, Model 944SB (51 mm x 100 mm)\*
  3. Ray-O-Lite, Model 2002 (51 mm x 117 mm)
  4. Ray-O-Lite, Model 2004 ARS (51 mm x 100 mm)\*
- \*For use only in 114 mm wide (older) recessed slots

**Non-Reflective, 100-mm Round**

1. Apex Universal (Ceramic)
2. Apex Universal, Models 929 (ABS) and 929PP (Polypropylene)
3. Glowlite, Inc. (Ceramic) and PP (Polypropylene)
4. Hi-Way Safety, Inc., Models P20-2000W and 2001Y (ABS)
5. Interstate Sales, "Diamond Back" (Polypropylene)
6. Novabrite Models Cdot (White) Cdot-y (Yellow), Ceramic
7. Novabrite Models Pdot-w (White) Pdot-y (Yellow), Polypropylene
8. Three D Traffic Works TD10000 (ABS), TD10500 (Polypropylene)

**PAVEMENT MARKERS, TEMPORARY TYPE**

**Temporary Markers For Long Term Day/Night Use (180 days or less)**

1. Vega Molded Products "Temporary Road Marker" (75 mm x 100 mm)

**Temporary Markers For Short Term Day/Night Use (14 days or less)**

(For seal coat or chip seal applications, clear protective covers are required)

1. Apex Universal, Model 932
2. Filtrona Extrusion, Models T.O.M., T.R.P.M., and "HH" (High Heat)
3. Hi-Way Safety, Inc., Model 1280/1281
4. Glowlite, Inc., Model 932

**STRIPING AND PAVEMENT MARKING MATERIAL**

**Permanent Traffic Striping and Pavement Marking Tape**

1. Advanced Traffic Marking, Series 300 and 400
2. Brite-Line, Series 1000
3. Brite-Line, "DeltaLine XRP"
4. Swarco Industries, "Director 35" (For transverse application only)
5. Swarco Industries, "Director 60"
6. 3M, "Stamark" Series 380 and 5730
7. 3M, "Stamark" Series 420 (For transverse application only)

**Temporary (Removable) Striping and Pavement Marking Tape (180 days or less)**

1. Advanced Traffic Marking, Series 200
2. Brite-Line, Series 100
3. Garlock Rubber Technologies, Series 2000
4. P.B. Laminations, Aztec, Grade 102
5. Swarco Industries, "Director-2"
6. Trelleborg Industries, R140 Series
7. 3M Series 620 "CR", and Series A750
8. 3M Series A145, Removable Black Line Mask  
(Black Tape: for use only on Hot mix asphalt surfaces)
9. Advanced Traffic Marking Black "Hide-A-Line"  
(Black Tape: for use only on Hot mix asphalt surfaces)
10. Brite-Line "BTR" Black Removable Tape

- (Black Tape: for use only on Hot mix asphalt surfaces)
11. Trelleborg Industries, RB-140  
(Black Tape: for use only on Hot mix asphalt surfaces)

**Preformed Thermoplastic (Heated in place)**

1. Flint Trading Inc., "Hot Tape"
2. Flint Trading Inc., "Premark Plus"
3. Ennis Paint Inc., "Flametape"

**Ceramic Surfacing Laminate, 150 mm x 150 mm**

1. Highway Ceramics, Inc.

**CLASS 1 DELINEATORS**

**One Piece Driveable Flexible Type, 1700-mm**

1. Filtrona Extrusion, "Flexi-Guide Models 400 and 566"
2. Carsonite, Curve-Flex CFRM-400
3. Carsonite, Roadmarker CRM-375
4. FlexStake, Model 654 TM
5. GreenLine Model CGD1-66

**Special Use Type, 1700-mm**

1. Filtrona Extrusion, Model FG 560 (with 450-mm U-Channel base)
2. Carsonite, "Survivor" (with 450-mm U-Channel base)
3. Carsonite, Roadmarker CRM-375 (with 450-mm U-Channel base)
4. FlexStake, Model 604
5. GreenLine Model CGD (with 450-mm U-Channel base)
6. Impact Recovery Model D36, with #105 Driveable Base
7. Safe-Hit with 200-mm pavement anchor (SH248-GP1)
8. Safe-Hit with 380-mm soil anchor (SH248-GP2) and with 450-mm soil anchor (SH248-GP3)

**Surface Mount Type, 1200-mm**

1. Bent Manufacturing Company, Masterflex Model MF-180EX-48
2. Carsonite, "Channelizer"
3. FlexStake, Models 704, 754 TM, and EB4
4. Impact Recovery Model D48, with #101 Fixed (Surface-Mount) Base
5. Three D Traffic Works "Channelflex" ID No. 522248W

**CHANNELIZERS**

**Surface Mount Type, 900-mm**

1. Bent Manufacturing Company, Masterflex Models MF-360-36 (Round) and MF-180-36 (Flat)
2. Filtrona Extrusion, Flexi-Guide Models FG300PE, FG300UR, and FG300EFX
3. Carsonite, "Super Duck" (Round SDR-336)
4. Carsonite, Model SDCF03601MB "Channelizer"
5. FlexStake, Models 703, 753 TM, and EB3
6. GreenLine, Model SMD-36
7. Hi-way Safety, Inc. "Channel Guide Channelizer" Model CGC36
8. Impact Recovery Model D36, with #101 Fixed (Surface-Mount) Base
9. Safe-Hit, Guide Post, Model SH236SMA and Dura-Post, Model SHL36SMA
10. Three D Traffic Works "Boomerang" 5200 Series

**Lane Separation System**

1. Filtrona Extrusion, "Flexi-Guide (FG) 300 Curb System"
2. Qwick Kurb, "Klemmfix Guide System"
3. Dura-Curb System
4. Tuff Curb

## **CONICAL DELINEATORS, 1070-mm**

(For 700-mm Traffic Cones, see Standard Specifications)

1. Bent Manufacturing Company "T-Top"
2. Plastic Safety Systems "Navigator-1070 mm"
3. Traffix Devices "Grabber"
4. Three D Traffic Works "Ringtop" TD7000, ID No. 742143
5. Three D Traffic Works, TD7500
6. Work Area Protection Corp. C-42

## **OBJECT MARKERS**

### **Type "K", 450-mm**

1. Filtrona Extrusion, Model FG318PE
2. Carsonite, Model SMD 615
3. FlexStake, Model 701 KM
4. Safe-Hit, Model SH718SMA

### **Type "K-4" / "Q" Object Markers, 600-mm**

1. Bent Manufacturing "Masterflex" Model MF-360-24
2. Filtrona Extrusion, Model FG324PE
3. Carsonite, "Channelizer"
4. FlexStake, Model 701KM
5. Safe-Hit, Models SH824SMA\_WA and SH824GP3\_WA
6. Three D Traffic Works ID No. 531702W and TD 5200
7. Three D Traffic Works ID No. 520896W

## **CONCRETE BARRIER MARKERS AND TEMPORARY RAILING (TYPE K) REFLECTORS**

### **Impactable Type**

1. ARTUK, "FB"
2. Filtrona Extrusion, Models PCBM-12 and PCBM-T12
3. Duraflex Corp., "Flexx 2020" and "Electriflexx"
4. Hi-Way Safety, Inc., Model GMKRM100
5. Plastic Safety Systems "BAM" Models OM-BARR and OM-BWAR
6. Three D Traffic Works "Roadguide" Model TD 9304

### **Non-Impactable Type**

1. ARTUK, JD Series
2. Plastic Safety Systems "BAM" Models OM-BITARW and OM-BITARA
3. Vega Molded Products, Models GBM and JD
4. Plastic Vacuum Forming, "Cap-It C400"

## **METAL BEAM GUARD RAIL POST MARKERS**

(For use to the left of traffic)

1. Filtrona Extrusion, "Mini" (75 mm x 254 mm)
2. Creative Building Products, "Dura-Bull, Model 11201"
3. Duraflex Corp., "Railrider"
4. Plastic Vacuum Forming, "Cap-It C300"

## **CONCRETE BARRIER DELINEATORS, 400-mm**

(For use to the right of traffic)

1. Filtrona Extrusion, Model PCBM T-16
2. Safe-Hit, Model SH216RBM

## **CONCRETE BARRIER-MOUNTED MINI-DRUM (260 mm x 360 mm x 570 mm)**

1. Stinson Equipment Company "SaddleMarker"

## **GUARD RAILING DELINEATOR**

(Place top of reflective element at 1200 mm above plane of roadway)

### **Wood Post Type, 686-mm**

1. Filtrona Extrusion, FG 427 and FG 527
2. Carsonite, Model 427
3. FlexStake, Model 102 GR
4. GreenLine GRD 27
5. Safe-Hit, Model SH227GRD
6. Three D Traffic Works "Guardflex" TD9100
7. New Directions Mfg, NDM27

### **Steel Post Type**

1. Carsonite, Model CFGR-327

## **RETROREFLECTIVE SHEETING**

### **Channelizers, Barrier Markers, and Delineators**

1. Avery Dennison T-6500 Series (For rigid substrate devices only)
2. Avery Dennison WR-7100 Series
3. Nippon Carbide Industries, Flexible Ultralite Grade (ULG) II
4. Reflexite, PC-1000 Metalized Polycarbonate
5. Reflexite, AC-1000 Acrylic
6. Reflexite, AP-1000 Metalized Polyester
7. Reflexite, Conformalight, AR-1000 Abrasion Resistant Coating
8. 3M, High Intensity

### **Traffic Cones, 100-mm and 150-mm Sleeves**

1. Nippon Carbide Industries, Flexible Ultralite Grade (ULG) II
2. Reflexite, Vinyl, "TR" (Semi-transparent) or "Conformalight"
3. 3M Series 3840
4. Avery Dennison S-9000C

### **Drums**

1. Avery Dennison WR-6100
2. Nippon Carbide Industries, Flexible Ultralite Grade (ULG) II
3. Reflexite, "Conformalight", "Super High Intensity" or "High Impact Drum Sheeting"
4. 3M Series 3810

### **Barricades: Type I, Medium-Intensity (Typically Enclosed Lens, Glass-Bead Element)**

1. Nippon Carbide Industries, CN8117
2. Avery Dennison, W 1100 series
3. 3M Series CW 44

### **Barricades: Type II, Medium-High-Intensity (Typically Enclosed Lens, Glass-Bead Element)**

1. Avery Dennison, W-2100 Series

### **Signs: Type II, Medium-High-Intensity (Typically Enclosed Lens, Glass-Bead Element)**

1. Avery Dennison, T-2500 Series
2. Nippon Carbide Industries, Nikkalite 18000

### **Signs: Type III, High-Intensity (Typically Encapsulated Glass-Bead Element)**

1. Avery Dennison, T-5500A and T-6500 Series
2. Nippon Carbide Industries, Nikkalite Brand Ultralite Grade II
3. 3M 3870 and 3930 Series

### **Signs: Type IV, High-Intensity (Typically Unmetallized Microprismatic Element)**

1. Avery Dennison, T-6500 Series

2. Nippon Carbide Industries, Crystal Grade, 94000 Series
3. Nippon Carbide Industries, Model No. 94847 Fluorescent Orange
4. 3M Series 3930 and Series 3924S

**Signs: Type VI, Elastomeric (Roll-Up) High-Intensity, without Adhesive**

1. Avery Dennison, WU-6014
2. Novabrite LLC, "Econobrite"
3. Reflexite "Vinyl"
4. Reflexite "SuperBright"
5. Reflexite "Marathon"
6. 3M Series RS20

**Signs: Type VII, Super-High-Intensity (Typically Unmetallized Microprismatic Element)**

1. 3M Series 3924S, Fluorescent Orange
2. 3M LDP Series 3970

**Signs: Type VIII, Super-High-Intensity (Typically Unmetallized Microprismatic Element)**

1. Avery Dennison, T-7500 Series
2. Avery Dennison, T-7511 Fluorescent Yellow
3. Avery Dennison, T-7513 Fluorescent Yellow Green
4. Avery Dennison, W-7514 Fluorescent Orange
5. Nippon Carbide Industries, Nikkalite Crystal Grade Series 92800
6. Nippon Carbide Industries, Nikkalite Crystal Grade Model 92847 Fluorescent Orange

**Signs: Type IX, Very-High-Intensity (Typically Unmetallized Microprismatic Element)**

1. 3M VIP Series 3981 Diamond Grade Fluorescent Yellow
2. 3M VIP Series 3983 Diamond Grade Fluorescent Yellow/Green
3. 3M VIP Series 3990 Diamond Grade
4. Avery Dennison T-9500 Series
5. Avery Dennison, T9513, Fluorescent Yellow Green
6. Avery Dennison, W9514, Fluorescent Orange
7. Avery Dennison, T-9511 Fluorescent Yellow

**SPECIALTY SIGNS**

1. Reflexite "Endurance" Work Zone Sign (with Semi-Rigid Plastic Substrate)

**ALTERNATIVE SIGN SUBSTRATES**

**Fiberglass Reinforced Plastic (FRP) and Expanded Foam PVC**

1. Fiber-Brite (FRP)
2. Sequentia, "Polyplate" (FRP)
3. Intoplast Group "InteCel" (13 mm for Post-Mounted CZ Signs, 1200 mm or less)(PVC)

**Aluminum Composite, Temporary Construction Signs and Permanent Signs up to 1400 mm.**

1. Alcan Composites "Dibond Material, 2 mm"
2. Mitsubishi Chemical America, Alpollic 350

**8-1.03 STATE-FURNISHED MATERIALS**

The State furnishes you with:

- Loop detector sensor units
- Model 170E controller unit
- Model 2070 controller unit
- Model 2070-6B Modem
- Model 332 controller cabinet
- Model 334 controller cabinet
- Components of battery backup system as follows:
  - Inverter/charger unit

Power transfer relay  
Manually-operated bypass switch  
Battery harness  
Utility interconnect wires  
Battery temperature probe  
Relay contact wires

- Padlocks for walk gates, irrigation controller enclosure cabinets and external cabinet for battery backup system
- Telephone service connection

The State furnishes you with completely wired controller cabinets with auxiliary equipment but without controller unit at Department of Transportation Maintenance Yard, 7310 East Bandini Boulevard, Commerce, CA 90040. At least 48 hours before you pick up the materials, inform the Engineer what you will pick up and when you will pick it up. The Contractor shall notify the District Warehouse Manager, Telephone (213)-620-2185 and the Engineer not less than 48 hours before State-furnished material is to be picked up by the Contractor. A full description of the material and the time the material will be picked up shall be provided.

#### **8-1.04 SLAG AGGREGATE**

Air-cooled iron blast furnace slag shall not be used to produce aggregate for:

1. Structure backfill material.
2. Pervious backfill material.
3. Permeable material.
4. Reinforced or prestressed portland cement concrete component or structure.

Aggregate produced from slag resulting from a steel-making process shall not be used for a highway construction project except for the following items:

1. Imported Borrow.
2. Aggregate Subbase.
3. Class 2 Aggregate Base.
4. Hot Mix Asphalt.

Steel slag to be used to produce aggregate for aggregate subbase and Class 2 aggregate base shall be crushed so that 100 percent of the material will pass a 19-mm sieve and then shall be control aged for a period of at least 3 months under conditions that will maintain all portions of the stockpiled material at a moisture content in excess of 6 percent of the dry mass of the aggregate.

A supplier of steel slag aggregate shall provide separate stockpiles for controlled aging of the slag. An individual stockpile shall contain not less than 9075 tonnes nor more than 45 350 tonnes of slag. The material in each individual stockpile shall be assigned a unique lot number and each stockpile shall be identified with a permanent system of signs. The supplier shall maintain a permanent record of the dates on which stockpiles are completed and controlled aging begun, of the dates when controlled aging was completed, and of the dates tests were made and the results of these tests. Moisture tests shall be made at least once each week. No credit for aging will be given for the time period covered by tests which show a moisture content of 6 percent or less. The stockpiles and records shall be available to the Engineer during normal working hours for inspection, check testing and review.

The supplier shall notify the Transportation Laboratory when each stockpile is completed and controlled aging begun. No more aggregate shall be added to the stockpile unless a new aging period is initiated. A further notification shall be sent when controlled aging is completed.

The supplier shall provide a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. Each stockpile or portion of a stockpile that is used in the work will be considered a lot. The Certificates of Compliance shall state that the steel slag aggregate has been aged in a stockpile for at least 3 months at a moisture content in excess of 6 percent of the dry mass of the aggregate.

Steel slag used for imported borrow shall be weathered for at least 3 months. Prior to the use of steel slag as imported borrow, the supplier shall furnish a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The Certificate of Compliance shall state that the steel slag has been weathered for at least 3 months.

Each delivery of aggregate containing steel slag for use as aggregate subbase or Class 2 aggregate base shall be accompanied by a delivery tag for each load which will identify the lot of material by stockpile number, where the slag was aged, and the date that the stockpile was completed and controlled aging begun.

Air-cooled iron blast furnace slag or natural aggregate may be blended in proper combinations with steel slag aggregate to produce the specified gradings, for those items for which steel slag aggregate is permitted, unless otherwise provided.

Aggregate containing slag shall meet the applicable quality requirements for the items in which the aggregate is used.

The combined slag aggregate shall conform to the specified grading for the item in which it is used. The grading will be determined by California Test 202, modified by California Test 105 when there is a difference in specific gravity of 0.2 or more between the coarse and fine portion of the aggregate or between blends of different aggregates.

No aggregate produced from slag shall be placed within 0.3-m, measured in any direction, of a non-cathodically protected pipe or structure unless the aggregate is incorporated in portland cement concrete pavement, in hot mix asphalt, or in treated base.

When slag is used as aggregate in hot mix asphalt, the  $K_c$  factor requirements, as determined by California Test 303, will not apply.

When slag aggregate is used for imported borrow, a layer of not less than 300 mm of topsoil, measured after compaction, shall be placed over the slag aggregate in areas where highway planting is to be performed. In other areas, slag aggregate used for embankment construction shall not be placed within 0.46-m of finished slope lines, measured normal to the plane of the slope. Full compensation for furnishing and placing topsoil and cover, as provided herein, shall be considered as included in the contract price paid per cubic meter for imported borrow and no additional compensation will be allowed therefor.

If steel slag aggregates are used to make hot mix asphalt, there shall be no other aggregates used in the mixture, except that up to 50 percent of the material passing the 4.75-mm sieve may consist of iron blast furnace slag aggregates or natural aggregates, or a combination thereof. If iron blast furnace aggregates or natural aggregates or a combination thereof are used in the mix, each type of aggregate shall be fed to the drier at a uniform rate. The rate of feed of each type of aggregate shall be maintained within 10 percent of the amount set. Adequate means shall be provided for controlling and checking the accuracy of the feeder.

Steel slag aggregate shall be stored separately from iron blast furnace slag aggregate and each type of slag aggregate shall also be stored separately from natural aggregate.

Hot mix asphalt produced from more than one of the following shall not be placed in the same layer: steel slag aggregates, iron blast furnace slag aggregates, natural aggregates or any combination thereof. Once a type of aggregate or aggregates is selected, it shall not be changed without prior approval by the Engineer.

If steel slag aggregates are used to produce hot mix asphalt, and if the specific gravity of a compacted stabilometer test specimen is in excess of 2.40, the quantity of hot mix asphalt to be paid for will be reduced. The stabilometer test specimen will be fabricated in conformance with the procedures in California Test 304 and the specific gravity of the specimen will be determined in conformance with Method C of California Test 308. The pay quantity of hot mix asphalt will be determined by multiplying the quantity of hot mix asphalt placed in the work by 2.40 and dividing the result by the specific gravity of the compacted stabilometer test specimen. Such reduction in quantity will be determined and applied as often as is necessary to ensure accurate results as determined by the Engineer.

#### **8-1.05 ENGINEERING FABRICS**

Engineering fabrics shall conform to the provisions in Section 88, "Engineering Fabrics," of the Standard Specifications and these special provisions.

Filter fabric for this project shall be ultraviolet (UV) ray protected.

### **SECTION 8-2. CONCRETE**

#### **8-2.01 PORTLAND CEMENT CONCRETE**

Portland cement concrete shall conform to the provisions in Section 90, "Portland Cement Concrete," of the Standard Specifications and these special provisions.

The Department maintains a list of sources of fine and coarse aggregate that have been approved for use with a reduced amount of supplementary cementitious material in the total amount of cementitious material to be used. A source of aggregate will be considered for addition to the approved list if the producer of the aggregate submits to the Transportation Laboratory certified test results from a qualified testing laboratory that verify the aggregate complies with the requirements. Before the testing starts, the aggregate test shall be registered with the Department. A registration number can be obtained by calling (916) 227-7228. The registration number shall be used as the identification for the aggregate sample in correspondence with the Department. Upon request, a split of the tested sample shall be provided to the Department. Approval of aggregate will depend upon compliance with the specifications, based on the certified test results submitted, together with any replicate testing the Department may elect to perform. Approval will expire 3 years from the date the most recent registered and evaluated sample was collected from the aggregate source.

Qualified testing laboratories shall conform to the following requirements:

1. Laboratories performing ASTM Designation: C 1293 shall participate in the Cement and Concrete Reference Laboratory (CCRL) Concrete Proficiency Sample Program and shall have received a score of 3 or better on each test of the previous 2 sets of concrete samples.
2. Laboratories performing ASTM Designation: C 1260 shall participate in the Cement and Concrete Reference Laboratory (CCRL) Pozzolan Proficiency Sample Program and shall have received a score of 3 or better on the shrinkage and soundness tests of the previous 2 sets of pozzolan samples.

Aggregates on the list shall conform to one of the following requirements:

1. When the aggregate is tested in conformance with the requirements in California Test 554 and ASTM Designation: C 1293, the average expansion at one year shall be less than or equal to 0.040 percent; or
2. When the aggregate is tested in conformance with the requirements in California Test 554 and ASTM Designation: C 1260, the average of the expansion at 16 days shall be less than or equal to 0.15 percent.

If the aggregates used in the concrete are on the Department's list, the minimum amount of supplementary cementitious material shall conform to the following:

1. If fly ash or natural pozzolan conforming to the provisions in Section 90-2.01C, "Required Use of Supplementary Cementitious Materials," of the Standard Specifications is used, the minimum amount of supplementary cementitious material shall be 15 percent by mass of the total cementitious material; or
2. If silica fume conforming to the provisions in Section 90-2.01C, "Required Use of Supplementary Cementitious Materials," of the Standard Specifications is used, the minimum amount of supplementary cementitious material shall be 7 percent by mass of the total cementitious material.

The limitation on tricalcium silicate (C<sub>3</sub>S) content in Type II cement specified in Section 90-2.01A, "Cement," of the Standard Specifications shall not apply.

## **8-2.02 PRECAST CONCRETE QUALITY CONTROL**

### **GENERAL**

Precast concrete quality control shall conform to these special provisions.

Unless otherwise specified, precast concrete quality control shall apply when any precast concrete members are fabricated in conformance with the provisions in Section 49, "Piling," or Section 51, "Concrete Structures," of the Standard Specifications.

Quality Control (QC) shall be the responsibility of the Contractor. The Contractor's QC inspectors shall perform inspection and testing prior to precasting, during precasting, and after precasting, and as specified in this section and additionally as necessary to ensure that materials and workmanship conform to the details shown on the plans, and to the specifications.

Quality Assurance (QA) is the prerogative of the Engineer. Regardless of the acceptance for a given precast element by the Contractor, the Engineer will evaluate the precast element. The Engineer will reject any precast element that does not conform to the approved Precast Concrete Quality Control Plan (PCQCP), the details shown on the plans, or to these special provisions.

The Contractor shall designate in writing a precast Quality Control Manager (QCM) for each precasting facility. The QCM shall be responsible directly to the Contractor for the quality of precasting, including materials and workmanship, performed by the Contractor and all subcontractors. The QCM shall be the sole individual responsible to the Contractor for submitting, receiving, and approving all correspondence, required submittals, and reports to and from the Engineer. The QCM shall not be employed or compensated by any subcontractor, or other persons or entities hired by subcontractors, or suppliers, who will provide other services or materials for the project. The QCM may be an employee of the Contractor.

Prior to submitting the PCQCP required herein, a meeting between the Engineer, the Contractor's QCM, and a representative from each entity performing precast concrete operations for this project, shall be held to discuss the requirements for precast quality control.

QC Inspectors shall either be 1) licensed as Civil Engineers in the State of California, or 2) have a current Plant Quality Personnel Certification, Level II, from the Precast/Prestressed Concrete Institute. A QC Inspector shall witness all precast concrete operations.

### **PRECAST CONCRETE QUALIFICATION AUDIT**

Unless otherwise specified, no Contractors or subcontractors performing precast concrete operations for the project shall commence work without having successfully completed the Department's Precast Fabrication Qualification Audit, hereinafter referred to as the audit. The Engineer will perform the audit, and copies of the audit form, along with procedures for requesting and completing the audit, are available at the Transportation Laboratory or at:

An audit that was previously approved by the Engineer no more than 3 years prior to the beginning of work on this contract will be acceptable for the entire period of this contract, provided the Engineer determines the audit is for the same type of work that is to be performed on this contract.

Successful completion of an audit shall not relieve the Contractor of the responsibility for furnishing materials or producing finished work of the quality specified in these special provisions and as shown on the plans.

### **PRECAST CONCRETE QUALITY CONTROL PLAN**

Prior to performing any precasting operations, the Contractor shall submit to the Engineer, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, 3 copies of a separate PCQCP for each item of work to be precast. A separate PCQCP shall be submitted for each facility. As a minimum, each PCQCP shall include the following:

- A. The name of the precasting firm, the concrete plants to be used, and any concrete testing firm to be used;
- B. A manual prepared by the precasting firm that includes equipment, testing procedures, safety plan, and the names, qualifications, and documentation of certifications for all personnel to be used;
- C. The name of the QCM and the names, qualifications, and documentation of certifications for all QC inspection personnel to be used;
- D. An organizational chart showing all QC personnel and their assigned QC responsibilities;
- E. The methods and frequencies for performing all required quality control procedures, including all inspections, material testing, and any required survey procedures for all components of the precast elements including prestressing systems, concrete, grout, reinforcement, steel components embedded or attached to the precast member, miscellaneous metal, and formwork;
- F. A system for identification and tracking of required precast element repairs, and a procedure for the reinspection of any repaired precast element. The system shall have provisions for a method of reporting nonconforming precast elements to the Engineer; and
- G. Forms to be used for Certificates of Compliance, daily production logs, and daily reports.

The Engineer shall have 4 weeks to review the PCQCP submittal after a complete plan has been received. No precasting shall be performed until the PCQCP is approved in writing by the Engineer.

A PCQCP that was previously approved by the Engineer no more than one year prior to the beginning of work on this contract will be acceptable for the entire period of this contract, provided the Engineer determines the PCQCP is for the same type of work that is to be performed on this contract.

An amended PCQCP or addendum shall be submitted to, and approved in writing by the Engineer, for any proposed revisions to the approved PCQCP. An amended PCQCP or addendum will be required for any revisions to the PCQCP, including but not limited to changes in concrete plants or source materials, changes in material testing procedures and testing labs, changes in procedures and equipment, changes in QC personnel, or updated systems for tracking and identifying precast elements. The Engineer shall have 2 weeks to complete the review of the amended PCQCP or addendum, once a complete submittal has been received. Work that is affected by any of the proposed revisions shall not be performed until the amended PCQCP or addendum has been approved.

After final approval of the PCQCP, amended PCQCP, or addendum, the Contractor shall submit 7 copies to the Engineer of each of these approved documents.

It is expressly understood that the Engineer's approval of the Contractor's PCQCP shall not relieve the Contractor of any responsibility under the contract for the successful completion of the work in conformance with the requirements of the plans and specifications. The Engineer's approval shall neither constitute a waiver of any of the requirements of the plans and specifications nor relieve the Contractor of any obligation thereunder; and defective work, materials, and equipment may be rejected notwithstanding approval of the PCQCP.

### **REPORTING**

The QC Inspector shall provide reports to the QCM on a daily basis for each day that precasting operations are performed.

A daily production log for precasting shall be kept by the QCM for each day that precasting operations, including setting forms, placing reinforcement, setting prestressing steel, casting, curing, post tensioning, and form release, are performed. The log shall include the facility location, and shall include a specific description of casting or related operations, any problems or deficiencies discovered, any testing or repair work performed, and the names of all QC personnel and the specific QC inspections they performed that day. The daily report from each QC Inspector shall also be included in the log. This daily log shall be available for viewing by the Engineer, at the precasting facility.

All reports regarding material tests and any required survey checks shall be signed by the person who performed the test or check, and then submitted directly to the QCM for review and signature prior to submittal to the Engineer. Corresponding names shall be clearly printed or type-written next to all signatures.

The Engineer shall be notified immediately in writing when any precasting problems or deficiencies are discovered and of the proposed repair or process changes required to correct them. The Engineer shall have 4 weeks to review these procedures. No remedial work shall begin until the Engineer approves these procedures in writing.

The following items shall be included in a precast report that is to be submitted to the Engineer following the completion of any precast element:

- A. Reports of all material tests and any required survey checks;
- B. Documentation that the Contractor has evaluated all tests and corrected all rejected deficiencies, and all repairs have been re-examined with the required tests and found acceptable; and
- C. A daily production log.

At the completion of any precast element, and if the QCM determines that element is in conformance with these special provisions, the QCM shall sign and furnish to the Engineer, a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. This Certificate of Compliance shall be submitted with the precast report. The certificate shall state that all of the materials and workmanship incorporated in the work, and all required tests and inspections of this work, have been performed in conformance with the details shown on the plans and the provisions of the Standard Specifications and these special provisions.

**PAYMENT**

In the event the Engineer fails to complete the review of 1) a PCQCP, 2) an amended PCQCP or addendum, or 3) a proposed repair or process change, within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

All required repair work or process changes required to correct precasting operation deficiencies, whether discovered by the QCM, QC Inspector, or by the Engineer, and any associated delays or expenses to the Contractor caused by performing these repairs, shall be at the Contractor's expense.

Full compensation for conforming to the requirements of this section shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

**SECTION 8-3. WELDING**

**8-3.01 WELDING**

**GENERAL**

Flux cored welding electrodes conforming to the requirements of AWS A5.20 E6XT-4 or E7XT-4 shall not be used to perform welding for this project.

Wherever reference is made to the following AWS welding codes in the Standard Specifications, on the plans, or in these special provisions, the year of adoption for these codes shall be as listed:

AWS Code	Year of Adoption
D1.1	2006
D1.4	2005
D1.5	2002
D1.6	1999

Requirements of the AWS welding codes shall apply unless otherwise specified in the Standard Specifications, on the plans, or in these special provisions. Wherever the abbreviation AWS is used, it shall be equivalent to the abbreviations ANSI/AWS or AASHTO/AWS.

Section 6.1.1.1 of AWS D1.5 is replaced with the following:

Quality Control (QC) shall be the responsibility of the Contractor. As a minimum, the Contractor shall perform inspection and testing of each weld joint prior to welding, during welding, and after welding as specified in this section and as necessary to ensure that materials and workmanship conform to the requirements of the contract documents.

Unless otherwise specified, Sections 6.1.3 through 6.1.4.3 of AWS D1.1, Section 7.1.2 of AWS D1.4, and Sections 6.1.1.2 through 6.1.3.3 of AWS D1.5 are replaced with the following:

The QC Inspector shall be the duly designated person who acts for and on behalf of the Contractor for inspection, testing, and quality related matters for all welding.

Quality Assurance (QA) is the prerogative of the Engineer. The QA Inspector is the duly designated person who acts for and on behalf of the Engineer.

The QC Inspector shall be responsible for quality control acceptance or rejection of materials and workmanship, and shall be currently certified as an AWS Certified Welding Inspector (CWI) in conformance with the requirements in AWS QC1, "Standard for AWS Certification of Welding Inspectors."

The QC Inspector may be assisted by an Assistant QC Inspector provided that this individual is currently certified as an AWS Certified Associate Welding Inspector (CAWI) in conformance with the requirements in AWS QC1, "Standard for AWS Certification of Welding Inspectors." The Assistant QC Inspector may perform inspection under the direct supervision of the QC Inspector provided the assistant is always within visible and audible range of the QC Inspector. The QC Inspector shall be responsible for signing all reports and for determining if welded materials conform to workmanship and acceptance criteria. The ratio of QC Assistants to QC Inspectors shall not exceed 5 to 1.

When the term "Inspector" is used without further qualification, it shall refer to the QC Inspector.

When any work is welded in conformance with the provisions in Section 75, "Miscellaneous Metal," of the Standard Specifications, not including Section 75-1.035, "Bridge Joint Restrainer Units," of the Standard Specifications, Section 6.1.4 of AWS D1.1 is replaced with the following:

The QC Inspector shall be responsible for quality control acceptance or rejection of materials and workmanship and shall be currently certified as an AWS CWI in conformance with the requirements in AWS QC1, "Standard for AWS Certification of Welding Inspectors," or as a Welding Inspector Specialist (WIS) in conformance with the requirements in AWS B5.2, "Specification for the Qualification of Welding Inspector Specialists and Welding Inspector Assistants."

Section 6.14.6, "Personnel Qualification," of AWS D1.1, Section 7.8, "Personnel Qualification," of AWS D1.4, and Section 6.1.3.4, "Personnel Qualification," of AWS D1.5 are replaced with the following:

Personnel performing nondestructive testing (NDT) shall be qualified and certified in conformance with the requirements of the American Society for Nondestructive Testing (ASNT) Recommended Practice No. SNT-TC-1A and the Written Practice of the NDT firm. The Written Practice of the NDT firm shall meet or exceed the guidelines of the ASNT Recommended Practice No. SNT-TC-1A. Individuals who perform NDT, review the results, and prepare the written reports shall be either:

- A. Certified NDT Level II technicians, or;
- B. Level III technicians who hold a current ASNT Level III certificate in that discipline and are authorized and certified to perform the work of Level II technicians.

Section 6.5.4 of AWS D1.5 is replaced with the following:

The QC Inspector shall inspect and approve each joint preparation, assembly practice, welding technique, joint fit-up, and the performance of each welder, welding operator, and tack welder to make certain that the applicable requirements of this code and the approved Welding Procedure Specification (WPS) are met. The QC Inspector shall examine the work to make certain that it meets the requirements of Sections 3 and 6.26. The size and contour of all welds shall be measured using suitable gages. Visual inspection for cracks in welds and base metal, and for other discontinuities shall be aided by strong light, magnifiers, or such other devices as may be helpful. Acceptance criteria different from those specified in this code may be used when approved by the Engineer.

Section 6.6.5, "Nonspecified NDT Other than Visual," of AWS D1.1, Section 7.6.5 of AWS D1.4 and Section 6.6.5 of AWS D1.5 shall not apply.

For any welding, the Engineer may direct the Contractor to perform NDT that is in addition to the visual inspection or NDT specified in the AWS or other specified welding codes, in the Standard Specifications, or in these special provisions. Except as provided for in these special provisions, additional NDT required by the Engineer, and associated repair work, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications. Prior to release of welded material by the Engineer, if testing by NDT methods other than those originally specified discloses an attempt to defraud or reveals a gross nonconformance, all costs associated with the repair of the deficient area, including NDT of the weld and of the repair, and any delays caused by the repair, shall be at the Contractor's expense. A gross nonconformance is defined as the sum of planar type rejectable indications in more than 20 percent of the tested length.

When less than 100 percent of NDT is specified for any weld, it is expected that the entire length of weld meet the specified acceptance-rejection criteria. Should any welding deficiencies be discovered by additional NDT directed or performed by the Engineer that utilizes the same NDT method as that originally specified, all costs associated with the repair of the deficient area, including NDT of the weld and of the weld repair, and any delays caused by the repair, shall be at the Contractor's expense.

Repair work to correct welding deficiencies discovered by visual inspection directed or performed by the Engineer, and any associated delays or expenses caused to the Contractor by performing these repairs, shall be at the Contractor's expense.

The Engineer shall have the authority to verify the qualifications or certifications of any welder, QC Inspector, or NDT personnel to specified levels by retests or other means approved by the Engineer.

Inspection and approval of all joint preparations, assembly practices, joint fit-ups, welding techniques, and the performance of each welder, welding operator, and tack welder shall be documented by the QC Inspector on a daily basis for each day welding is performed. For each inspection, including fit-up, Welding Procedure Specification (WPS) verification, and final weld inspection, the QC Inspector shall confirm and document compliance with the requirements of the AWS or other specified code criteria and the requirements of these special provisions on all welded joints before welding, during welding, and after the completion of each weld.

In addition to the requirements specified in the applicable code, the period of effectiveness for a welder's or welding operator's qualification shall be a maximum of 3 years for the same weld process, welding position, and weld type. If welding will be performed without gas shielding, then qualification shall also be without gas shielding. Excluding welding of fracture critical members, a valid qualification at the beginning of work on a contract will be acceptable for the entire period of the contract, as long as the welder's or welding operator's work remains satisfactory.

In addition to the requirements of AWS D1.1, welding procedures qualification for work welded in conformance with that code shall conform to the following:

When a nonstandard weld joint is to be made using a combination of WPSs, a single test may be conducted combining the WPSs to be used in production, provided the essential variables, including weld bead placement, of each process are limited to those established in Table 4.5.

In addition to the requirements of AWS D1.5, Section 5.12 or 5.13, welding procedures qualification for work welded in conformance with that code shall conform to the following requirements:

- A. Unless considered prequalified, fillet welds shall be qualified in each position. The fillet weld soundness test shall be conducted using the essential variables of the WPS as established by the Procedure Qualification Record (PQR).
- B. For qualification of joints that do not conform to Figures 2.4 and 2.5 of AWS D1.5, a minimum of two WPS qualification tests are required. The tests shall be conducted using both Figure 5.1 and Figure 5.3. The test conforming to Figure 5.1 shall be conducted in conformance with AWS D1.5, Section 5.12 or 5.13. The test conforming to Figure 5.3 shall be conducted using the welding electrical parameters that were established for the test conducted conforming to Figure 5.1. The ranges of welding electrical parameters established during welding per Figure 5.1 in conformance with AWS D1.5, Section 5.12, shall be further restricted according to the limits in Table 5.3 during welding per Figure 5.3.
- C. Multiple zones within a weld joint may be qualified. The travel speed, amperage, and voltage values that are used for tests conducted per AWS D1.5 Section 5.13 shall be consistent for each pass in a weld joint, and shall in no case vary by more than  $\pm 10$  percent for travel speed,  $\pm 10$  percent for amperage, and  $\pm 7$  percent for voltage as measured from a predetermined target value or average within each weld pass or zone. The travel speed shall in no case vary by more than  $\pm 15$  percent when using submerged arc welding.
- D. For a WPS qualified in conformance with AWS D1.5 Section 5.13, the values to be used for calculating ranges for current and voltage shall be based on the average of all weld passes made in the test. Heat input shall be calculated using the average of current and voltage of all weld passes made in the test for a WPS qualified in conformance with Section 5.12 or 5.13.
- E. Macroetch tests are required for WPS qualification tests, and acceptance shall be per AWS D1.5 Section 5.19.3.
- F. When a nonstandard weld joint is to be made using a combination of WPSs, a test conforming to Figure 5.3 may be conducted combining the WPSs to be used in production, provided the essential variables, including weld bead placement, of each process are limited to those established in Table 5.3.
- G. Prior to preparing mechanical test specimens, the PQR welds shall be inspected by visual and radiographic tests. Backing bar shall be 75-mm in width and shall remain in place during NDT testing. Results of the visual and radiographic tests shall comply with AWS D1.5 Section 6.26.2, excluding Section 6.26.2.2. Test plates that do not comply with both tests shall not be used.

## **WELDING QUALITY CONTROL**

Welding quality control shall conform to the requirements in the AWS or other specified welding codes, the Standard Specifications, and these special provisions.

Unless otherwise specified, welding quality control shall apply when any work is welded in conformance with the provisions in Section 49, "Piling," Section 52, "Reinforcement," Section 55, "Steel Structures," or Section 75-1.035, "Bridge Joint Restrainer Units," of the Standard Specifications.

All welding will require inspection by the Engineer. The Contractor shall request inspection at least 3 business days prior to the beginning of welding for locations within California and 5 business days for locations outside of California. The Contractor shall request inspection at:

<http://www.dot.ca.gov/hq/esc/Translab/OSM/smbforms.htm>

Continuous inspection shall be provided when any welding is being performed. Continuous inspection, as a minimum, shall include having a QC Inspector within such close proximity of all welders or welding operators so that inspections by the QC Inspector of each welding operation at each welding location does not lapse for a period exceeding 30 minutes.

When joint weld details that are not prequalified to the details of Section 3 of AWS D1.1 or to the details of Figure 2.4 or 2.5 of AWS D1.5 are proposed for use in the work, the joint details, their intended locations, and the proposed welding parameters and essential variables, shall be approved by the Engineer. The Contractor shall allow the Engineer 15 days to complete the review of the proposed joint detail locations. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications. Upon approval of the proposed joint detail locations and qualification of the proposed joint details, welders and welding operators using these details shall perform a qualification test plate using the WPS variables and the joint detail to be used in production. The test plate shall have the maximum thickness to be used in production and a minimum length of 450 mm. The test plate shall be mechanically and radiographically tested. Mechanical and radiographic testing and acceptance criteria shall be as specified in the applicable AWS codes.

The Engineer will witness all qualification tests for WPSs that were not previously approved by the Department. Unless otherwise specified, an approved independent third party will witness the qualification tests for welders or welding operators. The independent third party shall be a current CWI and shall not be an employee of the contractor performing the welding. The Contractor shall allow the Engineer 15 days to review the qualifications and copy of the current certification of the independent third party. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications. The Contractor shall notify the Engineer 7 days prior to performing any qualification tests. Witnessing of qualification tests by the Engineer shall not constitute approval of the intended joint locations, welding parameters, or essential variables.

The Contractor shall designate in writing a welding Quality Control Manager (QCM). The QCM shall be responsible directly to the Contractor for the quality of welding, including materials and workmanship, performed by the Contractor and subcontractors.

The QCM shall be the sole individual responsible to the Contractor for submitting, receiving, reviewing, and approving all correspondence, required submittals, and reports to and from the Engineer. The QCM shall be a registered professional engineer or shall be currently certified as a CWI.

Unless the QCM is hired by a subcontractor providing only QC services, the QCM shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project. The QCM may be an employee of the Contractor.

Welding inspection personnel or NDT firms to be used in the work shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project, except for the following conditions:

- A. The work is welded in conformance with AWS D1.5 and is performed at a permanent fabrication or manufacturing facility that is certified under the AISC Quality Certification Program, Category Cbr, Major Steel Bridges and Fracture Critical endorsement F, when applicable.
- B. The work is welded in conformance with AWS D1.1 at a permanent pipe manufacturing or fabrication facility that maintains a QC program that is independent from production.

For welding performed at such facilities, the inspection personnel or NDT firms may be employed or compensated by the facility performing the welding provided the facility maintains a QC program that is independent from production.

Prior to submitting the Welding Quality Control Plan (WQCP) required herein, a prewelding meeting between the Engineer, the Contractor's QCM, and a representative from each entity performing welding or inspection for this project, shall be held to discuss the requirements for the WQCP.

The Contractor shall submit to the Engineer, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, 2 copies of a separate WQCP for each subcontractor or supplier for each item of work for which welding is to be performed.

The Contractor shall allow the Engineer 15 days to review the WQCP submittal after a complete plan has been received. No welding shall be performed until the WQCP is approved in writing by the Engineer. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

An amended WQCP or any addendum to the approved WQCP shall be submitted to, and approved in writing by the Engineer, for proposed revisions to the approved WQCP. An amended WQCP or addendum will be required for revisions to the WQCP, including but not limited to a revised WPS; additional welders; changes in NDT firms, QC, or NDT personnel or procedures; or updated systems for tracking and identifying welds. The Engineer shall have 7 days to complete the review of the amended WQCP or addendum. Work affected by the proposed revisions shall not be performed until the amended WQCP or addendum has been approved. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Information regarding the contents, format, and organization of a WQCP, is available at the Transportation Laboratory and at:

<http://www.dot.ca.gov/hq/esc/Translab/OSM/smbresources.htm>

After final approval of the WQCP, amended WQCP, or addendum, the Contractor shall submit 7 copies to the Engineer of the approved documents. A copy of the Engineer approved document shall be available at each location where welding is to be performed.

A daily production log for welding shall be kept for each day that welding is performed. The log shall clearly indicate the locations of all welding. The log shall include the welders' names, amount of welding performed, any problems or deficiencies discovered, and any testing or repair work performed, at each location. The daily report from each QC Inspector shall also be included in the log.

The following items shall be included in a Welding Report that is to be submitted to the Engineer within 15 days following the performance of any welding:

- A. A daily production log.
- B. Reports of all visual weld inspections and NDT.
- C. Radiographs and radiographic reports, and other required NDT reports.
- D. A summary of welding and NDT activities that occurred during the reporting period.
- E. Reports of each application of heat straightening.
- F. A summarized log listing the rejected lengths of weld by welder, position, process, joint configuration, and piece number.
- G. Documentation that the Contractor has evaluated all radiographs and other nondestructive tests and corrected all rejectable deficiencies, and that all repaired welds have been reexamined using the required NDT and found acceptable.

The following information shall be clearly written on the outside of radiographic envelopes: name of the QCM, name of the nondestructive testing firm, name of the radiographer, date, contract number, complete part description, and all included weld numbers, report numbers, and station markers or views, as detailed in the WQCP. In addition, all interleaves shall have clearly written on them the part description and all included weld numbers and station markers or views, as detailed in the WQCP. A maximum of 2 pieces of film shall be used for each interleave.

Reports of all visual inspections and NDT shall be signed by the inspector or technician and submitted daily to the QCM for review and signature prior to submittal to the Engineer. Corresponding names shall be clearly printed or typewritten next to all signatures. Reports of all NDT, whether specified, additional, or informational, performed by the Contractor shall be submitted to the Engineer.

The Engineer will review the Welding Report to determine if the Contractor is in conformance with the WQCP. Except for steel pipe piling, the Engineer shall be allowed 15 days to review the report and respond in writing after the complete Welding Report has been received. Prior to receiving notification from the Engineer of the Contractor's conformance with the WQCP, the Contractor may encase in concrete or cover welds for which the Welding Report has been submitted. However, should the Contractor elect to encase or cover those welds prior to receiving notification from the Engineer, it is expressly understood that the Contractor shall not be relieved of the responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Material not conforming to these requirements will be subject to rejection. Should the Contractor elect to wait to encase or cover welds pending notification by the Engineer, and in the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of

the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

For steel pipe piling, including bar reinforcement in the piling, the Contractor shall allow the Engineer 2 business days to review the Welding Report and respond in writing after the required items have been received. No field welded steel pipe piling shall be installed, and no reinforcement in the piling shall be encased in concrete until the Engineer has approved the above requirements in writing.

In addition to the requirements in AWS D1.1 and AWS D1.5, second-time excavations of welds or base metal to repair unacceptable discontinuities, regardless of NDT method, and all repairs of cracks require prior approval of the Engineer.

The Engineer shall be notified immediately in writing when welding problems, deficiencies, base metal repairs, or any other type of repairs not submitted in the WQCP are discovered, and also of the proposed repair procedures to correct them. For requests to perform second-time repairs or repairs of cracks, the Contractor shall include an engineering evaluation of the proposed repair. The engineering evaluation, at a minimum, shall address the following:

- A. What is causing each defect?
- B. Why the repair will not degrade the material properties?
- C. What steps are being taken to prevent similar defects from happening again?

The Contractor shall allow the Engineer 7 days to review these procedures. No remedial work shall begin until the repair procedures are approved in writing by the Engineer. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The QCM shall sign and furnish to the Engineer, a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each item of work for which welding was performed. The certificate shall state that all of the materials and workmanship incorporated in the work, and all required tests and inspections of this work, have been performed in conformance with the details shown on the plans, the Standard Specifications, and these special provisions.

### **WELDING FOR OVERHEAD SIGN AND POLE STRUCTURES**

The Contractor shall meet the following requirements for any work welded in conformance with the provisions in Section 56-1, "Overhead Sign Structures," or Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications.

Welding inspection personnel or NDT firms to be used in the work shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project, except for when the welding is performed at a permanent fabrication or manufacturing facility which is certified under the AISC Quality Certification Program, Category Sbd, Conventional Steel Building Structures.

#### **Welding Qualification Audit**

Contractors or subcontractors performing welding operations for overhead sign and pole structures shall not deliver materials to the project without having successfully completed the Department's "Manufacturing Qualification Audit for Overhead Sign and Pole Structures," hereinafter referred to as the audit, not more than one year prior to the delivery of the materials. The Engineer will perform the audit. Copies of the audit form, and procedures for requesting and completing the audit, are available at the Transportation Laboratory or at:

<http://www.dot.ca.gov/hq/esc/Translab/OSM/smbresources.htm>

An audit that was approved by the Engineer no more than one year prior to the beginning of work on this contract will be acceptable for the entire period of this contract, provided the Engineer determines the audit was for the same type of work that is to be performed on this contract.

Successful completion of an audit shall not relieve the Contractor of the responsibility for furnishing materials or producing finished work of the quality specified in these special provisions and as shown on the plans.

#### **Welding Report**

For work welded in conformance with the provisions in Section 56-1, "Overhead Sign Structures," or Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications, a Welding Report shall be submitted in conformance with the provisions in "Welding Quality Control" of these special provisions.

## **PAYMENT**

Full compensation for conforming to the requirements of "Welding" shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

## **SECTION 9. DESCRIPTION OF BRIDGE WORK**

The bridge work must be done by widening a steel girder bridge and lengthening reinforced concrete pedestrian undercrossing in accordance with the details shown on the plans at the following locations:

Justin Avenue PUC (Lengthen)  
(Bridge No. 53-1078)

Western Avenue UC (Widen)  
(Bridge No. 53-1079S)

## **SECTION 10. CONSTRUCTION DETAILS**

### **SECTION 10-1. GENERAL**

#### **10-1.01 CONSTRUCTION PROJECT INFORMATION SIGNS**

Before any major physical construction work readily visible to highway users is started on this contract, the Contractor shall furnish and erect 2 Type 2 Construction Project Information signs at the locations designated by the Engineer.

The signs and overlays shall be of a type and material consistent with the estimated time of completion of the project and shall conform to the details shown on the plans.

The sign letters, border and the Department's construction logos shall conform to the colors (non-reflective) and details shown on the plans, and shall be on a white background (non-reflective). The colors blue and orange shall conform to PR Color Number 3 and Number 6, respectively, as specified in the Federal Highway Administration's Color Tolerance Chart.

The sign message to be used for fund types shall consist of the following, in the order shown:

STATE HIGHWAY FUNDS
---------------------

The sign message to be used for type of work shall consist of the following:

#### **HIGHWAY CONSTRUCTION**

The sign message to be used for the Year of Completion of Project Construction will be furnished by the Engineer. The Contractor shall furnish and install the "Year" sign overlay within 10 working days of notification of the year date to be used.

The letter sizes to be used shall be as shown on the plans. The information shown on the signs shall be limited to that shown on the plans.

The signs shall be kept clean and in good repair by the Contractor.

Upon completion of the work, the signs shall be removed and disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13 of the Standard Specifications.

Full compensation for furnishing, erecting, maintaining, and removing and disposing of the construction project information signs shall be considered as included in the contract lump sum price paid for construction area signs and no additional compensation will be allowed therefor.

#### **10-1.02 ORDER OF WORK**

Order of work shall conform to the provisions in Section 5-1.05, "Order of Work," of the Standard Specifications and these special provisions.

The Contractor shall schedule paving operations so that cold planed areas are paved with hot mix asphalt before reopening the work area to public traffic.

Attention is directed to "Miscellaneous Concrete Construction" of these special provisions regarding constructing a 600 mm by 600 mm test panel prior to constructing curb ramps with detectable warning surfaces.

The first order of work shall be to place the order for the electrical equipment.

The uppermost layer of new pavement shall not be placed until all underlying conduits and loop detectors have been installed.

Prior to commencement of the traffic signal functional test at any location, all items of work related to signal control shall be completed and all roadside signs, pavement delineation, and pavement markings shall be in place at that location.

Attention is directed to "Maintaining Traffic" and "Temporary Pavement Delineation" of these special provisions and to the stage construction sheets of the plans.

Attention is directed to "Progress Schedule (Critical Path Method)" of these special provisions regarding the submittal of a general time-scaled logic diagram within 10 days after approval of the contract. The diagram shall be submitted prior to performing any work that may be affected by any proposed deviations to the construction staging of the project.

The work shall be performed in conformance with the stages of construction shown on the plans. Nonconflicting work in subsequent stages may proceed concurrently with work in preceding stages, provided satisfactory progress is maintained in the preceding stages of construction.

In each stage, after completion of the preceding stage, the first order of work shall be the removal of existing pavement delineation as directed by the Engineer. Pavement delineation removal shall be coordinated with new delineation so that lane lines are provided at all times on traveled ways open to public traffic.

Before obliterating any pavement delineation (traffic stripes, pavement markings, and pavement markers) that is to be replaced on the same alignment and location, as determined by the Engineer, the pavement delineation shall be referenced by the Contractor, with a sufficient number of control points to reestablish the alignment and location of the new pavement delineation. The references shall include the limits or changes in striping pattern, including one- and 2-way barrier lines, limit lines, crosswalks and other pavement markings. Full compensation for referencing existing pavement delineation shall be considered as included in the contract prices paid for new pavement delineation and no additional compensation will be allowed therefor.

Prior to placing hot mix asphalt (Type B), the Contractor shall cover all manholes, valve and monument covers, grates, or other exposed facilities located within the area of application, using a plastic or oil resistant construction paper secured to the facility being covered by tape or adhesive. The covered facilities shall be referenced by the Contractor, with a sufficient number of control points to relocate the facilities after the hot mix asphalt (Type B) has been placed. After completion of the hot mix asphalt (Type B) operation, all covers shall be removed and disposed of in a manner satisfactory to the Engineer. Full compensation for covering manholes, valve and monument covers, grates, or other exposed facilities, referencing, and removing temporary cover shall be considered as included in the contract price paid per ton for hot mix asphalt (Type B), and no additional compensation will be allowed therefor.

At the end of each working day if a difference in excess of 2.4-meter exists between the elevation of the existing pavement and the elevation of excavations within 2.4 m of the traveled way, material shall be placed and compacted against the vertical cuts adjacent to the traveled way. During excavation operations, native material may be used for this purpose; however, once placing of the structural section commences, structural material shall be used. The material shall be placed to the level of the elevation of the top of existing pavement and tapered at a slope of 1:4 (vertical:horizontal) or flatter to the bottom of the excavation. Treated base shall not be used for the taper. Full compensation for placing the material on a 1:4 slope, regardless of the number of times the material is required, and subsequent removing or reshaping of the material to the lines and grades shown on the plans shall be considered as included in the contract price paid for the materials involved and no additional compensation will be allowed therefor. No payment will be made for material placed in excess of that required for the structural section.

At those locations exposed to public traffic where guard railings or barriers are to be constructed and removed, the Contractor shall schedule operations so that at the end of each working day there shall be no post holes open nor shall there be any railing or barrier posts installed without the blocks and rail elements assembled and mounted thereon.

At least 60 days before planting the plants, furnish the Engineer a statement from the vendor that the order for the plants required for this contract, including inspection plants, has been received and accepted by the vendor. The statement from the vendor must include the names, sizes, and quantities of plants ordered and the anticipated date of delivery.

Place orders for replacement plants with the vendor at the appropriate time so that the roots of the replacement plants are not in a root-bound condition.

Do not perform clearing, grubbing, and earthwork operations in areas where existing irrigation facilities are to remain in place until existing irrigation facilities have been checked for proper operation as specified under "Existing Highway Irrigation Facilities" of these special provisions.

Submittal of working drawings for electrical components must comply with Section 20-5.027B, "Wiring Plans and Diagrams," of the Standard Specifications.

Preinstall irrigation components in the irrigation controller enclosure cabinet before field installation as specified under "Irrigation Controller Enclosure Cabinet" of these special provisions.

When embankment settlement periods are specified, the settlement periods and the deferment of portions of the work shall comply with the provisions in Section 19-6.025, "Settlement Period," of the Standard Specifications and in "Earthwork" of these special provisions.

### **10-1.03 WATER POLLUTION CONTROL**

#### **GENERAL**

Water pollution control work shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications, section of these special provisions entitled "Relations With California Regional Water Quality Control Board," and these special provisions.

The Contractor may obtain other National Pollutant Discharge Elimination System (NPDES) permits that apply to activities and mobile operations within or outside of the project limits including hot mix asphalt batch plants, material borrow areas, concrete plants, staging areas, storage yards, or access roads.

The Contractor shall perform water pollution control work in conformance with the requirements in the "Storm Water Pollution Prevention Plan (SWPPP) and Water Pollution Control Program (WPCP) Preparation Manual" and its addenda in effect on the day the Notice to Contractors is dated. This manual is referred to as the "Preparation Manual." Copies of the Preparation Manual may be obtained from:

State of California  
Department of Transportation  
Publication Distribution Unit  
1900 Royal Oaks Drive  
Sacramento, California 95815  
Telephone: (916) 445-3520

The Preparation Manual and other references for performing water pollution control work are available from the Department's Construction Storm Water and Water Pollution Control web site at:

<http://www.dot.ca.gov/hq/construc/stormwater/stormwater1.htm>

Before the start of job site activities, the Contractor shall provide training for project managers, supervisory personnel, and employees involved with water pollution control work. The training shall include:

- A. Rules and regulations
- B. Implementation and maintenance for:
  - 1. Temporary Soil Stabilization
  - 2. Temporary Sediment Control
  - 3. Tracking Control
  - 4. Wind Erosion Control

The Contractor shall designate in writing a Water Pollution Control Manager (WPCM). The Contractor shall submit a statement of qualifications describing the training, work history, and expertise of the proposed WPCM. The qualifications shall include either:

- A. A minimum of 24 hours of Department approved storm water management training described at Department's Construction Storm Water and Water Pollution Control web site.
- B. Certification as a Certified Professional in Erosion and Sediment Control (CPESC).

The WPCM shall be:

- A. Responsible for water pollution control work.
- B. The primary contact for water pollution control work.
- C. Have authority to mobilize crews to make immediate repairs to water pollution control practices.

The Contractor may designate one manager to prepare the SWPPP and a different manager to implement the plan. The WPCP preparer shall meet the training requirements for the WPCM.

#### **STORM WATER POLLUTION PREVENTION PLAN**

The Contractor shall submit a Storm Water Pollution Prevention Plan (SWPPP) to the Engineer for approval. The SWPPP shall conform to the requirements in the Preparation Manual, the NPDES permit, and these special provisions. The SWPPP shall be submitted in place of the water pollution control program required by the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications.

The SWPPP shall include water pollution control practices:

- A. For storm water and non-storm water from areas outside of the job site related to construction activities for this contract such as:
  - 1. Staging areas.
  - 2. Storage yards.
  - 3. Access roads.
- B. Appropriate for each season as described in "Implementation Requirements" of these special provisions.
- C. For activities or mobile operations related to all NPDES permits.

The SWPPP shall include a schedule that:

- A. Describes when work activities that could cause water pollution will be performed.
- B. Identifies soil stabilization and sediment control practices for disturbed soil area.
- C. Includes dates when these practices will be 25, 50, and 100 percent complete.
- D. Shows 100 percent completion of these practices before the rainy season.

The SWPPP shall include the following temporary water pollution control practices and their associated contract items of work as shown on the plans or specified in these special provisions:

- A. Temporary Soil Stabilization
  - 1. Temporary Hydraulic Mulch (Bonded Filter Matrix)
  - 2. Temporary Erosion Control Blanket
- B. Temporary Sediment Control
  - 1. Temporary Fiber Roll
  - 2. Temporary Gravel Bag Berm
  - 3. Temporary Drainage Inlet Protection
  - 4. Street Sweeping
- C. Tracking Control
  - 1. Temporary Construction Entrance
- D. Non-Storm Water Management
  - 1. Construction Site Management (paving, sealing, sawcutting and grinding operations, concrete curing and concrete finishing)
- E. Waste Management and Materials Pollution Control
  - 1. Construction Site Management (material delivery and storage, material use, spill prevention and control, hazardous waste management, contaminated soil management, and sanitary/septic waste management)
  - 2. Temporary Concrete Washout Facility
  - 3. Temporary Concrete Washout (Portable)

The SWPPP shall include the following contract items of work for permanent water pollution control as shown on the plans or as specified in these special provisions:

- A. Highway Planting
- B. Minor Concrete (Textured Paving)

Within 20 days after contract approval, the Contractor shall submit 3 copies of the SWPPP to the Engineer. The Contractor shall allow 20 days for the Engineer's review. If revisions are required, the Engineer will provide comments and specify the date that the review stopped. The Contractor shall revise and resubmit the SWPPP within 7 days of receipt of the

Engineer's comments. The Engineer's review will resume when the complete SWPPP is resubmitted. When the Engineer approves the SWPPP, the Contractor shall submit 4 copies of the approved SWPPP to the Engineer. The Contractor may proceed with construction activities if the Engineer conditionally approves the SWPPP while minor revisions are being completed. If the Engineer fails to complete the review within the time allowed and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay, the Contractor will be compensated for resulting losses, and an extension of time will be granted, as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The Contractor shall not perform work that may cause water pollution until the SWPPP has been approved by the Engineer. The Engineer's review and approval shall not waive any contract requirements and shall not relieve the Contractor from complying with Federal, State and local laws, regulations, and requirements.

If there is a change in construction schedule or activities, the Contractor shall prepare an amendment to the SWPPP to identify additional or revised water pollution control practices. The Contractor shall submit the amendment to the Engineer for review within a time agreed to by the Engineer not to exceed the number of days specified for the initial submittal of the SWPPP. The Engineer will review the amendment within the same time allotted for the review of the initial submittal of the SWPPP.

If directed by the Engineer or requested in writing by the Contractor and approved by the Engineer, changes to the water pollution control work specified in these special provisions will be allowed. Changes may include addition of new water pollution control practices. The Contractor shall incorporate these changes in the SWPPP. Additional water pollution control work will be paid for as extra work in accordance with Section 4-1.03D, "Extra Work," of the Standard Specifications.

The Contractor shall keep a copy of the approved SWPPP at the job site. The SWPPP shall be made available when requested by a representative of the Regional Water Quality Control Board, State Water Resources Control Board, United States Environmental Protection Agency, or the local storm water management agency. Requests from the public shall be directed to the Engineer.

### **SAMPLING AND ANALYSIS**

The Contractor shall include a Sampling and Analysis Plan (SAP) in the SWPPP to monitor the effectiveness of the water pollution control practices. The Contractor shall prepare the SAP in conformance with the Preparation Manual.

The Contractor shall designate trained personnel to collect water quality samples. The personnel and training shall be documented in the SAP. Training shall consist of the following elements:

- A. SAP review,
- B. Health and safety review, and
- C. Sampling simulations.

In the SAP the Contractor shall describe the following water quality sampling procedures:

- A. Sampling preparation,
- B. Collection,
- C. Quality assurance and quality control,
- D. Sample labeling,
- E. Collection documentation,
- F. Sample shipping,
- G. Chain of custody,
- H. Sample numbering, and
- I. Precautions from the construction site health and safety plan.

The Contractor shall document sample collection during precipitation.

Samples to be analyzed in the field shall be taken by the Contractor's designated sampling personnel using collection and analysis methods, and equipment calibration specified by the manufacturer of the sampling equipment. Samples to be analyzed by a laboratory, shall be sampled, preserved, and analyzed by a State-certified laboratory in conformance with the requirements in 40 CFR Part 136, "Guidelines Establishing Test Procedures for the Analysis of Pollutants." The Contractor shall identify the State-certified laboratory, sample containers, preservation requirements, holding times, and analysis method in the SAP. A list of State-certified laboratories that are approved by the Department is available at:

<http://www.dhs.ca.gov/ps/ls/ELAP/html/lablist.htm>

### **Sediment and Turbidity**

This project discharges directly into Los Angeles River, a body of water required by the Clean Water Act, Section 303(d) to be listed as impaired due to trash, ammonia, nutrient (algae), copper, and lead. The Contractor shall describe in the SAP the schedule and strategy for monitoring pollutants of concern in the listed body of water in accordance with the provisions in this section.

The Contractor shall develop the SAP schedule so that water quality samples are taken within 2 hours of discharge from precipitation during daylight hours (sunrise to sunset), regardless of the time of year, day of the week, or condition of the construction site. If precipitation occurs again after at least 72 hours of dry weather the Contractor shall take new samples, however, sampling will not be required more than 4 times in 30 days.

In the SAP the Contractor shall identify the locations where runoff sources on the construction site discharge directly into the listed body of water, and the locations where water flows onto the project with the potential to combine with runoff that discharges directly into the listed body of water. These locations shall also be shown on the SWPPP Water Pollution Control Drawings.

The Contractor shall identify locations for collecting water quality samples and the reason for their selection. Sampling locations shall also be shown on the SWPPP Water Pollution Control Drawings. The sampling locations shall include:

- A. Upstream from direct discharges from the construction site,
- B. Immediately downstream from the last point of direct discharge from the construction site, and
- C. Immediately downhill from the locations where water flows onto the right of way.

The Contractor shall specify in the SAP that for discharges into bodies of water listed as impaired due to sedimentation/siltation, samples will be analyzed for both settleable solids in accordance with the requirements of EPA Test Method 160.5, and total suspended solids in accordance with EPA Test Method 160.2; or for suspended sediment concentration in accordance with the requirements in ASTM Designation: D 3977.

For discharges to 303(d) bodies of water listed as impaired due to turbidity the Contractor shall specify in the SAP that samples will be analyzed for turbidity in accordance with the requirements in EPA Test Method 180.1.

### **Non-Visible Pollutants**

This project has the potential to discharge non-visible pollutants in storm water from the construction site. The Contractor shall include in the SAP a description of the sampling and analysis strategy to be implemented on the project for monitoring non-visible pollutants.

In the SAP the Contractor shall identify potential non-visible pollutants that will be present on the construction site associated with the following:

- A. Construction materials and wastes;
- B. Existing contamination due to historical site usage; or
- C. Application of soil amendments, including soil stabilization products, with the potential to alter pH or contribute toxic pollutants to storm water.

The Contractor shall show the locations planned for storage and use of the potential non-visible pollutants on the SWPPP Water Pollution Control Drawings.

The Contractor shall include in the SAP the following list of conditions that require sampling when observed during a storm water inspection:

- A. Materials or wastes containing potential non-visible pollutants are not stored under watertight conditions.
- B. Materials or wastes containing potential non-visible pollutants are stored under watertight conditions, but:
  - 1. A breach, leakage, malfunction, or spill is observed;
  - 2. The leak or spill has not been cleaned up before precipitation; and
  - 3. There is the potential for discharge of non-visible pollutants to surface waters or drainage system.
- C. Construction activities; such as application of fertilizer, pesticide, herbicide, methyl methacrylate concrete sealant, or non-pigmented curing compound; have occurred during precipitation or within 24 hours preceding precipitation, and have the potential to discharge pollutants to surface waters or drainage system.
- D. Soil amendments, including soil stabilization products, with the potential to alter pH levels or contribute toxic pollutants to storm water runoff have been applied, and have the potential to discharge pollutants to surface waters or drainage system (unless independent test data are available that demonstrate acceptable concentrations of non-visible pollutants in the soil amendment).

- E. Storm water runoff from an area contaminated by historical usage of the site has the potential to discharge pollutants to surface waters or drainage system.

The Contractor shall describe in the SAP the schedule for collecting a sample downhill from each non-visible pollutant source and an uncontaminated control sample, during the first 2 hours of discharge from precipitation during daylight hours that result in enough discharge for sample collection. If discharge flows to the non-visible pollutant source, a sample shall be collected immediately downhill from where the discharge enters the Department's right of way. If precipitation occurs again after at least 72 hours of dry weather the Contractor shall take new samples.

In the SAP the Contractor shall identify sampling locations for collecting downstream and control samples, and the reason for their selection. The control sampling location shall be selected so the sample does not come into contact with materials, wastes or areas associated with potential non-visible pollutants or disturbed soil areas. The Contractor shall show non-visible pollutant sampling locations on the SWPPP Water Pollution Control Drawings.

The Contractor shall identify in the SAP the analytical method to be used for downhill and control samples for potential non-visible pollutants on the project.

### **Analytical Results and Evaluation**

The Contractor shall submit a hard copy and electronic copy of water quality analytical results, and quality assurance and quality control data to the Engineer within 5 days of sampling for field analyses, and within 30 days for laboratory analyses. The Contractor shall also provide an evaluation of whether the downhill samples show levels of the tested parameter higher than in the control sample. If downhill or downstream samples show increased levels, the Contractor will assess the water pollution control measures, site conditions, and surrounding influences to determine the probable cause for the increase. As determined by the assessment, the Contractor will repair or modify water pollution control measures to address increases and amend the SWPPP as necessary. Electronic results (in one of the following file formats: .xls, .txt, .csv, .dbs, or .mdb) shall have the following information:

- A. Sample identification number.
- B. Contract number.
- C. Constituent.
- D. Reported value.
- E. Analytical method.
- F. Method detection limit.
- G. Reported limit.

The Contractor shall maintain the water quality sampling documentation and analytical results with the SWPPP on the project site.

If construction activities or knowledge of site conditions change such that discharges or sampling locations change, the Contractor shall amend the SAP in conformance with this section, "Water Pollution Control."

### **IMPLEMENTATION REQUIREMENTS**

The Contractor's responsibility for SWPPP implementation shall continue throughout any temporary suspension of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications.

If the Contractor or the Engineer identifies a deficiency in the implementation of the approved SWPPP, the deficiency shall be corrected immediately, unless an agreed date for correction is approved in writing by the Engineer. The deficiency shall be corrected before the onset of precipitation. If the Contractor fails to correct the deficiency by the agreed date or before the onset of precipitation, the Department may correct the deficiency and deduct the cost of correcting deficiencies from payments.

If the Contractor fails to conform to the provisions of this section, "Water Pollution Control," the Engineer may order the suspension of work until the project complies with the requirements of this section.

### **Year-Round**

The Contractor shall monitor the National Weather Service weather forecast on a daily basis during the contract. The Contractor may use an alternative weather forecasting service if approved by the Engineer. Appropriate water pollution control practices shall be in place before precipitation.

The Contractor may discontinue earthwork operations for a disturbed area for up to 21 days and the disturbed soil area will still be considered active. When earthwork operations in the disturbed area have been completed, the Contractor shall implement appropriate water pollution control practices within 15 days, or before predicted precipitation, whichever occurs first.

### **Rainy Season**

The Contractor shall provide soil stabilization and sediment control practices during the rainy season between October 1 and May 1.

The Contractor shall implement soil stabilization and sediment control practices a minimum of 10 days before the start of the rainy season.

During the defined rainy season, the active disturbed soil area of the project site shall be not more than 2 hectares. The Engineer may approve expansions of the active disturbed soil area limit if requested in writing. The Contractor shall maintain soil stabilization and sediment control materials on site to protect disturbed soil areas.

### **INSPECTION AND MAINTENANCE**

The WPCM shall inspect the water pollution control practices identified in the SWPPP as follows:

- A. Before a forecasted storm,
- B. After precipitation that causes site runoff,
- C. At 24-hour intervals during extended precipitation,
- D. On a predetermined schedule, a minimum of once every 2 weeks outside of the defined rainy season, and
- E. On a predetermined schedule, a minimum of once a week during the defined rainy season.

The WPCM shall oversee the maintenance of the water pollution control practices.

The WPCM shall use the Storm Water Quality Construction Site Inspection Checklist provided in the Preparation Manual or an alternative inspection checklist provided by the Engineer. A copy of the completed site inspection checklist shall be submitted to the Engineer within 24 hours of finishing the inspection.

The Contractor may request approval from the Engineer to suspend inspections of water pollution control practices after work except plant establishment is complete. The Engineer's approval is contingent on approval from the Regional Water Quality Control Board. The Contractor shall not suspend inspections until written approval from the Engineer is received.

### **REPORTING REQUIREMENTS**

If the Contractor identifies discharges into surface waters or drainage systems causing or potentially causing pollution, or if the project receives a written notice or order from a regulatory agency, the Contractor shall immediately inform the Engineer. The Contractor shall submit a written report to the Engineer within 3 days of the discharge, notice or order. The report shall include the following information:

- A. The date, time, location, and nature of the operation, type of discharge and quantity, and the cause of the notice or order.
- B. The water pollution control practices used before the discharge, or before receiving the notice or order.
- C. The date of placement and type of additional or altered water pollution control practices placed after the discharge, or after receiving the notice or order.
- D. A maintenance schedule for affected water pollution control practices.

### **Annual Certifications**

By June 15 of each year, the Contractor shall complete and submit to the Engineer an Annual Certification of Compliance, as contained in the Preparation Manual.

### **PAYMENT**

During each estimate period the Contractor fails to conform to the provisions in this section, "Water Pollution Control," or fails to implement the water pollution control practices shown on the plans or specified elsewhere in these special provisions as items of work, the Department will withhold 25 percent of the progress payment.

Withholds for failure to perform water pollution control work will be in addition to all other withholds provided for in the contract. The Department will return performance-failure withholds in the progress payment following the correction of noncompliance.

The contract lump sum price paid for prepare storm water pollution prevention plan shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in preparing, obtaining approval of, and amending the SWPPP and inspecting water pollution control practices as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Payments for prepare storm water pollution prevention plan will be made as follows:

- A. After the SWPPP has been approved by the Engineer, 50 percent of the contract item price for prepare storm water pollution prevention plan will be included in the monthly progress estimate.
- B. Forty percent of the contract item price for prepare storm water pollution prevention plan will be paid over the life of the contract.
- C. After acceptance of the contract in conformance with the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, payment for the remaining 10 percent of the contract item price for prepare storm water pollution prevention plan will be made in conformance with the provisions in Section 9-1.07A, "Payment Prior to Proposed Final Estimate."

Storm water sampling and analysis will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications. No payment will be made for the preparation, collection, analysis, and reporting of storm water samples where appropriate water pollution control practices are not implemented before precipitation or if a failure of a water pollution control practice is not corrected before precipitation.

Implementation of water pollution control practices in areas outside the highway right of way not specifically provided for in the SWPPP or in these special provisions will not be paid for.

Water pollution control practices for which there are separate contract items of work will be measured and paid for as those contract items of work.

#### **10-1.04 CONSTRUCTION SITE MANAGEMENT**

Construction site management shall consist of controlling potential sources of water pollution before they come in contact with storm water systems or watercourses. The Contractor shall control material pollution and manage waste and non-storm water existing at the construction site by implementing effective handling, storage, use, and disposal practices.

Attention is directed to "Water Pollution Control" of these special provisions regarding the Contractor's appointment of a water pollution control manager (WPCM) for the project.

The Contractor shall train all employees and subcontractors regarding:

- A. Material pollution prevention and control;
- B. Waste management;
- C. Non-storm water management;
- D. Identifying and handling hazardous substances; and
- E. Potential dangers to humans and the environment from spills and leaks or exposure to toxic or hazardous substances.

Training shall take place before starting work on this project. New employees shall receive the complete training before starting work on this project. The Contractor shall have regular meetings to discuss and reinforce spill prevention and control; material delivery, storage, use, and disposal; waste management; and non-storm water management procedures.

Instructions for material and waste handling, storage, and spill reporting and cleanup shall be posted at all times in an open, conspicuous, and accessible location at the construction site.

Nonhazardous construction site waste and excess material shall be recycled when practical or disposed of in accordance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications, unless otherwise specified.

Vehicles and equipment at the construction site shall be inspected by the WPCM on a frequent, predetermined schedule, and by the operator each day of use. Leaks shall be repaired immediately, or the vehicle or equipment shall be removed from the construction site.

#### **SPILL PREVENTION AND CONTROL**

The Contractor shall implement spill and leak prevention procedures when chemicals or hazardous substances are stored. Spills of petroleum products; substances listed under CFR Title 40, Parts 110, 117, and 302; and sanitary and septic waste shall be contained and cleaned up as soon as is safe.

Minor spills involve small quantities of oil, gasoline, paint, or other material that can be controlled by the first responder upon discovery of the spill. Cleanup of minor spills includes:

- A. Containing the spread of the spill,
- B. Recovering the spilled material using absorption,
- C. Cleaning the contaminated area, and
- D. Disposing of contaminated material promptly and properly.

Semi-significant spills are those that can be controlled by the first responder with the help of other personnel. Cleanup of semi-significant spills shall be immediate. Cleanup of semi-significant spills includes:

- A. Containing the spread of the spill;
- B. Recovering the spilled material using absorption if the spill occurs on paved or an impermeable surface;
- C. Containing the spill with an earthen dike and digging up contaminated soil for disposal if the spill occurs on dirt;
- D. Covering the spill with plastic or other material to prevent contaminating runoff if the spill occurs during precipitation; and
- E. Disposing of contaminated material promptly and properly.

Significant or hazardous spills are those that cannot be controlled by construction personnel. Notifications of these spills shall be immediate. The following steps shall be taken:

- A. Construction personnel shall not attempt to cleanup the spill until qualified staff have arrived;
- B. Notify the Engineer and follow up with a written report;
- C. Obtain the services of a spills contractor or hazardous material team immediately;
- D. Notify the local emergency response team by dialing 911 and county officials at the emergency phone numbers kept on the construction site;
- E. Notify the Governor's Office of Emergency Services Warning Center at (805) 852-7550;
- F. Notify the National Response Center at (800) 424-8802 regarding spills of Federal reportable quantities in conformance with CFR Title 40, Parts 110, 119, and 302;
- G. Notify other agencies as appropriate, including:
  - 1. Fire Department,
  - 2. Public Works Department,
  - 3. Coast Guard,
  - 4. Highway Patrol,
  - 5. City Police or County Sheriff Department,
  - 6. Department of Toxic Substances,
  - 7. California Division of Oil and Gas,
  - 8. Cal OSHA, or
  - 9. Regional Water Resources Control Board.

The WPCM shall oversee and enforce proper spill prevention and control measures. Minor, semi-significant, and significant spills shall be reported to the Contractor's WPCM who shall notify the Engineer immediately.

The Contractor shall prevent spills from entering storm water runoff before and during cleanup. Spills shall not be buried or washed with water.

The Contractor shall keep material or waste storage areas clean, well organized, and equipped with enough cleanup supplies for the material being stored. Plastic shall be placed under paving equipment when not in use to catch drips.

#### **MATERIAL MANAGEMENT**

Material shall be delivered, used, and stored for this contract in a manner that minimizes or eliminates discharge of material into the air, storm drain systems, or watercourses.

The Contractor shall implement the practices described in this section when taking delivery of, using, or storing the following materials:

- A. Hazardous chemicals including:
  - 1. Acids,
  - 2. Lime,
  - 3. Glues,
  - 4. Adhesives,
  - 5. Paints,
  - 6. Solvents, and
  - 7. Curing compounds;
- B. Soil stabilizers and binders;
- C. Fertilizers;
- D. Detergents;
- E. Plaster;
- F. Petroleum products including:

1. Fuel,
2. Oil, and
3. Grease;

G. Asphalt components and concrete components; and  
H. Pesticides and herbicides.

The Contractor shall supply the Material Safety Data Sheet to the Engineer for material used or stored. The Contractor shall keep an accurate inventory of material delivered and stored at the construction site.

Employees trained in emergency spill cleanup procedures shall be present when hazardous materials or chemicals are unloaded.

The Contractor shall use recycled or less hazardous products when practical.

### **Material Storage**

The Contractor shall store liquids, petroleum products, and substances listed in CFR Title 40, Parts 110, 117, and 302 in containers or drums approved by the United States Environmental Protection Agency, and place them in secondary containment facilities.

Secondary containment facilities shall be impervious to the materials stored there for a minimum contact time of 72 hours.

Throughout the rainy season secondary containment facilities shall be covered during non-working days and when precipitation is predicted. Secondary containment facilities shall be adequately ventilated.

The Contractor shall keep the secondary containment facility free of accumulated rainwater or spills. After precipitation, or in the event of spills or leaks, accumulated liquid shall be collected and placed into drums within 24 hours. These liquids shall be handled as hazardous waste in accordance with the provisions in "Hazardous Waste" of these special provisions, unless testing determines them to be nonhazardous.

Incompatible materials, such as chlorine and ammonia, shall not be stored in the same secondary containment facility.

Materials shall be stored in the original containers with the original product labels maintained in legible condition. Damaged or illegible labels shall be replaced immediately.

The secondary containment facility shall have the capacity to contain precipitation from a 24-hour-long, 25-year storm; and 10 percent of the aggregate volume of all containers, or all of the volume of the largest container within the facility, whichever is greater.

The Contractor shall store bagged or boxed material on pallets. Throughout the rainy season, bagged or boxed material shall be protected from wind and rain during non-working days and when precipitation is predicted.

The Contractor shall provide sufficient separation between stored containers to allow for spill cleanup or emergency response access. Storage areas shall be kept clean, well organized, and equipped with cleanup supplies appropriate for the materials being stored.

The Contractor shall repair or replace perimeter controls, containment structures, covers, and liners as needed. Storage areas shall be inspected before and after precipitation, and at least weekly during other times.

### **Stockpile Management**

The Contractor shall reduce or eliminate potential air and water pollution from stockpiled material including soil, paving material, or pressure treated wood. Stockpiles shall be located out of floodplains when possible, and at least 15 m from concentrated flows of storm water, drainage courses, or inlets unless written approval is obtained from the Engineer.

The Contractor may discontinue adding or removing material for up to 21 days and a stockpile will still be considered active.

The Contractor shall protect active stockpiles with plastic or geotextile cover, soil stabilization measures, or with linear sediment barrier when precipitation is predicted. Active stockpiles of cold mix asphalt concrete shall be placed on an impervious surface and covered with plastic when precipitation is predicted.

The Contractor shall protect inactive soil stockpiles with a plastic or geotextile cover, or with soil stabilization measures at all times during the rainy season. A linear sediment barrier around the perimeter of the stockpile shall also be used. During the non-rainy season soil stockpiles shall be covered and protected with a linear sediment barrier when precipitation is predicted. The Contractor shall control wind erosion during dry weather as provided in Section 10, "Dust Control," of the Standard Specifications.

Stockpiles of portland cement concrete rubble, asphalt concrete (AC), hot mix asphalt (HMA), AC and HMA rubble, aggregate base, or aggregate subbase shall be covered with plastic or geotextile, or protected with a linear sediment barrier at all times during the rainy season, and when precipitation is predicted during the non-rainy season.

Stockpiles of cold mix asphalt concrete shall be placed on and covered with impermeable material at all times during the rainy season, and when precipitation is predicted during the non-rainy season.

Stockpiles of pressure treated wood shall be covered with impermeable material and placed on pallets at all times during the rainy season, and when precipitation is predicted during the non-rainy season.

The Contractor shall repair or replace linear sediment barriers and covers as needed or as directed by the Engineer to keep them functioning properly. Sediment shall be removed when it accumulates to 1/3 of the linear sediment barrier height.

## **WASTE MANAGEMENT**

### **Solid Waste**

The Contractor shall not allow litter or debris to accumulate anywhere on the construction site, including storm drain grates, trash racks, and ditch lines. The Contractor shall pick up and remove trash and debris from the construction site at least once a week. The WPCM shall monitor solid waste storage and disposal procedures on the construction site. The Contractor shall provide enough dumpsters of sufficient size to contain the solid waste generated by the project. Dumpsters shall be emptied when refuse reaches the fill line. Dumpsters shall be watertight. The Contractor shall not wash out dumpsters on the construction site. The Contractor shall provide additional containers and more frequent pickup during the demolition phase of construction

Solid waste includes:

- A. Brick,
- B. Mortar,
- C. Timber,
- D. Metal scraps,
- E. Sawdust,
- F. Pipe,
- G. Electrical cuttings,
- H. Non-hazardous equipment parts,
- I. Styrofoam and other packaging materials,
- J. Vegetative material and plant containers from highway planting, and
- K. Litter and smoking material, including litter generated randomly by the public.

Trash receptacles shall be provided and used in the Contractor's yard, field trailers, and locations where workers gather for lunch and breaks.

### **Hazardous Waste**

The Contractor shall implement hazardous waste management practices when waste is generated on the construction site from the following substances:

- A. Petroleum products,
- B. Asphalt products,
- C. Concrete curing compound,
- D. Pesticides,
- E. Acids,
- F. Paints,
- G. Stains,
- H. Solvents,
- I. Wood preservatives,
- J. Roofing tar, and
- K. Materials classified as hazardous by California Code of Regulations, Title 22, Division 4.5; or listed in CFR Title 40, Parts 110, 117, 261, or 302.

Nothing in these special provisions shall relieve the Contractor of the responsibility for compliance with Federal, State, and local laws regarding storage, handling, transportation, and disposal of hazardous wastes.

Hazardous material existing on the construction site before mobilization shall be handled and disposed of in accordance with "Aerially Deposited Lead" and "Air Quality – Basic NESHAP Asbestos Notification" of these special provisions.

The WPCM shall oversee and enforce hazardous waste management practices. Production of hazardous materials and hazardous waste on the construction site shall be kept to a minimum. Perimeter controls, containment structures, covers, and liners shall be repaired or replaced when damaged.

The Contractor shall have a laboratory certified by the Department of Health Services (DHS) sample and test waste when hazardous material levels are unknown to determine safe methods for storage and disposal.

The Contractor shall segregate potentially hazardous waste from nonhazardous waste at the construction site. Hazardous waste shall be handled, stored, and disposed of as required in California Code of Regulations, Title 22, Division 4.5, Section 66262.34; and in CFR Title 49, Parts 261, 262, and 263.

The Contractor shall store hazardous waste in sealed containers constructed and labeled with the contents and date accumulated as required in California Code of Regulations, Title 22, Division 4.5; and in CFR Title 49, Parts 172, 173, 178, and 179. Hazardous waste containers shall be kept in temporary containment facilities conforming to the provisions in "Material Storage" of these special provisions.

There shall be adequate storage volume and containers shall be conveniently located for hazardous waste collection. Containers of hazardous waste shall not be overfilled and hazardous wastes shall not be mixed. Containers of dry waste that are not watertight shall be stored on pallets. The Contractor shall not allow potentially hazardous waste to accumulate on the ground. Hazardous waste shall be stored away from storm drains, watercourses, moving vehicles, and equipment.

The Contractor shall clean water based or oil based paint from brushes or equipment within a contained area and shall not contaminate soil, watercourses, or storm drain systems. Paints, thinners, solvents, residues, and sludges that cannot be recycled or reused shall be disposed of as hazardous waste. When thoroughly dry, latex paint and paint cans, used brushes, rags, absorbent materials, and drop cloths shall be disposed of as solid waste.

The Contractor shall dispose of hazardous waste within 90 days of being generated. Hazardous waste shall be disposed of by a licensed hazardous waste transporter using uniform hazardous waste manifest forms and taken to a Class I Disposal Site. A copy of the manifest shall be provided to the Engineer.

### **Contaminated Soil**

The Contractor shall identify contaminated soil from spills or leaks by noticing discoloration, odors, or differences in soil properties. Soil with evidence of contamination shall be sampled and tested by a laboratory certified by DHS. If levels of contamination are found to be hazardous, the soil shall be handled and disposed of as hazardous waste.

Contaminated soil existing on the construction site before mobilization shall be handled and disposed of in accordance with "Material Containing Aerially Deposited Lead" of these special provisions.

The Contractor shall prevent the flow of water, including ground water, from mixing with contaminated soil by using one or a combination of the following measures:

- A. Berms,
- B. Cofferdams,
- C. Grout curtains,
- D. Freeze walls, or
- E. Concrete seal course.

If water mixes with contaminated soil and becomes contaminated, the water shall be sampled and tested by a laboratory certified by the DHS. If levels of contamination are found to be hazardous, the water shall be handled and disposed of as hazardous waste.

### **Concrete Waste**

The Contractor shall implement practices to prevent the discharge of portland cement concrete, AC, or HMA waste into storm drain systems or watercourses.

Portland cement concrete, AC, or HMA waste shall be collected at the following locations and disposed of:

- A. Where concrete material, including grout, is used;
- B. Where concrete dust and debris result from demolition;
- C. Where sawcutting, coring, grinding, grooving, or hydro-concrete demolition of portland cement concrete, AC, or HMA creates a residue or slurry; or
- D. Where concrete trucks or other concrete-coated equipment is cleaned at the construction site.

### **Sanitary and Septic Waste**

Wastewater from sanitary or septic systems shall not be discharged or buried within the Department right of way. The WPCM shall inspect sanitary or septic waste storage and monitor disposal procedures at least weekly. Sanitary facilities that discharge to the sanitary sewer system shall be properly connected and free from leaks.

The Contractor shall obtain written approval from the local health agency, city, county, and sewer district before discharging from a sanitary or septic system directly into a sanitary sewer system, and provide a copy to the Engineer. The Contractor shall comply with local health agency requirements when using an on-site disposal system.

## **Liquid Waste**

The Contractor shall not allow construction site liquid waste, including the following, to enter storm drain systems or watercourses:

- A. Drilling slurries or fluids,
- B. Grease-free or oil-free wastewater or rinse water,
- C. Dredgings,
- D. Liquid waste running off a surface including wash or rinse water, or
- E. Other non-storm water liquids not covered by separate permits.

The Contractor shall hold liquid waste in structurally sound, leak proof containers such as:

- A. Sediment traps,
- B. Roll-off bins, or
- C. Portable tanks.

Liquid waste containers shall be of sufficient quantity and volume to prevent spills and leaks. The containers shall be stored at least 15 m from storm drains, watercourses, moving vehicles, and equipment.

The Contractor shall remove and dispose of deposited solids from sediment traps as provided in "Solid Waste" of these special provisions, unless determined infeasible by the Engineer.

Liquid waste may require testing to determine hazardous material content before disposal.

Drilling fluids and residue shall be disposed of outside the highway right of way. If the Engineer determines that an appropriate location is available, fluids and residue exempt under California Code of Regulations, Title 23, Section 2511(g) may be dried by infiltration and evaporation in a leak proof container. The remaining solid waste may be disposed of as provided in "Solid Waste" of these special provisions.

## **NON-STORM WATER MANAGEMENT**

### **Water Control and Conservation**

The Contractor shall prevent erosion or the discharge of pollutants into storm drain systems or watercourses by managing the water used for construction operations. The Contractor shall obtain the Engineer's approval before washing anything on the construction site with water that could discharge into a storm drain system or watercourse. Discharges shall be reported to the Engineer immediately.

The Contractor shall implement water conservation practices when water is used on the construction site. Irrigation areas shall be inspected and watering schedules shall be adjusted to prevent erosion, excess watering, or runoff. The Contractor shall shut off the water source to broken lines, sprinklers, or valves, and they shall be repaired as soon as possible. When possible, water from waterline flushing shall be reused for landscape irrigation. Paved areas shall be swept and vacuumed, not washed with water.

Construction water runoff, including water from water line repair, shall be directed to areas to infiltrate into the ground and shall not be allowed to enter storm drain systems or watercourses. Spilled water shall not be allowed to escape water truck filling areas. When possible, the Contractor shall direct water from off-site sources around the construction site, or shall minimize contact with the construction site.

### **Illegal Connection and Discharge Detection and Reporting**

The Contractor shall inspect the construction site and the site perimeter before beginning work for evidence of illegal connections, discharges, or dumping. Subsequently, the construction site and perimeter shall be inspected on a frequent, predetermined schedule.

The Contractor shall immediately notify the Engineer when illegal connections, discharges, or dumping are discovered. The Contractor shall take no further action unless directed by the Engineer. Unlabeled or unidentifiable material shall be assumed to be hazardous.

The Contractor shall look for the following evidence of illegal connections, discharges, or dumping:

- A. Debris or trash piles,
- B. Staining or discoloration on pavement or soils,
- C. Pungent odors coming from drainage systems,
- D. Discoloration or oily sheen on water,
- E. Stains or residue in ditches, channels or drain boxes,
- F. Abnormal water flow during dry weather,
- G. Excessive sediment deposits,

- H. Nonstandard drainage junction structures, or
- I. Broken concrete or other disturbances near junction structures.

### **Vehicle and Equipment Cleaning**

The Contractor shall limit vehicle and equipment cleaning or washing on the construction site to that necessary to control vehicle tracking or hazardous waste. Vehicles and equipment shall not be cleaned on the construction site with soap, solvents, or steam until the Engineer has been notified. The resulting waste shall be contained and recycled, or disposed of as provided in "Liquid Waste" or "Hazardous Waste" of these special provisions, whichever is applicable. The Contractor shall not use diesel to clean vehicles or equipment, and shall minimize the use of solvents.

The Contractor shall clean or wash vehicles and equipment in a structure equipped with disposal facilities. If using a structure is not possible, vehicles and equipment shall be cleaned or washed in an outside area with the following characteristics:

- A. Located at least 15 m from storm drainage systems or watercourses,
- B. Paved with AC, HMA or portland cement concrete,
- C. Surrounded by a containment berm, and
- D. Equipped with a sump to collect and dispose of wash water.

When washing vehicles or equipment with water, the Contractor shall use as little water as possible. Hoses shall be equipped with a positive shutoff valve.

Wash racks shall discharge to a recycle system or to another system approved by the Engineer. Sumps shall be inspected regularly, and liquids and sediments shall be removed as needed.

### **Vehicle and Equipment Fueling and Maintenance**

The Contractor shall fuel or perform maintenance on vehicles and equipment off the construction site whenever practical. When fueling or maintenance must be done at the construction site, the Contractor shall designate a site, or sites, and obtain approval from the Engineer before using. The fueling or maintenance site shall be protected from storm water, shall be on level ground, and shall be located at least 15 m from drainage inlets or watercourses. The WPCM shall inspect the fueling or maintenance site regularly. Mobile fueling or maintenance shall be kept to a minimum.

The Contractor shall use containment berms or dikes around the fueling and maintenance area. Adequate amounts of absorbent spill cleanup material and spill kits shall be kept in the fueling and maintenance area and on fueling trucks. Spill cleanup material and kits shall be disposed of immediately after use. Drip pans or absorbent pads shall be used during fueling or maintenance unless performed over an impermeable surface.

Fueling or maintenance operations shall not be left unattended. Fueling nozzles shall be equipped with an automatic shutoff control. Vapor recovery fueling nozzles shall be used where required by the Air Quality Management District. Nozzles shall be secured upright when not in use. Fuel tanks shall not be topped-off.

The Contractor shall recycle or properly dispose of used batteries and tires.

### **Material and Equipment Used Over Water**

Drip pans and absorbent pads shall be placed under vehicles or equipment used over water, and an adequate supply of spill cleanup material shall be kept with the vehicle or equipment. Drip pans or plastic sheeting shall be placed under vehicles or equipment on docks, barges, or other surfaces over water when the vehicle or equipment will be idle for more than one hour.

The Contractor shall provide watertight curbs or toe boards on barges, platforms, docks, or other surfaces over water to contain material, debris, and tools. Material shall be secured to prevent spills or discharge into water due to wind.

### **Structure Removal Over or Adjacent to Water**

The Contractor shall not allow demolished material to enter storm water systems or watercourses. The Contractor shall use covers and platforms approved by the Engineer to collect debris. Attachments shall be used on equipment to catch debris on small demolition operations. Debris catching devices shall be emptied regularly and debris shall be handled as provided in "Waste Management" of these special provisions.

The WPCM shall inspect demolition sites within 15 m of storm water systems or watercourses every day.

### **Paving, Sealing, Sawcutting, and Grinding Operations**

The Contractor shall prevent the following material from entering storm drain systems or water courses:

- A. Cementitious material,
- B. Asphaltic material,

- C. Aggregate or screenings,
- D. Grinding or sawcutting residue,
- E. Pavement chunks, or
- F. Shoulder backing.

The Contractor shall cover drainage inlets and use linear sediment barriers to protect downhill watercourses until paving, sealing, sawcutting, or grinding operations are completed and excess material has been removed. Drainage inlets and manholes shall be covered during the application of seal coat, tack coat, slurry seal, or fog seal.

During the rainy season or when precipitation is predicted, paving, sawcutting, and grinding operations shall be limited to places where runoff can be captured. Seal coat, tack coat, slurry seal, or fog seal operations shall not begin if precipitation is predicted for the application or the curing period. The Contractor shall not excavate material from existing roadways during precipitation.

The Contractor shall vacuum up slurry from sawcutting operations immediately after the slurry is produced. Slurry shall not be allowed to run onto lanes open to public traffic or off the pavement.

The Contractor shall collect residue from portland cement concrete grinding operations with a vacuum attachment on the grinding machine. The residue shall not be left on the pavement or allowed to flow across the pavement.

Material excavated from existing roadways may be stockpiled as provided in "Stockpile Management" of these special provisions if approved by the Engineer. AC or HMA chunks used in embankment shall be placed above the water table and covered by at least 0.3-m of material.

Substances used to coat asphalt trucks and equipment shall not contain soap, foaming agents, or toxic chemicals.

### **Thermoplastic Striping and Pavement Markers**

Thermoplastic striping and preheating equipment shutoff valves shall work properly at all times when on the construction site. The Contractor shall not preheat, transfer, or load thermoplastic within 15 m of drainage inlets or watercourses. The Contractor shall not fill the preheating container to more than 150 mm from the top. Truck beds shall be cleaned daily of scraps or melted thermoplastic.

The Contractor shall not unload, transfer, or load bituminous material for pavement markers within 15 m of drainage inlets or watercourses. All pressure shall be released from melting tanks before removing the lid to fill or service. Melting tanks shall not be filled to more than 150 mm from the top.

The Contractor shall collect bituminous material from the roadway after marker removal.

### **Pile Driving**

The Contractor shall keep spill kits and cleanup material at pile driving locations. Pile driving equipment shall be parked over drip pans, absorbent pads, or plastic sheeting where possible. When not in use, pile driving equipment shall be stored at least 15 m from concentrated flows of storm water, drainage courses, or inlets. The Contractor shall protect pile driving equipment by parking it on plywood and covering it with plastic when precipitation is predicted. The WPCM shall inspect the pile driving area every day for leaks and spills.

The Contractor shall use vegetable oil instead of hydraulic fluid when practical.

### **Concrete Curing**

The Contractor shall not overspray chemical curing compound. Drift shall be minimized by spraying as close to the concrete as possible. Drainage inlets shall be covered before applying curing compound.

The Contractor shall minimize the use and discharge of water by using wet blankets or similar methods to maintain moisture when curing concrete.

### **Concrete Finishing**

The Contractor shall collect and dispose of water and solid waste from high-pressure water blasting. Drainage inlets within 15 m shall be covered before sandblasting. The nozzle shall be kept as close to the surface of the concrete as possible to minimize drift of dust and blast material. Blast residue may contain hazardous material.

Containment structures for concrete finishing operations shall be inspected for damage before each day of use and before predicted precipitation. Liquid and solid waste shall be removed from the containment structure after each work shift.

### **DEWATERING**

Dewatering shall consist of discharging accumulated storm water, ground water, or surface water from excavations or temporary containment facilities. The Contractor shall discharge water within the limits of the project.

Dewatering discharge shall not cause erosion, scour, or sedimentary deposits that impact natural bedding materials.

The Contractor shall conduct dewatering activities in accordance with the Field Guide for Construction Dewatering available at:

Before dewatering the Contractor shall submit a Dewatering and Discharge Plan to the Engineer in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications and "Water Pollution Control," of these special provisions. At a minimum, the Dewatering and Discharge Plan shall include the following:

- A. A title sheet and table of contents;
- B. A description of the dewatering and discharge operations detailing the locations, quantity of water, equipment, and discharge point;
- C. The estimated schedule for dewatering and discharge (begin and end dates, intermittent or continuous);
- D. Discharge alternatives such as dust control or percolation; and
- E. Visual monitoring procedures with inspection log.

The Contractor shall not discharge storm water or non-storm water that has an odor, discoloration other than sediment, an oily sheen, or foam on the surface and shall notify the Engineer immediately upon discovery.

If water cannot be discharged within the project limits due to site constraints it shall be disposed of in the same manner specified for material in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

### **PAYMENT**

The contract lump sum price paid for construction site management shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in spill prevention and control, material management, waste management, non-storm water management, and dewatering and identifying, sampling, testing, handling, and disposing of hazardous waste, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **10-1.05 STREET SWEEPING**

#### **GENERAL**

##### **Summary**

This work includes street sweeping.

The SWPPP must describe and include the use of street sweeping as a water pollution control practice for sediment control and tracking control.

##### **Submittals**

At least 5 business days before starting clearing and grubbing, earthwork, or other activities with the potential for tracking sediment or debris, submit:

1. Number of sweepers described in the SWPPP
2. Type of sweeper technology

##### **Quality Control and Assurance**

Retain and submit records of street sweeping including:

1. Quantity of sweeping waste disposal
2. Sweeping times and locations

### **CONSTRUCTION**

#### **Street Sweepers**

Sweepers must use one of these technologies:

1. Mechanical sweeper followed by a vacuum-assisted sweeper
2. Vacuum-assisted dry (waterless) sweeper
3. Regenerative-air sweeper

#### **Operation**

Street sweeping must be done at:

1. Paved roads at job site entrance and exit locations
2. Paved areas within the job site that flow to storm drains or water bodies

Street sweeping must be done:

1. During clearing and grubbing activities
2. During earthwork activities
3. During trenching activities
4. During roadway structural section activities
5. When vehicles are entering and leaving the job site
6. After soil disturbing activities
7. After observing offsite tracking of material

Monitor paved areas and roadway within the jobsite. Street sweeping must be done:

1. Within 24 hours, if sediment or debris is observed during activities that do not require sweeping

At least 1 sweeper must be on the job site at all times when sweeping work is required. The sweeper must be in good working order.

Perform street sweeping to minimize dust. If dust generation is excessive or sediment pickup is ineffective, use water or a vacuum.

You may stockpile collected material on the jobsite according to the approved SWPPP. Dispose of collected material at least once per week.

Material collected during street sweeping must be removed and disposed of under Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Your WPCM must inspect paved roads at job site access points:

1. Daily if earthwork and other sediment or debris generating activities occur daily
2. Weekly if earthwork and other sediment or debris generating activities do not occur daily
3. When the National Weather Service predicts precipitation with a probability of at least 30 percent

## **MEASUREMENT AND PAYMENT**

The contract lump sum price paid for street sweeping includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in street sweeping, including disposal of collected material, as shown on the plans, as specified in the Standard Specifications, these special provisions, and as directed by the Engineer.

### **10-1.06 TEMPORARY HYDRAULIC MULCH (BONDED FIBER MATRIX)**

#### **GENERAL**

##### **Summary**

This work includes applying, maintaining, and removing temporary hydraulic mulch (bonded fiber matrix). Hydraulic mulch uses a mixture of fiber, tackifier, and water to stabilize active and nonactive disturbed soil areas.

The SWPPP must describe and include the use of temporary hydraulic mulch (bonded fiber matrix) as a water pollution control practice for soil stabilization.

##### **Submittals**

At least 5 business days before applying hydraulic mulch, submit:

1. Material Safety Data Sheet for the tackifier.
2. Product label describing the tackifier as an erosion control product.
3. List of pollutant indicators and potential pollutants for the use of temporary hydraulic mulch. Pollutant indicators are described under "Sampling and Analysis Plan for Non-Visible Pollutants" in the Preparation Manual.
4. Determination of acute and chronic toxicity for aquatic organisms conforming to EPA methods for the tackifier.
5. Composition of ingredients including chemical formulation.

Submit a Certificate of Compliance as specified in Section 6-1.07, "Certificates of Compliance" of the Standard Specifications for:

1. Tackifier
2. Fiber

**Quality Control and Assurance**

Retain and submit records of temporary hydraulic mulch applications including:

1. Compliance with specified rates
2. Application area
3. Application time
4. Quantity

**MATERIALS**

**Tackifier**

The tackifier must be:

1. Nonflammable
2. Nontoxic to aquatic organisms
3. Free from growth or germination inhibiting factors
4. Bonded to the fiber or prepackaged with the fiber by the manufacturer
5. At least 10 percent of the weight of the dry fiber and include the weight of the activating agents and additives
6. Organic, high viscosity colloidal polysaccharide with activating agents, or a blended hydrocolloid-based binder

**Fiber**

Fiber must be:

1. Long strand, whole wood fibers, thermo-mechanically processed from clean, whole wood chips
2. Not made from sawdust, cardboard, paper, or paper byproducts
3. At least 25 percent of fibers 10 mm long
4. At least 50 percent held on a 710 µm sieve
5. Free from lead paint, printing ink, varnish, petroleum products, seed germination inhibitors, or chlorine bleach
6. Free from synthetic or plastic materials
7. At most 7 percent ash

**Coloring Agent**

Use a biodegradable nontoxic coloring agent free from copper, mercury, and arsenic to ensure the hydraulic mulch contrasts with the application area.

**CONSTRUCTION**

**Application**

Dilute hydraulic mulch with water to spread the mulch evenly.

Use hydroseeding equipment to apply hydraulic mulch.

Apply hydraulic mulch:

1. In the proportions indicated in the table below. Successive applications or passes may be needed to achieve the required proportion rate:

Material	Application Rate kg/ha
Bonded Fiber (includes fiber and tackifier material)	4,000

2. To form a continuous mat with no gaps between the mat and the soil surface.
3. From 2 or more directions to achieve a continuous mat.
4. In layers to avoid slumping and to aid drying.
5. During dry weather or at least 24 hours before predicted rain.

Do not apply hydraulic mulch if:

1. Water is standing on or moving across the soil surface
2. Soil is frozen
3. Air temperature is below 4 °C during the tackifier curing period unless allowed by the tackifier manufacturer and approved by the Engineer

Do not over-spray hydraulic mulch onto the traveled way, sidewalks, lined drainage channels, or existing vegetation.

#### **Maintenance**

Reapply hydraulic mulch within 24 hours of discovering visible erosion unless the Engineer approves a longer period.

#### **Removal**

Remove hydraulic mulch by mechanically blending it into the soil with track laying equipment, disking, or other approved method.

Temporary hydraulic mulch disturbed or displaced by your vehicles, equipment, or operations must be reapplied at your expense.

Cleanup, repair, removal, disposal, or replacement due to improper installation or your negligence are not included in the cost for performing maintenance.

### **MEASUREMENT AND PAYMENT**

Temporary hydraulic mulch (bonded fiber matrix) is measured by the square meter from measurements along the slope of the areas covered by the hydraulic mulch.

The contract price paid per square meter for temporary hydraulic mulch (bonded fiber matrix) includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in applying temporary hydraulic mulch, complete in place, including removal of hydraulic mulch, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The State and you share the cost of maintaining the temporary hydraulic mulch. The State determines the maintenance cost under Section 9-1.03, "Force Account Payment," of the Standard Specifications and pays you one-half of that cost.

### **10-1.07 TEMPORARY EROSION CONTROL BLANKET**

Temporary erosion control blanket shall be furnished, installed, maintained, and later removed in ditches or swales, on embankment slopes, and excavation slopes at the locations shown on the approved Storm Water Pollution Prevention Plan (SWPPP) in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Temporary erosion control blanket shall be one of the water pollution control practices for soil stabilization. The SWPPP shall include the use of temporary erosion control blanket.

#### **MATERIALS**

Materials for the temporary erosion control blanket shall conform to the provisions in Section 20-2, "Materials," of the Standard Specifications and these special provisions. Temporary erosion control blanket shall be a rolled erosion control product (RECP) and shall be classified either as temporary and degradable or long-term and nondegradable.

#### **Temporary and Degradable**

Temporary and degradable RECP shall be as follows:

1. Machine produced mats consisting of curled wood excelsior with 80 percent of the fiber 150 mm or longer. The excelsior blanket shall be of consistent thickness with wood fiber evenly distributed over the entire area of the blanket. The top surface of the blanket shall be covered with extruded photodegradable plastic netting or lightweight nonsynthetic netting. The blanket shall be smolder resistant without the use of chemical additives, nontoxic, and noninjurious to plant and animal life. Excelsior blanket shall be furnished in rolled strips with a minimum mass per unit area of 0.40-kg/m<sup>2</sup>.
2. Machine produced mats consisting of 70 percent straw and 30 percent coconut fiber with extruded photodegradable plastic netting or lightweight nonsynthetic netting on the top and bottom surfaces of the blanket. The straw and coconut shall adhere to the netting using thread or glue strip. The straw and coconut blanket shall be of consistent thickness, with straw and coconut fiber evenly distributed over the entire area of the blanket. Straw and coconut fiber blanket shall be furnished in rolled strips with a minimum mass per unit area of 0.27-kg/m<sup>2</sup>.

3. Machine produced mats consisting of 100 percent coir consisting of coconut fiber with extruded photodegradable plastic netting or lightweight nonsynthetic netting on the top and bottom surfaces of the blanket. The coconut fiber shall adhere to the netting using thread or glue strip. The coconut blanket shall be of consistent thickness, with coconut fiber evenly distributed over the entire area of the blanket. Coconut fiber blanket shall be furnished in rolled strips with a minimum mass per unit area of 0.27-kg/m<sup>2</sup>.
4. Machine woven netting consisting of 100 percent spun coir consisting of coconut fiber with an average open area of 63 percent to 70 percent. Coconut coir netting shall be furnished in rolled strips with a minimum mass per unit area of 0.40-kg/m<sup>2</sup>.

#### **Long-Term and Nondegradable Erosion Control Blanket**

The long-term and nondegradable erosion control blanket shall be a geotextile blanket conforming to the provisions in Section 88-1.04, "Rock Slope Protection Fabric," of the Standard Specifications for rock slope protection fabric (Type A).

#### **Staples**

An alternative attachment device such as geotextile pins or plastic pegs may be used instead of staples. The Contractor shall submit a sample of the alternative attachment device for the Engineer's approval before installation.

#### **INSTALLATION**

Temporary erosion control blanket shall be installed as follows:

1. Temporary erosion control blanket strips shall be placed loosely along the ditch or swale with the longitudinal edges and joints parallel to the centerline of the ditch or swale. Longitudinal joints of blankets shall be overlapped and stapled. The blanket on the upper portion of the slope shall overlap the blanket on the lower portion of the slope. Transverse joints of blankets shall be secured in intermediate joint trenches. Ends of the blankets shall be secured in place in key trenches.
2. Temporary erosion control blanket strips shall be placed loosely on the embankment or excavation slope with the longitudinal joints perpendicular to the slope contour lines. Longitudinal and transverse joints of blankets shall be overlapped and stapled. For transverse joints, the blanket on the upper portion of the slope shall overlap the blanket on the lower portion of the slope. For longitudinal joints, the blanket on the side of the prevailing wind shall overlap the blanket on the downwind side of the slope. Ends of the blankets shall be secured in place in key trenches.
3. Temporary erosion control blanket strips shall be secured in place with wire staples. Staples shall be driven perpendicular to the slopes.

When no longer required, as determined by the Engineer, temporary erosion control blanket fabric shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Ground disturbances, including holes and depressions caused by the installation and removal of the temporary erosion control blanket shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

#### **MAINTENANCE**

Sediment in excess of 50 mm above the surface of the blanket, or when directed by the Engineer, shall be removed. Removed sediment shall be deposited within the project limits and shall not be subject to erosion by wind or water.

Temporary erosion control blanket shall be repaired or replaced on the same day the damage occurs. When washouts occur between joints or beneath the temporary erosion control blanket, the blanket shall be repaired. Temporary erosion control blanket shall be repaired or replaced when the area treated with temporary erosion control blanket becomes exposed or exhibits visible erosion. Temporary erosion control blanket damaged during the progress of work or resulting from the Contractor's vehicles, equipment, or operations shall be repaired or replaced at the expense of the Contractor.

#### **MEASUREMENT AND PAYMENT**

The quantity of temporary erosion control blanket to be paid for will be measured by the square meter of the actual area covered excluding overlaps.

The contract price paid per square meter for temporary erosion control blanket shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing temporary erosion control blanket, complete in place, including trench excavation and backfill, maintenance, and removal of temporary erosion control blanket, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### 10-1.08 TEMPORARY CONCRETE WASHOUT FACILITY

Temporary concrete washout facilities shall be constructed, maintained, and later removed at the locations shown on the approved Storm Water Pollution Prevention Plan (SWPPP) in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Temporary concrete washout facilities shall be one of the water pollution control practices for waste management and materials pollution control. The SWPPP shall include the use of temporary concrete washout facilities.

#### MATERIALS

##### Plastic Liner

Plastic liners shall be single ply, new polyethylene sheeting, a minimum of 0.25-mm thick and shall be free of holes, punctures, tears or other defects that compromise the impermeability of the material. Plastic liners shall not have seams or overlapping joints.

##### Gravel-filled Bags

Gravel bag fabric shall be nonwoven polypropylene geotextile (or comparable polymer) and shall conform to the following requirements:

Specification	Requirements
Mass per unit area, grams per square meter, min. ASTM Designation: D 5261	270
Grab tensile strength (25-mm grip), kilonewtons, min. ASTM Designation: D4632*	0.89
Ultraviolet stability, percent tensile strength retained after 500 hours, ASTM Designation: D4355, xenon arc lamp method	70

\* or appropriate test method for specific polymer

Gravel bags shall be between 600 mm and 800 mm in length, and between 400 mm and 500 mm in width.

Yarn used for binding gravel bags shall be as recommended by the manufacturer or bag supplier and shall be of a contrasting color.

Gravel shall be between 10 mm and 20 mm in diameter, and shall be clean and free from clay balls, organic matter, and other deleterious materials.

The opening of gravel-filled bags shall be secured to prevent gravel from escaping. Gravel-filled bags shall be between 13 kg and 22 kg in mass.

##### Straw Bales

Straw for straw bales shall conform to the provisions in Section 20-2.06, "Straw," of the Standard Specifications.

Straw bales shall be a minimum of 360 mm in width, 450 mm in height, 900 mm in length and shall have a minimum mass of 23 kg. The straw bale shall be composed entirely of vegetative matter, except for binding material.

Straw bales shall be bound by either wire, nylon or polypropylene string. Jute or cotton binding shall not be used. Baling wire shall be a minimum 1.57 mm in diameter. Nylon or polypropylene string shall be approximately 2 mm in diameter with 360 N of breaking strength.

##### Stakes

Stakes shall be wood or metal. Wood stakes shall be untreated fir, redwood, cedar, or pine and cut from sound timber. They shall be straight and free of loose or unsound knots or other defects which would render them unfit for the purpose intended. Wood stakes shall be a minimum 50 mm x 50 mm in size. Metal stakes may be used as an alternative, and shall be a minimum 13 mm in diameter. Stakes shall be a minimum 1.2 m in length. The tops of the metal stakes shall be bent at a 90-degree angle or capped with an orange or red plastic safety cap that fits snugly to the metal stake. The Contractor shall submit a sample of the metal stake and plastic cap, if used, for the Engineer's approval before installation.

##### Staples

Staples shall be as shown on the plans. An alternative attachment device such as geotextile pins or plastic pegs may be used instead of staples. The Contractor shall submit a sample of the alternative attachment device for the Engineer's approval before installation.

## **Signs**

Wood posts for signs shall conform to the provisions in Section 56-2.02B, "Wood Posts," of the Standard Specifications. Lag screws shall conform to the provisions in Section 56-2.02D, "Sign Panel Fastening Hardware," of the Standard Specifications.

Plywood shall be freshly painted for each installation with not less than 2 applications of flat white paint. Sign letters shown on the plans shall be stenciled with commercial quality exterior black paint. Testing of paint will not be required.

## **INSTALLATION**

Temporary concrete washout facilities shall be as follows:

1. Temporary concrete washout facilities shall be installed before beginning placement of concrete and located a minimum of 15 m from storm drain inlets, open drainage facilities, and water courses unless determined infeasible by the Engineer. Temporary concrete washout facilities shall be located away from construction traffic or access areas at a location determined by the Contractor and approved by the Engineer.
2. A sign shall be installed adjacent to each washout facility at a location determined by the Contractor and approved by the Engineer. Signs shall be installed in conformance with the provisions in Section 56-2.03, "Construction," and Section 56-2.04, "Sign Panel Installation," of the Standard Specifications.
3. The length and width of a temporary concrete washout facility may be increased from the minimum dimensions shown on the plans upon approval of the Engineer.
4. Temporary concrete washout facilities shall be constructed in sufficient quantity and size to contain liquid and concrete waste generated by washout operations for concrete wastes. These facilities shall be constructed to contain liquid and concrete waste without seepage, spills, or overflow.
5. Berms for below grade temporary concrete washout facilities shall be constructed from compacted native material. Gravel may be used in conjunction with compacted native material.
6. A plastic liner shall be installed in below grade temporary concrete washout facilities.

Details for an alternative temporary concrete washout facility shall be submitted to the Engineer for approval at least 7 days before installation.

When temporary concrete washout facilities are no longer required for the work, as determined by the Engineer, the hardened concrete and liquid residue shall be removed and disposed of in conformance with the provisions in Section 15-3.02, "Removal Methods," of the Standard Specifications. Temporary concrete washout facilities shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Ground disturbance, including holes and depressions, caused by the installation and removal of the temporary concrete washout facilities shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

## **MAINTENANCE**

Temporary concrete washout facilities shall be maintained to provide adequate holding capacity with a minimum freeboard of 300 mm. Maintaining temporary concrete washout facilities shall include removing and disposing of hardened concrete and returning the facilities to a functional condition. Hardened concrete materials shall be removed and disposed of in conformance with the provisions in Section 15-3.02, "Removal Methods," of the Standard Specifications. Holes, rips, and voids in the plastic liner shall be patched and repaired by taping or the plastic liner shall be replaced. The plastic liner shall be replaced when patches or repairs compromise the impermeability of the material as determined by the Engineer.

Gravel bags shall be replaced when the bag material is ruptured or when the yarn has failed, allowing the bag contents to spill out.

Temporary concrete washout facilities shall be repaired or replaced on the same day the damage occurs. Damage to temporary concrete washout facilities resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor's expense.

## **MEASUREMENT AND PAYMENT**

Quantities of temporary concrete washout facilities will be measured as units determined from actual count in place.

The contract unit price paid for temporary concrete washout facility shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in constructing a temporary concrete washout facility, complete in place, including excavation and backfill, maintenance, and removal, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **10-1.09 TEMPORARY CONCRETE WASHOUT (PORTABLE)**

A portable temporary concrete washout shall be furnished, maintained, and removed as specified in the approved Storm Water Pollution Prevention Plan in conformance with "Water Pollution Control" of these special provisions and as directed by the Engineer.

A portable temporary concrete washout shall consist of a commercially available drum at a minimum size of 208-liter or alternate container upon written approval from the Engineer. The drum shall be stenciled "Concrete Waste Material." The letters shall be black and 100 mm in height on a white background. The top of the stenciling shall be 300 mm from the top of the barrel.

#### **PLACEMENT**

A portable temporary concrete washout shall be as follows:

- A. A portable temporary concrete washout shall be in place prior to placement of concrete and shall be located in the immediate area of the concrete work as approved by the Engineer. The temporary concrete washout shall be located away from construction traffic or public access areas. After initial placement, temporary concrete washout shall be moved as needed for concrete construction work. When the temporary concrete washout is no longer required, as determined by the Engineer, it shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.
- B. A sign shall be installed adjacent to each washout at a location determined by the Contractor and approved by the Engineer. Signs shall be installed in conformance with the provisions in Section 12-3.06B, "Portable Signs" of the Standard Specifications. Each portable sign shall consist of a base, framework and a sign panel. The sign panel shall be made out of plywood and shall have a minimum size of 610 mm by 1200 mm. The sign panel shall read "Concrete Washout" with black letters, 150 mm in height, on a white background.
- C. The Contractor shall provide sufficient temporary concrete washout capacity to contain liquid and concrete waste generated by washout operations without seepage or spills.

Maintaining the portable temporary concrete washout shall include removing and disposing of concrete waste. Concrete waste material generated shall be removed each day and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way" of the Standard Specifications.

The Contractor shall provide the name and location of the disposal facility to the Engineer before disposal of solid and liquid concrete waste. The Contractor shall provide verification that the off-site commercial or noncommercial disposal site has a permit issued by the California Regional Water Quality Control Board (RWQCB). If the disposal site is located outside of the State of California, the Contractor shall provide a copy of the permit issued by the state or local agency having jurisdiction over the disposal site.

When relocating or transporting a portable temporary concrete washout, the portable washout shall be properly secured to prevent spilling of concrete waste material.

#### **PAYMENT**

The contract lump sum price paid for temporary concrete washout (portable) shall include full compensation for furnishing all labor, materials, tools, equipment, including the sign, and incidentals, and for doing all the work involved in furnishing, placing, maintaining, repairing, replacing, transporting, disposing of concrete waste, and removing the washout, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **10-1.10 TEMPORARY FIBER ROLL**

Temporary fiber roll shall be furnished, installed, maintained, and later removed at the locations shown on the approved Storm Water Pollution Prevention Plan (SWPPP) in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Temporary fiber roll shall be installed on excavation and embankment slopes and other disturbed soil areas, active or nonactive.

Temporary fiber roll shall be one of the water pollution control practices for sediment control. The SWPPP shall include the use of temporary fiber roll.

Temporary fiber roll shall be either Type 1 or Type 2.

#### **MATERIALS**

##### **Fiber Roll**

Fiber roll shall be either:

1. Constructed with a premanufactured blanket consisting of either wood excelsior, rice or wheat straw, or coconut fibers or a combination of these materials. The blanket shall be between 2.0 m and 2.4 m in width and between 20 m and 29 m in length. Wood excelsior shall be individual fibers, of which 80 percent shall be 150 mm or longer in length. The blanket shall have a photodegradable plastic netting or biodegradable jute, sisal, or coir fiber netting on at least one side. The blanket shall be rolled along the width and secured with jute twine spaced 2 m apart along the full length of the roll and placed 150 mm from the ends of each roll. The finished roll shall be between 200 mm and 250 mm in diameter, a minimum of 6 m in length, and shall weigh a minimum 0.81-kg/m. More than one blanket may be required to achieve the finished roll diameter. When more than one blanket is required, blankets shall be jointed longitudinally with an overlap of 150 mm along the length of the blanket.
2. A premanufactured roll of rice or wheat straw, wood excelsior, or coconut fiber encapsulated within a photodegradable plastic or biodegradable jute, sisal, or coir fiber netting. The netting shall have a minimum durability of one year after installation. The netting shall be secured tightly at each end of the roll. Rolls shall be between 200 mm and 300 mm in diameter. Rolls between 200 mm and 250 mm in diameter shall have a minimum weight of 1.6 kg/m and a minimum length of 6 m. Rolls between 250 mm and 300 mm in diameter shall have a minimum weight of 4.5 kg/m and a minimum length of 3 m.

### **Stakes**

Wood stakes shall be a minimum of 19 mm x 19 mm x 450 mm in size for Type 1 installation, or a minimum of 19 mm x 38 mm x 450 mm in size for Type 2 installation. Wood stakes shall be untreated fir, redwood, cedar, or pine and cut from sound timber. They shall be straight and free of loose or unsound knots and other defects which would render them unfit for the purpose intended. Metal stakes shall not be used.

### **Rope**

Rope shall be biodegradable, such as sisal or manila, with a minimum diameter of 6.35 mm.

## **INSTALLATION**

Temporary fiber roll shall be installed as follows:

1. Temporary fiber roll (Type 1): Furrows shall be constructed to a depth between 50 mm and 100 mm, and to a sufficient width to hold the fiber roll. Stakes shall be installed 600 mm apart along the length of the fiber rolls and stopped at 300 mm from each end of the rolls. Stakes shall be driven to a maximum of 50 mm above, or flush with the top of the roll.
2. Temporary fiber roll (Type 2): Rope and notched stakes shall be used to restrain the fiber rolls against the slope. Stakes shall be driven into the slope until the notch is even with the top of the fiber roll. Rope shall be knotted at each stake and laced between stakes. After installation of the rope, stakes shall be driven into the slope such that the rope will hold the fiber roll tightly to the slope. Furrows will not be required.
3. Temporary fiber rolls shall be placed 3 m apart along the slope for slope inclination (vertical:horizontal) of 1:2 and steeper, 4.5 m apart along the slope for slope inclination between 1:2 and 1:4, 6 m apart along the slope for slope inclination between 1:4 and 1:10, and a maximum of 15 m apart along the slope for slope inclination of 1:10 and flatter.
4. The bedding area for the fiber roll shall be cleared of obstructions including rocks, clods, and debris greater than 25 mm in diameter before installation.
5. Temporary fiber rolls shall be installed approximately parallel to the slope contour.
6. Temporary fiber rolls shall be installed before the application of other temporary erosion control or soil stabilization materials in the same area.

When no longer required, as determined by the Engineer, temporary fiber rolls shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. Temporary fiber rolls may be abandoned in place when approved in writing by the Engineer.

Ground disturbances including holes and depressions caused by the installation and removal of the temporary fiber roll shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

## **MAINTENANCE**

Temporary fiber rolls shall be maintained to disperse concentrated water runoff and to reduce runoff velocities. Split, torn, or unraveling rolls shall be repaired or replaced. Broken or split stakes shall be replaced. Sagging or slumping fiber rolls shall be repaired with additional stakes or replaced. Locations where rills and other evidence of concentrated runoff

have occurred beneath the rolls shall be corrected. Temporary fiber rolls shall be repaired or replaced within 24 hours of identifying the deficiency.

**MEASUREMENT AND PAYMENT**

Quantities of temporary fiber rolls to be paid for will be determined by the meter measured along the centerline of the installed roll. Where temporary fiber rolls are joined and overlapped, the overlap will be measured as a single installed roll.

The contract price paid per meter for temporary fiber roll shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing temporary fiber rolls, complete in place, including furrow excavation and backfill, and removal, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Damage to temporary fiber rolls resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor's expense.

The cost of maintaining temporary fiber rolls will be borne equally by the State and the Contractor. The division of cost will be made by determining the cost of maintaining temporary fiber rolls in conformance with the provisions in Section 9-1.03, "Force Account Payment," of the Standard Specifications and paying half of that cost to the Contractor.

Cleanup, repair, removal, disposal, or replacement due to improper installation or the Contractor's negligence will not be considered as included in the cost for performing maintenance.

**10-1.11 TEMPORARY GRAVEL BAG BERM**

Temporary gravel bag berms shall be furnished, installed, maintained, and later removed at the locations shown on the approved Storm Water Pollution Prevention Plan in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Temporary gravel bag berms shall be one of the water pollution control practices for sediment control. The Storm Water Pollution Prevention Plan shall include the use of temporary gravel bag berms.

**MATERIALS**

**Gravel-filled Bags**

Gravel bag fabric shall be nonwoven polypropylene geotextile (or comparable polymer) and shall conform to the following requirements:

Specification	Requirements
Mass per unit area, grams per square meter, min. ASTM Designation: D 5261	270
Grab tensile strength (25-mm grip), kilonewtons, min. ASTM Designation: D4632*	0.89
Ultraviolet stability, percent tensile strength retained after 500 hours, ASTM Designation: D4355, xenon arc lamp method	70

\* or appropriate test method for specific polymer

Gravel bags shall be between 600 mm and 800 mm in length, and between 400 mm and 500 mm in width.

Yarn used for binding gravel bags shall be as recommended by the manufacturer or bag supplier and shall be of a contrasting color.

Gravel shall be between 10 mm and 20 mm in diameter, and shall be clean and free from clay balls, organic matter, and other deleterious materials. The opening of gravel-filled bags shall be secured to prevent gravel from escaping. Gravel-filled bags shall be between 13 kg and 22 kg in mass.

**INSTALLATION**

Temporary gravel bag berms shall be installed as follows:

- A. A single layer of gravel bags shall be placed with ends abutted tightly and not overlapped.
- B. The bedding area for the temporary gravel bag berm shall be cleared of obstructions, including rocks, clods, and debris greater than 25 mm in diameter, prior to installation.
- C. Temporary gravel bag berms shall be installed approximately parallel to the slope contour.
- D. The last 2 m of the temporary gravel bag berm shall be angled up-slope.

When no longer required, as determined by the Engineer, temporary gravel bag berm shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Ground disturbance, including holes and depressions, caused by the installation and removal of the temporary gravel bag berm shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

**MAINTENANCE**

Temporary gravel bag berms shall be maintained to provide a sediment holding capacity of approximately 1/3 the height of the gravel bag berm above the ground. When sediment exceeds this height, or when directed by the Engineer, sediment shall be removed. Removed sediment shall be deposited within the project limits in such a way that the sediment is not subject to erosion by wind or by water.

Temporary gravel bag berms shall be repaired or replaced on the same day the damage occurs. Damage to the temporary gravel bag berm resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor's expense.

Gravel bags shall be replaced when the bag material is ruptured or when the yarn has failed, allowing the bag contents to spill out.

**MEASUREMENT AND PAYMENT**

Quantities of temporary gravel bag berm to be paid for will be determined by the meter, measured along the centerline of the installed temporary gravel bag berm.

The contract price paid per meter for temporary gravel bag berm shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing temporary gravel bag berm, complete in place, including backfill, maintenance, and removal, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

**10-1.12 TEMPORARY CONSTRUCTION ENTRANCE**

Temporary construction entrances shall be constructed, maintained, and later removed at the locations shown on the approved Storm Water Pollution Prevention Plan (SWPPP) in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Temporary construction entrances shall be one of the water pollution control practices for tracking control. The SWPPP shall include the use of temporary construction entrances.

Temporary construction entrances shall be either Type 1 or Type 2.

**MATERIALS**

**Temporary Entrance Fabric**

Temporary entrance fabric shall be manufactured from polyester, nylon, or polypropylene material, or any combination thereof. Temporary entrance fabric shall be a nonwoven, needle-punched fabric, free of needles which may have broken off during the manufacturing process. Temporary entrance fabric shall be permeable and shall not act as a wicking agent.

Temporary entrance fabric shall be manufactured from virgin, recycled, or a combination of virgin and recycled polymer materials. No virgin or recycled materials shall contain biodegradable filler materials that can degrade the physical or chemical characteristics of the finished fabric. The Engineer may order tests to confirm the absence of biodegradable filler materials in conformance to the requirements in ASTM Designation: E 204 (Fourier Transformed Infrared Spectroscopy-FTIR).

Temporary entrance fabric shall conform to the following requirements:

Specification	Requirements
Mass per unit area, grams per square meter, min. ASTM Designation: D 5261	235
Grab tensile strength (25-mm grip), kilonewtons, min. ASTM Designation: D4632*	0.89
Elongation at break, percent min. ASTM Designation: D4632*	50
Toughness, kilonewtons, min. (percent elongation x grab tensile strength)	53

\* or appropriate test method for specific polymer

## **Rocks**

Rocks shall conform to the material quality requirements in Section 72-2.02, "Materials," of the Standard Specifications for shape and for apparent specific gravity, absorption, and durability index. Rocks used for the temporary entrance shall conform to the following sizes:

Square Screen Size (mm)	Percentage Passing	Percentage Retained
150	100	0
75	0	100

## **Corrugated Steel Panels**

Corrugated steel panels shall be prefabricated and shall be pressed or shop welded, with a slot or hooked section to facilitate coupling at the ends of the panels.

## **INSTALLATION**

Temporary construction entrances shall be installed as follows:

1. Before placing the temporary entrance fabric, the areas shall be cleared of all trash and debris. Vegetation shall be removed to the ground level. Trash, debris, and removed vegetation shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.
2. A sump shall be constructed within 6 m of each temporary construction entrance as shown on the plans.
3. Before placing the temporary entrance fabric, the ground shall be graded to a uniform plane. The relative compaction of the top 0.5-m shall be not less than 90 percent. The ground surface shall be free of sharp objects that may damage the temporary entrance fabric, and shall be graded to drain to the sump as shown on the plans.
4. Temporary entrance fabric shall be positioned longitudinally along the alignment of the entrance, as directed by the Engineer.
5. The adjacent ends of the fabric shall be overlapped a minimum length of 300 mm.
6. Rocks to be placed directly over the fabric shall be spread in the direction of traffic, longitudinally and along the alignment of the temporary construction entrance.
7. During spreading of the rocks, vehicles or equipment shall not be driven directly on the fabric. A layer of rocks a minimum 150 mm thick shall be placed between the fabric and the spreading equipment to prevent damage to the fabric.
8. For Type 2 temporary construction entrances, a minimum of 6 coupled panel sections shall be installed for each temporary construction entrance. Before installing the panels, the ground surface shall be cleared of all debris to ensure uniform contact with the ground surface.

Fabric damaged during rock placement shall be repaired by placing a new piece of fabric over the damaged area. The piece of fabric shall be large enough to cover the damaged area and provide a minimum 450-mm overlap on all edges.

Details for a proposed alternative temporary construction entrance or alternative sump shall be submitted to the Engineer for approval at least 7 days before installation. The Contractor may eliminate the sump if approved in writing by the Engineer.

When no longer required as determined by the Engineer, temporary construction entrances shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Ground disturbance, including holes and depressions, caused by the installation and removal of the temporary construction entrance, including the sumps, shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

While the temporary construction entrance is in use, pavement shall be cleaned and sediment removed at least once a day, and as often as necessary when directed by the Engineer. Soil and sediment or other extraneous material tracked onto existing pavement shall not be allowed to enter drainage facilities.

## **MAINTENANCE**

The Contractor shall maintain temporary construction entrances throughout the contract or until removed. The Contractor shall prevent displacement or migration of the rock surfacing or corrugated steel panels. Significant depressions resulting from settlement or heavy equipment shall be repaired by the Contractor, as directed by the Engineer.

Temporary construction entrances shall be maintained to minimize tracking of soil and sediment onto existing public roads.

If buildup of soil and sediment deter the function of the temporary construction entrance, the Contractor shall immediately remove and dispose of the soil and sediment, and install additional corrugated steel panels and spread additional rocks to increase the capacity of the temporary construction entrance.

Temporary construction entrances shall be repaired or replaced on the same day the damage occurs. Damage to the temporary construction entrance resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor's expense.

## **MEASUREMENT AND PAYMENT**

Quantities of temporary construction entrances will be determined from actual count in place.

The contract unit price paid for temporary construction entrance shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing temporary construction entrance, complete in place, including excavation and backfill, and removal, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The cost of maintaining the temporary construction entrance will be borne equally by the State and the Contractor. The division of cost will be made by determining the cost of maintaining temporary construction entrance in conformance with the provisions in Section 9-1.03, "Force Account Payment," of the Standard Specifications and paying to the Contractor one-half of that cost.

Cleanup, repair, removal, disposal, or replacement due to improper installation or the Contractor's negligence will not be considered as included in the cost for performing maintenance.

### **10-1.13 TEMPORARY DRAINAGE INLET PROTECTION**

Temporary drainage inlet protection shall be constructed, maintained, and removed at the locations shown on the approved Storm Water Pollution Prevention Plan (SWPPP) in accordance with "Water Pollution Control" of these special provisions, and in accordance with the details shown on the plans and these special provisions.

Temporary drainage inlet protection shall be one of the water pollution control practices for sediment control. The SWPPP shall include the use of temporary drainage inlet protection.

The Contractor shall select the appropriate drainage inlet protection in accordance with the details to meet the conditions around the drainage inlet. Throughout the duration of the contract, the Contractor shall provide protection to meet the changing conditions around the drainage inlet.

Temporary drainage inlet protection shall be Type 3A or 3B or 5.

## **MATERIALS**

### **Erosion Control Blanket**

The erosion control blanket shall be a rolled erosion control product (RECP) and shall be classified either as temporary and degradable or long-term and nondegradable, and shall conform to one of the following:

#### **A. Temporary and degradable:**

1. Machine produced mats consisting of curled wood excelsior with 80 percent of the fiber 150 mm or longer. The excelsior blanket shall be of consistent thickness with wood fiber evenly distributed over the entire area of the blanket. The top surface of the blanket shall be covered with extruded photodegradable plastic netting or lightweight nonsynthetic netting. The blanket shall be smolder resistant without the use of chemical additives and shall be nontoxic and noninjurious to plant and animal life. The excelsior blanket shall be furnished in rolled strips with a minimum mass per unit area of 0.40-kg/m<sup>2</sup>.
2. Machine produced mats consisting of 70 percent straw and 30 percent coconut fiber with extruded photodegradable plastic netting or lightweight nonsynthetic netting on the top and bottom surfaces of the blanket. The straw and coconut shall adhere to the netting using thread or glue strip. The straw and coconut blanket shall be of consistent thickness, and straw and coconut fiber shall be evenly distributed over the entire area of the blanket. The straw and coconut fiber blanket shall be furnished in rolled strips with a minimum mass per unit area of 0.27-kg/m<sup>2</sup>.
3. Machine produced mats that are 100 percent coir consisting of coconut fiber with extruded photodegradable plastic netting or lightweight nonsynthetic netting on the top and bottom surfaces of the blanket. The coconut fiber shall adhere to the netting using thread or glue strip. The coconut blanket shall be of consistent thickness, with coconut fiber evenly distributed over the entire area of the blanket. The coconut fiber blanket shall be furnished in rolled strips with a minimum mass per unit area of 0.27-kg/m<sup>2</sup>.
4. Machine woven netting that is 100 percent spun coir consisting of coconut fiber with an average open area of 63 percent to 70 percent. Coconut coir netting shall be furnished in rolled strips with a minimum mass per unit area of 0.40-kg/m<sup>2</sup>.

B. Long-term and nondegradable:

1. Geotextile blanket shall conform to the provisions for rock slope protection fabric (Type A) in Section 88-1.04, "Rock Slope Protection Fabric," of the Standard Specifications.

**Staples**

Staples shall be as shown on the plans. An alternative attachment device such as geotextile pins or plastic pegs may be used instead of staples. The Contractor shall submit a sample of the alternative attachment device for the Engineer's approval before installation.

**Gravel-filled Bags**

Gravel-filled bag fabric shall be nonwoven polypropylene geotextile or polymer material and shall conform to the following requirements:

Specification	Requirements
Mass per unit area, grams per square meter, minimum. ASTM Designation: D 5261	270
Grab tensile strength (25-mm grip), kilonewtons, minimum. ASTM Designation: D4632*	0.89
Ultraviolet stability, percent tensile strength retained after 500 hours, ASTM Designation: D4355, xenon arc lamp method	70

\* or appropriate test method for specific polymer

Gravel-filled bags shall be between 600 mm and 800 mm in length, and between 400 mm and 500 mm in width.

Yarn used for binding gravel bags shall be as recommended by the manufacturer or bag supplier and shall be of a contrasting color.

Gravel shall be between 10 mm and 20 mm in diameter, and shall be clean and free from clay balls, organic matter, and other deleterious materials. The opening of gravel-filled bags shall be secured to prevent gravel from escaping. Gravel-filled bags shall be between 13 kg and 22 kg in mass.

**Silt Fence**

At the Contractor's option, temporary silt fence shall be prefabricated or constructed with silt fence fabric, posts, and fasteners.

Silt fence fabric shall conform to the following requirements:

Specification	Requirements
Width, mm, min.	900
Grab tensile strength (25-mm grip), kilonewtons, minimum. in each direction ASTM Designation: D 4632 or appropriate test method for specific polymer	0.55
Elongation, percent minimum in each direction ASTM Designation: D 4632 or appropriate test method for specific polymer	15
Permittivity, 1/sec., minimum. ASTM Designation: D 4491	1.5
Flow rate, liters per minute per square meter, minimum. ASTM Designation: D 4491	400
Ultraviolet stability, percent tensile strength retained after 500 hours, minimum. ASTM Designation: D 4355 (xenon-arc lamp and water spray weathering method)	70

Silt fence fabric shall be geotextile manufactured from woven polypropylene or polymer material. Silt fence fabric may be made of recycled materials. No materials shall contain biodegradable filler materials that can degrade the physical or chemical characteristics of the finished fabric. The Engineer may order tests to confirm the absence of biodegradable filler materials in conformance to the requirements in ASTM Designation: E 204.

Posts for temporary silt fences shall be one of the following:

- A. Posts shall be untreated fir, redwood, cedar, or pine, shall be cut from sound timber, and shall be straight and free of loose or unsound knots and other defects which would render them unfit for the purpose intended. Wood post shall

be a minimum of 34 mm x 40 mm in size, and 4 feet in length. The end of the post to be embedded in the soil shall be pointed.

- B. Posts shall be steel and have a "U," "T," "L," or other cross sectional shape that can resist failure from lateral loads. The steel posts shall have a minimum mass per length of 1.1 kg/m and a minimum length of 1.2 m. One end of the steel posts shall be pointed and the other end shall be capped with an orange or red plastic safety cap which fits snugly to the steel post. The Contractor shall submit to the Engineer for approval a sample of the capped steel post before installation.

Fasteners for attaching silt fence fabric to posts shall be as follows:

- A. When prefabricated silt fence is used, posts shall be inserted into sewn pockets.
- B. Silt fence fabric shall be attached to wooden posts with nails or staples as shown on the plans or as recommended by the manufacturer or supplier. Tie wire or locking plastic fasteners shall be used to fasten the silt fence fabric to steel posts. Maximum spacing of fasteners shall be 200 mm along the length of the steel post.

**Sediment Filter Bag**

Sediment filter bag fabric shall be geotextile manufactured from woven polypropylene or polymer material. Sediment filter bag fabric may be made from recycled polymer materials. Polymer materials shall not contain biodegradable filler materials and shall conform to the requirements in ASTM Designation: E 204.

Sediment filter bag fabric shall conform to the following requirements:

Specification	Requirements
Grab tensile strength (25-mm grip), kilonewtons, minimum. in each direction ASTM Designation: D 4632 or appropriate test method for specific polymer	1.35
Elongation, percent minimum in each direction ASTM Designation: D 4632 or appropriate test method for specific polymer	15
Permittivity, 1/sec., minimum. ASTM Designation: D 4491	1.5
Flow rate, liters per minute per square meter, minimum. ASTM Designation: D 4491	8140
Ultraviolet stability, percent tensile strength retained after 500 hours, minimum. ASTM Designation: D 4355 (xenon-arc lamp and water spray weathering method)	80

The sediment filter bag shall be sized to fit the catch basin or drainage inlet and shall be complete with lifting loops and dump straps attached at the bottom to facilitate emptying of the sediment filter bag. The sediment filter bags shall have a restraint cord approximately halfway up the bag to keep the sides away from the catch basin walls.

**INSTALLATION**

Temporary drainage inlet protection shall be installed at drainage inlets in paved and unpaved areas as follows:

- A. Temporary drainage inlet protection shall be installed such that ponded runoff does not encroach on the traveled way or overtop the curb or dike. Gravel-filled bags shall be placed to control ponding and prevent runoff from overtopping the curb or dike.
- B. The bedding area for the temporary drainage inlet protection shall be cleared of obstructions including rocks, clods, and debris greater than 25 mm in diameter before installation.
- C. A temporary linear sediment barrier shall be installed up-slope of the existing drainage inlet and parallel with the curb, dike, or flow line to prevent sediment from entering the drainage inlet.

**Erosion Control Blanket and Geotextile Fabric**

The erosion control blanket and geotextile fabric shall be secured to the surface of the excavated sediment trap with staples and embedded in a trench adjacent to the drainage inlet. The perimeter edge of the erosion control blanket and geotextile fabric shall be anchored in a trench.

**Silt Fence**

Silt fence shall be installed along the perimeter of the erosion control blanket or geotextile fabric, with the posts facing the drainage inlet. The trench shall be backfilled and tamped to secure the silt fence fabric in the bottom of the trench.

### **Gravel-filled Bags**

Gravel-filled bags shall be stacked to form a gravel bag barrier. The gravel-filled bags shall be placed so that the bags are tightly abutted and overlap the joints in adjacent rows. A spillway shall be created by removing one or more gravel-filled bags from the upper layer of the gravel bag barrier.

Gravel-filled bags shall only be used within shoulder areas when placed behind temporary railing (Type K).

### **Sediment Filter Bags**

Sediment filter bags shall be installed by removing the drainage inlet grate, placing the sediment bag in the opening, and replacing the grate to secure the sediment filter bag in place.

### **MAINTENANCE**

Temporary drainage inlet protection shall be maintained to provide sediment holding capacity and to reduce runoff velocities. Temporary drainage inlet protection shall be repaired or replaced immediately after the damage occurs.

Sediment deposits, trash, and debris shall be removed from temporary drainage inlet protection as needed or when directed by the Engineer. Removed sediment shall be deposited within the project limits so that the sediment is not subject to erosion by wind or by water. Trash and debris shall be removed and disposed of in accordance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

At locations where rills and other evidence of concentrated runoff have occurred beneath the drainage inlet protection, the protection shall be adjusted to prevent another occurrence.

Temporary silt fence shall be repaired or replaced when silt fence fabric becomes split, torn, or unraveled. Sagging or slumping silt fence shall be repaired with additional stakes or replaced. Broken or split stakes shall be replaced. Temporary silt fence shall be maintained to provide a sediment holding capacity of approximately 1/3 the height of the silt fence fabric above ground.

Sediment in excess of 50 mm above the surface of the erosion control blanket or geotextile fabric shall be removed.

Sediment deposits shall be removed when the deposit is 1/3 the height of the gravel bag barrier or one half the height of the spillway; whichever is less.

Gravel-filled bags shall be replaced when the bag material ruptures or when the binding fails.

Sediment filter bags shall be emptied when the restraint cords are no longer visible. Sediment filter bags shall be emptied by placing 25 mm steel reinforcing bars through the lifting loops. The bag shall be emptied of its contents and rinsed before replacement in the drainage inlet.

### **REMOVAL**

When the temporary drainage inlet protection is no longer required the protection materials shall be removed and disposed of in accordance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Holes, depressions, or other ground disturbance caused by the removal of the temporary drainage inlet protection shall be backfilled and repaired in accordance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

### **MEASUREMENT**

Quantities of temporary drainage inlet protection will be determined from actual count in place. The protection will be measured one time only and no additional measurement will be recognized.

### **PAYMENT**

The contract unit price paid for temporary drainage inlet protection shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the temporary drainage inlet protection, complete in place, including removal of materials, including cleanup and disposal of retained sediment and debris, and backfilling and repairing holes, depressions and other ground disturbance, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

No additional compensation will be made if the temporary drainage inlet protection changes during the course of construction.

The cost of maintaining temporary drainage inlet protection will be borne equally by the State and the Contractor. The division of cost will be made by determining the cost of maintaining temporary drainage inlet protection in accordance with the provisions in Section 9-1.03, "Force Account Payment," of the Standard Specifications and paying to the Contractor one-half of that cost.

Cleanup, repair, removal, disposal, or replacement due to improper installation, or as a result of the Contractor's negligence will not be considered as included in the cost for performing maintenance.

**10-1.14 SCAFFOLDING**

Scaffolding shall be defined in accordance with and shall conform to the Construction Safety Orders of the Division of Occupational Safety and Health and these special provisions.

If scaffolding is constructed for this project over or adjacent to traffic, or suspended from the traveled way, the Contractor shall submit to the Engineer working drawings for scaffolding systems in conformance with Section 5-1.02, "Plans and Working Drawings" of the Standard Specifications, and these special provisions.

Scaffolding working drawings shall include the following:

- A. Descriptions, calculations, and values for all loads anticipated during the erection, use, and removal of scaffolding.
- B. Methods and equipment for erecting, moving, and removing scaffolding.
- C. Design details including bolt layouts, welding details, and any connections to existing structures.
- D. Stress sheets including a summary of computed stresses in the (1) scaffolding, (2) connections between scaffolding and any existing structures and (3) existing load supporting members. The computed stresses shall include the effects of erection, movement, and removal of the scaffolding.

If manufactured scaffolding is used, the manufacturer's name, address, and phone number shall be shown on the working drawings.

The working drawings shall be stamped and signed by an engineer who is registered as a Civil Engineer. In addition, prior to submitting the working drawings to the Engineer, the working drawings shall be stamped and signed by an independent reviewer who is registered as a Civil Engineer in the State of California. The independent reviewer shall not be employed by the same entity preparing the working drawings.

The Contractor shall allow 7 days for the review of a complete submittal for scaffolding working drawings. In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Welding for the manufacturing and erection of scaffolding shall conform to the requirements in AWS D1.1 or D1.2 for steel or aluminum construction respectively.

Full compensation for conforming to the above requirements shall be considered as included in the contract prices paid for the various contract items of work, and no additional compensation will be allowed therefor.

**10-1.15 COOPERATION**

It is anticipated that work by another contractor may be in progress adjacent to or within the limits of this project during progress of the work on this contract. The following table lists contracts anticipated to be in progress during this contract.

Contract No.	Co-Rte-KP	Location	Type of Work
07-0510C4	LA-5-45.0/45.8	Los Angeles County in Glendale and Burbank from 0.1 km north of Western Avenue Undercrossing to 0.4 km north of Alameda Avenue	Planting and Irrigation
07-121844	LA-5-42.7/47.0	Los Angeles County in Los Angeles, Glendale and Burbank from Route 5/134 Separation to Magnolia Boulevard Undercrossing	Construct HOV lane

Comply with Section 7-1.14, "Cooperation," of the Standard Specifications.

**10-1.16 PROGRESS SCHEDULE (CRITICAL PATH METHOD)**

**GENERAL**

**Summary**

Critical path method (CPM) progress schedules are required for this project. Whenever the term "schedule" is used in this section, it means CPM progress schedule.

The provisions in Section 8-1.04, "Progress Schedule," of the Standard Specifications do not apply.

## Definitions

The following definitions apply to this section:

**activity:** A task, event or other project element on a schedule that contributes to completing the project. Activities have a description, start date, finish date, duration and one or more logic ties.

**baseline schedule:** The initial schedule showing the original work plan beginning on the date of contract approval. This schedule shows no completed work to date and no negative float or negative lag to any activity.

**contract completion date:** The current extended date for completion of the contract shown on the weekly statement of working days furnished by the Engineer as specified in Section 8-1.06, "Time of Completion," of the Standard Specifications.

**critical path:** The longest continuous chain of activities for the project that has the least amount of total float of all chains. In general, a delay on the critical path will extend the scheduled completion date.

**critical path method (CPM):** A network based planning technique using activity durations and the relationships between activities to mathematically calculate a schedule for the entire project.

**data date:** The day after the date through which a schedule is current. Everything occurring earlier than the data date is "as-built" and everything on or after the data date is "planned."

**early completion time:** The difference in time between an early scheduled completion date and the contract completion date.

**float:** The difference between the earliest and latest allowable start or finish times for an activity.

**milestone:** An event activity that has zero duration and is typically used to represent the beginning or end of a certain stage of the project.

**narrative report:** A document submitted with each schedule that discusses topics related to project progress and scheduling.

**near critical path:** A chain of activities with total float exceeding that of the critical path but having no more than 10 working days of total float.

**scheduled completion date:** The planned project finish date shown on the current accepted schedule.

**State owned float activity:** The activity documenting time saved on the critical path by actions of the State. It is the last activity prior to the scheduled completion date.

**time impact analysis:** A schedule and narrative report developed specifically to demonstrate what effect a proposed change or delay has on the current scheduled completion date.

**time-scaled network diagram:** A graphic depiction of a CPM schedule comprised of activity bars with relationships for each activity represented by arrows. The tail of each arrow connects to the activity bar for the predecessor and points to the successor.

**total float:** The amount of time that an activity or chain of activities can be delayed before extending the scheduled completion date.

**updated schedule:** A current schedule developed from the baseline or subsequent schedule through regular monthly review to incorporate as-built progress and any planned changes.

## Submittals

### General Requirements

Submit to the Engineer baseline, monthly updated, and final updated schedules, each consistent in all respects with the time and order of work requirements of the contract. Work must be executed in the sequence indicated on the current accepted schedule.

Schedules must show the order in which you propose to prosecute the work with logical links between time-scaled work activities and calculations made using the critical path method to determine the controlling activities. You are responsible for assuring that all activity sequences are logical and that each schedule shows a coordinated plan for complete performance of the work.

Produce schedules using computer software and submit compatible software for the Engineer's exclusive possession and use. Submit network diagrams and schedule data as parts of each schedule submittal.

Schedule activities must include the following:

1. Project characteristics, salient features, or interfaces, including those with outside entities, that could affect time of completion
2. Project start date, scheduled completion date, and other milestones
3. Work performed by you, your subcontractors, and suppliers
4. Submittal development, delivery, review, and approval, including those from you, your subcontractors, and suppliers
5. Procurement, delivery, installation, and testing of materials, plants, and equipment
6. Testing and settlement periods

7. Utility notification and relocation
8. Erection and removal of falsework and shoring
9. Major traffic stage switches
10. Finishing roadway and final cleanup
11. State-owned float as the predecessor activity to the scheduled completion date

Schedules must have not less than 50 and not more than 500 activities, unless otherwise authorized by the Engineer. The number of activities must be sufficient to assure adequate planning of the project, to permit monitoring and evaluation of progress, and to do an analysis of time impacts.

Schedule activities must include the following:

1. A clear and legible description.
2. Start and finish dates.
3. A duration of not less than one working day, except for event activities, and not more than 20 working days, unless otherwise authorized by the Engineer.
4. At least one predecessor and one successor activity, except for project start and finish milestones.
5. Required constraints. Constraints other than those required by the special provisions may be included only if authorized by the Engineer.
6. Codes for responsibility, stage, work shifts, location, and contract pay item numbers.

You may show early completion time on any schedule provided that the requirements of the contract are met. Early completion time is considered a resource for your exclusive use. You may increase early completion time by improving production, reallocating resources to be more efficient, performing sequential activities concurrently, or by completing activities earlier than planned. You may also submit for approval a cost reduction incentive proposal as specified in Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications that will reduce time of construction.

You may show a scheduled completion date that is later than the contract completion date on an update schedule, after the baseline schedule is accepted. Provide an explanation for a late scheduled completion date in the narrative report that is included with the schedule.

State-owned float is considered a resource for the exclusive use of the State. The Engineer may accrue State-owned float by the early completion of review of any type of required submittal when it saves time on the critical path. Prepare a time impact analysis, when requested by the Engineer, to determine the effect of the action as specified in "Time Impact Analysis." The Engineer documents State-owned float by directing you to update the State-owned float activity on the next updated schedule. Include a log of the action on the State-owned float activity and include a discussion of the action in the narrative report. The Engineer may use State-owned float to mitigate past, present, or future State delays by offsetting potential time extensions for contract change orders.

The Engineer may adjust contract working days for ordered changes that affect the scheduled completion date as specified in Section 4-1.03, "Changes," of the Standard Specifications. Prepare a time impact analysis to determine the effect of the change as specified in "Time Impact Analysis" and include the impacts acceptable to the Engineer in the next updated schedule. Changes that do not affect the controlling operation on the critical path will not be considered as the basis for a time adjustment. Changes that do affect the controlling operation on the critical path will be considered by the Engineer in decreasing time or granting an extension of time for completion of the contract. Time extensions will only be granted if the total float is absorbed and the scheduled completion date is delayed one or more working days because of the ordered change.

The Engineer's review and acceptance of schedules does not waive any contract requirements and does not relieve you of any obligation or responsibility for submitting complete and accurate information. Correct rejected schedules and resubmit corrected schedules to the Engineer within 7 days of notification by the Engineer, at which time a new review period of 7 days will begin.

Errors or omissions on schedules do not relieve you from finishing all work within the time limit specified for completion of the contract. If, after a schedule has been accepted by the Engineer, either you or the Engineer discover that any aspect of the schedule has an error or omission, you must correct it on the next updated schedule.

### **Computer Software**

Submit to the Engineer for review a description of proposed schedule software to be used. After the Engineer accepts the proposed software, submit schedule software and all original software instruction manuals. All software must be compatible with the current version of the Windows operating system in use by the Engineer. The schedule software must include:

1. Latest version of Primavera SureTrak Project Manager for Windows, or equivalent
2. Latest version of schedule-comparing HST SureChange, or equivalent

If a schedule software equivalent to SureTrak is proposed, it must be capable of generating files that can be imported into SureTrak. The schedule-comparing software must be compatible with schedule software submitted and must be able to compare two schedules and provide reports of changes in activity ID, activity description, constraints, calendar assignments, durations, and logic ties.

The schedule software and schedule-comparing software will be returned to you before the final estimate. The Department will compensate you as specified in Section 4-1.03, "Extra Work," of the Standard Specifications for replacement of software or manuals damaged, lost, or stolen after delivery to the Engineer.

Instruct the Engineer in the use of the software and provide software support until the contract is accepted. Within 15 days of contract approval, provide a commercial 8-hour training session for 2 Department employees in the use of the software at a location acceptable to the Engineer. It is recommended that you also send at least 2 employees to the same training session to facilitate development of similar knowledge and skills in the use of the software. If schedule software other than SureTrak is submitted, then the training session must be a total of 16-hours for each Department employee.

### **Network Diagrams, Reports, and Data**

Include the following with each schedule submittal:

1. Two sets of originally plotted, time-scaled network diagrams
2. Two copies of a narrative report
3. One read-only compact disk or floppy diskette containing the schedule data

The time-scaled network diagrams must conform to the following:

1. Show a continuous flow of information from left to right
2. Be based on early start and early finish dates of activities
3. Clearly show the primary paths of criticality using graphical presentation
4. Be prepared on 860 mm x 1120 mm (34" x 44")
5. Include a title block and a timeline on each page

The narrative report must be organized in the following sequence with all applicable documents included:

1. Transmittal letter
2. Work completed during the period
3. Identification of unusual conditions or restrictions regarding labor, equipment or material; including multiple shifts, 6-day work weeks, specified overtime or work at times other than regular days or hours
4. Description of the current critical path
5. Changes to the critical path and scheduled completion date since the last schedule submittal
6. Description of problem areas
7. Current and anticipated delays:
  - 7.1. Cause of delay
  - 7.2. Impact of delay on other activities, milestones, and completion dates
  - 7.3. Corrective action and schedule adjustments to correct the delay
8. Pending items and status thereof:
  - 8.1. Permits
  - 8.2. Change orders
  - 8.3. Time adjustments
  - 8.4. Noncompliance notices
9. Reasons for an early or late scheduled completion date in comparison to the contract completion date

Schedule submittals will only be considered complete when all documents and data have been submitted as described above.

### **Preconstruction Scheduling Conference**

Schedule a preconstruction scheduling conference with your project manager and the Engineer within 15 days after contract approval. The Engineer will conduct the meeting and review the requirements of this section with you.

Submit a general time-scaled logic diagram displaying the major activities and sequence of planned operations and be prepared to discuss the proposed work plan and schedule methodology that comply with the requirements of this section. If you propose deviations to the construction staging, then the general time-scaled logic diagram must also display the deviations and resulting time impacts. Be prepared to discuss the proposal.

At this meeting, also submit the alphanumeric coding structure and activity identification system for labeling work activities. To easily identify relationships, each activity description must indicate its associated scope or location of work by including such terms as quantity of material, type of work, bridge number, station to station location, side of highway (such as left, right, northbound, southbound), lane number, shoulder, ramp name, ramp line descriptor, or mainline.

The Engineer reviews the logic diagram, coding structure, and activity identification system, and provide any required baseline schedule changes to you for implementation.

### **Baseline Schedule**

Beginning the week following the preconstruction scheduling conference, meet with the Engineer weekly to discuss schedule development and resolve schedule issues until the baseline schedule is accepted.

Submit to the Engineer a baseline schedule within 20 days of approval of the contract. Allow 20 days for the Engineer's review after the baseline schedule and all support data are submitted. In addition, the baseline schedule submittal is not considered complete until the computer software is delivered and installed for use in review of the schedule.

The baseline schedule must include the entire scope of work and how you plan to complete all work contemplated. The baseline schedule must show the activities that define the critical path. Multiple critical paths and near-critical paths must be kept to a minimum. A total of not more than 50 percent of the baseline schedule activities must be critical or near critical, unless otherwise authorized by the Engineer.

The baseline schedule must not extend beyond the number of contract working days. The baseline schedule must have a data date of contract approval. If you start work before contract approval, the baseline schedule must have a data date of the 1st day you performed work at the job site.

If you submit an early completion baseline schedule that shows contract completion in less than 85 percent of the contract working days, the baseline schedule must be supplemented with resource allocations for every task activity and include time-scaled resource histograms. The resource allocations must be shown to a level of detail that facilitates report generation based on labor crafts and equipment classes for you and your subcontractors. Use average composite crews to display the labor loading of on-site construction activities. Optimize and level labor to reflect a reasonable plan for accomplishing the work of the contract and to assure that resources are not duplicated in concurrent activities. The time-scaled resource histograms must show labor crafts and equipment classes to be used. The Engineer may review the baseline schedule activity resource allocations using Means Productivity Standards or equivalent to determine if the schedule is practicable.

### **Updated Schedule**

Submit an updated schedule and meet with the Engineer to review contract progress, on or before the 1st day of each month, beginning one month after the baseline schedule is accepted. Allow 15 days for the Engineer's review after the updated schedule and all support data are submitted, except that the review period will not start until the previous month's required schedule is accepted. Updated schedules that are not accepted or rejected within the review period are considered accepted by the Engineer.

The updated schedule must have a data date of the 21st day of the month or other date established by the Engineer. The updated schedule must show the status of work actually completed to date and the work yet to be performed as planned. Actual activity start dates, percent complete, and finish dates must be shown as applicable. Durations for work that has been completed must be shown on the updated schedule as the work actually occurred, including Engineer submittal review and your resubmittal times.

You may include modifications such as adding or deleting activities or changing activity constraints, durations, or logic that do not (1) alter the critical path(s) or near critical path(s) or (2) extend the scheduled completion date compared to that shown on the current accepted schedule. Justify in writing the reasons for any changes to planned work. If any proposed changes in planned work will result in (1) or (2) above, then submit a time impact analysis as specified in this section.

### **Time Impact Analysis**

Submit a written time impact analysis (TIA) to the Engineer with each request for adjustment of contract time, or when you or the Engineer considers that an approved or anticipated change may impact the critical path or contract progress.

The TIA must illustrate the impacts of each change or delay on the current scheduled completion date or internal milestone, as appropriate. The analysis must use the accepted schedule that has a data date closest to and before the event. If the Engineer determines that the accepted schedule used does not appropriately represent the conditions before the event, the accepted schedule must be updated to the day before the event being analyzed. The TIA must include an impact schedule developed from incorporating the event into the accepted schedule by adding or deleting activities, or by changing durations

or logic of existing activities. If the impact schedule shows that incorporating the event modifies the critical path and scheduled completion date of the accepted schedule, the difference between scheduled completion dates of the two schedules must be equal to the adjustment of contract time. The Engineer may construct and use an appropriate project schedule or other recognized method to determine adjustments in contract time until you provide the TIA.

Submit 2 copies of your TIA within 20 days of receiving a written request for a TIA from the Engineer. Allow the Engineer 15 days after receipt to review the submitted TIA. All approved TIA schedule changes must be shown on the next updated schedule.

If a TIA you submit is rejected, meet with the Engineer to discuss and resolve issues related to the TIA. If agreement is not reached, you are allowed 15 days from the meeting with the Engineer to give notice as specified in Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications. Only show actual as-built work, not unapproved changes related to the TIA, in subsequent updated schedules. If agreement is reached at a later date, approved TIA schedule changes must be shown on the next updated schedule. The Engineer withholds remaining payment on the schedule contract item if a TIA is requested and not submitted within 20 days. The schedule item payment resumes on the next estimate after the requested TIA is submitted. No other contract payment is retained regarding TIA submittals.

### **Final Updated Schedule**

Submit a final update, as-built schedule with actual start and finish dates for the activities, within 30 days after completion of contract work. Provide a written certificate with this submittal signed by your project manager or an officer of the company stating, "To my knowledge and belief, the enclosed final update schedule reflects the actual start and finish dates of the actual activities for the project contained herein." An officer of the company may delegate in writing the authority to sign the certificate to a responsible manager.

### **PAYMENT**

Progress schedule (critical path method) will be paid for at a lump sum price. The contract lump sum price paid for progress schedule (critical path method) includes full compensation for furnishing all labor, material, tools, equipment, and incidentals, including computer software, and for doing all the work involved in preparing, furnishing, and updating schedules, and instructing and assisting the Engineer in the use of computer software, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Payments for the progress schedule (critical path method) contract item will be made progressively as follows:

1. A total of 25 percent of the item amount or a total of 25 percent of the amount listed for progress schedule (critical path method) in "Payments" of Section 5 of these special provisions, whichever is less, will be paid upon achieving all of the following:
  - 1.1. Completion of 5 percent of all contract item work.
  - 1.2. Acceptance of all schedules and approval of all TIAs required to the time when 5 percent of all contract item work is complete.
  - 1.3. Delivery of schedule software to the Engineer.
  - 1.4. Completion of required schedule software training.
2. A total of 50 percent of the item amount or a total of 50 percent of the amount listed for progress schedule (critical path method) in "Payments" of Section 5 of these special provisions, whichever is less, will be paid upon completion of 25 percent of all contract item work and acceptance of all schedules and approval of all TIAs required to the time when 25 percent of all contract item work is complete.
3. A total of 75 percent of the item amount or a total of 75 percent of the amount listed for progress schedule (critical path method) in "Payments" of Section 5 of these special provisions, whichever is less, will be paid upon completion of 50 percent of all contract item work and acceptance of all schedules and approval of all TIAs required to the time when 50 percent of all contract item work is complete.
4. A total of 100 percent of the item amount or a total of 100 percent of the amount listed for progress schedule (critical path method) in "Payments" of Section 5 of these special provisions, whichever is less, will be paid upon completion of all contract item work, acceptance of all schedules and approval of all TIAs required to the time when all contract item work is complete, and submittal of the certified final update schedule.

If you fail to complete any of the work or provide any of the schedules required by this section, the Engineer makes an adjustment in compensation as specified in Section 4-1.03C, "Changes in Character of Work," of the Standard Specifications for the work not performed. Adjustments in compensation for schedules will not be made for any increased or decreased work ordered by the Engineer in submitting schedules.

### 10-1.17 TIME-RELATED OVERHEAD

The Contractor will be compensated for time-related overhead as described below and in conformance with "Force Account Payment" of these special provisions. The Contractor will not be compensated for time-related overhead for delays to the controlling operations caused by the Engineer that occur prior to the first working day, but will be compensated for actual overhead costs incurred, as determined by an independent Certified Public Accountant audit examination and report.

Attention is directed to "Beginning of Work, Time of Completion and Liquidated Damages," "Force Account Payment," and "Progress Schedule (Critical Path Method)" of these special provisions.

The provisions in Section 9-1.08, "Adjustment of Overhead Costs," of the Standard Specifications shall not apply.

Time-related overhead shall consist of those overhead costs, including field and home office overhead, that are in proportion to the time required to complete the work. Time-related overhead shall not include costs that are not related to time, including but not limited to, mobilization, licenses, permits, and other charges incurred only once during the contract. Time-related overhead shall not apply to subcontractors of any tier, suppliers, fabricators, manufacturers, or other parties associated with the Contractor.

Field office overhead expenses include time-related costs associated with the normal and recurring operations of the construction project, and shall not include costs directly attributable to the work of the contract. Time-related costs of field office overhead include, but are not limited to, salaries, benefits, and equipment costs of project managers, general superintendents, field office managers and other field office staff assigned to the project, and rent, utilities, maintenance, security, supplies, and equipment costs of the project field office.

Home office overhead or general and administrative expenses refer to the fixed costs of operating the Contractor's business. These costs include, but are not limited to, general administration, insurance, personnel and subcontract administration, purchasing, accounting, and project engineering and estimating. Home office overhead costs shall exclude expenses specifically related to other contracts or other businesses of the Contractor, equipment coordination, material deliveries, and consultant and legal fees.

The quantity of time-related overhead associated with a reduction in contract time for an accepted VECP under Section 4-1.035B, "Value Engineering Change Proposal," of the Standard Specifications shall be considered a construction cost attributable to the resultant estimated net savings due to the cost reduction incentive.

If the final increased quantity of time-related overhead exceeds 149 percent of the number of working days specified in the verified Bid Item List, the Contractor shall, within 60 days of the Engineer's written request, submit to the Engineer an audit examination and report performed by an independent Certified Public Accountant of the Contractor's actual overhead costs. The audit examination and report shall depict the Contractor's project and company-wide financial records and shall specify the actual overall average daily rates for both field and home office overhead for the entire duration of the project, and whether the costs have been properly allocated. The rates of field and home office overhead shall exclude unallowable costs as determined in the Federal Acquisition Regulations, 48 CFR, Chapter 1, Part 31.

Independent Certified Public Accountant's audit examinations shall be performed in conformance with the requirements of the American Institute of Certified Public Accountants Attestation Standards. Audit examinations and reports shall determine if the rates of field office overhead and home office overhead are:

- A. Allowable in conformance with the requirements of the Federal Acquisition Regulations, 48 CFR, Chapter 1, Part 31.
- B. Adequately supported by reliable documentation.
- C. Related solely to the project under examination.

Within 20 days of receipt of the Engineer's written request, the Contractor shall make its financial records available for audit by the State for the purpose of verifying the actual rate of time-related overhead specified in the audit submitted by the Contractor. The actual rate of time-related overhead specified in the audit, submitted by the Contractor, will be subject to approval by the Engineer.

If the Engineer requests the independent Certified Public Accountant audit, or if it is requested in writing by the Contractor, the contract item payment rate for time-related overhead, in excess of 149 percent of the number of working days specified in the verified Bid Item List, will be adjusted to reflect the actual rate.

The cost of performing an independent Certified Public Accountant audit examination and submitting the report, requested by the Engineer, will be borne equally by the State and the Contractor. The division of the cost will be made by determining the cost of providing an audit examination and report in conformance with the provisions of Section 9-1.03B, "Work Performed by Special Forces or Other Special Services," of the Standard Specifications, and paying to the Contractor one-half of that cost. The cost of performing an audit examination and submitting the independent Certified Public Accountant audit report for overhead claims other than for the purpose of verifying the actual rate of time-related overhead shall be entirely borne by the Contractor. The cost of performing an audit examination and submitting the independent Certified Public Accountant audit report to verify actual overhead costs incurred prior to the first working day shall be entirely borne by the Contractor.

The quantity of time-related overhead to be paid will be measured by the working day, designated in the verified Bid Item List as WDAY. The estimated number of working days is the number of working days, excluding days for plant establishment, as specified in "Beginning of Work, Time of Completion and Liquidated Damages" of these special provisions. The quantity of time-related overhead will be increased or decreased only as a result of suspensions or adjustments of contract time which revise the current contract completion date, and which satisfy any of the following criteria:

- A. Suspensions of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications, except:
  - 1. Suspensions ordered due to weather conditions being unfavorable for the suitable prosecution of the controlling operation or operations.
  - 2. Suspensions ordered due to the failure on the part of the Contractor to carry out orders given, or to perform the provisions of the contract.
  - 3. Suspensions ordered due to factors beyond the control of and not caused by the State or the Contractor, for which the Contractor is granted extensions of time in conformance with the provisions of the third paragraph of Section 8-1.07, "Liquidated Damages," of the Standard Specifications.
  - 4. Other suspensions that mutually benefit the State and the Contractor.
- B. Extensions of contract time granted by the State in conformance with the provisions in the fifth paragraph in Section 8-1.07, "Liquidated Damages," of the Standard Specifications and set forth in approved contract change orders, in conformance with the provisions in Section 4-1.03, "Changes," of the Standard Specifications.
- C. Reductions in contract time set forth in approved contract change orders, in conformance with the provisions in Section 4-1.03, "Changes," of the Standard Specifications.

A delay to the controlling operation may be concurrent and any of the following:

- 1. Nonexcusable: A nonexcusable delay is caused by the fault, nonperformance, or deficiency of the Contractor, subcontractors of any tier, or suppliers. No extension of contract time or additional compensation of loss is allowed.
- 2. Excusable: An excusable delay is caused by factors beyond the control and without the fault of the State or the Contractor. Only an extension of contract time is allowed.
- 3. Compensable: A compensable delay is caused solely by the fault, deficiency, error, or omission of the State. An extension of contract time and compensation for the actual cost without markup or profit are allowed.

A concurrent delay occurs when 2 separate delays overlap partially or entirely. A nonexcusable delay concurrent with either an excusable or a compensable delay is a nonexcusable delay. An excusable delay concurrent with a compensable delay is an excusable delay.

The quantity of time-related overhead is only adjusted as a result of a compensable delay and is not adjusted as a result of either a nonexcusable or an excusable delay.

An approved time impact analysis submitted as specified in "Progress Schedule (Critical Path Method)" of these special provisions is used to determine the type and duration of a delay.

In the event an early completion progress schedule, as defined in "Progress Schedule (Critical Path Method)" of these special provisions, is submitted by the Contractor and approved by the Engineer, the amount of time-related overhead eligible for payment will be based on the total number of working days for the project, in conformance with the provisions in "Beginning of Work, Time of Completion and Liquidated Damages" of these special provisions, rather than the Contractor's early completion progress schedule.

The contract price paid per working day for time-related overhead shall include full compensation for time-related overhead, including the Contractor's share of costs of the independent Certified Public Accountant audit of overhead costs requested by the Engineer, as specified in these special provisions, and as directed by the Engineer.

The provisions in Sections 4-1.03B, "Increased or Decreased Quantities," and 4-1.03C, "Changes in Character of the Work," of the Standard Specifications shall not apply to the contract item of time-related overhead.

Full compensation for additional overhead costs incurred during days of inclement weather when the contract work is extended into additional construction seasons due to delays caused by the State shall be considered as included in the time-related overhead paid during the contract working days, and no additional compensation will be allowed therefor.

Full compensation for additional overhead costs involved in performing additional contract item work that is not a controlling operation shall be considered as included in the contract items of work involved and no additional compensation will be allowed therefor.

Full compensation for overhead, other than time-related overhead measured and paid for as specified above, and other than overhead costs included in the markups specified in "Force Account Payment" of these special provisions, shall be considered as included in the various items of work and no additional compensation will be allowed therefor.

Overhead costs incurred by subcontractors of any tier, suppliers, fabricators, manufacturers, and other parties associated with the Contractor shall be considered as included in the various items of work and as specified in Section 9-1.03, "Force Account Payment," of the Standard Specifications.

For the purpose of making partial payments pursuant to the provisions in Section 9-1.06, "Partial Payments," of the Standard Specifications, the number of working days to be paid for time-related overhead in each monthly partial payment will be the number of working days, specified above to be measured for payment that occurred during that monthly estimate period, including compensable suspensions and right of way delays. Working days granted by contract change order due to extra work or changes in character of the work, will be paid for upon completion of the contract. The amount earned per working day for time-related overhead shall be the lesser of the following amounts:

- A. The contract item price.
- B. Twenty percent of the original total contract amount divided by the number of working days specified in "Beginning of Work, Time of Completion and Liquidated Damages," of these special provisions.

After the work has been completed, except plant establishment work, as provided in Section 20-4.08, "Plant Establishment Work," of the Standard Specifications, the amount of the total contract item price for time-related overhead not yet paid will be included for payment in the first estimate made after completion of roadway construction work, in conformance with the provisions in Section 9-1.06, "Partial Payments," of the Standard Specifications.

#### **10-1.18 SMALL BUSINESS UTILIZATION REPORT**

Submit a completed Small Business Utilization Report form on or before the following dates for the prior reporting period:

1. January 15th
2. April 15th
3. July 15th
4. October 15th

Submit a completed final Small Business Utilization Report form within 30 days after contract acceptance.

The Department pays \$250 for each report submitted. The contract unit price paid for small business utilization report includes full compensation for doing all the work involved in submitting the completed Small Business Utilization Report form. If you fail to submit a completed form by the specified time, you will not receive payment for that report.

The Department does not adjust payment for an increase or decrease in the quantity of small business utilization reports submitted. Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications does not apply.

The work to complete the final Small Business Utilization Report contract item is excluded from Section 7-1.17, "Acceptance of Contract," of the Standard Specifications.

#### **10-1.19 RIGHT OF WAY OBSTRUCTIONS**

Attention is directed to the occupied improvements located within the right of way at:

Parcel No. 77406	Work around parcel – December 1, 2010
Parcel No. 77407	Work around parcel – December 1, 2010
Parcel No. 77408	Work around parcel – December 1, 2010

It is anticipated that the State will have legal possession and control of the above referenced parcels by December 1, 2010. If control is obtained earlier than December 1, 2010, the Engineer will release the work-around parcel by notifying the Contractor in writing that the State has legal right and possession of the required right of way.

The Contractor shall take no action that will result in unnecessary inconvenience, disproportionate injury or any action coercive in nature to the occupants of these improvements who have not yet moved from the improvements.

In the event that the improvements in the right of way secured for the project mentioned on the parcels above are not removed by the date specified and, if in the opinion of the Engineer, the Contractor's operations are delayed or interfered with by reason of the improvements not being removed by the date specified, the State will compensate the Contractor for the delays to the extent provided in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

### 10-1.20 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES

Flagging, signs, and temporary traffic control devices furnished, installed, maintained, and removed when no longer required shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Category 1 temporary traffic control devices are defined as small and lightweight (less than 45 kg) devices. These devices shall be certified as crashworthy by crash testing, crash testing of similar devices, or years of demonstrable safe performance. Category 1 temporary traffic control devices include traffic cones, plastic drums, portable delineators, and channelizers.

If requested by the Engineer, the Contractor shall provide written self-certification for crashworthiness of Category 1 temporary traffic control devices at least 5 days before beginning any work using the devices or within 2 days after the request if the devices are already in use. Self-certification shall be provided by the manufacturer or Contractor and shall include the following:

- A. Date,
- B. Federal Aid number (if applicable),
- C. Contract number, district, county, route and kilometer post of project limits,
- D. Company name of certifying vendor, street address, city, state and zip code,
- E. Printed name, signature and title of certifying person; and
- F. Category 1 temporary traffic control devices that will be used on the project.

The Contractor may obtain a standard form for self-certification from the Engineer.

Category 2 temporary traffic control devices are defined as small and lightweight (less than 45 kg) devices that are not expected to produce significant vehicular velocity change, but may cause potential harm to impacting vehicles. Category 2 temporary traffic control devices include barricades and portable sign supports.

Category 2 temporary traffic control devices shall be on the Federal Highway Administration's (FHWA) list of Acceptable Crashworthy Category 2 Hardware for Work Zones. This list is maintained by FHWA and can be located at:

[http://safety.fhwa.dot.gov/roadway\\_dept/road\\_hardware/listing.cfm?code=workzone](http://safety.fhwa.dot.gov/roadway_dept/road_hardware/listing.cfm?code=workzone)

The Department also maintains this list at:

<http://www.dot.ca.gov/hq/traffops/signtech/signdel/pdf/Category2.pdf>

Category 2 temporary traffic control devices that have not received FHWA acceptance shall not be used. Category 2 temporary traffic control devices in use that have received FHWA acceptance shall be labeled with the FHWA acceptance letter number and the name of the manufacturer. The label shall be readable and permanently affixed by the manufacturer. Category 2 temporary traffic control devices without a label shall not be used.

If requested by the Engineer, the Contractor shall provide a written list of Category 2 temporary traffic control devices to be used on the project at least 5 days before beginning any work using the devices or within 2 days after the request if the devices are already in use.

Category 3 temporary traffic control devices consist of temporary traffic-handling equipment and devices that weigh 45 kg or more and are expected to produce significant vehicular velocity change to impacting vehicles. Temporary traffic-handling equipment and devices include crash cushions, truck-mounted attenuators, temporary railing, temporary barrier, and end treatments for temporary railing and barrier.

Type III barricades may be used as sign supports if the barricades have been successfully crash tested, meeting the NCHRP Report 350 criteria, as one unit with a construction area sign attached.

Category 3 temporary traffic control devices shall be shown on the plans or on the Department's Highway Safety Features list. This list is maintained by the Division of Engineering Services and can be found at:

[http://www.dot.ca.gov/hq/esc/approved\\_products\\_list/HighwaySafe.htm](http://www.dot.ca.gov/hq/esc/approved_products_list/HighwaySafe.htm)

Category 3 temporary traffic control devices that are not shown on the plans or not listed on the Department's Highway Safety Features list shall not be used.

Full compensation for providing self-certification for crashworthiness of Category 1 temporary traffic control devices and for providing a list of Category 2 temporary traffic control devices used on the project shall be considered as included in the prices paid for the various items of work requiring the use of the Category 1 or Category 2 temporary traffic control devices and no additional compensation will be allowed therefor.

**10-1.21 CONSTRUCTION AREA SIGNS**

Construction area signs for temporary traffic control shall be furnished, installed, maintained, and removed when no longer required in conformance with the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to "Furnish Sign" of these special provisions.

Attention is directed to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. Type II retroreflective sheeting shall not be used on construction area sign panels. Type III, IV, VII, VIII, or IX retroreflective sheeting shall be used for stationary mounted construction area sign panels.

Attention is directed to "Construction Project Information Signs" of these special provisions regarding the number and type of construction project information signs to be furnished, erected, maintained, and removed and disposed of.

Unless otherwise shown on the plans or specified in these special provisions, the color of construction area warning and guide signs shall have black legend and border on orange background, except W10-1 or W47(CA) (Highway-Rail Grade Crossing Advance Warning) sign shall have black legend and border on yellow background.

Orange background on construction area signs shall be fluorescent orange.

Repair to construction area sign panels will not be allowed, except when approved by the Engineer. At nighttime under vehicular headlight illumination, sign panels that exhibit irregular luminance, shadowing or dark blotches shall be immediately replaced at the Contractor's expense.

The Contractor shall notify the appropriate regional notification center for operators of subsurface installations at least 2 business days, but not more than 14 days, prior to commencing excavation for construction area sign posts. The regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert	811

Excavations required to install construction area signs shall be performed by hand methods without the use of power equipment, except that power equipment may be used if it is determined there are no utility facilities in the area of the proposed post holes. The post hole diameter, if backfilled with portland cement concrete, shall be at least 100 mm greater than the longer dimension of the post cross-section.

Construction area signs placed within 4.6 m from the edge of the travel way shall be mounted on stationary mounted sign supports as specified in "Construction Area Traffic Control Devices" of these special provisions.

The Contractor shall maintain accurate information on construction area signs. Signs that are no longer required shall be immediately covered or removed. Signs that convey inaccurate information shall be immediately replaced or the information shall be corrected. Covers shall be replaced when they no longer cover the signs properly. The Contractor shall immediately restore to the original position and location any sign that is displaced or overturned, from any cause, during the progress of work.

**10-1.22 MAINTAINING TRAFFIC**

Maintaining traffic shall conform to the provisions in Sections 7-1.08, "Public Convenience," Section 7-1.09, "Public Safety," and Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications, "Public Safety", "Portable Changeable Message Sign" and "Temporary Traffic Screen" of these special provisions and these special provisions.

Closure is defined as the closure of a traffic lane or lanes, including shoulder or ramp lanes, within a single traffic control system.

Closures shall conform to the provisions in "Traffic Control System for Lane Closure" of these special provisions.

In addition to the provisions set forth in "Public Safety" of these special provisions, whenever work, including the work of installing, maintaining, and removing temporary railing (Type K) is to be performed on the freeway within 1.8 m of the adjacent traffic lane, the adjacent traffic lane shall be closed.

Except as listed above, closure of adjacent traffic lane will not be required for installing loop detectors with an Impact Attenuator Vehicle (IAV) as a shadow vehicle and for installing, maintaining and removing traffic control devices.

Closures are only allowed during the hours shown in the lane requirement charts included in this section "Maintaining Traffic," except for work required under Sections 7-1.08, "Public Convenience," and Section 7-1.09, "Public Safety" or as shown on the Stage Construction/ Traffic Handling Plans.

At the Contractor's option, work may be performed during the hours designated as 'No work permitted' shown on Chart 1, provided temporary traffic screen is installed on top of temporary railing (Type K), as shown on the plans. No traffic screens will be permitted on the right side of traffic within the limits of a right horizontal curve with a radius less than 610 meters as viewed in the direction of travel and on the left side of traffic within the limits of a left horizontal curve with a radius less than 610 meters as viewed in the direction of travel. Temporary traffic screen shall be furnished, installed, maintained and removed at the Contractor's expense.

Northbound Route 5 freeway may be closed to public traffic at Western Ave. for striping and loop detector installation in conformance with the hours and requirements as shown on Chart 2. When an off-ramp is closed, the Contractor shall furnish and erect special signs for exit ramp closures (SP-3 or SP-5), as shown on the plans. This sign shall be placed on the right shoulder of freeway upstream of the preceding off-ramp.

Special advance notice publicity signs (SP-1), as shown on the plans, shall be posted at locations as determined by the Engineer, a minimum of 7 days prior to ramp closures. When work is not actively in progress, SP-1 signs shall be removed or covered.

Full compensation for furnishing, erecting, maintaining, and removing special advance notice publicity signs (SP-1), special portable freeway detour signs (SP-2) and special signs for exit ramp closures (SP-3 or SP-5) as shown on the plans shall be considered as included in the contract lump sum price paid for traffic control system and no separate payment will be made therefor.

Special signs shall be disposed of as provided in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way" of the Standard Specifications at the conclusion of the project.

Work that encroaches onto the freeway traveled ways will not be allowed from 3 hours before to 2 hours following events at the venues, or special events listed below, unless otherwise permitted by the Engineer.

Venue/Special Event	Affected Routes	Route Limits
Dodger Stadium	5	Route 10 to Route 134
Griffith Park Light Show	5	Route 2 to Route 134

Western Ave. and Flower St. traffic lanes shall be closed during the hours shown on Chart 8 and Chart 9 included in this section "Maintaining Traffic." When Western Ave. is completely closed, traffic shall be detoured as shown on the Traffic Handling Plans.

Local authorities shall be notified at least 5 business days before work begins. The Contractor shall cooperate with local authorities to handle traffic through the work area and shall make arrangements to keep the work area clear of parked vehicles.

Personal vehicles of the Contractor's employees shall not be parked within the right of way.

When work vehicles or equipment are parked on the shoulder within 1.8 m of a traffic lane, the shoulder area shall be closed as shown on the plans.

If minor deviations from the requirements of this section concerning hours of work are required, a written request shall be submitted to the Engineer at least 15 days before the proposed date of the closure. The Engineer may approve the deviations if there is no significant increase in the cost to the State and if the work can be expedited and better serve the public traffic.

Designated legal holidays are: January 1st, the third Monday in February, the last Monday in May, July 4th, the first Monday in September, November 11th, Thanksgiving Day, and December 25th. When a designated legal holiday falls on a Sunday, the following Monday shall be a designated legal holiday. When November 11th falls on a Saturday, the preceding Friday shall be a designated legal holiday.

Special Days are: Martin Luther King Day and Columbus Day.

**Freeway Lane Closure Restriction for Designated Legal Holidays and Special Days**

Thu	Fri	Sat	Sun	Mon	Tues	Wed	Thu	Fri	Sat	Sun
x	<b>H</b> xx	xx	xx							
x	xx	<b>H</b> xx	xx							
	x	xx	xx	<b>H</b> xx	xxx					
	x			<b>SD</b> xx						
				x	<b>H</b> xx					
					x	<b>H</b> xx				
						x	<b>H</b> xx	xx		xx

Legends:

	Refer to Chart 1
x	The full width of the traveled way shall be open for use by public traffic by 0600.
xx	The full width of the traveled way shall be open for use by public traffic.
xxx	The full width of the traveled way shall be open for use by public traffic until 0600.
<b>H</b>	Designated Legal Holiday
<b>SD</b>	Special Day

Chart No. 1 Freeway Lane Requirements and Hours of Work																									
County: LA										Route/Direction: 5/North															
Closure Limits: At Western Ave																									
FROM HOUR TO HOUR																									
	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mondays through Thursdays	1	1	1	1	2	3	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	3	2
Fridays	1	1	1	1	2	3	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	3	2
Saturdays	2	1	1	1	1	2	2	3	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	3
Sundays	2	2	1	1	1	1	2	2	3	N	N	N	N	N	N	N	N	N	N	N	N	N	N	3	2
Legend:																									
1 Provide at least one through freeway lane open in direction of travel																									
2 Provide at least two adjacent through freeway lanes open in direction of travel																									
3 Provide at least three adjacent through freeway lanes open in direction of travel																									
N No work permitted																									
REMARKS: Number of Through Traffic Lanes - 4*																									
* - Traffic lanes outside of the through traffic lanes delineated with a double line of pavement markers as shown on 'Pavement Markers and Traffic Lines Typical Details (Detail 37 series),' may be closed at the same time as adjacent through traffic lane or ramp is allowed to be closed.																									

Chart No. 2 Complete Freeway Closure Hours																									
County: LA										Route/Direction: 5/North															
Closure Limits: At Western Ave																									
FROM HOUR TO HOUR																									
	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mondays through Thursdays	C	C	C	C																					
Fridays	C	C	C	C																					
Saturdays		C	C	C	C																				
Sundays			C	C	C	C																			
Legend:																									
C Freeway may be closed completely																									
No complete freeway closure is permitted																									
REMARKS:																									
Detour traffic to exit at Western Ave off-ramp, north on Flower St, west on Alameda Ave to the on-ramp to northbound Route 5. Place a portable changeable message sign on the right shoulder of northbound Route 5 at Colorado Blvd on-ramp with the message: 'FREEWAY / CLOSED – AT / WESTERN / AVE'. Place a second portable changeable message sign on the right shoulder of westbound Route 134 at Pacific Ave off-ramp gore with the message: 'NORTH 5 / FREEWAY / CLOSED – AT / WESTERN / AVE'. A minimum of 8 special freeway detour signs shall be posted along the detour route as shown on the plan.																									

<b>Chart No. 3</b>																									
<b>Complete Ramp Closure Hours</b>																									
County: LA										Route/Direction: 5/North															
Closure Limits: Western Ave off-ramp																									
FROM HOUR TO HOUR    24 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24																									
Mondays through Thursdays		C	C	C	C	C	C	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	C	C
Fridays		C	C	C	C	C	C	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	C
Saturdays		C	C	C	C	C	C	C	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	C
Sundays		C	C	C	C	C	C	C	C	N	N	N	N	N	N	N	N	N	N	N	N	N	N	C	C
Legend:																									
C		Ramp may be closed completely																							
N		No work permitted																							

<b>Chart No. 4</b>																										
<b>Complete Ramp Closure Hours</b>																										
County: LA										Route/Direction: 5/North																
Closure Limits: (EB) Western Ave off-ramp																										
FROM HOUR TO HOUR    24 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24																										
Mondays through Thursdays		C	C	C	C	C	C	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	C	C
Fridays		C	C	C	C	C	C	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	C	
Saturdays		C	C	C	C	C	C	C	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	N	C	
Sundays		C	C	C	C	C	C	C	C	N	N	N	N	N	N	N	N	N	N	N	N	N	N	C	C	
Legend:																										
C		Ramp may be closed completely																								
N		No work permitted																								

Chart No. 5 Complete Ramp Closure Hours																										
County: LA										Route/Direction: 5/North																
Closure Limits: (EB) Western Ave on-ramp																										
FROM HOUR TO HOUR		24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mondays through Thursdays		C	C	C	C	C	C	N	N	N	C	C	C	C	C	C	N	N	N	N	N	C	C	C	C	
Fridays		C	C	C	C	C	C	N	N	N	C	C	C	C	C	C	N	N	N	N	N	C	C	C	C	
Saturdays		C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	
Sundays		C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	
Legend:																										
C		Ramp may be closed completely																								
N		No work permitted																								
REMARKS:																										
Detour traffic to continue east on Western Ave; north on Flower St; west on Alameda Ave to the on-ramp to northbound Route 5. A minimum of 10 special freeway detour signs (SP-2), as shown on plans, shall be posted along the detour route and shall be removed at the end of each closure. The full width of the traveled way shall be open for use by public traffic when construction operations are not actively in progress.																										

Chart No. 6 Complete Ramp Closure Hours																										
County: LA										Route/Direction: 5/North																
Closure Limits: (WB) Western Ave on-ramp																										
FROM HOUR TO HOUR		24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mondays through Thursdays		C	C	C	C	C	C	N	N	N	C	C	C	C	C	C	N	N	N	N	N	C	C	C	C	
Fridays		C	C	C	C	C	C	N	N	N	C	C	C	C	C	C	N	N	N	N	N	C	C	C	C	
Saturdays		C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	
Sundays		C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	
Legend:																										
C		Ramp may be closed completely																								
N		No work permitted																								
REMARKS:																										
Detour traffic to continue west on Western Ave; north on Victory Blvd; east on Alameda Ave to the on-ramp to northbound Route 5. A minimum of 10 special freeway detour signs (SP-2), as shown on plans, shall be posted along the detour route and shall be removed at the end of each closure. The full width of the traveled way shall be open for use by public traffic when construction operations are not actively in progress.																										

Chart No. 7 Complete Ramp Closure Hours																									
County: LA										Route/Direction: 5/North															
Closure Limits: (WB) Western Ave off-ramp																									
FROM HOUR TO HOUR 24 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24																									
Mondays through Thursdays		C	C	C	C	C	C	N	N	N	C	C	C	C	C	C	N	N	N	N	N	C	C	C	C
Fridays		C	C	C	C	C	C	N	N	N	C	C	C	C	C	C	N	N	N	N	N	C	C	C	C
Saturdays		C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Sundays		C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Legend:																									
C		Ramp may be closed completely																							
N		No work permitted																							

Chart No. 8 Complete City Street Closure																									
Location: Western Ave										Direction: East / West															
FROM HOUR TO HOUR 24 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24																									
Mondays through Thursdays		C	C	C	C	C	N	N	N	N	1	1	1	1	1	1	N	N	N	N	N	N	N	C	C
Fridays		C	C	C	C	C	N	N	N	N	1	1	1	1	1	1	N	N	N	N	N	N	N	C	C
Saturdays		C	C	C	C	C	C	1	1	N	N	N	N	N	N	N	N	N	N	N	N	N	N	C	C
Sundays		C	C	C	C	C	C	C	C	C	C	1	1	N	N	N	N	N	N	N	N	N	N	C	C
Legend:																									
1		Provide at least one city street lane open in direction of travel																							
C		Street may be closed																							
N		No work permitted																							
REMARKS: Number of Through Traffic Lanes - 2 in Each Direction.																									

Chart No. 9 City Street Requirements and Hours of Work																									
Location: Flower St										Direction: North / South															
FROM HOUR TO HOUR																									
	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mondays through Thursdays	1	1	1	1	1	N	N	N	N	1	1	1	1	1	1	N	N	N	N	1	1	1	1	1	1
Fridays	1	1	1	1	1	N	N	N	N	1	1	1	1	1	1	N	N	N	N	1	1	1	1	1	1
Saturdays	1	1	1	1	1	1	N	N	N	1	1	1	1	1	1	N	N	N	N	1	1	1	1	1	1
Sundays	1	1	1	1	1	1	1	N	N	1	1	1	1	1	1	N	N	N	N	1	1	1	1	1	1
Legend:																									
1		Provide at least one city street lane open in direction of travel																							
N		No work permitted																							
REMARKS: Number of Through Traffic Lanes – 2 in Each Direction																									

### 10-1.23 CLOSURE REQUIREMENTS AND CONDITIONS

Closures shall conform to the provisions in 'Maintaining Traffic' of these special provisions and these special provisions.

#### CLOSURE SCHEDULE

A written schedule of planned closures for the next week period, defined as Friday noon through the following Friday noon, shall be submitted by noon each Monday. A written schedule shall be submitted not less than 25 days and not more than 125 days before the anticipated start of any operation that will:

1. Reduce horizontal clearances, traveled way, including shoulders, to two lanes or less due to such operations as temporary barrier placement and paving
2. Reduce the vertical clearances available to the public due to such operations as pavement overlay, overhead sign installation, or falsework or girder erection

The Closure Schedule shall show the locations and times of the proposed closures. The Closure Schedule request forms furnished by the Engineer shall be used. Closure Schedules submitted to the Engineer with incomplete or inaccurate information will be rejected and returned for correction and resubmittal. The Contractor will be notified of disapproved closures or closures that require coordination with other parties as a condition of approval.

Closure Schedule amendments, including adding additional closures, shall be submitted by noon to the Engineer, in writing, at least 3 business days in advance of a planned closure. Approval of Closure Schedule amendments will be at the discretion of the Engineer.

The Engineer shall be notified of cancelled closures 2 business days before the date of closure.

Closures that are cancelled due to unsuitable weather may be rescheduled at the discretion of the Engineer.

#### CONTINGENCY PLAN

A detailed contingency plan shall be prepared for reopening closures to public traffic. If required by 'Beginning of Work, Time of Completion and Liquidated Damages' of these special provisions, the contingency plan shall be submitted to the Engineer before work at the job site begins. Otherwise, the contingency plan shall be submitted to the Engineer within one business day of the Engineer's request.

#### LATE REOPENING OF CLOSURES

If a closure is not reopened to public traffic by the specified time, work shall be suspended in conformance with the provisions in Section 8-1.05, 'Temporary Suspension of Work,' of the Standard Specifications. No further closures are to be made until the Engineer has accepted a work plan, submitted by the Contractor, that will insure that future closures will be reopened to public traffic at the specified time. The Engineer will have 2 business days to accept or reject the Contractor's proposed work plan. The Contractor will not be entitled to compensation for the suspension of work resulting from the late reopening of closures.

For each 10-minute interval, or fraction thereof past the time specified to reopen the closure (except for ramps and shoulders), the Department will deduct the amount per interval shown below from moneys due or that may become due the Contractor under the contract. Damages are limited to 5 percent of project cost per occurrence and will not be assessed when the Engineer requests that the closure remain in place beyond the scheduled pickup time.

Type of Facility	Route or Segment	Period	Damages/interval (\$)
Mainline	5	1st half hour	\$1,900 / 10 minutes
		2nd half hour	\$2,800 / 10 minutes
		2nd hour and beyond	\$3,800 / 10 minutes

**COMPENSATION**

The Engineer shall be notified of delays in the Contractor's operations due to the following conditions, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of those conditions, and the Contractor's loss due to that delay could not have been avoided by rescheduling the affected closure or by judicious handling of forces, equipment and plant, the delay will be considered a right of way delay and will be compensated in conformance with the provisions in Section 8-1.09, 'Right of Way Delays,' of the Standard Specifications:

1. The Contractor's proposed Closure Schedule is denied and his planned closures are within the time frame allowed for closures in 'Maintaining Traffic' of these special provisions, except that the Contractor will not be entitled to compensation for amendments to the Closure Schedule that are not approved.
2. The Contractor is denied a confirmed closure.

Should the Engineer direct the Contractor to remove a closure before the time designated in the approved Closure Schedule, delay to the Contractor's schedule due to removal of the closure will be considered a right of way delay and compensation for the delay will be determined in conformance with the provisions in Section 8-1.09, 'Right of Way Delays,' of the Standard Specifications.

**10-1.24 IMPACT ATTENUATOR VEHICLE**

**GENERAL**

**Summary**

Work includes protecting traffic and workers by using impact attenuator vehicle as a shadow vehicle when placing and removing components of a traffic control system, and when performing a moving lane closure.

Comply with Section 12-3.03, 'Flashing Arrow Signs,' of the Standard Specifications.

Impact attenuator vehicle must comply with the following test levels under National Cooperative Highway Research Program 350:

1. Test level 3 for pre-construction posted speed limit of -80 kph or more
2. Test levels 2 or 3 for pre-construction posted speed limit of -72 kph or less

Comply with the attenuator manufacturer's recommendations for:

1. Support truck
2. Trailer-mounted operation
3. Truck-mounted operation

**Definitions**

**impact attenuator vehicle:** Support truck towing a deployed attenuator mounted to a trailer or support truck with a deployed attenuator mounted to the support truck.

**Submittals**

Upon request, submit a Certificate of Compliance for attenuator to the Engineer under Section 6-1.07, 'Certificates of Compliance,' of the Standard Specifications.

**Quality Control and Assurance**

Attenuator must be a brand listed on the Department's pre-approved list under Highway Safety Features at:

[http://www.dot.ca.gov/hq/esc/approved\\_products\\_list/](http://www.dot.ca.gov/hq/esc/approved_products_list/)

## **MATERIALS**

The combined weight of the support truck and the attenuator must be at least 8,981 kg, except the weight of the support truck must not be less than 7,303 kg or greater than 11,975 kg.

If using the Trinity MPS-350 truck-mounted attenuator, the support truck must not have any underneath fuel tank mounted within 3.2 m of the rear of the support truck.

Each impact attenuator vehicle must:

1. Have standard brake lights, taillights, sidelights, and turn signals
2. Have an inverted 'V' chevron pattern placed across the entire rear of the attenuator composed of alternating 0.1 m wide non-reflective black stripes and 0.1 m wide yellow retroreflective stripes sloping at 45 degrees
3. Have a Type II flashing arrow sign
4. Have a flashing or rotating amber light
5. Have an operable 2-way communication system for maintaining contact with workers

## **CONSTRUCTION**

Use impact attenuator vehicle to follow behind equipment and workers who are placing and removing components of a traffic control system for a lane closure or a ramp closure. Flashing arrow sign must be operating in arrow mode during this activity. Follow at a distance to prevent intrusion into the workspace from passing traffic.

After placing components of a traffic control system for a lane closure or a ramp closure you may use impact attenuator vehicle in a closed lane and in advance of a work area to protect traffic and workers.

Use impact attenuator vehicle as a shadow vehicle under traffic control for a moving lane closure.

Secure objects including equipment, tools and ballast on impact attenuator vehicle to prevent loosening upon impact by an errant vehicle.

Do not use a damaged attenuator in the work. Replace, at your expense, an attenuator damaged from an impact during work.

## **MEASUREMENT AND PAYMENT**

Full compensation for furnishing and operating impact attenuator vehicle is included in the contract lump sum price paid for traffic control system, and no additional compensation will be allowed therefor.

### **10-1.25 TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE**

A traffic control system shall consist of closing traffic lanes and ramps in conformance with the details shown on the plans, the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications, the provisions under "Maintaining Traffic" and "Construction Area Signs" of these special provisions, and these special provisions.

The provisions in this section will not relieve the Contractor from the responsibility to provide additional devices or take measures as may be necessary to comply with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications.

Each vehicle used to place, maintain and remove components of a traffic control system on multilane highways shall be equipped with a Type II flashing arrow sign which shall be in operation when the vehicle is being used for placing, maintaining or removing components. Vehicles equipped with Type II flashing arrow sign not involved in placing, maintaining or removing components when operated within a stationary lane closure shall only display the caution display mode. The sign shall be controllable by the operator of the vehicle while the vehicle is in motion. The flashing arrow sign shown on the plans shall not be used on vehicles which are being used to place, maintain and remove components of a traffic control system and shall be in place before a lane closure requiring its use is completed.

If components in the traffic control system are displaced or cease to operate or function as specified, from any cause, during the progress of the work, the Contractor shall immediately repair the components to the original condition or replace the components and shall restore the components to the original location.

When lane and ramp closures are made for work periods only, at the end of each work period, components of the traffic control system, except portable delineators placed along open trenches or excavation adjacent to the traveled way, shall be removed from the traveled way and shoulder. If the Contractor so elects, the components may be stored at selected central locations designated by the Engineer within the limits of the highway right of way.

The contract lump sum price paid for traffic control system shall include full compensation for furnishing all labor, materials (including signs), tools, equipment, and incidentals, and for doing all the work involved in placing, removing, storing, maintaining, moving to new locations, replacing, and disposing of the components of the traffic control system shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The adjustment provisions in Section 4-1.03, "Changes," of the Standard Specifications shall not apply to the item of traffic control system. Adjustments in compensation for traffic control system will be made only for increased or decreased traffic control system required by changes ordered by the Engineer and will be made on the basis of the cost of the increased or decreased traffic control necessary. The adjustment will be made on a force account basis as provided in Section 9-1.03, "Force Account Payment," of the Standard Specifications for increased work and estimated on the same basis in the case of decreased work.

Traffic control system required by work which is classed as extra work, as provided in Section 4-1.03D of the Standard Specifications, will be paid for as a part of the extra work.

#### **10-1.26 TEMPORARY PAVEMENT DELINEATION**

Temporary pavement delineation shall be furnished, placed, maintained, and removed in conformance with the provisions in Section 12-3.01, "General," of the Standard Specifications and these special provisions. Nothing in these special provisions shall be construed as reducing the minimum standards specified in the California MUTCD or as relieving the Contractor from the responsibilities specified in Section 7-1.09, "Public Safety," of the Standard Specifications.

##### **GENERAL**

When the work causes obliteration of pavement delineation, temporary or permanent pavement delineation shall be in place before opening the traveled way to public traffic. Laneline pavement delineation shall be provided for traveled ways open to public traffic. On multilane roadways (freeways and expressways) edgeline delineation shall be provided for traveled ways open to public traffic.

The Contractor shall perform the work necessary to establish the alignment of temporary pavement delineation, including required lines or markers. Surfaces to receive application of paint or removable traffic tape temporary pavement delineation shall be dry and free of dirt and loose material. Temporary pavement delineation shall not be applied over existing pavement delineation or other temporary pavement delineation. Temporary pavement delineation shall be maintained until superseded or replaced with a new pattern of temporary pavement delineation or permanent pavement delineation, or as determined by the Engineer.

Temporary pavement markers, including underlying adhesive, and removable traffic tape that are applied to the final layer of surfacing or existing pavement to remain in place or that conflicts with a subsequent or new traffic pattern for the area shall be removed when no longer required for the direction of public traffic, as determined by the Engineer.

##### **TEMPORARY LANELINE DELINEATION**

When lanelines are obliterated and temporary pavement delineation to replace the lines is not shown on the plans, the minimum laneline delineation to be provided for that area shall be temporary pavement markers placed at longitudinal intervals of not more than 7.3 m. The temporary pavement markers shall be the same color as the laneline the pavement markers replace. Temporary pavement markers shall be, at the option of the Contractor, one of the temporary pavement markers listed for short term day/night use (14 days or less) or long term day/night use (180 days or less) in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. The temporary pavement markers shall be placed in conformance with the manufacturer's instructions. Temporary pavement markers for long term day/night use (180 days or less) shall be cemented to the surfacing with the adhesive recommended by the manufacturer, except epoxy adhesive shall not be used to place the temporary pavement markers in areas where removal of the temporary pavement markers will be required.

Temporary laneline delineation consisting entirely of temporary pavement markers listed for short term day/night use (14 days or less), shall be placed on longitudinal intervals of not more than 7.3 m and shall be used for a maximum of 14 days on lanes opened to public traffic. Before the end of the 14 days the permanent pavement delineation shall be placed. If the permanent pavement delineation is not placed within the 14 days, the Contractor shall replace the temporary pavement markers and provide additional temporary pavement delineation and shall bear the cost thereof. The additional temporary pavement delineation to be provided shall be equivalent to the pattern specified for the permanent pavement delineation for the area, as determined by the Engineer.

##### **TEMPORARY EDGELINE DELINEATION**

On multilane roadways (freeways and expressways), when edgelines are obliterated and temporary pavement delineation to replace those edgelines is not shown on the plans, the edgeline delineation to be provided for those areas adjacent to lanes open to public traffic shall be as follows:

1. Temporary pavement delineation for right edgelines shall, at the option of the Contractor, consist of either a solid 100-mm wide traffic stripe tape of the same color as the stripe it replaces, traffic cones, portable delineators or channelizers placed at longitudinal intervals not to exceed 30 m.

2. Temporary pavement delineation for left edgelines shall, at the option of the Contractor, consist of either solid 100-mm wide traffic stripe tape of the same color as the stripe it replaces, traffic cones, portable delineators or channelizers placed at longitudinal intervals not to exceed 30 m or temporary pavement markers placed at longitudinal intervals of not more than 1.8 m.

The lateral offset for traffic cones, portable delineators or channelizers used for temporary edgeline delineation shall be as determined by the Engineer. If traffic cones or portable delineators are used as temporary pavement delineation for edgelines, the Contractor shall provide personnel to remain at the project site to maintain the cones or delineators during the hours of the day that the portable delineators are in use.

Channelizers used for temporary edgeline delineation shall be the surface mounted type and shall be orange in color. Channelizer bases shall be cemented to the pavement in the same manner provided for cementing pavement markers to pavement in "Pavement Markers" of these special provisions, except epoxy adhesive shall not be used to place channelizers on the top layer of pavement. Channelizers shall be, at the Contractor's option, one of the surface mount types (900 mm) listed in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Temporary edgeline delineation shall be removed when no longer required for the direction of public traffic as determined by the Engineer.

#### **TEMPORARY TRAFFIC STRIPE (TAPE)**

The temporary traffic stripe tape shall be complete in place at the location shown before opening the traveled way to public traffic.

Removable traffic stripe tape shall be the temporary removable traffic stripe tape as listed in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Removable traffic stripe tape shall be applied in conformance with the manufacturer's installation instructions and shall be rolled slowly with a rubber tired vehicle or roller to ensure complete contact with the pavement surface. Traffic stripe tape shall be applied straight on tangent alignment and on a true arc on curved alignment. Traffic stripe tape shall not be applied when the air or pavement temperature is less than 10°C, unless the installation procedures to be used are approved by the Engineer, before beginning installation of the tape.

#### **TEMPORARY PAVEMENT MARKING (TAPE)**

Temporary pavement marking consisting of removable pavement marking tape shall be applied at the locations shown on the plans. The temporary pavement marking tape shall be complete in place at the location shown, before opening the traveled way to public traffic.

Removable pavement marking tape shall be the temporary removable type pavement marking tape listed in "Prequalified and Tested Signing and Delineation Materials" of these special provisions and shall be applied and removed in conformance with the provisions specified for applying and removing the temporary traffic stripe tape.

#### **TEMPORARY PAVEMENT MARKING (PAINT)**

Temporary pavement marking consisting of painted pavement marking shall be applied and maintained at the locations shown on the plans. The painted temporary pavement marking shall be complete in place at the location shown before opening the traveled way to public traffic. Removal of painted temporary pavement marking will not be required.

Temporary painted pavement marking shall conform to the provisions in "Paint Traffic Stripe and Pavement Marking" of these special provisions, except for payment. At the option of the Contractor, either one or 2 coats shall be applied regardless whether on new or existing pavement.

At the Contractor's option, temporary removable pavement marking tape or permanent pavement marking tape listed in "Prequalified and Tested Signing and Delineation Materials" of these special provisions may be used instead of painted temporary pavement markings. When pavement marking tape is used, regardless of which type of tape is placed, the tape will be measured and paid for by the square meter as temporary pavement marking (paint).

Retroreflective pavement markers conforming to the provisions in "Pavement Markers" of these special provisions may be used in place of temporary pavement markers for long term day/night use (180 days or less) except to simulate patterns of broken traffic stripe. Placement of the retroreflective pavement markers used for temporary pavement markers shall conform to the provisions in "Pavement Markers" of these special provisions except the waiting period provisions before placing the pavement markers on new hot mix asphalt surfacing as specified in Section 85-1.06, "Placement," of the Standard Specifications shall not apply and epoxy adhesive shall not be used to place pavement markers in areas where removal of the pavement markers will be required.

## **MEASUREMENT AND PAYMENT**

Temporary traffic stripe and temporary pavement marking shown on the plans will be measured and paid for in the same manner specified for paint traffic stripe and paint pavement marking in Section 84-3.06, "Measurement," and Section 84-3.07, "Payment," of the Standard Specifications.

Full compensation for furnishing, placing, maintaining, and removing the temporary pavement markers (including underlying adhesive, layout (dribble) lines to establish alignment of temporary pavement markers or used for temporary laneline delineation) for those areas where temporary laneline delineation is not shown on the plans and for providing equivalent patterns of permanent traffic lines for those areas when required, shall be considered as included in the contract prices paid for the items of work that obliterated the laneline pavement delineation and no separate payment will be made therefor.

Full compensation for furnishing, placing, maintaining, and removing temporary edgeline delineation not shown on the plans shall be considered as included in the contract prices paid for the items of work that obliterated the edgeline pavement delineation and no separate payment will be made therefor. The quantity of channelizers used as temporary edgeline delineation will not be included in the quantity of channelizer (surface mounted) to be paid for.

### **10-1.27 BARRICADE**

Barricades shall be furnished, placed and maintained at the locations shown on the plans, specified in the Standard Specifications or in these special provisions or where designated by the Engineer. Barricades shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to "Prequalified and Tested Signing and Delineation Materials" of these special provisions regarding retroreflective sheeting for barricades.

Construction area sign and marker panels conforming to the provisions in Section 12-3.06, "Construction Area Signs," of the Standard Specifications shall be installed on barricades in a manner determined by the Engineer at the locations shown on the plans.

Sign panels for construction area signs and marker panels installed on barricades shall conform to the provisions in Section 12-3.06A, "Stationary Mounted Signs," of the Standard Specifications.

Full compensation for furnishing, installing, maintaining, and removing construction area signs and marker panels on barricades shall be considered as included in the contract unit price paid for the type of barricade involved and no separate payment will be made therefor.

Barricades shown on the plans as part of a traffic control system will be paid for as provided in "Traffic Control System for Lane Closure" of these special provisions and will not be included in the count for payment of barricades.

### **10-1.28 PORTABLE CHANGEABLE MESSAGE SIGN**

Portable changeable message signs shall be furnished, placed, operated, and maintained at locations shown on the plans, as specified in "Maintaining Traffic" of these special provisions, or where designated by the Engineer and shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions. Messages displayed on the portable changeable message signs shall be as specified on the plans and shall conform to Section 12-3.12 "Portable Changeable Message Signs," of the Standard Specifications and "Maintaining Traffic" of these special provisions.'

Messages displayed on portable changeable message signs, as specified in these special provisions, as shown on the plans or as directed by the Engineer, shall not be displayed until 5 minutes prior to the closure installation as permitted by these special provisions. Portable changeable message signs shall have 24-hour timer control or remote control capability.

A Contractor's representative with a cellular phone shall be on the job site for operations that require portable changeable message signs. The representative shall modify messages as determined by the Engineer.

Full compensation for portable changeable message sign, including furnishing, placing, operating, maintaining, repairing, replacing, transporting from location to location, and modifying messages, shall be considered as included in the contract lump sum price paid for traffic control system and no separate payment will be made therefor.

### **10-1.29 CHANNELIZER**

Channelizers shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Channelizers shall conform to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

When no longer required for the work as determined by the Engineer, channelizers and underlying adhesive used to cement the channelizer bases to the pavement shall be removed. Removed channelizers and adhesive shall become the property of the Contractor and shall be removed from the site of work.

### **10-1.30 TEMPORARY TRAFFIC SCREEN**

Temporary traffic screen shall be furnished, installed, and maintained on top of temporary railing (Type K) at the locations designated on the plans, specified in the special provisions or directed by the Engineer and shall conform to the provisions specified for traffic handling equipment and devices in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Temporary traffic screen panels shall be new or used CDX Grade, or better, plywood or weather resistant strandboard mounted and anchored on temporary railing (Type K). Wale boards shall be new or used Douglas fir, rough sawn, Construction Grade, or better. Pipe screen supports shall be new or used galvanized steel pipe, Schedule 40. Nuts, bolts, and washers shall be cadmium plated. Screws shall be black or cadmium plated flat head, cross slotted screws with full thread length.

When no longer required, as determined by the Engineer, temporary traffic screen shall be removed from the site of the work and shall become the property of the Contractor.

### **10-1.31 TEMPORARY CRASH CUSHION MODULE**

This work shall consist of furnishing, installing, and maintaining sand filled temporary crash cushion modules in groupings or arrays at each location shown on the plans, as specified in these special provisions or where designated by the Engineer. The grouping or array of sand filled modules shall form a complete sand filled temporary crash cushion in conformance with the details shown on the plans and these special provisions.

Temporary crash cushions shall be secured in place prior to commencing work for which the temporary crash cushions are required.

Whenever the work or the Contractor's operations establishes a fixed obstacle, the exposed fixed obstacle shall be protected with a sand filled temporary crash cushion. The sand filled temporary crash cushion shall be in place prior to opening the lanes adjacent to the fixed obstacle to public traffic.

Sand filled temporary crash cushions shall be maintained in place at each location, including times when work is not actively in progress. Sand filled temporary crash cushions may be removed during a work period for access to the work provided that the exposed fixed obstacle is 4.6 m or more from a lane carrying public traffic and the temporary crash cushion is reset to protect the obstacle prior to the end of the work period in which the fixed obstacle was exposed. When no longer required, as determined by the Engineer, sand filled temporary crash cushions shall be removed from the site of the work.

Sand filled temporary crash cushion modules shall be one of the following, or equal, and be manufactured after March 31, 1997:

1. Energite III and Fitch Inertial Modules, manufactured by Energy Absorption Systems, Inc., 35 East Wacker Drive, Suite 1100, Chicago, IL 60601:
  - 1.1. Northern California: Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828, telephone (800) 884-8274, FAX (916) 387-9734
  - 1.2. Southern California: Traffic Control Service, Inc., 1818 E. Orangethorpe, Fullerton, CA 92831-5324, telephone (800) 222-8274, FAX (714) 526-9501
2. Traffix Sand Barrels, manufactured by Traffix Devices, Inc., 220 Calle Pinteroesco, San Clemente, CA 92672, telephone (949) 361-5663, FAX (949) 361-9205
  - 2.1. Northern California: United Rentals, Inc., 1533 Berger Drive, San Jose, CA 95112, telephone (408) 287-4303, FAX (408) 287-1929
  - 2.2. Southern California: Statewide Safety & Sign, Inc., P.O. Box 1440, Pismo Beach, CA 93448, telephone (800) 559-7080, FAX (805) 929-5786
3. CrashGard Model CC-48 Sand Barrels, manufactured by Plastic Safety Systems, Inc., 2444 Baldwin Road, Cleveland, OH 44104:
  - 3.1. Northern California:
    - 3.1.1. Capitol Barricade Safety & Sign, 6329 Elvas Ave, Sacramento, CA 95819, telephone (888) 868-5021, FAX (916) 451-5388
    - 3.1.2. Sierra Safety, Inc., 9093 Old State Highway, New Castle, CA 95658, telephone (916) 663-2026, FAX (916) 663-1858
  - 3.2. Southern California: Hi Way Safety Inc., 13310 5th Street, Chino, CA 91710, telephone (909) 591-1781, FAX (909) 627-0999

Modules contained in each temporary crash cushion shall be of the same type at each location. The color of the modules shall be the standard yellow color, as furnished by the vendor, with black lids. The modules shall exhibit good workmanship free from structural flaws and objectionable surface defects. The modules need not be new. Good used undamaged modules conforming to color and quality of the types specified herein may be utilized. If used Fitch modules requiring a seal are furnished, the top edge of the seal shall be securely fastened to the wall of the module by a continuous strip of heavy duty tape.

Modules shall be filled with sand in conformance with the manufacturer's directions, and to the sand capacity in pounds for each module shown on the plans. Sand for filling the modules shall be clean washed concrete sand of commercial quality. At the time of placing in the modules, the sand shall contain not more than 7 percent water as determined by California Test 226.

Modules damaged due to the Contractor's operations shall be repaired immediately by the Contractor at the Contractor's expense. Modules damaged beyond repair, as determined by the Engineer, due to the Contractor's operations shall be removed and replaced by the Contractor at the Contractor's expense.

Temporary crash cushion modules may be placed on movable pallets or frames. Comply with dimensions shown on the plans. The pallets or frames shall provide a full bearing base beneath the modules. The modules and supporting pallets or frames shall not be moved by sliding or skidding along the pavement or bridge deck.

A Type R or P marker panel shall be attached to the front of the crash cushion as shown on the plans, when the closest point of the crash cushion array is within 3.6 m of the traveled way. The marker panel, when required, shall be firmly fastened to the crash cushion with commercial quality hardware or by other methods determined by the Engineer.

At the completion of the project, temporary crash cushion modules, sand filling, pallets or frames, and marker panels shall become the property of the Contractor and shall be removed from the site of the work. Temporary crash cushion modules shall not be installed in the permanent work.

Temporary crash cushion modules will be measured by the unit as determined from the actual count of modules used in the work or ordered by the Engineer at each location. Temporary crash cushion modules placed in conformance with Section 7-1.09, "Public Safety," of the Standard Specifications and modules placed in excess of the number specified or shown will not be measured nor paid for.

Repairing modules damaged by public traffic will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. Modules damaged beyond repair by public traffic, when ordered by the Engineer, shall be removed and replaced immediately by the Contractor. Modules replaced due to damage by public traffic will be measured and paid for as temporary crash cushion module.

If the Engineer orders a lateral move of the sand filled temporary crash cushions and the repositioning is not shown on the plans, moving the sand filled temporary crash cushion will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications and these temporary crash cushion modules will not be counted for payment in the new position.

The contract unit price paid for temporary crash cushion module shall include full compensation for furnishing all labor, materials (including sand, pallets or frames and marker panels), tools, equipment, and incidentals, and for doing all the work involved in furnishing, installing, maintaining, moving, and resetting during a work period for access to the work, and removing from the site of the work when no longer required (including those damaged by public traffic) sand filled temporary crash cushion modules, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **10-1.32 EXISTING HIGHWAY FACILITIES**

The work performed in connection with various existing highway facilities shall conform to the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Attention is directed to Section 7-1.06, "Safety and Health Provisions," of the Standard Specifications. Work practices and worker health and safety shall conform to the California Division of Occupational Safety and Health Construction Safety Orders Title 8, of the California Code of Regulations including Section 5158, "Other Confined Space Operations."

#### **ABANDON PIPE LINE**

Existing utility pipelines, where shown on the plans to be abandoned, shall be abandoned in place or, at the option of the Contractor, the pipelines shall be removed and disposed of. Resulting openings into existing structures that are to remain in place shall be plugged with concrete conforming to the provisions in Section 90-10 "Minor Concrete," of the Standard Specifications. The concrete shall contain not less than 300 kg of cementitious material per cubic meter.

Abandoning pipelines in place shall conform to the following:

1. Pipelines that intersect the side slopes shall be removed to a depth of not less than one meter measured normal to the plane of the finished side slope, before being abandoned.
2. Pipelines 300 mm in diameter and larger, shall, at the Contractor's option, be backfilled with either sand, controlled low strength material or slurry cement backfill conforming to the provisions in Section 19-3.062, "Slurry Cement

Backfill," of the Standard Specifications by any method acceptable to the Engineer that completely fills the pipe. Sand backfill material shall be clean, free draining, and free from roots and other deleterious substances.

3. The ends of pipelines shall be securely closed by a 150 mm thick tight fitting plug or wall of commercial quality concrete.

Pipelines shall not be abandoned until their use is no longer required. The Contractor shall notify the Engineer in advance of any intended pipeline abandonment.

If the Contractor elects to remove and dispose of a pipeline which is specified to be abandoned, as provided herein, backfill specified for the pipe will be measured and paid for in the same manner as if the pipeline has been abandoned in place.

Backfill will be measured by the cubic meter determined from the dimensions of the pipelines to be abandoned.

The contract price paid per cubic meter for sand backfill shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in backfilling pipelines with sand, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Controlled low strength material and slurry cement backfill, if used at the Contractor's option, will be measured and paid for by the cubic meter as sand backfill.

Full compensation for concrete plugs, pipe removal, structure excavation, and backfill shall be considered as included in the contract price paid per meter for abandon pipeline and no additional compensation will be allowed therefor.

#### **REMOVE METAL BEAM GUARD RAILING**

Existing metal beam guard railing, where shown on the plans to be removed, shall be removed and disposed of.

Existing concrete anchors shall be completely removed and disposed of. Full compensation for removing concrete anchors shall be considered as included in the contract price paid per meter for remove metal beam guard railing and no separate payment will be made therefor.

Full compensation for removing cable anchor assemblies, terminal anchor assemblies shall be considered as included in the contract price paid per meter for remove metal beam guard railing and no separate payment will be made therefor.

#### **REMOVE SIGN STRUCTURE**

Existing sign structures, where shown on the plans to be removed, shall be removed and disposed of.

Overhead sign structure removal shall consist of removing posts, frames, portions of foundations, sign panels, walkways with safety railings, and sign lighting electrical equipment.

A sign structure shall not be removed until the structure is no longer required for the direction of public traffic.

Concrete foundations may be abandoned in place, except that the top portion, including anchor bolts, reinforcing steel, and conduits shall be removed to a depth of not less than 0.3 m below the adjacent finished grade. The resulting holes shall be backfilled and compacted with material equivalent to the surrounding material.

Electrical wiring shall be removed to the nearest pull box. Fuses within spliced connections in the pull box shall be removed and disposed of.

#### **REMOVE PAVEMENT MARKER**

Existing pavement markers, including underlying adhesive, when no longer required for traffic lane delineation as determined by the Engineer, shall be removed and disposed of.

#### **REMOVE CHAIN LINK FENCE**

Existing chain link fence, including post footings, where shown on the plans, shall be removed and disposed of.

Full compensation for backfilling and compacting post holes shall be considered as included in the contract price paid per meter for remove chain link fence and no additional compensation will be allowed therefor.

#### **REMOVE TRAFFIC STRIPE AND PAVEMENT MARKING**

Traffic stripe and pavement marking shall be removed at the locations shown on the plans and as directed by the Engineer.

Attention is directed to "Water Pollution Control" of these special provisions.

Waste from removal of yellow thermoplastic and yellow painted traffic stripe contains lead chromate in average concentrations greater than or equal to 5 mg/L Soluble Lead or 1000 mg/kg Total Lead. Yellow thermoplastic and yellow paint traffic stripe exist at locations shown on the plans. Residue produced from the removal of yellow thermoplastic and yellow paint contains heavy metals in concentrations that exceed thresholds established by the California Health and Safety Code and Title 22 of the California Code of Regulations. The Contractor shall assume that the residue is not regulated under

the Federal Resource Conservation and Recovery Act (RCRA). Yellow thermoplastic and yellow paint may produce toxic fumes when heated.

Waste from removal of yellow and white thermoplastic and yellow and white painted traffic stripe and white pavement marking contains lead chromate in average concentrations less than 5 mg/L Soluble Lead or 1000 mg/kg Total Lead. Yellow and white thermoplastic and yellow and white paint traffic stripe and white pavement marking exist at locations shown on the plans. The Contractor shall assume that the residue does not contain heavy metals in concentrations that exceed thresholds established by the California Health and Safety Code and Title 22 of the California Code of Regulations and is not regulated under the Federal Resource Conservation and Recovery Act (RCRA). Yellow and white thermoplastic and yellow and white paint may produce toxic fumes when heated.

The removed yellow thermoplastic and yellow paint shall be disposed of at a Class 1 disposal facility in conformance with the requirements of the disposal facility operator within 30 days after beginning accumulation of residue and dust. The Contractor shall make necessary arrangements to test the yellow thermoplastic and yellow paint residue as required by the disposal facility and these special provisions. Testing shall include, at a minimum, (1) Total Lead by EPA Method 6010B and Chromium by EPA Method 7000 series, (2) Soluble Lead and Chromium by California Waste Extraction Test, and (3) Soluble Lead and Chromium by Toxicity Characteristic Leaching Procedure. From the first 840 L of waste or portion thereof, if less than 840 L of waste are produced, a minimum of four randomly selected samples shall be taken and analyzed individually. Samples shall not be composited. From each additional 3360 L of waste or portion thereof, if less than 3360 L are produced, a minimum of one additional random sample shall be taken and analyzed. Each sample shall be homogenized prior to analysis by the laboratory performing the analyses. A sample aliquot sufficient to cover the amount necessary for the total and the soluble analyses shall then be taken. This aliquot shall be homogenized a second time and the total and soluble (if necessary) run on this aliquot. The homogenization process shall not include grinding of the samples. The Contractor shall submit the name and location of the disposal facility and analytical laboratory along with the testing requirements to the Engineer not less than 5 days prior to the start of removal of yellow thermoplastic and yellow painted traffic stripe. The analytical laboratory shall be certified by the Department of Health Services Environmental Laboratory Accreditation Program for all analyses to be performed. Test results shall be provided to the Engineer for review prior to signing a waste profile as requested by the disposal facility, prior to issuing an EPA identification number, and prior to allowing removal of the waste from the site.

The Contractor shall prepare a project specific Lead Compliance Plan to prevent or minimize worker exposure to lead while handling removed yellow and white thermoplastic and yellow and white paint residue. Attention is directed to Title 8, California Code of Regulations, Section 1532.1, "Lead," for specific Cal-OSHA requirements when working with lead.

The Lead Compliance Plan shall contain the elements listed in Title 8, California Code of Regulations, Section 1532.1(e)(2)(B). Before submission to the Engineer, the Lead Compliance Plan shall be approved by an Industrial Hygienist certified in Comprehensive Practice by the American Board of Industrial Hygiene. The Plan shall be submitted to the Engineer at least 7 days prior to beginning removal of yellow and white thermoplastic and yellow and white paint.

Prior to removing yellow and white thermoplastic and yellow and white painted traffic stripe and white pavement marking, personnel who have no prior training, including State personnel, shall complete a safety training program provided by the Contractor that meets the requirements of Title 8, California Code of Regulations, Section 1532.1, "Lead," and the Contractor's Lead Compliance Program.

Personal protective equipment, training, and washing facilities required by the Contractor's Lead Compliance Plan shall be supplied to State personnel by the Contractor. The number of State personnel will be 3.

Where grinding or other methods approved by the Engineer are used to remove yellow thermoplastic and yellow painted traffic stripe, the removed residue, including dust, shall be contained and collected immediately. Collection shall be by a high efficiency particulate air (HEPA) filter equipped vacuum attachment operated concurrently with the removal operations or other equally effective methods approved by the Engineer. The Contractor shall submit a written work plan for the removal, storage, and disposal of yellow thermoplastic and yellow painted traffic stripe to the Engineer for approval not less than 15 days prior to the start of the removal operations. Removal operations shall not be started until the Engineer has approved the work plan.

The removed yellow thermoplastic and yellow painted traffic stripe residue shall be stored and labeled in covered containers. Labels shall conform to the provisions of Title 22, California Code of Regulations, Sections 66262.31 and 66262.32. Labels shall be marked with date when the waste is generated, the words "Hazardous Waste," composition and physical state of the waste (for example, asphalt grindings with thermoplastic or paint), the word "Toxic," the name and address of the Engineer, the Engineer's telephone number, contract number, and Contractor or subcontractor. The containers shall be a type approved by the United States Department of Transportation for the transportation and temporary storage of the removed residue. The containers shall be handled so that no spillage will occur. The containers shall be stored in a secured fenced enclosure at a location within the project limits until disposal, as approved by the Engineer.

When the yellow thermoplastic and yellow painted traffic stripe residue is transported to a Class 1 disposal facility as a hazardous waste, a manifest shall be used, and the transporter shall be registered with the California Department of Toxic Substance Control. The Contractor shall submit a written request for the United States Environmental Protection Agency Identification Number (US EPA ID Number) to the Engineer. The Engineer will obtain the US EPA ID Number and sign all

manifests as the generator within 2 working days of receiving sample test results, approving the test methods, and receiving the written request for the US EPA ID Number from the Contractor. The Contractor shall submit receiving landfill documentation of proper disposal to the Engineer.

Additional disposal costs for removal residue regulated under RCRA, as determined by test results, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

Nothing in these special provisions shall relieve the Contractor of the Contractor's responsibilities as specified in Section 7-1.09, "Public Safety," of the Standard Specifications.

Attention is directed to "Material Containing Aerially Deposited Lead" of these special provisions regarding payment for the Lead Compliance Plan. One Lead Compliance Plan shall be prepared that addresses exposure to lead from traffic stripe and pavement marking and from lead in soil.

Full compensation for providing a written work plan for the removal, storage, and disposal of yellow thermoplastic and yellow painted traffic stripe and for providing receiving landfill documentation of proper disposal of yellow thermoplastic and yellow painted traffic stripe shall be considered as included in the contract prices paid per meter for remove yellow thermoplastic traffic stripe and remove yellow painted traffic stripe and no separate payment will be made therefor.

#### **REMOVE DRAINAGE FACILITY**

Existing pipes and inlets where shown on the plans to be removed, shall be completely removed and disposed of.

#### **REMOVE ROADSIDE SIGN**

Existing roadside signs, at those locations shown on the plans to be removed, shall be removed and disposed of.

Existing roadside signs shall not be removed until replacement signs have been installed or until the existing signs are no longer required for the direction of public traffic, unless otherwise directed by the Engineer.

#### **ADJUST INLET**

Existing pipe inlets and concrete drainage inlets shall be adjusted as shown on the plans.

Concrete shall be minor concrete conforming to the provisions in Section 90-10, "Minor Concrete," of the Standard Specifications. The concrete shall contain not less than 350 kg of cementitious material per cubic meter.

Adjustment of inlets shall be performed before paving and shall be limited to the area to be paved or surfaced during the working day in which the adjustment is performed. The top of the inlet grate or cover shall be protected from the hot mix asphalt during paving operations by means of heavy plywood covers, steel plate covers or by other methods approved by the Engineer. Excess paving material shall be removed before rolling.

#### **COLD PLANE ASPHALT CONCRETE PAVEMENT**

Existing asphalt concrete pavement shall be cold planed at the locations and to the dimensions shown on the plans.

Planing asphalt concrete pavement shall be performed by the cold planing method. Planing of the asphalt concrete pavement shall not be done by the heater planing method.

Cold planing machines shall be equipped with a cutter head not less than 750 mm in width and shall be operated so that no fumes or smoke will be produced. The cold planing machine shall plane the pavement without requiring the use of a heating device to soften the pavement during or prior to the planing operation.

The depth, width, and shape of the cut shall be as shown on the plans or as designated by the Engineer. The final cut shall result in a uniform surface conforming to the plans. The outside lines of the planed area shall be neat and uniform. Planing asphalt concrete pavement operations shall be performed without damage to the surfacing to remain in place.

Planed widths of pavement shall be continuous except for intersections at cross streets where the planing shall be carried around the corners and through the conform lines. Following planing operations, a drop-off of more than 45 mm will not be allowed between adjacent lanes open to public traffic.

Where transverse joints are planed in the pavement at conform lines no drop-off shall remain between the existing pavement and the planed area when the pavement is opened to public traffic. If Hot Mix Asphalt (HMA) has not been placed to the level of existing pavement before the pavement is to be opened to public traffic a temporary HMA taper shall be constructed. HMA for temporary tapers shall be placed to the level of the existing pavement and tapered on a slope of 1:30 (Vertical: Horizontal) or flatter to the level of the planed area.

HMA for temporary tapers shall be the same quality as the HMA used elsewhere on the project or shall conform to the material requirements for minor HMA. HMA for tapers shall be compacted by any method that will produce a smooth riding surface. Temporary HMA tapers shall be completely removed, including the removal of loose material from the underlying surface, before placing the permanent surfacing. The removed material shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The material planed from the roadway surface, including material deposited in existing gutters or on the adjacent traveled way, shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the

Highway Right of Way," of the Standard Specifications. Removal operations of cold planed material shall be concurrent with planing operations and follow within 15 m of the planer, unless otherwise directed by the Engineer.

Cold plane asphalt concrete pavement will be measured by the square meter. The quantity to be paid for will be the actual area of surface cold planed irrespective of the number of passes required to obtain the depth shown on the plans.

The contract price paid per square meter for cold plane asphalt concrete pavement shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in cold planing asphalt concrete surfacing and disposing of planed material, including furnishing the HMA for and constructing, maintaining, removing, and disposing of temporary HMA tapers, as specified in the Standard Specifications and these special provisions and as directed by the Engineer.

### **CAP INLET**

Existing pipe inlets and concrete drainage inlets, where shown on the plans to be capped, shall be capped and the bottoms of the inlets shall be rounded with portland cement concrete as shown on the plans.

Concrete shall be minor concrete conforming to the provisions in Section 90-10, "Minor Concrete," of the Standard Specifications. The concrete shall contain not less than 350 kg of cementitious material per cubic meter.

Inlets shall be removed to a depth of at least 0.3-m below the grading plane.

Concrete removal shall be performed without damage to portions of the inlet that are to remain in place. Damage to existing concrete, which is to remain in place, shall be repaired by the Contractor to a condition equal to that existing prior to the beginning of removal operations. The repair of existing concrete damaged by the Contractor's operations shall be at the Contractor's expense.

Existing reinforcement that is to be incorporated in the new work shall be protected from damage and shall be thoroughly cleaned of adhering material before being embedded in the new concrete.

The quantity of capping inlets will be determined as units from actual count.

The contract unit price paid for cap inlet shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in capping inlets, including removing portions of inlets, rounding bottoms of inlets, bar reinforcing steel, and structure excavation and structure backfill, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **EXISTING HIGHWAY IRRIGATION FACILITIES**

Existing irrigation facilities within the limits of work shall remain in place. Irrigation facilities that are damaged by the Contractor's operation shall be reported immediately to the Engineer.

Existing below ground irrigation facilities will be marked by the Engineer. Marked Irrigation facilities damaged by the Contractor's operations shall be repaired or replaced at the Contractor's expense. The replacement and repair of damaged unmarked below ground irrigation facilities will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Water shall be maintained in conformance with the provisions in Section 20-5.025, "Maintain Existing Water Supply," of the Standard Specifications.

### **BRIDGE REMOVAL**

Removing bridges or portions of bridges shall conform to the provisions in Section 15-4, "Bridge Removal," of the Standard Specifications and these special provisions.

Bridge removal (portion) shall consist of removing portions of structures including retaining wall, wing wall, bridge deck, railing, concrete box culvert, as required to complete the work as shown on the plans at the following locations:

Location A:  
Western Avenue UC (Widen)  
Bridge No. 53-1079S,

Location B:  
Justin Avenue PUC (Lengthen)  
Bridge No. 53-1078.

Removed materials that are not to be salvaged or used in the reconstruction shall become the property of the Contractor and shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The Contractor shall submit a complete bridge removal plan to the Engineer for each bridge listed above, detailing procedures, sequences, and all features required to perform the removal in a safe and controlled manner.

The bridge removal plan shall include, but not be limited to the following:

- A. The removal sequence, including staging of removal operations.
- B. Equipment locations on the structure during removal operations.
- C. Temporary support shoring or temporary bracing.
- D. Locations where work is to be performed over traffic or utilities.
- E. Details, locations, and types of protective covers to be used.
- F. Measures to assure that people, property, utilities, and improvements will not be endangered.
- G. Details and measures for preventing material, equipment, and debris from falling onto public traffic.

When protective covers are required for removal of portions of a bridge, or when superstructure removal works on bridges are involved, the Contractor shall submit working drawings, with design calculations, to the Engineer for the proposed bridge removal plan, and the bridge removal plan shall be prepared and signed by an engineer who is registered as a Civil Engineer in the State of California. The design calculations shall be adequate to demonstrate the stability of the structure during all stages of the removal operations. Calculations shall be provided for each stage of bridge removal and shall include dead and live load values assumed in the design of protective covers.

Temporary support shoring, temporary bracing, and protective covers, as required, shall be designed and constructed in conformance with the provisions in Section 51-1.06, "Falsework," of the Standard Specifications and these special provisions.

The assumed horizontal load to be resisted by the temporary support shoring and temporary bracing, for removal operations only, shall be the sum of the actual horizontal loads due to equipment, construction sequence or other causes, and an allowance for wind, but in no case shall the assumed horizontal load to be resisted in any direction be less than 5 percent of the total dead load of the structure to be removed.

The bridge removal plan shall conform to the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The number of sets of drawings, design calculations, and the time for reviewing bridge removal plans shall be the same as specified for falsework working drawings in Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications.

The following additional requirements apply to the removal of bridges or portions of bridges whenever the removal work is to be performed over public traffic:

- A. A protective cover shall be constructed before beginning bridge removal work. The protective cover shall be supported by shoring, falsework, or members of the existing structure. The Contractor shall be responsible for designing and constructing safe and adequate protective covers, shoring, and falsework with sufficient strength and rigidity to support the entire load to be imposed.
- B. The construction and removal of the protective cover, and the installation and removal of temporary railings shall conform to the provisions in "Maintaining Traffic," and "Temporary Railings" of these special provisions.
- C. Bridge removal methods shall be described in the working drawings, supported by calculations with sufficient details to substantiate live loads used in the protective cover design. Dead and live load values assumed for designing the protective cover shall be shown on the working drawings.
- D. The protective cover shall prevent any materials, equipment, or debris from falling onto public traffic. The protective cover shall have a minimum strength equivalent to that provided by good, sound Douglas fir planking having a nominal thickness of 50 mm. Additional layers of material shall be furnished as necessary to prevent fine materials or debris from sifting down upon the traveled way and shoulders.
- E. During the removal of bridge segments, and when portions of the bridge, such as deck slabs or box girder slabs, comply with the requirements for the protective cover, a separate protective cover need not be constructed.
- F. The protective cover shall extend at least 3 m beyond the outside face of the bridge railing, except that, at locations where the bridge railing is to be removed and new girders are not constructed, the protective cover shall extend from the face of the exterior girder or at least 0.6-m inside of the bridge railing to be removed, whichever is less, to at least 1.2 m beyond the outside face of the bridge railing.
- G. The protective cover shall provide the openings specified under "Maintaining Traffic" of these special provisions, except that when no openings are specified for bridge removal, a vertical opening of 4.6 m and a horizontal opening of 6.6 m shall be provided for the passage of public traffic.
- H. Falsework or supports for protective covers shall not extend below the vertical clearance level nor to the ground line at any location within the roadbed.
- I. The construction of the protective cover as specified herein shall not relieve the Contractor of responsibilities specified in Section 7-1.12A, "Indemnification," and Section 7-1.12B, "Insurance," of the Standard Specifications.
- J. Before removal of the protective cover, the Contractor shall clean the protective cover of all debris and fine material.

For bridge removal that requires the Contractor's registered engineer to prepare and sign the bridge removal plan, the Contractor's registered engineer shall be present at all times when bridge removal operations are in progress. The Contractor's registered engineer shall inspect the bridge removal operation and report in writing on a daily basis the progress of the operation and the status of the remaining structure. A copy of the daily report shall be available at the site of the work at all times. Should an unplanned event occur or the bridge operation deviate from the approved bridge removal plan, the Contractor's registered engineer shall submit immediately to the Engineer for approval, the procedure of operation proposed to correct or remedy the occurrence.

### **REMOVE CONCRETE**

Concrete, where shown on the plans to be removed, shall be removed.

The pay quantities of concrete to be removed will be measured by the cubic meter, measured before and during removal operations.

Concrete removed shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Where no joint exists between concrete to be removed and concrete to remain in place, the concrete shall be cut on a neat line to a minimum depth of 50 mm with a power driven saw before the concrete is removed.

Where concrete has been removed outside the roadway prism, the backfilled areas shall be graded to drain and blend in with the surrounding terrain.

Concrete to be removed which has portions of the same structure both above and below ground will be considered as concrete above ground for compensation.

### **10-1.33 CLEARING AND GRUBBING**

Clearing and grubbing shall conform to the provisions in Section 16, "Clearing and Grubbing," of the Standard Specifications.

### **10-1.34 EARTHWORK**

Earthwork shall conform to the provisions in Section 19, "Earthwork," of the Standard Specifications and these special provisions.

Structure backfill or roadway embankment within the limits of the bridge abutments as shown on the plans shall have an Expansion Index (EI) less than 50 and Sand Equivalent (SE) greater than 20. The Expansion Index shall be determined in accordance with ASTM D4829. The Sand Equivalent shall be determined in accordance with California Test Method 217.

At the locations and to the limits shown on the plans, structure backfill (bridge) shall also meet expansion index requirements as shown on the plans.

Full compensation for conforming to the above expansion index requirements shall be considered as included in the contract prices paid for the various contract items of work and no additional compensation will be allowed therefor.

Attention is directed to "Material Containing Aerially Deposited Lead" of these special provisions.

The grading plane of embankments beneath structure approach slabs and beneath the thickened portion of sleeper slabs shall not project above the grade established by the Engineer.

Surplus excavated material not designated as hazardous waste due to aerially deposited lead shall become the property of the Contractor and shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Where a portion of the existing surfacing is to be removed, the outline of the area to be removed shall be cut on a neat line with a power-driven saw to a minimum depth of 50 mm before removing the surfacing. Full compensation for cutting the existing surfacing shall be considered as included in the contract price paid per cubic meter for roadway excavation and no additional compensation will be allowed therefor.

The portion of imported borrow placed within 1.5 m of the finished grade shall have a Resistance (R-Value) of not less than 15.

Reinforcement or metal attached to reinforced concrete rubble placed in embankments shall not protrude above the grading plane. Prior to placement within 0.6-m below the grading plane of embankments, reinforcement or metal shall be trimmed to no greater than 20 mm from the face of reinforced concrete rubble. Full compensation for trimming reinforcement or metal shall be considered as included in the contract prices paid per cubic meter for the types of excavation shown in the Engineer's estimate, or the contract prices paid for furnishing and placing imported borrow or embankment material, as the case may be, and no additional compensation will be allowed therefor.

Imported borrow shall be mineral material including rock, sand, gravel, or earth. The Contractor shall not use man-made refuse in imported borrow including:

- A. Portland cement concrete

- B. Asphalt concrete
- C. Hot mix asphalt
- D. Material planed from roadway surfaces
- E. Residue from grooving or grinding operations
- F. Metal
- G. Rubber
- H. Mixed debris
- I. Rubble

Settlement periods are required for the bridge approach embankments at the bridges listed in the following table.

At the bridge bents listed in the following table, excavation for the footings, drilling holes for cast-in-place piles, or driving the foundation piles at each location shall not be done until the expiration of the settlement period for the embankment at the adjacent abutment of the same structure or an adjacent structure.

Surcharge embankments shall be constructed at or above the grading plane where listed in the following table:

Bridge Name or Number	Abutment Number	Bent Number	Surcharge Height (meters)	Settlement Period (days)
Western Ave UC (Widen)	1 and 3		0.0	30

The duration of the required settlement period at each location will be determined by the Engineer. The estimated duration of the settlement periods are listed in the tables of settlement data. The Engineer may order an increase or decrease in any settlement period. An ordered increase or decrease in any settlement period will result in an increase or decrease in the number of contract working days if the settlement period involved is considered to be the current controlling operation in conformance with the provisions in Section 8-1.06, "Time of Completion," of the Standard Specifications. Adjustments of contract time due to increases or decreases in settlement periods will be made by contract change order.

Pervious backfill material placed within the limits of payment for bridges will be measured and paid for as structure backfill (bridge).

Pervious backfill material placed within the limits of payment for retaining walls will be measured and paid for as structure backfill (retaining wall).

If structure excavation or structure backfill for bridges is not otherwise designated by type and payment for the structure excavation or structure backfill has not otherwise been provided for in the Standard Specifications or these special provisions, the structure excavation or structure backfill will be measured and paid for as structure excavation (bridge) or structure backfill (bridge), respectively.

### 10-1.35 CONTROLLED LOW STRENGTH MATERIAL

Controlled low strength material shall consist of a workable mixture of aggregate, cementitious materials, and water and shall conform to the provisions for slurry cement backfill in Section 19-3.062, "Slurry Cement Backfill," of the Standard Specifications and these special provisions.

At the option of the Contractor, controlled low strength material may be used as structure backfill for pipe culverts, except that controlled low strength material shall not be used as structure backfill for culverts having a diameter or span greater than 6.1 m.

When controlled low strength material is used for structure backfill, the width of the excavation shown on the plans may be reduced so that the clear distance between the outside of the pipe and the side of the excavation, on each side of the pipe, is a minimum of 300 mm. This minimum may be reduced to 150 mm when the height of cover is less than or equal to 6.1 m or the pipe diameter or span is less than 1050 mm.

Controlled low strength material in new construction shall not be permanently placed higher than the basement soil. For trenches in existing pavements, permanent placement shall be no higher than the bottom of the existing pavement permeable drainage layer. If a drainage layer does not exist, permanent placement in existing pavements shall be no higher than 25 mm below the bottom of the existing asphalt concrete surfacing or no higher than the top of base below the existing portland cement concrete pavement. The minimum height that controlled low strength material shall be placed, relative to the culvert invert, is 0.5 diameter or 0.5 height for rigid culverts and 0.7 diameter or 0.7 height for flexible culverts.

When controlled low strength material is proposed for use, the Contractor shall submit a mix design and test data to the Engineer for approval prior to excavating the trench for which controlled low strength material is proposed for use. The test data and mix design shall provide for the following:

- A. A 28-day compressive strength between 345 kPa and 690 kPa for pipe culverts having a height of cover of 6.1 m or less and a minimum 28-day compressive strength of 690 kPa for pipe culverts having a height of cover greater than 6.1 m. Compressive strength shall be determined in conformance with the requirements in ASTM Designation: D 4832.

- B. Cement shall be any type of portland cement conforming to the requirements in ASTM Designation: C 150; or any type of blended hydraulic cement conforming to the requirements in ASTM Designation: C 595M or the physical requirements in ASTM Designation: C 1157M. Testing of cement will not be required.
- C. Admixtures may be used in conformance with the provisions in Section 90-4, "Admixtures," of the Standard Specifications. Chemical admixtures containing chlorides as Cl in excess of one percent by mass of admixture, as determined in conformance with the requirements of California Test 415, shall not be used. If an air-entraining admixture is used, the maximum air content shall be limited to 20 percent. Mineral admixtures shall be used at the Contractor's option.

Materials for controlled low strength material shall be thoroughly machine-mixed in a pugmill, rotary drum or other approved mixer. Mixing shall continue until the cementitious material and water are thoroughly dispersed throughout the material. Controlled low strength material shall be placed in the work within 3 hours after introduction of the cement to the aggregates.

When controlled low strength material is to be placed within the traveled way or otherwise to be covered by paving or embankment materials, the material shall achieve a maximum indentation diameter of 76 mm prior to covering and opening to public traffic. Penetration resistance shall be measured in conformance with the requirements in ASTM Designation: D 6024.

Controlled low strength material used as structure backfill for pipe culverts will be considered structure backfill for compensation purposes.

#### **10-1.36 SAND BEDDING (AUSTIN VAULT)**

Sand bedding material shall consist of clean natural sand free from any organic matter and other deleterious materials in accordance with these special provisions.

##### **MATERIALS**

Sand bedding material shall consist of a clean natural sand conforming to the provisions in Section 90-3.03 "Fine Aggregate Grading," of the Standard Specifications.

Sand bedding material shall be thoroughly washed with a minimum of twice the sand bedding volume of potable water prior to placing in the austin vault.

##### **PLACEMENT**

Placement of the sand bedding material in austin vault sand filters shall conform to the following requirements:

1. The sand bedding material shall be placed in a manner that will not damage or cause permanent displacement of the filter fabric.
2. The sand bedding material shall be spread by methods that will produce a uniform finished surface to the grades shown on the plans.

##### **MEASUREMENT**

Sand bedding (austin vault) will be measured by the cubic meter. The quantity to be paid for will be calculated on the basis of the dimensions shown on the plans.

##### **PAYMENT**

The contract price paid per cubic meter for sand bedding (austin vault) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in furnishing and placing the sand bedding material, complete, in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

#### **10-1.37 MATERIAL CONTAINING AERIALY DEPOSITED LEAD**

Earthwork involving material containing aerially deposited lead shall conform to the provisions in Section 19, "Earthwork" of the Standard Specifications and these special provisions.

Attention is directed to "Aerially Deposited Lead" of these special provisions.

Type Y-2 material contains aerially deposited lead in average concentrations that exceed either 0.5 mg/L extractable lead (based on a modified waste extraction test using deionized water as the extractant) or 1411 mg/kg total lead but are less than 50 mg/L extractable lead (based on a modified waste extraction test using deionized water as the extractant) and less than 3397 mg/kg of total lead. Type Y-2 material exists as shown on the plans. This material shall be placed as shown on the plans, unless otherwise directed by the Engineer, and covered with a layer of pavement. This material is hazardous waste regulated by the State of California that may be reused as permitted under the Variance of DTSC provided that the lead

contaminated soil is placed a minimum of 1.5 m above the maximum water table elevation and protected from infiltration by a pavement structure which will be maintained by the Department. Temporary surplus material may be generated on this project due to the requirements of stage construction. Temporary surplus material shall not be transported outside the State right of way. In order to conform to the requirements of these provisions, it may be necessary to stockpile material for subsequent stages, to construct some embankments out of stage, or to handle temporary surplus material more than once.

Type Z-3 material contains aerially deposited lead in average concentrations (using the 95 percent Upper Confidence Limit) greater than 5.0 mg/L soluble lead, as tested using the Toxicity Characteristic Leaching Procedure Test. Type Z-3 material exists as shown on the plans. This material is Federally regulated hazardous waste and shall be transported to and disposed of at a Class I Disposal Site. Material excavated from these areas shall be transported by a hazardous waste transporter registered with the DTSC using the required procedures for creating a manifest for the material. The vehicles used to transport the hazardous material shall conform to the current certifications of compliance of the DTSC.

### **LEAD COMPLIANCE PLAN**

The Contractor shall prepare a project specific Lead Compliance Plan to prevent or minimize worker exposure to lead while handling material containing aerially deposited lead. Attention is directed to Title 8, California Code of Regulations, Section 1532.1, "Lead," for specific California Department of Industrial Relations, Division of Occupational Safety and Health (Cal-OSHA) requirements when working with lead.

The Lead Compliance Plan shall contain the elements listed in Title 8, California Code of Regulations, Section 1532.1(e)(2)(B). Before submission to the Engineer, the Lead Compliance Plan shall be approved by an Industrial Hygienist certified in Comprehensive Practice by the American Board of Industrial Hygiene. The plan shall be submitted to the Engineer for review and acceptance at least 15 days prior to beginning work in areas containing aerially deposited lead.

The Contractor shall not work in areas containing aerially deposited lead within the project limits, unless authorized in writing by the Engineer, until the Engineer has accepted the Lead Compliance Plan.

Prior to performing work in areas containing aerially deposited lead, personnel who have no prior training or are not current in their training status, including Department personnel, shall complete a safety training program provided by the Contractor. The safety training program shall meet the requirements of Title 8, California Code of Regulations, Section 1532.1, "Lead."

Personal protective equipment, training, and washing facilities required by the Contractor's Lead Compliance Plan shall be supplied to Department personnel by the Contractor. The number of Department personnel will be 3.

The Engineer will notify the Contractor of acceptance or rejection of the submitted or revised Lead Compliance Plan not more than 10 days after submittal of the plan.

The contract lump sum price paid for Lead Compliance Plan shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in preparing the Lead Compliance Plan, including paying the Certified Industrial Hygienist, and for providing personal protective equipment, training and medical surveillance, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **EXCAVATION AND TRANSPORTATION PLAN**

Within 15 days after approval of the contract, the Contractor shall submit 3 copies of an Excavation and Transportation Plan to the Engineer. The Engineer will have 7 days to review the plan. If revisions are required, as determined by the Engineer, the Contractor shall revise and resubmit the plan within 7 days of receipt of the Engineer's comments. The Engineer will have 7 days to review the revisions. Upon the Engineer's approval of the plan, 3 additional copies incorporating the required changes shall be submitted to the Engineer. Minor changes to or clarifications of the initial submittal may be made and attached as amendments to the Excavation and Transportation Plan. In order to allow construction to proceed, the Engineer may conditionally approve the plan while minor revisions or amendments are being completed.

The Contractor shall prepare the written, project specific Excavation and Transportation Plan establishing the procedures the Contractor will use to comply with requirements for excavating, stockpiling, transporting, and placing (or disposing) of material containing aerially deposited lead. The plan shall conform to the regulations of the DTSC and Cal-OSHA. The sampling and analysis portions of the Excavation and Transportation Plan shall meet the requirements for the design and development of the sampling plan, statistical analysis, and reporting of test results contained in USEPA, SW 846, "Test Methods for Evaluating Solid Waste," Volume II: Field Manual Physical/Chemical, Chapter Nine, Section 9.1. The plan shall contain, but not be limited to the following elements:

- A. Excavation schedule (by location and date),
- B. Temporary locations of stockpiled material,
- C. Dust control measures,
- D. Air monitoring,

1. Location and type of equipment,

2. Sampling frequency,
3. Analytical laboratory,

- E. Transportation equipment and routes,
- F. Method for preventing spills and tracking material onto public roads,
- G. Truck waiting and staging areas,
- H. Site for disposal of hazardous waste,
- I. Spill Contingency Plan for material containing aerielly deposited lead.

### **DUST CONTROL**

Excavation, transportation, placement, and handling of material containing aerielly deposited lead shall result in no visible dust migration. The Contractor shall have a water truck or tank on the job site at all times while clearing and grubbing and performing earthwork operations in work areas containing aerielly deposited lead.

### **STOCKPILING**

Stockpiles of material containing aerielly deposited lead shall not be placed where affected by surface run-on or run-off. Stockpiles shall be covered with plastic sheeting 0.33 mm minimum thickness or 0.3 m of non-hazardous material. Stockpiles shall not be placed in environmentally sensitive areas. Stockpiled material shall not enter storm drains, inlets, or waters of the State.

### **MATERIAL TRANSPORTATION**

Prior to traveling on public roads, loose and extraneous material shall be removed from surfaces outside the cargo areas of the transporting vehicles and the cargo shall be covered with tarpaulins or other cover, as outlined in the approved Excavation and Transportation Plan. The Contractor shall be responsible for costs due to spillage of material containing lead during transport.

The Department will not consider the Contractor a generator of the hazardous material, and the Contractor will not be obligated for further cleanup, removal, or remedial action for such material handled or disposed of in conformance with the requirements specified in these special provisions and the appropriate State and Federal laws and regulations and county and municipal ordinances and regulations regarding hazardous waste.

### **DISPOSAL**

Surplus material for which the lead content is not known shall be analyzed for aerielly deposited lead by the Contractor prior to removing the material from within the project limits. The Contractor shall submit a sampling and analysis plan and the name of the analytical laboratory to the Engineer at least 15 days prior to beginning sampling or analysis. The Contractor shall use a laboratory certified by the California Department of Health Services. Sampling shall be at a minimum rate of one sample for each 150 m<sup>3</sup> of surplus material and tested for lead using EPA Method 6010 or 7000 series.

Materials containing aerielly deposited lead shall be disposed of within California. The disposal site shall be operating under a permit issued by the appropriate California Environmental Protection Agency board or department.

The Engineer will obtain the Environmental Protection Agency Generator Identification Number for hazardous waste disposal. The Engineer will sign all hazardous waste manifests. The Contractor shall notify the Engineer 5 days before the manifests are to be signed.

Sampling, analyzing, transporting, and disposing of material containing aerielly deposited lead excavated outside the pay limits of excavation will be at the Contractor's expense.

### **MEASUREMENT AND PAYMENT**

Quantities of roadway excavation (aerielly deposited lead) and structure excavation (aerielly deposited lead), of the types shown in the Engineer's Estimate, will be measured and paid for in the same manner specified for roadway excavation and structure excavation, respectively, in Section 19, "Earthwork," of the Standard Specifications.

Full compensation for preparing an approved Excavation and Transportation Plan, transporting material containing aerielly deposited lead reused in the work from location to location, and transporting and disposing of material containing aerielly deposited lead shall be considered as included in the contract prices paid per cubic meter for the items of roadway excavation (aerielly deposited lead) and structure excavation (aerielly deposited lead) of the types involved, and no additional compensation will be allowed therefor.

No payment for stockpiling of material containing aerielly deposited lead will be made, unless the stockpiling is ordered by the Engineer.

Sampling, analyses, and reporting of results for surplus material not previously sampled will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

### **10-1.38 IRRIGATION CROSSOVERS**

Irrigation crossovers shall conform to the provisions in Section 20-5, "Irrigation Systems," of the Standard Specifications and these special provisions.

Conduits shall be placed in open trenches in conformance with the provisions in Section 20-5.03B, "Conduit for Irrigation Crossovers," of the Standard Specifications.

Conduits shall be corrugated high density polyethylene (CHDPE) pipe. Corrugated high density polyethylene pipe shall conform to the requirements in ASTM Designation: F 405 or F 667, or AASHTO Designation: M 252 or M 294 and shall be Type S. Couplings and fittings shall be as recommended by the pipe manufacturer.

Water line crossovers shall conform to the provisions in Section 20-5.03C, "Water Line Crossovers," of the Standard Specifications.

Sprinkler control crossovers shall conform to the provisions in Section 20-5.027D, "Sprinkler Control Crossovers," of the Standard Specifications.

Installation of pull boxes shall conform to the provisions in Section 20-5.027I, "Conductors, Electrical Conduit and Pull Boxes," of the Standard Specifications. When no conductors are installed in electrical conduits, pull boxes for irrigation crossovers shall be installed on a foundation of compacted soil.

Conduits shall be installed under existing paving by jacking or drilling methods in conformance with the provisions in Section 20-5.03B, "Conduit for Irrigation Crossovers," of the Standard Specifications.

### **10-1.39 WATER SUPPLY LINE (BRIDGE)**

Water supply lines identified on the plans as supply line (bridge) shall be of the size shown and shall conform to the details shown on the plans, the provisions in Section 20-5, "Irrigation Systems," of the Standard Specifications, and these special provisions.

#### **GENERAL**

Unless otherwise shown on the plans, casings shall be installed at each abutment and shall be extended to the greater of: (1) 1.5 m beyond the approach slab, (2) 1.5 m beyond the end of the adjacent wingwall, or (3) 6 m beyond the abutment.

#### **Working Drawings**

The Contractor shall submit complete working drawings for the temporary support of the casing at the abutments to the Offices of Structure Design (OSD) in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications.

For initial review, 5 sets of drawings shall be submitted. After review, between 6 and 12 sets, as requested by the Engineer, shall be submitted to the OSD for final approval and use during construction.

#### **MATERIALS**

##### **Pipe and Fittings for Supply Lines Less Than NPS 4**

Pipe and fittings for supply lines less than NPS 4 shall conform to the provisions in Section 20-2.15A, "Steel Pipe," of the Standard Specifications.

##### **Air Release Valve Assemblies for Supply Lines Less Than NPS 4**

Each air release valve assembly for supply lines less than NPS 4 shall consist of a threaded tee of the same diameter as the supply line or pipe saddle, an NPS 1 ball valve, an automatic air release valve, and a tank vent. The air release valve shall have a cast iron body with stainless steel trim and float, an NPS 1 inlet pipe connection, and a 4.8 mm orifice. The tank vent shall be the size of the air release valve outlet and shall have a double opening facing down with screen cover.

##### **Casing Insulators for Supply Lines Less Than NPS 4**

Casing insulators for supply lines less than NPS 4 shall be designed for the size of casing and the supply line shown on the plans. Casing insulators for supply lines shall be high density, injection molded polyethylene, 2-piece construction with cadmium plated nuts and bolts and shall have a nonconductive inner liner. Casing insulators shall be factory constructed to ensure the supply line is centered in the casing to avoid any pipe to pipe contact and shall have at least 2 runners seated on the bottom of the casing.

##### **Pipe End Seals for Supply Lines Less Than NPS 4**

Pipe end seals for supply lines less than NPS 4 shall cover the space between the supply line and the end of the casing. Pipe end seals shall be made with 50 mm thick construction grade redwood and cut to fit the supply line.

### **Expansion Assemblies for Supply Lines Less Than NPS 4**

Expansion assemblies for supply lines less than NPS 4 shall be the hose type. Hose shall be medium or heavy weight, oil resistant, flexible, reinforced with a minimum of 2-ply synthetic yarn or steel wire, equipped with steel flanges, and shall have rubber or synthetic rubber cover and tube. The hose and flange assembly shall have the same nominal inside diameter as the supply line and shall be rated for a minimum working pressure of 1.4 MPa. Hoses carrying potable water shall meet Food and Drug Administration standards.

### **Insulated Flange Connections**

Each insulated flange connection shall consist of a dielectric flange gasket, insulating washers, and sleeves held in place with steel bolts and nuts. The gasket shall have a minimum dielectric rating of 500 V/0.025 mm.

### **Casings**

Casings shall be welded steel pipe and shall conform to the provisions in Section 70-1.02B, "Welded Steel Pipe," of the Standard Specifications and these special provisions. Prior to shipping, exterior surfaces of welded steel pipe shall be cleaned and coated in conformance with the requirements in ANSI/AWWA C213, or at the option of the Contractor, cleaned, primed, and coated in conformance with the requirements in ANSI/AWWA C214.

### **Pipe Wrapping Tape**

Wrapping tape for pipe in contact with the earth shall be a pressure sensitive polyvinyl chloride or polyethylene tape with a minimum thickness of 1.27 mm.

### **Pipe Hanger Assemblies**

Each pipe hanger assembly shall consist of a concrete clevis plate or embedded steel welded linked eye rods, an adjustable steel yoke, a cast iron pipe roller, a steel roller rod, and hex nuts. Parts shall be galvanized. The pipe hanger assembly shall be suitable for the type and size of pipe installed and shall be as shown on the plans.

Steel hangers, anchor bolts, pipe clamps, nuts and bolts, and other fittings shall be suitable for the type and size of the supply lines or casings and shall conform to the provisions in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications.

### **Pipe Anchorages for Supply Lines Less Than NPS 4**

Each pipe anchorage located halfway between the hose assembly shall consist of a fabricated steel I beam, U bolts, concrete expansion anchors or L anchor bolts, and double nuts suitable for the type and size of pipe installed and shall conform to the details shown on the plans and the provisions in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications.

### **Epoxy Adhesive**

Epoxy adhesive shall conform to the provisions in Section 95, "Epoxy," of the Standard Specifications and one of the following:

- A. Section 95-2.01, "Binder (Adhesive), Epoxy Resin Base," for load bearing applications.
- B. Section 95-2.04, "Rapid Set Epoxy Adhesive for Pavement Markers."
- C. Section 95-2.05, "Standard Set Epoxy Adhesive for Pavement Markers."

### **INSTALLATION**

Water supply lines in bridge structures shall be supported as shown on the plans and in conformance with these special provisions.

If a blockout is provided in the bridge abutment wall for casing, the space between the casing and bridge abutment wall shall be filled with mortar conforming to the provisions in Section 51-1.135, "Mortar," of the Standard Specifications.

Openings for supply lines through bridge superstructure concrete shall either be formed or shall consist of pipe sleeves.

### **Cleaning and Closing of Pipe**

The interior of the pipe shall be cleaned before installation. Openings shall be capped or plugged as soon as the pipe is installed to prevent the entrance of foreign material. The caps or plugs shall remain in place until the adjacent pipe sections are to be installed.

### **Wrapping and Coating Pipe**

Damaged coating on supply line pipe in contact with the earth shall be wrapped with tape as follows:

- A. Pipe to be wrapped shall be thoroughly cleaned and primed as recommended by the tape manufacturer.
- B. Tape shall be tightly applied with one-half uniform lap, free from wrinkles and voids to provide not less than a 2.5 mm thickness.
- C. Field joints and fittings for wrapped pipe shall be covered by double wrapping 1.27 mm thick tape. Wrapping at joints shall extend a minimum of 150 mm over adjacent pipe coverings. Width of tape for wrapping fittings shall not exceed 50 mm. Adequate tension shall be applied so that the tape will conform closely to the contours of the joint.

**TESTING**

Water supply lines less than NPS 4 shall be tested in conformance with the provisions in Section 20-5.03H(1), "Method A," of the Standard Specifications, except that the testing period shall be 4 hours minimum with no leakage or pressure drop.

The Contractor shall furnish pipe anchorages to resist thrust forces occurring during testing. Leaks shall be repaired and defective materials shall be replaced by the Contractor at the Contractor's expense.

Pressure testing and necessary repairing of water lines shall be completed prior to backfilling, placing deck slabs over supply lines in box girder cells, or otherwise covering the supply lines.

Each end of the supply line shall be capped prior to and after the testing.

The supply line shall be tested as one unit. The limits of the unit shall be 1.5 m beyond the casing at each end of the bridge.

**MEASUREMENT AND PAYMENT**

Measurement and payment for supply line (bridge) for each size listed in the Engineer's Estimate shall be made in the same manner as galvanized steel pipe and plastic pipe supply lines in Section 20-5.04, "Measurement," and Section 20-5.05, "Payment," of the Standard Specifications.

Full compensation for furnishing and installing air release valve assemblies, steel hangers, steel brackets and other fittings, casings and casing insulators, pipe end seals, pipe anchorages, pipe wrapping tape, epoxy adhesives, and expansion assemblies; for cleaning, closing, wrapping, and coating pipe; and for pressure testing shall be considered as included in the contract prices paid per meter for the sizes of water supply line (bridge) involved, and no additional compensation will be allowed therefor.

**10-1.40 AGGREGATE BASE**

Aggregate bases must comply with Section 26, "Aggregate Bases," of the Standard Specifications and these special provisions.

Aggregate base must be Class 2 or Class 3 where specified.

Do not store reclaimed asphalt concrete or aggregate base with reclaimed asphalt concrete within 30 m measured horizontally of any culvert, watercourse, or bridge.

For Class 3 aggregate base, choose the 37.5-mm maximum or the 19-mm maximum grading.

Aggregate for Class 3 aggregate base must comply with:

Grading (Percentage Passing )

Sieve Sizes	37.5-mm Maximum		19-mm Maximum	
	Operating Range	Contract Compliance	Operating Range	Contract Compliance
50-mm	100	100	-----	-----
37.5-mm	90 - 100	87 - 100	-----	-----
25-mm	-----	-----	100	100
19-mm	50 - 90	45 - 95	90 - 100	87 - 100
4.75-mm	25 - 60	20 - 65	40 - 70	35 - 75
600-µm	10 - 35	6 - 39	12 - 40	7 - 45
75-µm	3 - 15	0 - 19	3 - 15	0 - 19

Quality

Tests	Operating Range	Contract Compliance
Sand Equivalent	21 min.	18 min.
Resistance (R-value)	-----	50 min.

If tests show grading or sand equivalent does not comply with the "Operating Range" specifications but complies with the "Contract Compliance" specifications, you may place aggregate base for the remainder of that day. Do not start another

day's work until tests or other information indicate the next day's material complies with the "Operating Range" specifications.

If tests show grading or sand equivalent does not comply with the "Contract Compliance" specifications, remove the aggregate base represented by the tests. If you request and the Engineer approves, that aggregate base may remain in place and the Department reduces payment by \$3.25 per cubic meter for that aggregate base quantity left in place. If the base remains in place and both the grading and sand equivalent do not comply with "Contract Compliance" specifications, the Department only makes one payment reduction.

No single grading or sand equivalent test may represent more than the smaller of 400 m<sup>3</sup> or one day's production.

If aggregate base is specified to be measured by the tonne, the Engineer converts tonnes to cubic meters for the purpose of reducing payment for noncompliant aggregate base left in place.

The maximum compacted thickness of any 1 layer of aggregate base must not exceed 150 mm.

#### 10-1.41 PERMEABLE MATERIAL (AUSTIN VAULT)

Permeable material for austin vault shall conform to the provisions in Section 26 "Aggregate Bases," of the Standard Specifications and these special provisions.

#### MATERIALS

The permeable material shall be considered Class 3 aggregate base, and shall conform to the grading requirements specified in the following table. At the option of the Contractor, the grading for either the No. 5 or No. 56 Coarse Aggregate shall be used; except that once a grading is selected the grading shall not be changed without the Engineer's written approval.

AGGREGATE GRADING REQUIREMENTS

Sieve Sizes	No. 5 Coarse Aggregate (AASHTO M43)	No. 56 Coarse Aggregate (AASHTO M43)
	% Passing	% Passing
37.5-mm	100	100
25-mm	90-100	90-100
19-mm	20-55	40-75
12.5-mm	0-10	15-35
9.5-mm	0-5	0-15
4.75-mm	N/A	0-5

#### PLACEMENT

Placement of the permeable material in Austin vault sand filters shall conform to the following requirements:

1. The permeable material shall be placed in a manner that will not damage or cause permanent displacement of the underdrain pipes.
2. The permeable material shall be spread by methods that will produce a uniform layer free from pockets of coarse or fine material.
3. Damage to the underdrain piping resulting from the Contractor's equipment or operations shall be replaced or repaired by the Contractor at the Contractor's expense.

#### MEASUREMENT

Permeable material (austin vault) will be measured by the cubic meter. The quantity to be paid for will be calculated on the basis of the dimensions shown on the plans.

#### PAYMENT

The contract price paid per cubic meter for permeable material (austin vault) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in furnishing and placing the permeable material, complete, in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

#### 10-1.42 LEAN CONCRETE BASE

Lean concrete base shall conform to the provisions in Section 28, "Lean Concrete Base," of the Standard Specifications and these special provisions.

The finished surface of lean concrete base shall not be above the grade established by the Engineer, or more than 15 mm below the grade established by the Engineer.

## 10-1.43 HOT MIX ASPHALT

### GENERAL

#### Summary

This work includes producing and placing hot mix asphalt (HMA) Type B using the Standard process. Comply with Section 39, "Hot Mix Asphalt," of the Standard Specifications.

#### Data Cores

Three business days before starting coring, submit proposed methods and materials for backfilling data core holes. Submit to the Engineer and electronically to [Coring@dot.ca.gov](mailto:Coring@dot.ca.gov):

1. A summary of data cores taken
2. A photograph of each data core

For each data core, the summary must include:

1. Project identification number
2. Date cored
3. Core identification number
4. Type of materials recovered
5. Type and approximate thickness of unstabilized material not recovered
6. Total core thickness
7. Thickness of each individual material to within:
  - 7.1 For recovered material, 12.5 mm
  - 7.2 For unstabilized material, 25 mm
8. Location including:
  - 8.1. County
  - 8.2. Route
  - 8.3. Post mile
  - 8.4. Lane number
  - 8.5. Lane direction
  - 8.6. Station

Each data core digital photograph must include a ruler laid next to the data core. Each photograph must include:

1. The core
2. Project identification number
3. Core identification number
4. Date cored
5. County
6. Route
7. Post mile
8. Lane number
9. Lane direction

After data core summary and photograph submittal, dispose of cores under Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

### MATERIALS

#### Asphalt Binder

The grade of asphalt binder mixed with aggregate for HMA Type B must be PG 70-10.

#### Aggregate

The aggregate for HMA Type B must comply with the 19-mm grading.

## **CONSTRUCTION**

### **Vertical Joints**

Before opening the lane to public traffic, pave shoulders and median borders adjacent to a lane being paved.

Do not leave a vertical joint more than 45 mm high between adjacent lanes open to public traffic.

Place HMA on adjacent traveled way lanes so that at the end of each work shift, the distance between the ends of HMA layers on adjacent lanes is between 1.5 m and 3.0 m. Place additional HMA along the transverse edge at each lane's end and along the exposed longitudinal edges between adjacent lanes. Hand rake and compact the additional HMA to form temporary conforms. You may place Kraft paper or another approved bond breaker under the conform tapers to facilitate the taper removal when paving operations resume.

### **Widening**

If widening existing pavement, construct new structural section on both sides of the existing pavement to match the elevation of the existing pavement's edge for the project's entire length before placing HMA over the existing pavement.

If widening existing pavement, construct new structural section on both sides of the existing pavement to match the elevation of the existing pavement's edge at each location before placing HMA over the existing pavement.

### **Conform Tapers**

Place shoulder conform tapers concurrently with the adjacent lane's paving.

Place additional HMA along the pavement's edge to conform to road connections and private drives. Hand rake, if necessary, and compact the additional HMA to form a smooth conform taper.

### **Data Cores**

Take data cores that include the completed HMA pavement, underlying base, and subbase material. Protect data cores and surrounding pavement from damage.

Take 100-mm or 150-mm diameter data cores:

1. At the beginning, end, and every 800 m within the paving limits of each route on the project
2. After all paving is complete
3. From the center of the specified lane

On a 2-lane roadway, take data cores from either lane. On a 4-lane roadway, take data cores from each direction in the outermost lane. On a roadway with more than 4 lanes, take data cores from the median lane and the outermost lane in each direction.

Each core must include the stabilized materials encountered. You may choose not to recover unstabilized material but you must identify the material. Unstabilized material includes:

1. Granular material
2. Crumbled or cracked stabilized material
3. Sandy or clayey soil

## **PAYMENT**

The contract lump sum price paid for data core includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in data coring, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

### **10-1.44 HOT MIX ASPHALT AGGREGATE LIME TREATMENT - SLURRY METHOD**

#### **GENERAL**

##### **Summary**

This work includes treating hot mix asphalt (HMA) aggregate with lime using the slurry method and placing it in stockpiles to marinate.

Treat aggregate for HMA Type B with lime slurry.

##### **Submittals**

Determine the exact lime proportions for fine and coarse virgin aggregate and submit them as part of the proposed job mix formula (JMF) under Section 39, "Hot Mix Asphalt," of the Standard Specifications.

Submit the averaged aggregate quality test results to the Engineer within 24 hours of sampling. Submit a treatment data log from the slurry proportioning device in the following order:

1. Treatment date
2. Time of day the data is captured
3. Aggregate size being treated
4. Wet aggregate flow rate collected directly from the aggregate weigh belt
5. Moisture content of the aggregate just before treatment, expressed as a percent of the dry aggregate mass
6. Dry aggregate flow rate calculated from the wet aggregate flow rate
7. Lime slurry flow rate measured by the slurry meter
8. Dry lime flow rate calculated from the slurry meter output
9. Approved lime ratio for each aggregate size being treated
10. Actual lime ratio calculated from the aggregate weigh belt and the slurry meter output, expressed as a percent of the dry aggregate mass
11. Calculated difference between the approved lime ratio and the actual lime ratio
12. Dry lime and water proportions at the slurry treatment time

Every day during lime treatment, submit the treatment data log on electronic media in tab delimited format on a removable CD-ROM storage disk. Each continuous treatment data set must be a separate record using a line feed carriage return to present the specified data on one line. The reported data must include data titles at least once per report.

### Quality Control and Assurance

Your quality control plan (QCP) must include aggregate quality control sampling and testing during aggregate lime treatment. Perform sampling and testing in compliance with:

#### Aggregate Quality Control During Lime Treatment

Quality Characteristic	Test Method	Minimum sampling and testing frequency
Sand Equivalent	CT 217	Once per 1 000 tonnes of aggregate treated with lime
Percent of crushed particles	CT 205	As necessary and as designated in the QCP
Los Angeles Rattler	CT 211	
Fine aggregate angularity	AASHTO T 304, Method A	
Flat and elongated particles	ASTM D 4791	

Note:

During lime treatment, sample coarse and fine aggregate from individual stockpiles. Combine aggregate in the JMF proportions. Run tests for aggregate quality in triplicate and report test results as the average of 3 tests.

The Engineer orders proportioning operations stopped for any of the following if you:

1. Do not submit the treatment data log.
2. Do not submit the aggregate quality control data.
3. Submit incomplete, untimely, or incorrectly formatted data.
4. Do not take corrective actions.
5. Take late or unsuccessful corrective actions.
6. Do not stop treatment when proportioning tolerances are exceeded.
7. Use malfunctioning or failed proportioning devices.

If you stop treatment, notify the Engineer of any corrective actions taken and conduct a successful 20-minute test run before resuming treatment.

For the aggregate to be treated, determine the moisture content at least once during each 2 hours of treatment. Calculate moisture content under California Test 226 or California Test 370 and report it as a percent of dry aggregate mass. Use the moisture content calculations as a set point for the proportioning process controller.

## MATERIALS

High-calcium hydrated lime and water must comply with Section 24-1.02, "Materials," of the Standard Specifications.

Before virgin aggregate is treated, it must comply with the aggregate quality specifications. Do not test treated aggregate for quality control except for gradation. The Engineer does not test treated aggregate for acceptance except for gradation. If reclaimed asphalt pavement (RAP) is used, the Engineer determines combined aggregate gradations containing RAP under Laboratory Procedure LP-9.

The Engineer determines the combined aggregate gradation during HMA production after you have treated aggregate. Treated aggregate must not have lime balls or clods.

## CONSTRUCTION

### General

Notify the Engineer at least 24 hours before the start of aggregate treatment.

Treat aggregate separate from HMA production.

Do not treat RAP.

Add lime to the aggregate as slurry consisting of mixed dry lime and water at a ratio of 1 part lime to between 2 parts and 3 parts water by mass. The slurry must completely coat the aggregate.

Lime treat and marinate coarse and fine aggregates separately.

Immediately before mixing lime slurry with aggregate, water must not visibly separate from aggregate.

Treat aggregate and stockpile for marination only once.

The lime ratio is the kilograms of dry hydrated lime per 100 kg of dry virgin aggregate expressed as a percent. Water content of slurry or untreated aggregate must not affect the lime ratio.

Lime ratio ranges are:

Aggregate Gradation	Lime Ratio
Coarse	0.4 to 1.0
Fine	1.5 to 2.0
Combined virgin aggregate	0.8 to 1.5

The lime ratio for fine and coarse aggregate must be within  $\pm 0.2$  percent of the lime ratio in the accepted JMF. The lime ratio must be within  $\pm 0.2$  percent of the approved lime ratio when you combine the individual aggregate sizes in the JMF proportions. Determine the lime ratio before adding RAP.

If 3 consecutive sets of recorded treatment data indicate deviation more than 0.2 percent above or below the lime ratio in the accepted JMF, stop treatment.

If a set of recorded treatment data indicates a deviation of more than 0.4 percent above or below the lime ratio in the accepted JMF, stop treatment and do not use the material represented by that set of data in HMA.

If 20 percent or more of the total daily treatment indicates deviation of more than 0.2 percent above or below the lime ratio in the accepted JMF, stop treatment and do not use the day's total treatment in HMA.

If you stop treatment for noncompliance, you must implement corrective action and successfully treat aggregate for a 20-minute period. Notify the Engineer before beginning the 20-minute treatment period.

### Lime Slurry Proportioning

Proportion lime and water with a continuous or batch operation.

The device controlling slurry proportioning must produce a treatment data log. The log consists of a series of data sets captured at 10-minute intervals throughout daily treatment. The data must be a treatment activity register and not a summation. The material represented by the data set is the amount produced 5 minutes before and 5 minutes after the capture time. For the contract's duration, collected data must be stored by the controller.

### Proportioning and Mixing Lime Slurry Treated Aggregate

Treat HMA aggregate by proportioning lime slurry and aggregate by mass in a continuous operation.

Marinate treated aggregate in stockpiles from 24 hours to 60 days before using in HMA. Do not use aggregate marinated longer than 60 days.

## MEASUREMENT AND PAYMENT

Full compensation for treating aggregates with lime slurry shall be considered as included in the contract price paid per tonne for HMA as designated in the Engineer's Estimate and no separate payment will be made therefor.

**10-1.45 HOT MIX ASPHALT AGGREGATE LIME TREATMENT - DRY LIME METHOD**

**GENERAL**

**Summary**

This work includes treating hot mix asphalt (HMA) aggregate with lime using the dry lime method either with marination or without.

Treat aggregate for HMA Type B with dry lime.

Marinate aggregate if the plasticity index determined under California Test 204 is from 4 to 10.

**Submittals**

Determine the exact lime proportions for fine and coarse virgin aggregate and submit them as part of the proposed job mix formula (JMF) under Section 39, "Hot Mix Asphalt," of the Standard Specifications.

If marination is required, submit in writing the averaged aggregate quality test results to the Engineer within 24 hours of sampling.

Submit in writing a treatment data log from the dry lime and aggregate proportioning device in the following order:

1. Treatment date
2. Time of day the data is captured
3. Aggregate size being treated
4. HMA type and mix aggregate size
5. Wet aggregate flow rate collected directly from the aggregate weigh belt
6. Aggregate moisture content, expressed as a percent of the dry aggregate mass
7. Flow rate of dry aggregate calculated from the flow rate of wet aggregate
8. Dry lime flow rate
9. Lime ratio from the accepted JMF for each aggregate size being treated
10. Lime ratio from the accepted JMF for the combined aggregate
11. Actual lime ratio calculated from the aggregate weigh belt output, the aggregate moisture input, and the dry lime meter output, expressed as a percent of the dry aggregate mass
12. Calculated difference between the approved lime ratio and the actual lime ratio

Every day during lime treatment, submit the treatment data log on electronic media in tab delimited format on a removable CD-ROM storage disk. Each continuous treatment data set must be a separate record using a line feed carriage return to present the specified data on one line. The reported data must include data titles at least once per report.

**Quality Control and Assurance**

If marination is required, the quality control plan (QCP) specified in Section 39-4, "Quality Control / Quality Assurance," must include aggregate quality control sampling and testing during lime treatment. Perform sampling and testing in compliance with:

Quality Characteristic	Test Method	Minimum sampling and testing frequency
Sand Equivalent	CT 217	Once per 1 000 tonnes of aggregate treated with lime
Percent of crushed particles	CT 205	As necessary and as designated in the QCP
Los Angeles Rattler	CT 211	
Fine aggregate angularity	AASHTO T 304, Method A	
Flat and elongated particles	ASTM D 4791	

Note: During lime treatment, sample coarse and fine aggregate from individual stockpiles. Combine aggregate in the JMF proportions. Run tests for aggregate quality in triplicate and report test results as the average of 3 tests.

The Engineer orders proportioning operations stopped for any of the following if you:

1. Do not submit the treatment data log
2. Do not submit the aggregate quality control data for marinated aggregate

3. Submit incomplete, untimely, or incorrectly formatted data
4. Do not take corrective actions
5. Take late or unsuccessful corrective actions
6. Do not stop treatment when proportioning tolerances are exceeded
7. Use malfunctioning or failed proportioning devices

If you stop treatment, notify the Engineer of any corrective actions taken and conduct a successful 20-minute test run before resuming treatment.

## **MATERIALS**

Lime must be high-calcium hydrated lime. Lime and water must comply with Section 24-1.02, "Materials," of the Standard Specifications.

Before virgin aggregate is treated, it must comply with the aggregate quality specifications. Do not test treated aggregate for quality control except for gradation. The Engineer does not test treated aggregate for acceptance except for gradation.

The Engineer determines the combined aggregate gradation during HMA production after you have treated aggregate. If reclaimed asphalt pavement (RAP) is used, the Engineer determines combined aggregate gradations containing RAP under Laboratory Procedure LP-9.

Treated aggregate must not have lime balls or clods.

## **CONSTRUCTION**

### **General**

Notify the Engineer in writing at least 24 hours before the start of aggregate treatment.

Do not treat RAP.

If marination is required:

1. Treat and marinate coarse and fine aggregates separately.
2. Treat aggregate and stockpile for marination only once.
3. Treat aggregate separate from HMA production.

The lime ratio is the kilograms of dry hydrated lime per 100 kg of dry virgin aggregate expressed as a percent. Water content of untreated aggregate must not affect the lime ratio.

Lime ratio ranges are:

Aggregate Gradation	Lime Ratio
Coarse	0.4 to 1.0
Fine	1.5 to 2.0
Combined virgin aggregate	0.8 to 1.5

The lime ratio for fine and coarse aggregate must be within  $\pm 0.2$  percent of the lime ratio in the accepted JMF. The lime ratio must be within  $\pm 0.2$  percent of the approved lime ratio when you combine the individual aggregate sizes in the JMF proportions. Determine the lime ratio before adding of RAP.

Proportion dry lime by mass with a continuous operation.

The device controlling dry lime and aggregate proportioning must produce a treatment data log. The log consists of a series of data sets captured at 10-minute intervals throughout daily treatment. The data must be a treatment activity register and not a summation. The material represented by a data set is the amount produced 5 minutes before and 5 minutes after the capture time. For the duration of the contract, collected data must be stored by the controller.

If 3 consecutive sets of recorded treatment data indicate deviation more than 0.2 percent above or below the lime ratio in the accepted JMF, stop treatment of lime treated aggregates.

If a set of recorded treatment data indicates a deviation of more than 0.4 percent above or below the lime ratio in the accepted JMF, stop treatment of lime treated aggregates and do not use the material represented by that set of data in HMA.

If 20 percent or more of the total daily treatment indicates deviation of more than 0.2 percent above or below the lime ratio in the accepted JMF, stop treatment and do not use the day's treated aggregate in HMA.

If you stop treatment for noncompliance, you must implement corrective action and successfully treat aggregate for a 20-minute period. Notify the Engineer before beginning the 20-minute treatment period.

If you use a batch-type proportioning operation for HMA production, control proportioning in compliance with the specifications for continuous mixing plants. Use a separate dry lime aggregate treatment operation from HMA batching operations including:

1. Pugmill mixer
2. Controller
3. Weigh belt for the lime
4. Weigh belt for the aggregate

If using a continuous mixing operation for HMA without lime marinated aggregates, use a controller that measures the blended aggregate mass after any additional water is added to the mixture. The controller must determine the amount of lime added to the aggregate from the aggregate weigh belt input in connection with the manually input total aggregate moisture, the manually input target lime content, and the lime proportioning system output. Use a continuous aggregate weigh belt and pugmill mixer for the lime treatment operation in addition to the weigh belt for the aggregate proportioning to asphalt binder in the HMA plant. If you use a water meter for moisture control for lime treatment, the meter must comply with California Test 109.

At the time of mixing dry lime with aggregate, the aggregate moisture content must ensure complete lime coating. The aggregate moisture content must not cause aggregate to be lost between the point of weighing the combined aggregate continuous stream and the dryer. Add water for mixing and coating aggregate to the aggregate before dry lime addition. Immediately before mixing lime with aggregate, water must not visibly separate from aggregate.

The HMA plant must be equipped with a bag house dust system. Material collected in the dust system must be returned to the mix.

### **Mixing Dry Lime and Aggregate**

Mix aggregate, water, and dry lime with a continuous pugmill mixer with twin shafts. Immediately before mixing lime with aggregate, water must not visibly separate from aggregate. Store dry lime in a uniform and free flowing condition. Introduce dry lime to the pugmill in a continuous operation. The introduction must occur after the aggregate cold feed and before the point of proportioning across a weigh belt and the aggregate dryer. Prevent loss of dry lime.

If marination is required, marinate treated aggregate in stockpiles between 24 hours and 60 days before using in HMA. Do not use aggregate marinated more than 60 days.

The pugmill must be equipped with paddles arranged to provide sufficient mixing action and mixture movement. The pugmill must produce a homogeneous mixture of uniformly coated aggregates at mixer discharge.

If the aggregate treatment operation is stopped longer than 1 hour, clean the equipment of partially treated aggregate and lime.

Aggregate must be completely treated before introduction into the mixing drum.

### **MEASUREMENT AND PAYMENT**

Full compensation for dry lime treating HMA aggregate including marination shall be considered as included in the contract price paid per tonne for HMA as designated in the Engineer's Estimate and no separate payment will be made therefor.

## **10-1.46 LIQUID ANTISTRIP TREATMENT**

### **GENERAL**

#### **Summary**

This work includes treating asphalt binder with liquid antistrip (LAS) treatment to bond the asphalt binder to aggregate in hot mix asphalt (HMA).

#### **Submittals**

For LAS, submit with the proposed job mix formula (JMF) submittal under Section 39, "Hot Mix Asphalt," of the Standard Specifications:

1. Materials Safety Data Sheet (MSDS)
2. One 1/2-L sample
3. Infrared analysis including copy of absorption spectra

Submit a certified copy of test results and a MSDS for each LAS lot.

Submit a Certificate of Compliance under Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each LAS shipment. With each certificate also submit:

1. Your signature and printed name
2. Shipment number
3. Material type

4. Material specific gravity
5. Refinery
6. Consignee
7. Destination
8. Quantity
9. Contact or purchase order number
10. Shipment Date

Submit proportions for LAS as part of the JMF submittal specified in Section 39-1.03, "Hot Mix Asphalt Mix Design Requirements," of the Standard Specifications. If you change the brand or type of LAS, submit a new JMF.

For each job site delivery of LAS, submit one 1/4-L sample to the Transportation Laboratory. Submit shipping documents to the Engineer. Label each LAS sampling container with:

1. LAS type
2. Application rate
3. Sample date
4. Contract number

At the end of each day's production shift, submit production data in electronic and printed media. Present data on electronic media in tab delimited format. Use line feed carriage return with one separate record per line for each production data set. Allow sufficient fields for the specified data. Include data titles at least once per report. For each mixing operation type, submit in order:

1. Batch Mixing:

- 1.1. Production date
- 1.2. Time of batch completion
- 1.3. Mix size and type
- 1.4. Each ingredient's mass
- 1.5. Asphalt binder content as percentage of dry aggregate mass
- 1.6. LAS content as percentage of asphalt binder mass

2. Continuous Mixing:

- 2.1. Production date
- 2.2. Data capture time
- 2.3. Mix size and type
- 2.4. Flow rate of wet aggregate collected directly from the aggregate weigh belt
- 2.5. Aggregate moisture content as percentage of dry aggregate mass
- 2.6. Flow rate of asphalt binder collected from the asphalt binder meter
- 2.7. Flow rate of LAS collected from the LAS meter
- 2.8. Asphalt binder content as percentage of dry aggregate mass calculated from:
  - 2.8.1. Aggregate weigh belt output
  - 2.8.2. Aggregate moisture input
  - 2.8.3. Asphalt binder meter output
- 2.9. LAS content as percentage of asphalt binder mass calculated from:
  - 2.9.1. Asphalt binder meter output
  - 2.9.2. LAS meter output

**Quality Control and Assurance**

For continuous mixing and batch mixing operations, sample asphalt binder before adding LAS. For continuous mixing operations, sample combined asphalt binder and LAS after the static mixer.

The Engineer orders proportioning operations stopped for any of the following if you:

1. Do not submit data
2. Submit incomplete, untimely, or incorrectly formatted data

3. Do not take corrective actions
4. Take late or unsuccessful corrective actions
5. Do not stop production when proportioning tolerances are exceeded
6. Use malfunctioning or failed proportioning devices

If you stop production, notify the Engineer of any corrective actions taken before resuming.

### **MATERIALS**

LAS-treated asphalt binder must comply with Section 39, "Hot Mix Asphalt," of the Standard Specifications. LAS does not substitute for asphalt binder.

LAS total amine value must be 325 minimum when tested under ASTM D 2074.

Use only 1 LAS type or brand at a time. Do not mix LAS types or brands.

Store and mix LAS under the manufacturer's recommendations.

### **CONSTRUCTION**

LAS must be between 0.5 and 1.0 percent by mass of asphalt binder.

If 3 consecutive sets of recorded production data show actual delivered LAS mass is more than  $\pm 1$  percent of the approved mix design LAS mass, stop production and take corrective action.

If a set of recorded production data shows actual delivered LAS mass is more than  $\pm 2$  percent of the approved mix design LAS mass, stop production. If the LAS mass exceeds 1.2 percent of the asphalt binder mass, do not use the HMA represented by that data.

The continuous mixing plant controller proportioning the HMA must produce a production data log. The log consists of a series of data sets captured at 10-minute intervals throughout daily production. The data must be a production activity register and not a summation. The material represented by the data is the amount produced 5 minutes before and 5 minutes after the capture time. For the duration of the contract, collected data must be stored by the plant controller or a computer's memory at the plant.

### **MEASUREMENT AND PAYMENT**

Full compensation for LAS is included in the contract price paid per tonne for HMA as designated in the Engineer's Estimate and no separate payment will be made therefor.

#### **10-1.47 EXIT RAMP TERMINI**

Portland cement concrete pavement at exit ramp termini shall be constructed as shown on the plans and as provided in Section 40, "Portland Cement Concrete Pavement," of the Standard Specifications and these special provisions.

The concrete for portland cement concrete pavement at exit ramp termini shall be minor concrete.

#### **10-1.48 PILING**

##### **GENERAL**

Piling shall conform to the provisions in Section 49, "Piling," of the Standard Specifications, and these special provisions.

Alternative "W" type piles shall not be used.

Unless otherwise specified, welding of any work performed in conformance with the provisions in Section 49, "Piling," of the Standard Specifications, shall be in conformance with the requirements in AWS D1.1.

Attention is directed to "Supplemental Project Information," "Precast Concrete Quality Control," and "Welding" of these special provisions.

Difficult pile installation is anticipated due to the presence hazardous and contaminated materials, underground utilities, sound control, and traffic control.

Alternative "X" type piles shall have a dimension, T, not less than 355 mm at the abutments and retaining walls for Western Avenue Undercrossing (Widen).

When a calculated nominal driving resistance is shown on the plans for piling, that value shall be utilized in lieu of nominal resistance in Section 49, "Piling," of the Standard Specifications, the plans, and these special provisions.

##### **Driving System Submittal**

Prior to installing driven piling, the Contractor shall provide a driving system submittal, including driveability analysis, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. A submittal shall be made for each control location shown below. All proposed driving systems (i.e., each hammer that may be brought onto the site) shall be included in the submittal.

Bridge Number	Control Location
53-1079S	Abutments 1 & 3
53-1079S	Bent 2

The driving system submittal shall contain an analysis showing that the proposed driving systems will install piling to the specified tip elevation and specified bearing. Driving systems shall generate sufficient energy to drive the piles with stresses not more than 95 percent of the specified yield strength of the steel pile or unfilled steel shell. Submittals shall include the following:

- A. Complete description of soil parameters used, including soil quake and damping coefficients, skin friction distribution, ratio of shaft resistance to nominal compression resistance, assumptions made regarding the formation of soil plugs, and assumptions made regarding drilling through the center of open ended steel shells.
- B. List of all hammer operation parameters assumed in the analysis, including fuel settings, stroke limitations, and hammer efficiency.
- C. Driveability studies that are based on a wave equation analysis using a computer program that has been approved by the Engineer. Driveability studies shall model the Contractor's proposed driving systems, including the hammers, capblocks, and pile cushions, as well as determine driving resistance and pile stresses for assumed site conditions. Separate analyses shall be completed at elevations above the specified tip elevations where difficult driving is anticipated. Studies shall include plots for a range of pile compression capacities above and below the nominal compression resistance shown on the plans. Plots shall include the following:
  1. Pile compressive stress versus blows per 0.30-m.
  2. Pile tensile stress versus blows per 0.30-m.
  3. Nominal compression resistance versus blows per 0.30-m.
- D. Copies of all test results from any previous pile load tests, dynamic monitoring, and all driving records used in the analyses.
- E. Completed "Pile and Driving Data Form," which is shown in these special provisions.





The driving system submittal shall be stamped and signed by an engineer who is registered as a Civil Engineer in the State of California. Prior to installing piling, the Contractor shall allow the Engineer 15 working days to review a driving system submittal after a complete set, as determined by the Engineer, has been received. Should the Engineer fail to complete his review within the time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in the driving system submittal review, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays" of the Standard Specifications.

The Contractor shall use the driving system and installation methods described in the approved driving system submittal for a given control location. Any change in hammers from those submitted and approved by the Engineer shall also meet the requirements for driving system submittals. Revised and new driving system submittals shall be approved by the Engineer prior to using corresponding driving systems on production piling. The Contractor shall allow the Engineer 15 working days to review each revised and each new driving system submittal after a complete set, as determined by the Engineer, has been received.

Approval of pile driving equipment will not relieve the Contractor of his responsibility to drive piling, free of damage, to the specified penetration.

# PILE AND DRIVING DATA FORM

Structure Name : \_\_\_\_\_ Contract No.: \_\_\_\_\_  
 \_\_\_\_\_ Project: \_\_\_\_\_  
 Structure No.: \_\_\_\_\_ Pile Driving Contractor or  
 Dist./Co./Rte./kilo.post: \_\_\_\_\_ Subcontractor \_\_\_\_\_ (Pile Driven By)

 <p><b>Ram</b> <b>Anvil</b></p>	<b>Hammer</b>	Manufacturer: _____ Model: _____ Type: _____ Serial No.: _____ Rated Energy: _____ at _____ Length of Stroke _____ Modifications: _____ _____ _____						
	<b>Capblock (Hammer Cushion)</b>	Material: _____ Thickness: _____ mm Area: _____ mm <sup>2</sup> Modulus of Elasticity - E: _____ MPa Coefficient of Restitution - e: _____						
	<b>Pile Cap</b>	<table border="1" style="display: inline-table; border-collapse: collapse;"> <tr> <td style="padding: 2px;">Helmet</td> <td rowspan="4" style="padding: 0 10px; vertical-align: middle;">Mass: _____</td> <td rowspan="4" style="padding: 0 10px; vertical-align: middle;">k</td> </tr> <tr> <td style="padding: 2px;">Bonnet</td> </tr> <tr> <td style="padding: 2px;">Anvil Block</td> </tr> <tr> <td style="padding: 2px;">Drivehead</td> </tr> </table>	Helmet	Mass: _____	k	Bonnet	Anvil Block	Drivehead
Helmet	Mass: _____	k						
Bonnet								
Anvil Block								
Drivehead								
	<b>Pile</b>	Material: _____ Thickness: _____ mm Area: _____ mm <sup>2</sup> Modulus of Elasticity - E: _____ MPa Coefficient of Restitution - e: _____						
	<b>Pile</b>	Pile Type: _____ Length (In Leads): _____ m kg/m.: _____ Taper: _____ Wall Thickness: _____ mm Cross Sectional Area: _____ mm <sup>2</sup> Design Pile Capacity: _____ kN Description of Splice: _____ _____ Tip Treatment Description: _____						

- DISTRIBUTE one copy**
- Translab,  
Foundation Testing
- Translab,  
Geotechnical Design
- Resident Engineer

Note: If mandrel is used to drive the pile, attach separate manufacturer's detail sheet(s) including mass (kg) and dimensions.

Submitted By: \_\_\_\_\_ Date: \_\_\_\_\_

## **Redriving**

Piles at Western Avenue Undercrossing which do not attain the required bearing value when the pile tip has reached the specified tip elevation shall be allowed to stand for a "set period" without driving. The "set period" shall be at least 24 hours unless bearing has been obtained sooner. After the required "set period" has elapsed, 2 piles or 10 percent of such piles in a footing, whichever is greater, shall be redriven. The Engineer will designate which piles are to be redriven. Redriving shall consist of operating the driving hammer at full rated energy on the pile and then measuring the bearing value of the pile.

If the required bearing value has been attained for each pile designated to be redriven, then the remaining piles in that footing shall be considered satisfactory and further driving will not be required. If redriving said designated piles demonstrates that the required bearing value has not been attained, all piles in that footing shall be redriven until the required bearing value has been reached.

Full compensation for redriving and for conforming to the requirements for "set period" and any delays in connection therewith shall be considered as included in the contract unit price paid for driving the piles involved and no separate payment will be made therefor.

## **CAST-IN-DRILLED-HOLE CONCRETE PILES**

### **GENERAL**

#### **Summary**

Cast-in-drilled-hole (CIDH) concrete piling shall conform to the provisions in Section 49-4, "Cast-In-Place Concrete Piles," of the Standard Specifications and these special provisions.

The provisions of "Welding" of these special provisions shall not apply to temporary steel casings.

### **SUBMITTALS**

#### **Pile Installation Plan**

The Contractor shall submit a pile installation plan to the Engineer for approval for all CIDH concrete piling. The pile installation plan shall be submitted at least 15 days before constructing CIDH concrete piling and shall include complete descriptions, details, and supporting calculations for the following:

- A. Concrete mix design, certified test data, and trial batch reports.
- B. Drilling or coring methods and equipment.
- C. Proposed method for casing installation and removal when necessary.
- D. Plan view drawing of pile showing reinforcement. Include inspection pipes on the drawing, if inspection pipes are required.
- E. Methods for placing, positioning, and supporting bar reinforcement.
- F. Methods and equipment for determining the depth of concrete and actual and theoretical volume placed, including effects on volume of concrete when any casings are withdrawn.
- G. Methods and equipment for verifying that the bottom of the drilled hole is clean before placing concrete.
- H. Methods and equipment for preventing upward movement of reinforcement, including the Contractor's means of detecting and measuring upward movement during concrete placement operations.

For concrete placed under slurry, the pile installation plan shall also include complete descriptions, details, and supporting calculations for the following:

- A. Concrete batching, delivery, and placing systems, including time schedules and capacities. Time schedules shall include the time required for each concrete placing operation at each pile.
- B. Concrete placing rate calculations. When requested by the Engineer, calculations shall be based on the initial pump pressures or static head on the concrete and losses throughout the placing system, including anticipated head of slurry and concrete to be displaced.
- C. Suppliers' test reports on the physical and chemical properties of the slurry and any proposed slurry chemical additives, including Material Safety Data Sheet.
- D. Slurry testing equipment and procedures.
- E. Methods of removal and disposal of excavation, slurry, and contaminated concrete, including removal rates.
- F. Methods and equipment for slurry agitating, recirculating, and cleaning.

### **QUALITY ASSURANCE**

#### **Concrete Test Batch**

Before concrete is deposited under slurry, a concrete test batch shall be produced and delivered to the project under conditions and in time periods similar to those expected during placement of concrete in the piles. Concrete shall be placed

in an excavated hole or suitable container of adequate size to allow for testing as specified herein. Depositing of concrete under slurry will not be required. In addition to meeting the specified nominal slump, the concrete test batch shall meet the following requirements:

- A. For piles where the time required for each concrete placing operation, as submitted in the placing plan, will be 2 hours or less, the concrete test batch shall demonstrate that the proposed concrete mix design achieves a slump of at least 175 mm after twice that time has elapsed.
- B. For piles where the time required for each concrete placing operation, as submitted in the placing plan, will be more than 2 hours, the concrete test batch shall demonstrate that the proposed concrete mix design achieves a slump of at least 175 mm after that time plus 2 hours has elapsed.

The time period shall begin at the start of placement. Concrete shall not be vibrated or agitated during the test period. Slump tests will be performed in conformance with the requirements in California Test 556.

Upon completion of testing, concrete shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

## **MATERIALS**

### **Concrete**

Concrete deposited under slurry shall have a nominal slump equal to or greater than 175 mm, contain not less than 400 kilograms of cementitious material per cubic meter, and be proportioned to prevent excessive bleed water and segregation. The nominal and maximum slump and penetration requirements in Section 90-6.06, "Amount of Water and Penetration," of the Standard Specifications shall not apply.

### **Aggregate Grading**

The combined aggregate grading shall be either the 25-mm maximum grading, the 12.5-mm maximum grading, or the 9.5-mm maximum grading and shall conform to the requirements in Section 90-3, "Aggregate Gradings," of the Standard Specifications.

When concrete is placed under slurry, the combined aggregate grading shall be either the 12.5-mm maximum grading or the 9.5-mm maximum grading and shall conform to the requirements in Section 90-3, "Aggregate Gradings," of the Standard Specifications.

### **Grout**

Grout used to backfill casings shall conform to the provisions in Section 50-1.09, "Bonding and Grouting," of the Standard Specifications. Aggregate shall be used to extend the grout, but only to the extent that the cement content of the grout is not less than 501 kilograms per cubic meter of grout. California Test 541 will not be required nor will the grout be required to pass through a sieve with a 1.8-mm maximum clear opening before being introduced into the grout pump. Aggregate shall consist of at least 70 percent fine aggregate and approximately 30 percent pea gravel, by weight. Fine aggregate shall conform to the provisions of Section 90-2, "Materials," of the Standard Specifications. The size of pea gravel shall be such that 100 percent passes the 12.5-mm sieve, a minimum 90 percent passes the 9.5-mm sieve, and not more than 5 percent passes the No.2.36-mm sieve.

### **Slurry**

#### **Mineral Slurry**

Mineral slurry shall be mixed and thoroughly hydrated in slurry tanks, and slurry shall be sampled from the slurry tanks and tested before placement in the drilled hole.

Slurry shall be recirculated or continuously agitated in the drilled hole to maintain the specified properties.

Recirculation shall include removal of drill cuttings from the slurry before discharging the slurry back into the drilled hole. When recirculation is used, the slurry shall be sampled and tested at least every 2 hours after beginning its use until tests show that the samples taken from the slurry tank and from near the bottom of the hole have consistent specified properties. Subsequently, slurry shall be sampled at least twice per shift as long as the specified properties remain consistent.

Slurry that is not recirculated in the drilled hole shall be sampled and tested at least every 2 hours after beginning its use. The slurry shall be sampled mid-height and near the bottom of the hole. Slurry shall be recirculated when tests show that the samples taken from mid-height and near the bottom of the hole do not have consistent specified properties.

Slurry shall also be sampled and tested prior to final cleaning of the bottom of the hole and again just prior to placing concrete. Samples shall be taken from mid-height and near the bottom of the hole. Cleaning of the bottom of the hole and

placement of the concrete shall not start until tests show that the samples taken from mid-height and near the bottom of the hole have consistent specified properties.

Mineral slurry shall be tested for conformance to the requirements shown in the following table:

MINERAL SLURRY		
PROPERTY	REQUIREMENT	TEST
Density (kg/m <sup>3</sup> ) - before placement in the drilled hole - during drilling  - prior to final cleaning - immediately prior to placing concrete	1030* to 1110*   1030* to 1200*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/liter)  bentonite  attapulgate	  29 to 53  29 to 42	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	8 to 10.5	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - prior to final cleaning - immediately prior to placing concrete	less than or equal to 4.0	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 32 kg/m <sup>3</sup> . Slurry temperature shall be at least 4°C when tested.		

Any caked slurry on the sides or bottom of hole shall be removed before placing reinforcement. If concrete is not placed immediately after placing reinforcement, the reinforcement shall be removed and cleaned of slurry, the sides of the drilled hole cleaned of caked slurry, and the reinforcement again placed in the hole for concrete placement.

### Synthetic Slurry

Synthetic slurries shall be used in conformance with the manufacturer's recommendations and these special provisions. The following synthetic slurries may be used:

PRODUCT	MANUFACTURER
SlurryPro CDP	KB Technologies Ltd. 3648 FM 1960 West Suite 107 Houston, TX 77068 (800) 525-5237
Super Mud	PDS Company c/o Champion Equipment Company 8140 East Rosecrans Ave. Paramount, CA 90723 (562) 634-8180
Shore Pac GCV	CETCO Drilling Products Group 1350 West Shure Drive Arlington Heights, IL 60004 (847) 392-5800
Novagel Polymer	Geo-Tech Drilling Fluids 220 N. Zapata Hwy, Suite 11A Laredo, TX 78043 (210) 587-4758

Inclusion of a synthetic slurry on the above list may be obtained by meeting the Department's requirements for synthetic slurries. The requirements can be obtained from the Office of Structure Design, P.O. Box 942874, Sacramento, CA 94274-0001.

Synthetic slurries listed may not be appropriate for a given site.

Synthetic slurries shall not be used in holes drilled in primarily soft or very soft cohesive soils as determined by the Engineer.

A manufacturer's representative, as approved by the Engineer, shall provide technical assistance for the use of their product, shall be at the site prior to introduction of the synthetic slurry into a drilled hole, and shall remain at the site until released by the Engineer.

Synthetic slurries shall be sampled and tested at both mid-height and near the bottom of the drilled hole. Samples shall be taken and tested during drilling as necessary to verify the control of the properties of the slurry. Samples shall be taken and tested when drilling is complete, but prior to final cleaning of the bottom of the hole. When samples are in conformance with the requirements shown in the following tables for each slurry product, the bottom of the hole shall be cleaned and any loose or settled material removed. Samples shall be obtained and tested after final cleaning and immediately prior to placing concrete.

SlurryPro CDP synthetic slurries shall be tested for conformance to the requirements shown in the following table:

SLURRYPRO CDP KB Technologies Ltd.		
PROPERTY	REQUIREMENT	TEST
Density (kg/m <sup>3</sup> ) - during drilling  - prior to final cleaning - just prior to placing concrete	less than or equal to 1075*  less than or equal to 1025*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/liter) - during drilling  -prior to final cleaning - just prior to placing concrete	53 to 127  less than or equal to 74	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	6 to 11.5	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - prior to final cleaning - just prior to placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 32 kg/m <sup>3</sup> . Slurry temperature shall be at least 4°C when tested.		

Super Mud synthetic slurries shall be tested for conformance to the requirements shown in the following table:

SUPER MUD PDS Company		
PROPERTY	REQUIREMENT	TEST
Density (kg/m <sup>3</sup> ) - prior to final cleaning - just prior to placing concrete	less than or equal to 1025*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/liter) - during drilling - prior to final cleaning - just prior to placing concrete	34 to 64  less than or equal to 64	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	8 to 10.0	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - prior to final cleaning -just prior to placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 32 kg/m <sup>3</sup> . Slurry temperature shall be at least 4°C when tested.		

Shore Pac GCV synthetic slurries shall be tested for conformance to the requirements shown in the following table:

Shore Pac GCV CETCO Drilling Products Group		
PROPERTY	REQUIREMENT	TEST
Density (kg/m <sup>3</sup> ) - prior to final cleaning - just prior to placing concrete	less than or equal to 1025*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/liter) - during drilling  - prior to final cleaning - just prior to placing concrete	35 to 78  less than or equal to 60	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	8.0 to 11.0	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - prior to final cleaning -just prior to placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 32 kg/m <sup>3</sup> . Slurry temperature shall be at least 4°C when tested.		

Novagel Polymer synthetic slurries shall be tested for conformance to the requirements shown in the following table:

NOVAGEL POLYMER Geo-Tech Drilling Fluids		
PROPERTY	REQUIREMENT	TEST
Density (kg/m <sup>3</sup> ) - during drilling  - prior to final cleaning - just prior to placing concrete	less than or equal to 1075*  less than or equal to 1025*	Mud Weight (Density) API 13B-1 Section 1
Viscosity (seconds/liter) - during drilling  - prior to final cleaning - just prior to placing concrete	48 to 110  less than or equal to 110	Marsh Funnel and Cup API 13B-1 Section 2.2
pH	6.0 to 11.5	Glass Electrode pH Meter or pH Paper
Sand Content (percent) - prior to final cleaning -just prior to placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, slurry may be used in salt water, and the allowable densities may be increased up to 32 kg/m <sup>3</sup> . Slurry temperature shall be at least 4°C when tested.		

**Water Slurry**

At the option of the Contractor, water may be used as slurry when casing is used for the entire length of the drilled hole. Water slurry shall be tested for conformance to the requirements shown in the following table:

WATER SLURRY		
PROPERTY	REQUIREMENT	TEST
Density (kg/m <sup>3</sup> ) - prior to final cleaning - just prior to placing concrete	1017 *	Mud Weight (Density) API 13B-1 Section 1
Sand Content (percent) - prior to final cleaning -just prior to placing concrete	less than or equal to 0.5	Sand API 13B-1 Section 5
*When approved by the Engineer, salt water slurry may be used, and the allowable densities may be increased up to 32 kg/m <sup>3</sup> .		

**CONSTRUCTION**

**General**

CIDH concrete piling 600 mm in diameter or larger may be constructed by excavation and depositing concrete under slurry.

Disposal of drill cuttings shall conform to the provisions in "Material Containing Aerially Deposited Lead," of these special provisions.

Portions of CIDH concrete piling shown on the plans to be formed shall be formed and finished in conformance with the provisions for concrete structures in Section 51, "Concrete Structures," of the Standard Specifications.

**Placing Concrete**

Concrete deposited under slurry shall be carefully placed in a compact, monolithic mass and by a method that will prevent washing of the concrete. Concrete deposited under slurry need not be vibrated. Placing concrete shall be a continuous operation lasting not more than the time required for each concrete placing operation at each pile, as submitted in the placing plan, unless otherwise approved in writing by the Engineer. Concrete shall be placed with concrete pumps and delivery tube system of adequate number and size to complete the placing of concrete in the time specified. The delivery tube system shall consist of one of the following:

- A. A tremie tube or tubes, each of which are at least 250 in diameter, fed by one or more concrete pumps.
- B. One or more concrete pump tubes, each fed by a single concrete pump.

The delivery tube system shall consist of watertight tubes with sufficient rigidity to keep the ends always in the mass of concrete placed. If only one delivery tube is utilized to place the concrete, the tube shall be placed near the center of the drilled hole. Multiple tubes shall be uniformly spaced in the hole. Internal bracing for the steel reinforcing cage shall accommodate the delivery tube system. Tremies shall not be used for piles without space for a 250-mm tube.

Spillage of concrete into the slurry during concrete placing operations shall not be allowed. Delivery tubes shall be capped with a watertight cap, or plugged above the slurry level with a good quality, tight fitting, moving plug that will expel the slurry from the tube as the tube is charged with concrete. The cap or plug shall be designed to be released as the tube is charged. The pump discharge or tremie tube shall extend to the bottom of the hole before charging the tube with concrete. After charging the delivery tube system with concrete, the flow of concrete through a tube shall be induced by slightly raising the discharge end. During concrete placement, the tip of the delivery tube shall be maintained as follows to prevent reentry of the slurry into the tube. Until at least 3 meters of concrete has been placed, the tip of the delivery tube shall be within 150 mm of the bottom of the drilled hole, and then the embedment of the tip shall be maintained at least 3 meters below the top surface of the concrete. Rapid raising or lowering of the delivery tube shall not be permitted. If the seal is lost or the delivery tube becomes plugged and must be removed, the tube shall be withdrawn, the tube cleaned, the tip of the tube

capped to prevent entrance of the slurry, and the operation restarted by pushing the capped tube 3 meters into the concrete and then reinitiating the flow of concrete.

When slurry is used, a fully operational standby concrete pump, adequate to complete the work in the time specified, shall be provided at the site during concrete placement. The slurry level shall be maintained 3 meters above the piezometric head or within 300 mm of the top of the drilled hole, whichever is higher.

A log of concrete placement for each drilled hole shall be maintained by the Contractor when concrete is deposited under slurry. The log shall show the pile location, tip elevation, dates of excavation and concrete placement, total quantity of concrete deposited, length and tip elevation of any casing, and details of any hole stabilization method and materials used. The log shall include a 215 mm X 280 mm sized graph of the concrete placed versus depth of hole filled. The graph shall be plotted continuously throughout placing of concrete. The depth of drilled hole filled shall be plotted vertically with the pile tip oriented at the bottom and the quantity of concrete shall be plotted horizontally. Readings shall be made at least at each 1.5 meters of pile depth, and the time of the reading shall be indicated. The graph shall be labeled with the pile location, tip elevation, cutoff elevation, and the dates of excavation and concrete placement. The log shall be delivered to the Engineer within one working day of completion of placing concrete in the pile.

After placing reinforcement and before placing concrete in the drilled hole, if drill cuttings settle out of the slurry, the bottom of the drilled hole shall be cleaned. The Contractor shall verify that the bottom of the drilled hole is clean.

If a temporary casing is used, concrete placed under slurry shall be maintained at a level at least 1.5 meters above the bottom of the casing. The withdrawal of the casing shall not cause contamination of the concrete with slurry. If slurry is not used, the temporary casing shall not be withdrawn until the concrete head in the casing is greater than the groundwater outside of the casing. This positive concrete head shall be maintained during the withdrawal of the casing.

Disposal of material resulting from using slurry shall conform to the provisions in "Material Containing Aerially Deposited Lead," of these special provisions.

### **Acceptance Testing and Mitigation**

Vertical inspection pipes for acceptance testing shall be provided in all CIDH concrete piling 600 mm in diameter or larger, except when the holes are dry or when the holes are dewatered without the use of temporary casing in a manner that controls ground water.

The furnishing and placing of inspection pipes shall conform to the following:

- A. Inspection pipes shall be Schedule 40 PVC pipe with a nominal inside diameter of 50 mm. Watertight PVC couplers are permitted to facilitate pipe lengths in excess of those which are commercially available. The Contractor shall log the location of the inspection pipe couplers with respect to the plane of pile cut off, and these logs shall be delivered to the Engineer upon completion of the placement of concrete in the drilled hole.
- B. Each inspection pipe shall be capped at the bottom and shall extend from 0.9 meter above the pile cutoff down to the bottom of the reinforcing cage. A temporary top cap or similar means shall be provided to keep the pipes clean before testing. If pile cutoff is below the ground surface or working platform, inspection pipes shall be extended to 0.9 meter above the ground surface or working platform. Approved covers or railings shall be provided and inspection pipes shall be located as necessary to minimize exposure of testing personnel to potential falling hazards.
- C. Inspection pipes shall be completely clean, dry, and unobstructed at the time of testing providing a 50 mm diameter clear opening.
- D. The inspection pipes shall be installed in straight alignment, parallel to the main reinforcement, and securely fastened in place to prevent misalignment during installation of the reinforcement and placing of concrete in the hole. The CIDH concrete piling shall be constructed so that the relative distance of inspection pipes to vertical steel reinforcement shall remain constant.
- E. When any changes are made to the tip of CIDH concrete piling, the Contractor shall also extend the inspection pipes to the bottom of the reinforcing cage.

The following additional requirements apply if inspection pipes are not shown on the plans:

- A. Inspection pipes shall be placed radially around the pile, inside the outermost spiral or hoop reinforcement and no more than 25 mm clear of the outermost spiral or hoop reinforcement.
- B. Inspection pipes shall be placed around the pile at a uniform spacing not exceeding 840 mm measured along the circle passing through the centers of inspection pipes. A minimum of 2 inspection pipes per pile shall be used. Inspection pipes shall be placed to provide the maximum diameter circle that passes through the centers of the inspection pipes while maintaining the spacing required herein.
- C. Inspection pipes shall be placed a minimum of 75 mm clear of the vertical reinforcement. When the vertical reinforcement configuration does not permit this clearance while achieving radial location requirements, distance to vertical rebar shall be maximized while still maintaining the requirement for radial location.

- D. Where the dimensions of the pile reinforcement do not permit inspection pipes to be placed per these requirements, a plan for tube placement shall be submitted to the Engineer for approval in the Pile Placement Plan with a request for deviation before fabricating pile reinforcement.

After placing concrete and before requesting acceptance tests, each inspection pipe shall be tested by the Contractor in the presence of the Engineer by passing a 32 mm diameter rigid cylinder 1.375 meters long through the length of pipe. If an inspection pipe fails to pass the 32-mm-diameter cylinder, the Contractor shall immediately fill all inspection pipes in the pile with water.

For each inspection pipe that does not pass the 32-mm diameter cylinder, the Contractor shall core a nominal 50-mm diameter hole through the concrete for the entire length of the pile. Cored holes shall be located as close as possible to the inspection pipes they are replacing and shall be no more than 125 mm clear from the reinforcement.

Coring shall not damage the pile reinforcement. Cored holes shall be made with a double wall core barrel system utilizing a split tube type inner barrel. Coring with a solid type inner barrel will not be allowed. Coring methods and equipment shall provide intact cores for the entire length of the pile. The coring operation shall be logged by an Engineering Geologist or Civil Engineer licensed in the State of California and experienced in core logging. Coring logs shall be in conformance with the Department's "Soil and Rock Logging, Classification, and Presentation Manual." Coring logs shall include Core Recovery (REC), Rock Quality Designation (RQD), locations of breaks, and complete descriptions of inclusions and voids encountered during coring, and shall be delivered to the Engineer upon completion. Concrete cores shall be preserved, identified with the exact location the core was recovered from within the pile, and delivered to the Engineer upon completion. The Engineer will evaluate the portion of the pile represented by the cored hole based on the submitted core logs.

Acceptance tests of the concrete will be made by the Engineer, without cost to the Contractor. Acceptance tests will evaluate the homogeneity of the placed concrete. Tests will include gamma-gamma logging conducted in conformance with California Test 233. The Contractor shall not conduct operations within 8 meters of the gamma-gamma logging operations. The Contractor shall separate reinforcing steel as necessary to allow the Engineer access to the inspection pipes to perform gamma-gamma logging or other acceptance testing. After requesting acceptance tests and providing access to the piles, the Contractor shall allow 20 days for the Engineer to conduct these tests and make determination of acceptance. Should the Engineer fail to complete these tests within the time allowance, and if in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in inspection, the delay will be considered a right of way delay as specified in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The Engineer may elect to perform additional tests to further evaluate a pile. These tests may include crosshole sonic logging and other means of inspection selected by the Engineer. When the Engineer elects to perform additional tests to further evaluate anomalies for a rejected pile, no time requirement exists for performing these tests. The Contractor may progress with the mitigation plan process without waiting for these supplemental results.

Inspection pipes and cored holes shall be dewatered and filled with grout after notification by the Engineer that the pile is acceptable. Grout shall conform to the provisions in Section 50-1.09, "Bonding and Grouting," of the Standard Specifications. Inspection pipes and holes shall be filled using grout tubes that extend to the bottom of the pipe or hole or into the grout already placed.

If acceptance testing performed by the Engineer determines that a pile does not meet the requirements of the specifications and California Test 233, Part 5C, then that pile will be rejected and all depositing of concrete under slurry or concrete placed using temporary casing for the purpose of controlling groundwater shall be suspended until written changes to the methods of pile construction are approved in writing by the Engineer.

The Engineer will determine whether the rejected pile requires mitigation due to structural, geotechnical, or corrosion concerns. The Engineer will consider the estimated size and location of the anomaly and potential effects upon the design. The Engineer will provide the conclusions of this analysis to the Contractor for development of a mitigation plan, if required. The Contractor shall allow 35 days for the Engineer to determine whether the pile requires mitigation and provide information to the Contractor. Day 1 of the 35 days shall be the first day after access has been provided to the Engineer to perform acceptance testing. If additional information is submitted to the Engineer that modifies the size, shape, or nature of the anomaly, the Contractor shall allow 15 additional days for the subsequent analysis.

If the Engineer determines that a rejected pile does not require mitigation, the Contractor may elect to 1) repair the pile per the approved mitigation plan, or 2) not repair anomalies found during acceptance testing of that pile. For such unrepaired piles, the Contractor shall pay to the State, \$400 per cubic meter for the portion of the pile affected by the anomalies. The volume, in cubic meter, of the portion of the pile affected by the anomalies, shall be calculated as the area of the cross section of the pile affected by each anomaly, in square meters, as determined by the Engineer, multiplied by the distance, in meters, from the top of each anomaly to the specified tip of the pile. If the volume calculated for one anomaly overlaps the volume calculated for additional anomalies within the pile, the calculated volume for the overlap shall only be counted once. In no case shall the amount of the payment to the State for any such pile be less than \$400. The Department may deduct the amount from any moneys due, or that may become due the Contractor under the contract.

If the Engineer determines that a rejected pile requires mitigation, the Contractor shall submit to the Engineer for approval a mitigation plan for repair, supplementation, or replacement for each rejected CIDH concrete pile conforming to the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. If the Engineer determines that it is not feasible to repair the rejected pile, the Contractor shall not include repair as a means of mitigation and shall proceed with the submittal of a mitigation plan for replacement or supplementation of the rejected pile.

Pile mitigation plans shall include the following:

- A. The designation and location of the pile addressed by the mitigation plan.
- B. A review of the structural, geotechnical, and corrosion design requirements of the rejected pile.
- C. A step by step description of the mitigation work to be performed, including drawings if necessary.
- D. An assessment of how the proposed mitigation work will address the structural, geotechnical, and corrosion design requirements of the rejected pile.
- E. Methods for preservation or restoration of existing earthen materials.
- F. A list of affected facilities, if any, with methods and equipment for protection of these facilities during mitigation.
- G. The State assigned contract number, bridge number, full name of the structure as shown on the contract plans, District-County-Route-Kilopost, and the Contractor's (and Subcontractor's if applicable) name on each sheet.
- H. A list of materials, with quantity estimates, and personnel, with qualifications, to be used to perform the mitigation work.
- I. The seal and signature of an engineer who is licensed as a Civil Engineer by the State of California. This requirement is waived for approved mitigation plans when either of the following conditions are present:
  1. The proposed mitigation will be performed in conformance with the most recent Department approved version of "ADSC Standard Mitigation Plan 'A' - Basic Repair" without exception or modification.
  2. The Engineer has determined that the rejected pile does not require mitigation due to structural, geotechnical, or corrosion concerns, and the Contractor elects to repair the pile using most recent Department approved version of "ADSC Standard Mitigation Plan 'B' - Grouting Repair" without exception or modification.

The most recent Department approved version of the "ADSC Standard Mitigation Plan" is available at:

<http://www.dot.ca.gov/hq/esc/geotech/ft/adscmitplan.htm>

For rejected piles to be repaired, the Contractor shall submit a pile mitigation plan that contains the following additional information:

- A. An assessment of the nature and size of the anomalies in the rejected pile.
- B. Provisions for access for additional pile testing if required by the Engineer.

For rejected piles to be replaced or supplemented, the Contractor shall submit a pile mitigation plan that contains the following additional information:

- A. The proposed location and size of additional piles.
- B. Structural details and calculations for any modification to the structure to accommodate the replacement or supplemental piles.

All provisions for CIDH concrete piling shall apply to replacement piles.

The Contractor shall allow the Engineer 20 days to review the mitigation plan after a complete submittal has been received.

Should the Engineer fail to review the complete pile mitigation submittal within the time specified, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the pile mitigation plan, an extension of time commensurate with the delay in completion of the work thus caused will be granted in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

When repairs are performed, the Contractor shall submit a mitigation report to the Engineer within 10 days of completion of the repair. This report shall state exactly what repair work was performed and quantify the success of the repairs relative to the submitted mitigation plan. The mitigation report shall be stamped and signed by an engineer that is licensed as a Civil Engineer by the State of California. The mitigation report shall show the State assigned contract number, bridge number, full name of the structure as shown on the contract plans, District-County-Route-Kilopost, and the Contractor (and subcontractor if applicable) name on each sheet. The Engineer will be the sole judge as to whether a mitigation proposal

is acceptable, the mitigation efforts are successful, and to whether additional repairs, removal and replacement, or construction of a supplemental foundation is required.

### **MEASUREMENT AND PAYMENT (PILING)**

Measurement and payment for the various types and classes of piles shall conform to the provisions in Sections 49-6.01, "Measurement," and 49-6.02, "Payment," of the Standard Specifications and these special provisions.

Full compensation for slurry, depositing concrete under slurry, test batches, inspection pipes, filling inspection holes and pipes with grout, drilling oversized cast-in-drilled-hole concrete piling, filling cave-ins and oversized piles with concrete, and redrilling through concrete, shall be considered as included in the contract prices paid per meter for cast-in-drilled-hole concrete piling of the types and sizes listed in the Engineer's Estimate, and no additional compensation will be allowed therefor.

### **10-1.49 CONCRETE STRUCTURES**

Portland cement concrete structures for austin vault sand filters and minor concrete (minor structure) shall conform to the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

High density polyethylene (HDPE) barrier at footing expansion joint locations shall consist of a smooth continuous sheathing of the thickness shown on the plans and shall have a density between 98 and 100 kg/m<sup>3</sup> as measured in accordance with ASTM Designation: D 792, A-2.

Joints at footing expansion joint locations shall be sealed in conformance with the details shown on the plans, the provisions in Section 51, "Concrete Structures," of the Standard Specifications, and these special provisions.

For the type AL seal, a pourable 2-component polyurethane or silicone sealant that meets the test requirements in Section 51-1.12F(3), "Materials and Installation," of the Standard Specifications and also has a minimum pot life of 10 minutes at a temperature of 32°C may be used, at the option of the Contractor. The 2 components of polyurethane or silicone sealants shall be thoroughly mixed in the ratio recommended by the manufacturer with power driven agitators or the static mixer process, respectively.

Concrete for drainage pads shall conform to the provisions for minor concrete in Section 90, "Portland Cement Concrete," of the Standard Specifications and these special provisions.

Full compensation for furnishing and placing Type AL seals and high density polyethylene (HDPE) barriers at footing expansion joint locations shall be considered as included in the contract price paid per cubic meter for structure concrete (austin vault) and no additional compensation will be allowed therefor.

Full compensation for furnishing and placing concrete drainage pads shall be considered as included in the contract price paid per cubic meter for structure concrete (austin vault) and no separate payment will be made therefor.

### **GENERAL**

Attention is directed to "Precast Concrete Quality Control" of these special provisions.

Shotcrete shall not be used as an alternative construction method for reinforced concrete members unless otherwise specified.

Neoprene strip shall be furnished and installed at joint between headwall and walls of existing reinforced concrete box, and top and walls of reinforced concrete box in conformance with the details shown on the plans, the provisions in the Standard Specifications, and these special provisions.

Furnishing and installing neoprene strip shall conform to the requirements for strip waterstops as provided in Section 51-1.145, "Strip Waterstops," of the Standard Specifications, except that the protective board will not be required.

### **DECK CRACK TREATMENT**

When methacrylate resin work is to be conducted within 31 meters of a residence, business, or public space, including sidewalks under a structure, the Contractor shall notify the public at least 7 days before starting work and monitor airborne emissions during the work. Public notification and monitoring of airborne emissions shall conform to the following:

- A. The public safety plan required in Section 51-1.17A, "Deck Crack Treatment," of the Standard Specifications shall include a copy of the notification letter and a list of addresses and locations where the letter will be delivered and posted. The letter shall state the methacrylate resin work locations, dates, times, and what to expect. The letter shall be delivered to each residence and each business within 31 meters of the methacrylate resin work. The letter shall be delivered to local fire and police responders, and it shall be posted at the job site.
- B. The public safety plan shall include an airborne emissions monitoring plan prepared by a certified industrial hygienist and a copy of the hygienist's certification. Airborne emissions shall be monitored at a minimum of 4 points including the point of mixing, the point of application, and the point of nearest public contact, as determined by the Engineer. At the completion of methacrylate resin work, a report by the certified industrial hygienist with results of the airborne emissions monitoring plan shall be submitted to the Engineer.

## **FALSEWORK**

Falsework shall conform to the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

Temporary crash cushion modules, as shown on the plans and conforming to the provisions in "Temporary Crash Cushion Module" of these special provisions, shall be installed at the approach end of temporary railings which are located less than 4.6 m from the edge of a traffic lane. For 2-way traffic openings, temporary crash cushion modules shall be installed at the departing end of temporary railings which are located less than 1.8 m from the edge of a traffic lane.

The Contractor's engineer who signs the falsework drawings shall also certify in writing that the falsework is constructed in conformance with the approved drawings and the contract specifications prior to placing concrete. This certification shall include performing any testing necessary to verify the ability of the falsework members to sustain the stresses required by the falsework design. The engineer who signs the drawings may designate a representative to perform this certification. Where falsework contains openings for railroads, vehicular traffic, or pedestrians, the designated representative shall be qualified to perform this work, shall have at least three years of combined experience in falsework design or supervising falsework construction, and shall be registered as a Civil Engineer in the State of California. For other falsework, the designated representative shall be qualified to perform this work and shall have at least three years of combined experience in falsework design or supervising falsework construction. The Contractor shall certify the experience of the designated representative in writing and provide supporting documentation demonstrating the required experience if requested by the Engineer.

### **Welding and Nondestructive Testing**

Welding of steel members, except for previously welded splices and except for when fillet welds are used where load demands are less than or equal to 175 N/mm for each 3 mm of fillet weld, shall conform to AWS D1.1 or other recognized welding standard. The welding standard to be utilized shall be specified by the Contractor on the working drawings. Previously welded splices for falsework members are defined as splices made prior to the member being shipped to the project site.

Splices made by field welding of steel beams at the project site shall undergo nondestructive testing (NDT). At the option of the Contractor, either ultrasonic testing (UT) or radiographic testing (RT) shall be used as the method of NDT for each field weld and any repair made to a previously welded splice in a steel beam. Testing shall be performed at locations selected by the Contractor. The length of a splice weld where NDT is to be performed, shall be a cumulative weld length equal to 25 percent of the original splice weld length. The cover pass shall be ground smooth at the locations to be tested. The acceptance criteria shall conform to the requirements of AWS D1.1, Section 6, for cyclically loaded nontubular connections subject to tensile stress. If repairs are required in a portion of the weld, additional NDT shall be performed on the repaired sections. The NDT method chosen shall be used for an entire splice evaluation including any required repairs.

For all field welded splices, the Contractor shall furnish to the Engineer a letter of certification which certifies that all welding and NDT, including visual inspection, are in conformance with the specifications and the welding standard shown on the approved working drawings. This letter of certification shall be signed by an engineer who is registered as a Civil Engineer in the State of California and shall be provided prior to placing any concrete for which the falsework is being erected to support.

For previously welded splices, the Contractor shall determine and perform all necessary testing and inspection required to certify the ability of the falsework members to sustain the stresses required by the falsework design. This welding certification shall (1) itemize the testing and inspection methods used, (2) include the tracking and identifying documents for previously welded members, (3) be signed by an engineer who is registered as a Civil Engineer in the State of California, (4) and shall be provided prior to erecting the members.

### **DECK CLOSURE POURS**

Where a deck closure pour is shown on the plans, reinforcement protruding into the closure space and forms for the closure pour shall conform to the following:

- A. During the time of placement of concrete in the deck, other than for the closure pour itself, reinforcing steel which protrudes into the closure space shall be completely free from any connection to the reinforcing steel, concrete, or other attachments of the adjacent structure, including forms. The reinforcing steel shall remain free of any connection for a period of not less than 24 hours following completion of the pour.
- B. Forms for the closure pour shall be supported from the superstructure on both sides of the closure space.

### **ELASTOMERIC BEARING PADS**

Elastomeric bearing pads shall conform to the provisions in Section 51-1.12H, "Elastomeric Bearing Pads," of the Standard Specifications.

Fabric reinforced bearing pads must not be used.

## MEASUREMENT AND PAYMENT

Measurement and payment for concrete in structures shall conform to the provisions in Section 51-1.22, "Measurement," and Section 51-1.23, "Payment," of the Standard Specifications and these special provisions.

Full compensation for public notification and airborne monitoring for deck crack treatment shall be considered as included in the contract price paid per cubic meter for structural concrete, bridge, and no additional compensation will be allowed therefor.

Full compensation for cored holes shall be considered as included in the contract price paid per cubic meter for structural concrete, bridge or retaining wall involved, and no additional compensation will be allowed therefor.

Wingwalls, parapet and cast-in-place concrete floors for Justin Ave Pedestrian Undercrossing will be measured and paid for as structural concrete, retaining wall.

Concrete footing for water quality outlet riser will be measured and paid for as minor concrete (minor structure).

### 10-1.50 PRECAST CONCRETE BOX CULVERTS

Precast concrete box culvert shall conform to the provisions in Section 51, "Concrete Structures," of the Standard Specifications and the following:

- A. Earthwork, including sand bedding, shall conform to the provisions in Section 19, "Earthwork," of the Standard Specifications.
- B. Reinforcement shall conform to the requirements in welded wire fabric of ASTM Designation: A 185 or A 497, at the Contractor's option.
- C. A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications shall be provided to the Engineer for each precast member shipment. The certificate shall be signed by the manufacturer's quality control representative and shall state that all materials and workmanship comply in all respects with the specification requirements and all approved submittals.
- D. The dry cast method of construction will be permitted when designated on the working drawings. When the dry cast method is used, the results shall be equal in all respects to those obtained by conformance with the provisions in Section 51 and adequate arrangements shall be made and carried out for curing, finishing and protecting the concrete. External vibrators shall be used and the forms shall be sufficiently rigid to resist displacement or damage. The dry casting forms may be removed at any time after consolidating the concrete providing no slumping of the concrete occurs.
- E. Working drawings shall be submitted to the Engineer for approval in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. Working drawings shall show the construction method, precast unit dimensions, configuration of the reinforcement (including splice type and location), and height of earth cover.
- F. Concrete for precast units shall be sampled and tested by the precast manufacturer for compressive strength at least once every production shift and not less often than once daily. Test result records shall be available to the Engineer at all times during regular work shifts.
- G. Each precast unit shall be clearly marked by indentation, waterproof paint, or other approved means. Markings shall include the State contract number, date of manufacture, name or trademark of the manufacturer, and design earth cover. Each precast unit shall be clearly marked by indentation on either the inner or outer surface during the process of manufacture so that the location of the top will be evident immediately after the forms are stripped. In addition, the word "top" shall be lettered with waterproof paint on the inside and outside surfaces of the top of each precast unit.
- H. Manufacturing tolerances for precast concrete box culvert sections shall conform to the requirements in Section 11, "Permissible Variations," of AASHTO Specification: M 259M.
- I. The ends of the precast members shall be so formed that the sections can be laid together to make a continuous line of box sections with a smooth interior free of appreciable irregularities in the flow line.
- J. Handling devices or holes will be permitted in each member for the purpose of handling and laying. Cored and handling holes shall be plugged and sealed so the members meet all the requirements in the specification.
- K. Splices in circumferential reinforcement shall be made by lapping. Welded connections at splices for the outside apron of steel will be allowed only in the splice area shown on the plans. The wall reinforcement on the inside of the box may be lapped and welded at any location or connected by welding at the corners to the slab reinforcement at the inside of the box.
- L. The exposure of spacers, standoffs or the ends of longitudinals used to position the reinforcement shall not be a cause for rejection. Spacers or standoffs shall not be welded to circumferential reinforcement. Spacers or standoffs may be welded to longitudinal reinforcement.
- M. Laying of precast concrete box culvert shall conform to the provisions for laying reinforced concrete pipe in Section 65-1.07, "Laying Pipe," of the Standard Specifications and these special provisions.

- N. Joints shall conform to the provisions for cement mortar or resilient material joints in Section 65-1.06, "Joints," of the Standard Specifications. An external sealing band conforming to the requirements in ASTM Designation: C 877 or C 877M may be used in lieu of the joint material in Section 65-1.06.
- O. Precast concrete box culvert will be measured and paid for by the meter in the same manner as specified for reinforced concrete pipe in Sections 65-1.09, "Measurement," and 65-1.10, "Payment," of the Standard Specifications.
- P. Full compensation for all structure excavation, structure backfill and for furnishing and placing all bar reinforcing steel and welded wire fabric, necessary to construct the precast concrete box culvert complete in place, shall be considered as included in the contract price paid for precast concrete box culvert and no separate payment will be made therefore.
- Q. Full compensation for erecting precast concrete box culvert members shall be considered as included in the contract price paid per meter for precast concrete box culvert and no additional compensation will be allowed therefor.
- R. Full compensation for providing Class 2 surface finish (gun finish) to the walls of the concrete box culvert as shown on the plans and as specified in Section 51-1.18C of the Standard Specifications shall be considered included in the contract price paid per meter for precast concrete box culvert and no additional compensation will be allowed therefor.

#### **10-1.51 DRILL AND BOND DOWEL (CHEMICAL ADHESIVE)**

Drilling and bonding dowels with chemical adhesives shall conform to the details shown on the plans and these special provisions.

Reinforcing steel dowels shall conform to the provisions in "Reinforcement" of these special provisions.

Threaded rods used as dowels shall conform to the provisions in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications. The threaded rods shall be installed in conformance with the requirements for dowels specified herein.

Chemical adhesives to be used shall be selected from the Pre-Qualified Products List at:

[http://www.dot.ca.gov/hq/esc/approved\\_products\\_list/](http://www.dot.ca.gov/hq/esc/approved_products_list/)

The Contractor may propose to use a chemical adhesive not on the Pre-Qualified Products List. Information regarding product qualification can be obtained at the Transportation Laboratory.

The chemical adhesive system used shall be appropriate for the concrete temperature and installation conditions in conformance with the requirements in the Department's prequalified list.

Chemical adhesive systems shall be accompanied by a Certificate of Compliance as provided in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The certificate shall state that the material complies in all respects to the requirements of ICBO AC58 and Caltrans Augmentation/Revisions to ICBO AC58 available at the Transportation Laboratory and at:

[http://www.dot.ca.gov/hq/esc/approved\\_products\\_list/](http://www.dot.ca.gov/hq/esc/approved_products_list/)

At least 25 days prior to use, the Contractor shall submit one sample of each chemical adhesive system per lot to the Transportation Laboratory for testing. The sample shall consist of one unit of chemical adhesive, one mixing nozzle, and one retaining nut. A lot of chemical adhesives is defined as 100 units, or fraction thereof, of the same brand and product name.

Each chemical adhesive system shall be clearly and permanently marked with the manufacturer's name, model number of the system, manufacturing date, lot number, shelf life or expiration date, and current ICBO Evaluation Report (ER) number. Each carton of chemical adhesives shall contain the manufacturer's recommended installation procedures and warnings or precautions concerning the contents as may be required by State or Federal laws and regulations.

The holes shall be drilled by methods that will not shatter or damage the concrete adjacent to the holes. If reinforcement is encountered during drilling, before the specified depth is attained, the Engineer shall be notified. Unless the Engineer approves coring through the reinforcement, the hole will be rejected and a new hole, in which reinforcement is not encountered, shall be drilled adjacent to the rejected hole. The drilled holes shall be cleaned in conformance with the manufacturer's instructions and shall be dry at the time of placing the chemical adhesive. Unless otherwise specified, the diameter and depth of drilled holes shall conform to the values listed in the ICBO ER for the size of dowel or rod being installed.

The depth of the drilled hole listed in the ICBO ER shall be increased by 50 percent when epoxy coating of dowels is required.

Storage and installation procedures shall be as recommended by the manufacturer. A copy of the manufacturer's recommended installation procedure shall be provided to the Engineer at least 2 days prior to the start of work.

Immediately after inserting the dowels into the chemical adhesive, the dowels shall be supported as necessary to prevent movement during curing and shall remain undisturbed until the epoxy has cured a minimum time as specified in the

Department's Pre-Qualified Products List. Dowels that are improperly bonded, as determined by the Engineer, will be rejected. Adjacent new holes shall be drilled, and new dowels shall be placed and securely bonded to the concrete. All work necessary to correct improperly bonded dowels shall be performed at the Contractor's expense.

Unless otherwise provided, dowels to be bonded into drilled holes will be measured and paid for as bar reinforcing steel (bridge).

Unless otherwise provided, drilling and bonding dowels with chemical adhesives will be measured and paid for by the unit as drill and bond dowel (chemical adhesive). The number of units to be paid for will be determined from actual count of the completed units in place.

The contract unit price paid for drill and bond dowel (chemical adhesive) shall include full compensation for furnishing all labor, materials (except dowels), tools, equipment, and incidentals, and for doing all the work involved in drilling the holes and bonding dowels with chemical adhesives, including coring through reinforcement when approved by the Engineer, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

#### **10-1.52 DRILL AND BOND DOWELS**

Drilling and bonding dowels shall conform to the details shown on the plans, the provisions in Section 83-2.02D(1), "General," of the Standard Specifications, and these special provisions.

Dowels shall conform to the provisions for bar reinforcement in "Reinforcement" of these special provisions.

If reinforcement is encountered during drilling before the specified depth is attained, the Engineer shall be notified. Unless the Engineer approves coring through the reinforcement, the hole will be rejected and a new hole, in which reinforcement is not encountered, shall be drilled adjacent to the rejected hole to the depth shown on the plans.

Unless otherwise provided, dowels to be bonded into drilled holes will be paid for as bar reinforcing steel (bridge).

Unless otherwise provided, drilling and bonding dowels will be measured and paid for by the meter determined by the number and the required depth of holes as shown on the plans or as ordered by the Engineer.

The contract price paid per meter for drill and bond dowel shall include full compensation for furnishing all labor, materials (except reinforcing steel dowels), tools, equipment, and incidentals, and for doing all the work involved in drilling the holes, including coring through reinforcement when approved by the Engineer, and bonding the dowels, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

#### **10-1.53 CORE CONCRETE**

Coring concrete shall consist of coring holes through reinforced concrete bridge members as shown on the plans and in conformance with these special provisions.

The holes shall be cored by methods that will not shatter or damage the concrete adjacent to the holes.

Water for core drilling operations shall be from the local domestic water supply or shall not contain more than 1000 parts per million of chlorides as Cl, nor more than 1300 parts per million of sulfates as SO<sub>4</sub>, nor shall the water contain any impurities in a sufficient amount that would cause discoloration of the concrete or produce etching of the surface.

Water from core drilling operations shall not be permitted to fall on public traffic, to flow across shoulders or lanes occupied by public traffic, or to flow into gutters or other drainage facilities.

#### **10-1.54 SEALING JOINTS**

Joints in concrete bridge decks and joints between concrete structures and concrete approach slabs must be sealed in conformance with the details shown on the plans, the provisions in Section 51, "Concrete Structures," of the Standard Specifications, and these special provisions.

When ordered by the Engineer, a joint seal larger than called for by the Movement Rating shown on the plans must be furnished and installed. Payment to the Contractor for furnishing the larger seal and for saw cutting the increment of additional depth of groove required will be determined as provided in Section 4-1.03, "Changes," of the Standard Specifications.

#### **10-1.55 ARCHITECTURAL SURFACE (TEXTURED CONCRETE)**

Architectural texture for concrete surfaces shall conform to the details shown on the plans and the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

Architectural textures listed below are required at concrete surfaces shown on the plans:

- A. Fractured rib texture
- B. Formed relief texture

The fractured rib texture shall be an architectural texture simulating the appearance of straight ribs of concrete with a fractured concrete texture imparted to the raised surface between the ribs. Grooves between ribs shall be continuous with no apparent curves or discontinuities. Variation of the groove from straightness shall not exceed 6 mm for each 3 m of groove. The architectural texture shall have random shadow patterns. Broken concrete at adjoining ribs and groups of ribs shall have a random pattern. The architectural texture shall not have secondary patterns imparted by shadows or repetitive fractured surfaces.

The architectural texture shall simulate a formed relief constructed to the dimensions and shapes shown on the plans. Corners at the intersection of plane surfaces shall be sharp and crisp without easing or rounding. A Class 1 surface finish shall be applied to the architectural texture.

**TEST PANEL**

A test panel at least 1.25 m x 1.25 m in size shall be successfully completed at a location approved by the Engineer before beginning work on architectural textures. The test panel shall be constructed and finished with the materials, tools, equipment and methods to be used in constructing the architectural texture. If ordered by the Engineer, additional test panels shall be constructed and finished until the specified finish, texture and color are obtained, as determined by the Engineer.

The test panel approved by the Engineer shall be used as the standard of comparison in determining acceptability of architectural texture for concrete-surfaces.

**FORM LINERS**

Form liners shall be used for textured concrete surfaces and shall be installed in conformance with the manufacturer's recommendations, unless other methods of forming textured concrete surfaces are approved by the Engineer. Form liners shall be manufactured from an elastomeric material or a semi-elastomeric polyurethane material by a manufacturer of commercially available concrete form liners. No substitution of other types of formliner material will be allowed. Form liners shall leave crisp, sharp definition of the architectural surface. Recurring textural configurations exhibited by repeating, recognizable shadow patterns shall be prevented by proper casting of form liner patterns. Textured concrete surfaces with such recurring textural configurations shall be reworked to remove such patterns as approved by the Engineer or the concrete shall be replaced.

Form liners shall have the following properties:

Description	ASTM Designation:	Range
Elastomeric material		
Shore A hardness	D 2240	20 to 65
Tensile strength (MPa)	D 412	0.9 to 6.2
Semi-elastomeric polyurethane		
Shore D hardness	D 2240	55 to 65
Tensile strength (MPa)	D 2370	18 minimum

Cuts and tears in form liners shall be sealed and repaired in conformance with the manufacturer's recommendations. Form liners that are delaminated from the form shall not be used. Form liners with deformations to the manufactured surface caused by improper storage practices or any other reason shall not be used.

Form liners shall extend the full length of texturing with transverse joints at 2.4 m minimum spacing. Small pieces of form liners shall not be used. Grooves shall be aligned straight and true. Grooves shall match at joints between form liners. Joints in the direction of grooves in grooved patterns shall be located only in the depressed portion of the textured concrete. Adjoining liners shall be butted together without distortion, open cracks or offsets at the joints. Joints between liners shall be cleaned before each use to remove any mortar in the joint.

Adhesives shall be compatible with the form liner material and with concrete. Adhesives shall be approved by the liner manufacturer. Adhesives shall not cause swelling of the liner material.

## RELEASING FORM LINERS

Products and application procedures for form release agents shall be approved by the form liner manufacturer. Release agents shall not cause swelling of the liner material or delamination from the forms. Release agents shall not stain the concrete or react with the liner material. For reliefs simulating fractured concrete or wood grain surfaces the application method shall include the scrubbing method using a natural bristle scrub brush in the direction of grooves or grain. The release agent shall coat the liner with a thin film. Following application of form release agent, the liner surfaces shall be cleaned of excess amounts of agent using compressed air. Buildup of form release agent caused by the reuse of a liner shall be removed at least every 5 uses.

Form liners shall release without leaving particles or pieces of liner material on the concrete and without pulling or breaking concrete from the textured surface. The concrete surfaces exposed by removing forms shall be protected from damage.

## CURING

Concrete surfaces with architectural texture shall be cured only by the forms-in-place or water methods. Seals and curing compounds shall not be used.

## MEASUREMENT AND PAYMENT

Fractured rib texture will be measured and paid for by the square meter.

The contract price paid per square meter for fractured rib texture shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in constructing fractured rib texture, complete in place, including test panels, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for architectural treatment on concrete barrier shall be considered as included in the contract price paid per meter for concrete barrier and no separate payment will be made therefor.

### 10-1.56 REINFORCEMENT

Reinforcement shall conform to the provisions in Section 52, "Reinforcement," of the Standard Specifications and these special provisions.

The Department's mechanical splices prequalified list can be found at the following internet site:

[http://www.dot.ca.gov/hq/esc/approved\\_products\\_list/](http://www.dot.ca.gov/hq/esc/approved_products_list/)

The provisions of "Welding Quality Control" of these special provisions shall not apply to resistance butt welding.

### 10-1.57 STEEL STRUCTURES

Construction of steel structures shall conform to the provisions in Section 55, "Steel Structures," of the Standard Specifications and these special provisions.

## GENERAL

Attention is directed to "Welding" in Section 8, "Materials," of these special provisions.

The following substitutions of high-strength steel fasteners shall be made:

METRIC SIZE SHOWN ON THE PLANS	SIZE TO BE SUBSTITUTED
ASTM Designation: A 325M (Nominal bolt diameter (mm))	ASTM Designation: A 325 (Nominal bolt diameter (inch))
13, 12.70, or M12	1/2
16, 15.88, or M16	5/8
19, 19.05, or M20	3/4
22, 22.22, or M22	7/8
24, 25, 25.40, or M24	1
29, 28.58, or M27	1 1/8
32, 31.75, or M30	1 1/4
38, 38.10, or M36	1 1/2

## **MATERIALS**

Structural steel rolled shapes used in Western Avenue Undercrossing, overhead sign structures, and standards, steel pedestals, and posts shall conform to the Charpy V-notch impact values specified for steel plate in Section 55-2, "Materials," of the Standard Specifications.

High-strength fastener assemblies and other bolts attached to structural steel with nuts and washers shall be zinc-coated. When direct tension indicators are used in these assemblies, the direct tension indicator and all components of the fastener assembly shall be zinc-coated by the mechanical deposition process.

## **ROTATIONAL CAPACITY TESTING PRIOR TO SHIPMENT TO JOB SITE**

Rotational capacity tests shall be performed on all lots of high-strength fastener assemblies prior to shipment of these lots to the project site. Zinc-coated assemblies shall be tested after all fabrication, coating, and lubrication of components has been completed. One hardened washer shall be used under each nut for the tests.

The requirements of this section do not apply to high-strength cap screws or high-strength bolts used for slip base plates.

Each combination of bolt production lot, nut lot, and washer lot shall be tested as an assembly.

A rotational capacity lot number shall be assigned to each combination of lots tested. Each shipping unit of fastener assemblies shall be plainly marked with the rotational capacity lot number.

Two fastener assemblies from each rotational capacity lot shall be tested.

The following equipment, procedure, and acceptance criteria shall be used to perform rotational capacity tests on and determine acceptance of long bolts. Fasteners are considered to be long bolts when full nut thread engagement can be achieved when installed in a bolt tension measuring device:

### **A. Long Bolt Test Equipment:**

1. Calibrated bolt tension measuring device with adequate tension capacity for the bolts being tested.
2. Calibrated dial or digital torque wrench. Other suitable tools will be required for performing Steps 7 and 8 of the Long Bolt Test Procedure. A torque multiplier may be required for large diameter bolts.
3. Spacer washers or bushings. When spacer washers or bushings are required, they shall have the same inside diameter and equal or larger outside diameter as the appropriate hardened washers conforming to the requirements in ASTM Designation: F436.
4. Steel beam or member, such as a girder flange or cross frame, to which the bolt tension measuring device will be attached. The device shall be accessible from the ground.

### **B Long Bolt Test Procedure:**

1. Measure the bolt length. The bolt length is defined as the distance from the end of the threaded portion of the shank to the underside of the bolt head.
2. Install the nut on the bolt so that 3 to 5 full threads of the bolt are located between the bearing face of the nut and the underside of the bolt head. Measure and record the thread stickout of the bolt. Thread stickout is determined by measuring the distance from the outer face of the nut to the end of the threaded portion of the shank.
3. Insert the bolt into the bolt tension measuring device and install the required number of washers, and additional spacers as needed, directly beneath the nut to produce the thread stickout measured in Step 2 of this procedure.
4. Tighten the nut using a hand wrench to a snug-tight condition. The snug tension shall not be less than the Table A value but may exceed the Table A value by a maximum of 2 kips.

Table A

High-Strength Fastener Assembly Tension Values to Approximate Snug-Tight Condition	
Bolt Diameter (inches)	Snug Tension (kips)
1/2	1
5/8	2
3/4	3
7/8	4
1	5
1 1/8	6
1 1/4	7
1 3/8	9
1 1/2	10

- Match-mark the assembly by placing a heavy reference start line on the face plate of the bolt tension measuring device which aligns with 1) a mark placed on one corner of the nut, and 2) a radial line placed across the flat on the end of the bolt, or on the exposed portions of the threads of tension control bolts. Place an additional mark on the outside of the socket that overlays the mark on the nut corner such that this mark will be visible while turning the nut. Make an additional mark on the face plate, either 2/3 of a turn, one turn, or 1 1/3 turn clockwise from the heavy reference start line, depending on the bolt length being tested as shown in Table B.

Table B

Required Nut Rotation for Rotational Capacity Tests <sup>(a,b)</sup>	
Bolt Length (measured in Step 1)	Required Rotation (turn)
4 bolt diameters or less	2/3
Greater than 4 bolt diameters but no more than 8 bolt diameters	1
Greater than 8 bolt diameters, but no more than 12 bolt diameters <sup>(c)</sup>	1 1/3
<p>(a) Nut rotation is relative to bolt, regardless of the element (nut or bolt) being turned. For bolts installed by 1/2 turn and less, the tolerance shall be plus or minus 30 degrees; for bolts installed by 2/3 turn and more, the tolerance shall be plus or minus 45 degrees.</p> <p>(b) Applicable only to connections in which all material within grip of the bolt is steel.</p> <p>(c) When bolt length exceeds 12 diameters, the required rotation shall be determined by actual tests in a suitable tension device simulating the actual conditions.</p>	

- Turn the nut to achieve the applicable minimum bolt tension value listed in Table C. After reaching this tension, record the moving torque, in foot-pounds, required to turn the nut, and also record the corresponding bolt tension value in pounds. Torque shall be measured with the nut in motion. Calculate the value, T (in ft-lbs), where  $T = [(the\ measured\ tension\ in\ pounds) \times (the\ bolt\ diameter\ in\ inches) / 48\ in/ft]$ .

Table C

Minimum Tension Values for High-Strength Fastener Assemblies	
Bolt Diameter (inches)	Minimum Tension (kips)
1/2	12
5/8	19
3/4	28
7/8	39
1	51
1 1/8	56
1 1/4	71
1 3/8	85
1 1/2	103

7. Turn the nut further to increase bolt tension until the rotation listed in Table B is reached. The rotation is measured from the heavy reference line made on the face plate after the bolt was snug-tight. Record this bolt tension.
8. Loosen and remove the nut and examine the threads on both the nut and bolt.

C. Long Bolt Acceptance Criteria:

1. An assembly shall pass the following requirements to be acceptable: 1) the measured moving torque (Step 6) shall be less than or equal to the calculated value, T (Step 6), 2) the bolt tension measured in Step 7 shall be greater than or equal to the applicable turn test tension value listed in Table D, 3) the nut shall be able to be removed from the bolt without signs of thread stripping or galling after the required rotation in Step 7 has been achieved, 4) the bolt does not shear from torsion or fail during the test, and 5) the assembly does not seize before the final rotation in Step 7 is reached. Elongation of the bolt in the threaded region between the bearing face of the nut and the underside of the bolt head is expected and will not be considered a failure. Both fastener assemblies tested from one rotational capacity lot shall pass for the rotational capacity lot to be acceptable.

Table D

Turn Test Tension Values	
Bolt Diameter (inches)	Turn Test Tension (kips)
1/2	14
5/8	22
3/4	32
7/8	45
1	59
1 1/8	64
1 1/4	82
1 3/8	98
1 1/2	118

The following equipment, procedure, and acceptance criteria shall be used to perform rotational capacity tests on and determine acceptance of short bolts. Fasteners are considered to be short bolts when full nut thread engagement cannot be achieved when installed in a bolt tension measuring device:

A. Short Bolt Test Equipment:

1. Calibrated dial or digital torque wrench. Other suitable tools will be required for performing Steps 7 and 8 of the Short Bolt Test Procedure. A torque multiplier may be required for large diameter bolts.
2. Spud wrench or equivalent.
3. Spacer washers or bushings. When spacer washers or bushings are required, they shall have the same inside diameter and equal or larger outside diameter as the appropriate hardened washers conforming to the requirements in ASTM Designation: F436.

4. Steel plate or girder with a hole to install bolt. The hole size shall be 1.6 mm greater than the nominal diameter of the bolt to be tested. The grip length, including any plates, washers, and additional spacers as needed, shall provide the proper number of threads within the grip, as required in Step 2 of the Short Bolt Test Procedure.

B. Short Bolt Test Procedure:

1. Measure the bolt length. The bolt length is defined as the distance from the end of the threaded portion of the shank to the underside of the bolt head.
2. Install the nut on the bolt so that 3 to 5 full threads of the bolt are located between the bearing face of the nut and the underside of the bolt head. Measure and record the thread stickout of the bolt. Thread stickout is determined by measuring the distance from the outer face of the nut to the end of the threaded portion of the shank.
3. Install the bolt into a hole on the plate or girder and install the required number of washers and additional spacers as needed between the bearing face of the nut and the underside of the bolt head to produce the thread stickout measured in Step 2 of this procedure.
4. Tighten the nut using a hand wrench to a snug-tight condition. The snug condition shall be the full manual effort applied to the end of a 305 mm long wrench. This applied torque shall not exceed 20 percent of the maximum allowable torque in Table E.

Table E

Maximum Allowable Torque for High-Strength Fastener Assemblies	
Bolt Diameter (inches)	Torque (ft-lbs)
1/2	145
5/8	285
3/4	500
7/8	820
1	1220
1 1/8	1500
1 1/4	2130
1 3/8	2800
1 1/2	3700

5. Match-mark the assembly by placing a heavy reference start line on the steel plate or girder which aligns with 1) a mark placed on one corner of the nut and 2) a radial line placed across the flat on the end of the bolt or on the exposed portions of the threads of tension control bolts. Place an additional mark on the outside of the socket that overlays the mark on the nut corner such that this mark will be visible while turning the nut. Make 2 additional small marks on the steel plate or girder, one 1/3 of a turn and one 2/3 of a turn clockwise from the heavy reference start line on the steel plate or girder.
6. Using the torque wrench, tighten the nut to the rotation value listed in Table F. The rotation is measured from the heavy reference line described in Step 5 made after the bolt was snug-tight. A second wrench shall be used to prevent rotation of the bolt head during tightening. Measure and record the moving torque after this rotation has been reached. The torque shall be measured with the nut in motion.

Table F

Nut Rotation Required for Turn-of-Nut Installation <sup>(a,b)</sup>	
Bolt Length (measured in Step 1)	Required Rotation (turn)
4 bolt diameters or less	1/3
(a) Nut rotation is relative to bolt, regardless of the element (nut or bolt) being turned. For bolts installed by 1/2 turn and less, the tolerance shall be plus or minus 30 degrees.	
(b) Applicable only to connections in which all material within grip of the bolt is steel.	

7. Tighten the nut further to the 2/3-turn mark as indicated in Table G. The rotation is measured from the heavy reference start line made on the plate or girder when the bolt was snug-tight. Verify that the radial line on the bolt end or on the exposed portions of the threads of tension control bolts is still in alignment with the start line.

Table G

Required Nut Rotation for Rotational Capacity Test	
Bolt Length (measured in Step 1)	Required Rotation (turn)
4 bolt diameters or less	2/3

8. Loosen and remove the nut and examine the threads on both the nut and bolt.

C. Short Bolt Acceptance Criteria:

1. An assembly shall pass the following requirements to be acceptable: 1) the measured moving torque from Step 6 shall be less than or equal to the maximum allowable torque from Table E, 2) the nut shall be able to be removed from the bolt without signs of thread stripping or galling after the required rotation in Step 7 has been achieved, 3) the bolt does not shear from torsion or fail during the test, and 4) the assembly shall not seize before the final rotation in Step 7 is reached. Elongation of the bolt in the threaded region between the bearing face of the nut and the underside of the bolt head will not be considered a failure. Both fastener assemblies tested from one rotational capacity lot shall pass for the rotational capacity lot to be acceptable.

**INSTALLATION TENSION TESTING AND ROTATIONAL CAPACITY TESTING AFTER ARRIVAL ON THE JOB SITE**

Installation tension tests and rotational capacity tests on high-strength fastener assemblies shall be performed by the Contractor prior to acceptance or installation and after arrival of the fastener assemblies on the project site. Installation tension tests and rotational capacity tests shall be performed at the job-site, in the presence of the Engineer, on each rotational capacity lot of fastener assemblies.

The requirements of this section do not apply to high-strength cap screws or high-strength bolts used for slip base plates.

Installation tension tests shall be performed on 3 representative fastener assemblies in conformance with the provisions in Section 8, "Installation," of the RCSC Specification. For short bolts, Section 8.2, "Pretensioned Joints," of the RCSC Specification shall be replaced by the "Pre-Installation Testing Procedures," of the "Structural Bolting Handbook," published by the Steel Structures Technology Center, Incorporated.

The rotational capacity tests shall be performed in conformance with the requirements for rotational capacity tests in "Rotational Capacity Testing Prior to Shipment to Job Site" of these special provisions.

At the Contractor's expense, additional installation tension tests, tests required to determine job inspecting torque, and rotational capacity tests shall be performed by the Contractor on each rotational capacity lot, in the presence of the Engineer, if 1) any fastener is not used within 3 months after arrival on the jobsite, 2) fasteners are improperly handled, stored, or subjected to inclement weather prior to final tightening, 3) significant changes are noted in original surface condition of threads, washers, or nut lubricant, or 4) the Contractor's required inspection is not performed within 48 hours after all fasteners in a joint have been tensioned.

Failure of a job-site installation tension test or a rotational capacity test will be cause for rejection of unused fasteners that are part of the rotational capacity lot.

When direct tension indicators are used, installation verification tests shall be performed in conformance with Appendix Section X1.4 of ASTM Designation: F959, except that bolts shall be initially tensioned to a value 5 percent greater than the minimum required bolt tension.

**SURFACE PREPARATION**

For all bolted connections, the new contact surfaces and inside surfaces of bolt holes shall be cleaned and coated before assembly in conformance with the provisions for cleaning and painting structural steel of these special provisions.

**SEALING**

When zinc-coated tension control bolts are used, the sheared end of each fastener shall be completely sealed with non-silicone type sealing compound conforming to the provisions in Federal Specification TT-S-230, Type II. The sealant shall be gray in color and shall have a minimum thickness of 1.3 mm. The sealant shall be applied to a clean sheared surface on the same day that the splined end is sheared off.

**WELDING**

Table 2.2 of AWS D1.5 is superseded by the following table:

Base Metal Thickness of the Thicker Part Joined, mm	Minimum Effective Partial Joint Penetration Groove Weld Size, * mm
Over 6 to 13 inclusive	5
Over 13 to 19 inclusive	6
Over 19 to 38 inclusive	8
Over 38 to 57 inclusive	10
Over 57 to 150 inclusive	13
Over 150	16

\* Except the weld size need not exceed the thickness of the thinner part

Dimensional details and workmanship for welded joints in tubular and pipe connections shall conform to the provisions in Part A, "Common Requirements of Nontubular and Tubular Connections," and Part D, "Specific Requirements for Tubular Connections," in Section 2 of AWS D1.1.

The requirement of conformance with AWS D1.5 shall not apply to work conforming to Section 56-1, "Overhead Sign Structures," or Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications.

**10-1.58 SIGN STRUCTURES**

Sign structures and foundations for overhead signs shall conform to the provisions in Section 56-1, "Overhead Sign Structures," of the Standard Specifications, "Steel Structures" of these special provisions, and the following requirements.

Before commencing fabrication of sign structures, the Contractor shall submit 2 sets of working drawings to the Engineer in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The working drawings shall include sign panel dimensions, span lengths, post heights, anchorage layouts, proposed splice locations, a snugging and tensioning pattern for anchor bolts and high-strength bolted connections, and details for permanent steel anchor bolt templates. The working drawings shall be supplemented with a written quality control program that includes methods, equipment, and personnel necessary to satisfy the requirements specified herein.

Working drawings shall be 559 mm x 864 mm or 279 mm x 432 mm in size and each drawing and calculation sheet shall include the State assigned designations for the sign structure type and reference as shown on the contract plans, District-County-Route-Kilometer Post, and contract number.

The Engineer shall have 30 days to review the sign structure working drawings after a complete submittal has been received. No fabrication or installation of sign structures shall be performed until the working drawings are approved in writing by the Engineer.

Should the Engineer fail to complete the review within the time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the sign structure working drawings, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Steel bolts not designated on the plans as high strength (HS) or stainless steel shall be for general applications and shall conform to the requirements in ASTM Designation: A 307.

A permanent steel template shall be used to maintain the proper anchor bolt spacing.

One top nut, one leveling nut, and 2 washers shall be provided for the upper threaded portion of each anchor bolt.

Flatness of surfaces for the following shall conform to the requirements in ASTM Designation: A 6/A 6M:

1. Base plates that are to come in contact with concrete, grout, or washers and leveling nuts
2. Plates in high-strength bolted connections

No holes shall be made in members unless the holes are shown on the plans or are approved in writing by the Engineer.

Longitudinal seam welds shall have 60 percent minimum penetration, except that within 150 mm of circumferential welds, longitudinal seam welds shall be complete joint penetration (CJP) groove welds. In addition, longitudinal seam welds on structures having telescopic pole segment splices shall be CJP groove welds on the female end for a length on each end equal to the designated slip fit splice length plus 150 mm.

Steel members used for overhead sign structures shall receive nondestructive testing (NDT) in conformance with AWS D1.1 and the following:

1.

Weld Location	Weld Type	Minimum Required NDT
Splice welds around the perimeter of tubular sections, poles, and arms.	CJP groove weld with backing ring	100% UT <sup>a</sup> or RT <sup>b</sup>
Longitudinal seam welds	CJP or PJP <sup>c</sup> groove weld	Random 25% MT <sup>d</sup>
Longitudinal seam welds within 150 mm of a circumferential splice.	CJP groove weld	100% UT or RT
Welds attaching base plates, flange plates, or pole or mast arm plates, to poles or arm tubes.	CJP groove weld with backing ring and reinforcing fillet	t > 4.5 mm: 100%UT and MT t < 4.5 mm: 100% MT after root weld pass & final weld pass t = pole or arm thickness
	External (top) fillet weld for socket-type connections	100% MT

<sup>a</sup> ultrasonic testing

<sup>b</sup> radiographic testing

<sup>c</sup> partial joint penetration

<sup>d</sup> magnetic particle testing

2. The acceptance and repair criteria for UT of welded joints where any of the members are less than 8 mm thick or where tubular sections are less than 325 mm in diameter shall conform to the requirements in AWS D1.1, Section 6.13.3.1. A written procedure approved by the Engineer shall be used when performing this UT. These written procedures shall conform to the requirements in AWS D1.1, Annex K. The acceptance and repair criteria for other welded joints receiving UT shall conform to the requirements in AWS D1.1, Section 6, Table 6.3 for cyclically loaded nontubular connections.
3. The acceptance and repair criteria for radiographic or real time image testing shall conform to the requirements of AWS D1.1 for tensile stress welds.
4. For longitudinal seam welds, the random locations for NDT will be selected by the Engineer. The cover pass shall be ground smooth at the locations to be tested. If repairs are required in a portion of a tested weld, the repaired portion shall receive NDT, and additional NDT shall be performed on untested portions of the weld. The additional NDT shall be performed on 25 percent of that longitudinal seam weld. After this additional NDT is performed and if more repairs are required, then that entire longitudinal seam weld shall receive NDT.

Circumferential welds and base plate to post welds may be repaired only one time without written permission from the Engineer.

Full compensation for furnishing anchor bolt templates and for testing of welds shall be considered as included in the contract price paid per kilogram for furnish sign structure, and no additional compensation will be allowed therefor.

#### 10-1.59 ROADSIDE SIGNS

Roadside signs shall be furnished and installed at the locations shown on the plans or where designated by the Engineer and in conformance with the provisions in Section 56-2, "Roadside Signs," of the Standard Specifications and these special provisions.

The Contractor shall furnish roadside sign panels in conformance with the provisions in "Furnish Sign" of these special provisions.

Wood posts shall be pressure treated after fabrication in conformance with the provisions in Section 58, "Preservative Treatment of Lumber, Timber and Piling," of the Standard Specifications and AWP A Use Category System: UC4A, Commodity Specification A or B. Type N, Type P, and Type R marker panels mounted on a post with a roadside sign shall be considered to be sign panels and will not be paid for as markers.

#### **10-1.60 FURNISH SIGN**

Signs shall be fabricated and furnished in accordance with details shown on the plans, the Traffic Sign Specifications, and these special provisions.

Traffic Sign Specifications for California sign codes are available for review at:

<http://www.dot.ca.gov/hq/traffops/signtech/signdel/specs.htm>

Traffic Sign Specifications for signs referenced with Federal MUTCD sign codes can be found in Standard Highway Signs Book, administered by the Federal Highway Administration, which is available for review at:

[http://mutcd.fhwa.dot.gov/ser-shs\\_millennium.htm](http://mutcd.fhwa.dot.gov/ser-shs_millennium.htm)

Information on cross-referencing California sign codes with the Federal MUTCD sign codes is available at:

<http://www.dot.ca.gov/hq/traffops/signtech/signdel/specs.htm>

Temporary or permanent signs shall be free from blemishes that may affect the serviceability and detract from the general sign color and appearance when viewing during daytime and nighttime from a distance of 8 m. The face of each finished sign shall be uniform, flat, smooth, and free of defects, scratches, wrinkles, gel, hard spots, streaks, extrusion marks, and air bubbles. The front, back, and edges of the sign panels shall be free of router chatter marks, burns, sharp edges, loose rivets, delaminated skins, excessive adhesive over spray and aluminum marks.

#### **QUALITY CONTROL FOR SIGNS**

The requirements of "Quality Control for Signs" in this section shall not apply to construction area signs.

No later than 14 days before sign fabrication, the Contractor shall submit a written copy of the quality control plan for signs to the Engineer for review. The Engineer will have 10 days to review the quality control plan. Sign fabrication shall not begin until the Engineer approves the Contractor's quality control plan in writing. The Contractor shall submit to the Engineer at least 3 copies of the approved quality control plan. The quality control plan shall include, but not be limited to the following requirements:

- A. Identification of the party responsible for quality control of signs,
- B. Basis of acceptance for incoming raw materials at the fabrication facility,
- C. Type, method and frequency of quality control testing at the fabrication facility,
- D. List (by manufacturer and product name) of process colors, protective overlay film, retroreflective sheeting and black non-reflective film,
- E. Recommended cleaning procedure for each product, and
- F. Method of packaging, transport and storage for signs.

No legend shall be installed at the project site. Legend shall include letters, numerals, tildes, bars, arrows, route shields, symbols, logos, borders, artwork, and miscellaneous characters. The style, font, size, and spacing of the legend shall conform to the Standard Alphabets published in the FHWA Standard Highway Signs Book. The legend shall be oriented in the same direction in accordance with the manufacturer's orientation marks found on the retroreflective sheeting.

On multiple panel signs, legend shall be placed across joints without affecting the size, shape, spacing, and appearance of the legend. Background and legend shall be wrapped around interior edges of formed panel signs as shown on plans to prevent delamination.

The following notation shall be placed on the lower right side of the back of each sign where the notation will not be blocked by the sign post or frame:

- A. PROPERTY OF STATE OF CALIFORNIA,
- B. Name of the sign manufacturer,
- C. Month and year of fabrication,
- D. Type of retroreflective sheeting, and
- E. Manufacturer's identification and lot number of retroreflective sheeting.

The above notation shall be applied directly to the aluminum sign panels in 6-mm upper case letters and numerals by die-stamp and applied by similar method to the fiberglass reinforced plastic signs. Painting, screening, or engraving the notation will not be allowed. The notation shall be applied without damaging the finish of the sign.

Signs with a protective overlay film shall be marked with a dot of 10 mm diameter. The dot placed on white border shall be black, while the dot placed on black border shall be white. The dot shall be placed on the lower border of the sign before application of the protective overlay film and shall not be placed over the legend and bolt holes. The application method and exact location of the dot shall be determined by the manufacturer of the signs.

For sign panels that have a minor dimension of 1220 mm or less, no splice will be allowed in the retroreflective sheet except for the splice produced during the manufacturing of the retroreflective sheeting. For sign panels that have a minor dimension greater than 1220 mm, only one horizontal splice will be allowed in the retroreflective sheeting.

Unless specified by the manufacturer of the retroreflective sheeting, splices in retroreflective sheeting shall overlap by a minimum of 25 mm. Splices shall not be placed within 50 mm from edges of the panels. Except at the horizontal borders, the splices shall overlap in the direction from top to bottom of the sign to prevent moisture penetration. The retroreflective sheeting at the overlap shall not exhibit a color difference under the incident and reflected light.

Signs exhibiting a significant color difference between daytime and nighttime shall be replaced immediately.

Repairing sign panels will not be allowed except when approved by the Engineer.

The Department will inspect signs at the Contractor's facility and delivery location, and in accordance with Section 6, "Control of Materials," of the Standard Specifications. The Engineer will inspect signs for damage and defects before and after installation.

Regardless of kind, size, type, or whether delivered by the Contractor or by a common carrier, signs shall be protected by thorough wrapping, tarping, or other methods to ensure that signs are not damaged by weather conditions and during transit. Signs shall be dry during transit and shipped on pallets, in crates, or tier racks. Padding and protective materials shall be placed between signs as appropriate. Finished sign panels shall be transported and stored by method that protects the face of signs from damage. The Contractor shall replace wet, damaged, and defective signs.

Signs shall be stored in dry environment at all times. Signs shall not rest directly on the ground or become wet during storage. Signs, whether stored indoor or outdoor, shall be free standing. In areas of high heat and humidity signs shall be stored in enclosed climate-controlled trailers or containers. Signs shall be stored indoor if duration of the storage will exceed 30 days.

Screen processed signs shall be protected, transported and stored as recommended by the manufacturer of the retroreflective sheeting.

When requested, the Contractor shall provide the Engineer test samples of signs and materials used at various stages of production. Sign samples shall be 300 mm x 300 mm in size with applied background, letter or numeral, and border strip.

The Contractor shall assume the costs and responsibilities resulting from the use of patented materials, equipment, devices, and processes for the Contractor's work.

## **SHEET ALUMINUM**

Alloy and temper designations for sheet aluminum shall be in accordance with ASTM Designation: B209.

The Contractor shall furnish the Engineer a Certificate of Compliance in accordance to Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for the sheet aluminum.

Sheet aluminum shall be pretreated in accordance to ASTM Designation: B449. Surface of the sheet aluminum shall be cleaned, deoxidized, and coated with a light and tightly adherent chromate conversion coating free of powdery residue. The conversion coating shall be Class 2 with a mass between 108 mg/m<sup>2</sup> and 377 mg/m<sup>2</sup>, and an average mass of 269 mg/m<sup>2</sup>. Following the cleaning and coating process, the sheet aluminum shall be protected from exposure to grease, oils, dust, and contaminants.

Sheet aluminum shall be free of buckles, warps, dents, cockles, burrs, and defects resulting from fabrication.

Base plate for standard route marker shall be die cut.

## **RETROREFLECTIVE SHEETING**

The contractor shall furnish retroreflective sheeting for sign background and legend in accordance with ASTM Designation: D4956 and "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Retroreflective sheeting shall be applied to sign panels as recommended by the retroreflective sheeting manufacturer without stretching, tearing, and damage.

Class 1, 3, or 4 adhesive backing shall be used for Type II, III, IV, VII, VIII, and IX retroreflective sheeting. Class 2 adhesive backing may also be used for Type II retroreflective sheeting. The adhesive backing shall be pressure sensitive and fungus resistant.

When the color of the retroreflective sheeting determined from instrumental testing is in dispute, the Engineer's visual test will govern.

## **PROCESS COLOR AND FILM**

The Contractor shall furnish and apply screened process color, non-reflective opaque black film, and protective overlay film of the type, kind, and product that are approved by the manufacturer of the retroreflective sheeting.

The Contractor shall furnish the Engineer a Certificate of Compliance in accordance to Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for the screened process color, non-reflective opaque black film, and protective overlay film.

The surface of the screened process color shall be flat and smooth. When the screened process colors determined from the instrumental testing in accordance to ASTM Designation: D4956 are in dispute, the Engineer's visual test will govern.

The Contractor shall provide patterns, layouts, and set-ups necessary for the screened process.

The Contractor may use green, red, blue, and brown reverse-screened process colors for background and non-reflective opaque black film or black screened process color for legend. The coefficient of retroreflection for reverse-screened process colors on white retroreflective sheeting shall not be less than 70 percent of the coefficient of retroreflection specified in ASTM Designation: D4956.

The screened process colors and non-reflective opaque black film shall have the same outdoor weatherability as that of the retroreflective sheeting.

After curing, screened process colors shall withstand removal when tested by applying 3M Company Scotch Brand Cellophane Tape No. 600 or equivalent tape over the color and removing with one quick motion at 90° angle.

## **SINGLE SHEET ALUMINUM SIGN**

Single Sheet aluminum signs shall be fabricated and furnished with or without frame. The Contractor shall furnish the sheet aluminum in accordance to "Sheet Aluminum" of these special provisions. Single sheet aluminum signs shall be fabricated from sheet aluminum alloy 6061-T6 or 5052-H38.

Single Sheet aluminum signs shall not have a vertical splice in the sheet aluminum. For signs with depth greater than 1220 mm, one horizontal splice will be allowed in the sheet aluminum.

Framing for single sheet aluminum sign shall consist of aluminum channel or rectangular aluminum tubing. The framing shall have a length tolerance of +3 mm. The face sheet shall be affixed to the frame with rivets of 5-mm diameter. Rivets shall be placed within the web of channels and shall not be placed less than 13 mm from edges of the sign panels. Rivets shall be made of aluminum alloy 5052 and shall be anodized or treated with conversion coating to prevent corrosion. The exposed portion of rivets on the face of signs shall be the same color as the background or legend where the rivets are placed.

Finished signs shall be flat within a tolerance of +31 mm per meter when measured across the plane of the sign in all directions. The finished signs shall have an overall tolerance within +3 mm of the detailed dimensions.

Aluminum channels or rectangular aluminum tubings shall be welded together with the inert gas shielded-arc welding process using E4043 aluminum electrode filler wires as shown on the plans. Width of the filler shall be equal to wall thickness of smallest welded channel or tubing.

## **FIBERGLASS REINFORCED PLASTIC PANEL SIGN**

The contractor shall furnish fiberglass reinforced plastic panel sign in accordance with ASTM Designation: D3841 and "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Fiberglass reinforced plastic shall be acrylic modified and ultraviolet stabilized for outdoor weatherability. The plastic shall contain additives designed to suppress fire ignition and flame propagation. When tested in accordance with the requirements in the ASTM Designation: D635, the extent of burning shall not exceed 25 mm.

Fiberglass reinforced plastic shall be stabilized to prevent the release solvents and monomers. The front and back surfaces of the laminate shall be clean and free of constituents and releasing agents that can interfere with the bonding of retroreflective sheeting.

The fiberglass reinforced plastic panel sign shall be weather resistant Grade II thermoset polyester laminate.

The fiberglass reinforced plastic panels shall be minimum 3.4 mm thick. Finished fiberglass reinforced plastic panel signs shall be flat within a tolerance of +31 mm per meter when measured across the plane of the sign in all directions. The finished signs shall have an overall tolerance within +3 mm of the specified dimensions.

Color of fiberglass reinforced plastic panels shall be uniform gray within Munsell range of N7.5 to N8.5.

Fiberglass reinforced plastic panels shall be cut from a single piece of laminate. Bolt holes shall be predrilled. The predrilled bolt holes, panel edges, and the front and back surfaces of the panels shall be true and smooth. The panel surfaces shall be free of visible cracks, pinholes, foreign inclusions, warping and wrinkles that can affect performance and serviceability.

## **FORMED PANEL SIGN**

Formed panel signs shall be fabricated from one continuous sheet aluminum alloy 5052-H32 of 1.6-mm thickness. The Contractor shall furnish sheet aluminum as provided in "Sheet Aluminum" of these special provisions.

The aluminum frame shall be affixed to the panel with aluminum rivets through the face of the sign panels. Color of the exposed portion of the rivets shall be the same color as the sign background or legend on which the rivets are placed.

The face of finished formed panel sign shall be flat with a tolerance of 10 mm per meter when measured across the plane of each panel in all directions.

The length and depth of the overhead formed panel signs shall be within  $\pm 2$  mm of the detailed dimension.

The formed edges of the overhead panel signs shall be square. The mounting holes shall be straight and perpendicular to the front and back surfaces of the formed edges at the spacing shown on the plans. Holes that are improperly spaced and placed at the wrong angle will be rejected.

### **MEASUREMENT AND PAYMENT**

Furnishing signs (except for construction area signs) will be measured by the square meter and the quantity to be paid for will be the total area, in square meters, of the sign panel types installed in place.

The contract price paid per square meter for furnish sign of the types specified in the Engineer's estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in fabricating and furnishing the signs, including fastening hardware, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for furnishing and installing protective overlay on signs shall be considered as included in the contract price paid per square meter for furnish sign of the various types and no separate payment will be made therefor.

### **10-1.61 CLEAN AND PAINT STRUCTURAL STEEL**

New metal surfaces shall be cleaned and painted in conformance with the provisions in Section 59-2, "Painting Structural Steel," Section 59-3, "Painting Galvanized Surfaces," and Section 91, "Paint," of the Standard Specifications and these special provisions.

#### **GENERAL**

Before performing any painting or paint removal, the Contractor shall submit to the Engineer, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, 3 copies of a separate Painting Quality Work Plan (PQWP) for each item of work for which painting or paint removal is to be performed. As a minimum, each PQWP shall include the following:

- A. The name of each Contractor or subcontractor to be used.
- B. One copy each of all current ASTM and "SSPC: The Society for Protective Coatings" specifications or qualification procedures applicable to the painting or paint removal to be performed. These documents shall become the permanent property of the Department.
- C. A copy of the coating manufacturer's guidelines and recommendations for surface preparation, painting, drying, curing, handling, shipping, and storage of painted structural steel, including testing methods and maximum allowable levels for soluble salts.
- D. Proposed materials, methods, and equipment to be used for any paint application.
- E. Proof of each of any required certifications, SSPC-QP 1, SSPC-QP 2, SSPC-QP 3. Where SSPC-QP 3 certification is required, an enclosed shop facility shall be required. Certification of AISC Sophisticated Paint Endorsement Quality Program, P-1 Enclosed endorsement, will be considered equivalent to SSPC-QP 3.
  1. In lieu of certification in conformance with the requirements in SSPC-QP 3 for this project, the Contractor may submit written documentation showing conformance with the requirements in Section 3, "General Qualification Requirements," of SSPC-QP 3.
- F. Proposed methods to control environmental conditions in accordance with the manufacturer's recommendations and these special provisions.
- G. Proposed methods to protect the coating during curing, shipping, handling, and storage.
- H. Proposed rinse water collection plan.
- I. A detailed paint repair plan for the repair of damaged areas.
- J. Procedures for containing blast media and water during application of coatings and coating repair of erected steel.
- K. Examples of proposed daily reports for all testing to be performed, including type of testing, location, lot size, time, weather conditions, test personnel, and results.

Before submitting the PQWP, a prepainting meeting between the Engineer, the Contractor, and a representative from each entity performing painting for this project shall be held to discuss the requirements for the PQWP.

The Engineer shall have 20 days to review the PQWP submittal after a complete plan has been received. No painting or paint removal shall be performed until the PQWP for that work is approved by the Engineer. Should the Engineer fail to complete the review within this time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the PQWP, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The Engineer's approval of the Contractor's PQWP shall not relieve the Contractor of any responsibility under the contract for the successful completion of the work in conformity with the requirements of the plans and specifications.

The Contractor shall provide enclosures to permit cleaning and painting during inclement weather. Provisions shall be made to control atmospheric conditions inside the enclosures within specified limits during cleaning and painting operations, drying to solvent insolubility, and throughout the curing period in accordance with the manufacturer's recommendations and these special provisions. Full compensation for providing and maintaining such enclosures shall be considered as included in the prices paid for the various contract items of work requiring paint and no additional compensation will be allowed therefor.

Fresh, potable water with a maximum chloride content of 75 mg/L and a maximum sulfate content of 200 mg/L shall be used for water rinsing or pressure washing operations. No continuous recycling of rinse water will be permitted. If rinse water is collected into a tank and subsequent testing determines the collected water conforms to the specified requirements, reuse may be permitted by the Engineer if no collected water is added to the tank after sample collection for determination of conformance to specified requirements.

## **CLEANING**

New metal surfaces, except where galvanized, shall be dry blast cleaned in conformance with the requirements in SSPC-SP 10, "Near White Blast Cleaning," of the "SSPC: The Society for Protective Coatings." Blast cleaning shall leave surfaces with a dense, uniform, angular anchor pattern of not less than 40  $\mu\text{m}$  nor more than 86  $\mu\text{m}$  as measured in conformance with the requirements in ASTM Designation: D 4417.

Mineral and slag abrasives used for blast cleaning steel surfaces shall conform to the requirements for Class A, Grade 2 to 3 abrasives contained in SSPC-AB 1, "Mineral and Slag Abrasives," of the "SSPC: The Society for Protective Coatings," and shall not contain hazardous material.

Steel abrasives used for blast cleaning steel surfaces shall comply with the requirements of SSPC-AB 3, "Ferrous Metallic Abrasive," of the "SSPC: The Society for Protective Coatings." If steel abrasive is recycled through shop or field abrasive blast cleaning units, the recycled abrasive shall conform to the requirements of SSPC-AB 2, "Specification for Cleanliness of Recycled Ferrous Metallic Abrasive," of the "SSPC: The Society for Protective Coatings."

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications and a Material Safety Data Sheet shall be furnished before use for each shipment of blast cleaning material for steel.

Abrasive blast cleaned surfaces shall be tested by the Contractor for soluble salts using a Class A or B retrieval method as described in Technology Guide 15, "Field Methods for Retrieval and Analysis of Soluble Salts on Steel and Other Nonporous Substrates," of the "SSPC: The Society for Protective Coatings," and cleaned so the maximum level of soluble salts does not exceed the lesser of the coating manufacturer's written recommendations or 10 micrograms per square centimeter. Areas of abrasive blast cleaned steel shall be tested at the rate of 3 tests for the first 100 square meters prepared per day, and one test for each additional 100 square meters or portion thereof, at locations selected by the Engineer. When less than 100 square meters of surface area is prepared in a shift, at least 2 tests shall be performed. If levels of soluble salts exceed the maximum allowed by these special provisions, the entire area represented by the testing will be rejected. The Contractor shall perform additional cleaning and testing of rejected areas until soluble salt levels conform to these requirements.

Corners shall be chamfered to remove sharp edges.

Thermal cut edges (TCEs) to be painted shall be conditioned before blast cleaning by shallow grinding or other method approved by the Engineer to remove the thin, hardened layer of material resulting from resolidification during cooling.

Visually evident base metal surface irregularities and defects shall be removed in accordance with ASTM Designation: A 6 or AASHTO Designation: M 160 before blast cleaning steel. When material defects exposed by blast cleaning are removed, the blast profile shall be restored by either blast cleaning or by using mechanical tools in accordance with SSPC-SP 11, "Power Tool Cleaning to Bare Metal," of the "SSPC: The Society for Protective Coatings."

## **PAINTING**

Blast cleaned surfaces shall receive a single undercoat of an inorganic zinc coating and, unless otherwise specified, a minimum of 2 finish coats of an exterior grade latex paint supplied by the manufacturer of the inorganic zinc coating.

The single undercoat shall consist of an inorganic zinc coating conforming to the requirements in AASHTO Designation: M 300, Type I or Type II, except that: 1) the first 3 sentences of Section 5.6, "Primer Field Performance

Requirements," shall not apply for Type II coatings, and 2) the entire Section 5.6.1 shall not apply for either type of inorganic zinc coating.

If the Contractor proposes to use a Type I coating, the Contractor shall furnish to the Engineer for review documentation as required in Section 5.6 of AASHTO Designation: M 300. The Contractor shall allow the Engineer 30 days to review the proposal. Type I coatings selected for use shall meet the current applicable volatile organic compound limits for the air quality district in which the project is located.

If the Contractor proposes to use a Type II coating, the coating shall be selected from the qualified products list, which may be obtained from the Transportation Laboratory.

The color of the final application of inorganic zinc coating shall match Federal Standard 595B No. 36373.

Inorganic zinc coating shall be used within 12 hours of initial mixing.

Application of inorganic zinc coating shall conform to the provisions for applying zinc-rich coating in Section 59-2.13, "Application of Zinc-Rich Primer," of the Standard Specifications.

The single undercoat of inorganic zinc coating shall be applied to the required dry film thickness in 2 or more applications within 8 hours of the start of blast cleaning. Abrasive blast cleaned steel shall not be exposed to relative humidity exceeding 85 percent before application of inorganic zinc coating.

The total dry film thickness of all applications of the inorganic zinc undercoat, including the surfaces of outside existing members within the grip under bolt heads, nuts, and washers, shall be not less than 100  $\mu\text{m}$  nor more than 200  $\mu\text{m}$ , except that the total dry film thickness on each faying (contact) surface of high strength bolted connections shall be between 25  $\mu\text{m}$  and the maximum allowable dry film thickness for Class B coatings as determined by certified testing in conformance with Appendix A of the "Specification for Structural Joints Using ASTM A325 or A490 Bolts" of the Research Council on Structural Connections (RCSC Specification). Unless otherwise stated, all inorganic zinc coatings used on faying surfaces shall meet the slip coefficient requirements for a Class B coating on blast-cleaned steel, as specified in the RCSC Specification. The Contractor shall provide results of certified testing showing the maximum allowable dry film thickness for the Class B coating from the qualifying tests for the coating chosen, and shall maintain the coating thickness on actual faying surfaces of the structure at or below this maximum allowable coating thickness.

Areas where mudcracking occurs in the inorganic zinc coating shall be blast cleaned and repainted with inorganic zinc coating to the specified thickness.

Steel surfaces coated with Type II inorganic zinc coating shall be protected from conditions that may cause the coating film to dissolve. The Contractor, at the Contractor's expense, shall repair areas where the coating has dissolved by blast cleaning and repainting with inorganic zinc coating to the specified thickness.

Dry spray, or overspray, as defined in the Steel Structures Painting Manual, Volume 1, "Good Painting Practice," of the "SSPC: The Society for Protective Coatings," shall be removed before application of subsequent coats or final acceptance. Removal of dry spray shall be by screening or other methods that minimize polishing of the inorganic zinc surface. The dry film thickness of the coating after removal of dry spray shall be in conformance with the provisions for applying the single undercoat, as specified herein.

The Contractor shall test the inorganic zinc coating before application of finish coats. The locations of the tests will be determined by the Engineer. The Contractor shall determine the sequence of the testing operations. The testing for adhesion and hardness shall be performed no sooner than 72 hours after application of the single undercoat of inorganic zinc coating. Satisfactory access shall be provided to allow the Engineer to determine the location of the tests.

The inorganic zinc coating shall pass the following tests:

- A. The inorganic zinc coating shall have a minimum adhesion to steel of 4 MPa when measured using a self-aligning adhesion tester in conformance with the requirements in ASTM Designation: D 4541. The Engineer will select 3 locations per girder or 100 square meters of painted surface, whichever is less, for adhesion testing. If less than 100 square meters of steel is painted in a work shift, the Engineer will select 3 areas painted during the work shift for testing. If 2 or more of the locations tested fail to meet adhesion requirements, the entire area represented by the tests will be rejected. If one of the locations tested fails to meet adhesion requirements, an additional 3 locations shall be tested. Should any of the additional locations fail to meet adhesion requirements, the entire area represented by the tests will be rejected. The Contractor, at the Contractor's expense, shall repair the rejected area by blast cleaning and repainting with inorganic zinc to the specified thickness. Test locations for areas of inorganic zinc meeting adhesion testing requirements shall be repaired by application of organic zinc primer as specified in Section 91-1.04, "Materials," of the Standard Specifications to the specified minimum dry film thickness.
- B. Areas of inorganic zinc coating where finish coats are to be applied shall be tested by the Contractor for soluble salts using a Class A or B retrieval method as described in Technology Guide 15, "Field Methods for Retrieval and Analysis of Soluble Salts on Steel and Other Nonporous Substrates," of the "SSPC: The Society for Protective Coatings," and cleaned so the maximum level of soluble salts does not exceed the lesser of the manufacturer's written recommendations or 10 micrograms per square centimeter. Areas of inorganic zinc coating shall be tested at the rate of 3 tests for the first 100 square meters to be painted per day and one test for each additional 100 square meters or portion thereof at locations selected by the Engineer. When less than 100 square meters of surface area is

painted in a shift, at least 2 tests shall be performed. If levels of soluble salts exceed the maximum allowed by these special provisions, the entire area represented by the testing will be rejected. The Contractor shall perform additional cleaning and testing of rejected areas until soluble salt levels conform to these requirements.

- C. Before application of finish coats, the inorganic zinc coating shall exhibit a solid, hard, and polished metal surface when firmly scraped with the knurled edge of a quarter. Inorganic zinc coating that is powdery, soft, or does not exhibit a polished metal surface, as determined by the Engineer, shall be repaired by the Contractor, at the Contractor's expense, by blast cleaning and repainting with inorganic zinc coating to the specified thickness.

#### **Additional Requirements for Water Borne Inorganic Zinc Primers**

- A. The surface pH of the inorganic zinc primer shall be tested by wetting the surface with de-ionized water for a minimum of 15 minutes but no longer than 30 minutes and applying pH paper with a capability of measuring in increments of 0.5 pH units. At least 2 surface pH readings shall be taken for every 50 square meters or portion thereof. If less than 50 square meters of steel is coated in a single shift or day, at least 2 surface pH readings shall be taken for primer applied during that period. Application of finish coats will not be permitted until the surface pH is less than or equal to 7.
- B. Dry to solvent insolubility for water borne inorganic zinc primers shall be determined in conformance with the requirements in ASTM Designation: D 4752, except that water shall be the solvent. The resistance rating shall be not less than 4. Areas of inorganic zinc coating shall be tested for solvent insolubility at the rate of one test per 50 square meters or portion thereof. Inorganic zinc coating represented by the tested area that does not meet the solvent insolubility requirements will be rejected. The Contractor, at the Contractor's expense, shall repair rejected areas by blast cleaning and repainting with inorganic zinc coating to the specified thickness.

#### **Additional Requirements for Solvent Borne Inorganic Zinc Primers**

- A. Dry to solvent insolubility for solvent borne inorganic zinc primers shall be determined in conformance with the requirements in ASTM Designation: D 4752. The resistance rating shall be not less than 4. Areas of inorganic zinc coating shall be tested for solvent insolubility at the rate of one test per 50 square meters or portion thereof. Inorganic zinc coating represented by the tested area that does not meet the solvent insolubility requirements will be rejected. The Contractor, at the Contractor's expense, shall repair rejected areas by blast cleaning and repainting with inorganic zinc coating to the specified thickness.
- B. Surface hardness of solvent borne inorganic zinc shall be a minimum 2H when measured in conformance with the requirements in ASTM Designation: D 3363. Areas of inorganic zinc coating shall be tested at the rate of one test per 50 square meters or portion thereof. Inorganic zinc coating that fails to meet the surface hardness requirements shall be repaired by the Contractor, at the Contractor's expense, by blast cleaning and repainting with inorganic zinc coating to the specified thickness.

The Contractor, at the Contractor's expense, shall retest all rejected areas of inorganic zinc coating after repairs have been completed.

All areas of inorganic zinc coating shall be water rinsed in conformance with the requirements in Section 59-1.03, "Application," of the Standard Specifications and these special provisions. Areas of the coating removed by water rinsing shall be reapplied in conformance with the provisions for applying zinc-rich coating in Section 59-2.13, "Application of Zinc-Rich Primer," of the Standard Specifications and these special provisions. Except as approved by the Engineer, a minimum time of 72 hours shall be allowed between application of inorganic zinc coating and water rinsing.

The first finish coat shall be applied within 48 hours following water rinsing and passing the soluble salt testing requirements herein.

The finish coat paint shall be formulated for application to inorganic zinc coating, shall meet the requirements for SSPC-Paint 24, "Latex Semi-Gloss Exterior Topcoat," of the "SSPC: The Society for Protective Coatings," and shall conform to the following:

- A. No visible color change in the finish coats shall occur when tested for 800 hours in conformance with the requirements in ASTM Designation: D 4587, Test Cycle 2.
- B. The vehicle shall be an acrylic or modified acrylic copolymer with a minimum of necessary additives.

The first finish coat shall be applied in 2 applications. The first application shall consist of a spray applied mist application. The second application shall be applied after the mist application has dried to a set to touch condition as determined by the procedure described in Section 7 of ASTM Designation: D 1640. The first finish coat color shall match Federal Standard 595B No. 34272. The total dry film thickness of both applications of the first finish coat shall be not less than 50  $\mu\text{m}$ .

Except as approved by the Engineer, a minimum drying time of 12 hours shall be allowed between finish coats.

The second finish coat color shall match Federal Standard 595B No. 14090. The total dry film thickness of the applications of the second finish coat shall be not less than 50 µm.

The 2 finish coats shall be applied in 3 or more applications to a total dry film thickness of not less than 100 µm nor more than 200 µm.

The total dry film thickness of all applications of inorganic zinc coating and finish coat paint shall be not less than 200 µm nor more than 350 µm.

#### **10-1.62 PLASTIC PIPE**

Plastic pipe shall conform to the provisions in Section 64, "Plastic Pipe," of the Standard Specifications.

#### **10-1.63 REINFORCED CONCRETE PIPE**

Reinforced concrete pipe shall conform to the provisions in Section 65, "Reinforced Concrete Pipe," of the Standard Specifications and these special provisions.

##### **GENERAL**

Where embankment will not be placed over the top of the pipe, a relative compaction of not less than 85 percent shall be required below the pipe spring line for pipe installed using Method 1 backfill in trench, as shown on Standard Plan A62D. Where the pipe is to be placed under the traveled way, a relative compaction of not less than 90 percent shall be required unless the minimum distance between the top of the pipe and the pavement surface is the greater of 1.2 meters or one half of the outside diameter of the pipe.

Except as otherwise designated by classification on the plans or in the specifications, joints for culvert and drainage pipes shall conform to the plans or specifications for standard joints.

##### **MATERIALS**

The concrete for reinforced concrete pipe must contain not less than 280 kg of cementitious material per cubic meter with a water-cementitious material ratio not to exceed 0.35 by weight. Supplementary cementitious material is optional. Reinforcement shall have a minimum cover of 25 mm.

#### **10-1.64 CORRUGATED METAL PIPE**

Corrugated steel pipe culverts shall conform to the provisions in Section 66, "Corrugated Metal Pipe," of the Standard Specifications and these special provisions.

Attention is directed to "Earthwork" and "Controlled Low Strength Material" of these special provisions regarding structure backfill for pipe culverts.

Corrugated steel pipe shall be fabricated from zinc-coated steel sheet.

#### **10-1.65 PLASTIC PIPE UNDERDRAIN (AUSTIN VAULT)**

Perforated and non-perforated underdrain plastic pipe specified for use at filtration basins shall conform to these special provisions.

Perforated underdrain pipe shall have round perforations of the size and spacing shown on the plans.

Plastic underdrain pipe shall be polyvinyl chloride (PVC) plastic pipe, Schedule 40, conforming to the provisions for pipe for edge drains and edge drain outlets in Section 68-3.02, "Materials," of the Standard Specifications.

Riser support brackets for clean-outs shall conform to the "Miscellaneous Metal (Austin Vault)" of these special provisions.

##### **MEASUREMENT**

Perforated and non-perforated plastic pipe will be measured by the meter along the line of each type of pipe without deductions for couplers, tees, elbow, and cross connectors. Cleanout pipe will be measured and paid for as plastic pipe underdrain of the sizes shown on the plans.

##### **PAYMENT**

The contract prices paid per meter for perforated plastic pipe underdrain (austin vault) and non-perforated plastic pipe underdrain (austin vault) of the size or sizes shown in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in installing the underdrain pipe complete in place, as shown on the plans, as specified in these special provisions, and as directed by the Engineer.

## **10-1.66 EMERGENCY DRAIN VALVE**

This work shall consist of furnishing all materials and constructing emergency gate valves in conformance with the details shown on the plans and these special provisions.

### **MATERIALS**

#### **Gate Valve**

Gate valves of the size shown on the plans shall be resilient wedge type rated for 1.72 MPa cold water working pressure. All ferrous components shall be ductile iron, ASTM A536. Valves shall be in full compliance with AWWA C515. The words "D.I." or "Ductile Iron" shall be cast on the valve. The wedge shall be ductile iron or bronze encapsulated with EPDM rubber.

The wedge shall be symmetrical and seal equally well with flow in either direction.

The gate valve stem and wedge nut shall be copper alloy in accordance with Section 4.4.5.1 of the AWWA C515 Standard. Stainless Steel stems are not acceptable. The NRS stem must have an integral thrust collar in accordance with Section 4.4.5.3 of AWWA C515 Standard. Two-piece stem collars are not acceptable. The wedge nut shall be independent of the wedge and held in place on three sides by the wedge to prevent possible misalignment.

Valves shall be certified by NSF to Standard 61.

Bolting materials shall develop the physical strength requirements of ASTM A307 and may have either regular square or hexagonal heads with dimensions conforming to ANSI B18.2.1. Metric size socket head cap screws, therefore, are not allowed.

The operating nut shall be constructed of ductile iron and shall have four flats at stem connection to ensure even input torque to the stem.

All gaskets shall be pressure-energized O-Rings.

Stem shall be sealed by three O-Rings. The top two O-Rings shall be replaceable with valve fully open and while subject to full rated working pressure. O-Rings set in a cartridge shall not be allowed.

Valve shall have thrust washers located with (1) above and (1) below the thrust collar to ensure trouble-free operation of the valve.

All internal and external surfaces of the valve body and bonnet shall have a fusion-bonded-epoxy coating, complying with ANSI/AWWA C550, applied electrostatically prior to assembly.

#### **Valve Box and Cover**

Valve boxes shall be cast iron, meet the minimum dimension requirements as shown on the plans, and be equipped with a removable lid that can be secured with bolts.

Valve boxes and lids shall be traffic rated.

#### **Concrete and Reinforcing Steel**

Concrete for valve boxes shall conform to the provisions for minor concrete in Section 90, "Portland Cement Concrete," of the Standard Specifications.

Reinforcing steel shall conform to the provisions for minor structures in Section 52, "Reinforcement," of the Standard Specifications.

#### **PVC Riser Pipe**

Riser pipe shall be polyvinyl chloride (PVC) plastic pipe, Schedule 40, conforming to the provisions for pipe for edge drains and edge drain outlets in Section 68-3.02, "Materials," of the Standard Specifications.

#### **Valve Stem Extension**

Valve stem extensions, when required, shall conform to the details as shown on the plans and the requirements in Section 75 Miscellaneous Metal," of the Standard Specifications. All components of valve stem extensions shall be galvanized.

### **MEASUREMENT**

Emergency drain valves will be measured and paid for by the unit.

### **PAYMENT**

The contract unit price paid for emergency drain valve shall include full compensation for furnishing all labor, materials (including PVC riser, valve stem extension, concrete, reinforcing steel, and valve boxes with covers), tools, equipment, and incidentals, and for doing all the work involved in furnishing and constructing emergency drain valves, complete in place, as shown on the plans, as specified in these special provisions, and as directed by the Engineer.

**10-1.67 MISCELLANEOUS FACILITIES**

Corrugated steel pipe risers and precast concrete pipe manholes shall conform to the provisions in Section 70, "Miscellaneous Facilities," of the Standard Specifications and these special provisions.

Full compensation for cutting the orifice holes to the sizes and locations shown on the plans shall be considered as included in the contract price paid per meter for corrugated steel pipe riser and no separate payment will be made therefor.

**10-1.68 SLOPE PROTECTION**

Slope protection shall be placed or constructed in conformance with the provisions in Section 72, "Slope Protection," of the Standard Specifications and these special provisions.

Rock slope protection fabric shall be woven or nonwoven type fabric, Type A or Type B, at the option of the Contractor.

**10-1.69 GABIONS**

Gabions shall be constructed as shown on the plans and in conformance with these special provisions.

Gabions shall consist of wire mesh, cubical-celled or mattress-styled baskets that are filled on the project site with hard, durable rock.

Standard gabion sizes and the overall plan and profile dimensions of the gabion structures shall be as shown on the plans. Each standard gabion size shall be divided into 900 mm long cells by diaphragm panels. The width, height or length of the standard gabions shall not vary more than 5 percent from the dimensions specified in these special provisions or as shown on the plans.

Empty gabion baskets shall be assembled individually and joined successively. Individual gabion mesh panels (base, front, ends, back, diaphragms, and lid) and successive gabions shall be assembled so that the strength and flexibility along the joints is comparable to a single panel.

**MATERIALS**

All materials for the gabions and gabion assembly shall conform to the provisions in these special provisions. Each shipment of gabion baskets to the project site shall be accompanied by a Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

**Mesh**

At the Contractor's option, either twisted mesh or welded mesh shall be used, in conformance with Table 1 and Table 2 herein. For each standard gabion size, the same mesh style shall be used for the base, front, ends, back, diaphragms, and lid panels. Individual wires of either the twisted-mesh style or the welded-mesh style shall conform to the definitions and requirements in ASTM Designation: A 641/A 641M.

Mattress-style gabion baskets that are 300-mm and 450-mm high shall be manufactured from either 11-gage welded mesh or twisted mesh. Cubical-celled gabion baskets that are 900 mm high by 900 mm wide shall be fabricated from 11-gage twisted mesh or welded mesh gages between 11-gage and 9-gage, inclusive.

Table 1

CUBICAL-CELLED FACILITIES	
USA WIRE GAGE	MESH STYLE
11	Twisted Mesh
11 Min to 9 Max	Welded Mesh

Table 2

MATTRESS-STYLE FACILITIES	
USA WIRE GAGE	MESH STYLE
11	Twisted Mesh
11	Welded Mesh

**GABION MESH MATERIAL PROPERTIES**

Characteristic	Test Designation	Requirement
Minimum tensile strength	ASTM A 370	410 Mpa
Wire Size	USA Steel Wire Gage	11
Wire Diameter	ASTM A 641/A 641M	3.05 mm
(Minimum)	ASTM A 641/A 641M	2.95 mm
Galvanizing, Zinc	ASTM A 641/A 641M, Class 3 and ASTM A 90/A 90M	240 g/m <sup>2</sup>
Wire Size	USA Steel Wire Gage	9
Wire Diameter	ASTM A 641/A 641M	3.76 mm
(Minimum)	ASTM A 641/A 641M	3.66 mm
Galvanizing, Zinc	ASTM A 641/A 641M, Class 3 and ASTM A 90/A 90M	270 g/m <sup>2</sup>

Twisted-mesh wires shall form a uniform hexagonal pattern and shall be formed with a nonraveling twist. The area of the hexagonal opening shall not exceed the dimensions shown on the plans. Twisted-mesh gabion panels shall be manufactured from 11 gage wires with 9 gage selvage wires.

Welded-mesh wires shall form a grid pattern as shown on the plans. Welds shall be made by resistance welding. Welds and panels shall conform to the requirements in ASTM Designation: A 185, except weld shears shall be 2.7 kN minimum for 11 gage wires and 3.6 kN minimum for 9 gage wires. Resistance welding after coating the wire with zinc will be acceptable if there are no large splashes, flakes or flashes of zinc at the weld.

**Joints**

Standard tie wire and standard spiral binder shall conform to the definitions and requirements in ASTM Designation: A 641/A 641M and shall conform to the following provisions:

Characteristic	Test Designation	Requirement
Minimum Tensile Strength	ASTM A 370	410 Mpa
Tie Wire		
Wire Size (Minimum)	USA Steel Wire Gage	13.5
Wire Diameter	ASTM A 641/A 641M	2.19 mm
(Minimum)	ASTM A 641/A 641M	2.09 mm
Zinc Coating	ASTM A 641/A 641M, Class 3 and ASTM A 90/A 90M	220 g/m <sup>2</sup>
Spirals		
Wire Size (Maximum)	USA Steel Wire Gage	9
Wire Diameter	ASTM A 641/A 641M	3.76 mm
(Minimum)	ASTM A 641/A 641M	3.66 mm
Zinc Coating	ASTM A 641/A 641M, Class 3 and ASTM A 90/A 90M	270 g/m <sup>2</sup>

Spiral binders shall have a 75 mm separation between continuous, successive loops.

Alternative fasteners shall have the configurations, wire diameters, and other dimensions shown on the plans. Alternative fasteners shall conform to the definitions and requirements in ASTM Designation: A 764 for "Metallic Coated Carbon Steel Wire, Coated at Size and Drawn to Size for Mechanical Springs." Interlocking fasteners shall conform to Tensile Requirement Class I, Finish 2 and shall have a Class 3 zinc coating, Overlapping fasteners shall conform to Tensile Requirement Class II, Finish 1 and shall have a Class 3 zinc coating.

**Internal Connecting Wire**

Internal connecting wires shall be 13.5-gage minimum. Each wire shall conform to the minimum requirements for standard tie wire in these special provisions and shall be installed in conformance with the provisions in these special provisions and as shown on the plans. Alternatively, at the Contractor's option, preformed stiffeners may be substituted for internal connecting wires. Preformed stiffener wire shall meet the requirements specified for standard tie wire and shall be installed in conformance with these special provisions and the manufacturer's recommendations.

**Rock**

Rock for filling gabions, which are greater than or equal to 450 mm in height, shall vary in size and shall conform to the following:

Screen Size (mm)	Percentage Passing
305	100
102	0-5

Rock for filling gabions, which are equal to 300 mm in height, shall vary in size and shall conform to the following:

Screen Size (mm)	Percentage Passing
203	100
102	0-5

Rock shall conform to the material provisions for rock slope protection in Section 72-2.02, "Materials," of the Standard Specifications.

The minimum unit weight of a rock-filled gabion shall be 1750 kg/m<sup>3</sup>. Verification of the 1750kg/m<sup>3</sup> shall be performed when ordered by the Engineer. Verification shall be performed on the smallest standard gabion size to be used on the project. The rock supplied for the project shall be used for verification. Filling shall be done using the same method intended for actual construction. The weight of a rock-filled gabion shall be determined using available certified scales. The volume for calculating the unit weight shall be determined on the theoretical volume of the standard gabion which is rock-filled and weighed.

### **GRADING, EXCAVATION AND BACKFILL**

Areas where gabions are to be placed shall be constructed to the lines and grades shown on the plans and as determined by the Engineer. Excavation or backfill for achieving the required grades shall conform to the provisions for structure excavation and backfill in Section 19, "Earthwork," of the Standard Specifications.

### **CONSTRUCTION**

Gabions shall be assembled individually as empty units. Each gabion shall be manufactured with the necessary panels, properly spaced and secured, so that the panels can be rotated into position at the construction site with no additional tying of the rotation joint. The panels and diaphragms shall be rotated into position and joined along the vertical edges.

For twisted mesh, the joint shall be constructed using alternating double and single half hitches (locked loops) of 13.5-gage standard tie wire at 100-mm nominal spacing. Joints shall not be constructed with simple spiraling (looping without locking) of the standard tie wires.

When standard tie wire is used as a joint connector for welded mesh, the joint shall be constructed using alternating double and single half hitches (locked loops) in every mesh opening along the joint. When 9 gage spiral binders are used, the spiral shall be placed so that the spiral binder passes through each mesh opening along the joint. Both ends of all 9 gage spiral binders shall be crimped to secure the spiral in place.

Temporary fasteners may be used to hold panels wherever gabion-to-gabion joints will be constructed. Temporary fasteners may remain in place.

At the Contractor's option, interlocking fasteners or overlapping fasteners may be used for assembly of either the twisted-mesh or welded-mesh gabions. A fastener shall be placed in each mesh opening along the joint (a minimum of 10 fasteners per meter).

### **ASSEMBLY OF SUCCESSIVE GABION BASKETS (GABION-TO-GABION JOINTS)**

Gabion baskets shall be set in place. Individually constructed gabion baskets shall then be joined successively to the next gabion baskets with 13.5-gage tie wire or 9 gage standard spiral binder before filling the basket with rock. The 13.5-gage standard tie wire or 9 gage standard spiral binder shall secure, in one pass, all selvage or end wires of the panels of all adjacent baskets along the joint.

When forming successive gabion-to-gabion joints with alternative fasteners, there shall be one alternative fastener in each mesh opening. The alternative fastener shall contain and secure all the wires along the joint.

Gabion baskets shall be joined along the front, back, and ends, including the tops and bottoms of the adjacent gabions.

### **ASSEMBLY OF MULTIPLE LAYERED GABIONS**

Multi-layered gabion configurations shall be stepped and staggered as shown on the plans or as designated by the Engineer.

When constructing multi-layered gabion configurations, each layer of gabions shall be joined to the underlying layer along the front, back, and ends.

### **FILLING WITH ROCK**

Before filling each gabion basket with rock, all kinks and folds in the wire fabric shall be straightened and all successive gabions shall be properly aligned.

Rock shall be placed in the baskets to provide proper alignment, avoid bulges in the wire mesh, and provide a minimum of voids. All exposed rock surfaces shall have a smooth and neat appearance. Sharp rock edges shall not project through the wire mesh.

Internal connecting wires or preformed stiffeners shall be used to produce a flat, smooth external surface, when constructing with 0.5-m or one meter high gabions. If the Engineer determines that there is excessive bulging or dimpling of the outside panels, the unit shall be reconstructed at the Contractor's expense.

When filling one meter high gabions, rock shall be placed in 3 nominal 0.33-m layers to allow placement of the 13.5-gage internal connecting wires. The wires shall be fastened as shown on the plans. Alternatively, preformed stiffeners may be installed at the one-third points in conformance with the recommendations of the manufacturer, to produce a smooth external surface.

When filling 0.5-m high gabions, 2 nominal 0.25-m layers of rock shall be placed to allow placement of a set of internal connecting wires or preformed stiffeners. The configuration of wires shall be similar to those used on the one meter high gabions, except there shall be only one set of internal connecting wires instead of the 2 sets of internal connecting wires or preformed stiffeners.

The last layer of rock shall slightly overfill the gabion baskets so that the lid will rest on rock when the lid is closed.

### **CLOSURE OF LIDS**

Lids shall be tied along the front, ends, and diaphragms in conformance with the provisions in "Assembly of Successive Gabion Baskets (Gabion-to-Gabion Joints)" of these special provisions.

### **MEASUREMENT**

Gabions will be measured by the cubic meter as determined from the dimensions shown on the plans or the dimensions directed by the Engineer and gabions placed in excess of these dimensions will not be paid for.

### **PAYMENT**

The contract price paid per cubic meter for gabion shall include full compensation for furnishing all labor, materials (including gabion baskets, and rock), tools, equipment, and incidentals, and for doing all the work involved in constructing gabions, complete, in place, including excavation and backfill, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

## **10-1.70 MISCELLANEOUS CONCRETE CONSTRUCTION**

Minor concrete (textured paving) and miscellaneous construction shall conform to the provisions in Section 73, "Concrete Curbs and Sidewalks," of the Standard Specifications and these special provisions.

Curb ramp detectable warning surface shall consist of raised truncated domes constructed or installed on curb ramps in conformance with the details shown on the plans and these special provisions. At the option of the Contractor, the detectable warning surface shall be prefabricated, cast-in-place, or stamped into the surface of the curb ramp. The color of the detectable warning surface shall be yellow conforming to Federal Standard 595B, Color No. 33538.

Full compensation for constructing or furnishing and installing curb ramp detectable warning surfaces shall be considered as included in the contract price paid per cubic meter for minor concrete (curb ramp) and no separate payment will be made therefor.

Aggregate for minor concrete (textured paving) shall conform to the grading specified for fine aggregate in Section 90-3.03, Fine Aggregate Grading," of the Standard Specification

Portland cement concrete closely conforming to the colors specified for textured paving are available through commercial concrete sources.

A sample of sufficient size and color of the textured paving, to demonstrate the textured paving, including color hardener, curing and finishing compounds and forming tools, shall be submitted to the Engineer for written approval.

Textured paving shall not be placed on the project prior to approval by the Engineer of the samples prepared and submitted by the Contractor. In the event more than one sample of each type and color of textured paving to be placed is required by the Engineer, each additional sample will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Welded wire fabric, of the size and type shown on the plans and conforming to the provisions in Section 52, "Reinforcement," of the Standard Specifications, shall be placed in the textured paving areas as shown on the plans.

Aggregate base shall be Class 2 and shall conform to the provisions in Section 26, "Aggregate Bases," of the Standard Specifications.

The respective pattern types for textured paving shall be placed at the locations shown on the plans, struck off and compacted until a layer of mortar is brought to the surface. The concrete shall be screeded to the required grade and cross section and floated to a uniform surface.

The forming tools for the textured paving shall be applied to form the patterned surfaces while the concrete is still in the plastic stage of set.

One set of forming tools for stamped concrete shall be delivered to the Engineer after completion of work.

Textured paving areas shall be cured by the curing compound method. The curing compound shall be curing compound (6) conforming to the provisions in Section 90-7.01B, "Curing Compound Method," of the Standard Specifications.

For payment purposes, the area in square meters of minor concrete (textured paving) will be determined from horizontal measurements of the finished textured paving.

The contract price paid per square meter for minor concrete (textured paving) shall include full compensation for furnishing all labor, materials (including welded wire fabric, where required, and aggregate base), tools, equipment, and incidentals, and for doing all the work involved in constructing , including removal of asphalt concrete, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

#### **10-1.71 MISCELLANEOUS IRON AND STEEL**

Miscellaneous iron and steel shall conform to the provisions in Section 75, "Miscellaneous Metal," of the Standard Specifications.

#### **10-1.72 MISCELLANEOUS METAL (AUSTIN VAULT)**

Miscellaneous metal (austin vault) and (water quality outlet riser) shall conform to the provisions for miscellaneous bridge metal in Section 75, "Miscellaneous Metal," of the Standard Specifications and these special provisions.

Attention is directed to "Welding" of these special provisions.

Miscellaneous metal (austin vault) shall consist of the following items:

- A. Steel Ladders
- B. Steel Angles
- C. Stainless Steel Expansion Anchors
- D. Stainless Steel Components of Riser Support Brackets
- E. Steel Handrails
- F. Steel Trash Screen

Cast-in-place inserts shall be the ferrule loop type.

Metal parts of concrete anchorage devices shall be fabricated from stainless steel conforming to the requirements of ASTM Designation: A 276, Type 316. Miscellaneous metal items designated on the plans to be stainless steel shall conform to the requirements of ASTM Designation: A276, Grade 304.

#### **10-1.73 BRIDGE DECK DRAINAGE SYSTEM**

Bridge deck drainage systems shall conform to the provisions for miscellaneous bridge metal in Section 75, "Miscellaneous Metal," of the Standard Specifications and these special provisions.

Self-tapping screws used for sleeve connections shall be hex-head stainless steel, installed in holes drilled to fit the self-tapping screws, conforming to the requirements of ASTM Designation: A 276, Type 304.

At the Contractor's option, fiberglass pipes and fittings with the same diameter and minimum bend radius as those shown on the plans, may be substituted for welded steel pipe in deck drain systems.

Fiberglass pipe and fittings shall conform to the requirements in ASTM Designation: D 2996, and shall have a minimum short-term rupture strength of 207 MPa. The adhesive type recommended by the manufacturer shall be used for joining pipe and fittings. Fiberglass pipe not enclosed in a box girder cell or encased in concrete shall be manufactured from ultraviolet-resistant resin pigmented with concrete-gray color, or be coated with a concrete-gray resin-rich exterior coating. Paint shall not be used. Fiberglass pipe treated with ultraviolet protection shall withstand a minimum of 2500 hours of accelerated weathering when tested in conformance with the requirements in ASTM Designation: G 154. Lamps shall be UV-B (313 nm wavelength). The resting cycle shall be 4 hours of ultraviolet exposure at 60°C, and then 4 hours of condensate exposure at 50°C. After testing, the surface of the pipe shall exhibit no fiber exposure, crazing, or checking, and only a slight chalking or color change.

Support spacing for fiberglass pipe shall be the same as shown on the plans for welded steel pipe. Pipe supports shall have a width of not less than 38 mm.

A Certificate of Compliance for fiberglass pipe and fittings shall be furnished to the Engineer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The Certificate of Compliance shall include all laboratory test results conforming to the provisions specified herein.

For drainage piping NPS 8 or smaller, which is: encased in concrete, the Contractor shall have the option of substituting polyvinyl chloride (PVC) plastic pipe and fittings, with the same diameter and minimum bend radius as shown on the plans, for welded steel pipe.

The PVC plastic pipe and fittings shall be Schedule 40 conforming to the requirements of ASTM Designations: D 1785. The maximum support spacing for PVC plastic pipe shall be 2 m.

Couplings used to connect PVC plastic pipe or fiberglass pipe to steel shall be threaded or flanged. The sleeve connections shown on the plans shall not be used for either PVC plastic pipe or fiberglass pipe.

If PVC plastic pipe or fiberglass pipe is substituted for welded steel pipe, the quantity of drainage piping will be computed on the basis of the dimensions and details shown on the plans, and no change in the quantities to be paid for will be made because of the use of PVC plastic pipe or fiberglass pipe.

Full compensation for constructing bridge deck drainage systems shall be considered included in the contract price paid per cubic meter for structural concrete, bridge, and no additional compensation will be allowed therefor.

#### **10-1.74 CHAIN LINK FENCE**

Chain link fence shall be Type CL-1.8 and shall conform to the provisions in Section 80, "Fences," of the Standard Specifications.

#### **10-1.75 CHAIN LINK WALK GATE**

Chain link walk gates shall be Type CL-1.8 conforming to the provisions in Section 80, "Fences," of the Standard Specifications and these special provisions.

Gates shall be installed in existing fences at the locations shown on the plans. Gate installations shall be complete with gate post, latch post, concrete footings, braces, truss rods, and hardware. Gate and latch posts shall be braced to the next existing line post as shown on the plans.

At each gate location, an existing line post shall be removed and the new gate installed so that the gate is centered on the post hole of the removed post. Holes resulting from the removal of line posts shall be backfilled.

Gate mounting and latching hardware shall not contain open-end slots for the fastening bolts.

Chain link fabric for gates shall be of the same mesh size as the existing fence in which the gates are installed.

Openings made in existing fences for installation of gates shall be closed during the working day in which the openings are made and when work is not in progress. Temporary closures shall be made with the existing fence fabric or with additional 1.83-m chain link fabric as directed by the Engineer.

Full compensation for making the openings in existing fences, for temporary closing of the openings (including furnishing additional fence fabric if necessary), and for new posts, footings, hardware, braces, and truss rods shall be considered as included in the contract unit price paid for 1.5-m chain link gate (Type CL-1.8) and no additional compensation will be allowed therefor.

#### **10-1.76 DELINEATORS**

Delineators shall conform to the provisions in Section 82, "Markers and Delineators," of the Standard Specifications and these special provisions.

Delineators on flexible posts shall conform to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. Flexible posts shall be made from a flexible white plastic which shall be resistant to impact, ultraviolet light, ozone, and hydrocarbons. Flexible posts shall resist stiffening with age and shall be free of burns, discoloration, contamination, and other objectionable marks or defects which affect appearance or serviceability.

Retroreflective sheeting for metal and flexible target plates shall be the retroreflective sheeting designated for channelizers, markers, and delineators conforming to the requirements in ASTM Designation: D 4956-95 and in conformance with the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

#### **10-1.77 METAL BEAM GUARD RAILING**

Metal beam guard railing shall be constructed in conformance with the provisions in Section 83-1, "Railings," of the Standard Specifications and these special provisions.

Attention is directed to "Order of Work" of these special provisions.

Line posts shall be wood. Blocks shall be wood.

#### **ALTERNATIVE FLARED TERMINAL SYSTEM**

Alternative flared terminal system shall be furnished and installed as shown on the plans and in conformance with these special provisions.

The allowable alternatives for a flared terminal system shall consist of one of the following or a Department approved equal.

- (1) **TERMINAL SYSTEM (TYPE FLEAT)** - Terminal system (Type FLEAT) shall be a Flared Energy Absorbing Terminal 350 manufactured by Road Systems, Inc., located in Big Spring, Texas, and shall include items detailed for terminal system (Type FLEAT) shown on the plans. The Flared Energy Absorbing Terminal 350 can be obtained from the distributor, Universal Industrial Sales, P.O. Box 699, Pleasant Grove, UT 84062, Telephone (801) 785-0505 or from the distributor, Gregory Highway Products, 4100 13<sup>th</sup> Street, S.W., Canton, OH 44708, Telephone (330) 477-4800.
- (2) **TERMINAL SYSTEM (TYPE SRT)** - Terminal system (Type SRT) shall be an SRT-350 Slotted Rail Terminal (8-post system) as manufactured by Trinity Industries, Inc., and shall include items detailed for terminal system (Type SRT) shown on the plans. The SRT-350 Slotted Rail Terminal (8-post system) can be obtained from the manufacturer, Trinity Industries, Inc., P.O. Box 99, 950 West 400S, Centerville, UT 84014, Telephone (800) 772-7976.

The Contractor shall provide the Engineer with a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The Certificate of Compliance shall certify that the terminal systems furnished conform to the contract plans and specifications, conform to the prequalified design and material requirements, and were manufactured in conformance with the approved quality control program.

Terminal systems shall be installed in conformance with the manufacturer's installation instructions and these requirements. Each terminal system installed shall be identified by painting the type of terminal system in neat black letters and figures 60 mm high on the backside of the rail element between system posts numbers 4 and 5.

For terminal system (Type SRT), the steel foundation tubes with soil plates attached shall be, at the Contractor's option, either driven, with or without pilot holes, or placed in drilled holes. Space around the steel foundation tubes shall be backfilled with selected earth, free of rock, placed in layers approximately 100 mm thick and each layer shall be moistened and thoroughly compacted. The wood terminal posts shall be inserted into the steel foundation tubes by hand and shall not be driven. Before the wood terminal posts are inserted, the inside surfaces of the steel foundation tubes to receive the wood posts shall be coated with a grease which will not melt or run at a temperature of 65°C or less. The edges of the wood terminal posts may be slightly rounded to facilitate insertion of the post into the steel foundation tubes.

For terminal system (Type FLEAT), the soil tubes shall be, at the Contractor's option, driven with or without pilot holes, or placed in drilled holes. Space around the steel foundation tubes shall be backfilled with selected earth, free of rock, placed in layers approximately 100 mm thick and each layer shall be moistened and thoroughly compacted. Wood posts shall be inserted into the steel foundation tubes by hand. Before the wood terminal posts are inserted, the inside surfaces of the steel foundation tubes to receive the wood posts shall be coated with a grease which will not melt or run at a temperature of 65°C or less. The edges of the wood posts may be slightly rounded to facilitate insertion of the post into the steel foundation tubes.

Surplus excavated material remaining after the terminal system has been installed shall be disposed of in a uniform manner along the adjacent roadway where designated by the Engineer.

The contract unit price paid for alternative flared terminal system shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in furnishing and installing alternative flared terminal system, complete in place, including excavation, backfill and disposal of surplus material, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

#### **10-1.78 CHAIN LINK RAILING**

Chain link railing shall conform to the provisions in Section 83-1, "Railings," of the Standard Specifications and these special provisions.

The chain link fabric shall be 9-gage (3.76 mm), Type IV, Class B, bonded vinyl coated fabric, conforming to the requirements in AASHTO Designation: M 181.

The strength of the bond between the coating material and steel of the bonded vinyl coated chain link fabric shall be equal to or greater than the cohesive strength of the polyvinyl chloride (PVC) coating material.

#### **10-1.79 CABLE RAILING**

Cable railing shall conform to the provisions in Section 83-1, "Railings," of the Standard Specifications.

#### **10-1.80 CONCRETE BARRIER**

Concrete barriers shall conform to the provisions in Section 83-2, "Barriers," of the Standard Specifications and these special provisions.

Concrete barrier markers shall conform to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. At those locations shown on the plans, concrete barrier markers shall be cemented to the barrier in conformance with the manufacturer's recommendations.

Full compensation for architectural treatment on concrete barrier shall be considered as included in the contract price paid per meter for concrete barrier of types shown in the Engineer's estimate and no separate payment will be made therefor.

**10-1.81 TRANSITION RAILING (TYPE WB)**

Transition railing (Type WB) shall be furnished and installed in conformance with details shown on the plans, the provisions in Section 83-2, "Barriers," of the Standard Specifications and these special provisions.

The 10-gage rail elements shall conform to the requirements of Class B, Type 1 three beam guard railing as shown in AASHTO Designation: M 180. End caps shall conform to the requirements of Class A, Type 1 three beam guard railing as shown in AASHTO Designation: M 180.

Surplus excavated material remaining after the transitional railing (Type WB) has been constructed shall be disposed of in a uniform manner along the adjacent roadway where designated by the Engineer.

The contract unit price paid for transition railing (Type WB) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in furnishing and installing transition railing (Type WB), complete in place, including drilling holes for wood posts, driving posts, backfill, and disposal of surplus material, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

**10-1.82 THERMOPLASTIC TRAFFIC STRIPE AND PAVEMENT MARKING**

Thermoplastic traffic stripes (traffic lines) and pavement markings shall be applied in conformance with the provisions in Section 84, "Traffic Stripes and Pavement Markings," of the Standard Specifications and these special provisions.

Thermoplastic material shall be free of lead and chromium, and shall conform to the requirements in State Specification PTH-02ALKYD.

Retroreflectivity of the thermoplastic traffic stripes and pavement markings shall conform to the requirements in ASTM Designation: D 6359-99. White thermoplastic traffic stripes and pavement markings shall have a minimum initial retroreflectivity of  $250 \text{ mcd}\cdot\text{m}^{-2}\cdot\text{lx}^{-1}$ . Yellow thermoplastic traffic stripes and pavement markings shall have a minimum initial retroreflectivity of  $150 \text{ mcd}\cdot\text{m}^{-2}\cdot\text{lx}^{-1}$ .

Where striping joins existing striping, as shown on the plans, the Contractor shall begin and end the transition from the existing striping pattern into or from the new striping pattern a sufficient distance to ensure continuity of the striping pattern.

Thermoplastic traffic stripes shall be applied at the minimum thickness and application rate as specified below. The minimum application rate is based on a solid stripe of 100 mm in width.

Minimum Stripe Thickness (mm)	Minimum Application Rate (kg/m)
2.0	0.4

Thermoplastic traffic stripes and pavement markings shall be free of runs, bubbles, craters, drag marks, stretch marks, and debris.

At the option of the Contractor, permanent traffic striping and pavement marking tape conforming to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions may be placed instead of the thermoplastic traffic stripes and pavement markings specified herein. Permanent tape, if used, shall be installed in conformance with the manufacturer's specifications.

If permanent tape is placed instead of thermoplastic traffic stripes and pavement markings, the tape will be measured and paid for by the meter as thermoplastic traffic stripe and by the square meter as thermoplastic pavement marking.

**10-1.83 PAINT TRAFFIC STRIPE AND PAVEMENT MARKING**

Painted traffic stripes (traffic lines) and pavement markings shall be applied in conformance with the provisions in Section 84, "Traffic Stripes and Pavement Markings," of the Standard Specifications and these special provisions.

Traffic stripe and pavement marking paint shall conform to the requirements in State Specification No. PTWB-01.

The color of the painted traffic stripes and pavement markings shall conform to the requirements in ASTM Designation: D 6628-01.

Retroreflectivity of the paint traffic stripes and pavement markings shall conform to the requirements in ASTM Designation: D 6359-99. White painted traffic stripes and pavement markings shall have a minimum initial retroreflectivity

of  $250 \text{ mcd}\cdot\text{m}^{-2}\cdot\text{lx}^{-1}$ . Yellow painted traffic stripes and pavement markings shall have a minimum initial retroreflectivity of  $150 \text{ mcd}\cdot\text{m}^{-2}\cdot\text{lx}^{-1}$ .

At the option of the Contractor, permanent traffic striping and pavement marking tape conforming to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions may be placed instead of painted traffic stripes and pavement markings. Permanent tape, if used, shall be placed in conformance with the manufacturer's specifications.

If permanent tape is placed instead of painted traffic stripes and pavement markings, the tape will be measured and paid for by the meter as paint traffic stripe and by the square meter as paint pavement marking of the number of coats designated in the Engineer's Estimate.

#### **10-1.84 PAVEMENT MARKERS**

Pavement markers shall be placed in conformance with the provisions in Section 85, "Pavement Markers," of the Standard Specifications and these special provisions.

Attention is directed to "Traffic Control System For Lane Closure" of these special provisions regarding the use of moving lane closures during placement of pavement markers with bituminous adhesive.

The Contractor shall furnish the Engineer certificates of compliance for the pavement markers in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

Retroreflective pavement markers shall be marked as abrasion resistant on the body of the markers.

### **SECTION 10-2 HIGHWAY PLANTING AND IRRIGATION SYSTEMS**

#### **10-2.01 GENERAL**

The work performed in connection with highway planting and irrigation systems shall conform to the provisions in Section 20, "Erosion Control and Highway Planting," of the Standard Specifications and these special provisions.

The Contractor shall notify the Engineer not less than 72 hours prior to requiring initial access to the existing irrigation controllers. When the Engineer determines that access to the controllers is required at other times, arrangements will be made to provide this access.

#### **PROGRESS INSPECTIONS**

Progress inspections will be performed by the Engineer for completed highway planting and irrigation system work at designated stages during the life of the contract.

Progress inspections will not relieve the Contractor of responsibility for installation in conformance with the special provisions, plans and Standard Specifications. Work within an area shall not progress beyond each stage until the inspection has been completed, corrective work has been performed, and the work is approved, unless otherwise permitted by the Engineer.

The requirements for progress inspections will not preclude additional inspections of work by the Engineer at other times during the life of the contract.

The Contractor shall notify the Engineer, in writing, at least 4 working days prior to completion of the work for each stage of an area and shall allow a minimum of 3 working days for the inspection.

Progress inspections will be performed at the following stages of work:

- A. During pressure testing of the pipelines on the supply side of control valves.
- B. During testing of low voltage conductors.
- C. Before planting begins and after completion of the work specified for planting in Section 20-4.03, "Preparing Planting Areas," of the Standard Specifications.
- D. Before plant establishment work begins and after completion of the work specified for planting in Section 20-4.05, "Planting," of the Standard Specifications.
- E. At intervals of one month during the plant establishment period.

#### **COST BREAK-DOWN**

The Contractor shall furnish the Engineer a cost break-down for the contract lump sum items of highway planting and irrigation system. Cost break-down tables shall be submitted to the Engineer for approval within 10 working days after the contract has been approved. Cost break-down tables will be approved, in writing, by the Engineer before any partial payment will be made for the applicable items of highway planting and irrigation system involved.

Attention is directed to "Time-Related Overhead" of these special provisions regarding compensation for time-related overhead.

Cost break-downs shall be completed and furnished in the format shown in the samples of the cost break-downs included in this section. Line item descriptions of work shown in the samples are the minimum to be submitted. Additional line item descriptions of work may be designated by the Contractor. If the Contractor elects to designate additional line item descriptions of work, the quantity, value and amount for those line items shall be completed in the same manner as for the unit descriptions shown in the samples. The line items and quantities given in the samples are to show the manner of preparing the cost break-downs to be furnished by the Contractor.

The Contractor shall determine the quantities required to complete the work shown on the plans. The quantities and their values shall be included in the cost break-downs submitted to the Engineer for approval. The Contractor shall be responsible for the accuracy of the quantities and values used in the cost break-downs submitted for approval.

The sum of the amounts for the line items of work listed in each cost break-down table for highway planting and for irrigation system work shall be equal to the contract lump sum price bid for Highway Planting and Irrigation System, respectively. Overhead and profit, except for time-related overhead, shall be included in each individual line item of work listed in a cost break-down table.

No adjustment in compensation will be made in the contract lump sum prices paid for highway planting and irrigation system due to differences between the quantities shown in the cost break-downs furnished by the Contractor and the quantities required to complete the work as shown on the plans and as specified in these special provisions.

Individual line item values in the approved cost break-down tables will be used to determine partial payments during the progress of the work and as the basis for calculating an adjustment in compensation for the contract lump sum items of highway planting and irrigation system due to changes in line items of work ordered by the Engineer. When the total of ordered changes to line items of work increases or decreases the lump sum price bid for either Highway Planting or Irrigation System by more than 25 percent, the adjustment in compensation for the applicable lump sum item will be determined in the same manner specified for increases and decreases in the total pay quantity of an item of work in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications.

**HIGHWAY PLANTING COST BREAK-DOWN**

**Contract No. 07-1786A4**

UNIT DESCRIPTION	UNIT	APPROXIMATE QUANTITY	VALUE	AMOUNT
ROADSIDE CLEARING	LS	LUMP SUM		
PLANT (GROUP A)	EA	345		
PLANT (GROUP F)	EA	27,150		
PLANT (GROUP H)	EA	83,672		
PLANT (GROUP U)	EA	105		
MULCH	M <sup>3</sup>	561		
COMMERCIAL FERTILIZER (SLOW RELEASE)	KG	110		
FERTILIZER PACKET	EA	345		

**TOTAL** \_\_\_\_\_

**IRRIGATION SYSTEM COST BREAK-DOWN**

**Contract No. 07-1786A4**

UNIT DESCRIPTION	UNIT	APPROXIMATE QUANTITY	VALUE	AMOUNT
CHECK AND TEST EXISTING IRRIGATION FACILITIES	LS	LUMP SUM		
CONTROL AND NEUTRAL CONDUCTORS	LS	LUMP SUM		
SPRINKLER (TYPE C-2)	EA	203		
SPRINKLER (TYPE A-5)	EA	232		
25 MM ELECTRIC REMOTE CONTROL VALVE	EA	12		
40 MM ELECTRIC REMOTE CONTROL VALVE	EA	10		
50 MM ELECTRIC REMOTE CONTROL VALVE	EA	4		
40 MM BALL VALVE	EA	5		
50 MM GATE VALVE	EA	2		
65 MM GATE VALVE	EA	2		
20 MM PLASTIC PIPE (PR 200) SUPPLY LINE	M	2633		
25 MM PLASTIC PIPE (PR 200) SUPPLY LINE	M	834		
32 MM PLASTIC PIPE (PR 200) SUPPLY LINE	M	1134		
40 MM PLASTIC PIPE (PR 200) SUPPLY LINE	M	70		
50 MM PLASTIC PIPE (PR 200) SUPPLY LINE	M	440		
65 MM PLASTIC PIPE (PR 200) SUPPLY LINE	M	350		
20 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	M	60		
25 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	M	20		
25 MM SPRINKLER CONTROL CONDUIT	M	20		
50 MM GALVANIZED STEEL PIPE (SUPPLY LINE)	M	20		
PIPE AND CONDUIT ANCHORS	LS	LUMP SUM		
IRRIGATION CONTROLLER ENCLOSURE CABINET	EA	1		
IRRIGATION CONTROLLER 12 STATION	EA	1		
IRRIGATION CONTROLLER 24 STATION	EA	1		
RECYCLE WATER WARNING SIGNS	LS	LUMP SUM		

IRRIGATION SYSTEMS FUNCTIONAL TEST	LS	LUMP SUM		
VINE POCKET	LS	LUMP SUM		
RISER/FLEXIBLE HOSE AND CONNECTIONS	LS	LUMP SUM		

**TOTAL** \_\_\_\_\_

**10-2.02 EXISTING HIGHWAY PLANTING**

In addition to the provisions in Section 20, "Erosion Control and Highway Planting," of the Standard Specifications, work performed in connection with existing highway planting shall conform to the provisions in "Existing Highway Facilities," of these special provisions.

**10-2.03 EXISTING HIGHWAY IRRIGATION FACILITIES**

The work performed in connection with the various existing highway irrigation system facilities shall conform to the provisions in "Existing Highway Facilities," of these special provisions.

Water shall be maintained in conformance with the provisions in Section 20-5.025, "Maintain Existing Water Supply," of the Standard Specifications.

**CHECK AND TEST EXISTING IRRIGATION FACILITIES**

Existing irrigation facilities that are to remain or to be relocated, and that are within those areas where clearing and grubbing or earthwork operations are to be performed, shall be checked for missing or damaged components and proper operation prior to performing clearing and grubbing or earthwork operations. Existing irrigation facilities outside of work areas that are affected by the construction work shall also be checked for proper operation.

A written list of existing irrigation system deficiencies shall be submitted to the Engineer within 5 working days after checking the existing facilities.

Deficiencies found during checking of the existing facilities shall be corrected as directed by the Engineer. Corrective work ordered by the Engineer will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

When existing irrigation facilities are checked, existing backflow preventers shall be tested for proper operation in conformance with the provisions in Section 20-5.03J, "Check and Test Backflow Preventers," of the Standard Specifications.

Existing backflow preventers shall be retested one year after the satisfactory completion of the previous test, and each year thereafter until the plant establishment period is completed. An additional test shall be provided not more than 10 days prior to acceptance of the contract.

Length of watering cycles for use of potable water from water meters for checking or testing existing irrigation facilities shall be as determined by the Engineer.

Additional repairs required for the existing irrigation system as ordered by the Engineer, except as otherwise provided for in "Existing Highway Irrigation Facilities" of these special provisions, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

Additional repairs required for the existing irrigation system as ordered by the Engineer, except as otherwise provided for in "Maintain Existing Irrigation Facilities" of these special provisions, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

**MAINTAIN EXISTING IRRIGATION FACILITIES**

Existing irrigation facilities shall be maintained throughout the life of the contract. Prior to the start of maintaining existing irrigation facilities work, the facilities shall be checked for proper operation, and repaired in conformance with the provisions in "Check and Test Existing Irrigation Facilities" of these special provisions.

After the existing facilities have been checked and repaired, the Contractor shall be responsible for the routine maintenance of existing irrigation systems. The work shall include, but not limited to, checking irrigation systems for proper operation and adjusting, repairing or replacing valves, valve boxes, sprinklers, risers, swing joints, wye strainers, valve assembly units, and filter assembly units.

The Contractor will not be responsible for maintaining existing water meters, underground pipe supply lines, control and neutral conductors, and electrical conduits. Except as otherwise specified in "Existing Highway Irrigation Facilities" of these special provisions, repair work to these facilities ordered by the Engineer will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

Existing automatic irrigation systems shall be operated automatically during the life of the contract, except manual operation will be allowed for the work during plant replacement, fertilization, weed germination, and the repair of irrigation facilities.

Irrigation controllers shall be programmed by the Contractor for seasonal water requirements. During winter seasons irrigation systems shall be operated automatically a minimum of 2 minutes every 2 weeks.

Irrigation systems and facilities shall be checked for proper operation at least once every 30 days. When required, as determined by the Engineer, adjusting, repairing or replacing irrigation facilities shall be completed within 5 working days after checking the irrigation systems. Except as provided in these special provisions, repair and replacement of irrigation facilities shall conform to the provisions in "Existing Highway Irrigation Facilities" of these special provisions.

Except as provided in these special provisions, the contract lump sum price paid for maintain existing irrigation facilities shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in maintaining existing irrigation facilities, complete in place, including checking irrigation facilities, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

#### **10-2.04 HIGHWAY PLANTING**

The work performed in connection with highway planting shall conform to the provisions in Section 20-4, "Highway Planting," of the Standard Specifications and these special provisions.

##### **HIGHWAY PLANTING MATERIALS**

###### **Mulch**

Mulch must be green material and must comply with the following:

1. The mulch provider must be a compost producer and a participant in the United States Composting Council (USCC) Seal of Testing Assurance (STA) program.
2. The green material producer must be fully permitted as a compost producer in accordance with requirements of the California Integrated Waste Management Board (CIWMB), Local Enforcement Agencies (LEA) and any other State and Local Agencies that regulate solid waste facilities. If exempt from State permitting requirements, the composting facility must certify that it follows all guidelines and procedures for production of compost meeting the environmental health standards of Title 14, California Code of Regulations, Division 7, Chapter 3.1, Article 7.
3. Green material may be derived from any single or mixture of chipped, shredded, or ground vegetation; or clean processed recycled wood products.
4. Compost green materials such that weed seeds, pathogens and deleterious materials are reduced as specified under Title 14, California Code of Regulations, Division 7, Chapter 3.1, Article 7, Section 17868.3.
5. Green material must not contain paint, petroleum products, herbicides, fungicides or other chemical residues harmful to animal life or plant growth. Compost must possess no objectionable odors.
6. Metal concentrations in green material must not exceed the maximum metal concentrations listed in Title 14, California Code of Regulations, Division 7, Chapter 3.1, Section 17868.2.
7. Green material must comply with the following table:

**Physical and Chemical Requirements**

Property	Test Method	Requirement
pH	TMECC 04.11-A, Elastometric pH 1:5 Slurry Method, pH Units	6.0–8.0
Soluble Salts	TMECC 04.10-A, Electrical Conductivity 1:5 Slurry Method dS/m (mmhos/cm)	0–10.0
Moisture Content	TMECC 03.09-A, Total Solids & Moisture at 70+/- 5 deg C, % Wet Weight Basis	N/A
Organic Matter Content	TMECC 05.07-A, Loss-On-Ignition Organic Matter Method (LOI), % Dry Weight Basis	30–100
Maturity	TMECC 05.05-A, Germination and Vigor Seed Emergence Seedling Vigor % Relative to Positive Control	N/A N/A
Stability	TMECC 05.08-B, Carbon Dioxide Evolution Rate mg CO <sub>2</sub> -C/g OM per day	N/A
Particle Size	TMECC 02.02-B Sample Sieving for Aggregate Size Classification % Dry Weight Basis	Millimeters % Passing 76.0 99% 9.5 < 25% Max. Length 100 mm
Pathogen	TMECC 07.01-B, Fecal Coliform Bacteria < 1000 MPN/gram dry wt.	Pass
Pathogen	TMECC 07.01-B, Salmonella < 3 MPN/4 grams dry wt.	Pass
Physical Contaminants	TMECC 02.02-C, Man Made Inert Removal and Classification: Plastic, Glass and Metal, % > 4mm fraction	Combined Total: < 1.0
Physical Contaminants	TMECC 02.02-C, Man Made Inert Removal and Classification: Sharps (Sewing needles, straight pins and hypodermic needles), % > 4mm fraction	None Detected

NOTE: TMECC refers to "Test Methods for the Examination of Composting and Compost," published by the United States Department of Agriculture and the United States Compost Council (USCC).

8. Before mulch application, submit a copy of the green material producer's Compost Technical Data Sheet and a copy of the compost producers STA certification. The Compost Technical Data Sheet must include laboratory analytical test results, directions for product use, and a list of product ingredients.
9. Before mulch application, submit a Certificate of Compliance under Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

Mulch must consist of either wood chips or tree bark or a combination of both.

Mulch for mulch areas must be green material, tree bark, wood chips, shredded bark, or either wood chips or tree bark or a combination of both. Wood chips produced from tree trimmings may contain leaves and small twigs.

**APPLICATION**

**Commercial Fertilizer (Slow Release)**

Commercial fertilizer (slow release) shall be a pelleted or granular form, shall be slow or controlled release with a nutrient release over an 8- to 12-month period, and shall fall within the following guaranteed chemical analysis range:

Ingredient	Percentage
Nitrogen	16-21
Phosphoric Acid	6-8
Water Soluble Potash	4-10

### **Commercial Fertilizer (Packets)**

Commercial fertilizer (packet) shall be slow or controlled release and shall be in a biodegradable packet form. The packet shall gradually release nutrients over a 12-month period. Each packet shall have a mass of  $10 \text{ g} \pm 1 \text{ g}$  and shall have the following guaranteed chemical analysis:

Ingredient	Percentage
Nitrogen	20
Phosphoric Acid	10
Water Soluble Potash	5

### **ROADSIDE CLEARING**

Prior to preparing planting areas or commencing irrigation trenching operations for planting areas, trash and debris shall be removed from these areas and a distance of 3 m beyond the edges of those areas. At locations where proposed planting areas are 3.6 m or more from the edges of dikes, curbs, sidewalks, fences, walls, paved shoulders and existing planting to remain, the clearing limit shall be 2 m beyond the outer limits of the proposed planting area.

In addition to removing trash and debris, the project area shall be cleared as specified herein:

- A. Existing plants, where shown on the plans to be removed, shall be removed.
- B. Weeds shall be killed and removed within proposed ground cover areas and within the area extending beyond the outer limits of the proposed ground cover areas to the adjacent edges of shoulders, dikes, curbs, sidewalks, walls, existing planting and fences. At those locations where proposed ground cover areas are 3.6 m or more from the adjacent edges of shoulders, dikes, curbs, sidewalks, walls, and fences, the clearing limit shall be 2 m beyond the outer limits of the proposed ground cover areas.
- C. Weeds shall be killed and removed within proposed mulch areas and within the area extending beyond the outer limits of the proposed mulch areas to the adjacent edges of shoulders, dikes, curbs, sidewalks, walls, existing planting and fences. At those locations where proposed mulch areas are 3.6 m or more from the adjacent edges of shoulders, dikes, curbs, sidewalks, walls, and fences, the clearing limit shall be 2 m beyond the outer limits of the proposed mulch areas.
- D. Weeds shall be killed and removed within planting areas where plants are to be planted in groups or rows 4.6 m or less apart and from within an area extending 2 m beyond the outer limits of the groups or rows of plants.
- E. Weeds shall be killed and removed within an area 2 m in diameter centered at each plant location where the plants are to be planted more than 4.6 m apart and are located outside of ground cover areas.

After the initial roadside clearing is complete, additional roadside clearing work shall be performed as necessary to maintain the areas, as specified above, in a neat appearance until the start of the plant establishment period. This work shall include the following:

- A. Trash and debris shall be removed.
- B. Rodents shall be controlled.
- C. Weed growth shall be killed before the weeds reach the seed stage of growth or exceed 150 mm in length, whichever occurs first.
- D. Existing ground cover shall be killed and removed from within the 2 m diameter areas specified for each proposed plant location within the existing ground cover areas.
- E. Weeds in plant basins, including basin walls, shall be removed by hand pulling, after the plants have been planted.
- F. Areas outside the areas specified to be cleared of weeds shall be mowed.

### **Weed Control**

Weed control shall also conform to the following:

- A. Stolon type weeds shall be killed with glyphosate.
- B. Tumbleweeds shall be removed by hand pulling before the tumbleweeds reach a height of 150 mm.
- C. Removed weeds and ground cover shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.
- D. At the option of the Contractor, weed growth in mowed areas may be controlled by growth regulators. Growth regulators shall be applied before weeds exceed 300 mm in height.

Roadside clearing work shall not include work required to be performed as clearing and grubbing as specified in Section 16, "Clearing and Grubbing," of the Standard Specifications.

### **PESTICIDES**

Pesticides used to control weeds shall conform to the provisions in Section 20-4.026, "Pesticides," of the Standard Specifications. Except as otherwise provided in these special provisions, pesticide use shall be limited to the following materials:

- Cacodylic Acid
- Diquat
- Fluazifop-butyl
- Glyphosate
- Isoxaben (Preemergent)
- Sethoxydim
- Oxadiazon - 50 percent WP (Preemergent)
- Oryzalin (Preemergent)
- Pendimethalin (Preemergent)
- Prodiamine (Preemergent)
- Trifluralin (Preemergent)
- Napropamide (Preemergent)

Glyphosate shall be used to kill stolon type weeds.

Oxadiazon shall be of the emulsifiable concentration or wettable powder type, except when Oxadiazon is used under mulch in conformance with these special provisions.

If the Contractor elects to request the use of other pesticides on this project, the request shall be submitted, in writing, to the Engineer not less than 15 days prior to the intended use of the other pesticides. Except for the pesticides listed in these special provisions, no pesticides shall be used or applied without prior written approval of the Engineer.

Pesticides shall not be applied within the limits of the plant basins. Pesticides shall not be applied in a manner that allows the pesticides to come in contact with the foliage and woody parts of the plants.

### **PLANTING**

Backfill material for plant holes shall be a mixture of soil and soil amendment. The quantity of soil amendment shall be as shown on the Plant List. Soil amendment shall conform to the provisions in Section 20-2.03, "Soil Amendment," of the Standard Specifications. Backfill material shall be thoroughly mixed and uniformly distributed throughout the entire depth of the plant hole without clods and lumps.

Commercial fertilizer (pelleted and granular) shall be applied or placed at the time of planting and at the rates shown on the Plant List and in conformance with the provisions in Section 20-4.05, "Planting," of the Standard Specifications and these special provisions.

Commercial fertilizer packets shall be placed in the backfill of each plant at the time of planting and at the rate shown on the Plant List to within 150 to 200 mm of the soil surface and approximately 25 mm from the roots. When more than one fertilizer packet is required per plant, the packets shall be distributed evenly around the root ball.

Mulch will not be required in the plant basins when mulch is not indicated on the Plant List for the plants involved.

Mulch placed in areas outside of plant basins shall be spread to a uniform depth of 100 mm.

Mulch shall not be placed within one meter of the centerline of earthen drainage ditches, within one meter of the edge of paved ditches, and within one meter of the centerline of drainage flow lines.

Attention is directed to "Irrigation Systems Functional Test" of these special provisions regarding functional tests of the irrigation systems. Planting shall not be performed in an area until the functional test has been completed for the irrigation system serving that area.

### **PLANT ESTABLISHMENT WORK**

The plant establishment period shall be Type 2 and shall not be less than 250 working days.

Attention is directed to "Relief From Maintenance and Responsibility" in these special provisions regarding relief from maintenance and protection.

Commercial fertilizer (slow release) shall be applied to trees, shrubs, vines and ground cover during the first week of March and October of each year. Commercial fertilizer shall be applied at the rates shown on the plans and shall be spread with a mechanical spreader wherever possible.

The center to center spacing of replacement plants for unsuitable ground cover plants shall be determined by the number of completed plant establishment working days at the time of replacement and the original spacing in conformance with the following:

ORIGINAL SPACING (Millimeters)	SPACING OF REPLACEMENT GROUND COVER PLANTS (Millimeters)		
	Number of Completed Plant Establishment Working Days		
	1-125	126-190	191-End of Plant Establishment
230	230	150	150
300	300	230	150
460	460	300	230
600	600	460	300
910	910	600	460

Weeds within plant basins, including basin walls and ground cover, shall be controlled by hand pulling.  
 Weeds within mulched and ground cover areas and outside of plant basins shall be controlled by killing.  
 Weeds within median areas, pavement, curbs, sidewalk, and other surfaced areas shall be controlled by killing.  
 Vines shall be trained onto walls.

Except as specified in these special provisions, disposal of mowed material will not be required unless ordered by the Engineer. Disposal of mowed material, as directed by the Engineer, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

At the option of the Contractor, plants of a larger container size than those originally specified may be used for replacement plants during the first 125 working days of the plant establishment period.

After 125 working days of the plant establishment period have been completed, replacement of plants, except for ground cover plants, shall be No. 1 size for seedlings, pot and liner size plants; No. 5 size for No. 1 size plants; No. 15 size for No. 5 size plants; and other plant replacement plants shall be the same size as originally specified.

When ordered by the Engineer, one application of a preemergent pesticide conforming to the provisions in "Pesticides" of these special provisions, shall be applied between 40 working days and 50 working days prior to completion of the plant establishment period. This work will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

The final inspection shall be performed in conformance with the provisions in Section 5-1.13, "Final Inspection," of the Standard Specifications and shall be completed a minimum of 20 working days before the estimated completion of the contract.

**10-2.05 IRRIGATION SYSTEMS**

Irrigation systems shall be furnished and installed in conformance with the provisions in Section 20-5, "Irrigation Systems," of the Standard Specifications, except materials containing asbestos fibers shall not be used.

Method A pressure testing shall conform to the provisions in Section 20-5.03H(1), "Method A", of the Standard Specifications, except leaks that develop in the tested portion of the system shall be located and repaired after each test period when a drop of more than 35 kPa is indicated by the pressure gage. After the leaks have been repaired, the one hour pressure test shall be repeated and additional repairs made until the drop in pressure is 35 kPa or less.

Only pipeline trenches and excavation pits for supply lines being supplied from one water service point shall be open at one time. After pressure testing is complete, trenches and pits excavated for pipe supply lines, being supplied from one water service point, shall be backfilled prior to commencing excavations for pipe supply lines being supplied from another water service point.

Full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in furnishing and installing "vine pockets" and "flexible hose" connections complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer, shall be considered as included in "Irrigation Systems" and no additional compensation will be allowed therefor.

**PIPE AND CONDUIT ANCHORS**

Anchors used to attach galvanized steel pipe supply lines and sprinkler control conduits (electrical conduits) to the exterior surfaces of concrete structures and walls shall consist of metal straps and anchoring devices. Metal straps shall be made of steel and shall be fabricated to the details and dimensions shown on the plans. Anchoring devices shall consist of resin capsule anchor bolts or mechanical expansion stud anchors. Anchors shall conform to the provisions in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications.

When galvanized steel pipe supply lines and conduits are installed vertically on a structure for a distance of 0.6-m or more, but less than 3 m, an anchor shall be installed at the top and bottom of the pipe within 150 mm of the elbows. Vertical distances of 3 m or more shall have anchors installed at 3 m on centers unless otherwise shown on the plans. Anchors used to support vertically installed pipe and conduit shall be installed as shown on the plans.

Holes for anchorage devices shall conform to the following:

- A. Holes shall not be drilled closer than 150 mm to the edge of a concrete structure.
- B. Holes shall be drilled with drills approved by the Engineer.
- C. Holes shall be relocated if reinforcing steel is encountered. Abandoned holes shall be filled with portland cement concrete mortar conforming to the provisions in Section 51-1.135, "Mortar," of the Standard Specifications.
- D. Holes shall be drilled to a minimum depth of 8 times the diameter of the anchor bolt or stud anchor.

**VALVE BOXES**

Valve boxes shall conform to the provisions in Section 20-2.24, "Valve Boxes," of the Standard Specifications, except as otherwise provided herein.

Covers for concrete valve boxes shall be cast iron or steel. Cast iron and steel covers shall be hinged with brass hinge pins for valve boxes containing valves smaller than 50 mm.

Covers for plastic valve boxes shall be glass fiber reinforced plastic.

Valve boxes shall be identified on the top surface of the covers by labels containing the appropriate abbreviation for the irrigation facility contained in the valve box as shown on the plans. Valve boxes that contain remote control valves shall be identified by the appropriate letters and numbers (controller and station numbers). Labels for valve boxes shall conform to the provisions in Section 20-5.03F, "Valves and Valve Boxes," of the Standard Specifications.

Label material shall be polyurethane.

**BALL VALVES**

Ball valves shall be furnished and installed as shown on the plans and in conformance with these special provisions.

Ball valves shall be manufactured from Chlorinated Polyvinyl Chloride (CPVC) or polyvinyl chloride (PVC) and shall conform to the following:

Specification	Minimum Requirement
Non-shock cold water working pressure for 20 mm - 100 mm valves	1623 kPa
Non-shock cold water working pressure for 150 mm valves	1034 kPa
Seats	PTFE (Teflon)
O-Ring Seals	EPDM or Viton

Ball valves shall be of the same size as the pipeline which the valves serve, unless otherwise noted on the plans.

Ball valves shall be installed in a valve box.

**GATE VALVES**

Gate valves shall be as shown on the plans and in conformance with the provisions in Section 20-2.28, "Gate Valves," of the Standard Specifications and these special provisions.

Gate valves, 75 mm and larger in size, shall be furnished with a square nut and 3 long shank keys that will operate the valve.

Gate valves, 75 mm and larger in size, shall be flanged type gate valves. Pipe flanges used to connect plastic or metal pipe to gate valves shall be plastic or metal.

Gate valves shall have a solid bronze or brass wedge.

**ELECTRIC AUTOMATIC IRRIGATION COMPONENTS**

**Irrigation Controllers**

Irrigation controllers shall be single, solid-state independent controllers conforming to the following:

- A. Irrigation controllers shall be fully automatic and shall operate a complete 14-day or longer irrigation program.

- B. A switch or switches shall be provided on the face of the control panel that will turn the irrigation controller "on" or "off" and provide for automatic or manual operation. Manual operation shall allow cycle start at the desired station and shall allow activation of a single station.
- C. The watering time of each station shall be displayed on the face of the control panel.
- D. The irrigation controller and the low voltage output source shall be protected by fuses or circuit breakers.
- E. The irrigation controller mechanism, panel and circuit board shall be connected to the low voltage control and neutral conductors by means of plug and receptacle connectors located in the irrigation controller enclosure.
- F. Each station shall have a variable or incremental timing adjustment with a range of 12 hours to a minimum of one minute.
- G. Irrigation controllers shall be capable of a minimum of 2 program schedules.
- H. Irrigation controllers shall have an output that can energize a pump start circuit or a remote control valve (master).
- I. When 2 or more irrigation controllers operate the same electric remote control valve (master), an isolation relay shall be provided and installed per the controller manufacturer's instructions.
- J. Irrigation controllers shall be manufactured by the same company.
- K. Where direct burial conductors are to be connected to the terminals strip, the conductors shall be connected with the proper size open-end crimp-on wire terminals. No exposed wire shall extend beyond the crimp of the terminal and the wires shall be parallel on the terminal strip.

Attention is directed to the provisions in "Electric Service (Irrigation)" of these special provisions regarding electrical power for irrigation controllers and irrigation controller enclosure cabinets.

#### **Electric Remote Control Valves**

Electric remote control valves shall conform to the provisions in Section 20-2.23, "Control Valves," of the Standard Specifications and the following:

- A. Valves shall be glass filled nylon.
- B. Valves shall be straight pattern (side inlet) as shown on the plans.

#### **Pull Boxes**

Pull box installations shall conform to the provisions in Section 20-5.027I, "Conductors, Electrical Conduits and Pull Boxes," of the Standard Specifications.

#### **Conductors**

Low voltage, as used in this section "Conductors," shall mean 36 V or less.

Low voltage control and neutral conductors in pull boxes and valve boxes, at irrigation controller terminals, and at splices shall be marked as follows:

- A. Conductor terminations and splices shall be marked with adhesive backed paper markers or adhesive cloth wrap-around markers, with clear, heat-shrinkable sleeves sealed over the markers.
- B. Non-spliced conductors in pull boxes and valve boxes shall be marked with clip-on, "C" shaped, white extruded polyvinyl chloride sleeves. Marker sleeves shall have black, indented legends of uniform depth with transparent overlays over the legends and "chevron" cuts for alignment of 2 or more sleeves.

Markers for the control conductors shall be identified with the appropriate number or letter designations of irrigation controllers and station numbers. Markers for neutral conductors shall be identified with the appropriate number or letter designations of the irrigation controllers.

New control and neutral conductors that are to replace existing control and neutral conductors shall be the same size and color as the existing control and neutral conductors being connected to.

The color of low voltage neutral and control conductor insulation, except for the striped portions, shall be homogeneous throughout the entire thickness of the insulation.

Insulation for conductors may be UL listed polyethylene conforming to UL44 test standards with a minimum insulation thickness of 1.05 mm for wire sizes 10AWG and smaller.

Relief from maintenance and responsibility for electric automatic irrigation components will be granted in conformance with "Relief from Maintenance and Responsibility" of these special provisions. Before the Engineer grants relief from maintenance and responsibility, the functional test specified in Section 20-5.027J, "Testing," of the Standard Specifications shall be satisfactorily completed, and the manufacturer's written instructions shall be provided to the Engineer on the use and adjustment of the installed irrigation controllers.

## **IRRIGATION CONTROLLER ENCLOSURE CABINET**

Irrigation controller enclosure cabinets shall be constructed and equipment installed in the cabinets in conformance with the details shown on the plans, the provisions of Section 86-3.04A, "Cabinet Construction," of the Standard Specifications, and these special provisions.

Electric service shall be installed in accordance with "Electric Service (Irrigation)" of these special provisions.

Irrigation controller enclosure cabinets shall be provided with cross ventilation, roof ventilation or a combination of both. The ventilation shall not compromise the weather resistance properties of the irrigation controller enclosure cabinets and shall be fabricated by the manufacturer.

The anchorage arrangement shall be inside the cabinet as shown on the plans. Dimensions of the cabinet shall be suitable for the equipment to be installed as shown on the plans and specified in these special provisions.

Irrigation controller enclosure cabinet dimensions for a single irrigation controller shall be 890 mm (Height) x 584 mm (Width) x 280 mm (Depth).

Irrigation controller enclosure cabinet dimensions for double irrigation controller shall be 890 mm (Height) x 888 mm (Width) x 280 mm (Depth).

Irrigation controller enclosure cabinets shall be fabricated in conformance with the provisions in Section 86-3.04A, "Cabinet Construction," of the Standard Specifications.

Irrigation controller enclosure cabinets shall be fabricated of stainless steel.

Irrigation controller enclosure cabinet doors shall not be furnished with integral door locks. Irrigation controller enclosure cabinet door handles shall have provisions for padlocking in the latched position. Padlocks will be State-furnished as provided under "State-Furnished Materials" of these special provisions.

Mounting panels shall be fabricated of metal sheets with a minimum thickness of 1.8 mm for cold rolled steel or 3 mm for aluminum.

Inside of the doors shall have provisions for storage of the irrigation plans.

Solid-state automatic shut-off rain sensor units shall be installed for the irrigation controller enclosure cabinets. Rain sensor units shall automatically interrupt the master remote control valves when approximately 3 mm of rain has fallen. The irrigation system shall automatically be enabled again when the accumulated rainfall evaporates from the rain sensor unit collection cup. Rain sensor units shall be rated 24 V (ac) to 30 V (ac). Static charge protection shall be included to protect against lightning damage.

Equipment, except for field wiring, shall be installed in the cabinet in a shop prior to field installation.

## **IRRIGATION SYSTEMS FUNCTIONAL TEST**

Functional tests for the irrigation controllers and associated automatic irrigation systems shall conform to the provisions in Section 20-5.027J, "Testing," of the Standard Specifications and these special provisions.

Tests shall demonstrate to the Engineer, through one complete cycle of the irrigation controllers in the automatic mode, that the associated automatic components of the irrigation systems operate properly. If automatic components of the irrigation systems fail a functional test, these components shall be repaired at the Contractor's expense and the testing repeated until satisfactory operation is obtained.

Associated automatic components shall include, but not be limited to remote control valves.

Upon completion of work on an irrigation system, including correction of deficiencies and satisfactory functional tests for the systems involved, the plants to be planted in the area watered by the irrigation system may be planted provided the planting areas have been prepared as specified in these special provisions.

## **PIPE**

### **Steel Pipe**

Galvanized steel pipe supply lines shall be installed not less than 450 mm below finished grade, measured to the top of the pipe.

### **Plastic Pipe**

Plastic pipe supply lines shall be polyvinyl chloride (PVC) 1120 or 1220 pressure rated pipe with the minimum pressure rating (PR) shown on the plans.

Plastic pipe supply lines less than 100 mm in diameter shall have solvent cemented type joints. Primers shall be used on the solvent cemented type joints.

Plastic pipe supply lines (main) shall have a minimum cover of 0.45 m.

Plastic pipe supply lines downstream from the remote control valves for Type C sprinklers shall have a minimum cover of 150 mm.

A nonhardening joint compound shall be used in place of the pipe thread sealant tape conforming to the provisions in Section 20-5.03E, "Pipe," of the Standard Specifications. Joint compounds shall be applied in conformance with the manufacturer's recommendations.

Fittings for plastic pipe supply lines with a pressure rating (PR) of 315 shall be Schedule 80.

### **Recycled Water Supply Lines**

New and exposed recycled water supply lines shall be marked with a permanently affixed purple warning tape bearing the continuous wording "CAUTION RECYCLED WATER." The tape shall be wrapped around the supply lines in a manner that produces a uniform and smooth fit, free of irregularities.

At the Contractor's option, purple colored polyvinyl chloride (PVC) supply lines may be used for recycled water supply lines in place of standard PVC supply line with affixed purple warning tape. Purple colored PVC supply lines shall conform to the following:

- A. Pipe shall be made of PVC 1120 with the minimum pressure ratings (PR) shown on the plans.
- B. Pipe shall conform to the requirements in one of the following Standards: ASTM Designation: D 1785, ASTM Designation: D 3139 and ASTM Designation: D 2241 or ASTM Designation: D 2672.
- C. Pipe shall have permanent wording "CAUTION RECYCLED WATER" in 2 rows, approximately 180 degrees apart, in the longitudinal direction of the pipe. The warning message shall be repeated every 600 mm continuously along the pipe.

### **SPRINKLERS**

Sprinklers shall conform to the type, pattern, material, and operating characteristics listed in the "Sprinkler Schedule" shown on the plans.

Flow shutoff device on risers shall automatically and instantly stop the flow of water from a riser when the riser is broken on the downstream side of the device. The flow shutoff device shall be installed as recommended by the manufacturer of the device.

### **RECYCLED WATER WARNING SIGNS**

Recycled water warning signs shall be furnished and installed at the locations shown on the plans, as specified in these special provisions, and as directed by the Engineer. Recycled water warning signs shall be affixed to the above ground irrigation facilities that use or are associated with recycled water.

Warning sign decals shall be commercially available, and shall include the following information: "Recycled Water, Do Not Drink" and the "Do Not Drink" drinking glass graphic symbol. Warning sign decals shall be UV fade resistant, purple in color with black text, manufactured from a flexible, vinyl based or flexible, vinyl based with mylar product. Warning sign decals shall be all-weather, self-adhesive with peel-off backs.

Aluminum sign plates shall be 1.6 mm thick aluminum.

Warning tags shall be purple, doubled sided, manufactured from polyurethane, incorporating an integral neck attachment and attachment hole. The attachment hole shall be capable of withstanding 81 kilograms of pull out resistance. Tag lettering shall be hot-stamped in black and capable of withstanding outdoor usage. Warning tags shall include the following information: "Recycled Water, Do Not Drink" and the "Do Not Drink" drinking glass graphic symbol.

Warning signs on above ground irrigation facilities shall be placed in visible locations.

Warning sign decals shall be applied directly to clean smooth surfaces. The smooth surfaces shall be cleaned with alcohol, or an equivalent cleaner, before applying the decals.

Warning sign decals shall be applied directly to irrigation facilities with smooth surfaces or affixed to aluminum sign plates, which shall be attached to the various above ground irrigation facilities.

Warning sign decals or warning sign decals on aluminum sign plates shall be permanently affixed to backflow preventers, valve boxes, nozzle lines, concrete sprinkler protectors, sprinkler risers, irrigation controller enclosure cabinets, flow sensors, irrigation controller enclosures not in cabinets, gates, fences, and other irrigation facilities in conformance with the details shown on the plans.

Warning sign decals approximately 65 mm x 75 mm shall be permanently affixed to sprinkler risers.

A 100 mm x 100 mm warning sign decal shall be permanently affixed to irrigation controller enclosure cabinet doors, irrigation controller enclosures not in cabinets, backflow preventer assemblies, backflow preventer assembly enclosures, and valve box covers. Decals for valve box covers shall be affixed to aluminum sign plates and the plates affixed to the valve box cover with a silicon base adhesive. Decals for cabinets may be affixed to aluminum sign plates and the plates attached with commercial quality, cadmium plated, non-removable, self-tapping screws or commercial quality, cadmium plated bolts, nuts and washers.

A 300 mm x 300 mm warning sign decal on aluminum sign plate shall be permanently affixed to gates, fences and walls 1.5 m above finished grade. Sign plates for gates and fences shall be attached with "S" hooks and "C" clips or 2.03 mm (14-gage) galvanized steel wire as shown on the plans. Sign plates for concrete walls or other rough surfaces shall be affixed with a silicon base adhesive.

Warning tags approximately 50 mm x 50 mm shall be attached to the remote control valves, remote control valves (master), inside the valve box in accordance with the manufacturers recommendations.

Marking underground pipe for recycled water shall conform to the provisions in "Pipe" of these special provisions.

### **FINAL IRRIGATION SYSTEM CHECK**

A final check of existing and new irrigation facilities shall be performed not more than 40 working days and not less than 30 working days prior to acceptance of the contract.

The length of watering cycles using potable water measured by water meters for the final check of irrigation facilities will be determined by the Engineer.

Remote control valves connected to existing and new irrigation controllers shall be checked for automatic performance when the controllers are in automatic mode.

Unsatisfactory performance of irrigation facilities installed or modified by the Contractor shall be repaired and rechecked at the Contractor's expense until satisfactory performance is obtained, as determined by the Engineer.

Repair or replacement of existing irrigation facilities due to unsatisfactory performance shall conform to the provisions in "Existing Highway Irrigation Facilities" of these special provisions.

Nothing in this section "Final Irrigation System Check" shall relieve the Contractor of full responsibility for making good or repairing defective work or materials found before the formal written acceptance of the entire contract by the Director.

Full compensation for checking the irrigation systems prior to the acceptance of the contract shall be considered as included in the contract lump sum price paid for plant establishment work and no additional compensation will be allowed therefor.

## **SECTION 10-3. SIGNALS, LIGHTING AND ELECTRICAL SYSTEMS**

### **10-3.01 DESCRIPTION**

Signal and lighting, lighting (temporary), electric service (irrigation), Traffic signal interconnect and wireless data service equipment, sprinkler control conduit, maintaining existing traffic management system elements during construction, modify lighting and sign illumination, modify lighting, modify ramp metering system, modify signal and lighting, and modify communication system shall conform to the provisions in Section 86, "Signals, Lighting and Electrical Systems," of the Standard Specifications and these special provisions.

Lighting equipment is included in the following structures:

- A. Western Avenue (Bridge No. 53-1079S), KP 44.8
- B. Justine Avenue Pedestrian undercrossing (Bridge No. 53-1078), KP 44.5

Communication conduit is included in the following structures:

- A. Western Avenue (Bridge No. 53-1079S), KP 44.8

Sprinkler control conduit is included in the following structures:

- A. Western Avenue (Bridge No. 53-1079S), KP 44.8

Traffic signal work shall be performed at the following locations:

- A. Route 5 northbound on and off ramp at Flower Street
- B. Flower Street and Western Avenue

### **10-3.02 ABBREVIATIONS AND GLOSSARY**

The following abbreviations and glossary apply to these special provisions.

#### **ABBREVIATIONS**

&	And
#	Number
ADM	Add Drop Multiplexer
AFC	Automatic Frequency Control
AGC	Automatic Gain Control
AIS	Alarm Insertion Signal

AISI	American Iron and Steel Institute
AMI	Alternate Mark Inversion (a data transmission protocol)
APD	Avalanche Photo Diode
APL	Average Picture Level
APS	Automatic Protection Switching
AVC	Automatic Vehicle Classification system
AWG	American Wire Gauge
AWM	Appliance Wiring Material
B8ZS	Bit eight Zero Suppression (data transmission protocol)
BER	Bit Error Rate
BERTS	Bit Error Rate Test Set
BITS	Building Integrated Timing Supply
BNC	Bayonet Navy Connector
bps	Bits per second
BPV	Bipolar Violation
CCD	Charged-Coupled Device
CCK	Camera Control Keypad
CCR	Camera Control Receiver
CCT	Camera Control Transmitter
CCTV	Closed Circuit Television
CFR	Code of Federal Regulations
CIDH	Cast-In-Drilled-Hole
CMIP	Common Management Information Protocol
CMISE	Common Management Information Service Element
CMP	Configuration Management Plan
CMS	Changeable Message Sign
CODEC	Coder-Decoder
COMM	Communication
CPU	Central Processing Unit
CRT	Cathode Ray Tube
CTRL	Controller
CTS	Clear to Send
DACCS	Digital Access Cross Connect System
D4	4 <sup>th</sup> version of the D-signal format for time division multiplexers
dB	Decibel
dBm	Decibel referred to milliwatts
dBm	Decibel above reference noise
DCD	Data Carrier Detect
DCE	Data Communication Equipment
DCS	Digital Cross-connect System
DEMARC	Demarcation
DEMUX	Demultiplexer
DS-1	Digital Signal Level 1. Digital transmission rate of 1.544 megabits per second.
DS-3	Digital Signal Level 3. Digital transmission rate of 44.736 megabits per second.
DTE	Data Terminal Equipment
DWP	Department of Water and Power (Los Angeles)
EIA	Electronics Industries Alliance
EMT	Electrical Metallic Tubing
ESF	Extended Superframe Format
FCC	Federal Communications Commission
FDF	Fiber Distribution Frame
FDU	Fiber Distribution Unit
FRP	Fiberglass Reinforced Plastic
FSK	Frequency-Shift Keying
FXS	Foreign eXchange Subscriber
GUI	Graphical user interface

HVAC	Heating, Ventilation and Air Conditioning
Hz	Hertz
IRE	IRE is a SMPTE standard video reference level
ITU	International Telecommunications Union
JKFD	Jackfield
LA	Los Angeles
M13	Multiplexer, 28 DS-1 circuits to 1 DS-3 circuit
MHz	Megahertz
MUX	Multiplexer
NEMA	National Electrical Manufacturers Association
NHD	North Hollywood
nm	nanometer
NMS	Network Management System
NRZ	Non-Return to Zero
NTSC	National Television Standards Committee
OC	Optical Channel
OD	Outside Diameter
OEM	Original Equipment Manufacturer
OSHA	Occupational Safety and Health Administration
OTDR	Optical Time Domain Reflectometer
OW	Order Wire (multiple voice circuit)
P	Pair
P22	Pair 22 American wire gauge
PACBELL	Pacific Bell telephone company
p-p	Peak to peak
PC	Personal computer
PCMS	Pasadena City Municipal Services or Portable Changeable Message Sign
PDA	Power Distribution Assembly
PIN	Positive-Intrinsic-Negative
PR	Pair
PRBS	Pseudo-Random Bit Sequence
QRSS	Quasi-Random Signal Source
RUS	United States Rural Utilities Service
RETMA	Radio Electronics Television Manufacturers Association (former name of EIA)
RF	Radio Frequency
RG	Regulatory Guide
RMS	Ramp Metering System
rms	Root-Mean-Square
RTS	Request To Send
Rx	Receive
SF	Superframe Format (D4)
SM	Singlemode
SMFO	Singlemode Fiber Optic
SONET	Synchronous Optical Network
SSOVP	Solid-State Over Voltage Protector
SSPC	Steel Structures Painting Council
ST	Type of connector
TDM	Time Division Multiplexer
THHN	Heat resistant thermoplastic with nylon jacket conductor
THWN	Moisture and heat resistant thermoplastic with nylon jacket conductor
TIA	Telecommunications Industry Association
TL-1	Transaction Language 1
TLP	Transmission Level Point
TOSNET	Traffic Operational System Network
TMC	Traffic Management Center
TSG	Traffic Signal Generator

TSI	Time Slot Interchange
Tx	Transmit
UNC	Unified National Coarse
UNIX	Specific operating system found in real time applications
UV	Ultraviolet
V	Volt
V(ac)	Volt, alternating current
V(dc)	Volt, direct current
VID	Video Identification and date/time Display
VSK	Video Switch Keypad
VSM	Video Switch Matrix
VT-1.5	Virtual Tributary – Level 1.5 (1.728 Mb/s)
VT	Virtual Tributary
W	Watt
WFM	Waveform Monitor
WTO	Wire Transit Only
X.11, X.25	Specific protocol standards generated by the International Telecommunications Union (formerly CCITT)
XHHW	Moisture and heat resistant cross-linked synthetic polymer conductor

## GLOSSARY

**Breakout:** Cable "breakout" is produced by removing jackets just beyond the last tie-wrap point, exposing 0.9 m to 1.8 m of cable buffers, Aramid strength yarn and central fiberglass strength members and cutting Aramid yarn, central strength members and buffer tubes to expose individual glass fibers for splicing or connection to the appropriate device.

**Cable Storage Cabinet:** A cabinet for holding excess cable slack, allowing flexibility in equipment location and allowing cable pulling for re-splicing.

**Channel:** An information path between a discrete input and a discrete output. One single input to a multiplexer or output from a demultiplexer.

**Closed Circuit Television Assembly:** Camera, lens, environmental enclosure, and necessary connectors and cables.

**Connector:** A mechanical device providing the means for attaching to and decoupling from a transmitter, receiver or another fiber (such as on a patch panel).

**Connectorized:** A fiber with a connector affixed to it.

**Connector Module Housing (CMH):** A patch panel used in the FDF to terminate singlemode fibers with most common connector types. It may include a jumper storage shelf and a hinged door.

**Couplers:** Devices normally located within FDF's mounted in panels, that mate 2 fiber optic connectors to facilitate the transition of optical light signals from one connector into another. They may also be used unmounted, to join 3 simplex fiber runs. Couplers may also be referred to as adapters, feed-throughs and barrels.

**Fiber Distribution Frame (FDF):** A rack mounted system usually installed in the TMC that consists of a standard equipment rack, fiber routing guides, horizontal jumper troughs, fiber distribution units (FDU), connector module housings (CMH) and splice module housings (SMH).

FDF's serves as the "home" for passive fiber optic components from cable breakout, for connection by jumpers, to the electronics.

**Fiber Distribution Unit (FDU):** An enclosure containing a connector module housing (CMH) and a splice module housing enclosure.

**Field Cabinet:** A roadside cabinet housing controllers or communications equipment.

**Intermediate Distribution Frame Room (IDF room):** The room or area inside a hub or hut containing the FDF and other distribution hardware.

**Jumper:** A short fiber optic cable with connectors installed on both ends, typically used for connection within an FDF.

**Light Source:** A portable piece of fiber optic test equipment used to perform end-to-end attenuation testing in conjunction with a power meter containing a stabilized light source operating at the designed wavelength of the system under test.

**Link:** A passive section of the system, the ends of which are to be connected to active components. A link may include splices and couplers. For example, a video link may be from a F/O transmitter to a video Multiplexer (MUX).

**Main Distribution Frame Room (MDF room):** The room inside the TMC which contains the FDF and other distribution hardware.

**Mux/Demux:** Multiplexer/Demultiplexer.

**Optical Time Domain Reflectometer (OTDR):** Fiber optic test equipment used to measure total amount of power loss between 2 points and the corresponding distance. It provides a visual and printed display of the relative location of system components such as fiber sections, splices and connectors and as losses attributable to each component or defect in fiber.

**Patchcord:** A short jumper.

**Pigtail:** A short length of fiber optic cable with a connector installed on one end.

**Power Meter:** A portable fiber optic test equipment used to perform end-to-end attenuation testing in conjunction with a light source, containing a detector that is sensitive to light at the designed wavelength of the system under test. Its display indicates the amount of power injected by the light source that arrives at the receiving end of the link.

**Segment:** A section of F/O cable not connected to an active device which may or may not have splices per the design.

**Splice Closure:** An environmentally sealed container used to organize and protect splice trays, normally installed in a splice vault that allows splitting or routing of fiber cables from multiple locations.

**Splice Module Housing (SMH):** A housing for storage of splice trays, pigtails and short cable lengths.

**Splice Tray:** A container used to organize and protect spliced fibers.

**Splice Vault:** A vault used to house splice closures.

### 10-3.03 COST BREAK-DOWN

Cost break-downs shall conform to the provisions in Section 86-1.03, "Cost Break-Down," of the Standard Specifications and these special provisions.

The Engineer shall be furnished a cost break-down for each contract lump sum item of work described in this Section 10-3.

The cost break-down shall be submitted to the Engineer for approval within 15 days after the contract has been approved. The cost break-down shall be approved, in writing, by the Engineer before any partial payment for the items of electrical work will be made.

### 10-3.04 MAINTAINING EXISTING AND TEMPORARY ELECTRICAL SYSTEMS

Traffic signal system shutdowns shall be limited to periods between the hours of 9:00 a.m. and 3:00 p.m.

### 10-3.05 MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION

Traffic Management System (TMS) elements include, but are not limited to ramp metering (RM) system, communication system, traffic monitoring stations, video image vehicle detection system (VIVDS), microwave vehicle detection system (MVDS), loop detection system, changeable message sign (CMS) system, extinguishable message sign (EMS) system, highway advisory radio (HAR) system, closed circuit television (CCTV) camera system, roadway weather information system (RWIS), visibility sensor, and fiber optic system.

Existing TMS elements, including detection systems, identified on the plans and located within the project limits shall remain in place, and be protected from damage. If the construction activities require existing TMS elements to be nonoperational or off line, and if temporary or portable TMS elements are not shown on the plans, the Contractor shall provide for temporary or portable TMS elements. The Contractor shall receive the Engineer's approval on the type of temporary or portable TMS elements and installation method.

Before work is performed, the Engineer, the Contractor, and the Department's Traffic Operations Electrical representatives shall jointly conduct a pre-construction operational status check of all existing TMS elements and each element's communication status with the Traffic Management Center (TMC), including existing TMS elements that are not shown on the plans and elements that may not be impacted by the Contractor's activities. The Department's Traffic Operations Electrical representatives will certify the TMS elements' location and status, and provide a copy of the certified list of the existing TMS elements within the project limits to the Contractor. The status list will include the operational, defined as having full functionality, and the nonoperational components.

The Contractor shall obtain written approval from the Engineer, at least 72 hours before interrupting existing TMS elements' communication with the TMC that will result in the elements being nonoperational or off line. The Contractor shall notify the Engineer at least 72 hours before starting excavation activities.

Traffic monitoring stations and their associated communication systems which were verified to be operational during the pre-construction operational status check, shall remain operational on freeway/highway mainline at all times, except:

1. for a duration of up to 15 days on any continuous segment of the freeway/highway longer than 4.8 kilometers
2. for a duration of up to 60 days on any continuous segment of the freeway/highway shorter than 4.8 kilometers

If the construction activities require existing detection systems to be nonoperational or off line for a longer time period or the spacing between traffic monitoring stations is more than the specified criteria above, and temporary or portable detection operations are not shown on the plans, the Contractor shall provide provisions for temporary or portable detection operations.

The Contractor shall receive the Engineer's approval on the type of detection and installation before installing the temporary or portable detection.

If existing TMS elements shown on the plans or identified during the pre-construction operational status check, except traffic monitoring stations, are damaged or fail due to the Contractor's activity, where the elements are not fully functional, the Engineer shall be notified immediately. If the Contractor is notified by the Engineer that existing TMS elements have been damaged, have failed or are not fully functional due to the Contractor's activity, the damaged or failed TMS elements, excluding Structure-related elements, shall be repaired or replaced, at the Contractor's expense, within 24 hours. For a Structure-related elements, the Contractor shall install temporary or portable TMS elements within 24 hours. For nonstructure-related TMS elements, the Engineer may approve temporary or portable TMS elements for use during the construction activities.

If fiber optic cables are damaged due to the Contractor's activities, the Contractor shall install new fiber optic cables from an original splice point or termination to an original splice point or termination, unless otherwise authorized in writing by the Engineer. Fiber optic cable shall be spliced at the splice vaults if available. The amount of new fiber optic cable slack in splice vaults and the number of new fiber optic cable splices shall be equivalent to the amount of slack and number of splices existing before the damage or as directed by the Engineer. Fusion splicing will be required.

The Contractor shall demonstrate that repaired or replaced elements operate in a manner equal to or better than the replaced equipment or as directed by the Engineer. If the Contractor fails to perform required repairs or replacement work, as determined by the Engineer, the State may perform the repair or replacement work and the cost will be deducted from monies due to the Contractor.

A TMS element shall be considered nonoperational or off line for the duration of time that active communications with the TMC is disrupted, resulting in messages and commands not transmitted from or to the TMS element.

The Contractor shall provide provisions for replacing existing TMS elements within the project limits, including detection systems, that were not identified on the plans or during the pre-construction operational status check that became damaged due to Contractor's activities.

If the pre-construction operational status check identified existing TMS elements, then the Contractor, the Engineer, and the Department's Traffic Operations Electrical representatives shall jointly conduct a post construction operational status check of all existing TMS elements and each element's communication status with the TMC. The Department's Traffic Operations Electrical representatives will certify the TMS elements' status and provide a copy of the certified list of the existing TMS elements within the project limits to the Contractor. The status list will include the operational, defined as having full functionality, and the nonoperational components. TMS elements that cease to be functional between pre and post construction status checks shall be repaired at the Contractor's expense and as directed by the Engineer.

The Engineer will approve, in writing, the schedule for final replacement, the replacement methods and the replacement elements, including element types and installation methods before repair or replacement work is performed. The final TMS elements shall be new and of equal or better quality than the existing TMS elements.

## **PAYMENT**

The contract lump sum price paid for maintaining existing traffic management system elements during construction shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in maintaining existing traffic management system elements as shown on the plans, specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

If no electrical work exists on the project and no TMS elements are identified within the project limits, the pre-construction operational status check will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

Furnishing and installing temporary or portable TMS elements that are not shown on the plans, but are required when an existing TMS element becomes nonoperational or off line due to construction activities, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

Furnishing and installing temporary or portable TMS elements and replacing TMS elements that are not shown on the plans nor identified during the pre-construction operational status check and were damaged by construction activities will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

If the Contractor is required to submit provisions for the replacement of TMS elements that were not identified, the provisions will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

## **10-3.06 CAST-IN-DRILLED-HOLE CONCRETE PILE FOUNDATIONS**

### **GENERAL**

#### **Summary**

This work includes constructing cast-in-drilled-hole concrete pile foundations for traffic signal and lighting standards. Comply with Section 86-2.03, "Foundations," of the Standard Specifications and "Piling" of these special provisions.

## MATERIALS

Concrete must contain not less than 350 kilograms of cementitious material per cubic meter.

## CONSTRUCTION

For standards located in sidewalk areas, the pile foundation must be:

1. Placed to final sidewalk grade before the sidewalk is placed
2. Square for the top 100 mm

## PAYMENT

Payment for cast-in-drilled-hole concrete pile foundations shall conform to the provisions in Section 86-8, "Payment," of the Standard Specifications.

### 10-3.07 STANDARDS, STEEL PEDESTALS, AND POSTS

Standards, steel pedestals, and posts for traffic signal and lighting standards shall conform to the provisions in Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications, "Steel Structures" of these special provisions, and the following requirements.

Steel bolts not designated on the plans as high-strength (HS) or stainless steel shall be for general applications and shall conform to the requirements in ASTM Designation: A 307.

Where the plans refer to the side tenon detail at the end of the signal mast arm, the applicable tip tenon detail may be substituted.

The sign mounting hardware shall be installed at the locations shown on the plans.

Handhole reinforcement rings for standards, steel pedestals, and posts shall be continuous around the handholes.

Type 1 standards shall be assembled and set with the handhole on the downstream side of the pole in relation to traffic or as shown on the plans.

All ferrous metal parts of tubular structures shall be galvanized and shall not be painted.

### 10-3.08 CONDUIT

Conduit to be installed underground shall be Type 1 or Type 3 unless otherwise specified. Detector termination conduits shall be Type 1.

The conduit in a foundation and between a foundation and the nearest pull box shall be Type 1.

Conduit sizes shown on the plans and specified in the Standard Specifications and these special provisions are referenced to metallic type conduit. When rigid non-metallic conduit is required or allowed, the nominal equivalent industry size shall be used as shown in the following table:

Size Designation for Metallic Type Conduit	Equivalent Size for Rigid Non-metallic Conduit
21	20
27	25
41	40
53	50
63	65
78	75
103	100

When a standard coupling cannot be used for joining Type 1 conduit, a UL listed threaded union coupling conforming to the provisions in Section 86-2.05C, "Installation," of the Standard Specifications, or a concrete-tight split coupling, or concrete-tight set screw coupling shall be used.

When Type 3 conduit is placed in a trench (not in pavement or under portland cement concrete sidewalk), after the bedding material is placed and the conduit is installed, the trench shall be backfilled to not less than 100 mm above the conduit with minor concrete conforming to the provisions in Section 90-10, "Minor Concrete," of the Standard Specifications. The concrete shall contain not less than 250 kg of cementitious material per cubic meter. The remaining trench shall be backfilled to finished grade with backfill material.

Conduit runs shown on the plans to be located behind curbs may be installed in the street, within 0.9-m of, and parallel with the face of the curb, by the "Trenching in Pavement Method" in conformance with the provisions in Section 86-2.05C, "Installation," of the Standard Specifications. Pull boxes shall be located behind the curb or at the locations shown on the plans.

After conductors have been installed, the ends of conduits terminating in pull boxes, service equipment enclosures, and controller cabinets shall be sealed with an approved type of sealing compound.

At those locations where conduit is required to be installed under pavement and underground facilities designated as high priority subsurface installation under Govt Code § 4216 et seq. exist, conduit shall be placed by the "Trenching in Pavement Method" in conformance with the provisions in Section 86-2.05C, "Installation," of the Standard Specifications.

At the option of the Contractor, the final 0.6-m of conduit entering a pull box in a reinforced concrete structure may be Type 4.

### **COMMUNICATION CONDUIT**

Communication conduit shall conform to the details shown on the plans, the provisions in "Conduit" of these special provisions, and the following requirements.

Excavation and slurry cement backfill shall conform to Section 19-3, "Structure Excavation and Backfill," of the Standard Specifications. Slurry cement backfill shall reach initial set prior to placing reinforced concrete for approach slabs.

Conduit shall enter splice vaults and communication pull boxes through knockouts. Conduits entering ends of communication pull boxes shall be vertically and horizontally aligned with conduits at the opposite end of communication pull boxes. Conduit ends shall not extend beyond interior wall of splice vaults and communication pull boxes. Space around conduits through end walls of splice vaults and communication pull boxes shall be filled with minor concrete cement mortar conforming to the provisions in Section 51-1.135, "Mortar," of the Standard Specifications. Conduit bodies or communication pull boxes shall not be used in lieu of specified bends to change the direction of communication conduit runs, except where specified.

Bends shall not be placed in sections of conduit in excess of those indicated on the plans without the approval of the Engineer. The total degrees of bending in a section of conduit between splice vaults and communication pull boxes shall not exceed a total of 180 degrees, except where specified.

Changes in indicated conduit bends may be made to suit field conditions if the change reduces the degree of bend or increases the radius of bend. The angle of the bend shall not be decreased without the approval of the Engineer.

Minimum bending radius for Size 78 and Size 103 communication conduits shall be 915 mm and 1220 mm, respectively. Bends greater than 22 degrees shall be factory bends and bends greater than 45 degrees shall be Type 1 with necessary adapters.

Deflections of communication conduit shall not exceed 83.3 mm/m when avoiding obstructions. Conduit from typical trench sections shall not deflect by more than 83.3 mm/m from the alignment preceding or following communication pull boxes and splice vaults.

Where edge drains are in the path of conduit routing, the Contractor shall first locate edge drains, then install conduit maintaining a minimum depth of 600 mm. If an edge drain is damaged by the Contractor's work, repairs shall be at the Contractor's expense.

Conduit adjacent to overcrossings or bridge foundations shall be trenched and installed in shoulders as close as possible to the edge of traveled way so a minimum of 1.5 m from the outside face of footing or pile cap is maintained.

Communication conduits shall not terminate in power pull boxes.

### **SIZE 25 INNERDUCT**

Innerducts shall be installed to protect fiber optic cables. Separate innerducts shall be installed for each fiber optic cable along communication mainlines, unless otherwise shown on the plans,

Innerducts shall be 25 mm, smooth or ribbed high density polyethylene (HDPE) duct with the following characteristics:

- A. Inner diameter greater than or equal to 25 mm, nominal.
- B. Environmental stress crack resistance in excess of 2000 hours at -100°C, no failures.
- C. Cold impact resistance to -76°C not brittle until -100°C.
- D. Minimum tensile strength of 2670 N for finished product.
- E. Minimum crush strength of 2900 N.
- F. Coefficient of friction less than 0.4 unlubricated on nonmetallic conduit and with common polyethylene cable jackets.

Yellow shall be used for the 36SMFO and 72SMFO fiber optic cables used for video/data and contrasting colors approved by the Engineer for the 12SMFO for video distribution. Exteriors of innerducts shall be marked with sequential measurement markings each meter.

Innerduct must be installed using manufacturer's recommended practices using cable pulling lubricants recommended by the innerduct manufacturer and pull ropes conforming to the requirements in Section 86-2.05C, "Installation," of the Standard Specifications. If innerduct is installed with adjacent cables in the same conduit, innerducts and cables must be installed together in one operation. Innerducts must be installed in continuous runs between communication pull boxes and splice vaults without splices or joints.

Ends shall be smooth to prevent scraping of cables. Dynamometers shall be used to record installation tensions and tension limiting devices shall be used to prevent exceeding maximum pulling tensions during installation. Breakaway devices shall be used to limit pulling tensions. One device shall be placed in series with every element rated for less than maximum pulling tensions of that element. Innerducts shall not be stressed beyond the minimum-bending radius allowed by the innerduct or fiber optic cable manufacturer.

Tension shall be set to the manufacturer's maximum limit. Maximum pulling tension shall be recorded for each innerduct run.

Immediately prior to installing cables, innerducts shall be blown out with compressed air until all foreign material is removed. After cables have been installed, ends of innerducts shall be sealed with an approved type of sealing compound.

Full compensation for Size 25 innerducts shall be included in contract lump sum price paid for the items of work involved and no additional compensation will be allowed therefor.

### **10-3.09 PULL BOXES**

Grout shall not be placed in the bottom of pull boxes, except communication pull boxes.

Pull boxes shall have tamper proof pinhead bolts to secure the metal lid to the box. Tamper proof pinhead bolts shall be approved by the Engineer before ordering and installing.

No. 9 pull boxes shall have tamper proof pinhead bolts to secure the metal lid to the box.

The size and the length of the tamper bolts are similar to the hold down bolts shown on the plans.

The Contractor shall provide the Engineer with special tools, such as bits, drivers, or wrenches, required for installing and removing tamper resistant bolts.

Pull boxes proposed to be installed in soil, shall be buried 150 mm to 200 mm below grade, except for communications pull boxes and splice vaults that contain only fiber optics. Cover the pull box with plastic sheet (0.5 mm) before burying the pull box.

Plastic sheets, 0.5-mm thick, manufactured from high density polyethylene (HDPE) virgin compounds or polyvinyl chloride (PVC) virgin compounds, shall be installed over the tops of the pull box and surrounding concrete, as shown on the plans and as directed by the Engineer.

Full compensation for burying pull boxes and special tools are included in the contract lump sum price paid for the items of work involved and no additional compensation will be allowed therefor.

Full compensation for 0.5-mm plastic sheets is included in contract price paid for the items of work involved and no additional compensation will be allowed therefor.

### **10-3.10 ELECTRONIC MARKERS**

#### **GENERAL**

Electronic Marker (EM) and Electronic Marker Locator (EML) together make a provision to electronically mark and locate underground facilities. The circuits of the EM, when excited by the compatible EML operating at standard industry frequencies, produces a uniform radio frequency (RF) field in all directions. The RF signal is picked up by the EML for precise location of the EM. Maximum signal strength appears when the EML is vertically above the EM.

The field and the range of the EM must be reliable for use in any terrain.

Electronic Markers must be passive and contain no batteries.

#### **Passive Electronic Marker**

The EM when activated by the EML sends uniform RF field in all directions and the exact location of the EM is at the point where the signal strength is vertically maximum.

### **MATERIALS LIST AND DRAWINGS**

#### **Submittals**

The Contractor shall provide EM to mark underground facilities that can be located later with the help of an EML.

The Contractor shall provide one EM for every buried pull box.

#### **Training**

The Contractor must provide a copy of the training material to the Engineer for approval 15 days prior to the training. The content of the training shall include instruction on installing and locating the marker.

#### **Certificate of Compliance**

A Certificate of Compliance for EM shall be furnished to the Engineer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

## FUNCTIONAL REQUIREMENTS

The EM must not require any particular orientation when buried and there shall not be any need for the EM to be leveled in the ground. The internal component must be capable of self-leveling and automatic orientation to a position providing maximum signal strength to the EML. The EM must be of the kind that it is just tossed in the trench or excavation and covered up with normal backfill.

The EM must be light weight, with no hazardous chemicals.

The EM must not require external or internal source of power and must be energized solely by electromagnetic energy received from the interrogating EML.

The EM must comply with the following features:

<b>Specifications</b>	
Shape	Spherical or geometrical shape
Weight	1 kg (Maximum)
Diameter	15 cm (Maximum)
Color	Red for power and orange for communication
Frequency	Standard frequencies, compatible with EML devices
Range	Easily locatable up to six feet between EML and the EM
Detection offset	15 cm (Maximum)

The EM must conform to the following:

1. Housing should be leak tight, moisture resistant, pressure tested per industry standards applicable to buried enclosures, buried splices, and buried cables
2. Housing Material should be chemical resistant like high density polyethylene with no hazardous chemicals
3. Operating Temperature: -20 °C to +50 C
4. Storage Temperature: -20 °C to +70 C
5. Life: 15 years minimum

## WARRANTY

The Contractor shall provide a manufacturer's warranty for the EM including estimate of expected life of 15 years.

## PAYMENT

Full compensation for electronic markers shall be considered as included in the contract lump sum price paid for the items of work involved and no additional compensation will be allowed therefor.

The contract lump sum price paid for modify lighting and sign illumination and modify ramp metering system shall include full compensation for printing information on the project drawings for site mapping of pull boxes with electronic markers.

### 10-3.11 COMMUNICATION PULL BOXES

Communication pull boxes shall comply with Section 86-2.07, "Traffic Pull Boxes," of the Standard Specifications and these special provisions.

Communication pull box steel covers shall have "CALTRANS COMMUNICATION" markings.

Concrete placed around and under communication pull boxes shall contain a minimum of 325 kg of cement per cubic meter.

Steel covers shall be installed and kept bolted down.

Communication pull boxes shown on the plans in shoulders are shown for general location. The exact location shall be outside of paved shoulders and will be determined by the Engineer.

Additional communication pull boxes shall not be installed without the Engineer's written approval.

Full compensation for communication pull boxes is included in contract price paid for the items of work involved and no separate payment will be made therefor.

### 10-3.12 CONDUCTORS AND WIRING

Splices shall be insulated by "Method B".  
Signal Interconnect Cable (SIC) shall be the 6-pair type.

#### FIBER OPTIC CABLE

Fiber optic cable shall conform to the details shown on the plans and these special provisions.

##### Definitions:

The following definitions shall apply to fiber optics:

- A. Fan Out Termination - Permits branching of fibers contained in optical cables into individual cables and can be done at field locations, allowing cables to be connectorized or terminated per system requirements. A kit provides pullout protection for individual bare fibers to support termination. It provides 3 layers of protection consisting of a Teflon inner tube, a dielectric strength member, and an outer protective PVC jacket. Fan out terminations shall not be used for more than 6 fibers. Use of a patch panel would be appropriate.
- B. F/O - Fiber optic.
- C. FOOP - Fiber optic outside plant cable.
- D. Loose Tube Cable - Type of cable construction in which fibers are placed in buffer tubes to isolate them from outside forces (stress). A flooding compound or material is applied to the interstitial cable core to prevent water migration and penetration. This type of cable is primarily for outdoor applications.
- E. MMFO - Multimode Fiber Optic Cable.
- F. Splice - The permanent joining of 2 fiber ends using a fusion splicer.
- G. Tight Buffered, Non-Breakout Cable (Tight Buffer Cable) - Type of cable construction where glass fiber is tightly buffered (directly coated) with a protective thermoplastic coating to 900  $\mu\text{m}$  (compared to 250  $\mu\text{m}$  for loose tube fibers).

##### Fiber optic outside plant cable

Fiber optic outside plant cable (FOOP) shall be dielectric, nongel filled or water-blocking material, duct type, with loose buffer tubes. Optical fibers shall be contained within loose buffer tubes. Loose buffer tubes shall be stranded around a dielectric central member. Aramid yarn or fiberglass shall be used as a primary strength member, and a polyethylene outside jacket shall provide protection.

Fiber optic (F/O) cable shall be from the same manufacturer who is regularly engaged in the production of fiber optic cables.

Cables shall be compliant with 7 CFR 1755.900 (RUS Bulletin 1753F-601), "RUS Specification for Filled Fiber Optic Cables."

##### Fiber Characteristics

Optical fiber shall be glass and consist of a doped silica core surrounded by concentric silica cladding. Fibers in buffer tubes shall be usable fibers, and shall be sufficiently free of surface imperfections and occlusions to meet optical, mechanical, and environmental requirements of these specifications. Required fiber grade shall reflect the maximum individual fiber attenuation to guarantee required performance of fiber in cables.

Coating shall be dual layered, UV cured acrylate, mechanically or chemically strippable without damaging fibers.

Cable shall comply with optical and mechanical requirements over an operating temperature range of  $-40^{\circ}\text{C}$  to  $+70^{\circ}\text{C}$ . Cable shall be tested in accordance with EIA-455-3A (FOTP-3), "Procedure to Measure Temperature Cycling Effects on Optical Fiber, Optical Cable, and Other Passive Fiber Optic Components." Change in attenuation at extreme operational temperatures ( $-40^{\circ}\text{C}$  to  $+70^{\circ}\text{C}$ ) for singlemode fiber shall not be greater than 0.20 dB/km, with 80 percent of measured values no greater than 0.10 dB/km. Singlemode fiber measurement shall be made at 1550 nm.

Fibers within finished cables shall meet the following requirements:

Fiber Characteristics Table	
Parameters	Multimode
Type	Graded index
Core diameter	50 $\mu\text{m} \pm 2.0 \mu\text{m}$
Cladding diameter	125 $\mu\text{m} \pm 2.0 \mu\text{m}$
Core to Cladding Offset	< 3.0 $\mu\text{m}$
Coating Diameter	250 $\mu\text{m} \pm 10 \mu\text{m}$
Cladding Non-circularity defined as: [1-(min. cladding dia $\div$ max. cladding dia.)] x 100	< 2.0%
Proof/Tensile Test	345 MPa, min.
Attenuation: (-40°C to +70°C) @850 nm @1300 nm	< 2.5 dB/km < 1.0 dB/km
Attenuation at the Water Peak	N/A
Bandwidth:	
@ 850 nm	> 500 MHz x km
@1,300 nm	> 1000 MHz x km
Numerical Aperture (measured in Accordance with EIA-455-47)	0.20 $\pm$ 0.02

### Color Coding

In buffer tubes containing multiple fibers, length of fiber shall be distinguishable from others in the same tube by means of color-coding according to the following:

1. Blue (BL)	7. Red (RD)
2. Orange (OR)	8. Black (BK)
3. Green (GR)	9. Yellow (YL)
4. Brown (BR)	10. Violet (VL)
5. Slate (SL)	11. Rose (RS)
6. White (WT)	12. Aqua (AQ)

Buffer tubes containing fibers shall be color-coded with distinct and recognizable colors according to the table listed above for fibers.

Colors shall be in accordance with the Munsell color shades (ASTM D 1535-01) and shall meet EIA/TIA-598 "Color Coding of Fiber Optic Cables."

Color formulations shall be compatible with fiber coatings and buffer tube filling compounds, and be heat stable. Colors shall not fade or smear or be susceptible to migration and shall not affect transmission characteristics of optical fibers and shall not cause fibers to stick together.

### Cable Construction

Fiber optic cable shall consist of, but not limited to, the following components:

- A. Buffer tubes
- B. Central member
- C. Filler rods
- D. Stranding
- E. Core and cable flooding
- F. Tensile strength member
- G. Ripcord
- H. Outer jacket

### Buffer Tubes

Clearance shall be provided in loose buffer tubes between fibers and insides of tubes to allow for expansion without constraining fibers. Fibers shall be loose or suspended within tubes and shall not adhere to insides of buffer tubes. Buffer tubes shall contain a maximum of 12 fibers.

Loose buffer tubes shall be extruded from material having a coefficient of friction sufficiently low to allow free movement of fibers. Material shall be tough and abrasion resistant to provide mechanical and environmental protection of fibers and permit safe intentional "scoring" and breakout without damaging or degrading internal fibers.

Buffer tube filling compound shall be a homogeneous hydrocarbon-based gel with anti-oxidant additives used to prevent water intrusion and migration. Filling compound shall be non-toxic and dermatologically safe to exposed skin, chemically and mechanically compatible with cable components, non-nutritive to fungus, non-hygroscopic and electrically non-conductive. Filling compound shall be free from dirt and foreign matter and shall be readily removable with conventional nontoxic solvents.

Buffer tubes shall be stranded around a central member by a method, such as the reverse oscillation stranding process, that will prevent stress on fibers when the cable jacket is placed under strain.

### **Central Member**

The central member functions as an anti-buckling element and shall be a glass reinforced plastic rod with similar expansion and contraction characteristics as the optical fibers and buffer tubes. A symmetrical linear overcoat of polyethylene may be applied to central members to achieve optimum diameter to ensure proper spacing between buffer tubes during stranding.

### **Filler Rods**

Fillers may be included in cables to maintain symmetry of cable cross-sections. Filler rods shall be solid medium or high-density polyethylene. The diameter of filler rods shall be the same as the outer diameter of buffer tubes.

### **Stranding**

Completed buffer tubes shall be stranded around the overcoated central member using stranding methods, lay lengths and positioning so cables meet mechanical, environmental and performance specifications. A polyester binding shall be applied over stranded buffer tubes to hold them in place. Binders shall be applied with sufficient tension to secure buffer tubes to central members without crushing buffer tubes. Binders shall be non-hygroscopic, non-wicking (or rendered so by the flooding compound) and dielectric with low shrinkage.

### **Core and Cable Flooding**

Cable core interstices shall contain a water blocking material to prevent water ingress and migration. Water blocking material shall be a polyolefin based compound, which fills the cable core interstices, or an absorbent polymer, which fills voids and swells to block ingress of water. Flooding compound or material shall be homogeneous, non-hygroscopic, electrically non-conductive, non-nutritive to fungus, nontoxic, dermatologically safe, and compatible with other cable components.

### **Tensile Strength Member**

Tensile strength shall be provided by high tensile strength Aramid yarns or fiberglass helically stranded evenly around cable cores and shall not adhere to other cable components.

### **Ripcord**

Cables shall contain at least one ripcord under the jacket for easy sheath removal.

### **Outer Jacket**

Jackets shall be free of holes, splits, and blisters and shall be medium or high-density polyethylene (PE), or medium density cross-linked polyethylene with minimum nominal jacket thickness of  $1 \text{ mm} \pm 0.076 \text{ mm}$ . Jacketing material shall be applied directly over tensile strength members and water blocking materials and shall not adhere to Aramid strength materials. Polyethylene shall contain carbon black to provide ultraviolet light protection and shall not promote fungus growth.

Jackets or sheaths shall be marked with the manufacturer's name, the words "Optical Cable", the number of fibers, "MM" as applicable, year of manufacture, and sequential measurement markings every meter. Actual cable lengths shall be within  $-0/+1$  percent of length markings. Markings shall be a contrasting color to cable jackets. Heights of markings shall be  $2.5 \text{ mm} \pm 0.2 \text{ mm}$ .

### **General Cable Performance Specifications**

F/O cable shall withstand water penetration when tested with one meter static head or equivalent continuous pressure applied at one end of a one meter length of filled cable for one hour. No water shall leak through open cable ends. Testing shall be in accordance with EIA-455-82 (FOTP-82), "Fluid Penetration Test for Fluid-Blocked Fiber Optic Cable."

A representative sample of cable shall be tested in accordance with EIA/TIA-455-81 (FOTP-81), "Compound Flow (Drip) Test for Filled Fiber Optic Cable". No preconditioning period shall be conducted. Cables shall exhibit no flow (drip or leak) at 70°C as defined in the test method.

Crush resistance of finished F/O cables shall be 220 N/cm applied uniformly over the length of cables without showing evidence of cracking or splitting when tested in accordance with EIA-455-41 (FOTP-41), "Compressive Loading Resistance of Fiber Optic Cables". The average increase in attenuation for fibers shall be 0.10 dB at 1550 nm (singlemode) for a cable subjected to this load. Cables shall not exhibit measurable increase in attenuation after removal of load. Testing shall be in accordance with EIA-455-41 (FOTP-41), except that loads shall be applied at the rate of 3 mm to 20 mm per minute and maintained for 10 minutes.

Cables shall withstand 25 cycles of mechanical flexing at a rate of 30 ±1 cycles/minute. The average increase in attenuation for fibers shall be 0.20 dB at 1550 nm (singlemode) at the completion of testing. Outer cable jacket cracking or splitting observed under 10x magnification shall constitute failure. Testing shall be conducted in accordance with EIA-455-104 (FOTP-104), "Fiber Optic Cable Cyclic Flexing Test," with sheave diameters a maximum of 20 times the outside diameter of cables. Cables shall be tested in accordance with Test Conditions I and II of FOTP-104.

Cables shall withstand 20 impact cycles, with a total impact energy of 5.9 N•m. Impact testing shall be conducted in accordance with TIA/EIA-455-25B (FOTP-25) "Impact Testing of Fiber Optic Cables and Cable Assemblies." The average increase in attenuation for fibers shall be <0.20 dB at 1550 nm for singlemode fiber. Cables shall not exhibit evidence of cracking or splitting.

Finished cable shall withstand a tensile load of 2700 N without exhibiting an average increase in attenuation of greater than 0.40 dB (multimode). Testing shall be conducted in accordance with EIA-455-33 (FOTP-33), "Fiber Optic Cable Tensile Loading and Bending Test." Load shall be applied for 30 minutes in Test Condition II of the EIA-455-33 (FOTP-33) procedure.

### **Packaging and Shipping Requirements**

Documentation of compliance to specifications shall be provided to the Engineer prior to ordering materials.

Attention is directed to "Fiber Optic Testing," of these special provisions.

Completed cables shall be packaged for shipment on reels. Cables shall be wrapped in weather and temperature resistant covering. Ends of cables shall be sealed to prevent ingress of moisture.

Ends of cables shall be securely fastened to reels to prevent cables from coming loose during transit. Four meters of cable on ends of cables shall be accessible for testing.

Cable reels shall have durable, weatherproof labels or tags showing the manufacturer's name, cable type, the actual length of cable on reels, the Contractor's name, the contract number, and the reel number. A shipping record shall be included in a weatherproof envelope showing the above information, including the date of manufacture, cable characteristics (size, attenuation, bandwidth, etc.), factory test results, cable identification number and other pertinent information.

Minimum hub diameter of reels shall be at least 30 times the diameter of the cable. F/O cable shall be in one continuous length per reel with no factory splices in fibers. Reels shall be marked to indicate the direction reels should be rolled to prevent loosening of cables.

Installation procedures and technical support information shall be furnished at the time of delivery.

## **LABELING**

### **General**

The Contractor shall label fiber optic cabling in a permanent consistent manner. Tags shall be of a material designed for long term permanent labeling of fiber optic cables. Metal tags shall be stainless steel with embossed lettering. Non-metal label materials shall be approved by the Engineer and marked with permanent ink. Labels shall be affixed to cables per the manufacturer's recommendations and shall not be affixed in a manner, which will cause damage to fibers. Handwritten labels will not be allowed.

### **Label Identification**

#### **Labeling of Cables**

Labeling of multimode fiber optic cables shall conform to the following unique identification code elements:

UNIQUE IDENTIFICATION CODE ELEMENTS For Backbone, Distribution or Drop Cables		
DESCRIPTION	CODE	NUMBER OF CHARACTERS
District	District number	2
Cable Type	Fiber: M: Multimode	1
Cable fiber Count	Number of fibers (Examples: 144 fibers)	3
Route Number	Hwy. Rte (Example: 005)	3
Begin Function	M: CCTV Camera;  S: Splice Vault	1
Begin Function Number	Unique ID number corresponds to Begin Function (Example: H02 [Hub 02])	2
End Function	M: CCTV Camera;  S: Splice Vault	1
End Function Number	Unique ID number corresponds to Begin Function (Example: H03 [Hub 03])	2
Unique Identifier	XX: If 2 or more cables of the same count are in the same run	2
TOTAL		17

Cables shall display one unique identification, regardless of where the cable is viewed. The begin function and end function correspond to end points of cables. The order of the begin and end functions follow the hierarchy listed below, where the lowest number corresponding to the begin/end function is listed first.

List of Hierarchy										
1	2	3	4	5	6	7	8	9	10	11
TMC	HUB	Video Node (VN)	Data Node (DN)	Cable Node	CCTV Camera	CMS	Traffic Signal	Ramp Meter	Traffic Monitoring/ Count Station	Splice Vault

A cable between the TMC and a HUB will have the TMC listed as the start function and the HUB as the end function. Between a CMS and a Splice Vault, the start function will be listed as the CMS, and so on. If a cable is connected between HUBs, the lowest number, will be listed as the start function.

A cable labeled 07S060010H02H0302 would contain the following information:

District	Mode	# of fibers	Route	Begin	End	Unique ID
07	S	060	010	H02	H03	02

Example: 07S060010H02H0302

This cable is located in District 7, identified as a singlemode fiber optic cable containing 60 fibers, installed along highway Route 10, beginning in Hub 2, and ending in Hub 3, with unique ID of number 2. The implication for the unique ID is that there may be another 60 fiber optic cable between those hubs. This is an example for a backbone cable.

### Labeling Jumpers and Pigtails

Labeling jumpers and pigtails shall conform to the following unique identification code elements:

UNIQUE IDENTIFICATION CODE ELEMENTS for JUMPERS (active component to FDU) and PIGTAILS (to connector # on patch panel)		
DESCRIPTION	CODE	NUMBER OF CHARACTERS
Hub Identifier	Hub, TMC , VN or DN ID Numbers or Alphanumeric or both	2
From (Source) Device	MU: Multiplexer FD: FDU (Fiber Distribution Unit) RP: Repeater	2
From (Source) Device Identifier	Numbers or Alphanumeric or both	2
Transmitter or Receiver	T or R	1
To (Destination) Device	MU: Multiplexer FD: FDU (Fiber Distribution Unit) RP: Repeater	2
To (Destination) Device Identifier	Numbers or Alphanumeric or both	2
Connector Identifier	Connector ID	2
TOTAL		13

A pigtail labeled 01MU01TFD0203 would contain the following information:

Hub	Multiplexer	Transmitting to	To Patch Panel Position (Connector)
01	MU01	TFD02	03

Example: 01MU01TFD0203.

This pigtail is located in Hub 1, from multiplexer 01, transmitting to FDU 02 to patch panel position (connector) 03.

### Label Placement

Label placement shall be as following:

- A. Cables - Cables shall be labeled with the unique identification code element method at terminations, even if no connections or splices are made, and at splice vault entrances and exits.
- B. Cable to Cable Splices - Cable jackets entering splice closures shall be labeled in accordance with the identification method.
- C. Cable to Fiber Distribution Units - Cable jackets shall be labeled at entries to FDU's in accordance with the unique identification code element method. Fibers shall be labeled with Fiber IDs and pigtails shall be labeled at connectors with Fiber IDs. FDU's shall be labeled with Cable IDs on faces of FDU's. If multiple cables are connected to FDU's, each block of connectors relating to individual cables shall be identified by a single label with Cable IDs. Individual connections shall be marked on the face of FDU's in the designated area with Fiber IDs.
- D. Fiber - Fiber labels shall be placed next to connectors of individual fibers.
- E. Patch Panels - Cable jackets shall be labeled at entries to Patch Panels in accordance with the unique identification code element method. Fibers shall be labeled with Fiber IDs and pigtails shall be labeled at connectors with Fiber IDs. Patch panels shall be labeled with Cable IDs on faces of Panels. If multiple cables are connected to Patch Panels, each block of connectors relating to individual cables shall be identified by a single label with the Cable ID. Individual connections shall be marked on faces of Panels in the designated area with Fiber IDs.
- F. Jumpers - Equipment to FDU jumpers shall be labeled as to equipment type connected and shall be labeled at both ends. FDU to FDU jumpers shall be labeled at each end in accordance with the unique identification code element method.
- G. Pigtails - Pigtails shall be labeled at the connector in accordance with the unique identification code element method described elsewhere in these special provisions.
- H. Copper Cable Labels - Twisted-pair communications cables shall be labeled in accordance with the unique identification code element method.

### CABLE INSTALLATION

Cable installation shall be in conformance with the procedures specified by the cable manufacturer. The Contractor shall submit the manufacturer's recommended procedures for pulling fiber optic cable at least 20 working days prior to installing cable. Mechanical aids may be used provided that a tension measuring device, and break-away swivel are placed in tension

to the end of cables. Tension in cables shall not exceed 2225 N or the manufacturer's recommended pulling tension, whichever is less.

During cable installation, the bend radius shall be a minimum of 20 times the outside diameter. Cable grips for installing fiber optic cables shall have a ball bearing swivel to prevent cables from twisting during installation.

F/O cable shall be installed using a cable pulling lubricant recommended by the F/O cable manufacturer and a pull rope conforming to Section 86-2.05, "Conduit," of Standard Specifications. Personnel shall be stationed at splice vaults and pull boxes through which cables are pulled to lubricate and prevent kinking or other damage.

F/O cable shall be installed without splices except where allowed on the plans and shall be limited to one cable splice every 6 km if splice locations are not shown on the plans. Midspan access splices or FDU terminations shall involve fibers being spliced as shown on the plans. Cable splices shall be located in splice closures installed in splice vaults. A minimum of 20 m of slack shall be provided for F/O cables at splice vaults. Slack shall be divided equally on each side of F/O splice closures.

## **SPLICING**

Field splices shall be done in splice vaults, cabinets, or in splice trays housed in splice closures. Splices in cabinets shall be done in splice trays.

Fiber splices shall be fusion type unless otherwise specified. Mean splice loss shall not exceed 0.07 dB per splice and shall be obtained by measuring loss through splices in both directions and averaging the resultant values.

Splices shall be protected with a metal reinforced thermal shrink sleeve.

The mid-span access method shall be used to access individual fibers in cables for splicing to other cables. Cable manufacturers recommended procedures and approved tools shall be used for mid-span access. Only fibers to be spliced shall be cut. Buffer tubes and individual fibers not being used in mid-span access shall not be modified or damaged.

Individual fibers shall be looped one full turn within splice trays to avoid micro bending. A 45 mm minimum bend radius shall be maintained during installation and after final assembly in optical fiber splice trays. Bare fibers shall be individually restrained in splice trays. Optical fibers in buffer tubes and placement of bare optical fibers in splice trays shall not produce tensile force on optical fibers.

The Contractor will be allowed to splice a total of 30 percent of fibers to repair damage done during mid-span access splicing without penalty. The Engineer will assess a fine of \$300.00 for each additional and unplanned splice. A single fiber may not have more than 3 unplanned splices. If a fiber requires more than 3 unplanned splices, the entire length of F/O cable shall be replaced at the Contractor's expense.

## **PASSIVE CABLE ASSEMBLIES AND COMPONENTS**

F/O cable assemblies and components shall be compatible components, manufactured by a company regularly engaged in the production of material for the fiber optic industry. Components or assemblies shall be best quality, non-corroding, with a minimum design life of 20 years.

The cable assemblies and components manufacturer shall be ISO 9001 registered.

## **FIBER OPTIC CABLE TERMINATIONS**

### **General**

Cables shall continue within conduit to the designated cable termination point. Components shall be the size and type required for the specified fiber. Fiber optic cable terminations may take place in several locations such as splice vault, and CCTV camera location.

### **Cable Termination**

When applicable, moisture-blocking gel shall be removed from exposed buffer tubes and fibers. The transition from the buffer tube to the bundle of jacketed fibers shall be treated by an accepted procedure for sleeve tubing, shrink tube and silicone blocking of the transition to prevent future gel leak. Manufacturer directions shall be followed to ensure gel will not flow from ends of buffer tubes throughout the specified temperature range. Individual fibers shall be stripped and prepared for splicing.

Factory terminated pigtails shall be spliced and placed in splice trays.

### **Fiber Optic Cable Assemblies and Pigtails**

Cables for cable assemblies shall be made of fiber meeting the performance requirements of these special provisions for the F/O cable being connected.

Pigtails shall be of simplex (one fiber) construction, in 900- $\mu$ m tight buffer form, surrounded by Aramid yarn for strength, with a PVC jacket with manufacturer's identification information, and a nominal outer jacket diameter of 3 mm.

Singlemode simplex cable jackets shall be yellow. Pigtails shall be factory terminated and tested and at least one meter in length.

Jumpers may be of simplex or duplex design. Duplex jumpers shall be duplex round cable construction and shall not have zipcord (Siamese) construction. Jumpers shall be at least 2 m in length.

Outer jackets of duplex jumpers shall be yellow. The 2 inner simplex jackets shall be contrasting colors to provide easy visual identification for polarity.

Connectors shall be ceramic ferrule ST type for MMFO. Indoor ST connector body housings shall be nickel-plated zinc or glass reinforced polymer construction. Outdoor ST connector body housings shall be glass reinforced polymer.

Associated couplers shall be the same material as connector housings.

F/O connectors shall be the 2.5 mm connector ferrule type with Zirconia Ceramic material with a PC (Physical Contact) pre-radiused tip.

ST connector operating temperature range shall be  $-40^{\circ}\text{C}$  to  $+70^{\circ}\text{C}$ . Insertion loss shall not exceed 0.4 dB for singlemode and return reflection loss on singlemode connectors shall be at least -35 dB. Connection durability shall be less than a 0.2 dB change per 500 mating cycles per EIA-455-21A (FOTP-21). Terminations shall provide a minimum 222 N pull out strength. Factory test results shall be documented and submitted to the Engineer prior to installing connectors. Singlemode connectors shall have a yellow color on the body and boot.

Field terminations shall be limited to splicing of adjoining cable ends and cables to ST pigtails.

Connectors shall be factory-installed and tested.

Unmated connectors shall have protective caps installed.

## **FIBER OPTIC TESTING**

### **General**

Testing shall include tests on elements of passive fiber optic components at the factory, after delivery to the project site but prior to installation, and after installation but prior to connection to other portions of the systems. The Contractor shall provide personnel, equipment, instrumentation, and materials necessary to perform testing. The Engineer shall be notified 2 working days prior to field tests. Notification shall include the exact location or portion of system to be tested.

Documentation of test results shall be provided to the Engineer within 2 working days after testing.

A minimum of 15 working days prior to arrival of cable at the site, the Contractor shall provide detailed test procedures for field testing for the Engineer's review and approval. Procedures shall include tests involved and how tests are to be conducted. Test procedures shall include the model, manufacturer, configuration, calibration, and alignment procedures for proposed test equipment.

### **Factory Testing**

Documentation of compliance with fiber specifications as listed in the Fiber Characteristics Table shall be supplied by the original equipment manufacturer. Before shipment, but while on shipping reels, 100 percent of fibers shall be tested for attenuation. Copies of the results shall be maintained on file by the manufacturer with a file identification number for a minimum of 7 years, attached to cable reels in waterproof pouches, and submitted to the Contractor and to the Engineer.

### **Arrival On Site**

Cables and reels shall be physically inspected on delivery and 100 percent of fibers shall be attenuation tested to confirm that cable meets requirements. Failure of a fiber in the cable shall be cause for rejection of the entire reel. Test results shall be recorded, dated, compared and filed with copies accompanying shipping reels in weatherproof envelopes. Attenuation deviations from shipping records of greater than 5 percent shall be brought to the attention of the Engineer. Cables shall not be installed until completion of testing and written approval of the Engineer. Copies of traces and test results shall be submitted to the Engineer. If test results are unsatisfactory, the reel of F/O cable shall be considered unacceptable and records corresponding to that reel of cable shall be marked accordingly. Unsatisfactory reels of cable shall be replaced with new reels of cable at the Contractor's expense. New reels of cable shall be tested to demonstrate acceptability. Copies of test results shall be submitted to the Engineer.

### **After Cable Installation**

Index matching gel will not be allowed in connectors during testing. After fiber optic cable has been pulled, but before breakout and termination, 100 percent of fibers shall be tested with an OTDR for attenuation. Test results shall be recorded, dated, compared, and filed with previous copies of these tests. Copies of traces and test results shall be submitted to the Engineer. If OTDR test results are unsatisfactory, the F/O cable segment of cable will be rejected. Unsatisfactory segments of cable shall be replaced with new segments, without additional splices, at the Contractor's expense. New cable segments shall be tested to demonstrate acceptability. Copies of test results shall be submitted to the Engineer.

## **System Cable Verification At Completion**

### **Power Meter and Light Source**

At the conclusion of OTDR testing, 100 percent of fiber links shall be tested end-to-end with a power meter and light source, in accordance with EIA Optical Test Procedure 171 and in the same wavelengths specified for OTDR tests. Tests shall be conducted in one direction. As shown in Appendix A, the Insertion Loss (IC) shall be calculated. Test results shall be recorded, compared, and filed with the other recordings of the same links. Test results shall be submitted to the Engineer. These values shall be recorded in the Cable Verification Worksheet in Appendix A.

### **OTDR Testing**

After passive cabling systems have been installed and are ready for activation, 100 percent of fibers shall be tested with OTDR for attenuation at wavelengths of 1310 nm and 1550 nm. OTDR testing shall be performed in both directions (bi-directional) on fibers. Test results shall be generated from software of test equipment, recorded, dated, compared and filed with previous copies. A hard copy printout and an electronic copy on a CD of traces and test results shall be submitted to the Engineer. The average of the 2 losses shall be calculated and recorded in the Cable Verification Worksheet in Appendix A. The OTDR shall be capable of recording and displaying anomalies of at least 0.02 dB. Connector losses shall be displayed on OTDR traces.

### **Cable Verification Worksheet**

The Cable Verification Worksheet shown in Appendix A shall be completed for links in fiber optic systems using data gathered during cable verification. Completed worksheets shall be included as part of system documentation.

### **Test Failures**

If link loss, measured from the power meter and light source, exceeds the calculated link loss or the actual location of fiber ends does not agree with the expected location of fiber ends, fiber optic links will not be accepted. Unsatisfactory segments of cable or splices shall be replaced with new segments of cables or splices at the Contractor's expense. OTDR testing, power meter and light source testing, and Cable Verification Worksheet shall be completed for repaired links to determine acceptability. Copies of test results shall be submitted to the Engineer. Removal and replacement of segments of cable shall be considered as removal and replacement of a single contiguous length of cable connecting 2 splices and 2 connectors. Removal of a section containing a failure will not be allowed.

### **Passive Component Package Testing and Documentation**

Components in the passive component package (pigtailed, jumpers, couplers, and splice trays) shall be from a manufacturer who is ISO 9001 registered.

Pigtails or jumpers shall be tested for insertion attenuation loss using optical power meters and light sources. Singlemode terminations shall be tested for return reflection loss. Values shall meet loss requirements specified and shall be recorded on tags attached to pigtails or jumpers.

After an assembly is complete, the manufacturer shall visually verify that tagging of loss values is complete. The manufacturer shall conduct an "end-to-end" optical power meter/light source test from pigtail ends to end of terminating points assuring continuity and overall attenuation loss values are acceptable.

### **Fiber Optic System Performance Margin Design Criteria**

Installed system performance margin shall be at least 6 dB for links. If the design system performance margin is less than 6 dB, the Engineer shall be notified of the Contractor's plan to meet this requirement.

### **Active Component Testing**

Transmitters and receivers shall be tested with power meters and light sources to record transmitter average output power (dBm) and receiver sensitivity (dBm). Values shall be recorded in the Fiber System Performance Margin Calculations Worksheet in Appendix B, section C, number 6.

### **PAYMENT**

Full compensation for fiber optic cable shall be considered as included in the contract lump sum price paid for modify communication system and no separate payment will be made therefor.

# APPENDIX A

## Cable Verification Worksheet

*End-to-End Attenuation (Power Meter and Light Source) Testing  
and OTDR Testing*

Contract No. \_\_\_\_\_ Contractor: \_\_\_\_\_

Operator: \_\_\_\_\_ Date: \_\_\_\_\_

Link Number: \_\_\_\_\_ Fiber Number: \_\_\_\_\_

Test Wavelength (Circle one):    1310 nm            1550 nm

Expected Location of fiber ends: End 1: \_\_\_\_\_ End 2: \_\_\_\_\_

### Power Meter and Light Source Test Results:

Power In: \_\_\_\_\_ 1A

Output Power: \_\_\_\_\_ dBm 1B

Insertion Loss [1A - 1B]: \_\_\_\_\_ 1C

\_\_\_\_\_ dBm  
\_\_\_\_\_ dB

### OTDR Test Results:

Forward Loss: \_\_\_\_\_ dB 2A

Reverse Loss: \_\_\_\_\_ dB 2B

Average Loss [(2A + 2B)/2]: \_\_\_\_\_ dB 2C

-----  
To Be Completed by Caltrans:  
Resident Engineer's Signature: \_\_\_\_\_  
Cable Link Accepted: \_\_\_\_\_

**APPENDIX B**  
**Fiber System Performance Margin Calculations Worksheet**

**A. Calculate the Passive Cable Attenuation**

1. Calculate Fiber Loss at Operating Wavelength: _____ nm	Cable Distance (times) Individual Fiber Loss (equal) @ 1310 nm (0.4 dB/km) @ 1550 nm (0.3 dB/km)	_____ km x _____ dB/km =
<b>Total Fiber Loss:</b>		_____ dB

**B. Calculate the Total Connector/Splice Loss**

2. Calculate Connectors/couplers Loss: (exclude Tx and Rx connectors)	Individual Connector Loss (times) Number of Connector Pairs (equal) <b>Total Connector Loss:</b>	0.4 dB x _____ = _____ dB
3. Calculate Splice Loss:	Individual Splice Loss (times) Number of Splices (equal) <b>Total Splice Loss:</b>	0.1 dB x _____ = _____ dB
4. Calculate Other Components Loss:	<b>Total Components:</b>	_____ dB
5. Calculate Total Losses:	Total Connector Loss (plus) Total Splice Loss (plus) Total Components (equal)	+ dB + dB + dB =
<b>Total Connector/Splice Loss:</b>		_____ dB

### C. Calculate Active Component Link Loss Budget

System Wavelength:		_____ nm
Fiber Type:		singlemode
Average Transmitter Output (Launch Power):		_____ dBm
Receiver MAX Sensitivity (10 <sup>9</sup> BER) (minus)		_____ dBm
Receiver MIN Sensitivity (equal)		- _____ dBm =
<b>Receiver Dynamic Range:</b>		_____ dB
6. Calculate Active Component Link Loss Budget:	Average Transmitter Output (Launch Power) (minus) Receiver MAX Sensitivity (equal)	_____ dBm - _____ dBm =
<b>Active Component Link Loss Budget:</b>		_____ dB

### D. Verify Performance

7. Calculate System Performance Margin to Verify Adequate Power:	Active Component Link Loss	_____ dB
	Budget [C] (minus)	
	Passive Cable Attenuation [A] (minus)	- _____ dB
	Total Connector/Splice Lost [B] (equal)	- _____ dB =
<b>System Performance Margin:</b>		_____ dB

#### TWISTED PAIR CABLE

Twisted pair cable shall be supplied and installed in the configurations shown on the plans, shall conform to the provisions in Section 86-2, "Materials and Installation," of the Standard Specifications, and as specified in these special provisions and the following requirements.

Twisted pair cables shall meet the requirements of Rural Utility Service (RUS) Bulletin 1753F-205 (PE-39) and the following:

- A. Conductors shall consist of a solid wire of plain annealed high conductivity copper, smoothly drawn, circular in section, uniform in quality, have a conductor size number 22 AWG and shall be insulated with colored, high density polyethylene jackets.
- B. Insulated conductors shall be uniformly twisted to form pairs with non-hygroscopic dielectric tape shall be wrapped around insulated pairs. The twisted length of pairs shall vary to minimize cross talk. A laid up core shall be wrapped with aluminum tape and bonded with an overlap to provide 100 percent shielding. Black, high molecular weight, medium or low density, polyethylene jackets shall be extruded over shields. Filling compound materials used in cables shall not support galvanic action.

Cables shall be color-coded using the RUS standard color code.

#### PACKING

Cables shall be supplied on reels. Reels shall have the following information labeled:

- A. Customer.

- B. Customer order number.
- C. Reel number.
- D. Destination.
- E. Ship date.
- F. Manufactured date.
- G. Manufacturer's name.
- H. Cable code.
- I. Length of cable.
- J. Manufacturers test Data

Replace damaged cable before, during or after installation at the your expense.

## **INSTALLATION**

Install cables in conduits. Conduit ends must have rough edges smoothed to prevent scraping cables. Apply manufacturer's recommended lubricant to cables to reduce friction between cables and conduits. Protect exposed cable ends from moisture ingress.

Do not stress the cable beyond the manufacturer's minimum bending radius. Dynamometers shall be used to measure installation tension and tension-limiting devices shall be used to prevent exceeding the manufacturer's maximum pulling tension specification. Maximum measured pulling tension must be recorded for each run of cable.

Provide a single loop of cable with a minimum length of 3.0 m at pull boxes. Train the cables to splice vault walls, tied with nylon ties and labeled with vinyl marking bands.

Provide a minimum 12-m slack for unspliced cables at splice vaults.

Seal conduit entrances at pull boxes, vaults and cabinets with conduit sealing compound following installation of cables in conduits to prevent ingress of moisture, foreign materials and rodents. Maintain the pair count and RUS color code during splicing. Identify cables and pair counts with cable markers. Field splices shall be made in twisted pair splice closures located in pull boxes. Secure cables in place within pull boxes and cabinets.

## **TESTING**

Testing shall be in conformance with the provisions of Section 86-2.14, "Testing," of the Standard Specifications and these special provisions.

Test cables at the factory to ensure the cable complies with the manufacturer's specifications. Record reel numbers from which cables came, identification of pairs measured, and results of continuity and insulation tests. Half of twisted wire pairs in cable reels shall be tested for insulation breakdown and continuity prior to installation in conduits.

Measure and record the continuity and insulation resistance of cable pairs in individual cable length after installation and submit the results to the Engineer.

System integration testing shall be performed to ensure that twisted-pair cables perform as specified when used in operation with installed equipment. Attention is directed to "System Testing" of these special provisions.

Full compensation for twisted pair cables is included in the contract lump sum price paid for items of work involved and no additional compensation will be allowed therefor.

### **10-3.13 BONDING AND GROUNDING**

Bonding and grounding shall conform to the provisions in Section 86-2.10, "Bonding and Grounding," of the Standard Specifications and these special provisions.

Bonding jumpers in standards with handholes and traffic pull box lid covers shall be attached by a UL listed lug using 4.5-mm diameter or larger brass or bronze bolts and shall run to the conduit or bonding wire in the adjacent pull box. The grounding jumper shall be visible after the standard has been installed and the mortar pad and cap have been placed on the foundation.

Standards without handholes shall have bonding accomplished by jumpers attached to UL listed ground clamps on each anchor bolt.

For slip base standards or slip base inserts, bonding shall be accomplished by jumpers attached to UL listed ground clamps on each anchor bolt, or a UL listed lug attached to the bottom slip base plate with a 4.5-mm diameter or larger brass or bronze bolt.

Equipment bonding and grounding conductors are required in conduits, except when the conduits contain only combinations of loop lead-in cable, fiber optic cable, or signal interconnect cable. A No. 8 minimum, bare copper wire shall run continuously in circuits. The bonding wire size shall be increased to match the circuit breaker size in conformance with the Code, or shall be as shown on the plans. Conduits to be installed for future conductors, may omit the copper wire.

Bonding of metallic conduits in metal pull boxes shall be by means of bonding bushings and bonding jumpers connected to the bonding wire running in the conduit system.

**10-3.14 SERVICE**

Continuous welding of exterior seams in service equipment enclosures is not required.

Circuit breakers shall be the cable-in/cable-out type, mounted on non-energized clips. All circuit breakers shall be mounted vertically with the up position of the handle being the "ON" position.

Each service shall be provided with up to 2 main circuit breakers which shall disconnect ungrounded service entrance conductors. Where the "Main" circuit breaker consists of 2 circuit breakers as shown on the plans or required in the special provisions, each of the circuit breakers shall have a minimum interrupting capacity of 10 000 A, rms.

**ELECTRIC SERVICE (IRRIGATION)**

Electric service (irrigation) shall be from the service points to the irrigation controllers (IC) and to the spaces provided in the irrigation controller enclosure cabinets (CEC) for irrigation controllers as shown on the plans.

Irrigation Controller (IC) B\_ & D : Electric service (irrigation) shall be a metered 120/240 V(ac), single-phase service in a Type III service equipment enclosure.

Service disconnects in service equipment enclosures shall be 1-pole, 20-A circuit breaker.

Nameplate inscriptions shall be as follows:

ITEMS	INSCRIPTION
Metering Equipment Enclosure	IC_B & D
Service Disconnect	IC Irrigation

The inscription on other nameplates shall be the identifying letter designation used on the plans and in these special provisions, or shall be as directed by the Engineer.

Full compensation for electric service (irrigation) is included in the contract lump sum price paid for modify lighting and sign illumination and no additional compensation will be allowed therefor.

**10-3.15 NUMBERING ELECTRICAL EQUIPMENT**

Self-adhesive retroreflective numbers and edge sealer shall be Contractor-furnished.

The numbers and edge sealer shall be placed on the equipment where designated by the Engineer.

Where new numbers are to be placed on existing or relocated equipment, the existing numbers shall be removed.

Retroreflective numbers shall be applied to a clean surface. Only the edges of the numbers shall be treated with edge sealer.

Five-digit, self-adhesive equipment numbers shall be placed for all electroliers, soffit lighting, sign lighting, and service pedestals. On service pedestals, the numbers shall be placed on the front door. On electroliers, the numbers shall be placed 3 m from the base of electrolier as shown on the plans and as directed by the Engineer.

Adhesive numbers for all locations except wood poles shall be white retroreflective adhesive sheeting, 76 mm in width, with 76 mm, Black Series D letters and numbers. The letters and numbers may be screened on to the retroreflective sheeting or may be die cut and adhesively attached. The labels for each location may be individual characters applied or a continuous strip applied. Retroreflective sheeting, numbers and letters shall comply with the respective specifications in the Department of Transportation publication, "Specifications for Aluminum Reflective Sheeting Signs".

Full compensation for retroreflective numbers and edge sealers is included in the contract lump sum price paid for modify lighting and sign illumination and no additional compensation will be allowed therefor.

**10-3.16 STATE-FURNISHED CONTROLLER ASSEMBLIES**

The Model 170E and 2070 controller assemblies, excluding anchor bolts, will be State-furnished as provided under "Materials" of these special provisions.

The Contractor shall construct each controller cabinet foundation as shown on the plans for Model 332 and 334 cabinets (including furnishing and installing anchor bolts), shall install the controller cabinet on the foundation, and shall make field wiring connections to the terminal blocks in the controller cabinet.

A listing of field conductor terminations, in each State-furnished controller cabinet, will be furnished free of charge to the Contractor at the site of the work.

State forces will maintain controller assemblies. The Contractor's responsibility for controller assemblies shall be limited to conforming to the provisions in Section 6-1.02, "State-Furnished Materials," of the Standard Specifications.

## **10-3.17 TRAFFIC SIGNAL INTERCONNECT AND WIRELESS DATA SERVICE EQUIPMENT**

### **GENERAL**

Contractor shall provide equipment for traffic signal interconnect and wireless data service equipment. Equipment includes, but not limited to, the list of submittals in these special provisions.

### **SUBMITTALS**

The Contractor shall install the following equipment for the traffic signal interconnect equipment as shown on the plans:

1. Model 400B modem
2. C2P modem interconnect harness

The Contractor shall install the following equipment for the wireless data service equipment as shown on the plans:.

1. Wireless modem device
2. Wireless modem AC adaptor
3. Wireless modem antenna
4. Wireless modem serial cable
5. Wireless modem mounting hardware
6. Wireless modem software tool
7. GPS Time Source Device
8. Cords and cables
9. Equipment Manuals

Submit list of equipment and manufacturer's technical specifications within 30 working days to the Engineer for approval before purchasing equipment. The Contractor shall receive submittal approval from the Engineer before ordering equipment.

Submit 5 copies of installation and test plan within 30 working days to the Engineer for approval.

Deliver equipment for testing and telephone service connection to CTNET Office at California Department of Transportation, Office of Intelligent Transportation Systems, CTNET Traffic Signals Branch, Mail Stop 15, 100 South Main Street – Suite 100, Los Angeles, CA 90012.

The Contractor shall receive approval from the Engineer before installing the equipment.

Present test results that include a copy of the results for all the tests conducted.

Present system schematic drawings and identify type of equipment at each location and the function of all equipment. The drawings shall also show how the system is interconnected.

### **CONSTRUCTION**

Equipment shall conform to rules and regulations of the Federal Communications Commission (FCC) and to the provisions in Section 86, "Signals, Lighting and Electrical Systems," of the Standard Specifications and these special provisions.

Arrange to have a licensed technician, qualified to install, work and test the equipment, present at the time the equipment is turned on.

Prototype equipment is not acceptable. Equipment shall be off the shelf, of current standard production units manufactured by original equipment manufacturer, and shall have been in production for a minimum of 6 months. Rebuilt, modified, or reconditioned equipment is not allowed.

Install State-furnished equipment listed in these special provisions under MATERIALS. Model 2070-6B modems shall be installed in slot A2 of Model 2070 controllers.

All Contractor furnished equipment shall work with the existing CTNET and traffic signal software and without existing software modification.

Notify the Engineer at least 3 working days prior to equipment installation.

Follow the manufacturer's recommendations and install equipment as specified in these special provisions at the location shown on the plans or as directed by the Engineer. Model 400B and Model 2070-6B modems shall be installed and connected to terminal block TB0 using port C2S in controller and C2P modem interconnect harness. Wireless modem device shall be mounted and connected to port C20S of Model 170E controller used as signal system master and connected to TNC connector of wireless modem antenna. GPS time source device shall be mounted and connected to port C40S of Model 170E controller used as signal system master and connected to BNC connector of wireless modem antenna. Wireless modem antenna shall be mounted and connected to GPS time source device and wireless modem device. Wireless modem AC

adaptor shall be connected to equipment outlet, not controller outlet, and to wireless modem device. Equipment installation shall not affect the controller cabinet door normal operation.

Equipment furnished and installed shall comply with TEES March 12, 2009 and the following:

1. Model 400B modem shall comply with Chapter 2-Section 3 or later TEES, and shall support 9600 baud rate communications with Model 2070-6B modems. Install modem in modem slot 1 of Model 170E controllers.
2. C2P modem interconnect harness: Before installing the harness, the Contractor shall identify and label terminals with a color code compliant with TEES. Connect the C2P modem interconnect harness to the controller's C2S port and to the Model 332 controller cabinet terminal block TB-0 terminals A1 through A4. Harness shall comply with the following:

TB-0 Terminal Block Connector	TB-0 terminal Block SIC Color	Local Controller			Master Controller		
		C2S Port Function	C2S Port Pin	TEES 2009 Color Code	C2S Port Function	C2S Port pin	TEES 2009 Color Code
A1	White	Audio IN	A	White	--	--	
A2	Blue	Audio IN	B	Black	--	--	
A3	White	Audio OUT	C	Red	--	--	
A4	Orange	Audio OUT	E	Green	--	--	--
A1	White	--	--	--	Audio OUT	C	Red
A2	Blue	--	--	--	Audio OUT	E	Green
A3	White	--	--	--	Audio IN	A	White
A4	Orange	--	--	--	Audio IN	B	Black

3. Wireless modem device: Wireless modem device shall be rugged, have a 5 year memory battery back up, Subscriber Identity Module (SIM) Card slot, have dedicated light emitting diodes (LEDs) for status of network registration and functionality, support over-the-air remote configuration and programmable firmware updates, and shall reduce radio frequency (RF) transmit output power when near a base station. Wireless modem device shall support TCP and UDP packet assembly/disassembly (PAD) of serial data frames and its operation shall be transparent to existing CTNET and traffic signal software communications without requiring software modification. The wireless modem device shall be circuit switched data capable, security configuration setting to limit access by IP address, and TCP point to point communications with the existing CTNET CommServer. Mount the wireless modem device using wireless modem mounting hardware and the status LEDs on the front panel shall face upward. The wireless modem device shall be compatible with the existing wireless data service provider used for other traffic signals, and shall support modem to modem communications with other wireless modem devices in use. Wireless modem device shall comply with the following:

Wireless modem device:	
Electrical Requirement	Input Voltage: From 9 V(dc) to 28 V(dc)
	Input Current: From 20 mA to 450 mA
	Maximum Idle/Transmit/Receive Load requirements: 414 mA at 12 V(dc)
	Transmit Power: 1.0 W at 1900 MHz, and 0.8 W at 850 MHz
Network/Interface	Serial Interface: EIA-232, from 300 bps to 115,200 bps Serial Port: DCE DB-9 receptacle
	Ethernet Interface: 10 Mbps 10-BASET and 100 Mbps 100-BASET, Ethernet: RJ-45 jack receptacle
	USB Interface: version 2.0, USB: Type B connector
	I/O Interface: 4 Digital Inputs, 3 Analog Inputs, and 2 Outputs, I/O Ports: multiple pin connector
	Application Interfaces: TCP/IP, UDP/IP, Hypertext Transfer Protocol (HTTP), Telecommunications Network (Telnet), Short Message Service (SMS).
	Network: Dual Band 1900/850 MHz HSUPA with Fallback to HSDPA, UMTS, GSM EDGE, and GPRS (MS-12)
	Power: multiple pin connector
RF Requirement	Transmit Frequency Bands: From 1850 MHz to 1910 MHz, and from 824 MHz to 849 MHz
	Receiver Frequency Bands: From 1930 MHz to 1990 MHz and from 869 MHz to 894 MHz
	Receiver Sensitivity: -107 dBm typical (2.439 percent BER)
	RF Antenna Connector: 50 ohm TNC receptacle, or 50 ohm SMA receptacle with SMA to TNC low loss adapter
GPS Requirement	GPS Reporting Protocols: National Marine Electronic Association (NMEA)
	Receiver Frequency: 1.57542 GHz
	Satellite Tracking: Up to 8 simultaneously
	GPS Connector: 50 ohm SMA receptacle
Environmental Requirement	Operating Temperature: -30 °C to +70 °C
	Humidity: From 5 percent to - 95 percent non-condensing
Mechanical Requirement	Maximum Device Size: 330 mm perimeter Integrated mounting including either 4 keyhole screw mounts or mounting bracket.

4. Wireless modem AC adaptor: adaptor shall be UL Listed Class 2 power unit, Support a 120 V(ac) at 60 Hz input, Have a power connector plug that connects to and fits the power receptacle in the wireless modem device, and Provide a 12 V(dc) at 800 mA output
5. Wireless modem antenna shall be black, tri-band and tri-mode cellular/PCS radio (all carriers) with Global Positioning System (GPS), have a low profile design with integrated ground plane for outdoor surface mount on most surfaces including fiberglass and metallic surfaces, and be a weatherproof polycarbonate radome. Before antenna is permanently installed, conduct signal strength measurements and submit to the Engineer a copy of the signal strength measurements report for approval, verification and selection of the antenna to be installed. After approval, install the wireless modem, and connect the it to the antennas and measure the radio signal strength in dBm with the cabinet doors and panels closed and verify that the radio signal exceeds the requirements or -90 dBm. The Contractor shall replace the antenna if it does not comply with the signal strength requirements. The Contractor may use a serial cable, a laptop computer, and the wireless modem software tool to measure the signal strength. The Contractor shall seal cabinet after installing antenna. The installation of the wireless modem antenna shall comply with the manufacturer's recommendations

:

6. Conduct signal strength measurements after installation and submit a copy of the report. The Contractor shall replace the antenna if it does not comply with the signal strength requirements and the signal strength measurements do not exceed the wireless modem device receiver sensitivity. Wireless modem antenna shall comply with the following:

Radio Electrical Requirement	Maximum Power Input: 10 W or more
	RF Nominal Input Impedance: 50 Ohm GPS Output Impedance: 50 Ohm
RF Requirement	PCS Frequency Range: From 1850 MHz to 1990 MHz
	Cellular Frequency Range: From 824 MHz to 894 MHz
	Minimum Gain: Unity
	Radiation Pattern: Omni Directional
	Center frequency: 1575.42 MHz
	Gain: 26 dB with 5 dBi antenna gain, Noise Figure: 2.0 dB maximum
	Bandwidth: 2 MHz minimum, VSWR: 2:1 maximum
Environmental Requirement	Operating Temperature: -30°C to +70°C
	Humidity: From 5 percent to - 95 percent non-condensing
Mechanical Requirement	Maximum Height: 31 mm, Maximum Diameter: 127 mm
	Radio Cable and Connector: 4.57 meters RG-58 with TNC Plug Connector
	GPS Cable and Connector: 4.57 meters RG-174 cable with BNC Plug Connector
	Bolt Mount including mounting hardware, locknut, and sealing gasket.

7. Wireless modem serial cable: shall be 4 twisted pair No. 24 AWG stranded tinned copper with polyethylene insulation, color coded, low capacitance computer communications (CM) cable for use in EIA RS-232 applications, and comply with UL-1581 test requirements. The core shall be covered with an overall aluminum-polyester foil tape for 100 percent shield coverage, and with an outer chrome PVC jacket. The cable shall have stranded tinned copper drain wire, have an operating temperature range of -30 degrees C to +80 degrees C and its nominal impedance shall be 100 ohm. The serial cable shall be 3 meters in length, shall have a C2 male connector with 6 pins to connect to Model 170E and 2070L controllers, shall have a DB-9M connector to connect to a modem device, shall not establish contact between modem and controller chassis and shall use the wiring shown in the table below:

C2 Connector		Wiring	Modem (DCE) RS-232 Signal	DB-9M	Color Code
DTE RS-232 Signal	Pin			Pin	Color
RD	L	Connected	RD	2	White/Blue Stripe
TD	K	Connected	TD	3	Blue/White Stripe
RTS	J	Connected	RTS	7	White/Orange Stripe
CTS	M	Connected	CTS	8	Orange/White Stripe
DC GND	N	Connected	Signal GND	5	White/Green Stripe
DCD	H	Connected	DCD	1	Green/White Stripe
		Jumpered to DSR	DTR	4	White/Brown Stripe
		Jumpered to DTR	DSR	6	Brown/White Stripe

8. Wireless modem mounting hardware shall include 4 self-tapping screws and washers that match the keyhole screw mounts or mounting bracket of the wireless modem device. The mounting hardware shall secure in place the

wireless modem device to the mounting plate under terminal block TB0 of the controller cabinet. Mounting screws shall not touch the cabinet walls.

9. Wireless modem software tool include user’s manual, multiple site license, and software tools on compact discs at no additional cost. The wireless software tool shall access wireless modem devices in the field from the CTNET Office. The wireless modem software tool shall support local and remote configuration, firmware upgrades, diagnostics, monitoring of signal level at receiver, and reset of the wireless modem device. The user’s manual shall describe the function of all configuration parameters accessed by the wireless modem software, describe default values, and provide valid range or values for all configuration settings.
10. GPS Time Source Device shall have a LED (light Emitting Diode) for indication of power, GPS unsynchronized, and GPS synchronized status. The device shall have a maximum drift of 0.3 seconds per day when the GPS signal is lost, shall have a rechargeable super capacitor for back-up power of the real time clock and memory for up to 24 hours during power outages. Terminate antenna’s cable on a BNC plug and connect it to GPS time source device. Device shall include an industrial grade cable with a DB-9 plug to connect to it and a C2 plug to connect to a Model 170E controller for serial data communications and power, and mounting hardware including self tapping screws and washers. GPS time source device shall be secured in place with mounting hardware to the mounting plate under terminal block TB0 of the controller cabinet and its status LEDs shall face upward. Mounting screws shall not touch the cabinet walls. Device shall comply with the following:

Electrical Requirement	DB-9 pin 9 Input Voltage: +5 VDC regulated, DB-9 pin 9 Input Current: 200 mA GPS Connector: 50 Ohm BNC receptacle
RF Requirement	DB-9 pin 8 Pulse per Second Output: TTL Signal Accuracy +/- 1 microsecond Serial Interface: EIA-232, from 300 bps to 19,200 bps Serial Interface Time Source: Data Accuracy +/- 1 milliseconds
	Factory Settings: Baud Rate (9600 bps), Time Zone (Pacific Time Zone), New Line Character (Carriage Return), Hour Format (12 Hour), Daylight Savings Time (Enabled)
	Receiver Frequency: 1.57542 GHz
	Serial Port: DCE DB-9 receptacle. Serial port shall: A. process Universal Time Base (UTB) set and query commands B. set commands: set baud rate (SB), set daylight savings time (SD), set time format (SM), set new line character (SN), and set time zone (So) C. query commands: get date and day of year (QD), get time (QT), and get date, time, status, and day of the week (QC)
	Includes DB-9 receptacle pin 9 for power from Model 170E or Model 2070 Traffic Controller C2 receptacles
GPS Requirement	Satellite Tracking: Up to 8 simultaneously
Environmental Requirement	Operating Temperature: -30 °C to +80 °C
Mechanical Requirement	Maximum combined length, width, and height: 305 mm, Two mounting flanges with 2 keyhole screw mounts

11. Cords and cables: use Cable ties, wire mounting devices, non-metallic cable strain relief, and fixed diameter clamps in the controller cabinet and equipment rack. Use wire management brackets every 600 mm at the cabinets to route cable. Cables and wire management system components shall avoid physical interference between cables and adjacent equipment, allow equipment to be removed from cabinets without physical interference and keep terminal blocks clearly visible
12. Equipment Manuals: Manuals shall provide all of the information necessary to operate, maintain, and repair all of the equipment installed by the Contractor. Manuals shall include Master Item Index that describes the purpose of each manual and brief description to the directory. It shall also reference equipment manuals as required for additional and support material. It shall contain an overall description of the system and associated equipment and cables with illustrative block diagrams. This section shall identify all equipment and cables in the system stating the exact module and option number that are employed in the system. Manufacturer contact information, technical data specification, parts lists, part description, and settings for every type of equipment or cable shall be provided. Clearly describe any modification done on the equipment. Manuals shall include fault diagnostic and repair

procedures to permit the location and correction of faults to the level of each replaceable module. The manual shall include procedures for preventative maintenance in order to maintain the performance parameters of the system, equipment and cables within the requirements of the specifications.

Furnish metal filler plates to cover any unused channel slots or card slots for Rack mounted equipment and card cage assemblies.

## **TESTING**

After notification from the Engineer or 30 days after delivery; the Contractor shall pick up equipment and test results from the CTNET office.

Replace equipment that fails testing and telephone service connection within 7 days of notification from the Engineer. Resubmit technical specifications and replace non compliant equipment with equipment from another manufacturer within 10 days of notification from the Engineer.

The Contractor shall test the equipment after installation in the presence of the Engineer. The Contractor shall verify that the AB3418 and AB3418E status request messages sent by the field master controller are received by the local controllers, that AB3418 and AB3418E status response messages sent by local controllers are received by the field master controller, and that AB3418 and AB3418E status response messages are received by an existing CTNET computer at the Los Angeles Regional TMC or CTNET Office.

Equipment testing shall comply with the testing requirements specified in "System Testing" of these special provisions.

### **System Testing**

System testing shall include test plan, pre-installation testing, acceptance testing, and final acceptance as specified on these special provisions.

### **Test Plan**

Develop and submit 5 copies of an installation and test plan within 30 working days to the Engineer for approval. Plan shall detail method of installation and testing for equipment and the associated schedule of activities, based on these special provisions, project plans, the manufacturer's recommended test procedures, and industry standard practices.

### **Pre-installation Testing**

Test all components prior to installation in the presence of the Engineer.

Perform a physical inspection and inspect all equipment for quality of workmanship free of manufacturing defects and provide documentation to prove delivery of equipment.

### **Acceptance Testing**

The acceptance testing shall comply with the approved test plan. The acceptance testing shall include conducting acceptance tests and subsequent retests, and documentation of the test results.

Perform functional tests of complete system functions to demonstrate that equipment satisfy the functional requirements of the specifications. The connectivity of each communication link shall be demonstrated including all links from local controllers to field masters, all communication links from field masters to communication devices, and all communication links from field master controllers to the Los Angeles Regional TMC or CTNET Office.

Document all functional test results. Submit documentation for review and approval to the Engineer, no later than 2 weeks after completion of the acceptance tests and incorporate all comments made during the approval stage

If any aspect of the functional tests is determined by the Engineer to have failed, cease all acceptance testing and determine the cause of the failure and make repairs to the satisfaction of the Engineer. Acceptance testing shall, at the discretion of the Engineer, be repeated from the start of functional tests. The Contractor is responsible for delay caused by replacement of non-compliant equipment.

### **Final Acceptance**

Final acceptance will not occur until the Contractor complies with the following conditions:

- A. All testing has been completed and the Engineer has approved the results.
- B. Equipment manuals have been approved and submitted to the Engineer.
- C. All connections that were changed to perform tests were restored and tested.

## **PAYMENT**

The contract lump sum price paid for traffic signal interconnect and wireless data service equipment includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals, arranging for a qualified technician employed by the various communication equipment manufacturers or their representatives and for doing all the work involved in installing equipment, complete in place, including analysis, set-up of the system, calibration of the equipment performance, verification of equipment accuracy, testing, and re-testing of failed units, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer and no additional compensation will be allowed therefor.

Full compensation for traffic signal interconnect and wireless data service equipment is included in the contract lump sum price paid for modify signal and lighting and no additional compensation will be allowed therefor.

### **10-3.18 VEHICLE SIGNAL FACES AND SIGNAL HEADS**

Type SV-1-T mountings with 5 sections and SV-2-TD mountings shall be bolted to the standard through the upper pipe fitting in the same manner shown for bolting the terminal compartment.

### **10-3.19 LIGHT EMITTING DIODE SIGNAL MODULE**

#### **GENERAL**

##### **Summary**

This work includes installing LED signal module. Comply with Section 86, "Signals, Lighting and Electrical Systems," of the Standard Specifications.

Location of LED signal module is shown on the plans. The Engineer will approve exact location.

Use LED signal module as the light source for the following traffic signal faces:

1. 300-mm section
2. 200-mm section
3. 300-mm arrow section
4. 300-mm programmed visibility (PV) section

##### **Submittals**

Before shipping LED signal modules to job site, submit the following to the Transportation Laboratory:

1. Delivery form including district number, EA, and contact information
2. List containing all LED signal module serial numbers anticipated for use
3. LED signal modules

##### **Quality Control and Assurance**

Module must be one listed on the Pre-Qualified Products List for LED traffic signals at:

[http://www.dot.ca.gov/hq/esc/approved\\_products\\_list](http://www.dot.ca.gov/hq/esc/approved_products_list)

The State will test LED signal module shipments as specified in ANSI/ASQ Z1.4.. Testing will be completed within 30 days of delivery to the Transportation Laboratory. LED signal modules tested or submitted for testing must be representative of typical production units. LED and circular LED signal modules will be tested as specified in California Test 604. Arrow, U-turn, and bicycle LED signal modules will be tested as specified in California Test 3001. All parameters of the specification may be tested on the modules. LEDs must be spread evenly across the module. LED arrow indication must provide the minimum initial luminous intensity listed. Measurements will be performed at the rated operating voltage of 120 V(ac).

Delays resulting from submittal of non-compliant materials do not relieve you from executing the contract within the allotted time. Non-compliant materials will be rejected. You must resubmit new LED for retesting and pick up the failed units within 7 days of notification. You must provide new LED signal modules and allow a minimum of 30 days for the retest. You must pay for all shipping and handling costs related to testing and retesting. Delays resulting from resubmittal and retesting are your responsibility and no extra time will be allowed.

After testing, you must pick up the tested LED signal modules from the Transportation Laboratory and deliver to the job site.

## Warranty

The manufacturer must provide a written warranty against defects in materials and workmanship for LED signal modules for a minimum period of 48 months after installation of LED signal modules. Replacement LED signal modules must be provided within 15 days after receipt of failed LED modules at your expense. The State pays for shipping the failed modules to you. All warranty documentation must be submitted to the Engineer before installation. Replacement LED signal modules must be delivered to State Maintenance Electrical Shop at Department of Transportation Maintenance Yard, 3710 East Bandini Boulevard, Commerce, CA 90040.

## MATERIALS

Minimum power consumption for LED signal module must be 5 W.

LED signal module must have an operational lifecycle rating of 48 months. During the operational lifecycle, LED signal module must meet all parameters of this specification.

LED signal module must be designed for installation in the door frame of standard traffic signal housing.

LED signal module must:

1. Be 1.8 kg maximum mass
2. Be manufactured for 300-mm circular, 200-mm circular
3. Be from the same manufacturer
4. Be the same model for each size
5. Be sealed units with:
  - 5.1. 2 color-coded conductors for power connection, except for lane control LED signal modules use 3 color-coded conductors.
  - 5.2. Printed circuit board and power supply contained inside and complying with Chapter 1, Section 6 of TEES published by the Department.
  - 5.3. Lens that is:
    - 5.3.1. Integral to the units
    - 5.3.2. Convex or flat with a smooth outer surface
    - 5.3.3. Made of UV stabilized plastic or glass, and withstands UV exposure from direct sunlight for 48 months without exhibiting evidence of deterioration
  - 5.4. 1-piece EPDM gasket
6. Include 1-meter long conductors with quick disconnect terminals attached as specified in Section 86-4.01C, "Electrical Components," of the Standard Specifications
7. Be sealed in door frames
8. Fit into existing traffic signal section housing and comply with ITE publication, Equipment and Material Standards, Chapter 2, "Vehicle Traffic Control Signal Heads"

Individual LEDs must be wired so catastrophic loss or failure of 1 LED will not result in loss of more than 5 percent of the signal module light output. Failure of an individual LED in a string must not result in loss of entire string or other indication.

No special tools for installation are allowed.

## 300-mm Arrow

Comply with Section 9.01 of ITE publication, Equipment and Material Standards, Chapter 2, "Vehicle Traffic Control Signal Heads" for arrow indications.

LED signal module must:

1. Be weather tight and connect directly to electrical wiring.
2. Be capable of optical unit replacement.
3. Be a single, self-contained device, ready for installation into traffic signal housing.
4. Have manufacturer's name, trademark, model number, serial number, lot number, month and year of manufacture, and required operating characteristics, including rated voltage, power consumption, and volt-ampere, permanently marked on the back of the module.

5. Have a symbol of module type and color. Symbol must be 25 mm in diameter. Color must be written out in 13 mm high letters next to the symbol.
6. Be AlInGaP technology for red and yellow indications and gallium nitride technology for green indications.
7. Be ultra bright type rated for 100,000 hours of continuous operation from -40 °C to +74 °C.
8. Have a maximum power consumption as follows:

**Power Consumption Requirements**

LED Signal Module Type	Power Consumption (Watts)					
	Red		Yellow		Green	
	25 °C	74 °C	25 °C	74 °C	25 °C	74 °C
300-mm circular	11	17	22	25	15	15
200-mm circular	8	13	13	16	12	12
300-mm arrow	9	12	10	12	11	11
Programmed Visibility	11	17	22	25	15	15

Lens may be tinted, or may use transparent film or materials with similar characteristics to enhance "ON/OFF" contrasts. Tinting or other materials to enhance "ON/OFF" contrast must not affect chromaticity and must be uniform across the face of the lens.

If polymeric lens is used, surface coating or chemical surface treatment must be applied for front surface abrasion resistance.

Power supply must be integral to the module.

Internal components must be adequately supported to withstand mechanical shock and vibration from high winds and other sources.

Lens and LED signal module material must comply with the ASTM specifications for that material.

Enclosures containing either the power supply or electronic components of LED signal module, except lenses, must be made of UL94VO flame-retardant material.

If a specific mounting orientation is required, the LED signal module must have prominent and permanent vertical markings for accurate indexing and orientation within the signal housing. Markings must include an up arrow, or the word "UP" or "TOP."

LED signal module must meet or exceed the following values when operating at 25 °C:

**Minimum Initial Intensities for Circular Indications (cd)**

Angle (v,h)	200-mm			300-mm		
	Red	Yellow	Green	Red	Yellow	Green
2.5, ±2.5	157	314	314	399	798	798
2.5, ±7.5	114	228	228	295	589	589
2.5, ±12.5	67	133	133	166	333	333
2.5, ±17.5	29	57	57	90	181	181
7.5, ±2.5	119	238	238	266	532	532
7.5, ±7.5	105	209	209	238	475	475
7.5, ±12.5	76	152	152	171	342	342
7.5, ±17.5	48	95	95	105	209	209
7.5, ±22.5	21	43	43	45	90	90
7.5, ±27.5	12	24	24	19	38	38
12.5, ±2.5	43	86	86	59	119	119
12.5, ±7.5	38	76	76	57	114	114
12.5, ±12.5	33	67	67	52	105	105
12.5, ±17.5	24	48	48	40	81	81
12.5, ±22.5	14	29	29	26	52	52
12.5, ±27.5	10	19	19	19	38	38
17.5, ±2.5	19	38	38	26	52	52
17.5, ±7.5	17	33	33	26	52	52
17.5, ±12.5	12	24	24	26	52	52
17.5, ±17.5	10	19	19	26	52	52
17.5, ±22.5	7	14	14	24	48	48
17.5, ±27.5	5	10	10	19	38	38

**Minimum Luminance for Arrows, U-turn, Bicycle, Lane Control, and PV Indications (cd/m<sup>2</sup>)**

	Red	Yellow	Green
Arrow Indication	5,500	11,000	11,000
PV Indication (cd at 2.5°±2.5°)	314	314	314

LED signal module must meet or exceed the following illumination values for 48 months when operating over a temperature range of -40 °C to + 74 °C. Yellow LED signal module must meet or exceed the following illumination values for 48 months, when operating at 25 °C:

**Minimum Maintained Intensities for Circular Indications (cd)**

Angle (v,h)	200-mm			300-mm		
	Red	Yellow	Green	Red	Yellow	Green
2.5, ±2.5	133	267	267	339	678	678
2.5, ±7.5	97	194	194	251	501	501
2.5, ±12.5	57	113	113	141	283	283
2.5, ±17.5	25	48	48	77	154	154
7.5, ±2.5	101	202	202	226	452	452
7.5, ±7.5	89	178	178	202	404	404
7.5, ±12.5	65	129	129	145	291	291
7.5, ±17.5	41	81	81	89	178	178
7.5, ±22.5	18	37	37	38	77	77
7.5, ±27.5	10	20	20	16	32	32
12.5, ±2.5	37	73	73	50	101	101
12.5, ±7.5	32	65	65	48	97	97
12.5, ±12.5	28	57	57	44	89	89
12.5, ±17.5	20	41	41	34	69	69
12.5, ±22.5	12	25	25	22	44	44
12.5, ±27.5	9	16	16	16	32	32
17.5, ±2.5	16	32	32	22	44	44
17.5, ±7.5	14	28	28	22	44	44
17.5, ±12.5	10	20	20	22	44	44
17.5, ±17.5	9	16	16	22	44	44
17.5, ±22.5	6	12	12	20	41	41
17.5, ±27.5	4	9	9	16	32	32

**Minimum Maintained Luminance for Arrow, U-turn, Bicycle, Lane Control, and PV Indications (cd/m2)**

	Red	Yellow	Green
Arrow Indication	5,500	11,000	11,000
PV Indication (at 2.5°±2.5°)	314	314	314

LED signal module must comply with the following chromaticity requirements for 48 months when operating over a temperature range of -40 °C to +74 °C.

**Chromaticity Standards (CIE Chart)**

Red	Y: not greater than 0.308, or less than 0.998 - x
Yellow	Y: not less than 0.411, nor less than 0.995 - x, nor greater than 0.452
Green	Y: not less than 0.506 - 0.519x, nor less than 0.150 + 1.068x, nor more than 0.730 - x

LED signal module must operate:

1. At a frequency of 60 Hz ± 3 Hz, over a voltage range from 95 V(ac) to 135 V(ac), without perceptible flicker to the unaided eye. Fluctuations of line voltage must have no visible effect on luminous intensity of the indications. Rated voltage for measurements must be 120 V(ac).
2. Compatible with currently used controller assemblies, including solid state load switches, flashers, and conflict monitors. Comply with TEES Chapters 3 and 6. If a 20 mA alternating current or less is applied to the unit, the voltage read across the 2 leads must be 15 V(ac) or less.

Wiring and terminal block must comply with Section 13.02 of ITE publication, Equipment and Material Standards, Chapter 2, "Vehicle Traffic Control Signal Heads." Electrical connection for each Type 1 LED signal module must be 2

secured, color-coded, 1-meter long, 600 V(ac), 20 AWG minimum stranded jacketed copper wires. Wires must comply with NEC, rated for service at +105 °C.

LED signal module on-board circuitry must:

1. Include voltage surge protection to withstand high-repetition noise transients. The voltage surge protection must comply with NEMA Standard TS2, Section 2.1.6.
2. Comply with FCC, Title 47, SubPart B, Section 15 regulations for Class A emission limits for electronic noise.

LED signal module must provide a power factor of 0.90 or greater.

Total harmonic distortion from current and voltage induced into an alternating current power line by LED signal module must not exceed 20 percent at an operating temperature of 25 °C.

When power is applied to LED signal module, light emission must occur within 90 ms.

### **10-3.20 PROGRAMMED VISIBILITY VEHICLE TRAFFIC SIGNAL HEADS**

A signal technician qualified to program the programmed visibility signal heads shall be present at the time the signal heads are placed in operation.

### **10-3.21 BATTERY BACKUP SYSTEM**

#### **GENERAL**

##### **Summary**

This work includes installing battery backup system (BBS). Comply with Section 86, "Signals, Lighting and Electrical Systems," of the Standard Specifications and TEES.

The State will furnish BBS components as listed in "Materials" of these special provisions.

You must furnish the external cabinet and batteries.

##### **Submittals**

Before shipping external cabinets to the jobsite, submit material list including contract number, cabinet serial numbers, and contact information to the Transportation Laboratory.

Submit a Certificate of Compliance for each external cabinet and batteries to the Engineer under Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

##### **Quality Control and Assurance**

The State may test the cabinets.

##### **Functional Testing**

After complete installation, BBS functional test must be performed. Test for 30 minutes of continuous, satisfactory operation with utility power turned off. Perform test in the presence of the Engineer.

##### **Warranty**

Batteries must be warranted by the manufacturer to operate within a temperature range of -25 °C to +74 °C for 2 years.

Batteries must have a written warranty against defects in materials and workmanship from the manufacturer prorated for a period of 60 months after installation. You must provide the Engineer with all warranty documentation before installation. Replacement batteries must be available within 5 business days after receipt of failed batteries at no cost to the State except the cost of shipping the failed batteries. Replacement batteries must be delivered to Caltrans Maintenance Electrical Shop at Department of Transportation Maintenance Yard, 7310 East Bandini Boulevard, Commerce, CA 90040.

#### **MATERIALS**

Batteries must:

1. Be deep cycle, sealed prismatic, lead-calcium-based, absorbed-glass mat and valve-regulated lead acid (AGM/VRLA) type
2. Have voltage rating of 12 V
3. Be group size 24
4. Be commercially available and stocked locally
5. Have a carrying handle
6. Be marked with date code, maximum recharge data, and recharge cycles
7. Have 2 top-mounted, threaded, stud posts that include all washers and nuts required for attaching 9.5-mm ring lugs of a State-furnished BBS battery harness

8. Include rubber insulating protective covers for protecting the lugs, posts, and wiring - red for positive terminal and black for negative terminal
9. Be new and fully-charged when furnished
10. Be free from damage or deformities

External cabinet must be one listed on the Pre-Qualified Products List at:

[http://www.dot.ca.gov/hq/esc/approved\\_products\\_list/](http://www.dot.ca.gov/hq/esc/approved_products_list/)

External cabinet must be capable of housing:

1. 4 batteries
2. Inverter/charger unit
3. Power transfer relay
4. Manually-operated bypass switch
5. Required control panels
6. Wiring and harnesses

Dimensions and details for the external cabinet, for attaching the external cabinet to the Model 332 cabinet, and for wiring the State-furnished equipment will be available in an information handout as described in "Project Information" of these special provisions.

The following details must comply with Section 86-3.04, "Controller Cabinets," of the Standard Specifications and TEES:

1. Door construction, including material, thickness, coating, and welds
2. Frame
3. Door seals
4. Continuous stainless steel piano hinge or 4 leaves with 2 bolts on each side of each leaf, used to connect the door to external cabinet
5. Padlock clasp or latch and lock mechanism

The external cabinet must be ventilated by using louvered vents, filter, and a thermostatically controlled fan. Fan must be AC-operated from the same line output as the Model 332 cabinet. A 2-position terminal block must be provided on the fan panel, along with 3 meters of connected hookup wire.

The external cabinet surface must be anodized aluminum. Anti-graffiti paint must not be used.

The external cabinet must include all bolts, washers, nuts, and cabinet-to-cabinet coupler fittings necessary for mounting it to the Model 332A cabinet.

Fasteners for the external cabinet must include:

1. 8 cabinet mounting bolts that are 18-8 stainless steel hex head, fully-threaded, and 9.5 mm – 16 x 25.4 mm
2. 2 washers per bolt designed for 9.5-mm bolt and are 18-8 stainless steel 25.4-mm OD round flat type
3. K-lock nut per bolt: K-lock washer that is 18-8 stainless steel and hex-nut

External cabinet to Model 332A cabinet couplings must include a conduit for power connections between the 2 cabinets. Couplings must include:

1. 51-mm nylon-insulated steel chase nipple
2. 51-mm sealing, steel locknut
3. 51-mm nylon-insulated steel bushing

## **CONSTRUCTION**

Mount external cabinet to either the left or right side of Model 332A cabinet. The typical side-mounting location of external cabinet is flush with the bottom of the Model 332A cabinet and approximately equidistant from the front and rear door edges.

## **MEASUREMENT AND PAYMENT**

Full compensation for assembling and installing battery backup system is included in the contract lump sum price paid for Signal and Lighting, and no separate payment will be made therefor.

## 10-3.22 LIGHT EMITTING DIODE PEDESTRIAN SIGNAL FACE MODULES

### GENERAL

#### Summary

This work includes installing LED pedestrian signal face (PSF) module into standard Type A pedestrian signal housing. Comply with Section 86, "Signals, Lighting and Electrical Systems," of the Standard Specifications.

#### Submittals

Before shipping LED PSF modules to job site, submit the following to the Transportation Laboratory:

1. Delivery form including district number, EA, and contact information
2. List containing all LED PSF module serial numbers anticipated for use
3. LED PSF modules

#### Quality Control and Assurance

Module must be one listed on the Pre-Qualified Products List for LED traffic signals at:

[http://www.dot.ca.gov/hq/esc/approved\\_products\\_list](http://www.dot.ca.gov/hq/esc/approved_products_list)

The State will test LED PSF module shipments as specified in ANSI/ASQ Z1.4.. Testing will be completed within 30 days of delivery to the Transportation Laboratory. LED PSF modules tested or submitted for testing must be representative of typical production units. LED PSF modules will be tested as specified in California Test 606. All parameters of the specification may be tested on the modules.

Delays resulting from submittal of non-compliant materials do not relieve you from executing the contract within the allotted time. Non-compliant materials will be rejected. You must resubmit new LED for retesting and pick up the failed units within 7 days of notification. You must provide new LED PSF modules and allow a minimum of 30 days for the retest. You must pay for all shipping and handling costs related to testing and retesting. Delays resulting from resubmittal and retesting are your responsibility and no extra time will be allowed.

After successful testing, you must pick up the tested LED PSF modules from the Transportation Laboratory and deliver to the job site.

#### Warranty

The manufacturer must provide a written warranty against defects in materials and workmanship for LED PSF modules for a minimum period of 48 months after installation of LED PSF modules. Replacement LED PSF modules must be provided within 15 days after receipt of failed LED PSF modules at your expense. The State pays for shipping the failed modules to you. All warranty documentation must be submitted to the Engineer before installation. Replacement LED PSF modules must be delivered to State Maintenance Electrical Shop at Department of Transportation Maintenance Yard, 7310 East Bandini Boulevard, Commerce, CA 90040.

### MATERIALS

LED PSF module must:

1. Be from the same manufacturer.
2. Be installed in standard Type A pedestrian signal housing, "UPRAISED HAND" and "WALKING PERSON." Do not include reflectors.
3. Use LED as the light source.
4. Be designed to mount behind or replace face plates of standard Type A housing as specified in ITE publication, Equipment and Material Standards, Chapter 3, "Pedestrian Traffic Control Signal Indications" and the "California MUTCD."
5. Have a minimum power consumption of 10 W.
6. Use required color and be ultra bright type rated for 100,000 hours of continuous operation from -40 °C to +74 °C.
7. Be able to replace signal lamp optical units and pedestrian signal faces with both LED and incandescent light sources.
8. Fit into pedestrian signal section housings without modifications to the housing. The housing must comply with ITE publication, Equipment and Materials Standards, Chapter 3, "Pedestrian Traffic Control Signal Heads."
9. Be a single, self-contained device, not requiring on-site assembly for installation into standard Type A housing.
10. Have the following information permanently marked on the back of module:

- 10.1. Manufacturer's name
- 10.2. Trademark
- 10.3. Model number
- 10.4. Serial number
- 10.5. Lot number
- 10.6. Month and year of manufacture
- 10.7. Required operating characteristics, as follows:

- 10.7.1. Rated voltage
- 10.7.2. Power consumption
- 10.7.3. Volt-ampere (VA)
- 10.7.4. Power factor

11. Have prominent and permanent vertical markings for accurate indexing and orientation within the signal housing if a specific mounting orientation is required. Markings must include an up arrow, or the word "UP" or "TOP." Marking must be a minimum of 25-mm diameter.

Circuit board and power supply must be contained inside the LED PSF modules. Circuit board must comply with Chapter 1, Section 6 of TEES published by the Department.

Individual LEDs must be wired so catastrophic loss or failure of 1 LED will not result in loss of more than 5 percent of the PSF module light output. Failure of an individual LED in a string must not result in the loss of entire string or other indication.

LEDs must be evenly distributed in each indication. Do not use outline forms.

No special tools for installation are allowed.

Installation of the LED PSF module into pedestrian signal face must require only removal of lenses, reflectors, lamps, and existing LED modules.

Power supply for LED PSF module must be integral to the module. Power supply for each symbol must be isolated to avoid turn-on conflict.

Assembly and manufacturing processes for LED PSF module must assure that all internal components are adequately supported to withstand mechanical shock and vibration from high winds and other sources.

Material used for LED PSF module must comply with ASTM D 3935.

Enclosures containing either the power supply or electronic components of LED PSF module, except lenses, must be made of UL94VO flame-retardant material.

Color of "UPRAISED HAND" symbol must be portland orange.

Color of "WALKING PERSON" symbol must be lunar white.

Each symbol must not be less than 250 mm high and 165 mm wide. Uniformity ratio of illuminated symbols must not exceed 4 to 1 between highest and lowest luminance areas. Symbols must comply with ITE publication, Equipment and Material Standards, Chapter 3, "Pedestrian Traffic Control Signal Indications," and the "California MUTCD."

LED PSF module must maintain an average luminance value over 48 months of continuous use in signal operation for a temperature range of -40 °C to +74 °C. In addition, LED PSF modules must meet or exceed the following luminance values upon initial testing at 25 °C.

**Luminance Values**

PSF module	Luminance
UPRAISED HAND	3,750 cd/m <sup>2</sup>
WALKING PERSON	5,300 cd/m <sup>2</sup>

Color output of LED PSF module must comply with chromaticity requirements in Section 5.3 of ITE publication, Equipment and Material Standards, Chapter 3, "Pedestrian Traffic Control Signal Indications."

Measured chromaticity coordinates of LED PSF module must comply with the following chromaticity requirements for 48 months when operating over a temperature range of -40 °C to +74 °C.

**Chromaticity Standards (CIE Chart)**

UPRAISED HAND (portland orange)	Not greater than 0.390, nor less than 0.331, nor less than 0.997-X
WALKING PERSON (lunar white)	X: not less than 0.280, nor greater than 0.320 Y: not less than 1.055*X - 0.0128, nor greater than 1.055*X + 0.0072

LED PSF module maximum power consumption must not exceed the following values:

<b>Power Consumption Requirements</b>		
PSF module	Power Consumption @ 24 °C	Power Consumption @ 74 °C
UPRAISED HAND	10.0 W	12.0 W
WALKING PERSON	9.0 W	12.0 W

Wiring and terminal block must comply with Section 13.02 of ITE publication, Equipment and Material Standards, Chapter 2, "Vehicle Traffic Control Signal Heads." The LED PSF module must be supplied with spade lugs and 3 secured, color-coded, 1 meter long, 600 V(ac), 20 AWG minimum stranded jacketed copper wires. Wires must comply with NEC, rated for service at +105 °C.

LED PSF module must operate:

1. At a frequency of 60 Hz  $\pm$  3 Hz over a voltage range from 95 V(ac) to 135 V(ac) without perceptible flicker to the unaided eye. Fluctuations of line voltage must have no visible effect on luminous intensity of the indications. Rated voltage for measurements must be 120 V(ac).
2. Compatible with currently used State controller assemblies including solid state load switches, flashers, and conflict monitors. Comply with TEES Chapters 3 and 6. If a 20 ma alternating current or less is applied to the unit, the voltage read across the 2 leads must be 15 V(ac) or less.

LED PSF module on-board circuitry must:

1. Include voltage surge protection to withstand high-repetition noise transients. The voltage surge protection must comply with NEMA Standard TS2, Section 2.1.6.
2. Comply with FCC, Title 47, SubPart B, Section 15 regulations for Class A emission limits for electronic noise.

LED PSF module must provide a power factor of 0.90 or greater.

Total harmonic distortion from current and voltage induced into an alternating current power line by LED PSF module must not exceed 20 percent at an operating temperature of 25 °C.

The LED PSF module circuitry must prevent perceptible light emission to the unaided eye when a voltage, 50 V(ac) or less is applied to the unit.

When power is applied to LED PSF module, light emission must occur within 90 ms.

The "UPRAISED HAND" and "WALKING PERSON" symbol indications must be electrically isolated from each other. Sharing a power supply or interconnect circuitry between the 2 indications is not allowed.

### **10-3.23 DETECTORS**

Loop detector sensor units will be State-furnished in conformance with the provisions in "Materials" of these special provisions.

Loop wire shall be Type 2.

Loop detector lead-in cable shall be Type B.

For Type E detector loops, sides of the slot shall be vertical and the minimum radius of the slot entering and leaving the circular part of the loop shall be 40 mm. Slot width shall be a maximum of 16 mm. Loop wire for circular loops shall be Type 2. Slots of circular loops shall be filled with hot melt rubberized asphalt sealant.

### **10-3.24 MICROWAVE VEHICLE DETECTION SYSTEM - SIDE FIRE**

This work consists of installing, maintaining, and removing microwave vehicle detection system (MVDS) for temporary ramp metering system in conformance with the details shown on the plans and conforming to the requirements in Sections 86-1.06, 86-2.01, and 86-7.01 of Standard Specifications and "Maintaining Traffic" of these special provisions.

### **MATERIALS LIST AND DRAWINGS**

A list of materials which the Contractor proposes to install for the MVDS together with the drawings and other data shall be submitted to the Engineer in conformance with Section 86-1.04, "Equipment List and Drawings," of the Standard Specifications. Additionally, the following shall be provided before the completion of the contract:

1. **Lane Configuration** - The documentation shall include a diagram that illustrates how the microwave beam is covering the traffic lanes as well as the corresponding MVDS connector pins or wire terminals that correspond to

the respective lanes. The lanes shall be identified by direction (NB, SB, EB, WB), and in order, with lane one being the lane nearest to the center of the roadway.

2. **Mounting and Wiring Information** - The Contractor shall provide to the Engineer for approval one set of detailed diagrams showing wiring and service connections for each MVDS. The approved diagrams shall be covered separately on each side with clear self-adhesive plastic and placed in a heavy-duty plastic envelope. The envelope shall be attached securely to the inside of the cabinet door or at a location designated by the Engineer.
3. **Communication Protocol** - The MVDS communication protocol shall be open and shall be freely available for use in the public domain. The Contractor shall provide documentation that defines the complete MVDS communication protocol (e.g. message structure organization, data packet length, as well as all information necessary to make use of such messages).
4. **Remote Programming** - The Contractor shall provide all information and software necessary for operating the system from a remote Windows 2000/NT or newer based Personal Computer (PC). This information and software shall include at minimum the capability to calibrate, tune, align, and program the MVDS and shall be provided on a Windows 2000/NT or newer compatible compact disc (CD). The information shall be formatted so that the files can be matched with the equipment being calibrated or aligned. This documentation shall contain files that allow for replacement equipment to be loaded with the same configuration.
5. **MVDS Accuracy Analysis** - The Contractor shall be responsible for conducting MVDS Performance Testing and shall submit to the Engineer an MVDS accuracy analysis that conforms to requirements of these special provisions within 15 days of MVDS testing. The original video recordings as well as digital versatile disc (DVD) or CD copies of the video images covering the analysis periods shall be included.
6. **Acceptance Testing Documentation** - The Contractor shall provide a test plan, containing time and period of the testing, to be approved by the engineer. The test plan shall be organized so that the Engineer will be able to perform acceptance testing using the documentation without assistance from the Contractor. The Contractor shall collect and submit the data to be certified by the Engineer. If required by the Engineer, the data shall be collected in the presence of the Engineer.
7. **Acceptance Testing Schedule** - The Contractor shall submit a testing schedule to the Engineer for approval 15 days prior to acceptance testing of the MVDS. If the testing period extends beyond the normal working shift or if the Contractor fails to provide the necessary material for the testing within one hour of the scheduled testing start time, the Engineer may cancel testing for the day.

## FUNCTIONAL REQUIREMENTS

MVDSs shall simultaneously provide vehicle detection data in the form of vehicle presence, counts, speed, and occupancy for a minimum of 8 lanes of traffic with the performance requirements of these special provisions. MVDSs shall provide a separate zone per lane and detect vehicles as close as 3 m and as far as 60 m from the MVDS sensor. MVDSs shall monitor traffic lanes in the presence of barrier railings, guardrails and other obstacles.

MVDSs shall meet the following detection performance criteria when installed a minimum of 3 m from the nearest lane and at a minimum height of 5 m above the roadway detection zone:

1. Average 30 second speed in any lane with better than 95 percent accuracy, for any 5 minute period selected by the Engineer.
2. Average 5 minute occupancy for any lane with better than 85 percent accuracy, for any 15 minute period selected by the Engineer.
3. Count accuracy, when compared to vehicles observed in video images for the same period, shall be not less than 90 percent for any lane and not less than 95 percent for all lanes combined.
4. The Contractor shall provide the criteria for speed and volume acceptance test for approval by the Engineer. The Contractor shall also provide speed and volume data for verification by the Engineer.

MVDS shall consist of a sensor unit and include all required mounting hardware, power supplies, surge suppression, cables, connectors and wiring. The MVDS sensor shall include, as a minimum, a directional microwave transmitter, antenna, microwave receiver, a processor, memory and communication interface.

The MVDS shall have an EIA-RS232 or EIA-485 or Ethernet communication port that supports the National Transportation Communication for ITS Protocol (NTCIP). The MVDS communication protocol shall be non-proprietary and openly specified and available for use in the public domain. The MVDS shall be addressable and shall download count, speed, and occupancy data when polled by the traffic management center computer. Speed shall be configurable in English or Metric units. The MVDS shall support unit set-up from a serial console port on the MVDS unit. The console port protocol shall support sensor unit setup from a local Windows 2000/NT or newer compatible laptop or from a remote location with a desktop computer and standard phone modem.

When MVDS sensor contact outputs will be connected to Model 170/2070 Controller to emulate inductive loops, then the following section will apply:

The MVDS sensors shall be connected to a microwave sensor interface card (MSIF) installed in the input file of a state furnished Model 170E or Model 2070 controller cabinet. Each detection zone shall provide an optically isolated relay contact pair that follows the presence of vehicles in every traffic lane and sends signals to the controller with the accuracy stated in these special provisions. The MSIF shall have indications for power, communication, as well as the real time operation of each detection contact output.

The Contractor shall install an MVDS termination assembly (MTA) as shown on the plans. The MTA shall be a single circuit board or a set of modular DIN rail mounted assemblies. The MTA shall provide screw lug cable terminations for all MVDS units with clearance for routing the cables and labels to identify the connected MVDS detectors. The MVDS unit shall be connected in the order shown on the plans or as directed by the engineer. Each lane detection zone shall have an LED that indicates vehicle presence. Power shall be routed from the MTA to each MVDS unit. Each MVDS power connection shall have fast-blow AGC type fuse or a resettable circuit breaker such that the loss of power to any single MVDS due to over-current shall not limit the operation of the other connected MVDS. The fuses or breakers shall be easily accessible, and replaceable or resettable without requiring tools or removing cables, connectors, or other terminations. The MTA shall have DB9 male connectors for every connected MVDS unit for EIA-232 or EIA-485 communications with a local laptop computer for performing setup and diagnostics as well as remote communications. The Connectors shall be labeled and provide internal routing of data between the DB9 connectors and the MVDS terminal strips. The Contractor shall supply the cable and connectors for connecting the communication modem as shown on the plans and specified elsewhere in these special provisions.

MVDSs shall be user programmable in the field, via the MVDS unit console port, with a Windows 2000/NT or newer compatible laptop computer. The Contractor shall provide software, firmware and equipment to set-up, calibrate and operate the unit. MVDS software shall observe the vehicular traffic and automatically places detection lanes and set the sensor sensitivity. MVDSs shall be designed so that a trained State employee can configure and calibrate the MVDS in less than 15 minutes per lane once the MVDS sensor unit is installed.

### **TECHNICAL REQUIREMENTS**

MVDSs shall be FCC certified under Part 15 for low-power, unlicensed, continuous radio transmitter operation.

The MVDS sensor enclosure shall be weatherproof with a NEMA 3R rating, and the sensor mounted and directed perpendicular to the flow of traffic lanes at the locations shown on the plans.

The MSIF shall be inserted into the controller input file slots using the edge connector to obtain limited 24 V(dc) power and to provide contact closure outputs. No rewiring to the Model 170E or Model 2070 cabinet shall be allowed. The MSIF shall conform to the requirements detailed in Chapter 1 as well as Sections 5.2.8, 5.2.8.1, 5.2.8.2, 5.4.1, 5.4.5, 5.4.5, and 5.4.6, 5.5.1, 5.5.5, and 5.5.6 of TEES.

MVDS sensors shall be wired with a connectorized cable harness. Cables shall run continuously (without splices) between the sensor and controller cabinet and terminate in labeled terminal blocks identified with the purpose served. The connector shall be a standard Mil Type and rated plug. The cable shall have the number of conductors specified by the MVDS manufacturer to support the number of detection zones depicted on the plans plus spares for two future zones with an overall shield and copper drain wire. Conductors shall be according to the MVDS manufacturer for the wiring distance involved and covered with a minimum 0.30 mm polyvinyl chloride (PVC) insulation, rated for 300 V at 105 degrees C.

MVDS sensor unit power supplies or transformers shall be vertically mounted on a standard DIN rack rail using standard mounting hardware. The Contractor shall wire the MVDS power conductors to DIN rail mounted terminal blocks in the controller cabinet as directed by the Engineer. The serial data communication output conductors shall be terminated at TB-0, and continue for a minimum of 3 m to a DB9F connector for setup and diagnostic access. The contact pair output conductors shall be terminated at terminal block, TB-2. The ends of unused and spare conductors shall be coiled and taped to prevent accidental contact to other circuits. Conductors inside the cabinet shall be labeled for the functions as shown on the approved detailed diagrams.

The power supply or transformer shall meet or exceed the following minimum requirements:

	Power Supply	Transformer
Power Cord	Standard 120V(ac), 3 prong cord, at least 1 meter in length (may be added by Contractor)	Standard 120V(ac), 3 prong cord, at least 1 meter in length (may be added by Contractor)
Type	Switching mode type	Class 2
Rated Power	Twice (2x) full system load	Twice (2x) full system load
Operating Temperature	From -35 °C to +74 °C	From -35 °C to +74 °C
Operating Humidity Range	From 5 percent to 95	From 5 percent to 95
Input Voltage	From 90 V to 135 VAC	From 90V to 135 VAC
Input Frequency	60 Hz +/- 1 Hz	60 Hz +/- 1 Hz
Inrush Current	Cold start, 25 A max. at 115 V	N/A
Output Voltage	As required by the MVDS	As required by the MVDS
Overload Protection	From 105 percent to 150 percent in output pulsing mode	Power limited at >150 percent
Over Voltage Protection	From 115 percent to 135 percent of rated output voltage	N/A
Setup, Rise, Hold Up	800ms, 50ms, 15ms at 115VAC	N/A
Withstand Voltage	I/P-0/P:3kV, I/P-FG:1.5kV, for 60 sec.	I/P-0/P:3kV, I/P-FG:1.5kV, for 60 sec
Working Temperature	Not to exceed 70 °C@30% load	Not to exceed 70 °C@30% load
Safety Standards	UL 1012, TUV EN60950	UL 1585
EMC Standards	EN55022 Class B, EN61000-4-2, 3, 4, 5 and EN61000-3-2, 3	N/A

Field terminated circuits shall include transient protection that complies with IEEE Standard 587-1980 Category C.

The MVDS shall automatically restore normal operation following a power failure within 3 minutes and not require manual intervention. The MVDS shall maintain the configuration and calibration information in non-volatile memory and retain the information while powered off for at least 90 days.

The MVDS shall be configurable for 30 second to 24-hour polling cycles and store vehicle count, speed, classification, and occupancy data in 10 second to not less than 15 minute intervals.

The MVDS system and all supporting equipment shall be designed to operate continuously in an outdoor traffic monitoring and control environment.

## CONSTRUCTION

The Contractor shall assure that the MVDS will not cause harmful interference to radio communication in the area of the installation as required by FCC Part 15 requirements. The MVDS units shall be installed such that each unit operates independently and that MVDS units not interfere with other MVDS units or other equipment in the vicinity.

The Contractor is responsible for site visits and analysis of each proposed pole location to assure that the detector placement will comply with the manufacturer's published installation instructions, and the performance required in these special provisions. The Contractor shall confirm detector placement with the manufacturer before performing work at the MVDS location. When the manufacturer's analysis requires a change in the proposed pole location, the Contractor shall arrange a meeting with the manufacturer and the Engineer to select a new pole location.

The Contractor shall not proceed with any MVDS installation without the Engineer's written approval of the pole location.

The Contractor shall be responsible for the compatibility of components and for making necessary calibration adjustment to deliver the performance required in these special provisions. The Contractor shall provide equipment required to setup, calibrate, verify performance and maintain the MVDS.

The Contractor shall provide programming software needed to support the MVDS. The software shall be installed in the appropriate equipment and used for the acceptance testing.

## TESTING

Accuracy of the MVDS system shall be verified by comparing the MVDS vehicle counts to recorded video image counts for the same period. The video camera shall be located and oriented so that traffic is visible in all lanes. Video images shall be time stamped and analysis periods recorded to a DVD or CD media for viewing on a PC. The video field of view shall totally encompass the area in which vehicles are detected. The Contractor shall provide a means for synchronizing the test start and test ending times or provide software that displays time stamped MVDS data along with the video images of the

moving vehicles. The Contractor shall provide the Engineer with the original recording medium and documentation that supports the accuracy analysis and make a copy of these materials for their own use.

The accuracy test shall take place during a complex traffic period as specified by the Engineer. The following video recording and analysis options that depend on the available traffic conditions are acceptable; however the heaviest expected traffic conditions should be used, if possible. The minimum recording period shall be 30 minutes when the recording includes congested traffic (vehicles traveling at less than 20 mph for five or more minutes in any lane). The minimum recording period shall be 45 minutes when the traffic flow exceeds 1500 vehicles per hour in any lane during the test period. The minimum recording period shall be 60 minutes when the flow is less than 1500 vehicles per hour in every lane. The analysis shall be based on a minimum of 100 detected vehicles in every lane and cover the same time period for all lanes. The time period within the selected video will be selected by the Engineer. The total vehicle count for every lane shall be used and include the first and last partial vehicles for each lane. Errors in the start and finish of the MVDS and manual counts are included in the performance criterion specified in these special provisions.

MVDS unit count shall be compared to vehicle counts under traffic conditions of the prior paragraph. Vehicles licensed for use on State roads shall be counted by the MVDS. The data accuracy shall be determined by the formula  $100\{1-[(TC-MC)/TC]\}$  where TC= Traffic Count derived from the media recording, MC = MVDS reported count over the same period of time, and where the resulting fraction is expressed as an absolute value.

The accuracy of each MVDS unit shall be determined and documented so that each unit may be approved or rejected separately by the Engineer. The recorded media serves as acceptance evidence and shall not be used for calibration. The calibration shall have been completed prior to testing and verification.

The Engineer will review the accuracy data findings and accept or reject the results within 15 days. Determination of vehicle anomalies or unusual occurrences will be decided by the Engineer. Data or counts that are not accepted by the Engineer shall be considered errors and count against the MVDS unit's calibration. If the Engineer finds that the MVDS does not meet performance requirements, the Contractor shall re-calibrate and re-test the unit and re-submit new test data within 10 days. Following three failed attempts, the Contractor shall replace the MVDS detector with a new unit.

### **MAINTAINING MICROWAVE VEHICLE DETECTION SYSTEM**

Maintaining microwave vehicle detection systems to be used for ramp metering system, except the controller assembly, shall be the responsibility of the Contractor.

If components in the microwave vehicle detection system are damaged, displaced or cease to operate or function as specified, from any cause during the progress of the work, the Contractor shall immediately repair the components to the original condition or replace the components and shall restore the components to the original location.

Upon completion of the work requiring microwave vehicle detection system, as determined by the Engineer, the microwave vehicle detection system shall become the property of the Contractor and shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Materials Outside the Highway Right of Way," of the Standard Specifications. Pole holes shall be backfilled.

Full compensation for backfilling the pole holes is included in the contract lump sum price paid for modify ramp metering system and no additional compensation will be allowed therefor.

Conductors placed in slots across paved areas as specified herein, when no longer required, shall be abandoned in place when determined by the Engineer. Direct buried conductors, installed 300 mm or more below the ground surface, and conduit may be abandoned in place.

### **PAYMENT**

Full compensation for microwave vehicle detection system is included in the contract lump sum price paid for modify ramp metering system and no additional compensation will be allowed therefor.

### **10-3.25 PEDESTRIAN PUSH BUTTONS**

At the option of the Contractor, pedestrian push button housings may be the plastic type.

### **10-3.26 LUMINAIRES**

Ballasts shall be the lag regulator type.

### **10-3.27 PEDESTRIAN UNDERCROSSING FIXTURES**

Pedestrian undercrossing fluorescent lighting fixtures shall conform to the details shown on the plans and these special provisions.

The design of the fixture shall be submitted to the Engineer for approval before fabrication of the fixtures is started. If deemed necessary by the Engineer, one complete prototype fixture shall be delivered to the Engineer for approval at least 30 calendar days before fabrication of the contract fixtures.

The shell of the fixture shall be cast aluminum alloy, industrial type or Federal Class 18 aluminum, 6 mm, minimum thickness.

The door shall be one piece of 6061-T6 aluminum alloy, 3 mm, minimum thickness.

The lens units in the door section shall be formed of 38-mm, methyl methacrylate rod, cut and fire glazed to provide a clear finish or, of cast units, providing equivalent tolerances and finish. Units shall conform to the dimensions shown on the plans.

The lenses shall be secured to the door section with an extruded lens retainer of 6063-T5 aluminum alloy conforming to the lens shape. The lens retainers shall fit the full length of the lens on both sides. Lens retainers which are continuous for the full length of the 3 lenses will be permitted. "Zee" bars of 5052-H32 or 5005-H14 aluminum alloy, 1.6-mm, minimum thickness, may be substituted for the extruded lens retainer.

The continuous piano hinge shall be Type 1100 aluminum alloy. The piano hinge shall be riveted to the door section with 3-mm, aluminum rivets. Matching holes shall be drilled in the piano hinge and the lower edge of the fixture. The door assembly shall be attached after the shell is in place by minimum 9-mm, No. 8 stainless steel, self-tapping screws.

A captive, positive keyed, screw-type, latching device, requiring a special wrench, shall be provided at the upper edge to secure the door in the closed position as shown on the plans. Two special wrenches shall be delivered to the Engineer.

A neoprene gasket shall be attached to the frame to provide a cushion between the shell and the door.

A chain or other satisfactory device shall be provided to prevent the door from coming in contact with the undercrossing wall when in the fully open position.

The fixture shall be held in place by three 9-mm x 200-mm anchor bolts with 2 nuts as shown on the plans.

Surfaces of the fixtures in contact with concrete and with anchor bolts and nuts shall be painted with a thick application of alkali-resistant bituminous paint. The paint shall conform to the requirements in Military Specification MIL-P-6883.

Each fixture shall contain a F48T12/CW, rapid start fluorescent lamp with recessed, double contact base installed on the back side of the door directly behind the lens.

Lampholders shall be listed by the UL for outdoor use without an enclosure and with 1500-mA rapid start, fluorescent lamps. The lampholder for each lamp shall be of the spring-loaded type.

The distance between the face of the lampholders for each lamp shall be designed to provide a compression of at least 2.5 mm on the spring type lampholder when the lamp is in place. The lamp shall have positive mechanical and electrical contact when the lamp is in place. The socket on the spring type lampholder shall have sufficient travel to permit installation of the lamp. Springs shall not be a part of the current carrying circuit.

The ballast shall be the high power factor type with weatherproof leads for operation of one 1220-mm rapid start lamp. Ballasts shall be listed by the UL for outdoor operation on 110 V (ac) to 125 V (ac), 60 Hz circuits and rated at 1500 mA.

Wiring connections in the fixtures shall be terminated on a molded, phenolic, barrier type, 2-pole terminal block rated at 15 A, 600 V (ac) and shall have integral type white waterproof marking strips. Current carrying parts of the terminal blocks shall be insulated from the fixture with integral plugs or strips to provide an insulating value in excess of the line to ground flashover voltage. If the Contractor elects to use sectionalized terminal blocks, each section shall be provided with an integral barrier on each side and shall be capable of rigid mounting and alignment.

Conductors from the ballast leads to the lampholders shall be No. 16, minimum size, stranded, UL listed copper appliance wiring material (AWM). Splicing of lampholder conductors to the ballast leads shall be done by use of mechanically secure connectors.

Sufficient slack shall be provided in the conductors to allow the fixture door to be fully opened.

Holes for Size 27 conduit shall be provided in both ends of the fixture. Unused holes shall be plugged with pressed metal closures.

Exposed surfaces of the fixture shall be clean, uniform in appearance and free from defects such as improper fit, dents, deep scratches and abrasions, burrs, roughness, off-square ends, holes off center or jagged, surface irregularities, and other significant defects. Screws for attaching components to the fixture door such as "Zee" bars, ballasts and terminal block shall be tapped into the door from inside only. No screwheads, nuts or other fasteners shall be removable from the outside.

Defective parts of the fixture, as determined by the Engineer before or after the fixture is installed, shall be removed and replaced at the Contractor's expense.

### **10-3.28 SIGN LIGHTING FIXTURES-INDUCTION**

Induction sign lighting fixtures shall conform to the provisions for mercury sign lighting fixtures in Section 86-6.05, "Sign Lighting Fixtures-Mercury," of the Standard Specifications and these special provisions.

Each fixture shall consist of a housing with door, a reflector, refractor or a lens, a lamp, a power coupler, a high frequency generator and a fuse block.

Fixtures shall have a minimum average rating of 60 000 hours. Fixtures shall be for a wattage of 87 W, 120/240 V(ac). The power factor of the fixtures shall be greater than 90 percent and the total harmonic distortion shall be less than 10 percent. Fixtures shall be Underwriter's Laboratories (UL) approved for wet locations and be Federal Communications Commission (FCC) Class A listed.

The mass of the fixture shall not exceed 20 kg. The manufacturer's brand name, trademark, model number, serial number and date of manufacture shall be located on the packaged assembly and permanently marked on the outside and inside of the housing.

## **MATERIALS**

### **Mounting Assembly**

The mounting assembly may be either cast aluminum, hot-dip galvanized steel plate or steel plate that has been galvanized and finished with a polymeric coating system or the same finish that is used for the housing.

### **Housing**

Housings shall have a door designed to hold a refractor or lens. Housing doors shall be designed to be opened without the use of tools. Housings and doors shall have a powder coat or polyester paint finish of a gray color resembling unfinished fabricated aluminum.

### **Reflector**

Reflectors shall be designed to be removed as a unit that includes the lamp and power coupler.

### **Refractor**

Refractors or lenses shall have smooth exteriors. Lenses shall be flat or convex. Convex lenses shall be made from heat resistant, high-impact resistant, tempered glass.

Convex lenses shall be designed or shielded so that no fixture luminance is visible when the fixture is approached directly from the rear and the viewing level is the bottom of the fixture. When a shield is used it shall be an integral part of the door casting.

### **Lamp**

Each fixture shall be furnished with a 85-W induction lamp. Interior lamp walls shall be fluorescent phosphor coated. Lamp light output shall be at least 70 percent at 60 000 hours. Lamps shall have a minimum color-rendering index of 80. Lamps shall be rated at a color temperature of 4000 K. Lamps shall be removable without the use of tools.

### **Power Coupler**

Power couplers shall consist of a construction base with antenna, heat sink and electrical connection cable. The power coupler shall be designed so that it can be removed with common hand tools.

### **High Frequency Generator**

High frequency generators shall start and operate lamps at an ambient temperature of -25 °C or greater for the rated life of the lamp.

Generator output frequency shall be 2.65 MHz  $\pm$  10 percent. The generator radio frequency interference shall meet the requirements of the Federal Communications Commission Title 47, Part 18, regulations concerning harmful interference.

High frequency generators shall operate continuously at ambient air temperatures from -25 °C to +25 °C without reduction in generator life. High frequency generators shall have a design life of at least 100 000 hours at 55 °C.

High frequency generators shall be capable of being replaced with common hand tools. Conductor terminals shall be identified as to the component terminal to which they connect.

High frequency generators shall be mounted to use the fixture upon which they are mounted as a heat sink.

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications, and a copy of the high frequency generator test methods and results shall be submitted by the manufacturer with each lot of fixtures. The certificate shall state that the high frequency generators meet the requirements of this section and the generator specifications of the lamp manufacturer.

## **10-3.29 INTERNALLY ILLUMINATED SIGN LIGHT EMITTING DIODE**

### **GENERAL**

#### **Summary**

This work includes installing LED "METER ON" in Type A modified pedestrian signal. Comply with Section 86 of the Standard Specifications.

#### **Submittals**

Before shipping LED signal modules to job site, submit the following to the Transportation Laboratory:

1. Delivery form including district number, EA, and contact information
2. List containing all LED signal module serial numbers anticipated for use
3. LED signal modules

**Quality Assurance Testing**

Module shall be one listed on the Pre-Qualified Products List for LED traffic signals at:

[http://www.dot.ca.gov/hq/esc/approved\\_products\\_list](http://www.dot.ca.gov/hq/esc/approved_products_list)

The State will test LED signal module shipments per ANSI/ASQC Z1. Testing will be completed within 30 days of delivery to the Transportation Laboratory. LED signal modules tested or submitted for testing shall be representative of typical production units. LED and circular LED signal modules will be tested as specified in California Test 604. Arrow, U-turn, and bicycle LED signal modules will be tested as specified in California Test 3001. All parameters of the specification may be tested on the modules. LEDs shall be spread evenly across the module. LED arrow indication shall provide the minimum initial luminous intensity listed. Measurements will be performed at the rated operating voltage of 120 V(ac).

Delays resulting from submittal of non-compliant materials do not relieve the Contractor from executing the contract within the allotted time. Non-compliant materials will be rejected. The Contractor shall resubmit new LED for retesting and pick up the failed units within one week of notification. The Contractor shall provide new LED signal modules and allow a minimum of 30 days for the retest. The Contractor shall pay for all shipping and handling costs related to testing and retesting. Delays resulting from resubmittal and retesting are the Contractor's responsibility and no extra time will be allowed.

After testing, the Contractor shall pick up the tested LED signal modules from the Transportation Laboratory and deliver to the job site.

**Warranty**

The manufacturer shall provide a written warranty against defects in materials and workmanship for LED signal modules for a minimum period of 48 months after installation of LED signal modules. Replacement LED signal modules shall be provided within 15 days after receipt of failed LED modules at no cost to the State, except the cost of shipping the failed modules. All warranty documentation shall be submitted to the Engineer before installation. Replacement LED signal modules shall be delivered to State Maintenance Electrical Shop at Department of Transportation Maintenance Yard, 7310 East Bandini Boulevard, Commerce, CA 90040.

**MATERIALS**

LED Meter on module shall:

1. Be weather tight and connect directly to electrical wiring.
2. Be capable of optical unit replacement.
3. Have manufacturer's name, trademark, model number, serial number, lot number, month and year of manufacture, and required operating characteristics, including rated voltage, power consumption, and volt-ampere, permanently marked on the back of the module.
4. Be AlInGaP technology
5. Be ultra bright type rated for 100,000 hours of continuous operation from -40°C to +74°C
6. Each module shall provide an average luminous intensity of at least 5,300 candela/m<sup>2</sup> throughout the useful life over the operating temperature range.
7. The uniformity ratio of an illuminated symbol shall not exceed 4 to 1 between the highest luminance area and the lowest luminance area in the module.
8. The color output of the module shall conform to the requirements of Section 5.3 in the ITE Publication: Equipment and Material Standards, Chapter 3 (Pedestrian Traffic Control Signal Indications).
9. Measured chromaticity coordinates of LED module shall comply with the following chromaticity requirements for 48 months when operating over a temperature range of -40 °C to +74 °C:

Chromaticity Standards (CIE Chart)
(lunar white)X: not less than 0.280, nor greater than 0.320
Y: not less than 1.055*X - 0.0128, nor greater than 1.055*X + 0.0072

10. Use LED as the light source.
11. Have a minimum power consumption of 10 W

12. Use required color and be ultra bright type rated for 100,000 hours of continuous operation from -40°C to +74°C.
13. Fit into Type A pedestrian signal modified so that the reflector shall be a single chamber.
14. Be a single, self-contained device, not requiring on-site assembly for installation into standard Type A housing.
15. Module Identification
  - a. Each module shall have the manufacturer's name, trademark, model number, serial number, date of manufacture (month-year), and lot number as identification permanently marked on the back of the module.
  - b. The following operating characteristics shall be permanently marked on the back of the module: rated voltage and rated power in Watts and Volt-Ampere.
16. Maximum power consumption requirements for the LED modules are as follows (in Watts):

	25°C	74°C
"Meter On"	15.0	17.0

LED Meter on module shall have an operational lifecycle rating of 48 months. During the operational lifecycle, LED signal module shall meet all parameters of this specification.

Individual LEDs shall be wired such that a catastrophic loss or failure of one LED will result in loss of not more than 5 percent of the module light output. Failure of an individual LED in a string shall not result in the loss of entire string or other indication.

No special tools for installation are allowed.

Wiring and terminal block shall comply with Section 13.02 of ITE publication, Equipment and Material Standards, Chapter 2, "Vehicle Traffic Control Signal Heads." The LED module shall be supplied with spade lugs and 3 secured, color-coded, one-meter long, 600 V, 20 AWG minimum stranded jacketed copper wires. Wires shall comply with NEC, rated for service at +105°C.

LED Meter on module shall operate:

1. At a frequency of 60 Hz  $\pm$  3 Hz, over a voltage range from 95 V(ac) to 135 V(ac), without perceptible flicker to the unaided eye. Fluctuations of line voltage shall have no visible effect on luminous intensity of the indications. Rated voltage for measurements shall be 120 V(ac).
2. Compatible with currently used State controller assemblies, including solid state load switches, flashers, and conflict monitors. Comply with TEES Chapters 3 and 6. If a 20 mA alternating current or less is applied to the unit, the voltage read across the 2 leads shall be 15 V(ac) or less.

LED Meter on module on-board circuitry shall:

1. Include voltage surge protection to withstand high-repetition noise transients. The voltage surge protection shall comply with NEMA Standard TS2, Section 2.1.6.
2. Comply with FCC, Title 47, SubPart B, Section 15 regulations for Class A emission limits for electronic noise.

LED signal module shall provide a power factor of 0.90 or greater.

Total harmonic distortion from current and voltage induced into an alternating current power line by LED signal module shall not exceed 20 percent at an operating temperature of 25°C.

When power is applied to LED signal module, light emission shall occur within 90 ms.

Power supply shall be integral to the module.

Internal components shall be adequately supported to withstand mechanical shock and vibration from high winds and other sources.

Lens and LED signal module material shall comply with the ASTM specifications for that material.

Enclosures containing either the power supply or electronic components of LED signal module, except lenses, shall be made of UL94VO flame-retardant material.

If a specific mounting orientation is required, the LED signal module shall have prominent and permanent vertical markings for accurate indexing and orientation within the signal housing. Markings shall include an up arrow, or the word "UP" or "TOP."

The message shall be white "METER ON" as shown on the plans. White color shall be in conformance with the provisions in Section 86-4.06, "Pedestrian Signal Faces," of the Standard Specifications.

Lenses shall be 4.8-mm, minimum thickness, clear acrylic or polycarbonate plastic or 3-mm nominal thickness glass fiber reinforced plastic, with molded, one piece, neoprene gasket. Message lettering for "METER" shall be "Series C," 113 mm high, with uniform 13-mm stroke, and for "ON" shall be "Series C," 150 mm high, with uniform 25-mm stroke. Letters shall be clear, transparent or translucent, with black opaque background silk screened on to the second surface of the lens.

Full compensation for internally illuminated sign light emitting diode is included in the contract lump sum price paid for items of work involved and no additional compensation will be allowed therefor.

### **10-3.30 INTERNALLY ILLUMINATED STREET NAME SIGNS**

Internally illuminated street name signs shall be Type A.

### **10-3.31 PHOTOELECTRIC CONTROLS**

Contactors shall be the mechanical armature type.

### **10-3.32 MODIFY COMMUNICATION SYSTEM**

Modify communication system shall consist of, but not be limited to:

- A. Removing, and disposing pull boxes, and conduits, of various sizes and types,
- B. Furnishing and installing:
  - 1. Conduits, conductors and cables of various sizes, types and installation methods,
  - 2. Pull boxes of various sizes, types and installation methods,
- C. Furnishing, installing, and connecting existing or new conductors of various sizes, types and installation methods, including, but not be limited to, conductors, and multimode fiber optic cables (2MMFO), and incidentals to make the installed or connected equipment fully operational, complete in place, as shown on the plans, and as directed by the Engineer.

New equipment shall be current standard production units and shall have been in production for a minimum of 6 months.

### **10-3.33 REMOVING, REINSTALLING OR SALVAGING ELECTRICAL EQUIPMENT**

Salvaged electrical materials shall be hauled to City of Glendale, Division of Traffic and Transportation located at 633 East Broadway, Glendale, CA 91206 and stockpiled.

The Contractor shall provide the equipment, as necessary, to safely unload and stockpile the material. A minimum notice of 2 business days shall be given prior to delivery. The Contractor shall contact field personnel at (818) 548-3960.

### **10-3.34 DISPOSING OF ELECTRICAL EQUIPMENT**

Ballasts and transformers that contain polychlorinated biphenyl (PCB) are designated as extremely hazardous wastes and fluorescent tubing and mercury lamps are designated as hazardous wastes under Title 22, Division 4.5, Chapter 11, Article 4.1 and Article 5, of the California Code of Regulations.

The State assumes generator responsibility for these wastes. The Engineer will prepare the Hazardous Waste Manifest for Shipment. Ballasts shall be packaged and transported to a hazardous waste disposal facility. The Contractor shall package and transport fluorescent lights to an appropriately permitted facility.

### **PAYMENT**

Full compensation for hauling, stockpiling, and disposing of transformers, fluorescent tubing and mercury lamps and non-leaking fluorescent light ballasts shall be considered as included in the contract price paid for the various items of work and no additional compensation will be allowed therefor.

### **10-3.35 PAYMENT**

The contract lump sum price or prices paid for signal and lighting shall include highway lighting at intersections in connection with signals only.

Other roadway lighting on the project shall be considered as included in the contract lump sum price paid for modify lighting and sign illumination.

Full compensation for hauling and stockpiling electrical materials shall be considered as included in the contract price paid for the item requiring the material to be salvaged and no additional compensation will be allowed therefor.

If any of the fabrication sites for the materials listed are located more than 480 air line kilometers from both Sacramento and Los Angeles, additional shop inspection expenses will be sustained by the State. Whereas it is and will be impractical and difficult to determine the actual increase in these expenses, it is agreed that payment to the Contractor for furnishing these listed materials from each fabrication site located more than 480 air line kilometers from both Sacramento and Los Angeles will be reduced \$2000:

## 1. Service equipment enclosures

The contract lump sum price paid for modify communication system shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in modify communication system, including removing existing fiber optic cables, pull boxes and other equipment, and installing new various types and sizes communication conduits, fiber optic cables, pull boxes and other equipment, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer

The contract unit price paid for sprinkler control conduit (bridge) includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in sprinkler control conduit (bridge), complete in place, including support hangers, pull boxes, cradles and expansion-deflection fittings, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for TOS cellular communication equipment is included in the contract lump sum price paid for modify ramp metering system and no additional compensation will be allowed therefor..

**AMENDMENTS TO THE STANDARD SPECIFICATIONS  
DATED JULY 1999**



Unless an object or activity is specified to be less than the total, the quantity or amount is all of the object or activity.  
 All items in a list apply unless the items are specified as choices.

Headings are included for the purposes of organization and referencing. Inclusion of a heading with no related content, "Reserved," or "Not Used" does not indicate that no specification exists for that subject; applicable specifications may be covered in a general or referenced specification.

## 1-2 REFERENCES

### 1-2.01 REFERENCES

A reference within parentheses to a law or regulation is included in the contract for convenience only and is not a comprehensive listing of related laws and regulations. Lack of a reference does not indicate no related laws or regulations exist.

If the version of a referenced document is not specified, use the current version in effect on the date of Notice to Bidders.

A reference to a subsection includes the section's general specifications of which the subsection is a part.

A code not specified as a Federal code is a California code.

## 1-3 ABBREVIATIONS AND MEASUREMENT UNITS

### 1-3.01 ABBREVIATIONS

#### Abbreviations

Abbreviation	Meaning
AAN	American Association of Nurserymen
AASHTO	American Association of State Highway and Transportation Officials
AISC	American Institute of Steel Construction
AISI	American Iron and Steel Institute
ANSI	American National Standards Institute
APHA	American Public Health Association
API	American Petroleum Institute
AREMA	American Railway Engineering and Maintenance-of-Way Association
ASME	American Society of Mechanical Engineers
ASTM	American Society for Testing and Materials
AWG	American Wire Gage
AWPA	American Wood-Preservers' Association
AWS	American Welding Society
AWWA	American Water Works Association
CIH	Certified Industrial Hygienist
DBE	Disadvantaged Business Enterprise
DVBE	Disabled Veteran Business Enterprise
EIA	Electronic Industries Alliance
ETL	Electrical Testing Laboratories
FHWA	Federal Highway Administration
IEEE	Institute of Electrical and Electronics Engineers
NETA	National Electrical Testing Association, Inc.
NEMA	National Electrical Manufacturers Association
PLAC	permit, license, agreement, certification, or any combination of these
SSPC	The Society for Protective Coatings
UL	Underwriters' Laboratories Inc.

### 1-3.02 MEASUREMENT UNITS

Some of the symbols for units of measurement used in the specifications and in the Bid Item List are defined as follows. The symbols for other units of measurement used in the specifications are as defined in ASTM E 380 or in the various specifications and test referenced in the specifications.

### Measurement Units

Symbols as used in the specifications	Symbols as used in the Bid Item List	Meaning
A	—	amperes
—	EA	each
g	G	gram
kg	KG	kilogram
ha	HA	hectare (10 000 m <sup>2</sup> )
h	H	hour
J	—	joule
—	LNKM	lane kilometer
L	L	liter
—	LS	lump sum
m	M	meter
km	KM	kilometer
mm	MM	millimeter
µm	—	micrometer
nm	—	nanometer
m <sup>2</sup>	M2	square meter
m <sup>3</sup>	M3	cubic meter
N	—	newton
N·m	—	newton meter
Ω	—	ohm
Pa	—	pascal
kPa	—	kilopascal
MPa	—	megapascal
s	—	second
—	STA	station (100 m)
—	TAB	tablet
tonne	TONN	metric ton (1000 kg)
W	—	watt

### 1-4 DEFINITIONS

#### 1-4.01 GENERAL

Interpret terms as defined in the contract documents. A construction-industry term not defined in the contract documents has the meaning defined in Means Illustrated Construction Dictionary, Condensed Version, Second Edition.

#### 1-4.02 GLOSSARY

**acceptance:** Formal written acceptance by the Director of an entire contract that has been completed in all respects in accordance with the plans and specifications and any modifications to them previously approved.

**base:** Layer of specified material of planned thickness placed immediately below the pavement or surfacing.

**basement material:** Material in excavation or embankments underlying the lowest layer of subbase, base, pavement, surfacing, or other specified layer to be placed.

**bid item:** Specific work unit for which the bidder provides a price.

**Bid Item List:** List of bid items and the associated quantities.

**Bid Item List, verified:** Bid Item List with verified prices. The Contract Proposal of Low Bidder at the Department's Web site is the verified Bid Item List.

**bridge:** Structure, with a bridge number, that carries a utility facility, or railroad, highway, pedestrian or other traffic, over a water course or over or under or around any obstruction.

**building-construction contract:** Contract that has "building construction" on the cover of the Notice to Bidders and Special Provisions.

**business day:** Day on the calendar except Saturday or holiday.

**California Manual on Uniform Traffic Control Devices:** The California Manual on Uniform Traffic Control Devices for Streets and Highways (California MUTCD) is issued by the Department of Transportation and is the Federal Highway Administration's MUTCD 2003 Edition, as amended for use in California.

**Certified Industrial Hygienist:** Industrial hygienist certified in comprehensive practice by the American Board of Industrial Hygiene.

**conduit:** Pipe or tube in which smaller pipes, tubes, or electrical conductors are inserted or are to be inserted.

**contract:** Written and executed contract between the Department and the Contractor.

**contract bonds:** Security for the payment of workers and suppliers furnishing materials, labor, and services and for guaranteeing the Contractor's work performance.

**contract item:** Bid item.

**Contractor:** Person or business or its legal representative entering into a contract with the Department for performance of the work.

**culvert:** Structure, other than a bridge, that provides an opening under a roadway for drainage or other purposes.

**day:** 24 consecutive hours running from midnight to midnight; calendar day.

**deduction:** Amount of money permanently taken from progress payment and final payment. Deductions are not retentions under Pub Cont Code § 7107.

**Department:** Department of Transportation as defined in St & Hwy Code § 20 and authorized in St & Hwy Code § 90; its authorized representatives.

**detour:** Temporary route for traffic around a closed road part. A passageway through a job site is not a detour.

**Director:** Department's Director.

**Disabled Veteran Business Enterprise:** Business certified as a DVBE by the Office of Small Business and DVBE Services, Department of General Services.

**divided highway:** Highway with separated traveled ways for traffic, generally in opposite directions.

**Engineer:** Department's Chief Engineer acting either directly or through properly authorized agents; the agents acting within the scope of the particular duties delegated to them.

**Federal-aid contract:** Contract that has a Federal-aid project number on the cover of the Notice to Bidders and Special Provisions.

**fixed costs:** Labor, material, or equipment cost directly incurred by the Contractor as a result of performing or supplying a particular bid item that remains constant regardless of the item's quantity.

**frontage road:** Local street or road auxiliary to and located generally on the side of an arterial highway for service to abutting property and adjacent areas and for control of access.

**grading plane:** Basement material surface on which the lowest layer of subbase, base, pavement, surfacing, or other specified layer is placed.

**highway:** Whole right of way or area that is reserved for and secured for use in constructing the roadway and its appurtenances.

**holiday:**

1. Every Sunday
2. January 1st, New Year's Day
3. 3rd Monday in January, Birthday of Martin Luther King, Jr.
4. February 12th, Lincoln's Birthday
5. 3rd Monday in February, Washington's Birthday
6. March 31st, Cesar Chavez Day
7. Last Monday in May, Memorial Day
8. July 4th, Independence Day
9. 1st Monday in September, Labor Day
10. 2nd Monday in October, Columbus Day
11. November 11th, Veterans Day
12. 4th Thursday in November, Thanksgiving Day
13. Day after Thanksgiving Day
14. December 25th, Christmas Day

If January 1st, February 12th, March 31st, July 4th, November 11th, or December 25th falls on a Sunday, the Monday following is a holiday. If November 11th falls on a Saturday, the preceding Friday is a holiday. Interpret "legal holiday" as "holiday."

**informal-bid contract:** Contract that has "Informal Bid Authorized by Pub Cont Code §10122" on the cover of the Notice to Bidders and Special Provisions.

**Information Handout:** Supplemental project information furnished to bidders as a handout.

**laboratory:** Laboratory authorized by the Department to test materials.

**liquidated damages:** Amount prescribed in the specifications, pursuant to the authority of Pub Cont Code § 10226, to be paid to the State or to be deducted for each day's delay in completing the whole or any specified portion of the work beyond the time allowed in the specifications.

**median:** Portion of a divided highway separating the traveled ways for traffic in opposite directions including inside shoulders.

**Notice to Bidders:** Document that provides a general work description, bidder and bid specifications, and the time and location the Department receives bids.

**pavement:** Uppermost layer of material placed on the traveled way or shoulders. This term is used interchangeably with surfacing.

**plans:** Official project plans and Standard Plans, profiles, typical cross sections, working drawings and supplemental drawings, or reproductions thereof, approved by the Engineer, which show the location, character, dimensions and details of the work to be performed. These documents are to be considered as a part of the plans.  
In the above definition, the following terms are defined as follows:  
**Standard Plans:** Standard Plans issued by the Department.  
**project plans:** Specific details and dimensions peculiar to the work supplemented by the Standard Plans insofar as the same may apply.

**roadbed:** Area between the intersection of the upper surface of the roadway and the side slopes or curb lines. The roadbed rises in elevation as each increment or layer of subbase, base, surfacing or pavement is placed. Where the medians are so wide as to include areas of undisturbed land, a divided highway is considered as including 2 separate roadbeds.

**roadway:** Highway portion included between the outside lines of sidewalks, or curbs, slopes, ditches, channels, waterways, and including all the appertaining structures, and other features necessary to proper drainage and protection.

**shoulder:** Roadway portion contiguous with the traveled way for accommodation of stopped vehicles, for emergency use, and for lateral support of base and surface courses.

**special provisions:** Specific clauses setting forth conditions or requirements peculiar to the work and supplementary to these Standard Specifications. The Department's publication titled "Labor Surcharge And Equipment Rental Rates" is part of the special provisions.

**specifications:** Directions, provisions, and requirements contained in these Standard Specifications, Amendments to the Standard Specifications, and the special provisions. Where the term "these specifications" or "these Standard Specifications" is used in this book, it means the provisions set forth in this book.

**State:** State of California, including its agencies, departments, or divisions, whose conduct or action is related to the work.

**Structure Design:** Offices of Structure Design of the Department.

**subbase:** Layer of specified material of planned thickness between a base and the basement material.

**subgrade:** Roadbed portion on which pavement, surfacing, base, subbase, or a layer of any other material is placed.

**substructure:** Bridge portions below the bridge seats, tops of piers, haunches of rigid frames, or below the spring lines of arches. Backwalls and parapets of abutments and wingwalls of bridges are portions of the substructure.

**superstructure:** Bridge portion except the bridge substructure.

**supplemental project information:** Information relevant to the project, specified as supplemental project information, and made available to bidders.

**surfacing:** Uppermost layer of material placed on the traveled way, or shoulders. This term is used interchangeably with pavement.

**traffic lane:** Portion of a traveled way for the movement of a single line of vehicles.

**traveled way:** Portion of the roadway for the movement of vehicles, exclusive of shoulders.

**total bid:** Sum of the item totals as verified by the Department; original contract price.

**withhold:** Money temporarily or permanently taken from progress payment. Withholds are not retentions under Pub Cont Code § 7107.

**work:** All the work specified, indicated, shown or contemplated in the contract to construct the improvement, including all alterations, amendments, or extensions to it made by contract change order or other written orders of the Engineer.

## 1-5 DISTRICTS

**District Composition and Office Addresses**

District	Counties	Location Address	Mailing Address
1	Del Norte (DN), Humboldt (Hum), Lake (Lak), Mendocino (Men)	1656 UNION ST EUREKA, CA	PO BOX 3700 EUREKA CA 95502
2	Lassen (Las), Modoc (Mod), Plumas (Plu), Shasta (Sha), Siskiyou (Sis), Tehama (Teh), Trinity (Tri)	1657 RIVERSIDE DR REDDING, CA	PO BOX 496073 REDDING CA 96049-6073
3	Butte (But), Colusa (Col), El Dorado (ED), Glenn (Gle), Nevada (Nev), Placer (Pla), Sacramento (Sac), Sierra (Sie), Sutter (Sut), Yolo (Yol), Yuba (Yub)	703 B ST MARYSVILLE, CA	PO BOX 911 MARYSVILLE CA 95901
4	Alameda (Ala), Contra Costa (CC), Marin (Mrn), Napa (Nap), San Francisco (SF), San Mateo (SM), Santa Clara (SCI), Solano (Sol), Sonoma (Son)	111 GRAND AVE OAKLAND, CA	PO BOX 23660 OAKLAND CA 94623-0660
5	Monterey (Mon), San Benito (SBt), San Luis Obispo (SLO), Santa Barbara (SB), Santa Cruz (SCr)	50 HIGUERA ST SAN LUIS OBISPO, CA	50 HIGUERA ST SAN LUIS OBISPO CA 93401-5415
6	Fresno (Fre), Kern (Ker), Kings (Kin), Madera (Mad), Tulare (Tul)	1352 W. OLIVE AVE FRESNO, CA	PO BOX 12616 FRESNO CA 93728-2616
7	Los Angeles (LA), Ventura (Ven)	100 S. MAIN ST LOS ANGELES	100 S MAIN ST LOS ANGELES CA 90012
8	Riverside (Riv), San Bernardino (SBd)	464 W 4TH ST SAN BERNARDINO, CA	464 W 4TH ST SAN BERNARDINO CA 92401-1400
9	Inyo (Iny), Mono (Mno)	500 S MAIN ST BISHOP, CA	500 S MAIN ST BISHOP CA 93514-3423
10	Alpine (Alp), Amador (Ama), Calaveras (Cal), Mariposa (Mpa), Merced (Mer), San Joaquin (SJ), Stanislaus (Sta), Tuolumne (Tuo)	1976 E CHARTER WAY STOCKTON, CA	PO BOX 2048 STOCKTON CA 95201
11	Imperial (Imp), San Diego (SD)	4050 TAYLOR ST SAN DIEGO, CA	4050 TAYLOR ST SAN DIEGO CA 92110-2737
12	Orange (Ora)	3347 MICHELSON DR STE 100 IRVINE, CA	3347 MICHELSON DR STE 100 IRVINE CA 92612-0661

A project with work in District 1, 2, or 3 is a North Region project. For Districts 1, 2, and 3, interpret each reference to the district office as the North Region office. The North Region office address is the District 3 address.

**1-6 WEB SITES, ADDRESSES, AND TELEPHONE NUMBERS**

**Web Sites, Addresses, and Telephone Numbers**

Agency, Department Unit, or Reference	Web Site	Address	Telephone No.
Bid Document Unit		MSC 26 BID DOCUMENT UNIT DEPARTMENT OF TRANSPORTATION 1120 N ST RM 200 SACRAMENTO CA 95814-5605	
Department	<a href="http://www.dot.ca.gov">www.dot.ca.gov</a>		
Department of General Services, Office of Small Business and DVBE Services	<a href="http://www.pd.dgs.ca.gov/smbus/default.htm">www.pd.dgs.ca.gov/smbus/default.htm</a>	OFFICE OF SMALL BUSINESS AND DVBE SERVICES DEPARTMENT OF GENERAL SERVICES 707 3RD ST WEST SACRAMENTO CA 95605-2811	(800) 559-5529 (916) 375-4940
Department of Industrial Relations	<a href="http://www.dir.ca.gov">www.dir.ca.gov</a>		
Department of Industrial Relations, Division of Apprenticeship Standards		455 GOLDEN GATE AVENUE SAN FRANCISCO, CA 94102	
Office Engineer		MSC 43 OFFICE ENGINEER DEPARTMENT OF TRANSPORTATION 1727 30TH ST SACRAMENTO CA 95816-7005	
Office Engineer– Verified Bid Results	<a href="http://www.dot.ca.gov/hq/esc/oe/awards/bidsum_html/6week_list.html">http://www.dot.ca.gov/hq/esc/oe/awards/bidsum_html/6week_list.html</a>		
Offices of Structure Design, Documents Unit		MSC 9-4/4I DOCUMENTS UNIT OFFICES OF STRUCTURE DESIGN DEPARTMENT OF TRANSPORTATION 1801 30TH ST SACRAMENTO CA 95816-7006	(916) 227-8252
Publication Distribution Unit		PUBLICATION UNIT DEPARTMENT OF TRANSPORTATION 1900 ROYAL OAKS DRIVE SACRAMENTO CA 95815-3800	
Transportation Laboratory		MATERIALS AND ENGINEERING TESTING SERVICES AND GEOTECHNICAL SERVICES DEPARTMENT OF TRANSPORTATION 5900 FOLSOM BLVD SACRAMENTO CA 95819-4612	(916) 227-7000
Department's Pre- Qualified Products List	<a href="http://www.dot.ca.gov/hq/esc/approved_products_list">http://www.dot.ca.gov/hq/esc/approved_products_list</a>		



As-built drawings may not show existing dimensions and conditions. Where new construction dimensions are dependent on existing bridge dimensions, verify the field dimensions and adjust dimensions of the work to fit existing conditions.

## **2-1.04–2-1.10 RESERVED**

### **2-1.11 JOB SITE AND DOCUMENT EXAMINATION**

Examine the job site and bid documents.

Bid submission is your acknowledgment that you have examined the job site and bid documents and are satisfied with:

1. General and local conditions to be encountered
2. Character, quality, and scope of work to be performed
3. Quantities of materials to be furnished
4. Character, quality, and quantity of surface and subsurface materials or obstacles
5. Requirements of the contract

### **2-1.12 BID DOCUMENT COMPLETION**

#### **2-1.12A General**

Complete forms in the Bid book.

On the Subcontractor List you may either submit each subcontracted bid item number and corresponding percentage with your bid or fax this information to (916) 227-6282 within 24 hours after bid opening. If you fail to submit this information within the time specified, your bid is nonresponsive.

Except for the bid item number and the percentage of each item subcontracted, do not fax submittals.

#### **2-1.12B Bid Item List and Bid Comparison**

Submit a bid based on the work item quantities the Department shows in the Bid Item List.

For a lump sum based bid, the Department compares bids based on the total price.

For a unit price based bid, the Department compares bids based on the sum of the item totals.

For a cost plus time based bid, the Department compares bids based on the sum of the item totals and the total bid for time. If your bid for time exceeds the number of working days described in the Notice to Bidders, your bid is nonresponsive.

#### **2-1.12C Subcontractor List**

In the Subcontractor List, list each subcontractor to perform work in an amount in excess of 1/2 of 1 percent of the total bid or \$10,000, whichever is greater (Pub Cont Code § 4100 et seq.)

The Subcontractor List must show the name, address, and work portions to be performed by each subcontractor listed. Show work portion by bid item number, description, and percentage of each bid item subcontracted.

### **2-1.13 BIDDER'S SECURITY**

Submit your bid with one of the following forms of bidder's security equal to at least 10 percent of the bid:

1. Cash
2. Cashier's check
3. Certified check
4. Bidder's bond signed by a surety insurer who is licensed in California

Make checks and bonds payable to the Department of Transportation.

If paying with a bidder's bond, you may use the form in the Bid book. If you do not use the form in the Bid book, use a form containing the same information.

### **2-1.14 BID SUBMITTAL**

Submit your bid:

1. Under sealed cover
2. Marked as a bid
3. Identifying the contract number and the bid opening date



**Contract Award Period**

Days	Project Estimated Cost shown in the Notice to Bidders
30	< \$200 million
60	≥ \$200 million

The Department may extend the specified award period if the bidder agrees.

**3-1.03 CONTRACT BONDS (PUB CONT CODE §§ 10221 AND 10222)**

The successful bidder must furnish 2 bonds:

1. Payment bond to secure the claim payments of laborers, workers, mechanics, or materialmen providing goods, labor, or services under the contract. This bond must be equal to at least 100 percent of the total bid.
2. Performance bond to guarantee the faithful performance of the contract. This bond must be equal to at least 50 percent of the total bid.

The Department furnishes the successful bidder with bond forms.

**3-1.04 CONTRACTOR LICENSE**

For a Federal-aid contract, the Contractor must be properly licensed as a contractor (Pub Cont Code § 10164) from contract award through contract acceptance.

For a non-Federal-aid contract:

1. The Contractor must be properly licensed as a contractor from bid opening through contract acceptance (Bus & Prof Code § 7028.15)
2. Joint venture bidders must obtain a joint venture license before contract award (Bus & Prof Code § 7029.1)

**3-1.05 INSURANCE POLICIES**

The successful bidder must submit:

1. Copy of its commercial general liability policy and its excess policy or binder until such time as a policy is available, including the declarations page, applicable endorsements, riders, and other modifications in effect at the time of contract execution. Standard ISO form No. CG 0001 or similar exclusions are allowed if not inconsistent with Section 7-1.12, "Indemnification and Insurance." Allowance of additional exclusions is at the discretion of the Department.
2. Certificate of insurance showing all other required coverages. Certificates of insurance, as evidence of required insurance for the auto liability and any other required policy, shall set forth deductible amounts applicable to each policy and all exclusions that are added by endorsement to each policy. The evidence of insurance shall provide that no cancellation, lapse, or reduction of coverage will occur without 10 days prior written notice to the Department.
3. A declaration under the penalty of perjury by a CPA certifying the accountant has applied GAAP guidelines confirming the successful bidder has sufficient funds and resources to cover any self-insured retentions if the self-insured retention is \$50,000 or higher.

If the successful bidder uses any form of self-insurance for workers compensation in lieu of an insurance policy, it shall submit a certificate of consent to self-insure under Labor Code § 3700.

**3-1.06 RESERVED**

**3-1.07 PAYEE DATA RECORD**

Complete and sign the Payee Data Record form included in the contract documents.

**3-1.08 RESERVED**

**3-1.09 CONTRACT EXECUTION**

The successful bidder must sign the contract.

Deliver to the Office Engineer:

1. Signed Contract form
2. Contract bonds
3. Documents identified in Section 3-1.05, "Insurance Policies"
4. Payee data record

For a non-informal-bid contract, the Office Engineer must receive these documents before the 10th business day after the bidder receives the contract.

For an informal-bid contract, the Office Engineer must receive these documents before the 5th business day after the bidder receives the contract.

The bidder's security may be forfeited for failure to execute the contract (Pub Cont Code §§ 10181 and 10182).

The following is a copy of the Contract form:



STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION  
CONTRACT NO. \_\_\_\_\_

This contract is entered into between the State of California's Department of Transportation and the Contractor named below.

\_\_\_\_\_  
CONTRACTOR'S NAME

The parties agree to comply with the terms of the following exhibits that are by this reference made a part of this contract.

- Exhibit A - Bid book dated \_\_\_\_\_
- Exhibit B - Notice to Bidders and Special Provisions dated \_\_\_\_\_
- Exhibit C - Project Plans approved \_\_\_\_\_
- Exhibit D - Standard Specifications dated \_\_\_\_\_
- Exhibit E - Amendments to the Standard Specifications dated \_\_\_\_\_
- Exhibit F - Standard Plans dated \_\_\_\_\_
- Exhibit G - Addenda \_\_\_\_\_

Exhibits A, B, C, and G are those exhibits identified with the same contract number as this contract.

**This contract has been executed by the following parties:**

\_\_\_\_\_  
**CONTRACTOR**

CONTRACTOR'S NAME (if other than an individual, state whether a corporation, partnership, etc.)

BY (Authorized Signature) \_\_\_\_\_ DATE SIGNED (Do not type) \_\_\_\_\_

PRINTED NAME AND TITLE OF PERSON SIGNING \_\_\_\_\_

FEDERAL EMPLOYER IDENTIFICATION NUMBER \_\_\_\_\_ LICENSE NUMBER \_\_\_\_\_

\_\_\_\_\_  
**DEPARTMENT OF TRANSPORTATION**

BY (Authorized Signature) \_\_\_\_\_ DATE SIGNED (Do not type) \_\_\_\_\_

PRINTED NAME AND TITLE OF PERSON SIGNING \_\_\_\_\_

**This contract has been certified as complying with the State Contract Act:**

BY (Authorized Signature) \_\_\_\_\_ DATE SIGNED (Do not type) \_\_\_\_\_

PRINTED NAME AND TITLE OF PERSON SIGNING \_\_\_\_\_

**ADA Notice** For individuals with sensory disabilities, this document is available in alternate formats. For information call (916) 654-6410 or TDD (916) 654-3880 or write Records and Forms Management, 1120 N Street, MS-89, Sacramento, CA 95814.

**3-1.10 BIDDERS' SECURITIES**

The Department keeps the securities of the 1st, 2nd, and 3rd lowest responsible bidders until the contract has been executed. The other bidders' securities, other than bidders' bonds, are returned upon determination of the 1st, 2nd, and 3rd apparent lowest bidders, and their bidders' bonds are of no further effect.



The Department is not required to consider a VECP. If a VECP is similar to a change in the plans or specifications being considered by the Department at the time the proposal is submitted or if the proposal is based on or similar to drawings or specifications adopted by the Department before Contract award, the Department does not accept the VECP and may make these changes without VECP payments.

Until the Department approves a change order incorporating the VECP or parts of it, continue to perform the work under the contract. If the Department does not approve a change order before the deadline stated in the VECP or other date you subsequently stated in writing, the VECP is rejected. The Department does not adjust time or payment for a rejected VECP.

The Department decides whether to accept a VECP and the estimated net construction-cost savings from adopting the VECP or parts of it.

The Department may require you to accept a share of the investigation cost as a condition of reviewing a VECP. After written acceptance, the Department considers the VECP and deducts the agreed cost.

If the Department accepts the VECP or parts of it, the Department issues a change order that:

1. Incorporates changes in the contract necessary to implement the VECP or the parts adopted
2. Includes the Department's acceptance conditions
3. States the estimated net construction-cost savings resulting from the VECP
4. Obligates the Department to pay you 50 percent of the estimated net savings

In determining the estimated net construction-cost savings, the Department excludes your VECP preparation cost and the Department's VECP investigation cost, including parts paid by you.

If a VECP providing for a reduction in working days is accepted by the Department, 50 percent of the reduction is deducted from contract time.

If a VECP providing for a reduction in traffic congestion or avoiding traffic congestion is accepted by the Department, the Department pays 60 percent of the estimated net savings in construction costs attributable to the VECP. Submit detailed traffic handling comparisons between the existing contract and the proposed change, including estimates of the traffic volumes and congestion.

The Department may apply an accepted VECP for general use on other contracts.

If an accepted VECP is adopted for general use, the Department pays only the contractor who first submitted the VECP and only to the contracts awarded to that contractor before the submission of the accepted VECP.

If the Department does not adopt a general-use VECP, an identical or similar submitted proposal is eligible for acceptance.

#### **4-1.035C Value Analysis Workshop**

Section 4-1.035C, "Value Analysis Workshop," applies to a non-building-work contract with a total bid of over \$5 million.

You may request a value analysis workshop by submitting a request after contract approval.

The Department offers a value analysis workshop to:

1. Identify value enhancing opportunities
2. Consider changes to the contract that will reduce the total cost of construction, construction activity duration, or traffic congestion without impairing the essential functions specified for a VECP in Section 4-1.035B, "Value Engineering Change Proposal."

If the request is authorized, you and the Engineer:

1. Schedule a value analysis workshop
2. Select a facilitator and workshop site
3. Agree to other workshop administrative details

The workshop must be conducted under the methods described in the Department's Value Analysis Team Guide available at:

<http://www.dot.ca.gov/hq/oppd/value/>

The facilitator must be a certified value specialist as recognized by the Society of American Value Engineers.

The Department reimburses you for 1/2 of the workshop cost. The workshop cost is the sum of the workshop-facilitator cost and the workshop-site cost. The Department determines the workshop cost based on the facilitator and workshop-site invoice prices minus any available or offered discounts. The Department does not pay you for any other associated costs.



## 8. Establishing periodic joint evaluations of the partnering process and attainment of mutual goals

Partnering does not void any contract part.

The Department's "Field Guide to Partnering on Caltrans Construction Projects" current at the time of bid is available to the project team as reference. This guide provides structure, context, and clarity to the partnering process requirements. This guide is available at the Department's Partnering Program website:

<http://www.dot.ca.gov/hq/construc/partnering.html>

In implementing project partnering, the project team must:

1. Create a partnering charter that includes:
  - 1.1. Mutual goals, including core project goals and may also include project-specific goals and mutually supported individual goals.
  - 1.2. Partnering maintenance and close-out plan.
  - 1.3. Dispute resolution plan that includes a dispute resolution ladder and may also include use of facilitated dispute resolution sessions.
  - 1.4. Team commitment statement and signatures.
2. Participate in monthly partnering evaluation surveys to measure progress on mutual goals and may also measure short-term key issues as they arise.
3. Evaluate the partnering facilitator on Forms CEM-5501 and CEM-5502. The Engineer provides the evaluation forms to the project team and collects the results. The Department makes evaluation results available upon request. Facilitator evaluations must be completed:
  - 3.1. At the end of the initial partnering workshop on Form CEM-5501.
  - 3.2. At the end of the project close-out partnering workshop on Form CEM-5502.
4. Conduct a project close-out partnering workshop.
5. Document lessons learned before contract acceptance.

### **5-1.012B Partnering Facilitator, Workshops, and Monthly Evaluation Surveys**

The Engineer sends you a written invitation to enter into a partnering relationship after contract approval. Respond within 15 days to accept the invitation and request the initial and additional partnering workshops. After the Engineer receives the request, you and the Engineer cooperatively:

1. Select a partnering facilitator that offers the service of a monthly partnering evaluation survey with a 5-point rating and agrees to follow the Department's "Partnering Facilitator Standards and Expectations" available at the Department's Partnering Program website
2. Schedule initial partnering workshop
3. Determine initial workshop site and duration
4. Agree to other workshop administrative details

Additional partnering workshops and sessions are encouraged throughout the life of the project as determined necessary by you and the Engineer, recommended quarterly.

### **5-1.012C Training in Partnering Skills Development**

For a project with a total bid of \$25 million or greater, training in partnering skills development is required.

For a project with a total bid between \$10 million and \$25 million, training in partnering skills is optional.

You and the Engineer cooperatively schedule the training session and select a professional trainer, training site, and 1 to 4 topics from the following list to be covered in the training:

1. Active Listening
2. Building Teams
3. Change Management
4. Communication
5. Conflict Resolution

6. Cultural Diversity
7. Dealing with Difficult People
8. Decision Making
9. Effective Escalation Ladders
10. Emotional Intelligence
11. Empathy
12. Ethics
13. Facilitation Skills
14. Leadership
15. Partnering Process and Concepts
16. Project Management
17. Project Organization
18. Problem Solving
19. Running Effective Meetings
20. Time Management
21. Win-Win Negotiation

Before the initial partnering workshop, the trainer conducts a 1-day training session in partnering skills development for the Contractor's and the Engineer's representatives. This training session must be a separate session from the initial partnering workshop and must be conducted locally. The training session must be consistent with the partnering principles under the Department's "Field Guide to Partnering on Caltrans Construction Projects."

Send at least 2 representatives to the training session. One of these must be your assigned representative as specified in Section 5-1.06, "Superintendence," of the Standard Specifications.

#### **5-1.012D Payment**

The Department pays you for:

1. 1/2 of partnering workshops and sessions based on facilitator and workshop site cost
2. 1/2 of monthly partnering evaluation survey service cost
3. Partnering skills development trainer and training site cost

The Department determines the costs based on invoice prices minus any available or offered discounts. The Department does not pay markups on these costs.

The Department does not pay for wages, travel expenses, or other costs associated with the partnering workshops and sessions, monthly partnering evaluation surveys, and training in partnering skills development.

#### **Add:**

#### **5-1.015 RECORDS**

##### **5-1.015A General**

Reserved

##### **5-1.015B Record Retention**

Retain project records from bid preparation through:

1. Final payment
2. Resolution of claims, if any

For at least 3 years after the later of these, retain cost records, including records of:

1. Bid preparation
2. Overhead
3. Payrolls
4. Payments to suppliers and subcontractors
5. Cost accounting

Maintain the records in an organized way in the original format, electronic and hard copy, conducive to professional review and audit.

### **5-1.015C Record Inspection, Copying, and Auditing**

Make your records available for inspection, copying, and auditing by State representatives for the same time frame specified under Section 5-1.015B, "Record Retention." The records of subcontractors and suppliers must be made available for inspection, copying, and auditing by State representatives for the same period. Before contract acceptance, the State representative notifies the Contractor, subcontractor, or supplier 5 business days before inspection, copying, or auditing.

If an audit is to start more than 30 days after contract acceptance, the State representative notifies the Contractor, subcontractor, or supplier when the audit is to start.

### **5-1.015D Cost Accounting Records**

Maintain cost accounting records for the project distinguishing between the following work cost categories:

1. Contract item work
2. Work character changes
3. Force account work
4. Extra work
5. Work performed under protests and claim notifications
6. Overhead
7. Subcontractors, suppliers, owner-operators, and professional services

Cost accounting records must include:

1. Final cost code lists and definitions
2. Itemization of the materials used and corresponding vendor's invoice copies
3. Direct cost of labor
4. Equipment rental charges
5. Workers' certified payrolls
6. Equipment:
  - 6.1. Size
  - 6.2. Type
  - 6.3. Identification number
  - 6.4. Hours operated

### **5-1.015E Extra Work Bills**

Maintain separate records for force account costs.

Submit extra work bills using the Department's Internet extra work billing system.

The Contractor submitting and the Engineer approving an extra work bill using the Internet force account work billing system is the same as each party signing the report.

The Department provides billing system:

1. Training within 30 days of your written request
2. Accounts and user identification to your assigned representatives after a representative has received training

Each representative must maintain a unique password.

### **Replace Section 5-1.02A with:**

#### **5-1.02A Excavation Safety Plans**

The Construction Safety Orders of the Division of Occupational Safety and Health shall apply to all excavations. For all excavations 1.5 m or more in depth, the Contractor shall submit to the Engineer a detailed plan showing the design and details of the protective systems to be provided for worker protection from the hazard of caving ground during excavation. The detailed plan shall include any tabulated data and any design calculations used in the preparation of the plan. Excavation shall not begin until the detailed plan has been reviewed and approved by the Engineer.

Detailed plans of protective systems for which the Construction Safety Orders require design by a registered professional engineer shall be prepared and signed by an engineer who is registered as a Civil Engineer in the State of California, and shall include the soil classification, soil properties, soil design calculations that demonstrate adequate stability of the protective system, and any other design calculations used in the preparation of the plan.

No plan shall allow the use of a protective system less effective than that required by the Construction Safety Orders.

If the detailed plan includes designs of protective systems developed only from the allowable configurations and slopes, or Appendices, contained in the Construction Safety Orders, the plan shall be submitted at least 5 days before the Contractor intends to begin excavation. If the detailed plan includes designs of protective systems developed from tabulated data, or designs for which design by a registered professional engineer is required, the plan shall be submitted at least 3 weeks before the Contractor intends to begin excavation.

Attention is directed to Section 7-1.01E, "Trench Safety."

**Replace Section 5-1.04 with:**

**5-1.04 CONTRACT COMPONENTS**

A component in one contract part applies as if appearing in each. The parts are complementary and describe and provide for a complete work.

If a discrepancy exists:

1. The governing ranking of contract parts in descending order is:
  - 1.1. Special provisions
  - 1.2. Project plans
  - 1.3. Revised Standard Plans
  - 1.4. Standard Plans
  - 1.5. Amendments to the Standard Specifications
  - 1.6. Standard Specifications
  - 1.7. Supplemental project information
2. Written numbers and notes on a drawing govern over graphics
3. A detail drawing governs over a general drawing
4. A detail specification governs over a general specification
5. A specification in a section governs over a specification referenced by that section

If a discrepancy is found or confusion arises, request correction or clarification.

**Add:**

**5-1.055 SUBCONTRACTING**

**5-1.055A General**

No subcontract releases you from the contract or relieves you of your responsibility for a subcontractor's work.

If you violate Pub Cont Code § 4100 et seq., the Department may exercise the remedies provided under Pub Cont Code § 4110. The Department may refer the violation to the Contractors State License Board as provided under Pub Cont Code § 4111.

Perform work equaling at least 30 percent of the value of the original total bid with your employees and with equipment owned or rented by you, with or without operators.

Each subcontract must comply with the contract.

Each subcontractor must have an active and valid State contractor's license with a classification appropriate for the work to be performed (Bus & Prof Code, § 7000 et seq.).

Submit copies of subcontracts upon request.

Before subcontracted work starts, submit a Subcontracting Request form.

Do not use a debarred contractor; a current list of debarred contractors is available at the Department of Industrial Relations' Web site.

Upon request, immediately remove and not again use a subcontractor who fails to prosecute the work satisfactorily.

**Replace Section 5-1.07 with:**

**5-1.07 LINES AND GRADES**

The Engineer places stakes and marks under Chapter 12, "Construction Surveys," of the Department's Surveys Manual. Submit your request for Department-furnished stakes:

1. On a Request for Construction Stakes form. Ensure:
  - 1.1. Requested staking area is ready for stakes
  - 1.2. You use the stakes in a reasonable time
2. A reasonable time before starting an activity using the stakes

Establish priorities for stakes and note priorities on the request.

Preserve stakes and marks placed by the Engineer. If the stakes or marks are destroyed, the Engineer replaces them at the Engineer's earliest convenience and deducts the cost.

**Replace Section 5-1.116 with:**

**5-1.116 DIFFERING SITE CONDITIONS (23 CFR 635.109)**

**5-1.116A Contractor's Notification**

Promptly notify the Engineer if you find either of the following:

1. Physical conditions differing materially from either of the following:
  - 1.1. Contract documents
  - 1.2. Job site examination
2. Physical conditions of an unusual nature, differing materially from those ordinarily encountered and generally recognized as inherent in the work provided for in the contract

Include details explaining the information you relied on and the material differences you discovered.

If you fail to notify the Engineer promptly, you waive the differing site condition claim for the period between your discovery of the differing site condition and your notification to the Engineer.

If you disturb the site after discovery and before the Engineer's investigation, you waive the differing site condition claim.

**5-1.116B Engineer's Investigation and Decision**

Upon your notification, the Engineer investigates job site conditions and:

1. Notifies you whether to resume affected work
2. Decides whether the condition differs materially and is cause for an adjustment of time, payment, or both

**5-1.116C Protests**

You may protest the Engineer's decision by:

1. Submitting an Initial Notice of Potential Claim within 5 business days after receipt of the Engineer's notification
2. Complying with claim procedures

The Initial Notice of Potential Claim must detail the differences in your position from the Engineer's determination and support your position with additional information, including additional geotechnical data. Attach to the Initial Notice of Potential Claim a certification stating that you complied with Section 2-1.11, "Job Site and Document Examination."

Promptly submit supplementary information when obtained.

**Replace Section 5-1.14 with:**

**5-1.14 COST REDUCTION INCENTIVE**

Comply with Section 4-1.035B, "Value Engineering Change Proposal."

**Add:**

## **5-1.15 DISPUTE RESOLUTION**

### **5-1.15A General**

Section 5-1.15, "Dispute Resolution," applies to a contract with 100 or more working days.

In the Dispute Resolution Advisor Agreement and in the Dispute Review Board Agreement, interpret a reference to the special provisions as a reference to the Amendments to the Standard Specifications. In the Dispute Review Board Agreement, replace "Proposal and Contract" with "Bid book." Where the section title does not match the section number for a reference, refer to the referenced title.

### **5-1.15B Dispute Resolution Advisor**

Section 5-1.15B, "Dispute Resolution Advisor," applies to a contract from \$3 million to \$10 million.

A dispute resolution advisor, hereinafter referred to as "DRA", is chosen by the Department and the Contractor to assist in the resolution of disputes. The DRA is a part of the contract administrative claims process as specified in the provisions in Section 9-1.04, "Notice of Potential Claim," and Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications. The DRA shall not serve as a substitute for filing a protest or a notice of potential claim.

The DRA shall be established by the Department and the Contractor within 30 days of contract approval.

The Department and the Contractor shall each propose 3 potential DRA candidates. Each potential candidate shall provide the Department and the Contractor with their disclosure statement. The disclosure statement shall include a resume of the potential candidate's experience and a declaration statement describing past, present, anticipated, and planned relationships with all parties involved in this contract.

The Department and the Contractor shall select one of the 6 nominees to be the DRA. If the Department and the Contractor cannot agree on one candidate, the Department and the Contractor shall each choose one of the 3 nominated by the other. The final selection of the DRA will be decided by a coin toss between the two candidates.

The Department and the Contractor shall complete and adhere to the Dispute Resolution Advisor Agreement. No DRA meeting shall take place until the Dispute Resolution Advisor Agreement has been signed by all parties, unless all parties agree to sign it at the first meeting.

If DRA needs outside technical services, technical services shall be preapproved by both the Department and the Contractor.

DRA recommendations are nonbinding.

The Contractor shall not use the DRA for disputes between subcontractors or suppliers that have no grounds for a lawsuit against the Department.

DRA replacement is selected in the same manner as the original selection. The appointment of a replacement DRA will begin promptly upon determination of the need for replacement. The Dispute Resolution Advisor Agreement shall be amended to reflect the change of the DRA.

Failure of the Contractor to participate in selecting DRA will result in the withhold of 25 percent of the estimated value of all work performed during each estimate period that the Contractor fails to comply. DRA withholds will be released for payment on the next monthly progress payment following the date that the Contractor has provided assistance in choosing the DRA and no interest will be due the Contractor.

The State and the Contractor shall bear the costs and expenses of the DRA equally.

The DRA shall be compensated at an agreed rate of \$1,500 per day for time spent per meeting either at the start of the project or for a dispute. A member serving on more than one State DRA or Dispute Review Board, regardless the number of meetings per day shall not be paid more than the agreed rate per day. The agreed rate shall be considered full compensation for on-site time, travel expenses, transportation, lodging, time for travel, and incidentals for each day or portion thereof that the DRA is at an authorized DRA meeting.

No additional compensation will be made for time spent by the DRA to review and research activities outside the official DRA meetings unless that time, such as time spent evaluating and preparing recommendations on specific issues presented to the DRA, has been specifically agreed to in advance by the State and Contractor. Time away from the project that has been specifically agreed to in advance by the Department and the Contractor will be compensated at an agreed rate of \$150 per hour. The agreed amount of \$150 per hour shall include all incidentals including expenses for telephone, fax, and computer services.

The State will provide conference facilities for DRA meetings at no cost to the Contractor.

The Contractor shall make direct payments to the DRA for participation in authorized meetings and approved hourly rate charges from invoices submitted.

The State will reimburse the Contractor for the State's share of the costs.

There will be no markups applied to expenses associated with the DRA, either by the DRA or by the Contractor when requesting payment of the State's share of DRA expenses. Regardless of the DRA recommendation, neither party will be entitled to reimbursement of DRA costs from the other party.

The Contractor shall submit extra work bills and include invoices with original supporting documents for reimbursement of the State's share.

The cost of technical services will be borne equally by the State and Contractor. There will be no markups for these costs.

A copy of the "Dispute Resolution Advisor Agreement" to be executed by the Contractor, State and the DRA is as follows:

Form CEM 6206 Rev (04-06-07)

**DISPUTE RESOLUTION ADVISOR AGREEMENT**

\_\_\_\_\_  
(Contract Identification)

Contract No. \_\_\_\_\_

**THIS DISPUTE RESOLUTION ADVISOR AGREEMENT, hereinafter called "AGREEMENT"**, made and entered into this \_\_\_\_\_ day of \_\_\_\_\_, \_\_\_\_\_, between the State of California, acting through the California Department of Transportation and the Director of Transportation, hereinafter called the "STATE," \_\_\_\_\_ hereinafter called the "CONTRACTOR," and \_\_\_\_\_, the Dispute Resolution Advisor, hereinafter called the "DRA." .

WITNESSETH, that

WHEREAS, the STATE and the CONTRACTOR, hereinafter called the "parties," are now engaged in the construction on the State Highway project referenced above; and

WHEREAS, the special provisions for the above referenced contract provides for the establishment and operation of the DRA to assist in resolving disputes; and

WHEREAS, the DRA is composed of one person, chosen by the CONTRACTOR and the STATE;

NOW THEREFORE, in consideration of the terms, conditions, covenants, and performance contained herein, or attached and incorporated and made a part hereof, the STATE, the CONTRACTOR, and the DRA hereto agree as follows:

**SECTION I DESCRIPTION OF WORK**

To assist in the timely resolution of disputes between the parties, the contract provides for the establishment and the operation of the DRA. The DRA is to fairly and impartially consider disputes placed before it and provide recommendations for resolution of these disputes to the parties. The DRA shall provide recommendations based on the facts related to the dispute, the contract and applicable laws and regulations. The DRA shall perform the services necessary to participate in the DRA's actions as designated in Section III, Scope of Work.

**SECTION II DRA QUALIFICATIONS**

DRA shall be knowledgeable in the type of construction and contract documents anticipated by the contract and shall have completed training through the Dispute Review Board Foundation. In addition, it is desirable for the DRA to have served on several State Dispute Review Boards (DRB).

No DRA shall have prior direct involvement in this contract. No DRA shall have a financial interest in this contract or parties thereto, including but not limited to the CONTRACTOR, subcontractors, suppliers, consultants, and legal and business services, within a period 6 months prior to award and during this contract. Exceptions to above are compensation for services on this or other DRAs and DRBs or retirement payments or pensions received from a party that are not tied to, dependent on or affected by the net worth of the party.

DRA shall fully disclose all direct or indirect professional or personal relationships with all key members of the contract.

**SECTION III SCOPE OF WORK**

The Scope of Work of the DRA includes, but is not limited to, the following:

**A. PROCEDURES**

The DRA shall meet with the parties at the start of the project to establish procedures that will govern the conduct of its business and reporting procedures in conformance with the requirements of the contract and the terms of this AGREEMENT.

The DRA established procedures shall only be implemented upon approval by the parties. Subsequent meetings shall be held only to hear disputes between the parties.

The DRA shall not meet with, or discuss contract issues with individual parties.

State shall provide the DRA with the contract and all written correspondence regarding the dispute between the parties and, if available, the Contractor's supplemental notice of potential claim, and the Engineer's response to the supplemental notice of potential claim.

The parties shall not call the DRA who served on this contract as a witness in arbitration proceedings, which may arise from this contract.

The DRA shall have no claim against the STATE or the CONTRACTOR, or both, from claimed harm arising out of the parties' evaluations of the DRA's opinions.

## **B. DISPUTE MEETING**

The term "dispute meeting" as used in this subsection shall refer to both the informal and traditional dispute meeting processes, unless otherwise noted.

If the CONTRACTOR requests a dispute meeting with the DRA, the Contractor must simultaneously notify the STATE. Upon being notified of the need for a dispute meeting, the DRA shall review and consider the dispute. The DRA shall determine the time and location of the dispute meeting with due consideration for the needs and preferences of the parties, while recognizing the importance of a speedy resolution to the dispute.

Dispute meetings shall be conducted at any location that would be convenient and provide required facilities and access to necessary documentation.

Only the STATE's Resident Engineer or Area Construction Engineer and the CONTRACTOR's or subcontractor's, if the dispute involves a subcontractor, Superintendent or Project Manager may present information at a dispute meeting. There shall be no participation of persons who are not directly involved in the contract or who do not have direct knowledge of the dispute. The exception to this is technical services, as described below:

The DRA, with approval of the parties, may obtain technical services necessary to adequately review the disputes presented, including audit, geotechnical, schedule analysis and other services. The parties' technical staff may supply those services as appropriate. The cost of technical services, as agreed to by the parties, shall be borne equally by the two parties as specified in an approved contract change order. The CONTRACTOR shall not be entitled to markups for the payments made for these services.

At the dispute meeting the DRA may ask questions, seek clarification, and request further clarification of data presented by either of the parties as may be necessary to assist in making a fully informed recommendation. However, the DRA shall refrain from expressing opinions on the merits of statements on matters under dispute during the parties' presentations. Each party will be given ample time to fully present its position, make rebuttals, provide relevant documents, and respond to DRA questions and requests.

There shall be no testimony under oath or cross-examination, during DRA dispute meetings. There shall be no reporting of the procedures by a shorthand reporter or by electronic means. Documents and verbal statements shall be received by the DRA in conformance with the rules and regulations established at the first meeting between the DRA and parties. These established rules and regulations need not comply with prescribed legal laws of evidence.

Failure to attend a dispute meeting by either of the parties shall be conclusively considered by the DRA as indication that the non-attending party considers all written documents and correspondence submitted as their entire and complete argument. The claimant shall discuss the dispute, followed by the other party. Each party shall then be allowed one or more rebuttals at the meeting until all aspects of the dispute are thoroughly covered.

### **1. TRADITIONAL DISPUTE MEETING:**

The following procedure shall be used for the traditional dispute meeting:

- a. Within 5 days, after receiving the STATE's written response to the CONTRACTOR's supplemental notice of potential claim, the CONTRACTOR shall refer the dispute to the DRA, if the CONTRACTOR wishes to further pursue the dispute. The CONTRACTOR shall make the referral in writing to the DRA, simultaneously copied to the STATE. The written dispute referral shall describe the disputed matter in individual discrete segments, so that it will be clear to both parties and the DRA what discrete elements of the dispute have been resolved, and which remain unresolved, and shall include an estimate of the cost of the affected work and impacts, if any, on project completion.
- b. The parties shall each be afforded an opportunity to be present and to be heard by the DRA, and to offer evidence. Either party furnishing written evidence or documentation to the DRA must furnish copies of such information to the other party a minimum of 10 days prior to the date the DRA is scheduled to convene the meeting for the dispute. Either party shall produce such additional evidence as the DRA may deem necessary to

reach an understanding and a determination of the dispute. The party furnishing additional evidence shall furnish copies of such additional evidence to the other party at the same time the evidence is provided to the DRA. The DRA shall not consider evidence not furnished in conformance with the terms specified herein.

- c. Upon receipt by the DRA of a written referral of a dispute, the DRA shall convene to review and consider the dispute. The dispute meeting shall be held no later than 25 days after receipt of the written referral unless otherwise agreed to by all parties.
- d. The DRA shall furnish a written report to both parties. The DRA may request clarifying information of either party within 5 days after the DRA dispute meeting. Requested information shall be submitted to the DRA within 5 days of the DRA request. The DRA shall complete its report and submit it to the parties within 10 days of the DRA dispute meeting, except that time extensions may be granted at the request of the DRA with the written concurrence of both parties. The report shall summarize the facts considered, the contract language, law or regulation viewed by the DRA as pertinent to the dispute, and the DRA's interpretation and philosophy in arriving at its conclusions and recommendations and, if appropriate, recommends guidelines for determining compensation. The DRA's written opinion shall stand on its own, without attachments or appendices.
- e. Within 10 days after receiving the DRA's report, both parties shall respond to the DRA in writing signifying that the dispute is either resolved or remains unresolved. Failure to provide the written response within the time specified, or a written rejection of the DRA's recommendation or response to a request for reconsideration presented in the report by either party, shall conclusively indicate that the party(s) failing to respond accepts the DRA recommendation. Immediately after responses have been received from both parties, the DRA shall provide copies of both responses to the parties simultaneously. Either party may request clarification of elements of the DRA's report from the DRA prior to responding to the report. The DRA shall consider any clarification request only if submitted within 5 days of receipt of the DRA's report, and if submitted simultaneously in writing to both the DRA and the other party. Each party may submit only one request for clarification for any individual DRA report. The DRA shall respond, in writing, to requests for clarification within 5 days of receipt of such requests.
- f. Either party may seek a reconsideration of the DRA's recommendation. The DRA shall only grant reconsideration based upon submission of new evidence and if the request is submitted within the 10 day time limit specified for response to the DRA's written report. Each party may submit only one request for reconsideration regarding an individual DRA recommendation.
- g. If the parties are able to settle their dispute with the aid of the DRA's report, the STATE and CONTRACTOR shall promptly accept and implement the settlement of the parties. If the parties cannot agree on compensation within 30 days of the acceptance by both parties of the settlement, either party may request the DRA to make a recommendation regarding compensation.

## **2. INFORMAL DISPUTE MEETING**

An informal dispute meeting shall be convened, only if, the parties and the DRA agree that this dispute resolution process is appropriate to settle the dispute.

The following procedure shall be used for the informal dispute meeting:

- a. The parties shall furnish the DRA with one copy of pertinent documents requested by the DRA that are or may become necessary for the DRA to perform its function. The party furnishing documents shall furnish such documents to the other party at the same time the document is provided to the DRA.
- b. After the dispute meeting has concluded; the DRA shall deliberate in private the same day, until a response to the parties is reached or as otherwise agreed to by the parties.
- c. The DRA then verbally delivers its recommendation with findings to the parties.
- d. After the recommendation is presented, the parties may ask for clarifications.
- e. Occasionally the DRA on complex issues may be unable to formulate a recommendation based on the information given at a dispute meeting. However, the DRA may provide the parties with advice on strengths and weaknesses of their prospective positions, in the hope of the parties reaching settlement.
- f. If the parties are able to settle their dispute with the aid of the DRA's opinion, the STATE and CONTRACTOR shall promptly accept and implement the settlement of the parties.
- g. The DRA will not be bound by its oral recommendation in the event that a dispute is later heard by the DRA in a traditional dispute meeting.

Unless the dispute is settled, use of the informal dispute meeting does not relieve the parties of their responsibilities under Section 5-1.12, "Dispute Resolution Advisor," of the Special Provisions or Subsection, "Traditional Dispute Meeting," of this AGREEMENT. There will be no extension of time allowed for the process to permit the use of the informal dispute meeting, unless otherwise agreed to by the parties.

## **SECTION IV TIME FOR BEGINNING AND COMPLETION**

Once established, the DRA shall be in operation until the day the Director accepts the contract. The DRA shall not begin work under the terms of this AGREEMENT until authorized in writing by the STATE or as agreed to by the parties.

## **SECTION V PAYMENT**

DRA shall be compensated at an agreed rate of \$1,500 per day for time spent per meeting, either at the start of the project or for a dispute. A member serving on more than one State DRA or DRB, regardless the number of meetings per day, shall not be paid more than the agreed rate per day. The agreed rate shall be considered full compensation for onsite time, travel expenses, transportation, lodging, time for travel and incidentals for each day, or portion thereof that the DRA is at an authorized DRA meeting. No additional compensation will be made for time spent by DRA to review and research activities outside the official DRA meetings unless that time, (such as time spent evaluating and preparing recommendations on specific issues presented to the DRA), has been specifically agreed to in advance by the parties. Time away from the project, which has been specifically agreed to in advance by the parties, will be compensated at an agreed rate of \$150 per hour. The agreed amount of \$150 per hour shall include all incidentals including expenses for telephone, fax, and computer services. The State will provide administrative services such as conference facilities to the DRA.

### **A. PAYMENT PROCESSING**

CONTRACTOR shall make direct payments to DRA for their participation in authorized meetings and approved hourly rate charges, from invoices submitted by the DRA, and technical services.

DRA may submit invoices to the CONTRACTOR for partial payment for work performed and services rendered for their participation in authorized meetings not more often than once per month during the progress of the work. The invoices shall be in a format approved by the parties and accompanied by a general description of activities performed during that billing period. Payment for hourly fees, at the agreed rate, shall not be paid to a DRA until the amount and extent of those fees are approved by the STATE and CONTRACTOR.

### **B. INSPECTION OF COSTS RECORDS**

DRA and the CONTRACTOR shall keep available for inspection by representatives of the STATE and the United States, for a period of 3 years after final payment, the cost records and accounts pertaining to this AGREEMENT. If any litigation, claim, or audit arising out of, in connection with, or related to this contract is initiated before the expiration of the 3-year period, the cost records and accounts shall be retained until such litigation, claim, or audit involving the records is completed.

## **SECTION VI ASSIGNMENT OF TASKS OF WORK**

DRA shall not assign the work of this AGREEMENT.

## **SECTION VII TERMINATION OF A DRA MEMBER**

DRA may resign after providing not less than 15 days written notice of the resignation to the STATE and CONTRACTOR. The DRA may be terminated, by either party, for failing to fully comply at all times with all required employment or financial disclosure conditions of DRA membership in conformance with the terms of the contract and this AGREEMENT. Each party shall document the need for replacement and substantiate the replacement request in writing to the other party and the DRA.

## **SECTION VIII LEGAL RELATIONS**

The parties hereto mutually understand and agree that the DRA in the performance of duties is acting in the capacity of an independent agent and not as an employee of either party.

No party to this AGREEMENT shall bear a greater responsibility for damages or personal injury than is normally provided by Federal or State of California Law.

Notwithstanding the provisions of this contract that require the CONTRACTOR to indemnify and hold harmless the STATE, the parties shall jointly indemnify and hold harmless the DRA from and against all claims, damages, losses, and expenses, including but not limited to attorney's fees, arising out of and resulting from the findings and recommendations of the DRA.

## **SECTION IX CONFIDENTIALITY**

The parties hereto mutually understand and agree that all documents and records provided by the parties in reference to issues brought before the DRA, which documents and records are marked "Confidential - for use by the DRA only," shall be kept in confidence and used only for the purpose of resolution of subject disputes, and for assisting in development of DRA

findings and recommendations; that such documents and records will not be utilized or revealed to others, except to officials of the parties who are authorized to act on the subject disputes, for any purposes, during the life of this AGREEMENT. Upon termination of this AGREEMENT, said confidential documents and records, and all copies thereof, shall be returned to the parties who furnished them to the DRA. However, the parties understand that such documents may be subsequently discoverable and admissible in court or arbitration proceedings unless a protective order has been obtained by the party seeking further confidentiality.

**SECTION X DISPUTES**

Disputes between the parties arising out of the work or other terms of this AGREEMENT that cannot be resolved by negotiation and mutual concurrence between the parties or through the administrative process provided in the contract shall be resolved by arbitration as provided in Section 9-1.10, "Arbitration," of the Standard Specifications. Disputes between the DRA and the parties that cannot be resolved by negotiation and mutual concurrence shall be resolved in the appropriate forum.

**SECTION XI VENUE, APPLICABLE LAW, AND PERSONAL JURISDICTION**

In the event that any party, including the DRA, deems it necessary to institute arbitration proceedings to enforce any right or obligation under this AGREEMENT, the parties hereto agree that such action shall be initiated in the Office of Administrative Hearings of the State of California. The parties hereto agree that all questions shall be resolved by arbitration by application of California law and that the parties to such arbitration shall have the right of appeal from such decisions to the Superior Court in conformance with the laws of the State of California. Venue for the arbitration shall be Sacramento or any other location as agreed to by the parties.

**SECTION XII FEDERAL REVIEW AND REQUIREMENTS**

On Federal-Aid contracts, the Federal Highway Administration shall have the right to review the work of the DRA in progress, except for private meetings or deliberations of the DRA. Other Federal requirements in this agreement shall only apply to Federal-Aid contracts.

**SECTION XIII CERTIFICATION OF CONTRACTOR, DRA, AND STATE**

IN WITNESS WHEREOF, the parties hereto have executed this AGREEMENT as of the day and year first above written.

DRA

By: \_\_\_\_\_

Title: \_\_\_\_\_

CONTRACTOR

CALIFORNIA STATE DEPARTMENT  
OF TRANSPORTATION

By: \_\_\_\_\_

By: \_\_\_\_\_

Title: \_\_\_\_\_

Title: \_\_\_\_\_

**5-1.15C Dispute Review Board**

- Section 5-1.15C, "Dispute Review Board," applies to a contract over \$10 million.

**5-1.15C(1) General**

To assist in the resolution of disputes or potential claims arising out of the work of this project, a Dispute Review Board, hereinafter referred to as the "DRB," shall be established by the Engineer and Contractor cooperatively upon approval of the contract. The DRB is intended to assist the contract administrative claims resolution process as specified in the provisions in Section 9-1.04, "Notice of Potential Claim," and Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications and these special provisions. The DRB shall not serve as a substitute for provisions in the specifications in regard to filing potential claims. The requirements and procedures established in this section shall be a prerequisite to filing a claim, filing for arbitration, or filing for litigation prior or subsequent to project completion.

The DRB shall be utilized when dispute or potential claim resolution at the project level is unsuccessful. The DRB shall function as specified herein until the day of acceptance of the contract, at which time the work of the DRB will cease except for completion of unfinished reports. No DRB dispute meetings shall take place later than 30 days prior to acceptance of

contract. After acceptance of contract, disputes or potential claims which have followed the dispute resolution processes of the Standard Specifications and these special provisions, but have not been resolved, shall be stated or restated by the Contractor, in response to the Proposed Final Estimate within the time limits provided in Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications. The State will review those claims in conformance with the provisions in Section 9-1.07B of the Standard Specifications. Following the adherence to and completion of the contractual administrative claims procedure, the Contractor may file for arbitration in conformance with the provisions in Section 9-1.10, "Arbitration," of the Standard Specifications and these special provisions.

Disputes, as used in this section, shall include differences of opinion, properly noticed as provided hereinafter, between the State and Contractor on matters related to the work and other subjects considered by the State or Contractor, or by both, to be of concern to the DRB on this project, except matters relating to Contractor, subcontractor or supplier potential claims not actionable against the Department as specified in these special provisions or quantification of disputes for overhead type expenses or costs. Disputes for overhead type expenses or costs shall conform to the requirements of Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications. Whenever the term "dispute" or "disputes" is used herein, it shall be deemed to include potential claims as well as disputes.

The DRB shall serve as an advisory body to assist in the resolution of disputes between the State and the Contractor, hereinafter referred to as the "parties." The DRB shall consider disputes referred to it, and furnish written reports containing findings and recommendations pertaining to those disputes, to the parties to aid in resolution of the differences between them. DRB findings and recommendations are not binding on the parties.

#### **5-1.15C(2) Selection Process, Disclosure and Appointments**

The DRB shall consist of one member selected by the State and approved by the Contractor, one member selected by the Contractor and approved by the State, and a third member selected by the first 2 members and approved by both the State and the Contractor. The third member shall act as the DRB Chairperson.

DRB members shall be especially knowledgeable in the type of construction and contract documents potentially anticipated by the contract. DRB members shall discharge their responsibilities impartially as an independent body, considering the facts and circumstances related to the matters under consideration, pertinent provisions of the contract and applicable laws and regulations.

The State and the Contractor shall nominate and approve DRB members in conformance with the terms and conditions of the Dispute Review Board Agreement and these special provisions, within 45 days of the approval of the contract. Each party shall provide written notification to the other of the name of their selected DRB nominee along with the prospective member's complete written disclosure statement.

Disclosure statements shall include a resume of the prospective member's experience and a declaration statement describing past, present, anticipated, and planned relationships, including indirect relationships through the prospective member's primary or full-time employer, to this project and with the parties involved in this construction contract, including but not limited to, relevant subcontractors or suppliers to the parties, parties' principals, or parties' counsel. DRB members shall also include a full disclosure of close professional or personal relationships with all key members of the contract. Objections to nominees must be based on a specific breach or violation of nominee responsibilities or on nominee qualifications under these provisions unless otherwise specified. The Contractor or the State may, on a one-time basis, object to the other's nominee without specifying a reason and this person will not be selected for the DRB. Another person shall then be nominated within 15 days.

The first duty of the State and Contractor selected members of the DRB shall be to select and recommend a prospective third DRB member to the parties for final selection and approval. The first 2 DRB members shall proceed with the selection of the third DRB member immediately upon receiving written notification from the State of their selection, and shall provide their recommendation simultaneously to the parties within 15 days of the notification.

The first 2 DRB members shall select a third DRB member subject to mutual approval of the parties or may mutually concur on a list of potentially acceptable third DRB members and submit the list to the parties for final selection and approval of the third member. The goal in the selection of the third member is to complement the professional experience of the first 2 members and to provide leadership for the DRB's activities.

The third prospective DRB member shall supply a full disclosure statement to the first 2 DRB members and to the parties prior to appointment.

An impasse shall be considered to have been reached if the parties are unable to approve a third member within 15 days of receipt of the recommendation of the first 2 DRB members, or if the first 2 DRB members are unable to agree upon a recommendation within their 15 day time limit. In the event of an impasse in selection of third DRB member the State and the Contractor shall each propose 3 candidates for the third DRB member position. The parties shall select the candidates proposed under this paragraph from the current list of arbitrators certified by the Public Works Contract Arbitration Committee created by Article 7.2 (commencing with Section 10245) of the State Contract Act. The first 2 DRB members shall then select one of the 6 proposed candidates in a blind draw.

No DRB member shall have prior direct involvement in this contract. No member shall have a financial interest in this contract or the parties thereto, within a period of 6 months prior to award of this contract or during the contract, except as follows:

- A. Compensation for services on this DRB.
- B. Ownership interest in a party or parties, documented by the prospective DRB member, that has been reviewed and determined in writing by the State to be sufficiently insignificant to render the prospective member acceptable to the State.
- C. Service as a member of other Dispute Review Boards on other contracts.
- D. Retirement payments or pensions received from a party that are not tied to, dependent on or affected by the net worth of the party.
- E. The above provisions apply to parties having a financial interest in this contract, including but not limited to contractors, subcontractors, suppliers, consultants, and legal and business services.

The Contractor or the State may reject any of the 3 DRB members who fail to fully comply at all times with all required employment and financial disclosure conditions of DRB membership as described in the Dispute Review Board Agreement and as specified herein. A copy of the Dispute Review Board Agreement is included in this section.

The Contractor, the State, and the 3 members of the DRB shall complete and adhere to the Dispute Review Board Agreement in administration of this DRB within 15 days of the parties' concurrence in the selection of the third member. No DRB meeting shall take place until the Dispute Review Board Agreement has been signed by all parties. The State authorizes the Engineer to execute and administer the terms of the Agreement. The person(s) designated by the Contractor as authorized to execute contract change orders shall be authorized to execute and administer the terms of this agreement, or to delegate the authority in writing. The operation of the DRB shall be in conformance with the terms of the Dispute Review Board Agreement.

#### **5-1.15C(3) Compensation**

The State and the Contractor shall bear the costs and expenses of the DRB equally. Each DRB member shall be compensated at an agreed rate of \$1,200 per day if time spent per meeting, including on-site time plus one hour of travel time, is greater than 4 hours. Each DRB member shall be compensated at an agreed rate of \$700 per day if time spent per meeting, including on-site time plus one hour of travel time, is less than or equal to 4 hours. The agreed rates shall be considered full compensation for on-site time, travel expenses, transportation, lodging, time for travel and incidentals for each day, or portion thereof, that the DRB member is at an authorized DRB meeting. No additional compensation will be made for time spent by DRB members in review and research activities outside the official DRB meetings unless that time, (such as time spent evaluating and preparing recommendations on specific issues presented to the DRB), has been specifically agreed to in advance by the State and Contractor. Time away from the project, which has been specifically agreed to in advance by the parties, will be compensated at an agreed rate of \$125 per hour. The agreed amount of \$125 per hour shall include all incidentals including expenses for telephone, fax, and computer services. Members serving on more than one DRB involving the Department, regardless of the number of meetings per day, shall not be paid more than the all inclusive rate per day or rate per hour for an individual project. The State will provide, at no cost to the Contractor, administrative services such as conference facilities and secretarial services to the DRB. These special provisions and the Dispute Review Board Agreement state the provisions for compensation and expenses of the DRB. DRB members shall be compensated at the same daily and hourly rate. The Contractor shall make direct payments to each DRB member for their participation in authorized meetings and approved hourly rate charges from invoices submitted by each DRB member. The State will reimburse the Contractor for the State's share of the costs. There will be no markups applied to expenses connected with the DRB, either by the DRB members or by the Contractor when requesting payment of the State's share of DRB expenses. Regardless of the DRB recommendation, neither party shall be entitled to reimbursement of DRB costs from the other party.

#### **5-1.15C(4) Replacement of DRB Members**

Service of a DRB member may be terminated at any time with not less than 15 days notice as follows:

- A. The State may terminate service of the State appointed member.
- B. The Contractor may terminate service of the Contractor appointed member.
- C. Upon the written recommendation of the State and Contractor appointed members for the removal of the third member.
- D. Upon resignation of a member.
- E. The State or Contractor may terminate the service of any member who fails to fully comply with all required employment and financial disclosure conditions of DRB membership.

When a member of the DRB is replaced, the replacement member shall be appointed in the same manner as the replaced member was appointed. The appointment of a replacement DRB member will begin promptly upon determination of the need for replacement and shall be completed within 15 days. Changes in either of the DRB members chosen by the 2 parties will not require re-selection of the third member, unless both parties agree to such re-selection in writing. The Dispute Review Board Agreement shall be amended to reflect the change of a DRB member.

#### **5-1.15C(5) Operation**

The following procedure shall be used for dispute resolution:

- A. If the Contractor objects to any decision, act or order of the Engineer, the Contractor shall give written notice of potential claim in conformance with the provisions in Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications and these special provisions, including the provision of applicable cost documentation; or file written protests or notices in conformance with the provisions in the Standard Specifications and these special provisions.
- B. The Engineer will respond, in writing, to the Contractor's written supplemental notice of potential claim within 20 days of receipt of the notice.
- C. Within 15 days after receipt of the Engineer's written response, the Contractor shall, if the Contractor still objects, file a written reply with the Engineer, stating clearly and in detail the basis of the objection.
- D. Following an objection to the Engineer's written response, the Contractor shall refer the dispute to the DRB if the Contractor wishes to further pursue the objection to the Engineer's decision. The Contractor shall make the referral in writing to the DRB, simultaneously copied to the State, within 21 days after receipt of the written response from the Engineer. The written dispute referral shall describe the disputed matter in individual discrete segments so that it will be clear to both parties and the DRB what discrete elements of the dispute have been resolved, and which remain unresolved, and shall include an estimate of the cost of the affected work and impacts, if any, on project completion.
- E. By failing to submit the written notice of referral to the DRB, within 21 days after receipt of the Engineer's written response to the supplemental notice of potential claim, the Contractor waives future claims and arbitration on the matter in contention.
- F. The Contractor and the State shall each be afforded an opportunity to be present and to be heard by the DRB, and to offer evidence. Either party furnishing written evidence or documentation to the DRB must furnish copies of such information to the other party a minimum of 15 days prior to the date the DRB is scheduled to convene the meeting for the dispute. Either party shall produce such additional evidence as the DRB may deem necessary to reach an understanding and a determination of the dispute. The party furnishing additional evidence shall furnish copies of such additional evidence to the other party at the same time the evidence is provided to the DRB. The DRB shall not consider evidence not furnished in conformance with the terms specified herein.
- G. Upon receipt by the DRB of a written referral of a dispute, the DRB shall convene to review and consider the dispute. The dispute meeting shall be held no earlier than 30 days and no later than 60 days after receipt of the written referral unless otherwise agreed to by all parties. The DRB shall determine the time and location of the DRB dispute meeting, with due consideration for the needs and preferences of the parties while recognizing the paramount importance of a timely hearing of the dispute.
- H. There shall be no participation of either party's attorneys at DRB dispute meetings.
- I. There shall be no participation of persons who are not directly involved in the contract or who do not have direct knowledge of the dispute, including but not limited to consultants, except for expert testimony allowed at the discretion of the DRB and with approval prior to the dispute meeting by both parties.
- J. The DRB shall furnish a report, containing findings and recommendations as described in the Dispute Review Board Agreement, in writing to both the State and the Contractor. The DRB may request clarifying information of either party within 10 days after the DRB dispute meeting. Requested information shall be submitted to the DRB within 10 days of the DRB request. The DRB shall complete its report, including minority opinion, if any, and submit it to the parties within 30 days of the DRB dispute meeting, except that time extensions may be granted at the request of the DRB with the written concurrence of both parties. The report shall include the facts and circumstances related to the matters under consideration, pertinent provisions of the contract, applicable laws and regulations, and actual costs and time incurred as shown on the Contractor's cost accounting records. The DRB shall make recommendations on the merit of the dispute and, if appropriate, recommend guidelines for determining compensation.
- K. Within 30 days after receiving the DRB's report, both the State and the Contractor shall respond to the DRB in writing signifying that the dispute is either resolved or remains unresolved. Failure to provide the written response within the time specified, or a written rejection of the DRB's recommendation or response to a request for reconsideration presented in the report by either party, shall conclusively indicate that the party(s) failing to respond accepts the DRB recommendation. Immediately after responses have been received from both parties, the DRB shall provide copies of both responses to the parties simultaneously. Either party may request clarification of

elements of the DRB's report from the DRB prior to responding to the report. The DRB shall consider any clarification request only if submitted within 10 days of receipt of the DRB's report, and if submitted simultaneously in writing to both the DRB and the other party. Each party may submit only one request for clarification for any individual DRB report. The DRB shall respond, in writing, to requests for clarification within 10 days of receipt of such requests.

- L. The DRB's recommendations, stated in the DRB's reports, are not binding on either party. Either party may seek a reconsideration of a recommendation of the DRB. The DRB shall only grant a reconsideration based upon submission of new evidence and if the request is submitted within the 30-day time limit specified for response to the DRB's written report. Each party may submit only one request for reconsideration regarding an individual DRB recommendation.
- M. If the State and the Contractor are able to resolve their dispute with the aid of the DRB's report, the State and Contractor shall promptly accept and implement the recommendations of the DRB. If the parties cannot agree on compensation within 60 days of the acceptance by both parties of the DRB's recommendation, either party may request the DRB to make a recommendation regarding compensation.
- N. The State or the Contractor shall not call DRB members who served on the DRB for this contract as witnesses in arbitration proceedings which may arise from this contract, and all documents created by the DRB shall be inadmissible as evidence in subsequent arbitration proceedings, except the DRB's final written reports on each issue brought before it.
- O. The State and Contractor shall jointly indemnify and hold harmless the DRB members from and against all claims, damages, losses, and expenses, including but not limited to attorney's fees, arising out of and resulting from the findings and recommendations of the DRB.
- P. The DRB members shall have no claim against the State or the Contractor, or both, from claimed harm arising out of the parties' evaluations of the DRB's report.

#### **5-1.15C(6) Disputes Involving Subcontractor Potential Claims**

For purposes of this section, a "subcontractor potential claim" shall include any potential claim by a subcontractor (including also any pass through potential claims by a lower tier subcontractor or supplier) against the Contractor that is actionable by the Contractor against the Department which arises from the work, services, or materials provided or to be provided in connection with the contract. If the Contractor determines to pursue a dispute against the Department that includes a subcontractor potential claim, the dispute shall be processed and resolved in conformance with these special provisions and in conformance with the following:

- A. The Contractor shall identify clearly in submissions pursuant to this section, that portion of the dispute that involves a subcontractor potential claim or potential claims.
- B. The Contractor shall include, as part of its submission pursuant to Step D above, a certification (False Claims Act Certification) by the subcontractor's or supplier's officer, partner, or authorized representative with authority to bind the subcontractor and with direct knowledge of the facts underlying the subcontractor potential claim. The Contractor shall submit a certification that the subcontractor potential claim is acknowledged and forwarded by the Contractor. The form for these certifications is available from the Engineer.
- C. At DRB dispute meetings involving one or more subcontractor potential claims, the Contractor shall require that each subcontractor involved in the dispute have present an authorized representative with actual knowledge of the facts underlying the subcontractor potential claim to assist in presenting the subcontractor potential claim and to answer questions raised by the DRB members or the Department's representatives.
- D. Failure by the Contractor to declare a subcontractor potential claim on behalf of its subcontractor (including lower tier subcontractors' and suppliers' pass through potential claims) at the time of submission of the Contractor's potential claims, as provided hereunder, shall constitute a release of the State by the Contractor of such subcontractor potential claim.
- E. The Contractor shall include in all subcontracts under this contract that subcontractors and suppliers of any tier (a) agree to submit subcontractor potential claims to the Contractor in a proper form and in sufficient time to allow processing by the Contractor in conformance with the Dispute Review Board resolution specifications; (b) agree to be bound by the terms of the Dispute Review Board provisions to the extent applicable to subcontractor potential claims; (c) agree that, to the extent a subcontractor potential claim is involved, completion of all steps required under these Dispute Review Board special provisions shall be a condition precedent to pursuit by the subcontractor of other remedies permitted by law, including without limitation of a lawsuit against the Contractor; and (d) agree that the existence of a dispute resolution process for disputes involving subcontractor potential claims shall not be deemed to create any claim, right, or cause of action by any subcontractor or supplier against the Department.

Notwithstanding the foregoing, this Dispute Review Board special provision shall not apply to, and the DRB shall not have the authority to consider, subcontractor potential claims between the subcontractor(s) or supplier(s) and the Contractor that are not actionable by the Contractor against the Department.

**5-1.15C(7) Dispute Review Board Agreement**

A copy of the "Dispute Review Board Agreement" to be executed by the Contractor, State and the 3 DRB members after approval of the contract follows:

Form 6202 Rev (09/01/02)

**DISPUTE REVIEW BOARD AGREEMENT**

\_\_\_\_\_  
(Contract Identification)

Contract No. \_\_\_\_\_

**THIS DISPUTE REVIEW BOARD AGREEMENT, hereinafter called "AGREEMENT"**, made and entered into this \_\_\_\_\_ day of \_\_\_\_\_, \_\_\_\_\_, between the State of California, acting through the California Department of Transportation and the Director of Transportation, hereinafter called the "STATE," \_\_\_\_\_ hereinafter called the "CONTRACTOR," and the Dispute Review Board, hereinafter called the "DRB" consisting of the following members:

\_\_\_\_\_,  
(Contractor Appointee) ,

\_\_\_\_\_,  
(State Appointee) ,

and \_\_\_\_\_  
(Third Person)

WITNESSETH, that

WHEREAS, the STATE and the CONTRACTOR, hereinafter called the "parties," are now engaged in the construction on the State Highway project referenced above; and

WHEREAS, the special provisions for the above referenced contract provides for the establishment and operation of the DRB to assist in resolving disputes; and

WHEREAS, the DRB is composed of three members, one selected by the STATE, one selected by the CONTRACTOR, and the third member selected by the other two members and approved by the parties;

NOW THEREFORE, in consideration of the terms, conditions, covenants, and performance contained herein, or attached and incorporated and made a part hereof, the STATE, the CONTRACTOR, and the DRB members hereto agree as follows:

**SECTION I DESCRIPTION OF WORK**

To assist in the resolution of disputes between the parties, the contract provides for the establishment and the operation of the DRB. The intent of the DRB is to fairly and impartially consider disputes placed before it and provide written recommendations for resolution of these disputes to both parties. The members of this DRB shall perform the services necessary to participate in the DRB's actions as designated in Section II, Scope of Work.

**SECTION II SCOPE OF WORK**

The scope of work of the DRB includes, but is not limited to, the following:

**A. OBJECTIVE**

The principal objective of the DRB is to assist in the timely resolution of disputes between the parties arising from performance of this contract. It is not intended for either party to default on their normal responsibility to amicably and fairly

settle their differences by indiscriminately assigning them to the DRB. It is intended that the mere existence of the DRB will encourage the parties to resolve disputes without resorting to this review procedure. But when a dispute that is serious enough to warrant the DRB's review does develop, the process for prompt and efficient action will be in place.

## **B. PROCEDURES**

The DRB shall render written reports on disputes between the parties arising from the construction contract. Prior to consideration of a dispute, the DRB shall establish rules and regulations that will govern the conduct of its business and reporting procedures in conformance with the requirements of the contract and the terms of this AGREEMENT. DRB recommendations, resulting from its consideration of a dispute, shall be furnished in writing to both parties. The recommendations shall be based on facts and circumstances involved in the dispute, pertinent contract provisions, applicable laws and regulations. The recommendations shall find one responsible party in a dispute; shared or "jury" determinations shall not be rendered. The DRB shall make recommendations on the merit of the dispute, and if appropriate, recommend guidelines for determining compensation. If the parties cannot agree on compensation within 60 days of the acceptance by both parties of the DRB's recommendation, either party may request the DRB to make a recommendation regarding compensation.

The DRB shall refrain from officially giving advice or consulting services to anyone involved in the contract. The individual members shall act in a completely independent manner and while serving as members of the DRB shall have no consulting business connections with either party or its principals or attorneys or other affiliates (subcontractors, suppliers, etc.) who have a beneficial interest in the contract.

During scheduled meetings of the DRB as well as during dispute meetings, DRB members shall refrain from expressing opinions on the merits of statements on matters under dispute or potential dispute. Opinions of DRB members expressed in private sessions shall be kept strictly confidential. Individual DRB members shall not meet with, or discuss contract issues with individual parties, except as directed by the DRB Chairperson. Such discussions or meetings shall be disclosed to both parties. Other discussions regarding the project between the DRB members and the parties shall be in the presence of all three members and both parties. Individual DRB members shall not undertake independent investigations of any kind pertaining to disputes or potential disputes, except with the knowledge of both parties and as expressly directed by the DRB Chairperson.

## **C. CONSTRUCTION SITE VISITS, PROGRESS MEETINGS AND FIELD INSPECTIONS**

The DRB members shall visit the project site and meet with representatives of the parties to keep abreast of construction activities and to develop familiarity with the work in progress. Scheduled progress meetings shall be held at or near the project site. The DRB shall meet at least once at the start of the project, and at least once every 4 months thereafter. The frequency, exact time, and duration of additional site visits and progress meetings shall be as recommended by the DRB and approved by the parties consistent with the construction activities or matters under consideration and dispute. Each meeting shall consist of a round table discussion and a field inspection of the work being performed on the contract, if necessary. Each meeting shall be attended by representatives of both parties. The agenda shall generally be as follows:

1. Meeting opened by the DRB Chairperson.
2. Remarks by the STATE's representative.
3. A description by the CONTRACTOR's representative of work accomplished since the last meeting; the current schedule status of the work; and a forecast for the coming period.
4. An outline by the CONTRACTOR's representative of potential problems and a description of proposed solutions.
5. An outline by the STATE's representative of the status of the work as the STATE views it.
6. A brief description by the CONTRACTOR's or STATE's representative of potential claims or disputes which have surfaced since the last meeting.
7. A summary by the STATE's representative, the CONTRACTOR's representative, or the DRB of the status of past disputes and potential claims.

The STATE's representative will prepare minutes of all progress meetings and circulate them for revision and approval by all concerned within 10 days of the meeting.

The field inspection shall cover all active segments of the work, the DRB being accompanied by both parties' representatives. The field inspection may be waived upon mutual agreement of the parties.

## **D. DRB CONSIDERATION AND HANDLING OF DISPUTES**

Upon receipt by the DRB of a written referral of a dispute, the DRB shall convene to review and consider the dispute. The dispute meeting shall be held no earlier than 30 days and no later than 60 days after receipt of the written referral, unless otherwise agreed to by all parties. The DRB shall determine the time and location of DRB dispute meetings, with due

consideration for the needs and preferences of the parties while recognizing the paramount importance of speedy resolution of issues. No dispute meetings shall take place later than 30 days prior to acceptance of contract.

Normally, dispute meetings shall be conducted at or near the project site. However, any location that would be more convenient and still provide required facilities and access to necessary documentation shall be satisfactory.

Both parties shall be given the opportunity to present their evidence at these dispute meetings. It is expressly understood that the DRB members are to act impartially and independently in the consideration of the contract provisions, applicable laws and regulations, and the facts and conditions surrounding any dispute presented by either party, and that the recommendations concerning any such dispute are advisory and nonbinding on the parties.

The DRB may request that written documentation and arguments from both parties be sent to each DRB member, through the DRB Chairperson, for review before the dispute meeting begins. A party furnishing written documentation to the DRB shall furnish copies of such information to the other party at the same time that such information is supplied to the DRB.

DRB dispute meetings shall be informal. There shall be no testimony under oath or cross-examination. There shall be no reporting of the procedures by a shorthand reporter or by electronic means. Documents and verbal statements shall be received by the DRB in conformance with acceptance standards established by the DRB. These standards need not comply with prescribed legal laws of evidence.

The third DRB member shall act as Chairperson for dispute meetings and all other DRB activities. The parties shall have a representative at all dispute meetings. Failure to attend a duly noticed dispute meeting by either of the parties shall be conclusively considered by the DRB as indication that the non-attending party considers written submittals as their entire and complete argument. The claimant shall discuss the dispute, followed by the other party. Each party shall then be allowed one or more rebuttals until all aspects of the dispute are thoroughly covered. DRB members shall ask questions, seek clarification, and request further data from either of the parties as may be necessary to assist in making a fully informed recommendation. The DRB may request from either party documents or information that would assist the DRB in making its findings and recommendations including, but not limited to, documents used by the CONTRACTOR in preparing the bid for the project. A refusal by a party to provide information requested by the DRB may be considered by the DRB as an indication that the requested material would tend to disprove that party's position. In large or complex cases, additional dispute meetings may be necessary in order to consider all the evidence presented by both parties. All involved parties shall maintain the confidentiality of all documents and information, as provided in this AGREEMENT.

During dispute meetings, no DRB member shall express an opinion concerning the merit of any facet of the case. DRB deliberations shall be conducted in private, with interim individual views kept strictly confidential.

After dispute meetings are concluded, the DRB shall meet in private and reach a conclusion supported by 2 or more members. Private sessions of the DRB may be held at a location other than the job site or by electronic conferencing as deemed appropriate, in order to expedite the process.

The DRB's findings and recommendations, along with discussion of reasons therefor, shall then be submitted as a written report to both parties. Recommendations shall be based on the pertinent contract provisions, applicable laws and regulations, and facts and circumstances related to the dispute. The report shall be thorough in discussing the facts considered, the contract language, law or regulation viewed by the DRB as pertinent to the issues, and the DRB's interpretation and philosophy in arriving at its conclusions and recommendations. The DRB's report shall stand on its own, without attachments or appendices. The DRB Chairperson shall furnish a copy of the written recommendation report to the DRB Coordinator, Division of Construction, MS 44, P.O. Box 942874, Sacramento, CA 94274.

With prior written approval of both parties, the DRB may obtain technical services necessary to adequately review the disputes presented, including audit, geotechnical, schedule analysis and other services. The parties' technical staff may supply those services as appropriate. The cost of technical services, as agreed to by the parties, shall be borne equally by the 2 parties as specified in an approved contract change order. The CONTRACTOR will not be entitled to markups for the payments made for these services.

The DRB shall resist submittal of incremental portions of information by either party, in the interest of making a fully informed decision and recommendation.

The DRB shall make every effort to reach a unanimous decision. If this proves impossible, the dissenting member shall prepare a minority opinion, which shall be included in the DRB's report.

Although both parties should place weight upon the DRB's recommendations, they are not binding. Either party may appeal a recommendation to the DRB for reconsideration. However, reconsideration shall only be allowed when there is new evidence to present, and the DRB shall accept only one appeal from each party pertaining to an individual DRB recommendation. The DRB shall hear appeals in conformance with the terms described in the Section entitled "Dispute Review Board" in the special provisions.

#### **E. DRB MEMBER REPLACEMENT**

Should the need arise to appoint a replacement DRB member, the replacement DRB member shall be appointed in the same manner as the original DRB members were appointed. The selection of a replacement DRB member shall begin

promptly upon notification of the necessity for a replacement and shall be completed within 15 days. This AGREEMENT shall be amended to indicate change in DRB membership.

### **SECTION III CONTRACTOR RESPONSIBILITIES**

The CONTRACTOR shall furnish to each DRB member one copy of pertinent documents that are or may become necessary for the DRB to perform their function. Pertinent documents are written notices of potential claim, responses to those notices, drawings or sketches, calculations, procedures, schedules, estimates, or other documents which are used in the performance of the work or in justifying or substantiating the CONTRACTOR's position. The CONTRACTOR shall also furnish a copy of such pertinent documents to the STATE, in conformance with the terms outlined in the special provisions.

### **SECTION IV STATE RESPONSIBILITIES**

The STATE will furnish the following services and items:

#### **A. CONTRACT RELATED DOCUMENTS**

The STATE will furnish to each DRB member one copy of Notice to Contractors and Special Provisions, Proposal and Contract, Plans, Standard Specifications, and Standard Plans, change orders, written instructions issued by the STATE to the CONTRACTOR, or other documents pertinent to any dispute that has been referred to the DRB and necessary for the DRB to perform its function.

#### **B. COORDINATION AND SERVICES**

The STATE, through the Engineer, will, in cooperation with the CONTRACTOR, coordinate the operations of the DRB. The Engineer will arrange or provide conference facilities at or near the project site and provide secretarial and copying services to the DRB without charge to the CONTRACTOR.

### **SECTION V TIME FOR BEGINNING AND COMPLETION**

Once established, the DRB shall be in operation until the day of acceptance of the contract. The DRB members shall not begin work under the terms of this AGREEMENT until authorized in writing by the STATE.

### **SECTION VI PAYMENT**

#### **A. ALL INCLUSIVE RATE PAYMENT**

The STATE and the CONTRACTOR shall bear the costs and expenses of the DRB equally. Each DRB member shall be compensated at an agreed rate of \$1,200 per day if time spent per meeting, including on-site time plus one hour of travel time, is greater than 4 hours. Each DRB member shall be compensated at an agreed rate of \$700 per day if time spent per meeting, including on-site time plus one hour of travel time, is less than or equal to 4 hours. The agreed rates shall be considered full compensation for on-site time, travel expenses, transportation, lodging, time for travel and incidentals for each day, or portion thereof, that the DRB member is at an authorized DRB meeting. No additional compensation will be made for time spent by DRB members in review and research activities outside the official DRB meetings unless that time has been specifically agreed to in advance by the STATE and CONTRACTOR. Time away from the project that has been specifically agreed to in advance by the parties will be compensated at an agreed rate of \$125 per hour. The agreed amount of \$125 per hour shall include all incidentals including expenses for telephone, fax, and computer services. Members serving on more than one DRB involving the State, regardless of the number of meetings per day, shall not be paid more than the all inclusive rate per day or rate per hour for an individual project. The STATE will provide, at no cost to the CONTRACTOR, administrative services such as conference facilities and secretarial services to the DRB.

#### **B. PAYMENTS**

DRB members shall be compensated at the same rate. The CONTRACTOR shall make direct payments to each DRB member for their participation in authorized meetings and approved hourly rate charges from invoices submitted by each DRB member. The STATE will reimburse the CONTRACTOR for its share of the costs of the DRB.

The DRB members may submit invoices to the CONTRACTOR for partial payment for work performed and services rendered for their participation in authorized meetings not more often than once per month during the progress of the work. The invoices shall be in a format approved by the parties and accompanied by a general description of activities performed during that billing period. Payment for hourly fees, at the agreed rate, shall not be paid to a DRB member until the amount and extent of those fees are approved by the STATE and CONTRACTOR.

Invoices shall be accompanied by original supporting documents, which the CONTRACTOR shall include with the extra work billing when submitting for reimbursement of the STATE's share of cost from the STATE. The CONTRACTOR will be reimbursed for one-half of approved costs of the DRB. No markups will be added to the CONTRACTOR's payment.

### **C. INSPECTION OF COSTS RECORDS**

The DRB members and the CONTRACTOR shall keep available for inspection by representatives of the STATE and the United States, for a period of 3 years after final payment, the cost records and accounts pertaining to this AGREEMENT. If any litigation, claim, or audit arising out of, in connection with, or related to this contract is initiated before the expiration of the 3-year period, the cost records and accounts shall be retained until such litigation, claim, or audit involving the records is completed.

### **SECTION VII ASSIGNMENT OF TASKS OF WORK**

The DRB members shall not assign the work of this AGREEMENT.

### **SECTION VIII TERMINATION OF DRB MEMBERS**

DRB members may resign from the DRB by providing not less than 15 days written notice of the resignation to the STATE and CONTRACTOR. DRB members may be terminated by their original appointing power or by either party, for failing to fully comply at all times with all required employment and financial disclosure conditions of DRB membership in conformance with the terms of the contract.

### **SECTION IX LEGAL RELATIONS**

The parties hereto mutually understand and agree that the DRB member in the performance of duties on the DRB, is acting in the capacity of an independent agent and not as an employee of either party.

No party to this AGREEMENT shall bear a greater responsibility for damages or personal injury than is normally provided by Federal or State of California Law.

Notwithstanding the provisions of this contract that require the CONTRACTOR to indemnify and hold harmless the STATE, the parties shall jointly indemnify and hold harmless the DRB members from and against all claims, damages, losses, and expenses, including but not limited to attorney's fees, arising out of and resulting from the findings and recommendations of the DRB.

### **SECTION X CONFIDENTIALITY**

The parties hereto mutually understand and agree that all documents and records provided by the parties in reference to issues brought before the DRB, which documents and records are marked "Confidential - for use by the DRB only," shall be kept in confidence and used only for the purpose of resolution of subject disputes, and for assisting in development of DRB findings and recommendations; that such documents and records will not be utilized or revealed to others, except to officials of the parties who are authorized to act on the subject disputes, for any purposes, during the life of the DRB. Upon termination of this AGREEMENT, said confidential documents and records, and all copies thereof, shall be returned to the parties who furnished them to the DRB. However, the parties understand that such documents shall be subsequently discoverable and admissible in court or arbitration proceedings unless a protective order has been obtained by the party seeking further confidentiality.

### **SECTION XI DISPUTES**

Disputes between the parties hereto, including disputes between the DRB members and either party or both parties, arising out of the work or other terms of this AGREEMENT, which cannot be resolved by negotiation and mutual concurrence between the parties, or through the administrative process provided in the contract, shall be resolved by arbitration as provided in Section 9-1.10, "Arbitration," of the Standard Specifications.

### **SECTION XII VENUE, APPLICABLE LAW, AND PERSONAL JURISDICTION**

In the event that any party, including an individual member of the DRB, deems it necessary to institute arbitration proceedings to enforce any right or obligation under this AGREEMENT, the parties hereto agree that such action shall be initiated in the Office of Administrative Hearings of the State of California. The parties hereto agree that all questions shall be resolved by arbitration by application of California law and that the parties to such arbitration shall have the right of appeal from such decisions to the Superior Court in conformance with the laws of the State of California. Venue for the arbitration shall be Sacramento or any other location as agreed to by the parties.

### **SECTION XIII FEDERAL REVIEW AND REQUIREMENTS**

On Federal-Aid contracts, the Federal Highway Administration shall have the right to review the work of the DRB in progress, except for private meetings or deliberations of the DRB.

Other Federal requirements in this agreement shall only apply to Federal-Aid contracts.

**SECTION XIV CERTIFICATION OF THE CONTRACTOR, THE DRB MEMBERS, AND THE STATE**

IN WITNESS WHEREOF, the parties hereto have executed this AGREEMENT as of the day and year first above written.

DRB MEMBER

DRB MEMBER

By: \_\_\_\_\_

By: \_\_\_\_\_

Title: \_\_\_\_\_

Title : \_\_\_\_\_

DRB MEMBER

By : \_\_\_\_\_

Title : \_\_\_\_\_

CONTRACTOR

CALIFORNIA STATE DEPARTMENT  
OF TRANSPORTATION

By: \_\_\_\_\_

By: \_\_\_\_\_

Title: \_\_\_\_\_

Title: \_\_\_\_\_

**Add:**

**5-1.16-5-17 (BLANK)**

**Add:**

**5-1.18 PROPERTY AND FACILITY PRESERVATION**

**5-1.18A General**

Preserve property and facilities, including:

1. Adjacent property
2. Department's instrumentation
3. ESAs
4. Lands administered by other agencies
5. Railroads and railroad equipment
6. Roadside vegetation not to be removed
7. Utilities
8. Waterways

Immediately report damage to the Engineer.

If you cause damage, you are responsible.

Install sheet piling, cribbing, bulkheads, shores, or other supports necessary to support existing facilities or support material carrying the facilities.

Dispose of temporary facilities when they are no longer needed.

If you damage plants not to be removed:

1. Dispose of them outside the right of way unless the Engineer allows you to reduce them to chips and spread the chips within the highway at locations designated by the Engineer
2. Replace them

Replace plants with plants of the same species.

Replace trees with 600 mm-box trees.

Replace shrubs with No. 15 container shrubs.



1. Follows Contract award
2. Allows 30 days for review
3. Causes no delay

Include substantiating data with the substitution request that proves the substitution:

1. Is of equal or better quality and suitability
2. Causes no delay in product delivery and installation

**Add:**

**6-1.075 GUARANTEE**

Guarantee the work remains free from substantial defects for 1 year after contract acceptance except for work parts for which you were relieved of maintenance and protection. Guarantee each of these relieved work parts for 1 year after the relief date.

The guarantee excludes damage or displacement caused by an event outside your control including:

1. Normal wear and tear
2. Improper operation
3. Insufficient maintenance
4. Abuse
5. Unauthorized change
6. Act of God

During the guarantee period, repair or replace each work portion having a substantial defect.

The Department does not pay for corrective work.

During corrective work activities, provide insurance coverage specified for coverage before contract acceptance.

The contract bonds must be in full force and effect until the later of:

1. Expiration of guarantee period
2. Completion of corrective work

If a warranty specification conflicts with Section 6-1.075, "Guarantee," comply with the warranty specification.

During the guarantee period, the Engineer monitors the completed work. If the Engineer finds work having a substantial defect, the Engineer lists work parts and furnishes you the list.

Within 10 days of receipt of the list, submit for authorization a detailed plan for correcting the work. Include a schedule that includes:

1. Start and completion dates
2. List of labor, equipment, materials, and any special services you plan to use
3. Work related to the corrective work, including traffic control and temporary and permanent pavement markings

The Engineer notifies you when the plan is authorized. Start corrective work and related work within 15 days of notice.

If the Engineer determines corrective work is urgently required to prevent injury or property damage:

1. The Engineer furnishes you a request to start emergency repair work and a list of parts requiring corrective work
2. Mobilize within 24 hours and start work
3. Submit a corrective work plan within 5 days of starting emergency repair work

If you fail to perform work as specified, the Department may perform the work and bill you.

**Add:**

**6-1.085 BUY AMERICA (23 CFR 635.410)**

For a Federal-aid contract, furnish steel and iron materials to be incorporated into the work that are produced in the United States except:

1. Foreign pig iron and processed, pelletized, and reduced iron ore may be used in the domestic production of the steel and iron materials [60 Fed Reg 15478 (03/24/1995)]
2. If the total combined cost of the materials does not exceed the greater of 0.1 percent of the total bid or \$2 500, material produced outside the United States may be used

Production includes:

1. Processing steel and iron materials, including smelting or other processes that alter the physical form or shape (such as rolling, extruding, machining, bending, grinding, and drilling) or chemical composition
2. Coating application, including epoxy coating, galvanizing, and painting, that protects or enhances the value of steel and iron materials

For steel and iron materials to be incorporated into the work, submit a Certificate of Compliance under Section 6-1.07, "Certificates of Compliance," of the Standard Specifications that certifies all production processes occurred in the United States except for the above exceptions.

**Add:**

**6-1.087 BUY AMERICA (PUB RES CODE § 42703(d))**

Furnish crumb rubber to be incorporated into the work that is produced in the United States and is derived from waste tires taken from vehicles owned and operated in the United States.

For crumb rubber to be incorporated into the work, submit a Certificate of Compliance under Section 6-1.07, "Certificates of Compliance," of the Standard Specifications that certifies only crumb rubber manufactured in the United States and derived from waste tires taken from vehicles owned and operated in the United States is used.

**In Section 6-2.01 delete the 4th paragraph.**

**In Section 6-2.01 replace the 7th paragraph with:**

Upon the Contractor's written request, the Department tests materials from an untested local source. If satisfactory material from that source is used in the work, the Department does not charge the Contractor for the tests; otherwise, the Department deducts the test cost.

**In Section 6-2.01 delete the 8th paragraph.**

**In Section 6-2.02 delete the 3rd paragraph.**

**In Section 6-2.02 in the 7th paragraph, replace the 2nd sentence with:**

The Department deducts the charges for the removed material.

**In Section 6-3.01 delete the 4th paragraph.**

**In Section 6-3.01 in the 6th paragraph, delete the 1st sentence.**

**In Section 6-3.01 add:**

As used in Section 6-3.01, "Testing," tests are tests to assure the quality and to determine the acceptability of the work. The Department deducts costs of testing work found to be noncompliant.



**In Section 7-1.01A(3) delete the 5th paragraph.**

**Replace Section 7-1.01A(6) with:**

**7-1.01A(6) (Blank)**

**Add:**

**7-1.01K Solid Waste Disposal and Recycling**

Submit an annual Solid Waste Disposal and Recycling Report between January 1 and 15 for each year work is performed under the Contract at any time during the previous calendar year. Show the types and amounts of project-generated solid waste taken to or diverted from landfills or reused on the project from January 1 through December 31 of the previous calendar year.

Submit a final annual Solid Waste Disposal and Recycling Report within 5 business days after Contract acceptance. Show the types and amounts of project-generated solid waste taken to or diverted from landfills or reused on the project from January 1 to contract acceptance.

For each failure to submit a completed form, the Department withholds \$10,000.

**Add:**

**7-1.01L Asbestos and Hazardous Substances**

• Upon discovery, immediately stop working in and notify the Engineer of areas where asbestos or a hazardous substance is present if the:

1. Contractor reasonably believes the substance is asbestos as defined in Labor Code § 6501.7 or a hazardous substance as defined in Health & Safety Code §§ 25316 and 25317
2. Presence is not described in the contract
3. Substance has not been made harmless

**Add:**

**7-1.01M Archaeological Discoveries**

If archaeological materials are discovered at the job site, protect and leave them undisturbed in place and comply with:

1. Pub Res Code §§ 5097.5, 5097.98, and 5097.99
2. 14 CA Code of Regs § 4308
4. Penal Code § 622-1/2
5. Health & Safety Code § 7050.5

Archaeological materials are the remains of past human activity including historic-period archaeological materials and prehistoric Native American archaeological materials. Nonhuman fossils are not archaeological materials unless they show direct evidence of human use or alteration or when found in direct physical association with archaeological materials

Historic-period archaeological materials include cultural remains beginning with initial European contact in California but at least 50 years old and include:

1. Trash deposits or clearly defined disposal pits containing tin cans, bottles, ceramic dishes, or other refuse indicating previous occupation or use of the site
2. Structural remains of stone, brick, concrete, wood, or other building material found above or below ground
3. Human skeletal remains from the historic period, with or without coffins or caskets, including any associated grave goods

Prehistoric Native American archaeological materials include:

1. Human skeletal remains or associated burial goods such as beads or ornaments

2. Evidence of tool making or hunting such as arrowheads and associated chipping debris of fine-grained materials such as obsidian, chert, or basalt
3. Evidence of plant processing such as pestles, grinding slabs, or stone bowls
4. Evidence of habitation such as cooking pits, stone hearths, packed or burnt earth floors
5. Remains from food processing such as concentrations of discarded or burnt animal bone, shellfish remains, or burnt rocks used in cooking

Immediately upon discovering archaeological materials, stop all work within an 18.5-meter radius of the archaeological materials and notify the Engineer. Archaeological materials discovered are the property of the State. Do not resume work within the 18.5-meter radius of the discovery until the Engineer gives you written approval. If, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of an archeological discovery or investigation or recovery of archeological materials, you will be compensated for resulting losses and an extension of time will be granted in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The Department may use other forces to investigate and recover archaeological materials from the location of the discovery. If ordered by the Engineer furnish labor, material, tools, and equipment to secure the location of the discovery and assist in the investigation or recovery of archaeological materials; the cost of this work will be paid for as extra work as specified in Section 4-1.03D, "Extra Work," of the Standard Specifications.

**In Section 7-1.02 in the 2nd paragraph, replace the 4th sentence with:**

Trucks used to haul treated base, portland cement concrete, or hot mix asphalt shall enter onto the base to dump at the nearest practical entry point ahead of spreading equipment.

**In Section 7-1.02 between the 4th and 5th paragraphs, add:**

Loads imposed on existing, new, or partially completed structures shall not exceed the load carrying capacity of the structure or any portion of the structure as determined by AASHTO LRFD with interims and California Amendments, Design Strength Limit State II. The compressive strength of concrete ( $f_c$ ) to be used in computing the load carrying capacity shall be the smaller of the following:

1. Actual compressive strength at the time of loading
2. Value of  $f_c$  shown on the plans for that portion of the structure or 2.5 times the value of  $f_c$  (extreme fiber compressive stress in concrete at service loads) shown on the plans for portions of the structure where no  $f_c$  is shown

**In Section 7-1.06 in the 1st paragraph, add:**

The Contractor's Injury and Illness Prevention Program shall be submitted to the Engineer. The program shall address the use of personal and company issued electronic devices during work. The use of entertainment and personal communication devices in the work zone shall not be allowed. Workers may use a communication device for business purposes in the work area, at a location where their safety and the safety of other workers and the traveling public is not compromised.

**In Section 7-1.09 replace the 8th paragraph with:**

Signs, lights, flags, and other warning and safety devices and their use shall conform to the requirements set forth in Part 6 of the California MUTCD except where a discrepancy exists between the California MUTCD and the specifications; for discrepancies, comply with the specifications. Signs or other protective devices furnished and erected by the Contractor, at the Contractor's expense, as above provided, shall not obscure the visibility of, nor conflict in intent, meaning and function of either existing signs, lights and traffic control devices or any construction area signs and traffic control devices for which furnishing of, or payment for, is provided elsewhere in the specifications. Signs furnished and erected by the Contractor, at the Contractor's expense, shall be approved by the Engineer as to size, wording and location.

**In Section 7-1.09 replace the 14th paragraph with:**

The Contractor shall notify the Engineer not less than 18 days and no more than 90 days prior to the anticipated start of an operation that will change the vertical or horizontal clearance available to public traffic (including shoulders).

**In Section 7-1.09 replace the 16th paragraph with:**

When vertical clearance is temporarily reduced to 4.72 m or less, low clearance warning signs shall be placed in accordance with Part 2 of the California MUTCD and as directed by the Engineer. Signs shall conform to the dimensions, color, and legend requirements of the California MUTCD and these specifications except that the signs shall have black letters and numbers on an orange retroreflective background. W12-2P signs shall be illuminated so that the signs are clearly visible.

**Add to Section 7-1.09:**

The Contractor shall install temporary railing (Type K) between a lane open to public traffic and an excavation, obstacle or storage area when the following conditions exist:

- A. Excavations-The near edge of the excavation is 3.6 m or less from the edge of the lane, except:
  - 1. Excavations covered with sheet steel or concrete covers of adequate thickness to prevent accidental entry by traffic or the public.
  - 2. Excavations less than 0.3 m deep.
  - 3. Trenches less than 0.3 m wide for irrigation pipe or electrical conduit, or excavations less than 0.3 m in diameter.
  - 4. Excavations parallel to the lane for the purpose of pavement widening or reconstruction.
  - 5. Excavations in side slopes, where the slope is steeper than 4:1 (horizontal:vertical).
  - 6. Excavations protected by existing barrier or railing.
- B. Temporarily Unprotected Permanent Obstacles-The work includes the installation of a fixed obstacle together with a protective system, such as a sign structure together with protective railing, and the Contractor elects to install the obstacle prior to installing the protective system; or the Contractor, for the Contractor's convenience and with permission of the Engineer, removes a portion of an existing protective railing at an obstacle and does not replace such railing complete in place during the same day.
- C. Storage Areas-Material or equipment is stored within 3.6 m of the lane and the storage is not otherwise prohibited by the provisions of the Standard Specifications and these special provisions.

The approach end of temporary railing (Type K), installed in conformance with the provisions in this section "Public Safety" and in Section 7-1.09, "Public Safety," of the Standard Specifications, shall be offset a minimum of 4.6 m from the edge of the traffic lane open to public traffic. The temporary railing shall be installed on a skew toward the edge of the traffic lane of not more than 0.3 m transversely to 3 m longitudinally with respect to the edge of the traffic lane. If the 4.6 m minimum offset cannot be achieved, the temporary railing shall be installed on the 10 to 1 skew to obtain the maximum available offset between the approach end of the railing and the edge of the traffic lane, and an array of temporary crash cushion modules shall be installed at the approach end of the temporary railing.

Temporary railing (Type K) shall be secured in place before starting work for which the temporary railing is required.

Except for installing, maintaining and removing traffic control devices, whenever work is performed or equipment is operated in the following work areas, the Contractor shall close the adjacent traffic lane unless otherwise provided in the Standard Specifications and these special provisions:

Approach Speed of Public Traffic (Posted Limit) (Kilometers Per Hour)	Work Areas
Over 72 (45 Miles Per Hour)	Within 1.8 m of a traffic lane but not on a traffic lane
56 to 72 (35 to 45 Miles Per Hour)	Within 0.9 m of a traffic lane but not on a traffic lane

The lane closure provisions of this section shall not apply if the work area is protected by permanent or temporary railing or barrier.

When traffic cones or delineators are used to delineate a temporary edge of a traffic lane, the line of cones or delineators shall be considered to be the edge of the traffic lane, however, the Contractor shall not reduce the width of an existing lane to less than 3 m without written approval from the Engineer.

When work is not in progress on a trench or other excavation that required closure of an adjacent lane, the traffic cones or portable delineators used for the lane closure shall be placed off of and adjacent to the edge of the traveled way. The spacing of the cones or delineators shall be not more than the spacing used for the lane closure.

Suspended loads or equipment shall not be moved nor positioned over public traffic or pedestrians.

**Replace Section 7-1.11 with:**

**7-1.11 PRESERVATION OF PROPERTY**

Comply with Section 5-1.18, "Property and Facility Preservation."

**Replace Section 7-1.12 with:**

**7-1.12 INDEMNIFICATION AND INSURANCE**

The Contractor's obligations regarding indemnification of the State of California and the requirements for insurance shall conform to the provisions in Section 3-1.05, "Insurance Policies," and Sections 7-1.12A, "Indemnification," and 7-1.12B, "Insurance," of this Section 7-1.12.

**7-1.12A Indemnification**

The Contractor shall defend, indemnify, and save harmless the State, including its officers, employees, and agents (excluding agents who are design professionals) from any and all claims, demands, causes of action, damages, costs, expenses, actual attorneys' fees, losses or liabilities, in law or in equity (Section 7-1.12A Claims) arising out of or in connection with the Contractor's performance of this contract for:

1. Bodily injury including, but not limited to, bodily injury, sickness or disease, emotional injury or death to persons, including, but not limited to, the public, any employees or agents of the Contractor, the State, or any other contractor; and
2. Damage to property of anyone including loss of use thereof; caused or alleged to be caused in whole or in part by any negligent or otherwise legally actionable act or omission of the Contractor or anyone directly or indirectly employed by the Contractor or anyone for whose acts the Contractor may be liable.

Except as otherwise provided by law, these requirements apply regardless of the existence or degree of fault of the State. The Contractor is not obligated to indemnify the State for Claims arising from conduct delineated in Civil Code Section 2782 and to Claims arising from any defective or substandard condition of the highway that existed at or before the start of work, unless this condition has been changed by the work or the scope of the work requires the Contractor to maintain existing highway facilities and the Claim arises from the Contractor's failure to maintain. The Contractor's defense and indemnity obligation shall extend to Claims arising after the work is completed and accepted if the Claims are directly related to alleged acts or omissions by the Contractor that occurred during the course of the work. State inspection is not a waiver of full compliance with these requirements.

The Contractor's obligation to defend and indemnify shall not be excused because of the Contractor's inability to evaluate liability or because the Contractor evaluates liability and determine that the Contractor is not liable. The Contractor shall respond within 30 days to the tender of any Claim for defense and indemnity by the State, unless this time has been extended by the State. If the Contractor fails to accept or reject a tender of defense and indemnity within 30 days, in addition to any other remedy authorized by law, the Department may withhold such funds the State reasonably considers necessary for its defense and indemnity until disposition has been made of the Claim or until the Contractor accepts or rejects the tender of defense, whichever occurs first.

With respect to third-party claims against the Contractor, the Contractor waives all rights of any type to express or implied indemnity against the State, its officers, employees, or agents (excluding agents who are design professionals).

Nothing in the Contract is intended to establish a standard of care owed to any member of the public or to extend to the public the status of a third-party beneficiary for any of these indemnification specifications.

**7-1.12B Insurance**

**7-1.12B(1) General**

Nothing in the contract is intended to establish a standard of care owed to any member of the public or to extend to the public the status of a third-party beneficiary for any of these insurance specifications.

**7-1.12B(2) Casualty Insurance**

The Contractor shall procure and maintain insurance on all of its operations with companies acceptable to the State as follows:

1. The Contractor shall keep all insurance in full force and effect from the beginning of the work through contract acceptance.

2. All insurance shall be with an insurance company with a rating from A.M. Best Financial Strength Rating of A- or better and a Financial Size Category of VII or better.
3. The Contractor shall maintain completed operations coverage with a carrier acceptable to the State through the expiration of the patent deficiency in construction statute of repose set forth in Code of Civil Procedure Section 337.1.

**7-1.12B(3) Workers' Compensation and Employer's Liability Insurance**

In accordance with Labor Code Section 1860, the Contractor shall secure the payment of worker's compensation in accordance with Labor Code Section 3700.

In accordance with Labor Code Section 1861, the Contractor shall submit to the Department the following certification before performing the work:

I am aware of the provisions of Section 3700 of the Labor Code which require every employer to be insured against liability for workers' compensation or to undertake self-insurance in accordance with the provisions of that code, and I will comply with such provisions before commencing the performance of the work of this contract.

Contract execution constitutes certification submittal.

The Contractor shall provide Employer's Liability Insurance in amounts not less than:

1. \$1 000 000 for each accident for bodily injury by accident
2. \$1 000 000 policy limit for bodily injury by disease
3. \$1 000 000 for each employee for bodily injury by disease

If there is an exposure of injury to the Contractor's employees under the U.S. Longshoremen's and Harbor Workers' Compensation Act, the Jones Act, or under laws, regulations, or statutes applicable to maritime employees, coverage shall be included for such injuries or claims.

**7-1.12B(4) Liability Insurance**

**7-1.12B(4)(a) General**

The Contractor shall carry General Liability and Umbrella or Excess Liability Insurance covering all operations by or on behalf of the Contractor providing insurance for bodily injury liability and property damage liability for the following limits and including coverage for:

1. Premises, operations, and mobile equipment
2. Products and completed operations
3. Broad form property damage (including completed operations)
4. Explosion, collapse, and underground hazards
5. Personal injury
6. Contractual liability

**7-1.12B(4)(b) Liability Limits/Additional Insureds**

The limits of liability shall be at least the amounts shown in the following table:

Total Bid	For Each Occurrence <sup>1</sup>	Aggregate for Products/Completed Operation	General Aggregate <sup>2</sup>	Umbrella or Excess Liability <sup>3</sup>
≤\$1 000 000	\$1 000 000	\$2 000 000	\$2 000 000	\$5 000 000
>\$1 000 000				
≤\$10 000 000	\$1 000 000	\$2 000 000	\$2 000 000	\$10 000 000
>\$10 000 000				
≤\$25 000 000	\$2 000 000	\$2 000 000	\$4 000 000	\$15 000 000
>\$25 000 000	\$2 000 000	\$2 000 000	\$4 000 000	\$25 000 000
1. Combined single limit for bodily injury and property damage. 2. This limit shall apply separately to the Contractor's work under this contract. 3. The umbrella or excess policy shall contain a clause stating that it takes effect (drops down) in the event the primary limits are impaired or exhausted.				

The Contractor shall not require certified Small Business subcontractors to carry Liability Insurance that exceeds the limits in the table above. Notwithstanding the limits specified herein, at the option of the Contractor, the liability insurance limits for certified Small Business subcontractors of any tier may be less than those limits specified in the table. For Small Business subcontracts, "Total Bid" shall be interpreted as the amount of subcontracted work to a certified Small Business.

The State, including its officers, directors, agents (excluding agents who are design professionals), and employees, shall be named as additional insureds under the General Liability and Umbrella Liability Policies with respect to liability arising out of or connected with work or operations performed by or on behalf of the Contractor under this contract. Coverage for such additional insureds does not extend to liability:

1. Arising from any defective or substandard condition of the roadway which existed at or before the time the Contractor started work, unless such condition has been changed by the work or the scope of the work requires the Contractor to maintain existing roadway facilities and the claim arises from the Contractor's failure to maintain;
2. For claims occurring after the work is completed and accepted unless these claims are directly related to alleged acts or omissions of the Contractor that occurred during the course of the work; or
3. To the extent prohibited by Insurance Code Section 11580.04

Additional insured coverage shall be provided by a policy provision or by an endorsement providing coverage at least as broad as Additional Insured (Form B) endorsement form CG 2010, as published by the Insurance Services Office (ISO), or other form designated by the Department.

#### **7-1.12B(4)(c) Contractor's Insurance Policy is Primary**

The policy shall stipulate that the insurance afforded the additional insureds applies as primary insurance. Any other insurance or self-insurance maintained by the State is excess only and shall not be called upon to contribute with this insurance.

#### **7-1.12B(5) Automobile Liability Insurance**

The Contractor shall carry automobile liability insurance, including coverage for all owned, hired, and nonowned automobiles. The primary limits of liability shall be not less than \$1 000 000 combined single limit each accident for bodily injury and property damage. The umbrella or excess liability coverage required under Section 7-1.12B(4)(b) also applies to automobile liability.

#### **7-1.12B(6) Policy Forms, Endorsements, and Certificates**

The Contractor shall provide its General Liability Insurance under Commercial General Liability policy form No. CG0001 as published by the Insurance Services Office (ISO) or under a policy form at least as broad as policy form No. CG0001.

#### **7-1.12B(7) Deductibles**

The State may expressly allow deductible clauses, which it does not consider excessive, overly broad, or harmful to the interests of the State. Regardless of the allowance of exclusions or deductions by the State, the Contractor is responsible for any deductible amount and shall warrant that the coverage provided to the State is in accordance with Section 7-1.12B, "Insurance."

#### **7-1.12B(8) Enforcement**

The Department may assure the Contractor's compliance with its insurance obligations. Ten days before an insurance policy lapses or is canceled during the contract period, the Contractor shall submit to the Department evidence of renewal or replacement of the policy.

If the Contractor fails to maintain any required insurance coverage, the Department may maintain this coverage and withhold or charge the expense to the Contractor or terminate the Contractor's control of the work in accordance with Section 8-1.08, "Termination of Control."

The Contractor is not relieved of its duties and responsibilities to indemnify, defend, and hold harmless the State, its officers, agents, and employees by the Department's acceptance of insurance policies and certificates.

Minimum insurance coverage amounts do not relieve the Contractor for liability in excess of such coverage, nor do they preclude the State from taking other actions available to it, including the withholding of funds under this contract.

#### **7-1.12B(9) Self-Insurance**

Self-insurance programs and self-insured retentions in insurance policies are subject to separate annual review and approval by the State.

If the Contractor uses a self-insurance program or self-insured retention, the Contractor shall provide the State with the same protection from liability and defense of suits as would be afforded by first-dollar insurance. Execution of the contract is the Contractor's acknowledgement that the Contractor will be bound by all laws as if the Contractor were an insurer as defined under Insurance Code Section 23 and that the self-insurance program or self-insured retention shall operate as insurance as defined under Insurance Code Section 22.

**In Section 7-1.13 delete the 5th and 6th paragraphs.**

**Add:**

**7-1.50 FEDERAL LAWS FOR FEDERAL-AID CONTRACTS**

**7-1.50A General**

Section 7-1.50, "Federal Laws for Federal-Aid Contracts," includes specifications required in a Federal-aid construction contract and applies to a Federal-aid contract.

Form FHWA-1273 is included in the contract in Section 7-1.50B, "FHWA-1273." Some contract terms on the form are different than those used in other contract parts as shown in the following table:

<b>FHWA-1273 Terms and Department Equivalencies</b>	
FHWA-1273 Term	Equivalent Term Used in Other Contract Parts
SHA	Department
SHA contracting officer	Engineer
SHA resident engineer	Engineer

**7-1.50B FHWA-1273**

FHWA-1273 Electronic version -- March 10, 1994  
with revised Section VI

**REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS**

- I. General
- II. Nondiscrimination
- III. Nonsegregated Facilities
- IV. Payment of Predetermined Minimum Wage
- V. Statements and Payrolls
- VI. Record of Materials, Supplies, and Labor
- VII. Subletting or Assigning the Contract
- VIII. Safety: Accident Prevention
- IX. False Statements Concerning Highway Projects
- X. Implementation of Clean Air Act and Federal Water Pollution Control Act
- XI. Certification Regarding Debarment, Suspension, Ineligibility, and Voluntary Exclusion
- XII. Certification Regarding Use of Contract Funds for Lobbying

**ATTACHMENTS**

- A. Employment Preference for Appalachian Contracts (included in Appalachian contracts only)

**I. GENERAL**

- 1. These contract provisions shall apply to all work performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.
- 2. Except as otherwise provided for in each section, the contractor shall insert in each subcontract all of the stipulations contained in these Required Contract Provisions, and further require their inclusion in any lower tier subcontract or purchase order that may in turn be made. The Required Contract Provisions shall not be incorporated by reference in any case. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with these Required Contract Provisions.
- 3. A breach of any of the stipulations contained in these Required Contract Provisions shall be sufficient grounds for termination of the contract.
- 4. A breach of the following clauses of the Required Contract Provisions may also be grounds for debarment as provided in 29 CFR 5.12:

Section I, paragraph 2;  
Section IV, paragraphs 1, 2, 3, 4, and 7;  
Section V, paragraphs 1 and 2a through 2g.

5. Disputes arising out of the labor standards provisions of Section IV (except paragraph 5) and Section V of these Required Contract Provisions shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the U.S. Department of Labor (DOL) as set forth in 29 CFR 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the DOL, or the contractor's employees or their representatives.
6. **Selection of Labor:** During the performance of this contract, the contractor shall not:
  - a. discriminate against labor from any other State, possession, or territory of the United States (except for employment preference for Appalachian contracts, when applicable, as specified in Attachment A), or
  - b. employ convict labor for any purpose within the limits of the project unless it is labor performed by convicts who are on parole, supervised release, or probation.

## II. NONDISCRIMINATION

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$10,000 or more.)

1. **Equal Employment Opportunity:** Equal employment opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (28 CFR 35, 29 CFR 1630 and 41 CFR 60) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140 shall constitute the EEO and specific affirmative action standards for the contractor's project activities under this contract. The Equal Opportunity Construction Contract Specifications set forth under 41 CFR 60-4.3 and the provisions of the American Disabilities Act of 1990 (42 U.S.C. 12101 *et seq.*) set forth under 28 CFR 35 and 29 CFR 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:
  - a. The contractor will work with the State highway agency (SHA) and the Federal Government in carrying out EEO obligations and in their review of his/her activities under the contract.
  - b. The contractor will accept as his operating policy the following statement:

"It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, preapprenticeship, and/or on-the-job training."
2. **EEO Officer:** The contractor will designate and make known to the SHA contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active contractor program of EEO and who must be assigned adequate authority and responsibility to do so.
3. **Dissemination of Policy:** All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:
  - a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.
  - b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.
  - c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minority group employees.
  - d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.

- e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.
4. **Recruitment:** When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minority groups in the area from which the project work force would normally be derived.
    - a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minority group applicants. To meet this requirement, the contractor will identify sources of potential minority group employees, and establish with such identified sources procedures whereby minority group applicants may be referred to the contractor for employment consideration.
    - b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, he is expected to observe the provisions of that agreement to the extent that the system permits the contractor's compliance with EEO contract provisions. (The DOL has held that where implementation of such agreements have the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Executive Order 11246, as amended.)
    - c. The contractor will encourage his present employees to refer minority group applicants for employment. Information and procedures with regard to referring minority group applicants will be discussed with employees.
  5. **Personnel Actions:** Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, national origin, age or disability. The following procedures shall be followed:
    - a. The contractor will conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.
    - b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.
    - c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.
    - d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with his obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of his avenues of appeal.
  6. **Training and Promotion:**
    - a. The contractor will assist in locating, qualifying, and increasing the skills of minority group and women employees, and applicants for employment.
    - b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance. Where feasible, 25 percent of apprentices or trainees in each occupation shall be in their first year of apprenticeship or training. In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision.
    - c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.
    - d. The contractor will periodically review the training and promotion potential of minority group and women employees and will encourage eligible employees to apply for such training and promotion.
  7. **Unions:** If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use his/her best efforts to obtain the cooperation of such unions to increase opportunities for minority groups and women within the unions, and to effect referrals by such unions of minority and female employees. Actions by the

contractor either directly or through a contractor's association acting as agent will include the procedures set forth below:

- a. The contractor will use best efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minority group members and women for membership in the unions and increasing the skills of minority group employees and women so that they may qualify for higher paying employment.
  - b. The contractor will use best efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age or disability.
  - c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the SHA and shall set forth what efforts have been made to obtain such information.
  - d. In the event the union is unable to provide the contractor with a reasonable flow of minority and women referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age or disability; making full efforts to obtain qualified and/or qualifiable minority group persons and women. (The DOL has held that it shall be no excuse that the union with which the contractor has a collective bargaining agreement providing for exclusive referral failed to refer minority employees.) In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these specifications, such contractor shall immediately notify the SHA.
8. **Selection of Subcontractors, Procurement of Materials and Leasing of Equipment:** The contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment.
- a. The contractor shall notify all potential subcontractors and suppliers of his/her EEO obligations under this contract.
  - b. Disadvantaged business enterprises (DBE), as defined in 49 CFR 23, shall have equal opportunity to compete for and perform subcontracts which the contractor enters into pursuant to this contract. The contractor will use his best efforts to solicit bids from and to utilize DBE subcontractors or subcontractors with meaningful minority group and female representation among their employees. Contractors shall obtain lists of DBE construction firms from SHA personnel.
  - c. The contractor will use his best efforts to ensure subcontractor compliance with their EEO obligations.
9. **Records and Reports:** The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following completion of the contract work and shall be available at reasonable times and places for inspection by authorized representatives of the SHA and the FHWA.
- a. The records kept by the contractor shall document the following:
    1. The number of minority and non-minority group members and women employed in each work classification on the project;
    2. The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women;
    3. The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minority and female employees; and
    4. The progress and efforts being made in securing the services of DBE subcontractors or subcontractors with meaningful minority and female representation among their employees.
  - b. The contractors will submit an annual report to the SHA each July for the duration of the project, indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on Form FHWA-1391. If on-the-job training is being required by special provision, the contractor will be required to collect and report training data.

### III. NONSEGREGATED FACILITIES

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$10,000 or more.)

- a. By submission of this bid, the execution of this contract or subcontract, or the consummation of this material supply agreement or purchase order, as appropriate, the bidder, Federal-aid construction contractor, subcontractor, material supplier, or vendor, as appropriate, certifies that the firm does not maintain or provide for its employees any segregated facilities at any of its establishments, and that the firm does not permit its employees to perform their services at any location, under its control, where segregated facilities are maintained. The firm agrees that a breach of this certification is a violation of the EEO provisions of this contract. The firm further certifies that no employee will be denied access to adequate facilities on the basis of sex or disability.
- b. As used in this certification, the term "segregated facilities" means any waiting rooms, work areas, restrooms and washrooms, restaurants and other eating areas, timeclocks, locker rooms, and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are segregated by explicit directive, or are, in fact, segregated on the basis of race, color, religion, national origin, age or disability, because of habit, local custom, or otherwise. The only exception will be for the disabled when the demands for accessibility override (e.g. disabled parking).
- c. The contractor agrees that it has obtained or will obtain identical certification from proposed subcontractors or material suppliers prior to award of subcontracts or consummation of material supply agreements of \$10,000 or more and that it will retain such certifications in its files.

#### **IV. PAYMENT OF PREDETERMINED MINIMUM WAGE**

(Applicable to all Federal-aid construction contracts exceeding \$2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural minor collectors, which are exempt.)

##### **1. General:**

- a. All mechanics and laborers employed or working upon the site of the work will be paid unconditionally and not less often than once a week and without subsequent deduction or rebate on any account [except such payroll deductions as are permitted by regulations (29 CFR 3) issued by the Secretary of Labor under the Copeland Act (40 U.S.C. 276c)] the full amounts of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment. The payment shall be computed at wage rates not less than those contained in the wage determination of the Secretary of Labor (hereinafter "the wage determination") which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor or its subcontractors and such laborers and mechanics. The wage determination (including any additional classifications and wage rates conformed under paragraph 2 of this Section IV and the DOL poster (WH-1321) or Form FHWA-1495) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers. For the purpose of this Section, contributions made or costs reasonably anticipated for bona fide fringe benefits under Section 1(b) (2) of the Davis- Bacon Act (40 U.S.C. 276a) on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of Section IV, paragraph 3b, hereof. Also, for the purpose of this Section, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs, which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in paragraphs 4 and 5 of this Section IV.
- b. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein, provided, that the employer's payroll records accurately set forth the time spent in each classification in which work is performed.
- c. All rulings and interpretations of the Davis-Bacon Act and related acts contained in 29 CFR 1, 3, and 5 are herein incorporated by reference in this contract.

##### **2. Classification:**

- a. The SHA contracting officer shall require that any class of laborers or mechanics employed under the contract, which is not listed in the wage determination, shall be classified in conformance with the wage determination.
- b. The contracting officer shall approve an additional classification, wage rate and fringe benefits only when the following criteria have been met:
  1. the work to be performed by the additional classification requested is not performed by a classification in the wage determination;
  2. the additional classification is utilized in the area by the construction industry;
  3. the proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination; and

4. with respect to helpers, when such a classification prevails in the area in which the work is performed.
  - c. If the contractor or subcontractors, as appropriate, the laborers and mechanics (if known) to be employed in the additional classification or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the DOL, Administrator of the Wage and Hour Division, Employment Standards Administration, Washington, D.C. 20210. The Wage and Hour Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
  - d. In the event the contractor or subcontractors, as appropriate, the laborers or mechanics to be employed in the additional classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Wage and Hour Administrator for determination. Said Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
  - e. The wage rate (including fringe benefits where appropriate) determined pursuant to paragraph 2c or 2d of this Section IV shall be paid to all workers performing work in the additional classification from the first day on which work is performed in the classification.
3. **Payment of Fringe Benefits:**
- a. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor or subcontractors, as appropriate, shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly case equivalent thereof.
  - b. If the contractor or subcontractor, as appropriate, does not make payments to a trustee or other third person, he/she may consider as a part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, provided, that the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.
4. **Apprentices and Trainees (Programs of the U.S. DOL) and Helpers:**
- a. Apprentices:
    1. Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the DOL, Employment and Training Administration, Bureau of Apprenticeship and Training, or with a State apprenticeship agency recognized by the Bureau, or if a person is employed in his/her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Bureau of Apprenticeship and Training or a State apprenticeship agency (where appropriate) to be eligible for probationary employment as an apprentice.
    2. The allowable ratio of apprentices to journeyman-level employees on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any employee listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate listed in the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor or subcontractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman-level hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.
    3. Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable

wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator for the Wage and Hour Division determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.

4. In the event the Bureau of Apprenticeship and Training, or a State apprenticeship agency recognized by the Bureau, withdraws approval of an apprenticeship program, the contractor or subcontractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the comparable work performed by regular employees until an acceptable program is approved.

b. Trainees:

1. Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the DOL, Employment and Training Administration.
2. The ratio of trainees to journeyman-level employees on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.
3. Every trainee must be paid at not less than the rate specified in the approved program for his/her level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman-level wage rate on the wage determination which provides for less than full fringe benefits for apprentices, in which case such trainees shall receive the same fringe benefits as apprentices.
4. In the event the Employment and Training Administration withdraws approval of a training program, the contractor or subcontractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

c. Helpers:

Helpers will be permitted to work on a project if the helper classification is specified and defined on the applicable wage determination or is approved pursuant to the conformance procedure set forth in Section IV.2. Any worker listed on a payroll at a helper wage rate, who is not a helper under an approved definition, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed.

5. **Apprentices and Trainees (Programs of the U.S. DOT):**

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.

6. **Withholding:**

The SHA shall upon its own action or upon written request of an authorized representative of the DOL withhold, or cause to be withheld, from the contractor or subcontractor under this contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to Davis-Bacon prevailing wage requirements which is held by the same prime contractor, as much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the SHA contracting officer may, after written notice to the contractor,

take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

**7. Overtime Requirements:**

No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers, mechanics, watchmen, or guards (including apprentices, trainees, and helpers described in paragraphs 4 and 5 above) shall require or permit any laborer, mechanic, watchman, or guard in any workweek in which he/she is employed on such work, to work in excess of 40 hours in such workweek unless such laborer, mechanic, watchman, or guard receives compensation at a rate not less than one-and-one-half times his/her basic rate of pay for all hours worked in excess of 40 hours in such workweek.

**8. Violation:**

Liability for Unpaid Wages; Liquidated Damages: In the event of any violation of the clause set forth in paragraph 7 above, the contractor and any subcontractor responsible thereof shall be liable to the affected employee for his/her unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory) for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer, mechanic, watchman, or guard employed in violation of the clause set forth in paragraph 7, in the sum of \$10 for each calendar day on which such employee was required or permitted to work in excess of the standard work week of 40 hours without payment of the overtime wages required by the clause set forth in paragraph 7.

**9. Withholding for Unpaid Wages and Liquidated Damages:**

The SHA shall upon its own action or upon written request of any authorized representative of the DOL withhold, or cause to be withheld, from any monies payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to the contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph 8 above.

**V. STATEMENTS AND PAYROLLS**

(Applicable to all Federal-aid construction contracts exceeding \$2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural collectors, which are exempt.)

**1. Compliance with Copeland Regulations (29 CFR 3):**

The contractor shall comply with the Copeland Regulations of the Secretary of Labor which are herein incorporated by reference.

**2. Payrolls and Payroll Records:**

- a. Payrolls and basic records relating thereto shall be maintained by the contractor and each subcontractor during the course of the work and preserved for a period of 3 years from the date of completion of the contract for all laborers, mechanics, apprentices, trainees, watchmen, helpers, and guards working at the site of the work.
- b. The payroll records shall contain the name, social security number, and address of each such employee; his or her correct classification; hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalent thereof the types described in Section 1(b)(2)(B) of the Davis Bacon Act); daily and weekly number of hours worked; deductions made; and actual wages paid. In addition, for Appalachian contracts, the payroll records shall contain a notation indicating whether the employee does, or does not, normally reside in the labor area as defined in Attachment A, paragraph 1. Whenever the Secretary of Labor, pursuant to Section IV, paragraph 3b, has found that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in Section 1(b)(2)(B) of the Davis Bacon Act, the contractor and each subcontractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, that the plan or program has been communicated in writing to the laborers or mechanics affected, and show the cost anticipated or the actual cost incurred in providing benefits. Contractors or subcontractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprentices and trainees, and ratios and wage rates prescribed in the applicable programs.
- c. Each contractor and subcontractor shall furnish, each week in which any contract work is performed, to the SHA resident engineer a payroll of wages paid each of its employees (including apprentices, trainees, and helpers, described in Section IV, paragraphs 4 and 5, and watchmen and guards engaged on work during the preceding weekly payroll period). The payroll submitted shall set out accurately and completely all of the information required to be maintained under paragraph 2b of this Section V. This information may be submitted

in any form desired. Optional Form WH-347 is available for this purpose and may be purchased from the Superintendent of Documents (Federal stock number 029- 005-0014-1), U.S. Government Printing Office, Washington, D.C. 20402. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors.

- d. Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor or his/her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:
  1. that the payroll for the payroll period contains the information required to be maintained under paragraph 2b of this Section V and that such information is correct and complete;
  2. that such laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in the Regulations, 29 CFR 3;
  3. that each laborer or mechanic has been paid not less than the applicable wage rate and fringe benefits or cash equivalent for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.
- e. The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 2d of this Section V.
- f. The falsification of any of the above certifications may subject the contractor to civil or criminal prosecution under 18 U.S.C. 1001 and 31 U.S.C. 231.
- g. The contractor or subcontractor shall make the records required under paragraph 2b of this Section V available for inspection, copying, or transcription by authorized representatives of the SHA, the FHWA, or the DOL, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the SHA, the FHWA, the DOL, or all may, after written notice to the contractor, sponsor, applicant, or owner, take such actions as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

## **VI. RECORD OF MATERIALS, SUPPLIES, AND LABOR**

(As of May 22, 2007, Form FHWA-47 is no longer required.)

## **VII. SUBLETTING OR ASSIGNING THE CONTRACT**

1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the State. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635).
  - a. "Its own organization" shall be construed to include only workers employed and paid directly by the prime contractor and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor, assignee, or agent of the prime contractor.
  - b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid on the contract as a whole and in general are to be limited to minor components of the overall contract.
2. The contract amount upon which the requirements set forth in paragraph 1 of Section VII is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.
3. The contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the SHA contracting officer determines is necessary to assure the performance of the contract.
4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the SHA contracting officer, or authorized representative, and such consent when given shall not be construed to relieve

the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the SHA has assured that each subcontract is evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract.

#### **VIII. SAFETY: ACCIDENT PREVENTION**

1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the SHA contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.
2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).
3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).

#### **IX. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS**

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by Engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, the following notice shall be posted on each Federal-aid highway project (23 CFR 635) in one or more places where it is readily available to all persons concerned with the project:

#### **NOTICE TO ALL PERSONNEL ENGAGED ON FEDERAL-AID HIGHWAY PROJECTS**

18 U.S.C. 1020 reads as follows:

"Whoever, being an officer, agent, or employee of the United States, or of any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 1, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined not more that \$10,000 or imprisoned not more than 5 years or both."

#### **X. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT**

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$100,000 or more.)

By submission of this bid or the execution of this contract, or subcontract, as appropriate, the bidder, Federal-aid construction contractor, or subcontractor, as appropriate, will be deemed to have stipulated as follows:

1. That any facility that is or will be utilized in the performance of this contract, unless such contract is exempt under the Clean Air Act, as amended (42 U.S.C. 1857 *et seq.*, as amended by Pub.L. 91-604), and under the Federal Water Pollution Control Act, as amended (33 U.S.C. 1251 *et seq.*, as amended by Pub.L. 92-500), Executive Order 11738, and regulations in implementation thereof (40 CFR 15) is not listed, on the date of contract award, on the U.S. Environmental Protection Agency (EPA) List of Violating Facilities pursuant to 40 CFR 15.20.

2. That the firm agrees to comply and remain in compliance with all the requirements of Section 114 of the Clean Air Act and Section 308 of the Federal Water Pollution Control Act and all regulations and guidelines listed thereunder.
3. That the firm shall promptly notify the SHA of the receipt of any communication from the Director, Office of Federal Activities, EPA, indicating that a facility that is or will be utilized for the contract is under consideration to be listed on the EPA List of Violating Facilities.
4. That the firm agrees to include or cause to be included the requirements of paragraph 1 through 4 of this Section X in every nonexempt subcontract, and further agrees to take such action as the government may direct as a means of enforcing such requirements.

## **XI. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION**

### **1. Instructions for Certification - Primary Covered Transactions:**

(Applicable to all Federal-aid contracts - 49 CFR 29)

- a. By signing and submitting this proposal, the prospective primary participant is providing the certification set out below.
- b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this covered transaction. The prospective participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective primary participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction.
- c. The certification in this clause is a material representation of fact upon which reliance was placed when the department or agency determined to enter into this transaction. If it is later determined that the prospective primary participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause of default.
- d. The prospective primary participant shall provide immediate written notice to the department or agency to whom this proposal is submitted if any time the prospective primary participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- e. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the department or agency to which this proposal is submitted for assistance in obtaining a copy of those regulations.
- f. The prospective primary participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction.
- g. The prospective primary participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," provided by the department or agency entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.
- h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the nonprocurement portion of the "Lists of Parties Excluded From Federal Procurement or Nonprocurement Programs" (Nonprocurement List) which is compiled by the General Services Administration.
- i. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- j. Except for transactions authorized under paragraph f of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

\* \* \* \* \*

**Certification Regarding Debarment, Suspension, Ineligibility and  
Voluntary Exclusion--Primary Covered Transactions**

1. The prospective primary participant certifies to the best of its knowledge and belief, that it and its principals:
  - a. Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
  - b. Have not within a 3-year period preceding this proposal been convicted of or had a civil judgement rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;
  - c. Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph 1b of this certification; and
  - d. Have not within a 3-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
2. Where the prospective primary participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

\* \* \* \* \*

**2. Instructions for Certification - Lower Tier Covered Transactions:**

(Applicable to all subcontracts, purchase orders and other lower tier transactions of \$25,000 or more - 49 CFR 29)

- a. By signing and submitting this proposal, the prospective lower tier is providing the certification set out below.
- b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department, or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.
- c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances.
- d. The terms "covered transaction," "debarred," "suspended," "ineligible," "primary covered transaction," "participant," "person," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations.
- e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.
- f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.
- g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the Nonprocurement List.
- h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

- i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

\* \* \* \* \*

**Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Covered Transactions:**

1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.
2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

\* \* \* \* \*

**XII. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING**

(Applicable to all Federal-aid construction contracts and to all related subcontracts which exceed \$100,000 - 49 CFR 20)

1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:
  - a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
  - b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.
2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.
3. The prospective participant also agrees by submitting his or her bid or proposal that he or she shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such recipients shall certify and disclose accordingly.

**7-1.50C Female and Minority Goals**

To comply with Section II, "Nondiscrimination," of "Required Contract Provisions Federal-Aid Construction Contracts," the Department is including in Section 7-1.50C, "Female and Minority Goals," female and minority utilization goals for Federal-aid construction contracts and subcontracts that exceed \$10,000.

The nationwide goal for female utilization is 6.9 percent.

The goals for minority utilization [45 Fed Reg 65984 (10/3/1980)] are as follows:

**Minority Utilization Goals**

Economic Area		Goal (Percent)
174	Redding CA: Non-SMSA Counties: CA Lassen; CA Modoc; CA Plumas; CA Shasta; CA Siskiyou; CA Tehama	6.8
175	Eureka, CA Non-SMSA Counties: CA Del Norte; CA Humboldt; CA Trinity	6.6
176	San Francisco-Oakland-San Jose, CA: SMSA Counties: 7120 Salinas-Seaside-Monterey, CA CA Monterey 7360 San Francisco-Oakland CA Alameda; CA Contra Costa; CA Marin; CA San Francisco; CA San Mateo 7400 San Jose, CA CA Santa Clara, CA 7485 Santa Cruz, CA CA Santa Cruz 7500 Santa Rosa CA Sonoma 8720 Vallejo-Fairfield-Napa, CA CA Napa; CA Solano Non-SMSA Counties: CA Lake; CA Mendocino; CA San Benito	28.9  25.6   19.6  14.9  9.1  17.1  23.2
177	Sacramento, CA: SMSA Counties: 6920 Sacramento, CA CA Placer; CA Sacramento; CA Yolo Non-SMSA Counties CA Butte; CA Colusa; CA El Dorado; CA Glenn; CA Nevada; CA Sierra; CA Sutter; CA Yuba	16.1  14.3
178	Stockton-Modesto, CA: SMSA Counties: 5170 Modesto, CA CA Stanislaus 8120 Stockton, CA CA San Joaquin Non-SMSA Counties CA Alpine; CA Amador; CA Calaveras; CA Mariposa; CA Merced; CA Toulumne	12.3  24.3  19.8
179	Fresno-Bakersfield, CA SMSA Counties: 0680 Bakersfield, CA CA Kern 2840 Fresno, CA CA Fresno Non-SMSA Counties: CA Kings; CA Madera; CA Tulare	19.1  26.1  23.6
180	Los Angeles, CA: SMSA Counties: 0360 Anaheim-Santa Ana-Garden Grove, CA CA Orange 4480 Los Angeles-Long Beach, CA CA Los Angeles 6000 Oxnard-Simi Valley-Ventura, CA CA Ventura 6780 Riverside-San Bernardino-Ontario, CA	11.9  28.3  21.5  19.0

	CA Riverside; CA San Bernardino 7480 Santa Barbara-Santa Maria-Lompoc, CA	19.7
	CA Santa Barbara Non-SMSA Counties CA Inyo; CA Mono; CA San Luis Obispo	24.6
181	San Diego, CA: SMSA Counties 7320 San Diego, CA	16.9
	CA San Diego Non-SMSA Counties CA Imperial	18.2

For each July during which work is performed under the contract, you and each non-material-supplier subcontractor with a subcontract of \$10,000 or more must complete Form FHWA PR-1391 (Appendix C to 23 CFR 230). Submit the forms by August 15.

### 7-1.50D Training

Section 7-1.50D, "Training," applies if a number of trainees or apprentices is specified in the special provisions.

As part of your equal opportunity affirmative action program, provide on-the-job training to develop full journeymen in the types of trades or job classifications involved.

You have primary responsibility for meeting this training requirement.

If you subcontract a contract part, determine how many trainees or apprentices are to be trained by the subcontractor.

Include these training requirements in your subcontract.

Where feasible, 25 percent of apprentices or trainees in each occupation must be in their 1st year of apprenticeship or training.

Distribute the number of apprentices or trainees among the work classifications on the basis of your needs and the availability of journeymen in the various classifications within a reasonable recruitment area.

Before starting work, submit to the Department:

1. Number of apprentices or trainees to be trained for each classification
2. Training program to be used
3. Training starting date for each classification

Obtain the Department's approval for this submitted information before you start work. The Department credits you for each apprentice or trainee you employ on the work who is currently enrolled or becomes enrolled in an approved program.

The primary objective of Section 7-1.50D, "Training," is to train and upgrade minorities and women toward journeyman status. Make every effort to enroll minority and women apprentices or trainees, such as conducting systematic and direct recruitment through public and private sources likely to yield minority and women apprentices or trainees, to the extent they are available within a reasonable recruitment area. Show that you have made the efforts. In making these efforts, do not discriminate against any applicant for training.

Do not employ as an apprentice or trainee an employee:

1. In any classification in which the employee has successfully completed a training course leading to journeyman status or in which the employee has been employed as a journeyman
2. Who is not registered in a program approved by the US Department of Labor, Bureau of Apprenticeship and Training

Ask the employee if the employee has successfully completed a training course leading to journeyman status or has been employed as a journeyman. Your records must show the employee's answers to the questions.

In your training program, establish the minimum length and training type for each classification. The Department and FHWA approves a program if one of the following is met:

1. It is calculated to:
  - 1.1. Meet the your equal employment opportunity responsibilities
  - 1.2. Qualify the average apprentice or trainee for journeyman status in the classification involved by the end of the training period





**In Section 9-1.03C delete the 6th paragraph.**

**Replace Section 9-1.04 with:**

**9-1.04 NOTICE OF POTENTIAL CLAIM**

It is the intention of this section that disputes between the parties arising under and by virtue of the contract be brought to the attention of the Engineer at the earliest possible time in order that the matters may be resolved, if possible, or other appropriate action promptly taken.

Disputes will not be considered unless the Contractor has first complied with specified notice or protest requirements, including Section 4-1.03, "Changes," Section 5-1.116, "Differing Site Conditions," Section 8-1.06, "Time of Completion," Section 8-1.07, "Liquidated Damages," and Section 8-1.10, "Utility and Non-Highway Facilities."

For disputes arising under and by virtue of the contract, including an act or failure to act by the Engineer, the Contractor shall provide a signed written initial notice of potential claim to the Engineer within 5 days from the date the dispute first arose. The initial notice of potential claim shall provide the nature and circumstances involved in the dispute which shall remain consistent through the dispute. The initial notice of potential claim shall be submitted on Form CEM-6201A furnished by the Department and shall be certified with reference to the California False Claims Act, Government Code Sections 12650-12655. The Contractor shall assign an exclusive identification number for each dispute, determined by chronological sequencing, based on the date of the dispute.

The exclusive identification number for each dispute shall be used on the following corresponding documents:

1. Initial notice of potential claim
2. Supplemental notice of potential claim
3. Full and final documentation of potential claim
4. Corresponding claim included in the Contractor's written statement of claims

The Contractor shall provide the Engineer the opportunity to examine the site of work within 5 days from the date of the initial notice of potential claim. The Contractor shall proceed with the performance of contract work unless otherwise specified or directed by the Engineer.

Throughout the disputed work, the Contractor shall maintain records that provide a clear distinction between the incurred direct costs of disputed work and that of undisputed work. The Contractor shall allow the Engineer access to the Contractor's project records deemed necessary by the Engineer to evaluate the potential claim within 20 days of the date of the Engineer's written request.

Within 15 days of submitting the initial notice of potential claim, the Contractor shall provide a signed supplemental notice of potential claim to the Engineer that provides the following information:

1. The complete nature and circumstances of the dispute which caused the potential claim
2. The contract provisions that provide the basis of claim
3. The estimated cost of the potential claim, including an itemized breakdown of individual costs and how the estimate was determined
4. A time impact analysis of the project schedule that illustrates the effect on the scheduled completion date due to schedule changes or disruptions where a request for adjustment of contract time is made

The information provided in items 1 and 2 above shall provide the Contractor's complete reasoning for additional compensation or adjustments.

The supplemental notice of potential claim shall be submitted on Form CEM-6201B furnished by the Department and shall be certified with reference to the California False Claims Act, Government Code Sections 12650-12655. The Engineer will evaluate the information presented in the supplemental notice of potential claim and provide a written response to the Contractor within 20 days of its receipt. If the estimated cost or effect on the scheduled completion date changes, the Contractor shall update information in items 3 and 4 above as soon as the change is recognized and submit this information to the Engineer.

Within 30 days of the completion of work related to the potential claim, the Contractor shall provide the full and final documentation of potential claim to the Engineer that provides the following information:

1. A detailed factual narration of events fully describing the nature and circumstances that caused the dispute, including, but not limited to, necessary dates, locations, and items of work affected by the dispute

2. The specific provisions of the contract that support the potential claim and a statement of the reasons these provisions support and provide a basis for entitlement of the potential claim
3. When additional monetary compensation is requested, the exact amount requested calculated in conformance with Section 9-1.03, "Force Account Payment," or Section 8-1.09, "Right of Way Delays," including an itemized breakdown of individual costs. These costs shall be segregated into the following cost categories:
  - 3.1. Labor – A listing of individuals, classifications, regular hours and overtime hours worked, dates worked, and other pertinent information related to the requested reimbursement of labor costs
  - 3.2. Materials – Invoices, purchase orders, location of materials either stored or incorporated into the work, dates materials were transported to the project or incorporated into the work, and other pertinent information related to the requested reimbursement of material costs
  - 3.3. Equipment – Listing of detailed description (make, model, and serial number), hours of use, dates of use and equipment rates. Equipment rates shall be at the applicable State rental rate as listed in the Department of Transportation publication entitled "Labor Surcharge and Equipment Rental Rates," in effect when the affected work related to the dispute was performed.
  - 3.4. Other categories as specified by the Contractor or the Engineer
4. When an adjustment of contract time is requested the following information shall be provided:
  - 4.1. The specific dates for which contract time is being requested
  - 4.2. The specific reasons for entitlement to a contract time adjustment
  - 4.3. The specific provisions of the contract that provide the basis for the requested contract time adjustment
  - 4.4. A detailed time impact analysis of the project schedule. The time impact analysis shall show the effect of changes or disruptions on the scheduled completion date to demonstrate entitlement to a contract time adjustment.
5. The identification and copies of the Contractor's documents and the substance of oral communications that support the potential claim

The full and final documentation of the potential claim shall be submitted on Form CEM-6201C furnished by the Department and shall be certified with reference to the California False Claims Act, Government Code Sections 12650-12655.

Pertinent information, references, arguments, and data to support the potential claim shall be included in the full and final documentation of potential claim. Information submitted subsequent to the full and final documentation submittal will not be considered. Information required in the full and final documentation of potential claim, as listed in items 1 to 5 above, that is not applicable to the dispute may be exempted as determined by the Engineer. No full and final documentation of potential claim will be considered that does not have the same nature and circumstances, and basis of claim as those specified on the initial and supplemental notices of potential claim.

The Engineer will evaluate the information presented in the full and final documentation of potential claim and provide a written response to the Contractor within 30 days of its receipt unless otherwise specified. The Engineer's receipt of the full and final documentation of potential claim shall be evidenced by postal receipt or the Engineer's written receipt if delivered by hand. If the full and final documentation of potential claim is submitted by the Contractor after acceptance of the work by the Director, the Engineer need not provide a written response.

Provisions in this section shall not apply to those claims for overhead costs and administrative disputes that occur after issuance of the proposed final estimate. Administrative disputes are disputes of administrative deductions or withholds, contract item quantities, contract item adjustments, interest payments, protests of contract change orders as provided in Section 4-1.03A, "Procedure and Protest," and protests of the Weekly Statement of Working Days as provided in Section 8-1.06, "Time of Completion." Administrative disputes that occur prior to issuance of the proposed final estimate shall follow applicable requirements of this section. Information listed in the supplemental notice and full and final documentation of potential claim that is not applicable to the administrative dispute may be exempted as determined by the Engineer.

Unless otherwise specified in the special provisions, the Contractor may pursue the administrative claim process pursuant to Section 9-1.07B, "Final Payment and Claims," for any potential claim found by the Engineer to be without merit.

Failure of the Contractor to conform to specified dispute procedures shall constitute a failure to pursue diligently and exhaust the administrative procedures in the contract, and is deemed as the Contractor's waiver of the potential claim and a waiver of the right to a corresponding claim for the disputed work in the administrative claim process in conformance with Section 9-1.07B, "Final Payment of Claims," and shall operate as a bar to arbitration pursuant to Section 10240.2 of the California Public Contract Code.

**Replace Section 9-1.05 with:**

**9-1.05 STOP NOTICE WITHHOLDS**

The Department may withhold payments to cover claims filed under Civ Code § 3179 et seq.

**Add:**

**9-1.053 PERFORMANCE FAILURE WITHHOLDS**

During each estimate period you fail to comply with a contract part, including submittal of a document as specified, the Department withholds a part of the progress payment. The documents include quality control plans, schedules, traffic control plans, and water pollution control submittals.

For 1 performance failure, the Department withholds 25 percent of the progress payment but does not withhold more than 10 percent of the total bid.

For multiple performance failures, the Department withholds 100 percent of the progress payment but does not withhold more than 10 percent of the total bid.

The Department returns performance-failure withholds in the progress payment following the correction of noncompliance.

**Add:**

**9-1.055 PENALTY WITHHOLDS**

Penalties include fines and damages that are proposed, assessed, or levied against you or the Department by a governmental agency or citizen lawsuit. Penalties are also payments made or costs incurred in settling alleged permit violations of Federal, State, or local laws, regulations, or requirements. The cost incurred may include the amount spent for mitigation or correcting a violation.

If you or the Department is assessed a penalty, the Department may withhold the penalty amount until the penalty disposition has been resolved. The Department may withhold penalty funds and notify you within 15 days of the withhold. If the penalty amount is less than the amount being withheld from progress payments for retentions, the Department will not withhold the penalty amount.

If the penalty is resolved for less than the amount withheld, the Department pays interest at a rate of 6 percent per year on the excess withhold. If the penalty is not resolved, the withhold becomes a deduction.

Instead of the withhold, you may provide a bond payable to the Department of Transportation equal to the highest estimated liability for any disputed penalties proposed.

**Add:**

**9-1.057 PROGRESS WITHHOLDS**

The Department withholds 10 percent of a partial payment for noncompliant progress. Noncompliant progress occurs when:

1. Total days to date exceed 75 percent of the revised contract working days
2. Percent of working days elapsed exceeds the percent of value of work completed by more than 15 percent

The Engineer determines the percent of working days elapsed by dividing the total days to date by the revised contract working days and converting the quotient to a percentage.

The Engineer determines the percent of value of work completed by summing payments made to date and the amount due on the current progress estimate, dividing this sum by the current total estimated value of the work, and converting the quotient to a percentage. These amounts are shown on the Progress Payment Voucher.

When the percent of working days elapsed minus the percent of value of work completed is less than or equal to 15 percent, the Department returns the withhold in the next progress payment.

**In Section 9-1.06 in the 4th paragraph, replace the 1st sentence with:**

The Department shall pay monthly to the Contractor, while carrying on the work, the balance not retained, as aforesaid, after deducting therefrom all previous payments and all sums to be deducted or withheld under the provisions of the contract.

**In Section 9-1.065 replace the title and the 1st and 2nd paragraphs with:**

**9-1.065 RELEASE OF RETAINED FUNDS**

The Department releases retained funds if you:

1. Request release of the retention (Pub Cont Code § 10263) in writing
2. Deposit securities equivalent to the funds you want released into escrow with the State Treasurer or with a bank acceptable to the Department
3. Are the beneficial owner of and receive interest on the deposited securities substituted for the retained funds

**In Section 9-1.07A replace the 2nd sentence with:**

The Department pays the balance due less previous payments, deductions, withholds, and retentions under the provisions of the contract and those further amounts that the Engineer determines to be necessary pending issuance of the proposed final estimate and payment thereon.

**Replace Section 9-1.07B with:**

**9-1.07B Final Payment and Claims**

After acceptance by the Director, the Engineer makes a proposed final estimate of the total amount payable to the Contractor, including an itemization of the total amount, segregated by contract item quantities, extra work, and other basis for payment, and shows each deduction made or to be made for prior payments and amounts to be deducted, withheld, or retained under the provisions of the contract. Prior estimates and payments are subject to correction in the proposed final estimate. The Contractor must submit written approval of the proposed final estimate or a written statement of claims arising under or by virtue of the contract so that the Engineer receives the written approval or statement of claims no later than close of business of the 30th day after receiving the proposed final estimate. The Contractor's receipt of the proposed final estimate must be evidenced by postal receipt. The Engineer's receipt of the Contractor's written approval or statement of claims must be evidenced by postal receipt or the Engineer's written receipt if delivered by hand.

On the Contractor's approval, or if the Contractor files no claim within the specified period of 30 days, the Engineer will issue a final estimate in writing in conformance with the proposed final estimate submitted to the Contractor, and within 30 days thereafter the State will pay the entire sum so found to be due. That final estimate and payment thereon shall be conclusive and binding against both parties to the contract on all questions relating to the amount of work done and the compensation payable therefor, except as otherwise provided in Sections 9-1.03C, "Records," and 9-1.09, "Clerical Errors."

If the Contractor within the specified period of 30 days files claims, the Engineer will issue a semifinal estimate in conformance with the proposed final estimate submitted to the Contractor and within 30 days thereafter the State will pay the sum found to be due. The semifinal estimate and corresponding payment shall be conclusive and binding against both parties to the contract on each question relating to the amount of work done and the compensation payable therefor, except insofar as affected by the claims filed within the time and in the manner required hereunder and except as otherwise provided in Sections 9-1.03C, "Records," and 9-1.09, "Clerical Errors."

Except for claims for overhead costs and administrative disputes that occur after issuance of the proposed final estimate, the Contractor shall only provide the following two items of information for each claim:

1. The exclusive identification number that corresponds to the supporting full and final documentation of potential claim
2. The final amount of requested additional compensation

If the final amount of requested additional compensation is different than the amount of requested compensation included in the full and final documentation of potential claim, the Contractor shall provide in the written statement of claims the reasons for the changed amount, the specific provisions of the contract which support the changed amount, and a statement of the reasons the provisions support and provide a basis for the changed amount. If the Contractor's claim fails to provide an exclusive identification number or if there is a disparity in the provided exclusive identification number, the Engineer will notify the Contractor of the omission or disparity. The Contractor shall have 15 days after receiving notification from the Engineer to correct the omission or disparity. If after the 15 days has elapsed, there is still an omission or disparity of the exclusive identification number assigned to the claim, the Engineer will assign the number. No claim will be considered that has any of the following deficiencies:

1. The claim does not have the same nature, circumstances, and basis as the corresponding full and final documentation of potential claim.
2. The claim does not have a corresponding full and final documentation of potential claim.

3. The claim was not included in the written statement of claims.
4. The Contractor did not comply with applicable notice or protest requirements of Sections 4-1.03, "Changes," 5-1.116, "Differing Site Condition," 8-1.06, "Time of Completion," 8-1.07, "Liquidated Damages," 8-1.10, "Utility and Non-Highway Facilities," and 9-1.04, "Notice of Potential Claim."

Administrative disputes that occur after issuance of the proposed final estimate shall be included in the Contractor's written statement of claims in sufficient detail to enable the Engineer to ascertain the basis and amounts of those claims.

The Contractor shall keep full and complete records of the costs and additional time incurred for work for which a claim for additional compensation is made. The Engineer or designated claim investigators or auditors shall have access to those records and any other records as may be required by the Engineer to determine the facts or contentions involved in the claims. Failure to permit access to those records shall be sufficient cause for denying the claims.

The written statement of claims submitted by the Contractor shall be accompanied by a notarized certificate containing the following language:

Under the penalty of law for perjury or falsification and with specific reference to the California False Claims Act, Government Code Section 12650 et. seq., the undersigned,

\_\_\_\_\_  
*(name)* \_\_\_\_\_ of  
 \_\_\_\_\_  
*(title)* \_\_\_\_\_  
 \_\_\_\_\_  
*(company)*

hereby certifies that the claim for the additional compensation and time, if any, made herein for the work on this contract is a true statement of the actual costs incurred and time sought, and is fully documented and supported under the contract between parties.

Dated \_\_\_\_\_

/s/ \_\_\_\_\_

Subscribed and sworn before me this \_\_\_\_\_ day

of \_\_\_\_\_

\_\_\_\_\_  
*(Notary Public)*

My Commission

Expires \_\_\_\_\_

Failure to submit the notarized certificate will be sufficient cause for denying the claim.

Any claim for overhead, in addition to being certified as stated above, shall be supported and accompanied by an audit report of an independent Certified Public Accountant. Omission of a supporting audit report of an independent Certified Public Accountant shall result in denial of the claim and shall operate as a bar to arbitration, as to the claim, in conformance with the requirements in Section 10240.2 of the California Public Contract Code. Any claim for overhead shall be subject to audit by the State at its discretion. The costs of performing an audit examination and submitting the report shall be borne by the Contractor. The Department will deduct an offset amount for field and home office overhead paid on all added work from any claim for overhead as appropriate, as determined by the Department. The value of the added work equals the value of the work completed minus the total bid. The home office overhead offset equals 5 percent of the added work. The field office overhead offset equals 5-1/2 percent of the added work. The Certified Public Accountant's audit examination shall be performed in conformance with the requirements of the American Institute of Certified Public Accountants Attestation Standards. The audit examination and report shall depict the Contractor's project and company-wide financial records and shall specify the actual overall average daily rates for both field and home office overhead for the entire duration of the project, and whether the costs have been properly allocated. The rates of field and home office overhead shall exclude unallowable costs as determined in Title 48 of the Federal Acquisition Regulations, Chapter 1, Part 31. The audit examination and report shall determine if the rates of field and home office overhead are:

1. Allowable in conformance with the requirements in Title 48 of the Federal Acquisition Regulations, Chapter 1, Part 31.







**Physical/Chemical Requirements**

Property	Test Method	Requirement
pH	*TMECC 04.11-A, Elastometric pH 1:5 Slurry Method, pH Units	6.0–8.0
Soluble Salts	TMECC 04.10-A, Electrical Conductivity 1:5 Slurry Method dS/m (mmhos/cm)	0-10.0
Moisture Content	TMECC 03.09-A, Total Solids & Moisture at 70+/- 5 deg C, % Wet Weight Basis	30–60
Organic Matter Content	TMECC 05.07-A, Loss-On-Ignition Organic Matter Method (LOI), % Dry Weight Basis	30–65
Maturity	TMECC 05.05-A, Germination and Vigor Seed Emergence Seedling Vigor % Relative to Positive Control	80 or Above 80 or Above
Stability	TMECC 05.08-B, Carbon Dioxide Evolution Rate mg CO <sub>2</sub> -C/g OM per day	8 or below
Particle Size	TMECC 02.02-B Sample Sieving for Aggregate Size Classification % Dry Weight Basis	95% Passing 5/8 inch 70% Passing 3/8 inch
Pathogen	TMECC 07.01-B, Fecal Coliform Bacteria < 1000 MPN/gram dry wt.	Pass
Pathogen	TMECC 07.01-B, Salmonella < 3 MPN/4 grams dry wt.	Pass
Physical Contaminants	TMECC 02.02-C, Man Made Inert Removal and Classification: Plastic, Glass and Metal, % > 4mm fraction	Combined Total: < 1.0
Physical Contaminants	TMECC 02.02-C, Man Made Inert Removal and Classification: Sharps (Sewing needles, straight pins and hypodermic needles), % > 4mm fraction	None Detected

\*TMECC refers to "Test Methods for the Examination of Composting and Compost," published by the United States Department of Agriculture and the United States Compost Council (USCC).

Prior to application, the Contractor shall provide the Engineer with a copy of the soil amendment producer's Compost Technical Data Sheet and a copy of the compost producers STA certification. The Compost Technical Data Sheet shall include laboratory analytical test results, directions for product use, and a list of product ingredients.

Prior to application, the Contractor shall provide the Engineer with a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

**In Section 20-2.10 delete the 8th, 9th, and 10th paragraphs.**

**Replace Section 20-2.25 with:**

**20-2.25 BACKFLOW PREVENTERS**

Backflow preventers shall be one of the reduced pressure principle devices as specified in these specifications and the special provisions.

Backflow preventers shall be factory assembled and shall include 2 check valves, one pressure differential relief valve, 2 shut-off valves and 4 test cocks. Backflow preventer and valves shall be the same size as the pipeline in which they are installed, unless otherwise shown on the plans.

Backflow preventer shut-off valves shall be manufactured from iron or bronze and shall be either resilient wedged gate valves, resilient seated and fully ported ball valves, or resilient seated butterfly valves. Threaded type shut-off valves shall be provided with a union on one side of each valve. Unions shall be brass or malleable iron.

**In Section 20-3.04A delete the last paragraph.**







## **SECTION 29 TREATED PERMEABLE BASES**

**(Issued 07-31-07)**

### **In Section 29-1.02A replace the 4th paragraph with:**

The type and grade of asphalt binder to be mixed with aggregate will be specified in the special provisions.

### **In Section 29-1.02B replace the 2nd paragraph with:**

Cement shall be Type II portland cement conforming to the provisions in Section 90-2.01A, "Cement."

### **In Section 29-1.04A replace the 1st paragraph with:**

Aggregates and asphalt for asphalt treated permeable base shall be stored, proportioned and mixed in the same manner provided for storing, proportioning and mixing aggregates and asphalt for hot mix asphalt in Section 39-1.08, "Production," except as follows:

1. The aggregate need not be separated into sizes.
2. The temperature of the aggregate before adding the asphalt binder shall be not less than 135°C nor more than 165°C.
3. Asphalt treated permeable base stored in excess of 2 hours shall not be used in the work.
4. The aggregate shall be combined with 2.5 percent paving asphalt by mass of the dry aggregate. After testing samples of the Contractor's proposed aggregate supply, the Engineer may order an increase or decrease in the asphalt content. If an increase or decrease is ordered, and the increase or decrease exceeds the specified amount by more than 0.1-percent by mass of the dry aggregate, the compensation payable to the Contractor for the asphalt treated permeable base will be increased or decreased on the basis of the total increase or decrease in asphalt.
5. The asphalt content of the asphalt mixture will be determined, at the option of the Engineer, by extraction tests in conformance with the requirements in California Test 310 or 362, or will be determined in conformance with the requirements in California Test 379. The bitumen ratio kilograms of asphalt per 100 kg of dry aggregate shall not vary by more than 0.5-kg of asphalt above or 0.5-kg of asphalt below the amount designated by the Engineer. Compliance with this requirement will be determined either by taking samples from trucks at the plant or from the mat behind the paver before rolling. If the sample is taken from the mat behind the paver, the bitumen ratio shall be not less than the amount designated by the Engineer, less 0.7-kg of asphalt per 100 kg of dry aggregate.

### **In Section 29-1.04B replace the 2nd paragraph with:**

Cement treated permeable base shall contain not less than 170 kg of cement per cubic meter.

### **In Section 29-1.05 replace the 1st paragraph with:**

Asphalt treated permeable base shall be spread and compacted as specified for hot mix asphalt under the "Method" construction process in Section 39, "Hot Mix Asphalt," and these specifications.

### **In Section 29-1.07 replace the 2nd paragraph with:**

Hardened treated permeable base with a surface lower than 15 mm below the grade established by the Engineer shall be removed and replaced with treated permeable base which complies with these specifications, or if permitted by the Engineer, the low areas shall be filled with pavement material as follows:

1. When pavement material is hot mix asphalt, the low areas shall be filled with hot mix asphalt conforming to the requirements for the lowest layer of hot mix asphalt to be placed as pavement. This shall be done as a separate operation prior to placing the lowest layer of pavement.
2. When pavement material is portland cement concrete, the low areas shall be filled with pavement concrete at the time and in the same operation in which the pavement is placed.
3. Full compensation for filling low areas will be considered as included in the contract price paid per cubic meter for treated permeable base and no additional compensation will be allowed therefor.



3. Open graded friction course (OGFC). OGFC includes hot mix asphalt (open graded), rubberized hot mix asphalt (open graded) (RHMA-O) and rubberized hot mix asphalt (open graded high binder) (RHMA-O-HB)
4. Rubberized hot mix asphalt (gap graded) (RHMA-G)

The special provisions specify the HMA construction process, including:

1. Standard
2. Method
3. Quality Control / Quality Assurance (QC / QA)

### **39-1.02 MATERIALS**

#### **39-1.02A Geosynthetic Pavement Interlayer**

Geosynthetic pavement interlayer must comply with the specifications for pavement reinforcing fabric in Section 88, "Engineering Fabrics."

#### **39-1.02B Tack Coat**

Tack coat must comply with the specifications for asphaltic emulsion in Section 94, "Asphaltic Emulsion," or asphalt binder in Section 92, "Asphalts." Choose the type and grade.

Notify the Engineer if you dilute asphaltic emulsion with water. The mass ratio of added water to asphaltic emulsion must not exceed 1 to 1.

Measure added water either by mass or volume in compliance with the specifications for weighing, measuring, and metering devices under Section 9-1.01, "Measurement of Quantities," or you may use water meters from water districts, cities, or counties. If you measure water by volume, apply a conversion factor to determine the correct mass.

With each dilution, submit in writing:

1. The mass ratio of water to bituminous material in the original asphaltic emulsion
2. The mass of asphaltic emulsion before diluting
3. The mass of added water
4. The final dilution mass ratio of water to asphaltic emulsion

#### **39-1.02C Asphalt Binder**

Asphalt binder in HMA must comply with Section 92, "Asphalts," or Section 39-1.02D, "Asphalt Rubber Binder." The special provisions specify the grade.

Asphalt binder for geosynthetic pavement interlayer must comply with Section 92, "Asphalts." Choose from Grades PG 64-10, PG 64-16, or PG 70-10.

#### **39-1.02D Asphalt Rubber Binder**

##### **General**

Use asphalt rubber binder in RHMA-G, RHMA-O, and RHMA-O-HB. Asphalt rubber binder must be a combination of:

1. Asphalt binder
2. Asphalt modifier
3. Crumb rubber modifier (CRM)

The combined asphalt binder and asphalt modifier must be  $80.0 \pm 2.0$  percent by mass of the asphalt rubber binder.

##### **Asphalt Modifier**

Asphalt modifier must be a resinous, high flash point, and aromatic hydrocarbon, and comply with:

**Asphalt Modifier for Asphalt Rubber Binder**

Quality Characteristic	ASTM	Specification
Viscosity, m <sup>2</sup> /s (x 10 <sup>-6</sup> ) at 100 °C	D 445	X ± 3 <sup>a</sup>
Flash Point, CL.O.C., °C	D 92	207 minimum
Molecular Analysis		
Asphaltenes, percent by mass	D 2007	0.1 maximum
Aromatics, percent by mass	D 2007	55 minimum

Note:

<sup>a</sup> The symbol "X" is the proposed asphalt modifier viscosity. "X" must be between 19 and 36. A change in "X" requires a new asphalt rubber binder design.

Asphalt modifier must be from 2.0 percent to 6.0 percent by mass of the asphalt binder in the asphalt rubber binder.

**Crumb Rubber Modifier**

CRM consists of a ground or granulated combination of scrap tire CRM and high natural CRM. CRM must be 75.0 ± 2.0 percent scrap tire CRM and 25.0 ± 2.0 percent high natural CRM by total mass of CRM. Scrap tire CRM must be from any combination of automobile tires, truck tires, or tire buffings.

Sample and test scrap tire CRM and high natural CRM separately. CRM must comply with:

**Crumb Rubber Modifier for Asphalt Rubber Binder**

Quality Characteristic	Test Method	Specification
Scrap tire CRM gradation (% passing 2.36-mm sieve)	LP-10	100
High natural CRM gradation (% passing 2.00-mm sieve)	LP-10	100
Wire in CRM (% max.)	LP-10	0.01
Fabric in CRM (% max.)	LP-10	0.05
CRM particle length (mm max.) <sup>a</sup>	--	4.75
CRM specific gravity <sup>a</sup>	CT 208	1.1 – 1.2
Natural rubber content in high natural CRM (%) <sup>a</sup>	ASTM D 297	40.0 – 48.0

Note:

<sup>a</sup> Test at mix design and for Certificate of Compliance.

Only use CRM ground and granulated at ambient temperature. If steel and fiber are cryogenically separated, it must occur before grinding and granulating. Only use cryogenically produced CRM particles that can be ground or granulated and not pass through the grinder or granulator.

CRM must be dry, free-flowing particles that do not stick together. CRM must not cause foaming when combined with the asphalt binder and asphalt modifier. You may add calcium carbonate or talc up to 3 percent by mass of CRM.

**Asphalt Rubber Binder Design and Profile**

Submit in writing an asphalt rubber binder design and profile that complies with the asphalt rubber binder specifications. In the design, designate the asphalt, asphalt modifier, and CRM and their proportions. The profile must include the same component sources for the asphalt rubber binder used.

Design the asphalt rubber binder from testing you perform for each quality characteristic and for the reaction temperatures expected during production. The 24-hour (1,440-minute) interaction period determines the design profile. At a minimum, mix asphalt rubber binder components, take samples, and perform and record the following tests:

**Asphalt Rubber Binder Reaction Design Profile**

Test	Minutes of Reaction <sup>a</sup>							Limits
	45	60	90	120	240	360	1440	

Cone penetration @ 77 °F, 0.10 mm (ASTM D 217)	X <sup>b</sup>				X		X	25 - 70
Resilience @ 77 °F, percent rebound (ASTM D 5329)	X				X		X	18 min.
Field softening point, °F (ASTM D 36)	X				X		X	125 - 165
Viscosity, centipoises (LP-11)	X	X	X	X	X	X	X	1,500 - 4,000

Notes:

<sup>a</sup> Six hours (360 minutes) after CRM addition, reduce the oven temperature to 135 °C for a period of 16 hours. After the 16-hour (1320 minutes) cool-down after CRM addition, reheat the binder to the reaction temperature expected during production for sampling and testing at 24 hours (1440 minutes).

<sup>b</sup> "X" denotes required testing

### Asphalt Rubber Binder

After interacting for a minimum of 45 minutes, asphalt rubber binder must comply with:

#### Asphalt Rubber Binder

Quality Characteristic	Test for Quality Control or Acceptance	Test Method	Specification	
			Minimum	Maximum
Cone penetration @ 77 °F, 0.10 mm	Acceptance	ASTM D 217	25	70
Resilience @ 77 °F, percent rebound	Acceptance	ASTM D 5329	18	--
Field softening point, °F	Acceptance	ASTM D 36	125	165
Viscosity @ 177 °C, centipoises	Quality Control	LP-11	1,500	4,000

### 39-1.02E Aggregate

Aggregate must be clean and free from deleterious substances. Aggregate:

1. Retained on the 4.75-millimeter sieve is coarse
2. Passing the 4.75-millimeter sieve is fine
3. Added and passing the 0.6-millimeter sieve is supplemental fine, including:
  - 3.1. Hydrated lime
  - 3.2. Portland cement
  - 3.3. Fines from dust collectors

The special provisions specify the aggregate gradation for each HMA type.

The specified aggregate gradation is before the addition of asphalt binder and includes supplemental fines. The Engineer tests for aggregate grading under California Test 202, modified by California Test 105 if there is a difference in specific gravity of 0.2 or more between the coarse and fine parts of different aggregate blends.

Choose a sieve size target value (TV) within each target value limit presented in the aggregate gradation tables.

**Aggregate Gradation  
(Percentage Passing)  
HMA Types A and B**

19-mm HMA Types A and B

Sieve Sizes	Target Value Limits	Allowable Tolerance
25-mm	100	—
19-mm	90 - 100	TV ±5
12.5-mm	70 - 90	TV ±6
4.75-mm	45 - 55	TV ±7
2.36-mm	32 - 40	TV ±5
0.6-mm	12 - 21	TV ±4
0.075-mm	2 - 7	TV ±2

12.5-mm HMA Types A and B

Sieve Sizes	Target Value Limits	Allowable Tolerance
19-mm	100	—
12.5-mm	95 - 99	TV ±6
9.5-mm	75 - 95	TV ±6
4.75-mm	55 - 66	TV ±7
2.36-mm	38 - 49	TV ±5
0.6-mm	15 - 27	TV ±4
0.075-mm	2 - 8	TV ±2

9.5-mm HMA Types A and B

Sieve Sizes	Target Value Limits	Allowable Tolerance
12.5-mm	100	—
9.5-mm	95 - 100	TV ±6
4.75-mm	58 - 72	TV ±7
2.36-mm	34 - 48	TV ±6
0.6-mm	18 - 32	TV ±5
0.075-mm	2 - 9	TV ±2

4.75-mm HMA Types A and B

Sieve Sizes	Target Value Limits	Allowable Tolerance
9.5-mm	100	—
4.75-mm	95 - 100	TV ±7
2.36-mm	72 - 77	TV ±7
0.6-mm	37 - 43	TV ±7
0.075-mm	2 - 12	TV ±4

**Rubberized Hot Mix Asphalt - Gap Graded (RHMA-G)**

19-mm RHMA-G

Sieve Sizes	Target Value Limits	Allowable Tolerance
25-mm	100	—
19-mm	95 - 100	TV ±5
12.5-mm	83 - 87	TV ±6
9.5-mm	65 - 70	TV ±6
4.75-mm	28 - 42	TV ±7
2.36-mm	14 - 22	TV ±5
0.075-mm	0 - 6	TV ±2

12.5-mm RHMA-G

Sieve Sizes	Target Value Limits	Allowable Tolerance
19-mm	100	—
12.5-mm	90 - 100	TV ±6
9.5-mm	83 - 87	TV ±6
4.75-mm	28 - 42	TV ±7
2.36-mm	14 - 22	TV ±5
0.075-mm	0 - 6	TV ±2

**Open Graded Friction Course (OGFC)**

25-mm OGFC

Sieve Sizes	Target Value Limits	Allowable Tolerance
37.5-mm	100	—
25-mm	99 - 100	TV ±5
19-mm	85 - 96	TV ±5
12.5-mm	55 - 71	TV ±6
4.75-mm	10 - 25	TV ±7
2.36-mm	6 - 16	TV ±5
0.075-mm	1 - 6	TV ±2

12.5-mm OGFC

Sieve Sizes	Target Value Limits	Allowable Tolerance
19-mm	100	—
12.5-mm	95 - 100	TV ±6
9.5-mm	78 - 89	TV ±6
4.75-mm	28 - 37	TV ±7
2.36-mm	7 - 18	TV ±5
0.6-mm	0 - 10	TV ±4
0.075-mm	0 - 3	TV ±2

9.5-mm OGFC

Sieve Sizes	Target Value Limits	Allowable Tolerance
12.5-mm	100	—
9.5-mm	90 - 100	TV ±6
4.75-mm	29 - 36	TV ±7
2.36-mm	7 - 18	TV ±6
0.6-mm	0 - 10	TV ±5
0.075-mm	0 - 3	TV ±2

Before the addition of asphalt binder and lime treatment, aggregate must comply with:

### Aggregate Quality

Quality Characteristic	Test Method	HMA Type			
		A	B	RHMA-G	OGFC
Percent of crushed particles Coarse aggregate (% min.) One fractured face	CT 205	90	25	--	90
Two fractured faces		75	--	90	75
Fine aggregate (% min.) (Passing 4.75-mm sieve and retained on 2.36-mm sieve.) One fractured face		70	20	70	90
Los Angeles Rattler (% max.) Loss at 100 Rev.	CT 211	12	--	12	12
Loss at 500 Rev.		45	50	40	40
Sand equivalent (min.) <sup>a</sup>	CT 217	47	42	47	--
Fine aggregate angularity (% min.) <sup>b</sup>	AASHTO T 304 Method A	45	45	45	--
Flat and elongated particles (% max. by mass @ 5:1)	ASTM D 4791	10	10	10	10

Notes:

<sup>a</sup> Reported value must be the average of 3 tests from a single sample.

<sup>b</sup> The Engineer waives this specification if HMA contains less than 10 percent of nonmanufactured sand by mass of total aggregate. Manufactured sand is fine aggregate produced by crushing rock or gravel.

#### 39-1.02F Reclaimed Asphalt Pavement

You may produce HMA using reclaimed asphalt pavement (RAP). HMA produced using RAP must comply with the specifications for HMA except aggregate quality specifications do not apply to RAP. You may substitute RAP aggregate for a part of the virgin aggregate in HMA in a quantity not exceeding 15.0 percent of the aggregate blend. Do not use RAP in OGFC and RHMA-G.

Assign the substitution rate of RAP aggregate for virgin aggregate with the job mix formula (JMF) submittal. The JMF must include the percent of RAP used. If you change your assigned RAP aggregate substitution rate by more than 5 percent (within the 15.0 percent limit), submit a new JMF.

Process RAP from asphalt concrete. You may process and stockpile RAP throughout the project's life. Prevent material contamination and segregation. Store RAP in stockpiles on smooth surfaces free of debris and organic material. Processed RAP stockpiles must consist only of homogeneous RAP.

#### 39-1.03 HOT MIX ASPHALT MIX DESIGN REQUIREMENTS

##### 39-1.03A General

A mix design consists of performing California Test 367 and laboratory procedures on combinations of aggregate gradations and asphalt binder contents to determine the optimum binder content (OBC) and HMA mixture qualities. If RAP is used, use Laboratory Procedure LP-9. The result of the mix design becomes the proposed JMF.

Use Form CEM-3512 to document aggregate quality and mix design data. Use Form CEM-3511 to present the JMF.

Laboratories testing aggregate qualities and preparing the mix design and JMF must be qualified under the Department's Independent Assurance Program. Take samples under California Test 125.

The Engineer reviews the aggregate qualities, mix design, and JMF and verifies and accepts the JMF.

You may change the JMF during production. Do not use the changed JMF until the Engineer accepts it. Except when adjusting the JMF in compliance with Section 39-1.03E, "Job Mix Formula Verification," perform a new mix design and submit in writing a new JMF submittal for changing any of the following:

1. Target asphalt binder percentage
2. Asphalt binder supplier
3. Asphalt rubber binder supplier
4. Component materials used in asphalt rubber binder or percentage of any component materials
5. Combined aggregate gradation
6. Aggregate sources
7. Substitution rate for RAP aggregate of more than 5 percent
8. Any material in the JMF

For OGFC, submit in writing a complete JMF submittal except asphalt binder content. The Engineer determines the asphalt binder content under California Test 368 within 20 days of your complete JMF submittal and provides you a Form CEM-3513.

**39-1.03B Hot Mix Asphalt Mix Design**

Perform a mix design that produces HMA in compliance with:

**Hot Mix Asphalt Mix Design Requirements**

Quality Characteristic	Test Method	HMA Type		
		A	B	RHMA-G
Air voids content (%)	CT 367 <sup>a</sup>	4.0	4.0	Special Provisions
Voids in mineral aggregate (% min.)	LP-2			
4.75-mm grading		17.0	17.0	--
9.5-mm grading		15.0	15.0	--
12.5-mm grading		14.0	14.0	18.0 – 23.0 <sup>b</sup>
19-mm grading		13.0	13.0	18.0 – 23.0 <sup>b</sup>
Voids filled with asphalt (%)	LP-3			
4.75-mm grading		76.0 – 80.0	76.0 – 80.0	Note d
9.5-mm grading		73.0 – 76.0	73.0 – 76.0	
12.5-mm grading		65.0 – 75.0	65.0 – 75.0	
19-mm grading	65.0 – 75.0	65.0 – 75.0		
Dust proportion	LP-4			
4.75-mm and 9.5-mm gradings		0.9 – 2.0	0.9 – 2.0	Note d
12.5-mm and 19-mm gradings		0.6 – 1.3	0.6 – 1.3	
Stabilometer value (min.) <sup>c</sup>	CT 366			
4.75-mm and 9.5-mm gradings		30	30	--
12.5-mm and 19-mm gradings		37	35	23

Notes:

<sup>a</sup> Calculate the air voids content of each specimen using California Test 309 and Lab Procedure LP-1. Modify California Test 367, Paragraph C5, to use the exact air voids content specified in the selection of OBC.

<sup>b</sup> Voids in mineral aggregate for RHMA-G must be within this range.

<sup>c</sup> Modify California Test 304, Part 2.B.2.c: "After compaction in the compactor, cool to 60 ± 3 °C by allowing the briquettes to cool at room temperature for 0.5-hour, then place the briquettes in the oven at 60 °C for a minimum of 2 hours and not more than 3 hours."

<sup>d</sup> Report this value in the JMF submittal.

For stability and air voids, prepare 3 briquettes at the OBC and test for compliance. Report the average of 3 tests. Prepare new briquettes and test if the range of stability for the 3 briquettes is more than 8 points. The average air void content may vary from the specified air void content by ±0.5 percent.

You may use the briquettes used for stability testing to determine bulk specific gravity under CT 308. If you use the same briquettes and tests using bulk specific gravity fail, you may prepare 3 new briquettes and determine a new bulk specific gravity.

**39-1.03C Job Mix Formula Submittal**

Each JMF submittal must consist of:

1. Proposed JMF on Form CEM-3511
2. Mix design documentation on Form CEM-3512 dated within 12 months of submittal
3. JMF verification on Form CEM-3513, if applicable
4. JMF renewal on Form CEM-3514, if applicable
5. Materials Safety Data Sheets (MSDS) for:
  - 5.1. Asphalt binder
  - 5.2. Base asphalt binder used in asphalt rubber binder
  - 5.3. CRM and asphalt modifier used in asphalt rubber binder
  - 5.4. Blended asphalt rubber binder mixture

- 5.5. Supplemental fine aggregate except fines from dust collectors
- 5.6. Antistrip additives

If the Engineer requests in writing, sample the following materials in the presence of the Engineer and place in labeled containers weighing no more than 22.5 kg each:

1. Coarse, fine, and supplemental fine aggregate from stockpiles, cold feed belts, or hot bins. Samples must include at least 55 kg for each coarse aggregate, 35 kg for each fine aggregate, and 4.5 kg for each type of supplemental fines. The Department combines these aggregate samples to comply with the JMF target values submitted on Form CEM-3511.
2. RAP from stockpiles or RAP system. Samples must be at least 30 kg.
3. Asphalt binder from the binder supplier. Samples must be in two 1-liter cylindrical shaped cans with open top and friction lids.
4. Asphalt rubber binder with the components blended in the proportions to be used. Samples must be in four 1-liter cylindrical shaped cans with open top and friction lids.

Notify the Engineer in writing at least 2 business days before sampling materials. For aggregate and RAP, split the samples into at least 4 parts. Submit 3 parts to the Engineer and use 1 part for your testing.

#### **39-1.03D Job Mix Formula Review**

The Engineer reviews each mix design and proposed JMF within 5 business days from the complete JMF submittal. The review consists of reviewing the mix design procedures and comparing the proposed JMF with the specifications.

The Engineer may verify aggregate qualities during this review period.

#### **39-1.03E Job Mix Formula Verification**

If you cannot submit a Department-verified JMF on Form CEM-3513 dated within 12 months before HMA production, the Engineer verifies the JMF.

Based on your testing and production experience, you may submit on Form CEM-3511 an adjusted JMF before the Engineer's verification testing. JMF adjustments may include a change in the:

1. Asphalt binder content target value up to  $\pm 0.6$  percent from the optimum binder content value submitted on Form CEM-3512 except do not adjust the target value for asphalt rubber binder for RHMA-G below 7.0 percent
2. Aggregate gradation target values within the target value limits specified in the aggregate gradation tables

For HMA Type A, Type B, and RHMA-G, the Engineer verifies the JMF from samples taken from HMA produced by the plant to be used. Notify the Engineer in writing at least 2 business days before sampling materials.

In the Engineer's presence and from the same production run, take samples of:

1. Aggregate
2. Asphalt binder
3. RAP
4. HMA

Sample aggregate from cold feed belts or hot bins. Sample RAP from the RAP system. Sample HMA under California Test 125 except if you request in writing and the Engineer approves, you may sample from any of the following locations:

1. The plant
2. A truck
3. A windrow
4. The paver hopper
5. The mat behind the paver

You may sample from a different project including a non-Department project if you make arrangements for the Engineer to be present during sampling.

For aggregate, RAP, and HMA, split the samples into at least 4 parts and label their containers. Submit 3 split parts to the Engineer and use 1 part for your testing.

The Engineer verifies each proposed JMF within 20 days of receiving verification samples. If you request in writing, the Engineer verifies RHMA-G quality requirements within 3 business days of sampling. Verification is testing for compliance with the specifications for:

1. Aggregate quality
2. Aggregate gradation (JMF TV  $\pm$  tolerance)
3. Asphalt binder content (JMF TV  $\pm$  tolerance)
4. HMA quality specified in the table Hot Mix Asphalt Mix Design Requirements except:
  - 4.1. Air voids content (design value  $\pm$  2.0 percent)
  - 4.2. Voids filled with asphalt (report only if an adjustment for asphalt binder content target value is less than or equal to  $\pm$  0.3 percent from OBC)
  - 4.3. Dust proportion (report only if an adjustment for asphalt binder content target value is less than or equal to  $\pm$  0.3 percent from OBC)

The Engineer prepares 3 briquettes from a single split sample. To verify the JMF for stability and air voids content, the Engineer tests the 3 briquettes and reports the average of 3 tests. The Engineer prepares new briquettes if the range of stability for the 3 briquettes is more than 8 points.

The Engineer may use the briquettes used for stability testing to determine bulk specific gravity under CT 308. If the Engineer uses the same briquettes and the tests using bulk specific gravity fail, the Engineer prepares 3 new briquettes and determines a new bulk specific gravity.

If the Engineer verifies the JMF, the Engineer provides you a Form CEM-3513.

If the Engineer's tests on plant-produced samples do not verify the JMF, the Engineer notifies you in writing and you must submit a new JMF submittal or submit an adjusted JMF based on your testing. JMF adjustments may include a change in the:

1. Asphalt binder content target value up to  $\pm$ 0.6 percent from the optimum binder content value submitted on Form CEM-3512 except do not adjust the target value for asphalt rubber binder for RHMA-G below 7.0 percent
2. Aggregate gradation target values within the target value limits specified in the aggregate gradation tables

You may adjust the JMF only once due to a failed verification test. An adjusted JMF requires a new Form CEM-3511 and verification of a plant-produced sample.

The Engineer reverifies the JMF if HMA production has stopped for longer than 30 days and the verified JMF is older than 12 months.

For each HMA type and aggregate size specified, the Engineer verifies at the State's expense up to 2 proposed JMF including a JMF adjusted after verification failure. The Engineer deducts \$3,000 from payments for each verification exceeding this limit. This deduction does not apply to verifications initiated by the Engineer or if a JMF expires while HMA production is stopped longer than 30 days.

### **39-1.03F Job Mix Formula Renewal**

You may request a JMF renewal by submitting the following:

1. Proposed JMF on Form CEM-3511
2. A previously verified JMF documented on Form CEM-3513 dated within 12 months
3. Mix design documentation on Form CEM-3512 used for the previously verified JMF

If the Engineer request in writing, sample the following materials obtained in the presence of the Engineer and place in labeled containers weighing no more than 22.5 kg each:

1. Coarse, fine, and supplemental fine aggregate from stockpiles, cold feed belts, or hot bins. Samples must include at least 55 kg for each coarse aggregate, 35 kg for each fine aggregate, and 4.5 kg for each type of supplemental fines. The Department combines these aggregate samples to comply with the JMF target values submitted on Form CEM-3511.
2. RAP from stockpiles or RAP system. Samples must be at least 30 kg.
3. Asphalt binder from the binder supplier. Samples must be in two 1-liter cylindrical shaped cans with open top and friction lids.
4. Asphalt rubber binder with the components blended in the proportions to be used. Samples must be in four 1-liter cylindrical shaped cans with open top and friction lids.

Notify the Engineer in writing at least 2 business days before sampling materials. For aggregate and RAP, split samples into at least 4 parts. Submit 3 parts to the Engineer and use 1 part for your testing.

The Engineer reviews each complete JMF renewal submittal within 5 business days.

The Engineer may verify aggregate qualities during this review period.

Notify the Engineer in writing at least 2 business days before sampling materials. For aggregate, RAP, and HMA, split the samples into at least 4 parts. Submit 3 parts to the Engineer and use 1 part for your testing.

The Engineer verifies the JMF renewal submittal under Section 39-1.03E, "Job Mix Formula Verification," except:

1. The Engineer retains samples until you provide test results for your part on Form CEM-3514.
2. The Engineer tests samples of materials obtained from the HMA production unit after you submit test results that comply with the specifications for the quality characteristics under Section 39-1.03E, "Job Mix Formula Verification."
3. The Engineer verifies each proposed JMF within 30 days of receiving verification samples.
4. You may not adjust the JMF due to a failed verification.
5. For each HMA type and aggregate gradation specified, the Engineer verifies at the State's expense 1 proposed JMF.

If the Engineer verifies the JMF renewal, the Engineer provides you a Form CEM-3513.

### **39-1.03G Job Mix Formula Acceptance**

You may start HMA production if:

1. The Engineer's review of the JMF shows compliance with the specifications.
2. The Department has verified the JMF within 12 months before HMA production.
3. The Engineer accepts the verified JMF.

## **39-1.04 CONTRACTOR QUALITY CONTROL**

### **39-1.04A General**

Establish, maintain, and change a quality control system to ensure materials and work comply with the specifications. Submit quality control test results to the Engineer within 3 days of a request except when QC / QA is specified.

You must identify the HMA sampling location in your Quality Control Plan. During production, take samples under California Test 125 except if you request in writing and the Engineer approves, you may sample HMA from:

1. The plant
2. The truck
3. A windrow
4. The paver hopper
5. The mat behind the paver

### **39-1.04B Prepaving Conference**

Meet with the Engineer at a prepaving conference at a mutually agreed time and place. Discuss methods of performing the production and paving work.

### **39-1.04C Asphalt Rubber Binder**

Take asphalt rubber binder samples from the feed line connecting the asphalt rubber binder tank to the HMA plant. Sample and test asphalt rubber binder under Laboratory Procedure LP-11.

Test asphalt rubber binder for compliance with the viscosity specifications in Section 39-1.02, "Materials." During asphalt rubber binder production and HMA production using asphalt rubber binder, measure viscosity every hour with not less than 1 reading for each asphalt rubber binder batch. Log measurements with corresponding time and asphalt rubber binder temperature. Submit the log daily in writing.

Submit a Certificate of Compliance under Section 6-1.07, "Certificates of Compliance." With the Certificate of Compliance, submit test results in writing for CRM and asphalt modifier with each truckload delivered to the HMA plant. A Certificate of Compliance for asphalt modifier must not represent more than 2250 kg. Use an AASHTO-certified laboratory for testing.

Sample and test gradation and wire and fabric content of CRM once per 4500 kg of scrap tire CRM and once per 1500 kg of high natural CRM. Sample and test scrap tire CRM and high natural CRM separately.

Submit certified weight slips in writing for the CRM and asphalt modifier furnished.

### **39-1.04D Aggregate**

Determine the aggregate moisture content and RAP moisture content in continuous mixing plants at least twice a day during production and adjust the plant controller. Determine the RAP moisture content in batch mixing plants at least twice a day during production and adjust the plant controller.

### **39-1.04E Reclaimed Asphalt Pavement**

Perform RAP quality control testing each day.

Sample RAP once daily and determine the RAP aggregate gradation under Laboratory Procedure LP-9 and submit the results to the Engineer in writing with the combined aggregate gradation.

### **39-1.04F Density Cores**

For Standard and QC / QA projects, take 100-millimeter or 150-millimeter diameter cores at least once every 5 business days. Take 1 core for every 250 tonnes of HMA from random locations the Engineer designates. Take cores in the Engineer's presence and backfill and compact holes with material authorized by the Engineer. Before submitting a core to the Engineer, mark it with the core's location and place it in a protective container.

If a core is damaged, replace it with a core taken within 0.3 m longitudinally from the original core. Relocate any core located within 0.3 m of a rumble strip to 0.3 m transversely away from the rumble strip.

### **39-1.04G Briquettes**

Prepare 3 briquettes for each stability and air voids determination. Report the average of 3 tests. Prepare new briquettes and test if the range of stability for the 3 briquettes is more than 12 points.

You may use the briquettes used for stability testing to determine bulk specific gravity under CT 308. If you use these briquettes and tests using bulk specific gravity fail, you may prepare 3 new briquettes and determine a new bulk specific gravity.

### **39-1.05 ENGINEER'S ACCEPTANCE**

The Engineer's acceptance of HMA is specified in the sections for each HMA construction process.

The Engineer samples materials for testing under California Test 125 and the applicable test method except samples may be taken from:

1. The plant from:
  - 1.1. A truck
  - 1.2. An automatic sampling device
2. The mat behind the paver

Sampling must be independent of Contractor quality control, statistically-based, and random.

If you request, the Engineer splits samples and provides you with a part.

The Engineer accepts HMA based on:

1. Accepted JMF
2. Accepted QCP for Standard and QC / QA
3. Compliance with the HMA Acceptance tables
4. Acceptance of a lot for QC / QA
5. Visual inspection

The Engineer prepares 3 briquettes for each stability and air voids determination. The Engineer reports the average of 3 tests. The Engineer prepares new briquettes and test if the range of stability for the 3 briquettes is more than 8 points.

The Engineer may use the briquettes used for stability testing to determine bulk specific gravity under CT 308. If the Engineer uses the same briquettes and the tests using bulk specific gravity fail, the Engineer prepares 3 new briquettes and determines a new bulk specific gravity.

### **39-1.06 DISPUTE RESOLUTION**

You and the Engineer must work together to avoid potential conflicts and to resolve disputes regarding test result discrepancies. Notify the Engineer in writing within 5 days of receiving a test result if you dispute the test result.

If you or the Engineer dispute each other's test results, submit written quality control test results and copies of paperwork including worksheets used to determine the disputed test results to the Engineer. An Independent Third Party (ITP) performs referee testing. Before the ITP participates in a dispute resolution, the ITP must be accredited under the Department's Independent Assurance Program. The ITP must be independent of the project. By mutual agreement, the ITP is chosen from:

1. A Department laboratory
2. A Department laboratory in a district or region not in the district or region the project is located
3. The Transportation Laboratory
4. A laboratory not currently employed by you or your HMA producer

If split quality control or acceptance samples are not available, the ITP uses any available material representing the disputed HMA for evaluation.

### **39-1.07 PRODUCTION START-UP EVALUATION**

The Engineer evaluates HMA production and placement at production start-up.

Within the first 750 tonnes produced on the first day of HMA production, in the Engineer's presence and from the same production run, take samples of:

1. Aggregate
2. Asphalt binder
3. RAP
4. HMA

Sample aggregate from cold feed belts or hot bins. Take RAP samples from the RAP system. Sample HMA under California Test 125 except if you request in writing and the Engineer approves, you may sample HMA from:

1. The plant
2. The truck
3. A windrow
4. The paver hopper
5. The mat behind the paver

For aggregate, RAP, and HMA, split the samples into at least 4 parts and label their containers. Submit 3 split parts to the Engineer and keep 1 part.

For Standard and QC / QA projects, you and the Engineer must test the split samples and report test results in writing within 3 business days of sampling. If you proceed before receipt of the test results, the Engineer may consider the HMA placed to be represented by these test results.

For Standard and QC / QA projects, take 100-millimeter or 150-millimeter diameter first 750 tonnes on the first day of HMA production. For each density core, the Engineer reports the bulk specific gravity determined under California Test 308, Method A in addition to the percent of maximum theoretical density. You may test for in-place density at the density core locations and include them in your production tests for percent of maximum theoretical density.

### **39-1.08 PRODUCTION**

#### **39-1.08A General**

Produce HMA in a batch mixing plant or a continuous mixing plant. Proportion aggregate by hot or cold feed control.

HMA plants must be Department-qualified. Before production, the HMA plant must have a current qualification under the Department's Materials Plant Quality Program.

During production, you may adjust:

1. Hot or cold feed proportion controls for virgin aggregate and RAP
2. The set point for asphalt binder content

#### **39-1.08B Mixing**

Mix HMA ingredients into a homogeneous mixture of coated aggregates.

Asphalt binder must be between 135 °C and 190 °C when mixed with aggregate.

Asphalt rubber binder must be between 177 °C and 218 °C when mixed with aggregate.

When mixed with asphalt binder, aggregate must not be more than 163 °C except aggregate for OGFC with unmodified asphalt binder must be not more than 135 °C. Aggregate temperature specifications do not apply when you use RAP.

HMA with or without RAP must not be more than 163 °C.

#### **39-1.08C Asphalt Rubber Binder**

Deliver scrap tire CRM and high natural CRM in separate bags.

Either proportion and mix asphalt binder, asphalt modifier, and CRM simultaneously or premix the asphalt binder and asphalt modifier before adding CRM. If you premix asphalt binder and asphalt modifier, mix them for at least 20 minutes. When you add CRM, the asphalt binder and asphalt modifier must be between 177 °C and 218 °C.

Do not use asphalt rubber binder during the first 45 minutes of the reaction period. During this period, the asphalt rubber binder mixture must be between 177 °C and the lower of 218 °C or 6 °C below the asphalt binder's flash point indicated in the MSDS.

If any asphalt rubber binder is not used within 4 hours after the reaction period, discontinue heating. If the asphalt rubber binder drops below 177 °C, reheat before use. If you add more scrap tire CRM to the reheated asphalt rubber binder, the binder must undergo a 45-minute reaction period. The added scrap tire CRM must not exceed 10 percent of the total asphalt rubber binder mass. Reheated and reacted asphalt rubber binder must comply with the viscosity specifications for asphalt rubber binder in Section 39-1.02, "Materials." Do not reheat asphalt rubber binder more than twice.

**39-1.09 SUBGRADE, TACK COAT, AND GEOSYNTHETIC PAVEMENT INTERLAYER**

**39-1.09A General**

Prepare subgrade or apply tack coat to surfaces receiving HMA. If specified, place geosynthetic pavement interlayer over a coat of asphalt binder.

**39-1.09B Subgrade**

Subgrade to receive HMA must comply with the compaction and elevation tolerance specifications in the sections for the material involved. Subgrade must be free of loose and extraneous material. If HMA is paved on existing base or pavement, remove loose paving particles, dirt, and other extraneous material by any means including flushing and sweeping.

**39-1.09C Tack Coat**

Apply tack coat:

1. To existing pavement including planed surfaces
2. Between HMA layers
3. To vertical surfaces of:
  - 3.1. Curbs
  - 3.2. Gutters
  - 3.3. Construction joints

Before placing HMA, apply tack coat in 1 application at the minimum residual rate specified for the condition of the underlying surface:

**Tack Coat Application Rates for HMA Type A, Type B, and RHMA-G**

HMA over:	Minimum Residual Rates (liters per square meter)		
	CSS1/CSS1h, SS1/SS1h and QS1h/CQS1h Asphaltic Emulsion	CRS1/CRS2, RS1/RS2 and QS1/CQS1 Asphaltic Emulsion	Asphalt Binder and PMRS2/PMCRS2 and PMRS2h/PMCRS2h Asphaltic Emulsion
New HMA (between layers)	0.09	0.14	0.09
Existing AC and PCC pavement	0.14	0.18	0.14
Planed pavement	0.23	0.27	0.18

**Tack Coat Application Rates for OGFC**

OGFC over:	Minimum Residual Rates (liters per square meter)		
	CSS1/CSS1h, SS1/SS1h and QS1h/CQS1h Asphaltic Emulsion	CRS1/CRS2, RS1/RS2 and QS1/CQS1 Asphaltic Emulsion	Asphalt Binder and PMRS2/PMCRS2 and PMRS2h/PMCRS2h Asphaltic Emulsion
New HMA	0.14	0.18	0.14
Existing AC and PCC pavement	0.23	0.27	0.18
Planed pavement	0.27	0.32	0.23

If you dilute asphaltic emulsion, mix until homogeneous before application.

Apply to vertical surfaces with a residual tack coat rate that will thoroughly coat the vertical face without running off.

If you request in writing and the Engineer authorizes, you may:

1. Change tack coat rates
2. Omit tack coat between layers of new HMA during the same work shift if:
  - 2.1. No dust, dirt, or extraneous material is present
  - 2.2. The surface is at least 60 °C

Immediately in advance of placing HMA, apply additional tack coat to damaged areas or where loose or extraneous material is removed.

Close areas receiving tack coat to traffic. Do not track tack coat onto pavement surfaces beyond the job site.

Asphalt binder tack coat must be between 140 °C and 175 °C when applied.

**39-1.09D Geosynthetic Pavement Interlayer**

Place geosynthetic pavement interlayer in compliance with the manufacturer's recommendations.

Before placing the geosynthetic pavement interlayer and asphalt binder:

1. Repair cracks 6.5 mm and wider, spalls, and holes in the pavement. The State pays for this repair work under Section 4-1.03D, "Extra Work."
2. Clean the pavement of loose and extraneous material.

Immediately before placing the interlayer, apply 1.13 L ± 0.14 L of asphalt binder per square meter of interlayer or until the fabric is saturated. Apply asphalt binder the width of the geosynthetic pavement interlayer plus 75 mm on each side. At interlayer overlaps, apply asphalt binder on the lower interlayer the same overlap distance as the upper interlayer.

Align and place the interlayer with no overlapping wrinkles, except a wrinkle that overlaps may remain if it is less than 12.5 mm thick. If the overlapping wrinkle is more than 12.5 mm thick, cut the wrinkle out and overlap the interlayer no more than 50 mm.

The minimum HMA thickness over the interlayer must be 35 mm thick including conform tapers. Do not place the interlayer on a wet or frozen surface.

Overlap the interlayer borders between 50 mm and 100 mm. In the direction of paving, overlap the following roll with the preceding roll at any break.

You may use rolling equipment to correct distortions or wrinkles in the interlayer.

If asphalt binder tracked onto the interlayer or brought to the surface by construction equipment causes interlayer displacement, cover it with a small quantity of HMA.

Before placing HMA on the interlayer, do not expose the interlayer to:

1. Traffic except for crossings under traffic control and only after you place a small HMA quantity
2. Sharp turns from construction equipment
3. Damaging elements

Pave HMA on the interlayer during the same work shift.

**39-1.10 SPREADING AND COMPACTING EQUIPMENT**

Paving equipment for spreading must be:

1. Self-propelled
2. Mechanical
3. Equipped with a screed or strike-off assembly that can distribute HMA the full width of a traffic lane
4. Equipped with a full-width compacting device
5. Equipped with automatic screed controls and sensing devices that control the thickness, longitudinal grade, and transverse screed slope

Install and maintain grade and slope references.

The screed must produce a uniform HMA surface texture without tearing, shoving, or gouging.

The paver must not leave marks such as ridges and indentations unless you can eliminate them by rolling.

Rollers must be equipped with a system that prevents HMA from sticking to the wheels. You may use a parting agent that does not damage the HMA or impede the bonding of layers.

In areas inaccessible to spreading and compacting equipment:

1. Spread the HMA by any means to obtain the specified lines, grades and cross sections.
2. Use a pneumatic tamper, plate compactor, or equivalent to achieve thorough compaction.

### **39-1.11 TRANSPORTING, SPREADING, AND COMPACTING**

Do not pave HMA on a wet pavement or frozen surface.

You may deposit HMA in a windrow and load it in the paver if:

1. Paver is equipped with a hopper that automatically feeds the screed
2. Loading equipment can pick up the windrowed material and deposit it in the paver hopper without damaging base material
3. Activities for deposit, pick-up, loading, and paving are continuous
4. HMA temperature in the windrow does not fall below 127 °C

You may pave HMA in 1 or more layers on areas less than 1.5 m wide and outside the traveled way including shoulders. You may use mechanical equipment other than a paver for these areas. The equipment must produce a uniform smoothness and texture.

HMA handled, spread, or windrowed must not stain the finished surface of any improvement including pavement.

Do not use petroleum products such as kerosene or diesel fuel to release HMA from trucks, spreaders, or compactors.

HMA must be free of:

1. Segregation
2. Coarse or fine aggregate pockets
3. Hardened lumps

Longitudinal joints in the top layer must match specified lane edges. Alternate longitudinal joint offsets in lower layers at least 0.15 m from each side of the specified lane edges. You may request in writing other longitudinal joint placement patterns.

Until the adjoining through lane's top layer has been paved, do not pave the top layer of:

1. Shoulders
2. Tapers
3. Transitions
4. Road connections
5. Driveways
6. Curve widenings
7. Chain control lanes
8. Turnouts
9. Turn pockets

If the number of lanes change, pave each through lane's top layer before paving a tapering lane's top layer. Simultaneous to paving a through lane's top layer, you may pave an adjoining area's top layer including shoulders. Do not operate spreading equipment on any area's top layer until completing final compaction.

If HMA (leveling) is specified, fill and level irregularities and ruts with HMA before spreading HMA over base, existing surfaces, or bridge decks. You may use mechanical equipment other than a paver for these areas. The equipment must

produce a uniform smoothness and texture. HMA used to change an existing surface's cross slope or profile is not HMA (leveling).

If placing HMA against the edge of existing pavement, sawcut or grind the pavement straight and vertical along the joint and remove extraneous material without damaging the surface remaining in place. If placing HMA against the edge of a longitudinal or transverse construction joint and the joint is damaged or not placed to a neat line, sawcut or grind the pavement straight and vertical along the joint and remove extraneous material without damaging the surface remaining in place. Repair or remove and replace damaged pavement at your expense.

Rolling must leave the completed surface compacted and smooth without tearing, cracking, or shoving. Complete finish rolling activities before the pavement surface temperature is:

1. Below 65 °C for HMA with unmodified binder
2. Below 60 °C for HMA with modified binder
3. Below 93 °C for RHMA-G

If a vibratory roller is used as a finish roller, turn the vibrator off.

Do not use a pneumatic tired roller to compact RHMA-G.

For Standard and QC/QA, if a 19-millimeter aggregate grading is specified, you may use a 12.5-millimeter aggregate grading if the specified paved thickness is from between 38 mm and 60 mm thick.

Spread and compact HMA under Section 39-3.03, "Spreading and Compacting Equipment," and Section 39-3.04, "Transporting, Spreading, and Compacting," for any of the following:

1. Specified paved thickness is less than 45 mm.
2. Specified paved thickness is less than 60 mm and a 19-millimeter aggregate grading is specified and used.
3. You spread and compact at:
  - 3.1. Asphalt concrete surfacing replacement areas
  - 3.2. Leveling courses
  - 3.3. Areas the Engineer determines conventional compaction and compaction measurement methods are impeded

Do not allow traffic on new HMA pavement until its mid-depth temperature is below 71 °C.

If you request in writing and the Engineer authorizes, you may cool HMA Type A and Type B with water when rolling activities are complete. Apply water under Section 17, "Watering."

Spread sand at a rate between 0.5 kg and 1 kg per square meter on new RHMA-G, RHMA-O, and RHMA-O-HB pavement when finish rolling is complete. Sand must be free of clay or organic matter. Sand must comply with Section 90-3.03, "Fine Aggregate Grading." Keep traffic off the pavement until spreading sand is complete.

### **39-1.12 SMOOTHNESS**

#### **39-1.12A General**

Determine HMA smoothness with a profilograph and a straightedge.

Smoothness specifications do not apply to OGFC placed on existing pavement not constructed under the same project.

If portland cement concrete is placed on HMA:

1. Cold plane the HMA finished surface to within specified tolerances if it is higher than the grade specified by the Engineer.
2. Remove and replace HMA if the finished surface is lower than 15 mm below the grade specified by the Engineer.

#### **39-1.12B Straightedge**

The HMA pavement top layer must not vary from the lower edge of a 3.66-meter long straightedge:

1. More than 3 mm when the straight edge is laid parallel with the centerline
2. More than 6 mm when the straightedge is laid perpendicular to the centerline and extends from edge to edge of a traffic lane
3. More than 6 mm when the straightedge is laid within 7.3 m of a pavement conform

#### **39-1.12C Profilograph**

Under California Test 526, determine the zero (null) blanking band Profile Index ( $PI_0$ ) and must-grinds on the top layer of HMA Type A, Type B, and RHMA-G pavement. Take 2 profiles within each traffic lane, 1 m from and parallel with the edge of each lane.

A must-grind is a deviation of 7.5 mm or more in a length of 7.5 m. You must correct must-grinds.

For OGFC, only determine must-grinds when placed over HMA constructed under the same project. The top layer of the underlying HMA must comply with the smoothness specifications before placing OGFC.

Profile pavement in the Engineer's presence. Choose the time of profiling.

On tangents and horizontal curves with a centerline radius of curvature 600 m or more, the  $PI_0$  must be at most 75 mm per 160-meter section.

On horizontal curves with a centerline radius of curvature between 300 m and 600 m including pavement within the superelevation transitions, the  $PI_0$  must be at most 150 mm per 160-meter section.

Before the Engineer accepts HMA pavement for smoothness, submit written final profilograms.

Submit 1 electronic copy of profile information in Microsoft Excel and 1 electronic copy of longitudinal pavement profiles in ".erd" format or other ProVAL compatible format to the Engineer and to:

Smoothness@dot.ca.gov

The following HMA pavement areas do not require a  $PI_0$ . You must measure these areas with a 3.6-meter straightedge and determine must-grinds with a profilograph:

1. New HMA with a total thickness less than or equal to 75 mm
2. HMA sections of city or county streets and roads, turn lanes and collector lanes that are less than 460 m in length

The following HMA pavement areas do not require a  $PI_0$ . You must measure these areas with a 3.6-meter straightedge:

1. Horizontal curves with a centerline radius of curvature less than 300 m including pavement within the superelevation transitions of those curves
2. Within 3.66 m of a transverse joint separating the pavement from:
  - 2.1. Existing pavement not constructed under the same project
  - 2.2. A bridge deck or approach slab
3. Exit ramp termini, truck weigh stations, and weigh-in-motion areas
4. If steep grades and superelevation rates greater than 6 percent are present on:
  - 4.1. Ramps
  - 4.2. Connectors
5. Turn lanes
6. Areas within 5 m of manholes or drainage transitions
7. Acceleration and deceleration lanes for at-grade intersections
8. Shoulders and miscellaneous areas
9. HMA pavement within 1 m from and parallel to the construction joints formed between curbs, gutters, or existing pavement

### **39-1.12D Smoothness Correction**

If the top layer of HMA Type A, Type B, or RHMA-G pavement does not comply with the smoothness specifications, grind the pavement to within tolerances, remove and replace it, or place a layer of HMA. The Engineer must authorize your choice of correction before the work begins.

Remove and replace the areas of OGFC not in compliance with the must-grind and straightedge specifications, except you may grind OGFC for correcting smoothness:

1. At a transverse joint separating the pavement from pavement not constructed under the same project
2. Within 3.66 m of a transverse joint separating the pavement from a bridge deck or approach slab

Corrected HMA pavement areas must be uniform rectangles with edges:

1. Parallel to the nearest HMA pavement edge or lane line
2. Perpendicular to the pavement centerline

Measure the corrected HMA pavement surface with a profilograph and a 3.66-meter straightedge and correct the pavement to within specified tolerances. If a must-grind area or straightedged pavement cannot be corrected to within specified tolerances, remove and replace the pavement.

On ground areas not overlaid with OGFC, apply fog seal coat under Section 37-1, "Seal Coats."

### **39-1.13 MISCELLANEOUS AREAS AND DIKES**

Miscellaneous areas are outside the traveled way and include:

1. Median areas not including inside shoulders
2. Island areas
3. Sidewalks
4. Gutters
5. Gutter flares
6. Ditches
7. Overside drains
8. Aprons at the ends of drainage structures

Spread miscellaneous areas in 1 layer and compact to the specified lines and grades.

For miscellaneous areas and dikes:

1. Do not submit a JMF.
2. Choose the 9.5-millimeter or 12.5-millimeter HMA Type A and Type B aggregate gradations.
3. Minimum asphalt binder content must be 6.8 percent for 9.5-millimeter aggregate and 6.0 percent for 12.5-millimeter aggregate. If you request in writing and the Engineer authorizes, you may reduce the minimum asphalt binder content.
4. Choose asphalt binder Grade PG 70-10 or the same grade specified for HMA.

## **39-2 STANDARD**

### **39-2.01 DESCRIPTION**

If HMA is specified as Standard, construct it under Section 39-1, "General," this Section 39-2, "Standard," and Section 39-5, "Measurement and Payment."

### **39-2.02 CONTRACTOR QUALITY CONTROL**

#### **39-2.02A Quality Control Plan**

Establish, implement, and maintain a Quality Control Plan (QCP) for HMA. The QCP must describe the organization and procedures you will use to:

1. Control the quality characteristics
2. Determine when corrective actions are needed (action limits)
3. Implement corrective actions

When you submit the proposed JMF, submit the written QCP. You and the Engineer must discuss the QCP during the pre-paving conference.

The QCP must address the elements affecting HMA quality including:

1. Aggregate
2. Asphalt binder
3. Additives
4. Production
5. Paving

The Engineer reviews each QCP within 5 business days from the submittal. Hold HMA production until the Engineer accepts the QCP in writing. The Engineer's QCP acceptance does not mean your compliance with the QCP will result in acceptable HMA. Section 39-1.05, "Engineer's Acceptance," specifies HMA acceptance.

#### **39-2.02B Quality Control Testing**

Perform sampling and testing at the specified frequency for the following quality characteristics:

**Minimum Quality Control – Standard**

Quality Characteristic	Test Method	Minimum Sampling and Testing Frequency	HMA Type			
			A	B	RHMA-G	OGFC
Aggregate gradation <sup>a</sup>	CT 202	1 per 750 tonnes and any remaining part	JMF ± Tolerance <sup>b</sup>			
Sand equivalent (min.) <sup>c</sup>	CT 217		47	42	47	--
Asphalt binder content (%)	CT 379 or 382		JMF ± 0.45	JMF ± 0.45	JMF ± 0.50	JMF ± 0.50
HMA moisture content (% max.)	CT 226 or CT 370	1 per 2500 tonnes but not less than 1 per paving day	1.0	1.0	1.0	1.0
Percent of maximum theoretical density (%) <sup>d,e</sup>	Quality control plan	2 per business day (min.)	91 - 97	91 - 97	91 - 97	--
Stabilometer value (min.) <sup>e,f</sup> 4.75-mm and 9.5-mm gradings 12.5-mm and 19-mm gradings	CT 366	One per 4000 tonnes or 2 per 5 business days, whichever is more	30	30	--	--
			37	35	23	--
Air voids content (%) <sup>e,g</sup>	CT 367		4 ± 2	4 ± 2	Specification ± 2	--
Aggregate moisture content at continuous mixing plants and RAP moisture content at continuous mixing plants and batch mixing plants <sup>h</sup>	CT 226 or CT 370	2 per day during production	--	--	--	--
Percent of crushed particles coarse aggregate (% min.) One fractured face Two fractured faces Fine aggregate (% min) (Passing 4.75-mm sieve and retained on 2.36-mm sieve.) One fractured face	CT 205	As necessary and designated in the QCP. At least once per project	90	25	--	90
			75	--	90	75
			70	20	70	90
Los Angeles Rattler (% max.) Loss at 100 rev. Loss at 500 rev.	CT 211		12 45	-- 50	12 40	12 40

Flat and elongated particles (% max. by mass @ 5:1)	ASTM D 4791		Report only	Report only	Report only	Report only
Fine aggregate angularity (% min.)	AASHTO T 304, Method A		45	45	45	--
Voids filled with asphalt (%) <sup>i</sup> 4.75-mm grading 9.5-mm grading 12.5-mm grading 19-mm grading	LP-3		76.0 – 80.0 73.0 – 76.0 65.0 – 75.0 65.0 – 75.0	76.0 – 80.0 73.0 – 76.0 65.0 – 75.0 65.0 – 75.0	Report only	--
Voids in mineral aggregate (% min.) <sup>i</sup> 4.75-mm grading 9.5-mm grading 12.5-mm grading 19-mm grading	LP-2		17.0 15.0 14.0 13.0	17.0 15.0 14.0 13.0	-- -- 18.0 – 23.0 <sup>j</sup> 18.0 – 23.0 <sup>j</sup>	--
Dust proportion <sup>1</sup> 4.75-mm and 9.5-mm gradings 12.5-mm and 19-mm gradings	LP-4		0.9 – 2.0 0.6 – 1.3	0.9 – 2.0 0.6 – 1.3	Report only	--
Smoothness	Section 39-1.12	--	3.66-m straightedge, must-grind, and PI <sub>0</sub>	3.66-m straightedge, must-grind, and PI <sub>0</sub>	3.66-m straightedge, must-grind, and PI <sub>0</sub>	3.66-m straightedge and must-grind
Asphalt rubber binder viscosity @ 177 °C, centipoises	Section 39-1.02D	Section 39-1.04C	--	--	1500 – 4000	1500 – 4000
Asphalt modifier	Section 39-1.02D	Section 39-1.04C	--	--	Section 39-1.02D	Section 39-1.02D
Crumb rubber modifier	Section 39-1.02D	Section 39-1.04C	--	--	Section 39-1.02D	Section 39-1.02D

Notes:

<sup>a</sup> Determine combined aggregate gradation containing RAP under Laboratory Procedure LP-9.

<sup>b</sup> The tolerances must comply with the allowable tolerances in Section 39-1.02E, "Aggregate."

<sup>c</sup> Report the average of 3 tests from a single split sample.

<sup>d</sup> Required for HMA Type A, Type B, and RHMA-G if the specified paved thickness is at least 45 mm.

<sup>e</sup> Determine maximum theoretical density (California Test 309) at the frequency specified for Test Maximum Density under California Test 375, Part 5.D.

<sup>f</sup> Modify California Test 304, Part 2.B.2.c: "After compaction in the mechanical compactor, cool to 60 °C ± 3 °C by allowing the briquettes to cool at room temperature for 0.5 hour, then place the briquettes in the oven at 69 °C for a minimum of 2 hours and not more than 3 hours."

<sup>g</sup> Determine the bulk specific gravity of each lab-compacted briquette under California Test 308, Method A, and theoretical maximum specific gravity under California Test 309.

<sup>h</sup> For adjusting the plant controller at the HMA plant.

<sup>i</sup> Report only if the adjustment for asphalt binder content target value is less than or equal to ± 0.3 percent from OBC.

<sup>j</sup> Voids in mineral aggregate for RHMA-G must be within this range.

For any single quality characteristic except smoothness, if 2 consecutive quality control test results do not comply with the action limits or specifications:

1. Stop production.
2. Notify the Engineer in writing.
3. Take corrective action.
4. Demonstrate compliance with the specifications before resuming production and placement on the State highway.

### **39-2.03 ENGINEER'S ACCEPTANCE**

#### **39-2.03A Testing**

The Engineer samples for acceptance testing and tests for:

**HMA Acceptance - Standard**

Quality Characteristic				Test Method	HMA Type			
					A	B	RHMA-G	OGFC
Aggregate gradation <sup>a</sup>				CT 202	JMF ± Tolerance <sup>c</sup>	JMF ± Tolerance <sup>c</sup>	JMF ± Tolerance <sup>c</sup>	JMF ± Tolerance <sup>c</sup>
Sieve	19-mm	12.5-mm	9.5-mm					
12.5-mm	X <sup>b</sup>							
9.5-mm		X						
2.36-mm	X	X	X					
0.075-mm	X	X	X					
Sand equivalent (min.) <sup>d</sup>				CT 217	47	42	47	--
Asphalt binder content (%)				CT 379 or 382	JMF ± 0.45	JMF ± 0.45	JMF ± 0.5	JMF ± 0.50
HMA moisture content (% max.)				CT 226 or CT 370	1.0	1.0	1.0	1.0
Percent of maximum theoretical density (%) <sup>e, f</sup>				CT 375	91 – 97	91 – 97	91 – 97	--
Stabilometer value (min.) <sup>d, g</sup>				CT 366	30 37	30 35	-- 23	-- --
4.75-mm and 9.5-mm gradings								
12.5-mm and 19-mm gradings								
Air voids content (%) <sup>d, h</sup>				CT 367	4 ± 2	4 ± 2	Specification ± 2	--
Percent of crushed particles Coarse aggregate (% min.)				CT 205	90 75	25 --	-- 90	90 75
One fractured face								
Two fractured faces								
Fine aggregate (% min.) (Passing 4.75-mm sieve and retained on 2.36-mm sieve.)				CT 205	70	20	70	90
One fractured face								
Percent of crushed particles Coarse aggregate (% min.)				CT 205	90 75	25 --	-- 90	90 75
One fractured face								
Two fractured faces								
Los Angeles Rattler (% max.)				CT 211	12 45	-- 50	12 40	12 40
Loss at 100 rev.								
Loss at 500 rev.								
Fine aggregate angularity (% min.)				AASHTO T 304, Method A	45	45	45	--
Flat and elongated particles (% max. by mass @ 5:1)				ASTM D 4791	Report only	Report only	Report only	Report only
Voids filled with asphalt (%) <sup>1</sup>				LP-3	76.0 – 80.0 73.0 – 76.0 65.0 – 75.0 65.0 – 75.0	76.0 – 80.0 73.0 – 76.0 65.0 – 75.0 65.0 – 75.0	Report only	--
4.75-mm grading								
9.5-mm grading								
12.5-mm grading								
19-mm grading								
Voids in mineral aggregate (% min.) <sup>i</sup>				LP-2	17.0 15.0 14.0 13.0	17.0 15.0 14.0 13.0	-- -- 18.0 – 23.0 <sup>j</sup> 18.0 – 23.0 <sup>j</sup>	--
4.75-mm grading								
9.5-mm grading								
12.5-mm grading								
19-mm grading								
Dust proportion <sup>1</sup>				LP-4	0.9 – 2.0	0.9 – 2.0	Report only	--
4.75-mm and 9.5-mm gradings								

12.5-mm and 19-mm gradings		0.6 – 1.3	0.6 – 1.3		
Smoothness	Section 39-1.12	3.66-m straightedge, must-grind, and PI <sub>0</sub>	3.66-m straightedge, must-grind, and PI <sub>0</sub>	3.66-m straightedge, must-grind, and PI <sub>0</sub>	3.66-m straightedge and must-grind
Asphalt binder	Various	Section 92	Section 92	Section 92	Section 92
Asphalt rubber binder	Various	--	--	Section 92-1.02(C) and Section 39-1.02D	Section 92-1.02(C) and Section 39-1.02D
Asphalt modifier	Various	--	--	Section 39-1.02D	Section 39-1.02D
Crumb rubber modifier	Various	--	--	Section 39-1.02D	Section 39-1.02D

<sup>a</sup> The Engineer determines combined aggregate gradations containing RAP under Laboratory Procedure LP-9.

<sup>b</sup> "X" denotes the sieves the Engineer considers for the specified aggregate gradation.

<sup>c</sup> The tolerances must comply with the allowable tolerances in Section 39-1.02E, "Aggregate."

<sup>d</sup> The Engineer reports the average of 3 tests from a single split sample.

<sup>e</sup> The Engineer determines percent of maximum theoretical density if the specified paved thickness is at least 45-mm under California Test 375 except the Engineer uses:

1. California Test 308, Method A, to determine in-place density of each density core instead of using the nuclear gauge in Part 4, "Determining In-Place Density By The Nuclear Density Device."
2. California Test 309 to determine maximum theoretical density instead of calculating test maximum density in Part 5, "Determining Test Maximum Density."

<sup>f</sup> The Engineer determines maximum theoretical density (California Test 309) at the frequency specified for Test Maximum Density under California Test 375, Part 5.D.

<sup>g</sup> Modify California Test 304, Part 2.B.2.c: "After compaction in the mechanical compactor, cool to 60 °C ± 3 °C by allowing the briquettes to cool at room temperature for 0.5 hour, then place the briquettes in the oven at 69 °C for a minimum of 2 hours and not more than 3 hours."

<sup>h</sup> The Engineer determines the bulk specific gravity of each lab-compacted briquette under California Test 308, Method A, and theoretical maximum specific gravity under California Test 309.

<sup>i</sup> Report only if the adjustment for asphalt binder content target value is less than or equal to ± 0.3 percent from OBC.

<sup>j</sup> Voids in mineral aggregate for RHMA-G must be within this range.

No single test result may represent more than the smaller of 750 tonnes or 1 day's production.

For any single quality characteristic except smoothness, if 2 consecutive acceptance test results do not comply with the specifications:

1. Stop production.
2. Take corrective action.
3. In the Engineer's presence, take samples and split each sample into 4 parts. Test 1 part for compliance with the specifications and submit 3 parts to the Engineer. The Engineer tests 1 part for compliance with the specifications and reserves and stores 2 parts.
4. Demonstrate compliance with the specifications before resuming production and placement on the State highway.

The Engineer tests the density core you take from each 250 tonnes of HMA production. The Engineer determines the percent of maximum theoretical density for each density core by determining the density core's density and dividing by the maximum theoretical density.

If the specified total paved thickness is at least 45 mm and any layer is less than 45 mm, the Engineer determines the percent of maximum theoretical density from density cores taken from the final layer measured the full depth of the total paved HMA thickness.

For percent of maximum theoretical density, the Engineer determines a deduction for each test result outside the specifications in compliance with:

**Reduced Payment Factors for Percent of Maximum Theoretical Density**

HMA Type A and B and RHMA-G Percent of Maximum Theoretical Density	Reduced Payment Factor	HMA Type A and B and RHMA-G Percent of Maximum Theoretical Density	Reduced Payment Factor
91.0	0.0000	97.0	0.0000
90.9	0.0125	97.1	0.0125
90.8	0.0250	97.2	0.0250
90.7	0.0375	97.3	0.0375
90.6	0.0500	97.4	0.0500
90.5	0.0625	97.5	0.0625
90.4	0.0750	97.6	0.0750
90.3	0.0875	97.7	0.0875
90.2	0.1000	97.8	0.1000
90.1	0.1125	97.9	0.1125
90.0	0.1250	98.0	0.1250
89.9	0.1375	98.1	0.1375
89.8	0.1500	98.2	0.1500
89.7	0.1625	98.3	0.1625
89.6	0.1750	98.4	0.1750
89.5	0.1875	98.5	0.1875
89.4	0.2000	98.6	0.2000
89.3	0.2125	98.7	0.2125
89.2	0.2250	98.8	0.2250
89.1	0.2375	98.9	0.2375
89.0	0.2500	99.0	0.2500
< 89.0	Remove and Replace	> 99.0	Remove and Replace

**39-2.04 TRANSPORTING, SPREADING, AND COMPACTING**

Determine the number of rollers needed to obtain the specified density and surface finish.

**39-3 METHOD**

**39-3.01 DESCRIPTION**

If HMA is specified as Method, construct it under Section 39-1, "General," this Section 39-3, "Method," and Section 39-5, "Measurement and Payment."

**39-3.02 ENGINEER'S ACCEPTANCE**

**39-3.02A Testing**

The Engineer samples for acceptance testing and tests for:

**HMA Acceptance - Method**

Quality Characteristic	Test Method	HMA Type			
		A	B	RHMA-G	OGFC
Aggregate gradation <sup>a</sup>	CT 202	JMF ± Tolerance <sup>b</sup>			
Sand equivalent (min.) <sup>c</sup>	CT 217	47	42	47	--
Asphalt binder content (%)	CT 379 or 382	JMF ± 0.45	JMF ± 0.45	JMF ± 0.5	JMF ± 0.50
HMA moisture content (% max.)	CT 226 or CT 370	1.0	1.0	1.0	1.0
Stabilometer value (min.) <sup>c, d</sup>	CT 366				
4.75-mm and 9.5-mm gradings		30	30	--	--
12.5-mm and 19-mm gradings		37	35	23	--
Percent of crushed particles	CT 205				
Coarse aggregate (% min.)					
One fractured face		90	25	--	90
Two fractured faces		75	--	90	75
Fine aggregate (% min) (Passing 4.75-mm sieve and retained on 2.36-mm sieve.)					
One fractured face		70	20	70	90
Los Angeles Rattler (% max.)	CT 211				
Loss at 100 rev.		12	--	12	12
Loss at 500 rev.		45	50	40	40
Air voids content (%) <sup>c, e</sup>	CT 367	4 ± 2	4 ± 2	Specification ± 2	--
Fine aggregate angularity (% min.)	AASHTO T 304, Method A	45	45	45	--
Flat and elongated particles (% max. by mass @ 5:1)	ASTM D 4791	Report only	Report only	Report only	Report only
Voids filled with asphalt (%) <sup>f</sup>	LP-3			Report only	
4.75-mm grading		76.0 – 80.0	76.0 – 80.0		--
9.5-mm grading		73.0 – 76.0	73.0 – 76.0		
12.5-mm grading		65.0 – 75.0	65.0 – 75.0		
19-mm grading		65.0 – 75.0	65.0 – 75.0		
Voids in mineral aggregate (% min.) <sup>f</sup>	LP-2				
4.75-mm grading		17.0	17.0	--	--
9.5-mm grading		15.0	15.0	--	
12.5-mm grading		14.0	14.0	18.0 – 23.0 <sup>g</sup>	
19-mm grading		13.0	13.0	18.0 – 23.0 <sup>g</sup>	
Dust proportion <sup>f</sup>	LP-4			Report only	
4.75-mm and 9.5-mm gradings		0.9 – 2.0	0.9 – 2.0		--
12.5-mm and 19-mm gradings		0.6 – 1.3	0.6 – 1.3		
Smoothness	Section 39-1.12	3.66-m straightedge and must-grind			
Asphalt binder	Various	Section 92	Section 92	Section 92	Section 92

Asphalt rubber binder	Various	--	--	Section 92-1.02(C) and Section 39-1.02D	Section 92-1.02(C) and Section 39-1.02D
Asphalt modifier	Various	--	--	Section 39-1.02D	Section 39-1.02D
Crumb rubber modifier	Various	--	--	Section 39-1.02D	Section 39-1.02D

<sup>a</sup>The Engineer determines combined aggregate gradations containing RAP under Laboratory Procedure LP-9.

<sup>b</sup>The tolerances must comply with the allowable tolerances in Section 39-1.02E, "Aggregate."

<sup>c</sup>The Engineer reports the average of 3 tests from a single split sample.

<sup>d</sup>Modify California Test 304, Part 2.B.2.c: "After compaction in the mechanical compactor, cool to 60 °C ± 3 °C by allowing the briquettes to cool at room temperature for 0.5 hour, then place the briquettes in the oven at 69 °C for a minimum of 2 hours and not more than 3 hours."

<sup>e</sup>The Engineer determines the bulk specific gravity of each lab-compacted briquette under California Test 308, Method A, and theoretical maximum specific gravity under California Test 309.

<sup>f</sup>Report only if the adjustment for asphalt binder content target value is less than or equal to ± 0.3 percent from OBC.

<sup>g</sup>Voids in mineral aggregate for RHMA-G must be within this range.

No single test result may represent more than the smaller of 750 tonnes or 1 day's production.

For any single quality characteristic except smoothness, if 2 consecutive acceptance test results do not comply with the specifications:

1. Stop production.
2. Take corrective action.
3. In the Engineer's presence, take samples and split each sample into 4 parts. Test 1 part for compliance with the specifications and submit 3 parts to the Engineer. The Engineer tests 1 part for compliance with the specifications and reserves and stores 2 parts.
4. Demonstrate compliance with the specifications before resuming production and placement on the State highway.

### 39-3.03 SPREADING AND COMPACTING EQUIPMENT

Each paver spreading HMA Type A and Type B must be followed by 3 rollers:

1. One vibratory roller specifically designed to compact HMA. The roller must be capable of at least 2500 vibrations per minute and must be equipped with amplitude and frequency controls. The roller's gross static mass must be at least 6.8 tonnes.
2. One oscillating type pneumatic-tired roller at least 1.2 m wide. Pneumatic tires must be of equal size, diameter, type, and ply. The tires must be inflated to 415 kilopascals minimum and maintained so that the air pressure does not vary more than 35 kilopascals.
3. One steel-tired, 2-axle tandem roller. The roller's gross static mass must be at least 6.8 tonnes.

Each roller must have a separate operator. Rollers must be self-propelled and reversible.

Compact RHMA-G under the specifications for compacting HMA Type A and Type B except do not use pneumatic-tired rollers.

Compact OGFC with steel-tired, 2-axle tandem rollers. If placing over 275 tonnes of OGFC per hour, use at least 3 rollers for each paver. If placing less than 275 tonnes of OGFC per hour, use at least 2 rollers for each paver. Each roller must weigh between 2250 kilograms to 3075 kilograms per linear meter of drum width. Turn the vibrator off.

### 39-3.04 TRANSPORTING, SPREADING, AND COMPACTING

Pave HMA in maximum 75-millimeter thick compacted layers.

If the surface to be paved is both in sunlight and shade, pavement surface temperatures are taken in the shade.

Spread HMA Type A and Type B only if atmospheric and surface temperatures are:

### Minimum Atmospheric and Surface Temperatures

Compacted Layer Thickness, mm				
	Unmodified Asphalt Binder	Modified Asphalt Binder <sup>a</sup>	Unmodified Asphalt Binder	Modified Asphalt Binder <sup>a</sup>
< 45	12.8	10	15.6	12.8
45 – 75	7.2	7.2	10	10

Note:

<sup>a</sup> Except asphalt rubber binder.

If the asphalt binder for HMA Type A and Type B is:

1. Unmodified asphalt binder, complete:

- 1.1. First coverage of breakdown compaction before the surface temperature drops below 120 °C
- 1.2. Breakdown and intermediate compaction before the surface temperature drops below 95 °C
- 1.3. Finish compaction before the surface temperature drops below 65 °C

2. Modified asphalt binder, complete:

- 2.1. First coverage of breakdown compaction before the surface temperature drops below 115 °C
- 2.2. Breakdown and intermediate compaction before the surface temperature drops below 85 °C
- 2.3. Finish compaction before the surface temperature drops below 60 °C

For RHMA-G:

1. Only spread and compact if the atmospheric temperature is at least 12.8 °C and the surface temperature is at least 15.6 °C.
2. Complete the first coverage of breakdown compaction before the surface temperature drops below 140 °C.
3. Complete breakdown and intermediate compaction before the surface temperature drops below 120 °C.
4. Complete finish compaction before the surface temperature drops below 95 °C.
5. If the atmospheric temperature is below 21 °C, cover loads in trucks with tarpaulins. The tarpaulins must completely cover the exposed load until you transfer the mixture to the paver's hopper or to the pavement surface.

For OGFC with unmodified asphalt binder:

1. Only spread and compact if the atmospheric temperature is at least 12.8 °C and the surface temperature is at least 15.6 °C.
2. Complete first coverage using 2 rollers before the surface temperature drops below 115 °C.
3. Complete all compaction before the surface temperature drops below 95 °C.
4. If the atmospheric temperature is below 21 °C, cover loads in trucks with tarpaulins. The tarpaulins must completely cover the exposed load until you transfer the mixture to the paver's hopper or to the pavement surface.

For OGFC with modified asphalt binder except asphalt rubber binder:

1. Only spread and compact if the atmospheric temperature is at least 10 °C and the surface temperature is at least 10 °C.
2. Complete first coverage using 2 rollers before the surface temperature drops below 115 °C.
3. Complete all compaction before the surface temperature drops below 85 °C.
4. If the atmospheric temperature is below 21 °C, cover loads in trucks with tarpaulins. The tarpaulins must completely cover the exposed load until you transfer the mixture to the paver's hopper or to the pavement surface.

For RHMA-O and RHMA-O-HB:

1. Only spread and compact if the atmospheric temperature is at least 12.8 °C and surface temperature is at least 15.6 °C.
2. Complete the 1st coverage using 2 rollers before the surface temperature drops below 140 °C.
3. Complete compaction before the surface temperature drops below 120 °C.
4. If the atmospheric temperature is below 21 °C, cover loads in trucks with tarpaulins. The tarpaulins must completely cover the exposed load until the mixture is transferred to the paver's hopper or to the pavement surface.

For RHMA-G and OGFC, tarpaulins are not required if the time from discharge to truck until transfer to the paver's hopper or the pavement surface is less than 30 minutes.

HMA compaction coverage is the number of passes needed to cover the paving width. A pass is 1 roller's movement parallel to the paving in either direction. Overlapping passes are part of the coverage being made and are not a subsequent coverage. Do not start a coverage until completing the prior coverage.

Start rolling at the lower edge and progress toward the highest part.

Perform breakdown compaction of each layer of HMA Type A, Type B, and RHMA-G with 3 coverages using a vibratory roller. The speed of the vibratory roller in kilometers per hour must not exceed the vibrations per minute divided by 1600. If the HMA layer thickness is less than 25 mm, turn the vibrator off. The Engineer may order fewer coverages if the HMA layer thickness is less than 45 mm.

Perform intermediate compaction of each layer of HMA Type A and Type B with 3 coverages using a pneumatic-tired roller at a speed not to exceed 8 kilometers per hour.

Perform finish compaction of HMA Type A, Type B, and RHMA-G with 1 coverage using a steel-tired roller.

Compact OGFC with 2 coverages using steel-tired rollers.

## **39-4 QUALITY CONTROL / QUALITY ASSURANCE**

### **39-4.01 DESCRIPTION**

If HMA is specified as Quality Control / Quality Assurance, construct it under Section 39-1, "General," this Section 39-4, "Quality Control / Quality Assurance," and Section 39-5, "Measurement and Payment."

### **39-4.02 GENERAL**

The QC / QA construction process consists of:

1. Establishing, maintaining, and changing if needed a quality control system providing assurance the HMA complies with the specifications
2. Sampling and testing at specified intervals, or sublots, to demonstrate compliance and to control process
3. The Engineer sampling and testing at specified intervals to verify testing process and HMA quality
4. The Engineer using test results, statistical evaluation of verified quality control tests, and inspection to accept HMA for payment

A lot is a quantity of HMA. The Engineer designates a new lot when:

1. 20 sublots are complete
2. The JMF changes
3. Production stops for more than 30 days

Each lot consists of no more than 20 sublots. A subplot is 750 tonnes except HMA paved at day's end greater than 250 tonnes is a subplot. If HMA paved at day's end is less than 250 tonnes, you may either make this quantity a subplot or include it in the previous subplot's test results for statistical evaluation.

### **39-4.03 CONTRACTOR QUALITY CONTROL**

#### **39-4.03A General**

Use a composite quality factor,  $QF_C$ , and individual quality factors,  $QF_{QCi}$ , to control your process and evaluate your quality control program. For quality characteristics without quality factors, use your quality control plan's action limits to control process.

Control HMA quality including:

1. Materials
2. Proportioning
3. Spreading and compacting
4. Finished roadway surface

Develop, implement, and maintain a quality control program that includes:

1. Inspection
2. Sampling
3. Testing

### **39-4.03B Quality Control Plan**

With the JMF submittal, submit a written Quality Control Plan (QCP). The QCP must comply with the Department's Quality Control Manual for Hot Mix Asphalt Production and Placement. Discuss the QCP with the Engineer during the prepaving conference.

The Engineer reviews each QCP within 5 business days from the submittal. Hold HMA production until the Engineer accepts the QCP in writing. The Engineer's QCP acceptance does not mean your compliance with the QCP will result in acceptable HMA. Section 39-1.05, "Engineer's Acceptance," specifies HMA acceptance.

The QCP must include the name and qualifications of a Quality Control Manager. The Quality Control Manager administers the QCP and during paving must be at the job site within 3 hours of receiving notice. The Quality Control Manager must not be any of the following on the project:

1. Foreman
2. Production or paving crewmember
3. Inspector
4. Tester

The QCP must include action limits and details of corrective action you will take if a test result for any quality characteristic falls outside an action limit.

As work progresses, you must submit a written QCP supplement to change quality control procedures, personnel, tester qualification status, or laboratory accreditation status.

### **39-4.03C Quality Control Inspection, Sampling, And Testing**

Sample, test, inspect, and manage HMA quality control.

Provide a roadway inspector while HMA paving activities are in progress. Provide a plant inspector during HMA production.

Inspectors must comply with the Department's Quality Control Manual for Hot Mix Asphalt Production and Placement.

Provide a testing laboratory and personnel for quality control testing. Provide the Engineer unrestricted access to the quality control activities. Before providing services for the project, the Engineer reviews, accredits, and qualifies the testing laboratory and personnel under the Department's Independent Assurance Program.

The minimum random sampling and testing for quality control is:

**Minimum Quality Control – QC / QA**

Quality Characteristic	Test Method	Minimum Sampling and Testing Frequency	HMA Type			Location of Sampling	Max. Reporting Time Allowance
			A	B	RHMA-G		
Aggregate gradation <sup>a</sup>	CT 202	1 per 750 tonnes	JMF ± Tolerance <sup>b</sup>	JMF ± Tolerance <sup>b</sup>	JMF ± Tolerance <sup>b</sup>	CT 125	24 hours
Asphalt binder content (%)	CT 379 or 382		JMF ±0.45	JMF ±0.45	JMF ±0.5	Loose Mix Behind Paver See CT 125	
Percent of maximum theoretical density (%) <sup>c, d</sup>	QC Plan		92 - 96	92 - 96	91 - 96	QC Plan	
Aggregate moisture content at continuous mixing plants and RAP moisture content at continuous mixing plants and batch mixing plants <sup>e</sup>	CT 226 or CT 370	2 per day during production	--	--	--	Stock-piles or cold feed belts	--
Sand equivalent (min.) <sup>f</sup>	CT 217	1 per 750 tonnes	47	42	47	CT 125	24 hours
HMA moisture content (% max.)	CT 226 or CT 370	1 per 2500 tonnes but not less than 1 per paving day	1.0	1.0	1.0	Loose Mix Behind Paver See CT 125	24 hours
Stabilometer Value (min.) <sup>f, g</sup> 4.75-mm and 9.5-mm gradings 12.5-mm and 19-mm gradings	CT 366	1 per 4000 tonnes or 2 per 5 business days, whichever is more	30	30	--		48 hours
			37	35	23		
Air voids content (%) <sup>f, h</sup>	CT 367		4 ± 2	4 ± 2	Specification ± 2		

Percent of crushed particles coarse aggregate (% min.) One fractured face Two fractured faces	CT 205	As necessary and designated in QCP. At least once per project.	90	25	--	CT 125	48 hours	
Fine aggregate (% min) (Passing 4.75-mm sieve and retained on 2.36-mm sieve.) One fractured face			75	--	90			
Los Angeles Rattler (% max.) Loss at 100 rev. Loss at 500 rev.			CT 211	12 45	-- 50			12 40
Fine aggregate angularity (% min.)	AASHTO T 304, Method A		45	45	45	CT 125		
Flat and elongated particle (% max. by mass @ 5:1)	ASTM D 4791		Report only	Report only	Report only	CT 125		
Voids filled with asphalt (%) <sup>i</sup> 4.75-mm grading 9.5-mm grading 12.5-mm grading 19-mm grading	LP-3		76.0 – 80.0 73.0 – 76.0 65.0 – 75.0 65.0 – 75.0	76.0 – 80.0 73.0 – 76.0 65.0 – 75.0 65.0 – 75.0	Report only	LP-3		
Voids in mineral aggregate (% min.) <sup>i</sup> 4.75-mm grading 9.5-mm grading 12.5-mm grading 19-mm grading	LP-2		17.0 15.0 14.0 13.0	17.0 15.0 14.0 13.0	-- -- 18.0 – 23.0 <sup>j</sup> 18.0 – 23.0 <sup>j</sup>	LP-2		
Dust proportion <sup>1</sup> 4.75-mm and 9.5-mm gradings 12.5-mm and 19-mm gradings	LP-4		0.9 – 2.0 0.6 – 1.3	0.9 – 2.0 0.6 – 1.3	Report only	LP-4		
Smoothness	Section 39-1.12		--	3.66-m straight-edge, must-grind, and PI <sub>0</sub>	3.66-m straight-edge, must-grind, and PI <sub>0</sub>	3.66-m straight-edge, must-grind, and PI <sub>0</sub>		--
Asphalt rubber binder viscosity @ 177 °C, centipoises	Section 39-1.02D		--	--	--	1500 – 4000		Section 39-1.02D
Crumb rubber modifier	Section 39-1.02D	--	--	--	Section 39-1.02D	Section 39-1.02D	48 hours	

Notes:

<sup>a</sup> Determine combined aggregate gradation containing RAP under Laboratory Procedure LP-9.

<sup>b</sup> The tolerances must comply with the allowable tolerances in Section 39-1.02E, "Aggregate."

<sup>c</sup> Required for HMA Type A, Type B, and RHMA-G if the specified paved thickness is at least 45 mm.

<sup>d</sup> Determine maximum theoretical density (California Test 309) at the frequency specified for test maximum density under California Test 375, Part 5 D.

<sup>e</sup> For adjusting the plant controller at the HMA plant.

<sup>f</sup> Report the average of 3 tests from a single split sample.

<sup>g</sup> Modify California Test 304, Part 2.B.2.c: "After compaction in the mechanical compactor, cool to  $60\text{ }^{\circ}\text{C} \pm 3\text{ }^{\circ}\text{C}$  by allowing the briquettes to cool at room temperature for 0.5 hour, then place the briquettes in the oven at  $69\text{ }^{\circ}\text{C}$  for a minimum of 2 hours and not more than 3 hours."

<sup>h</sup> Determine the bulk specific gravity of each lab-compacted briquette under California Test 308, Method A, and theoretical maximum specific gravity under California Test 309.

<sup>i</sup> Report only if the adjustment for asphalt binder content target value is less than or equal to  $\pm 0.3$  percent from OBC

<sup>j</sup> Voids in mineral aggregate for RHMA-G must be within this range.

Within the specified reporting time, submit written test results including:

1. Sampling location, quantity, and time
2. Testing results
3. Supporting data and calculations

If test results for any quality characteristic are beyond the action limits in the QCP, take corrective actions. Document the corrective actions taken in the inspection records under Section 39-4.03E, "Records of Inspection and Testing."

Stop production, notify the Engineer in writing, take corrective action, and demonstrate compliance with the specifications before resuming production and placement on the State highway if:

1. A lot's composite quality factor,  $Q_{FC}$ , or an individual quality factor,  $Q_{FCi}$  for  $i = 3, 4, \text{ or } 5$ , is below 0.90 determined under Section 39-4.03F, "Statistical Evaluation"
2. An individual quality factor,  $Q_{FCi}$  for  $i = 1 \text{ or } 2$ , is below 0.75
3. Quality characteristics for which a quality factor,  $Q_{FCi}$ , is not determined has 2 consecutive acceptance or quality control tests not in compliance with the specifications

#### **39-4.03D Charts And Records**

Record sampling and testing results for quality control on forms provided in the "Quality Control Manual for Hot Mix Asphalt," or on forms you submit with the QCP. The QCP must also include form posting locations and submittal times.

Submit quality control test results using the Department's statistical evaluation program, HMAPay, available at

[www.dot.ca.gov/hq/construc/hma/index.htm](http://www.dot.ca.gov/hq/construc/hma/index.htm)

#### **39-4.03E Records Of Inspection And Testing**

During HMA production, submit in writing a daily:

1. HMA Construction Daily Record of Inspection. Also make this record available at the HMA plant and job site each day.
2. HMA Inspection and Testing Summary. Include in the summary:
  - 2.1. Test forms with the testers' signatures and Quality Control Manager's initials.
  - 2.2. Inspection forms with the inspectors' signatures and Quality Control Manager's initials.
  - 2.3. A list and explanation of deviations from the specifications or regular practices.
  - 2.4. A signed statement by the Quality Control Manager that says:

"It is hereby certified that the information contained in this record is accurate, and that information, tests, or calculations documented herein comply with the specifications of the contract and the standards set forth in the testing procedures. Exceptions to this certification are documented as part of this record."

Retain for inspection the records generated as part of quality control including inspection, sampling, and testing for at least 3 years after final acceptance.

#### **39-4.03F Statistical Evaluation**

##### **General**

Determine a lot's composite quality factor,  $Q_{FC}$ , and the individual quality factors,  $Q_{FCi}$ . Perform statistical evaluation calculations to determine these quality factors based on quality control test results for:

1. Aggregate gradation
2. Asphalt binder content
3. Percent of maximum theoretical density

The Engineer grants a waiver and you must use 1.0 as the individual quality factor for percent of maximum theoretical density,  $QF_{QC5}$ , for HMA paved in:

1. Areas where the specified paved thickness is less than 45 mm
2. Areas where the specified paved thickness is less than 60 mm and a 19-millimeter grading is specified and used
3. Dig outs
4. Leveling courses
5. Areas where, in the opinion of the Engineer, compaction or compaction measurement by conventional methods is impeded

### Statistical Evaluation Calculations

Use the Variability-Unknown / Standard Deviation Method to determine the percentage of a lot not in compliance with the specifications. The number of significant figures used in the calculations must comply with AASHTO R-11, Absolute Method.

Determine the percentage of work not in compliance with the specification limits for each quality characteristic as follows:

1. Calculate the arithmetic mean ( $\bar{X}$ ) of the test values

$$\bar{X} = \frac{\sum X}{n}$$

where:

x = individual test values  
n = number of test values

2. Calculate the standard deviation

$$s = \sqrt{\frac{n(\sum x^2) - (\sum x)^2}{n(n-1)}}$$

where:

$\sum(x^2)$  = sum of the squares of individual test values  
 $(\sum x)^2$  = sum of the individual test values squared  
n = number of test values

3. Calculate the upper quality index ( $Q_u$ )

$$Q_u = \frac{USL - \bar{X}}{s}$$

where:

USL = target value plus the production tolerance or upper specification limit  
s = standard deviation  
 $\bar{X}$  = arithmetic mean

4. Calculate the lower quality index ( $Q_L$ );

$$Q_L = \frac{\bar{X} - LSL}{s}$$

where:

LSL = target value minus production tolerance or lower specification limit

$s =$  standard deviation  
 $\bar{X} =$  arithmetic mean

5. From the table, Upper Quality Index  $Q_U$  or Lower Quality Index  $Q_L$ , of this Section 39-4.03F, "Statistical Evaluation", determine  $P_U$ ;

where:

$P_U =$  the estimated percentage of work outside the USL.  
 $P_U = 0$ , when USL is not specified.

6. From the table, Upper Quality Index  $Q_U$  or Lower Quality Index  $Q_L$ , of this Section 39-4.03F, "Statistical Evaluation," determine  $P_L$ ;

where:

$P_L =$  the estimated percentage of work outside the LSL.  
 $P_L = 0$ , when LSL is not specified.

7. Calculate the total estimated percentage of work outside the USL and LSL, percent defective

$$\text{Percent defective} = P_U + P_L$$

$P_U$  and  $P_L$  are determined from:

$P_U$ or $P_L$	Upper Quality Index $Q_U$ or Lower Quality Index $Q_L$												
	Sample Size (n)												
	5	6	7	8	9	10-11	12-14	15-17	18-22	23-29	30-42	43-66	>66
0	1.72	1.88	1.99	2.07	2.13	2.20	2.28	2.34	2.39	2.44	2.48	2.51	2.56
1	1.64	1.75	1.82	1.88	1.91	1.96	2.01	2.04	2.07	2.09	2.12	2.14	2.16
2	1.58	1.66	1.72	1.75	1.78	1.81	1.84	1.87	1.89	1.91	1.93	1.94	1.95
3	1.52	1.59	1.63	1.66	1.68	1.71	1.73	1.75	1.76	1.78	1.79	1.80	1.81
4	1.47	1.52	1.56	1.58	1.60	1.62	1.64	1.65	1.66	1.67	1.68	1.69	1.70
5	1.42	1.47	1.49	1.51	1.52	1.54	1.55	1.56	1.57	1.58	1.59	1.59	1.60
6	1.38	1.41	1.43	1.45	1.46	1.47	1.48	1.49	1.50	1.50	1.51	1.51	1.52
7	1.33	1.36	1.38	1.39	1.40	1.41	1.41	1.42	1.43	1.43	1.44	1.44	1.44
8	1.29	1.31	1.33	1.33	1.34	1.35	1.35	1.36	1.36	1.37	1.37	1.37	1.38
9	1.25	1.27	1.28	1.28	1.29	1.29	1.30	1.30	1.30	1.31	1.31	1.31	1.31
10	1.21	1.23	1.23	1.24	1.24	1.24	1.25	1.25	1.25	1.25	1.25	1.26	1.26
11	1.18	1.18	1.19	1.19	1.19	1.19	1.20	1.20	1.20	1.20	1.20	1.20	1.20
12	1.14	1.14	1.15	1.15	1.15	1.15	1.15	1.15	1.15	1.15	1.15	1.15	1.15
13	1.10	1.10	1.10	1.10	1.10	1.10	1.11	1.11	1.11	1.11	1.11	1.11	1.11
14	1.07	1.07	1.07	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
15	1.03	1.03	1.03	1.03	1.02	1.02	1.02	1.02	1.02	1.02	1.02	1.02	1.02
16	1.00	0.99	0.99	0.99	0.99	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98
17	0.97	0.96	0.95	0.95	0.95	0.95	0.94	0.94	0.94	0.94	0.94	0.94	0.94
18	0.93	0.92	0.92	0.92	0.91	0.91	0.91	0.91	0.90	0.90	0.90	0.90	0.90
19	0.90	0.89	0.88	0.88	0.88	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87
20	0.87	0.86	0.85	0.85	0.84	0.84	0.84	0.83	0.83	0.83	0.83	0.83	0.83
21	0.84	0.82	0.82	0.81	0.81	0.81	0.80	0.80	0.80	0.80	0.80	0.80	0.79
22	0.81	0.79	0.79	0.78	0.78	0.77	0.77	0.77	0.76	0.76	0.76	0.76	0.76
23	0.77	0.76	0.75	0.75	0.74	0.74	0.74	0.73	0.73	0.73	0.73	0.73	0.73
24	0.74	0.73	0.72	0.72	0.71	0.71	0.70	0.70	0.70	0.70	0.70	0.70	0.70
25	0.71	0.70	0.69	0.69	0.68	0.68	0.67	0.67	0.67	0.67	0.67	0.67	0.66
26	0.68	0.67	0.67	0.65	0.65	0.65	0.64	0.64	0.64	0.64	0.64	0.64	0.63
27	0.65	0.64	0.63	0.62	0.62	0.62	0.61	0.61	0.61	0.61	0.61	0.61	0.60
28	0.62	0.61	0.60	0.59	0.59	0.59	0.58	0.58	0.58	0.58	0.58	0.58	0.57
29	0.59	0.58	0.57	0.57	0.56	0.56	0.55	0.55	0.55	0.55	0.55	0.55	0.54
30	0.56	0.55	0.54	0.54	0.53	0.53	0.52	0.52	0.52	0.52	0.52	0.52	0.52
31	0.53	0.52	0.51	0.51	0.50	0.50	0.50	0.49	0.49	0.49	0.49	0.49	0.49
32	0.50	0.49	0.48	0.48	0.48	0.47	0.47	0.47	0.46	0.46	0.46	0.46	0.46
33	0.47	0.48	0.45	0.45	0.45	0.44	0.44	0.44	0.44	0.43	0.43	0.43	0.43
34	0.45	0.43	0.43	0.42	0.42	0.42	0.41	0.41	0.41	0.41	0.41	0.41	0.40
35	0.42	0.40	0.40	0.39	0.39	0.39	0.38	0.38	0.38	0.38	0.38	0.38	0.38
36	0.39	0.38	0.37	0.37	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36
37	0.36	0.35	0.34	0.34	0.34	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.32
38	0.33	0.32	0.32	0.31	0.31	0.31	0.30	0.30	0.30	0.30	0.30	0.30	0.30
39	0.30	0.30	0.29	0.28	0.28	0.28	0.28	0.28	0.28	0.28	0.28	0.28	0.28
40	0.28	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25
41	0.25	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23
42	0.23	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20
43	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18
44	0.16	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15
45	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13
46	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10
47	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08
48	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05
49	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03
50	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

1. If the value of  $Q_U$  or  $Q_L$  does not correspond to a value in the table, use the next lower value.
2. If  $Q_U$  or  $Q_L$  are negative values,  $P_U$  or  $P_L$  is equal to 100 minus the table value for  $P_U$  or  $P_L$ .

### Quality Factor Determination

Determine individual quality factors,  $QF_{QC_i}$ , using percent defective =  $P_U + P_L$  and:

Quality Factor	Quality Factors												
	Maximum Allowable Percent Defective ( $P_U + P_L$ )												
	Sample Size (n)												
	5	6	7	8	9	10-11	12-14	15-17	18-22	23-29	30-42	43-66	>66
1.05				0	0	0	0	0	0	0	0	0	0
1.04			0	1	3	5	4	4	4	3	3	3	3
1.03		0	2	4	6	8	7	7	6	5	5	4	4
1.02		1	3	6	9	11	10	9	8	7	7	6	6
1.01	0	2	5	8	11	13	12	11	10	9	8	8	7
1.00	22	20	18	17	16	15	14	13	12	11	10	9	8
0.99	24	22	20	19	18	17	16	15	14	13	11	10	9
0.98	26	24	22	21	20	19	18	16	15	14	13	12	10
0.97	28	26	24	23	22	21	19	18	17	16	14	13	12
0.96	30	28	26	25	24	22	21	19	18	17	16	14	13
0.95	32	29	28	26	25	24	22	21	20	18	17	16	14
0.94	33	31	29	28	27	25	24	22	21	20	18	17	15
0.93	35	33	31	29	28	27	25	24	22	21	20	18	16
0.92	37	34	32	31	30	28	27	25	24	22	21	19	18
0.91	38	36	34	32	31	30	28	26	25	24	22	21	19
0.90	39	37	35	34	33	31	29	28	26	25	23	22	20
0.89	41	38	37	35	34	32	31	29	28	26	25	23	21
0.88	42	40	38	36	35	34	32	30	29	27	26	24	22
0.87	43	41	39	38	37	35	33	32	30	29	27	25	23
0.86	45	42	41	39	38	36	34	33	31	30	28	26	24
0.85	46	44	42	40	39	38	36	34	33	31	29	28	25
0.84	47	45	43	42	40	39	37	35	34	32	30	29	27
0.83	49	46	44	43	42	40	38	36	35	33	31	30	28
0.82	50	47	46	44	43	41	39	38	36	34	33	31	29
0.81	51	49	47	45	44	42	41	39	37	36	34	32	30
0.80	52	50	48	46	45	44	42	40	38	37	35	33	31
0.79	54	51	49	48	46	45	43	41	39	38	36	34	32
0.78	55	52	50	49	48	46	44	42	41	39	37	35	33
0.77	56	54	52	50	49	47	45	43	42	40	38	36	34
0.76	57	55	53	51	50	48	46	44	43	41	39	37	35
0.75	58	56	54	52	51	49	47	46	44	42	40	38	36
Reject	60	57	55	53	52	51	48	47	45	43	41	40	37
	61	58	56	55	53	52	50	48	46	44	43	41	38
	62	59	57	56	54	53	51	49	47	45	44	42	39
	63	61	58	57	55	54	52	50	48	47	45	43	40
	64	62	60	58	57	55	53	51	49	48	46	44	41

Reject Values Greater Than Those Shown Above

Notes:

- To obtain a quality factor when the estimated percent outside specification limits from table, "Upper Quality Index  $Q_U$  or Lower Quality Index  $Q_L$ ," does not correspond to a value in the table, use the next larger value.

Compute the composite of single quality factors,  $QF_C$ , for a lot using:

$$QF_C = \sum_{i=1}^5 w_i QF_{QC_i}$$

where:

- $QF_C$  = the composite quality factor for the lot rounded to 2 decimal places.  
 $QF_{QC_i}$  = the quality factor for the individual quality characteristic.  
 $w$  = the weighting factor listed in the table HMA Acceptance – QC / QA.

$i =$  the quality characteristic index number in the table HMA Acceptance – QC / QA.

### 39-4.04 ENGINEER'S QUALITY ASSURANCE

#### 39-4.04A General

The Engineer assures quality by:

1. Reviewing mix designs and proposed JMF
2. Inspecting procedures
3. Conducting oversight of quality control inspection and records
4. Verification sampling and testing during production and paving

#### 39-4.04B Verification Sampling And Testing

##### General

The Engineer samples:

1. Aggregate to verify gradation
2. HMA to verify asphalt binder content

##### Verification

For aggregate gradation and asphalt binder content, the ratio of verification testing frequency to the minimum quality control testing frequency is 1:5. The Engineer performs at least 3 verification tests per lot.

Using the t-test, the Engineer compares quality control tests results for aggregate gradation and asphalt binder content with corresponding verification test results. The Engineer uses the average and standard deviation of up to 20 sequential sublots for the comparison. The Engineer uses production start-up evaluation tests to represent the first subplot. When there are less than 20 sequential sublots, the Engineer uses the maximum number of sequential sublots available. The 21st subplot becomes the 1st subplot ( $n = 1$ ) in the next lot.

The t-value for a group of test data is computed as follows:

$$t = \frac{|\bar{X}_c - \bar{X}_v|}{S_p \sqrt{\frac{1}{n_c} + \frac{1}{n_v}}} \quad \text{and} \quad S_p^2 = \frac{S_c^2(n_c - 1) + S_v^2(n_v - 1)}{n_c + n_v - 2}$$

where:

$n_c =$  Number of quality control tests (2 minimum, 20 maximum).

$n_v =$  Number of verification tests (minimum of 1 required).

$\bar{X}_c =$  Mean of quality control tests.

$\bar{X}_v =$  Mean of verification tests.

$S_p =$  Pooled standard deviation (When  $n_v = 1$ ,  $S_p = S_c$ ).

$S_c =$  Standard deviation of quality control tests.

$S_v =$  Standard deviation of verification tests (when  $n_v > 1$ ).

The comparison of quality control test results and the verification test results is at a level of significance of  $\alpha = 0.025$ . The Engineer computes t and compares it to the critical t-value,  $t_{crit}$ , from:

**Critical T-Value**

Degrees of freedom ( $n_c+n_v-2$ )	$t_{crit}$ (for $\alpha = 0.025$ )	Degrees of freedom ( $n_c+n_v-2$ )	$t_{crit}$ (for $\alpha = 0.025$ )
1	24.452	18	2.445
2	6.205	19	2.433
3	4.177	20	2.423
4	3.495	21	2.414
5	3.163	22	2.405
6	2.969	23	2.398
7	2.841	24	2.391
8	2.752	25	2.385
9	2.685	26	2.379
10	2.634	27	2.373
11	2.593	28	2.368
12	2.560	29	2.364
13	2.533	30	2.360
14	2.510	40	2.329
15	2.490	60	2.299
16	2.473	120	2.270
17	2.458	$\infty$	2.241

If the t-value computed is less than or equal to  $t_{crit}$ , quality control test results are verified.

If the t-value computed is greater than  $t_{crit}$  and both  $\bar{X}_v$  and  $\bar{X}_c$  comply with acceptance specifications, the quality control tests are verified. You may continue to produce and place HMA with the following allowable differences:

1.  $|\bar{X}_v - \bar{X}_c| \leq 1.0$  percent for any grading
2.  $|\bar{X}_v - \bar{X}_c| \leq 0.1$  percent for asphalt binder content

If the t-value computed is greater than  $t_{crit}$  and the  $|\bar{X}_v - \bar{X}_c|$  for grading and asphalt binder content are greater than the allowable differences, quality control test results are not verified and:

1. The Engineer notifies you in writing.
2. You and the Engineer must investigate why the difference exist.
3. If the reason for the difference cannot be found and corrected, the Engineer's test results are used for acceptance and pay.

**39-4.05 ENGINEER'S ACCEPTANCE**

**39-4.05A Testing**

The Engineer samples for acceptance testing and tests for:

**HMA Acceptance – QC / QA**

Index (i)	Quality Characteristic				Weight -ing Factor (w)	Test Method	HMA Type		
							A	B	RHMA-G
	Aggregate gradation <sup>a</sup>					CT 202	JMF ± Tolerance <sup>c</sup>		
	Sieve	19-mm	12.5-mm	9.5-mm					
1	12.5-mm	X <sup>b</sup>	--	--	0.05				
1	9.5-mm	--	X	--	0.05				
1	4.75-mm	--	--	X	0.05				
2	2.36-mm	X	X	X	0.10				
3	0.075-mm	X	X	X	0.15				
4	Asphalt binder content (%)				0.30	CT 379 or 382	JMF ± 0.45	JMF ± 0.45	JMF ± 0.5
5	Percent of maximum theoretical density (%) <sup>d, e</sup>				0.40	CT 375	92 – 96	92 – 96	91 – 96
	Sand equivalent (min.) <sup>f</sup>					CT 217	47	42	47
	Stabilometer value (min.) <sup>f, g</sup> 4.75-mm and 9.5-mm gradings 12.5-mm and 19-mm gradings					CT 366	30 37	30 35	-- 23
	Air voids content (%) <sup>f, h</sup>					CT 367	4 ± 2	4 ± 2	Specification ± 2
	Percent of crushed particles coarse aggregate (% min.) One fractured face Two fractured faces Fine aggregate (% min.) (Passing 4.75-mm sieve and retained on 2.36-mm sieve.) One fractured face					CT 205	90 70	25 --	-- 90
	HMA moisture content (% max.)					CT 226 or CT 370	1.0	1.0	1.0
	Los Angeles Rattler (% max.) Loss at 100 rev. Loss at 500 rev.					CT 211	12 45	-- 50	12 45
	Fine aggregate angularity (% min.)					AASHTO T 304, Method A	45	45	45
	Flat and elongated particle (% max. by mass @ 5:1)					ASTM D 4791	Report only	Report only	Report only
	Voids in mineral aggregate (% min.) <sup>i</sup> 4.75-mm grading 9.5-mm grading 12.5-mm grading 19-mm grading					LP-2	17.0 15.0 14.0 13.0	17.0 15.0 14.0 13.0	(Note j) -- -- 18.0 - 23.0 18.0 - 23.0
	Voids filled with asphalt (%) <sup>i</sup> 4.75-mm grading 9.5-mm grading 12.5-mm grading 19-mm grading					LP-3	76.0 - 80.0 73.0 - 76.0 65.0 - 75.0 65.0 - 75.0	76.0 - 80.0 73.0 - 76.0 65.0 - 75.0 65.0 - 75.0	Report only
	Dust proportion <sup>i</sup> 4.75-mm and 9.5-mm gradings 12.5-mm and 19-mm gradings					LP-4	0.9 - 2.0 0.6 - 1.3	0.9 - 2.0 0.6 - 1.3	Report only

	Smoothness		Section 39-1.12	3.66-m straight-edge, must-grind, and PI <sub>0</sub>	3.66-m straight-edge, must-grind, and PI <sub>0</sub>	3.66-m straight-edge, must-grind, and PI <sub>0</sub>
	Asphalt binder		Various	Section 92	Section 92	Section 92
	Asphalt rubber binder		Various	--	--	Section 92-1.02(C) and Section 39-1.02D
	Asphalt modifier		Various	--	--	Section 39-1.02D
	Crumb rubber modifier		Various	--	--	Section 39-1.02D

Notes:

<sup>a</sup> The Engineer determines combined aggregate gradations containing RAP under Laboratory Procedure LP-9.

<sup>b</sup> "X" denotes the sieves the Engineer considers for the specified aggregate gradation.

<sup>c</sup> The tolerances must comply with the allowable tolerances in Section 39-1.02E, "Aggregate."

<sup>d</sup> The Engineer determines percent of maximum theoretical density if the specified paved thickness is at least 45 mm under California Test 375 except the Engineer uses:

1. California Test 308, Method A, to determine in-place density of each density core instead of using the nuclear gauge in Part 4, "Determining In-Place Density By The Nuclear Density Device."
2. California Test 309 to determine maximum theoretical density instead of calculating test maximum density in Part 5, "Determining Test Maximum Density."

<sup>e</sup> The Engineer determines maximum theoretical density (California Test 309) at the frequency specified for Test Maximum Density under California Test 375, Part 5.D.

<sup>f</sup> The Engineer reports the average of 3 tests from a single split sample.

<sup>g</sup> Modify California Test 304, Part 2.B.2.c: "After compaction in the mechanical compactor, cool to 60 °C ± 3 °C by allowing the briquettes to cool at room temperature for 0.5 hour, then place the briquettes in the oven at 69 °C for a minimum of 2 hours and not more than 3 hours."

<sup>h</sup> The Engineer determines the bulk specific gravity of each lab-compacted briquette under California Test 308, Method A, and theoretical maximum specific gravity under California Test 309.

<sup>i</sup> Report only if the adjustment for asphalt binder content target value is less than or equal to ± 0.3 percent from OBC.

<sup>j</sup> Voids in mineral aggregate for RHMA-G must be within this range.

The Engineer determines the percent of maximum theoretical density from the average density of 3 density cores you take from every 750 tonnes of production or part thereof divided by the maximum theoretical density.

If the specified total paved thickness is at least 45 mm and any layer is less than 45 mm, the Engineer determines the percent of maximum theoretical density from density cores taken from the final layer measured the full depth of the total paved HMA thickness.

The Engineer stops production and terminates a lot if:

1. The lot's composite quality factor, Q<sub>FC</sub>, or an individual quality factor, Q<sub>FQCi</sub> for i = 3, 4, or 5, is below 0.90 determined under Section 39-4.03F, "Statistical Evaluation"
2. An individual quality factor, Q<sub>FQCi</sub> for i = 1 or 2, is below 0.75
3. Quality characteristics for which a quality factor, Q<sub>FQCi</sub>, is not determined has 2 consecutive acceptance or quality control tests not in compliance with the specifications

For any single quality characteristic for which a quality factor, Q<sub>FQCi</sub>, is not determined, except smoothness, if 2 consecutive acceptance test results do not comply with specifications:

1. Stop production.
2. Take corrective action.

3. In the Engineer's presence, take samples and split each sample into 4 parts. Test 1 part for compliance with the specifications and submit 3 parts to the Engineer. The Engineer tests 1 part for compliance with the specifications and reserves and stores 2 parts.
4. Demonstrate compliance with the specifications before resuming production and placement on the State highway.

### 39-4.05B Statistical Evaluation, Determination Of Quality Factors And Acceptance

#### Statistical Evaluation and Determination of Quality Factors

To determine the individual quality factor,  $QF_{QC_i}$ , for any quality factor  $i = 1$  through 5 or a lot's composite quality factor,  $QF_C$ , for acceptance and payment adjustment, the Engineer uses the evaluation specifications under Section 39-4.03F, "Statistical Evaluation," and:

1. Verified quality control test results for aggregate gradation
2. Verified quality control test results for asphalt binder content
3. The Engineer's test results for percent of maximum theoretical density

#### Lot Acceptance Based on Quality Factors

The Engineer accepts a lot based on the quality factors determined for aggregate gradation and asphalt binder content,  $QF_{QC_i}$  for  $i = 1$  through 4, using the total number of verified quality control test result values and the total percent defective ( $P_U + P_L$ ).

The Engineer accepts a lot based on the quality factor determined for maximum theoretical density,  $QF_{QC_5}$ , using the total number of test result values from density cores and the total percent defective ( $P_U + P_L$ ).

The Engineer calculates the quality factor for the lot,  $QF_C$ , which is a composite of weighted individual quality factors,  $QF_{QC_i}$ , determined for each quality characteristic in the HMA Acceptance – QC / QA table in Section 39-4.05A, "Testing."

The Engineer accepts a lot based on quality factors if:

1. The current composite quality factor,  $QF_C$ , is 0.90 or greater
2. Each individual quality factor,  $QF_{QC_i}$  for  $i = 3, 4,$  and  $5$ , is 0.90 or greater
3. Each individual quality factor,  $QF_{QC_i}$  for  $i = 1$  and  $2$ , is 0.75 or greater

No single quality characteristic test may represent more than the smaller of 750 tonnes or 1 day's production.

#### Payment Adjustment

If a lot is accepted, the Engineer adjusts payment with the following formula:

$$PA = \sum_{i=1}^n HMA CP * w_i * [QF_{QC_i} * (HMATT - WHMATT_i) + WHMATT_i] - (HMA CP * HMATT)$$

where:

$PA =$	Payment adjustment rounded to 2 decimal places.
$HMA CP =$	HMA contract price.
$HMATT =$	HMA total tonnes represented in the lot.
$WHMATT_i =$	Total tonnes of waived quality characteristic HMA.
$QF_{QC_i} =$	Running quality factor for the individual quality characteristic. $QF_{QC_i}$ for $i = 1$ through 4 must be from verified Contractor's QC results. $QF_{QC_5}$ must be determined from the Engineer's results on density cores taken for percent of maximum theoretical density determination.
$w =$	Weighting factor listed in the HMA acceptance table.
$i =$	Quality characteristic index number in the HMA acceptance table.

If the payment adjustment is a negative value, the Engineer deducts this amount from payment. If the payment adjustment is a positive value, the Engineer adds this amount to payment.

The 21st subplot becomes the 1st subplot ( $n = 1$ ) in the next lot. When the 21st sequential subplot becomes the 1st subplot, the previous 20 sequential sublots become a lot for which the Engineer determines a quality factor. The Engineer uses this quality factor to pay for the HMA in the lot. If the next lot consists of less than 8 sublots, these sublots must be added to the previous lot for quality factor determination using 21 to 27 sublots.

### **39-4.05C Dispute Resolution**

For a lot, if you or the Engineer dispute any quality factor,  $QF_{QCi}$ , or verification test result, every subplot in that lot must be retested.

Referee tests must be performed under the specifications for acceptance testing.

Any quality factor,  $QF_{QCi}$ , must be determined using the referee tests.

For any quality factor,  $QF_{QCi}$ , for  $i = 1$  through 5, dispute resolution:

1. If the difference between the quality factors for  $QF_{QCi}$  using the referee test result and the disputed test result is less than or equal to 0.01, the original test result is correct.
2. If the difference between the quality factor for  $QF_{QCi}$  using the referee test result and the disputed test result is more than 0.01, the quality factor determined from the referee tests supersedes the previously determined quality factor.

## **39-5 MEASUREMENT AND PAYMENT**

### **39-5.01 MEASUREMENT**

The contract item for HMA is measured by mass. The mass of each HMA mixture designated in the Engineer's Estimate must be the combined mixture mass.

If tack coat, asphalt binder, and asphaltic emulsion are paid with separate contract items, their contract items are measured under Section 92, "Asphalts," or Section 94, "Asphaltic Emulsions," as the case may be.

If recorded batch masses are printed automatically, the contract item for HMA is measured by using the printed batch masses, provided:

1. Total aggregate and supplemental fine aggregate mass per batch is printed. If supplemental fine aggregate is weighed cumulatively with the aggregate, the total aggregate batch mass must include the supplemental fine aggregate mass.
2. Total asphalt binder mass per batch is printed.
3. Each truckload's zero tolerance mass is printed before weighing the first batch and after weighing the last batch.
4. Time, date, mix number, load number and truck identification is correlated with a load slip.
5. A copy of the recorded batch mass is certified by a licensed weighmaster and submitted to the Engineer.

The contract item for placing HMA dike is measured by the meter along the completed length. The contract item for placing HMA in miscellaneous areas is measured as the in-place compacted area in square meters. In addition to the quantities measured on a meter or square meter basis, the HMA for dike and miscellaneous areas are measured by mass.

The contract item for geosynthetic pavement interlayer is measured by the square meter for the actual pavement area covered.

### **39-5.02 PAYMENT**

The contract prices paid per tonne for hot mix asphalt as designated in the Engineer's Estimate include full compensation for furnishing all labor, materials, tools, equipment, and incidentals for doing all the work involved in constructing hot mix asphalt, complete in place, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

If HMA is specified to comply with Section 39-4, "Quality Control / Quality Assurance," the Engineer adjusts payment under that section.

Full compensation for the Quality Control Plan and prepaving conference is included in the contract prices paid per tonne for hot mix asphalt as designated in the Engineer's Estimate and no additional compensation will be allowed therefor.

Full compensation for performing and submitting mix designs and for Contractor sampling, testing, inspection, testing facilities, and preparation and submittal of results is included in the contract prices paid per tonne for HMA as designated in the Engineer's Estimate and no additional compensation will be allowed therefor.

Full compensation for reclaimed asphalt pavement is included in the contract prices paid per tonne for HMA as designated in the Engineer's Estimate and no additional compensation will be allowed therefor.

The contract price paid per tonne for hot mix asphalt (leveling) includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals for doing all the work involved in hot mix asphalt (leveling), complete in place, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

The State will pay for HMA dike at the contract price per meter for place HMA dike and by the tonne for HMA. The contract prices paid per meter for place hot mix asphalt dike as designated in the Engineer's Estimate include full compensation for furnishing all labor, tools, equipment, and incidentals, and for doing all the work involved in placing HMA dike, complete in place, including excavation, backfill, and preparation of the area to receive the dike, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.





## SECTION 49 PILING

(Issued 06-06-08)

### **In Section 49-1.03 replace the 1st paragraph with:**

Foundation piles of any material shall be of such length as is required to obtain the specified penetration, and to extend into the cap or footing block as shown on the plans, or specified in the special provisions.

### **In Section 49-1.03 replace the 4th paragraph with:**

Modification to the specified installation methods and specified pile tip elevation will not be considered at locations where tension or lateral load demands control design pile tip elevations or when the plans state that specified pile tip elevation shall not be revised.

### **In Section 49-1.03 replace the 6th and 7th paragraphs with:**

Indicator compression pile load testing shall conform to the requirements in ASTM Designation: D 1143-81. The pile shall sustain the first compression test load applied which is equal to the nominal resistance in compression, as shown on the plans, with no more than 13 mm total vertical movement at the top of the pile measured relative to the top of the pile prior to the start of compression load testing.

Indicator tension pile load testing shall conform to the requirements in ASTM Designation: D 3689-90. The loading apparatus described as "Load Applied to Pile by Hydraulic Jack(s) Acting at One End of Test Beam(s) Anchored to the Pile" shall not be used. The pile shall sustain the first tension test load applied which is equal to the nominal resistance in tension, as shown on the plans, with no more than 13 mm total vertical movement at the top of the pile measured relative to the top of the pile prior to the start of tension load testing.

### **In Section 49-1.03 replace the 9th paragraph with:**

The Contractor shall furnish piling of sufficient length to obtain the specified tip elevation shown on the plans or specified in the special provisions.

### **In Section 49-1.03, delete the 10th paragraph**

### **In Section 49-1.04 replace the 4th, 5th, and 6th paragraphs with:**

Load test piles and anchor piles which are not to be incorporated in the completed structure shall be removed in conformance with the provisions in Section 15-4.02, "Removal Methods," and the remaining holes shall be backfilled with earth or other suitable material approved by the Engineer.

Load test anchorages in piles used as anchor piles shall conform to the following requirements:

- A. High strength threaded steel rods shall conform to the provisions for bars in Section 50-1.05, "Prestressing Steel," except Type II bars shall be used.
- B. High strength steel plates shall conform to the requirements in ASTM Designation: A 709/A 709M, Grade 345.
- C. Anchor nuts shall conform to the provisions in the second paragraph in Section 50-1.06, "Anchorages and Distribution."

The Contractor may use additional cementitious material in the concrete for the load test and anchor piles.

### **In Section 49-1.05 replace the 1st paragraph with:**

Driven piles shall be installed with impact hammers that are approved in writing by the Engineer. Impact hammers shall be steam, hydraulic, air or diesel hammers. Impact hammers shall develop sufficient energy to drive the piles at a penetration rate of not less than 3 mm per blow at the specified nominal resistance.

### **In Section 49-1.05 replace the 7th paragraph with:**

When necessary to obtain the specified penetration and when authorized by the Engineer, the Contractor may supply and operate one or more water jets and pumps, or furnish the necessary drilling apparatus and drill holes not greater than the least dimension of the pile to the proper depth and drive the piles therein. Jets shall not be used at locations where the stability of embankments or other improvements would be endangered. In addition, for steel piles, steel shells, or steel casings, when necessary to obtain the specified penetration or to prevent damage to the pile during installation, the Contractor shall provide special driving tips or heavier pile sections or take other measures as approved by the Engineer.

The use of followers or underwater hammers for driving piles will be permitted if authorized in writing by the Engineer. When a follower or underwater hammer is used, its efficiency shall be verified by furnishing the first pile in each bent or footing sufficiently long and driving the pile without the use of a follower or underwater hammer.

**In Section 49-1.07 replace the 2nd paragraph with:**

Timber piles shall be fresh-headed and square and when permitted by the Engineer, the heads of the piles may be protected by means of heavy steel or wrought iron rings. During driving operations timber piling shall be restrained from lateral movement at intervals not to exceed 6 m over the length between the driving head and the ground surface. During driving operations, the timber pile shall be kept moving by continuous operation of the hammer. When the blow count exceeds either 2 times the blow count required in 300 mm, or 3 times the blow count required in 75 mm for the nominal resistance as shown on the plans, computed in conformance with the provisions in Section 49-1.08, "Pile Driving Acceptance Criteria," additional aids shall be used to obtain the specified penetration. These aids may include the use of water jets or drilling, where permitted, or the use of a larger hammer employing a heavy ram striking with a low velocity.

**Replace Section 49-1.08 with:**

**49-1.08 PILE DRIVING ACCEPTANCE CRITERIA**

Except for piles to be load tested, driven piles shall be driven to a value of not less than the nominal resistance shown on the plans unless otherwise specified in the special provisions or permitted in writing by the Engineer. In addition, when a pile tip elevation is specified, driven piles shall penetrate at least to the specified tip elevation, unless otherwise permitted in writing by the Engineer. Piles to be load tested shall be driven to the specified tip elevation.

When the pile nominal resistance is omitted from the plans or the special provisions, timber piles shall be driven to a nominal resistance of 800 kN, and steel and concrete piles shall be driven to a nominal resistance of 1250 kN.

The nominal resistance for driven piles shall be determined from the following formula in which " $R_u$ " is the nominal resistance in kilonewtons, " $E_r$ " is the manufacturer's rating for joules of energy developed by the hammer at the observed field drop height, and " $N$ " is the number of hammer blows in the last 300 millimeters. (maximum value to be used for  $N$  is 100):

$$R_u = (7 * (E_r)^{1/2} * \log_{10} (0.83 * N)) - 550$$

**In Section 49-2.03 replace the 1st paragraph with:**

When preservative treatment of timber piles is required by the plans or specified in the special provisions, the treatment shall conform to the provisions in Section 58, "Preservative Treatment of Lumber, Timber and Piling," and the applicable AWWA Use Category.

**In Section 49-2.04 replace the 1st paragraph with:**

- A. An application of wood preservative conforming to the provisions in Section 58-1.04, "Wood Preservative for Manual Treatment," shall first be applied to the head of the pile and a protective cap shall then be built up by applying alternate layers of loosely woven fabric and hot asphalt or tar similar to membrane waterproofing, using 3 layers of asphalt or tar and 2 layers of fabric. The fabric shall measure at least 150 mm more in each direction than the diameter of the pile and shall be turned down over the pile and the edges secured by binding with 2 turns of No. 10 galvanized wire. The fabric shall be wired in advance of the application of the final layer of asphalt or tar, which shall extend down over the wiring.
- B. The sawed surface shall be covered with 3 applications of a hot mixture of 60 percent creosote and 40 percent roofing pitch, or thoroughly brushcoated with 3 applications of hot creosote and covered with hot roofing pitch. A covering of 3.50-mm nominal thickness galvanized steel sheet shall be placed over the coating and bent down over the sides of each pile to shed water.

**In Section 49-3.01 the 5th paragraph is deleted**

**In Section 49-3.01 replace the 6th and 7th paragraphs with:**

Except for precast prestressed concrete piles in a corrosive environment, lifting anchors used in precast prestressed concrete piles shall be removed, and the holes filled in conformance with the provisions in Section 51-1.18A, "Ordinary Surface Finish."

Lifting anchors used in precast prestressed concrete piles in a corrosive environment shall be removed to a depth of at least 25 mm below the surface of the concrete, and the resulting hole shall be filled with epoxy adhesive before the piles are delivered to the job site. The epoxy adhesive shall conform to the provisions in Sections 95-1, "General," and 95-2.01, "Binder (Adhesive), Epoxy Resin Base (State Specification 8040-03)."

**In Section 49-4.01 replace the 1st and 2nd paragraphs with:**

Cast-in-place concrete piles shall consist of one of the following:

- A. Steel shells driven permanently to the required nominal resistance and penetration and filled with concrete.
- B. Steel casings installed permanently to the required penetration and filled with concrete.
- C. Drilled holes filled with concrete.
- D. Rock sockets filled with concrete.

The drilling of holes shall conform to the provisions in these specifications. Concrete filling for cast-in-place concrete piles is designated by compressive strength and shall have a minimum 28-day compressive strength of 25 MPa. At the option of the Contractor, the combined aggregate grading for the concrete shall be either the 25-mm maximum grading, the 12.5-mm maximum grading, or the 9.5-mm maximum grading. Concrete shall conform to the provisions in Section 90, "Portland Cement Concrete," and Section 51, "Concrete Structures." Reinforcement shall conform to the provisions in Section 52, "Reinforcement."

**In Section 49-4.03 replace the 4th paragraph with:**

After placing reinforcement and prior to placing concrete in the drilled hole, if caving occurs or deteriorated foundation material accumulates on the bottom of the hole, the bottom of the drilled hole shall be cleaned. The Contractor shall verify that the bottom of the drilled hole is clean.

**In Section 49-4.04 replace the 1st and 2nd paragraphs with:**

Steel shells shall be sufficiently watertight to exclude water during the placing of concrete. The shells may be cylindrical or tapered, step-tapered, or a combination of either, with cylindrical sections.

**In Section 49-4.05 replace the 1st paragraph with:**

After being driven and prior to placing reinforcement and concrete therein, the steel shells shall be examined for collapse or reduced diameter at any point. Any shell which is improperly driven or broken or shows partial collapse to such an extent as to materially decrease its nominal resistance will be rejected. Rejected shells shall be removed and replaced, or a new shell shall be driven adjacent to the rejected shell. Rejected shells which cannot be removed shall be filled with concrete by the Contractor at the Contractor's expense. When a new shell is driven to replace a rejected shell, the Contractor, at the Contractor's expense, shall enlarge the footing as determined necessary by the Engineer.

**In Section 49-4.05 replace the 3rd paragraph with:**

Steel pipe piles shall conform to the following requirements:

1. Steel pipe piles less than 360 mm in diameter shall conform to the requirements in ASTM Designation: A 252, Grade 2 or 3.
2. Steel pipe piles 360 mm and greater in diameter shall conform to the requirements in ASTM Designation: A 252, Grade 3.
3. Steel pipe piles shall be of the nominal diameter and nominal wall thickness shown on the plans or specified in the special provisions.
4. The carbon equivalency (CE) of steel for steel pipe piles, as defined in AWS D 1.1, Section XI5.1, shall not exceed 0.45.
5. The sulfur content of steel for steel pipe piles shall not exceed 0.05-percent.



**In Section 50-1.02 delete the 8th paragraph.**

**Replace Section 50-1.05 with:**

**50-1.05 PRESTRESSING STEEL**

Prestressing steel shall be high-tensile wire conforming to the requirements in ASTM Designation: A 421, including Supplement I; high-tensile seven-wire strand conforming to the requirements in ASTM Designation: A 416; or uncoated high-strength steel bars conforming to the requirements in ASTM Designation: A 722, including all supplementary requirements. The maximum mass requirement of ASTM Designation: A 722 will not apply.

In addition to the requirements of ASTM Designation: A 722, for deformed bars, the reduction of area shall be determined from a bar from which the deformations have been removed. The bar shall be machined no more than necessary to remove the deformations over a length of 300 mm, and reduction will be based on the area of the machined portion.

In addition to the requirements specified herein, epoxy-coated seven-wire prestressing steel strand shall be grit impregnated and filled in conformance with the requirements in ASTM Designation: A 882/A 882M, including Supplement I, and the following:

- A. The film thickness of the coating after curing shall be 381  $\mu\text{m}$  to 1143  $\mu\text{m}$ .
- B. Prior to coating the strand, the Contractor shall furnish to the Transportation Laboratory a representative 230-g sample from each batch of epoxy coating material to be used. Each sample shall be packaged in an airtight container identified with the manufacturer's name and batch number.
- C. Prior to use of the epoxy-coated strand in the work, written certifications referenced in ASTM Designation: A 882/A 882M, including a representative load-elongation curve for each size and grade of strand to be used and a copy of the quality control tests performed by the manufacturer, shall be furnished to the Engineer.
- D. In addition to the requirements in Section 50-1.10, "Samples for Testing," four 1.5-m long samples of coated strand and one 1.5-m long sample of uncoated strand of each size and reel shall be furnished to the Engineer for testing. These samples, as selected by the Engineer, shall be representative of the material to be used in the work.
- E. Epoxy-coated strand shall be cut using an abrasive saw.
- F. All visible damage to coatings caused by shipping and handling, or during installation, including cut ends, shall be repaired in conformance with the requirements in ASTM Designation: A 882/A 882M. The patching material shall be furnished by the manufacturer of the epoxy powder and shall be applied in conformance with the manufacturer's written recommendations. The patching material shall be compatible with the original epoxy coating material and shall be inert in concrete.

All bars in any individual member shall be of the same grade, unless otherwise permitted by the Engineer.

When bars are to be extended by the use of couplers, the assembled units shall have a tensile strength of not less than the manufacturer's minimum guaranteed ultimate tensile strength of the bars. Failure of any one sample to meet this requirement will be cause for rejection of the heat of bars and lot of couplers. The location of couplers in the member shall be subject to approval by the Engineer.

Wires shall be straightened if necessary to produce equal stress in all wires or wire groups or parallel lay cables that are to be stressed simultaneously or when necessary to ensure proper positioning in the ducts.

Where wires are to be button-headed, the buttons shall be cold formed symmetrically about the axes of the wires. The buttons shall develop the minimum guaranteed ultimate tensile strength of the wire. No cold forming process shall be used that causes indentations in the wire. Buttonheads shall not contain wide open splits, more than 2 splits per head, or splits not parallel with the axis of the wire.

Prestressing steel shall be protected against physical damage and rust or other results of corrosion at all times from manufacture to grouting or encasing in concrete. Prestressing steel that has sustained physical damage at any time shall be rejected. The development of visible rust or other results of corrosion shall be cause for rejection, when ordered by the Engineer.

Epoxy-coated prestressing steel strand shall be covered with an opaque polyethylene sheeting or other suitable protective material to protect the strand from exposure to sunlight, salt spray, and weather. For stacked coils, the protective covering shall be draped around the perimeter of the stack. The covering shall be adequately secured; however, it should allow for air circulation around the strand to prevent condensation under the covering. Epoxy-coated strand shall not be stored within 300 m of ocean or tidal water for more than 2 months.

Prestressing steel shall be packaged in containers or shipping forms for the protection of the steel against physical damage and corrosion during shipping and storage. Except for epoxy-coated strand, a corrosion inhibitor which prevents rust or other results of corrosion, shall be placed in the package or form, or shall be incorporated in a corrosion inhibitor carrier type packaging material, or when permitted by the Engineer, may be applied directly to the steel. The corrosion inhibitor

shall have no deleterious effect on the steel or concrete or bond strength of steel to concrete. Packaging or forms damaged from any cause shall be immediately replaced or restored to original condition.

The shipping package or form shall be clearly marked with a statement that the package contains high-strength prestressing steel, and the type of corrosion inhibitor used, including the date packaged.

Prestressing steel for post-tensioning which is installed in members prior to placing and curing of the concrete, and which is not epoxy-coated, shall be continuously protected against rust or other results of corrosion, until grouted, by means of a corrosion inhibitor placed in the ducts or applied to the steel in the duct. The corrosion inhibitor shall conform to the provisions specified herein.

When steam curing is used, prestressing steel for post-tensioning shall not be installed until the steam curing is completed.

Water used for flushing ducts shall contain either quick lime (calcium oxide) or slaked lime (calcium hydroxide) in the amount of 0.01-kg/L. Compressed air used to blow out ducts shall be oil free.

When prestressing steel for post-tensioning is installed in the ducts after completion of concrete curing, and if stressing and grouting are completed within 10 days after the installation of the prestressing steel, rust which may form during those 10 days will not be cause for rejection of the steel. Prestressing steel installed, tensioned, and grouted in this manner, all within 10 days, will not require the use of a corrosion inhibitor in the duct following installation of the prestressing steel. Prestressing steel installed as above but not grouted within 10 days shall be subject to all the requirements in this section pertaining to corrosion protection and rejection because of rust. The requirements in this section pertaining to tensioning and grouting within 10 days shall not apply to epoxy-coated prestressing steel strand.

Any time prestressing steel for pretensioning is placed in the stressing bed and is exposed to the elements for more than 36 hours prior to encasement in concrete, adequate measures shall be taken by the Contractor, as approved by the Engineer, to protect the steel from contamination or corrosion.

After final fabrication of the seven-wire prestressing steel strand, no electric welding of any form shall be performed on the prestressing steel. Whenever electric welding is performed on or near members containing prestressing steel, the welding ground shall be attached directly to the steel being welded.

Pretensioned prestressing steel shall be cut off flush with the end of the member. For epoxy-coated prestressing steel, only abrasive saws shall be used to cut the steel. The exposed ends of the prestressing steel and a 25-mm strip of adjoining concrete shall be cleaned and painted. Cleaning shall be by wire brushing or abrasive blast cleaning to remove all dirt and residue on the metal or concrete surfaces. Immediately after cleaning, the surfaces shall be covered with one application of unthinned zinc-rich primer (organic vehicle type) conforming to the provisions in Section 91, "Paint," except that 2 applications shall be applied to surfaces which will not be covered by concrete or mortar. Aerosol cans shall not be used. The paint shall be thoroughly mixed at the time of application and shall be worked into any voids in the prestressing tendons.

**In Section 50-1.07 replace the 2nd paragraph with:**

Ducts shall be fabricated with either welded or interlocked seams. Galvanizing of the welded seam will not be required. Ducts shall have sufficient strength to maintain their correct alignment during placing of concrete. Joints between sections of duct shall be positive metallic connections which do not result in angle changes at the joints. Waterproof tape shall be used at the connections. Ducts shall be bent without crimping or flattening. Transition couplings connecting the ducts to anchoring devices shall be either ferrous metal or polyolefin. Ferrous metal transition couplings need not be galvanized.

**In Section 50-1.07 replace the 7th paragraph with:**

All ducts with a total length of 120 m or more shall be vented. Vents shall be placed at intervals of not more than 120 m and shall be located within 2 m of every high point in the duct profile. Vents shall be 12 mm minimum diameter standard pipe or suitable plastic pipe. Connections to ducts shall be made with metallic or plastic structural fasteners. Plastic components, if selected, shall not react with the concrete or enhance corrosion of the prestressing steel and shall be free of water soluble chlorides. The vents shall be mortar tight, taped as necessary, and shall provide means for injection of grout through the vents and for sealing the vents. Ends of vents shall be removed 25 mm below the roadway surface after grouting has been completed.

**In Section 50-1.08 replace the 6th paragraph with:**

The following formula and friction coefficients shall be used in calculating friction losses in tendons:

$$T_o = T_x e^{(\mu\alpha + KL)}$$

Where:

$T_o$  = steel stress at jacking end  
 $T_x$  = steel stress at any point  $x$   
 $e$  = base of Naperian logarithms  
 $\mu$  = friction curvature coefficient  
 $\alpha$  = total angular change of prestressing steel profile in radians from jacking end to point  $x$   
 $K$  = friction wobble coefficient (=0.00066/m)  
 $L$  = length of prestressing steel from jacking end to point  $x$

Type of Steel Tendon	Length of Tendon L(m)	Type of Duct	$\mu$
Wire or Strand	0 to less than 183	Rigid or semi-rigid galvanized sheet metal	0.15
	183 to less than 275		0.20
	275 to less than 366		0.25
	Greater than or equal to 366		0.25*
Wire or Strand	All	Plastic	0.23
	All	Rigid Steel Pipes	0.25*
High Strength Bar	All	Rigid or semi-rigid galvanized sheet metal	0.30

\* With the use of lubrication

**In Section 50-1.08 in the 11th paragraph, replace item 2 with:**

2. When the concrete is designated by class or cementitious material content, either the concrete compressive strength shall have reached the strength shown on the plans at the time of stressing or at least 28 days shall have elapsed since the last concrete to be prestressed has been placed, whichever occurs first.

**In Section 50-1.08 replace the 13th and 14th paragraphs with:**

Prestressing steel in pretensioned members shall not be cut or released until the concrete in the member has attained a compressive strength of not less than the value shown on the plans or 28 MPa, whichever is greater. In addition to these concrete strength requirements, when epoxy-coated prestressing steel strand is used, the steel shall not be cut or released until the temperature of the concrete surrounding the strand is less than 65°C, and falling.

When ordered by the Engineer, prestressing steel strands in pretensioned members, if tensioned individually, shall be checked by the Contractor for loss of prestress not more than 48 hours prior to placing concrete for the members. The method and equipment for checking the loss of prestress shall be subject to approval by the Engineer. Strands which show a loss of prestress in excess of 3 percent shall be retensioned to the original computed jacking stress.

**In Section 50-1.09 replace the 2nd and 3rd paragraphs with:**

Grout shall consist of cement and water and may contain an admixture if approved by the Engineer. Cement shall conform to the provisions in Section 90-2.01A, "Cement."

**In Section 50-1.10 replace the 5th paragraph with:**

The following samples of materials and tendons, selected by the Engineer from the prestressing steel at the plant or jobsite, shall be furnished by the Contractor to the Engineer well in advance of anticipated use:

- A. For wire or bars, one 2-m long sample and for strand, one 1.5-m long sample, of each size shall be furnished for each heat or reel.
- B. For epoxy-coated strand, one 1.5-m long sample of uncoated strand of each size shall be furnished for each reel.



less than the review time specified above for that plan, plus 2 weeks for each plan of higher priority which is still under review. A falsework plan submittal shall consist of plans for a single bridge or portion thereof. For multi-frame bridges, each frame shall require a separate falsework plan submittal.

**In Section 51-1.06A, add:**

If structural composite lumber is proposed for use, the falsework drawings shall clearly identify the structural composite lumber members by grade (E value), species, and type. The Contractor shall provide technical data from the manufacturer showing the tabulated working stress values of the composite lumber. The Contractor shall furnish a certificate of compliance as specified in Section 6-1.07, "Certificates of Compliance," for each delivery of structural composite lumber to the project site.

For falsework piles with a calculated loading capacity greater than 900 kN, the falsework piles shall be designed by an engineer who is registered as either a Civil Engineer or a Geotechnical Engineer in the State of California, and the calculations shall be submitted to the Engineer.

**In Section 51-1.06A(1) replace the 1st paragraph with:**

The design load for falsework shall consist of the sum of dead and live vertical loads, and an assumed horizontal load. The minimum total design load for any falsework, including members that support walkways, shall be not less than 4800 N/m<sup>2</sup> for the combined live and dead load regardless of slab thickness.

**In Section 51-1.06A(1) replace the 8th paragraph with:**

In addition to the minimum requirements specified in this Section 51-1.06A, falsework for box girder structures with internal falsework bracing systems using flexible members capable of withstanding tensile forces only, shall be designed to include the vertical effects caused by the elongation of the flexible member and the design horizontal load combined with the dead and live loads imposed by concrete placement for the girder stems and connected bottom slabs. Falsework comprised of individual steel towers with bracing systems using flexible members capable of withstanding tensile forces only to resist overturning, shall be exempt from these additional requirements.

**In Section 51-1.06B replace the 3rd paragraph with:**

When falsework is supported on piles, the piles shall be driven and the actual nominal resistance assessed in conformance with the provisions in Section 49, "Piling."

**In Section 51-1.06B, add:**

For falsework piles with a calculated nominal resistance greater than 1800 kN, the Contractor shall conduct dynamic monitoring of pile driving and generate field acceptance criteria based on a wave equation analysis. These analyses shall be signed by an engineer who is registered as a Civil Engineer in the State of California and submitted to the Engineer prior to completion of falsework erection.

Prior to the placement of falsework members above the stringers, the final bracing system for the falsework shall be installed.

**In Section 51-1.06C, add:**

The falsework removal operation shall be conducted in such a manner that any portion of the falsework not yet removed remains in a stable condition at all times.

**In Section 51-1.09 replace the 6th paragraph with:**

Vibrators used to consolidate concrete containing epoxy-coated bar reinforcement or epoxy-coated prestressing steel shall have a resilient covering to prevent damage to the epoxy-coating on the reinforcement or prestressing steel.

**In Section 51-1.11 replace the 6th paragraph with:**

Construction methods and equipment employed by the Contractor shall conform to the provisions in Section 7-1.02, "Load Limitations."

**In Section 51-1.12D replace the 4th paragraph with:**

Expanded polystyrene shall be a commercially available polystyrene board. Expanded polystyrene shall have a minimum flexural strength of 240 kPa determined in conformance with the requirements in ASTM Designation: C 203 and a compressive yield strength of between 110 and 275 kPa at 5 percent compression. Surfaces of expanded polystyrene against which concrete is placed shall be faced with hardboard. Hardboard shall be 3 mm minimum thickness, conforming to ANSI A135.4, any class. Other facing materials may be used provided they furnish equivalent protection. Boards shall be held in place by nails, waterproof adhesive, or other means approved by the Engineer.

**In Section 51-1.12F, add:**

The opening of the joints at the time of placing shall be that shown on the plans adjusted for temperature. Care shall be taken to avoid impairment of the clearance in any manner.

**In Section 51-1.12F replace the 1st and 2nd paragraphs with:**

Where shown on the plans, joints in structures shall be sealed with joint seals, joint seal assemblies, or seismic joints in conformance with the details shown on the plans, the provisions in these specifications, and the special provisions.

Type A and AL joint seals shall consist of a groove in the concrete that is filled with field-mixed silicone sealant.

**In Section 51-1.12F replace the 4th and 5th paragraphs with:**

Joint seal assemblies and seismic joints shall consist of metal or metal and elastomeric assemblies which are anchored or cast into a recess in the concrete over the joint. Strip seal joint seal assemblies consist of only one joint cell. Modular unit joint seal assemblies consist of more than one joint cell.

The Movement Rating (MR) shall be measured normal to the longitudinal axis of the joint. The type of seal to be used for the MR shown on the plans shall be as follows:

Movement Rating (MR)	Seal Type
MR ≤ 25 mm	Type A or Type B
25 mm < MR ≤ 50 mm	Type B
50 mm < MR ≤ 100 mm	Joint Seal Assembly (Strip Seal)
MR > 100 mm	Joint Seal Assembly (Modular Unit) or Seismic Joint

**In Section 51-1.12F(3)(a) replace the 1st and 2nd paragraphs with:**

The sealant must consist of a 2-component silicone sealant that will withstand up to ±50 percent movement. Silicone sealants must be tested under California Test 435 and must comply with the following:

Specification	Requirement
Modulus at 150 percent elongation	35–520 kPa
Recovery	17 mm max.
Notch Test	Notched or loss of bond 6 mm, max.
Water Resistance	Notched or loss of bond 6 mm, max.
Ultraviolet Exposure ASTM Designation: G 154, Table X2.1, Cycle 2.	No more than slight checking or cracking.
Cone Penetration	4.5-12.0 mm

**In Section 51-1.12F(3)(a) delete the 3rd and 8th paragraphs.**

**In Section 51-1.12F(3)(a) replace the 10th paragraph with:**

A Certificate of Compliance accompanied by a certified test report must be furnished for each batch of silicone sealant in conformance with the provisions in Section 6-1.07, "Certificates of Compliance."

**In Section 51-1.12F(3)(b) replace the 2nd paragraph with:**

The preformed elastomeric joint seal must conform to the requirements in ASTM D 2628 and the following:

1. The seal must consist of a multichannel, nonporous, homogeneous material furnished in a finished extruded form.
2. The minimum depth of the seal measured at the contact surface must be at least 95 percent of the minimum uncompressed width of the seal as designated by the manufacturer.
3. When tested in conformance with the requirements in California Test 673 for Type B seals, joint seals must provide a movement rating (MR) of not less than that shown on the plans.
4. The top and bottom edges of the joint seal must maintain continuous contact with the sides of the groove over the entire range of joint movement.
5. The seal must be furnished full length for each joint with no more than 1 shop splice in any 18 m length of seal.
6. The Contractor must demonstrate the adequacy of the procedures to be used in the work before installing seals in the joints.
7. One field splice per joint may be made at locations and by methods approved by the Engineer. The seals are to be manufactured full length for the intended joint, then cut at the approved splice section and rematched before splicing. The Contractor must submit splicing details prepared by the joint seal manufacturer for approval before beginning splicing work.
8. Shop splices and field splices must have no visible offset of exterior surfaces and must show no evidence of bond failure.
9. At all open ends of the seal that would admit water or debris, each cell must be filled to a depth of 80 mm with commercial quality open cell polyurethane foam or closed by other means subject to approval by the Engineer.

**In Section 51-1.12F(3)(b) replace the 7th paragraph with:**

The joint seal must be installed full length for each joint with equipment that does not twist or distort the seal, elongate the seal longitudinally, or otherwise cause damage to the seal or to the concrete forming the groove.

**Replace Section 51-1.12F(3)(c), with:**

**(c) Joint Seal Assemblies and Seismic Joints**

Joint seal assemblies and seismic joints shall be furnished and installed in joints in bridge decks as shown on the plans and as specified in the special provisions.

**In Section 51-1.12H(1) replace the 8th paragraph with:**

The elastomer, as determined from test specimens, shall conform to the following:

Test	ASTM Designation	Requirement
Tensile strength, MPa	D 412	15.5 Min.
Elongation at break, percent	D 412	350 Min.
Compression set, 22 h at 70°C, percent	D 395 (Method B)	25 Max.
Tear strength, kN/m	D 624 (Die C)	31.5 Min.
Hardness (Type A)	D 2240 with 2 kg. mass	55 ±5
Ozone resistance 20% strain, 100 h at 40°C ±2°C	D 1149 (except 100 ±20 parts per 100 000 000)	No cracks
Instantaneous thermal stiffening at -40°C	D 1043	Shall not exceed 4 times the stiffness measured at 23°C
Low temperature brittleness at -40°C	D 746 (Procedure B)	Pass

**In Section 51-1.12H(1) in the 9th paragraph replace the table, with:**

Tensile strength, percent	-15
Elongation at break, percent	-40; but not less than 300% total elongation of the material
Hardness, points	+10

**In Section 51-1.12H(2) replace the 1st paragraph with:**

Steel reinforced elastomeric bearings shall conform to the requirements for steel-laminated elastomeric bearings in ASTM Designation: D 4014 and the following:

- A. The bearings shall consist of alternating steel laminates and internal elastomer laminates with top and bottom elastomer covers. Steel laminates shall have a nominal thickness of 1.9 mm (14 gage). Internal elastomer laminates shall have a thickness of 12 mm, and top and bottom elastomer covers shall each have a thickness of 6 mm. The combined thickness of internal elastomer laminates and top and bottom elastomer covers shall be equal to the bearing pad thickness shown on the plans. The elastomer cover to the steel laminates at the sides of the bearing shall be 3 mm. If guide pins or other devices are used to control the side cover over the steel laminates, any exposed portions of the steel laminates shall be sealed by vulcanized patching. The length, width, or diameter of the bearings shall be as shown on the plans.
- B. The total thickness of the bearings shall be equal to the thickness of elastomer laminates and covers plus the thickness of the steel laminates.
- C. Elastomer for steel reinforced elastomeric bearings shall conform to the provisions for elastomer in Section 51-1.12H(1), "Plain and Fabric Reinforced Elastomeric Bearing Pads."
- D. A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," shall be furnished to the Engineer certifying that the bearings to be furnished conform to all of the above provisions. The Certificate of Compliance shall be supported by a certified copy of the results of tests performed by the manufacturer on the bearings.
- E. One sample bearing shall be furnished to the Engineer from each lot of bearings to be furnished for the contract. Samples shall be available at least 3 weeks in advance of intended use. The sample bearing shall be one of the following:

Bearing Pad Thickness as Shown on the Plans	Sample Bearing
≤ 50 mm	Smallest complete bearing shown on the plans
> 50 mm	* 57 ± 3 mm thick sample not less than 200 mm x 305 mm in plan and cut by the manufacturer from the center of one of the thickest complete bearings

\* The sample bearing plus remnant parts of the complete bearing shall be furnished to the Engineer.

- F. A test specimen taken from the sample furnished to the Engineer will be tested in conformance with the requirements in California Test 663. Specimens tested shall show no indication of loss of bond between the elastomer and steel laminates.

**In Section 51-1.135 replace the 1st paragraph with:**

Mortar shall be composed of cementitious material, sand, and water proportioned and mixed as specified in this Section 51-1.135.

**In Section 51-1.135 replace the 3rd paragraph with:**

The proportion of cementitious material to sand, measured by volume, shall be 1:2 unless otherwise specified.

**In Section 51-1.14 replace the 4th paragraph with:**

Neoprene shall be manufactured from a vulcanized elastomeric compound containing neoprene as the sole elastomer and shall conform to the following:

Test	ASTM Designation	Requirement
Tensile strength, MPa	D 412	13.8 Min.
Elongation at break, percent	D 412	300 Min.
Compression set, 22 h at 70°C, percent	D 395 (Method B)	30 Max.
Tear strength, kN/m	D 624 (Die C)	26.3 Min.
Hardness (Type A)	D 2240	55±5
Ozone resistance 20% strain, 100 h at 38°C ±1°C	D 1149 (except 100±20 parts per 100 000 000)	No cracks
Low temperature brittleness at -40°C	D 746 (Procedure B)	Pass
Flame resistance	C 542	Must not propagate flame
Oil Swell, ASTM Oil #3, 70 h at 100°C, volume change, percent	D 471	80 Max.
Water absorption, immersed 7 days at 70°C, change in mass, percent	D 471	15 Max.

**In Section 51-1.17 in 4th paragraph, replace the 1st sentence with:**

The smoothness of completed roadway surfaces of structures, approach slabs and the adjacent 15 m of approach pavement, and the top surfaces of concrete decks which are to be covered with another material, will be tested by the Engineer with a bridge profilograph in conformance with the requirements in California Test 547 and the requirements herein.

**In Section 51-1.17 delete the 7th paragraph**

**In Section 51-1.17 delete the 13th paragraph**

**In Section 51-1.17 delete the 14th paragraph**

**Add Section:**

**51-1.17A DECK CRACK TREATMENT**

The Contractor shall use all means necessary to minimize the development of shrinkage cracks.

The Contractor shall remove all equipment and materials from the deck and clean the surface as necessary for the Engineer to measure the surface crack intensity. Surface crack intensity will be determined by the Engineer after completion of concrete cure, before prestressing, and before the release of falsework. In any 50 square meter portion of deck within the limits of the new concrete deck, should the intensity of cracking be such that there are more than 5 m of cracks whose width at any location exceeds 0.5 mm, the deck shall be treated with methacrylate resin. The area of deck to be treated shall have a width that extends for the entire width of new deck inside the concrete barriers and a length that extends at least 1.5 m beyond the furthest single continuous crack outside the 50 square meter portion, measured from where that crack exceeds 0.5 mm in width, as determined by the Engineer.

Deck crack treatment shall include furnishing, testing, and application of methacrylate resin and sand. If grinding is required, deck treatment shall take place before grinding.

**51-1.17A(1) Submittals**

Before starting deck treatment, the Contractor shall submit plans in conformance with Section 5-1.02, "Plans and Working Drawings," for the following:

1. Public safety plan for the use of methacrylate resin
2. Placement plan for the construction operation

The plans shall identify materials, equipment, and methods to be used.  
 The public safety plan for the use of methacrylate resin shall include details for the following:

1. Shipping
2. Storage
3. Handling
4. Disposal of residual methacrylate resin and the containers

The placement plan for construction shall include the following:

1. Schedule of deck treatment for each bridge. The schedule shall be consistent with "Maintaining Traffic," of the special provisions and shall include time for the Engineer to perform California Test 342.
2. Methods and materials to be used, including the following:
  - 2.1. Description of equipment for applying the resin
  - 2.2. Description of equipment for applying the sand
  - 2.3. Gel time range and final cure time for the resin

If the measures proposed in the safety plan are inadequate to provide for public safety associated with the use of methacrylate resin, the Engineer will reject the plan and direct the Contractor to revise the plan. Directions for revisions will be in writing and include detailed comments. The Engineer will notify the Contractor of the approval or rejection of a submitted or revised plan within 15 days of receipt of that plan.

In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays."

**51-1.17A(2) Materials**

Before using methacrylate resin, a Material Safety Data Sheet shall be submitted for each shipment of resin.

Methacrylate resin shall be low odor and have a high molecular weight. Before adding initiator, the resin shall have a maximum volatile content of 30 percent when tested in conformance with the requirements in ASTM Designation: D 2369, and shall conform to the following:

PROPERTY	REQUIREMENT	TEST METHOD
* Viscosity	0.025 Pa·s, maximum, (Brookfield RVT with UL adaptor, 50 RPM at 25°C	ASTM D 2196
* Specific Gravity	0.90 minimum, at 25°C	ASTM D 1475
* Flash Point	82°C, minimum	ASTM D 3278
* Vapor Pressure	1.0 mm Hg, maximum, at 25°C	ASTM D 323
Tack-free Time	400 minutes, maximum, at 25°C	Specimen prepared per California Test 551
PCC Saturated Surface-Dry Bond Strength	3.5 MPa, minimum at 24 hours and 21±1°C	California Test 551
* Test shall be performed before adding initiator.		

**51-1.17A(3) Testing**

The Contractor shall allow 20 days for sampling and testing by the Engineer of the methacrylate resin before proposed use. If bulk resin is to be used, the Contractor shall notify the Engineer in writing at least 15 days before the delivery of the bulk resin to the job site. Bulk resin is any resin stored in containers in excess of 209 liters.

Before starting production treatment, the Contractor shall treat a test area of approximately 50 square meters that is within the project limits and at a location approved by the Engineer. When available the test area shall be outside of the traveled way. Weather and pavement conditions during the test treatment shall be similar to those expected on the deck. Equipment used for testing shall be similar to those used for deck treating operations.

During test and production deck treatment, test tiles shall be used to evaluate the resin cure time. The Contractor shall coat at least one 102 mm x 102 mm commercial quality smooth glazed tile for each batch of methacrylate resin. The coated tile shall be placed adjacent to the corresponding treated area. Sand shall not be applied to the test tiles.

The acceptance criteria for a treated area is as follows:

1. The test tiles are dry to the touch.
2. The treated deck surface is tack free (non-oily).
3. The sand cover adheres and resists brushing by hand.
4. Excess sand has been removed by vacuuming or sweeping.
5. The coefficient of friction is at least 0.35 when tested in conformance with California Test 342.

If a test or production area fails to meet the acceptance criteria, as determined by the Engineer, the treatment will be rejected, and the treatment shall be removed and replaced until the area complies with the acceptance criteria.

#### **51-1.17A(4) Construction**

Equipment shall be fitted with suitable traps, filters, drip pans, or other devices as necessary to prevent oil or other deleterious material from being deposited on the deck.

Before deck treatment with methacrylate resin, the bridge deck surface shall be cleaned by abrasive blasting, and all loose material shall be blown from visible cracks using high-pressure air. Concrete curing seals shall be cleaned from the deck surface to be treated, and the deck shall be dry when blast cleaning is performed. If the deck surface becomes contaminated at any time before placing the resin, the deck surface shall be cleaned by abrasive blasting.

Where abrasive blasting is being performed within 3 m of a lane occupied by public traffic, the residue including dust shall be removed immediately after contact between the abrasive and the surface being treated. The removal shall be by a vacuum attachment operating concurrently with the abrasive blasting operation.

A compatible promoter/initiator system shall be capable of providing the resin gel time range shown on the placement plan. Gel time shall be adjusted to compensate for the changes in temperature throughout treatment application.

Resin shall be applied by machine and by using a two-part resin system with a promoted resin for one part and an initiated resin for the other part. This two-part resin system shall be combined at equal volumes to the spray bars through separate positive displacement pumps. Combining of the 2 components shall be by either static in-line mixers or by external intersecting spray fans. The pump pressure at the spray bars shall not be great enough to cause appreciable atomization of the resin. Compressed air shall not be used to produce the spray. A shroud shall be used to enclose the spray bar apparatus.

At the Contractor's option, manual application may be used. For manual application, (1) the quantity of resin mixed with promoter and initiator shall be limited to 20 L at a time, and (2) the resin shall be distributed by squeegees and brooms within 10 minutes after application.

The Contractor shall apply methacrylate resin only to the specified area. Barriers, railing, joints, and drainage facilities shall be adequately protected to prevent contamination by the treatment material. Contaminated items shall be repaired at the Contractor's expense.

The relative humidity shall be less than 90 percent at the time of treatment. The prepared area shall be dry and the surface temperature shall be at least 10°C, and not more than 38°C when the resin is applied. The rate of application of promoted/initiated resin shall be 2.2 square meter per liter; the exact rate shall be determined by the Engineer.

The deck surfaces to be treated shall be completely covered with resin so the resin penetrates and fills all cracks. The resin shall be applied within 5 minutes after complete mixing. A significant increase in viscosity shall be cause for rejection. Excess material shall be redistributed by squeegees or brooms within 10 minutes after application. For textured deck surfaces, including grooved surfaces, excess material shall be removed from the texture indentations.

After the resin has been applied, at least 20 minutes shall elapse before applying sand. The sand shall be commercial quality dry blast sand. At least 95 percent of the sand shall pass the 2.36-mm sieve and at least 95 percent shall be retained on the 850-µm sieve. The sand shall be applied at a rate of approximately one kilogram per square meter or until refusal as determined by the Engineer.

Traffic will not be allowed on treated areas until the acceptance criteria has been met as determined by the Engineer.

#### **In Section 51-1.18C replace the 2nd paragraph with:**

When Class 2 surface finish (gun finish) is specified, ordinary surface finish shall first be completed. The concrete surfaces shall then be abrasive blasted to a rough texture and thoroughly washed down with water. While the washed surfaces are damp, but not wet, a finish coating of machine applied mortar, approximately 6 mm thick, shall be applied in not



**In Section 52-1.07 in the 3rd paragraph, delete item C**

**In Section 52-1.07 replace the 11th paragraph with:**

Attention is directed to the provisions in Section 7-1.09, "Public Safety." Whenever a portion of an assemblage of bar reinforcing steel that is not encased in concrete exceeds 6 m in height, the Contractor shall submit to the Engineer for approval, in accordance with the provisions in Section 5-1.02, "Plans and Working Drawings," working drawings and design calculations for the temporary support system to be used. The working drawings and design calculations shall be signed by an engineer who is registered as a Civil Engineer in the State of California. The temporary support system shall be designed to resist all expected loads and shall be adequate to prevent collapse or overturning of the assemblage. If the installation of forms or other work requires revisions to or temporary release of any portion of the temporary support system, the working drawings shall show the support system to be used during each phase of construction. The minimum horizontal wind load to be applied to the bar reinforcing steel assemblage, or to a combined assemblage of reinforcing steel and forms, shall be the sum of the products of the wind impact area and the applicable wind pressure value for each height zone. The wind impact area is the total projected area of the cage normal to the direction of the applied wind. Wind pressure values shall be determined from the following table:

Height Zone (Meters above ground)	Wind Pressure Value (Pa)
0-9.0	960
9.1-15.0	1200
15.1-30.0	1440
Over 30	1675

**Replace Section 52-1.08 with:**

#### **52-1.08 SPLICING**

Splices of reinforcing bars shall consist of lap splices, service splices, or ultimate butt splices.

Splicing of reinforcing bars will not be permitted at a location designated on the plans as a "No-Splice Zone." At the option of the Contractor, reinforcing bars may be continuous at locations where splices are shown on the plans. The location of splices, except where shown on the plans, shall be determined by the Contractor using available commercial lengths where practicable.

Unless otherwise shown on the plans, splices in adjacent reinforcing bars at any particular section shall be staggered. The minimum distance between staggered lap splices or mechanical lap splices shall be the same as the length required for a lap splice in the largest bar. The minimum distance between staggered butt splices shall be 600 mm, measured between the midpoints of the splices along a line which is centered between the axes of the adjacent bars.

#### **52-1.08A Lap Splicing Requirements**

Splices made by lapping shall consist of placing reinforcing bars in contact and wiring them together, maintaining the alignment of the bars and the minimum clearances. Should the Contractor elect to use a butt welded or mechanical splice at a location not designated on the plans as requiring a service or ultimate butt splice, this splice shall conform to the testing requirements for service splice.

Reinforcing bars shall not be spliced by lapping at locations where the concrete section is not sufficient to provide a minimum clear distance of 50 mm between the splice and the nearest adjacent bar. The clearance to the surface of the concrete specified in Section 52-1.07, "Placing," shall not be reduced.

Reinforcing bars Nos. 43 and 57 shall not be spliced by lapping.

Where ASTM Designations: A 615/A 615M, Grade 420 or A 706/A 706M reinforcing bars are required, the length of lap splices shall be as follows: Reinforcing bars No. 25 or smaller shall be lapped at least 45 diameters of the smaller bar joined; and reinforcing bars Nos. 29, 32, and 36 shall be lapped at least 60 diameters of the smaller bar joined, except when otherwise shown on the plans.

Where ASTM Designation: A 615/A 615M, Grade 280 reinforcing bars are permitted, the length of lap splices shall be as follows: Reinforcing bars No. 25 or smaller shall be lapped at least 30 diameters of the smaller bar joined; and reinforcing bars Nos. 29, 32, and 36 shall be lapped at least 45 diameters of the smaller bar joined, except when otherwise shown on the plans.

Splices in bundled bars shall conform to the following:

A In bundles of 2 bars, the length of the lap splice shall be the same as the length of a single bar lap splice.

B. In bundles of 3 bars, the length of the lap splice shall be 1.2 times the length of a single bar lap splice.

Welded wire fabric shall be lapped such that the overlap between the outermost cross wires is not less than the larger of:

- A. 150 mm,
- B. The spacing of the cross wires plus 50 mm, or
- C. The numerical value of the longitudinal wire size (MW-Size Number) times 370 divided by the spacing of the longitudinal wires in millimeters.

**52-1.08B Service Splicing and Ultimate Butt Splicing Requirements**

Service splices and ultimate butt splices shall be either butt welded or mechanical splices, shall be used at the locations shown on the plans, and shall conform to the requirements of these specifications and the special provisions.

**52-1.08B(1) Mechanical Splices**

Mechanical splices to be used in the work shall be on the Department's current prequalified list before use. The prequalified list can be obtained from the Department's internet site listed in the special provisions or by contacting the Transportation Laboratory directly.

When tested in conformance with the requirements in California Test 670, the total slip shall not exceed the values listed in the following table:

Reinforcing Bar Number	Total Slip (µm)
13	250
16	250
19	250
22	350
25	350
29	350
32	450
36	450
43	600
57	750

Slip requirements shall not apply to mechanical lap splices, splices that are welded, or splices that are used on hoops.

Splicing procedures shall be in conformance with the manufacturer's recommendations, except as modified in this section. Splices shall be made using the manufacturer's standard equipment, jigs, clamps, and other required accessories.

Splice devices shall have a clear coverage of not less than 40 mm measured from the surface of the concrete to the outside of the splice device. Stirrups, ties, and other reinforcement shall be adjusted or relocated, and additional reinforcement shall be placed, if necessary, to provide the specified clear coverage to reinforcement.

The Contractor shall furnish the following information for each shipment of splice material in conformance with the provisions in Section 6-1.07, "Certificates of Compliance:"

- A. The type or series identification of the splice material including tracking information for traceability.
- B. The bar grade and size number to be spliced.
- C. A copy of the manufacturer's product literature giving complete data on the splice material and installation procedures.
- D. A statement that the splicing systems and materials used in conformance with the manufacturer's installation procedures will develop the required tensile strengths, based on the nominal bar area, and will conform to the total slip requirements and the other requirements in these specifications.
- E. A statement that the splice material conforms to the type of mechanical splice in the Department's current prequalified list.

**52-1.08B(2) Butt Welded Splices**

Except for resistance butt welds, butt welded splices of reinforcing bars shall be complete joint penetration butt welds conforming to the requirements in AWS D 1.4, and these specifications.

Welders and welding procedures shall be qualified in conformance with the requirements in AWS D 1.4.

Only the joint details and dimensions as shown in Figure 3.2, "Direct Butt Joints," of AWS D 1.4, shall be used for making complete joint penetration butt welds of bar reinforcement. Split pipe backing shall not be used.

Butt welds shall be made with multiple weld passes using a stringer bead without an appreciable weaving motion. The maximum stringer bead width shall be 2.5 times the diameter of the electrode and slagging shall be performed between each weld pass. Weld reinforcement shall not exceed 4 mm in convexity.

Electrodes used for welding shall meet the minimum Charpy V-notch impact requirement of 27°J at -20°C.

For welding of bars conforming to the requirements of ASTM Designation: A 615/A 615M, Grade 280 or Grade 420, the requirements of Table 5.2, "Minimum Preheat and Interpass Temperatures," of AWS D 1.4 are superseded by the following:

The minimum preheat and interpass temperatures shall be 200°C for Grade 280 bars and 300°C for Grade 420 bars. Immediately after completing the welding, at least 150 mm of the bar on each side of the splice shall be covered by an insulated wrapping to control the rate of cooling. The insulated wrapping shall remain in place until the bar has cooled below 90°C.

When welding different grades of reinforcing bars, the electrode shall conform to Grade 280 bar requirements and the preheat shall conform to the Grade 420 bar requirements.

In the event that any of the specified preheat, interpass, and post weld cooling temperatures are not met, all weld and heat affected zone metal shall be removed and the splice rewelded.

Welding shall be protected from air currents, drafts, and precipitation to prevent loss of heat or loss of arc shielding. The method of protecting the welding area from loss of heat or loss of arc shielding shall be subject to approval by the Engineer.

Reinforcing bars shall not be direct butt spliced by thermite welding.

Procedures to be used in making welded splices in reinforcing bars, and welders employed to make splices in reinforcing bars, shall be qualified by tests performed by the Contractor on sample splices of the type to be used, before making splices to be used in the work.

### **52-1.08B(3) Resistance Butt Welds**

Shop produced resistance butt welds shall be produced by a fabricator who is approved by the Transportation Laboratory. The list of approved fabricators can be obtained from the Department's internet site or by contacting the Transportation Laboratory directly.

Before manufacturing hoops using resistance butt welding, the Contractor shall submit to the Engineer the manufacturer's Quality Control (QC) manual for the fabrication of hoops. As a minimum, the QC manual shall include the following:

- A. The pre-production procedures for the qualification of material and equipment.
- B. The methods and frequencies for performing QC procedures during production.
- C. The calibration procedures and calibration frequency for all equipment.
- D. The welding procedure specification (WPS) for resistance welding.
- E. The method for identifying and tracking lots.

### **52-1.08C Service Splice and Ultimate Butt Splice Testing Requirements**

The Contractor shall designate in writing a splicing Quality Control Manager (QCM). The QCM shall be responsible directly to the Contractor for 1) the quality of all service and ultimate butt splicing including the inspection of materials and workmanship performed by the Contractor and all subcontractors; and 2) submitting, receiving, and approving all correspondence, required submittals, and reports regarding service and ultimate splicing to and from the Engineer.

The QCM shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project. The QCM may be an employee of the Contractor.

Testing on prequalification and production sample splices shall be performed at the Contractor's expense, at an independent qualified testing laboratory. The laboratory shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors who will provide other services or materials for the project, and shall have the following:

- A. Proper facilities, including a calibrated tensile testing machine capable of breaking the largest size of reinforcing bar to be tested.
- B. A device for measuring the total slip of the reinforcing bars across the splice to the nearest 25 µm, that, when placed parallel to the longitudinal axis of the bar is able to simultaneously measure movement across the splice at 2 locations 180 degrees apart.
- C. Operators who have received formal training for performing the testing requirements of ASTM Designation: A 370 and California Test 670.

- D. A record of annual calibration of testing equipment performed by an independent third party that has 1) standards that are traceable to the National Institute of Standards and Technology, and 2) a formal reporting procedure, including published test forms.

The Contractor shall provide samples for quality assurance testing in conformance with the provisions in these specifications and the special provisions.

Prequalification and production sample splices and testing shall conform to California Test 670 and these specifications.

The Contractor shall ensure that sample splices are properly secured and transported to the testing laboratory in such a manner that no alterations to the physical conditions occur during transportation. Sample splices shall be tested in the same condition as received. No modifications to the sample splices shall be made before testing.

Each set or sample splice, as defined herein, shall be identified as representing either a prequalification or production test sample splice.

For the purpose of production testing, a lot of either service splices or ultimate butt splices is defined as 1) 150, or fraction thereof, of the same type of mechanical splices used for each bar size and each bar deformation pattern that is used in the work, or 2) 150, or fraction thereof, of complete joint penetration butt welded splices or resistance butt welded splices for each bar size used in the work. If different diameters of hoop reinforcement are shown on the plans, separate lots shall be used for each different hoop diameter.

Whenever a lot of splices is rejected, the rejected lot and subsequent lots of splices shall not be used in the work until 1) the QCM performs a complete review of the Contractor's quality control process for these splices, 2) a written report is submitted to the Engineer describing the cause of failure for the splices in this lot and provisions for preventing similar failures in future lots, and 3) the Engineer has provided the Contractor with written notification that the report is acceptable. The Engineer shall have 3 working days after receipt of the report to provide notification to the Contractor. In the event the Engineer fails to provide notification within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in providing notification, the Contractor will be compensated for any resulting loss, and an extension of time will be granted in the same manner as provided for in Section 8-1.09, "Right of Way Delays."

#### **52-1.08C(1) Splice Prequalification Report**

Before using any service splices or ultimate butt splices in the work, the Contractor shall submit a Splice Prequalification Report. The report shall include splice material information, names of the operators who will be performing the splicing, and descriptions of the positions, locations, equipment, and procedures that will be used in the work.

The Splice Prequalification Report shall also include certifications from the fabricator for prequalifications of operators and procedures based on sample tests performed no more than 2 years before submitting the report. Each operator shall be certified by performing 2 sample splices for each bar size of each splice type that the operator will be performing in the work. For deformation-dependent types of splice devices, each operator shall be certified by performing 2 additional samples for each bar size and deformation pattern that will be used in the work.

Prequalification sample splices shall be tested by an independent qualified testing laboratory and shall conform to the appropriate production test criteria and slip requirements specified herein. When epoxy-coated reinforcement is required, resistance butt welded sample splices shall have the weld flash removed by the same procedure as will be used in the work, before coating and testing. The Splice Prequalification Report shall include the certified test results for all prequalification sample splices.

The QCM shall review and approve the Splice Prequalification Report before submitting it to the Engineer for approval. The Contractor shall allow 2 weeks for the review and approval of a complete report before performing any service splicing or ultimate butt splicing in the work. In the event the Engineer fails to complete the review within the time allowed, and in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays."

#### **52-1.08C(2) Service Splice Test Criteria**

Service production and quality assurance sample splices shall be tensile tested in conformance with the requirements in ASTM Designation: A 370 and California Test 670 and shall develop a minimum tensile strength of not less than 550 MPa.

#### **52-1.08C(2)(a) Production Test Requirements for Service Splices**

Production tests shall be performed by the Contractor's independent laboratory for all service splices used in the work. A production test shall consist of testing 4 sample splices prepared for each lot of completed splices. The samples shall be prepared by the Contractor using the same splice material, position, operators, location, and equipment, and following the same procedure as used in the work.

At least one week before testing, the Contractor shall notify the Engineer in writing of the date when and the location where the testing of the samples will be performed.

The 4 samples from each production test shall be securely bundled together and identified with a completed sample identification card before shipment to the independent laboratory. The card will be furnished by the Engineer. Bundles of samples containing fewer than 4 samples of splices shall not be tested.

Before performing any tensile tests on production test sample splices, one of the 4 samples shall be tested for, and shall conform to, the requirements for total slip. Should this sample not meet the total slip requirements, one retest, in which the 3 remaining samples are tested for total slip, will be allowed. Should any of the 3 remaining samples not conform to the total slip requirements, all splices in the lot represented by this production test will be rejected.

If 3 or more sample splices from a production test conform to the provisions in this Section 52-1.08C(2), "Service Splice Test Criteria," all splices in the lot represented by this production test will be considered acceptable.

Should only 2 sample splices from a production test conform to the provisions in this Section 52-1.08C(2), "Service Splice Test Criteria," one additional production test shall be performed on the same lot of splices. This additional production test shall consist of testing 4 sample splices that have been randomly selected by the Engineer and removed by the Contractor from the actual completed lot of splices. Should any of the 4 splices from this additional test fail to conform to these provisions, all splices in the lot represented by these production tests will be rejected.

If only one sample splice from a production test conforms to the provisions in this Section 52-1.08C(2), "Service Splice Test Criteria," all splices in the lot represented by this production test will be rejected.

If a production test for a lot fails, the Contractor shall repair or replace all reinforcing bars from which sample splices were removed before the Engineer selects additional splices from this lot for further testing.

#### **52-1.08C(2)(b) Quality Assurance Test Requirements for Service Splices**

For the first production test performed, and for at least one, randomly selected by the Engineer, of every 5 subsequent production tests, or portion thereof, the Contractor shall concurrently prepare 4 additional service quality assurance sample splices. These service quality assurance sample splices shall be prepared in the same manner as specified herein for service production sample splices.

These 4 additional quality assurance sample splices shall be shipped to the Transportation Laboratory for quality assurance testing. The 4 sample splices shall be securely bundled together and identified by location and contract number with weatherproof markings before shipment. Bundles containing fewer than 4 samples of splices will not be tested. Sample splices not accompanied by the supporting documentation required in Section 52-1.08B(1), for mechanical splices, or in Section 52-1.08B(3), for resistance butt welds, will not be tested.

Quality assurance testing will be performed in conformance with the requirements for service production sample splices in Section 52-1.08C(2)(a), "Production Test Requirements for Service Splices."

#### **52-1.08C(3) Ultimate Butt Splice Test Criteria**

Ultimate production and quality assurance sample splices shall be tensile tested in conformance with the requirements described in ASTM Designation: A 370 and California Test 670.

A minimum of 1 control bar shall be removed from the same bar as, and adjacent to, all ultimate prequalification, production, and quality assurance sample splices. The lengths of control bars shall conform to the lengths specified for sample splices in California Test 670. The portion of adjacent bar remaining in the work shall also be identified with weatherproof markings that correspond to its adjacent control bar.

Each sample splice and its associated control bar shall be identified and marked as a set. Each set shall be identified as representing a prequalification, production, or quality assurance sample splice.

The portion of hoop reinforcing bar, removed to obtain a sample splice and control bar, shall be replaced using a prequalified ultimate mechanical butt splice, or the hoop shall be replaced in kind.

Reinforcing bars, other than hoops, from which sample splices are removed, shall be repaired using ultimate mechanical butt splices conforming to the provisions in Section 52-1.08C(1), "Splice Prequalification Report," or the bars shall be replaced in kind. These bars shall be repaired or replaced such that no splices are located in any "No Splice Zone" shown on the plans.

Ultimate production and quality assurance sample splices shall rupture in the reinforcing bar either: 1) outside of the affected zone or 2) within the affected zone, provided that the sample splice has achieved at least 95 percent of the ultimate tensile strength of the control bar associated with the sample splice. In addition, necking of the bar, as defined in California Test 670, shall occur at rupture regardless of whether the bar breaks inside or outside the affected zone.

The affected zone is the portion of the reinforcing bar where any properties of the bar, including the physical, metallurgical, or material characteristics, have been altered by fabrication or installation of the splice.

The ultimate tensile strength shall be determined for all control bars by tensile testing the bars to rupture, regardless of where each sample splice ruptures. If 2 control bars are tested for one sample splice, the bar with the lower ultimate tensile strength shall be considered the control bar.

### **52-1.08C(3)(a) Production Test Requirements for Ultimate Butt Splices**

Production tests shall be performed for all ultimate butt splices used in the work. A production test shall consist of testing 4 sets of sample splices and control bars removed from each lot of completed splices, except when quality assurance tests are performed.

After the splices in a lot have been completed, and the bars have been epoxy-coated when required, the QCM shall notify the Engineer in writing that the splices in this lot conform to the specifications and are ready for testing. Except for hoops, sample splices will be selected by the Engineer at the job site. Sample splices for hoops will be selected by the Engineer either at the job site or a fabrication facility.

After notification has been received, the Engineer will randomly select the 4 sample splices to be removed from the lot and place tamper-proof markings or seals on them. The Contractor shall select the adjacent control bar for each sample splice bar, and the Engineer will place tamper-proof markings or seals on them. These ultimate production sample splices and control bars shall be removed by the Contractor, and tested by an independent qualified testing laboratory.

At least one week before testing, the Contractor shall notify the Engineer in writing of the date when and the location where the testing of the samples will be performed.

A sample splice or control bar from any set will be rejected if a tamper-proof marking or seal is disturbed before testing.

The 4 sets from each production test shall be securely bundled together and identified with a completed sample identification card before shipment to the independent laboratory. The card will be furnished by the Engineer. Bundles of samples containing fewer than 4 sets of splices shall not be tested.

Before performing any tensile tests on production test sample splices, one of the 4 sample splices shall be tested for, and shall conform to, the requirements for total slip. Should this sample splice not meet these requirements, one retest, in which the 3 remaining sample splices are tested for total slip, will be allowed. Should any of the 3 remaining sample splices not conform to these requirements, all splices in the lot represented by this production test will be rejected.

If 3 or more sample splices from a production test conform to the provisions in Section 52-1.08C(3), "Ultimate Butt Splice Test Criteria," all splices in the lot represented by this production test will be considered acceptable.

Should only 2 sample splices from a production test conform to the provisions in Section 52-1.08C(3), "Ultimate Butt Splice Test Criteria," one additional production test shall be performed on the same lot of splices. Should any of the 4 sample splices from this additional test fail to conform to these provisions, all splices in the lot represented by these production tests will be rejected.

If only one sample splice from a production test conforms to the provisions in Section 52-1.08C(3), "Ultimate Butt Splice Test Criteria," all splices in the lot represented by this production test will be rejected.

If a production test for a lot fails, the Contractor shall repair or replace all reinforcing bars from which sample splices were removed, complete in place, before the Engineer selects additional splices from this lot for further testing.

Production tests will not be required on repaired splices from a lot, regardless of the type of prequalified ultimate mechanical butt splice used to make the repair. However, should an additional production test be required, the Engineer may select any repaired splice for the additional production test.

### **52-1.08C(3)(b) Quality Assurance Test Requirements for Ultimate Butt Splices**

For the first production test performed, and for at least one, randomly selected by the Engineer, of every 5 subsequent production tests, or portion thereof, the Contractor shall concurrently prepare 4 additional ultimate quality assurance sample splices along with associated control bars.

Each time 4 additional ultimate quality assurance sample splices are prepared, 2 of these quality assurance sample splice and associated control bar sets and 2 of the production sample splice and associated control bar sets, together, shall conform to the requirements for ultimate production sample splices in Section 52-1.08C(3)(a), "Production Test Requirements for Ultimate Butt Splices."

The 2 remaining quality assurance sample splice and associated control bar sets, along with the 2 remaining production sample splice and associated control bar sets shall be shipped to the Transportation Laboratory for quality assurance testing. The 4 sets shall be securely bundled together and identified by location and contract number with weatherproof markings before shipment. Bundles containing fewer than 4 sets will not be tested.

Quality assurance testing will be performed in conformance with the requirements for ultimate production sample splices in Section 52-1.08C(3)(a), "Production Test Requirements for Ultimate Butt Splices."

### **52-1.08C(3)(c) Nondestructive Splice Tests**

When the specifications allow for welded sample splices to be taken from other than the completed lot of splices, the Contractor shall meet the following additional requirements.

Except for resistance butt welded splices, radiographic examinations shall be performed on 25 percent of all complete joint penetration butt welded splices from a production lot. The size of a production lot will be a maximum of 150 splices. The Engineer will select the splices which will compose the production lot and also the splices within each production lot to be radiographically examined.

All required radiographic examinations of complete joint penetration butt welded splices shall be performed by the Contractor in conformance with the requirements in AWS D 1.4 and these specifications.

Before radiographic examination, welds shall conform to the requirements in Section 4.4, "Quality of Welds," of AWS D 1.4.

Should more than 12 percent of the splices which have been radiographically examined in any production lot be defective, an additional 25 percent of the splices, selected by the Engineer from the same production lot, shall be radiographically examined. Should more than 12 percent of the cumulative total of splices tested from the same production lot be defective, all remaining splices in the lot shall be radiographically examined.

Additional radiographic examinations performed due to the identification of defective splices shall be at the Contractor's expense.

All defects shall be repaired in conformance with the requirements in AWS D 1.4.

The Contractor shall notify the Engineer in writing 48 hours before performing any radiographic examinations.

The radiographic procedure used shall conform to the requirements in AWS D1.1, AWS D1.4, and the following:

- A. Two exposures shall be made for each complete joint penetration butt welded splice. For each of the 2 exposures, the radiation source shall be centered on each bar to be radiographed. The first exposure shall be made with the radiation source placed at zero degrees from the top of the weld and perpendicular to the weld root and identified with a station mark of "0." The second exposure shall be at 90 degrees to the "0" station mark and shall be identified with a station mark of "90." When obstructions prevent a 90 degree placement of the radiation source for the second exposure, and when approved in writing by the Engineer, the source may be rotated, around the centerline of the reinforcing bar, a maximum of 25 degrees.
- B. For field produced complete joint penetration butt welds, no more than one weld shall be radiographed during one exposure. For shop produced complete joint penetration butt welds, if more than one weld is to be radiographed during one exposure, the angle between the root line of each weld and the direction to the radiation source shall be not less than 65 degrees.
- C. Radiographs shall be made by either X-ray or gamma ray. Radiographs made by X-ray or gamma rays shall have densities of not less than 2.3 nor more than 3.5 in the area of interest. A tolerance of 0.05 in density is allowed for densitometer variations. Gamma rays shall be from the iridium 192 isotope and the emitting specimen shall not exceed 4.45 mm in the greatest diagonal dimension.
- D. The radiographic film shall be placed perpendicular to the radiation source at all times; parallel to the root line of the weld unless source placement determines that the film must be turned; and as close to the root of the weld as possible.
- E. The minimum source to film distance shall be maintained so as to ensure that all radiographs maintain a maximum geometric unsharpness of 0.020 at all times, regardless of the size of the reinforcing bars.
- F. Penetrators shall be placed on the source side of the bar and perpendicular to the radiation source at all times. One penetrator shall be placed in the center of each bar to be radiographed, perpendicular to the weld root, and adjacent to the weld. Penetrator images shall not appear in the weld area.
- G. When radiography of more than one weld is being performed per exposure, each exposure shall have a minimum of one penetrator per bar, or 3 penetrators per exposure. When 3 penetrators per exposure are used, one penetrator shall be placed on each of the 2 outermost bars of the exposure, and the remaining penetrator shall be placed on a centrally located bar.
- H. An allowable weld buildup of 4 mm may be added to the total material thickness when determining the proper penetrator selection. No image quality indicator equivalency will be accepted. Wire penetrators or penetrator blocks shall not be used.
- I. Penetrators shall be sufficiently shimmed using a radiographically identical material. Penetrator image densities shall be a minimum of 2.0 and a maximum of 3.6.
- J. Radiographic film shall be Class 1, regardless of the size of reinforcing bars.
- K. Radiographs shall be free of film artifacts and processing defects, including, but not limited to, streaks, scratches, pressure marks or marks made for the purpose of identifying film or welding indications.
- L. Each splice shall be clearly identified on each radiograph and the radiograph identification and marking system shall be established between the Contractor and the Engineer before radiographic inspection begins. Film shall be identified by lead numbers only; etching, flashing or writing in identifications of any type will not be permitted. Each piece of film identification information shall be legible and shall include, as a minimum, the following information: Contractor's name, date, name of nondestructive testing firm, initials of radiographer, contract number, part number and weld number. The letter "R" and repair number shall be placed directly after the weld number to designate a radiograph of a repaired weld.
- M. Radiographic film shall be developed within a time range of one minute less to one minute more than the film manufacturer's recommended maximum development time. Sight development will not be allowed.





**In Section 55-1.01 replace the 4th paragraph with:**

Details of connections for highway bridges selected for use by the Contractor shall conform to the AASHTO LRFD Bridge Design Specifications with Caltrans Amendments.

Details of design selected by the Contractor, fabrication and workmanship, for steel railway bridges shall conform to the requirements of the Specifications for Steel Railway Bridges, for Fixed Spans Not Exceeding 400 Feet in Length of the AREMA, as set forth in the special provisions.

**In Section 55-1.05 replace the 3rd paragraph with:**

Construction methods and equipment employed by the Contractor shall conform to the provisions in Section 7-1.02, "Load Limitations."

**In Section 55-2.01 replace the 4th and 5th paragraphs with:**

All structural steel plate used for the fabrication of tension members, tension flanges, eyebars and hanger plates and for splice plates of tension members, tension flanges and eyebars shall meet the longitudinal Charpy V-notch impact value requirements specified herein. Sampling procedures shall conform to the requirements in ASTM Designation: A 673. The H (Heat) frequency of testing shall be used for structural steels conforming to the requirements in ASTM Designations: A 709/A 709M, Grades 36 [250], 50 [345], 50W [345W], and HPS 50W [345W]. The P (Piece) frequency of testing shall be used for structural steel conforming to the requirements in ASTM Designation: A 709/A 709M, Grades HPS 70W [485W], 100 [690], and 100W [690W]. Charpy V-notch impact values shall be determined in conformance with the requirements in ASTM Designation: E 23.

Charpy V-notch (CVN) impact values shall conform to the following minimum values for non fracture critical members:

Material Conforming to ASTM Designation: A 709/A 709M	CVN Impact Value (Joules at Temp.)
Grade 36 [250]	20 at 4°C
Grade 50 [345]* (50 mm and under in thickness)	20 at 4°C
Grade 50W [345W]* (50 mm and under in thickness)	20 at 4°C
Grade 50 [345]* (Over 50 mm to 100 mm in thickness)	27 at 4°C
Grade 50W [345W]* (Over 50 mm to 100 mm in thickness)	27 at 4°C
Grade HPS 50W [345W]* (100 mm and under in thickness)	27 at -12°C
Grade HPS 70W [485]* (100 mm and under in thickness)	34 at -23°C
Grade 100 [490] (65 mm and under in thickness)	34 at -18°C
Grade 100W [490W] (Over 65 mm to 100 mm in thickness)	48 at -18°C

\* If the yield point of the material exceeds 450 MPa, the temperature for the CVN impact value for acceptability shall be reduced 8°C for each increment of 70 MPa above 450 MPa.

#### Structural Steel Materials

Material	Specification
Structural steel:	
Carbon steel	ASTM: A 709/A 709M, Grade 36 [250] or {A 36/A 36M}a
High strength low alloy columbium vanadium steel	ASTM: A 709/A 709M, Grade 50 [345] or {A 572/A 572M, Grade 50 [345]}a
High strength low alloy structural steel	ASTM: A 709/A 709M, Grade 50W [345W], Grade HPS 50W [HSP 345W], or {A 588/A 588M}a
High strength low alloy structural steel plate	ASTM: A 709/A 709M, Grade HPS 70W [HPS 485W]
High-yield strength, quenched and tempered alloy steel plate suitable for welding	ASTM: A 709/A 709M, Grade 100 [690] and Grade 100W [690W], or {A 514/A 514M}a
Steel fastener components for general applications:	
Bolts and studs	ASTM: A 307
Headed anchor bolts	ASTM: A 307, Grade B, including S1 supplementary requirements
Nonheaded anchor bolts	ASTM: A 307, Grade C, including S1 supplementary requirements and S1.6 of AASHTO: M 314 supplementary requirements or AASHTO: M 314, Grade 36 or 55, including S1 supplementary requirements
High-strength bolts and studs	ASTM: A 449, Type 1
High-strength threaded rods	ASTM: A 449, Type 1
High-strength nonheaded anchor bolts	ASTM: A 449, Type 1
Nuts	ASTM: A 563, including Appendix X1b
Washers	ASTM: F 844

Components of high-strength steel fastener assemblies for use in structural steel joints:	
Bolts	ASTM: A 325, Type 1
Tension control bolts	ASTM: F 1852, Type 1
Nuts	ASTM: A 563, including Appendix X1b
Hardened washers	ASTM: F 436, Type 1, Circular, including S1 supplementary requirements
Direct tension indicators	ASTM: F 959, Type 325, zinc-coated
Carbon steel for forgings, pins and rollers	ASTM: A 668/A 668M, Class D
Alloy steel for forgings	ASTM: A 668/A 668M, Class G
Pin nuts	ASTM: A 36/A 36M
Carbon-steel castings	ASTM: A 27/A 27M, Grade 65-35, Class 1
Malleable iron castings	ASTM: A 47, Grade 32510 or A 47M, Grade 22010
Gray iron castings	ASTM: A 48, Class 30B
Carbon steel structural tubing	ASTM: A 500, Grade B or A 501
Steel pipe (Hydrostatic testing will not apply)	ASTM: A 53, Type E or S, Grade B; A 106, Grade B; or A 139, Grade B
Stud connectors	ASTM: A 108 and AASHTO/AWS D1.5

- a Grades that may be substituted for the equivalent ASTM Designation: A 709 steel, at the Contractor's option, subject to the modifications and additions specified and to the requirements of A 709.
- b Zinc-coated nuts that will be tightened beyond snug or wrench tight shall be furnished with a dry lubricant conforming to Supplementary Requirement S2 in ASTM Designation: A 563.

**In Section 55-2.02 in the 1st paragraph, replace the 1st sentence with:**

Unless otherwise specified or shown on the plans, all structural steel plates, shapes, and bars shall conform to ASTM Designation: A 709/A 709M, Grade 50 [345].

**In Section 55-3.05 replace the 1st paragraph with:**

Surfaces of bearing and base plates and other metal surfaces that are to come in contact with each other or with ground concrete surfaces or with asbestos sheet packing shall be flat to within one mm tolerance in 305 mm and to within 2 mm tolerance overall. Surfaces of bearing and base plates and other metal bearing surfaces that are to come in contact with preformed fabric pads, elastomeric bearing pads, or mortar shall be flat to within 3 mm tolerance in 305 mm and to within 5 mm tolerance overall.

**In Section 55-3.14, after the 9th paragraph add:**

If a torque multiplier is used in conjunction with a calibrated wrench as a method for tightening fastener assemblies to the required tension, both the multiplier and the wrench shall be calibrated together as a system. The same length input and output sockets and extensions that will be used in the work shall also be included in the calibration of the system. The manufacturer's torque multiplication ratio shall be adjusted during calibration of the system, such that when this adjusted ratio is multiplied by the actual input calibrated wrench reading, the product is a calculated output torque that is within 2 percent of the true output torque. When this system is used in the work to perform any installation tension testing, rotational capacity testing, fastener tightening, or tension verification, it shall be used, intact as calibrated.

**In Section 55-3.17 replace the 2nd paragraph with:**

The minimum size of all fillet welds, except those to reinforce groove welds, shall be as shown in the following table:



Ribbed sheet metal for box beam-closed truss sign structures shall be fabricated from galvanized sheet steel conforming to the requirements in ASTM Designation: A 653/A 653M, Designation SS, Grade 33[230]. Sheet metal panels shall be G 165 coating designation in conformance with the requirements in ASTM Designation: A 653/A 653M.

**Replace Section 56-1.02F with:**

**56-1.02F Steel Walkway Gratings**

Steel walkway gratings shall be furnished and installed in conformance with the details shown on the plans and the following provisions:

- A. Gratings shall be the standard product of an established grating manufacturer.
- B. Material for gratings shall be structural steel conforming to the requirements in ASTM Designation: A 1011/A 1011M, Designation CS, Type B.
- C. For welded type gratings, each joint shall be full resistance welded under pressure, to provide a sound, completely beaded joint.
- D. For mechanically locked gratings, the method of fabrication and interlocking of the members shall be approved by the Engineer, and the fabricated grating shall be equal in strength to the welded type.
- E. Gratings shall be accurately fabricated and free from warps, twists, or other defects affecting their appearance or serviceability. Ends of all rectangular panels shall be square. The tops of the bearing bars and cross members shall be in the same plane. Gratings distorted by the galvanizing process shall be straightened.

**In Section 56-1.03 replace the 5th through the 13th paragraphs with:**

Clips, eyes, or removable brackets shall be affixed to all signs and all posts and shall be used to secure the sign during shipping and for lifting and moving during erection as necessary to prevent damage to the finished galvanized or painted surfaces. Brackets on tubular sign structures shall be removed after erection. Details of the devices shall be shown on the working drawings.

High-strength bolted connections, where shown on the plans, shall conform to the provisions in Section 55-3.14, "Bolted Connections," except that only fastener assemblies consisting of a high-strength bolt, nut, hardened washer, and direct tension indicator shall be used.

High-strength fastener assemblies, and any other bolts, nuts, and washers attached to sign structures shall be zinc-coated by the mechanical deposition process.

Nuts for high-strength bolts designated as snug-tight shall not be lubricated.

An alternating snugging and tensioning pattern for anchor bolts and high-strength bolted splices shall be used. Once tensioned, high-strength fastener components and direct tension indicators shall not be reused.

For bolt diameters less than 10 mm, the diameter of the bolt hole shall be not more than 0.80-mm larger than the nominal bolt diameter. For bolt diameters greater than or equal to 10 mm, the diameter of the bolt hole shall be not more than 1.6 mm larger than the nominal bolt diameter.

Sign structures shall be fabricated into the largest practical sections prior to galvanizing.

Ribbed sheet metal panels for box beam closed truss sign structures shall be fastened to the truss members by cap screws or bolts as shown on the plans, or by 4.76 mm stainless steel blind rivets conforming to Industrial Fasteners Institute, Standard IFI-114, Grade 51. The outside diameter of the large flange rivet head shall be not less than 15.88 mm in diameter. Web splices in ribbed sheet metal panels may be made with similar type blind rivets of a size suitable for the thickness of material being connected.

Spalling or chipping of concrete structures shall be repaired by the Contractor at the Contractor's expense.

**In Section 56-1.03 after the 13th paragraph add:**

Overhead sign supports shall have an aluminum identification plate permanently attached near the base, adjacent to the traffic side on one of the vertical posts, using either stainless steel rivets or stainless steel screws. As a minimum, the information on the plate shall include the name of the manufacturer, the date of manufacture and the contract number.

**In Section 56-1.10 replace the 4th paragraph with:**

The contract price paid per kilogram for install sign structure of the type or types designated in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in installing sign structures, complete in place, including installing anchor bolt assemblies, removable sign panel frames, and sign panels and performing any welding, painting or galvanizing required during installation, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.















**In Section 75-1.02 in the 10th paragraph, replace the table with:**

Material	Specification
Steel bars, plates and shapes	ASTM Designation: A 36/A 36M or A 575, A 576 (AISI or M Grades 1016 through 1030)
Steel fastener components for general applications:	
Bolts and studs	ASTM Designation: A 307
Headed anchor bolts	ASTM Designation: A 307, Grade B, including S1 supplementary requirements
Nonheaded anchor bolts	ASTM Designation: A 307, Grade C, including S1 supplementary requirements and S1.6 of AASHTO Designation: M 314 supplementary requirements or AASHTO Designation: M 314, Grade 36 or 55, including S1 supplementary requirements
High-strength bolts and studs, threaded rods, and nonheaded anchor bolts	ASTM Designation: A 449, Type 1
Nuts	ASTM Designation: A 563, including Appendix X1*
Washers	ASTM Designation: F 844
Components of high-strength steel fastener assemblies for use in structural steel joints:	
Bolts	ASTM Designation: A 325, Type 1
Tension control bolts	ASTM Designation: F 1852, Type 1
Nuts	ASTM Designation: A 563, including Appendix X1*
Hardened washers	ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements
Direct tension indicators	ASTM Designation: F 959, Type 325, zinc-coated
Stainless steel fasteners (Alloys 304 & 316) for general applications:	
Bolts, screws, studs, threaded rods, and nonheaded anchor bolts	ASTM Designation: F 593 or F 738M
Nuts	ASTM Designation: F 594 or F 836M
Washers	ASTM Designation: A 240/A 240M and ANSI B 18.22M
Carbon-steel castings	ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1
Malleable iron castings	ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010
Gray iron castings	ASTM Designation: A 48, Class 30B
Ductile iron castings	ASTM Designation: A 536, Grade 65-45-12
Cast iron pipe	Commercial quality
Steel pipe	Commercial quality, welded or extruded
Other parts for general Applications	Commercial quality

\* Zinc-coated nuts that will be tightened beyond snug or wrench tight shall be furnished with a dyed dry lubricant conforming to Supplementary Requirement S2 in ASTM Designation: A 563.

**In Section 75-1.03 replace the 2nd paragraph with:**

Miscellaneous bridge metal shall consist of the following, except as further provided in Section 51-1.19, "Utility Facilities," and in the special provisions:

- A. Bearing assemblies, equalizing bolts and expansion joint armor in concrete structures.
- B. Expansion joint armor in steel structures.
- C. Manhole frames and covers, frames and grates, ladder rungs, guard posts and access door assemblies.
- D. Deck drains, area drains, retaining wall drains, and drainage piping, except drainage items identified as "Bridge Deck Drainage System" in the special provisions.

**In Section 75-1.03 replace the 7th paragraph with:**

Sheet steel for access doors shall be galvanized sheet conforming to the requirements in ASTM Designation: A 653/A 653M, Coating Designation Z600 {G210}.

**In Section 75-1.03 replace the 13th paragraph with:**

Concrete anchorage devices shall be mechanical expansion or resin capsule types installed in drilled holes or cast-in-place insert types. The anchorage devices shall be selected from the Department's Pre-Qualified Products List at:

[http://www.dot.ca.gov/hq/esc/approved\\_products\\_list](http://www.dot.ca.gov/hq/esc/approved_products_list)

The anchorage devices shall be a complete system, including threaded studs, hex nuts, and cut washers. Thread dimensions for externally threaded concrete anchorage devices prior to zinc coating, shall conform to the requirements in ANSI Standard: B1.1 having Class 2A tolerances or ANSI Standard: B1.13M having Grade 6g tolerances. Thread dimensions for internally threaded concrete anchorage devices shall conform to the requirements in ASTM A 563.

**In Section 75-1.03 replace the 18th paragraph with:**

Mechanical expansion anchors shall, when installed in accordance with the manufacturer's instructions and these specifications and tested in conformance with the requirements in California Test 681, withstand the application of a sustained tension test load of at least the following values for at least 48 hours with a movement not greater than 0.90 mm:

Stud Diameter (millimeters)	Sustained Tension Test Load (kilonewtons)
*18.01-21.00	22.2
15.01-18.00	18.2
12.01-15.00	14.2
9.01-12.00	9.34
6.00-9.00	4.23

\* Maximum stud diameter permitted for mechanical expansion anchors.

Resin capsule anchors shall, when installed in accordance with the manufacturer's instructions and these specifications and tested in conformance with the requirements in California Test 681, withstand the application of a sustained tension test load of at least the following values for at least 48 hours with a movement not greater than 0.25 mm:

Stud Diameter (millimeters)	Sustained Tension Test Load (kilonewtons)
29.01-33.00	137.9
23.01-29.00	79.6
21.01-23.00	64.1
18.01-21.00	22.2
15.01-18.00	18.2
12.01-15.00	14.2
9.01-12.00	9.34
6.00-9.00	4.23

At least 25 days before use, the Contractor shall submit one sample of each resin capsule anchor per lot to the Transportation Laboratory for testing. A lot of resin capsule anchors is 100 units, or fraction thereof, of the same brand and product name.

**In Section 75-1.03 in the 19th paragraph, replace the table with:**

Stud Diameter (millimeters)	Ultimate Tensile Load (kilonewtons)
30.01-33.00	112.1
27.01-30.00	88.1
23.01-27.00	71.2
20.01-23.00	51.6
16.01-20.00	32.0
14.01-16.00	29.4
12.00-14.00	18.7

**In Section 75-1.03, replace the 20th paragraph with:**

The Pre-Qualified Products List for concrete anchorage devices has been developed from data previously furnished by suppliers or manufacturers for each type and size. Approval of additional anchorage device types and sizes is contingent upon the Contractor submitting to the Engineer one sample of each type of concrete anchorage device, manufacturer's installation instructions, and certified results of tests, either by a private testing laboratory or the manufacturer, indicating compliance with the above requirements.

**In Section 75-1.03 in the 22nd paragraph, replace the table with:**

Installation Torque Values, (newton meters)

Stud Diameter (millimeters)	Shell Type Mechanical Expansion Anchors	Integral Stud Type Mechanical Expansion Anchors	Resin Capsule Anchors and Cast-in-Place Inserts
29.01-33.00	—	—	540
23.01-29.00	—	—	315
21.01-23.00	—	—	235
18.01-21.00	110	235	200
15.01-18.00	45	120	100
12.01-15.00	30	65	40
9.01-12.00	15	35	24
6.00-9.00	5	10	—

**In Section 75-1.03, replace the 24th paragraph with:**

Sealing compound, for caulking and adhesive sealing, shall be a polysulfide or polyurethane material conforming to the requirements in ASTM Designation: C 920, Type S, Grade NS, Class 25, Use O.

**In Section 75-1.035 replace the 3rd paragraph with:**

Cables shall be 19 mm preformed, 6 x 19, wire strand core or independent wire rope core (IWRC), galvanized in conformance with the requirements in Federal Specification RR-W-410, right regular lay, manufactured of improved plow steel with a minimum breaking strength of 200 kN. Two certified copies of mill test reports of each manufactured length of cable used shall be furnished to the Engineer.

**In Section 75-1.035 replace the 12th paragraph with:**

Concrete for filling cable drum units shall conform to the provisions in Section 90-10, "Minor Concrete," or at the option of the Contractor, may be a mix with 9.5 mm maximum size aggregate and not less than 400 kilograms of cementitious material per cubic meter.





**In Section 83-1.02B replace the 11th paragraph with:**

After fabrication, wood posts and blocks shall be pressure treated in conformance with Section 58, "Preservative Treatment of Lumber, Timber and Piling," and AWWA Use Category System: UC4A, Commodity Specification A.

**In Section 83-1.02B replace the 12th paragraph with:**

If copper naphthenate, ammoniacal copper arsenate, chromated copper arsenate, ammoniacal copper zinc arsenate, ammoniacal copper quat or copper azole is used to treat the wood posts and blocks, the bolt holes shall be treated as follows:

- A. Before the bolts are inserted, bolt holes shall be filled with a grease, recommended by the manufacturer for corrosion protection, which will not melt or run at a temperature of 65°C.

**In Section 83-1.02B replace the 24th paragraph with:**

End anchor assemblies and rail tensioning assemblies for metal beam guard railing shall be constructed as shown on the plans and shall conform to the following provisions:

1. An end anchor assembly (Type SFT) for metal beam guard railing shall consist of an anchor cable, an anchor plate, a wood post, a steel foundation tube, a steel soil plate and hardware.
2. An end anchor assembly (Type CA) for metal beam guard railing shall consist of an anchor cable, an anchor plate, a single anchor rod or double anchor rods, hardware and one concrete anchor.
3. A rail tensioning assembly for metal beam guard railing shall consist of an anchor cable, an anchor plate, and hardware.
4. The anchor plate, metal plates, steel foundation tubes and steel soil plate shall be fabricated of steel conforming to the requirements in ASTM Designation: A 36/A 36M.
5. The anchor rods shall be fabricated of steel conforming to the requirements in ASTM Designation: A 36/A 36M, A 441 or A 572, or ASTM Designation: A 576, Grades 1018, 1019, 1021 or 1026. The eyes shall be hot forged or formed with full penetration welds. After fabrication, anchor rods with eyes that have been formed with any part of the eye below 870°C during the forming operation or with eyes that have been closed by welding shall be thermally stress relieved prior to galvanizing. The completed anchor rod, after galvanizing, shall develop a strength of 220 kN.
6. In lieu of built-up fabrication of anchor plates as shown on the plans, anchor plates may be press-formed from steel plate, with or without welded seams.
7. All bolts and nuts shall conform to the requirements in ASTM Designation: A 307, unless otherwise specified in the special provisions or shown on the plans.
8. Anchor cable shall be 19 mm preformed, 6 x 19, wire strand core or independent wire rope core (IWRC), galvanized in conformance with the requirements in Federal Specification RR-W-410, right regular lay, manufactured of improved plow steel with a minimum breaking strength of 200 kN. Two certified copies of mill test reports of each manufactured length of cable used shall be furnished to the Engineer. The overall length of each cable anchor assembly shall be as shown on the plans, but shall be a minimum of 2 m.
9. Where shown on the plans, cable clips and a cable thimble shall be used to attach cable to the anchor rod. Thimbles shall be commercial quality, galvanized steel. Cable clips shall be commercial quality drop forged galvanized steel.
10. The swaged fitting shall be machined from hot-rolled bars of steel conforming to AISI Designation: C 1035, and shall be annealed suitable for cold swaging. The swaged fitting shall be galvanized before swaging. A lock pin hole to accommodate a 6 mm, plated, spring steel pin shall be drilled through the head of the swage fitting to retain the stud in proper position. The manufacturer's identifying mark shall be stamped on the body of the swage fitting.
11. The 25 mm nominal diameter stud shall conform to the requirements in ASTM Designation: A 449 after galvanizing. Prior to galvanizing, a 10 mm slot for the locking pin shall be milled in the stud end.
12. The swaged fittings, stud and nut assembly shall develop the specified breaking strength of the cable.
13. The cable assemblies shall be shipped as a complete unit including stud and nut.
14. Clevises shall be drop forged galvanized steel and shall develop the specified breaking strength of the cable.
15. One sample of cable properly fitted with swaged fitting and right hand thread stud at both ends as specified above, including a clevis when shown on the plans, one meter in total length, shall be furnished the Engineer for testing.
16. The portion of the anchor rod to be buried in earth shall be coated with a minimum 0.5 mm thickness of coal tar enamel conforming to AWWA Standard: C203 or a coal tar epoxy conforming to the requirements in Steel Structures Painting Council Paint Specification No. 16, Coal-Tar Epoxy-Polyimide Black Paint or Corps of Engineers Specification, Formula C-200a, Coal-Tar Epoxy Paint.
17. Metal components of the anchor assembly shall be fabricated in conformance with good shop practice and shall be hot-dip galvanized in conformance with the provisions in Section 75-1.05, "Galvanizing."
18. Anchor cables shall be tightened after the concrete anchor has cured for at least 5 days.

19. Concrete used to construct anchors for end anchor assemblies shall be Class 3 or minor concrete conforming to the provisions in Section 90, "Portland Cement Concrete."
20. Concrete shall be placed against undisturbed material of the excavated holes for end anchors. The top 300 mm of holes shall be formed, if required by the Engineer.
21. Reinforcing steel in concrete anchors for end anchor assemblies shall conform to the provisions in Section 52, "Reinforcement."

**In Section 83-1.02D replace the 2nd paragraph with:**

Structural shapes, tubing, plates, bars, bolts, nuts, and washers shall be structural steel conforming to the provisions in Section 55-2, "Materials." Other fittings shall be commercial quality.

**In Section 83-1.02E replace the 2nd paragraph with:**

Pipe for posts and braces shall be standard steel pipe or pipe that conforms to the provisions in Section 80-4.01A, "Posts and Braces."

**In Section 83-1.02E, delete the 3rd paragraph**

**In Section 83-1.02E in the 7th paragraph, replace the 2nd sentence with:**

Cable shall be galvanized in conformance with the requirements in Federal Specification RR-W-410.

**In Section 83-1.02I replace the 5th paragraph with:**

Where shown on the plans, cables used in the frame shall be 8 mm in diameter, wire rope, with a minimum breaking strength of 22 kN and shall be galvanized in conformance with the requirements in Federal Specification RR-W-410.

**In Section 83-1.02I replace the 14th paragraph with:**

Chain link fabric shall be either 11-gage Type I zinc-coated fabric conforming to the requirements in AASHTO M 181 or 11-gage Type IV polyvinyl chloride (PVC) coated fabric conforming to the requirements in Federal Specification RR-F-191/1.

**In Section 83-1.03 replace the 2nd paragraph with:**

Except for metal beam guard railing within the pay limits of a terminal system end treatment or transition railing (Type WB), metal beam guard railing will be measured by the meter along the face of the rail element from end post to end post of the completed railing at each installation. The point of measurement at each end post will be the center of the bolt attaching the rail element to the end post.

**In Section 83-1.03 replace the 7th and 8th paragraphs with:**

The quantities of end anchor assemblies (Type SFT or Type CA) and rail tensioning assemblies will be measured as units determined from actual count. An end anchor assembly (Type CA) with 2 cables attached to one concrete anchor will be counted as one terminal anchor assembly (Type CA) for measurement and payment.

The quantities of return and end caps and the various types of terminal sections for metal beam guard railing will be determined as units from actual count.

**In Section 83-1.04 replace the 3rd and 4th paragraphs with:**

The contract unit prices paid for end anchor assembly (Type SFT), end anchor assembly (Type CA), and rail tensioning assembly shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all work involved in constructing the end anchor assemblies, complete in place, including drilling anchor plate bolt holes in rail elements, driving steel foundation tubes, excavating for concrete anchor holes and disposing of surplus material, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

The contract unit prices paid for return caps, end caps, and the various types of terminal sections for metal beam guard railing shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing terminal sections, return and end caps, complete in place, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

**In Section 83-2.02B replace the 2nd paragraph with:**

Rail elements, backup plates, terminal connectors, terminal sections, and return caps shall conform to Class A, Type 1 thrie beam guard railing as shown in AASHTO Designation: M 180.

**In Section 83-2.02B replace the 14th paragraph with:**

All metal work shall be fabricated in the shop, and no punching, cutting or welding will be permitted in the field. Rail elements shall be lapped so that the exposed ends will not face approaching traffic. Terminal sections and return caps shall be installed in conformance with the manufacturer's recommendation.

**In Section 83-2.02D(2) replace the 1st paragraph with:**

Type 50 and 60 series concrete barriers shall be constructed of minor concrete conforming to the provisions in Section 90-10, "Minor Concrete," except as follows:

- a. The maximum size of aggregate used for extruded or slip-formed concrete barriers shall be at the option of the Contractor, but in no case shall the maximum size be larger than 37.5-mm or smaller than 9.5-mm.
- b. If the 9.5 mm maximum size aggregate grading is used to construct extruded or slip-formed concrete barriers, the cementitious material content of the minor concrete shall be not less than 400 kilograms per cubic meter.

**In Section 83-2.02D(2) replace the 3rd paragraph with:**

The concrete paving between the tops of the 2 walls of concrete barrier (Types 50E, 60E, 60GE, and 60SE) and the optional concrete slab at the base between the 2 walls of concrete barrier (Types 50E, 60E, 60GE, and 60SE) shall be constructed of minor concrete conforming to the provisions of Section 90-10, "Minor Concrete," except that the minor concrete shall contain not less than 300 kilograms of cementitious material per cubic meter.

**In Section 83-2.03 replace the 1st and 2nd paragraphs with:**

Except for single thrie beam barrier within the pay limits of transition railing (Type STB), single thrie beam barrier will be measured by the meter from end post to end post along the face of the rail element of the installed barrier. Single thrie beam barriers constructed on each side of piers under structures or other obstructions will be measured for payment along each line of the installed barrier.

Except for double thrie beam barrier within the pay limits of transition railing (Type DTB), double thrie beam barrier will be measured by the meter from end post to end post along the center line of the installed barrier.

**In Section 83-2.03 replace the 5th and 6th paragraphs with:**

The quantity of return caps, terminal connectors and the various types of terminal sections for single and double thrie beam barriers will be determined as units from actual count.

The quantity of end anchor assemblies will be paid for as units determined from actual count.

**In Section 83-2.04 replace the 1st and 2nd paragraphs with:**

The various types of thrie beam barrier, measured as specified in Section 83-2.03, "Measurement," will be paid for at the contract price per meter for single or double thrie beam barrier, whichever applies, and the contract unit price or prices for end anchor assemblies, return caps, terminal connectors and the various types of terminal sections.

The above prices and payments shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in constructing the barrier, complete in place, including drilling holes for wood posts, driving posts, backfilling the space around posts, excavating and backfilling end anchor assembly holes, connecting thrie beam barrier to concrete surfaces and disposing of surplus excavated material, and for furnishing, placing, removing and disposing of the temporary railing for closing the gap between existing barrier and the barrier being constructed as shown on the plans, and as specified in these specifications and the special provisions, and as directed by the Engineer.

**In Section 83-2.04 replace the 4th paragraph with:**

Steel plate barrier attached to concrete barrier at overhead sign foundations, electroliers, drainage structures, and other locations shown on the plans will be measured and paid for as the type of concrete barrier attached thereto.



**SECTION 85 PAVEMENT MARKERS**

(Issued 07-31-07)

**In Section 85-1.03 replace the 2nd through 5th paragraphs with:**

**Sampling**

Twenty markers selected at random will constitute a representative sample for each lot of markers. The lot size shall not exceed 25 000 markers.

**Tolerances**

Three test specimens will be randomly selected from the sample for each test and tested in conformance with these specifications. Should any one of the 3 specimens fail to conform with the requirements in these specifications, 6 additional specimens will be tested. The failure of any one of these 6 specimens shall be cause for rejection of the entire lot or shipment represented by the sample.

The entire sample of retroreflective pavement markers will be tested for reflectance. The failure of 10 percent or more of the original sampling shall be cause for rejection.

**Replace Section 85-1.04 with:**

**85-1.04 NON-REFLECTIVE PAVEMENT MARKERS**

Non-reflective pavement markers (Types A and AY) shall be, at the option of the Contractor, either ceramic or plastic conforming to these specifications.

The top surface of the marker shall be convex with a gradual change in curvature. The top, bottom and sides shall be free of objectionable marks or discoloration that will affect adhesion or appearance.

The bottom of markers shall have areas of integrally formed protrusions or indentations, which will increase the effective bonding surface area of adhesive. The bottom surface of the marker shall not deviate more than 1.5 mm from a flat surface. The areas of protrusion shall have faces parallel to the bottom of the marker and shall project approximately one mm from the bottom.

**In Section 85-1.04A, delete the 2nd through 4th paragraphs.**

**In Section 85-1.04A replace the 5th paragraph with:**

**Testing**

Tests shall be performed in conformance with the requirements in California Test 669.

Test	Test Description	Requirement
a	Bond strength	4.8 MPa, min.
b	Glaze thickness	180 µm, min.
c	Hardness	6 Moh, min.
d	Luminance factor, Type A, white markers only, glazed surface	75, min.
e	Yellowness index, Type A, white markers only, glazed surface	7, max.
f	Color-yellow, Type AY, yellow markers only. The chromaticity coordinates shall be within a color box defined in CTM 669	Pass
g	Compressive strength	6700 N, min.
h	Water absorption	2.0 %, max.
i	Artificial weathering, 500 hours exposure, yellowness index	20, max.

**Replace Section 85-1.04B with:**

**85-1.04B Non-Reflective Pavement Markers (Plastic)**

Plastic non-reflective pavement markers Types A and AY shall be, at the option of the Contractor, either polypropylene or acrylonitrile-butadiene-styrene (ABS) plastic type.

Plastic markers shall conform to the testing requirements specified in Section 85-1.04A, "Non-Reflective Pavement Markers (Ceramic)," except that Tests a, b, c, and h shall not apply. The plastic markers shall not be coated with substances that interfere with the ability of the adhesive bonding to the marker.

**In Section 85-1.05 replace the 6th and 7th paragraphs with:**

**Testing**

Tests shall be performed in conformance with the requirements in California Test 669.

Test Description	Requirement		
Bond strength <sup>a</sup>	3.4 MPa, min.		
Compressive strength <sup>b</sup>	8900 N, min.		
Abrasion resistance, marker must meet the respective specific intensity minimum requirements after abrasion.	Pass		
Water Soak Resistance	No delamination of the body or lens system of the marker nor loss of reflectance		
Reflectance	Specific Intensity		
	Clear	Yellow	Red
0° Incidence Angle, min.	3.0	1.5	0.75
20° Incidence Angle, min.	1.2	0.60	0.30
After one year field evaluation	0.30	0.15	0.08

- a. Failure of the marker body or filler material prior to reaching 3.4 MPa shall constitute a failing bond strength test.
- b. Deformation of the marker of more than 3 mm at a load of less than 8900 N or delamination of the shell and the filler material of more than 3 mm regardless of the load required to break the marker shall be cause for rejection of the markers as specified in Section 85-1.03, "Sampling, Tolerances and Packaging."

Pavement markers to be placed in pavement recesses shall conform to the above requirements for retroreflective pavement markers except that the minimum compressive strength requirement shall be 5338 N.

**In Section 85-1.05 delete the 8th paragraph.**

**In Section 85-1.06 replace the 6th paragraph with:**

Pavement markers shall not be placed on new hot mix asphalt surfacing or seal coat until the surfacing or seal coat has been opened to public traffic for a period of not less than 7 days when hot melt bituminous adhesive is used, and not less than 14 days when epoxy adhesive is used.

**In Section 85-1.06 replace the 8th paragraph with:**

Epoxy adhesive shall not be used to apply non-reflective plastic pavement markers.

**In Section 85-1.06 in the 14th paragraph, replace the 2nd sentence with:**

Cleaning shall be done by blast cleaning on all surfaces regardless of age or type, except that blast cleaning of clean, new hot mix asphalt and clean, new seal coat surfaces will not be required when hot melt bituminous adhesive is used.



**In Section 86-2.03, delete the 8th paragraph.**

**In Section 86-2.03 replace the 12th paragraph with:**

Plumbing of the standards shall be accomplished by adjusting the leveling nuts before placing the mortar or before the foundation is finished to final grade. Shims or other similar devices shall not be used for plumbing or raking of posts, standards, or pedestals. After final adjustments of both top nuts and leveling nuts on anchorage assemblies have been made, firm contact shall exist between all bearing surfaces of the anchor bolt nuts, washers, and the base plates.

**In Section 86-2.04 replace the 1st and 2nd paragraphs with:**

Bolts, nuts and washers, and anchor bolts for use in signal and lighting support structures shall conform to the provisions in Section 55-2, "Materials." Except when bearing-type connections or slipbases are specified, high-strength bolted connections shall conform to the provisions in Section 55-3.14, "Bolted Connections." Welding, nondestructive testing (NDT) of welds, and acceptance and repair criteria for NDT of steel members shall conform to the requirements of AWS D1.1 and the special provisions.

On each lighting standard except Type 1, one rectangular corrosion resistant metal identification tag shall be permanently attached above the hand hole, near the base of the standard, using stainless steel rivets. On each signal pole support, two corrosion resistant metal identification tags shall be attached, one above the hand hole near the base of the vertical standard and one on the underside of the signal mast arm near the arm plate. As a minimum, the information on each identification tag shall include the name of the manufacturer, the date of manufacture, the identification number as shown on the plans, the contract number, and a unique identification code assigned by the fabricator. This number shall be traceable to a particular contract and the welds on that component, and shall be readable after the support structure is coated and installed. The lettering shall be a minimum of 7 mm high. The information may be either depressed or raised, and shall be legible.

**In Section 86-2.04 replace the 4th paragraph with:**

Ferrous metal parts of standards, with shaft length of 4.6 m and longer, shall conform to the details shown on the plans, the provisions in Section 55-2, "Materials," except as otherwise noted, and the following requirements:

- A. Except as otherwise specified, standards shall be fabricated from sheet steel of weldable grade having a minimum yield strength, after fabrication, of 276 MPa.
- B. Certified test reports which verify conformance to the minimum yield strength requirements shall be submitted to the Engineer. The test reports may be the mill test reports for the as-received steel or, when the as-received steel has a lower yield strength than required, the Contractor shall provide supportive test data which provides assurance that the Contractor's method of cold forming will consistently increase the tensile properties of the steel to meet the specified minimum yield strength. The supportive test data shall include tensile properties of the steel after cold forming for specific heats and thicknesses.
- C. When a single-ply 8-mm thick pole is specified, a 2-ply pole with equivalent section modulus may be substituted.
- D. Standards may be fabricated of full-length sheets or shorter sections. Each section shall be fabricated from not more than 2 pieces of sheet steel. Where 2 pieces are used, the longitudinal welded seams shall be directly opposite one another. When the sections are butt-welded together, the longitudinal welded seams on adjacent sections shall be placed to form continuous straight seams from base to top of standard.
- E. Butt-welded circumferential joints of tubular sections requiring CJP groove welds shall be made using a metal sleeve backing ring inside each joint. The sleeve shall be 3-mm nominal thickness, or thicker, and manufactured from steel having the same chemical composition as the steel in the tubular sections to be joined. When the sections to be joined have different specified minimum yield strengths, the steel in the sleeve shall have the same chemical composition as the tubular section having the higher minimum yield strength. The width of the metal sleeve shall be consistent with the type of NDT chosen and shall be a minimum width of 25 mm. The sleeve shall be centered at the joint and be in contact with the tubular section at the point of the weld at time of fit-up.
- F. Welds shall be continuous.
- G. The weld metal at the transverse joint shall extend to the sleeve, making the sleeve an integral part of the joint.
- H. During fabrication, longitudinal seams on vertical tubular members of cantilevered support structures shall be centered on and along the side of the pole that the pole plate is located. Longitudinal seams on horizontal tubular members, including signal and luminaire arms, shall be within +/-45 degrees of the bottom of the arm.
- I. The longitudinal seam welds in steel tubular sections may be made by the electric resistance welding process.
- J. Longitudinal seam welds shall have 60 percent minimum penetration, except that within 150 mm of circumferential welds, longitudinal seam welds shall be CJP groove welds. In addition, longitudinal seam welds on lighting support structures having telescopic pole segment splices shall be CJP groove welds on the female end for a length on each end equal to the designated slip fit splice length plus 150 mm.

- K. Exposed circumferential welds, except fillet and fatigue-resistant welds, shall be ground flush (-0, +2 mm) with the base metal prior to galvanizing or painting.
- L. Circumferential welds and base plate-to-pole welds may be repaired only one time without written permission from the Engineer.
- M. Exposed edges of the plates that make up the base assembly shall be finished smooth and exposed corners of the plates shall be broken unless otherwise shown on the plans. Shafts shall be provided with slip-fitter shaft caps.
- N. Flatness of surfaces of 1) base plates that are to come in contact with concrete, grout, or washers and leveling nuts; 2) plates in high-strength bolted connections; 3) plates in joints where cap screws are used to secure luminaire and signal arms; and 4) plates used for breakaway slip base assemblies shall conform to the requirements in ASTM A6.
- O. Standards shall be straight, with a permissive variation not to exceed 25 mm measured at the midpoint of a 9-m or 11-m standard and not to exceed 20 mm measured at the midpoint of a 5-m through 6-m standard. Variation shall not exceed 25 mm at a point 4.5 m above the base plate for Type 35 and Type 36 standards.
- P. Zinc-coated nuts used on fastener assemblies having a specified preload (obtained by specifying a prescribed tension, torque value, or degree of turn) shall be provided with a colored lubricant that is clean and dry to the touch. The color of the lubricant shall be in contrast to the zinc coating on the nut so that the presence of the lubricant is visually obvious. In addition, either the lubricant shall be insoluble in water, or fastener components shall be shipped to the job site in a sealed container.
- Q. No holes shall be made in structural members unless the holes are shown on the plans or are approved in writing by the Engineer.
- R. Standards with an outside diameter of 300 mm or less shall be round. Standards with an outside diameter greater than 300 mm shall be round or multisided. Multisided standards shall have a minimum of 12 sides which shall be convex and shall have a minimum bend radius of 100 mm.
- S. Mast arms for standards shall be fabricated from material as specified for standards, and shall conform to the dimensions shown on the plans.
- T. The cast steel option for slip bases shall be fabricated from material conforming to the requirements in ASTM Designation: A 27/A 27M, Grade 70-40. Other comparable material may be used if written permission is given by the Engineer. The casting tolerances shall be in conformance with the Steel Founder's Society of America recommendations (green sand molding).
- U. One casting from each lot of 50 castings or less shall be subject to radiographic inspection, in conformance with the requirements in ASTM Designation: E 94. The castings shall comply with the acceptance criteria severity level 3 or better for the types and categories of discontinuities in conformance with the requirements in ASTM Designations: E 186 and E 446. If the one casting fails to pass the inspection, 2 additional castings shall be radiographed. Both of these castings shall pass the inspection, or the entire lot of 50 will be rejected.
- V. Material certifications, consisting of physical and chemical properties, and radiographic films of the castings shall be filed at the manufacturer's office. These certifications and films shall be available for inspection upon request.
- W. High-strength bolts, nuts, and flat washers used to connect slip base plates shall conform to the requirements in ASTM Designation: A 325 or A 325M and shall be galvanized in conformance with the provisions in Section 75-1.05, "Galvanizing."
- X. Plate washers shall be fabricated by saw cutting and drilling steel plate conforming to the requirements in AISI Designation: 1018, and be galvanized in conformance with the provisions in Section 75-1.05, "Galvanizing." Prior to galvanizing, burrs and sharp edges shall be removed and holes shall be chamfered sufficiently on each side to allow the bolt head to make full contact with the washer without tension on the bolt.
- Y. High-strength cap screws shown on the plans for attaching arms to standards shall conform to the requirements in ASTM Designation: A 325, A 325M, or A 449, and shall comply with the mechanical requirements in ASTM Designation: A 325 or A 325M after galvanizing. The cap screws shall be galvanized in conformance with the provisions in Section 75-1.05, "Galvanizing." The threads of the cap screws shall be coated with a colored lubricant that is clean and dry to the touch. The color of the lubricant shall be in contrast to the color of the zinc coating on the cap screw so that presence of the lubricant is visually obvious. In addition, either the lubricant shall be insoluble in water, or fastener components shall be shipped to the job site in a sealed container.
- Z. Unless otherwise specified, bolted connections attaching signal or luminaire arms to poles shall be considered slip critical. Galvanized faying surfaces on plates on luminaire and signal arms and matching plate surfaces on poles shall be roughened by hand using a wire brush prior to assembly and shall conform to the requirements for Class C surface conditions for slip-critical connections in "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts," a specification approved by the Research Council on Structural Connections (RCSC) of the Engineering Foundation. For faying surfaces required to be painted, the paint shall be an approved type, brand, and thickness that has been tested and approved according to the RCSC Specification as a Class B coating.
- AA. Samples of fastener components will be randomly taken from each production lot by the Engineer and submitted, along with test reports required by appropriate ASTM fastener specifications, for QA testing and evaluation. Sample sizes for each fastener component shall be as determined by the Engineer.

**In Section 86-2.04 replace the 7th paragraph with:**

To avoid interference of arm plate-to-tube welds with cap screw heads, and to ensure cap screw heads can be turned using conventional installation tools, fabricators shall make necessary adjustments to details prior to fabrication and properly locate the position of arm tubes on arm plates during fabrication.

**In Section 86-2.05C in the 18th paragraph, replace the 4th and 5th subparagraphs with:**

The conduit shall be placed in the bottom of the trench, and the trench shall be backfilled with minor concrete conforming to the provisions in Section 90-10, "Minor Concrete." Minor concrete shall contain not less than 350 kilograms of cementitious material per cubic meter. Concrete backfill shall be placed to the pavement surface except, when the trench is in hot mix asphalt pavement and additional pavement is not being placed, the top 30 mm of the trench shall be backfilled with hot mix asphalt produced from commercial quality paving asphalt and aggregates.

Prior to spreading hot mix asphalt, tack coat shall be applied in conformance with the provisions in Section 39, "Hot Mix Asphalt." Spreading and compacting of hot mix asphalt shall be performed by any method which will produce a hot mix asphalt surfacing of uniform smoothness, texture and density.

**In Section 86-2.05C in the 23rd paragraph, replace the 3rd subparagraph with:**

Precast concrete conduit cradles shall conform to the dimensions shown on the plans and shall be constructed of minor concrete and commercial quality welded wire fabric. Minor concrete shall conform to the provisions in Section 90-10, "Minor Concrete," and shall contain not less than 350 kilograms of cementitious material per cubic meter. The cradles shall be moist cured for not less than 3 days.

**In Section 86-2.05C in the 23rd paragraph, replace the 7th subparagraph with:**

The space around conduits through bridge abutment walls shall be filled with mortar conforming to the provisions in Section 51-1.135, "Mortar," except that the proportion of cementitious material to sand shall be 1:3.

**In Section 86-2.07 replace the 5th paragraph with:**

Concrete placed around and under traffic pull boxes as shown on the plans shall be minor concrete conforming to the provisions in Section 90-10, "Minor Concrete."

**In Section 86-2.08A in the 1st paragraph in the table, after the heading replace the 4th row with:**

Traffic Signal	Ungrounded Circuit Conductor	Blk	None	CON-1	6
Controller Cabinet	Grounded Circuit Conductor	Wht	None	CON-2	6

**In Section 86-2.08B replace the 2nd paragraph with:**

At any point, the minimum insulation thickness of any Type USE, RHH, or RHW insulation shall be 1.0 mm for conductor sizes No. 14 to No. 10, inclusive; and 1.3 mm for No. 8 to No. 2, inclusive.

At any point, the minimum insulation thickness of any Type THW or TW wires shall be 0.7 mm for conductor sizes No. 14 to No. 10, inclusive; 1.0 mm for No. 8; and 1.4 mm for No. 6 to No. 2, inclusive.

**In Section 86-2.12 replace the 6 and 7th paragraphs with:**

After fabrication, wood poles shall be pressure treated in conformance with the provisions in Section 58, "Preservative Treatment of Lumber, Timber and Piling," and AWPA Use Category System: UC4B, Commodity Specification D.

Wood poles, when specified in the special provisions to be painted, shall be treated with waterborne wood preservatives.

**In Section 86-2.15 replace the 1st paragraph with:**

Galvanizing shall be in conformance with the provisions in Section 75-1.05, "Galvanizing," except that cabinets may be constructed of material galvanized prior to fabrication in conformance with the requirements in ASTM Designation: A 653/653M, Coating Designation G 90, in which case all cut or damaged edges shall be painted with at least 2 applications of approved unthinned zinc-rich primer (organic vehicle type) conforming to the provisions in Section 91, "Paint." Aerosol cans shall not be used. Other types of protective coating must be approved by the Engineer prior to installation.

**In Section 86-2.16, in the 13th paragraph, replace item B with:**

- B. Salt Spray Resistance - The undercutting of the film of the coating system shall not exceed 3 mm average, from lines scored diagonally and deep enough to expose the base metal, after 336 hours exposure in a salt spray cabinet in conformance with the requirements in ASTM Designation: B 117.

**In Section 86-4.01 replace the 1st paragraph with:**

Each vehicle signal face shall be of the adjustable type conforming to the requirements in Institute of Transportation Engineers (ITE) Publication: ST-017B, "Vehicle Traffic Control Signal Heads."

**In Section 86-4.01A in the 1st paragraph, replace the 1st and 3rd subparagraphs with:**

Lenses, reflectors, reflector assemblies, lamp receptacles, lamps, wiring and light distribution shall conform to the requirements in ITE Publication: ST-017B.

All reflectors shall conform to the requirements in ITE Publication: ST-017B except that reflectors shall be made of silvered glass or of specular aluminum with an anodic coating. Reflector ring holder shall be made of cast aluminum.

**In Section 86-4.01B replace the 1st paragraph with:**

Each signal section housing shall be either die-cast or permanent mold-cast aluminum conforming to ITE Publication: ST-017B or, when specified in the special provisions, shall be structural plastic.

**In Section 86-4.01C replace the 1st paragraph with:**

Lamp receptacles and wiring shall conform to ITE Publication: ST-017B. The metal portion of the medium base lamp socket shall be brass, copper or phosphor bronze.

**In Section 86-4.01D replace the 1st paragraph with:**

Each signal section shall be provided with a removable visor conforming to the requirements in ITE Publication: ST-017B. Visors are classified, on the basis of lens enclosure, as full circle, tunnel (bottom open), or cap (bottom and lower sides open). Unless otherwise specified, visors shall be the tunnel type.

**In Section 86-4.02A replace the 1st paragraph with:**

Light emitting diode signal modules shall be designed as retrofit replacements for optical units of standard traffic signal sections and shall not require special tools for installation. Light emitting diode signal modules shall fit into existing traffic signal section housings built in conformance with the requirements in the Institute of Transportation Engineers (ITE) publication ST-017B, "Vehicle Traffic Control Signal Heads (VTCSH)" without modification to the housing.

**In Section 86-4.02A replace the 7th paragraph with:**

Light emitting diode signal modules shall be protected against dust and moisture intrusion in conformance with the requirements in NEMA Standard 250 for Type 4 enclosures to protect the internal components.

**In Section 86-4.02B replace the 1st paragraph with:**

The minimum initial luminous intensity values for light emitting diode signal modules shall conform to the requirements in Section 11.04 of the Institute of Transportation Engineers (ITE) publication ST-017B, "Vehicle Traffic Control Signal Heads (VTCSH)" at 25°C.

**In Section 86-4.02C replace the 3rd paragraph with:**

The light emitting diode signal module on-board circuitry shall include voltage surge protection to withstand high-repetition noise transients as specified in Section 2.1.6 of NEMA Standard TS2.

**In Section 86-4.02D(1), in the 4th paragraph, replace the 7th subparagraph with:**

Moisture resistance testing shall be performed on light emitting diode signal modules in conformance with the requirements in NEMA Standard 250 for Type 4 enclosures. Evidence of internal moisture after testing shall be cause for rejection.

**In Section 86-4.05 replace the 2nd paragraph with:**

Each programmed visibility signal section shall provide a nominal 300-mm diameter circular or arrow indication. Color and arrow configuration shall conform to the requirements in ITE Publication: ST-017B.

**In Section 86-4.06 replace the 1st paragraph with:**

Message symbols for pedestrian signal faces shall be white WALKING PERSON and Portland orange UPRAISED HAND conforming to the requirements in the Institute of Transportation Engineers Standards: "Pedestrian Traffic Control Signal Indications" and "California MUTCD." The height of each symbol shall be not less than 250 mm and the width of each symbol shall be not less than 165 mm.

**In Section 86-4.06(A) in the 1st paragraph, replace the 3rd subparagraph with:**

Each reflector assembly shall consist of a double reflector or 2 single reflectors. Each reflector shall be made of either aluminum or plastic. Reflectors shall conform to the requirements in Institute of Transportation Engineers Publication: ST-017B, "Vehicle Traffic Control Signal Heads." Plastic reflectors shall consist of molded or vacuum-formed plastic with a vacuum-deposited aluminum reflecting surface. The plastic material shall not distort when the reflector is used with the lamp of the wattage normally furnished with the signal. In addition, the UL nonmechanical loading temperature of the material shall exceed, by at least 10°C, the maximum temperature in the signal section with the lamp "ON" and measured in an ambient air temperature of 25°C in conformance with the requirements in UL Publication UL 746B. Each completed reflector shall, when operated with the appropriate lamp and lens, provide the message brightness specified.

**In Section 86-4.07 replace the 10th paragraph with:**

The luminance of the "UPRAISED HAND" symbol shall be 3750 cd/m<sup>2</sup> minimum. The color of "UPRAISED HAND" shall be Portland orange conforming to the requirements of the Institute of Transportation Engineers Standards: "Pedestrian Traffic Control Signal Indications" and "California MUTCD." The height of each symbol shall be not less than 250 mm and the width of each symbol shall be not less than 165 mm.

**In Section 86-4.07C replace the 2nd paragraph with:**

On-board circuitry of the light emitting diode pedestrian signal modules shall include voltage surge protection to withstand high-repetition noise transients as stated in Section 2.1.6 of NEMA Standard TS2.

**In Section 86-4.07D(1) replace the 2nd paragraph with:**

A quantity of 2 units for each design shall be submitted for Design Qualification Testing. Test units shall be submitted to the Transportation Laboratory, after manufacturer's testing is complete.

**In Section 86-4.07D(1) in the 4th paragraph, replace the 5th and 7th subparagraphs with:**

Mechanical vibration testing shall be in conformance with the requirements in Military Specification MIL-STD-883, Test Method 2007, using three 4-minute cycles along each x, y and z axis, at a force of 2.5 Gs, with a frequency sweep from 2 Hz to 120 Hz. The loosening of the lens or of internal components, or other physical damage shall be cause for rejection.

Moisture resistance testing shall be performed on modules mounted in a standard pedestrian signal housing in conformance to the requirements in NEMA Standard 250 for Type 4 enclosures. Evidence of internal moisture after testing shall be cause for rejection.

**In Section 86-5.07A(5) in Section "Elastomeric Sealant" in the 1st paragraph, replace the 2nd sentence with:**

Sealant shall be suitable for use in both hot mix asphalt and portland cement concrete.

**In Section 86-5.07A(5) in Section "Asphatic Emulsion Sealant" in the 1st paragraph, replace the 1st sentence with:**

Asphatic emulsion sealant shall conform to the requirements in State Specification 8040-41A-15 and shall be used only for filling slots in hot mix asphalt pavement.

**In Section 86-5.07A(5) in Section "Hot-Melt Rubberized Asphalt Sealant" in the 1st paragraph, replace the 3rd sentence with:**

Sealant shall be suitable for use in both hot mix asphalt and portland cement concrete.

**In Section 86-5.07A(5) in Section "Hot-Melt Rubberized Asphalt Sealant" in the 2nd paragraph in the table, after the heading replace rows 1 through 3 with:**

Cone Penetration, 25°C, 150 g, 5 s	D 5329, Sec. 6	3.5 mm, max.
Flow, 60°C	D 5329, Sec. 8	5 mm, max.
Resilience, 25°C	D 5329, Sec. 12	25%, min.

**In Section 86-5.07A(5) in Section "Hot-Melt Rubberized Asphalt Sealant", replace the 10th paragraph with:**

If hot mix asphalt surfacing is to be placed, the loop conductors shall be installed prior to placing the uppermost layer of hot mix asphalt. The conductors shall be installed, as shown on the plans, in the compacted layer of hot mix asphalt immediately below the uppermost layer. Installation details shall be as shown on the plans, except the sealant shall fill the slot flush to the surface.

**In Section 86-5.01D replace the 1st paragraph with:**

When a foundation for a pressure-sensitive vehicle detector is to be removed, the hole left by removing the detector frame and foundation shall be filled with minor concrete, except the roadway surface shall be reconstructed with material to match existing surfacing. Minor concrete shall conform to the provisions in Section 90-10, "Minor Concrete," except that the concrete shall contain not less than 250 kilograms of cementitious material per cubic meter for hot mix asphalt surfaced roadways and not less than 350 kilograms of cementitious material per cubic meter for portland cement concrete surfaced roadways.

**In Section 86-6.065 in Section "Mounting Assemblies", replace the 3rd paragraph with:**

At least 4.9 m of clearance shall be provided between the bottom of the fixture and the roadway.

**In Section 86-8.01 replace the 1st paragraph with:**

The contract lump sum price or prices paid for signal, ramp metering, flashing beacon, lighting, sign illumination, traffic monitoring station, highway advisory radio systems, closed circuit television systems, or combinations thereof; for modifying or removing those systems; for temporary systems; or the lump sum or unit prices paid for various units of those systems; or the lump sum or per meter price paid for conduit of the various sizes, types and installation methods listed in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in furnishing and installing, modifying, or removing the systems, combinations or units thereof, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer, including any necessary pull boxes (except when the type required is shown as a separate contract item); excavation and backfill; concrete foundations (except when shown as a separate contract item); pedestrian barricades; furnishing and installing illuminated street name signs; installing sign panels on pedestrian barricades, on flashing beacon standards, and on traffic signal mast arms; restoring sidewalk, pavement and appurtenances damaged or destroyed during construction; salvaging existing materials; and making all required tests.



Minor concrete shall contain not less than 325 kg of cementitious material per cubic meter unless otherwise specified in these specifications or the special provisions.

Unless otherwise designated on the plans or specified in these specifications or the special provisions, the amount of cementitious material used per cubic meter of concrete in structures or portions of structures shall conform to the following:

Use	Cementitious Material Content (kg/m <sup>3</sup> )
Concrete designated by compressive strength:	
Deck slabs and slab spans of bridges	400 min., 475 max.
Roof sections of exposed top box culverts	400 min., 475 max.
Other portions of structures	350 min., 475 max.
Concrete not designated by compressive strength:	
Deck slabs and slab spans of bridges	400 min.
Roof sections of exposed top box culverts	400 min.
Prestressed members	400 min.
Seal courses	400 min.
Other portions of structures	350 min.
Concrete for precast members	350 min., 550 max.

Whenever the 28-day compressive strength shown on the plans is greater than 25 MPa, the concrete shall be designated by compressive strength. If the plans show a 28-day compressive strength that is 28 MPa or greater, an additional 14 days will be allowed to obtain the specified strength. The 28-day compressive strengths shown on the plans that are 25 MPa or less are shown for design information only and are not a requirement for acceptance of the concrete.

Concrete designated by compressive strength shall be proportioned such that the concrete will attain the strength shown on the plans or specified in the special provisions.

Before using concrete for which the mix proportions have been determined by the Contractor, or in advance of revising those mix proportions, the Contractor shall submit in writing to the Engineer a copy of the mix design.

Compliance with cementitious material content requirements will be verified in conformance with procedures described in California Test 518 for cement content. For testing purposes, supplementary cementitious material shall be considered to be cement. Batch proportions shall be adjusted as necessary to produce concrete having the specified cementitious material content.

If any concrete has a cementitious material, portland cement, or supplementary cementitious material content that is less than the minimum required, the concrete shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place and the Contractor shall pay to the State \$0.55 for each kilogram of cementitious material, portland cement, or supplementary cementitious material that is less than the minimum required. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract. The deductions will not be made unless the difference between the contents required and those actually provided exceeds the batching tolerances permitted by Section 90-5, "Proportioning." No deductions will be made based on the results of California Test 518.

The requirements of the preceding paragraph shall not apply to minor concrete or commercial quality concrete.

## 90-2 MATERIALS

### 90-2.01 CEMENTITIOUS MATERIALS

Unless otherwise specified, cementitious material shall be either a combination of Type II or Type V portland cement and a supplementary cementitious material, or a blended cement.

Cementitious materials used in cast-in-place concrete for exposed surfaces of like elements of a structure shall be from the same sources and of the same proportions.

Cementitious materials shall be protected from moisture until used. Sacked cementitious materials shall be piled to permit access for tallying, inspecting, and identifying each shipment.

Facilities shall be provided to ensure that cementitious materials meeting this Section 90-2.01 are kept separate from other cementitious materials. Sampling cementitious materials shall be in conformance with California Test 125.

The Contractor shall furnish a Certificate of Compliance for cementitious materials in conformance with the provisions in Section 6-1.07, "Certificates of Compliance." The Certificate of Compliance shall indicate the source by name and location (including country, state, and city). If cementitious material is delivered directly to the job site, the Certificate of Compliance shall be signed by the cementitious material supplier. If the cementitious material is used in ready-mixed concrete or in precast concrete products purchased as such by the Contractor, the Certificate of Compliance shall be signed by the manufacturer of the concrete or product.

### **90-2.01A CEMENT**

Portland cement shall conform to the requirements in ASTM Designation: C 150 except, using a 10-sample moving average, limestone shall not exceed 2.5 percent. The C<sub>3</sub>S content of Type II cement shall not exceed 65 percent.

Blended cement shall conform to the requirements for Portland Blast-Furnace Slag, Cement Type IS (MS) or Portland-Pozzolan Cement, Type IP (MS) in AASHTO Designation: M 240 and shall be comprised of an intimate and uniform blend of Type II or Type V cement and supplementary cementitious material in an amount conforming to the requirements in Section 90-2.01C, "Required Use of Supplementary Cementitious Materials."

In addition, blended cement, Type II portland cement, and Type V portland cement shall conform to the following requirements:

- A. The cement shall not contain more than 0.60-percent by mass of alkalis, calculated as the percentage of Na<sub>2</sub>O plus 0.658 times the percentage of K<sub>2</sub>O, when determined by methods as required in AASHTO Designation: T 105;
- B. The autoclave expansion shall not exceed 0.50-percent; and
- C. Mortar, containing the cement to be used and Ottawa sand, when tested in conformance with California Test 527, shall not expand in water more than 0.010-percent and shall not contract in air more than 0.048-percent, except that when cement is to be used for precast prestressed concrete piling, precast prestressed concrete members, or steam cured concrete products, the mortar shall not contract in air more than 0.053-percent.

Type III portland cement shall be used only as specified in the special provisions or with the approval of the Engineer. Type III portland cement shall conform to the additional requirements listed above for Type II portland cement, except when tested in conformance with California Test 527, mortar containing Type III portland cement shall not contract in air more than 0.075-percent.

### **90-2.01B SUPPLEMENTARY CEMENTITIOUS MATERIALS (SCM)**

Fly ash shall conform to the requirements in AASHTO Designation: M 295, Class F, and the following:

- A. Calcium oxide content shall not exceed 10 percent.
- B. The available alkali, as sodium oxide equivalent, shall not exceed 1.5 percent when determined in conformance with the requirements in ASTM Designation: C 311 or the total alkali, as sodium oxide equivalent, shall not exceed 5.0 percent when determined in conformance with the requirements in AASHTO Designation: T 105.
- C. Commingling of fly ash from different sources at uncontrolled ratios is permissible only if the following criteria are satisfied:
  1. Sources of fly ash to be commingled shall be on the approved list of materials for use in concrete.
  2. Testing of the commingled product is the responsibility of the fly ash supplier.
  3. Each fly ash's running average of density shall not differ from any other by more than 0.25g/cm<sup>3</sup> at the time of commingling.
  4. Each fly ash's running average of loss on ignition shall not differ from any other by more than one percent at the time of commingling.
  5. The final product of commingled fly ash shall conform to the requirement in AASHTO Designation: M 295.

Raw or calcined natural pozzolans shall conform to the requirements in AASHTO Designation: M 295, Class N and the following requirements:

- A. Calcium oxide content shall not exceed 10 percent.
- B. The available alkali, as sodium oxide equivalent, shall not exceed 1.5 percent when determined in conformance with the requirements in ASTM Designation: C 311 or the total alkali, as sodium oxide equivalent, shall not exceed 5.0 percent when determined in conformance with the requirements in AASHTO Designation: T 105.

Ground Granulated Blast Furnace Slag (GGBFS) shall conform to the requirements in AASHTO Designation: M 302, Grade 100 or Grade 120.

Silica Fume shall conform to the requirements of AASHTO Designation: M 307 with reduction in mortar expansion of 80 percent, minimum, using the cement from the proposed mix design.

### **90-2.01C REQUIRED USE OF SUPPLEMENTARY CEMENTITIOUS MATERIALS**

The amount of portland cement and SCM used in portland cement concrete shall conform to the minimum cementitious material content provisions in Section 90-1.01, "Description," or Section 90-4.05, "Optional Use of Chemical Admixtures," and the following:

- A. If a blended cement conforming to the provisions in Section 90-2.01A, "Cement," is used, the minimum amount of SCM incorporated into the cement shall conform to the provisions in this Section 90-2.01C.
- B. Fly ash or natural pozzolan, silica fume, or GGBFS shall not be used with Type IP or Type IS cements.

Use of SCMs shall conform to the following:

- A. If fly ash or natural pozzolan is used:
  - 1. The minimum amount of portland cement shall not be less than 75 percent by mass of the specified minimum cementitious material content.
  - 2. The minimum amount of fly ash or natural pozzolan shall be:
    - a. Fifteen percent by mass of the total amount of cementitious material if the calcium oxide content of fly ash or natural pozzolan is equal to or less than 2 percent by mass;
    - b. Twenty-five percent by mass of the total amount of cementitious material if the calcium oxide content of fly ash or natural pozzolan is greater than 2 percent by mass.
- B. The total amount of fly ash or natural pozzolan shall not exceed 35 percent by mass of the total amount of cementitious material to be used in the mix. If Section 90-1.01, "Description," specifies a maximum cementitious material content in kilograms per cubic meter, the total mass of portland cement and fly ash or natural pozzolan per cubic meter shall not exceed the specified maximum cementitious material content.
- C. If silica fume is used:
  - 1. The amount of silica fume shall not be less than 10 percent by mass of the total amount of cementitious material.
  - 2. The amount of portland cement shall not be less than 75 percent by mass of the specified minimum cementitious material content.
  - 3. If Section 90-1.01, "Description," specifies a maximum cementitious material content in kilograms per cubic meter, the total mass of portland cement and silica fume per cubic meter shall not exceed the specified maximum cementitious material content.
- D. If GGBFS is used:
  - 1. The minimum amount of GGBFS shall be either:
    - a. Forty percent of the total cementitious material to be used, if the aggregates used in the concrete are on the Department's list of "Approved Aggregates For Use in Concrete with Reduced Fly Ash."
    - b. No less than 50 percent.
  - 2. The amount of GGBFS shall not exceed 60 percent by mass of the total amount of cementitious materials to be used.

## **90-2.02 AGGREGATES**

Aggregates shall be free from deleterious coatings, clay balls, roots, bark, sticks, rags, and other extraneous material.

The Contractor shall provide safe and suitable facilities, including necessary splitting devices for obtaining samples of aggregates, in conformance with California Test 125.

Aggregates shall be of such character that it will be possible to produce workable concrete within the limits of water content provided in Section 90-6.06, "Amount of Water and Penetration."

Aggregates shall have not more than 10 percent loss when tested for soundness in conformance with the requirements in California Test 214. The soundness requirement for fine aggregate will be waived, provided that the durability index,  $D_f$ , of the fine aggregate is 60 or greater when tested for durability in conformance with California Test 229.

If the results of any one or more of the Cleanness Value, Sand Equivalent, or aggregate grading tests do not meet the requirements specified for "Operating Range" but all meet the "Contract Compliance" requirements, the placement of concrete shall be suspended at the completion of the current pour until tests or other information indicate that the next material to be used in the work will comply with the requirements specified for "Operating Range."

If the results of either or both the Cleanness Value and coarse aggregate grading tests do not meet the requirements specified for "Contract Compliance," the concrete that is represented by the tests shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place, and the Contractor shall pay to the State \$4.60 per cubic meter for paving concrete and \$7.20 per cubic meter for all other concrete for the concrete represented

by these tests and left in place. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract.

If the results of either or both the Sand Equivalent and fine aggregate grading tests do not meet the requirements specified for "Contract Compliance," the concrete that is represented by the tests shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place and the Contractor shall pay to the State \$4.60 per cubic meter for paving concrete and \$7.20 per cubic meter for all other concrete for the concrete represented by these tests and left in place. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract.

The 2 preceding paragraphs apply individually to the "Contract Compliance" requirements for coarse aggregate and fine aggregate. When both coarse aggregate and fine aggregate do not conform to the "Contract Compliance" requirements, both paragraphs shall apply. The payments specified in those paragraphs are in addition to any payments made in conformance with the provisions in Section 90-1.01, "Description."

No single Cleanness Value, Sand Equivalent, or aggregate grading test shall represent more than 250 m<sup>3</sup> of concrete or one day's pour, whichever is smaller.

When the source of an aggregate is changed, the Contractor shall adjust the mix proportions and submit in writing to the Engineer a copy of the mix design before using the aggregates.

**90-2.02A COARSE AGGREGATE**

Coarse aggregate shall consist of gravel, crushed gravel, crushed rock, reclaimed aggregate, crushed air-cooled iron blast furnace slag or combinations thereof. Crushed air-cooled blast furnace slag shall not be used in reinforced or prestressed concrete.

Reclaimed aggregate is aggregate that has been recovered from plastic concrete by washing away the cementitious material. Reclaimed aggregate shall conform to all aggregate requirements.

Coarse aggregate shall conform to the following quality requirements:

Tests	California Test	Requirements
Loss in Los Angeles Rattler (after 500 revolutions)	211	45% max.
Cleanness Value		
Operating Range	227	75 min.
Contract Compliance	227	71 min.

In lieu of the above Cleanness Value requirements, a Cleanness Value "Operating Range" limit of 71, minimum, and a Cleanness Value "Contract Compliance" limit of 68, minimum, will be used to determine the acceptability of the coarse aggregate if the Contractor furnishes a Certificate of Compliance, as provided in Section 6-1.07, "Certificates of Compliance," certifying that:

- A. Coarse aggregate sampled at the completion of processing at the aggregate production plant had a Cleanness Value of not less than 82 when tested in conformance with the requirements in California Test 227; and
- B. Prequalification tests performed in conformance with the requirements in California Test 549 indicated that the aggregate would develop a relative strength of not less than 95 percent and would have a relative shrinkage not greater than 105 percent, based on concrete.

**90-2.02B FINE AGGREGATE**

Fine aggregate shall consist of natural sand, manufactured sand produced from larger aggregate or a combination thereof. Manufactured sand shall be well graded.

Fine aggregate shall conform to the following quality requirements:

Test	California Test	Requirements
Organic Impurities	213	Satisfactory <sup>a</sup>
Mortar Strengths Relative to Ottawa Sand	515	95%, min.
Sand Equivalent:		
Operating Range	217	75, min.
Contract Compliance	217	71, min.

- a Fine aggregate developing a color darker than the reference standard color solution may be accepted if it is determined by the Engineer, from mortar strength tests, that a darker color is acceptable.

In lieu of the above Sand Equivalent requirements, a Sand Equivalent "Operating Range" limit of 71, minimum, and a Sand Equivalent "Contract Compliance" limit of 68, minimum, will be used to determine the acceptability of the fine aggregate if the Contractor furnishes a Certificate of Compliance, as provided in Section 6-1.07, "Certificates of Compliance," certifying that:

- A. Fine aggregate sampled at the completion of processing at the aggregate production plant had a Sand Equivalent value of not less than 82 when tested by California Test 217; and
- B. Prequalification tests performed in conformance with California Test 549 indicated that the aggregate would develop a relative strength of not less than 95 percent and would have a relative shrinkage not greater than 105 percent, based on concrete.

### 90-2.03 WATER

In conventionally reinforced concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 1000 parts per million of chlorides as Cl, when tested in conformance with California Test 422, nor more than 1300 parts per million of sulfates as SO<sub>4</sub>, when tested in conformance with California Test 417. In prestressed concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 650 parts per million of chlorides as Cl, when tested in conformance with California Test 422, nor more than 1300 parts per million of sulfates as SO<sub>4</sub>, when tested in conformance with California Test 417. In no case shall the water contain an amount of impurities that will cause either: 1) a change in the setting time of cement of more than 25 percent when tested in conformance with the requirements in ASTM Designation: C 191 or ASTM Designation: C 266 or 2) a reduction in the compressive strength of mortar at 14 days of more than 5 percent, when tested in conformance with the requirements in ASTM Designation: C 109, when compared to the results obtained with distilled water or deionized water, tested in conformance with the requirements in ASTM Designation: C 109.

In nonreinforced concrete work, the water for curing, for washing aggregates and for mixing shall be free from oil and shall not contain more than 2000 parts per million of chlorides as Cl, when tested in conformance with California Test 422, or more than 1500 parts per million of sulfates as SO<sub>4</sub>, when tested in conformance with California Test 417.

In addition to the above provisions, water for curing concrete shall not contain impurities in a sufficient amount to cause discoloration of the concrete or produce etching of the surface.

Water reclaimed from mixer wash-out operations may be used in mixing concrete. The water shall not contain coloring agents or more than 300 parts per million of alkalis (Na<sub>2</sub>O + 0.658 K<sub>2</sub>O) as determined on the filtrate. The specific gravity of the water shall not exceed 1.03 and shall not vary more than ±0.010 during a day's operations.

### 90-2.04 ADMIXTURE MATERIALS

Admixture materials shall conform to the requirements in the following ASTM Designations:

- A. Chemical Admixtures—ASTM Designation: C 494.
- B. Air-entraining Admixtures—ASTM Designation: C 260.

## 90-3 AGGREGATE GRADINGS

### 90-3.01 GENERAL

Before beginning concrete work, the Contractor shall submit in writing to the Engineer the gradation of the primary aggregate nominal sizes that the Contractor proposes to furnish. If a primary coarse aggregate or the fine aggregate is separated into 2 or more sizes, the proposed gradation shall consist of the gradation for each individual size, and the proposed proportions of each individual size, combined mathematically to indicate one proposed gradation. The proposed gradation shall meet the grading requirements shown in the table in this section, and shall show the percentage passing each of the sieve sizes used in determining the end result.

The Engineer may waive, in writing, the gradation requirements in this Section 90-3.01 and in Sections 90-3.02, "Coarse Aggregate Grading," 90-3.03, "Fine Aggregate Grading," and 90-3.04, "Combined Aggregate Gradings," if, in the Engineer's opinion, furnishing the gradation is not necessary for the type or amount of concrete work to be constructed.

Gradations proposed by the Contractor shall be within the following percentage passing limits:

Primary Aggregate Nominal Size	Sieve Size	Limits of Proposed Gradation
37.5-mm x 19-mm	25-mm	19 - 41
25-mm x 4.75-mm	19-mm	52 - 85
25-mm x 4.75-mm	9.5-mm	15 - 38
12.5-mm x 4.75-mm	9.5-mm	40 - 78
9.5-mm x 2.36-mm	9.5-mm	50 - 85
Fine Aggregate	1.18-mm	55 - 75
Fine Aggregate	600- $\mu$ m	34 - 46
Fine Aggregate	300- $\mu$ m	16 - 29

Should the Contractor change the source of supply, the Contractor shall submit in writing to the Engineer the new gradations before their intended use.

### 90-3.02 COARSE AGGREGATE GRADING

The grading requirements for coarse aggregates are shown in the following table for each size of coarse aggregate:

Sieve Sizes	Percentage Passing Primary Aggregate Nominal Sizes							
	37.5-mm x 19-mm		25-mm x 4.75-mm		12.5-mm x 4.75-mm		9.5-mm x 2.36-mm	
	Operating Range	Contract Compliance	Operating Range	Contract Compliance	Operating Range	Contract Compliance	Operating Range	Contract Compliance
50-mm	100	100	—	—	—	—	—	—
37.5-mm	88 - 100	85 - 100	100	100	—	—	—	—
25-mm	X $\pm$ 18	X $\pm$ 25	88 - 100	86 - 100	—	—	—	—
19-mm	0 - 17	0 - 20	X $\pm$ 15	X $\pm$ 22	100	100	—	—
12.5-mm	—	—	—	—	82 - 100	80 - 100	100	100
9.5-mm	0 - 7	0 - 9	X $\pm$ 15	X $\pm$ 22	X $\pm$ 15	X $\pm$ 22	X $\pm$ 15	X $\pm$ 20
4.75-mm	—	—	0 - 16	0 - 18	0 - 15	0 - 18	0 - 25	0 - 28
2.36-mm	—	—	0 - 6	0 - 7	0 - 6	0 - 7	0 - 6	0 - 7

In the above table, the symbol X is the gradation that the Contractor proposes to furnish for the specific sieve size as provided in Section 90-3.01, "General."

Coarse aggregate for the 37.5-mm, maximum, combined aggregate grading as provided in Section 90-3.04, "Combined Aggregate Gradings," shall be furnished in 2 or more primary aggregate nominal sizes. Each primary aggregate nominal size may be separated into 2 sizes and stored separately, provided that the combined material conforms to the grading requirements for that particular primary aggregate nominal size.

When the 25-mm, maximum, combined aggregate grading as provided in Section 90-3.04, "Combined Aggregate Gradings," is to be used, the coarse aggregate may be separated into 2 sizes and stored separately, provided that the combined material shall conform to the grading requirements for the 25-mm x 4.75-mm primary aggregate nominal size.

### 90-3.03 FINE AGGREGATE GRADING

Fine aggregate shall be graded within the following limits:

Sieve Sizes	Percentage Passing	
	Operating Range	Contract Compliance
9.5-mm	100	100
4.75-mm	95 - 100	93 - 100
2.36-mm	65 - 95	61 - 99
1.18-mm	X ±10	X ±13
600-µm	X ±9	X ±12
300-µm	X ±6	X ±9
150-µm	2 - 12	1 - 15
75-µm	0 - 8	0 - 10

In the above table, the symbol X is the gradation that the Contractor proposes to furnish for the specific sieve size as provided in Section 90-3.01, "General."

In addition to the above required grading analysis, the distribution of the fine aggregate sizes shall be such that the difference between the total percentage passing the 1.18-mm sieve and the total percentage passing the 600-µm sieve shall be between 10 and 40, and the difference between the percentage passing the 600-µm and 300-µm sieves shall be between 10 and 40.

Fine aggregate may be separated into 2 or more sizes and stored separately, provided that the combined material conforms to the grading requirements specified in this Section 90-3.03.

#### 90-3.04 COMBINED AGGREGATE GRADINGS

Combined aggregate grading limits shall be used only for the design of concrete mixes. Concrete mixes shall be designed so that aggregates are combined in proportions that shall produce a mixture within the grading limits for combined aggregates as specified herein.

The combined aggregate grading, except when otherwise specified in these specifications or the special provisions, shall be either the 37.5-mm, maximum grading, or the 25-mm, maximum grading, at the option of the Contractor.

Grading Limits of Combined Aggregates

Sieve Sizes	Percentage Passing			
	37.5-mm Max.	25-mm Max.	12.5-mm Max.	9.5-mm Max.
50-mm	100	—	—	—
37.5-mm	90 - 100	100	—	—
25-mm	50 - 86	90 - 100	—	—
19-mm	45 - 75	55 - 100	100	—
12.5-mm	—	—	90-100	100
9.5-mm	38 - 55	45 - 75	55 - 86	50 - 100
4.75-mm	30 - 45	35 - 60	45 - 63	45 - 63
2.36-mm	23 - 38	27 - 45	35 - 49	35 - 49
1.18-mm	17 - 33	20 - 35	25 - 37	25 - 37
600-µm	10 - 22	12 - 25	15 - 25	15 - 25
300-µm	4 - 10	5 - 15	5 - 15	5 - 15
150-µm	1 - 6	1 - 8	1 - 8	1 - 8
75-µm	0 - 3	0 - 4	0 - 4	0 - 4

Changes from one grading to another shall not be made during the progress of the work unless permitted by the Engineer.

### 90-4 ADMIXTURES

#### 90-4.01 GENERAL

Admixtures used in portland cement concrete shall conform to and be used in conformance with the provisions in this Section 90-4 and the special provisions. Admixtures shall be used when specified or ordered by the Engineer and may be used at the Contractor's option as provided herein.

Chemical admixtures and air-entraining admixtures containing chlorides as Cl in excess of one percent by mass of admixture, as determined by California Test 415, shall not be used.

Admixtures shall be uniform in properties throughout their use in the work. Should it be found that an admixture as furnished is not uniform in properties, its use shall be discontinued.

If more than one admixture is used, the admixtures shall be compatible with each other so that the desirable effects of all admixtures used will be realized.

Chemical admixtures shall be used in conformance with the manufacturer's written recommendations.

#### **90-4.02 MATERIALS**

Admixture materials shall conform to the provisions in Section 90-2.04, "Admixture Materials."

#### **90-4.03 ADMIXTURE APPROVAL**

No admixture brand shall be used in the work unless it is on the Department's current list of approved brands for the type of admixture involved.

Admixture brands will be considered for addition to the approved list if the manufacturer of the admixture submits to the Transportation Laboratory a sample of the admixture accompanied by certified test results demonstrating that the admixture complies with the requirements in the appropriate ASTM Designation and these specifications. The sample shall be sufficient to permit performance of all required tests. Approval of admixture brands will be dependent upon a determination as to compliance with the requirements, based on the certified test results submitted, together with tests the Department may elect to perform.

If the Contractor proposes to use an admixture of a brand and type on the current list of approved admixture brands, the Contractor shall furnish a Certificate of Compliance from the manufacturer, as provided in Section 6-1.07, "Certificates of Compliance," certifying that the admixture furnished is the same as that previously approved. If a previously approved admixture is not accompanied by a Certificate of Compliance, the admixture shall not be used in the work until the Engineer has had sufficient time to make the appropriate tests and has approved the admixture for use. The Engineer may take samples for testing at any time, whether or not the admixture has been accompanied by a Certificate of Compliance.

#### **90-4.04 REQUIRED USE OF CHEMICAL ADMIXTURES**

If the use of a chemical admixture is specified, the admixture shall be used at the dosage specified, except that if no dosage is specified, the admixture shall be used at the dosage normally recommended by the manufacturer of the admixture.

#### **90-4.05 OPTIONAL USE OF CHEMICAL ADMIXTURES**

The Contractor may use Type A or F, water-reducing; Type B, retarding; or Type D or G, water-reducing and retarding admixtures as described in ASTM Designation: C 494 to conserve cementitious material or to facilitate any concrete construction application subject to the following conditions:

- A. If a water-reducing admixture or a water-reducing and retarding admixture is used, the cementitious material content specified or ordered may be reduced by a maximum of 5 percent by mass, except that the resultant cementitious material content shall be not less than 300 kilograms per cubic meter; and
- B. When a reduction in cementitious material content is made, the dosage of admixture used shall be the dosage used in determining approval of the admixture.

Unless otherwise specified, a Type C accelerating chemical admixture conforming to the requirements in ASTM Designation: C 494, may be used in portland cement concrete. Inclusion in the mix design submitted for approval will not be required provided that the admixture is added to counteract changing conditions that contribute to delayed setting of the portland cement concrete, and the use or change in dosage of the admixture is approved in writing by the Engineer.

#### **90-4.06 REQUIRED USE OF AIR-ENTRAINING ADMIXTURES**

When air-entrainment is specified or ordered by the Engineer, the air-entraining admixture shall be used in amounts to produce a concrete having the specified air content as determined by California Test 504.

#### **90-4.07 OPTIONAL USE OF AIR-ENTRAINING ADMIXTURES**

When air-entrainment has not been specified or ordered by the Engineer, the Contractor will be permitted to use an air-entraining admixture to facilitate the use of any construction procedure or equipment provided that the average air content, as determined by California Test 504, of 3 successive tests does not exceed 4 percent, and no single test value exceeds 5.5 percent. If the Contractor elects to use an air-entraining admixture in concrete for pavement, the Contractor shall so indicate at the time the Contractor designates the source of aggregate.

#### **90-4.08 BLANK**

## **90-4.09 BLANK**

### **90-4.10 PROPORTIONING AND DISPENSING LIQUID ADMIXTURES**

Chemical admixtures and air-entraining admixtures shall be dispensed in liquid form. Dispensers for liquid admixtures shall have sufficient capacity to measure at one time the prescribed quantity required for each batch of concrete. Each dispenser shall include a graduated measuring unit into which liquid admixtures are measured to within  $\pm 5$  percent of the prescribed quantity for each batch. Dispensers shall be located and maintained so that the graduations can be accurately read from the point at which proportioning operations are controlled to permit a visual check of batching accuracy prior to discharge. Each measuring unit shall be clearly marked for the type and quantity of admixture.

Each liquid admixture dispensing system shall be equipped with a sampling device consisting of a valve located in a safe and readily accessible position such that a sample of the admixture may be withdrawn slowly by the Engineer.

If more than one liquid admixture is used in the concrete mix, each liquid admixture shall have a separate measuring unit and shall be dispensed by injecting equipment located in such a manner that the admixtures are not mixed at high concentrations and do not interfere with the effectiveness of each other. When air-entraining admixtures are used in conjunction with other liquid admixtures, the air-entraining admixture shall be the first to be incorporated into the mix, unless it is demonstrated that a different sequence improves performance.

When automatic proportioning devices are required for concrete pavement, dispensers for liquid admixtures shall operate automatically with the batching control equipment. The dispensers shall be equipped with an automatic warning system in good operating condition that will provide a visible or audible signal at the point at which proportioning operations are controlled when the quantity of admixture measured for each batch of concrete varies from the preselected dosage by more than 5 percent, or when the entire contents of the measuring unit are not emptied from the dispenser into each batch of concrete.

Unless liquid admixtures are added to premeasured water for the batch, their discharge into the batch shall be arranged to flow into the stream of water so that the admixtures are well dispersed throughout the batch, except that air-entraining admixtures may be dispensed directly into moist sand in the batching bins provided that adequate control of the air content of the concrete can be maintained.

Liquid admixtures requiring dosages greater than  $2.5 \text{ L/m}^3$  shall be considered to be water when determining the total amount of free water as specified in Section 90-6.06, "Amount of Water and Penetration."

## **90-4.11 BLANK**

## **90-5 PROPORTIONING**

### **90-5.01 STORAGE OF AGGREGATES**

Aggregates shall be stored or stockpiled in such a manner that separation of coarse and fine particles of each size shall be avoided and the various sizes shall not become intermixed before proportioning.

Aggregates shall be stored or stockpiled and handled in a manner that prevent contamination by foreign materials. In addition, storage of aggregates at batching or mixing facilities that are erected subsequent to the award of the contract and that furnish concrete to the project shall conform to the following:

- A. Intermingling of the different sizes of aggregates shall be positively prevented. The Contractor shall take the necessary measures to prevent intermingling. The preventive measures may include, but are not necessarily limited to, physical separation of stockpiles or construction of bulkheads of adequate length and height; and
- B. Contamination of aggregates by contact with the ground shall be positively prevented. The Contractor shall take the necessary measures to prevent contamination. The preventive measures shall include, but are not necessarily limited to, placing aggregates on wooden platforms or on hardened surfaces consisting of portland cement concrete, asphalt concrete, or cement treated material.

In placing aggregates in storage or in moving the aggregates from storage to the weigh hopper of the batching plant, any method that may cause segregation, degradation, or the combining of materials of different gradings that will result in any size of aggregate at the weigh hopper failing to meet the grading requirements shall be discontinued. Any method of handling aggregates that results in excessive breakage of particles shall be discontinued. The use of suitable devices to reduce impact of falling aggregates may be required by the Engineer.

### **90-5.02 PROPORTIONING DEVICES**

Weighing, measuring, or metering devices used for proportioning materials shall conform to the requirements in Section 9-1.01, "Measurement of Quantities," and this Section 90-5.02. In addition, automatic weighing systems shall comply with the requirements for automatic proportioning devices in Section 90-5.03A, "Proportioning for Pavement."

Automatic devices shall be automatic to the extent that the only manual operation required for proportioning the aggregates, cement, and supplementary cementitious material for one batch of concrete is a single operation of a switch or starter.

Proportioning devices shall be tested as frequently as the Engineer may deem necessary to ensure their accuracy.

Weighing equipment shall be insulated against vibration or movement of other operating equipment in the plant. When the plant is in operation, the mass of each batch of material shall not vary from the mass designated by the Engineer by more than the tolerances specified herein.

Equipment for cumulative weighing of aggregate shall have a zero tolerance of  $\pm 0.5$  percent of the designated total batch mass of the aggregate. For systems with individual weigh hoppers for the various sizes of aggregate, the zero tolerance shall be  $\pm 0.5$  percent of the individual batch mass designated for each size of aggregate. Equipment for cumulative weighing of cement and supplementary cementitious material shall have a zero tolerance of  $\pm 0.5$  percent of the designated total batch mass of the cement and supplementary cementitious material. Equipment for weighing cement or supplementary cementitious material separately shall have a zero tolerance of  $\pm 0.5$  percent of their designated individual batch masses. Equipment for measuring water shall have a zero tolerance of  $\pm 0.5$  percent of its designated mass or volume.

The mass indicated for any batch of material shall not vary from the preselected scale setting by more than the following:

- A. Aggregate weighed cumulatively shall be within 1.0 percent of the designated total batch mass of the aggregate. Aggregates weighed individually shall be within 1.5 percent of their respective designated batch masses; and
- B. Cement shall be 99 to 102 percent of its designated batch mass. When weighed individually, supplementary cementitious material shall be 99 to 102 percent of its designated batch mass. When supplementary cementitious material and cement are permitted to be weighed cumulatively, cement shall be weighed first to 99 to 102 percent of its designated batch mass, and the total for cement and supplementary cementitious material shall be 99 to 102 percent of the sum of their designated batch masses; and
- C. Water shall be within 1.5 percent of its designated mass or volume.

Each scale graduation shall be approximately 0.001 of the total capacity of the scale. The capacity of scales for weighing cement, supplementary cementitious material, or cement plus supplementary cementitious material and aggregates shall not exceed that of commercially available scales having single graduations indicating a mass not exceeding the maximum permissible mass variation above, except that no scale shall be required having a capacity of less than 500 kg, with 0.5-kg graduations.

### **90-5.03 PROPORTIONING**

Proportioning shall consist of dividing the aggregates into the specified sizes, each stored in a separate bin, and combining them with cementitious material and water as provided in these specifications. Aggregates shall be proportioned by mass.

At the time of batching, aggregates shall have been dried or drained sufficiently to result in a stable moisture content such that no visible separation of water from aggregate will take place during transportation from the proportioning plant to the point of mixing. In no event shall the free moisture content of the fine aggregate at the time of batching exceed 8 percent of its saturated, surface-dry mass.

Should separate supplies of aggregate material of the same size group, but of different moisture content or specific gravity or surface characteristics affecting workability, be available at the proportioning plant, withdrawals shall be made from one supply exclusively and the materials therein completely exhausted before starting upon another.

Bulk Type IP (MS) cement shall be weighed in an individual hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer.

Bulk cement and supplementary cementitious material may be weighed in separate, individual weigh hoppers or may be weighed in the same weigh hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer. If the cement and supplementary cementitious material are weighed cumulatively, the cement shall be weighed first.

If cement and supplementary cementitious material are weighed in separate weigh hoppers, the weigh systems for the proportioning of the aggregate, the cement, and the supplementary cementitious material shall be individual and distinct from all other weigh systems. Each weigh system shall be equipped with a hopper, a lever system, and an indicator to constitute an individual and independent material weighing device. The cement and the supplementary cementitious material shall be discharged into the mixer simultaneously with the aggregate.

The scales and weigh hoppers for bulk weighing cement, supplementary cementitious material, or cement plus supplementary cementitious material shall be separate and distinct from the aggregate weighing equipment.

For batches of one cubic meter or more, the batching equipment shall conform to one of the following combinations:

- A. Separate boxes and separate scale and indicator for weighing each size of aggregate.
- B. Single box and scale indicator for all aggregates.
- C. Single box or separate boxes and automatic weighing mechanism for all aggregates.

In order to check the accuracy of batch masses, the gross mass and tare mass of batch trucks, truck mixers, truck agitators, and non-agitating hauling equipment shall be determined when ordered by the Engineer. The equipment shall be weighed on scales designated by the Engineer.

### **90-5.03A PROPORTIONING FOR PAVEMENT**

Aggregates and bulk supplementary cementitious material for use in pavement shall be proportioned by mass by means of automatic proportioning devices of approved type conforming to these specifications.

The Contractor shall install and maintain in operating condition an electronically actuated moisture meter that will indicate, on a readily visible scale, changes in the moisture content of the fine aggregate as it is batched within a sensitivity of 0.5 percent by mass of the fine aggregate.

The batching of cement, supplementary cementitious material, or cement plus supplementary cementitious material and aggregate shall be interlocked so that a new batch cannot be started until all weigh hoppers are empty, the proportioning devices are within zero tolerance, and the discharge gates are closed. The interlock shall permit no part of the batch to be discharged until all aggregate hoppers and the cement and supplementary cementitious material hoppers or the cement plus supplementary cementitious material hopper are charged with masses that are within the tolerances specified in Section 90-5.02, "Proportioning Devices."

If interlocks are required for cement and supplementary cementitious material charging mechanisms and cement and supplementary cementitious material are weighed cumulatively, their charging mechanisms shall be interlocked to prevent the introduction of mineral admixture until the mass of cement in the cement weigh hopper is within the tolerances specified in Section 90-5.02, "Proportioning Devices."

If concrete is completely mixed in stationary paving mixers, the supplementary cementitious materials shall be weighed in a separate weigh hopper and the supplementary cementitious material and cement shall be introduced simultaneously into the mixer proportionately with the aggregate. If the Contractor provides certification that the stationary mixer is capable of mixing the cement, supplementary cementitious material, aggregates, and water uniformly before discharge, weighing the supplementary cementitious material cumulatively with the cement is permitted. Certification shall contain the following:

- A. Test results for 2 compressive strength test cylinders of concrete taken within the first one-third and 2 compressive strength test cylinders of concrete taken within the last one-third of the concrete discharged from a single batch from the stationary paving mixer. Strength tests and cylinder preparation will be in conformance with the provisions of Section 90-9, "Compressive Strength";
- B. Calculations demonstrating that the difference in the averages of 2 compressive strengths taken in the first one-third is no greater than 7.5 percent different than the averages of 2 compressive strengths taken in the last one-third of the concrete discharged from a single batch from the stationary paving mixer. Strength tests and cylinder preparation will be in conformance with the provisions of Section 90-9, "Compressive Strength;" and
- C. The mixer rotation speed and time of mixing before discharge that are required to produce a mix that meets the requirements above.

The discharge gate on the cement and supplementary cementitious material hoppers or the cement plus supplementary cementitious material hopper shall be designed to permit regulating the flow of cement, supplementary cementitious material, or cement plus supplementary cementitious material into the aggregate as directed by the Engineer.

If separate weigh boxes are used for each size of aggregate, the discharge gates shall permit regulating the flow of each size of aggregate as directed by the Engineer.

Material discharged from the several bins shall be controlled by gates or by mechanical conveyors. The means of withdrawal from the several bins, and of discharge from the weigh box, shall be interlocked so that not more than one bin can discharge at a time, and so that the weigh box cannot be tripped until the required quantity from each of the several bins has been deposited therein. Should a separate weigh box be used for each size of aggregate, all may be operated and discharged simultaneously.

If the discharge from the several bins is controlled by gates, each gate shall be actuated automatically so that the required mass is discharged into the weigh box, after which the gate shall automatically close and lock.

The automatic weighing system shall be designed so that all proportions required may be set on the weighing controller at the same time.

## **90-6 MIXING AND TRANSPORTING**

### **90-6.01 GENERAL**

Concrete shall be mixed in mechanically operated mixers, except that when permitted by the Engineer, batches not exceeding 0.25-m<sup>3</sup> may be mixed by hand methods in conformance with the provisions in Section 90-6.05, "Hand-Mixing."

Equipment having components made of aluminum or magnesium alloys that would have contact with plastic concrete during mixing, transporting, or pumping of portland cement concrete shall not be used.

Concrete shall be homogeneous and thoroughly mixed, and there shall be no lumps or evidence of undispersed cementitious material.

Uniformity of concrete mixtures will be determined by differences in penetration as determined by California Test 533, or slump as determined by ASTM Designation: C 143, and by variations in the proportion of coarse aggregate as determined by California Test 529.

When the mix design specifies a penetration value, the difference in penetration, determined by comparing penetration tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed 10 mm. When the mix design specifies a slump value, the difference in slump, determined by comparing slump tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed the values given in the table below. Variation in the proportion of coarse aggregate will be determined by comparing the results of tests of 2 samples of mixed concrete from the same batch or truck mixer load and the difference between the 2 results shall not exceed 100 kg per cubic meter of concrete.

Average Slump	Maximum Permissible Difference
Less than 100-mm	25-mm
100-mm to 150-mm	38-mm
Greater than 150-mm to 225-mm	50-mm

The Contractor shall furnish samples of the freshly mixed concrete and provide satisfactory facilities for obtaining the samples.

#### **90-6.02 MACHINE MIXING**

Concrete mixers may be of the revolving drum or the revolving blade type, and the mixing drum or blades shall be operated uniformly at the mixing speed recommended by the manufacturer. Mixers and agitators that have an accumulation of hard concrete or mortar shall not be used.

The temperature of mixed concrete, immediately before placing, shall be not less than 10°C or more than 32°C. Aggregates and water shall be heated or cooled as necessary to produce concrete within these temperature limits. Neither aggregates nor mixing water shall be heated to exceed 65°C. If ice is used to cool the concrete, discharge of the mixer will not be permitted until all ice is melted.

The batch shall be so charged into the mixer that some water will enter in advance of cementitious materials and aggregates. All water shall be in the drum by the end of the first one-fourth of the specified mixing time.

Cementitious materials shall be batched and charged into the mixer by means that will not result either in loss of cementitious materials due to the effect of wind, in accumulation of cementitious materials on surfaces of conveyors or hoppers, or in other conditions that reduce or vary the required quantity of cementitious material in the concrete mixture.

Paving and stationary mixers shall be operated with an automatic timing device. The timing device and discharge mechanism shall be interlocked so that during normal operation no part of the batch will be discharged until the specified mixing time has elapsed.

The total elapsed time between the intermingling of damp aggregates and all cementitious materials and the start of mixing shall not exceed 30 minutes.

The size of batch shall not exceed the manufacturer's guaranteed capacity.

When producing concrete for pavement or base, suitable batch counters shall be installed and maintained in good operating condition at job site batching plants and stationary mixers. The batch counters shall indicate the exact number of batches proportioned and mixed.

Concrete shall be mixed and delivered to the job site by means of one of the following combinations of operations:

- A. Mixed completely in a stationary mixer and the mixed concrete transported to the point of delivery in truck agitators or in nonagitating hauling equipment (central-mixed concrete).
- B. Mixed partially in a stationary mixer, and the mixing completed in a truck mixer (shrink-mixed concrete).
- C. Mixed completely in a truck mixer (transit-mixed concrete).
- D. Mixed completely in a paving mixer.

Agitators may be truck mixers operating at agitating speed or truck agitators. Each mixer and agitator shall have attached thereto in a prominent place a metal plate or plates on which is plainly marked the various uses for which the equipment is designed, the manufacturer's guaranteed capacity of the drum or container in terms of the volume of mixed concrete and the speed of rotation of the mixing drum or blades.

Truck mixers shall be equipped with electrically or mechanically actuated revolution counters by which the number of revolutions of the drum or blades may readily be verified.

When shrink-mixed concrete is furnished, concrete that has been partially mixed at a central plant shall be transferred to a truck mixer and all requirements for transit-mixed concrete shall apply. No credit in the number of revolutions at mixing speed will be allowed for partial mixing in a central plant.

### **90-6.03 TRANSPORTING MIXED CONCRETE**

Mixed concrete may be transported to the delivery point in truck agitators or truck mixers operating at the speed designated by the manufacturer of the equipment as agitating speed, or in nonagitating hauling equipment, provided the consistency and workability of the mixed concrete upon discharge at the delivery point is suitable for adequate placement and consolidation in place, and provided the mixed concrete after hauling to the delivery point conforms to the provisions in Section 90-6.01, "General."

Truck agitators shall be loaded not to exceed the manufacturer's guaranteed capacity and shall maintain the mixed concrete in a thoroughly mixed and uniform mass during hauling.

Bodies of nonagitating hauling equipment shall be constructed so that leakage of the concrete mix, or any part thereof, will not occur at any time.

Concrete hauled in open-top vehicles shall be protected during hauling against rain or against exposure to the sun for more than 20 minutes when the ambient temperature exceeds 24°C.

No additional mixing water shall be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer. If the Engineer authorizes additional water to be incorporated into the concrete, the drum shall be revolved not less than 30 revolutions at mixing speed after the water is added and before discharge is commenced.

The rate of discharge of mixed concrete from truck mixer-agitators shall be controlled by the speed of rotation of the drum in the discharge direction with the discharge gate fully open.

If a truck mixer or agitator is used for transporting concrete to the delivery point, discharge shall be completed within 1.5 hours or before 250 revolutions of the drum or blades, whichever occurs first, after the introduction of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or if the temperature of the concrete is 30°C or above, the time allowed may be less than 1.5 hours. If an admixture is used to retard the set time, the temperature of the concrete shall not exceed 30°C, the time limit shall be 2 hours, and the revolution limitation shall be 300.

If nonagitating hauling equipment is used for transporting concrete to the delivery point, discharge shall be completed within one hour after the addition of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C or above, the time between the introduction of cement to the aggregates and discharge shall not exceed 45 minutes.

Each load of concrete delivered at the job site shall be accompanied by a weighmaster certificate showing the mix identification number, nonrepeating load number, date and time at which the materials were batched, the total amount of water added to the load, and for transit-mixed concrete, the reading of the revolution counter at the time the truck mixer is charged with cement. This weighmaster certificate shall also show the actual scale masses (kilograms) for the ingredients batched. Theoretical or target batch masses shall not be used as a substitute for actual scale masses.

Weighmaster certificates shall be provided in printed form, or if approved by the Engineer, the data may be submitted in electronic media. Electronic media shall be presented in a tab-delimited format on a 90 mm diskette with a capacity of at least 1.4 megabytes. Captured data, for the ingredients represented by each batch shall be "line feed, carriage return" (LFCR) and "one line, separate record" with allowances for sufficient fields to satisfy the amount of data required by these specifications.

The Contractor may furnish a weighmaster certificate accompanied by a separate certificate that lists the actual batch masses or measurements for a load of concrete provided that both certificates are imprinted with the same nonrepeating load number that is unique to the contract and delivered to the job site with the load.

Weighmaster certificates furnished by the Contractor shall conform to the provisions in Section 9-1.01, "Measurement of Quantities."

### **90-6.04 TIME OR AMOUNT OF MIXING**

Mixing of concrete in paving or stationary mixers shall continue for the required mixing time after all ingredients, except water and admixture, if added with the water, are in the mixing compartment of the mixer before any part of the batch is released. Transfer time in multiple drum mixers shall not be counted as part of the required mixing time.

The required mixing time, in paving or stationary mixers, of concrete used for concrete structures, except minor structures, shall be not less than 90 seconds or more than 5 minutes, except that when directed by the Engineer in writing, the requirements of the following paragraph shall apply.

The required mixing time, in paving or stationary mixers, except as provided in the preceding paragraph, shall be not less than 50 seconds or more than 5 minutes.

The minimum required revolutions at the mixing speed for transit-mixed concrete shall not be less than that recommended by the mixer manufacturer, but in no case shall the number of revolutions be less than that required to consistently produce concrete conforming to the provisions for uniformity in Section 90-6.01, "General."

When a high range water-reducing admixture is added to the concrete at the job site, the total number of revolutions shall not exceed 300.

**90-6.05 HAND-MIXING**

Hand-mixed concrete shall be made in batches of not more than 0.25-m<sup>3</sup> and shall be mixed on a watertight, level platform. The proper amount of coarse aggregate shall be measured in measuring boxes and spread on the platform and the fine aggregate shall be spread on this layer, the 2 layers being not more than 0.3-meters in total depth. On this mixture shall be spread the dry cementitious materials and the whole mass turned no fewer than 2 times dry; then sufficient clean water shall be added, evenly distributed, and the whole mass again turned no fewer than 3 times, not including placing in the carriers or forms.

**90-6.06 AMOUNT OF WATER AND PENETRATION**

The amount of water used in concrete mixes shall be regulated so that the penetration of the concrete as determined by California Test 533 or the slump of the concrete as determined by ASTM Designation: C 143 is within the nominal values shown in the following table. When the penetration or slump of the concrete is found to exceed the nominal values listed, the mixture of subsequent batches shall be adjusted to reduce the penetration or slump to a value within the nominal range shown. Batches of concrete with a penetration or slump exceeding the maximum values listed shall not be used in the work. If Type F or Type G chemical admixtures are added to the mix, the penetration requirements shall not apply and the slump shall not exceed 225 mm after the chemical admixtures are added.

Type of Work	Nominal		Maximum	
	Penetration (mm)	Slump (mm)	Penetration (mm)	Slump (mm)
Concrete Pavement	0 - 25	—	40	—
Non-reinforced concrete facilities	0 - 35	—	50	—
Reinforced concrete structures				
Sections over 300-mm thick	0 - 35	—	65	—
Sections 300-mm thick or less	0 - 50	—	75	—
Concrete placed under water	—	150 - 200	—	225
Cast-in-place concrete piles	65 - 90	130 - 180	100	200

The amount of free water used in concrete shall not exceed 183 kg/m<sup>3</sup>, plus 20 kg for each required 100 kg of cementitious material in excess of 325 kg/m<sup>3</sup>.

The term free water is defined as the total water in the mixture minus the water absorbed by the aggregates in reaching a saturated surface-dry condition.

If there are adverse or difficult conditions that affect the placing of concrete, the above specified penetration and free water content limitations may be exceeded providing the Contractor is granted permission by the Engineer in writing to increase the cementitious material content per cubic meter of concrete. The increase in water and cementitious material shall be at a ratio not to exceed 30 kg of water per added 100 kg of cementitious material per cubic meter. Full compensation for additional cementitious material and water added under these conditions shall be considered as included in the contract price paid for the concrete work involved and no additional compensation will be allowed therefor.

The equipment for supplying water to the mixer shall be constructed and arranged so that the amount of water added can be measured accurately. Any method of discharging water into the mixer for a batch shall be accurate within 1.5 percent of the quantity of water required to be added to the mix for any position of the mixer. Tanks used to measure water shall be designed so that water cannot enter while water is being discharged into the mixer and discharge into the mixer shall be made rapidly in one operation without dribbling. All equipment shall be arranged so as to permit checking the amount of water delivered by discharging into measured containers.

**90-7 CURING CONCRETE**

**90-7.01 METHODS OF CURING**

Newly placed concrete shall be cured by the methods specified in this Section 90-7.01 and the special provisions.

**90-7.01A WATER METHOD**

The concrete shall be kept continuously wet by the application of water for a minimum curing period of 7 days after the concrete has been placed.

Cotton mats, rugs, carpets, or earth or sand blankets may be used as a curing medium to retain the moisture during the curing period.

If a curing medium consisting of cotton mats, rugs, carpets, polyethylene sheeting, polyethylene sheeting on burlap, or earth or sand blankets is to be used to retain the moisture, the entire surface of the concrete shall be kept damp by applying

water with a nozzle that so atomizes the flow that a mist and not a spray is formed, until the surface of the concrete is covered with the curing medium. The moisture from the nozzle shall not be applied under pressure directly upon the concrete and shall not be allowed to accumulate on the concrete in a quantity sufficient to cause a flow or wash the surface. At the expiration of the curing period, the concrete surfaces shall be cleared of all curing media.

At the option of the Contractor, a curing medium consisting of white opaque polyethylene sheeting extruded onto burlap may be used to cure concrete structures. The polyethylene sheeting shall have a minimum thickness of 100  $\mu\text{m}$ , and shall be extruded onto 283.5-gram burlap.

At the option of the Contractor, a curing medium consisting of polyethylene sheeting may be used to cure concrete columns. The polyethylene sheeting shall have a minimum thickness of 250  $\mu\text{m}$  achieved in a single layer of material.

If the Contractor chooses to use polyethylene sheeting or polyethylene sheeting on burlap as a curing medium, these media and any joints therein shall be secured as necessary to provide moisture retention and shall be within 75 mm of the concrete at all points along the surface being cured. When these media are used, the temperature of the concrete shall be monitored during curing. If the temperature of the concrete cannot be maintained below 60°C, use of these curing media shall be disallowed.

When concrete bridge decks and flat slabs are to be cured without the use of a curing medium, the entire surface of the bridge deck or slab shall be kept damp by the application of water with an atomizing nozzle as specified above, until the concrete has set, after which the entire surface of the concrete shall be sprinkled continuously with water for a period of not less than 7 days.

### **90-7.01B CURING COMPOUND METHOD**

Surfaces of the concrete that are exposed to the air shall be sprayed uniformly with a curing compound.

Curing compounds to be used shall be as follows:

1. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class B, except the resin type shall be poly-alpha-methylstyrene.
2. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class B.
3. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class A.
4. Nonpigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 1, Class B.
5. Nonpigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 1, Class A.
6. Nonpigmented curing compound with fugitive dye conforming to the requirements in ASTM Designation: C 309, Type 1-D, Class A.

The infrared scan for the dried vehicle from curing compound (1) shall match the infrared scan on file at the Transportation Laboratory.

The loss of water for each type of curing compound, when tested in conformance with the requirements in California Test 534, shall not be more than 0.15-kg/m<sup>2</sup> in 24 hours.

The curing compound to be used will be specified elsewhere in these specifications or in the special provisions.

If the use of curing compound is required or permitted elsewhere in these specifications or in the special provisions and no specific kind is specified, any of the curing compounds listed above may be used.

Curing compound shall be applied at a nominal rate of 3.7 m<sup>2</sup>/L, unless otherwise specified.

At any point, the application rate shall be within  $\pm 1.2$  m<sup>2</sup>/L of the nominal rate specified, and the average application rate shall be within  $\pm 0.5$  m<sup>2</sup>/L of the nominal rate specified when tested in conformance with the requirements in California Test 535. Runs, sags, thin areas, skips, or holidays in the applied curing compound shall be evidence that the application is not satisfactory.

Curing compounds shall be applied using power operated spray equipment. The power operated spraying equipment shall be equipped with an operational pressure gage and a means of controlling the pressure. Hand spraying of small and irregular areas that are not reasonably accessible to mechanical spraying equipment, in the opinion of the Engineer, may be permitted.

The curing compound shall be applied to the concrete following the surface finishing operation, immediately before the moisture sheen disappears from the surface, but before any drying shrinkage or craze cracks begin to appear. In the event of any drying or cracking of the surface, application of water with an atomizing nozzle as specified in Section 90-7.01A, "Water Method," shall be started immediately and shall be continued until application of the compound is resumed or started; however, the compound shall not be applied over any resulting freestanding water. Should the film of compound be damaged from any cause before the expiration of 7 days after the concrete is placed in the case of structures and 72 hours in the case of pavement, the damaged portion shall be repaired immediately with additional compound.

At the time of use, compounds containing pigments shall be in a thoroughly mixed condition with the pigment uniformly dispersed throughout the vehicle. A paddle shall be used to loosen all settled pigment from the bottom of the container, and a power driven agitator shall be used to disperse the pigment uniformly throughout the vehicle.

Agitation shall not introduce air or other foreign substance into the curing compound.

The manufacturer shall include in the curing compound the necessary additives for control of sagging, pigment settling, leveling, de-emulsification, or other requisite qualities of a satisfactory working material. Pigmented curing compounds shall be manufactured so that the pigment does not settle badly, does not cake or thicken in the container, and does not become granular or curdled. Settlement of pigment shall be a thoroughly wetted, soft, mushy mass permitting the complete and easy vertical penetration of a paddle. Settled pigment shall be easily redispersed, with minimum resistance to the sideways manual motion of the paddle across the bottom of the container, to form a smooth uniform product of the proper consistency.

Curing compounds shall remain sprayable at temperatures above 4°C and shall not be diluted or altered after manufacture.

The curing compound shall be packaged in clean 1040-L totes, 210-L barrels, or 19-L pails, or shall be supplied from a suitable storage tank located at the job site. The containers shall comply with "Title 49, Code of Federal Regulations, Hazardous Materials Regulations." The 1040-L totes and the 210-L barrels shall have removable lids and airtight fasteners. The 19-L pails shall be round and have standard full open head and bail. Lids with bungholes will not be permitted. Settling or separation of solids in containers, except tanks, must be completely redispersed with low speed mixing prior to use, in conformance with these specifications and the manufacturer's recommendations. Mixing shall be accomplished either manually by use of a paddle or by use of a mixing blade driven by a drill motor, at low speed. Mixing blades shall be the type used for mixing paint. On-site storage tanks shall be kept clean and free of contaminants. Each tank shall have a permanent system designed to completely redisperse settled material without introducing air or other foreign substances.

Steel containers and lids shall be lined with a coating that will prevent destructive action by the compound or chemical agents in the air space above the compound. The coating shall not come off the container or lid as skins. Containers shall be filled in a manner that will prevent skinning. Plastic containers shall not react with the compound.

Each container shall be labeled with the manufacturer's name, kind of curing compound, batch number, volume, date of manufacture, and volatile organic compound (VOC) content. The label shall also warn that the curing compound containing pigment shall be well stirred before use. Precautions concerning the handling and the application of curing compound shall be shown on the label of the curing compound containers in conformance with the Construction Safety Orders and General Industry Safety Orders of the State.

Containers of curing compound shall be labeled to indicate that the contents fully comply with the rules and regulations concerning air pollution control in the State.

When the curing compound is shipped in tanks or tank trucks, a shipping invoice shall accompany each load. The invoice shall contain the same information as that required herein for container labels.

Curing compound will be sampled by the Engineer at the source of supply, at the job site, or at both locations.

Curing compound shall be formulated so as to maintain the specified properties for a minimum of one year. The Engineer may require additional testing before use to determine compliance with these specifications if the compound has not been used within one year or whenever the Engineer has reason to believe the compound is no longer satisfactory.

Tests will be conducted in conformance with the latest ASTM test methods and methods in use by the Transportation Laboratory.

#### **90-7.01C WATERPROOF MEMBRANE METHOD**

The exposed finished surfaces of concrete shall be sprayed with water, using a nozzle that so atomizes the flow that a mist and not a spray is formed, until the concrete has set, after which the curing membrane, shall be placed. The curing membrane shall remain in place for a period of not less than 72 hours.

Sheeting material for curing concrete shall conform to the requirements in AASHTO Designation: M 171 for white reflective materials.

The sheeting material shall be fabricated into sheets of such width as to provide a complete cover for the entire concrete surface. Joints in the sheets shall be securely cemented together in such a manner as to provide a waterproof joint. The joint seams shall have a minimum lap of 100 mm.

The sheets shall be securely weighted down by placing a bank of earth on the edges of the sheets or by other means satisfactory to the Engineer.

Should any portion of the sheets be broken or damaged before the expiration of 72 hours after being placed, the broken or damaged portions shall be immediately repaired with new sheets properly cemented into place.

Sections of membrane that have lost their waterproof qualities or have been damaged to such an extent as to render them unfit for curing the concrete shall not be used.

#### **90-7.01D FORMS-IN-PLACE METHOD**

Formed surfaces of concrete may be cured by retaining the forms in place. The forms shall remain in place for a minimum period of 7 days after the concrete has been placed, except that for members over 0.5-m in least dimension the forms shall remain in place for a minimum period of 5 days.

Joints in the forms and the joints between the end of forms and concrete shall be kept moisture tight during the curing period. Cracks in the forms and cracks between the forms and the concrete shall be resealed by methods subject to the approval of the Engineer.

## **90-7.02 CURING PAVEMENT**

The entire exposed area of the pavement, including edges, shall be cured by the waterproof membrane method, or curing compound method using curing compound (1) or (2) as the Contractor may elect. Should the side forms be removed before the expiration of 72 hours following the start of curing, the exposed pavement edges shall also be cured. If the pavement is cured by means of the curing compound method, the sawcut and all portions of the curing compound that have been disturbed by sawing operations shall be restored by spraying with additional curing compound.

Curing shall commence as soon as the finishing process provided in Section 40-1.10, "Final Finishing," has been completed. The method selected shall conform to the provisions in Section 90-7.01, "Methods of Curing."

When the curing compound method is used, the compound shall be applied to the entire pavement surface by mechanical sprayers. Spraying equipment shall be of the fully atomizing type equipped with a tank agitator that provides for continual agitation of the curing compound during the time of application. The spray shall be adequately protected against wind, and the nozzles shall be so oriented or moved mechanically transversely as to result in the minimum specified rate of coverage being applied uniformly on exposed faces. Hand spraying of small and irregular areas, and areas inaccessible to mechanical spraying equipment, in the opinion of the Engineer, will be permitted. When the ambient air temperature is above 15°C, the Contractor shall fog the surface of the concrete with a fine spray of water as specified in Section 90-7.01A, "Water Method." The surface of the pavement shall be kept moist between the hours of 10:00 a.m. and 4:30 p.m. on the day the concrete is placed. However, the fogging done after the curing compound has been applied shall not begin until the compound has set sufficiently to prevent displacement. Fogging shall be discontinued if ordered in writing by the Engineer.

## **90-7.03 CURING STRUCTURES**

Newly placed concrete for cast-in-place structures, other than highway bridge decks, shall be cured by the water method, the forms-in-place method, or, as permitted herein, by the curing compound method, in conformance with the provisions in Section 90-7.01, "Methods of Curing."

The curing compound method using a pigmented curing compound may be used on concrete surfaces of construction joints, surfaces that are to be buried underground, and surfaces where only ordinary surface finish is to be applied and on which a uniform color is not required and that will not be visible from a public traveled way. If the Contractor elects to use the curing compound method on the bottom slab of box girder spans, the curing compound shall be curing compound (1).

The top surface of highway bridge decks shall be cured by both the curing compound method and the water method. The curing compound shall be curing compound (1).

Concrete surfaces of minor structures, as defined in Section 51-1.02, "Minor Structures," shall be cured by the water method, the forms-in-place method or the curing compound method.

When deemed necessary by the Engineer during periods of hot weather, water shall be applied to concrete surfaces being cured by the curing compound method or by the forms-in-place method, until the Engineer determines that a cooling effect is no longer required. Application of water for this purpose will be paid for as extra work as provided in Section 4-1.03D, "Extra Work."

## **90-7.04 CURING PRECAST CONCRETE MEMBERS**

Precast concrete members shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing." Curing shall be provided for the minimum time specified for each method or until the concrete reaches its design strength, whichever is less. Steam curing may also be used for precast members and shall conform to the following provisions:

- A. After placement of the concrete, members shall be held for a minimum 4-hour presteaming period. If the ambient air temperature is below 10°C, steam shall be applied during the presteaming period to hold the air surrounding the member at a temperature between 10°C and 32°C.
- B. To prevent moisture loss on exposed surfaces during the presteaming period, members shall be covered as soon as possible after casting or the exposed surfaces shall be kept wet by fog spray or wet blankets.
- C. Enclosures for steam curing shall allow free circulation of steam about the member and shall be constructed to contain the live steam with a minimum moisture loss. The use of tarpaulins or similar flexible covers will be permitted, provided they are kept in good repair and secured in such a manner as to prevent the loss of steam and moisture.
- D. Steam at the jets shall be at low pressure and in a saturated condition. Steam jets shall not impinge directly on the concrete, test cylinders, or forms. During application of the steam, the temperature rise within the enclosure shall not exceed 22°C per hour. The curing temperature throughout the enclosure shall not exceed 65°C and shall be maintained at a constant level for a sufficient time necessary to develop the required transfer strength. Control cylinders shall be covered to prevent moisture loss and shall be placed in a location where temperature is representative of the average temperature of the enclosure.

- E. Temperature recording devices that will provide an accurate, continuous, permanent record of the curing temperature shall be provided. A minimum of one temperature recording device per 60 m of continuous bed length will be required for checking temperature.
- F. Members in pretension beds shall be detensioned immediately after the termination of steam curing while the concrete and forms are still warm, or the temperature under the enclosure shall be maintained above 15°C until the stress is transferred to the concrete.
- G. Curing of precast concrete will be considered completed after termination of the steam curing cycle.

#### **90-7.05 CURING PRECAST PRESTRESSED CONCRETE PILES**

Newly placed concrete for precast prestressed concrete piles shall be cured in conformance with the provisions in Section 90-7.04, "Curing Precast Concrete Members," except that piles in a corrosive environment shall be cured as follows:

- A. Piles shall be either steam cured or water cured. If water curing is used, the piles shall be kept continuously wet by the application of water in conformance with the provisions in Section 90-7.01A, "Water Method."
- B. If steam curing is used, the steam curing provisions in Section 90-7.04, "Curing Precast Concrete Members," shall apply except that the piles shall be kept continuously wet for their entire length for a period of not less than 3 days, including the holding and steam curing periods.

#### **90-7.06 CURING SLOPE PROTECTION**

Concrete slope protection shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing."

Concreted-rock slope protection shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing," with a blanket of earth kept wet for 72 hours, or by sprinkling with a fine spray of water every 2 hours during the daytime for a period of 3 days.

#### **90-7.07 CURING MISCELLANEOUS CONCRETE WORK**

Exposed surfaces of curbs shall be cured by pigmented curing compounds as specified in Section 90-7.01B, "Curing Compound Method."

Concrete sidewalks, gutter depressions, island paving, curb ramps, driveways, and other miscellaneous concrete areas shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing."

Shotcrete shall be cured for at least 72 hours by spraying with water, by a moist earth blanket, or by any of the methods provided in Section 90-7.01, "Methods of Curing."

Mortar and grout shall be cured by keeping the surface damp for 3 days.

After placing, the exposed surfaces of sign structure foundations, including pedestal portions, if constructed, shall be cured for at least 72 hours by spraying with water, by a moist earth blanket, or by any of the methods provided in Section 90-7.01, "Methods of Curing."

### **90-8 PROTECTING CONCRETE**

#### **90-8.01 GENERAL**

In addition to the provisions in Section 7-1.16, "Contractor's Responsibility for the Work and Materials," the Contractor shall protect concrete as provided in this Section 90-8. If required by the Engineer, the Contractor shall submit a written outline of the proposed methods for protecting the concrete.

The Contractor shall protect concrete from damage from any cause, which shall include, but not be limited to: rain, heat, cold, wind, Contractor's actions, and actions of others.

Concrete shall not be placed on frozen or ice-coated ground or subgrade nor on ice-coated forms, reinforcing steel, structural steel, conduits, precast members, or construction joints.

Under rainy conditions, placing of concrete shall be stopped before the quantity of surface water is sufficient to damage surface mortar or cause a flow or wash of the concrete surface, unless the Contractor provides adequate protection against damage.

Concrete that has been frozen or damaged by other causes, as determined by the Engineer, shall be removed and replaced by the Contractor at the Contractor's expense.

#### **90-8.02 PROTECTING CONCRETE STRUCTURES**

Structure concrete and shotcrete used as structure concrete shall be maintained at a temperature of not less than 7°C for 72 hours after placing and at not less than 4°C for an additional 4 days.

### **90-8.03 PROTECTING CONCRETE PAVEMENT**

Pavement concrete shall be maintained at a temperature of not less than 4°C for 72 hours.

Except as provided in Section 7-1.08, "Public Convenience," the Contractor shall protect concrete pavement against construction and other activities that abrade, scar, discolor, reduce texture depth, lower coefficient of friction, or otherwise damage the surface. Stockpiling, drifting, or excessive spillage of soil, gravel, petroleum products, and concrete or asphalt mixes on the surface of concrete pavement is prohibited unless otherwise specified in these specifications, the special provisions or permitted by the Engineer.

If ordered by the Engineer or shown on the plans or specified in the special provisions, pavement crossings shall be constructed for the convenience of public traffic. The material and work necessary for the construction of the crossings, and their subsequent removal and disposal, will be paid for at the contract unit prices for the items of work involved and if there are no contract items for the work involved, payment for pavement crossings will be made by extra work as provided in Section 4-1.03D, "Extra Work." Where public traffic will be required to cross over the new pavement, Type III portland cement may be used in concrete, if permitted in writing by the Engineer. The pavement may be opened to traffic as soon as the concrete has developed a modulus of rupture of 3.8 MPa. The modulus of rupture will be determined by California Test 523.

No traffic or Contractor's equipment, except as hereinafter provided, will be permitted on the pavement before a period of 10 days has elapsed after the concrete has been placed, nor before the concrete has developed a modulus of rupture of at least 3.8 MPa. Concrete that fails to attain a modulus of rupture of 3.8 MPa within 10 days shall not be opened to traffic until directed by the Engineer.

Equipment for sawing weakened plane joints will be permitted on the pavement as specified in Section 40-1.08B, "Weakened Plane Joints."

When requested in writing by the Contractor, the tracks on one side of paving equipment will be permitted on the pavement after a modulus of rupture of 2.4 MPa has been attained, provided that:

- A. Unit pressure exerted on the pavement by the paver shall not exceed 135 kPa;
- B. Tracks with cleats, grousers, or similar protuberances shall be modified or shall travel on planks or equivalent protective material, so that the pavement is not damaged; and
- C. No part of the track shall be closer than 0.3-m from the edge of pavement.

In case of visible cracking of, or other damage to the pavement, operation of the paving equipment on the pavement shall be immediately discontinued.

Damage to the pavement resulting from early use of pavement by the Contractor's equipment as provided above shall be repaired by the Contractor.

The State will furnish the molds and machines for testing the concrete for modulus of rupture, and the Contractor, at the Contractor's expense, shall furnish the material and whatever labor the Engineer may require.

### **90-9 COMPRESSIVE STRENGTH**

#### **90-9.01 GENERAL**

Concrete compressive strength requirements consist of a minimum strength that shall be attained before various loads or stresses are applied to the concrete and, for concrete designated by strength, a minimum strength at the age of 28 days or at the age otherwise allowed in Section 90-1.01, "Description." The various strengths required are specified in these specifications or the special provisions or are shown on the plans.

The compressive strength of concrete will be determined from test cylinders that have been fabricated from concrete sampled in conformance with the requirements of California Test 539. Test cylinders will be molded and initially field cured in conformance with California Test 540. Test cylinders will be cured and tested after receipt at the testing laboratory in conformance with the requirements of California Test 521. A strength test shall consist of the average strength of 2 cylinders fabricated from material taken from a single load of concrete, except that, if any cylinder should show evidence of improper sampling, molding, or testing, that cylinder shall be discarded and the strength test shall consist of the strength of the remaining cylinder.

When concrete compressive strength is specified as a prerequisite to applying loads or stresses to a concrete structure or member, test cylinders for other than steam cured concrete will be cured in conformance with Method 1 of California Test 540. The compressive strength of concrete determined for these purposes will be evaluated on the basis of individual tests.

When concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete strength to be used as a basis for acceptance of other than steam cured concrete will be determined from cylinders cured in conformance with Method 1 of California Test 540. If the result of a single compressive strength test at the maximum age specified or allowed is below the specified strength but is 95 percent or more of the specified strength, the Contractor shall make corrective changes, subject to approval of the Engineer, in the mix proportions or in the concrete fabrication

procedures, before placing additional concrete, and shall pay to the State \$14 for each in-place cubic meter of concrete represented by the deficient test. If the result of a single compressive strength test at the maximum age specified or allowed is below 95 percent of the specified strength, but is 85 percent or more of the specified strength, the Contractor shall make the corrective changes specified above, and shall pay to the State \$20 for each in place cubic meter of concrete represented by the deficient test. In addition, such corrective changes shall be made when the compressive strength of concrete tested at 7 days indicates, in the judgment of the Engineer, that the concrete will not attain the required compressive strength at the maximum age specified or allowed. Concrete represented by a single test that indicates a compressive strength of less than 85 percent of the specified 28-day compressive strength will be rejected in conformance with the provisions in Section 6-1.04, "Defective Materials."

If the test result indicates that the compressive strength at the maximum curing age specified or allowed is below the specified strength, but is 85 percent or more of the specified strength, payments to the State as required above shall be made, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength of the concrete placed in the work meets or exceeds the specified 28-day compressive strength. If the test result indicates a compressive strength at the maximum curing age specified or allowed below 85 percent, the concrete represented by that test will be rejected, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength and quality of the concrete placed in the work are acceptable. If the evidence consists of tests made on cores taken from the work, the cores shall be obtained and tested in conformance with the requirements in ASTM Designation: C 42.

No single compressive strength test shall represent more than 250 m<sup>3</sup>.

If a precast concrete member is steam cured, the compressive strength of the concrete will be determined from test cylinders that have been handled and stored in conformance with Method 3 of California Test 540. The compressive strength of steam cured concrete will be evaluated on the basis of individual tests representing specific portions of production. If the concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete shall be considered to be acceptable whenever its compressive strength reaches the specified 28-day compressive strength provided that strength is reached in not more than the maximum number of days specified or allowed after the member is cast.

When concrete is specified by compressive strength, prequalification of materials, mix proportions, mixing equipment, and procedures proposed for use will be required prior to placement of the concrete. Prequalification shall be accomplished by the submission of acceptable certified test data or trial batch reports by the Contractor. Prequalification data shall be based on the use of materials, mix proportions, mixing equipment, procedures, and size of batch proposed for use in the work.

Certified test data, in order to be acceptable, shall indicate that not less than 90 percent of at least 20 consecutive tests exceed the specified strength at the maximum number of cure days specified or allowed, and none of those tests are less than 95 percent of specified strength. Strength tests included in the data shall be the most recent tests made on concrete of the proposed mix design and all shall have been made within one year of the proposed use of the concrete.

Trial batch test reports, in order to be acceptable, shall indicate that the average compressive strength of 5 consecutive concrete cylinders, taken from a single batch, at not more than 28 days (or the maximum age allowed) after molding shall be at least 4 MPa greater than the specified 28-day compressive strength, and no individual cylinder shall have a strength less than the specified strength at the maximum age specified or allowed. Data contained in the report shall be from trial batches that were produced within one year of the proposed use of specified strength concrete in the project. Whenever air-entrainment is required, the air content of trial batches shall be equal to or greater than the air content specified for the concrete without reduction due to tolerances.

Tests shall be performed in conformance with either the appropriate California Test methods or the comparable ASTM test methods. Equipment employed in testing shall be in good condition and shall be properly calibrated. If the tests are performed during the life of the contract, the Engineer shall be notified sufficiently in advance of performing the tests in order to witness the test procedures.

The certified test data and trial batch test reports shall include the following information:

- A. Date of mixing.
- B. Mixing equipment and procedures used.
- C. The size of batch in cubic meters and the mass, type, and source of all ingredients used.
- D. Penetration or slump (if the concrete will be placed under water or placed in cast-in-place concrete piles) of the concrete.
- E. The air content of the concrete if an air-entraining admixture is used.
- F. The age at time of testing and strength of all concrete cylinders tested.

Certified test data and trial batch test reports shall be signed by an official of the firm that performed the tests.

When approved by the Engineer, concrete from trial batches may be used in the work at locations where concrete of a lower quality is required and the concrete will be paid for as the type or class of concrete required at that location.

After materials, mix proportions, mixing equipment, and procedures for concrete have been prequalified for use, additional prequalification by testing of trial batches will be required prior to making changes that, in the judgment of the Engineer, could result in a strength of concrete below that specified.

The Contractor's attention is directed to the time required to test trial batches and the Contractor shall be responsible for production of trial batches at a sufficiently early date so that the progress of the work is not delayed.

When precast concrete members are manufactured at the plant of an established manufacturer of precast concrete members, the mix proportions of the concrete shall be determined by the Contractor, and a trial batch and prequalification of the materials, mix proportions, mixing equipment, and procedures will not be required.

## **90-10 MINOR CONCRETE**

### **90-10.01 GENERAL**

Concrete for minor structures, slope paving, curbs, sidewalks and other concrete work, when designated as minor concrete on the plans, in the specifications, or in the contract item, shall conform to the provisions specified herein.

The Engineer, at the Engineer's discretion, will inspect and test the facilities, materials and methods for producing the concrete to ensure that minor concrete of the quality suitable for use in the work is obtained.

### **90-10.02 MATERIALS**

Minor concrete shall conform to the following requirements:

#### **90-10.02A CEMENTITIOUS MATERIAL**

Cementitious material shall conform to the provisions in Section 90-1.01, "Description."

#### **90-10.02B AGGREGATE**

Aggregate shall be clean and free from deleterious coatings, clay balls, roots, and other extraneous materials.

Use of crushed concrete or reclaimed aggregate is acceptable only if the aggregate satisfies all aggregate requirements.

The Contractor shall submit to the Engineer for approval, a grading of the combined aggregate proposed for use in the minor concrete. After acceptance of the grading, aggregate furnished for minor concrete shall conform to that grading, unless a change is authorized in writing by the Engineer.

The Engineer may require the Contractor to furnish periodic test reports of the aggregate grading furnished. The maximum size of aggregate used shall be at the option of the Contractor, but in no case shall the maximum size be larger than 37.5 mm or smaller than 19 mm.

The Engineer may waive, in writing, the gradation requirements in this Section 90-10.02B, if, in the Engineer's opinion, the furnishing of the gradation is not necessary for the type or amount of concrete work to be constructed.

#### **90-10.02C WATER**

Water used for washing, mixing, and curing shall be free from oil, salts, and other impurities that would discolor or etch the surface or have an adverse affect on the quality of the concrete.

#### **90-10.02D ADMIXTURES**

The use of admixtures shall conform to the provisions in Section 90-4, "Admixtures."

### **90-10.03 PRODUCTION**

Cementitious material, water, aggregate, and admixtures shall be stored, proportioned, mixed, transported, and discharged in conformance with recognized standards of good practice that will result in concrete that is thoroughly and uniformly mixed, that is suitable for the use intended, and that conforms to requirements specified herein. Recognized standards of good practice are outlined in various industry publications such as are issued by American Concrete Institute, AASHTO, or the Department.

The cementitious material content of minor concrete shall conform to the provisions in Section 90-1.01, "Description."

The amount of water used shall result in a consistency of concrete conforming to the provisions in Section 90-6.06, "Amount of Water and Penetration." Additional mixing water shall not be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer.

Discharge of ready-mixed concrete from the transporting vehicle shall be made while the concrete is still plastic and before stiffening occurs. An elapsed time of 1.5 hours (one hour in nonagitating hauling equipment), or more than 250 revolutions of the drum or blades, after the introduction of the cementitious material to the aggregates, or a temperature of concrete of more than 32°C will be considered conditions contributing to the quick stiffening of concrete. The Contractor shall take whatever action is necessary to eliminate quick stiffening, except that the addition of water will not be permitted.

The required mixing time in stationary mixers shall be not less than 50 seconds or more than 5 minutes.





## **92-1.02 MATERIALS**

### **GENERAL**

Furnish asphalt under the Department's "Certification Program for Suppliers of Asphalt." The Department maintains the program requirements, procedures, and a list of approved suppliers at:

<http://www.dot.ca.gov/hq/esc/Translab/fpm/fpmcoc.htm>

Transport, store, use, and dispose of asphalt safely.

Prevent the formation of carbonized particles caused by overheating asphalt during manufacturing or construction.

### **GRADES**

Performance graded (PG) asphalt binder is:

Performance Graded Asphalt Binder

Property	AASHTO Test Method	Specification				
		Grade				
		PG 58-22 <sup>a</sup>	PG 64-10	PG 64-16	PG 64-28	PG 70-10
Original Binder						
Flash Point, Minimum °C	T 48	230	230	230	230	230
Solubility, Minimum % <sup>b</sup>	T 44	99	99	99	99	99
Viscosity at 135°C, <sup>c</sup> Maximum, Pa·s	T 316	3.0	3.0	3.0	3.0	3.0
Dynamic Shear, Test Temp. at 10 rad/s, °C Minimum G*/sin(delta), kPa	T 315	58 1.00	64 1.00	64 1.00	64 1.00	70 1.00
RTFO Test, <sup>e</sup> Mass Loss, Maximum, %	T 240	1.00	1.00	1.00	1.00	1.00
RTFO Test Aged Binder						
Dynamic Shear, Test Temp. at 10 rad/s, °C Minimum G*/sin(delta), kPa	T 315	58 2.20	64 2.20	64 2.20	64 2.20	70 2.20
Ductility at 25°C Minimum, cm	T 51	75	75	75	75	75
PAV <sup>f</sup> Aging, Temperature, °C	R 28	100	100	100	100	110
RTFO Test and PAV Aged Binder						
Dynamic Shear, Test Temp. at 10 rad/s, °C Maximum G*/sin(delta), kPa	T 315	22 <sup>d</sup> 5000	31 <sup>d</sup> 5000	28 <sup>d</sup> 5000	22 <sup>d</sup> 5000	34 <sup>d</sup> 5000
Creep Stiffness, Test Temperature, °C Maximum S-value, Mpa Minimum M-value	T 313	-12 300 0.300	0 300 0.300	-6 300 0.300	-18 300 0.300	0 300 0.300

Notes:

- a. Use as asphalt rubber base stock for high mountain and high desert area.
- b. The Engineer waives this specification if the supplier is a Quality Supplier as defined by the Department's "Certification Program for Suppliers of Asphalt."
- c. The Engineer waives this specification if the supplier certifies the asphalt binder can be adequately pumped and mixed at temperatures meeting applicable safety standards.
- d. Test the sample at 3°C higher if it fails at the specified test temperature. G\*/sin(delta) remains 5000 kPa maximum.
- e. "RTFO Test" means the asphaltic residue obtained using the Rolling Thin Film Oven Test, AASHTO Test Method T 240 or ASTM Designation: D 2872. The residue from mass change determination may be used for other tests.
- f. "PAV" means Pressurized Aging Vessel.

Performance graded polymer modified asphalt binder (PG Polymer Modified) is:

Performance Graded Polymer Modified Asphalt Binder <sup>a</sup>

Property	AASHTO Test Method	Specification Grade		
		PG 58-34 PM	PG 64-28 PM	PG 76-22 PM
<b>Original Binder</b>				
Flash Point, Minimum °C	T 48	230	230	230
Solubility, Minimum % <sup>b</sup>	T 44 <sup>c</sup>	98.5	98.5	98.5
Viscosity at 135°C, <sup>d</sup> Maximum, Pa·s	T 316	3.0	3.0	3.0
Dynamic Shear, Test Temp. at 10 rad/s, °C Minimum G*/sin(delta), kPa	T 315	58 1.00	64 1.00	76 1.00
RTFO Test , Mass Loss, Maximum, %	T 240	1.00	1.00	1.00
<b>RTFO Test Aged Binder</b>				
Dynamic Shear, Test Temp. at 10 rad/s, °C Minimum G*/sin(delta), kPa	T 315	58 2.20	64 2.20	76 2.20
Dynamic Shear, Test Temp. at 10 rad/s, °C Maximum (delta), %	T 315	Note e 80	Note e 80	Note e 80
Elastic Recovery <sup>f</sup> , Test Temp., °C Minimum recovery, %	T 301	25 75	25 75	25 65
PAV <sup>g</sup> Aging, Temperature, °C	R 28	100	100	110
<b>RTFO Test and PAV Aged Binder</b>				
Dynamic Shear, Test Temp. at 10 rad/s, °C Maximum G* sin(delta), kPa	T 315	16 5000	22 5000	31 5000
Creep Stiffness, Test Temperature, °C Maximum S-value, MPa Minimum M-value	T 313	-24 300 0.300	-18 300 0.300	-12 300 0.300

Notes:

- a. Do not modify PG Polymer Modified using acid modification.
- b. The Engineer waives this specification if the supplier is a Quality Supplier as defined by the Department's "Certification Program for Suppliers of Asphalt."
- c. The Department allows ASTM D 5546 instead of AASHTO T 44
- d. The Engineer waives this specification if the supplier certifies the asphalt binder can be adequately pumped and mixed at temperatures meeting applicable safety standards.
- e. Test temperature is the temperature at which G\*/sin(delta) is 2.2 kPa. A graph of log G\*/sin(delta) plotted against temperature may be used to determine the test temperature when G\*/sin(delta) is 2.2 kPa. A graph of (delta) versus temperature may be used to determine delta at the temperature when G\*/sin(delta) is 2.2 kPa. The Engineer also accepts direct measurement of (delta) at the temperature when G\*/sin(delta) is 2.2 kPa.
- f. Tests without a force ductility clamp may be performed.
- g. "PAV" means Pressurized Aging Vessel.

**SAMPLING**

Provide a sampling device in the asphalt feed line connecting the plant storage tanks to the asphalt weighing system or spray bar. Make the sampling device accessible between 600 and 750 mm above the platform. Provide a receptacle for flushing the sampling device.

Include with the sampling device a valve:

1. Between 10 and 20 mm in diameter
2. Manufactured in a manner that a one-liter sample may be taken slowly at any time during plant operations



**Replace Section 95 with:**

**SECTION 95 EPOXY**

**95-1 GENERAL**

**95-1.01 DESCRIPTION**

These specifications are intended to specify epoxy that will meet service requirements for highway construction. Epoxy shall be furnished as 2 components, which shall be mixed together at the site of the work.

**95-1.02 SAMPLING AND TESTING**

Epoxy shall not be used prior to sampling and testing unless its use is permitted prior to sampling and testing in conformance with the provisions in Section 6-1.07, "Certificates of Compliance."

Tests will be conducted in conformance with the latest test methods of the American Society for Testing and Materials, and California Test Methods in use by the Transportation Laboratory.

Epoxy components shall be formulated to maintain the specified properties for a minimum of one year. The Engineer may require additional testing of any epoxy component that has not been used within one year of manufacture.

**95-1.03 PACKAGING, LABELING AND STORING**

Each component shall be packaged in containers of size proportional to the amount of that component in the mix so that one container of each component is used in mixing one batch of epoxy. The containers shall be of such design that all of the contents may be readily removed and shall be well sealed to prevent leakage. The containers and labeling shall meet U.S. Department of Transportation Hazardous Material Shipping Regulations, and the containers shall be of a material, or lined with a material, of such character as to resist any action by the components. Each container shall be clearly labeled with the ASTM Designation: C881 Class and Type; designation (Component A or B); manufacturer's name; date of manufacture; batch number (a batch shall consist of a single charge of all components in a mixing chamber); all directions for use (as specified elsewhere) and such warning or precautions concerning the contents as may be required by State or Federal Laws and Regulations. The manufacturer of the finished epoxy components shall furnish a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," and a copy of the label for each material. The certificate shall include a list, by Title and Section, of the State and Federal packaging and labeling laws and regulations that the manufacturer has complied with.

Attention is directed to the characteristic of some epoxy components to crystallize or thicken excessively prior to use when stored at temperatures below 2°C. Any material which shows evidence of crystallization or a permanent increase in viscosity or settling of pigments which cannot be readily redispersed with a paddle shall not be used.

**95-1.04 DIRECTIONS FOR USE**

At the time of mixing, components A and B shall be at a temperature between 15°C and 30°C, unless otherwise specified. Any heating of the adhesive components shall be done by application of indirect heat. Immediately prior to mixing, each component shall be thoroughly mixed with a paddle. Separate paddles shall be used to stir each component. Immediately prior to use, the 2 components shall be thoroughly mixed together in the specified ratios. No solvent shall be added to any epoxy.

After mixing, epoxies shall be placed in the work and any overlaying or inserted material which is to be bonded to the work by the epoxy shall also be placed before thickening of the epoxy has begun. Surfaces upon which epoxy is to be placed shall be free of rust, paint, grease, asphalt, and loose and deleterious material. When epoxy is used as a binder to make epoxy concrete or mortar, the 2 components of epoxy shall be thoroughly mixed together before the aggregate is added and, unless otherwise specified, the mix proportions shall consist of one part of binder to approximately 4 parts of aggregate, by volume. Aggregate for use in epoxy concrete and mortar shall be clean and shall have a moisture content of not more than 0.50-percent when tested by California Test 226. Surfaces against which epoxy concrete and mortar are to be placed shall be primed with a coat of the epoxy used just prior to placing the concrete or mortar.

**95-2 TYPES OF EPOXIES**

**95-2.01 BINDER (ADHESIVE), EPOXY RESIN BASE**

**Classification:**

This specification covers a low viscosity epoxy formulated primarily for use in making high-strength epoxy concrete and epoxy mortar and in pressure grouting of cracks in concrete. For load bearing applications, use ASTM Designation: C 881, Type IV, Grade 1, Class B or C. Class B or C shall be used depending on the substrate and ambient temperatures. Use Grade B for atmospheric and surface temperatures as low as 4°C. Use Class C when temperatures are 15°C or higher. For non-load bearing applications use ASTM Designation: C881, Type I, Grade 1, Class B or C. Apply no thicker than

recommended by the manufacturer. Thick sections of this epoxy are not suitable for use in freeze thaw environments. In a freeze-thaw environment, increase the aggregate loading to improve the properties of the epoxy concrete.

**Directions for Use:**

Mix in conformance with the manufacturer's written recommendations. No more material shall be mixed than can be used within the pot-life from the time mixing operations are started.

**95-2.02 (BLANK)**

**95-2.03 EPOXY RESIN ADHESIVE FOR BONDING NEW CONCRETE TO OLD CONCRETE**

**Classification:**

This specification covers a low viscosity paste epoxy formulated primarily for use in bonding new portland cement concrete to hardened portland cement concrete. The epoxy shall meet the specification requirements of ASTM Designation: C 881, Type V, Grade 2. This epoxy is available in 2 Classes: Class C for general use at temperature greater than 15°C and Class B for use when cure temperatures are below 15°C and above 4°C, or when a faster cure is required.

**Directions for Use:**

The mixing ratio and use shall be in conformance with the manufacturer's written recommendations. When measuring as individual Components A and B, stir and tap the measuring containers to remove possible air voids. The ingredients in Components A and B shall be thoroughly dispersed such that each component forms a uniform paste. Do not mix more material than can be spread within the pot life from the time mixing operations are started. The spreading rate shall be sufficient to thoroughly coat the surface. Spread the mixed adhesive by brush or roller over blast-cleaned concrete at a rate recommended by the manufacturer. The new concrete shall be placed against the adhesive coating on the old concrete before the adhesive has set. If the adhesive has set and is not tacky prior to placing the new concrete, a new coating of adhesive shall be applied.

**95-2.04 RAPID SET EPOXY ADHESIVE FOR PAVEMENT MARKERS**

**Classification:**

This specification covers a high viscosity paste, rapid set epoxy formulated primarily for use in bonding pavement markers to portland cement concrete and asphalt concrete. The adhesive shall meet ASTM Designation: C 881, Type IV, Grade 3, Class B and C except that the gel time may be shorter than 30 minutes. The adhesive shall conform to these requirements and the following.

**Characteristics of Combined Components:**

All tests shall be performed in conformance with the requirements in California Test 434.

Property	Requirement
Gel time, minutes, maximum, at 25°C	30
Bond Strength to Concrete, Time, minutes (maximum) to reach not less than 1.4 MPa	
at 25°C ±1°C	35
at 10°C ±1°C	45
Slant Shear Strength	
2 days at 25°C ±1°C, MPa	7
14 days at 25°C ±1°C, plus water soak, MPa	10.5
Tensile Adhesion and Cohesion	
Ceramic marker bottom, MPa	4.8 min.
Ceramic marker bottom, including post cure, MPa	4.8 min.
Retroreflective pavement marker bottom, MPa	3.4 min.
Color of mixed epoxy	gray
Glass transition temperature, Tg, samples conditioned at 25°C for 24 hours, ASTM Designation: D 4065	30°C min.

**Directions for Use:**

Components A and B shall be mixed in conformance with the manufacturer's written recommendations. When an automatic proportioning and mixing machine is used, the temperature of the components shall be maintained by indirect heating or cooling, so that the adhesive will meter, mix and extrude properly. The maximum temperature shall be such that after proper mixing no excess adhesive shall flow from under the marker other than that specified in Section 85-1.06, "Placement."

**95-2.05 STANDARD SET EPOXY ADHESIVE FOR PAVEMENT MARKERS**

**Classification:**

This specification covers a high viscosity paste standard set epoxy formulated primarily for use in bonding pavement markers to portland cement concrete and asphalt concrete. The epoxy shall meet ASTM Designation: C 881, Type IV, Viscosity Grade 3, Classes B or C, except that the gel time may be shorter than 30 minutes.

**Characteristics of Combined Components:**

All tests shall be performed in conformance with the requirements in California Test 434.

Property	Requirement
Gel time, minutes, maximum, at 25°C	30
Bond Strength to Concrete, Time (maximum) to reach not less than 1.4 MPa	
at 25°C ±1°C	3.5 hours
at 13°C ±1°C	24 hours
Slant Shear Strength	
2 days at 25°C ±1°C, MPa	7 min.
14 days at 25°C ±1°C, plus water soak, MPa	10.5 min.
Tensile Adhesion and Cohesion	
Ceramic marker bottom, MPa	4.8 min.
Ceramic marker bottom, including post cure, MPa	4.8 min.
Reflective pavement marker bottom, MPa	3.4 min.
Color of Mixed Components	gray
Glass transition temperature, Tg, samples conditioned at 25°C for 24 hours, ASTM Designation: D 4065	30°C min.

**Directions for Use:**

Components A and B shall be mixed in conformance with the manufacturer's written recommendations. When an automatic proportioning and mixing machine is used, the temperature of the components shall be maintained by indirect heating or cooling, so that the adhesive will meter, mix and extrude properly. The maximum temperature shall be such that after proper mixing no excess adhesive shall flow from under the marker other than that specified in Section 85-1.06, "Placement."

**95-2.06 (BLANK)**

**95-2.07 (BLANK)**

**95-2.08 (BLANK)**

**95-2.09 EPOXY SEALANT FOR INDUCTIVE LOOPS**

**Classification:**

This specification covers a high viscosity liquid epoxy formulated primarily for use in sealing inductive wire loops and leads imbedded in asphalt concrete and portland cement concrete for traffic signal controls and vehicle counters. This epoxy is to be used for repair work on existing spalls, cracks and other deformations in and around saw cuts housing inductor loops and leads. The rapid cure allows minimum traffic delay. This sealant is suitable for use in freeze-thaw areas. The epoxy shall meet ASTM Designation: C 881, Type I, Grade 2 and the following requirements.

**Characteristics of Combined Components:**

All tests shall be performed in conformance with the requirements in California Test 434.

Property	Requirement
Gel time, minutes, maximum	30
On 3-mm cast sheet, cured 18 hours at 25°C, + 5 hours at 70°C	
Tensile Strength, MPa	2.7 min.
Elongation, percent	90 min.
Shore D Hardness	45 min.

**Directions for Use:**

Saw cuts shall be cleaned with compressed air to remove all excess moisture and debris. For repairing damaged saw cuts, all loose spalled material shall be cleaned away from the saw cut, chipping back to sound asphalt concrete or portland cement concrete and all loose material cleaned from loop wires.

The mixing ratio shall be in conformance with the manufacturer's recommendations. No more material shall be mixed than can be used within the gel time from the time mixing operations are started.

When automatic mixing equipment is used for mixing the sealant, the provisions in the twelfth paragraph in Section 85-1.06, "Placement," shall apply.

**95-2.10 (BLANK)****95-2.11 EPOXY RESIN ADHESIVE FOR INJECTION GROUTING OF PORTLAND CEMENT CONCRETE PAVEMENTS****Directions for Use:**

Both components and the mixed material shall contain no solvents. The mixing ratio of the components in terms of volume and mass shall be clearly stated. The material shall be suitable for use in the mixing equipment used by the applicator. Epoxy adhesive samples shall be furnished to the Engineer for testing at least 12 days before the expected time of use.

**Characteristics of Adhesive:**

Test <sup>a</sup>	California Test	Requirement
Brookfield Viscosity, No. 3 Spindle at 20 rpm, Pa·s at 25°C	434, Part 4	0.9 max.
Gel time, minutes	434, Part 1	2 to 15
Slant Shear Strength on Dry Concrete, MPa, after 4 days of cure in air at 25°C ±1°C	434, Part 5 <sup>b</sup>	41.4 min.
Slant Shear Strength on Wet Concrete, MPa, after 4 days of cure in air at 25°C ±1°C	434, Part 5 <sup>b</sup>	21.1 min.
Tensile Strength, Mpa	434, Part 7, except test after 4 days of cure at 25°C ±1°C	31.0 min.
Elongation, %	434, Part 7, except test after 4 days of cure at 25°C ±1°C	10 max.

a The mixing ratio used will be that recommended by the manufacturer.

b For slant shear strength on concrete, delete Sections B-1 and B-5 of California Test 434, Part 5. For dry concrete, use Step "2" below only. For wet concrete, use both Steps "1" & "2":

1 Soak blocks in water for 24 hours at 25°C ±1°C. Remove and wipe off excess water.

2 Mix epoxy as described in California Test 434, Part 1, and apply a coat approximately 250 µm thick to each diagonal surface. Place four 3-mm square pieces of shim stock 305 µm thick on one block to control final film thickness. Before pressing the coated surfaces together, leave the blocks so that the coated surfaces are horizontal until the epoxy reacts slightly to prevent excessive flow.

**END OF AMENDMENTS**