

**DEPARTMENT OF TRANSPORTATION**  
**DIVISION OF ENGINEERING SERVICES**  
OFFICE ENGINEER, MS 43  
1727 30<sup>TH</sup> STREET  
P.O. BOX 168041  
SACRAMENTO, CA 95816-8041  
FAX (916) 227-6214  
TTY (916) 227-8454



*Flex your power!  
Be energy efficient!*

**\*\* WARNING \*\* WARNING \*\* WARNING \*\* WARNING \*\***  
**This document is intended for informational purposes only.**

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

October 28, 2007

07-LA-5-C45.4/C46.1  
07-1X8404  
ACSTP-43Y1(001)E

Addendum No. 3

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in LOS ANGELES COUNTY NEAR LOS ANGELES FROM SOUTH 14 TO SOUTH 5 CONNECTOR OVERHEAD TO 0.4 MILE SOUTH OF WELDON CANYON OVERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on October 29, 2007 at 10:00 a.m.

This addendum is being issued to revise the Project Plans, the Notice to Contractors and Special Provisions, and the Proposal and Contract.

Project Plan Sheet 44 is revised as follows:

"SPRAY MORTAR 45 CF" is added to the QUANTITIES table.

In the Special Provisions, Section 10-1.27, "MAINTAINING TRAFFIC," the tenth through sixteenth paragraphs are deleted.

In the Special Provisions, Section 10-1.33, "BARRICADE," is deleted.

In the Special Provisions, Section 10-1.45, "CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)," subsection "RAPID STRENGTH CONCRETE," subtitle "General," the following paragraph is added after the fifth paragraph as follows:

"Cracks shall be sealed conforming to the requirements in "DECK CRACK TREATMENT" in "CONCRETE STRUCTURES" of these special provisions."

In the Special Provisions, Section 10-1.45, "CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)," subsection "MEASUREMENT AND PAYMENT," the third paragraph is revised as follows:

"Full compensation for tie bars, dowels, sealing cracks, and the pre-operation conference, including furnishing the facility to hold the pre-operation conference in, shall be considered as included in the contract prices paid for the item involving RSC and no additional compensation will be made therefor."

07-LA-5-C45.4/C46.1  
07-1X8404  
ACSTP-43Y1(001)E

In the Special Provisions, Section 10-1.54, "SHOTCRETE (STRUCTURAL SECTION)," the third paragraph is revised as follows:

"Where the removal of unsound concrete at the abutment walls is deeper than the centerline of the existing No. 8 and larger reinforcing steel bars, the volume behind the bars shall be filled with spray mortar."

In the Special Provisions, Section 10-1.54, "SHOTCRETE (STRUCTURAL SECTION)," subsection "MEASUREMENT AND PAYMENT," the first and second paragraphs are revised as follows:

"Spray mortar will be measured and paid for by the cubic foot as spray mortar. Shotcrete will be measured and paid for by the cubic yard as shotcrete (structural section).

The contract price paid per cubic yard for shotcrete (structural section) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in applying shotcrete, including welded wire fabric, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer."

In the Special Provisions, Section 10-1.54, "SHOTCRETE (STRUCTURAL SECTION)," subsection "MEASUREMENT AND PAYMENT," the following paragraphs are added as follows:

"The contract price paid per cubic foot for spray mortar shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in applying spray mortar, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Bar reinforcing steel will be measured and paid for as bar reinforcing steel (bridge)."

In the Proposal and Contract, the Engineer's Estimate Items 78 and 79 are added and Item 77 is deleted as attached.

To Proposal and Contract book holders:

Replace page 6 of the Engineer's Estimate in the Proposal with the attached revised page 6 of the Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the NOTICE TO CONTRACTORS section of the Notice to Contractors and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

Addendum No. 3  
Page 3  
October 28, 2007

07-LA-5-C45.4/C46.1  
07-1X8404  
ACSTP-43Y1(001)E

This office is sending this addendum by confirmed facsimile to Proposal and Contract book holders to ensure that each receives it. A copy of this addendum is available for the contractor's use on the Web site:

**[http://www/hq/esc/oe/project\\_ads\\_addenda/07/07-1X8404/pdf/](http://www/hq/esc/oe/project_ads_addenda/07/07-1X8404/pdf/)**

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief  
Office of Plans, Specifications & Estimates  
Division of Engineering Services - Office Engineer

Attachments

**ENGINEER'S ESTIMATE  
07-1X8404**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
61 (S)	839605	CRASH CUSHION (REACT 9SCBS)	EA	2		
62	839701	CONCRETE BARRIER (TYPE 60)	LF	490		
63	839720	CONCRETE BARRIER (TYPE 732)	LF	54		
64	013033	CONCRETE BARRIER (TYPE 732 RETROFIT)	LF	80		
65 (S)	840504	4" THERMOPLASTIC TRAFFIC STRIPE	LF	17,800		
66 (S)	840506	8" THERMOPLASTIC TRAFFIC STRIPE	LF	2,210		
67 (S)	840525	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12)	LF	8,820		
68 (S)	850101	PAVEMENT MARKER (NON-REFLECTIVE)	EA	740		
69 (S)	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	630		
70 (S)	860090	MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION	LS	LUMP SUM	LUMP SUM	
71 (S)	041221	UNDERCROSSING ELECTRICAL WORK	LS	LUMP SUM	LUMP SUM	
72 (S)	013034	VEHICLE SPEED FEEDBACK SYSTEM	LS	LUMP SUM	LUMP SUM	
73 (S)	861504	MODIFY LIGHTING AND SIGN ILLUMINATION	LS	LUMP SUM	LUMP SUM	
74	BLANK					
75	013049	HAZARDOUS MATERIALS MITIGATION PLANS AND REPORTS	LS	LUMP SUM	LUMP SUM	
76	041222	PREPARE CONCRETE ABUTMENT WALL SURFACE	SQ FT	18,915		
77	BLANK					
78	041223	SPRAY MORTAR	CF	45		
79	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

**TOTAL BID: \_\_\_\_\_**