Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	LA	5	R59.7/R73.7	17	50

REGISTERED CIVIL ENGINEER 6-10-10 DATE

6-28-10
PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER DEBORAH WONG No. 58313 Exp. 6-30-12 CIVIL STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

SUMMARY OF QUANTITIES OF RAMPS

DIRECTION	LOCATION	COLD PLANE CONCRETE PAVEMENT	ASPHALT RUBBER SEAL COAT: ASPHALT-RUBBER BINDER	ASPHALT RUBBER SEAL COAT: SCREENINGS (HOTAPPLIED)	HOT MIX ASPHALT CONCRETE (TYPE B)	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	RAMP TERMINI (RAPID STRENGTH CONCRETE)	LEAN CONCRETE BASE (RAPID SETTING)	CLASS 3 AGGREGATE BASE	REMOVE CONCRETE (CURB, GUTTER, AND SIDEWALK)	ROADWAY EXCAVATION	MINOR CONCRETE (CURB RAMP)	MINOR CONCRETE (CURB AND GUTTER)	REMOVE AC DIKE
		SQYD	TON	TON	TON	TON	CY	CY	CY	CY	CY	CY	CY	LF
SB	TEMPLIN HIGHWAY OFF RAMP	4,267	10.7	72.5		720	120	42	29.4	6.22	266.22	6.22	12.4	400
SB	TEMPLIN HIGHWAY ON RAMP									6.22	6.22	6.22		
NB	TEMPLIN HIGHWAY OFF RAMP						120	42	29.4	6.22	266.22	6.22	12.4	400
NB	TEMPLIN HIGHWAY ON RAMP	4,133	10.3	70.3		698				6.22	6.22	6.22		
SB	TRUCK BRAKE INSPECTION OFF RAMP	2,556			345									
SB	TRUCK BRAKE INSPECTION ON RAMP	7,778			1050									
SUB TOTAL		18,734	21	142.8	1395	1418	240	84	58.8	24.9	544.9	24.9	24.8	800

TOTAL QUANTITIES

	LOCATION	COLD PLANE ASPHALT CONCRETE PAVEMENT	ASPHALT RUBBER SEAL COAT: ASPHALT-RUBBER BINDER	ASPHALT RUBBER SEAL COAT: SCREENINGS (HOT APPLIED)	HOT MIX ASPHALT CONCRETE (TYPE B)	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	HOT MIX ASPHALT CONCRETE (TYPE C)	TACK COAT	REPLACE CONCRETE PAVEMENT (RSC)	RAMP TERMINI (RAPID STRENGTH CONCRETE)	DOWEL BAR	TIE BAR	SEAL PAVEMENT JOINT	SEAL ISOLATION JOINT	LEAN CONCRETE BASE (RAPID SETTING)	CLASS 3 AGGREGATE BASE	GRIND EXISTING AND REPLACEMENT CONCRETE PAVEMENT (RSC)	REMOVE CONCRETE	ROADWAY EXCAVATION	MINOR CONCRETE (CURB RAMP)	MINOR CONCRETE (CURB AND GUTTER)	REMOVE AC DIKE
		SQYD	TON	TON	TON	TON	TON	TON	CY	CY	EA	EA	LF	LF	CY	CY	SQYD	CY	CY	CY	CY	LF
4	MAINLINES	963,774 ~~1,053,534~~	1972	13,403		122,601 ~~142,226~~	15,015 ~~7508~~	884	3202		10,755	3534	19,695	15,756	1673		53,504					
	RAMPS	18,734	21	145	1395	1,418				240					84	58.8		24.9	544.9	24.9	24.8	800
4	TOTAL	982,508 ~~1,072,268~~	1993	13,548	1395	124,019 ~~143,644~~	15,015 ~~7508~~	884	3202	240	10,755	3534	19,695	15,756	1757	58.8	53,504	24.9	544.9	24.9	24.8	800

4 4

4 REVISED PER ADDENDUM No. 4 DATED NOVEMBER 12, 2010

SUMMARY OF QUANTITIES

Q-2

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
MAINTENANCE ENGINEERING

FUNCTIONAL SUPERVISOR: MONIR IBRAHIM
CALCULATED-DESIGNED BY: ROXANA DIANATI
CHECKED BY: DEBORAH WONG
REVISED BY
DATE REVISED

LAST REVISION DATE PLOTTED => 13-AUG-2010
06-28-10 TIME PLOTTED => 12:15