

DEPARTMENT OF TRANSPORTATION

DES-OE MS #43
1727 30TH Street, 2ND Floor
Sacramento, CA 95816



**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

July 17, 2003

07-Ven-101-14.6
07-4H9104

Addendum No. 2

Dear Contractor:

This addendum is being issued to the contract for Building Construction in VENTURA COUNTY AT THE CONEJO WESTBOUND WEIGH STATION.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on August 7, 2003, instead of the original date of July 24, 2003.

This addendum is being issued to set a new bid opening date as shown herein, and to revise Notice to Contractors Instructions to Bidders General Conditions and Special Provisions.

In the Special Provisions, Division 2, "**SITWORK**," the following new Division is added after the last Division:

"2.04 CONCRETE RAILING (TYPE K)

The Contractor shall furnish and install concrete railing (Type K) as shown on the project plans, as shown on Standard Plan T3 in the State of California Department of Transportation "Standard Plans" dated July 1999, and in conformance with the provisions for temporary railing (Type K) in Section 12-3.08, "Temporary Railing (Type K)," of the Standard Specifications, dated July 1999.

Removable panels shall not be used and the concrete railing (Type K) shall remain in place at the completion of the contract.

Type K railing fabricated prior to January 1, 1993, and conforming to 1988 Standard Plan B11-30 may be used, provided the fabrication date is printed on a Certificate of Compliance and vertical holes are not drilled in the top of the temporary railing to secure temporary traffic screen.

The Type K railing shall be permanently anchored to the existing pavement."

07-Ven-101-14.6
07-4H9104

In the Special Provisions, Division 13.01, "**MODULAR BUILDING**" in the sub-division "**SYSTEM DESCRIPTION**," the following new requirement is added at the end:

"Foundation requirements.—Foundation shall be a pier and pad type with tie-down system."

In the Special Provisions, Division 13.01, "**MODULAR BUILDING**," the first paragraph of sub-division "**SUBMITTALS**," is replaced as follows:

"Shop drawings.—Shop drawings shall be submitted for approval in accordance with the General Requirements. Shop drawings shall consist of catalog cuts, design and erection drawings, shop painting and finishing specifications, instruction manuals, and other data as necessary to clearly describe design, materials, sizes, layouts, construction details, fasteners, erection, and foundation anchoring system. All module designs shall be accompanied by engineering design calculations for structural, foundation, and covering components. The calculations shall be signed by a registered Civil or Structural Engineer registered in the State of California. The Engineer's original signature shall be submitted with the expiration date of the registration shown. Copies will not be accepted."

In the Special Provisions, Division 13.01, "**MODULAR BUILDING**," the sub-division "**WARRANTY**," is replaced as follows:

"WARRANTY.—The Contractor shall furnish the manufacturer's 5 year warranty for the modular building system, including structural elements, exterior cladding, flashings, and finishes defects caused by poor materials or workmanship. The warranty shall run directly to the Department.

The warranty shall state that: When within the warranty period the modular building system becomes non-watertight or separates at seams because of defective materials and workmanship, the repair or replacement of defective materials and correction of defective workmanship shall be the responsibility of the building manufacture. When the manufacturer or the manufacturer's approved applicator fail to perform repairs within 72 hours of notification, emergency repairs performed by others shall not void the warranty. Damage to the modular building system caused by sustained winds having a velocity of 90 kilometers per hour or less shall be covered by the warranty."

In the Special Provisions, Division 13.01, "**MODULAR BUILDING**," the first paragraph of sub-division "**PROJECT/SITE CONDITIONS**," is replaced with the following:

"Existing conditions.—The modules shall be installed on the existing asphalt paving."

To Proposal and Contract book holders:

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

Addendum No. 2
Page 3
July 17, 2003

07-Ven-101-14.6
07-4H9104

This office is sending this addendum by confirmed facsimile to all book holders to ensure that each receives it. A copy of this addendum is available for the contractor's use on the Internet Site:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief
Office of Plans, Specifications & Estimates
Office Engineer