

**DEPARTMENT OF TRANSPORTATION**  
DIVISION OF ENGINEERING SERVICES  
OFFICE ENGINEER, MS 43  
1727 30<sup>TH</sup> STREET  
P.O. BOX 168041  
SACRAMENTO, CA 95816-8041  
FAX (916) 227-6214  
TTY 711



*Flex your power!  
Be energy efficient!*

January 4, 2010

08-Riv-91-R0.0/9.0  
08-0A5504  
ACNH-P091(128)E

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN RIVERSIDE COUNTY IN AND NEAR CORONA FROM ORANGE/RIVERSIDE COUNTY LINE TO 0.2 MILE WEST OF MCKINLEY STREET.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Thursday, January 7, 2010.

This addendum is being issued to revise the Notice to Bidders and Special Provisions and the Bid book.

In the Special Provisions, Section 10-1.01, "ORDER OF WORK," the following paragraph is added after the fourth paragraph:

"The Contractor shall not perform construction work between PM 0.0 to PM 2.9 eastbound Route 91 until September 2010, or as directed by the Engineer."

In the Special Provisions, Section 10-1.15, "MAINTAINING TRAFFIC," Lane Closure Chart Nos. 2 and 4 are revised as attached.

In the Special Provisions, Section 10-1.15, "MAINTAINING TRAFFIC," Lane Closure Chart No. 19 is added after Lane Closure Chart No. 18 as attached.

In the Special Provisions, Section 10-1.31, "PAVING NOTCH EXTENSION," the fifteenth and sixteenth paragraphs are revised as follows:

"The quantity of concrete for paving notch extension will be measured by the cubic yard.

The contract price paid per cubic yard for paving notch extension shall include full compensation for furnishing all labor, materials (including concrete for the paving notch spalled areas), tools, equipment, and incidentals, and for doing all the work involved in constructing the paving notch extension, complete in place, including structure excavation and backfill, reinforcement, and drilling and bonding dowels, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer."

Addendum No. 1  
Page 2  
January 4, 2010

08-Riv-91-R0.0/9.0  
08-0A5504  
ACNH-P091(128)E

In the Bid book, in the "Bid Item List," Item 11 is deleted as attached.

To Bid book holders:

Replace page 3 of the "Bid Item List" in the Bid book with the attached revised page 3 of the Bid Item List. The revised Bid Item List is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This addendum and attachments are available for the Contractors' download on the Web site:

**[http://www.dot.ca.gov/hq/esc/oe/project\\_ads\\_addenda/08/08-0A5504](http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/08/08-0A5504)**

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL  
Chief, Office of Plans, Specifications & Estimates  
Office Engineer  
Division of Engineering Services

Attachments

**Chart No. 2 (4 lane + 1 HOV lane section)  
Freeway/Expressway Lane Requirements**

County: Riverside	Route/Direction: 91/eb	PM: 1.5/9.0
-------------------	------------------------	-------------

Closure Limits: SR-91/SR-71 connector to McKinley St

FROM HOUR TO HOUR	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mondays through Thursdays	1	1	1	1	1	3																			3
Fridays	1	1	1	1	1	3																			
Saturdays	3	1	1	1	1	1	3																		
Sundays	3	1	1	1	1	1	1	2	3																3

Legend:

- 1 Provide at least one through freeway lane open in direction of travel
- 2 Provide at least two adjacent through freeway lanes open in direction of travel
- 3 Provide at least three adjacent through freeway lanes open in direction of travel
- Work permitted within project right of way where shoulder or lane closure is not required.

**REMARKS:** The Contractor will close or utilize the HOV lanes as the mix flow lanes during the working hours

**Chart No. 4 (4 mix flow + 1 HOV lane section)  
Freeway/Expressway Lane Requirements**

County: Riverside	Route/Direction: 91/wb	PM: 1.5/9.0
-------------------	------------------------	-------------

Closure Limits: SR-91/SR-71 connector to McKinley St

FROM HOUR TO HOUR	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	
Mondays through Thursdays	1	1	1	1																				3	3	1
Fridays	1	1	1	1																					3	2
Saturdays	3	1	1	1	1	3																				
Sundays	3	1	1	1	1	1	2	3																		3

Legend:

- Provide at least one through freeway lane open in direction of travel
- Provide at least two adjacent through freeway lanes open in direction of travel
- Provide at least three adjacent through freeway lanes open in direction of travel
- Work permitted within project right of way where shoulder or lane closure is not required.

**REMARKS:** The Contractor will close or utilize the HOV lanes as the mix flow lanes during the working hours

**Chart No. 19 (4 mix flow + 1 HOV lane section)  
Freeway/Expressway Lane Requirements**

County: Riverside	Route/Direction: 91/eb & wb	PM: 1.5/9.0
-------------------	-----------------------------	-------------

Closure Limits: SR-91/SR-71 connector to McKinley St

FROM HOUR TO HOUR	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	
Mondays through Thursdays																										
Fridays																										
Saturdays																										
Sundays	1	1	1	1	1	1	1	1																		

Legend:

1	Provide at least one through freeway lane open in direction of travel
	Work permitted within project right of way where shoulder or lane closure is not required.

**REMARKS:** This chart shall be utilized only when work is being done on the number 2 mixed flow lane and #2 mixed flow lane of the bridge approach and departure slabs.

**BID ITEM LIST  
08-0A5504**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	070012	PROGRESS SCHEDULE (CRITICAL PATH METHOD)	LS	LUMP SUM	LUMP SUM	
2	070013	SMALL BUSINESS UTILIZATION REPORT	EA	4	250.00	1,000.00
3	070018	TIME-RELATED OVERHEAD	WDAY	180		
4	074016	CONSTRUCTION SITE MANAGEMENT	LS	LUMP SUM	LUMP SUM	
5	074019	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	LUMP SUM	LUMP SUM	
6	074031	TEMPORARY GRAVEL BAG BERM	LF	5,000		
7	074033	TEMPORARY CONSTRUCTION ENTRANCE	EA	2		
8	074034	TEMPORARY COVER	SQYD	30,000		
9	074041	STREET SWEEPING	LS	LUMP SUM	LUMP SUM	
10	074042	TEMPORARY CONCRETE WASHOUT (PORTABLE)	LS	LUMP SUM	LUMP SUM	
11	BLANK					
12	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
13	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
14	128650	PORTABLE CHANGEABLE MESSAGE SIGN	EA	4		
15	150722	REMOVE PAVEMENT MARKER	EA	34,500		
16	153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	134,000		
17	160101	CLEARING AND GRUBBING	LS	LUMP SUM	LUMP SUM	
18	190110	LEAD COMPLIANCE PLAN	LS	LUMP SUM	LUMP SUM	
19	260210	AGGREGATE BASE (APPROACH SLAB)	CY	133		
20	374206	SEAL RANDOM CRACKS	LNMI	12		