

**** WARNING ** WARNING ** WARNING ** WARNING ****

This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.



Caltrans[®]

**STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION**

**NOTICE TO BIDDERS
AND
SPECIAL PROVISIONS**

**FOR CONSTRUCTION ON STATE HIGHWAY IN RIVERSIDE COUNTY ABOUT 1.0 MILE
EAST OF CALIMESA IN BEAUMONT AT BROOKSIDE SAFETY ROADSIDE REST AREA**

In District 08 On Route 10

Under

Bid book dated October 14, 2008

Standard Specifications dated 2006

Project Plans approved August 25, 2008

Standard Plans dated 2006

Identified by

Contract No. 08-0F3504

08-Riv-10-R4.3

Bids Open: November 13, 2008

Dated: October 14, 2008

OSD

IH

SPECIAL NOTICES

- The Department moved the Amendments to the Standard Specifications to the back of the book titled "Notice to Bidders and Special Provisions."
- The Department retitled the "Proposal and Contract" book to "Bid" book and:
 1. Simplified the language
 2. Moved clauses and the contract form from the "Proposal and Contract" book into the Amendments to the Standard Specifications
 3. Standardized the forms
- The Department retitled the "Notice to Contractors" to "Notice to Bidders" and:
 1. Simplified the language
 2. Moved clauses from the "Notice to Contractors" into the Amendments to the Standard Specifications
 3. Standardized instructions for bidders' inquiries
- The Department incorporated boilerplate special provisions into the Amendments to the Standard Specifications.

TABLE OF CONTENTS

NOTICE TO BIDDERS	1
COPY OF BID ITEM LIST.....	3
SPECIAL PROVISIONS.....	4
SECTION 1 (BLANK).....	4
SECTION 2 BIDDING.....	4
SECTION 2-1 GENERAL.....	4
SECTION 3 CONTRACT AWARD AND EXECUTION.....	4
SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION, AND LIQUIDATED DAMAGES	4
SECTION 5 GENERAL.....	4
SECTION 5-1 MISCELLANEOUS.....	4
5-1.01 SUPPLEMENTAL PROJECT INFORMATION	4
5-1.02 AREAS FOR CONTRACTOR'S USE.....	4
5-1.03 PAYMENTS	5
5-1.04 RELATIONS WITH CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD.....	5
5-1.05 PRESERVATION OF PROPERTY.....	5
SECTION 6. (BLANK).....	6
SECTION 7. (BLANK).....	6
SECTION 8. MATERIALS.....	6
SECTION 8-1. MISCELLANEOUS.....	6
8-1.01 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS.....	6
SECTION 8-2. CONCRETE	11
8-2.01 PORTLAND CEMENT CONCRETE	11
SECTION 8-3. (BLANK).....	12
SECTION 9. (BLANK).....	12
SECTION 10. CONSTRUCTION DETAILS	12
SECTION 10-1. GENERAL.....	12
10-1.01 ORDER OF WORK.....	12
10-1.02 WATER POLLUTION CONTROL.....	12
10-1.03 CONSTRUCTION SITE MANAGEMENT.....	16
10-1.04 TEMPORARY COVER.....	24
10-1.05 TEMPORARY CONCRETE WASHOUT (PORTABLE)	26
10-1.06 OBSTRUCTIONS.....	26
10-1.07 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES.....	27
10-1.08 CONSTRUCTION AREA SIGNS.....	28
10-1.09 MAINTAINING TRAFFIC	28
10-1.10 TRAFFIC CONTROL SYSTEM FOR RAMP CLOSURES.....	29
10-1.11 TEMPORARY CRASH CUSHION MODULE	29
10-1.12 EXISTING HIGHWAY FACILITIES.....	31
EXISTING HIGHWAY IRRIGATION FACILITIES.....	31
REMOVE CONCRETE.....	31
REMOVE ASPHALT CONCRETE	31
10-1.13 REMOVE TREE	31
10-1.14 MINOR HOT MIX ASPHALT.....	31
10-1.15 PRECAST CONCRETE PICNIC TABLES AND BENCHES.....	32
10-1.16 INSTALL ROADSIDE SIGN PANEL ON EXISTING POST	32
10-1.17 FURNISH SIGN.....	32
RETROREFLECTIVE SHEETING.....	34
PROCESS COLOR AND FILM.....	34
10-1.18 MINOR CONCRETE (EXPOSED AGGREGATE SIDEWALK)	34
SECTION 10-2 HIGHWAY PLANTING AND IRRIGATION SYSTEMS	35
10-2.01 GENERAL	35
PROGRESS INSPECTIONS	35
10-2.02 EXISTING HIGHWAY PLANTING	35

MAINTAIN EXISTING PLANTED AREAS	35
PRUNE EXISTING PLANTS.....	36
10-2.03 EXISTING HIGHWAY IRRIGATION FACILITIES.....	36
CHECK AND TEST EXISTING IRRIGATION FACILITIES.....	36
RELOCATE EXISTING IRRIGATION FACILITIES	37
10-2.04 IRRIGATION SYSTEMS.....	37
FINAL IRRIGATION SYSTEM CHECK.....	37
SECTION 11. (BLANK).....	37
SECTION 12. BUILDING WORK.....	37
SECTION 12-1. GENERAL REQUIREMENTS.....	37
12-1.01 SCOPE.....	37
12-1.02 ABBREVIATIONS.....	38
12-1.03 GUARANTEE	38
12-1.04 COOPERATION.....	39
12-1.05 SUBMITTALS.....	39
12-1.06 PROGRESS SCHEDULE.....	40
12-1.07 SCHEDULE OF VALUES	40
12-1.08 INSPECTION.....	40
12-1.09 OBSTRUCTIONS.....	40
12-1.10 PRESERVATION OF PROPERTY.....	40
12-1.11 UTILITY CONNECTION	41
12-1.12 TEMPORARY UTILITIES.....	41
12-1.13 SANITARY FACILITIES.....	41
12-1.14 MEASUREMENT AND PAYMENT.....	41
12-1.15 PROJECT RECORD DRAWINGS.....	42
SECTION 12-2. SITEWORK.....	42
12-2.01 REMOVING PORTIONS OF EXISTING FACILITIES	42
12-2.02 LEAD RELATED CONSTRUCTION WORK	43
12-2.03 EARTHWORK FOR BUILDING WORK	47
12-2.04 FREE DRAINING GRANULAR MATERIAL.....	48
12-2.05 PAINTED PAVEMENT MARKINGS	49
12-2.06 PARKING BUMPERS.....	50
12-2.07 ACCESSIBLE PARKING AND PARKING AREA ENTRANCE SIGNS.....	51
SECTION 12-3. CONCRETE AND REINFORCEMENT	52
12-3.01 CAST-IN-PLACE CONCRETE	52
SECTION 12-5. METALS	58
12-5.01 BUILDING MISCELLANEOUS METAL.....	58
12-5.02 ALUMINUM HANDRAIL AND RAILINGS.....	61
SECTION 12-6. WOOD AND PLASTICS.....	63
12-6.01 ROUGH CARPENTRY	63
SECTION 12-7. THERMAL AND MOISTURE PROTECTION	66
12-7.01 PREPARATION FOR RE-ROOFING.....	66
12-7.02 BUILT-UP ASPHALT ROOFING SYSTEM.....	68
12-7.03 SHEET METAL FLASHING	74
12-7.04 JOINT SEALANT.....	76
12-7.05 SEALANTS AND CAULKING	78
SECTION 12-8. DOORS AND WINDOWS	79
12-8.01 HINGED DOORS.....	79
12-8.02 GLAZING.....	80
SECTION 12-9. FINISHES.....	81
12-9.01 CERAMIC AND QUARRY TILE.....	81
12-9.02 DETECTABLE WARNING	88
12-9.03 PAINTING.....	90
SECTION 12-10. SPECIALTIES.....	95
12-10.01 METAL TOILET PARTITIONS	95
12-10.02 SIGNS	97
12-10.03 TELEPHONE ENCLOSURES	98
12-10.04 TOILET ROOM ACCESSORIES.....	98
12-10.05 PREFABRICATED PICNIC SHELTER.....	100

SECTION 12-11. (BLANK).....	100
SECTION 12-12. (BLANK).....	100
SECTION 12-13. (BLANK).....	100
SECTION 12-14. (BLANK).....	100
SECTION 12-15. MECHANICAL.....	100
12-15.01 MECHANICAL WORK.....	100
12-15.02 PIPE, FITTINGS AND VALVES.....	102
12-15.03 PLUMBING FIXTURES.....	106
SECTION 12-16. ELECTRICAL.....	109
12-16.01 ELECTRICAL WORK.....	109
12-16.02 BASIC MATERIALS AND METHODS.....	110
16.03 LIGHTING.....	114
AMENDMENTS TO THE STANDARD SPECIFICATIONS.....	117

STANDARD PLANS LIST

The Standard Plan sheets applicable to this contract include, but are not limited to those indicated below. The Revised Standard Plans (RSP) and New Standard Plans (NSP) which apply to this contract are included as individual sheets of the project plans.

A10A	Acronyms and Abbreviations (Sheet 1 of 2)
A10B	Acronyms and Abbreviations (Sheet 2 of 2)
A10C	Symbols (Sheet 1 of 2)
A10D	Symbols (Sheet 2 of 2)
H1	Planting and Irrigation – Abbreviations
RSP H2	Planting and Irrigation – Symbols
H3	Planting and Irrigation Details
H4	Planting and Irrigation Details
H5	Planting and Irrigation Details
H6	Planting and Irrigation Details
H7	Planting and Irrigation Details
H8	Planting and Irrigation Details
H9	Planting and Irrigation Details
RSP T1A	Temporary Crash Cushion, Sand Filled (Unidirectional)
RSP T1B	Temporary Crash Cushion, Sand Filled (Bidirectional)
RSP T2	Temporary Crash Cushion, Sand Filled (Shoulder Installations)
T3	Temporary Railing (Type K)
T14	Traffic Control System for Ramp Closure
T53	Temporary Water Pollution Control Details (Temporary Cover)
RS1	Roadside Signs, Typical Installation Details No. 1
RS2	Roadside Signs – Wood Post, Typical Installation Details No. 2
RS4	Roadside Signs, Typical Installation Details No. 4

DEPARTMENT OF TRANSPORTATION

NOTICE TO BIDDERS

Bids Open: November 13, 2008

Dated: October 14, 2008

General work description: Upgrade Safety Roadside Rest Area.

The Department will receive sealed bids for CONSTRUCTION ON STATE HIGHWAY IN RIVERSIDE COUNTY ABOUT 1.0 MILE EAST OF CALIMESA IN BEAUMONT AT BROOKSIDE SAFETY ROADSIDE REST AREA.

District-County-Route-Post Mile: 08-Riv-10-R4.3

Contract No. 08-0F3504

The Contractor must have either a Class A license or Class B license or a combination of Class C licenses which constitutes a majority of the work.

The DVBE Contract goal is 5 percent.

Bids must be on a unit price basis.

Complete the work within 83 working days.

The estimated cost of the project is \$420,000.

No prebid meeting is scheduled for this project.

The Department will receive bids until 2:00 p.m. on the bid open date at 3347 Michelson Drive, Suite 100, Irvine, CA 92612-1692. Bids received after this time will not be accepted.

The Department will open and publicly read aloud the bids immediately after the specified closing time. The Department invites bidders or their authorized agents to attend.

Standard Specifications and Standard Plans may be viewed at the Department's Web site and may be purchased at:

Department of Transportation, Publications Unit
1900 Royal Oaks Drive
Sacramento, CA 95815

Special Provisions and Project Plans may be viewed at:

1. The Department's Web site
2. District office of the district in which the work is located
3. Districts 4 and 12 offices
4. Department of Transportation, Bid Documents
1120 N Street, Room 0200, Mail Station 26
Sacramento, CA 95814
Telephone no.: (916) 654-4490

District office addresses are provided in the Standard Specifications.

The Bid book, Special Provisions, Project Plans, and Information Handout may be obtained at the 1120 N Street location. To expedite orders, a bidder may obtain these documents by faxing an order to (916) 654-7028. Fax orders must include credit card charge number, card expiration date, and authorizing signature.

Bidders' inquiries may be presented to the Department by following the instructions at:

http://www.dot.ca.gov/hq/esc/oe/project_status/bid_inq.html

The Department posts responses to the questions at the District Web sites.

Questions about alleged patent ambiguity of the plans, specifications, or estimate must be asked before bid opening. After bid opening, such questions will not be treated as bid protests.

Submit your bid with bidder's security equal to at least 10 percent of the bid.

Under Govt Code § 14835 et seq. and 2 CA Code of Regs § 1896 et seq., the Department gives preference to certified small businesses and non-small businesses who commit to 25 percent certified small business participation.

Under Pub Cont Code § 6107, the Department gives a reciprocal preference to a California company for bid comparison purposes over a nonresident contractor from any state that provides a preference to contractors from that state on construction contracts.

Prevailing wages are required on this Contract. The Director of the California Department of Industrial Relations determines the general prevailing wage rates. Obtain the wage rates at the DIR Web site, <http://www.dir.ca.gov>, or from the Department's Labor Compliance Office of the district in which the work is located.

DEPARTMENT OF TRANSPORTATION

Dated October 14, 2008

THM

**COPY OF BID ITEM LIST
(NOT TO BE USED FOR BIDDING PURPOSES)**

08-0F3504

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity
1	074016	CONSTRUCTION SITE MANAGEMENT	LS	LUMP SUM
2	074017	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM
3	074034	TEMPORARY COVER	SQYD	40
4	074042	TEMPORARY CONCRETE WASHOUT (PORTABLE)	LS	LUMP SUM
5	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM
6	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM
7	150769	REMOVE ASPHALT CONCRETE	CY	2
8	153210	REMOVE CONCRETE	CY	32
9	160120	REMOVE TREE	EA	1
10	200052	PRUNE EXISTING PLANTS	LS	LUMP SUM
11	204096	MAINTAIN EXISTING PLANTED AREAS	LS	LUMP SUM
12	015210	RELOCATE EXISTING IRRIGATION FACILITIES	LS	LUMP SUM
13	390136	MINOR HOT MIX ASPHALT	TON	4
14	015211	PRECAST CONCRETE PICNIC TABLES AND BENCHES	EA	6
15	568017	INSTALL ROADSIDE SIGN PANEL ON EXISTING POST	EA	2
16	731512	MINOR CONCRETE (EXPOSED AGGREGATE SIDEWALK)	CY	33
17	994650	BUILDING WORK	LS	LUMP SUM

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISIONS

SECTION 1 (BLANK)

SECTION 2 BIDDING

SECTION 2-1 GENERAL

Reserved

SECTION 3 CONTRACT AWARD AND EXECUTION

Reserved.

SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION, AND LIQUIDATED DAMAGES

Complete the work within 83 working days starting on the 15th day after contract approval or on the day you start work at the job site, whichever occurs first.

Liquidated damages are \$1,000 per day starting on the 1st day after exceeding 83 working days.

SECTION 5 GENERAL

SECTION 5-1 MISCELLANEOUS

5-1.01 SUPPLEMENTAL PROJECT INFORMATION

Supplemental project information included in the Information Handout is:

1. Asbestos and Lead Based Paint Survey Report

5-1.02 AREAS FOR CONTRACTOR'S USE

Attention is directed to the provisions in Section 7-1.19, "Rights in Land and Improvements," of the Standard Specifications and these special provisions.

The highway right of way shall be used only for purposes that are necessary to perform the required work. The Contractor shall not occupy the right of way, or allow others to occupy the right of way, for purposes which are not necessary to perform the required work.

No State-owned parcels adjacent to the right of way are available for the exclusive use of the Contractor within the contract limits. The Contractor shall secure, at the Contractor's own expense, areas required for plant sites, storage of equipment or materials, or for other purposes.

No area is available within the contract limits for the exclusive use of the Contractor. However, temporary storage of equipment and materials on State property may be arranged with the Engineer, subject to the prior demands of State maintenance forces and to other contract requirements. Use of the Contractor's work areas and other State-owned property shall be at the Contractor's own risk, and the State shall not be held liable for damage to or loss of materials or equipment located within such areas.

Use of the Contractor's work areas and other State-owned property shall be at the Contractor's own risk, and the State shall not be held liable for damage to or loss of materials or equipment located within these areas.

Residence trailers will not be allowed within the highway right of way, except that one trailer will be allowed for yard security purposes.

The Contractor shall remove equipment, materials, and rubbish from the work areas and other State--owned property which the Contractor occupies. The Contractor shall leave the areas in a presentable condition in conformance with the provisions in Section 4-1.02, "Final Cleaning Up," of the Standard Specifications.

5-1.03 PAYMENTS

Attention is directed to Sections 9-1.06, "Partial Payments," and 9-1.07, "Payment After Acceptance," of the Standard Specifications and these special provisions.

No partial payment will be made for any materials on hand which are furnished but not incorporated in the work.

5-1.04 RELATIONS WITH CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD

This project lies within the boundaries of the Santa Ana Regional Water Quality Control Board (RWQCB).

The Contractor shall know and comply with provisions of Federal, State, and local regulations and requirements that govern the Contractor's operations and storm water and non-storm water discharges from the project site and areas of disturbance outside the project limits during construction. Attention is directed to Sections 7-1.01, "Laws to be Observed," 7-1.11, "Preservation of Property," and 7-1.12, "Indemnification and Insurance," of the Standard Specifications.

The Contractor shall be responsible for penalties assessed on the Contractor or the Department as a result of the Contractor's failure to comply with the provisions in "Water Pollution Control" of these special provisions or with the applicable provisions of the Federal, State, and local regulations and requirements.

Penalties as used in this section shall include fines, penalties, and damages, whether proposed, assessed, or levied against the Department or the Contractor, including those levied under the Federal Clean Water Act and the State Porter-Cologne Water Quality Control Act, by governmental agencies or as a result of citizen suits. Penalties shall also include payments made or costs incurred in settlement for alleged violations of applicable laws, regulations, or requirements. Costs incurred could include sums spent instead of penalties, in mitigation or to remediate or correct violations.

WITHHOLDS

The Department will withhold money due the Contractor, in an amount estimated by the Department, to include the full amount of penalties and mitigation costs proposed, assessed, or levied as a result of the Contractor's violation of the permits, or Federal or State law, regulations, or requirements. Funds will be withheld by the Department until final disposition of these costs has been made. The Contractor shall remain liable for the full amount until the potential liability is finally resolved with the entity seeking the penalties. Instead of the withhold, the Contractor may provide a suitable bond in favor of the Department to cover the highest estimated liability for any disputed penalties proposed as a result of the Contractor's violation of the permits, law, regulations, or requirements.

If a regulatory agency identifies a failure to comply with the permits and modifications thereto, or other Federal, State, or local requirements, the Department will withhold money due the Contractor, subject to the following:

- A. The Department will give the Contractor 30 days notice of the Department's intention to withhold funds from payments which may become due to the Contractor before acceptance of the contract. Funds withheld after acceptance of the contract will be made without prior notice to the Contractor.
- B. No withholds of additional amounts out of payments will be made if the amount to be withheld does not exceed the amount being withheld from partial payments in accordance with Section 9-1.06, "Partial Payments," of the Standard Specifications.
- C. If the Department has withheld funds and it is subsequently determined that the State is not subject to the entire amount of the costs and liabilities assessed or proposed in connection with the matter for which the withhold was made, the Department will return the excess amount withheld to the Contractor in the progress payment following the determination. If the matter is resolved for less than the amount withheld, the Department will pay interest at a rate of 6 percent per year on the excess withhold.

The Contractor shall notify the Engineer immediately upon request from the regulatory agencies to enter, inspect, sample, monitor, or otherwise access the project site or the Contractor's records pertaining to water pollution control work. The Contractor and the Department shall provide copies of correspondence, notices of violation, enforcement actions, or proposed fines by regulatory agencies to the requesting regulatory agency.

5-1.05 PRESERVATION OF PROPERTY

Attention is directed to Section 7-1.11, "Preservation of Property," of the Standard Specifications and these special provisions.

Existing trees, shrubs and other plants, that are not to be removed as shown on the plans or specified in these special provisions, and are injured or damaged by reason of the Contractor's operations, shall be replaced by the Contractor. The minimum size of tree replacement shall be 24 inch box and the minimum size of shrub replacement shall be 15-gallon. Replacement ground cover plants shall be from flats and shall be planted 12 inches on center. Replacement of Carpobrotus ground cover plants shall be from cuttings and shall be planted 12 inches on center. Replacement planting shall conform to the requirements in Section 20-4.07, "Replacement," of the Standard Specifications. The Contractor shall water replacement plants in conformance with the provisions in Section 20-4.06, "Watering," of the Standard Specifications.

Damaged or injured plants shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. At the option of the Contractor, removed trees and shrubs may be reduced to chips. The chipped material shall be spread within the highway right of way at locations designated by the Engineer.

Replacement planting of injured or damaged trees, shrubs and other plants shall be completed not less than 20 working days prior to acceptance of the contract. Replacement plants shall be watered as necessary to maintain the plants in a healthy condition.

SECTION 6. (BLANK)

SECTION 7. (BLANK)

SECTION 8. MATERIALS

SECTION 8-1. MISCELLANEOUS

8-1.01 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS

The Department maintains the following list of Prequalified and Tested Signing and Delineation Materials. The Engineer shall not be precluded from sampling and testing products on the list of Prequalified and Tested Signing and Delineation Materials.

The manufacturer of products on the list of Prequalified and Tested Signing and Delineation Materials shall furnish the Engineer a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each type of traffic product supplied.

For those categories of materials included on the list of Prequalified and Tested Signing and Delineation Materials, only those products shown within the listing may be used in the work. Other categories of products, not included on the list of Prequalified and Tested Signing and Delineation Materials, may be used in the work provided they conform to the requirements of the Standard Specifications.

Materials and products may be added to the list of Prequalified and Tested Signing and Delineation Materials if the manufacturer submits a New Product Information Form to the New Product Coordinator at the Transportation Laboratory. Upon a Departmental request for samples, sufficient samples shall be submitted to permit performance of required tests. Approval of materials or products will depend upon compliance with the specifications and tests the Department may elect to perform.

PAVEMENT MARKERS, PERMANENT TYPE

Retroreflective With Abrasion Resistant Surface (ARS)

1. Apex, Model 921AR (4" x 4")
2. Ennis Paint, Models C88 (4" x 4"), 911 (4" x 4") and C80FH
3. Ray-O-Lite, Models "AA" ARS (4" x 4") and ARC Round Shoulder (4" x 4")
4. 3M Series 290 (3.5" x 4")
5. 3M Series 290 PSA
6. Glowlite, Inc Model 988AR (4" x 4")

Retroreflective With Abrasion Resistant Surface (ARS)

(for recessed applications only)

1. Ennis Paint, Model 948 (2.3" x 4.7")
2. Ennis Paint, Model 944SB (2" x 4")*
3. Ray-O-Lite, Model 2002 (2" x 4.6")
4. Ray-O-Lite, Model 2004 ARS (2" x 4")*

*For use only in 4.5 inch wide (older) recessed slots

Non-Reflective, 4-inch Round

1. Apex Universal (Ceramic)
2. Apex Universal, Models 929 (ABS) and 929PP (Polypropylene)
3. Glowlite, Inc. (Ceramic) and PP (Polypropylene)
4. Hi-Way Safety, Inc., Models P20-2000W and 2001Y (ABS)
5. Interstate Sales, "Diamond Back" (Polypropylene)
6. Novabrite Models Cdot (White) Cdot-y (Yellow), Ceramic

7. Novabrite Models Pdot-w (White) Pdot-y (Yellow), Polypropylene
8. Three D Traffic Works TD10000 (ABS), TD10500 (Polypropylene)

PAVEMENT MARKERS, TEMPORARY TYPE

Temporary Markers For Long Term Day/Night Use (180 days or less)

1. Vega Molded Products "Temporary Road Marker" (3" x 4")

Temporary Markers For Short Term Day/Night Use (14 days or less)

(For seal coat or chip seal applications, clear protective covers are required)

1. Apex Universal, Model 932
2. Filtrona Extrusion, Models T.O.M., T.R.P.M., and "HH" (High Heat)
3. Hi-Way Safety, Inc., Model 1280/1281
4. Glowlite, Inc., Model 932

STRIPING AND PAVEMENT MARKING MATERIAL

Permanent Traffic Striping and Pavement Marking Tape

1. Advanced Traffic Marking, Series 300 and 400
2. Brite-Line, Series 1000
3. Brite-Line, "DeltaLine XRP"
4. Swarco Industries, "Director 35" (For transverse application only)
5. Swarco Industries, "Director 60"
6. 3M, "Stamark" Series 380 and 5730
7. 3M, "Stamark" Series 420 (For transverse application only)

Temporary (Removable) Striping and Pavement Marking Tape (180 days or less)

1. Advanced Traffic Marking, Series 200
2. Brite-Line, Series 100
3. Garlock Rubber Technologies, Series 2000
4. P.B. Laminations, Aztec, Grade 102
5. Swarco Industries, "Director-2"
6. Trelleborg Industries, R140 Series
7. 3M Series 620 "CR", and Series A750
8. 3M Series A145, Removable Black Line Mask
(Black Tape: for use only on Hot mix asphalt surfaces)
9. Advanced Traffic Marking Black "Hide-A-Line"
(Black Tape: for use only on Hot mix asphalt surfaces)
10. Brite-Line "BTR" Black Removable Tape
(Black Tape: for use only on Hot mix asphalt surfaces)
11. Trelleborg Industries, RB-140
(Black Tape: for use only on Hot mix asphalt surfaces)

Preformed Thermoplastic (Heated in place)

1. Flint Trading Inc., "Hot Tape"
2. Flint Trading Inc., "Premark Plus"
3. Ennis Paint Inc., "Flametape"

Ceramic Surfacing Laminate, 6" x 6"

1. Highway Ceramics, Inc.

CLASS 1 DELINEATORS

One Piece Driveable Flexible Type, 66-inch

1. Filtrona Extrusion, "Flexi-Guide Models 400 and 566"
2. Carsonite, Curve-Flex CFRM-400
3. Carsonite, Roadmarker CRM-375
4. FlexStake, Model 654 TM
5. GreenLine Model CGD1-66

Special Use Type, 66-inch

1. Filtrona Extrusion, Model FG 560 (with 18-inch U-Channel base)
2. Carsonite, "Survivor" (with 18-inch U-Channel base)
3. Carsonite, Roadmarker CRM-375 (with 18-inch U-Channel base)
4. FlexStake, Model 604
5. GreenLine Model CGD (with 18-inch U-Channel base)
6. Impact Recovery Model D36, with #105 Driveable Base
7. Safe-Hit with 8-inch pavement anchor (SH248-GP1)
8. Safe-Hit with 15-inch soil anchor (SH248-GP2) and with 18-inch soil anchor (SH248-GP3)

Surface Mount Type, 48-inch

1. Bent Manufacturing Company, Masterflex Model MF-180EX-48
2. Carsonite, "Channelizer"
3. FlexStake, Models 704, 754 TM, and EB4
4. Impact Recovery Model D48, with #101 Fixed (Surface-Mount) Base
5. Three D Traffic Works "Channelflex" ID No. 522248W

CHANNELIZERS

Surface Mount Type, 36-inch

1. Bent Manufacturing Company, Masterflex Models MF-360-36 (Round) and MF-180-36 (Flat)
2. Filtrona Extrusion, Flexi-Guide Models FG300PE, FG300UR, and FG300EFX
3. Carsonite, "Super Duck" (Round SDR-336)
4. Carsonite, Model SDCF03601MB "Channelizer"
5. FlexStake, Models 703, 753 TM, and EB3
6. GreenLine, Model SMD-36
7. Hi-way Safety, Inc. "Channel Guide Channelizer" Model CGC36
8. Impact Recovery Model D36, with #101 Fixed (Surface-Mount) Base
9. Safe-Hit, Guide Post, Model SH236SMA and Dura-Post, Model SHL36SMA
10. Three D Traffic Works "Boomerang" 5200 Series

Lane Separation System

1. Filtrona Extrusion, "Flexi-Guide (FG) 300 Curb System"
2. Qwick Kurb, "Klemmfix Guide System"
3. Dura-Curb System
4. Tuff Curb

CONICAL DELINEATORS, 42-inch

(For 28-inch Traffic Cones, see Standard Specifications)

1. Bent Manufacturing Company "T-Top"
2. Plastic Safety Systems "Navigator-42"
3. Traffix Devices "Grabber"
4. Three D Traffic Works "Ringtop" TD7000, ID No. 742143
5. Three D Traffic Works, TD7500
6. Work Area Protection Corp. C-42

OBJECT MARKERS

Type "K", 18-inch

1. Filtrona Extrusion, Model FG318PE
2. Carsonite, Model SMD 615
3. FlexStake, Model 701 KM
4. Safe-Hit, Model SH718SMA

Type "K-4" / "Q" Object Markers, 24-inch

1. Bent Manufacturing "Masterflex" Model MF-360-24
2. Filtrona Extrusion, Model FG324PE
3. Carsonite, "Channelizer"
4. FlexStake, Model 701KM
5. Safe-Hit, Models SH824SMA_WA and SH824GP3_WA
6. Three D Traffic Works ID No. 531702W and TD 5200
7. Three D Traffic Works ID No. 520896W

CONCRETE BARRIER MARKERS AND TEMPORARY RAILING (TYPE K) REFLECTORS

Impactable Type

1. ARTUK, "FB"
2. Filtrona Extrusion, Models PCBM-12 and PCBM-T12
3. Duraflex Corp., "Flexx 2020" and "Electriflexx"
4. Hi-Way Safety, Inc., Model GMKRM100
5. Plastic Safety Systems "BAM" Models OM-BARR and OM-BWAR
6. Three D Traffic Works "Roadguide" Model TD 9304

Non-Impactable Type

1. ARTUK, JD Series
2. Plastic Safety Systems "BAM" Models OM-BITARW and OM-BITARA
3. Vega Molded Products, Models GBM and JD
4. Plastic Vacuum Forming, "Cap-It C400"

METAL BEAM GUARD RAIL POST MARKERS

(For use to the left of traffic)

1. Filtrona Extrusion, "Mini" (3" x 10")
2. Creative Building Products, "Dura-Bull, Model 11201"
3. Duraflex Corp., "Railrider"
4. Plastic Vacuum Forming, "Cap-It C300"

CONCRETE BARRIER DELINEATORS, 16-inch

(For use to the right of traffic)

1. Filtrona Extrusion, Model PCBM T-16
2. Safe-Hit, Model SH216RBM

CONCRETE BARRIER-MOUNTED MINI-DRUM (10" x 14" x 22")

1. Stinson Equipment Company "SaddleMarker"

GUARD RAILING DELINEATOR

(Place top of reflective element at 48 inches above plane of roadway)

Wood Post Type, 27-inch

1. Filtrona Extrusion, FG 427 and FG 527
2. Carsonite, Model 427
3. FlexStake, Model 102 GR
4. GreenLine GRD 27
5. Safe-Hit, Model SH227GRD
6. Three D Traffic Works "Guardflex" TD9100
7. New Directions Mfg, NDM27

Steel Post Type

1. Carsonite, Model CFGR-327

RETROREFLECTIVE SHEETING

Channelizers, Barrier Markers, and Delineators

1. Avery Dennison T-6500 Series (For rigid substrate devices only)
2. Avery Dennison WR-7100 Series
3. Nippon Carbide Industries, Flexible Ultralite Grade (ULG) II
4. Reflexite, PC-1000 Metalized Polycarbonate
5. Reflexite, AC-1000 Acrylic
6. Reflexite, AP-1000 Metalized Polyester
7. Reflexite, Conformalight, AR-1000 Abrasion Resistant Coating
8. 3M, High Intensity

Traffic Cones, 4-inch and 6-inch Sleeves

1. Nippon Carbide Industries, Flexible Ultralite Grade (ULG) II
2. Reflexite, Vinyl, "TR" (Semi-transparent) or "Conformalight"
3. 3M Series 3840
4. Avery Dennison S-9000C

Drums

1. Avery Dennison WR-6100
2. Nippon Carbide Industries, Flexible Ultralite Grade (ULG) II
3. Reflexite, "Conformalight", "Super High Intensity" or "High Impact Drum Sheeting"
4. 3M Series 3810

Barricades: Type I, Medium-Intensity (Typically Enclosed Lens, Glass-Bead Element)

1. Nippon Carbide Industries, CN8117
2. Avery Dennison, W 1100 series
3. 3M Series CW 44

Barricades: Type II, Medium-High-Intensity (Typically Enclosed Lens, Glass-Bead Element)

1. Avery Dennison, W-2100 Series

Signs: Type II, Medium-High-Intensity (Typically Enclosed Lens, Glass-Bead Element)

1. Avery Dennison, T-2500 Series
2. Nippon Carbide Industries, Nikkalite 18000

Signs: Type III, High-Intensity (Typically Encapsulated Glass-Bead Element)

1. Avery Dennison, T-5500A and T-6500 Series
2. Nippon Carbide Industries, Nikkalite Brand Ultralite Grade II
3. 3M 3870 and 3930 Series

Signs: Type IV, High-Intensity (Typically Unmetallized Microprismatic Element)

1. Avery Dennison, T-6500 Series
2. Nippon Carbide Industries, Crystal Grade, 94000 Series
3. Nippon Carbide Industries, Model No. 94847 Fluorescent Orange
4. 3M Series 3930 and Series 3924S

Signs: Type VI, Elastomeric (Roll-Up) High-Intensity, without Adhesive

1. Avery Dennison, WU-6014
2. Novabrite LLC, "Econobrite"
3. Reflexite "Vinyl"
4. Reflexite "SuperBright"
5. Reflexite "Marathon"
6. 3M Series RS20

Signs: Type VII, Super-High-Intensity (Typically Unmetallized Microprismatic Element)

1. 3M Series 3924S, Fluorescent Orange
2. 3M LDP Series 3970

Signs: Type VIII, Super-High-Intensity (Typically Unmetallized Microprismatic Element)

1. Avery Dennison, T-7500 Series
2. Avery Dennison, T-7511 Fluorescent Yellow
3. Avery Dennison, T-7513 Fluorescent Yellow Green
4. Avery Dennison, W-7514 Fluorescent Orange
5. Nippon Carbide Industries, Nikkalite Crystal Grade Series 92800
6. Nippon Carbide Industries, Nikkalite Crystal Grade Model 92847 Fluorescent Orange

Signs: Type IX, Very-High-Intensity (Typically Unmetallized Microprismatic Element)

1. 3M VIP Series 3981 Diamond Grade Fluorescent Yellow
2. 3M VIP Series 3983 Diamond Grade Fluorescent Yellow/Green
3. 3M VIP Series 3990 Diamond Grade
4. Avery Dennison T-9500 Series
5. Avery Dennison, T9513, Fluorescent Yellow Green
6. Avery Dennison, W9514, Fluorescent Orange
7. Avery Dennison, T-9511 Fluorescent Yellow

SPECIALTY SIGNS

1. Reflexite "Endurance" Work Zone Sign (with Semi-Rigid Plastic Substrate)

ALTERNATIVE SIGN SUBSTRATES

Fiberglass Reinforced Plastic (FRP) and Expanded Foam PVC

1. Fiber-Brite (FRP)
2. Sequentia, "Polyplate" (FRP)
3. Inteplast Group "InteCel" (0.5 inch for Post-Mounted CZ Signs, 48-inch or less)(PVC)

Aluminum Composite, Temporary Construction Signs and Permanent Signs up to 4 foot, 7 Inches

1. Alcan Composites "Dibond Material, 80 mils"
2. Mitsubishi Chemical America, Alpolic 350

SECTION 8-2. CONCRETE

8-2.01 PORTLAND CEMENT CONCRETE

Portland cement concrete shall conform to the provisions in Section 90, "Portland Cement Concrete," of the Standard Specifications and these special provisions.

The Department maintains a list of sources of fine and coarse aggregate that have been approved for use with a reduced amount of supplementary cementitious material in the total amount of cementitious material to be used. A source of aggregate will be considered for addition to the approved list if the producer of the aggregate submits to the Transportation Laboratory certified test results from a qualified testing laboratory that verify the aggregate complies with the requirements. Before the testing starts, the aggregate test shall be registered with the Department. A registration number can be obtained by calling (916) 227-7228. The registration number shall be used as the identification for the aggregate sample in correspondence with the Department. Upon request, a split of the tested sample shall be provided to the Department. Approval of aggregate will depend upon compliance with the specifications, based on the certified test results submitted, together with any replicate testing the Department may elect to perform. Approval will expire 3 years from the date the most recent registered and evaluated sample was collected from the aggregate source.

Qualified testing laboratories shall conform to the following requirements:

1. Laboratories performing ASTM Designation: C 1293 shall participate in the Cement and Concrete Reference Laboratory (CCRL) Concrete Proficiency Sample Program and shall have received a score of 3 or better on each test of the previous 2 sets of concrete samples.
2. Laboratories performing ASTM Designation: C 1260 shall participate in the Cement and Concrete Reference Laboratory (CCRL) Pozzolan Proficiency Sample Program and shall have received a score of 3 or better on the shrinkage and soundness tests of the previous 2 sets of pozzolan samples.

Aggregates on the list shall conform to one of the following requirements:

1. When the aggregate is tested in conformance with the requirements in California Test 554 and ASTM Designation: C 1293, the average expansion at one year shall be less than or equal to 0.040 percent; or
2. When the aggregate is tested in conformance with the requirements in California Test 554 and ASTM Designation: C 1260, the average of the expansion at 16 days shall be less than or equal to 0.15 percent.

If the aggregates used in the concrete are on the Department's list, the minimum amount of supplementary cementitious material shall conform to the following:

1. If fly ash or natural pozzolan conforming to the provisions in Section 90-2.01C, "Required Use of Supplementary Cementitious Materials," of the Standard Specifications is used, the minimum amount of supplementary cementitious material shall be 15 percent by weight of the total cementitious material; or
2. If silica fume conforming to the provisions in Section 90-2.01C, "Required Use of Supplementary Cementitious Materials," of the Standard Specifications is used, the minimum amount of supplementary cementitious material shall be 7 percent by weight of the total cementitious material.

The limitation on tricalcium silicate (C₃S) content in Type II cement specified in Section 90-2.01A, "Cement," of the Standard Specifications shall not apply.

SECTION 8-3. (BLANK)

SECTION 9. (BLANK)

SECTION 10. CONSTRUCTION DETAILS

SECTION 10-1. GENERAL

10-1.01 ORDER OF WORK

Order of work shall conform to the provisions in Section 5-1.05, "Order of Work," of the Standard Specifications and these special provisions.

10-1.02 WATER POLLUTION CONTROL

GENERAL

Water pollution control work shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications, section of these special provisions entitled "Relations With California Regional Water Quality Control Board," and these special provisions.

The Contractor shall perform water pollution control work in conformance with the requirements in the "Storm Water Pollution Prevention Plan (SWPPP) and Water Pollution Control Program (WPCP) Preparation Manual" and its addenda in effect on the day the Notice to Contractors is dated. This manual is referred to as the "Preparation Manual." Copies of the Preparation Manual may be obtained from:

State of California
Department of Transportation
Publication Distribution Unit
1900 Royal Oaks Drive
Sacramento, California 95815
Telephone: (916) 445-3520

The Preparation Manual and other references for performing water pollution control work are available from the Department's Construction Storm Water and Water Pollution Control web site at:

<http://www.dot.ca.gov/hq/construc/stormwater/stormwater1.htm>

Before the start of job site activities, the Contractor shall provide training for project managers, supervisory personnel, and employees involved with water pollution control work. The training shall include:

- A. Rules and regulations
- B. Implementation and maintenance for:
 - 1. Temporary Soil Stabilization
 - 2. Temporary Sediment Control
 - 3. Tracking Control
 - 4. Wind Erosion Control

The Contractor shall designate in writing a Water Pollution Control Manager (WPCM). The Contractor shall submit a statement of qualifications describing the training, work history, and expertise of the proposed WPCM. The qualifications shall include either:

- A. A minimum of 24 hours of Department approved storm water management training described at Department's Construction Storm Water and Water Pollution Control web site.
- B. Certification as a Certified Professional in Erosion and Sediment Control (CPESC).

The WPCM shall be:

- A. Responsible for water pollution control work.
- B. The primary contact for water pollution control work.
- C. Have authority to mobilize crews to make immediate repairs to water pollution control practices.

The Contractor may designate one manager to prepare the WPCP and a different manager to implement the plan. The WPCP preparer shall meet the training requirements for the WPCM.

WATER POLLUTION CONTROL PROGRAM

The Contractor shall submit a Water Pollution Control Program (WPCP) to the Engineer for approval. The WPCP shall conform to the requirements in the Preparation Manual and these special provisions.

The WPCP shall include water pollution control practices:

- A. For storm water and non-storm water from areas outside of the job site related to construction activities for this contract such as:
 - 1. Staging areas.
 - 2. Storage yards.
 - 3. Access roads.
- B. Appropriate for each season as described in "Implementation Requirements" of these special provisions.

The WPCP shall include a schedule that:

- A. Describes when work activities that could cause water pollution will be performed.
- B. Identifies soil stabilization and sediment control practices for disturbed soil area.
- C. Includes dates when these practices will be 25, 50, and 100 percent complete.
- D. Shows 100 percent completion of these practices before the rainy season.

The WPCP shall include the following temporary water pollution control practices and their associated contract items of work as shown on the plans or specified in these special provisions:

- A. Temporary Sediment Control
 - 1. Temporary Cover
- B. Wind Erosion Control
 - 1. Construction Site Management

C. Non-Storm Water Management

1. Construction Site Management

D. Waste Management and Materials Pollution Control

1. Temporary Concrete Washout (Portable)
2. Construction Site Management

Within 7 days after contract approval, the Contractor shall submit 2 copies of the WPCP to the Engineer. The Contractor shall allow 15 days for the Engineer's review. If revisions are required, the Engineer will provide comments and specify the date that the review stopped. The Contractor shall revise and resubmit the WPCP within 7 days of receipt of the Engineer's comments. The Engineer's review will resume when the complete WPCP is resubmitted. When the Engineer approves the WPCP, the Contractor shall submit 3 copies of the approved WPCP to the Engineer. The Contractor may proceed with construction activities if the Engineer conditionally approves the WPCP while minor revisions are being completed. If the Engineer fails to complete the review within the time allowed and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay, the Contractor will be compensated for resulting losses, and an extension of time will be granted, as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The Contractor shall not perform work that may cause water pollution until the WPCP has been approved by the Engineer. The Engineer's review and approval shall not waive any contract requirements and shall not relieve the Contractor from complying with Federal, State and local laws, regulations, and requirements.

If there is a change in construction schedule or activities, the Contractor shall prepare an amendment to the WPCP to identify additional or revised water pollution control practices. The Contractor shall submit the amendment to the Engineer for review within a time agreed to by the Engineer not to exceed the number of days specified for the initial submittal of the WPCP. The Engineer will review the amendment within the same time allotted for the review of the initial submittal of the WPCP.

If directed by the Engineer or requested in writing by the Contractor and approved by the Engineer, changes to the water pollution control work specified in these special provisions will be allowed. Changes may include addition of new water pollution control practices. The Contractor shall incorporate these changes in the WPCP. Additional water pollution control work will be paid for as extra work in accordance with Section 4-1.03D, "Extra Work," of the Standard Specifications.

The Contractor shall keep a copy of the approved WPCP at the job site. The WPCP shall be made available when requested by a representative of the Regional Water Quality Control Board, State Water Resources Control Board, United States Environmental Protection Agency, or the local storm water management agency. Requests from the public shall be directed to the Engineer.

IMPLEMENTATION REQUIREMENTS

The Contractor's responsibility for WPCP implementation shall continue throughout any temporary suspension of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications.

If the Contractor or the Engineer identifies a deficiency in the implementation of the approved WPCP, the deficiency shall be corrected immediately, unless an agreed date for correction is approved in writing by the Engineer. The deficiency shall be corrected before the onset of precipitation. If the Contractor fails to correct the deficiency by the agreed date or before the onset of precipitation, the Department may correct the deficiency and deduct the cost of correcting deficiencies from payments.

Year-Round

The Contractor shall monitor the National Weather Service weather forecast on a daily basis during the contract. The Contractor may use an alternative weather forecasting service if approved by the Engineer. Appropriate water pollution control practices shall be in place before precipitation.

The Contractor may discontinue earthwork operations for a disturbed area for up to 21 days and the disturbed soil area will still be considered active. When earthwork operations in the disturbed area have been completed, the Contractor shall implement appropriate water pollution control practices within 15 days or before predicted precipitation, whichever occurs first.

Rainy Season

Soil stabilization and sediment control practices conforming to these special provisions shall be in place during the rainy season between October 1 and May 1.

The Contractor shall implement soil stabilization and sediment control practices a minimum of 10 days before the start of the rainy season.

INSPECTION AND MAINTENANCE

The WPCM shall inspect the water pollution control practices identified in the WPCP as follows:

- A. Before a forecasted storm,
- B. After precipitation that causes site runoff,
- C. At 24-hour intervals during extended precipitation,
- D. On a predetermined schedule, a minimum of once every 2 weeks outside of the defined rainy season, and
- E. On a predetermined schedule, a minimum of once a week during the defined rainy season.

The WPCM shall oversee the maintenance of the water pollution control practices.

The WPCM shall use the Storm Water Quality Construction Site Inspection Checklist provided in the Preparation Manual or an alternative inspection checklist provided by the Engineer. A copy of the completed site inspection checklist shall be submitted to the Engineer within 24 hours of finishing the inspection.

REPORTING REQUIREMENTS

If the Contractor identifies discharges into surface waters or drainage systems causing or potentially causing pollution or if the project receives a written notice or order from a regulatory agency, the Contractor shall immediately inform the Engineer. The Contractor shall submit a written report to the Engineer within 7 days of the discharge, notice, or order. The report shall include the following information:

- A. The date, time, location, and nature of the operation, type of discharge and quantity, and the cause of the notice or order.
- B. The water pollution control practices used before the discharge, or before receiving the notice or order.
- C. The date of placement and type of additional or altered water pollution control practices placed after the discharge or after receiving the notice or order.
- D. A maintenance schedule for affected water pollution control practices.

PAYMENT

During each estimate period the Contractor fails to conform to the provisions in this section, "Water Pollution Control," or fails to implement the water pollution control practices shown on the plans or specified elsewhere in these special provisions as items of work, the Department will withhold 25 percent of the progress payment.

Withholds for failure to perform water pollution control work will be in addition to all other withholds provided for in the contract. The Department will return performance-failure withholds in the progress payment following the correction for noncompliance.

The contract lump sum price paid for prepare water pollution control program shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in preparing, obtaining approval of, and amending the WPCP and inspecting water pollution control practices as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Payments for prepare water pollution control program will be made as follows:

- A. After the WPCP has been approved by the Engineer, up to 75 percent of the contract item price for prepare water pollution control program will be included in the monthly progress estimate.
- B. After acceptance of the contract in conformance with the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, payment for the remaining percentage of the contract item price for prepare water pollution control program will be made in conformance with the provisions in Section 9-1.07A, "Payment Prior to Proposed Final Estimate."

Implementation of water pollution control practices in areas outside the highway right of way not specifically provided for in the WPCP or in these special provisions will not be paid for.

Water pollution control practices for which there are separate contract items of work will be measured and paid for as those contract items of work.

10-1.03 CONSTRUCTION SITE MANAGEMENT

Construction site management shall consist of controlling potential sources of water pollution before they come in contact with storm water systems or watercourses. The Contractor shall control material pollution and manage waste and non-storm water existing at the construction site by implementing effective handling, storage, use, and disposal practices.

Attention is directed to "Water Pollution Control" of these special provisions regarding the Contractor's appointment of a water pollution control manager (WPCM) for the project.

The Contractor shall train all employees and subcontractors regarding:

- A. Material pollution prevention and control;
- B. Waste management;
- C. Non-storm water management;
- D. Identifying and handling hazardous substances; and
- E. Potential dangers to humans and the environment from spills and leaks or exposure to toxic or hazardous substances.

Training shall take place before starting work on this project. New employees shall receive the complete training before starting work on this project. The Contractor shall have regular meetings to discuss and reinforce spill prevention and control; material delivery, storage, use, and disposal; waste management; and non-storm water management procedures.

Instructions for material and waste handling, storage, and spill reporting and cleanup shall be posted at all times in an open, conspicuous, and accessible location at the construction site.

Nonhazardous construction site waste and excess material shall be recycled when practical or disposed of in accordance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications, unless otherwise specified.

Vehicles and equipment at the construction site shall be inspected by the WPCM on a frequent, predetermined schedule, and by the operator each day of use. Leaks shall be repaired immediately, or the vehicle or equipment shall be removed from the construction site.

SPILL PREVENTION AND CONTROL

The Contractor shall implement spill and leak prevention procedures when chemicals or hazardous substances are stored. Spills of petroleum products; substances listed under CFR Title 40, Parts 110, 117, and 302; and sanitary and septic waste shall be contained and cleaned up as soon as is safe.

Minor spills involve small quantities of oil, gasoline, paint, or other material that can be controlled by the first responder upon discovery of the spill. Cleanup of minor spills includes:

- A. Containing the spread of the spill,
- B. Recovering the spilled material using absorption,
- C. Cleaning the contaminated area, and
- D. Disposing of contaminated material promptly and properly.

Semi-significant spills are those that can be controlled by the first responder with the help of other personnel. Cleanup of semi-significant spills shall be immediate. Cleanup of semi-significant spills includes:

- A. Containing the spread of the spill;
- B. Recovering the spilled material using absorption if the spill occurs on paved or an impermeable surface;
- C. Containing the spill with an earthen dike and digging up contaminated soil for disposal if the spill occurs on dirt;
- D. Covering the spill with plastic or other material to prevent contaminating runoff if the spill occurs during precipitation; and
- E. Disposing of contaminated material promptly and properly.

Significant or hazardous spills are those that cannot be controlled by construction personnel. Notifications of these spills shall be immediate. The following steps shall be taken:

- A. Construction personnel shall not attempt to cleanup the spill until qualified staff have arrived;
- B. Notify the Engineer and follow up with a written report;
- C. Obtain the services of a spills contractor or hazardous material team immediately;
- D. Notify the local emergency response team by dialing 911 and county officials at the emergency phone numbers kept on the construction site;
- E. Notify the Governor's Office of Emergency Services Warning Center at (805) 852-7550;

- F. Notify the National Response Center at (800) 424-8802 regarding spills of Federal reportable quantities in conformance with CFR Title 40, Parts 110, 119, and 302;
- G. Notify other agencies as appropriate, including:
 - 1. Fire Department,
 - 2. Public Works Department,
 - 3. Coast Guard,
 - 4. Highway Patrol,
 - 5. City Police or County Sheriff Department,
 - 6. Department of Toxic Substances,
 - 7. California Division of Oil and Gas,
 - 8. Cal OSHA, or
 - 9. Regional Water Resources Control Board.

The WPCM shall oversee and enforce proper spill prevention and control measures. Minor, semi-significant, and significant spills shall be reported to the Contractor's WPCM who shall notify the Engineer immediately.

The Contractor shall prevent spills from entering storm water runoff before and during cleanup. Spills shall not be buried or washed with water.

The Contractor shall keep material or waste storage areas clean, well organized, and equipped with enough cleanup supplies for the material being stored. Plastic shall be placed under paving equipment when not in use to catch drips.

MATERIAL MANAGEMENT

Material shall be delivered, used, and stored for this contract in a manner that minimizes or eliminates discharge of material into the air, storm drain systems, or watercourses.

The Contractor shall implement the practices described in this section when taking delivery of, using, or storing the following materials:

A. Hazardous chemicals including:

- 1. Acids,
- 2. Lime,
- 3. Glues,
- 4. Adhesives,
- 5. Paints,
- 6. Solvents, and
- 7. Curing compounds;

B. Soil stabilizers and binders;

C. Fertilizers;

D. Detergents;

E. Plaster;

F. Petroleum products including:

- 1. Fuel,
- 2. Oil, and
- 3. Grease;

G. Asphalt components and concrete components; and

H. Pesticides and herbicides.

The Contractor shall supply the Material Safety Data Sheet to the Engineer for material used or stored. The Contractor shall keep an accurate inventory of material delivered and stored at the construction site.

Employees trained in emergency spill cleanup procedures shall be present when hazardous materials or chemicals are unloaded.

The Contractor shall use recycled or less hazardous products when practical.

Material Storage

The Contractor shall store liquids, petroleum products, and substances listed in CFR Title 40, Parts 110, 117, and 302 in containers or drums approved by the United States Environmental Protection Agency, and place them in secondary containment facilities.

Secondary containment facilities shall be impervious to the materials stored there for a minimum contact time of 72 hours.

Throughout the rainy season secondary containment facilities shall be covered during non-working days and when precipitation is predicted. Secondary containment facilities shall be adequately ventilated.

The Contractor shall keep the secondary containment facility free of accumulated rainwater or spills. After precipitation, or in the event of spills or leaks, accumulated liquid shall be collected and placed into drums within 24 hours. These liquids shall be handled as hazardous waste in accordance with the provisions in "Hazardous Waste" of these special provisions, unless testing determines them to be nonhazardous.

Incompatible materials, such as chlorine and ammonia, shall not be stored in the same secondary containment facility.

Materials shall be stored in the original containers with the original product labels maintained in legible condition. Damaged or illegible labels shall be replaced immediately.

The secondary containment facility shall have the capacity to contain precipitation from a 24-hour-long, 25-year storm; and 10 percent of the aggregate volume of all containers, or all of the volume of the largest container within the facility, whichever is greater.

The Contractor shall store bagged or boxed material on pallets. Throughout the rainy season, bagged or boxed material shall be protected from wind and rain during non-working days and when precipitation is predicted.

The Contractor shall provide sufficient separation between stored containers to allow for spill cleanup or emergency response access. Storage areas shall be kept clean, well organized, and equipped with cleanup supplies appropriate for the materials being stored.

The Contractor shall repair or replace perimeter controls, containment structures, covers, and liners as needed. Storage areas shall be inspected before and after precipitation, and at least weekly during other times.

Stockpile Management

The Contractor shall reduce or eliminate potential air and water pollution from stockpiled material including soil, paving material, or pressure treated wood. Stockpiles shall be located out of floodplains when possible, and at least 50 feet from concentrated flows of storm water, drainage courses, or inlets unless written approval is obtained from the Engineer.

The Contractor may discontinue adding or removing material for up to 21 days and a stockpile will still be considered active.

The Contractor shall protect active stockpiles with plastic or geotextile cover, soil stabilization measures, or with linear sediment barrier when precipitation is predicted. Active stockpiles of cold mix asphalt concrete shall be placed on an impervious surface and covered with plastic when precipitation is predicted.

The Contractor shall protect inactive soil stockpiles with a plastic or geotextile cover, or with soil stabilization measures at all times during the rainy season. A linear sediment barrier around the perimeter of the stockpile shall also be used. During the non-rainy season soil stockpiles shall be covered and protected with a linear sediment barrier when precipitation is predicted. The Contractor shall control wind erosion during dry weather as provided in Section 10, "Dust Control," of the Standard Specifications.

Stockpiles of portland cement concrete rubble, asphalt concrete (AC), hot mix asphalt (HMA), AC and HMA rubble, aggregate base, or aggregate subbase shall be covered with plastic or geotextile, or protected with a linear sediment barrier at all times during the rainy season, and when precipitation is predicted during the non-rainy season.

Stockpiles of cold mix asphalt concrete shall be placed on and covered with impermeable material at all times during the rainy season, and when precipitation is predicted during the non-rainy season.

Stockpiles of pressure treated wood shall be covered with impermeable material and placed on pallets at all times during the rainy season, and when precipitation is predicted during the non-rainy season.

The Contractor shall repair or replace linear sediment barriers and covers as needed or as directed by the Engineer to keep them functioning properly. Sediment shall be removed when it accumulates to 1/3 of the linear sediment barrier height.

WASTE MANAGEMENT

Solid Waste

The Contractor shall not allow litter or debris to accumulate anywhere on the construction site, including storm drain grates, trash racks, and ditch lines. The Contractor shall pick up and remove trash and debris from the construction site at least once a week. The WPCM shall monitor solid waste storage and disposal procedures on the construction site. The Contractor shall provide enough dumpsters of sufficient size to contain the solid waste generated by the project. Dumpsters shall be emptied when refuse reaches the fill line. Dumpsters shall be watertight. The Contractor shall not wash out dumpsters on the construction site. The Contractor shall provide additional containers and more frequent pickup during the demolition phase of construction.

Solid waste includes:

- A. Brick,
- B. Mortar,
- C. Timber,
- D. Metal scraps,
- E. Sawdust,
- F. Pipe,
- G. Electrical cuttings,
- H. Non-hazardous equipment parts,
- I. Styrofoam and other packaging materials,
- J. Vegetative material and plant containers from highway planting, and
- K. Litter and smoking material, including litter generated randomly by the public.

Trash receptacles shall be provided and used in the Contractor's yard, field trailers, and locations where workers gather for lunch and breaks.

Hazardous Waste

The Contractor shall implement hazardous waste management practices when waste is generated on the construction site from the following substances:

- A. Petroleum products,
- B. Asphalt products,
- C. Concrete curing compound,
- D. Pesticides,
- E. Acids,
- F. Paints,
- G. Stains,
- H. Solvents,
- I. Wood preservatives,
- J. Roofing tar, and
- K. Materials classified as hazardous by California Code of Regulations, Title 22, Division 4.5; or listed in CFR Title 40, Parts 110, 117, 261, or 302.

Nothing in these special provisions shall relieve the Contractor of the responsibility for compliance with Federal, State, and local laws regarding storage, handling, transportation, and disposal of hazardous wastes.

The WPCM shall oversee and enforce hazardous waste management practices. Production of hazardous materials and hazardous waste on the construction site shall be kept to a minimum. Perimeter controls, containment structures, covers, and liners shall be repaired or replaced when damaged.

The Contractor shall have a laboratory certified by the Department of Health Services (DHS) sample and test waste when hazardous material levels are unknown to determine safe methods for storage and disposal.

The Contractor shall segregate potentially hazardous waste from nonhazardous waste at the construction site. Hazardous waste shall be handled, stored, and disposed of as required in California Code of Regulations, Title 22, Division 4.5, Section 66262.34; and in CFR Title 49, Parts 261, 262, and 263.

The Contractor shall store hazardous waste in sealed containers constructed and labeled with the contents and date accumulated as required in California Code of Regulations, Title 22, Division 4.5; and in CFR Title 49, Parts 172, 173, 178, and 179. Hazardous waste containers shall be kept in temporary containment facilities conforming to the provisions in "Material Storage" of these special provisions.

There shall be adequate storage volume and containers shall be conveniently located for hazardous waste collection. Containers of hazardous waste shall not be overfilled and hazardous wastes shall not be mixed. Containers of dry waste that are not watertight shall be stored on pallets. The Contractor shall not allow potentially hazardous waste to accumulate on the ground. Hazardous waste shall be stored away from storm drains, watercourses, moving vehicles, and equipment.

The Contractor shall clean water based or oil based paint from brushes or equipment within a contained area and shall not contaminate soil, watercourses, or storm drain systems. Paints, thinners, solvents, residues, and sludges that cannot be recycled or reused shall be disposed of as hazardous waste. When thoroughly dry, latex paint and paint cans, used brushes, rags, absorbent materials, and drop cloths shall be disposed of as solid waste.

The Contractor shall dispose of hazardous waste within 90 days of being generated. Hazardous waste shall be disposed of by a licensed hazardous waste transporter using uniform hazardous waste manifest forms and taken to a Class I Disposal Site. A copy of the manifest shall be provided to the Engineer.

Contaminated Soil

The Contractor shall identify contaminated soil from spills or leaks by noticing discoloration, odors, or differences in soil properties. Soil with evidence of contamination shall be sampled and tested by a laboratory certified by DHS. If levels of contamination are found to be hazardous, the soil shall be handled and disposed of as hazardous waste.

The Contractor shall prevent the flow of water, including ground water, from mixing with contaminated soil by using one or a combination of the following measures:

- A. Berms,
- B. Cofferdams,
- C. Grout curtains,
- D. Freeze walls, or
- E. Concrete seal course.

If water mixes with contaminated soil and becomes contaminated, the water shall be sampled and tested by a laboratory certified by the DHS. If levels of contamination are found to be hazardous, the water shall be handled and disposed of as hazardous waste.

Concrete Waste

The Contractor shall implement practices to prevent the discharge of portland cement concrete, AC, or HMA waste into storm drain systems or watercourses.

Portland cement concrete, AC, or HMA waste shall be collected at the following locations and disposed of:

- A. Where concrete material, including grout, is used;
- B. Where concrete dust and debris result from demolition;
- C. Where sawcutting, coring, grinding, grooving, or hydro-concrete demolition of portland cement concrete, AC, or HMA creates a residue or slurry; or
- D. Where concrete trucks or other concrete-coated equipment is cleaned at the construction site.

Sanitary and Septic Waste

Wastewater from sanitary or septic systems shall not be discharged or buried within the Department right of way. The WPCM shall inspect sanitary or septic waste storage and monitor disposal procedures at least weekly. Sanitary facilities that discharge to the sanitary sewer system shall be properly connected and free from leaks.

The Contractor shall obtain written approval from the local health agency, city, county, and sewer district before discharging from a sanitary or septic system directly into a sanitary sewer system, and provide a copy to the Engineer. The Contractor shall comply with local health agency requirements when using an on-site disposal system.

Liquid Waste

The Contractor shall not allow construction site liquid waste, including the following, to enter storm drain systems or watercourses:

- A. Drilling slurries or fluids,
- B. Grease-free or oil-free wastewater or rinse water,
- C. Dredgings,
- D. Liquid waste running off a surface including wash or rinse water, or
- E. Other non-storm water liquids not covered by separate permits.

The Contractor shall hold liquid waste in structurally sound, leak proof containers such as:

- A. Sediment traps,
- B. Roll-off bins, or
- C. Portable tanks.

Liquid waste containers shall be of sufficient quantity and volume to prevent spills and leaks. The containers shall be stored at least 50 feet from storm drains, watercourses, moving vehicles, and equipment.

The Contractor shall remove and dispose of deposited solids from sediment traps as provided in "Solid Waste" of these special provisions, unless determined infeasible by the Engineer.

Liquid waste may require testing to determine hazardous material content before disposal.

Drilling fluids and residue shall be disposed of outside the highway right of way. If the Engineer determines that an appropriate location is available, fluids and residue exempt under California Code of Regulations, Title 23, Section 2511(g) may be dried by infiltration and evaporation in a leak proof container. The remaining solid waste may be disposed of as provided in "Solid Waste" of these special provisions.

NON-STORM WATER MANAGEMENT

Water Control and Conservation

The Contractor shall prevent erosion or the discharge of pollutants into storm drain systems or watercourses by managing the water used for construction operations. The Contractor shall obtain the Engineer's approval before washing anything on the construction site with water that could discharge into a storm drain system or watercourse. Discharges shall be reported to the Engineer immediately.

The Contractor shall implement water conservation practices when water is used on the construction site. Irrigation areas shall be inspected and watering schedules shall be adjusted to prevent erosion, excess watering, or runoff. The Contractor shall shut off the water source to broken lines, sprinklers, or valves, and they shall be repaired as soon as possible. When possible, water from waterline flushing shall be reused for landscape irrigation. Paved areas shall be swept and vacuumed, not washed with water.

Construction water runoff, including water from water line repair, shall be directed to areas to infiltrate into the ground and shall not be allowed to enter storm drain systems or watercourses. Spilled water shall not be allowed to escape water truck filling areas. When possible, the Contractor shall direct water from off-site sources around the construction site, or shall minimize contact with the construction site.

Illegal Connection and Discharge Detection and Reporting

The Contractor shall inspect the construction site and the site perimeter before beginning work for evidence of illegal connections, discharges, or dumping. Subsequently, the construction site and perimeter shall be inspected on a frequent, predetermined schedule.

The Contractor shall immediately notify the Engineer when illegal connections, discharges, or dumping are discovered. The Contractor shall take no further action unless directed by the Engineer. Unlabeled or unidentifiable material shall be assumed to be hazardous.

The Contractor shall look for the following evidence of illegal connections, discharges, or dumping:

- A. Debris or trash piles,
- B. Staining or discoloration on pavement or soils,
- C. Pungent odors coming from drainage systems,
- D. Discoloration or oily sheen on water,
- E. Stains or residue in ditches, channels or drain boxes,
- F. Abnormal water flow during dry weather,
- G. Excessive sediment deposits,
- H. Nonstandard drainage junction structures, or
- I. Broken concrete or other disturbances near junction structures.

Vehicle and Equipment Cleaning

The Contractor shall limit vehicle and equipment cleaning or washing on the construction site to that necessary to control vehicle tracking or hazardous waste. Vehicles and equipment shall not be cleaned on the construction site with soap, solvents, or steam until the Engineer has been notified. The resulting waste shall be contained and recycled, or disposed of as provided in "Liquid Waste" or "Hazardous Waste" of these special provisions, whichever is applicable. The Contractor shall not use diesel to clean vehicles or equipment, and shall minimize the use of solvents.

The Contractor shall clean or wash vehicles and equipment in a structure equipped with disposal facilities. If using a structure is not possible, vehicles and equipment shall be cleaned or washed in an outside area with the following characteristics:

- A. Located at least 50 feet from storm drainage systems or watercourses,
- B. Paved with AC, HMA, or portland cement concrete,
- C. Surrounded by a containment berm, and
- D. Equipped with a sump to collect and dispose of wash water.

When washing vehicles or equipment with water, the Contractor shall use as little water as possible. Hoses shall be equipped with a positive shutoff valve.

Wash racks shall discharge to a recycle system or to another system approved by the Engineer. Sumps shall be inspected regularly, and liquids and sediments shall be removed as needed.

Vehicle and Equipment Fueling and Maintenance

The Contractor shall fuel or perform maintenance on vehicles and equipment off the construction site whenever practical. When fueling or maintenance must be done at the construction site, the Contractor shall designate a site, or sites, and obtain approval from the Engineer before using. The fueling or maintenance site shall be protected from storm water, shall be on level ground, and shall be located at least 50 feet from drainage inlets or watercourses. The WPCM shall inspect the fueling or maintenance site regularly. Mobile fueling or maintenance shall be kept to a minimum.

The Contractor shall use containment berms or dikes around the fueling and maintenance area. Adequate amounts of absorbent spill cleanup material and spill kits shall be kept in the fueling and maintenance area and on fueling trucks. Spill cleanup material and kits shall be disposed of immediately after use. Drip pans or absorbent pads shall be used during fueling or maintenance unless performed over an impermeable surface.

Fueling or maintenance operations shall not be left unattended. Fueling nozzles shall be equipped with an automatic shutoff control. Vapor recovery fueling nozzles shall be used where required by the Air Quality Management District. Nozzles shall be secured upright when not in use. Fuel tanks shall not be topped-off.

The Contractor shall recycle or properly dispose of used batteries and tires.

Material and Equipment Used Over Water

Drip pans and absorbent pads shall be placed under vehicles or equipment used over water, and an adequate supply of spill cleanup material shall be kept with the vehicle or equipment. Drip pans or plastic sheeting shall be placed under vehicles or equipment on docks, barges, or other surfaces over water when the vehicle or equipment will be idle for more than one hour.

The Contractor shall provide watertight curbs or toe boards on barges, platforms, docks, or other surfaces over water to contain material, debris, and tools. Material shall be secured to prevent spills or discharge into water due to wind.

Structure Removal Over or Adjacent to Water

The Contractor shall not allow demolished material to enter storm water systems or watercourses. The Contractor shall use covers and platforms approved by the Engineer to collect debris. Attachments shall be used on equipment to catch debris on small demolition operations. Debris catching devices shall be emptied regularly and debris shall be handled as provided in "Waste Management" of these special provisions.

The WPCM shall inspect demolition sites within 50 feet of storm water systems or watercourses every day.

Paving, Sealing, Sawcutting, and Grinding Operations

The Contractor shall prevent the following material from entering storm drain systems or water courses:

- A. Cementitious material,
- B. Asphaltic material,
- C. Aggregate or screenings,
- D. Grinding or sawcutting residue,
- E. Pavement chunks, or
- F. Shoulder backing.

The Contractor shall cover drainage inlets and use linear sediment barriers to protect downhill watercourses until paving, sealing, sawcutting, or grinding operations are completed and excess material has been removed. Drainage inlets and manholes shall be covered during the application of seal coat, tack coat, slurry seal, or fog seal.

During the rainy season or when precipitation is predicted, paving, sawcutting, and grinding operations shall be limited to places where runoff can be captured. Seal coat, tack coat, slurry seal, or fog seal operations shall not begin if precipitation is predicted for the application or the curing period. The Contractor shall not excavate material from existing roadways during precipitation.

The Contractor shall vacuum up slurry from sawcutting operations immediately after the slurry is produced. Slurry shall not be allowed to run onto lanes open to public traffic or off the pavement.

The Contractor shall collect residue from portland cement concrete grinding operations with a vacuum attachment on the grinding machine. The residue shall not be left on the pavement or allowed to flow across the pavement.

Material excavated from existing roadways may be stockpiled as provided in "Stockpile Management" of these special provisions if approved by the Engineer. AC or HMA chunks used in embankment shall be placed above the water table and covered by at least one foot of material.

Substances used to coat asphalt trucks and equipment shall not contain soap, foaming agents, or toxic chemicals.

Thermoplastic Striping and Pavement Markers

Thermoplastic striping and preheating equipment shutoff valves shall work properly at all times when on the construction site. The Contractor shall not preheat, transfer, or load thermoplastic within 50 feet of drainage inlets or watercourses. The Contractor shall not fill the preheating container to more than 6 inches from the top. Truck beds shall be cleaned daily of scraps or melted thermoplastic.

The Contractor shall not unload, transfer, or load bituminous material for pavement markers within 50 feet of drainage inlets or watercourses. All pressure shall be released from melting tanks before removing the lid to fill or service. Melting tanks shall not be filled to more than 6 inches from the top.

The Contractor shall collect bituminous material from the roadway after marker removal.

Pile Driving

The Contractor shall keep spill kits and cleanup material at pile driving locations. Pile driving equipment shall be parked over drip pans, absorbent pads, or plastic sheeting where possible. When not in use, pile driving equipment shall be stored at least 50 feet from concentrated flows of storm water, drainage courses, or inlets. The Contractor shall protect pile driving equipment by parking it on plywood and covering it with plastic when precipitation is predicted. The WPCM shall inspect the pile driving area every day for leaks and spills.

The Contractor shall use vegetable oil instead of hydraulic fluid when practical.

Concrete Curing

The Contractor shall not overspray chemical curing compound. Drift shall be minimized by spraying as close to the concrete as possible. Drainage inlets shall be covered before applying curing compound.

The Contractor shall minimize the use and discharge of water by using wet blankets or similar methods to maintain moisture when curing concrete.

Concrete Finishing

The Contractor shall collect and dispose of water and solid waste from high-pressure water blasting. Drainage inlets within 50 feet shall be covered before sandblasting. The nozzle shall be kept as close to the surface of the concrete as possible to minimize drift of dust and blast material. Blast residue may contain hazardous material.

Containment structures for concrete finishing operations shall be inspected for damage before each day of use and before predicted precipitation. Liquid and solid waste shall be removed from the containment structure after each work shift.

DEWATERING

Dewatering shall consist of discharging accumulated storm water, ground water, or surface water from excavations or temporary containment facilities. The Contractor shall discharge water within the limits of the project.

Dewatering discharge shall not cause erosion, scour, or sedimentary deposits that impact natural bedding materials.

The Contractor shall conduct dewatering activities in accordance with the Field Guide for Construction Dewatering available at:

<http://www.dot.ca.gov/hq/construc/stormwater/manuals.htm>

Before dewatering the Contractor shall submit a Dewatering and Discharge Plan to the Engineer in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications and "Water Pollution Control," of these special provisions. At a minimum, the Dewatering and Discharge Plan shall include the following:

- A. A title sheet and table of contents;
- B. A description of the dewatering and discharge operations detailing the locations, quantity of water, equipment, and discharge point;
- C. The estimated schedule for dewatering and discharge (begin and end dates, intermittent or continuous);
- D. Discharge alternatives such as dust control or percolation; and
- E. Visual monitoring procedures with inspection log.

The Contractor shall not discharge storm water or non-storm water that has an odor, discoloration other than sediment, an oily sheen, or foam on the surface and shall notify the Engineer immediately upon discovery.

If water cannot be discharged within the project limits due to site constraints it shall be disposed of in the same manner specified for material in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

PAYMENT

The contract lump sum price paid for construction site management shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in spill prevention and control, material management, waste management, non-storm water management, and dewatering and identifying, sampling, testing, handling, and disposing of hazardous waste, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.04 TEMPORARY COVER

Temporary cover shall be furnished, installed, maintained, and later removed at the locations shown on the approved Water Pollution Control Program (WPCP) in conformance with "Water Pollution Control" of these special provisions, and in conformance with details shown on the plans and these special provisions.

Temporary cover shall be one of the water pollution control practices for soil stabilization. The WPCP shall include the use of temporary cover.

MATERIALS

Temporary Cover Fabric

Temporary cover fabric shall be either a geotextile (engineering fabric) or a geomembrane (plastic sheeting) conforming to the following requirements:

- 1. Geotextile shall be a woven, slit film fabric which is also known as woven tape. The fabric shall be nonbiodegradable, resistant to deterioration by sunlight, and inert to most soil chemicals. Edges of the film fabric shall be selvage or serge to prevent unraveling. The film fabric shall also conform to the following requirements:

Specification	Requirements
Grab tensile strength (one inch grip), pounds, min. ASTM Designation: D4632*	200
Elongation at break, percent, min. ASTM Designation: D4632*	15
Toughness, pounds, min. (percent elongation x grab tensile strength)	3000
Permittivity, l/sec, max. (gallons per minute per square foot) ASTM Designation: D 4491	0.07 (6)
Ultraviolet light stability, percent tensile strength retained after 500 hours, min. ASTM Designation: D 4355 (xenon arc lamp method)	70

* or appropriate test method for specific polymer

- 2. The geomembrane shall consist of 10 mils thick, single-ply material in conformance with the requirements in ASTM Designation: D 5199.

Temporary cover fabric shall be manufactured from polyethylene, polypropylene, or comparable polymers. The polymer materials may be virgin, recycled, or a combination of virgin and recycled materials. The polymer materials shall not contain biodegradable filler materials that can degrade the physical or chemical characteristics of the finished fabric. The Engineer may order tests to confirm the absence of biodegradable filler materials in conformance with the requirements in ASTM Designation: E 204 (Fourier Transformed Infrared Spectroscopy-FTIR).

Restrainers

Restrainers for securing the temporary cover fabric on slopes and stockpiles shall consist of one or a combination of the following:

1. Gravel-filled bags used as restrainers shall be knotted, roped, and placed at a maximum of 6 feet apart on the temporary cover fabric as shown on the plans. Gravel-filled bags shall be between 30 pounds and 50 pounds in weight, between 24 inches and 32 inches in length, and between 16 inches and 20 inches in width. Gravel bag fabric shall be nonwoven polypropylene geotextile with a minimum unit weight of 8.0 ounces per square yard. The fabric shall have a minimum grab tensile strength (one-inch grip) of 200 pounds in conformance with the requirements in ASTM Designation: D 4632, and an ultraviolet (UV) stability of 70 percent tensile strength retained after 500 hours in conformance with the requirements in ASTM Designation: D 4355, xenon arc lamp method. Gravel shall consist of noncohesive material between 3/8 inch and 3/4 inch in diameter, free of clay balls, organic matter, and other deleterious material. The openings of gravel-filled bags shall be secured to prevent escape of gravel.
2. Restrainers consisting of a steel anchor with a wooden lath shall be fabricated and placed as shown on the plans. Wooden lath shall conform to the provisions in Section 20-2.12, "Lumber," of the Standard Specifications and shall be fir or pine, 2" x 4" in size, and 8 feet in length. The wooden lath shall be secured to the temporary cover with steel anchors placed 4 feet apart along the lath.

The Contractor may use an alternative restrainer if approved by the Engineer in writing. The Contractor shall submit details for an alternative restrainer to the Engineer before installation. The alternative restrainer shall be installed and maintained in conformance with these special provisions.

INSTALLATION

Temporary cover shall be installed as follows:

1. Temporary cover fabric shall be placed and anchored as shown on the plans.
2. Abutting edges of the temporary cover fabric shall overlap a minimum of 24 inches. Nonabutting edges shall be embedded in the soil a minimum of 6 inches.
3. Restrainers shall be placed at the overlap area and along the toe of the slope. Restrainers outside the overlap areas shall be placed at a maximum spacing of 8 feet.
4. Steel anchors shall be installed to allow the leg of the steel anchor to pierce through the temporary cover fabric into the slope with the crown section securing the wooden lath firmly against the slope.
5. Earthen berm, a linear sediment barrier, shall be constructed adjacent to the toe of the slope with a minimum height of 8 inches and a minimum width of 36 inches. The earthen berm shall be hand or mechanically compacted. Alternative linear sediment barrier may be used if approved by the Engineer in writing.

If the Contractor removes the temporary cover in order to facilitate other work, the temporary cover shall be replaced and secured.

When no longer required as determined by the Engineer, temporary cover shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Ground disturbances, including holes and depressions, caused by the installation and removal of the temporary cover shall be backfilled and repaired in conformance with the provisions in Section 15-1.02, "Preservation of Property," of the Standard Specifications.

MAINTENANCE

The Contractor shall maintain the temporary cover throughout the contract to prevent displacement or migration of the material on the slope or stockpiled.

Temporary cover shall be maintained to minimize exposure of the protected area. Restrainers shall be relocated and secured as needed to restrain the temporary cover fabric in place. Temporary cover that breaks free shall be immediately secured. Holes, tears, and voids in the temporary cover fabric shall be patched, repaired, or replaced. When patches or repairs are unacceptable as determined by the Engineer, the temporary cover shall be replaced.

Temporary cover shall be repaired or replaced on the same day when the damage occurs. Damage to the temporary cover resulting from the Contractor's vehicles, equipment, or operations shall be repaired at the Contractor's expense.

MEASUREMENT AND PAYMENT

The quantity of temporary cover to be paid for will be measured by the square yard for the actual area covered.

The contract price paid per square yard for temporary cover shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing temporary cover, complete in place, including trench excavation and backfill, maintenance, and removal of temporary cover, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.05 TEMPORARY CONCRETE WASHOUT (PORTABLE)

A portable temporary concrete washout shall be furnished, maintained, and removed as specified in the approved Water Pollution Control Program in conformance with "Water Pollution Control" of these special provisions and as directed by the Engineer.

A portable temporary concrete washout shall consist of a commercially available drum at a minimum size of 55 gallons or alternate container upon written approval from the Engineer. The drum shall be stenciled "Concrete Waste Material." The letters shall be black and 4 inches in height on a white background. The top of the stenciling shall be 12 inches from the top of the barrel.

PLACEMENT

A portable temporary concrete washout shall be as follows:

- A. A portable temporary concrete washout shall be in place prior to placement of concrete and shall be located in the immediate area of the concrete work as approved by the Engineer. The temporary concrete washout shall be located away from construction traffic or public access areas. After initial placement, temporary concrete washout shall be moved as needed for concrete construction work. When the temporary concrete washout is no longer required, as determined by the Engineer, it shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.
- B. A sign shall be installed adjacent to each washout at a location determined by the Contractor and approved by the Engineer. Signs shall be installed in conformance with the provisions in Section 12-3.06B, "Portable Signs" of the Standard Specifications. Each portable sign shall consist of a base, framework and a sign panel. The sign panel shall be made out of plywood and shall have a minimum size of 48" x 24". The sign panel shall read "Concrete Washout" with black letters, 6 inches in height, on a white background.
- C. The Contractor shall provide sufficient temporary concrete washout capacity to contain liquid and concrete waste generated by washout operations without seepage or spills.

Maintaining the portable temporary concrete washout shall include removing and disposing of concrete waste. Concrete waste material generated shall be removed each day and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way" of the Standard Specifications.

The Contractor shall provide the name and location of the disposal facility to the Engineer before disposal of solid and liquid concrete waste. The Contractor shall provide verification that the off-site commercial or noncommercial disposal site has a permit issued by the California Regional Water Quality Control Board (RWQCB). If the disposal site is located outside of the State of California, the Contractor shall provide a copy of the permit issued by the state or local agency having jurisdiction over the disposal site.

When relocating or transporting a portable temporary concrete washout, the portable washout shall be properly secured to prevent spilling of concrete waste material.

PAYMENT

The contract lump sum price paid for temporary concrete washout (portable) shall include full compensation for furnishing all labor, materials, tools, equipment, including the sign, and incidentals, and for doing all the work involved in furnishing, placing, maintaining, repairing, replacing, transporting, disposing of concrete waste, and removing the washout, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.06 OBSTRUCTIONS

Attention is directed to Section 8-1.10, "Utility and Non-Highway Facilities," and Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

The Contractor shall notify the Engineer and the appropriate regional notification center for operators of subsurface installations at least 2 business days, but not more than 14 days, prior to performing any excavation or other work close to any underground pipeline, conduit, duct, wire or other structure. Regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert	811

10-1.07 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES

Flagging, signs, and temporary traffic control devices furnished, installed, maintained, and removed when no longer required shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Category 1 temporary traffic control devices are defined as small and lightweight (less than 100 pounds) devices. These devices shall be certified as crashworthy by crash testing, crash testing of similar devices, or years of demonstrable safe performance. Category 1 temporary traffic control devices include traffic cones, plastic drums, portable delineators, and channelizers.

If requested by the Engineer, the Contractor shall provide written self-certification for crashworthiness of Category 1 temporary traffic control devices at least 5 days before beginning any work using the devices or within 2 days after the request if the devices are already in use. Self-certification shall be provided by the manufacturer or Contractor and shall include the following:

- A. Date,
- B. Federal Aid number (if applicable),
- C. Contract number, district, county, route and post mile of project limits,
- D. Company name of certifying vendor, street address, city, state and zip code,
- E. Printed name, signature and title of certifying person; and
- F. Category 1 temporary traffic control devices that will be used on the project.

The Contractor may obtain a standard form for self-certification from the Engineer.

Category 2 temporary traffic control devices are defined as small and lightweight (less than 100 pounds) devices that are not expected to produce significant vehicular velocity change, but may cause potential harm to impacting vehicles. Category 2 temporary traffic control devices include barricades and portable sign supports.

Category 2 temporary traffic control devices shall be on the Federal Highway Administration's (FHWA) list of Acceptable Crashworthy Category 2 Hardware for Work Zones. This list is maintained by FHWA and can be located at:

http://safety.fhwa.dot.gov/roadway_dept/road_hardware/listing.cfm?code=workzone

The Department also maintains this list at:

<http://www.dot.ca.gov/hq/traffops/signtech/signdel/pdf/Category2.pdf>

Category 2 temporary traffic control devices that have not received FHWA acceptance shall not be used. Category 2 temporary traffic control devices in use that have received FHWA acceptance shall be labeled with the FHWA acceptance letter number and the name of the manufacturer. The label shall be readable and permanently affixed by the manufacturer. Category 2 temporary traffic control devices without a label shall not be used.

If requested by the Engineer, the Contractor shall provide a written list of Category 2 temporary traffic control devices to be used on the project at least 5 days before beginning any work using the devices or within 2 days after the request if the devices are already in use.

Category 3 temporary traffic control devices consist of temporary traffic-handling equipment and devices that weigh 100 pounds or more and are expected to produce significant vehicular velocity change to impacting vehicles. Temporary traffic-handling equipment and devices include crash cushions, truck-mounted attenuators, temporary railing, temporary barrier, and end treatments for temporary railing and barrier.

Type III barricades may be used as sign supports if the barricades have been successfully crash tested, meeting the NCHRP Report 350 criteria, as one unit with a construction area sign attached.

Category 3 temporary traffic control devices shall be shown on the plans or on the Department's Highway Safety Features list. This list is maintained by the Division of Engineering Services and can be found at:

http://www.dot.ca.gov/hq/esc/approved_products_list/HighwaySafe.htm

Category 3 temporary traffic control devices that are not shown on the plans or not listed on the Department's Highway Safety Features list shall not be used.

Full compensation for providing self-certification for crashworthiness of Category 1 temporary traffic control devices and for providing a list of Category 2 temporary traffic control devices used on the project shall be considered as included in the prices paid for the various items of work requiring the use of the Category 1 or Category 2 temporary traffic control devices and no additional compensation will be allowed therefor.

10-1.08 CONSTRUCTION AREA SIGNS

Construction area signs for temporary traffic control shall be furnished, installed, maintained, and removed when no longer required in conformance with the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to "Furnish Sign" of these special provisions.

Attention is directed to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. Type II retroreflective sheeting shall not be used on construction area sign panels. Type III, IV, VII, VIII, or IX retroreflective sheeting shall be used for stationary mounted construction area sign panels.

Unless otherwise shown on the plans or specified in these special provisions, the color of construction area warning and guide signs shall have black legend and border on orange background, except W10-1 or W47(CA) (Highway-Rail Grade Crossing Advance Warning) sign shall have black legend and border on yellow background.

Orange background on construction area signs shall be fluorescent orange.

Repair to construction area sign panels will not be allowed, except when approved by the Engineer. At nighttime under vehicular headlight illumination, sign panels that exhibit irregular luminance, shadowing or dark blotches shall be immediately replaced at the Contractor's expense.

The Contractor shall notify the appropriate regional notification center for operators of subsurface installations at least 2 business days, but not more than 14 days, prior to commencing excavation for construction area sign posts. The regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert	811

Excavations required to install construction area signs shall be performed by hand methods without the use of power equipment, except that power equipment may be used if it is determined there are no utility facilities in the area of the proposed post holes. The post hole diameter, if backfilled with portland cement concrete, shall be at least 4 inches greater than the longer dimension of the post cross section.

Construction area signs placed within 15 feet from the edge of the travel way shall be mounted on stationary mounted sign supports as specified in "Construction Area Traffic Control Devices" of these special provisions.

The Contractor shall maintain accurate information on construction area signs. Signs that are no longer required shall be immediately covered or removed. Signs that convey inaccurate information shall be immediately replaced or the information shall be corrected. Covers shall be replaced when they no longer cover the signs properly. The Contractor shall immediately restore to the original position and location any sign that is displaced or overturned, from any cause, during the progress of work.

10-1.09 MAINTAINING TRAFFIC

Maintaining traffic shall conform to the provisions in Sections 7-1.08, "Public Convenience," Section 7-1.09, "Public Safety," and Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications, "Public Safety" of these special provisions and these special provisions.

Closure is defined as the closure of a traffic lane or lanes, including shoulder, ramp or connector lanes, within a single traffic control system.

Chart No. 1 Complete Ramp Closure Hours/Ramp Lane Requirements																										
County: Riv							Route/Direction: 10/ WB							PM: R4.3												
Closure Limits: On & off ramps																										
FROM HOUR TO HOUR		24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mondays through Thursdays		C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Fridays		C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Saturdays		C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Sundays		C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Legend:																										
C		Ramp may be closed completely																								
REMARKS:																										
Both on & off ramps shall be closed for 83 continuous days to upgrade the rest area.																										

10-1.10 TRAFFIC CONTROL SYSTEM FOR RAMP CLOSURES

At the times and locations specified under "Maintaining Traffic" of these special provisions, ramps shall be closed in conformance with the details shown on the plans, the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications, and these special provisions.

The provisions in this section will not relieve the Contractor of the responsibility to provide additional devices or take measures as may be necessary to comply with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications.

If components used for closing a ramp are displaced or cease to operate or function as specified, from any cause, during the progress of the work, the Contractor shall immediately repair the components to the original condition or replace the components and shall restore the components to the original location.

When ramp closures are made for work periods only, at the end of each work period, components used for the ramp closure, except portable delineators placed along open trenches or excavation adjacent to the traveled way, shall be removed from the traveled way and shoulder. If the Contractor so elects, the components may be stored at selected central locations designated by the Engineer within the limits of the highway right of way.

RAMP CLOSED signs [SC6-3(CA)] shall be used to inform motorists of the temporary closing of a freeway or expressway entrance or exit ramp for not more than one day.

RAMP CLOSED signs [SC6-4(CA)] shall be used to inform motorists of the temporary closing of a freeway or expressway entrance or exit ramp for more than one day.

The SC6-3(CA) or SC6-4(CA) signs shall be installed at least 7 calendar days prior to closing the ramp, but not more than 14 days in advance of the ramp closure. The Contractor shall notify the Engineer not less than 2 calendar days prior to installing the SC6-3(CA) or SC6-4(CA) signs. The SC6-3(CA) or SC6-4(CA) signs shall be stationary mounted at locations shown on the plans and shall remain in place and visible to motorists during ramp closures.

The Contractor shall be responsible for maintaining accurate and timely information on the SC6-3(CA) or SC6-4(CA) signs. The SC6-3(CA) or SC6-4(CA) signs, when no longer required or when the information becomes outdated, shall be immediately covered or removed, or the sign message shall be updated.

Full compensation for providing the ramp closures shown on the plans, including furnishing, installing, maintaining, covering, and removing SC6-3(CA) and SC6-4(CA) signs, shall be considered as included in the contract prices paid for the various items of work involved and no separate payment will be made therefor.

10-1.11 TEMPORARY CRASH CUSHION MODULE

This work shall consist of furnishing, installing, and maintaining sand filled temporary crash cushion modules in groupings or arrays at each location shown on the plans, as specified in these special provisions or where designated by the Engineer. The grouping or array of sand filled modules shall form a complete sand filled temporary crash cushion in conformance with the details shown on the plans and these special provisions.

Attention is directed to "Public Safety" of these special provisions.

Temporary crash cushions shall be secured in place prior to commencing work for which the temporary crash cushions are required.

Whenever the work or the Contractor's operations establishes a fixed obstacle, the exposed fixed obstacle shall be protected with a sand filled temporary crash cushion. The sand filled temporary crash cushion shall be in place prior to opening the lanes adjacent to the fixed obstacle to public traffic.

Sand filled temporary crash cushions shall be maintained in place at each location, including times when work is not actively in progress. Sand filled temporary crash cushions may be removed during a work period for access to the work provided that the exposed fixed obstacle is 15 feet or more from a lane carrying public traffic and the temporary crash cushion is reset to protect the obstacle prior to the end of the work period in which the fixed obstacle was exposed. When no longer required, as determined by the Engineer, sand filled temporary crash cushions shall be removed from the site of the work.

Sand filled temporary crash cushion modules shall be one of the following, or equal, and be manufactured after March 31, 1997:

1. Energite III and Fitch Inertial Modules, manufactured by Energy Absorption Systems, Inc., 35 East Wacker Drive, Suite 1100, Chicago, IL 60601:
 - 1.1. Northern California: Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828, telephone (800) 884-8274, FAX (916) 387-9734
 - 1.2. Southern California: Traffic Control Service, Inc., 1818 E. Orangethorpe, Fullerton, CA 92831-5324, telephone (800) 222-8274, FAX (714) 526-9501
2. Traffix Sand Barrels, manufactured by Traffix Devices, Inc., 220 Calle Pintoresco, San Clemente, CA 92672, telephone (949) 361-5663, FAX (949) 361-9205
 - 2.1. Northern California: United Rentals, Inc., 1533 Berger Drive, San Jose, CA 95112, telephone (408) 287-4303, FAX (408) 287-1929
 - 2.2. Southern California: Statewide Safety & Sign, Inc., P.O. Box 1440, Pismo Beach, CA 93448, telephone (800) 559-7080, FAX (805) 929-5786
3. CrashGard Model CC-48 Sand Barrels, manufactured by Plastic Safety Systems, Inc., 2444 Baldwin Road, Cleveland, OH 44104:
 - 3.1. Northern California:
 - 3.1.1. Capitol Barricade Safety & Sign, 6329 Elvas Ave, Sacramento, CA 95819, telephone (888) 868-5021, FAX (916) 451-5388
 - 3.1.2. Sierra Safety, Inc., 9093 Old State Highway, New Castle, CA 95658, telephone (916) 663-2026, FAX (916) 663-1858
 - 3.2. Southern California: Hi Way Safety Inc., 13310 5th Street, Chino, CA 91710, telephone (909) 591-1781, FAX (909) 627-0999

Modules contained in each temporary crash cushion shall be of the same type at each location. The color of the modules shall be the standard yellow color, as furnished by the vendor, with black lids. The modules shall exhibit good workmanship free from structural flaws and objectionable surface defects. The modules need not be new. Good used undamaged modules conforming to color and quality of the types specified herein may be utilized. If used Fitch modules requiring a seal are furnished, the top edge of the seal shall be securely fastened to the wall of the module by a continuous strip of heavy duty tape.

Modules shall be filled with sand in conformance with the manufacturer's directions, and to the sand capacity in pounds for each module shown on the plans. Sand for filling the modules shall be clean washed concrete sand of commercial quality. At the time of placing in the modules, the sand shall contain not more than 7 percent water as determined by California Test 226.

Modules damaged due to the Contractor's operations shall be repaired immediately by the Contractor at the Contractor's expense. Modules damaged beyond repair, as determined by the Engineer, due to the Contractor's operations shall be removed and replaced by the Contractor at the Contractor's expense.

Temporary crash cushion modules may be placed on movable pallets or frames. Comply with dimensions shown on the plans. The pallets or frames shall provide a full bearing base beneath the modules. The modules and supporting pallets or frames shall not be moved by sliding or skidding along the pavement or bridge deck.

A Type R or P marker panel shall be attached to the front of the crash cushion as shown on the plans, when the closest point of the crash cushion array is within 12 feet of the traveled way. The marker panel, when required, shall be firmly fastened to the crash cushion with commercial quality hardware or by other methods determined by the Engineer.

At the completion of the project, temporary crash cushion modules, sand filling, pallets or frames, and marker panels shall become the property of the Contractor and shall be removed from the site of the work. Temporary crash cushion modules shall not be installed in the permanent work.

Temporary crash cushion modules placed in conformance with the provisions in "Public Safety" of these special provisions will not be measured nor paid for.

10-1.12 EXISTING HIGHWAY FACILITIES

The work performed in connection with various existing highway facilities shall conform to the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

EXISTING HIGHWAY IRRIGATION FACILITIES

Existing irrigation facilities within the limits of work shall remain in place. Irrigation facilities that are damaged by the Contractor's operation shall be reported immediately to the Engineer.

Water shall be maintained in conformance with the provisions in Section 20-5.025, "Maintain Existing Water Supply," of the Standard Specifications.

REMOVE CONCRETE

Concrete, where shown on the plans to be removed, shall be removed.

The pay quantities of concrete to be removed will be measured by the cubic yard, measured before and during removal operations.

Concrete removed shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

REMOVE ASPHALT CONCRETE

Concrete, where shown on the plans to be removed, shall be removed.

The pay quantities of asphalt concrete to be removed will be measured by the cubic yard, measured before and during removal operations.

Asphalt concrete removed shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

10-1.13 REMOVE TREE

The existing olive tree shown on the plans shall be completely removed and disposed of, including trunk and roots, to a minimum depth of 18" below finished grade. The hole will be backfilled to a smooth finished grade with soil from the project site.

The contract unit price paid for remove tree shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work, including backfill soil, and disposal of tree, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.14 MINOR HOT MIX ASPHALT

GENERAL

Summary

This work includes producing hot mix asphalt (HMA) at a central mixing plant and placing it as specified.

MATERIALS

For minor HMA:

1. Do not submit a job mix formula.
2. Choose the 1/2-inch HMA Type A aggregate gradation under Section 39-1.02E, "Aggregate," of the Standard Specifications.
3. Minimum asphalt binder content must be 6.0 percent for 1/2-inch aggregate gradation.
4. Choose asphalt binder Grade PG 64-16 under Section 92, "Asphalts," of the Standard Specifications.

If you request and the Engineer authorizes, you may reduce the minimum asphalt binder content.

Tack coat must comply with Section 39, "Hot Mix Asphalt," of the Standard Specifications.

CONSTRUCTION

Spread and compact minor HMA by methods that produce an HMA surfacing:

1. Textured uniformly
2. Compacted firmly
3. Without depressions, humps, and irregularities

MEASUREMENT AND PAYMENT

The contract item price paid per ton for minor hot mix asphalt includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in minor hot mix asphalt complete in place including tack coat, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.15 PRECAST CONCRETE PICNIC TABLES AND BENCHES

Precast concrete picnic tables and benches shall be Americans with Disabilities Act (ADA) approved, furnished and installed in conformance with details shown on the plans and these special provisions and as directed by the Engineer. Precast concrete picnic tables and benches shall be of one piece design and shall be manufactured of aggregates, sand and cement conforming to ASTM designation C-150. Steel reinforcing shall consist of No.2 and No.3 bar with welded wire mesh reinforcing producing a tensile strength of 80,900 psi.

Precast concrete picnic tables and benches shall be colored terracotta and shall have an acid etch finish with a matte sealer coating.

The contract unit price paid for precast concrete picnic table and benches shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in precast concrete table and benches, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.16 INSTALL ROADSIDE SIGN PANEL ON EXISTING POST

Roadside sign panels shall be installed on existing posts at the locations shown on the plans or where designated by the Engineer and in conformance with the provisions in Section 56-2.04, "Sign Panel Installation," of the Standard Specifications and these special provisions.

The Contractor shall furnish roadside sign panels in conformance with the provisions in "Furnish Sign" of these special provisions.

Cutting the ends of wood posts in the field and field application of wood preservatives shall conform to the provisions in Section 56-2.02B, "Wood Posts," of the Standard Specifications.

Two holes shall be drilled in each existing post as required to provide a breakaway feature as shown on the plans.

Installing roadside sign panels on existing posts will be paid for by the unit as determined from actual count in place.

The contract unit price paid for install roadside sign panel on existing post shall include full compensation for furnishing all labor, materials (except sign panels), tools, equipment, and incidentals, and for doing all the work involved in installing roadside sign panels on existing posts (including drilling holes in existing posts, removing, salvaging, and disposing of existing sign panels), complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.17 FURNISH SIGN

Signs shall be fabricated and furnished in accordance with details shown on the plans, the Traffic Sign Specifications, and these special provisions.

Traffic Sign Specifications for California sign codes are available for review at:

<http://www.dot.ca.gov/hq/traffops/signtech/signdel/specs.htm>

Traffic Sign Specifications for signs referenced with Federal MUTCD sign codes can be found in Standard Highway Signs Book, administered by the Federal Highway Administration, which is available for review at:

http://mutcd.fhwa.dot.gov/ser-shs_millennium.htm

Information on cross-referencing California sign codes with the Federal MUTCD sign codes is available at:

<http://www.dot.ca.gov/hq/traffops/signtech/signdel/specs.htm>

Temporary or permanent signs shall be free from blemishes that may affect the serviceability and detract from the general sign color and appearance when viewing during daytime and nighttime from a distance of 25 feet. The face of each finished sign shall be uniform, flat, smooth, and free of defects, scratches, wrinkles, gel, hard spots, streaks, extrusion marks, and air bubbles. The front, back, and edges of the sign panels shall be free of router chatter marks, burns, sharp edges, loose rivets, delaminated skins, excessive adhesive over spray and aluminum marks.

QUALITY CONTROL FOR SIGNS

The requirements of "Quality Control for Signs" in this section shall not apply to construction area signs.

No later than 14 days before sign fabrication, the Contractor shall submit a written copy of the quality control plan for signs to the Engineer for review. The Engineer will have 10 days to review the quality control plan. Sign fabrication shall not begin until the Engineer approves the Contractor's quality control plan in writing. The Contractor shall submit to the Engineer at least 3 copies of the approved quality control plan. The quality control plan shall include, but not be limited to the following requirements:

- A. Identification of the party responsible for quality control of signs,
- B. Basis of acceptance for incoming raw materials at the fabrication facility,
- C. Type, method and frequency of quality control testing at the fabrication facility,
- D. List (by manufacturer and product name) of process colors, protective overlay film, retroreflective sheeting and black non-reflective film,
- E. Recommended cleaning procedure for each product, and
- F. Method of packaging, transport and storage for signs.

No legend shall be installed at the project site. Legend shall include letters, numerals, tildes, bars, arrows, route shields, symbols, logos, borders, artwork, and miscellaneous characters. The style, font, size, and spacing of the legend shall conform to the Standard Alphabets published in the FHWA Standard Highway Signs Book. The legend shall be oriented in the same direction in accordance with the manufacturer's orientation marks found on the retroreflective sheeting.

On multiple panel signs, legend shall be placed across joints without affecting the size, shape, spacing, and appearance of the legend. Background and legend shall be wrapped around interior edges of formed panel signs as shown on plans to prevent delamination.

The following notation shall be placed on the lower right side of the back of each sign where the notation will not be blocked by the sign post or frame:

- A. PROPERTY OF STATE OF CALIFORNIA,
- B. Name of the sign manufacturer,
- C. Month and year of fabrication,
- D. Type of retroreflective sheeting, and
- E. Manufacturer's identification and lot number of retroreflective sheeting.

The above notation shall be applied directly to the aluminum sign panels in 1/4-inch upper case letters and numerals by die-stamp and applied by similar method to the fiberglass reinforced plastic signs. Painting, screening, or engraving the notation will not be allowed. The notation shall be applied without damaging the finish of the sign.

Signs with a protective overlay film shall be marked with a dot of 3/8 inch in diameter. The dot placed on white border shall be black, while the dot placed on black border shall be white. The dot shall be placed on the lower border of the sign before application of the protective overlay film and shall not be placed over the legend and bolt holes. The application method and exact location of the dot shall be determined by the manufacturer of the signs.

For sign panels that have a minor dimension of 48 inches or less, no splice will be allowed in the retroreflective sheet except for the splice produced during the manufacturing of the retroreflective sheeting. For sign panels that have a minor dimension greater than 48 inches, only one horizontal splice will be allowed in the retroreflective sheeting.

Unless specified by the manufacturer of the retroreflective sheeting, splices in retroreflective sheeting shall overlap by a minimum of one inch. Splices shall not be placed within 2 inches from edges of the panels. Except at the horizontal borders, the splices shall overlap in the direction from top to bottom of the sign to prevent moisture penetration. The retroreflective sheeting at the overlap shall not exhibit a color difference under the incident and reflected light.

Signs exhibiting a significant color difference between daytime and nighttime shall be replaced immediately.

Repairing sign panels will not be allowed except when approved by the Engineer.

The Department will inspect signs at the Contractor's facility and delivery location, and in accordance with Section 6, "Control of Materials," of the Standard Specifications. The Engineer will inspect signs for damage and defects before and after installation.

Regardless of kind, size, type, or whether delivered by the Contractor or by a common carrier, signs shall be protected by thorough wrapping, tarping, or other methods to ensure that signs are not damaged by weather conditions and during transit. Signs shall be dry during transit and shipped on pallets, in crates, or tier racks. Padding and protective materials shall be placed between signs as appropriate. Finished sign panels shall be transported and stored by method that protects the face of signs from damage. The Contractor shall replace wet, damaged, and defective signs.

Signs shall be stored in dry environment at all times. Signs shall not rest directly on the ground or become wet during storage. Signs, whether stored indoor or outdoor, shall be free standing. In areas of high heat and humidity signs shall be stored in enclosed climate-controlled trailers or containers. Signs shall be stored indoor if duration of the storage will exceed 30 days.

Screen processed signs shall be protected, transported and stored as recommended by the manufacturer of the retroreflective sheeting.

When requested, the Contractor shall provide the Engineer test samples of signs and materials used at various stages of production. Sign samples shall be 12" x 12" in size with applied background, letter or numeral, and border strip.

The Contractor shall assume the costs and responsibilities resulting from the use of patented materials, equipment, devices, and processes for the Contractor's work.

RETROREFLECTIVE SHEETING

The Contractor shall furnish retroreflective sheeting for sign background and legend in conformance with ASTM Designation: D 4956 and "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

Retroreflective sheeting shall be applied to sign panels as recommended by the retroreflective sheeting manufacturer without stretching, tearing, and damage.

Class 1, 3, or 4 adhesive backing shall be used for Type II, III, IV, VII, VIII, and IX retroreflective sheeting. Class 2 adhesive backing may also be used for Type II retroreflective sheeting. The adhesive backing shall be pressure sensitive and fungus resistant.

When the color of the retroreflective sheeting determined from instrumental testing is in dispute, the Engineer's visual test will govern.

PROCESS COLOR AND FILM

The Contractor shall furnish and apply screened process color, non-reflective opaque black film, and protective overlay film of the type, kind, and product that are approved by the manufacturer of the retroreflective sheeting.

The Contractor shall furnish the Engineer a Certificate of Compliance in accordance to Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for the screened process color, non-reflective opaque black film, and protective overlay film.

The surface of the screened process color shall be flat and smooth. When the screened process colors determined from the instrumental testing in accordance to ASTM Designation: D 4956 are in dispute, the Engineer's visual test will govern.

The Contractor shall provide patterns, layouts, and set-ups necessary for the screened process.

The Contractor may use green, red, blue, and brown reverse-screened process colors for background and non-reflective opaque black film or black screened process color for legend. The coefficient of retroreflection for reverse-screened process colors on white retroreflective sheeting shall not be less than 70 percent of the coefficient of retroreflection specified in ASTM Designation: D 4956.

The screened process colors and non-reflective opaque black film shall have the same outdoor weatherability as that of the retroreflective sheeting.

After curing, screened process colors shall withstand removal when tested by applying 3M Company Scotch Brand Cellophane Tape No. 600 or equivalent tape over the color and removing with one quick motion at 90° angle.

10-1.18 MINOR CONCRETE (EXPOSED AGGREGATE SIDEWALK)

Minor Concrete (Exposed Aggregate Sidewalk) shall conform to the provisions in Section 73, "Concrete Curbs and Sidewalks," of the Standard Specifications and these special provisions.

Aggregate for minor concrete (exposed aggregate sidewalk) shall conform to the grading specified for fine aggregate in Section 90-3.03, "Fine Aggregate Grading," of the Standard Specifications. Aggregate for exposed aggregate sidewalk shall conform to the following grading:

Sieve Sizes	Percentage Passing
½ inch	100
¼ inch	40-60
No. 6	10-20

A sample of 3 feet by 3 feet minor concrete (exposed aggregate sidewalk) panel shall be poured on site in the presence of the Engineer for approval.

Welded wire fabric and steel dowels of the size and type shown on the plans and conforming to the provisions in Section 52, "Reinforcement," of the Standard Specifications, shall be placed in the sidewalk as shown on the plans.

Joint filler shall conform to the provisions in section 51-1.12B "Filler Joints" of the Standard Specifications.

Sidewalks shown on the plans to receive exposed aggregate surfacing shall have a dense layer of aggregate, approximately ½" thick, broadcast uniformly over the wood floated surface. The layer shall be tamped into the surface to embed the top particles between 40 percent and 75 percent of the depth.

After the concrete matrix has set sufficiently to prevent dislodging or loosening of the exposed aggregate stones, all cement film and other loose material shall be cleaned from the exposed aggregate surfacing using stiff brooms and water.

An equivalent exposed aggregate finish produced by a concrete set retarder method, when approved by the Engineer, may be used as an alternative to the procedure specified herein.

The contract price paid per cubic yard for minor concrete (exposed aggregate sidewalk) shall include full compensation for furnishing all labor, materials (including welded wire fabric, steel dowels, dowel sleeves, joint fillers and aggregates for exposed aggregate sidewalk, tools, equipment, 3'x3' test panel and incidentals, and for doing all the work involved in constructing exposed aggregate sidewalk complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

SECTION 10-2 HIGHWAY PLANTING AND IRRIGATION SYSTEMS

10-2.01 GENERAL

The work performed in connection with highway planting and irrigation systems shall conform to the provisions in Section 20, "Erosion Control and Highway Planting," of the Standard Specifications and these special provisions.

The Contractor shall notify the Engineer not less than 72 hours prior to requiring initial access to the existing irrigation controllers. When the Engineer determines that access to the controllers is required at other times, arrangements will be made to provide this access.

PROGRESS INSPECTIONS

Progress inspections will be performed by the Engineer for completed highway planting and irrigation system work at designated stages during the life of the contract.

Progress inspections will not relieve the Contractor of responsibility for installation in conformance with the special provisions, plans and Standard Specifications. Work within an area shall not progress beyond each stage until the inspection has been completed, corrective work has been performed, and the work is approved, unless otherwise permitted by the Engineer.

The requirements for progress inspections will not preclude additional inspections of work by the Engineer at other times during the life of the contract.

The Contractor shall notify the Engineer, in writing, at least 4 working days prior to completion of the work for each stage of an area and shall allow a minimum of 3 working days for the inspection.

10-2.02 EXISTING HIGHWAY PLANTING

In addition to the provisions in Section 20, "Erosion Control and Highway Planting," of the Standard Specifications, work performed in connection with existing highway planting shall conform to the provisions in "Existing Highway Facilities," of these special provisions.

MAINTAIN EXISTING PLANTED AREAS

Existing planted areas, designated on the plans to be maintained, shall be maintained throughout the life of the contract in conformance with these special provisions.

Attention is directed to "Preservation of Property" of these special provisions.

Existing plants shall be watered in conformance with the provisions in Section 20-4.06, "Watering," of the Standard Specifications.

Existing planted areas to be maintained shall be inspected for deficiencies by the Contractor in the presence of the Engineer. Deficiencies requiring corrective action shall include weeds; dead, diseased, or unhealthy plants; missing plant stakes and tree ties; inadequate plant basins; and other deficiencies needing corrective action to promote healthy plant life. The inspection shall be completed within 15 days after the start of work.

When the existing turf has reached a height of 3 inches the turf shall be mowed to a height of 1.5 inches. Turf edges, including edges adjacent to sidewalks, shall be trimmed to a uniform edge not extending beyond the edge of turf or the facilities. Mowed and trimmed growth shall be removed and disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. Trimming shall be repeated whenever the edge of turf exceeds 1 inch.

When directed by the Engineer, existing plants shall be pruned and the work will be paid for as extra work in conformance with the provisions in Section 4-1.03D, "Extra Work," of the Standard Specifications.

After deficiencies have been corrected, the Contractor shall perform work to maintain existing planted areas in a neat appearance and to promote healthy plant growth. The work shall include the following:

- A. Weeds shall be killed before the weeds reach the seed stage of growth or exceed 6 inches in length whichever comes first.
- B. Trash, debris and weeds shall be removed from existing planted areas.
- C. Pesticides for maintaining existing planted areas shall conform to the provisions in "Pesticides" of these special provisions.

The contract lump sum price paid for maintain existing planted areas shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in maintain existing planted areas, complete in place, as shown on the plans, as specified in the standard specifications and these special provisions, and as directed by the Engineer.

PRUNE EXISTING PLANTS

Existing plants shown on the plans to be pruned shall be pruned in conformance with the provisions in Section 20-4.055, "Pruning," of the Standard Specifications.

Pruning shall include removal of deadwood, suckers, and broken or bruised branches one inch or larger in diameter. Tree seal compounds shall not be used to cover pruning cuts.

Removed pruned materials shall be disposed of in conformance to the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. At the Contractor's option, prunings may be reduced to chips. Chipped materials shall be spread within the highway right of way where designated by the Engineer.

The contract lump sum price paid for prune existing plants, except as otherwise provided, shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in pruning existing plants, complete in place, including removing and disposing of pruned materials, or chipping and spreading of chipped materials, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-2.03 EXISTING HIGHWAY IRRIGATION FACILITIES

The work performed in connection with the various existing highway irrigation system facilities shall conform to the provisions in "Existing Highway Facilities," of these special provisions.

Water shall be maintained in conformance with the provisions in Section 20-5.025, "Maintain Existing Water Supply," of the Standard Specifications.

CHECK AND TEST EXISTING IRRIGATION FACILITIES

Existing irrigation facilities that are to remain or to be relocated, and that are within those areas where clearing and grubbing or earthwork operations are to be performed, shall be checked for missing or damaged components and proper operation prior to performing clearing and grubbing or earthwork operations. Existing irrigation facilities outside of work areas that are affected by the construction work shall also be checked for proper operation.

A written list of existing irrigation system deficiencies shall be submitted to the Engineer within 5 working days after checking the existing facilities.

When existing irrigation facilities are checked, existing backflow preventers shall be tested for proper operation in conformance with the provisions in Section 20-5.03J, "Check and Test Backflow Preventers," of the Standard Specifications.

Length of watering cycles for use of potable water from water meters for checking or testing existing irrigation facilities shall be as determined by the Engineer.

Additional repairs required for the existing irrigation system as ordered by the Engineer, except as otherwise provided for in "Existing Highway Irrigation Facilities" of these special provisions, will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

RELOCATE EXISTING IRRIGATION FACILITIES

Relocate existing irrigation facilities shall consist of relocating existing electric remote control valves, sprinklers, pull boxes, backflow preventers, gate valves, wye strainers, irrigation controllers, and other facilities shown on the plans or specified in these special provisions.

Relocate existing sprinklers shall consist of relocating existing sprinklers, risers, riser supports, check valves, and concrete protectors as shown on the plans.

Existing irrigation facilities, shown on the plans to be relocated, that are, in the opinion of the Engineer, unsuitable for the purpose intended, shall be replaced in conformance with the provisions in Section 15-2.05, "Reconstruction," of the Standard Specifications.

After irrigation facilities have been relocated, the Contractor shall demonstrate that the relocated facilities function properly in the presence of the Engineer.

10-2.04 IRRIGATION SYSTEMS

Irrigation systems shall be furnished and installed in conformance with the provisions in Section 20-5, "Irrigation Systems," of the Standard Specifications, except materials containing asbestos fibers shall not be used.

Attention is directed to the provisions in "Obstructions" of these special provisions, regarding work over or adjacent to existing underground facilities. Excavation for proposed irrigation facilities shall not be started until the existing underground facilities have been located.

Method A pressure testing shall conform to the provisions in Section 20-5.03H(1), "Method A", of the Standard Specifications, except leaks that develop in the tested portion of the system shall be located and repaired after each test period when a drop of more than 5 pounds per square inch is indicated by the pressure gage. After the leaks have been repaired, the one hour pressure test shall be repeated and additional repairs made until the drop in pressure is 5 pounds per square inch or less.

FINAL IRRIGATION SYSTEM CHECK

A final check of existing and new irrigation facilities shall be performed not more than 40 working days and not less than 30 working days prior to acceptance of the contract.

The length of watering cycles using potable water measured by water meters for the final check of irrigation facilities will be determined by the Engineer.

Remote control valves connected to existing and new irrigation controllers shall be checked for automatic performance when the controllers are in automatic mode.

Unsatisfactory performance of irrigation facilities installed or modified by the Contractor shall be repaired and rechecked at the Contractor's expense until satisfactory performance is obtained, as determined by the Engineer.

Repair or replacement of existing irrigation facilities due to unsatisfactory performance shall conform to the provisions in "Existing Highway Irrigation Facilities" of these special provisions.

Nothing in this section "Final Irrigation System Check" shall relieve the Contractor of full responsibility for making good or repairing defective work or materials found before the formal written acceptance of the entire contract by the Director.

SECTION 11. (BLANK)

SECTION 12. BUILDING WORK

SECTION 12-1. GENERAL REQUIREMENTS

12-1.01 SCOPE

Building work described herein and as shown on the plans shall conform to the requirements of these special provisions and Sections 1 through 9 of the Standard Specifications. Sections 10 through 95 of the Standard Specifications shall not apply to the work in this Section 12 except when specific reference is made thereto.

The building work to be done consists, in general, of upgrade of existing comfort station, removal and replacement of existing picnic shelters, construction of new ADA parking stalls, and such other items or details, not mentioned above, that are required by the plans, Standard Specifications, or these special provisions to be performed, placed, constructed or installed.

12-1.02 ABBREVIATIONS

Section 1-1.02, "Abbreviations," of the Standard Specifications is amended by adding the following:

AAMA	American Architectural Manufacturers' Association
ACI	American Concrete Institute
AGA	American Gas Association
AITC	American Institute of Timber Construction
AMCA	Air Movement and Control Association
APA	American Plywood Association
ARI	Air-Conditioning and Refrigeration Institute
ASHRAE	American Society of Heating, Refrigeration and Air Conditioning Engineers
BIA	Brick Industry Association
CBC	California Building Code (2007 Edition)
CEC	California Electrical Code (2007 Edition)
CMC	California Mechanical Code (2007 Edition)
CPC	California Plumbing Code (2007 Edition)
ESO	Electrical Safety Orders
EWA	Engineered Wood Association
FM	FM Global
FS	Federal Specification
GA	Gypsum Association
GANA	Glass Association of North America
ICC	International Code Council
NAAMM	National Association of Architectural Metal Manufacturers
NEC	National Electrical Code
NFPA	National Fire Protection Association or National Forests Products Association
PEI	Porcelain Enamel Institute
PS	Product Standard (US Department of Commerce)
RIS	Redwood Inspection Service
SMACNA	Sheet Metal and Air Conditioning Contractors' National Association
SSPC	Steel Structures Paint Council
TCNA	Tile Council of North America
TPI	Truss Plate Institute
WCLIB	West Coast Lumber Inspection Bureau (stamped WCLB)
WCLB	Grade stamp for WCLIB
WI	Woodwork Institute
WIC	Woodwork Institute of California
WWPA	Western Wood Products' Association

12-1.03 GUARANTEE

The Contractor hereby unconditionally guarantees that the building work will be done in accordance with the requirements of the contract, and further guarantees the building work of the contract to be and remain free of defects in workmanship and materials for a period of one year from the date of acceptance of the contract, unless a longer guarantee period is required elsewhere in these special provisions. The Contractor hereby agrees to repair or replace any and all building work, together with any other adjacent work which may be displaced in so doing, that may prove to be not in accordance with the requirements of the contract or that may be defective in its workmanship or material within the guarantee period specified, without any expense whatsoever to the Department, ordinary wear and tear and unusual abuse or neglect excepted.

The performance bond for contract price of the building work, shall remain in full force and effect during the guarantee period.

The Contractor further agrees, that within 10 calendar days after being notified in writing by the Department of any building work not in accordance with the requirements of the contract or any defects in the building work, he shall commence and prosecute with due diligence all work necessary to fulfill the terms of this guarantee, and shall complete the work within a reasonable period of time, and, in the event he fails to comply, he does hereby authorize the Department to proceed to have such work done at the Contractor's expense and he shall honor and pay the cost and charges therefor upon demand. The Department shall be entitled to all costs and expenses, including reasonable attorney's fees, necessarily incurred upon the Contractor's refusal to honor and pay the above costs and charges.

12-1.04 COOPERATION

Attention is directed to Sections 7-1.14, "Cooperation," and 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications and these special provisions.

12-1.05 SUBMITTALS

Working drawings, material lists, descriptive data, samples and other submittals specified in these special provisions shall be submitted for approval in accordance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications and these special provisions.

Unless otherwise permitted in writing by the Engineer, all submittals required by these special provisions shall be submitted within 35 days after the contract has been approved.

Attention is directed to the provisions in Section 5-1.01, "Authority of Engineer," of the Standard Specifications. The Engineer may request submittals for materials or products where submittals have not been specified in these special provisions, or may request that additional information be included in specified submittals, as necessary to determine the quality or acceptability of such materials or products.

Attention is directed to Section 6-1.05, "Trade Names and Alternatives," of the Standard Specifications. The second indented paragraph of the first paragraph of said Section 6-1.05 is amended to read:

Whenever the specifications permit the substitution of a similar or equivalent material or article, no test or action relating to the approval of such substituted material will be made until the request for substitution is made in writing by the Contractor accompanied by complete data as to the equality of the material or article proposed. Such request shall be made within 35 days after the date the contract has been approved and in ample time to permit approval without delaying the work, but need not be made in less than 35 days after award of the contract.

Work requiring the submittal of working drawings, material lists, descriptive data, samples, or other submittals shall not begin prior to approval of said submittal by the Engineer. Fifteen working days shall be allowed for approval or return for correction of each submittal or resubmittal. Should the Engineer fail to complete his review within the time specified and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in review, an extension of time commensurate with the delay in completion of the work thus caused will be granted as provided in Section 8-1.07, "Liquidated Damages," of the Standard Specifications.

Submittals shall be delivered to the locations indicated in these special provisions. If a specific location is not indicated, the submittal shall be delivered to the Division of Structure Design, Documents Unit, Fourth Floor, Mail Station 9-4/4I, 1801 30th Street, Sacramento, California 95816, telephone (916) 227-8252, or the submittals shall be mailed to the Division of Structure Design, Documents Unit, Mail Station 9-4/4I, P. O. Box 942874, Sacramento, California 94274-0001.

Each submission of drawings, material lists and descriptive data shall consist of at least 5 copies. Two copies will be returned to the Contractor either approved for use or returned for correction and resubmittal.

Each separate item submitted shall bear a descriptive title, the name of the project, district, county, and contract number. Plans and detailed drawings shall be not larger than 22" x 36".

The material list shall be complete as to name of manufacturer, catalog number, size, capacity, finish, all pertinent ratings, and identification symbols used on the plans and in the special provisions for each unit.

Parts lists and service instructions packaged with or accompanying the equipment installed in the work shall be delivered to the Engineer at the jobsite. Required operating and maintenance instructions shall be submitted in triplicate.

Manufacturer's warranties for products installed in the work shall be delivered to the Engineer at the jobsite.

Unapproved samples and samples not incorporated in the work shall be removed from State property, when directed by the Engineer.

12-1.06 PROGRESS SCHEDULE

A progress schedule shall be submitted in duplicate for the building work in accordance with the requirements in Section 8-1.04, "Progress Schedule," of the Standard Specifications.

12-1.07 SCHEDULE OF VALUES

The Contractor shall prepare and submit to the Engineer for approval 2 copies of a Schedule of Values within 15 working days of approval of the contract covering each lump sum item for building work. Fifteen working days shall be allowed for approval or return for correction of each submittal or resubmittal. Should the Engineer fail to complete his review within the time specified and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in review, an extension of time commensurate with the delay in completion of the work thus caused will be granted as provided in Section 8-1.07, "Liquidated Damages," of the Standard Specifications.

The Schedule of Values must be accurately divided into sections representing the cost of each separate building or structure. All work that is not part of a separate building or structure, such as excavation, grading, curbs, gutters, sidewalks, paving, sewer and storm drainage and utility distribution lines are to be included under a specific section as General Work and not included in the building or structure cost. Indirect costs and general condition items are to be listed as a separate line item of work. The sections representing each building or structure must be identified as to the building or structure they represent and be broken down to show the corresponding value of each craft, trade or other significant portion of the work. A sub-total for each section shall be provided.

The Schedule of Values shall be approved by the Engineer before any partial payment estimate is prepared.

The sum of the items listed in the Schedule of Values shall equal the contract lump sum price for building work. Overhead, profit and bond premium are to be proportionally distributed across all line items of cost.

12-1.08 INSPECTION

All items covered or all stages of work that are not to remain observable must be inspected and approved before progress of work conceals portions to be inspected. The Contractor shall notify the Engineer not less than 72 hours in advance of when such inspection is needed.

12-1.09 OBSTRUCTIONS

Attention is directed to "Obstructions," of Section 10 "Construction Details," of these special provisions.

12-1.10 PRESERVATION OF PROPERTY

Attention is directed to Sections 7-1.11, "Preservation of Property," 7-1.12, "Indemnification and Insurance," 7-1.16, "Contractor's Responsibility for the Work and Materials," and 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications.

Operations shall be conducted in such a manner that existing facilities, surfacing, installations, and utilities which are to remain in place will not be damaged. Temporary surfacing, facilities, utilities and installations shall also be protected until they are no longer required. The Contractor, at his expense shall furnish and install piling, sheet piling, cribbing, bulkheads, shores, or whatever means may be necessary to adequately support material carrying such facilities, or to support the facilities themselves and shall maintain such support until they are no longer needed.

12-1.11 UTILITY CONNECTION

The Contractor shall make all arrangements, and obtain all permits and licenses required for the extension of and connection to each utility service applicable to this project, shall furnish all labor and materials necessary for such extensions which are not performed or provided by the utility, and shall furnish and install any intermediate equipment required by the serving utilities.

Upon written request by the Contractor, the State will pay all utility permits, licenses, connection charges, and excess length charges directly to the utility. Such request shall be submitted not less than 45 days before service connections are required.

The costs incurred by the Contractor for the extensions of utilities beyond the limits shown on the plans, and in furnishing and installing any intermediate equipment required by the serving utilities, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Full compensation for any costs incurred by the Contractor to obtain the permits and licenses shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

12-1.12 TEMPORARY UTILITIES

The Contractor may obtain electrical power and water from existing State electrical power and water outlets within the contract limits free of charge for contract operations where such utilities exist, provided that such utility services are in service and are not required by the State for other purposes and subject to the provisions in the section "Cooperation" of these special provisions.

The Contractor shall make his own arrangements to obtain any additional electrical power and water or other utilities required for his operations and shall make and maintain the necessary service connections at his own expense.

When existing utility systems are being modified, periods of shutdown will be determined by the Engineer.

The Contractor shall provide adequate temporary lighting to perform the work and allow the Engineer to inspect the project as each portion is completed.

The Contractor shall provide and pay for telephone service he may require. State telephone facilities shall not be used.

12-1.13 SANITARY FACILITIES

When operational, State sanitary facilities will be available for use by the Contractor's employees, during normal State working hours. Tools shall not be cleaned nor shall cleaning liquids be disposed of in State sanitary facilities or sewers.

During toilet room renovation or other periods when State-owned sanitary facilities are not operational, the Contractor shall provide and pay for wash facilities, drinking water fixtures and a minimum of two temporary toilet units for State forces. Separate toilet facilities shall be provided for Contractor's personnel. Facilities shall include the periodic flushing, waste removal and cleaning of such facilities. Units shall to be maintained in a clean and sanitary condition, including a supply of toilet tissue, toilet seat covers, paper towels and paper cups. Waste material shall be disposed of off site in a lawful manner. Temporary toilet units shall be single occupant units of the chemical, aerated recirculation or combustion type, properly vented and fully enclosed with a glass fiber reinforced polyester shell or similar nonabsorbent material.

12-1.14 MEASUREMENT AND PAYMENT

The contract lump sum price paid for building work shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the building work, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for any incidental materials and labor, not shown on the plans or specified, which are necessary to complete the buildings and appurtenances shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

12-1.15 PROJECT RECORD DRAWINGS

The Contractor shall prepare and maintain one set of project record drawings, using an unaltered set of original project plans, to clearly show all as-constructed information for the project. As a minimum, the information to be shown shall include 1) any plan clarifications or change orders, 2) locations of any underground utilities, or 3) the location, size, type, and manufacturer of all major products or components selected by the Contractor for use in the work.

All markings shall be placed on the project record drawings using red ink or red pencil. Original figures shall not be eradicated nor written over and superseded material shall be neatly lined out. Additional drawings shall be submitted if the required information cannot be clearly shown on the original set of project plans. The additional drawings shall be not less than 11" x 17" in size and shall have the contract number on each sheet. The Contractor shall sign and date each sheet of the project record drawings to verify that all as-constructed information shown on the drawings is correct.

The Contractor shall periodically review the set of project record drawings with the Engineer during the progress of the work to assure that all changes and other required information are being recorded.

Before completion of the work, the Contractor shall request a review of the project record drawings to determine the completeness and adequacy of them. If the project record drawings are unacceptable, the Contractor shall inspect, measure, and survey the project as necessary to record the required additional information.

The set of completed project record drawings shall be delivered to the Engineer prior to acceptance of the contract.

SECTION 12-2. SITEWORK

12-2.01 REMOVING PORTIONS OF EXISTING FACILITIES

PART 1 - GENERAL

Scope: This work shall consist of removing portions of the existing facilities, including removal of existing work to gain access to or for new work, in accordance with the details shown on the plans and these special provisions.

PART 2 - PRODUCTS (Not applicable)

PART 3 - EXECUTION

PREPARATION

The limits of removal shall be located and identified. Items to be removed and the interface of items to be removed and items to remain intact shall be identified and marked.

Prior to removing concrete or masonry, a saw cut approximately one inch deep shall be made along the limits of removal on all faces that will be visible in the completed work.

REMOVAL

Removal shall be to the limits shown on the plans. Removal shall be done carefully to minimize damage to the portions to remain. Remaining portions that are damaged by the Contractor's operation shall be restored to original condition at the Contractor's expense.

Assemblies to be salvaged which require dismantling for removal shall be matchmarked before dismantling.

Existing apparatuses, devices, or accessories which would be functionally impaired by new construction or remodeling shall be moved, brought out to new surfaces, or provided with new access covers, as necessary to restore apparatuses, devices, or accessories to their original usefulness.

Piping and conduits to be abandoned shall be capped or plugged.

Surfaces that are exposed to view at the limits of removal work shall be patched, bumps shall be removed and depressions filled, and the surface shall be finished to match the existing surrounding surfaces. Depressions in concrete less than one inch deep shall be deepened to one inch minimum depth before filling with cement mortar.

Anchor bolts and reinforcement shall be removed at least one inch below the surrounding surfaces, and the resulting hole shall be patched with cement mortar.

Existing reinforcement that is to be incorporated into the new work shall be protected from damage and thoroughly cleaned before being embedded in new concrete.

DISPOSAL

Materials that are to be removed, shall become the property of the Contractor and shall be disposed of outside the highway right of way in accordance with the requirements in Section 7-1.13, "Disposal of Material Outside of the Highway Right of Way," of the Standard Specifications.

SALVAGE

Materials or equipment shown on the plans to be salvaged shall remain the property of the State and shall be removed, cleaned and stockpiled at a location at the project site designated by the Engineer.

12-2.02 LEAD RELATED CONSTRUCTION WORK

GENERAL

SUMMARY

The work shall consist of removal and disposal of lead related construction materials which are specified in these special provisions to be removed and disposed of.

The Contractor shall take special precautions for that part of the work which involves the demolition and handling of materials which may contain lead, either during demolition or construction.

SITE CONDITIONS

The building areas to be removed are known to contain lead containing materials. A hazardous material survey report by SECOR International Incorporated, Project No. 04OT.08098.23 dated October 23, 2006, is included as an Information Handout. The following items tested positive for Lead Based Paint material:

Lead based paint		
Location	Description	Total Lead (mg/kg)
Picnic Area #1	Metal Roof, Tan	1810
Picnic Area #1	Metal Roof, Tan	1510
Picnic Area #1	Steel Support, Tan	3000
Picnic Area #2	Metal Roof, Tan	1190
Picnic Area #2	Metal Roof, Tan	1720
Picnic Area #2	Steel Support, Tan	1480
Picnic Area #2	Steel Support, Tan	960
Picnic Area #3	Metal Roof, Tan	2060
Picnic Area #3	Metal Roof, Tan	1530
Picnic Area #3	Metal Roof, Tan	1670

Where existing lead based materials are to be removed during demolition, construction or alterations, such material may need to be treated as hazardous waste, and shall be removed, hauled and disposed of in accordance with all applicable Federal, State and local laws and ordinances.

SUBMITTALS

The Contractor shall submit to the Engineer a lead compliance plan, abatement procedure plan and debris containment and collection plan. No work shall be done on any portion of the work which contains or may contain lead based materials until the Engineer has reviewed and accepted the submittals. The Contractor shall allow 15 days for the review of the submittals.

These plans shall be submitted as specified in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications.

Lead Compliance Plan:

The Contractor shall prepare a project specific lead compliance plan to prevent or minimize worker exposure to lead.

The lead compliance plan shall contain the elements listed in Title 8, California Code of Regulations, Section 1532.1(e)(2)(B). The lead compliance plan shall be prepared, signed and stamped by an Industrial Hygienist certified in Comprehensive Practice by the American Board of Industrial Hygiene.

Abatement Procedure Plan:

The abatement procedure plan prepared, signed and stamped by a lead project monitor or lead project designer currently certified by the California Department of Health Services. The plan shall address but not be limited to the following abatement procedures:

1. Personal monitoring procedures.
2. Phasing of abatement work indicating daily roster of workers for each phase.
3. Security system warning sign locations.
4. Detailed plans for decontamination facilities, toilets, and systems providing anteroom and work area to outside communication showing connections to the existing building.
5. Standard procedures for protecting workers, visitors, and employees and protection of spaces outside work area from contamination.
6. Engineering systems exposure control indicating number, location, and capacity of supply and exhaust systems, the expected direction of flow, and the range of expected differential pressure in each area.

7. Safety precautions such as lockout, tagout, fall protection, confined space entry procedures and equipment and work procedures to be used in the encapsulation, removal and disposal of lead based paint..
8. Final clearance inspection criteria.

Debris Containment and Collection Plan:

The debris containment and collection plan shall be prepared, signed and stamped by a lead project monitor or lead project designer currently certified by the California Department of Health Services. The program shall identify materials, equipment, and methods to be used when the existing paint system is disturbed and shall include working drawings of containment systems, and provisions for ventilation and air movement for visibility and worker safety.

QUALITY ASSURANCE

Codes which govern removal and disposal of materials containing lead include, but are not limited to the following:

1. California Health and Safety Code, Division 20, Chapter 6.5, "Hazardous Waste Control."
2. California Code of Regulations, Title 17, Division 1, Chapter 11, "Occupational Lead Poisoning Prevention Program."
3. California Code of Regulations, Title 22, Division 4.5, Chapter 10, "Hazardous Waste Management System: General."
4. California Code of Regulations, Title 8, Division 1, Chapter 4, Subchapter 4, Article 4, "Lead."
5. Occupational Safety and Health Administration (OSHA), 29 Code of Federal Regulation (CFR) Part 1926.62, "Lead."

NOTIFICATION

The Contractor shall notify the Engineer 3 business days in advance of the start of removal operations of lead based material.

Prior to performing operations involving the removal of lead based material, the Contractor shall provide written notification to all Federal, State and local agencies that regulate the removal, handling, transporting and disposal of lead in construction.

The Contractor shall notify the Division of Occupational Safety and Health (CAL OSHA) 24 hours prior to performing removal operations of materials containing lead or lead based materials.

QUALITY ASSURANCE

The lead related construction work shall be supervised by a California Department of Health Services Certified Lead Supervisor. The supervisor shall be on-site during abatement work preparation and post-abatement clean-up and be readily available as required by the California Code of Regulations, Title 17, Division 1, Chapter 8, Article 16, Work Practice Standard, 36100. Personnel for lead related construction work shall be California Department of Health Services Lead Worker Certified.

REGULATORY REQUIREMENTS

If measures being taken by the Contractor are inadequate to provide for worker safety and the containment and collection of residue from existing paint systems, the Engineer will direct the Contractor to revise operations and the compliance plans. Such directions will be in writing and will specify the items of work for which the Contractor's compliance plans are inadequate. No further work shall be performed on said items until the compliance plans are adequate and, if required, a revised compliance plan has been approved.

SAFETY

Construction activities (including demolition) that disturb materials or paints containing any amount of lead are subject to requirements in the California Code of Regulations, Title 8, Division 1, Chapter 4, Subchapter 4, Article 4, "Lead."

Any work that disturbs the lead based paint will expose workers to health hazards and will:

1. Produce debris containing heavy metal in amounts that may exceed the thresholds established in Titles 8 and 22 of the California Code of Regulations.
2. Produce toxic fumes when heated.

The Contractor shall be responsible for verifying that all employees, who are involved in removal operations, wear the required protective devices during removal operations.

Personal protective equipment, training, and washing facilities, required by the Contractor's health and safety plan shall be supplied to State personnel by the Contractor. The number of State personnel will be 4.

State personnel shall complete a safety training program provided by the Contractor, that meets the requirements of Title 8, California Code of Regulations, Division 1, Chapter 4 and the Contractor's lead compliance plan.

MATERIAL

Not Used

CONSTRUCTION

REMOVAL

Painted materials shall be removed using the wet process, vacuum blasting process or other acceptable processes that contain paint debris. The Contractor shall remove all paint and provide clean substrate suitable for a new finish.

Removed material and water used for removal shall be collected. Removed material shall be separated from water using approved filters.

HANDLING

The Contractor shall comply with all Federal, State, and local regulations for the removal of material containing lead prior to demolition and place removed material in approved plastic containers (double ply, 6 mil minimum thickness, plastic bags) with caution labels affixed to said bags. Such caution labels shall have conspicuous, legible lettering which spells out the following, or equivalent warning:

**CAUTION
CONTAINS LEAD**

Temporary storage on the ground of material and residue produced when the existing paint system is disturbed will not be permitted. Material and residue shall be stored in leak proof containers and shall be handled in such a manner that no spillage will occur.

At the option of the Contractor, the removed lead based materials may be placed directly into a roll off or drop box which shall have the same caution label affixed on all sides.

TRANSPORTING

The debris shall be hauled by a transporter currently registered with the California Department of Toxic Substances Control using correct manifesting procedures and vehicles displaying current certification of compliance. The Contractor shall make all arrangements with the operator of the disposal facility and perform any testing of the debris required by the operator. All vehicles used to transport hazardous waste material shall have affixed to the vehicle a valid Certificate of Compliance issued by United States Department of Transportation. If a roll off or drop box is utilized, both the drop box and the transporting vehicle shall have a valid Certificate of Compliance issued by the United States Department of Transportation.

DISPOSAL

The Engineer will obtain the required EPA generator identification numbers, and will sign the hazardous waste manifests.

All material and residue produced during removal operations shall be tested and profiled to determine hazardous waste characteristics. Dispose of residue and waste at an approved disposal facility in accordance with the requirements of the disposal facility operator.

The Contractor shall notify the proper authorities at the disposal site in advance of delivery of hazardous waste containing lead to the disposal site.

12-2.03 EARTHWORK FOR BUILDING WORK

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of performing earthwork for building work in accordance with the details shown on the plans and these special provisions.

Earthwork for building work shall consist of structure excavation. Structure excavation shall include excavation for footings and slabs.. In addition to structure excavation, earthwork for building work shall include any other earthwork, not mentioned, but necessary to complete the building work.

SITE CONDITIONS

Existing Underground Piping and Conduit: The location of existing underground piping and conduit is based on the best records available. Before beginning work, the Contractor shall accurately locate the piping and conduit involved in the work. If the location of the existing piping or conduit deviates from the location shown on the plans by more than 5 feet, or, if no elevations are indicated and the piping or conduit is more than 3 feet below grade, the cost of the additional excavation, backfill, piping or conduit, and removal and replacement of concrete, if any, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Existing Surfaced or Planted Areas:

Existing surfaced or planted areas that are removed, broken or damaged by the Contractor's operations shall be restored to their original condition except as otherwise shown on the plans or specified herein.

Restoration materials shall be equal to or better than the original materials. Surfacing shall be replaced to match the material thickness, grades, and finish of the adjacent surrounding surfaces.

PART 2 - PRODUCTS

Not applicable.

PART 3 - EXECUTION

PREPARATION AND RESTORATION

Sawcutting: Prior to excavation or trenching, existing surfacing shall be removed to saw cut lines, or to existing wood dividers or expansion joints, if any. The saw cut shall be to a neat line and have a depth not less than one inch.

Restoration: Surfacing shall be replaced to match the thickness, grades and finish of the adjacent surrounding surfaces.

STRUCTURE EXCAVATION

Unless otherwise noted, all excavation for building work shall be classified as structure excavation.

Footing Excavation:

The bottom of excavation shall not be disturbed. The contractor shall excavate by hand to the final grade. The bottom of concrete footings shall be poured against undisturbed material. Unless otherwise noted, compaction of the bottom of footing excavation is not required unless the material is disturbed. The footing depths shown on the plans shall be changed to suit field conditions when directed by the Engineer. Solid rock at or near required depths shall not be disturbed. Unsuitable material shall be excavated down to firm bearing as directed by the Engineer. Work and materials required because of excavation in excess of the depths shown on the plans, when such excavation has been ordered by the Engineer, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Excavate to the elevations and dimensions within a tolerance of $\pm 1/2$ inch. Limits of the excavation shall allow for adequate working space for installing materials and as required for safety of personnel. Such working space excavation shall be replaced in kind and compacted at the Contractor's expense.

Overdepth excavation for footings shall be backfilled with concrete or such other material recommended by the Contractor and approved by the Engineer. Relative compaction shall be not less than 95 percent.

DISPOSAL

Surplus Material: Surplus material from the excavation shall be removed and disposed of outside the right-of-way in accordance with Section 7-1.13 of the Standard Specifications.

FIELD QUALITY CONTROL

Inspection: When the excavation is substantially completed to grade, the Contractor shall notify the Engineer. No concrete shall be placed until the foundation has been approved by the Engineer.

12-2.04 FREE DRAINING GRANULAR MATERIAL

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and placing free draining granular material beneath slabs in accordance with the details shown on the plans and these special provisions.

PART 2 - PRODUCTS

Free Draining Granular Material: Free draining granular material shall be clean, hard, durable, free-draining rock. The material gradation shall be such that all passes the one-inch screen, and not more than 10 percent passes the No. 4 sieve as determined by California Test 202. Granular material shall be free from organic material, clay balls or other deleterious substances.

PART 3 - EXECUTION

SPREADING AND CONSOLIDATING

Free draining granular material shall be placed, spread, and consolidated by tamping or vibrating.

12-2.05 PAINTED PAVEMENT MARKINGS

PART 1 - GENERAL

Scope: This work shall consist of furnishing and applying paint, temporary striping, and pavement marking tape for pavement markings in conformance with the details shown on the plans and these special provisions.

Pavement markings include, but are not limited to, word and symbol markings, and parking stall markings.

Prior to re-striping the parking lot, apply one coat of black latex paint over existing white parking stripe and treat the parking stall area as shown on the plans with Type I thermoplastic coal-tar asphalt seal.

PART 2 - PRODUCTS

Paint:

Paint shall be commercial quality for pavement marking, formulated for the use intended, and manufactured by a nationally recognized manufacturer of coating products.

Traffic paint shall conform to the rules for control of volatile organic compound (VOC) emissions adopted by the air quality control district in the air basin in which the coatings are applied.

Temporary (Removable) Striping and Pavement Marking Tape (6 months or less): Products used for temporary (removable) striping and pavement marking tape (6 months or less) shall be selected from the pre-qualified products list below:

1. Advanced Traffic Marking, Series 200
2. Brite-Line, Series 100
3. Garlock Rubber Technologies, Series 2000
4. P.B. Laminations, Aztec, Grade 102
5. Swarco Industries, "Director-2"
6. Trelleborg Industries, R140 Series
7. 3M Series 620 "CR", and Series A750
8. 3M Series A145, Removable Black Line Mask
(Black Tape: for use only on Asphalt Concrete Surfaces)
9. Advanced Traffic Marking Black "Hide-A-Line"
(Black Tape: for use only on Asphalt Concrete Surfaces)
10. Brite-Line "BTR" Black Removable Tape
(Black Tape: for use only on Asphalt Concrete Surfaces)
11. Trelleborg Industries, RB-140
(Black Tape: for use only on Asphalt Concrete Surfaces)

PART 3 - EXECUTION

Alignment and Layout:

All necessary alignment and layout work shall be performed by the Contractor, in a manner that will not damage the pavement.

Unless otherwise shown on the plans, the width of parking stall markings shall be 4 inches.

Equipment and Operation:

Mechanical means shall be used to paint pavement markings.

All equipment used in the application of paint shall produce pavement markings of uniform quality.

All spray equipment shall be the proper type and of adequate capacity for the work involved.

Air atomized spray equipment shall be equipped with oil and water extractors and pressure regulators, and shall have adequate air volume and compressor recovery capacity. Spray gun tip needle assemblies and orifices shall be the proper size.

Stencils and hand spray equipment shall be used to paint word and symbol markings. Stencils shall be furnished by the Contractor. The stencil layout shall conform to the dimensions shown on the plans.

Surface Preparation: Surfaces to receive paint, temporary striping, or pavement marking tape shall be cleaned of all dirt and loose material.

Application:

Paint shall be applied only on dry surfaces, and only during periods of favorable weather, in conformance with the manufacturer's recommendations.

On new surfacing, paint shall be applied in 2 coats. The first coat shall be dry before application of the second coat is applied.

On existing surfacing, paint shall be applied in one coat.

Completed pavement markings shall have clean and well-defined edges, and shall conform to the dimensions shown on the plans or as specified in these special provisions.

Drips, oversprays, improper markings, and paint material tracked by traffic shall be immediately removed from the pavement by methods approved by the Engineer. All such removal shall be at the Contractor's expense.

Application Rates: Each application of paint shall be applied at the rates recommended by the paint manufacturer for the type of surface involved.

Protection: Newly placed pavement markings shall be protected from damage by traffic or other causes until the paint is thoroughly dry.

Disabled Accessible Parking Stall Symbol: Each parking space reserved for persons with physical disabilities shall have a minimum 3' x 3' surface identification with the international symbol of accessibility. The symbol and border shall be white and the background shall be blue conforming to Federal Standard 595B, Color No. 15090.

12-2.06 PARKING BUMPERS

PART 1 - GENERAL

Scope: This work shall consist of furnishing and installing precast concrete parking bumpers in accordance with the details shown on the plans and these special provisions.

PART 2 - PRODUCTS

Parking Bumpers:

Parking bumpers shall be commercially available precast parking bumpers.

Parking Bumpers shall be 48 inches long, nominal 8 inches wide and 6 inches high with both top longitudinal corners continuously chamfered, and anchor holes 9 inches from each end.

PART 3 - EXECUTION

Layout:

Arrangement of parking bumpers shall be coordinated with the layout of parking stalls and traffic aisles, providing the proper angle to engage wheels and proper location to prevent overtravel of vehicles.

Parking bumpers shall be anchored with two 3/4-inch diameter reinforcing bars 15 inches in length. The reinforcing bars shall be installed such that the top of the bars is flush with the top of the parking bumper.

12-2.07 ACCESSIBLE PARKING AND PARKING AREA ENTRANCE SIGNS

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing accessible parking and parking area entrance signs in accordance with the details shown on the plans and these special provisions.

SUBMITTALS

Product Data: Manufacturer's descriptive data and sign fastening details shall be submitted for approval.

PART 2 - PRODUCTS

Accessible Parking Sign: Accessible parking sign shall be a metal sign with baked enamel finish and the international symbol of accessibility. Sign background shall be blue and shall conform to Federal Standard 595B, Color No. 15090. Symbol, lettering and border shall be white and shall conform to Federal Standard 595B, Color No. 17886.

Van Accessible Sign: Van accessible sign shall be a metal sign with baked enamel finish and the international symbol of accessibility. Sign background shall be blue and shall conform to Federal Standard 595B, Color No. 15090. Lettering and border shall be white and shall conform to Federal Standard 595B, Color No. 17886.

Directional Sign: Directional sign shall be a metal sign with baked enamel finish and the international symbol of accessibility. Sign background shall be blue and shall conform to Federal Standard 595B, Color No. 15090. Symbol and border shall be white and shall conform to Federal Standard 595B, Color No. 17886.

Parking Area Entrance Sign: Parking Area Entrance sign shall be a metal sign with baked enamel finish. Sign background shall be blue and shall conform to Federal Standard 595B, Color No. 15090. Lettering and border shall be white and shall conform to Federal Standard 595B, Color No. 17886. Lettering shall be not less than one-inch in height and shall read as shown on the plans.

Support Post: Support post shall be commercial quality, standard weight, galvanized steel pipe. Pipe diameter shall be 1¾ inch.

Fastening Hardware: Fastening hardware shall be galvanized or cadmium plated.

Concrete: Concrete for support posts shall be commercial quality concrete, proportioned to provide a workable mix suitable for the intended use, with not less than 470 pounds of cement per cubic yard.

PART 3 - EXECUTION

Installation:

Support posts shall be placed in holes excavated to the depth and cross-section shown on the plans. Posts shall be set vertical and shall be firmly embedded in concrete backfill. The top of the concrete backfill around the post shall be crowned to drain water.

Support posts shall be fitted with a rainproof top.

Sign shall be fastened rigidly and securely to the support post.

The Engineer will provide the Contractor with the necessary information for the parking area entrance sign.

SECTION 12-3. CONCRETE AND REINFORCEMENT

12-3.01 CAST-IN-PLACE CONCRETE

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of constructing cast-in-place concrete facilities in accordance with the details shown on the plans and these special provisions.

SUBMITTALS

Product Data:

Manufacturer's descriptive data for admixtures, expansion joint material, vapor barrier, hardener, and sealer shall be submitted for approval.

Descriptive data shall be delivered to the Engineer at the jobsite.

QUALITY ASSURANCE

Certificates of Compliance:

Certificates of Compliance shall be furnished for cement, reinforcement, epoxy products, and admixtures in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

PART 2 - PRODUCTS

CONCRETE MIXES

Concrete (Structural Work):

Commercial quality concrete shall be proportioned to provide a workable mix suitable for the intended use; shall have not less than 564 pounds of cement per cubic yard; 0 to 2-inch penetration, inclusive, as determined by California Test 533.

Concrete (Minor Work):

Commercial quality concrete for concrete curbs shall be proportioned to provide a workable mix suitable for the intended use; shall have not less than 470 pounds of cement per cubic yard; 0 to 2-inch penetration, inclusive, as determined by California Test 533.

CONCRETE MATERIALS

Cement: Cement shall conform to ASTM Designation: C 150, Types II, or III portland cement; or Type IP (MS) Modified cement. Type IP (MS) Modified shall conform to ASTM Designation: C 595 and shall be comprised of an intimate mixture of Type II Modified cement and not more than 20 percent of a pozzolanic material.

Aggregates:

Aggregates shall be free from deleterious coatings, clay balls and other extraneous materials.

Admixtures: Admixtures used in portland cement concrete shall be included on the Department's current list of approved admixtures, and shall conform to ASTM Designation: C 494, Types A, B, D, F or G for chemical admixtures; ASTM Designation: C 260 for air-entraining admixtures; and ASTM Designation: C 618 for mineral admixtures, except loss on ignition shall not exceed 4 percent. Properties of admixtures shall be uniform in each lot.

FORM MATERIALS

Forms for Exposed Finish Concrete:

Forms for exposed surfaces shall be plywood, metal or other panel type materials. Plywood shall be not less than 5/8 inch thick and without scars, dents, and delaminations. Forms shall be furnished in largest practical pieces to minimize number of joints.

Plywood shall conform to the requirements of U. S. Product Standard PS-1 for Exterior B-B (Concrete Form) Class I.

Forms for edges of slabs shall be nominal 2-inch solid stock lumber, plywood, or metal forms.

Forms for Unexposed Finish Concrete: Forms for unexposed finish concrete surfaces shall be plywood, lumber, metal or other acceptable material.

Forms for Cylindrical Columns or Supports: Forms for cylindrical columns shall be metal, fiberglass reinforced plastic, paper or fiber tubes. Paper or fiber tubes shall be constructed of laminated plies using water-resistant adhesive with wax-impregnated exterior for protection against weather or moisture.

Form Ties: Form ties shall be factory fabricated, removable or snapoff metal ties for use as necessary to prevent spreading of forms during concrete placement.

Form Oil: Form oil shall be commercial quality form oil which will permit the ready release of the forms and will not discolor the concrete.

REINFORCING MATERIALS

Bar Reinforcement: Bar reinforcement shall conform to ASTM Designation: A 615/A 615M, Grade 60 [420], or ASTM Designation: A 706/A 706M.

Bar Supports: Bar supports for reinforcement shall be precast mortar blocks or ferrous metal chairs, spacers, metal hangers, supporting wires, and other approved devices of sufficient strength to resist crushing under applied loads.

EPOXY

Epoxy shall be furnished as 2 components which shall be mixed together at the site of the work.

Epoxy Resin Adhesive: Epoxy resin adhesive shall conform to State of California Specification No. 8040-21M-08 or other epoxy suitable for bonding new concrete to old.

Epoxy Mortars: Epoxy mortar and epoxy mortar surface treatment shall consist of a commercial quality, trowelable mixture consisting of epoxy and sand. Epoxy shall have a pull-off strength of not less than 1,000 psi and a 90-percent cure in 24 hours. Epoxy shall be of the type that requires no primer as a bonding agent.

Sand:

Sand for use in epoxy mortars shall be clean and shall have a moisture content of not more than 0.50-percent when tested in accordance with California Test 226.

Sand for epoxy mortar surface treatment shall be graded such that 100-percent passes the No. 100 sieve.

RELATED MATERIALS

Anchor Bolts, Nuts, and Washers:

Nonheaded anchor bolts shall conform to ASTM Designation: A 36/A 36M, with a minimum hook length of 6.2 diameters.

Headed anchor bolts shall conform to ASTM Designation: A 307.

Threaded rods shall conform to ASTM Designation: A 572.

Nuts shall conform to ASTM Designation: A 563, Grade A.

Washers for anchor bolts shall be commercial quality.

Exposed anchor bolts, nuts, and washers shall be hot dipped galvanized.

Expansion Joint Material: Expansion joint material shall be commercial quality asphalt impregnated pressed fiber sheets, 1/2-inch minimum thickness.

Bond Breaker: Bond breaker shall be Type I asphalt saturated organic felt or such other material approved by the Engineer.

Attention is directed to "Minor Concrete (Exposed Aggregate Sidewalk)," of Section 10 "Construction Details," of these special provisions regarding the picnic shelter slab and transition slab surface finish.

Type A Control Joints: Type A control joints shall be commercial quality, preformed, T-shaped plastic strips with detachable top flange.

Keyed Construction Joint Forms: Keyed construction joint forms shall be commercial quality, galvanized metal or plastic, factory fabricated construction joint forms. Forms shall produce a rabbeted key type joint.

Divider and Edger Strips: Divider and edger strips shall be foundation grade redwood.

Mortar: Mortar shall consist of one part cement to 2 parts clean sand and only enough water to permit placing and packing.

Curing Compound: Curing compound shall be a non-pigmented curing compound with fugitive dye conforming to the requirements of ASTM Designation: C 309, Type 1-D, Class A.

Splash Block: Splash blocks shall be precast concrete splash blocks with depressed runoff trough. Splash blocks shall be 12" x 24" x 3 1/2" in size unless otherwise shown on the plans.

ADMIXTURES

Admixtures shall be used when specified or ordered by the Engineer and may be used at the Contractor's option to conserve cement or to facilitate any construction operation.

Calcium chloride shall not be used in any concrete.

Admixtures shall be combined with concrete materials by methods that produce uniform properties throughout the concrete.

If more than one admixture is used, said admixtures shall be compatible with each other so that the desirable effects of all admixtures will be realized.

Mineral admixtures may be used to replace up to 15 percent of Type II portland cement provided the weight of mineral admixture used is not less than the weight of cement replaced. Mineral admixtures shall not be used to replace Type IP (MS) Modified or Type III cements. Chemical admixtures may be used to reduce up to 5 percent of the portland cement except that the cement content shall not be less than 470 pounds per cubic yard. When both chemical and mineral admixtures are used with Type II cement, the weight of cement replaced by mineral admixture may be considered as cement in determining the resulting cement content.

Mineral admixtures will be required in the manufacture of concrete containing aggregates that are determined to be "deleterious" or "potentially deleterious" when tested in accordance with ASTM Designation: C 289. The use of mineral admixture in such concrete shall conform to the requirements in this section except that the use of set retarding admixtures will not be permitted.

When the use of a chemical admixture is specified or is ordered by the Engineer, the admixture shall be used at the rate specified or ordered. If no rate is specified or ordered, or if the Contractor uses a chemical admixture for his own convenience, the admixture shall be used at the dosage normally recommended by the admixture manufacturer.

When air-entrainment is specified or is ordered by the Engineer, the air-entraining admixture shall be used in amounts to produce concrete having the specified or ordered air content as determined by California Test 504. If the Contractor uses air-entrainment for his own convenience, the average air content shall not exceed 4 percent and no single test shall exceed 5½ percent.

Chemical admixtures and air-entraining admixtures shall be dispensed in liquid form. Dispensers shall have sufficient capacity to measure at one time the total quantity required for each batch. If more than one liquid admixture is used in the concrete, a separate measuring unit shall be provided for each liquid admixture and dispensing shall be such that the admixtures are not mixed at high concentrations. When air-entraining admixtures are used with other liquid admixtures, the air-entraining admixtures shall be the first to be incorporated into the mix. Unless liquid admixtures are added to premeasured water for the batch, they shall be discharged to flow into the stream of water so that the admixtures are well dispersed throughout the batch.

BAR REINFORCING STEEL

Bending:

Reinforcing steel bars shall accurately conform to the dimensions shown on the plans.

Bars shall be bent or straightened in a manner that will not crack or break the material. Bars with kinks or improper bends shall not be used.

Hooks, bends and splices shall conform to the provisions of the Building Code Requirements for Reinforced Concrete of the American Concrete Institute.

MIXING AND TRANSPORTING CONCRETE

When a truck mixer or agitator is used for transporting concrete to the delivery point, discharge shall be complete within 1½ hours, or before 250 revolutions of the drum or blades, whichever comes first, after the introduction of cement to the aggregates.

The temperature of mixed concrete, immediately before placing, shall be not less than 50°F nor more than 90°F.

Truck mixers or agitator shall be equipped with electrically or mechanically actuated revolution counters by which the number of revolutions of the drum or blades may readily be verified. The counters shall be of the continuous-registering type, which accurately register the number of revolutions and shall be mounted on the truck so that the Engineer may

safely and conveniently inspect them from alongside the truck. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 86°F or above, a time less than 1½ hours may be required.

When non-agitating hauling equipment is used for transporting concrete to the delivery point, discharge shall be complete within one hour after the introduction of cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 86°F, or above, the time between the introduction of cement to the aggregates and discharge shall not exceed 45 minutes.

Each load of concrete for the work shall be accompanied by a trip ticket, a copy of which shall be delivered to the Engineer at the jobsite. The trip ticket shall show volume of concrete, weight of cement and aggregates, quantity of each admixture, quantity of water including water added at the jobsite, time of day the concrete is batched, and revolution counter readings on transit mix trucks at the times the truck is charged and unloaded.

PART 3 - EXECUTION

PREPARATION

Existing Concrete Construction:

Where fresh concrete joins existing or previously placed concrete or masonry, the contact surfaces of the existing or previously placed material shall be roughened, cleaned, flushed with water and allowed to dry to a surface dry condition immediately prior to placing the fresh concrete. The roughened surface shall be no smoother than a wood trowelled surface. Cleaning of the contact surfaces shall remove laitance, curing compounds, debris, dirt and such other substances or materials which would prevent bonding of the fresh concrete.

Abrasive blast methods shall be used to clean horizontal construction joints to the extent that clean aggregate is exposed.

Exposed reinforcing steel located at the contact surfaces which is to be encased in the fresh concrete shall be cleaned to remove any substance or material that would prevent bonding of the fresh concrete.

Forms:

Forms shall be mortar tight, true to the dimensions, lines, and grades shown on the plans, securely fastened and supported, and of adequate rigidity to prevent distortion during placing of concrete.

Forms for exposed surfaces shall be constructed with triangular fillets not less than 3/4" x 3/4" attached so as to prevent mortar runs and to produce smooth straight chamfers at all sharp edges of the concrete.

Form fasteners shall be removable without chipping, spalling, heating or otherwise damaging the concrete surface. Form ties shall be removed to a depth of at least one inch below the surface of the concrete.

The inside surfaces of forms shall be cleaned of all dirt, mortar and foreign material. Forms shall be thoroughly coated with form oil prior to use.

Forms shall not be stripped until at least 40 hours after placing concrete, except soffit forms and supports shall not be released or removed until at least 10 days after placing concrete.

Anchorage and embedded items shall be placed and rigidly secured at their planned locations prior to placing concrete.

Reglets or embedded flashing shall be installed on concrete forms before the concrete is placed.

Redwood dividers shall have 16d galvanized nails partially driven into both vertical faces at 18 inches on center.

Placing Reinforcing Steel:

Reinforcing steel bars shall be accurately placed to the dimensions shown on the plans.

Bar reinforcement conforming to ASTM Designation: A 615/A 615M, Grade 60 [420], or A 706/A 706M shall be lapped at least 45 diameters.

Bars shall be firmly and securely held in position by means of wiring and approved bar supports. The spacing of supports and ties shall prevent displacement of the reinforcing or crushing of supports.

Tie wire shall be clear of concrete formwork and concrete surfaces.

All reinforcing steel shall be in place and inspected before concrete placement begins. Placing of bars on fresh layers of concrete will not be permitted.

PLACING CONCRETE

Concrete shall be placed and consolidated by means of internal vibrators to form dense, homogeneous concrete free of voids and rock pockets.

Forms and subgrade shall be thoroughly moistened with water immediately before placing concrete.

Concrete shall be placed as nearly as possible to its final location and the use of vibrators for extensive shifting of the concrete will not be permitted.

Concrete shall be deposited and consolidated in a continuous operation within limits of construction joints, until the placing of the panel or section is completed.

When concrete is to be placed in large areas requiring more than two pours, concrete shall be placed in alternate long strips between construction joints and the final slab infilled.

Vibrators used to consolidate concrete containing epoxy-coated bar reinforcement shall have a resilient covering to prevent damage to such reinforcement.

FINISHING CONCRETE SURFACES

Finishing Unformed Surfaces:

Slabs shall be placed full thickness to finish elevation and leveled to screeds by use of long straightedges. The screeds shall be set to grade at approximately 6-foot centers. After leveling, screeds shall be removed and the surface shall be floated with wooden floats.

Type A control joint strips shall be inserted into the floated concrete so that the bottom of the top flange is flush with the finish elevation. Strips shall be standard manufactured lengths and shall be placed on an approximate straight line. The top flange of the strips shall be removed after the concrete has set and cured.

The floated surface shall be trowelled with steel trowels. Troweling shall form a dense, smooth and true finish. Walkways, pedestrian ramps, stairs and outdoor slabs for pedestrian traffic shall be given a non-slip broom finish unless a different finish is called for on the plans or in these special provisions.

The application of cement dust coat will not be permitted.

Steel trowel finish and broom finish will not be required for slabs to receive exposed aggregate finish nor for slabs to be covered with ceramic tile.

Concrete floor surfaces to receive ceramic tile shall be floated to grade and then, before final set of the concrete, the floated surfaces shall be roughened with stiff bristled brushes or rakes.

Finished surfaces of floor slabs shall not deviate more than 1/8 inch from the lower edge of a 10-foot long straight edge.

Finishing Formed Surfaces:

Formed concrete surfaces shall be finished by filling holes or depressions in the surface, repairing all rock pockets, and removing fins. All surfaces of formed concrete exposed to view shall have stains and discolorations removed, unsightly bulges removed, and all areas which do not exhibit the required smooth, even surface of uniform texture and appearance shall be sanded with power sanders or other approved abrasive means until smooth, even surfaces of uniform texture and appearance are obtained.

Cement mortar, patching and finishing materials used to finish exposed surfaces of concrete shall closely match the color of surrounding surfaces.

CURING CONCRETE

Freshly placed concrete shall be protected from premature drying and excessive cold or hot temperatures.

Initial curing of floor slabs shall start as soon as free water has disappeared from the concrete surface. The concrete shall be kept continuously wet by application of water for not less than 7 days after the concrete has been placed.

Cotton mats, rugs, carpets, or sand blankets may be used as a curing medium to retain the moisture during the curing period. Curing materials that will stain or discolor concrete shall not be used on surfaces exposed to view.

Prior to placing the curing medium, the entire surface of the concrete shall be kept damp by applying water with a nozzle that so atomizes the flow that a mist and not a spray is formed, until the surface of the concrete is covered with the curing medium. At the expiration of the curing period, the concrete surfaces shall be cleared of all curing mediums.

Concrete surfaces, other than floor slabs, shall be kept moist for a period of at least 5 days by leaving the forms in place or by covering the exposed surfaces using moist rugs, cotton mats or other curing materials approved by the Engineer.

Concrete curbs, sidewalks, collars, and gutter depressions may be cured with a curing compound.

PROTECTING CONCRETE

Concrete shall not be placed on frozen or frost covered surfaces.

Concrete shall be protected from damage due to rain, freezing or inclement weather, and shall be maintained at a temperature of not less than 40°F for 72 hours. When required by the Engineer, the Contractor shall provide a written outline of his proposed methods of protecting concrete.

Vehicles, equipment, or concentrated loads weighing more than 300 pounds individually and material stockpiles weighing more than 50 pounds per square foot will not be permitted on the concrete within 10 calendar days after placing.

SECTION 12-5. METALS

12-5.01 BUILDING MISCELLANEOUS METAL

PART 1 - GENERAL

Scope: This work shall consist of fabricating, furnishing, and installing building miscellaneous metal in accordance with the details shown on the plans and these special provisions.

Building miscellaneous metal shall consist of the following:

Loose bearing and leveling plates.

Miscellaneous steel trim including steel angle corner guards

Anchor Bolts, steel pipe sleeves, and wedge-type inserts indicated to be cast into concrete or built into unit masonry.

REFERENCES

Codes and Standards: Welding of steel shall be in accordance with American Welding Society (AWS) D 1.1, "Structural Welding Code - Steel" and D 1.3, "Structural Welding Code - Sheet Steel."

SUBMITTALS

Product Data: Submit manufacturer's specifications, anchor details, and installation instructions for products used in miscellaneous metal fabrications.

Working Drawings: Working drawings of fabricated items shall be submitted for approval.

QUALITY ASSURANCE

Shop Assembly: Preassemble items in shop to the greatest extent possible to minimize field splicing and assembly. Disassemble units only as necessary for shipping and handling limitations. Clearly mark all units for reassembly and installation.

Inspection and Tests: Materials and fabrication procedures shall be subject to inspection and tests by the Engineer, in mill, shop, and field. Such tests will not relieve the Contractor of responsibility of providing materials and fabrication procedures in compliance with specified requirements.

PART 2 - PRODUCTS

MATERIALS

Steel Bars, Plates, and Hot-rolled Shapes: Steel bars, plates, and hot-rolled shapes shall conform to ASTM A 36/A 36M.

Galvanized Sheet Steel: Galvanized sheet steel shall conform to ASTM A 653/A 653M, Grade 33. Galvanizing shall be G60.

Pipe: Pipe shall be commercial quality standard steel pipe.

Hollow Structural Sections: Hollow structural sections shall conform to ASTM A 500/A 500M, Grade B, or A 501.

Bolts, Studs, Threaded Rods, Nuts, and Washers:

Bolts, studs, and threaded rods for general application shall conform to ASTM A 307 or F 1554, Grade 36.

Nuts shall conform to ASTM A 563.

Washers bearing on wood surfaces shall be commercial quality. Washers bearing on steel surfaces shall conform to ASTM F 844 or F 436.

Fittings: Brackets, bolt, threaded studs, nuts, washers, and other fittings for railings and handrailings shall be commercial quality pipe and fittings.

Expansion Anchors: Expansion anchors shall be ICC approved for the purpose intended, integral stud type anchor or internally threaded type with independent stud, hex nut, and washer.

Powder Driven Anchors: Powder driven anchors shall be plated, spring steel alloy drive pin or threaded stud type anchors for use in concrete or steel. Spring steel shall conform to ASTM A 227, Class 1. The diameter, length, and type of shank and the number and type of washer shall be as recommended by the manufacturer for the types and thickness of material being anchored or fastened.

Mortar: Mortar shall consist of one part cement, measured by volume, to 2 parts clean sand and only enough water to permit placing and packing.

FABRICATION

Workmanship and Finish:

Workmanship and finish shall be equal to the best general practice in modern shops.

Miscellaneous metal shall be clean and free from loose mill scale, flake rust and rust pitting, and shall be well formed and finished to shape and size with sharp lines and angles. Bends from shearing or punching shall be straightened.

The thickness of metal and details of assembly and support shall give ample strength and stiffness.

Built-up parts shall be true to line and without sharp bends, twists, and kinks. Exposed ends and edges of metal shall be milled or ground smooth, with corners slightly rounded.

Joints exposed to the weather shall be made up to exclude water.

Galvanizing: Items indicated on the plans to be galvanized shall be hot-dip galvanized after fabrication. The weight of galvanized coating shall be at least 1½ ounces per square foot of surface area, except drainage grates shall have at least 2 ounces per square foot of surface area.

Painting: Building miscellaneous metal items that are not galvanized shall be cleaned and coated with one prime coat prior to erection in accordance with the requirements specified under "Painting" in Section 12-9 of these special provisions. After erection, surfaces shall be coated with a second prime coat, and finish coats when specified, in accordance with the requirements specified under "Painting" in Section 12-9.

Loose Bearing and Leveling Plates: Loose bearing and leveling plates shall be furnished for steel items bearing on masonry or concrete construction, made flat, free from warps or twists, and of required thickness and bearing area. Plates shall be drilled to receive anchor bolts. Galvanize after fabrication.

PART 3 - EXECUTION

GENERAL

Anchorage:

Anchorage devices and fasteners shall be provided for securing miscellaneous metal in-place construction; including threaded fasteners for concrete and masonry inserts, toggle bolts, through bolts, lag bolts, wood screws, and other connectors.

Cutting, drilling, and fitting shall be performed as required for installation of miscellaneous metal fabrications. Work is to set accurately in location, alignment and elevation, plumb, level, true and free of rack, measured from established lines and levels.

Loose Leveling and Bearing Plates: Plates shall be set on wedges or other adjustable devices. Anchor bolts shall be wrench tightened after the plates have been positioned and plumbed. Mortar shall be packed solidly between bearing surfaces and plates to ensure that no voids remain.

Powder Driven Anchors: Powder driven anchors shall be installed with low velocity powder actuated equipment in accordance with the manufacturer's instructions and State and Federal OSHA regulations.

DAMAGED SURFACES

Galvanized surfaces that are abraded or damaged shall be repaired by thoroughly wire brushing the damaged areas and removing all loose and cracked coating. The clean areas shall then be painted with 2 spot applications of a coating conforming to the requirements in the Detailed Performance Standards of the Master Painters Institute (MPI) and listed on MPI List Number 18, Primer, Zinc Rich, Organic.

12-5.02 ALUMINUM HANDRAIL AND RAILINGS

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of fabricating, furnishing, and installing aluminum handrails and railing systems in conformance with the details shown on the plans and these special provisions.

SUBMITTALS

Product Data: Manufacturer's descriptive data for products and processes used in handrails and railing systems shall be submitted for approval.

Working Drawings:

Working drawings of handrails and railings shall be submitted for approval.

Working drawings shall show fabrication and installation for each type of handrail and railing system required including plans, elevations, sections, profiles of rails, fittings, connections and anchors.

Samples: Two 6-inch long samples of each railing member with differing sizes or profiles, including handrails, top rails, posts and balusters, shall be submitted for approval.

QUALITY ASSURANCE

Single Source Responsibility: Handrails and railing systems of each type and material shall be obtained from a single manufacturer.

DELIVERY, STORAGE AND HANDLING

Storage: Handrails and railing systems shall be stored in a clean, dry location, away from uncured concrete and masonry, protected from damage of any kind. Handrails and railing systems shall be covered with waterproof paper, tarpaulin, or polyethylene sheeting in such a manner that air circulation will be provided.

PART 2 - PRODUCTS

MANUFACTURERS

Acceptable manufactures: Subject to conformance with the plans and special provisions, the aluminum railing manufacturer shall be Feeney Inc. toll free number (800) 888-2418, Flotation System Inc. Home Product Division, toll free number (800) 711-1785, and Duradek U.S. Inc. toll free number (800) 338-3568, or equal.

MATERIALS

Railing Elements: Railing elements shall conform to the requirements in ASTM Designation: B 221/B 221M, Aluminum and Aluminum-Alloy extruded Bars, Wire, Profiles, and Tubes, Type 6063-T6 aluminum alloy, 3/4 inch square tubes with A powder coated finish.

Brackets, Flanges, Fittings and Anchors: Brackets, flanges, fittings and anchors shall be the manufacturer's standard for interconnection of handrail and railing members to other work.

Fasteners:

Fasteners shall be the same basic metal as the fastened metal. Corrosive metals and metals that are incompatible with the metals joined shall not be used.

Concealed fasteners shall be used for interconnections of handrail and railing components and for their attachments to other work except where exposed fasteners are unavoidable or are the standard fastening method for handrail and railing systems indicated.

Exposed fasteners shall be Phillips flat head screws unless otherwise noted on the plans.

FABRICATION

Handrails and railing systems shall be fabricated to the dimensions and details shown on the plans.

Items shall be preassembled in the shop to the greatest extent possible to minimize field splicing and assembly. Units shall be disassembled only as necessary for shipping and handling.

Returns shall be made at free ends of handrailing to bring the pipe to within ¼ inch of the wall. Ends of railing elements shall be capped. Concealed weeps shall be provided at low points.

Expansion joints shall have pipe sleeves.

Changes in direction of railing members shall be formed by bending members, insertion of prefabricated elbow fittings, radius bends, or by mitering. Elbow bends shall be by using mitered joints.

Welding shall be by the tungsten inert gas arc welding method or the consumable electrode inert gas method. Welding processes that require the use of flux will not be permitted.

Welding shall conform to the requirements in the American Welding Society publication No. AWS D 1.2, "Structural Welding Code - Aluminum."

Exposed welds shall be ground smooth and flush.

FINISHES

Anodizing: After fabrication, exposed surfaces of aluminum shall be given a clear anodic oxide coating conforming to the requirements in ASTM Designation: B 580, Type B, Architectural Class I. Surfaces to be coated shall be free of scratches, porosity, inclusions, roll and die marks, cold-shuts, and cracks that will adversely affect the appearance and performance of the anodic coatings.

PART 3 - EXECUTION

INSTALLATION

The handrailing shall be erected to line and grade without welding in the field. Installation shall be in conformance with the manufacturer's recommendations. Posts shall be within 1/8 inch of vertical.

Exposed connections shall be accurately fitted to form tight, hairline joints.

The location of expansion joints shall be in conformance with the manufacturer's recommendation except that joints shall be spaced not closer than 15 feet apart and shall be coordinated with joint locations in the support structure.

Corrosion Protections:

Aluminum surfaces to be in contact with grout or concrete materials shall be given a heavy coat of alkali-resistant bituminous paint.

An inert washer or gasket shall be used on aluminum surfaces in contact with dissimilar metals.

Railing Connections:

Railing ends shall be anchored to concrete or masonry with manufacturer's standard fittings designed for this purpose, unless otherwise shown on the plans.

CLEANING

Paint, dirt, stains and grout shall be removed without marring or scratching the aluminum surfaces. Solvents and cleaning compounds shall be chemically compatible with the anodic coating and aluminum.

PROTECTION

Finishes of railing systems and handrails shall be protected from damage during constructions by use of temporary protective coverings. Coverings are to be removed upon completion of the work.

Finishes damaged during installation and construction shall be restored so that no evidence remains of construction work.

SECTION 12-6. WOOD AND PLASTICS

12-6.01 ROUGH CARPENTRY

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing materials and performing rough carpentry work including wood framing, furring, and sheathing in accordance with the details shown on the plans and these special provisions.

Rough carpentry includes carpentry work not specified as part of other sections and which is generally not exposed.

SUBMITTALS

Product Data: Manufacturer's material data and installation instructions shall be submitted for gypsum sheathing, framing hardware and underlayments.

Wood Treatment Data:

Chemical treatment manufacturer's instructions shall be submitted for the handling, sorting, installation, and finishing of treated materials.

For each type of preservative treatment used, certification by treating plant shall include type of preservative solution and pressure process used, net amount of preservative retained and conformance with the applicable standards of the American Wood Preservers Association.

For each type of fire-retardant treatment, include certification by treating plant that the treated material complies with the applicable standards and other requirements.

DELIVERY, HANDLING AND STORAGE

Delivery and Storage: Materials shall be kept under cover and dry. All materials shall be protected from exposure to weather and contact with damp or wet surfaces with blocking and stickers. All lumber, plywood and other panels shall be stacked in such a manner to provide air circulation within and around the stacks.

PART 2 - PRODUCTS

LUMBER

Lumber shall be manufactured to comply with PS 20, "American Softwood Lumber Standard," and with applicable grading rules of inspection.

Softwood lumber shall be quality grade stamped or shall be accompanied by a certificate of inspection. Inspection certificates or grade stamps shall indicate compliance with the grading requirements of WWPA, WCLIB, RIS, or other approved lumber inspection agencies.

All lumber used shall be nominal sized and dressed S4S unless otherwise specified in these special provisions.

Framing lumber shall be solid stock lumber, Douglas Fir-Larch, and the grades indicated under WCLIB or WWPA rules. Moisture content shall not exceed 19 percent and shall be grade stamped "S-Dry."

DIMENSION LUMBER

Except as otherwise shown on the plans, lumber shall have the following grades.

Vertical Framing Lumber:

Vertical framing lumber, nominal 2" x 2" through 4" x 4", shall be Construction grade or better.

Vertical framing lumber, nominal 2" x 6" through 4" x 6", shall be No. 2 or better.

Horizontal Framing Lumber:

Horizontal framing lumber, nominal 2" x 4" and wider, including joists and rafters, shall be No. 2 or better.

Horizontal framing lumber, nominal 4" x 4" and wider, including joist and rafters, shall be No. 1 or better.

Exposed Framing Lumber: Exposed framing lumber which is not concealed and is to receive a stain or natural finish shall be the same grade and species as indicated for structural framing and hand selected for appearance.

Miscellaneous Lumber:

Miscellaneous lumber for support or attachment of other work including rooftop equipment curbs and support bases, cant strips, bucks, nailers, blocking, furring, grounds, stripping and similar members shall be not less than No. 2 or better.

Lumber in contact with concrete or masonry construction shall be pressure treated Douglas Fir-Larch.

PLYWOOD PANELS

Plywoodpanels shall comply with Voluntary Product Standard PS1, "U. S. Product Standard for Construction and Industrial Plywood."

Plywood panels shall be Group 1 unless otherwise noted.

Each plywood panel shall be factory marked with APA or other trademark evidencing compliance with grade requirements.

Structural Plywood Wall Sheathing: Structural plywood wall sheathing for walls shall be APA RATED SHEATHING, Exposure 1. Thickness and grade shall be as shown on the plans.

Structural Plywood Roof Sheathing:

Structure plywood roof sheathing shall be APA RATED SHEATHING, Exposure 1. Span rating, thickness and grade shall be as shown on the plans.

Structure plywood roof sheathing in exposed overhangs shall be APA RATED SHEATHING, A-C, Exterior, Group 1. Thickness shall be the same as the remainder of the sheathing.

MISCELLANEOUS MATERIALS

Rough Carpentry Hardware:

Steel plates and rolled sections shall be mild, weldable steel, conforming to AISI grades 1016 through 1030 except 1017.

Nails, screws, bolts, nuts, washers shall be commercial quality. Exposed fasteners shall be hot dipped galvanized or stainless steel.

Joist hangers, clips and other standard framing hardware shall be ICBO approved, commercial quality, galvanized sheet steel or hot dipped galvanized, of the size shown on the plans.

Expansion anchors and powder driven anchors shall be as specified under "Building Miscellaneous Metal," in Section 12-5, "Metals," of these special provisions.

Nails: Nails shall conform to ASTM F 1667-95. "Common" nails shall conform to the following table:

Nail Size	Length (inches)	Diameter (inches)
8d	2½	0.131
10d	3	0.148
16d	3½	0.162

Building Paper: Building paper shall be kraft type waterproofing building paper, Type I (No. 15) asphalt saturated roofing felt or high density, bonded polyethylene fiber building paper.

Adhesive: Adhesive for plywood glue-nailed systems shall conform to APA Specification: AFG-01.

WOOD TREATMENT BY PRESSURE PROCESS

Preservative Treatment:

Preservative treatment shall be copper napthenate, pentachlorophenol or water-borne arsenicals (ACA, CCA or ACZA).

The following items shall be treated:

Wood cants, nailers, curbs, equipment support bases, blocking, stripping and similar members in connection with roofing, flashing, vapor barriers and waterproofing.

Wood sills, sleepers, blocking, furring and other similar members in contact with concrete or masonry.

All holes, daps and cut ends of treated lumber shall be thoroughly swabbed with 2 applications of copper napthenate.

Fire Retardant Treatment: Fire retardant treatment shall be paintable, odorless fire retardant preservative applied by pressure treating methods.

PART 3 - EXECUTION

INSTALLATION

Wood Framing:

Wood framing shall be in accordance with Chapter 23 of the California Building Code.

Framing members shall be of sizes and spacing shown on the plans. Unless otherwise shown on the plans, structural members shall not be spliced between supports.

Wood framing shall be accurately cut and assembled to provide closely fitted members. Framing shall be erected true to the lines and grades shown on the plans and shall be rigidly secured in place as shown and as required by recognized standards. Bracing shall be placed wherever necessary to support all loads on the structure during erection.

The size and spacing of fasteners and the edge distance for nails shall be as shown on the plans.

Nailing schedule shall be as shown on the plans and shall comply with the California Building Code.

Wall coverings exposed to the weather shall have a backing of building paper applied weatherboard fashion to the framing or sheathing. Backing shall be lapped 2 inches at horizontal joints, 6 inches at vertical joints and 12 inches at building corners.

Plywood Panels:

Plywood panels shall be attached to the framing as shown on the plans and these special provisions. All structural plywood sheathing (both roof and wall) shall be nailed with "Common" nails.

Plywood sheathing shall be nailed to the framing system and shall be continuous over 2 or more supports. Roof and floor panels shall be installed with the long dimension across the supports, with end joints staggered 4 feet. Wall sheathing shall have all edges blocked. Spacing between panels shall be 1/8 inch.

SECTION 12-7. THERMAL AND MOISTURE PROTECTION

12-7.01 PREPARATION FOR RE-ROOFING

PART 1 - GENERAL

SUMMARY

Scope: This work consists of the requirements for complete or partial roof tear-off where indicated and roof re-cover preparation as indicated on the plans and in these special provisions.

DEFINITIONS

Roofing Terminology: Refer to ASTM D 1079 and glossary in NRCA's "The NRCA Roofing and Waterproofing Manual" for definition of terms related to roofing work in this section.

Existing Membrane Roofing System: Built-up asphalt roofing membrane, surfacing, and components and accessories between deck and roofing membrane.

Roof Tear-Off: Removal of existing membrane roofing system from deck.

Remove: Detach items from existing construction and legally dispose of them off-site unless indicated to be removed and reinstalled.

Existing to Remain: Existing items of construction that are not indicated to be removed.

MATERIALS OWNERSHIP

Except for items or materials indicated to be reused, reinstalled, or otherwise indicated to remain Department's property, demolished materials shall become Contractor's property and shall be removed from State property.

SUBMITTALS

Provide submittals applicable to preparation for reroofing that meet the requirements of the indicated membrane roofing system specified in Section 12-7 "Thermal and Moisture Protection," of the Special Provisions.

QUALITY ASSURANCE

Regulatory Requirements: Preparation for reroofing shall conform to the applicable provisions of the California Code of Regulations (CCR), Title 24, Part 2, California Building Code, Appendix Chapter 15, "Reroofing," and Chapter 34, "Existing Structures."

Quality assurance for the reroofing work shall conform with the quality assurance requirements applicable to the indicated membrane roofing system specified in Section 12-7- "Thermal and Moisture Protection," of the Special Provisions.

PROJECT CONDITIONS

Protection: Protect building to be reroofed, adjacent buildings, walkways, site improvements, exterior plantings, and landscaping from damage or soiling from reroofing operations.

Limit construction loads on roof to rooftop equipment wheel loads and uniformly distributed loads.

Weather Limitations: Proceed with reroofing preparation only when existing and forecasted weather conditions permit work to proceed without water entering into existing roofing system or building.

PART 2 PRODUCTS

MATERIALS, EQUIPMENT, AND FACILITIES

General: Furnish all materials, tools, equipment, devices, appurtenances, facilities, and services as required to perform removal and roof tear-off work.

PART 3 - EXECUTION

PREPARATION

Coordinate with the Engineer to shut down air intake equipment in the vicinity of the work. Cover air intake louvers before proceeding with reroofing work that could affect indoor air quality or activate smoke detectors in the ductwork.

Verify that rooftop utilities and service piping have been shut off before beginning work.

ROOF TEAR-OFF

General: Remove existing roof system and associated components in their entirety down to existing plywood sheathing. Remove only as much roofing as can be recovered by the end of the work day, unless approved by the Engineer. Do not attempt to open the roof covering system in threatening weather. Reseal all openings prior to suspension of work the same day.

Temporary Roofing: Install temporary roofing and flashing as necessary to maintain a watertight condition throughout the course of the work. Remove temporary work prior to installation of permanent roof system materials unless approved by the Engineer.

DISPOSAL OF DEBRIS

Except for items or materials indicated to be reused, salvaged, reinstalled, or otherwise indicated to remain Department's property, remove demolished materials from the project site and legally dispose of them in an approved landfill.

Remove trash and debris from the site at frequent intervals so that their presence will not delay the progress of the work.

Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.

Remove debris from elevated portions of the building by chute, hoist, or other device that will convey debris to grade level in a controlled descent.

12-7.02 BUILT-UP ASPHALT ROOFING SYSTEM

PART 1 GENERAL

SUMMARY

Scope: This work consists of the requirements to furnish and install asphalt built-up roof covering system in accordance with the details shown on the plans and these special provisions.

Related Sections:

1. Metal roof penetration flashings, flashings, and counterflashings are specified under "Sheet Metal Flashing" in Section 12-7, "Thermal and Moisture Protection," of the Special Provisions.
2. Rough Carpentry for wood nailers, cants, curbs, and blocking are specified under "Rough Carpentry," in Section 12-6 "Wood and Plastics," of the Special Provisions.

DEFINITIONS

Roofing Terminology: Refer to ASTM D 1079 and glossary of NRCA's "The NRCA Roofing and Waterproofing Manual" for definition of terms related to roofing work in this Section.

Hot Roofing Asphalt: Roofing asphalt heated to its equiviscous temperature, the temperature at which its viscosity is 125 centipoise for mopping application and 75 centipoise for mechanical application, within a range of plus or minus 25 F, measured at the mop cart or mechanical spreader immediately before application.

ROOF SYSTEM DESCRIPTION

Roof System Description: Provide built-up bituminous composition roofing, base flashings, counter flashings, and flashings at metalwork and roof penetrations that remain watertight; do not permit the passage of water; and resist specified uplift pressures, thermally induced movement, and exposure to weather without failure.

1. Roofing system shall be a mineral-surfaced cap sheet built-up roofing, using glass fabric felts, as indicated.

Material Compatibility: Provide roofing materials that are compatible with one another under conditions of service and application required, as demonstrated by roofing manufacturer based on testing and field experience.

FMG Listing: Provide roofing membrane, base flashings, and component materials that comply with requirements in FMG 4450 and FMG 4470 as part of a roofing system and that are listed in FMG's "Approval Guide" for Class 1 or noncombustible construction, as applicable. Identify materials with FMG markings.

1. Fire/Windstorm Classification: Class 1A-90.

2. Hail Resistance: MH.

The Contractor and the roofing materials manufacturer shall determine the requirement or necessity for a vapor barrier or ventilating base sheet over the plywood sheathing or substrate, and provide such vapor barrier or ventilating base sheet as required to install a serviceable roof without defects and failures.

The Contractor and roofing materials manufacturer shall determine the probability of thermal and structural movement in the roofing system and provide manufacturer's standard expansion joints in the roofing system as required to provide a serviceable roof without failures.

SUBMITTALS

Shop Drawings and Product Data: Submit manufacturer's specifications for materials and installation of the appropriate roofing system and related flashings, including pertinent flashing details.

Samples: Submit sample square, 8 by 10 inches in size, of the mineral-surfaced cap sheet with manufacturer's standard colors for selection.

QUALITY ASSURANCE

Regulatory Requirements: California Code of Regulations (CCR), Title 24, Part 2, California Building Code, Chapter 15, "Roofs and Roof Structures."

Installer Qualifications: A qualified firm that is approved, authorized, or licensed by roofing system manufacturer to install manufacturer's product and that is eligible to receive manufacturer's warranty.

Manufacturer Qualifications: A qualified manufacturer that has FMG approval for roofing system identical to that used for this project.

Testing Agency Qualifications: An independent testing agency with the experience and capability to conduct the testing indicated, as documented according to ASTM E 548.

Source Limitations: Obtain components for roofing system from or approved by the roofing system manufacturer.

Fire-Test-Response Characteristics: Provide roofing materials with the fire-test-response characteristics indicated as determined by testing identical products per test method below by UL, FMG, or another testing and inspecting agency acceptable to authorities having jurisdiction. Materials shall be identified with appropriate markings of applicable testing and inspecting agency.

1. Exterior Fire-Test Exposure: Class A; ASTM E 108 (UL 90), for application and roof slopes indicated.

2. Fire-Resistance Ratings: ASTM E 119 (UL 263), for fire-resistance-rated roof assemblies of which roofing system is a part.

DELIVERY, STORAGE, AND HANDLING

Deliver roofing materials to Project site in original containers with seals unbroken and labeled with manufacturer's name, product brand name and type, date of manufacture, and directions for storage.

Store liquid materials in their original undamaged containers in a clean, dry, protected location and within the temperature range required by roofing system manufacturer. Protect stored liquid material from direct sunlight.

1. Discard and legally dispose of liquid material that cannot be applied within its stated shelf life.

Protect roof insulation materials from physical damage and from deterioration by sunlight, moisture, soiling, and other sources. Store in a dry location. Comply with insulation manufacturer's written instructions for handling, storing, and protecting during installation.

Handle and store roofing materials and place equipment in a manner to avoid permanent deflection of deck.

PROJECT CONDITIONS

Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit roofing system to be installed according to manufacturer's written instructions and warranty requirements.

WARRANTY

Special Warranty: In addition to the guaranty requirements specified in General Conditions, provide manufacturer's standard form, without monetary limitation, in which manufacturer agrees to repair or replace components of roofing system that fail in materials or workmanship within specified warranty period. Failure includes roof leaks and Bulging or wrinkling of built-up roof surfaces.

1. Special warranty includes roofing membrane, base flashings, roofing membrane accessories, roof insulation, fasteners, cover boards, substrate board, vapor retarder, and other components of roofing system.
2. Warranty Period: 15 years from date of project completion.

PART 2 PRODUCTS

BASE-SHEET MATERIALS

Vapor Barrier: As recommended by the roofing materials' manufacturer for the type of substrate.

Base Sheet: ASTM D 4601, Type II, nonperforated, asphalt-impregnated and coated, glass-fiber sheet, dusted with fine mineral surfacing on both sides.

Ventilating Base Sheet: ASTM D 4897, Type II, nonperforated, heavyweight, asphalt-impregnated and coated, glass-fiber base sheet with coarse granular surfacing or embossed venting channels on bottom surface.

ROOFING MEMBRANE PLIES

Ply Sheet: ASTM D 2178, Type IV, asphalt-impregnated, glass-fiber felt, as required to meet the requirements of the manufacturer's specifications approved for this work

Mineral-Surfaced Cap Sheet: ASTM D3909, asphalt-impregnated and coated, glass-fiber cap sheet, with coarse mineral-granule top surfacing and fine mineral surfacing on bottom surface as required to meet the requirements of the manufacturer's specifications approved for this work. Provide a minimum weight of 70 pounds per 108 square feet, in color as selected and approved by the Engineer from manufacturer's standards. Include loose, matching mineral granules for over-runs of lap cement or asphalt.

1. Lap Cement: ASTM D3019.

FLASHING MATERIALS

Composition Flashing System: Composition flashing system shall be by the same manufacturer as the roofing system, and shall be asphalt-impregnated and coated, glass-fiber sheet, dusted with fine mineral surfacing on both sides.

Flashing Cement: Bituminous product expressly recommended by the roofing materials manufacturer for flashing work on vertical surfaces, asphaltic flashing cement or flashing compound of troweling consistency.

Fabric Reinforcement: Asphalt-saturated cotton fabric, treated with asphaltic resin, meeting requirements of ASTM D173, or woven glass fabric, treated with asphalt resin, meeting requirements of ASTM D1668, as applicable.

Bituminous Plastic Cement: Asphaltic plastic cement, meeting requirements of ASTM D2822 or D4586.

ASPHALT MATERIALS

Asphalt Primer: ASTM D 41.

Roofing Asphalt: ASTM D 312, Type III or IV as recommended by built-up roofing system manufacturer for application.

AUXILIARY ROOFING MEMBRANE MATERIALS

General: Auxiliary materials recommended by roofing system manufacturer for intended use and compatible with built-up roofing.

Mastic Sealant: Polyisobutylene, plain or modified bitumen, nonhardening, nonmigrating, nonskinning, and nondrying.

Fasteners: Factory-coated steel fasteners and metal or plastic plates meeting corrosion-resistance provisions in FM 4470; designed for fastening roofing membrane components to substrate; tested by manufacturer for required pullout strength; and acceptable to roofing system manufacturer.

Metal Flashing Sheet: Metal flashing sheet is specified under "Sheet Metal Flashing" in Section 12-7 "Thermal and Moisture Protection," of the Special Provisions.

ROOF INSULATION

General: Provide preformed roof insulation boards that comply with requirements and referenced standards, selected from manufacturer's standard sizes and thicknesses, with a minimum R-value of 30.

Polyisocyanurate Board Insulation: ASTM C 1289, Type II, felt or glass-fiber mat facer on both major surfaces.

Provide preformed saddles, crickets, tapered edge strips, and other insulation shapes where indicated for sloping to drain. Fabricate to slope of 1/4 inch per 12 inches (1:48), unless otherwise indicated.

INSULATION ACCESSORIES

General: Roof insulation accessories recommended by insulation manufacturer for intended use and compatible with membrane roofing.

Fasteners: Factory-coated steel fasteners and metal or plastic plates meeting corrosion-resistance provisions in FMG 4470, designed for fastening roof insulation to substrate, and acceptable to roofing system manufacturer.

Cold Fluid-Applied Adhesive: Manufacturer's standard cold fluid-applied adhesive formulated to adhere roof insulation to substrate.

Insulation Cant Strips: Preformed cants of sizes or dimensions indicated, 45-degree slope, manufactured of compressed fiberglass or perlite board, or fabricated of pressure-treated Douglas fir with preservative, "Construction" or "No. 1" grade.

Wood Nailer Strips: Comply with requirements specified under "Rough Carpentry" in Section 12-6 "Wood and Plastics," of the Special Provisions.

Tapered Edge Strips: ASTM C 728, perlite insulation board.

Cover Board: ASTM C 1177/C 1177M, glass-mat, water-resistant gypsum substrate, Type X, 5/8 inch thick.

Substrate Joint Tape: 6- or 8-inch- wide, coated glass-fiber joint tape.

WALKWAYS

Walkway Pads: Mineral-granule-surfaced, reinforced asphaltic composition, slip-resisting pads, manufactured as a traffic pad for foot traffic and acceptable to roofing system manufacturer, 3/4 inch thick, minimum.

PART 3 EXECUTION

EXAMINATION

Examine substrates, areas, and conditions, with Installer present, for compliance with the following requirements and other conditions affecting performance of roofing system:

1. Verify that roof openings and penetrations are in place and set and braced and that roof drains are securely clamped in place.
2. Verify that wood cants, blocking, curbs, and nailers are securely anchored to plywood sheathing at penetrations and terminations and that nailers match thicknesses of insulation.

PREPARATION

Clean substrate of dust, debris, moisture, and other substances detrimental to roofing installation according to roofing system manufacturer's written instructions. Remove sharp projections.

Prevent materials from entering and clogging roof drains and conductors and from spilling or migrating onto surfaces of other construction. Remove roof-drain plugs when no work is taking place or when rain is forecast.

INSULATION AND INSTALLATION

Coordinate installing roofing system components so insulation is not exposed to precipitation or left exposed at the end of the workday.

Comply with roofing system manufacturer's written instructions for installing roof insulation.

Insulation Cant Strips: Install and secure preformed 45-degree insulation cant strips at junctures of built-up roofing membrane system with vertical surfaces or angle changes greater than 45 degrees.

Install tapered insulation under area of roofing to conform to slopes indicated.

Install insulation with long joints of insulation in a continuous straight line with end joints staggered between rows, abutting edges and ends between boards. Fill gaps exceeding 1/4 inch with insulation.

1. Cut and fit insulation within 1/4 inch of nailers, projections, and penetrations.

Install one or more layers of insulation under area of roofing to achieve required R-Value. Where overall insulation thickness is 2 inches or greater, install 2 or more layers with joints of each succeeding layer staggered from joints of previous layer a minimum of 6 inches in each direction.

Trim surface of insulation where necessary at roof drains so completed surface is flush and does not restrict flow of water.

Install tapered edge strips at perimeter edges of roof that do not terminate at vertical surfaces.

Mechanically Fastened Insulation: Install each layer of insulation and secure to deck using mechanical fasteners specifically designed and sized for fastening specified board-type roof insulation to deck type.

1. Fasten insulation according to requirements in FMG's "Approval Guide" for specified Windstorm Resistance Classification.

Install cover boards over insulation with long joints in continuous straight lines with end joints staggered between rows. Stagger joints from joints in insulation below a minimum of 6 inches in each direction. Loosely butt cover boards together and fasten to plywood sheathing. Tape joints if required by roofing system manufacturer.

1. Fasten according to requirements in FMG's "Approval Guide" for specified Windstorm Resistance Classification.

ROOFING MEMBRANE INSTALLATION, GENERAL

Install built-up roofing membrane system according to roofing system manufacturer's written instructions and applicable recommendations of ARMA/NRCA's "Quality Control Guidelines for the Application of Built-up Roofing."

Start installation of built-up roofing membrane in presence of roofing system manufacturer's technical personnel.

Cooperate with testing and inspecting agencies engaged or required to perform services for installing built-up roofing system.

Coordinate installing roofing system components so insulation and roofing membrane sheets are not exposed to precipitation or left exposed at the end of the workday or when rain is forecast.

1. Provide tie-offs at end of each day's work to cover exposed roofing membrane sheets and insulation with a course of coated felt set in roofing cement or hot roofing asphalt with joints and edges sealed.
2. Complete terminations and base flashings and provide temporary seals to prevent water from entering completed sections of roofing system.
3. Remove and discard temporary seals before beginning work on adjoining roofing.

Asphalt Heating: Heat roofing asphalt and apply within plus or minus 25 F of equiviscous temperature unless otherwise required by roofing system manufacturer. Do not raise roofing asphalt temperature above equiviscous temperature range more than one hour before time of application. Do not exceed roofing asphalt manufacturer's recommended temperature limits during roofing asphalt heating. Do not heat roofing asphalt within 25 F of flash point. Discard roofing asphalt maintained at a temperature exceeding finished blowing temperature for more than 4 hours.

ROOFING MEMBRANE INSTALLATION

Install indicated number of ply sheets starting at low point of roofing system. Align ply sheets without stretching. Shingle side laps of ply sheets uniformly to achieve required number of plies throughout thickness of roofing membrane. Shingle in direction to shed water. Extend ply sheets over and terminate beyond cants.

1. Embed each ply sheet in a solid mopping of hot roofing asphalt applied at rate required by roofing system manufacturer, to form a uniform membrane without ply sheets touching.

Cap Sheet: Install lapped granulated cap sheet starting at low point of roofing system. Offset laps from laps of preceding ply sheets and align cap sheet without stretching. Lap in direction to shed water. Extend cap sheet over and terminate beyond cants.

1. Embed cap sheet in a solid mopping of hot roofing asphalt applied at rate required by roofing system manufacturer.

FLASHING AND STRIPPING INSTALLATION

Install base flashing over cant strips and other sloping and vertical surfaces, at roof edges, and at penetrations through roof, and secure to substrates according to roofing system manufacturer's written instructions and as follows:

1. Backer Sheet Application: Mechanically fasten backer sheet to walls or parapets. Adhere backer sheet over roofing membrane at cants in a solid mopping of hot roofing asphalt.
2. Flashing Sheet Application: Adhere flashing sheet to substrate in a solid mopping of hot roofing asphalt applied at not less than 425 F. Apply hot roofing asphalt to back of flashing sheet if recommended by roofing system manufacturer.

WALKWAY INSTALLATION

Walkway Pads: Install walkway pads using units of size indicated according to walkway pad manufacturer's written instructions.

FIELD QUALITY CONTROL

Testing Agency: Engage a qualified independent testing and inspecting agency to perform roof tests and inspections and to prepare test reports.

Test Cuts: Before flood coating and surfacing built-up roofing membrane, test specimens shall be removed to evaluate problems observed during quality-assurance inspections of roofing membrane as follows:

1. Approximate quantities of components within roofing membrane shall be determined according to ASTM D 3617.
2. Test specimens will be examined for interply voids according to ASTM D 3617 and to comply with criteria established in Appendix 3 of ARMA/NRCA's "Quality Control Guidelines for the Application of Built-up Roofing."

Final Roof Inspection: Arrange for roofing system manufacturer's technical personnel to inspect roofing installation on completion and submit report to the Engineer. Notify the Engineer 48 hours in advance of date and time of inspection.

Repair or remove and replace components of roofing system where test results or inspections indicate that they do not comply with specified requirements.

Additional testing and inspecting, at Contractor's expense, shall be performed to determine compliance of replaced or additional work with specified requirements.

PROTECTING AND CLEANING

Protect roofing system from damage and wear during remainder of construction period. When remaining construction will not affect or endanger roofing, inspect roofing for deterioration and damage, describing its nature and extent in a written report, with copies to the Engineer.

Correct deficiencies in or remove roofing system that does not comply with requirements, repair substrates, and repair or reinstall roofing system to a condition free of damage and deterioration at time of project completion and according to warranty requirements.

Clean overspray and spillage from adjacent construction using cleaning agents and procedures recommended by manufacturer of affected construction.

12-7.03 SHEET METAL FLASHING

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of fabricating, furnishing and installing sheet metal flashing in accordance with the details shown on the plans and these special provisions.

Sheet metal shall include metal flashings and counterflashings.

Alternatives: Premolded roof flashings may be used in lieu of sheet metal flashings where shown on the plans.

QUALITY ASSURANCE

Codes and Standards: Sheet metal work shall in accordance with the requirements in the latest edition of the Sheet Metal and Air Conditioning Contractors National Association (SMACNA) "Standard Practice in Architectural Sheet Metal Work."

PART 2 - PRODUCTS

MATERIALS

Galvanized Sheet Steel: Galvanized sheet steel shall conform to ASTM Designation: A 653/A 653M with G 90 [Z275] coating, not less than 24-gage, unless otherwise shown on the plans. Surfaces to be painted shall not have factory coatings on galvanizing that cannot be removed by paint thinner.

Hardware and Fastenings: Hardware and fastening for premolded roof flashings shall be stainless steel.

Solder: Solder shall conform to ASTM Designation: B 32, Alloy Grade Sn50.

Soldering Flux: Soldering flux shall be acid type, conforming to Federal Specification: O-F-506C, Type I, Form A.

Insect Screen: Insect screen shall be industrial wire cloth and screen, medium grade, 18 mesh, 0.017-inch diameter, 0.039-inch openings, plain weave, galvanized steel conforming to ASTM Designation: E 437.

Lap Joint Sealant: Lap joint sealant for concealed locations shall be a non-drying butyl.

Flashing Cement: Flashing cement shall be a bituminous plastic cement, asbestos free, conforming to ASTM Designation: D 4586, Type II.

Sealant: Sealant for exposed locations shall be a silicone sealant conforming to ASTM Designation: C 920.

Primer: Primer shall be as recommended by the sealant manufacturer.

Coal Tar Paint: Coal tar paint shall be coal-tar epoxy coating conforming to U.S. Corps of Engineers Specification: C-200 or Steel Structures Painting Council Paint Specification: SSPC-16-68T.

FABRICATION

Sheet metal shall be assembled to Sheet Metal and Air Conditioning Contractors National Association Standards.

Sheet metal shall be formed to the sizes, shapes and dimensions shown on the plans or as specified herein with angles and lines straight, sharp and in true alignment. The number of joints shall be kept to a minimum.

Angle bends and folds for interlocking the metal shall be made with full regard for expansion and contraction to avoid buckling or fullness in the metal after it is installed.

Joints in sheet metal work shall be closed watertight unless slip joints are specifically required. Watertight joints shall be mechanically interlocked and then thoroughly soldered for metals other than aluminum. Watertight joints in aluminum or between aluminum and other metals shall be sealed with acrylic sealant.

Sheet metal joints to be soldered shall be cleaned with steel wool or other means, pre-tinned and soldered watertight.

All joints shall be wiped clean of flux after soldering. Acid flux shall be neutralized by washing the joints with sodium bicarbonate.

Flashings shall have a 45 degree drip return at bottom edges. Unless otherwise shown on the plans, counterflashing shall extend not less than 4 inches over roofing or other materials protected by the counterflashing and shall be arranged so that roofing or materials can be repaired without damage to the counterflashing. Where reglets are indicated, counterflashing shall be fastened by lead wedges or snap-in flashing.

PART 3 - EXECUTION

Preparation: Surfaces to receive sheet metal shall be clean, smooth and free from defects.

Protection: Aluminum surfaces to be in contact with concrete, mortar, or dissimilar metals shall be given a heavy coat of coal tar paint.

INSTALLATION

Roof Penetration Flashings:

All pipes, ducts, vents and flues passing through roofs shall be made waterproof with flashings of storm collars or counterflashings.

Roof penetration flashings shall be fabricated from galvanized sheet steel, not less than 24-gage.

On built-up roofing, 2 flashings shall be furnished for each pipe, vent or flue through roof. Flashings shall be constructed so that the lower flashing shall sit directly on the roof deck, with the top flashing set over it on top of the roof felts.

The lower flashing shall be galvanized sheet metal, 24-gage, and extend 6 inches minimum from outside of the pipe in all directions and 1½ inches above the top of the roofing.

The top flashing shall be galvanized sheet steel as shown on the plans.

Premolded Roof Flashings: Premolded roof flashings shall be installed in accordance with the manufacturer's instructions.

After metal work is completed and watertight, flashings shall be covered by one of the following methods:

1. The top of the stop flanges and inside the upstanding lip at the joints shall be cleaned with an acid etching detergent, rinsed and dried. A ½-inch thick coat of plastic cement shall be applied on the roof flange and onto the roofing at least 4 inches wide. A ½-inch thick coat of plastic cement shall be applied 4 inches wide on the upstanding lip at the joints.
2. A hot mopping of roofing asphalt or a uniform coating of plastic cement shall be applied, over which shall be laid Type IV asphalt saturated felt strips, 10 inches and 13 inches wide, in 2 layers over the flange of the stops feathered out onto the roofing.

12-7.04 JOINT SEALANT

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of preparing and placing a joint sealant in accordance with the details shown on the plans and these special provisions.

The sealed joint shall consist of tempered hardboard, expanded polystyrene and a pourable joint seal.

SUBMITTALS

Product Data: Manufacturer's descriptive data, specifications and installation instructions shall be submitted to the Engineer at the jobsite for approval.

PART 2 - PRODUCTS

Tempered Hardboard: Tempered hardboard shall be 1/8-inch minimum thickness, commercial quality suitable for the use intended. Other facing materials may be used provided they furnish equivalent protection.

Expanded Polystyrene: Expanded polystyrene shall be commercially available polystyrene board.

Polyethylene Foam: Polyethylene foam shall be commercial quality, with a continuous, impervious, glazed top surface, suitable for retaining the liquid sealant in the joint while hardening.

Primer: Primer shall be as recommended by the sealant manufacturer.

Joint Sealant: Joint sealant shall be a commercial quality, 2 component polyurethane sealant, which shall be self-levelling and withstand up to 25 percent movement.

PART 3 - EXECUTION

PREPARATION

Forming:

Groove for joint seal shall be formed to a uniform width and depth and to the alignment shown on the plans or as ordered by the Engineer. The completed groove shall have a top width within 1/8 inch of the width shown on the plans and the bottom width shall not vary from the top width by more than 1/16 inch.

At least 24 hours prior to installing the joint seal, the Contractor shall repair all spalls, fractures, breaks, or voids in the concrete surfaces of the joint groove.

The lip of the joint shall be beveled by grinding as shown on the plans.

Cleaning:

Prior to sealing joints, expanded polystyrene, hardboard, concrete spillage and all foreign material shall be removed from the deck to the bottom of the formed joint.

Prior to placing the joint seal, the joint shall be cleaned by a method which shall include abrasive blast cleaning and then be cleaned with a high pressure air jets to remove all residue and foreign material.

INSTALLATION

Materials:

No material shall be used which has skinned over or which has settled in the container to the extent that it cannot be easily redispersed by hand stirring to form a smooth uniform product.

Each container of material shall be clearly labeled or each delivery of material in the tanks of 2-component equipment shall be accompanied with a ticket showing designation (Component A or B), the manufacturer's name, lot or batch number, date of manufacture, date of packaging, and date, if any, beyond which the sealant shall not be used.

Primer: A primer shall be applied to the sides of the groove and all exposed vertical surfaces in the joint prior to placing the sealant. Primer shall be dry at the time of placing the sealant. Contaminated primer shall be removed and replaced.

Joint Sealant: The 2-component sealant shall be mixed and placed in the groove in accordance with manufacturer's instructions. Unmixed liquid components which have been exposed to the atmosphere for more than 24 hours, shall not be used.

12-7.05 SEALANTS AND CAULKING

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and applying sealants and caulking which are required for this project, but not specified elsewhere, in accordance with the details shown on the plans and these special provisions.

Related Work: Pourable polyurethane joint sealant shall conform to the requirements under "Joint Sealant" elsewhere in this Section 12-7.

QUALITY ASSURANCE

Certificates of Compliance: Certificates of compliance shall be furnished for the sealants and caulking in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

SUBMITTALS

Product Data: Manufacturer's descriptive data and installation instructions for all sealants shall be submitted for approval.

Samples: Color samples of all sealants shall be submitted for approval. Unless otherwise shown on the plans, colors will be selected by the Engineer from the manufacturer's standard colors.

PART 2 - PRODUCTS

MATERIALS

All sealants, primers and accessories shall be non-staining to adjacent exposed surfaces. Products having similar applications and usage shall be of the same type and same manufacturer. Gun consistency compound shall be used unless otherwise required by the job conditions.

Acrylic Sealant: Acrylic sealant shall be one compound, solvent release acrylic sealant.

Butyl Sealant: Butyl sealant shall be one component, skinning type.

Silicone Sealant: Silicone sealant shall be one component, low modulus building sealant. Sealant shall be tack-free in one hour, shall not sag or flow, shall be ozone resistant and capable of 100 percent extension without failure.

Joint Sealant: Joint sealant shall be a two-part, non sag polysulfide base, synthetic rubber sealant formulated from liquid polysulfide polymer.

Backer Rod: Backer rod shall be round, open or closed cell polyurethane. Backer rod shall be sized such that it must be compressed between 25 percent and 75 percent of its uncompressed diameter during installation in the joint.

Neoprene: Neoprene shall conform to the requirements of ASTM Designation: C 542.

PART 3 - EXECUTION

APPLICATION

Unless otherwise shown on the plans, sealants shall be applied in accordance with the manufacturer's instructions.

Silicone sealants shall not be used in locations where painting is required.

Butyl sealants shall not be used in exterior applications, and acrylic sealants shall not be used in interior applications.

Sealants shall be applied in a continuous operation for the full length of the joint. Immediately following the application of the sealant, the sealant shall be tooled smooth using a tool similar to that used to produce concave masonry joints. Following tooling, the sealant shall remain undisturbed for not less than 48 hours.

SECTION 12-8. DOORS AND WINDOWS

12-8.01 HINGED DOORS

PART 1 – GENERAL

Scope: This work shall consist of furnishing and installing hinged doors in accordance with the details shown on the plans and these special provisions.

SUBMITTALS

Manufacturer's descriptive data, installation instructions for fire rated assemblies and a door schedule shall be submitted for approval. The door schedule shall include a description of the type, location and size of each door.

PART 2 - PRODUCTS

Wood Door:

Wood door shall be Woodwork Institute of California (WIC) "Custom" grade flush, hollow or solid core wood doors as shown on the plans. Face shall be paint grade hardwood veneer except as otherwise shown on the plans. Doors shall bear the WIC quality grade mark or shall be accompanied by a Certificate of Compliance certifying compliance with the WIC quality specified herein. Certificates of Compliance shall be in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

Where fire rated doors are required, solid core doors shall be listed and labeled for the fire rating shown on the plans.

Sealants: Sealants shall be ultraviolet and ozone resistant, gun grade polysulfide or polyurethane, multicomponent, Federal Specification: TT-S-227.

PART 3 - EXECUTION

INSTALLATION

Doors shall be installed rigidly, securely, plumb and true and in such a manner that the doors operate freely without rubbing or binding. Clearance between frame and door shall be not more than 1/8 inch. The exterior frame shall be sealed weathertight.

Painting: Except for the primer application specified herein, doors and frames shall be cleaned, prepared and painted in accordance with the requirements specified under "Painting" in Section 12-9, "Finishes," of these special provisions.

12-8.02 GLAZING

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing glazing in accordance with the details shown on the plans and these special provisions.

Glazing shall consist of acrylic sheets for display cases.

All acrylic sheets shall conform to ASTM Designation: D 702, Type III, Grade 3.

SUBMITTALS

A detailed list of glazing materials including acrylic sheet and sealants shall be submitted for approval.

PART 2 - PRODUCTS

Acrylic Plastic Sheet: Acrylic plastic sheet shall be cast acrylic substrate with crosslinked fluorocarbon copolymer surface coating; 93 percent luminous transmission and 0.5 percent haze as determined by ASTM Designation: D 1003.

PART 3 - EXECUTION

INSTALLATION

Glazing shall conform to the general conditions and applicable details in the publications of the Flat Glass Marketing Association.

Panes shall be bedded fully and evenly, set straight and square within panels in such a manner that the pane is entirely free of any contact with metal edges and surfaces.

Panes in assemblies using extruded gasket glazing shall be set in accordance with the assembly manufacturer's instructions using gaskets and stops supplied by the manufacturer.

REPLACEMENT AND CLEANING

Panes shall be kept clean of cement and plaster products, cleansers, sealants, tapes and all other foreign material that may cause discoloration, etching, staining, or surface blemishes to the materials.

Solvents and cleaning compounds shall be chemically compatible with materials, coatings and glazing compounds to remain. Cleaners shall not have abrasives that scratch or mar the surfaces.

The protective covering on acrylic sheet surfaces shall be left until construction is completed or 2 weeks after glazing, whichever is shorter. The covering shall be removed before adhesives dry sufficiently to adhere to the sheet during removal rather than the protective membrane.

Acrylic sheets shall be protected against scuffs, scratches and marring of the surface during construction and any such damaged sheet shall be replaced or restored to like new condition. Restoration work shall conform to the manufacturer's recommendations.

All panes shall be cleaned just before the final inspection. All stains and defects shall be removed. Paint, dirt, stains, labels (except etched labels), and surplus glazing compound shall be removed without scratching or marring the surface of the panes or metal work.

SECTION 12-9. FINISHES

12-9.01 CERAMIC AND QUARRY TILE

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing ceramic and quarry tile in accordance with the details shown on the plans and these special provisions.

Ceramic tile shall include glazed wall tile, patterned porcelain tile, matte porcelain tile, textured porcelain tile, polished porcelain tile, trim tile, setting materials, grouts and such other materials as may be required for a complete installation.

SUBMITTALS

Product Data:

Manufacturer's descriptive data, a list of materials to be used, color selections, and installation instructions for all materials required for the work shall be submitted for approval.

Manufacturer's descriptive data shall be submitted for each type of tile, mortar bed materials, bond coat materials and additives, and grout materials and additives.

Materials list and installation instructions shall include all products and materials to be incorporated into the work.

Friction reports shall be submitted for tile products to be used on floors and other pedestrian surfaces.

Samples: Samples shall include 2 individual samples of each type and color of tile and trim to be installed and shall be of the same size, shape, pattern and finish as the tile and trim to be installed.

QUALITY ASSURANCE

Single Source Responsibility: Each type and color of tile, grout and setting materials shall be obtained from a single source.

Master Grade Certificates: Each shipment of tile to the project site shall be accompanied by a Master Grade Certificate issued by the tile manufacturer.

Certificates of Compliance: Certificates of compliance shall be furnished for bond coat materials, setting bed materials and grout in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

DELIVERY, STORAGE AND HANDLING

Delivery: Tile and packaged materials shall be delivered to the job site in sealed, unbroken, unopened containers with the labels intact. Tile containers shall bear the Standard Grade label.

Storage and Handling: Materials shall be stored and handled in such a manner as to prevent damage or contamination by water, freezing or foreign matter.

PROJECT CONDITIONS

Protection: Tile work shall be protected and environmental conditions maintained during and after installation to comply with the reference standards and manufacturer's printed instructions.

Temperatures:

Unless otherwise specified in the manufacturer's installation instructions, the ambient temperature shall be maintained at not less than 50°F nor more than 100°F in tiled areas during installation and for 7 days after completion. Exterior work areas shall be shaded from direct sunlight during installation.

Tile shall not be installed when the temperature of the substrate is greater than 90°F or is frost covered.

Illumination: Interior work areas shall be illuminated to provide the same level and angle of illumination as will be available during final inspection.

PART 2 - PRODUCTS

MANUFACTURERS

Available Manufacturers: Subject to compliance with the specifications, tile shall be American Olean Tile Co., Inc.; Summitville Tiles, Inc.; United States Ceramic Tile Co.; or equal.

GENERAL

Ceramic Tile:

Ceramic tile shall conform to the requirements in ANSI Standard: A137.1, "American National Standard Specifications for Ceramic Tile" for types and grades of tile indicated.

Ceramic tile shall conform to the "Standard Grade" requirements.

Tile Installation Materials: Tile installation materials shall conform to the requirements in ANSI standard referenced with products and materials indicated for setting and grouting.

Tile Color and Size: Tile color shall be as shown on the plans; tile size shall be as indicated in the Schedule elsewhere in this special provision.

Slip Resistant Tile: Slip resistant tile shall have sufficient abrasives added such that the static coefficient of friction, wet or dry, shall be not less than 0.6 for walking surfaces and 0.8 for ramps when tested in accordance with ASTM Designation: C 1028.

TILE PRODUCTS

Glazed Wall Tile:

Glazed wall tile shall be machine made, dust pressed white body clay, and shall have a glossy glaze finish, plain face, and cushion edges. Tile shall be 5/16-inch nominal thickness.

Ceramic tile trim shall match material, size and finish of field tile. Free edges of tiled areas of walls shall have bullnose type trim. Outside corners shall have bullnose type runner trim (not beads). Reentrant corners shall have cove type trim.

Matte Porcelain Tile:

Matte porcelain tile shall be machine made, unpolished, dust pressed natural porcelain clay and shall have a plain face. Tile shall have a nominal thickness of 5/16 inch. Matte porcelain tile shall be slip resistant.

Matte porcelain trim tile shall include cove type base at walls and single piece intersecting cove base at corners.

Polished Porcelain Tile: Polished porcelain tile shall be machine made, dust pressed natural porcelain clay. Tile shall have less than 0.5 percent water absorption and be suitable for exterior use. Tile shall have a glossy polished finish and plain face. Tiles shall have a nominal thickness of not less than 5/16 inch.

SETTING MATERIALS

Portland Cement Mortar Installation Materials: Materials for portland cement mortar installation shall conform to the requirements in ANSI Standard: A108.1 as required for installation method designated, unless otherwise indicated.

Membrane: Membrane shall be asphalt impregnated felt conforming to ASTM Designation: D 226, Type I, or polyethylene film conforming to ASTM Designation: C 171, Type 1.1.2. Polyethylene film shall not be less than 4 mils thick.

Reinforcement: Reinforcement shall be galvanized welded wire fabric with 2" x 2"-W0.3 x W0.3 conforming to ASTM Designations: A 82 and A 185 except for minimum wire size. Reinforcement shall be provided in flat sheets.

Metal Lath: Metal lath shall be self furring, galvanized, conforming to ASTM Designation: C 847, flat expanded type weighing not less than 2.5 pounds per square yard. Factory assembled metal lath and paper backing may be used where reinforcement over paper is shown on the plans.

Tile Bond Coat:

Tile bond coat shall be latex-portland cement bond coat.

Latex-portland cement mortar bond coat shall be a prepackaged mortar mix, conforming to ANSI Standard: A118.4, incorporating a dry acrylic resin, and to which only water is added at the job site. Mortar shall be suitable for exterior use and be labeled for the type of tile to be installed.

Epoxy Bond Coat: Epoxy bond coat shall be a 2 part prepackaged epoxy mortar conforming to ANSI Standard: A118.3, suitable for exterior use. Mortar shall be labeled for the type of tile to be installed.

GROUTING MATERIALS

Tile Grout:

Tile grout shall be latex-portland cement grout.

Latex-portland cement grout shall be a prepackaged grout mix, conforming to ANSI Standard: A118.6, incorporating a dry acrylic resin, and to which only water is added at the jobsite. Grout shall be suitable for exterior use and labeled for the type of tile to be installed.

Epoxy Grout: Epoxy grout shall be a 2 part prepackaged epoxy grout conforming to ANSI Standard: A118.3 and suitable for exterior use. Grout shall be labeled for the type of tile to be used.

Grout Pigment: Grout pigment shall be chemically inert, fade resistant mineral oxide or synthetic type.

SEALANTS

Sealant:

Sealant for vertical expansion joints shall be a medium modulus silicone or polyurethane. Sealant for horizontal joints shall be a 2-part polyurethane type material with a Shore Hardness of 35 to 45.

Color of exposed sealants shall match color of grout in tile adjoining sealed joints.

MORTAR BEDS

Cement Mortar Bed:

Cement mortar bed for walls shall be proportioned of one part cement, ½ part hydrated lime, 6 parts damp sand by volume and only enough water to provide the necessary workability. Ingredients shall be dry mixed, water added, and materials blended to produce a stiff mix. Mortar bed shall be not less than ¾ inch in thickness.

Cement mortar bed for floors shall be proportioned of one part cement, 1/10 parts hydrated lime, 5 parts damp sand by volume and only enough water added to provide the necessary workability. Ingredients shall be dry mixed, water added, and materials blended to produce a stiff mix. Mortar bed shall be not less than 1¼ inches in thickness.

MISCELLANEOUS MATERIALS

Sand: Sand shall be a natural or manufactured sand conforming to ASTM Designation: C 144, except that no more than 10 percent shall pass the No. 100 sieve.

Sealers:

Sealer for unglazed quarry tile shall be water repellent, clear solution of ammonium cementitious compound, silicone base material, or other commercially manufactured sealer.

Sealer for grout shall be a penetrating proprietary compound designed for sealing grout. Silicone sealers shall not be used.

Cement: Cement shall conform to ASTM Designation: C 150, Type I.

Hydrated Lime: Hydrated lime shall conform to ASTM Designation: C 206, Type S, or ASTM Designation: C 207, Type S.

Water: Water shall be clean and potable.

Metal Edge Strips: Metal edge strips shall be stainless steel terrazzo strips, 1/8 inch wide at top edge with integral provision for anchorage to mortar bed or substrate.

Marble Thresholds:

Marble thresholds shall conform to the requirements in ASTM Designation: C 503 for exterior use and abrasion resistance for use in areas subject to heavy foot traffic.

Marble threshold shall be uniform in color and finish and fabricated to sizes and profiles shown on the plans or required to provide a smooth transition between tile surfaces and adjoining finished floor surfaces.

Cementitious Tile Backer Board: Cementitious backer board shall be a backing and underlayment panel composed of a concrete core with fiberglass mesh reinforcing on both faces and conforming to the requirements of ANSI Standard: A118.9.

MIXING MORTAR AND GROUT

Mixing: Mortar and grout shall be mixed to comply with the requirements of referenced standards and manufacturers for accurately proportioning of materials, water or additive content, mixing equipment and mixer speeds, mixing containers, mixing time, and other procedures need to produce mortars and grout of uniform quality with optimum performance characteristics for application intended.

PART 3 - EXECUTION

PREPARATION

Concrete, mortar, or masonry substrate surfaces which are to receive a mortar bed shall not vary more than ¼ inch in 8 feet from the required plane and shall be true, plumb at vertical surfaces, and square at intersection edges.

Surfaces to receive a mortar setting bed or a bond coat shall be cleaned adequately to assure a tight bond to the applied material. Such cleaning shall leave the surface thoroughly roughened and free from laitance, coatings, oil, sand, dust and loose particles.

The cleaned surfaces which are to receive a mortar bed shall be saturated with water just prior to placing mortar or the cleaned surfaces shall be coated with fresh neat cement slurry. If the surface is saturated with water, excess water shall be removed and the wetted surfaces uniformly dusted with portland cement. The slurry or wetted cement dust shall be broomed to completely coat the surface with a thin and uniform coating just prior to placing the mortar.

Substrates shall be inspected to insure that grounds, anchors, plugs, recessed frames, bucks, drains, electrical work, mechanical work, and similar items in or behind the tile have been installed before proceeding with installation of the tiles.

INSTALLATION

Tile installation shall conform to applicable parts of ANSI 108 Series of the tile installation standards included under "American National Standard Specifications for the Installation of Ceramic Tile" and Tile Council of American, "Handbook for Ceramic Tile Installation."

All tile shall be installed on a bond coat over a setting bed. The setting bed shall be a cured cement mortar bed or a prepared, dimensionally stable substrate of concrete, masonry, cementitious backer board, or other cementitious material.

The back face of the tile shall be free of paper, adhesives, fiber mesh, resins, or other materials affecting the bond of the tile to the bedding material.

Tile sheets shall have permanent edge bonding or temporary mounting materials on the exposed face. Water soluble or absorbent adhesives shall not be used for edge bonding. Temporary mounting materials shall allow observation during tile setting operations.

Tile work shall extend into recesses and under or behind equipment and fixtures, to form a complete covering without interruptions, except as shown on the plans. Work shall be terminated neatly at obstructions, edges and corners without disrupting pattern or joint alignments.

Intersections and returns shall be accurately formed. Cutting and drilling of tile shall be performed without marring visible surfaces. Cut edges of tile abutting trim, finish or built-in items shall be carefully ground to produce straight aligned joints. Tile shall be closely fit to electrical outlets, piping, fixtures and other penetrations such that plates, collars, or covers overlap the tile.

Mortar Bed Placement:

The mortar bed, with or without reinforcement as shown on the plans, shall be placed, consolidated, and finished to the required thickness.

The surface of the mortar bed shall be true and pitched as shown on the plans, without high or low spots. The mortar bed surface shall not vary more than 1/8 inch in 8 feet from a plane parallel to the finished tile surface when tile is installed on a cured mortar bed.

In no case shall the allowed tolerances result in offsets between adjoining tiles, low spots on finished tile surfaces than can pond water, or finished tile surfaces that are not plumb or not true.

Pea gravel mortar shall be tightly compacted so as to fill all voids in the aggregate. Compaction shall be obtained using a stand-up wooden tamper weighing not less than 35 pounds or using a motor driven tamper and leveler.

Pea gravel mortar beds shall be damp cured under cover for not less than 72 hours at a temperature of not less than 70°F.

Cement mortar beds to receive a tile bond coat shall be damp cured under cover for a minimum of 48 hours at a temperature of not less than 70°F.

Cement mortar beds to receive an epoxy bond coat shall be damp cured under cover for a minimum of 96 hours at a temperature of not less than 70°F and allowed to dry thoroughly prior to setting tile.

Cementitious Backer Board: Cementitious backer board shall be installed in accordance with the provisions of ANSI Standard: A118.11.

Tile Bond Coat:

The tile bond coat mortar shall be mixed according to the manufacturer's recommendations. The consistency of the mixture shall be such that ridges formed with the recommended notched trowel shall not flow or slump. Reworking will be allowed provided no water or materials are added. The setting bed surfaces shall be dampened before placing the bond coat as necessary tile installation, but the setting bed shall not be soaked. The setting bed surfaces for epoxy bond coat shall be dry.

The bond coat shall be floated onto the cured mortar bed surface with sufficient pressure to cover the surface evenly with no bare spots. The surface area to be covered with the bond coat shall be no greater than the area that can be tiled while the bond coat is still plastic. The bond coat shall be combed with a notched trowel as recommended by the manufacturer within 10 minutes before installing tile. Tile shall not be installed on a skinned over bond coat.

Installing Tiles:

Tile shall be installed in accordance with the manufacturer's instructions and shall be set solid and shall be well bonded to the substrate.

Tile set on a tile bond coat shall be installed in accordance with ANSI Standard: A108.5, and tile set on an epoxy mortar shall be installed in accordance with ANSI Standard: A108.6.

If tiles are cut, the cuts shall be made with saws. Cut edges shall be rubbed with an abrasive stone to bring the edge of the glaze slightly back from the body of the tile. Cuts shall be accurately made to neatly fit the tile in place. Cut edges shall not be butted against other tile. Cut tile shall be at least half the size of a full size tile.

Tile shall completely cover wall areas behind mirrors and fixtures.

Tile shall be installed so that the finished tile surface does not vary more than 1/8 inch in 8 feet from the finished tile surface shown on the plans. In no case shall there be offsets in adjoining tiles, low spots on finished tile surfaces that can pond water, or finished tile surfaces that are not plumb or true in the completed tile work.

Tiles shall be firmly pressed into the freshly notched bond coat. Tile on interior surfaces shall be tapped and beat into a true surface and to obtain at least 80 percent coverage by the mortar on the back of each tile. Tile on exterior surfaces shall have 100 percent coverage and shall be back-buttered immediately prior to setting the tile.

If tile is face mounted, the paper and glue shall be removed within one hour after tile is installed and all tiles that do not meet the requirements for joints and surface tolerance shall be adjusted or replaced.

Mortar that exudes into the grout spaces between tiles shall be removed to the bottom of tile.

Marble Thresholds: Marble thresholds shall be set in same type of setting bed as abutting tile unless otherwise shown on the plans.

Joints: Joints between tile shall be continuous both vertically and horizontally. Joints shall be straight and of uniform and equal width. Where tiles on adjoining surface are the same size, the joints shall align, one with the other. Joint width shall be as recommended by the tile manufacturer.

Grouting Tile:

Grout shall be mixed, applied and cured in accordance with the manufacturer's recommendations and ANSI Standard: A108.10 for cement grout and ANSI Standard: A108.9 for epoxy grout.

Spacers, strings, ropes, pegs, glue, paper, and face mounting material shall be removed before grouting. Joints between glazed wall tile shall be wetted if they have become dry. Joints for epoxy mortar shall be dry.

Grouting shall not begin until at least 48 hours after installing tile.

A maximum amount of grout shall be forced into the joints between tiles in accordance with the manufacturer's recommendations. The grout shall be finished to the depth of the cushion for cushion edge tile and finished flush with the surface for square edge tile. All gaps and skips in the grout spaces shall be filled.

Mortar or mounting mesh shall not show through the grouted joints.

The finished grout shall have a uniform color and shall be smooth without voids, pinholes or low spots.

Expansion joints shall be kept free of grout or mortar.

Grout shall be protected from freezing or frost for a least 5 days after installation.

Expansion Joints:

Expansion joints shall be installed at the perimeter of all tile floors and at all substrate control joints and changes in the substrate material. Exterior expansion joint spacing shall not exceed 16 feet in any direction.

All expansion joints shall be made with sealant over backer rods. The thickness of sealant at the center of expansion joints shall not exceed the width of the joint. Joint edges shall be primed as recommended by the sealant manufacturer.

Edge Strips: Edge strips shall be installed at openings where the threshold has not been shown on the plans, but where tile floor abuts other flooring materials at the same level. Edge strips shall be installed centered under the closed door, or where there is no door, centered in the opening.

Sounding Tile: Tiled surfaces shall be sounded with a metal bar or chain for improperly bonded tile or setting bed. Tile or setting bed that emits a hollow sound shall be replaced.

Replacement: Cracked, chipped, broken, or otherwise defective tiles shall be removed and replaced. All tiles which differ more than 1/16 inch in elevation from adjacent tile edges shall be removed and replaced.

Curing:

After the installation of tile and the grouting of joints, the tile and grout shall be cured by keeping the surface continuously damp for at least 72 hours after grouting. Curing materials shall not stain the tile or grouted joints. Curing methods shall not erode away the grout.

After grouting, horizontal tiled surfaces shall be closed to traffic, and all tiled surfaces shall be kept free from impact, vibration or shock, for at least 72 hours.

Sealing Unglazed Quarry Tile: Sealer shall be applied to unglazed quarry tile only. The sealer shall be applied in accordance with the manufacturer's recommendations.

CLEANING AND PROTECTION

Cleaning Tile Surfaces:

All exposed tile surfaces shall be cleaned of all grout haze upon completion of grouting. Acids and chemicals used to clean tile shall conform to the tile manufacturer's recommendations. Cleaners shall not be harmful to materials on surfaces of abutting floors, walls, and ceilings. Tile work shall be rinsed thoroughly with clean water before and after using acid or chemical cleaners. After cleaning and rinsing, tile surfaces shall be polished using a soft cloth.

Tile work shall be cleaned and polished again immediately prior to completion of the contract. All dirt, grime, stains, paints, grease, and other discoloring agents or foreign materials shall be removed.

Protection:

After grouting, horizontal tiled surfaces shall be closed to traffic, and all tiled surfaces shall be kept free from impact, vibration or shock, for at least 72 hours after.

Tile surfaces damaged by construction operations shall be retiled.

SCHEDULES

Wall Tile:

Wall tile shall be nominal 2" x 2" glazed wall tile.

Installation on mortar bed, using a tile bond coat and grout, shall conform to the requirements of Method W 222, "Handbook for Ceramic Tile Installation."

Installation on gypsum wallboard, using a tile bond coat and grout, shall conform to the requirements of Method W 243, "Handbook for Ceramic Tile Installation."

Installation on cementitious backer board, using a tile bond coat and grout, shall conform to the requirements of Method W 244, "Handbook for Ceramic Tile Installation."

Installation on concrete and masonry shall be on a mortar bed using tile bond coat and grout, and shall conform to the requirements of Method W 211, "Handbook for Ceramic Tile Installation."

Floor Tile: Floor tile shall be nominal 2" x 2" matte porcelain tile installed on a mortar bed using a tile bond coat and grout and shall conform to the requirements of Method F 112, "Handbook for Ceramic Tile Installation."

12-9.02 DETECTABLE WARNING

PART 1 - GENERAL

This work shall consist of furnishing and installing a detectable warning of raised, truncated domes in conformance with the details shown on the plans and these special provisions.

SUBMITTALS

Manufacturer's descriptive data, color and texture samples, and installation instructions shall be submitted for approval. Two samples a minimum of 6" x 6" shall be submitted.

REGULATORY REQUIREMENTS

The detectable warning shall comply with the following regulations:

1. Americans with Disabilities Act (ADA) Title III Regulations, 28 CFR Part 36 "ADA Standards For Accessible Design," Appendix A, Section 4.29. for "Detectable Warnings."
2. Division of the State Architect - Access Compliance (DSA-AC) approved detectable warning products as provided in the California Code of Regulations (CCR) Title 24, Part 2, Section 205 definition of "Detectable Warning."

DELIVERY, STORAGE AND HANDLING

Materials shall be delivered to the jobsite in the manufacturer's original and unopened containers and bearing labels as to type of material. Finished surfaces shall be packaged with protective wrappings to protect panels from residue before and during installation.

WARRANTY

The manufacturer shall provide a written 5-year warranty for detectable warning, guaranteeing replacement when there is a defect in the dome shape, color fastness, sound-on-cane acoustic quality, resilience, or attachment. The warranty period shall begin upon acceptance of the contract.

PART 2 - PRODUCTS

ACCEPTABLE MANUFACTURERS

Available Manufacturers: Subject to conformance with the plans and special provisions, the detectable warning shall be ADA Solutions, Answer Industries,-Armor-Tile, or equal.

MATERIALS

Detectable Warning:

The detectable warning shall be prefabricated, surface or flush mounted, truncated dome panels. Truncated domes shall have dimensions and spacing as shown on the plans. The color of the detectable warning shall be safety yellow, conforming to Federal Standard 595B, Color No. 33538.

The detectable warning shall be vitrified polymer composite with aluminum oxide particles imbedded on truncated domes; homogeneous coloring.

Performance requirements shall conform to the following:

Property	Value	Test Methods
Compressive Strength	Not less than 28,000 psi	ASTM D 695
Tensile Strength	Not less than 11,000 psi	ASTM D 638
Flexural Strength	Not less than 25,000 psi	ASTM D 790
Fire Resistance	Flame spread shall be less than 15	ASTM E 84
Water Absorption	Not to exceed 0.07%	ASTM D 570
Slip Resistance	The combined Wet and Dry Static Co-Efficient of Friction not to be less than 0.80 on top of domes and field area	ASTM C 1028

Adhesives, Fasteners, and Sealant: Adhesives, fasteners, and sealant shall conform to the manufacturers recommendations.

PART 3 - EXECUTION

INSTALLATION

The detectable warning shall be installed securely and shall conform to the manufacturer's printed instructions for installation.

12-9.03 PAINTING

PART 1 - GENERAL

Scope: This work shall consist of preparing surfaces to receive coatings, and furnishing and applying coatings, in conformance with the schedules and details shown on the plans and these special provisions.

The coatings specified in this section are in addition to any factory finishes, shop priming, or surface treatment specified elsewhere in these special provisions.

DEFINITIONS

Detergent Wash: Removal of dirt and water-soluble chemicals by scrubbing with a solution of detergent and water, and removal of all solution and residues with clean water.

Hand Cleaning: Removal of dirt, loose rust, mill scale, excess base material, filler, aluminum oxide, chalking paint, peeling paint, or paint that is not firmly bonded to the surfaces by using hand or powered wire brushes, hand scraping tools, power grinders, or sandpaper and removal of all loose particles and dust prior to coating.

Mildew Wash: Removal of mildew by scrubbing with a solution of detergent, hypochlorite-type household bleach, and warm water, and removal of all solution and residues with clean water.

Abrasive Blasting:

Removal of loosely adhering paint, dirt, rust, mill scale, efflorescence, weak concrete, or laitance, shall be by the use of airborne abrasives. Loose particles, dust, and abrasives shall be removed by blasting with clean, oil-free air.

Abrasives shall be limited to mineral grit, steel grit, or steel shot, and shall be graded to produce the surface profile recommended in the manufacturer's data sheet.

Steam Cleaning: Removal of oil, grease, dirt, or other foreign matter by using steam generated by commercial steam cleaning equipment, from a solution of water and steam cleaning compounds, and removal of all residues and cleaning compounds with clean water.

TSP Wash: Removal of oil, grease, dirt, paint gloss, and other foreign matter by scrubbing with a solution of trisodium phosphate and warm water, and removal of all solution and residues with clean water.

Water Blasting: Removal of dirt, loose scale, chalking, or peeling paint by low-pressure water cleaning. Water blasting shall be performed in conformance with the requirements in SSPC-SP12 and shall produce a surface cleanliness meeting the requirements of SSPC-SP12-WJ4. Equipment used shall have a minimum flow rate of 1.5 GPM. If a detergent solution is used, it shall be biodegradable and shall be removed from all surfaces with clean water.

Protection:

The Contractor shall provide protective devices, such as tarps, screens or covers, as necessary to prevent damage to the work and to other property or persons from all cleaning and painting operations.

Paint or paint stains on surfaces not designated to be painted shall be removed by the Contractor at the Contractor's expense and the original surface shall be restored.

SUBMITTALS

Manufacturer's descriptive data, a materials list, and color samples shall be submitted for approval.

Product descriptive data shall include product description, manufacturer's recommendations for product mixing, thinning, tinting, handling, site environmental requirements, product application, and drying time.

Materials list shall include manufacturer's name, trade name, and product numbers for each type coating to be applied.

Color samples shall be manufacturer's color cards, approximately 2" x 3", for each color of coating shown on the plans. Color samples for stains shall be submitted on wood of the same species, color, and texture as the wood to receive the stain.

QUALITY ASSURANCE

Certificates of Compliance: Certificates of Compliance shall be furnished when products are required to conform with the requirements of The Society for Protective Coatings (SSPC) in conformance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

REGULATORY REQUIREMENTS

Coatings and applications shall conform to the rules for control of Volatile Organic Compound (VOC) emissions adopted by the air quality control district in the air basin in which the coatings are applied.

SITE ENVIRONMENTAL REQUIREMENTS

Coatings shall be applied in conformance with the environmental constraints specified in the manufacturer's printed instructions. These conditions shall be maintained until the coating has cured and is ready for recoat.

Continuous ventilation shall be provided during application of the coatings.

Adequate lighting, as determined by the Engineer, shall be provided while surfaces are being prepared for coatings and during coating applications.

DELIVERY, STORAGE, AND HANDLING

Products shall be delivered to the site in sealed, labeled containers and stored in a well-ventilated area at an ambient air temperature of not less than 45°F. Container labeling shall include manufacturer's name, type of coating, trade name, color designation, drying time, and instructions for tinting, mixing, and thinning.

MAINTENANCE STOCK

Upon completion of coating work, a full one-gallon container of each type and color of finish coat and stain used shall be delivered to the location at the project site designated by the Engineer. Containers shall be tightly sealed and labeled with color, texture, and room locations where used, in addition to the manufacturer's standard product label.

PART 2 - PRODUCTS

Products for each coating system shall be from a single manufacturer and shall conform to the requirements in the Detailed Performance Standards of the Master Painters Institute (MPI). Each product shall be shown on the MPI Approved Products List unless otherwise specified in these special provisions.

PART 3 - EXECUTION

INSPECTION

Coatings shall not be applied until surface preparation has been approved by the Engineer. The Contractor shall notify the Engineer at least 3 working days prior to the application of coatings.

SURFACE PREPARATION

Surfaces scheduled to be coated shall be prepared in conformance with the coating manufacturer's printed instructions unless otherwise specified in these special provisions.

Hardware, cover plates, light fixture trim, and similar items shall be removed prior to preparing surfaces for coating. Following the application of the finish coating, the removed items shall be reinstalled in their original locations.

Wood:

Coatings for exterior applications shall have the surface lightly sanded no more than 24 hours prior to the coating application.

A sealer recommended by the coating manufacturer shall be spot applied to knots, sap, pitch, tar, creosote, and other bleeding substances.

After the application of the prime coat, all nail holes, cracks, open joints, dents, scars, and surface irregularities shall be filled, hand cleaned, and spot primed to provide smooth surfaces for the application of finish coats.

Irregularities in wood surfaces to receive a transparent stain finish shall be filled and hand cleaned after the first coat of stain has been applied. The color of the filler shall match the color of the stained wood.

Irregularities in wood surfaces to receive a clear finish shall be filled and hand cleaned before the application of coatings. The color of the filler shall match the color of the coated wood.

Galvanized Metal:

New surfaces shall be roughened by hand sanding or light abrasive blasting. Galvanizing shall not be removed during cleaning or roughening.

Damaged or corroded areas shall be cleaned and given 2 spot applications of a coating that conforms to the requirements in the Detailed Performance Standards of the MPI, and listed on MPI List "Number 18, Primer, Zinc Rich, Organic."

Steel and Other Ferrous Metals: Surface shall be cleaned in conformance with the requirements in SSPC-SP 1. Surface profile shall be as required for the coating system specified.

Concrete and Concrete Masonry Unit: New material shall be cleaned and prepared in conformance with the requirements in SSPC-SP 13. Cracks and voids shall be filled with cement mortar patching material. Concrete shall be cured until the surface moisture is below the level specified in the coating manufacturer's printed instructions.

Previously Coated Surfaces:

Dirt, oil, grease, or other surface contaminants shall be removed by water blasting, steam cleaning, or TSP wash. Minor surface imperfections shall be filled as required for new work. Mildew shall be removed by mildew wash. Chalking paint shall be removed by hand cleaning. The surfaces of existing hard or glossy coatings shall be abraded to dull the finish by hand cleaning or light abrasive blasting. Abrasive blasting shall not be used on wood or non-ferrous metal surfaces.

Chipped, peeling, blistered, or loose coatings shall be removed by hand cleaning or water blasting. Bare areas shall be pretreated and primed as required for new work.

APPLICATION

Coatings shall be applied in conformance with the printed instructions and at the application rates recommended by the manufacturer to achieve the dry film thickness stated in the coating technical data sheet.

Mixing, thinning and tinting shall conform to the manufacturer's printed instructions. After thinning, the coating shall conform to the regulatory requirements in these special provisions.

Coatings shall be applied only when surfaces are dry and properly prepared.

Cleaning and painting shall be scheduled so that dust and other contaminants from the cleaning process will not fall on wet, newly coated surfaces.

Materials required to be coated shall have coatings applied to all exposed surfaces, including the tops and bottoms of wood and metal doors, the insides of cabinets, and other surfaces not normally visible from eye level.

Surface Finish Application:

Each coat shall be applied to a uniform finish. Finished surfaces shall be free of surface deviations and imperfections such as skips, cloudiness, spotting, holidays, laps, brush marks, runs, sags, curtains, ropiness, improper cutting in, overspray, drips, ridges, waves, and variations in color and texture.

Each application of a multiple application finish system shall closely resemble the final color coat, except each application shall provide enough contrast in shade to distinguish the separate applications.

Work Required Between Applications:

Each application of material shall be cured in conformance with the coating manufacturer's printed instructions before applying the succeeding coating.

Enamels and clear finishes shall be lightly sanded, dusted, and wiped clean between applications.

Stain blocking primer shall be spot applied whenever bleeding substances are visible through the previous application of a coating.

Timing of Applications: The first application of the coating system shall be during the same work shift that the final surface preparation was performed. Additional coats shall be applied as soon as the required drying time of the preceding coat, specified in the coating manufacturer's printed instructions, has been met.

Application Methods:

Coatings shall be applied by brush, roller or spray. Rollers shall be of a type which do not leave a stippled texture in the paint film. Extension handles for rollers shall not be greater than 6 feet in length.

If spray methods are used, surface deviations and imperfections such as overspray, thickness deviations, lap marks, and orange peel shall be considered as evidence the work is unsatisfactory and the Contractor shall apply the remainder of the coating by brush or roller, as approved by the Engineer.

Back Priming:

The first application of the coating system shall be applied to all wood surfaces (face, back, edges, and ends) of wood materials that are not factory coated, immediately upon delivery to the project site. Surfaces of interior finish woodwork that adjoin concrete or masonry shall be coated with one application of exterior wood primer before installation.

Patches in Previously Coated Surfaces: Where patches are made on surfaces of previously coated walls or ceilings, the entire surface to corners on every side of the patch shall be coated with a minimum of one application of the finish coat.

Finishing Mechanical and Electrical Components:

Shop primed mechanical and electrical components shall be finish coated in conformance with the coating system specified for the substrate material. Louvers, grilles, covers, and access panels on mechanical and electrical components shall be removed and coated separately.

Interior surfaces of air ducts which are visible through grilles or louvers shall be coated with one application of flat black enamel, to limit of the sight line.

Conduit and piping visible in the finished work shall be painted.

Both sides and all surfaces, including edges and back of wood mounting panels for electrical and telephone equipment shall be finish coated before installing equipment.

CLEANING

Upon completion of all operations, the coated surfaces shall be thoroughly cleaned of dust, dirt, grease, or other unsightly materials or substances.

Surfaces marred or damaged as a result of the Contractor's operations shall be repaired, at his expense, to match the condition of the surfaces prior to the beginning of the Contractor's operations.

COATING SYSTEM

The surfaces to be coated shall be as shown on the plans and as specified in these special provisions. When a coating system is not shown or specified for a surface to be finish coated, the coating system to be used shall be as specified below for the substrate material. The number of applications specified for each coating system listed herein is a minimum. Additional coats shall be applied if necessary to obtain a uniform color, texture, appearance, or required dry film thickness.

SYSTEM 1- CONCRETE MASONRY UNIT

One Prime Coat:

Block Filler: Latex, Interior/Exterior MPI List Number 4

2 Finish Coats:

Flat: Latex, Exterior, MPI Gloss Level 1, MPI List Number 10

Semi-Gloss: Latex, Exterior, MPI Gloss Level 5, MPI List Number 11

SYSTEM 2 - GALVANIZED METAL

2 Finish Coats:

Flat: Latex, Exterior, MPI Gloss Level 1, MPI List Number 10

Eggshell-like: Light Industrial coating, Water Based, Exterior, MPI Gloss Level 3, MPI List Number 161

Semi-Gloss: Light Industrial coating, Water Based, Exterior, MPI Gloss Level 5, MPI List Number 163

Gloss: Light Industrial coating, Water Based, Exterior, MPI Gloss Level 6, MPI List Number 164

SYSTEM 3 - PREVIOUSLY COATED EXTERIOR SURFACES

2 Finish Coats:

Flat: Latex, Exterior, MPI Gloss Level 1, MPI List Number 10

Low Sheen: Latex, Exterior, MPI Gloss Level 3/4, MPI List Number 15

Semi-Gloss: Latex, Exterior, MPI Gloss Level 5, MPI List Number 11

Gloss: Latex, Exterior, MPI Gloss Level 6, MPI List Number 119

SYSTEM 4 - PREVIOUSLY COATED INTERIOR SURFACES

2 Finish Coats:

Flat: Latex, Interior, MPI Gloss Level 1, MPI List Number 53

Eggshell-like: Latex, Interior, MPI Gloss Level 3, MPI List Number 52

Semi-Gloss: Latex, Interior, MPI Gloss Level 5, MPI List Number 54

Gloss: Latex, Interior, MPI Gloss Level 6, MPI List Number 114

SYSTEM 5 - STEEL AND OTHER FERROUS METALS, SEMI-CORROSIVE ENVIRONMENT

VISIBLE IN FINISHED WORK:

2 Prime Coats:

Primer: Rust Inhibitive, Water Based, MPI List Number 107

2 Finish Coats:

Flat: Latex, Exterior, MPI Gloss Level 1, MPI List Number 10

Eggshell-like: Light Industrial coating, Water Based, Exterior, MPI Gloss Level 3, MPI List Number 161

Semi-Gloss: Light Industrial coating, Water Based, Exterior, MPI Gloss Level 5, MPI List Number 163

Gloss: Light Industrial coating, Water Based, Exterior, MPI Gloss Level 6, MPI List Number 164

NOT VISIBLE IN FINISHED WORK:

2 Prime Coats:

Primer: Rust Inhibitive, Water Based, MPI List Number 107

SYSTEM 6 - WOOD, PAINTED

1 Prime Coat:

Primer: Latex for Exterior Wood, MPI List Number 6

2 Finish Coats:

Flat: Latex, Exterior, MPI Gloss Level 1, MPI List Number 10

Low Sheen: Latex, Exterior, MPI Gloss Level 3/4, MPI List Number 15

Semi-Gloss: Latex, Exterior, MPI Gloss Level 5, MPI List Number 11

Gloss: Latex, Exterior, MPI Gloss Level 6, MPI List Number 119

COLOR SCHEDULE

Colors shall be as shown on the plans.

SECTION 12-10. SPECIALTIES

12-10.01 METAL TOILET PARTITIONS

PART 1 - GENERAL

Scope: This work shall consist of furnishing and installing metal toilet partitions in accordance with the details shown on the plans and these special provisions.

Metal toilet partitions shall consist of panels, doors, pilasters urinal screens, fasteners, anchorages and hardware. Internal reinforcement shall be provided at all fasteners, anchorages, hardware and accessories.

Doors, panels, pilasters, and urinal screens shall be stainless steel with a No. 4 satin finish.

SUBMITTALS

Manufacturer's descriptive data, installation instructions, and working drawings shall be submitted for approval.

Working drawings shall show the plan layout, door and panel elevations and all details required for the complete installation and anchorage of the partition system.

PART 2 - PRODUCTS

Doors and Panels:

Doors and panels shall be flush, one inch thick, formed of two 0.030-inch (22-gage) Type 304 stainless steel sheets over a honeycomb core. Doors and panels shall have formed edges sealed with a continuous oval crown locking strip, and shall be mitered, welded, and finished at corners.

Doors shall have controlled action hinges, with vertical pintle and ball bearing roller operating on adjustable cams, or moving parts of nylon and stainless steel. Top pivots shall be recessed into edges of doors.

Doors shall be provided with slide bar latch and a combination coat-hat hook and door stop, except as otherwise specified.

Doors on stalls designed for use by the disabled shall be provided with a grip and turn latch, combination coat-hat hook and door stop, and U-shaped door pulls immediately below the latch on the inside and outside of the door.

Pilasters: Pilasters shall be 1¼ inches thick, of the same construction as the doors and panels, except face sheets shall be 0.052 inch for galvanized steel and 0.048 inch for stainless steel (18-gage), with adjustable, leveling base incorporating two 3/8-inch diameter stud expansion anchors with leveling nuts.

Urinal Screens: Urinal screens shall be wedge type, wall-mounted, and of the same construction as the doors and panels, except face sheets shall be 0.040-inch (20-gage) minimum thickness. All fasteners shall be concealed.

Fasteners and Anchorages: Fasteners and anchorages shall be stainless steel with vandal resistant heads.

Hardware: Hardware shall be highly polished chromium plated, cast alloy, or heavy duty anodized aluminum.

Pilasters Anchors: Pilasters anchors shall be integral stud anchor type or internally threaded expansion sleeve type with single cone expander. Self-drilling type anchorage shall not be used.

Pilaster Shoes: Pilaster shoes shall be one-piece, stainless steel, with concealed hold down clips, and of sufficient height to completely cover the base and anchors.

PART 3 - EXECUTION

INSTALLATION

Metal toilet partitions shall be installed rigidly, securely, plumb, and true and in accordance with the manufacturer's recommendations. Tops and bottoms of doors shall align with tops and bottoms of panels, and all horizontal lines shall be level.

Rigid backing shall be provided in walls to receive anchorages.

Panels shall be anchored with at least 3 brackets at each wall and pilaster. Two anchors shall be used to fasten each pilaster base to the floor.

Doors shall not bind during opening and closing. The clearance between the door edges and pilasters shall be uniform, equidistant, and shall not exceed 3/16 inch. Hinges shall be adjusted to hold doors ajar when unlatched. Doors on stalls designed for use by the disabled shall return to the closed position.

Drilling, cutting and fitting of wall and floor finishes shall be concealed by the completed installation.

CLEAN-UP

Toilet partitions shall be cleaned, polished and free of all defects. Chipped, dented, scratched, or otherwise damaged work shall be replaced at the Contractor's expense.

12-10.02 SIGNS

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing signs in accordance with the details shown on the plans and these special provisions.

SUBMITTALS

Product Data: Manufacturer's descriptive data for sign materials, colors, graphics, and fastening hardware shall be submitted for approval.

QUALITY ASSURANCE

Regulatory Requirements: Identification, directional, informational, exit and accessibility signs and symbols shall conform to the requirements in the CCR, Title 24, Part 2, Section 1115B.6, "Identification symbols," and Section 1117B.5, "Signs and identification."

PART 2 - PRODUCTS

Sign Colors: The color white shall conform to Federal Standard 595, Color No. 17886. The color blue shall conform to Federal Standard 595, Color No. 15090.

Signs:

Signs shall be scratch resistant, non-static, fire retardant, washable acrylic laminate with a non-glare surface, not less than 1/8 inch thick. All wall mounted sign colors shall be in contrast to walls.

Telephone Sign and Restroom Accompany Sign shall be sheet aluminum, not less than 0.080-inch thick (12-gauge) with rounded corners. Sign covering shall be engineer grade reflective sheeting. Letters shall be upper case Sans-Serif, black letters on a white background. Sign size shall be 24 inches wide by 18 inches high with 2 1/2-inch letters.

Fastening hardware and material: Fastening hardware and material shall be as recommended by the sign manufacturer. Fasteners shall be noncorrosive.

PART 3 - EXECUTION

INSTALLATION

Signs and symbols shall be fastened or secured to clean, finished surfaces in accordance with the sign manufacturer's instructions. Signs shall be installed at a location and height as shown on the plans.

Metal signs shall be attached securely with galvanized or cadmium plated fasteners.

12-10.03 TELEPHONE ENCLOSURES

PART 1 - GENERAL

Scope: This work shall consist of furnishing and installing telephone enclosures in accordance with the details shown on the plans and these special provisions.

SUBMITTALS

Manufacturer's descriptive data and installation instructions shall be submitted for approval.

PART 2 - PRODUCTS

Telephone Enclosure:

Telephone enclosure shall be standard factory fabricated, wall mounted unit with integral stainless steel writing and directory shelves, concealed theft and vandal resistant steel mounting bracket, steel frame with acoustical blanket behind perforated stainless steel back panel and 1/2-inch thick clear acrylic side panels. The telephone enclosure shall be not less than 34 inches high by 30 inches wide (clear width inside enclosure), and by 12 inches deep.

The size of the telephone apparatus box shall be verified with the telephone company prior to ordering or fabricating the enclosure.

Electrical Service and Telephone Service Conduit and Conductors: Electrical service and telephone service conduit and conductors shall be as specified in Section 12-16, "Electrical" of these special provisions.

PART 3 - EXECUTION

INSTALLATION

The telephone enclosures shall be installed and fastened rigidly and securely in accordance with the manufacturer's instructions.

Electrical Service: Electrical service conduits and conductors shall be installed as shown on the plans.

Telephone Service:

Conduits for the telephone service conductors shall be installed as shown on the plans. A pull wire shall be installed in the telephone conduit, and shall be doubled back into the conduit at both ends.

The telephone company shall furnish and install the telephone set, apparatus box and telephone service conductors in accordance with the provisions specified under "Utility Connection" in Section 12-1, "General Requirements," of these special provisions.

12-10.04 TOILET ROOM ACCESSORIES

PART 1 - GENERAL

Scope: This work shall consist of furnishing and installing toilet room accessories in accordance with the details shown on the plans and these special provisions.

SUBMITTALS

Manufacturer's descriptive data and installation instructions and details shall be submitted for approval.

PART 2 - PRODUCTS

Toilet Tissue Dispenser: Toilet tissue dispenser shall be dual roll, surface mounted, stainless steel with satin finish, approximately 8½" x 5" x 3" deep. Dispenser shall utilize standard toilet tissue rolls. The top roll shall automatically drop into place after the bottom roll is depleted. One dispenser per toilet stall.

Soap Dispenser System: Soap dispenser system shall be wall-mounted and shall have gravity feed, plunger type spouts, and a remote stainless steel liquid soap reservoir equipped with soap level indicator, outlet valves, and brass tubing and fittings. Brass tubing and fittings shall be as recommended by the dispenser manufacturer. The stainless steel and chrome plated brass construction soap dispensing mechanisms shall be capable of delivering fixed amounts of liquid soap in lather form. The vandal resistant valves shall project not more than 3½ inches from the wall and shall not be removable from within the restroom.

Toilet Seat Cover Dispenser: Toilet seat cover dispenser shall be stainless steel, lockable dispenser. Approximate dimensions: 15" x 11½" x 2 3/8" deep. One dispenser per toilet stall.

Mirror, Wall Hung: Mirror, wall hung shall be Number 1 quality, ¼ inch thick, electrolytically copper plated float or plate glass mirror with nonmoisture-absorbing filler. Mirror shall have a heavy gage galvanized steel back and stainless steel frame. The frame shall have a satin finish and shall be mitered and welded and the corners shall be ground smooth. Fasteners shall not penetrate surfaces of the frame exposed to view. Mirror shall conform to Federal Specification: DD-M-411b and shall be guaranteed against silver spoilage for not less than 10 years.

Grab Bars: Grab bars shall be stainless steel, 1½-inch diameter bars with integral mounting flanges concealed under integral escutcheons.

Electric Hand Dryer: Electric hand dryer shall be a surface-mounted, 230-volt, 10-ampere unit with a maximum lockout timer of 35 seconds. Hand dryer shall be mounted on a heavy duty backing plate with 2 chrome plated tamper resistant bolts. The backing plate shall have two 7/8-inch diameter holes for electrical access and shall be bolted to the wall with four thru-wall concealed mounting bolts. Hand dryer cover plate shall be a one piece, heavy duty, rib-reinforced, die-cast zinc alloy, cover plate, painted with an electrostatically applied white epoxy and chip-proof finish paint. Nozzle shall be fixed in the downward air position.

Electric Hand Dryer Motor: The motor shall be 460 watts minimum, series commutated, 20,000 RPM, through-flow discharge blower motor. The fan and motor combination shall produce an air velocity of 4,850 linear meters per minute at the air outlet, and 14,000 linear feet per minute at a distance of 4 inches away from the air outlet. Fan and motor assembly shall be insulated from the housing by a resilient rubber mounting.

Heater: A 900-watt, nichrome wire heating element protected by an automatic resetting high temperature limit control switch that opens when air flow stops, and automatically re-closes when air flow resumes. The heating element shall produce an air temperature of up to 135°F at a distance of 4 inches away from the air outlet, at a 72°F ambient room temperature.

Controls: Hand dryer shall be activated by an infrared optical sensor located adjacent to the air outlet. The hand dryer shall operate as long as hands are under the air outlet for the maximum lockout time of 35 seconds. Under normal conditions of atmospheric temperature, hand dryer shall be able to dry the hands within 15 seconds.

PART 3 - EXECUTION

Toilet room accessories shall be installed in accordance with the manufacturer's recommendations. Fasteners for mounting toilet room accessories shall be concealed and vandal resistant.

Expansion anchors shall be used for mounting accessories on masonry or concrete walls.

Toilet room accessories shall be mounted after painting work has been completed.

All toilet room accessories shall be mounted plumb, secure and rigid. Grab bars shall be supported adequately so the bars will withstand an applied load of 250 pounds at any point.

12-10.05 PREFABRICATED PICNIC SHELTER

PART 1- GENERAL

Contractor shall furnish and install new pre-engineered prefabricated steel picnic shelters in accordance with the plans and these special provisions.

SUBMITTALS

Product data: Manufacturer's descriptive data, complete shop drawings with structure details and foundation details along with structure calculations signed by a California registered structural engineer, along with specifications and installation instruction shall be submitted for review and approval.

PART 2- PRODUCTS

The new picnic shelters shall be one single manufacturer's prefabricated units and each shall have four steel columns 7'-6" high and hip metal roof with 4" on 12" standard slope. The roof of the shelters shall be 24 GA factory painted steel galvanized roof panels and the roof canopy shall cover an area of 23 feet by 15 feet. The four tubular steel columns, spaced 20 feet apart along the longer side of the concrete pad and 12 feet apart along the shorter side of the concrete pad (measured from each column centerline) shall be bolted to each footing to allow future relocation and all the steel structure of the shelter shall receive standard powder coat finish.

MANUFACTURERS

Acceptable manufacturers: Subject to compliance with the plans and special provisions, prefabricated picnic shelter manufacturer shall be Poligon Porter Corp. toll free number (800) 354-7721, RCP Shelters, Inc. toll free number (800) 525-0207, Skylark Shelters System, toll free (800) 433-3180, or equal.

SECTION 12-11. (BLANK)

SECTION 12-12. (BLANK)

SECTION 12-13. (BLANK)

SECTION 12-14. (BLANK)

SECTION 12-15. MECHANICAL

12-15.01 MECHANICAL WORK

PART 1 - GENERAL

Scope: This work shall consist of performing mechanical work in accordance with the details shown on the plans and these special provisions.

Mechanical work shall include furnishing all labor, materials, equipment and services required for providing plumbing distribution systems.

Earthwork, foundations, sheet metal, painting, electrical, and such other work incidental and necessary to the proper installation and operation of the mechanical work shall be in accordance with the requirements specified for similar type work elsewhere in these special provisions.

System layouts are generally diagrammatic and location of equipment is approximate. Exact routing of pipes and location of equipment is to be governed by structural conditions and obstructions. Equipment requiring maintenance and inspection is to be readily accessible.

Roof penetrations shall be flashed and sealed watertight in accordance with the requirements specified under "Sheet Metal Flashing" in Section 12-7, "Thermal and Moisture Protection," of these special provisions.

SUBMITTALS

Product Data:

A list of materials and equipment to be installed, manufacturer's descriptive data, and such other data as may be requested by the Engineer shall be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions for plumbing fixtures, and component layout shall be included where applicable.

Manufacturer's descriptive data shall be submitted for the following:

- Drinking Fountains
- Infrared Flush Valves
- Hose Faucet
- Lavatories
- Urinals
- Water Chiller
- Water Closets
- Water Hammer Arrestors
- Water Meter

CLOSEOUT SUBMITTALS

Operation and Maintenance Manuals:

Prior to the completion of the contract, 3 identified copies of the operation and maintenance instructions with parts lists for the equipment specified herein shall be delivered to the Engineer at the jobsite. The instructions and parts lists shall be indexed and bound in a manual form and shall be complete and adequate for the equipment installed. Inadequate or incomplete material shall be returned. The Contractor shall resubmit adequate and complete manuals at no expense to the State.

Operation and maintenance manuals shall be submitted for the following equipment:

- Drinking Fountains
- Lavatories
- Urinals
- Water Chiller
- Water Closets
- Water Hammer Arrestors
- Infrared Flush Valves

QUALITY ASSURANCE

Codes and Standards: Mechanical work, including equipment, materials and installation, shall conform to the CBC,CMC, and to the California Code of Regulations, Title 8, Chapter 4, Division of Industrial Safety (DIS).

WARRANTY

Warranties and Guarantees: Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

12-15.02 PIPE, FITTINGS AND VALVES

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing pipes, fittings and valves in accordance with the details shown on the plans and these special provisions. Pipe, fittings and valves shall include such plumbing and piping accessories and appurtenances, not mentioned, that are required for the proper installation and operation of the plumbing and piping systems.

The pipe sizes shown on the plans are nominal inside diameter. No change in the pipe size shown on the plans shall be permitted without written permission from the Engineer.

The pipe and fitting classes and material descriptions shall be as specified herein. No change in class or description shall be permitted without written permission from the Engineer.

QUALITY ASSURANCE

Codes and Standards: Pipe, fittings and valves shall be installed in accordance with the requirements in the CPC, the manufacturer's recommendations and the requirements specified herein.

PART 2 - PRODUCTS

MATERIALS

PIPE AND FITTINGS (Class and Description)

C1: Hub and plain end cast iron soil pipe with neoprene gaskets conforming to Cast Iron Soil Pipe Institute's Standard 301. Pipe, fittings and gaskets shall be of one manufacturer.

C2: Hubless cast iron soil pipe with neoprene gaskets, corrugated stainless steel shields and stainless steel clamps conforming to Cast Iron Soil Pipe Institute's Standard 301. Joint materials shall be furnished by pipe manufacturer.

H1: Type DWV hard copper tubing conforming to ASTM Designation: B 306, with DWV drainage fittings, stop type couplings and threaded adapters.

H3: Type L hard copper tubing conforming to ASTM Designation: B 88, with wrought copper or cast bronze solder joint pressure fittings, stop type couplings and threaded adapters. Solder shall be lead-free.

Unions (for Steel Pipe): Unions (for steel pipe) shall be 250 psi, threaded malleable iron, ground joint, brass to iron seat, galvanized or black to match piping.

Unions (for Copper or Brass Pipe): Unions (for copper or brass pipe) shall be 150 psi cast bronze, ground joint, bronze to bronze seat with silver brazing threadless ends or 125 psi cast brass, ground joint, brass to brass seat with threaded ends.

Dielectric Waterway: Dielectric waterway shall be a premanufactured unit that incorporates an insulated interior lining at least 3 inches in length between the 2 pipes being connected while maintaining metal to metal contact on the exterior surface. Dielectric water way shall be listed by IAPMO (International Association of Plumbing and Mechanical Officials).

Insulating Union: Insulating union or flange as applicable shall be suitable for the service on which used. Connections shall be constructed such that the 2 pipes being connected are completely insulated from each other with no metal to metal contact. Insulating couplings shall not be used. Insulating union shall be F. H. Maloney; Central Plastics; EPCO; or equal.

VALVES

Ball Valve: Ball valve shall be two piece, minimum 400 psi WOG, bronze body and chrome plated or brass ball with full size port. Valve shall be Nibco Scott, T-580; Watts, B-6000; Kitz, 56; or equal.

FAUCET

Hose Faucet: Hose faucet shall be compression type, angle pattern, wall flange at exterior locations, tee handle, 3/4-inch female thread with hose end, rough chrome or nickel plated finish for locations inside building, rough brass finish for others. Hose faucet shall be supplied with an integral or nonremovable threaded outlet vacuum breaker which meets the requirements of the American Society of Sanitary Engineering (ASSE) Standard: 1011. Hose faucet shall be Nibco, No. 63VB; Chicago, No. 13T; or equal.

CLEANOUTS

Cleanout: Cleanout shall be cast iron cleanout tee type with polished stainless access plates. Plug shall be countersunk brass or bronze with tapered threads. Cleanout shall be Wade, Smith, Zurn, No. or equal.

MISCELLANEOUS ITEMS

Water Hammer Arrestor: Water hammer arrestor shall be stainless steel body with bellows or piston. Arrestor compression chambers shall be pneumatically charged. Water hammer arrestors shall be tested and certified in accordance with the Plumbing and Drainage Institute Standard: PDI-WH201 and sized as shown on the plans.

Compression Stop (Exposed): Compression stop (exposed) shall be metal full free waterway, angle type, ground joint union, non-rising stem, molded rubber seat and wheel handle or ball valve, and shall be installed as shown in the plans.

Water Meter: Water meter shall be disc or turbine type, suitable for water service with a magnetic coupling and a minimum 125 psi working pressure. Meter shall be 1 1/2 inches with a maximum pressure drop of 7 psi at 20 GPM. Readout shall be in gallons. Water meter shall be Badger; Neptune; Rockwell; Master Meter, or equal.

Pipe Hanger (for piping supported from overhead): Pipe hanger (for piping supported from overhead) shall be Grinnell, Model 269; Super Struct, C711; or equal.

PART 3 - EXECUTION

INSTALLATION

INSTALLATION OF PIPES AND FITTINGS

Pipe and Fittings: Pipe and fittings shall be installed in accordance with the following designated uses:

Designated Use	Pipe and Fitting Class
Domestic water (CW) in buildings	H3
Sanitary drain piping above ground in building	H1, C1, or C2
Sanitary vent piping above ground in building	H1, C1, or C2
Equipment drains and relief valve discharge	H3
Soap lines	H3

Installing Piping:

Water piping shall be installed generally level, free of traps and bends, and arranged to conform to the building requirements.

Public use areas shall have concealed piping.

Pipe Space Room shall have exposed piping.

Piping shall be installed parallel to walls. All obstructions shall be cleared, headroom preserved and openings and passageways kept clear whether shown or not. Piping shall not interfere with other work.

Where pipes pass through exterior walls, a clear space around pipe shall be provided. Space shall be caulked water tight with silicone caulk.

Exposed supply and drain piping in rest rooms shall be chrome finished.

Forty-five degree bends shall be used where offsets are required in venting. Vent pipe headers shall be sloped to eliminate any water or condensation.

Vent piping shall extend a minimum of 8 inches above the roof.

Horizontal sanitary sewer pipe inside buildings shall be installed on a uniform grade of not less than ¼ inch per foot unless shown otherwise on the plans.

Drainage pipe shall be run as straight as possible and shall have easy bends with long turns.

Wye fittings and 1/8 or 1/16 bends shall be used where possible. Long sweep bends and combination Wye and 1/8 bends may be used only for the connection of branch pipes to fixtures and on vertical runs of pipe.

Cutting Pipe: Pipe shall be cut straight and true and the ends shall be reamed to the full inside diameter of the pipe after cutting.

Damaged Pipe: Pipe that is cracked, bent or otherwise damaged shall be removed from the work.

Pipe Joints and Connections:

Joints in threaded steel pipe shall be made with teflon tape or a pipe joint compound that is nonhardening and noncorrosive, placed on the pipe and not in the fittings.

The use of thread cement or caulking on threaded joints will not be permitted. Threaded joints shall be made tight. Long screw or other packed joints will not be permitted. Any leaky joints shall be remade with new material.

Exposed polished or enameled connections to fixtures or equipment shall be made with special care, showing no tool marks or threads.

Cleaning and Closing Pipe: The interior of all pipe shall be cleaned before installation. All openings shall be capped or plugged as soon as the pipe is installed to prevent the entrance of any materials. The caps or plugs shall remain in place until their removal is necessary for completion of the installation.

Securing Pipe: Pipe in the buildings shall be held in place by iron hangers, supports, pipe rests, anchors, sway braces, guides or other special hangers. Material for hangers and supports shall be compatible with the piping or neoprene isolators shall be used. Allowances shall be made for expansion and contraction. Steel pipe shall have hangers or supports every 10 feet. Copper pipe one inch or less in diameter shall have hangers or supports every 6 feet and sizes larger than one inch shall have hangers or supports every 10 feet. Cast iron soil pipe with neoprene gaskets shall be supported at each joint. Vertical pipes shall be supported with clamps or straps. Horizontal and vertical piping shall be securely supported and braced to prevent swaying, sagging or flexing of joints.

Hangers and Supports:

Hangers and supports shall be selected to withstand all conditions of loading to which the piping and associated equipment may be subjected and within the manufacturer's load ratings. Hangers and supports shall be spaced and distributed so as to avoid load concentrations and to minimize the loading effect on the building structure.

Hangers and supports shall be sized to fit the outside diameter of pipe or pipe insulation. Hangers shall be removable from around pipe and shall have provisions for vertical adjustment after erection. Turnbuckles may be used.

Materials for holding pipe in place shall be compatible with piping material.

Hanger rods shall be provided with locknuts at all threaded connections. Hanger rods shall be sized as follows:

Pipe Size	Minimum Hanger Rod Diameter
1/2" to 2"	3/8"
2 1/2" to 3 1/2"	1/2"

Union: Unions shall be installed at each threaded or soldered connection to equipment. Unions shall be located so piping can be easily disconnected for removal of equipment.

Dielectric Waterway: Dielectric waterway shall be provided between metal pipes of different material.

Insulating Union and Insulating Connection:

Insulating union and insulating connection shall be provided where shown.

Compression Stop: Each fixture, including hose faucets, shall be equipped with a compression stop installed on water supply pipes to permit repairs without shutting off water mains. Ball valves may be installed where shown on the plans or otherwise permitted by the Engineer.

INSTALLATION OF FAUCETS

Hose Faucet : Faucet shall be installed with outlet 18 inches above finished grade.

INSTALLATION OF CLEANOUTS

Cleanouts:

Cleanout plug shall be located to provide sufficient room for rodding.

INSTALLATION OF MISCELLANEOUS ITEMS

Water Hammer Arrestor: Water hammer arrestor shall be installed so that they are vertical and accessible for replacement. Water hammer arrestor shall be installed with access door when in walls or there is no access to ceiling crawl spaces. Access door location shall be where shown on the plans or as approved by the Engineer.

Water Meter: Water meter shall be installed in horizontal piping run with no fittings located within 15 inches of either side of the meter.

Flushing Completed Systems: All completed systems shall be flushed and blown out.

Chlorination:

The Contractor shall flush and chlorinate all domestic water piping and fixtures.

Calcium hypochlorite granules or tablets, if used, shall not be applied in the dry form, but shall first be dissolved into a solution before application.

The Contractor shall take adequate precautions in handling chlorine so as not to endanger workmen or damage materials. All pipes and fittings shall be completely filled with water containing a minimum of 50 ppm available

chlorine. Each outlet in the system shall be opened and water run to waste until a strong chlorine test is obtained. The line shall then be closed and the chlorine solution allowed to remain in the system for a minimum of 24 hours so that the line shall contain no less than 25 ppm chlorine throughout. After the retention period, the system shall be drained, flushed and refilled with fresh water.

FIELD QUALITY CONTROL

Testing:

The Contractor shall test piping at completion of roughing in and at other times as directed by the Engineer.

The system shall be tested as a single unit, or in sections as approved by the Engineer. The Contractor shall furnish necessary materials, test pumps, instruments and labor and notify the Engineer at least 3 working days in advance of testing. After testing, the Contractor shall repair all leaks and retest to determine that leaks have been stopped. Surplus water shall be disposed of after testing as directed by the Engineer.

The Contractor shall take precautions to prevent joints from drawing while pipes and appurtenances are being tested. The Contractor shall repair damage to pipes and appurtenances or to other structures resulting from or caused by tests.

General Tests:

All piping shall be tested after assembly and prior to connecting fixtures. Systems shall show no loss in pressure or visible leaks.

The Contractor shall test systems according to the following schedule for a period of not less than 4 hours:

Test Schedule		
Piping System	Test Pressure	Test Media
Sanitary sewer and vent	10-foot head	Water
Water	125 psig	Water

During testing of water systems, valves shall be closed and pipeline filled with water. Provisions shall be made for release of air.

Sanitary sewers shall be cleared of obstructions before testing for leakage. The pipe shall be proved clear of obstructions by pulling an appropriate size inflatable plug through the pipe. The plug shall be moved slowly through the pipe with a tag line. The Contractor shall remove or repair any obstructions or irregularities.

12-15.03 PLUMBING FIXTURES

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of the furnishing and installing plumbing fixtures in accordance with the details shown on the plans and these special provisions.

PART 2 - PRODUCTS

Plumbing fixtures shall be white in color and shall meet the following requirements:

Water Closet: Water closet shall be wall hung, ADA accessible, vitreous china, Siphon jet, elongated bowl, 1½-inch back spud; with solid plastic, open front elongated seat with check hinges of the following types or equal:

	American Standard	Toto	Zurn
Closet	"Afwall" 2259.125	CT708V	Z5620
Seat	Olsonite 95	SC134	Z5955SS-EI
Electronic Flush valve	1.6 gallon per flush, Diaphragm or piston type concealed behind wall with integral control stop and through the wall infrared "hands free" sensor and manual flushing button. Flush valve shall have vacuum breaker suitable for use with 1 ½" spud water closets.		
		TOTO, Model No. TET2ARS-31. Transformer Model No. TEF61RSV-17.	SLOAN, Model No. 152-ES-S. Transformer Model No. EL-208-100VA.
Carrier	Adjustable height, horizontal, cast iron concealed closet chair carrier with 4" outlet connection; Zurn, J.R. Smith, Josam, Wade, or equal.		

Urinal (ADA Accessible): Urinal shall be ADA accessible, vitreous china, washout type, 1½-inch back spud, wall hung, integral shields, spreader, and trap of following types or equal:

	American Standard	Kohler	Eljer
Urinal	"Washbrook" 6506.011	Bardon Superior 4960-ER	"Savon Watersaver" 161-1095
Electronic Flush valve	1.06 gallon per flush, Diaphragm or piston type concealed behind wall with integral control stop and through the wall infrared "hand free" push button sensor and manual flushing button. Flush valve shall have vacuum breaker suitable for use with 1 ½" spud urinals.		
	TOTO, Model No. TET2ARS & VB13RB-11. Transformer Model TEF61RSV-17	SLOAN, Model No. 195-ES-S. Transformer Model No. EL-208-100VA.	
Carrier	Concealed carrier with top and bottom bearing plates and 3" outlet connection; Zurn, J.R. Smith, Josam, Wade, or equal.		

Lavatory: Lavatory shall be ADA accessible, vitreous china, with back, integral perforated grid drain, drilled for 4-inch centers, size 20" x 18", with infrared sensor faucet, overflow tube, and concealed arm carrier, of the following types, or equal:

	Eljer	American Standard	Kohler
Lavatory	"Delwyn" 051-1644	"Lucerin" 0355.012	"Greenwich" K-2032
Drain	803-0552		K-7715
Electronic Faucet	Electronic faucet shall be AC power source with 24 VAC transformer included, ADA compliance with mounting plates.		
	TOTO, TEL3AAC-10 & TN71V1	SLOAN, ETF-600A	K-13662-2E
Carrier	Concealed wall mounted carrier with leveling screws and locking devices; Zurn, J.R. Smith, Josam, Wade, or equal.		

Note: Verify if faucet requires single hole 4" centers.

Water Chiller:

Water chiller shall be standard commercially manufactured remote type, 115 volts AC, air-cooled with an adjustable temperature control dial, and shall produce a minimum of 10gallons of 50°F water per hour based on an inlet water temperature of 80°F and an ambient room temperature of 90°F.

Water chiller compressor shall be hermetically sealed and insulated.

Water chiller shall be Halsey Talor, Elkay, Oasis, or equal.

Drinking Fountain: Drinking fountain shall have approximately 14-inch diameter stainless steel circular receptor and stainless steel combination drain enclosure and mounting bracket. Fountain shall be ADA accessible and be equipped with front push bar operator, 1/4-inch drain, screwdriver stop, bubbler, and vandal resistant bottom plate fasteners. Size requirements shall be as shown on the plans.

PART 3 - EXECUTION

INSTALLATION

All finish for exposed metal on any fixture, including wall flanges, bolts, nuts and washers, shall be polished chrome plated.

Fixtures shall be sealed to wall with silicone caulk bead.

All exposed metal surfaces on fixture supports shall be enameled to harmonize with fixtures.

Wall mounted fixtures shall be installed on concealed carriers designed to support weight of fixture from the floor. Carriers shall be made for the specific fixture to be supported and for the particular installation conditions.

All fixtures shall be provided with accessible compression stops.

Fixture mounting heights: Unless otherwise noted, all fixtures shall be mounted at the heights shown on plans.

Lavatory: Faucet shall be mounted in right-side hole. Unused faucet holes shall be closed with chrome plated covers. Traps shall be installed behind wall in plumbing gallery.

Water chiller: Water chiller shall be installed in the plumbing gallery near the drinking fountains on a galvanized steel wall shelf with brackets, adequately sized and bolted to the wall. Headroom and walking spaces in the plumbing gallery shall be preserved.

Insulation: All water pipe between the water chiller and drinking fountains shall be wrapped with insulating material.

FIELD QUALITY CONTROL

Testing:

The Contractor shall test piping as specified elsewhere in these special provisions.

The Engineer will inspect all installed fixtures for proper installation and test for proper operation after all plumbing work is complete.

SECTION 12-16. ELECTRICAL

12-16.01 ELECTRICAL WORK

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of performing electrical work in accordance with the details shown on the plans and these special provisions.

Electrical work shall include furnishing all labor, materials, equipment and services required to construct and install the complete electrical system shown on the plans and the work of installing electrical connections for the thermostats, motors, and controls specified elsewhere in these special provisions.

System layouts are generally diagrammatic and location of equipment is approximate. Exact routing of conduits and other facilities and location of equipment is to be governed by structural conditions and other obstructions, and shall be coordinated with the work of other trades. Equipment requiring maintenance and inspection shall be located where it is readily accessible for the performance of such maintenance and inspection.

Related Work: Earthwork, foundations, sheet metal, painting, mechanical and such other work incidental to and necessary for the proper installation and operation of the electrical work shall be done in accordance with the requirements specified for similar work elsewhere in these special provisions.

CLOSEOUT SUBMITTALS

Operation and Maintenance Manuals:

Prior to the completion of the contract, 3 identified copies of the operation and maintenance instructions with parts lists for the equipment specified herein shall be delivered to the Engineer at the jobsite. The instructions and parts lists shall be in a bound manual form and shall be complete and adequate for the equipment installed. Inadequate or incomplete material will be returned. The Contractor shall resubmit adequate and complete manuals at no expense to the State.

QUALITY ASSURANCE

Codes and Standards: All work performed and materials installed shall be in accordance with the CEC and the California Code of Regulations, Title 8, Chapter 4, "Electrical Safety Orders."

Warranties and Guarantees: Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

PART 2 - PRODUCTS (Not applicable)

PART 3 - EXECUTION

TESTING

After the electrical system installation work has been completed, the electrical system shall be tested in the presence of the Engineer to demonstrate that the electrical system functions properly. The Contractor shall make necessary repairs, replacements, adjustments and retests at his expense.

12-16.02 BASIC MATERIALS AND METHODS

PART 1 - GENERAL

SUMMARY

Scope: This work shall consist of furnishing and installing conduits, conductors, fittings, and wiring devices in accordance with the details shown on the plans and these special provisions.

Conduits, conductors, fittings, and wiring devices shall include those accessories and appurtenances, not mentioned, that are required for the proper installation and operation of the electrical system.

Related Work:

Roof penetrations shall be flashed and sealed watertight conforming to the requirements specified under "Sheet Metal Flashing" in Section 12-7, "Thermal and Moisture Protection," of these special provisions.

Where conduits pass through fire rated walls, floor or ceiling assemblies, the penetrations shall be protected in accordance with the requirements specified under "Through-Penetration Firestopping" in Section 12-7, "Thermal and Moisture Protection," of these special provisions.

SUBMITTALS

Product Data:

A list of materials and equipment to be installed and the manufacturer's descriptive data shall be submitted for approval. Any other data as requested by the Engineer shall also be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions for recessed junction and pull boxes, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

PART 2 - PRODUCTS

CONDUITS AND FITTINGS

Rigid Steel Conduit and Fittings:

Rigid steel conduit shall be threaded, full weight rigid steel, hot-dip galvanized inside and outside with steel or malleable iron fittings. Fittings shall be threaded unless otherwise specified or shown on the plans.

Split or three-piece couplings shall be electroplated, malleable cast iron couplings.

Insulated grounding bushings shall be threaded malleable cast iron body with plastic insulated throat and steel, lay-in ground lug with compression screw.

Insulated metallic bushings shall be threaded malleable cast iron body with plastic insulated throat.

Electrical Metallic Tubing (EMT) and Fittings:

Electrical metallic tubing shall be formed of cold rolled strip steel, electrical resistance welded continuously along the longitudinal seam with zinc coating outside and enamel or lacquer coating inside.

Couplings shall be electroplated, rain and concrete tight, gland compression type, steel body couplings with malleable iron nuts.

Connectors shall be electroplated, rain and concrete tight, gland compression type, steel body connectors with male hub, malleable iron nut and insulated plastic throat.

Flexible Metallic Conduit and Fittings:

Flexible metallic conduit shall be fabricated in continuous lengths from galvanized steel strip, spirally wound and formed to provide an interlocking design.

Fittings shall be electroplated screw-in type with malleable cast iron body and threaded male hub with insulated throat.

Liquid Tight Flexible Metallic Conduit and Fittings:

Liquid tight flexible metallic conduit shall be fabricated in continuous length from galvanized sheet steel, spirally wound and formed to provide an interlocking design with an extruded polyvinyl chloride cover.

Fittings shall be electroplated, malleable cast iron body, with cap nut, grounding ferrule, and connector body with insulated throat.

CONDUCTORS

Conductors:

Conductors shall be stranded copper wire.

Conductor insulation types unless otherwise shown or specified, shall be as follows:

1. Conductors shall be type XHHW-2 in wet, underground, and outdoor locations.
2. Conductors shall be type THHN in dry locations.

Wire Connections and Devices: Wire connections and devices shall be pressure or compression type, except that connectors for No. 10 AWG and smaller conductors in dry locations may be preinsulated spring-pressure type.

ELECTRICAL BOXES

Outlet, Device and Junction Boxes:

Unless otherwise shown or specified, boxes shall be galvanized steel boxes with knock-outs and shall be the size and configuration best suited to the application indicated on the plans. Minimum size of outlet, receptacle, switch or junction boxes shall be 4 inches square by 1½ inches deep, except that switch boxes for the installation of single switches and outlet boxes for flush-mounted light fixtures shall be 2" x 3" x 1½" deep.

Flush-mounted boxes shall have stainless steel covers, 0.04 inch thick. Cover screws shall be metal with finish to match cover finish.

Unless otherwise shown or specified, surface-mounted boxes shall have galvanized steel covers with metal screws. Sectional device plates will not be permitted.

RECEPTACLES

Ground Fault Circuit Interrupter Receptacles, (GFCI): Ground fault circuit interrupter receptacles shall be NEMA Type 5-20R, feed-through type, ivory color, 3-wire, 20-ampere, 125-volt AC, grounding type, specification grade, duplex receptacle with ground fault interruption. Receptacle shall detect and trip at current leakage of 5 milliamperes and shall have front mounted test and reset buttons.

MISCELLANEOUS MATERIALS

Anchorage Devices: Anchorage devices shall be corrosion resistant, toggle bolts, wood screws, bolts, machine screws, studs, expansion shields, and expansion anchors and inserts.

Electrical Supporting Devices:

Electrical supporting devices shall be one hole conduit clamps with clamp backs, hot-dipped galvanized, malleable cast iron.

Construction channel shall be 1 5/8 inches by 1 5/8 inches, 12-gage galvanized steel channel with 17/32-inch diameter bolt holes, 1½ inches on center in the base of the channel.

PART 3 - EXECUTION

INSTALLATION

Conduit:

Rigid steel conduit shall be used unless otherwise shown on the plans or specified in these special provisions.

Electrical metallic tubing may be used in furred spaces and for exposed work indoors above the switch height.

Unless otherwise specified or shown on the plans, flexible metal conduit shall be used to connect suspended lighting fixtures, motors, HVAC equipment, and other equipment subject to vibration in dry locations.

Unless otherwise specified or shown on the plans, liquid-tight flexible metal conduit shall be used to connect motors, HVAC equipment, and other equipment subject to vibration in wet locations.

Conduit Installation:

Conduit trade sizes are shown on the plans. No deviation from the conduit size shown on the plans will be permitted without written permission from the Engineer.

Conduit shall be concealed unless otherwise shown on the plans.

Conduits shall be tightly covered and well protected during construction using metallic bushings and bushing "pennies" to seal open ends.

Locations of conduit runs shall be planned in advance of the installation and coordinated with the ductwork, plumbing, ceiling and wall construction in the same areas and shall not unnecessarily cross other conduits or pipe, nor prevent removal of ceiling tiles or panels, nor block access to mechanical or electrical equipment.

Where practical, conduits shall be installed in groups in parallel, vertical or horizontal runs and at elevations that avoid unnecessary offsets.

Exposed conduit shall be installed parallel and at right angles to the building lines.

Conduits shall not be placed closer than 12 inches from a parallel hot water or steam pipe or 3 inches from such lines crossing perpendicular to the runs.

All raceway systems shall be secured to the building structures using specified fasteners, clamps and hangers.

All metal conduits, metal conduit risers, and metal conduit elbows in contact with soil or concrete shall be wrapped with a double layer of 20-mil thick pipe wrapping tape. Each individual layer shall be overlapped a minimum of 50%.

Single conduit runs shall be supported by using one hole pipe clamps. Where run horizontally on walls in damp or wet locations, conduit shall be installed with "clamp backs" to space conduit off the surface.

Multiple conduit runs shall be supported with construction channel secured to the building structure. Conduits shall be fastened to construction channel with channel compatible pipe clamps.

Raceways of different types shall be joined using approved couplings or transition fittings.

Expansion couplings shall be installed where conduit crosses a building separation or expansion joint.

All floor and wall penetrations shall be sealed water-tight.

Conduit Terminations:

Rigid steel conduits shall be securely fastened to cabinets, boxes and gutters using 2 locknuts and specified insulating metallic bushing. Electrical metallic tubing shall be securely fastened to cabinets, boxes and gutters using specified connectors. Conduit terminations at exposed weatherproof enclosures and cast outlet boxes shall be made watertight using specified hubs.

Grounding bushings with bonding jumpers shall be installed on all type of conduits terminating at concentric knockouts and on all conduits containing service conductors, grounding electrode conductor, and conductors feeding separate buildings.

All future conduits terminated in underground pull boxes or exposed indoor and outdoor shall be provided with watertight conduit plugs.

Conductor and Cable Installation:

Conductors shall not be installed in conduit until all work of any nature that may cause injury is completed. Care shall be taken in pulling conductors that insulation is not damaged. An approved non-petroleum base and insulating type pulling compound shall be used as needed.

Splices and joints shall be insulated with insulation equivalent to that of the conductor.

Provide 6 inches of slack at each outlet and device connection. If the outlet or device is not at the end of a run of wire, connection shall be made with correctly colored pigtails tapped to the runs with splices as specified herein.

Branch circuit conductors in panelboards and load centers shall be neatly trained along a path from the breaker terminals to their exit point. The conductors shall have ample length to transverse the path without strain, but shall not be so long as to require coiling, doubling back, or cramming. The path shall transverse the panelboard gutter spaces without entering a gutter containing service conductors and, unless otherwise shown on the plans, without entering the gutter space of any panelboard feeder.

All pressure type connectors and lugs shall be retightened after the initial set.

Splices in underground pull boxes and similar locations shall be made watertight.

Junction boxes in furred or accessible ceiling spaces shall be identified with felt-tip pen denoting the circuits contained in the box.

Conductor Identification:

The neutral and equipment grounding conductors shall be identified as follows:

Neutral conductor shall have a white or natural gray insulation except that conductors No. 4 and larger may be identified by distinctive white marker such as paint or white tape at each termination.

Equipment grounding conductor shall be bare or insulated. If insulated, equipment grounding conductors shall have green or green with one or more yellow stripes insulation over its entire length except that conductors No. 4 and larger may be permanently identified by distinctive green markers such as paint or green tape over its entire exposed insulation.

SYSTEM	COLOR CODE
120/240 V-Single phase	Black, blue

Once an insulated circuit conductor, including grounded and ungrounded conductors, is identified with a specific color code, that color code shall be used for the entire length of the circuit.

Where more than one branch circuit enters or leaves a conduit, panel, gutter, or junction box, each conductor shall be identified by its panelboard and circuit number. All control conductors including control conductors of manufacturer supplied and field wired control devices shall be identified at each termination with the wire numbers shown on the plans, approved working drawings, and as directed by the Engineer where deemed necessary. Identification shall be made with one of the following:

1. Adhesive backed paper or cloth wrap-around markers with clear, heat shrinkable tubing sealed over either type of marker.
2. Self-laminating wrap around type, printable, transparent, permanent heat bonding type thermoplastic film markers.
3. Pre-printed, white, heat-shrinkable tubing.

Each terminal block shall have a molded marking strip attached with screws. The identifying numbers of the terminating conductors, as shown on the plans or on the submittal drawings, shall be engraved in the marking strip.

Outlet, Device and Junction Box Installation:

Where exposed threaded steel conduits are connected to an outlet, device, or junction box below switch height, the box shall be a cast metal box. Unless otherwise shown on the plans or specified in these special provisions, all other boxes shall be sheet steel boxes. Weatherproof outlet, device and junction boxes shall have cast metal covers with gaskets. Unless otherwise shown on the plans or specified in these special provisions, all other boxes shall have standard galvanized covers.

All boxes shall finish flush with building walls, ceiling and floors except where exposed work is called for.

Raised device covers (plaster rings) shall be installed on all boxes concealed in concrete, masonry or stud walls.

No unused openings shall be left in any box. Knockout seals shall be installed as required to close openings.

Outlet, device, and junction boxes shall be installed at the locations and elevations shown on the plans or specified herein. Adjustments to locations may be made as required by structural conditions and to suit coordination requirements of other trades.

Boxes in stud walls and partitions shall not be mounted back to back. Through-wall boxes shall not be used.

Boxes installed in metal stud walls shall be equipped with brackets designed for attaching directly to the studs or shall be mounted on heavy gauge galvanized steel, snap-in box supports.

Fixture outlet boxes installed in suspended ceilings of gypsum board or lath and plaster construction shall be mounted on 16-gage metal channel bars attached to main ceiling runners.

Fixture outlet boxes for pendant-mounted fixtures installed in suspended ceilings supporting acoustical tiles or panels shall be supported directly from the structures above.

Anchorage:

Hangers, brackets, conduit straps, supports, and electrical equipment shall be rigidly and securely fastened to surfaces by means of toggle bolts on hollow masonry; expansion shields and machine screws, or expansion anchors and studs or standard preset inserts on concrete or solid masonry; machine screws or bolts on metal surfaces; and wood or lag screws on wood construction.

Anchorage devices shall be installed in accordance with the anchorage manufacturer's recommendations.

Mounting heights: Electrical system components shall be mounted as shown on the plans.

16.03 LIGHTING

PART 1 – GENERAL

Scope: This work shall consist of furnishing, installing and connecting all lighting equipment in accordance with the details shown on the plans and these special provisions.

SUBMITTALS

Manufacturer's descriptive information, photometric curves, catalog cuts, and installation instructions shall be submitted for approval. Any other data as requested by the Engineer shall also be submitted for approval.

PART 2 - PRODUCTS

Lighting Fixture Lamps: Lighting fixture lamps shall be type and size as shown on the plans. Lamps shall be General Electric, Phillips, Sylvania, or equal. Fluorescent lamps, unless otherwise noted, shall be 4100K tri-phosphor with a CRI of 70 or greater.

Ballasts: All fixtures shall be equipped with high power factor ballasts suitable for the line voltage and for the type, size and number of lamps required by the fixture. Fluorescent ballasts shall be UL Listed, Class P and ETL Certified ballasts with sound rating A. Fluorescent ballasts shall be high-frequency electronic ballasts with power factor greater than 0.95, nominal ballast factor of 0.88 unless specified otherwise, total harmonic distortion less than 20 percent, crest factor less than or equal to 1.7, complying with ANSI C 62.41 Category A for surge protection, and FCC Part 18 for interference. Dimming ballasts shall be high frequency ballasts as specified above and shall be capable of dimming the light output from 100 percent to 20 percent of the rated light output.

Lighting Fixtures: Lighting fixtures shall be as shown on the plans and as specified herein. Outdoor luminaires shall be listed and labeled "Fixture Suitable For Wet Locations."

F1: Stem or bracket mounted fluorescent fixture with two 32-watt T8 lamps, 120-volts electronic ballast, white body finish and one-piece, acrylic diffuser, complete with end plates. The fixture shall be Lithonia, M series; Day Brite, SM series; or equal.

F2: Surface mounted narrow striplight, fluorescent fixture with one 32-watt T8 lamp, electronic ballast and high-gloss, baked enamel finish. The fixture shall be Lithonia, S series; Day Brite, N series; or equal.

MH: Ceiling mounted, 100-watt, 120-volt metal halide luminaire with integral ballast at location as shown on plans. The luminaire shall be vandal-resistant with clear prismatic polycarbonate lens. Housing shall be constructed from 16-gauge steel. Diffuser shall be secured by tamper-resistant screws. Two screwdrivers for tamperproof screws shall be furnished and delivered to the engineer. Luminaire shall be UL listed for wet locations. The luminaire shall be Lithonia, VR3C series; Day Brite, CLI series or equal.

PART 3 - EXECUTION

Lighting Fixtures:

Lighting fixtures shall be mounted securely in accordance with the manufacturer's recommendations. Mounting methods shall be suitable for the particular type of ceiling or support at each location.

The Contractor shall provide all supports, hangers, spacers, channels, fasteners and other hardware necessary to support the fixtures.

Fixtures shall be set at the mounting heights shown on the plans, except heights shown shall be adjusted to meet conditions.

Ballasts:

All fluorescent fixtures shall be equipped with high power factor ballasts suitable for the line voltage and for the type, size and number of lamps required by fixture. The Contractor has the option to install low voltage dimming control provided that the Contractor submit plans and specifications with appropriate revisions for the low voltage dimming control to the Engineers for approval prior to installation.

All ballasts used in unheated areas inside the building shall be 0°F ballasts or less.

WALL MOUNTED OCCUPANCY SENSOR

Wall mounted occupancy sensor shall be a low voltage, passive infrared (PIR) sensor switch. Switch shall have an adjustable photocell override and time delay. Switch shall operate on 24 V(dc) and shall be provided with a power pack unit. The sensor switch shall cover a minimum of 90 feet long by 16 feet wide when mounted at 10 feet high. The time delay off setting shall be adjustable from 30 seconds to 30 minutes, initially set at 10 minutes. Light level adjustment shall be adjustable from 3 to 200 footcandles, initially set at 80 footcandles. Switch shall be provided with a swivel mounting bracket or a twist and lock base mounting hardware for fast alignments.

POWER PACK UNIT

Power pack unit shall be a combination 24 V(dc) power supply and a 20 A line voltage relay. Power supply shall be a self-contained transformer with 24 V(dc) and minimum 150 mA output. Input voltage to power pack unit shall be suitable for 120/277 V(ac). Relay shall be Class B (130 °C) insulating material and have a contact rating of 20 A at 120/277 V(ac). Power pack unit and occupancy sensor shall be from the same manufacturer. Power pack unit shall be mounted inside a junction box.

WALL MOUNTED OCCUPANCY SENSORS

Occupancy sensors shall be mounted securely in accordance to manufacturer's recommendations. Contractor shall provide all supports, hangers, spacers, channels, fasteners and other necessary hardware to support the sensors. Final location of sensors shall be per manufacturer's recommendations to provide the best coverage for the application. All power packs and auxiliary packs shall be mounted inside an appropriately sized junction boxes or NEMA Type 1 enclosures. All splices or connections shall be made inside the junction box or enclosure.

AMENDMENTS TO THE STANDARD SPECIFICATIONS
DATED MAY 2006
(Issued 09-19-08)

1-2 REFERENCES

1-2.01 REFERENCES

A reference within parentheses to a law or regulation is included in the contract for convenience only and is not a comprehensive listing of related laws and regulations. Lack of a reference does not indicate no related laws or regulations exist.

If the version of a referenced document is not specified, use the current version in effect on the date of Notice to Bidders.

A reference to a subsection includes the section's general specifications of which the subsection is a part.

A code not specified as a Federal code is a California code.

1-3 ABBREVIATIONS AND MEASUREMENT UNITS

1-3.01 ABBREVIATIONS

Abbreviations	
Abbreviation	Meaning
AAN	American Association of Nurserymen
AASHTO	American Association of State Highway and Transportation Officials
AISC	American Institute of Steel Construction
AISI	American Iron and Steel Institute
ANSI	American National Standards Institute
APHA	American Public Health Association
API	American Petroleum Institute
AREMA	American Railway Engineering and Maintenance-of-Way Association
ASME	American Society of Mechanical Engineers
ASTM	American Society for Testing and Materials
AWG	American Wire Gage
AWPA	American Wood-Preservers' Association
AWS	American Welding Society
AWWA	American Water Works Association
CIH	Certified Industrial Hygienist
DBE	Disadvantaged Business Enterprise
DVBE	Disabled Veteran Business Enterprise
EIA	Electronic Industries Alliance
ETL	Electrical Testing Laboratories
FHWA	Federal Highway Administration
IEEE	Institute of Electrical and Electronics Engineers
NETA	National Electrical Testing Association, Inc.
NEMA	National Electrical Manufacturers Association
PLAC	permit, license, agreement, certification, or any combination of these
SSPC	The Society for Protective Coatings
UL	Underwriters' Laboratories Inc.

1-3.02 MEASUREMENT UNITS

Measurement Units		
Symbols as used in the specifications	Symbols as used in the Bid Item List	Meaning
A	—	amperes
	ACRE	acre
	CF	cubic foot
	CY	cubic yard
--	EA	each
g	--	gram
ksi	--	kips per square inch
	GAL	gallon
h	H	hour
	LB	pound
--	LS	lump sum
	LF	linear foot
	LNMI	lane mile
	MFBM	thousand foot board measure
	MI	mile
	MSYD	thousand station yard
Ω	--	ohm
pcf	--	pounds per cubic foot
s	--	second
	STA	100 feet
	SQFT	square foot
	SQYD	square yard
	TAB	tablet
ton	TON	2,000 pounds
W	--	watt
V	--	volt

1-4 DEFINITIONS

1-4.01 GENERAL

Interpret terms as defined in the contract documents. A construction-industry term not defined in the contract documents has the meaning defined in Means Illustrated Construction Dictionary, Condensed Version, Second Edition.

1-4.02 GLOSSARY

acceptance: Formal written acceptance by the Director of an entire contract that has been completed in all respects in accordance with the plans and specifications and any modifications to them previously approved.

base: Layer of specified material of planned thickness placed immediately below the pavement or surfacing.

basement material: Material in excavation or embankments underlying the lowest layer of subbase, base, pavement, surfacing, or other specified layer to be placed.

bid item: Specific work unit for which the bidder provides a price.

Bid Item List: List of bid items and the associated quantities.

Bid Item List, verified: Bid Item List with verified prices. The Contract Proposal of Low Bidder at the Department's Web site is the verified Bid Item List.

bridge: Structure, with a bridge number, that carries a utility facility, or railroad, highway, pedestrian or other traffic, over a water course or over or under or around any obstruction.

building-construction contract: Contract that has "building construction" on the cover of the Notice to Bidders and Special Provisions.

business day: Day on the calendar except Saturday or holiday.

California Manual on Uniform Traffic Control Devices: The California Manual on Uniform Traffic Control Devices for Streets and Highways (California MUTCD) is issued by the Department of Transportation and is the Federal Highway Administration's MUTCD 2003 Edition, as amended for use in California.

Certified Industrial Hygienist: Industrial hygienist certified in comprehensive practice by the American Board of Industrial Hygiene.

conduit: Pipe or tube in which smaller pipes, tubes, or electrical conductors are inserted or are to be inserted.

contract: Written and executed contract between the Department and the Contractor.

contract bonds: Security for the payment of workers and suppliers furnishing materials, labor, and services and for guaranteeing the Contractor's work performance.

contract item: Bid item.

Contractor: Person or business or its legal representative entering into a contract with the Department for performance of the work.

culvert: Structure, other than a bridge, that provides an opening under a roadway for drainage or other purposes.

day: 24 consecutive hours running from midnight to midnight; calendar day.

deduction: Amount of money permanently taken from progress payment and final payment. Deductions are not retentions under Pub Cont Code § 7107.

Department: Department of Transportation as defined in St & Hwy Code § 20 and authorized in St & Hwy Code § 90; its authorized representatives.

detour: Temporary route for traffic around a closed road part. A passageway through a job site is not a detour.

Director: Department's Director.

Disabled Veteran Business Enterprise: Business certified as a DVBE by the Office of Small Business and DVBE Services, Department of General Services.

divided highway: Highway with separated traveled ways for traffic, generally in opposite directions.

Engineer: Department's Chief Engineer acting either directly or through properly authorized agents; the agents acting within the scope of the particular duties delegated to them.

Federal-aid contract: Contract that has a Federal-aid project number on the cover of the Notice to Bidders and Special Provisions.

fixed costs: Labor, material, or equipment cost directly incurred by the Contractor as a result of performing or supplying a particular bid item that remains constant regardless of the item's quantity.

frontage road: Local street or road auxiliary to and located generally on the side of an arterial highway for service to abutting property and adjacent areas and for control of access.

grading plane: Basement material surface on which the lowest layer of subbase, base, pavement, surfacing, or other specified layer is placed.

highway: Whole right of way or area that is reserved for and secured for use in constructing the roadway and its appurtenances.

holiday:

1. Every Sunday
2. January 1st, New Year's Day
3. 3rd Monday in January, Birthday of Martin Luther King, Jr.
4. February 12th, Lincoln's Birthday
5. 3rd Monday in February, Washington's Birthday
6. March 31st, Cesar Chavez Day
7. Last Monday in May, Memorial Day
8. July 4th, Independence Day
9. 1st Monday in September, Labor Day
10. 2nd Monday in October, Columbus Day
11. November 11th, Veterans Day
12. 4th Thursday in November, Thanksgiving Day
13. Day after Thanksgiving Day
14. December 25th, Christmas Day

If January 1st, February 12th, March 31st, July 4th, November 11th, or December 25th falls on a Sunday, the Monday following is a holiday. If November 11th falls on a Saturday, the preceding Friday is a holiday. Interpret "legal holiday" as "holiday."

informal-bid contract: Contract that has "Informal Bid Authorized by Pub Cont Code §10122" on the cover of the Notice to Bidders and Special Provisions.

Information Handout: Supplemental project information furnished to bidders as a handout.

laboratory: Laboratory authorized by the Department to test materials.

liquidated damages: Amount prescribed in the specifications, pursuant to the authority of Pub Cont Code § 10226, to be paid to the State or to be deducted for each day's delay in completing the whole or any specified portion of the work beyond the time allowed in the specifications.

median: Portion of a divided highway separating the traveled ways for traffic in opposite directions including inside shoulders.

Notice to Bidders: Document that provides a general work description, bidder and bid specifications, and the time and location the Department receives bids.

pavement: Uppermost layer of material placed on the traveled way or shoulders. This term is used interchangeably with surfacing.

plans: Official project plans and Standard Plans, profiles, typical cross sections, working drawings and supplemental drawings, or reproductions thereof, approved by the Engineer, which show the location, character, dimensions and details of the work to be performed. These documents are to be considered as a part of the plans.
In the above definition, the following terms are defined as follows:
Standard Plans: Standard Plans issued by the Department.
project plans: Specific details and dimensions peculiar to the work supplemented by the Standard Plans insofar as the same may apply.

roadbed: Area between the intersection of the upper surface of the roadway and the side slopes or curb lines. The roadbed rises in elevation as each increment or layer of subbase, base, surfacing or pavement is placed. Where the medians are so wide as to include areas of undisturbed land, a divided highway is considered as including 2 separate roadbeds.

roadway: Highway portion included between the outside lines of sidewalks, or curbs, slopes, ditches, channels, waterways, and including all the appertaining structures, and other features necessary to proper drainage and protection.

shoulder: Roadway portion contiguous with the traveled way for accommodation of stopped vehicles, for emergency use, and for lateral support of base and surface courses.

special provisions: Specific clauses setting forth conditions or requirements peculiar to the work and supplementary to these Standard Specifications. The Department's publication titled "Labor Surcharge And Equipment Rental Rates" is part of the special provisions.

specifications: Directions, provisions, and requirements contained in these Standard Specifications, Amendments to the Standard Specifications, and the special provisions. Where the term "these specifications" or "these Standard Specifications" is used in this book, it means the provisions set forth in this book.

State: State of California, including its agencies, departments, or divisions, whose conduct or action is related to the work.

Structure Design: Offices of Structure Design of the Department.

subbase: Layer of specified material of planned thickness between a base and the basement material.

subgrade: Roadbed portion on which pavement, surfacing, base, subbase, or a layer of any other material is placed.

substructure: Bridge portions below the bridge seats, tops of piers, haunches of rigid frames, or below the spring lines of arches. Backwalls and parapets of abutments and wingwalls of bridges are portions of the substructure.

superstructure: Bridge portion except the bridge substructure.

supplemental project information: Information relevant to the project, specified as supplemental project information, and made available to bidders.

surfacing: Uppermost layer of material placed on the traveled way, or shoulders. This term is used interchangeably with pavement.

traffic lane: Portion of a traveled way for the movement of a single line of vehicles.

traveled way: Portion of the roadway for the movement of vehicles, exclusive of shoulders.

total bid: Sum of the item totals as verified by the Department; original contract price.

withhold: Money temporarily or permanently taken from progress payment. Withholds are not retentions under Pub Cont Code § 7107.

work: All the work specified, indicated, shown or contemplated in the contract to construct the improvement, including all alterations, amendments, or extensions to it made by contract change order or other written orders of the Engineer.

1-5 DISTRICTS

District Composition and Office Addresses

District	Counties	Location Address	Mailing Address
1	Del Norte (DN), Humboldt (Hum), Lake (Lak), Mendocino (Men)	1656 UNION ST EUREKA, CA	PO BOX 3700 EUREKA CA 95502
2	Lassen (Las), Modoc (Mod), Plumas (Plu), Shasta (Sha), Siskiyou (Sis), Tehama (Teh), Trinity (Tri)	1657 RIVERSIDE DR REDDING, CA	PO BOX 496073 REDDING CA 96049-6073
3	Butte (But), Colusa (Col), El Dorado (ED), Glenn (Gle), Nevada (Nev), Placer (Pla), Sacramento (Sac), Sierra (Sie), Sutter (Sut), Yolo (Yol), Yuba (Yub)	703 B ST MARYSVILLE, CA	PO BOX 911 MARYSVILLE CA 95901
4	Alameda (Ala), Contra Costa (CC), Marin (Mrn), Napa (Nap), San Francisco (SF), San Mateo (SM), Santa Clara (SCI), Solano (Sol), Sonoma (Son)	111 GRAND AVE OAKLAND, CA	PO BOX 23660 OAKLAND CA 94623-0660
5	Monterey (Mon), San Benito (SBt), San Luis Obispo (SLO), Santa Barbara (SB), Santa Cruz (SCr)	50 HIGUERA ST SAN LUIS OBISPO, CA	50 HIGUERA ST SAN LUIS OBISPO CA 93401-5415
6	Fresno (Fre), Kern (Ker), Kings (Kin), Madera (Mad), Tulare (Tul)	1352 W. OLIVE AVE FRESNO, CA	PO BOX 12616 FRESNO CA 93728-2616
7	Los Angeles (LA), Ventura (Ven)	100 S. MAIN ST LOS ANGELES	100 S MAIN ST LOS ANGELES CA 90012
8	Riverside (Riv), San Bernardino (SBd)	464 W 4TH ST SAN BERNARDINO, CA	464 W 4TH ST SAN BERNARDINO CA 92401-1400
9	Inyo (Iny), Mono (Mno)	500 S MAIN ST BISHOP, CA	500 S MAIN ST BISHOP CA 93514-3423
10	Alpine (Alp), Amador (Ama), Calaveras (Cal), Mariposa (Mpa), Merced (Mer), San Joaquin (SJ), Stanislaus (Sta), Tuolumne (Tuo)	1976 E CHARTER WAY STOCKTON, CA	PO BOX 2048 STOCKTON CA 95201
11	Imperial (Imp), San Diego (SD)	4050 TAYLOR ST SAN DIEGO, CA	4050 TAYLOR ST SAN DIEGO CA 92110-2737
12	Orange (Ora)	3347 MICHELSON DR STE 100 IRVINE, CA	3347 MICHELSON DR STE 100 IRVINE CA 92612-0661

A project with work in District 1, 2, or 3 is a North Region project. For Districts 1, 2, and 3, interpret each reference to the district office as the North Region office. The North Region office address is the District 3 address.

1-6 WEB SITES, ADDRESSES, AND TELEPHONE NUMBERS

Web Sites, Addresses, and Telephone Numbers

Agency, Department Unit, or Reference	Web Site	Address	Telephone No.
Bid Document Unit		MSC 26 BID DOCUMENT UNIT DEPARTMENT OF TRANSPORTATION 1120 N ST RM 200 SACRAMENTO CA 95814-5605	
Department	www.dot.ca.gov		
Department of General Services, Office of Small Business and DVBE Services	www.pd.dgs.ca.gov/smbus/default.htm	OFFICE OF SMALL BUSINESS AND DVBE SERVICES DEPARTMENT OF GENERAL SERVICES 707 3RD ST WEST SACRAMENTO CA 95605-2811	(800) 559-5529 (916) 375-4940
Department of Industrial Relations	www.dir.ca.gov		
Department of Industrial Relations, Division of Apprenticeship Standards		455 GOLDEN GATE AVENUE SAN FRANCISCO, CA 94102	
Office Engineer		MSC 43 OFFICE ENGINEER DEPARTMENT OF TRANSPORTATION 1727 30TH ST SACRAMENTO CA 95816-7005	
Office Engineer– Verified Bid Results	http://www.dot.ca.gov/hq/esc/oe/awards/bidsum_html/6week_list.html		
Offices of Structure Design, Documents Unit		MSC 9-4/4I DOCUMENTS UNIT OFFICES OF STRUCTURE DESIGN DEPARTMENT OF TRANSPORTATION 1801 30TH ST SACRAMENTO CA 95816-7006	(916) 227-8252
Publication Distribution Unit		PUBLICATION UNIT DEPARTMENT OF TRANSPORTATION 1900 ROYAL OAKS DRIVE SACRAMENTO CA 95815-3800	
Transportation Laboratory		MATERIALS AND ENGINEERING TESTING SERVICES AND GEOTECHNICAL SERVICES DEPARTMENT OF TRANSPORTATION 5900 FOLSOM BLVD SACRAMENTO CA 95819-4612	(916) 227-7000
Department's Pre- Qualified Products List	http://www.dot.ca.gov/hq/esc/approved_products_list		

2-1.04 SMALL BUSINESS ENTERPRISE GOAL

The Department has established an overall 25 percent small business participation goal. To determine if the goal is achieved, the Department is tracking small business participation on all contracts.

Contractors, subcontractors, suppliers, and service providers who qualify as small business are encouraged to apply for certification as a small business by submitting their application to the Department of General Services, Office of Small Business and DVBE Services.

2-1.05 DISADVANTAGED BUSINESS ENTERPRISES

Section 2-1.05, "Disadvantaged Business Enterprises," applies to a Federal-aid contract.
Under 49 CFR 26.13(b):

The contractor, sub recipient or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR part 26 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate.

In order to ensure the Department achieves its federally mandated statewide overall DBE goal, the Department encourages the participation of DBEs as defined in 49 CFR 26.

2-1.06 DISABLED VETERAN BUSINESS ENTERPRISES

2-1.06A General

Section 2-1.06, "Disabled Veteran Business Enterprises," applies to a non-Federal-aid contract.
Take necessary and reasonable steps to ensure that DVBEs have opportunity to participate in the contract.
Comply with Mil & Vet Code § 999 et seq.

2-1.06B No Goal

Section 2-1.06B, "No Goal," applies if no DVBE goal is shown in the Notice to Bidders.
The Department encourages bidders to obtain DVBE participation in order to ensure the Department achieves its State-mandated overall DVBE goal.

2-1.06C Goal

Section 2-1.06C, "Goal," applies if a DVBE goal is shown in the Notice to Bidders.
Make work available to DVBEs and select work parts consistent with available DVBE subcontractors and suppliers.
Meet the goal shown or demonstrate that you made good faith efforts to meet this goal.
If a DVBE joint venture is used, submit the joint venture agreement with the Certified DVBE Subcontractor Summary form.
The Department determines a bidder has made good faith efforts if it submits evidence within the specified time that it:

1. Contacted the Office of Small Business and DVBE Services, Department of General Services
2. Advertised in trade media and media focusing on DVBEs unless time limits the Department imposes do not allow the advertising
3. Submitted invitations to bid to potential DVBE contractors
4. Considered available DVBEs

2-1.07 SMALL BUSINESS AND NON-SMALL BUSINESS SUBCONTRACTOR PREFERENCES (GOVT CODE § 14835 ET SEQ. AND 2 CA CODE OF REGS § 1896 ET SEQ.)

2-1.07A General

Section 2-1.07, "Small Business and Non-Small Business Subcontractor Preferences (Govt Code § 14835 et seq. and 2 CA Code of Regs § 1896 et seq.)," applies to a non-Federal-aid contract.

2-1.07B Small Business Preference

The Department allows a bidder certified as a small business by the Office of Small Business and DVBE Services, Department of General Services, a preference if:

1. You completed a Request for Small Business Preference or Non-Small Business Preference form

2. You attached a copy of your Office of Small Business and DVBE Services small business certification to the form
3. The apparent low bidder is not certified as a small business

The bidder's signature on the Request for Small Business Preference or Non-Small Business Preference form certifies that the bidder is certified as a small business at the time and day of bid or has submitted a complete application to the Department of General Services. The complete application and any required substantiating documentation must be received by the Department of General Services by 5:00 p.m. on bid opening date.

The Department of General Services determines if a bidder was certified on bid opening date. The Department confirms the bidder's status as a small business before applying the small business preference.

The small business preference is a reduction for bid comparison in the total bid submitted by the small business subcontractor by the lesser of:

1. 5 percent of the verified total bid of the apparent low bidder
2. \$50,000

If this reduction results in the small business contractor becoming the low bidder, the contract award is based on the total bid, not the reduced bid.

2-1.07C Non-Small Business Subcontractor Preference

The Department allows a bidder not certified as a small business by the Office of Small Business and DVBE Services, Department of General Services, a preference if:

1. You completed a Request for Small Business Preference or Non-Small Business Preference form
2. The apparent low bidder is not certified as a small business and has not requested preference

The listed subcontractors and suppliers must be certified as a small business at the time and day of bid or must have submitted a complete application to the Department of General Services. The complete application and any required substantiating documentation must be received by the Department of General Services by 5:00 p.m. on bid opening date.

The Department of General Services determines if a bidder was certified on bid opening date. The Department confirms the bidder's status as a small business before applying the small business preference.

The non-small business subcontractor preference is a reduction for bid comparison in the total bid submitted by the non-small business contractor requesting the preference by the lesser of:

1. 5 percent of the verified total bid of the apparent low bidder
2. \$50,000

If this reduction results in the non-small business contractor becoming the low bidder or a tie with a non-small business apparent low bidder not requesting the preference, the contract award is based on the total bid, not the reduced bid.

2-1.08 DVBE INCENTIVE EVALUATION

The Department applies the Small Business and Non-Small Business preference during bid verification and proceeds with the following evaluation for DVBE incentive.

The Department grants a DVBE incentive to bidders who achieve a DVBE participation of 1 percent or greater of the value of their bid (Mil & Vet Code and Code of Regs § 1896.98 et seq).

The DVBE incentive is a reduction, for bid comparison only, in the total bid submitted by the lesser of:

1. Percentage of DVBE achievement, rounded to 2 decimal places, of the verified total bid of the original low bidder
2. 5 percent of the verified total bid of the original low bidder
3. \$100,000

The Department applies DVBE incentive and determines if bid ranking changes.

A non-small business bidder cannot displace a small business bidder. However, a small business bidder with higher DVBE achievement can displace another small business bidder.

The Department proceeds with awarding the contract to the new apparent low bidder and posts the new verified bid results at its Office Engineer Web site.

2-1.09 PREFERENCE HIERARCHY

If a small business bidder and a non-small business bidder request preferences and the reductions result in a tied bid, the Department awards the contract to the small business bidder.

If a DVBE bidder and a non-DVBE bidder request preferences and the reduction results in a tied bid, the Department awards the contract to the DVBE bidder.

2-1.10 CALIFORNIA COMPANIES

Under Pub Cont Code § 6107, the Department gives preference to a "California company," as defined, for bid comparison purposes over a nonresident contractor from any state that gives or requires a preference to be given contractors from that state on its public entity construction contracts.

Complete a California Company Preference form.

The California company reciprocal preference amount is equal to the preference amount applied by the state of the nonresident contractor with the lowest responsive bid unless the California company is eligible for a small business preference or a non-small business subcontractor preference; in which case the preference amount is the greater of the two, but not both.

If the bidder submitting the lowest responsive bid is a California company and with the reciprocal preference, a California company's responsive bid is equal to or less than the original lowest responsive bid, the Department awards the contract to the California company on the basis of its total bid, not the reduced bid used for comparison except as specified in Section 2-1.09, "Preference Hierarchy."

2-1.11 JOB SITE AND DOCUMENT EXAMINATION

Examine the job site and bid documents.

Bid submission is your acknowledgment that you have examined the job site and bid documents and are satisfied with:

1. General and local conditions to be encountered
2. Character, quality, and scope of work to be performed
3. Quantities of materials to be furnished
4. Character, quality, and quantity of surface and subsurface materials or obstacles
5. Requirements of the contract

2-1.12 BID DOCUMENT COMPLETION

2-1.12A General

Complete forms in the Bid book. Submit the forms with your bid except:

1. For the following 2 forms for non-federal-aid non-informal-bid contracts:
 - 1.1. Certified DVBE Summary form. You may submit this form with your bid. If you do not and you are the apparent low bidder or the second or third low bidder, submit it so that it is received at the Office Engineer no later than 4:00 p.m. on the 4th business day after bid opening. If you are not the apparent low bidder or the second or third low bidder, you are not required to submit this form unless the Department asks for it.
 - 1.2. Certified Small Business Subcontractor form. If you are applying for the non-small business subcontractor preference, you may submit this information with your bid. If you do not, submit it so that it is received at the Office Engineer no later than 4:00 p.m. on the 2nd business day after bid opening.
2. On the Subcontractor List you may either submit the percentage of each bid item subcontracted with your bid or fax the percentage to (916) 227-6282 within 24 hours after bid opening.

Except for the percentage of each bid item subcontracted, do not fax submittals.

2-1.12B Bid Item List and Bid Comparison

Submit a bid based on the work item quantities the Department shows in the Bid Item List.

For a lump sum based bid, the Department compares bids based on the total price.

For a unit price based bid, the Department compares bids based on the sum of the item totals.

For a cost plus time based bid, the Department compares bids based on the sum of the item totals and the total bid for time.

2-1.12C Subcontractor List

In the Subcontractor List, list each subcontractor to perform work in an amount in excess of 1/2 of 1 percent of the total bid or \$10,000, whichever is greater (Pub Cont Code § 4100 et seq.). The Subcontractor List must show the name, address, and work portions to be performed by each subcontractor listed. Show work portion by bid item number, description, and percentage of each bid item subcontracted.

2-1.13 BIDDER'S SECURITY

Submit your bid with one of the following forms of bidder's security equal to at least 10 percent of the bid:

1. Cash
2. Cashier's check
3. Certified check
4. Bidder's bond signed by a surety insurer who is licensed in California

Make checks and bonds payable to the Department of Transportation.

If paying with a bidder's bond, you may use the form in the Bid book. If you do not use the form in the Bid book, use a form containing the same information.

2-1.14 BID SUBMITTAL

Submit your bid:

1. Under sealed cover
2. Marked as a bid
3. Identifying the contract number and the bid opening date

If an agent other than the authorized corporation officer or a partnership member signs the bid, file a Power of Attorney with the Department either before opening bids or with the bid. Otherwise, the bid may be nonresponsive.

2-1.15 BID WITHDRAWAL

You or an authorized agent may withdraw a bid before the bid opening date and time by submitting a written bid withdrawal request at the location where the bid was submitted. Withdrawing a bid does not prevent you from submitting a new bid.

After the bid opening time, you cannot withdraw a bid.

2-1.16 BID OPENING

The Department publicly opens and reads bids at the time and place described in the Notice to Bidders. The Department invites bidders or their authorized agents to attend.

2-1.17 BID REJECTION

The Department may reject:

1. All bids
2. A nonresponsive bid

2-1.18 BID RELIEF

The Department may grant bid relief under Pub Cont Code § 5100 et seq. Submit any request for bid relief to the Office Engineer. For Relief of Bid Request form, go to:

http://www.dot.ca.gov/hq/esc/oe/contractor_info/relief.pdf

2-1.19 SUBMITTAL FAILURE HISTORY

The Department considers a bidder's past failure to submit documents required after bid opening in determining a bidder's responsibility.

2-1.20 BID RIGGING

Section 2-1.20, "Bid Rigging," applies to a Federal-aid contract.

with Section 7-1.12, "Indemnification and Insurance." Allowance of additional exclusions is at the discretion of the Department.

2. Certificate of insurance showing all other required coverages. Certificates of insurance, as evidence of required insurance for the auto liability and any other required policy, shall set forth deductible amounts applicable to each policy and all exclusions that are added by endorsement to each policy. The evidence of insurance shall provide that no cancellation, lapse, or reduction of coverage will occur without 10 days prior written notice to the Department.
3. A declaration under the penalty of perjury by a CPA certifying the accountant has applied GAAP guidelines confirming the successful bidder has sufficient funds and resources to cover any self-insured retentions if the self-insured retention is \$50,000 or higher.

If the successful bidder uses any form of self-insurance for workers compensation in lieu of an insurance policy, it shall submit a certificate of consent to self-insure under Labor Code § 3700.

3-1.06 SMALL BUSINESS PARTICIPATION REPORT

A Small Business Participation Report will be included in the contract documents to be executed by the successful bidder. The purpose of this form is to collect small business participation data. Even if no small business participation is reported, the successful bidder must execute and return the form.

3-1.07 PAYEE DATA RECORD

The Department includes a Payee Data Record in the contract documents to be signed by the successful bidder, the payee. Complete the form.

3-1.08 CALTRANS BIDDER - DBE INFORMATION FORM

Section 3-1.08, "Caltrans Bidder - DBE Information Form," applies to a Federal-aid contract.

The Department includes a Caltrans Bidder - DBE Information form in the contract documents to be completed and signed by the successful bidder.

The purpose of this form is to collect data required under 49 CFR 26.

The Department encourages you to provide written confirmation from each DBE that the DBE is participating in the contract. A copy of a DBE's quote serves as written confirmation. If a DBE is participating as a joint venture partner, the Department encourages you to submit a copy of the joint venture agreement.

3-1.09 CONTRACT EXECUTION

The successful bidder must sign the contract.

Deliver to the Office Engineer:

1. Signed Contract form
2. Contract bonds
3. Documents identified in Section 3-1.05, "Insurance Policies"
4. Small Business Participation Report
5. Payee data record
6. For a Federal-aid contract, Caltrans Bidder - DBE Information form

For a non-informal-bid contract, the Office Engineer must receive these documents before the 10th business day after the bidder receives the contract.

For an informal-bid contract, the Office Engineer must receive these documents before the 5th business day after the bidder receives the contract.

The bidder's security may be forfeited for failure to execute the contract (Pub Cont Code §§ 10181 and 10182).

The following is a copy of the Contract form:



STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION
CONTRACT NO. _____

This contract is entered into between the State of California's Department of Transportation and the Contractor named below:

CONTRACTOR'S NAME

The parties agree to comply with the terms of the following exhibits that are by this reference made a part of this contract.

- Exhibit A - Bid book dated _____
- Exhibit B - Notice to Bidders and Special Provisions dated _____
- Exhibit C - Project Plans approved _____
- Exhibit D - Standard Specifications dated _____
- Exhibit E - Standard Plans dated _____
- Exhibit F - Addenda

Exhibits A, B, C, and F are those exhibits identified with the same contract number as this contract.

This contract has been executed by the following parties:

CONTRACTOR

CONTRACTOR'S NAME (if other than an individual, state whether a corporation, partnership, etc.)

BY (Authorized Signature)

DATE SIGNED (Do not type)

PRINTED NAME AND TITLE OF PERSON SIGNING

FEDERAL EMPLOYER IDENTIFICATION NUMBER

DEPARTMENT OF TRANSPORTATION

BY (Authorized Signature)

DATE SIGNED (Do not type)

PRINTED NAME AND TITLE OF PERSON SIGNING

ADA Notice For individuals with sensory disabilities, this document is available in alternate formats. For information call (916) 654-6410 or TDD (916) 654-3880 or write Records and Forms Management, 1120 N Street, MS-89, Sacramento, CA 95814.

3. Detailed cost estimate for performing the work under the existing contract and under the proposed change. Determine the estimates under Section 9-1.03, "Force Account Payment."
4. Deadline for the Engineer to decide on the changes.
5. Bid items affected and resulting quantity changes.

The Department is not required to consider a VECP. If a VECP is similar to a change in the plans or specifications being considered by the Department at the time the proposal is submitted or if the proposal is based on or similar to drawings or specifications adopted by the Department before Contract award, the Department does not accept the VECP and may make these changes without VECP payments.

Until the Department approves a change order incorporating the VECP or parts of it, continue to perform the work under the contract. If the Department does not approve a change order before the deadline stated in the VECP or other date you subsequently stated in writing, the VECP is rejected. The Department does not adjust time or payment for a rejected VECP.

The Department decides whether to accept a VECP and the estimated net construction-cost savings from adopting the VECP or parts of it.

The Department may require you to accept a share of the investigation cost as a condition of reviewing a VECP. After written acceptance, the Department considers the VECP and deducts the agreed cost.

If the Department accepts the VECP or parts of it, the Department issues a change order that:

1. Incorporates changes in the contract necessary to implement the VECP or the parts adopted
2. Includes the Department's acceptance conditions
3. States the estimated net construction-cost savings resulting from the VECP
4. Obligates the Department to pay you 50 percent of the estimated net savings

In determining the estimated net construction-cost savings, the Department excludes your VECP preparation cost and the Department's VECP investigation cost, including parts paid by you.

If a VECP providing for a reduction in working days is accepted by the Department, 50 percent of the reduction is deducted from contract time.

If a VECP providing for a reduction in traffic congestion or avoiding traffic congestion is accepted by the Department, the Department pays 60 percent of the estimated net savings in construction costs attributable to the VECP. Submit detailed traffic handling comparisons between the existing contract and the proposed change, including estimates of the traffic volumes and congestion.

The Department may apply an accepted VECP for general use on other contracts.

If an accepted VECP is adopted for general use, the Department pays only the contractor who first submitted the VECP and only to the contracts awarded to that contractor before the submission of the accepted VECP.

If the Department does not adopt a general-use VECP, an identical or similar submitted proposal is eligible for acceptance.

4-1.035C Value Analysis Workshop

Section 4-1.035C, "Value Analysis Workshop," applies to a non-building-work contract with a total bid of over \$5 million.

You may request a value analysis workshop by submitting a request after contract approval.

The Department offers a value analysis workshop to:

1. Identify value enhancing opportunities
2. Consider changes to the contract that will reduce the total cost of construction, construction activity duration, or traffic congestion without impairing the essential functions specified for a VECP in Section 4-1.035B, "Value Engineering Change Proposal."

If the request is authorized, you and the Engineer:

1. Schedule a value analysis workshop
2. Select a facilitator and workshop site
3. Agree to other workshop administrative details

The workshop must be conducted under the methods described in the Department's Value Analysis Team Guide available at:

<http://www.dot.ca.gov/hq/oppd/value/>

4. Developing strategies for using risk management concepts
5. Implementing timely communication and decision making
6. Resolving potential problems at the lowest possible level to avoid negative impacts
7. Holding periodic partnering meetings and workshops as appropriate to maintain partnering relationships and benefits throughout the life of the project
8. Establishing periodic joint evaluations of the partnering process and attainment of mutual goals

Partnering does not void any contract part.

The Department's "Field Guide to Partnering on Caltrans Construction Projects" current at the time of bid is available to the project team as reference. This guide provides structure, context, and clarity to the partnering process requirements. This guide is available at the Department's Partnering Program website:

<http://www.dot.ca.gov/hq/construc/partnering.html>

In implementing project partnering, the project team must:

1. Create a partnering charter that includes:
 - 1.1. Mutual goals, including core project goals and may also include project-specific goals and mutually supported individual goals.
 - 1.2. Partnering maintenance and close-out plan.
 - 1.3. Dispute resolution plan that includes a dispute resolution ladder and may also include use of facilitated dispute resolution sessions.
 - 1.4. Team commitment statement and signatures.
2. Participate in monthly partnering evaluation surveys to measure progress on mutual goals and may also measure short-term key issues as they arise.
3. Evaluate the partnering facilitator on Forms CEM-5501 and CEM-5502. The Engineer provides the evaluation forms to the project team and collects the results. The Department makes evaluation results available upon request. Facilitator evaluations must be completed:
 - 3.1. At the end of the initial partnering workshop on Form CEM-5501.
 - 3.2. At the end of the project close-out partnering workshop on Form CEM-5502.
4. Conduct a project close-out partnering workshop.
5. Document lessons learned before contract acceptance.

5-1.012B Partnering Facilitator, Workshops, and Monthly Evaluation Surveys

The Engineer sends you a written invitation to enter into a partnering relationship after contract approval. Respond within 15 days to accept the invitation and request the initial and additional partnering workshops. After the Engineer receives the request, you and the Engineer cooperatively:

1. Select a partnering facilitator that offers the service of a monthly partnering evaluation survey with a 5-point rating and agrees to follow the Department's "Partnering Facilitator Standards and Expectations" available at the Department's Partnering Program website
2. Schedule initial partnering workshop
3. Determine initial workshop site and duration
4. Agree to other workshop administrative details

Additional partnering workshops and sessions are encouraged throughout the life of the project as determined necessary by you and the Engineer, recommended quarterly.

5-1.012C Training in Partnering Skills Development

For a project with a total bid of \$25 million or greater, training in partnering skills development is required.

For a project with a total bid between \$10 million and \$25 million, training in partnering skills is optional.

You and the Engineer cooperatively schedule the training session and select a professional trainer, training site, and 1 to 4 topics from the following list to be covered in the training:

1. Active Listening
2. Building Teams
3. Change Management
4. Communication
5. Conflict Resolution
6. Cultural Diversity
7. Dealing with Difficult People
8. Decision Making
9. Effective Escalation Ladders
10. Emotional Intelligence
11. Empathy
12. Ethics
13. Facilitation Skills
14. Leadership
15. Partnering Process and Concepts
16. Project Management
17. Project Organization
18. Problem Solving
19. Running Effective Meetings
20. Time Management
21. Win-Win Negotiation

Before the initial partnering workshop, the trainer conducts a 1-day training session in partnering skills development for the Contractor's and the Engineer's representatives. This training session must be a separate session from the initial partnering workshop and must be conducted locally. The training session must be consistent with the partnering principles under the Department's "Field Guide to Partnering on Caltrans Construction Projects."

Send at least 2 representatives to the training session. One of these must be your assigned representative as specified in Section 5-1.06, "Superintendence," of the Standard Specifications.

5-1.012D Payment

The Department pays you for:

1. 1/2 of partnering workshops and sessions based on facilitator and workshop site cost
2. 1/2 of monthly partnering evaluation survey service cost
3. Partnering skills development trainer and training site cost

The Department determines the costs based on invoice prices minus any available or offered discounts. The Department does not pay markups on these costs.

The Department does not pay for wages, travel expenses, or other costs associated with the partnering workshops and sessions, monthly partnering evaluation surveys, and training in partnering skills development.

Add:

5-1.015 RECORDS

5-1.015A General

Reserved

5-1.015B Record Retention

Retain project records from bid preparation through:

1. Final payment
2. Resolution of claims, if any

For at least 3 years after the later of these, retain cost records, including records of:

1. Bid preparation
2. Overhead

3. Payrolls
4. Payments to suppliers and subcontractors
5. Cost accounting

Maintain the records in an organized way in the original format, electronic and hard copy, conducive to professional review and audit.

5-1.015C Record Inspection, Copying, and Auditing

Make your records available for inspection, copying, and auditing by State representatives for the same time frame specified under Section 5-1.015B, "Record Retention." The records of subcontractors and suppliers must be made available for inspection, copying, and auditing by State representatives for the same period. Before contract acceptance, the State representative notifies the Contractor, subcontractor, or supplier 5 business days before inspection, copying, or auditing.

If an audit is to start more than 30 days after contract acceptance, the State representative notifies the Contractor, subcontractor, or supplier when the audit is to start.

5-1.015D Cost Accounting Records

Maintain cost accounting records for the project distinguishing between the following work cost categories:

1. Contract item work
2. Work character changes
3. Force account work
4. Extra work
5. Work performed under protests and claim notifications
6. Overhead
7. Subcontractors, suppliers, owner-operators, and professional services

Cost accounting records must include:

1. Final cost code lists and definitions
2. Itemization of the materials used and corresponding vendor's invoice copies
3. Direct cost of labor
4. Equipment rental charges
5. Workers' certified payrolls
6. Equipment:
 - 6.1. Size
 - 6.2. Type
 - 6.3. Identification number
 - 6.4. Hours operated

5-1.015E Extra Work Bills

Maintain separate records for force account costs.

Submit extra work bills using the Department's Internet extra work billing system.

The Contractor submitting and the Engineer approving an extra work bill using the Internet force account work billing system is the same as each party signing the report.

The Department provides billing system:

1. Training within 30 days of your written request
2. Accounts and user identification to your assigned representatives after a representative has received training

Each representative must maintain a unique password.

Replace Section 5-1.04 with:

5-1.04 CONTRACT COMPONENTS

A component in one contract part applies as if appearing in each. The parts are complementary and describe and provide for a complete work.

If a discrepancy exists:

1. The governing ranking of contract parts in descending order is:
 - 1.1. Special provisions
 - 1.2. Project plans
 - 1.3. Revised Standard Plans
 - 1.4. Standard Plans
 - 1.5. Amendments to the Standard Specifications
 - 1.6. Standard Specifications
 - 1.7. Supplemental project information
2. Written numbers and notes on a drawing govern over graphics
3. A detail drawing governs over a general drawing
4. A detail specification governs over a general specification
5. A specification in a section governs over a specification referenced by that section

If a discrepancy is found or confusion arises, request correction or clarification.

Add:

5-1.055 SUBCONTRACTING

5-1.055A General

No subcontract releases you from the contract or relieves you of your responsibility for a subcontractor's work.

If you violate Pub Cont Code § 4100 et seq., the Department may exercise the remedies provided under Pub Cont Code § 4110. The Department may refer the violation to the Contractors State License Board as provided under Pub Cont Code § 4111.

Perform work equaling at least 30 percent of the value of the original total bid with your employees and with equipment owned or rented by you, with or without operators.

Each subcontract must comply with the contract.

Each subcontractor must have an active and valid State contractor's license with a classification appropriate for the work to be performed (Bus & Prof Code, § 7000 et seq.).

Submit copies of subcontracts upon request.

Before subcontracted work starts, submit a Subcontracting Request form.

Do not use a debarred contractor; a current list of debarred contractors is available at the Department of Industrial Relations' Web site.

Upon request, immediately remove and not again use a subcontractor who fails to prosecute the work satisfactorily.

5-1.055B Disadvantaged Business Enterprises

Section 5-1.055B, "Disadvantaged Business Enterprises," applies to a Federal-aid contract.

Use each subcontractor as listed on the Subcontractor List form unless you receive authorization for a substitution.

The Department requests the Contractor to:

1. Notify the Engineer of any changes to its anticipated DBE participation
2. Provide this notification before starting the affected work

Maintain records including:

1. Name and business address of each 1st-tier subcontractor
2. Name and business address of each DBE subcontractor, DBE vendor, and DBE trucking company, regardless of tier
2. Date of payment and total amount paid to each business

If you are a DBE contractor, include the date of work performed by your own forces and the corresponding value of the work.

Before the 15th of each month, submit a Monthly DBE Trucking Verification form.

For a DBE that leases trucks from a non-DBE, count only the fee or commission the DBE receives as a result of the lease arrangement.

If a DBE subcontractor is decertified before completing subcontracted work, the subcontractor must notify you in writing of the decertification date. If a subcontractor becomes a certified DBE before completing subcontracted work, the

subcontractor must notify you in writing of the certification date. Submit the notifications. On contract work completion, complete a Disadvantaged Business Enterprises (DBE) Certification Status Change form. Submit the form within 90 days of contract acceptance.

Upon contract work completion, complete a Final Report – Utilization of Disadvantaged Business Enterprises (DBE), First-Tier Subcontractors form. Submit it within 90 days of contract acceptance. The Department withholds \$10,000 until the form is submitted. The Department releases the withhold upon submission of the completed form.

5-1.055C Disabled Veteran Business Enterprises

Section 5-1.055C, "Disabled Veteran Business Enterprises," applies to a non-Federal-aid contract.

If a DVBE goal is shown in the Notice to Bidders:

1. Use each DVBE as shown on the Certified DVBE Summary form unless you receive authorization for a substitution
2. The requirement that DVBEs be certified by the bid opening date does not apply to DVBE substitutions after contract award
3. Maintain records of subcontracts made with certified DVBEs. Include in the records:
 - 3.1. Name and business address of each business
 - 3.2. Total amount paid to each business
4. For the purpose of determining compliance with Pub Cont Code § 10115 et seq.:
 - 4.1. Provide the Department relevant information requested
 - 4.2. Upon reasonable notice and during normal business hours, permit access to its premises for the purpose of:
 - 4.2.1. Interviewing employees
 - 4.2.2. Inspecting and copying books, records, accounts and other material that may be relevant to a matter under investigation

If no DVBE goal is shown in the Notice to Bidders and if you obtain DVBE participation, submit the participating DVBE names and value of work or supplies supplied by each DVBE transaction upon contract completion.

5-1.055D Non-Small Businesses

Section 5-1.055D, "Non-Small Businesses," applies to a non-Federal-aid contract.

Use each subcontractor as shown on the Certified Small Business Listing for the Non-Small Business Preference form unless you receive authorization for a substitution.

The requirement that small businesses be certified by the bid opening date does not apply to small business substitutions after contract award.

Maintain records of subcontracts made with certified small business subcontractors and records of materials purchased from certified small business suppliers. Include in the records:

1. Name and business address of each business
2. Total amount paid to each business

For the purpose of determining compliance with 2 CA Code of Regs § 1896 et seq.:

1. Provide the Department relevant information requested.
2. Upon reasonable notice and during normal business hours, permit access to its premises for the purpose of:
 - 2.1. Interviewing employees
 - 2.2. Inspecting and copying books, records, accounts and other material that may be relevant to a matter under investigation

Replace Section 5-1.07 with:

5-1.07 LINES AND GRADES

The Engineer places stakes and marks under Chapter 12, "Construction Surveys," of the Department's Surveys Manual. Submit your request for Department-furnished stakes:

1. On a Request for Construction Stakes form. Ensure:
 - 1.1. Requested staking area is ready for stakes
 - 1.2. You use the stakes in a reasonable time
2. A reasonable time before starting an activity using the stakes

Establish priorities for stakes and note priorities on the request.

Preserve stakes and marks placed by the Engineer. If the stakes or marks are destroyed, the Engineer replaces them at the Engineer's earliest convenience and deducts the cost.

Replace Section 5-1.116 with:

5-1.116 DIFFERING SITE CONDITIONS (23 CFR 635.109)

5-1.116A Contractor's Notification

Promptly notify the Engineer if you find either of the following:

1. Physical conditions differing materially from either of the following:
 - 1.1. Contract documents
 - 1.2. Job site examination
2. Physical conditions of an unusual nature, differing materially from those ordinarily encountered and generally recognized as inherent in the work provided for in the contract

Include details explaining the information you relied on and the material differences you discovered.

If you fail to notify the Engineer promptly, you waive the differing site condition claim for the period between your discovery of the differing site condition and your notification to the Engineer.

If you disturb the site after discovery and before the Engineer's investigation, you waive the differing site condition claim.

5-1.116B Engineer's Investigation and Decision

Upon your notification, the Engineer investigates job site conditions and:

1. Notifies you whether to resume affected work
2. Decides whether the condition differs materially and is cause for an adjustment of time, payment, or both

5-1.116C Protests

You may protest the Engineer's decision by:

1. Submitting an Initial Notice of Potential Claim within 5 business days after receipt of the Engineer's notification
2. Complying with claim procedures

The Initial Notice of Potential Claim must detail the differences in your position from the Engineer's determination and support your position with additional information, including additional geotechnical data. Attach to the Initial Notice of Potential Claim a certification stating that you complied with Section 2-1.11, "Job Site and Document Examination."

Promptly submit supplementary information when obtained.

Replace Section 5-1.14 with:

5-1.14 COST REDUCTION INCENTIVE

Comply with Section 4-1.035B, "Value Engineering Change Proposal."

Add:

5-1.15 DISPUTE RESOLUTION

5-1.15A General

Section 5-1.15, "Dispute Resolution," applies to a contract with 100 or more working days.

In the Dispute Resolution Advisor Agreement and in the Dispute Review Board Agreement, interpret a reference to the special provisions as a reference to the Amendments to the Standard Specifications. In the Dispute Review Board Agreement, replace "Proposal and Contract" with "Bid book." Where the section title does not match the section number for a reference, refer to the referenced title.

5-1.15B Dispute Resolution Advisor

Section 5-1.15B, "Dispute Resolution Advisor," applies to a contract from \$3 million to \$10 million.

A dispute resolution advisor, hereinafter referred to as "DRA", is chosen by the Department and the Contractor to assist in the resolution of disputes. The DRA is a part of the contract administrative claims process as specified in the provisions in Section 9-1.04, "Notice of Potential Claim," and Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications. The DRA shall not serve as a substitute for filing a protest or a notice of potential claim.

The DRA shall be established by the Department and the Contractor within 30 days of contract approval.

The Department and the Contractor shall each propose 3 potential DRA candidates. Each potential candidate shall provide the Department and the Contractor with their disclosure statement. The disclosure statement shall include a resume of the potential candidate's experience and a declaration statement describing past, present, anticipated, and planned relationships with all parties involved in this contract.

The Department and the Contractor shall select one of the 6 nominees to be the DRA. If the Department and the Contractor cannot agree on one candidate, the Department and the Contractor shall each choose one of the 3 nominated by the other. The final selection of the DRA will be decided by a coin toss between the two candidates.

The Department and the Contractor shall complete and adhere to the Dispute Resolution Advisor Agreement. No DRA meeting shall take place until the Dispute Resolution Advisor Agreement has been signed by all parties, unless all parties agree to sign it at the first meeting.

If DRA needs outside technical services, technical services shall be preapproved by both the Department and the Contractor.

DRA recommendations are nonbinding.

The Contractor shall not use the DRA for disputes between subcontractors or suppliers that have no grounds for a lawsuit against the Department.

DRA replacement is selected in the same manner as the original selection. The appointment of a replacement DRA will begin promptly upon determination of the need for replacement. The Dispute Resolution Advisor Agreement shall be amended to reflect the change of the DRA.

Failure of the Contractor to participate in selecting DRA will result in the withhold of 25 percent of the estimated value of all work performed during each estimate period that the Contractor fails to comply. DRA withholds will be released for payment on the next monthly progress payment following the date that the Contractor has provided assistance in choosing the DRA and no interest will be due the Contractor.

The State and the Contractor shall bear the costs and expenses of the DRA equally.

The DRA shall be compensated at an agreed rate of \$1,500 per day for time spent per meeting either at the start of the project or for a dispute. A member serving on more than one State DRA or Dispute Review Board, regardless the number of meetings per day shall not be paid more than the agreed rate per day. The agreed rate shall be considered full compensation for on-site time, travel expenses, transportation, lodging, time for travel, and incidentals for each day or portion thereof that the DRA is at an authorized DRA meeting.

No additional compensation will be made for time spent by the DRA to review and research activities outside the official DRA meetings unless that time, such as time spent evaluating and preparing recommendations on specific issues presented to the DRA, has been specifically agreed to in advance by the State and Contractor. Time away from the project that has been specifically agreed to in advance by the Department and the Contractor will be compensated at an agreed rate of \$150 per hour. The agreed amount of \$150 per hour shall include all incidentals including expenses for telephone, fax, and computer services.

The State will provide conference facilities for DRA meetings at no cost to the Contractor.

The Contractor shall make direct payments to the DRA for participation in authorized meetings and approved hourly rate charges from invoices submitted.

The State will reimburse the Contractor for the State's share of the costs.

There will be no markups applied to expenses associated with the DRA, either by the DRA or by the Contractor when requesting payment of the State's share of DRA expenses. Regardless of the DRA recommendation, neither party will be entitled to reimbursement of DRA costs from the other party.

The Contractor shall submit extra work bills and include invoices with original supporting documents for reimbursement of the State's share.

The cost of technical services will be borne equally by the State and Contractor. There will be no markups for these costs.

A copy of the "Dispute Resolution Advisor Agreement" to be executed by the Contractor, State and the DRA is as follows:

Form CEM 6206 Rev (04-06-07)

DISPUTE RESOLUTION ADVISOR AGREEMENT

(Contract Identification)

Contract No. _____

THIS DISPUTE RESOLUTION ADVISOR AGREEMENT, hereinafter called "AGREEMENT", made and entered into this _____ day of _____, _____, between the State of California, acting through the California Department of Transportation and the Director of Transportation, hereinafter called the "STATE," _____ hereinafter called the "CONTRACTOR," and _____, the Dispute Resolution Advisor, hereinafter called the "DRA." .

WITNESSETH, that

WHEREAS, the STATE and the CONTRACTOR, hereinafter called the "parties," are now engaged in the construction on the State Highway project referenced above; and

WHEREAS, the special provisions for the above referenced contract provides for the establishment and operation of the DRA to assist in resolving disputes; and

WHEREAS, the DRA is composed of one person, chosen by the CONTRACTOR and the STATE;

NOW THEREFORE, in consideration of the terms, conditions, covenants, and performance contained herein, or attached and incorporated and made a part hereof, the STATE, the CONTRACTOR, and the DRA hereto agree as follows:

SECTION I DESCRIPTION OF WORK

To assist in the timely resolution of disputes between the parties, the contract provides for the establishment and the operation of the DRA. The DRA is to fairly and impartially consider disputes placed before it and provide recommendations for resolution of these disputes to the parties. The DRA shall provide recommendations based on the facts related to the dispute, the contract and applicable laws and regulations. The DRA shall perform the services necessary to participate in the DRA's actions as designated in Section III, Scope of Work.

SECTION II DRA QUALIFICATIONS

DRA shall be knowledgeable in the type of construction and contract documents anticipated by the contract and shall have completed training through the Dispute Review Board Foundation. In addition, it is desirable for the DRA to have served on several State Dispute Review Boards (DRB).

No DRA shall have prior direct involvement in this contract. No DRA shall have a financial interest in this contract or parties thereto, including but not limited to the CONTRACTOR, subcontractors, suppliers, consultants, and legal and business services, within a period 6 months prior to award and during this contract. Exceptions to above are compensation for services on this or other DRAs and DRBs or retirement payments or pensions received from a party that are not tied to, dependent on or affected by the net worth of the party.

DRA shall fully disclose all direct or indirect professional or personal relationships with all key members of the contract.

SECTION III SCOPE OF WORK

The Scope of Work of the DRA includes, but is not limited to, the following:

A. PROCEDURES

The DRA shall meet with the parties at the start of the project to establish procedures that will govern the conduct of its business and reporting procedures in conformance with the requirements of the contract and the terms of this AGREEMENT.

The DRA established procedures shall only be implemented upon approval by the parties. Subsequent meetings shall be held only to hear disputes between the parties.

The DRA shall not meet with, or discuss contract issues with individual parties.

State shall provide the DRA with the contract and all written correspondence regarding the dispute between the parties and, if available, the Contractor's supplemental notice of potential claim, and the Engineer's response to the supplemental notice of potential claim.

The parties shall not call the DRA who served on this contract as a witness in arbitration proceedings, which may arise from this contract.

The DRA shall have no claim against the STATE or the CONTRACTOR, or both, from claimed harm arising out of the parties' evaluations of the DRA's opinions.

B. DISPUTE MEETING

The term "dispute meeting" as used in this subsection shall refer to both the informal and traditional dispute meeting processes, unless otherwise noted.

If the CONTRACTOR requests a dispute meeting with the DRA, the Contractor must simultaneously notify the STATE. Upon being notified of the need for a dispute meeting, the DRA shall review and consider the dispute. The DRA shall determine the time and location of the dispute meeting with due consideration for the needs and preferences of the parties, while recognizing the importance of a speedy resolution to the dispute.

Dispute meetings shall be conducted at any location that would be convenient and provide required facilities and access to necessary documentation.

Only the STATE's Resident Engineer or Area Construction Engineer and the CONTRACTOR's or subcontractor's, if the dispute involves a subcontractor, Superintendent or Project Manager may present information at a dispute meeting. There shall be no participation of persons who are not directly involved in the contract or who do not have direct knowledge of the dispute. The exception to this is technical services, as described below:

The DRA, with approval of the parties, may obtain technical services necessary to adequately review the disputes presented, including audit, geotechnical, schedule analysis and other services. The parties' technical staff may supply those services as appropriate. The cost of technical services, as agreed to by the parties, shall be borne equally by the two parties as specified in an approved contract change order. The CONTRACTOR shall not be entitled to markups for the payments made for these services.

At the dispute meeting the DRA may ask questions, seek clarification, and request further clarification of data presented by either of the parties as may be necessary to assist in making a fully informed recommendation. However, the DRA shall refrain from expressing opinions on the merits of statements on matters under dispute during the parties' presentations. Each party will be given ample time to fully present its position, make rebuttals, provide relevant documents, and respond to DRA questions and requests.

There shall be no testimony under oath or cross-examination, during DRA dispute meetings. There shall be no reporting of the procedures by a shorthand reporter or by electronic means. Documents and verbal statements shall be received by the DRA in conformance with the rules and regulations established at the first meeting between the DRA and parties. These established rules and regulations need not comply with prescribed legal laws of evidence.

Failure to attend a dispute meeting by either of the parties shall be conclusively considered by the DRA as indication that the non-attending party considers all written documents and correspondence submitted as their entire and complete argument. The claimant shall discuss the dispute, followed by the other party. Each party shall then be allowed one or more rebuttals at the meeting until all aspects of the dispute are thoroughly covered.

1. TRADITIONAL DISPUTE MEETING:

The following procedure shall be used for the traditional dispute meeting:

- a. Within 5 days, after receiving the STATE's written response to the CONTRACTOR's supplemental notice of potential claim, the CONTRACTOR shall refer the dispute to the DRA, if the CONTRACTOR wishes to further pursue the dispute. The CONTRACTOR shall make the referral in writing to the DRA, simultaneously copied to the STATE. The written dispute referral shall describe the disputed matter in individual discrete segments, so that it will be clear to both parties and the DRA what discrete elements of the dispute have been resolved, and which remain unresolved, and shall include an estimate of the cost of the affected work and impacts, if any, on project completion.
- b. The parties shall each be afforded an opportunity to be present and to be heard by the DRA, and to offer evidence. Either party furnishing written evidence or documentation to the DRA must furnish copies of such information to the other party a minimum of 10 days prior to the date the DRA is scheduled to convene the

meeting for the dispute. Either party shall produce such additional evidence as the DRA may deem necessary to reach an understanding and a determination of the dispute. The party furnishing additional evidence shall furnish copies of such additional evidence to the other party at the same time the evidence is provided to the DRA. The DRA shall not consider evidence not furnished in conformance with the terms specified herein.

- c. Upon receipt by the DRA of a written referral of a dispute, the DRA shall convene to review and consider the dispute. The dispute meeting shall be held no later than 25 days after receipt of the written referral unless otherwise agreed to by all parties.
- d. The DRA shall furnish a written report to both parties. The DRA may request clarifying information of either party within 5 days after the DRA dispute meeting. Requested information shall be submitted to the DRA within 5 days of the DRA request. The DRA shall complete its report and submit it to the parties within 10 days of the DRA dispute meeting, except that time extensions may be granted at the request of the DRA with the written concurrence of both parties. The report shall summarize the facts considered, the contract language, law or regulation viewed by the DRA as pertinent to the dispute, and the DRA's interpretation and philosophy in arriving at its conclusions and recommendations and, if appropriate, recommends guidelines for determining compensation. The DRA's written opinion shall stand on its own, without attachments or appendices.
- e. Within 10 days after receiving the DRA's report, both parties shall respond to the DRA in writing signifying that the dispute is either resolved or remains unresolved. Failure to provide the written response within the time specified, or a written rejection of the DRA's recommendation or response to a request for reconsideration presented in the report by either party, shall conclusively indicate that the party(s) failing to respond accepts the DRA recommendation. Immediately after responses have been received from both parties, the DRA shall provide copies of both responses to the parties simultaneously. Either party may request clarification of elements of the DRA's report from the DRA prior to responding to the report. The DRA shall consider any clarification request only if submitted within 5 days of receipt of the DRA's report, and if submitted simultaneously in writing to both the DRA and the other party. Each party may submit only one request for clarification for any individual DRA report. The DRA shall respond, in writing, to requests for clarification within 5 days of receipt of such requests.
- f. Either party may seek a reconsideration of the DRA's recommendation. The DRA shall only grant reconsideration based upon submission of new evidence and if the request is submitted within the 10 day time limit specified for response to the DRA's written report. Each party may submit only one request for reconsideration regarding an individual DRA recommendation.
- g. If the parties are able to settle their dispute with the aid of the DRA's report, the STATE and CONTRACTOR shall promptly accept and implement the settlement of the parties. If the parties cannot agree on compensation within 30 days of the acceptance by both parties of the settlement, either party may request the DRA to make a recommendation regarding compensation.

2. INFORMAL DISPUTE MEETING

An informal dispute meeting shall be convened, only if, the parties and the DRA agree that this dispute resolution process is appropriate to settle the dispute.

The following procedure shall be used for the informal dispute meeting:

- a. The parties shall furnish the DRA with one copy of pertinent documents requested by the DRA that are or may become necessary for the DRA to perform its function. The party furnishing documents shall furnish such documents to the other party at the same time the document is provided to the DRA.
- b. After the dispute meeting has concluded; the DRA shall deliberate in private the same day, until a response to the parties is reached or as otherwise agreed to by the parties.
- c. The DRA then verbally delivers its recommendation with findings to the parties.
- d. After the recommendation is presented, the parties may ask for clarifications.
- e. Occasionally the DRA on complex issues may be unable to formulate a recommendation based on the information given at a dispute meeting. However, the DRA may provide the parties with advice on strengths and weaknesses of their prospective positions, in the hope of the parties reaching settlement.
- f. If the parties are able to settle their dispute with the aid of the DRA's opinion, the STATE and CONTRACTOR shall promptly accept and implement the settlement of the parties.
- g. The DRA will not be bound by its oral recommendation in the event that a dispute is later heard by the DRA in a traditional dispute meeting.

Unless the dispute is settled, use of the informal dispute meeting does not relieve the parties of their responsibilities under Section 5-1.12, "Dispute Resolution Advisor," of the Special Provisions or Subsection, "Traditional Dispute Meeting," of this AGREEMENT. There will be no extension of time allowed for the process to permit the use of the informal dispute meeting, unless otherwise agreed to by the parties.

SECTION IV TIME FOR BEGINNING AND COMPLETION

Once established, the DRA shall be in operation until the day the Director accepts the contract. The DRA shall not begin work under the terms of this AGREEMENT until authorized in writing by the STATE or as agreed to by the parties.

SECTION V PAYMENT

DRA shall be compensated at an agreed rate of \$1,500 per day for time spent per meeting, either at the start of the project or for a dispute. A member serving on more than one State DRA or DRB, regardless the number of meetings per day, shall not be paid more than the agreed rate per day. The agreed rate shall be considered full compensation for onsite time, travel expenses, transportation, lodging, time for travel and incidentals for each day, or portion thereof that the DRA is at an authorized DRA meeting. No additional compensation will be made for time spent by DRA to review and research activities outside the official DRA meetings unless that time, (such as time spent evaluating and preparing recommendations on specific issues presented to the DRA), has been specifically agreed to in advance by the parties. Time away from the project, which has been specifically agreed to in advance by the parties, will be compensated at an agreed rate of \$150 per hour. The agreed amount of \$150 per hour shall include all incidentals including expenses for telephone, fax, and computer services. The State will provide administrative services such as conference facilities to the DRA.

A. PAYMENT PROCESSING

CONTRACTOR shall make direct payments to DRA for their participation in authorized meetings and approved hourly rate charges, from invoices submitted by the DRA, and technical services.

DRA may submit invoices to the CONTRACTOR for partial payment for work performed and services rendered for their participation in authorized meetings not more often than once per month during the progress of the work. The invoices shall be in a format approved by the parties and accompanied by a general description of activities performed during that billing period. Payment for hourly fees, at the agreed rate, shall not be paid to a DRA until the amount and extent of those fees are approved by the STATE and CONTRACTOR.

B. INSPECTION OF COSTS RECORDS

DRA and the CONTRACTOR shall keep available for inspection by representatives of the STATE and the United States, for a period of 3 years after final payment, the cost records and accounts pertaining to this AGREEMENT. If any litigation, claim, or audit arising out of, in connection with, or related to this contract is initiated before the expiration of the 3-year period, the cost records and accounts shall be retained until such litigation, claim, or audit involving the records is completed.

SECTION VI ASSIGNMENT OF TASKS OF WORK

DRA shall not assign the work of this AGREEMENT.

SECTION VII TERMINATION OF A DRA MEMBER

DRA may resign after providing not less than 15 days written notice of the resignation to the STATE and CONTRACTOR. The DRA may be terminated, by either party, for failing to fully comply at all times with all required employment or financial disclosure conditions of DRA membership in conformance with the terms of the contract and this AGREEMENT. Each party shall document the need for replacement and substantiate the replacement request in writing to the other party and the DRA.

SECTION VIII LEGAL RELATIONS

The parties hereto mutually understand and agree that the DRA in the performance of duties is acting in the capacity of an independent agent and not as an employee of either party.

No party to this AGREEMENT shall bear a greater responsibility for damages or personal injury than is normally provided by Federal or State of California Law.

Notwithstanding the provisions of this contract that require the CONTRACTOR to indemnify and hold harmless the STATE, the parties shall jointly indemnify and hold harmless the DRA from and against all claims, damages, losses, and expenses, including but not limited to attorney's fees, arising out of and resulting from the findings and recommendations of the DRA.

SECTION IX CONFIDENTIALITY

The parties hereto mutually understand and agree that all documents and records provided by the parties in reference to issues brought before the DRA, which documents and records are marked "Confidential - for use by the DRA only," shall be

kept in confidence and used only for the purpose of resolution of subject disputes, and for assisting in development of DRA findings and recommendations; that such documents and records will not be utilized or revealed to others, except to officials of the parties who are authorized to act on the subject disputes, for any purposes, during the life of this AGREEMENT. Upon termination of this AGREEMENT, said confidential documents and records, and all copies thereof, shall be returned to the parties who furnished them to the DRA. However, the parties understand that such documents may be subsequently discoverable and admissible in court or arbitration proceedings unless a protective order has been obtained by the party seeking further confidentiality.

SECTION X DISPUTES

Disputes between the parties arising out of the work or other terms of this AGREEMENT that cannot be resolved by negotiation and mutual concurrence between the parties or through the administrative process provided in the contract shall be resolved by arbitration as provided in Section 9-1.10, "Arbitration," of the Standard Specifications. Disputes between the DRA and the parties that cannot be resolved by negotiation and mutual concurrence shall be resolved in the appropriate forum.

SECTION XI VENUE, APPLICABLE LAW, AND PERSONAL JURISDICTION

In the event that any party, including the DRA, deems it necessary to institute arbitration proceedings to enforce any right or obligation under this AGREEMENT, the parties hereto agree that such action shall be initiated in the Office of Administrative Hearings of the State of California. The parties hereto agree that all questions shall be resolved by arbitration by application of California law and that the parties to such arbitration shall have the right of appeal from such decisions to the Superior Court in conformance with the laws of the State of California. Venue for the arbitration shall be Sacramento or any other location as agreed to by the parties.

SECTION XII FEDERAL REVIEW AND REQUIREMENTS

On Federal-Aid contracts, the Federal Highway Administration shall have the right to review the work of the DRA in progress, except for private meetings or deliberations of the DRA.

Other Federal requirements in this agreement shall only apply to Federal-Aid contracts.

SECTION XIII CERTIFICATION OF CONTRACTOR, DRA, AND STATE

IN WITNESS WHEREOF, the parties hereto have executed this AGREEMENT as of the day and year first above written.

DRA

By: _____

Title: _____

CONTRACTOR

CALIFORNIA STATE DEPARTMENT
OF TRANSPORTATION

By: _____

By: _____

Title: _____

Title: _____

5-1.15C Dispute Review Board

Section 5-1.15C, "Dispute Review Board," applies to a contract over \$10 million.

5-1.15C(1) General

To assist in the resolution of disputes or potential claims arising out of the work of this project, a Dispute Review Board, hereinafter referred to as the "DRB," shall be established by the Engineer and Contractor cooperatively upon approval of the contract. The DRB is intended to assist the contract administrative claims resolution process as specified in the provisions in Section 9-1.04, "Notice of Potential Claim," and Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications and these special provisions. The DRB shall not serve as a substitute for provisions in the specifications in regard to filing potential claims. The requirements and procedures established in this section shall be a prerequisite to filing a claim, filing for arbitration, or filing for litigation prior or subsequent to project completion.

The DRB shall be utilized when dispute or potential claim resolution at the project level is unsuccessful. The DRB shall function as specified herein until the day of acceptance of the contract, at which time the work of the DRB will cease except for completion of unfinished reports. No DRB dispute meetings shall take place later than 30 days prior to acceptance of contract. After acceptance of contract, disputes or potential claims which have followed the dispute resolution processes of the Standard Specifications and these special provisions, but have not been resolved, shall be stated or restated by the Contractor, in response to the Proposed Final Estimate within the time limits provided in Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications. The State will review those claims in conformance with the provisions in Section 9-1.07B of the Standard Specifications. Following the adherence to and completion of the contractual administrative claims procedure, the Contractor may file for arbitration in conformance with the provisions in Section 9-1.10, "Arbitration," of the Standard Specifications and these special provisions.

Disputes, as used in this section, shall include differences of opinion, properly noticed as provided hereinafter, between the State and Contractor on matters related to the work and other subjects considered by the State or Contractor, or by both, to be of concern to the DRB on this project, except matters relating to Contractor, subcontractor or supplier potential claims not actionable against the Department as specified in these special provisions or quantification of disputes for overhead type expenses or costs. Disputes for overhead type expenses or costs shall conform to the requirements of Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications. Whenever the term "dispute" or "disputes" is used herein, it shall be deemed to include potential claims as well as disputes.

The DRB shall serve as an advisory body to assist in the resolution of disputes between the State and the Contractor, hereinafter referred to as the "parties." The DRB shall consider disputes referred to it, and furnish written reports containing findings and recommendations pertaining to those disputes, to the parties to aid in resolution of the differences between them. DRB findings and recommendations are not binding on the parties.

5-1.15C(2) Selection Process, Disclosure and Appointments

The DRB shall consist of one member selected by the State and approved by the Contractor, one member selected by the Contractor and approved by the State, and a third member selected by the first 2 members and approved by both the State and the Contractor. The third member shall act as the DRB Chairperson.

DRB members shall be especially knowledgeable in the type of construction and contract documents potentially anticipated by the contract. DRB members shall discharge their responsibilities impartially as an independent body, considering the facts and circumstances related to the matters under consideration, pertinent provisions of the contract and applicable laws and regulations.

The State and the Contractor shall nominate and approve DRB members in conformance with the terms and conditions of the Dispute Review Board Agreement and these special provisions, within 45 days of the approval of the contract. Each party shall provide written notification to the other of the name of their selected DRB nominee along with the prospective member's complete written disclosure statement.

Disclosure statements shall include a resume of the prospective member's experience and a declaration statement describing past, present, anticipated, and planned relationships, including indirect relationships through the prospective member's primary or full-time employer, to this project and with the parties involved in this construction contract, including but not limited to, relevant subcontractors or suppliers to the parties, parties' principals, or parties' counsel. DRB members shall also include a full disclosure of close professional or personal relationships with all key members of the contract. Objections to nominees must be based on a specific breach or violation of nominee responsibilities or on nominee qualifications under these provisions unless otherwise specified. The Contractor or the State may, on a one-time basis, object to the other's nominee without specifying a reason and this person will not be selected for the DRB. Another person shall then be nominated within 15 days.

The first duty of the State and Contractor selected members of the DRB shall be to select and recommend a prospective third DRB member to the parties for final selection and approval. The first 2 DRB members shall proceed with the selection of the third DRB member immediately upon receiving written notification from the State of their selection, and shall provide their recommendation simultaneously to the parties within 15 days of the notification.

The first 2 DRB members shall select a third DRB member subject to mutual approval of the parties or may mutually concur on a list of potentially acceptable third DRB members and submit the list to the parties for final selection and approval of the third member. The goal in the selection of the third member is to complement the professional experience of the first 2 members and to provide leadership for the DRB's activities.

The third prospective DRB member shall supply a full disclosure statement to the first 2 DRB members and to the parties prior to appointment.

An impasse shall be considered to have been reached if the parties are unable to approve a third member within 15 days of receipt of the recommendation of the first 2 DRB members, or if the first 2 DRB members are unable to agree upon a recommendation within their 15 day time limit. In the event of an impasse in selection of third DRB member the State and the Contractor shall each propose 3 candidates for the third DRB member position. The parties shall select the candidates proposed under this paragraph from the current list of arbitrators certified by the Public Works Contract Arbitration

Committee created by Article 7.2 (commencing with Section 10245) of the State Contract Act. The first 2 DRB members shall then select one of the 6 proposed candidates in a blind draw.

No DRB member shall have prior direct involvement in this contract. No member shall have a financial interest in this contract or the parties thereto, within a period of 6 months prior to award of this contract or during the contract, except as follows:

- A. Compensation for services on this DRB.
- B. Ownership interest in a party or parties, documented by the prospective DRB member, that has been reviewed and determined in writing by the State to be sufficiently insignificant to render the prospective member acceptable to the State.
- C. Service as a member of other Dispute Review Boards on other contracts.
- D. Retirement payments or pensions received from a party that are not tied to, dependent on or affected by the net worth of the party.
- E. The above provisions apply to parties having a financial interest in this contract, including but not limited to contractors, subcontractors, suppliers, consultants, and legal and business services.

The Contractor or the State may reject any of the 3 DRB members who fail to fully comply at all times with all required employment and financial disclosure conditions of DRB membership as described in the Dispute Review Board Agreement and as specified herein. A copy of the Dispute Review Board Agreement is included in this section.

The Contractor, the State, and the 3 members of the DRB shall complete and adhere to the Dispute Review Board Agreement in administration of this DRB within 15 days of the parties' concurrence in the selection of the third member. No DRB meeting shall take place until the Dispute Review Board Agreement has been signed by all parties. The State authorizes the Engineer to execute and administer the terms of the Agreement. The person(s) designated by the Contractor as authorized to execute contract change orders shall be authorized to execute and administer the terms of this agreement, or to delegate the authority in writing. The operation of the DRB shall be in conformance with the terms of the Dispute Review Board Agreement.

5-1.15C(3) Compensation

• The State and the Contractor shall bear the costs and expenses of the DRB equally. Each DRB member shall be compensated at an agreed rate of \$1,200 per day if time spent per meeting, including on-site time plus one hour of travel time, is greater than 4 hours. Each DRB member shall be compensated at an agreed rate of \$700 per day if time spent per meeting, including on-site time plus one hour of travel time, is less than or equal to 4 hours. The agreed rates shall be considered full compensation for on-site time, travel expenses, transportation, lodging, time for travel and incidentals for each day, or portion thereof, that the DRB member is at an authorized DRB meeting. No additional compensation will be made for time spent by DRB members in review and research activities outside the official DRB meetings unless that time, (such as time spent evaluating and preparing recommendations on specific issues presented to the DRB), has been specifically agreed to in advance by the State and Contractor. Time away from the project, which has been specifically agreed to in advance by the parties, will be compensated at an agreed rate of \$125 per hour. The agreed amount of \$125 per hour shall include all incidentals including expenses for telephone, fax, and computer services. Members serving on more than one DRB involving the Department, regardless of the number of meetings per day, shall not be paid more than the all inclusive rate per day or rate per hour for an individual project. The State will provide, at no cost to the Contractor, administrative services such as conference facilities and secretarial services to the DRB. These special provisions and the Dispute Review Board Agreement state the provisions for compensation and expenses of the DRB. DRB members shall be compensated at the same daily and hourly rate. The Contractor shall make direct payments to each DRB member for their participation in authorized meetings and approved hourly rate charges from invoices submitted by each DRB member. The State will reimburse the Contractor for the State's share of the costs. There will be no markups applied to expenses connected with the DRB, either by the DRB members or by the Contractor when requesting payment of the State's share of DRB expenses. Regardless of the DRB recommendation, neither party shall be entitled to reimbursement of DRB costs from the other party.

5-1.15C(4) Replacement of DRB Members

Service of a DRB member may be terminated at any time with not less than 15 days notice as follows:

- A. The State may terminate service of the State appointed member.
- B. The Contractor may terminate service of the Contractor appointed member.
- C. Upon the written recommendation of the State and Contractor appointed members for the removal of the third member.
- D. Upon resignation of a member.

- E. The State or Contractor may terminate the service of any member who fails to fully comply with all required employment and financial disclosure conditions of DRB membership.

When a member of the DRB is replaced, the replacement member shall be appointed in the same manner as the replaced member was appointed. The appointment of a replacement DRB member will begin promptly upon determination of the need for replacement and shall be completed within 15 days. Changes in either of the DRB members chosen by the 2 parties will not require re-selection of the third member, unless both parties agree to such re-selection in writing. The Dispute Review Board Agreement shall be amended to reflect the change of a DRB member.

5-1.15C(5) Operation

The following procedure shall be used for dispute resolution:

- A. If the Contractor objects to any decision, act or order of the Engineer, the Contractor shall give written notice of potential claim in conformance with the provisions in Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications and these special provisions, including the provision of applicable cost documentation; or file written protests or notices in conformance with the provisions in the Standard Specifications and these special provisions.
- B. The Engineer will respond, in writing, to the Contractor's written supplemental notice of potential claim within 20 days of receipt of the notice.
- C. Within 15 days after receipt of the Engineer's written response, the Contractor shall, if the Contractor still objects, file a written reply with the Engineer, stating clearly and in detail the basis of the objection.
- D. Following an objection to the Engineer's written response, the Contractor shall refer the dispute to the DRB if the Contractor wishes to further pursue the objection to the Engineer's decision. The Contractor shall make the referral in writing to the DRB, simultaneously copied to the State, within 21 days after receipt of the written response from the Engineer. The written dispute referral shall describe the disputed matter in individual discrete segments so that it will be clear to both parties and the DRB what discrete elements of the dispute have been resolved, and which remain unresolved, and shall include an estimate of the cost of the affected work and impacts, if any, on project completion.
- E. By failing to submit the written notice of referral to the DRB, within 21 days after receipt of the Engineer's written response to the supplemental notice of potential claim, the Contractor waives future claims and arbitration on the matter in contention.
- F. The Contractor and the State shall each be afforded an opportunity to be present and to be heard by the DRB, and to offer evidence. Either party furnishing written evidence or documentation to the DRB must furnish copies of such information to the other party a minimum of 15 days prior to the date the DRB is scheduled to convene the meeting for the dispute. Either party shall produce such additional evidence as the DRB may deem necessary to reach an understanding and a determination of the dispute. The party furnishing additional evidence shall furnish copies of such additional evidence to the other party at the same time the evidence is provided to the DRB. The DRB shall not consider evidence not furnished in conformance with the terms specified herein.
- G. Upon receipt by the DRB of a written referral of a dispute, the DRB shall convene to review and consider the dispute. The dispute meeting shall be held no earlier than 30 days and no later than 60 days after receipt of the written referral unless otherwise agreed to by all parties. The DRB shall determine the time and location of the DRB dispute meeting, with due consideration for the needs and preferences of the parties while recognizing the paramount importance of a timely hearing of the dispute.
- H. There shall be no participation of either party's attorneys at DRB dispute meetings.
- I. There shall be no participation of persons who are not directly involved in the contract or who do not have direct knowledge of the dispute, including but not limited to consultants, except for expert testimony allowed at the discretion of the DRB and with approval prior to the dispute meeting by both parties.
- J. The DRB shall furnish a report, containing findings and recommendations as described in the Dispute Review Board Agreement, in writing to both the State and the Contractor. The DRB may request clarifying information of either party within 10 days after the DRB dispute meeting. Requested information shall be submitted to the DRB within 10 days of the DRB request. The DRB shall complete its report, including minority opinion, if any, and submit it to the parties within 30 days of the DRB dispute meeting, except that time extensions may be granted at the request of the DRB with the written concurrence of both parties. The report shall include the facts and circumstances related to the matters under consideration, pertinent provisions of the contract, applicable laws and regulations, and actual costs and time incurred as shown on the Contractor's cost accounting records. The DRB shall make recommendations on the merit of the dispute and, if appropriate, recommend guidelines for determining compensation.
- K. Within 30 days after receiving the DRB's report, both the State and the Contractor shall respond to the DRB in writing signifying that the dispute is either resolved or remains unresolved. Failure to provide the written response within the time specified, or a written rejection of the DRB's recommendation or response to a request for

reconsideration presented in the report by either party, shall conclusively indicate that the party(s) failing to respond accepts the DRB recommendation. Immediately after responses have been received from both parties, the DRB shall provide copies of both responses to the parties simultaneously. Either party may request clarification of elements of the DRB's report from the DRB prior to responding to the report. The DRB shall consider any clarification request only if submitted within 10 days of receipt of the DRB's report, and if submitted simultaneously in writing to both the DRB and the other party. Each party may submit only one request for clarification for any individual DRB report. The DRB shall respond, in writing, to requests for clarification within 10 days of receipt of such requests.

- L. The DRB's recommendations, stated in the DRB's reports, are not binding on either party. Either party may seek a reconsideration of a recommendation of the DRB. The DRB shall only grant a reconsideration based upon submission of new evidence and if the request is submitted within the 30-day time limit specified for response to the DRB's written report. Each party may submit only one request for reconsideration regarding an individual DRB recommendation.
- M. If the State and the Contractor are able to resolve their dispute with the aid of the DRB's report, the State and Contractor shall promptly accept and implement the recommendations of the DRB. If the parties cannot agree on compensation within 60 days of the acceptance by both parties of the DRB's recommendation, either party may request the DRB to make a recommendation regarding compensation.
- N. The State or the Contractor shall not call DRB members who served on the DRB for this contract as witnesses in arbitration proceedings which may arise from this contract, and all documents created by the DRB shall be inadmissible as evidence in subsequent arbitration proceedings, except the DRB's final written reports on each issue brought before it.
- O. The State and Contractor shall jointly indemnify and hold harmless the DRB members from and against all claims, damages, losses, and expenses, including but not limited to attorney's fees, arising out of and resulting from the findings and recommendations of the DRB.
- P. The DRB members shall have no claim against the State or the Contractor, or both, from claimed harm arising out of the parties' evaluations of the DRB's report.

5-1.15C(6) Disputes Involving Subcontractor Potential Claims

For purposes of this section, a "subcontractor potential claim" shall include any potential claim by a subcontractor (including also any pass through potential claims by a lower tier subcontractor or supplier) against the Contractor that is actionable by the Contractor against the Department which arises from the work, services, or materials provided or to be provided in connection with the contract. If the Contractor determines to pursue a dispute against the Department that includes a subcontractor potential claim, the dispute shall be processed and resolved in conformance with these special provisions and in conformance with the following:

- A. The Contractor shall identify clearly in submissions pursuant to this section, that portion of the dispute that involves a subcontractor potential claim or potential claims.
- B. The Contractor shall include, as part of its submission pursuant to Step D above, a certification (False Claims Act Certification) by the subcontractor's or supplier's officer, partner, or authorized representative with authority to bind the subcontractor and with direct knowledge of the facts underlying the subcontractor potential claim. The Contractor shall submit a certification that the subcontractor potential claim is acknowledged and forwarded by the Contractor. The form for these certifications is available from the Engineer.
- C. At DRB dispute meetings involving one or more subcontractor potential claims, the Contractor shall require that each subcontractor involved in the dispute have present an authorized representative with actual knowledge of the facts underlying the subcontractor potential claim to assist in presenting the subcontractor potential claim and to answer questions raised by the DRB members or the Department's representatives.
- D. Failure by the Contractor to declare a subcontractor potential claim on behalf of its subcontractor (including lower tier subcontractors' and suppliers' pass through potential claims) at the time of submission of the Contractor's potential claims, as provided hereunder, shall constitute a release of the State by the Contractor of such subcontractor potential claim.
- E. The Contractor shall include in all subcontracts under this contract that subcontractors and suppliers of any tier (a) agree to submit subcontractor potential claims to the Contractor in a proper form and in sufficient time to allow processing by the Contractor in conformance with the Dispute Review Board resolution specifications; (b) agree to be bound by the terms of the Dispute Review Board provisions to the extent applicable to subcontractor potential claims; (c) agree that, to the extent a subcontractor potential claim is involved, completion of all steps required under these Dispute Review Board special provisions shall be a condition precedent to pursuit by the subcontractor of other remedies permitted by law, including without limitation of a lawsuit against the Contractor; and (d) agree that the existence of a dispute resolution process for disputes involving subcontractor potential claims shall not be deemed to create any claim, right, or cause of action by any subcontractor or supplier against the Department.

Notwithstanding the foregoing, this Dispute Review Board special provision shall not apply to, and the DRB shall not have the authority to consider, subcontractor potential claims between the subcontractor(s) or supplier(s) and the Contractor that are not actionable by the Contractor against the Department.

5-1.15C(7) Dispute Review Board Agreement

A copy of the "Dispute Review Board Agreement" to be executed by the Contractor, State and the 3 DRB members after approval of the contract follows:

Form 6202 Rev (09/01/02)

DISPUTE REVIEW BOARD AGREEMENT

(Contract Identification)

Contract No. _____

THIS DISPUTE REVIEW BOARD AGREEMENT, hereinafter called "AGREEMENT", made and entered into this _____ day of _____, _____, between the State of California, acting through the California Department of Transportation and the Director of Transportation, hereinafter called the "STATE," _____ hereinafter called the "CONTRACTOR," and the Dispute Review Board, hereinafter called the "DRB" consisting of the following members:

(Contractor Appointee) ,

(State Appointee) ,

and _____
(Third Person)

WITNESSETH, that

WHEREAS, the STATE and the CONTRACTOR, hereinafter called the "parties," are now engaged in the construction on the State Highway project referenced above; and

WHEREAS, the special provisions for the above referenced contract provides for the establishment and operation of the DRB to assist in resolving disputes; and

WHEREAS, the DRB is composed of three members, one selected by the STATE, one selected by the CONTRACTOR, and the third member selected by the other two members and approved by the parties;

NOW THEREFORE, in consideration of the terms, conditions, covenants, and performance contained herein, or attached and incorporated and made a part hereof, the STATE, the CONTRACTOR, and the DRB members hereto agree as follows:

SECTION I DESCRIPTION OF WORK

To assist in the resolution of disputes between the parties, the contract provides for the establishment and the operation of the DRB. The intent of the DRB is to fairly and impartially consider disputes placed before it and provide written recommendations for resolution of these disputes to both parties. The members of this DRB shall perform the services necessary to participate in the DRB's actions as designated in Section II, Scope of Work.

SECTION II SCOPE OF WORK

The scope of work of the DRB includes, but is not limited to, the following:

A. OBJECTIVE

The principal objective of the DRB is to assist in the timely resolution of disputes between the parties arising from performance of this contract. It is not intended for either party to default on their normal responsibility to amicably and fairly settle their differences by indiscriminately assigning them to the DRB. It is intended that the mere existence of the DRB will encourage the parties to resolve disputes without resorting to this review procedure. But when a dispute that is serious enough to warrant the DRB's review does develop, the process for prompt and efficient action will be in place.

B. PROCEDURES

The DRB shall render written reports on disputes between the parties arising from the construction contract. Prior to consideration of a dispute, the DRB shall establish rules and regulations that will govern the conduct of its business and reporting procedures in conformance with the requirements of the contract and the terms of this AGREEMENT. DRB recommendations, resulting from its consideration of a dispute, shall be furnished in writing to both parties. The recommendations shall be based on facts and circumstances involved in the dispute, pertinent contract provisions, applicable laws and regulations. The recommendations shall find one responsible party in a dispute; shared or "jury" determinations shall not be rendered. The DRB shall make recommendations on the merit of the dispute, and if appropriate, recommend guidelines for determining compensation. If the parties cannot agree on compensation within 60 days of the acceptance by both parties of the DRB's recommendation, either party may request the DRB to make a recommendation regarding compensation.

The DRB shall refrain from officially giving advice or consulting services to anyone involved in the contract. The individual members shall act in a completely independent manner and while serving as members of the DRB shall have no consulting business connections with either party or its principals or attorneys or other affiliates (subcontractors, suppliers, etc.) who have a beneficial interest in the contract.

During scheduled meetings of the DRB as well as during dispute meetings, DRB members shall refrain from expressing opinions on the merits of statements on matters under dispute or potential dispute. Opinions of DRB members expressed in private sessions shall be kept strictly confidential. Individual DRB members shall not meet with, or discuss contract issues with individual parties, except as directed by the DRB Chairperson. Such discussions or meetings shall be disclosed to both parties. Other discussions regarding the project between the DRB members and the parties shall be in the presence of all three members and both parties. Individual DRB members shall not undertake independent investigations of any kind pertaining to disputes or potential disputes, except with the knowledge of both parties and as expressly directed by the DRB Chairperson.

C. CONSTRUCTION SITE VISITS, PROGRESS MEETINGS AND FIELD INSPECTIONS

The DRB members shall visit the project site and meet with representatives of the parties to keep abreast of construction activities and to develop familiarity with the work in progress. Scheduled progress meetings shall be held at or near the project site. The DRB shall meet at least once at the start of the project, and at least once every 4 months thereafter. The frequency, exact time, and duration of additional site visits and progress meetings shall be as recommended by the DRB and approved by the parties consistent with the construction activities or matters under consideration and dispute. Each meeting shall consist of a round table discussion and a field inspection of the work being performed on the contract, if necessary. Each meeting shall be attended by representatives of both parties. The agenda shall generally be as follows:

1. Meeting opened by the DRB Chairperson.
2. Remarks by the STATE's representative.
3. A description by the CONTRACTOR's representative of work accomplished since the last meeting; the current schedule status of the work; and a forecast for the coming period.
4. An outline by the CONTRACTOR's representative of potential problems and a description of proposed solutions.
5. An outline by the STATE's representative of the status of the work as the STATE views it.
6. A brief description by the CONTRACTOR's or STATE's representative of potential claims or disputes which have surfaced since the last meeting.
7. A summary by the STATE's representative, the CONTRACTOR's representative, or the DRB of the status of past disputes and potential claims.

The STATE's representative will prepare minutes of all progress meetings and circulate them for revision and approval by all concerned within 10 days of the meeting.

The field inspection shall cover all active segments of the work, the DRB being accompanied by both parties' representatives. The field inspection may be waived upon mutual agreement of the parties.

D. DRB CONSIDERATION AND HANDLING OF DISPUTES

Upon receipt by the DRB of a written referral of a dispute, the DRB shall convene to review and consider the dispute. The dispute meeting shall be held no earlier than 30 days and no later than 60 days after receipt of the written referral, unless otherwise agreed to by all parties. The DRB shall determine the time and location of DRB dispute meetings, with due consideration for the needs and preferences of the parties while recognizing the paramount importance of speedy resolution of issues. No dispute meetings shall take place later than 30 days prior to acceptance of contract.

Normally, dispute meetings shall be conducted at or near the project site. However, any location that would be more convenient and still provide required facilities and access to necessary documentation shall be satisfactory.

Both parties shall be given the opportunity to present their evidence at these dispute meetings. It is expressly understood that the DRB members are to act impartially and independently in the consideration of the contract provisions, applicable laws and regulations, and the facts and conditions surrounding any dispute presented by either party, and that the recommendations concerning any such dispute are advisory and nonbinding on the parties.

The DRB may request that written documentation and arguments from both parties be sent to each DRB member, through the DRB Chairperson, for review before the dispute meeting begins. A party furnishing written documentation to the DRB shall furnish copies of such information to the other party at the same time that such information is supplied to the DRB.

DRB dispute meetings shall be informal. There shall be no testimony under oath or cross-examination. There shall be no reporting of the procedures by a shorthand reporter or by electronic means. Documents and verbal statements shall be received by the DRB in conformance with acceptance standards established by the DRB. These standards need not comply with prescribed legal laws of evidence.

The third DRB member shall act as Chairperson for dispute meetings and all other DRB activities. The parties shall have a representative at all dispute meetings. Failure to attend a duly noticed dispute meeting by either of the parties shall be conclusively considered by the DRB as indication that the non-attending party considers written submittals as their entire and complete argument. The claimant shall discuss the dispute, followed by the other party. Each party shall then be allowed one or more rebuttals until all aspects of the dispute are thoroughly covered. DRB members shall ask questions, seek clarification, and request further data from either of the parties as may be necessary to assist in making a fully informed recommendation. The DRB may request from either party documents or information that would assist the DRB in making its findings and recommendations including, but not limited to, documents used by the CONTRACTOR in preparing the bid for the project. A refusal by a party to provide information requested by the DRB may be considered by the DRB as an indication that the requested material would tend to disprove that party's position. In large or complex cases, additional dispute meetings may be necessary in order to consider all the evidence presented by both parties. All involved parties shall maintain the confidentiality of all documents and information, as provided in this AGREEMENT.

During dispute meetings, no DRB member shall express an opinion concerning the merit of any facet of the case. DRB deliberations shall be conducted in private, with interim individual views kept strictly confidential.

After dispute meetings are concluded, the DRB shall meet in private and reach a conclusion supported by 2 or more members. Private sessions of the DRB may be held at a location other than the job site or by electronic conferencing as deemed appropriate, in order to expedite the process.

The DRB's findings and recommendations, along with discussion of reasons therefor, shall then be submitted as a written report to both parties. Recommendations shall be based on the pertinent contract provisions, applicable laws and regulations, and facts and circumstances related to the dispute. The report shall be thorough in discussing the facts considered, the contract language, law or regulation viewed by the DRB as pertinent to the issues, and the DRB's interpretation and philosophy in arriving at its conclusions and recommendations. The DRB's report shall stand on its own, without attachments or appendices. The DRB Chairperson shall furnish a copy of the written recommendation report to the DRB Coordinator, Division of Construction, MS 44, P.O. Box 942874, Sacramento, CA 94274.

With prior written approval of both parties, the DRB may obtain technical services necessary to adequately review the disputes presented, including audit, geotechnical, schedule analysis and other services. The parties' technical staff may supply those services as appropriate. The cost of technical services, as agreed to by the parties, shall be borne equally by the 2 parties as specified in an approved contract change order. The CONTRACTOR will not be entitled to markups for the payments made for these services.

The DRB shall resist submittal of incremental portions of information by either party, in the interest of making a fully informed decision and recommendation.

The DRB shall make every effort to reach a unanimous decision. If this proves impossible, the dissenting member shall prepare a minority opinion, which shall be included in the DRB's report.

Although both parties should place weight upon the DRB's recommendations, they are not binding. Either party may appeal a recommendation to the DRB for reconsideration. However, reconsideration shall only be allowed when there is new evidence to present, and the DRB shall accept only one appeal from each party pertaining to an individual DRB recommendation. The DRB shall hear appeals in conformance with the terms described in the Section entitled "Dispute Review Board" in the special provisions.

E. DRB MEMBER REPLACEMENT

Should the need arise to appoint a replacement DRB member, the replacement DRB member shall be appointed in the same manner as the original DRB members were appointed. The selection of a replacement DRB member shall begin promptly upon notification of the necessity for a replacement and shall be completed within 15 days. This AGREEMENT shall be amended to indicate change in DRB membership.

SECTION III CONTRACTOR RESPONSIBILITIES

The CONTRACTOR shall furnish to each DRB member one copy of pertinent documents that are or may become necessary for the DRB to perform their function. Pertinent documents are written notices of potential claim, responses to those notices, drawings or sketches, calculations, procedures, schedules, estimates, or other documents which are used in the performance of the work or in justifying or substantiating the CONTRACTOR's position. The CONTRACTOR shall also furnish a copy of such pertinent documents to the STATE, in conformance with the terms outlined in the special provisions.

SECTION IV STATE RESPONSIBILITIES

The STATE will furnish the following services and items:

A. CONTRACT RELATED DOCUMENTS

The STATE will furnish to each DRB member one copy of Notice to Contractors and Special Provisions, Proposal and Contract, Plans, Standard Specifications, and Standard Plans, change orders, written instructions issued by the STATE to the CONTRACTOR, or other documents pertinent to any dispute that has been referred to the DRB and necessary for the DRB to perform its function.

B. COORDINATION AND SERVICES

The STATE, through the Engineer, will, in cooperation with the CONTRACTOR, coordinate the operations of the DRB. The Engineer will arrange or provide conference facilities at or near the project site and provide secretarial and copying services to the DRB without charge to the CONTRACTOR.

SECTION V TIME FOR BEGINNING AND COMPLETION

Once established, the DRB shall be in operation until the day of acceptance of the contract. The DRB members shall not begin work under the terms of this AGREEMENT until authorized in writing by the STATE.

SECTION VI PAYMENT

A. ALL INCLUSIVE RATE PAYMENT

The STATE and the CONTRACTOR shall bear the costs and expenses of the DRB equally. Each DRB member shall be compensated at an agreed rate of \$1,200 per day if time spent per meeting, including on-site time plus one hour of travel time, is greater than 4 hours. Each DRB member shall be compensated at an agreed rate of \$700 per day if time spent per meeting, including on-site time plus one hour of travel time, is less than or equal to 4 hours. The agreed rates shall be considered full compensation for on-site time, travel expenses, transportation, lodging, time for travel and incidentals for each day, or portion thereof, that the DRB member is at an authorized DRB meeting. No additional compensation will be made for time spent by DRB members in review and research activities outside the official DRB meetings unless that time has been specifically agreed to in advance by the STATE and CONTRACTOR. Time away from the project that has been specifically agreed to in advance by the parties will be compensated at an agreed rate of \$125 per hour. The agreed amount of \$125 per hour shall include all incidentals including expenses for telephone, fax, and computer services. Members serving on more than one DRB involving the State, regardless of the number of meetings per day, shall not be paid more than the all inclusive rate per day or rate per hour for an individual project. The STATE will provide, at no cost to the CONTRACTOR, administrative services such as conference facilities and secretarial services to the DRB.

B. PAYMENTS

DRB members shall be compensated at the same rate. The CONTRACTOR shall make direct payments to each DRB member for their participation in authorized meetings and approved hourly rate charges from invoices submitted by each DRB member. The STATE will reimburse the CONTRACTOR for its share of the costs of the DRB.

The DRB members may submit invoices to the CONTRACTOR for partial payment for work performed and services rendered for their participation in authorized meetings not more often than once per month during the progress of the work. The invoices shall be in a format approved by the parties and accompanied by a general description of activities performed during that billing period. Payment for hourly fees, at the agreed rate, shall not be paid to a DRB member until the amount and extent of those fees are approved by the STATE and CONTRACTOR.

Invoices shall be accompanied by original supporting documents, which the CONTRACTOR shall include with the extra work billing when submitting for reimbursement of the STATE's share of cost from the STATE. The CONTRACTOR will be reimbursed for one-half of approved costs of the DRB. No markups will be added to the CONTRACTOR's payment.

C. INSPECTION OF COSTS RECORDS

The DRB members and the CONTRACTOR shall keep available for inspection by representatives of the STATE and the United States, for a period of 3 years after final payment, the cost records and accounts pertaining to this AGREEMENT. If any litigation, claim, or audit arising out of, in connection with, or related to this contract is initiated before the expiration of the 3-year period, the cost records and accounts shall be retained until such litigation, claim, or audit involving the records is completed.

SECTION VII ASSIGNMENT OF TASKS OF WORK

The DRB members shall not assign the work of this AGREEMENT.

SECTION VIII TERMINATION OF DRB MEMBERS

DRB members may resign from the DRB by providing not less than 15 days written notice of the resignation to the STATE and CONTRACTOR. DRB members may be terminated by their original appointing power or by either party, for failing to fully comply at all times with all required employment and financial disclosure conditions of DRB membership in conformance with the terms of the contract.

SECTION IX LEGAL RELATIONS

The parties hereto mutually understand and agree that the DRB member in the performance of duties on the DRB, is acting in the capacity of an independent agent and not as an employee of either party.

No party to this AGREEMENT shall bear a greater responsibility for damages or personal injury than is normally provided by Federal or State of California Law.

Notwithstanding the provisions of this contract that require the CONTRACTOR to indemnify and hold harmless the STATE, the parties shall jointly indemnify and hold harmless the DRB members from and against all claims, damages, losses, and expenses, including but not limited to attorney's fees, arising out of and resulting from the findings and recommendations of the DRB.

SECTION X CONFIDENTIALITY

The parties hereto mutually understand and agree that all documents and records provided by the parties in reference to issues brought before the DRB, which documents and records are marked "Confidential - for use by the DRB only," shall be kept in confidence and used only for the purpose of resolution of subject disputes, and for assisting in development of DRB findings and recommendations; that such documents and records will not be utilized or revealed to others, except to officials of the parties who are authorized to act on the subject disputes, for any purposes, during the life of the DRB. Upon termination of this AGREEMENT, said confidential documents and records, and all copies thereof, shall be returned to the parties who furnished them to the DRB. However, the parties understand that such documents shall be subsequently discoverable and admissible in court or arbitration proceedings unless a protective order has been obtained by the party seeking further confidentiality.

SECTION XI DISPUTES

Disputes between the parties hereto, including disputes between the DRB members and either party or both parties, arising out of the work or other terms of this AGREEMENT, which cannot be resolved by negotiation and mutual concurrence between the parties, or through the administrative process provided in the contract, shall be resolved by arbitration as provided in Section 9-1.10, "Arbitration," of the Standard Specifications.

SECTION XII VENUE, APPLICABLE LAW, AND PERSONAL JURISDICTION

In the event that any party, including an individual member of the DRB, deems it necessary to institute arbitration proceedings to enforce any right or obligation under this AGREEMENT, the parties hereto agree that such action shall be initiated in the Office of Administrative Hearings of the State of California. The parties hereto agree that all questions shall be resolved by arbitration by application of California law and that the parties to such arbitration shall have the right of appeal from such decisions to the Superior Court in conformance with the laws of the State of California. Venue for the arbitration shall be Sacramento or any other location as agreed to by the parties.

Add:

6-1.075 GUARANTEE

Guarantee the work remains free from substantial defects for 1 year after contract acceptance except for work parts for which you were relieved of maintenance and protection. Guarantee each of these relieved work parts for 1 year after the relief date.

The guarantee excludes damage or displacement caused by an event outside your control including:

1. Normal wear and tear
2. Improper operation
3. Insufficient maintenance
4. Abuse
5. Unauthorized change
6. Act of God

During the guarantee period, repair or replace each work portion having a substantial defect.

The Department does not pay for corrective work.

During corrective work activities, provide insurance coverage specified for coverage before contract acceptance.

The contract bonds must be in full force and effect until the later of:

1. Expiration of guarantee period
2. Completion of corrective work

If a warranty specification conflicts with Section 6-1.075, "Guarantee," comply with the warranty specification.

During the guarantee period, the Engineer monitors the completed work. If the Engineer finds work having a substantial defect, the Engineer lists work parts and furnishes you the list.

Within 10 days of receipt of the list, submit for authorization a detailed plan for correcting the work. Include a schedule that includes:

1. Start and completion dates
2. List of labor, equipment, materials, and any special services you plan to use
3. Work related to the corrective work, including traffic control and temporary and permanent pavement markings

The Engineer notifies you when the plan is authorized. Start corrective work and related work within 15 days of notice.

If the Engineer determines corrective work is urgently required to prevent injury or property damage:

1. The Engineer furnishes you a request to start emergency repair work and a list of parts requiring corrective work
2. Mobilize within 24 hours and start work
3. Submit a corrective work plan within 5 days of starting emergency repair work

If you fail to perform work as specified, the Department may perform the work and bill you.

Add:

6-1.085 BUY AMERICA (23 CFR 635.410)

For a Federal-aid contract, furnish steel and iron materials to be incorporated into the work that are produced in the United States except:

1. Foreign pig iron and processed, pelletized, and reduced iron ore may be used in the domestic production of the steel and iron materials [60 Fed Reg 15478 (03/24/1995)]
2. If the total combined cost of the materials does not exceed the greater of 0.1 percent of the total bid or \$2,500, material produced outside the United States may be used

Production includes:

1. Processing steel and iron materials, including smelting or other processes that alter the physical form or shape (such as rolling, extruding, machining, bending, grinding, and drilling) or chemical composition
2. Coating application, including epoxy coating, galvanizing, and painting, that protects or enhances the value of steel and iron materials

employees. Immediately report to the Engineer in writing a discrepancy or inconsistency between the contract and a law, regulation, order, decree, or PLAC.

In Section 7-1.01A replace the 1st clause with:

Work on the job site must comply with Labor Code §§ 1727 and 1770-1815 and 8 CA Code of Regs § 16000 et seq. Work includes roadside production and processing of materials.

In Section 7-1.01A(2) in the 1st paragraph, replace item 3 with:

3. Upon becoming aware of the subcontractor's failure to pay the specified prevailing rate of wages to the subcontractor's workers, the Contractor must diligently take corrective action to stop or rectify the failure, including withholding sufficient funds due the subcontractor for work performed on the public works project.

In Section 7-1.01A(2), replace the 2nd paragraph with:

Pursuant to Section 1775 of the Labor Code, the Division of Labor Standards Enforcement must notify the Contractor on a public works project within 15 days of the receipt by the Division of Labor Standards Enforcement of a complaint of the failure of a subcontractor on that public works project to pay workers the general prevailing rate of per diem wages. If the Division of Labor Standards Enforcement determines that employees of a subcontractor were not paid the general prevailing rate of per diem wages and if the Department did not withhold sufficient money under the contract to pay those employees the balance of wages owed under the general prevailing rate of per diem wages, the Contractor must withhold an amount of moneys due the subcontractor sufficient to pay those employees the general prevailing rate of per diem wages if requested by the Division of Labor Standards Enforcement. The Contractor must pay any money withheld from and owed to a subcontractor upon receipt of notification by the Division of Labor Standards Enforcement that the wage complaint has been resolved. If notice of the resolution of the wage complaint has not been received by the Contractor within 180 days of the filing of a valid notice of completion or acceptance of the public works project, whichever occurs later, the Contractor must pay all moneys withheld from the subcontractor to the Department. The Department withholds these moneys pending the final decision of an enforcement action.

In Section 7-1.01A(2) replace 7th paragraph with:

Changes in general prevailing wage determinations apply to the contract when the Director of Industrial Relations has issued them at least 10 days before advertisement (Labor Code § 1773.6 and 8 CA Code of Regs 16204).

In Section 7-1.01A(3) replace the 2nd paragraph with:

The Department withholds the penalties specified in subdivision (g) of Labor Code § 1776 for noncompliance with the requirements in Section 1776.

In Section 7-1.01A(3) replace the 4th paragraph with:

The Department withholds for delinquent or inadequate payroll records (Labor Code § 1771.5). If the Contractor has not submitted an adequate payroll record by the month's 15th day for the period ending on or before the 1st of that month, the Department withholds 10 percent of the monthly progress estimate, exclusive of mobilization. The Department does not withhold more than \$10,000 or less than \$1,000.

In Section 7-1.01A(3) delete the 5th paragraph.

Replace Section 7-1.01A(6) with:

7-1.01A(6) (Blank)

Add:

7-1.01K Solid Waste Disposal and Recycling

Submit an annual Solid Waste Disposal and Recycling Report between January 1 and 15 for each year work is performed under the Contract at any time during the previous calendar year. Show the types and amounts of project-generated solid waste taken to or diverted from landfills or reused on the project from January 1 through December 31 of the previous calendar year.

Submit a final annual Solid Waste Disposal and Recycling Report within 5 business days after Contract acceptance. Show the types and amounts of project-generated solid waste taken to or diverted from landfills or reused on the project from January 1 to contract acceptance.

For each failure to submit a completed form, the Department withholds \$10,000.

Add:

7-1.01L Asbestos and Hazardous Substances

• Upon discovery, immediately stop working in and notify the Engineer of areas where asbestos or a hazardous substance is present if the:

1. Contractor reasonably believes the substance is asbestos as defined in Labor Code § 6501.7 or a hazardous substance as defined in Health & Safety Code §§ 25316 and 25317
2. Presence is not described in the contract
3. Substance has not been made harmless

Add:

7-1.01M Archaeological Discoveries

If archaeological materials are discovered at the job site, protect and leave them undisturbed in place and comply with:

1. Pub Res Code §§ 5097.5, 5097.98, and 5097.99
2. 14 CA Code of Regs § 4308
4. Penal Code § 622-1/2
5. Health & Safety Code § 7050.5

Archaeological materials are the remains of past human activity including historic-period archaeological materials and prehistoric Native American archaeological materials. Nonhuman fossils are not archaeological materials unless they show direct evidence of human use or alteration or when found in direct physical association with archaeological materials

Historic-period archaeological materials include cultural remains beginning with initial European contact in California but at least 50 years old and include:

1. Trash deposits or clearly defined disposal pits containing tin cans, bottles, ceramic dishes, or other refuse indicating previous occupation or use of the site
2. Structural remains of stone, brick, concrete, wood, or other building material found above or below ground
3. Human skeletal remains from the historic period, with or without coffins or caskets, including any associated grave goods

Prehistoric Native American archaeological materials include:

1. Human skeletal remains or associated burial goods such as beads or ornaments
2. Evidence of tool making or hunting such as arrowheads and associated chipping debris of fine-grained materials such as obsidian, chert, or basalt
3. Evidence of plant processing such as pestles, grinding slabs, or stone bowls
4. Evidence of habitation such as cooking pits, stone hearths, packed or burnt earth floors
5. Remains from food processing such as concentrations of discarded or burnt animal bone, shellfish remains, or burnt rocks used in cooking

Immediately upon discovering archaeological materials, stop all work within a 60-foot radius of the archaeological materials and notify the Engineer. Archaeological materials discovered are the property of the State. Do not resume work within the 60-foot radius of the discovery until the Engineer gives you written approval. If, in the opinion of the Engineer,

completion of the work is delayed or interfered with by reason of an archeological discovery or investigation or recovery of archeological materials, you will be compensated for resulting losses and an extension of time will be granted in the same manner as provided for in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The Department may use other forces to investigate and recover archaeological materials from the location of the discovery. If ordered by the Engineer furnish labor, material, tools, and equipment to secure the location of the discovery and assist in the investigation or recovery of archaeological materials; the cost of this work will be paid for as extra work as specified in Section 4-1.03D, "Extra Work," of the Standard Specifications.

In Section 7-1.02 in the 2nd paragraph, replace the 4th sentence with:

Trucks used to haul treated base, portland cement concrete, or hot mix asphalt shall enter onto the base to dump at the nearest practical entry point ahead of spreading equipment.

In Section 7-1.02 between the 4th and 5th paragraphs, add:

Loads imposed on existing, new, or partially completed structures shall not exceed the load carrying capacity of the structure or any portion of the structure as determined by AASHTO LRFD with interims and California Amendments, Design Strength Limit State II. The compressive strength of concrete (f_c) to be used in computing the load carrying capacity shall be the smaller of the following:

1. Actual compressive strength at the time of loading
2. Value of f_c shown on the plans for that portion of the structure or 2.5 times the value of f_c (extreme fiber compressive stress in concrete at service loads) shown on the plans for portions of the structure where no f_c is shown

In Section 7-1.06 in the 1st paragraph, add:

The Contractor's Injury and Illness Prevention Program shall be submitted to the Engineer. The program shall address the use of personal and company issued electronic devices during work. The use of entertainment and personal communication devices in the work zone shall not be allowed. Workers may use a communication device for business purposes in the work area, at a location where their safety and the safety of other workers and the traveling public is not compromised.

In Section 7-1.09 in the 8th paragraph, replace the 1st sentence with:

Signs, lights, flags, and other warning and safety devices and their use shall conform to the requirements set forth in Part 6 of the California MUTCD except where a discrepancy exists between the California MUTCD and the specifications; for discrepancies, comply with the specifications.

In Section 7-1.09 replace the 16th paragraph with:

When vertical clearance is temporarily reduced to 15.5 feet or less, low clearance warning signs shall be placed in accordance with Part 2 of the California MUTCD and as directed by the Engineer. Signs shall conform to the dimensions, color, and legend requirements of the California MUTCD and these specifications except that the signs shall have black letters and numbers on an orange retroreflective background. W12-2P signs shall be illuminated so that the signs are clearly visible.

Add to Section 7-1.09:

The Contractor shall install temporary railing (Type K) between a lane open to public traffic and an excavation, obstacle or storage area when the following conditions exist:

- A. Excavations-The near edge of the excavation is 12 feet or less from the edge of the lane, except:
 1. Excavations covered with sheet steel or concrete covers of adequate thickness to prevent accidental entry by traffic or the public.
 2. Excavations less than one foot deep.

3. Trenches less than one foot wide for irrigation pipe or electrical conduit, or excavations less than one foot in diameter.
 4. Excavations parallel to the lane for the purpose of pavement widening or reconstruction.
 5. Excavations in side slopes, where the slope is steeper than 4:1 (horizontal:vertical).
 6. Excavations protected by existing barrier or railing.
- B. Temporarily Unprotected Permanent Obstacles-The work includes the installation of a fixed obstacle together with a protective system, such as a sign structure together with protective railing, and the Contractor elects to install the obstacle prior to installing the protective system; or the Contractor, for the Contractor's convenience and with permission of the Engineer, removes a portion of an existing protective railing at an obstacle and does not replace such railing complete in place during the same day.
- C. Storage Areas-Material or equipment is stored within 12 feet of the lane and the storage is not otherwise prohibited by the provisions of the Standard Specifications and these special provisions.

The approach end of temporary railing (Type K), installed in conformance with the provisions in this section "Public Safety" and in Section 7-1.09, "Public Safety," of the Standard Specifications, shall be offset a minimum of 15 feet from the edge of the traffic lane open to public traffic. The temporary railing shall be installed on a skew toward the edge of the traffic lane of not more than one foot transversely to 10 feet longitudinally with respect to the edge of the traffic lane. If the 15-foot minimum offset cannot be achieved, the temporary railing shall be installed on the 10 to 1 skew to obtain the maximum available offset between the approach end of the railing and the edge of the traffic lane, and an array of temporary crash cushion modules shall be installed at the approach end of the temporary railing.

Temporary railing (Type K) shall be secured in place before starting work for which the temporary railing is required.

Except for installing, maintaining and removing traffic control devices, whenever work is performed or equipment is operated in the following work areas, the Contractor shall close the adjacent traffic lane unless otherwise provided in the Standard Specifications and these special provisions:

Approach Speed of Public Traffic (Posted Limit) (Miles Per Hour)	Work Areas
Over 45	Within 6 feet of a traffic lane but not on a traffic lane
35 to 45	Within 3 feet of a traffic lane but not on a traffic lane

The lane closure provisions of this section shall not apply if the work area is protected by permanent or temporary railing or barrier.

When traffic cones or delineators are used to delineate a temporary edge of a traffic lane, the line of cones or delineators shall be considered to be the edge of the traffic lane, however, the Contractor shall not reduce the width of an existing lane to less than 10 feet without written approval from the Engineer.

When work is not in progress on a trench or other excavation that required closure of an adjacent lane, the traffic cones or portable delineators used for the lane closure shall be placed off of and adjacent to the edge of the traveled way. The spacing of the cones or delineators shall be not more than the spacing used for the lane closure.

Suspended loads or equipment shall not be moved nor positioned over public traffic or pedestrians.

In Section 7-1.11 in the 2nd paragraph, replace the last sentence with:

The cost of the repairs must be borne by the Contractor and will be deducted.

Replace Section 7-1.12 with:

7-1.12 INDEMNIFICATION AND INSURANCE

The Contractor's obligations regarding indemnification of the State of California and the requirements for insurance shall conform to the provisions in Section 3-1.025, "Insurance Policies," and Sections 7-1.12A, "Indemnification," and 7-1.12B, "Insurance," of this Section 7-1.12.

7-1.12A Indemnification

The Contractor shall defend, indemnify, and save harmless the State, including its officers, employees, and agents (excluding agents who are design professionals) from any and all claims, demands, causes of action, damages, costs, expenses, actual attorneys' fees, losses or liabilities, in law or in equity (Section 7-1.12A Claims) arising out of or in connection with the Contractor's performance of this contract for:

1. Bodily injury including, but not limited to, bodily injury, sickness or disease, emotional injury or death to persons, including, but not limited to, the public, any employees or agents of the Contractor, the State, or any other contractor; and
2. Damage to property of anyone including loss of use thereof; caused or alleged to be caused in whole or in part by any negligent or otherwise legally actionable act or omission of the Contractor or anyone directly or indirectly employed by the Contractor or anyone for whose acts the Contractor may be liable.

Except as otherwise provided by law, these requirements apply regardless of the existence or degree of fault of the State. The Contractor is not obligated to indemnify the State for Claims arising from conduct delineated in Civil Code Section 2782 and to Claims arising from any defective or substandard condition of the highway that existed at or before the start of work, unless this condition has been changed by the work or the scope of the work requires the Contractor to maintain existing highway facilities and the Claim arises from the Contractor's failure to maintain. The Contractor's defense and indemnity obligation shall extend to Claims arising after the work is completed and accepted if the Claims are directly related to alleged acts or omissions by the Contractor that occurred during the course of the work. State inspection is not a waiver of full compliance with these requirements.

The Contractor's obligation to defend and indemnify shall not be excused because of the Contractor's inability to evaluate liability or because the Contractor evaluates liability and determine that the Contractor is not liable. The Contractor shall respond within 30 days to the tender of any Claim for defense and indemnity by the State, unless this time has been extended by the State. If the Contractor fails to accept or reject a tender of defense and indemnity within 30 days, in addition to any other remedy authorized by law, the Department may withhold such funds the State reasonably considers necessary for its defense and indemnity until disposition has been made of the Claim or until the Contractor accepts or rejects the tender of defense, whichever occurs first.

With respect to third-party claims against the Contractor, the Contractor waives all rights of any type to express or implied indemnity against the State, its officers, employees, or agents (excluding agents who are design professionals).

Nothing in the Contract is intended to establish a standard of care owed to any member of the public or to extend to the public the status of a third-party beneficiary for any of these indemnification specifications.

7-1.12B Insurance

7-1.12B(1) General

Nothing in the contract is intended to establish a standard of care owed to any member of the public or to extend to the public the status of a third-party beneficiary for any of these insurance specifications.

7-1.12B(2) Casualty Insurance

The Contractor shall procure and maintain insurance on all of its operations with companies acceptable to the State as follows:

1. The Contractor shall keep all insurance in full force and effect from the beginning of the work through contract acceptance.
2. All insurance shall be with an insurance company with a rating from A.M. Best Financial Strength Rating of A- or better and a Financial Size Category of VII or better.
3. The Contractor shall maintain completed operations coverage with a carrier acceptable to the State through the expiration of the patent deficiency in construction statute of repose set forth in Code of Civil Procedure Section 337.1.

7-1.12B(3) Workers' Compensation and Employer's Liability Insurance

In accordance with Labor Code Section 1860, the Contractor shall secure the payment of worker's compensation in accordance with Labor Code Section 3700.

In accordance with Labor Code Section 1861, the Contractor shall submit to the Department the following certification before performing the work:

I am aware of the provisions of Section 3700 of the Labor Code which require every employer to be insured against liability for workers' compensation or to undertake self-insurance in accordance with the provisions of that code, and I will comply with such provisions before commencing the performance of the work of this contract.

Contract execution constitutes certification submittal.

The Contractor shall provide Employer's Liability Insurance in amounts not less than:

1. \$1,000,000 for each accident for bodily injury by accident
2. \$1,000,000 policy limit for bodily injury by disease
3. \$1,000,000 for each employee for bodily injury by disease

If there is an exposure of injury to the Contractor's employees under the U.S. Longshoremen's and Harbor Workers' Compensation Act, the Jones Act, or under laws, regulations, or statutes applicable to maritime employees, coverage shall be included for such injuries or claims.

7-1.12B(4) Liability Insurance

7-1.12B(4)(a) General

The Contractor shall carry General Liability and Umbrella or Excess Liability Insurance covering all operations by or on behalf of the Contractor providing insurance for bodily injury liability and property damage liability for the following limits and including coverage for:

1. Premises, operations, and mobile equipment
2. Products and completed operations
3. Broad form property damage (including completed operations)
4. Explosion, collapse, and underground hazards
5. Personal injury
6. Contractual liability

7-1.12B(4)(b) Liability Limits/Additional Insureds

The limits of liability shall be at least the amounts shown in the following table:

Total Bid	For Each Occurrence ¹	Aggregate for Products/Completed Operation	General Aggregate ²	Umbrella or Excess Liability ³
≤\$1,000,000	\$1,000,000	\$2,000,000	\$2,000,000	\$5,000,000
>\$1,000,000 ≤\$5,000,000	\$1,000,000	\$2,000,000	\$2,000,000	\$10,000,000
>\$5,000,000 ≤\$25,000,000	\$2,000,000	\$2,000,000	\$4,000,000	\$15,000,000
>\$25,000,000	\$2,000,000	\$2,000,000	\$4,000,000	\$25,000,000
<ol style="list-style-type: none"> 1. Combined single limit for bodily injury and property damage. 2. This limit shall apply separately to the Contractor's work under this contract. 3. The umbrella or excess policy shall contain a clause stating that it takes effect (drops down) in the event the primary limits are impaired or exhausted. 				

The Contractor shall not require certified Small Business subcontractors to carry Liability Insurance that exceeds the limits in the table above. Notwithstanding the limits specified herein, at the option of the Contractor, the liability insurance limits for certified Small Business subcontractors of any tier may be less than those limits specified in the table. For Small Business subcontracts, "Total Bid" shall be interpreted as the amount of subcontracted work to a certified Small Business.

The State, including its officers, directors, agents (excluding agents who are design professionals), and employees, shall be named as additional insureds under the General Liability and Umbrella Liability Policies with respect to liability arising out of or connected with work or operations performed by or on behalf of the Contractor under this contract. Coverage for such additional insureds does not extend to liability:

1. Arising from any defective or substandard condition of the roadway which existed at or before the time the Contractor started work, unless such condition has been changed by the work or the scope of the work requires the Contractor to maintain existing roadway facilities and the claim arises from the Contractor's failure to maintain;
2. For claims occurring after the work is completed and accepted unless these claims are directly related to alleged acts or omissions of the Contractor that occurred during the course of the work; or
3. To the extent prohibited by Insurance Code Section 11580.04

Additional insured coverage shall be provided by a policy provision or by an endorsement providing coverage at least as broad as Additional Insured (Form B) endorsement form CG 2010, as published by the Insurance Services Office (ISO), or other form designated by the Department.

7-1.12B(4)(c) Contractor's Insurance Policy is Primary

The policy shall stipulate that the insurance afforded the additional insureds applies as primary insurance. Any other insurance or self-insurance maintained by the State is excess only and shall not be called upon to contribute with this insurance.

7-1.12B(5) Automobile Liability Insurance

The Contractor shall carry automobile liability insurance, including coverage for all owned, hired, and nonowned automobiles. The primary limits of liability shall be not less than \$1,000,000 combined single limit each accident for bodily injury and property damage. The umbrella or excess liability coverage required under Section 7-1.12B(4)(b) also applies to automobile liability.

7-1.12B(6) Policy Forms, Endorsements, and Certificates

The Contractor shall provide its General Liability Insurance under Commercial General Liability policy form No. CG0001 as published by the Insurance Services Office (ISO) or under a policy form at least as broad as policy form No. CG0001.

7-1.12B(7) Deductibles

The State may expressly allow deductible clauses, which it does not consider excessive, overly broad, or harmful to the interests of the State. Regardless of the allowance of exclusions or deductions by the State, the Contractor is responsible for any deductible amount and shall warrant that the coverage provided to the State is in accordance with Section 7-1.12B, "Insurance."

7-1.12B(8) Enforcement

The Department may assure the Contractor's compliance with its insurance obligations. Ten days before an insurance policy lapses or is canceled during the contract period, the Contractor shall submit to the Department evidence of renewal or replacement of the policy.

If the Contractor fails to maintain any required insurance coverage, the Department may maintain this coverage and withhold or charge the expense to the Contractor or terminate the Contractor's control of the work in accordance with Section 8-1.08, "Termination of Control."

The Contractor is not relieved of its duties and responsibilities to indemnify, defend, and hold harmless the State, its officers, agents, and employees by the Department's acceptance of insurance policies and certificates.

Minimum insurance coverage amounts do not relieve the Contractor for liability in excess of such coverage, nor do they preclude the State from taking other actions available to it, including the withholding of funds under this contract.

7-1.12B(9) Self-Insurance

Self-insurance programs and self-insured retentions in insurance policies are subject to separate annual review and approval by the State.

If the Contractor uses a self-insurance program or self-insured retention, the Contractor shall provide the State with the same protection from liability and defense of suits as would be afforded by first-dollar insurance. Execution of the contract is the Contractor's acknowledgement that the Contractor will be bound by all laws as if the Contractor were an insurer as defined under Insurance Code Section 23 and that the self-insurance program or self-insured retention shall operate as insurance as defined under Insurance Code Section 22.

In Section 7-1.13 delete the 5th and 6th paragraphs.

Add:

7-1.50 FEDERAL LAWS FOR FEDERAL-AID CONTRACTS

7-1.50A General

Section 7-1.50, "Federal Laws for Federal-Aid Contracts," includes specifications required in a Federal-aid construction contract and applies to a Federal-aid contract.

Form FHWA-1273 is included in the contract in Section 7-1.50B, "FHWA-1273." Some contract terms on the form are different than those used in other contract parts as shown in the following table:

FHWA-1273 Terms and Department Equivalencies

FHWA-1273 Term	Equivalent Term Used in Other Contract Parts
SHA	Department
SHA contracting officer	Engineer
SHA resident engineer	Engineer

7-1.50B FHWA-1273

FHWA-1273 Electronic version -- March 10, 1994
with revised Section VI

REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS

- I. General
- II. Nondiscrimination
- III. Nonsegregated Facilities
- IV. Payment of Predetermined Minimum Wage
- V. Statements and Payrolls
- VI. Record of Materials, Supplies, and Labor
- VII. Subletting or Assigning the Contract
- VIII. Safety: Accident Prevention
- IX. False Statements Concerning Highway Projects
- X. Implementation of Clean Air Act and Federal Water Pollution Control Act
- XI. Certification Regarding Debarment, Suspension, Ineligibility, and Voluntary Exclusion
- XII. Certification Regarding Use of Contract Funds for Lobbying

ATTACHMENTS

- A. Employment Preference for Appalachian Contracts (included in Appalachian contracts only)

I. GENERAL

1. These contract provisions shall apply to all work performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.
2. Except as otherwise provided for in each section, the contractor shall insert in each subcontract all of the stipulations contained in these Required Contract Provisions, and further require their inclusion in any lower tier subcontract or purchase order that may in turn be made. The Required Contract Provisions shall not be incorporated by reference in any case. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with these Required Contract Provisions.
3. A breach of any of the stipulations contained in these Required Contract Provisions shall be sufficient grounds for termination of the contract.
4. A breach of the following clauses of the Required Contract Provisions may also be grounds for debarment as provided in 29 CFR 5.12:

 Section I, paragraph 2;
 Section IV, paragraphs 1, 2, 3, 4, and 7;
 Section V, paragraphs 1 and 2a through 2g.
5. Disputes arising out of the labor standards provisions of Section IV (except paragraph 5) and Section V of these Required Contract Provisions shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the U.S. Department of Labor (DOL) as set forth in 29 CFR 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the DOL, or the contractor's employees or their representatives.
6. **Selection of Labor:** During the performance of this contract, the contractor shall not:
 - a. discriminate against labor from any other State, possession, or territory of the United States (except for employment preference for Appalachian contracts, when applicable, as specified in Attachment A), or
 - b. employ convict labor for any purpose within the limits of the project unless it is labor performed by convicts who are on parole, supervised release, or probation.

II. NONDISCRIMINATION

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$10,000 or more.)

1. **Equal Employment Opportunity:** Equal employment opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (28 CFR 35, 29 CFR 1630 and 41 CFR 60) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140 shall constitute the EEO and specific affirmative action standards for the contractor's project activities under this contract. The Equal Opportunity Construction Contract Specifications set forth under 41 CFR 60-4.3 and the provisions of the American Disabilities Act of 1990 (42 U.S.C. 12101 *et seq.*) set forth under 28 CFR 35 and 29 CFR 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:
 - a. The contractor will work with the State highway agency (SHA) and the Federal Government in carrying out EEO obligations and in their review of his/her activities under the contract.
 - b. The contractor will accept as his operating policy the following statement:

"It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, preapprenticeship, and/or on-the-job training."
2. **EEO Officer:** The contractor will designate and make known to the SHA contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active contractor program of EEO and who must be assigned adequate authority and responsibility to do so.
3. **Dissemination of Policy:** All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:
 - a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.
 - b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.
 - c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minority group employees.
 - d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.
 - e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.
4. **Recruitment:** When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minority groups in the area from which the project work force would normally be derived.
 - a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minority group applicants. To meet this requirement, the contractor will identify sources of potential minority group employees, and establish with such identified sources procedures whereby minority group applicants may be referred to the contractor for employment consideration.
 - b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, he is expected to observe the provisions of that agreement to the extent that the system permits the contractor's compliance with EEO contract provisions. (The DOL has held that where implementation of such agreements have the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Executive Order 11246, as amended.)

- c. The contractor will encourage his present employees to refer minority group applicants for employment. Information and procedures with regard to referring minority group applicants will be discussed with employees.
5. **Personnel Actions:** Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, national origin, age or disability. The following procedures shall be followed:
- a. The contractor will conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.
 - b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.
 - c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.
 - d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with his obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of his avenues of appeal.
6. **Training and Promotion:**
- a. The contractor will assist in locating, qualifying, and increasing the skills of minority group and women employees, and applicants for employment.
 - b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance. Where feasible, 25 percent of apprentices or trainees in each occupation shall be in their first year of apprenticeship or training. In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision.
 - c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.
 - d. The contractor will periodically review the training and promotion potential of minority group and women employees and will encourage eligible employees to apply for such training and promotion.
7. **Unions:** If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use his/her best efforts to obtain the cooperation of such unions to increase opportunities for minority groups and women within the unions, and to effect referrals by such unions of minority and female employees. Actions by the contractor either directly or through a contractor's association acting as agent will include the procedures set forth below:
- a. The contractor will use best efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minority group members and women for membership in the unions and increasing the skills of minority group employees and women so that they may qualify for higher paying employment.
 - b. The contractor will use best efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age or disability.
 - c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the SHA and shall set forth what efforts have been made to obtain such information.
 - d. In the event the union is unable to provide the contractor with a reasonable flow of minority and women referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age or disability; making full efforts to obtain qualified and/or qualifiable minority group persons and women. (The DOL has held that it shall be no excuse that the union with which the contractor has a

collective bargaining agreement providing for exclusive referral failed to refer minority employees.) In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these specifications, such contractor shall immediately notify the SHA.

8. **Selection of Subcontractors, Procurement of Materials and Leasing of Equipment:** The contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment.
 - a. The contractor shall notify all potential subcontractors and suppliers of his/her EEO obligations under this contract.
 - b. Disadvantaged business enterprises (DBE), as defined in 49 CFR 23, shall have equal opportunity to compete for and perform subcontracts which the contractor enters into pursuant to this contract. The contractor will use his best efforts to solicit bids from and to utilize DBE subcontractors or subcontractors with meaningful minority group and female representation among their employees. Contractors shall obtain lists of DBE construction firms from SHA personnel.
 - c. The contractor will use his best efforts to ensure subcontractor compliance with their EEO obligations.
9. **Records and Reports:** The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following completion of the contract work and shall be available at reasonable times and places for inspection by authorized representatives of the SHA and the FHWA.
 - a. The records kept by the contractor shall document the following:
 1. The number of minority and non-minority group members and women employed in each work classification on the project;
 2. The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women;
 3. The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minority and female employees; and
 4. The progress and efforts being made in securing the services of DBE subcontractors or subcontractors with meaningful minority and female representation among their employees.
 - b. The contractors will submit an annual report to the SHA each July for the duration of the project, indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on Form FHWA-1391. If on-the-job training is being required by special provision, the contractor will be required to collect and report training data.

III. NONSEGREGATED FACILITIES

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$10,000 or more.)

- a. By submission of this bid, the execution of this contract or subcontract, or the consummation of this material supply agreement or purchase order, as appropriate, the bidder, Federal-aid construction contractor, subcontractor, material supplier, or vendor, as appropriate, certifies that the firm does not maintain or provide for its employees any segregated facilities at any of its establishments, and that the firm does not permit its employees to perform their services at any location, under its control, where segregated facilities are maintained. The firm agrees that a breach of this certification is a violation of the EEO provisions of this contract. The firm further certifies that no employee will be denied access to adequate facilities on the basis of sex or disability.
- b. As used in this certification, the term "segregated facilities" means any waiting rooms, work areas, restrooms and washrooms, restaurants and other eating areas, timeclocks, locker rooms, and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are segregated by explicit directive, or are, in fact, segregated on the basis of race, color, religion, national origin, age or disability, because of habit, local custom, or otherwise. The only exception will be for the disabled when the demands for accessibility override (e.g. disabled parking).
- c. The contractor agrees that it has obtained or will obtain identical certification from proposed subcontractors or material suppliers prior to award of subcontracts or consummation of material supply agreements of \$10,000 or more and that it will retain such certifications in its files.

IV. PAYMENT OF PREDETERMINED MINIMUM WAGE

(Applicable to all Federal-aid construction contracts exceeding \$2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural minor collectors, which are exempt.)

1. General:

- a. All mechanics and laborers employed or working upon the site of the work will be paid unconditionally and not less often than once a week and without subsequent deduction or rebate on any account [except such payroll deductions as are permitted by regulations (29 CFR 3) issued by the Secretary of Labor under the Copeland Act (40 U.S.C. 276c)] the full amounts of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment. The payment shall be computed at wage rates not less than those contained in the wage determination of the Secretary of Labor (hereinafter "the wage determination") which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor or its subcontractors and such laborers and mechanics. The wage determination (including any additional classifications and wage rates conformed under paragraph 2 of this Section IV and the DOL poster (WH-1321) or Form FHWA-1495) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers. For the purpose of this Section, contributions made or costs reasonably anticipated for bona fide fringe benefits under Section 1(b) (2) of the Davis- Bacon Act (40 U.S.C. 276a) on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of Section IV, paragraph 3b, hereof. Also, for the purpose of this Section, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs, which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in paragraphs 4 and 5 of this Section IV.
- b. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein, provided, that the employer's payroll records accurately set forth the time spent in each classification in which work is performed.
- c. All rulings and interpretations of the Davis-Bacon Act and related acts contained in 29 CFR 1, 3, and 5 are herein incorporated by reference in this contract.

2. Classification:

- a. The SHA contracting officer shall require that any class of laborers or mechanics employed under the contract, which is not listed in the wage determination, shall be classified in conformance with the wage determination.
- b. The contracting officer shall approve an additional classification, wage rate and fringe benefits only when the following criteria have been met:
 1. the work to be performed by the additional classification requested is not performed by a classification in the wage determination;
 2. the additional classification is utilized in the area by the construction industry;
 3. the proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination; and
 4. with respect to helpers, when such a classification prevails in the area in which the work is performed.
- c. If the contractor or subcontractors, as appropriate, the laborers and mechanics (if known) to be employed in the additional classification or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the DOL, Administrator of the Wage and Hour Division, Employment Standards Administration, Washington, D.C. 20210. The Wage and Hour Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
- d. In the event the contractor or subcontractors, as appropriate, the laborers or mechanics to be employed in the additional classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Wage and Hour Administrator for determination. Said Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so

advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.

- e. The wage rate (including fringe benefits where appropriate) determined pursuant to paragraph 2c or 2d of this Section IV shall be paid to all workers performing work in the additional classification from the first day on which work is performed in the classification.

3. Payment of Fringe Benefits:

- a. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor or subcontractors, as appropriate, shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly case equivalent thereof.
- b. If the contractor or subcontractor, as appropriate, does not make payments to a trustee or other third person, he/she may consider as a part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, provided, that the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

4. Apprentices and Trainees (Programs of the U.S. DOL) and Helpers:

a. Apprentices:

- 1. Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the DOL, Employment and Training Administration, Bureau of Apprenticeship and Training, or with a State apprenticeship agency recognized by the Bureau, or if a person is employed in his/her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Bureau of Apprenticeship and Training or a State apprenticeship agency (where appropriate) to be eligible for probationary employment as an apprentice.
- 2. The allowable ratio of apprentices to journeyman-level employees on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any employee listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate listed in the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor or subcontractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman-level hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.
- 3. Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator for the Wage and Hour Division determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.
- 4. In the event the Bureau of Apprenticeship and Training, or a State apprenticeship agency recognized by the Bureau, withdraws approval of an apprenticeship program, the contractor or subcontractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the comparable work performed by regular employees until an acceptable program is approved.

b. Trainees:

- 1. Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the DOL, Employment and Training Administration.

2. The ratio of trainees to journeyman-level employees on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.
3. Every trainee must be paid at not less than the rate specified in the approved program for his/her level of progress, expressed as a percentage of the journeyman-level hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman-level wage rate on the wage determination which provides for less than full fringe benefits for apprentices, in which case such trainees shall receive the same fringe benefits as apprentices.
4. In the event the Employment and Training Administration withdraws approval of a training program, the contractor or subcontractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

c. **Helpers:**

Helpers will be permitted to work on a project if the helper classification is specified and defined on the applicable wage determination or is approved pursuant to the conformance procedure set forth in Section IV.2. Any worker listed on a payroll at a helper wage rate, who is not a helper under an approved definition, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed.

5. **Apprentices and Trainees (Programs of the U.S. DOT):**

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.

6. **Withholding:**

The SHA shall upon its own action or upon written request of an authorized representative of the DOL withhold, or cause to be withheld, from the contractor or subcontractor under this contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to Davis-Bacon prevailing wage requirements which is held by the same prime contractor, as much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the SHA contracting officer may, after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

7. **Overtime Requirements:**

No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers, mechanics, watchmen, or guards (including apprentices, trainees, and helpers described in paragraphs 4 and 5 above) shall require or permit any laborer, mechanic, watchman, or guard in any workweek in which he/she is employed on such work, to work in excess of 40 hours in such workweek unless such laborer, mechanic, watchman, or guard receives compensation at a rate not less than one-and-one-half times his/her basic rate of pay for all hours worked in excess of 40 hours in such workweek.

8. **Violation:**

Liability for Unpaid Wages; Liquidated Damages: In the event of any violation of the clause set forth in paragraph 7 above, the contractor and any subcontractor responsible thereof shall be liable to the affected employee for his/her unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory) for liquidated damages. Such

liquidated damages shall be computed with respect to each individual laborer, mechanic, watchman, or guard employed in violation of the clause set forth in paragraph 7, in the sum of \$10 for each calendar day on which such employee was required or permitted to work in excess of the standard work week of 40 hours without payment of the overtime wages required by the clause set forth in paragraph 7.

9. Withholding for Unpaid Wages and Liquidated Damages:

The SHA shall upon its own action or upon written request of any authorized representative of the DOL withhold, or cause to be withheld, from any monies payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to the contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph 8 above.

V. STATEMENTS AND PAYROLLS

(Applicable to all Federal-aid construction contracts exceeding \$2,000 and to all related subcontracts, except for projects located on roadways classified as local roads or rural collectors, which are exempt.)

1. Compliance with Copeland Regulations (29 CFR 3):

The contractor shall comply with the Copeland Regulations of the Secretary of Labor which are herein incorporated by reference.

2. Payrolls and Payroll Records:

- a. Payrolls and basic records relating thereto shall be maintained by the contractor and each subcontractor during the course of the work and preserved for a period of 3 years from the date of completion of the contract for all laborers, mechanics, apprentices, trainees, watchmen, helpers, and guards working at the site of the work.
- b. The payroll records shall contain the name, social security number, and address of each such employee; his or her correct classification; hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalent thereof of the types described in Section 1(b)(2)(B) of the Davis Bacon Act); daily and weekly number of hours worked; deductions made; and actual wages paid. In addition, for Appalachian contracts, the payroll records shall contain a notation indicating whether the employee does, or does not, normally reside in the labor area as defined in Attachment A, paragraph 1. Whenever the Secretary of Labor, pursuant to Section IV, paragraph 3b, has found that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in Section 1(b)(2)(B) of the Davis Bacon Act, the contractor and each subcontractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, that the plan or program has been communicated in writing to the laborers or mechanics affected, and show the cost anticipated or the actual cost incurred in providing benefits. Contractors or subcontractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprentices and trainees, and ratios and wage rates prescribed in the applicable programs.
- c. Each contractor and subcontractor shall furnish, each week in which any contract work is performed, to the SHA resident engineer a payroll of wages paid each of its employees (including apprentices, trainees, and helpers, described in Section IV, paragraphs 4 and 5, and watchmen and guards engaged on work during the preceding weekly payroll period). The payroll submitted shall set out accurately and completely all of the information required to be maintained under paragraph 2b of this Section V. This information may be submitted in any form desired. Optional Form WH-347 is available for this purpose and may be purchased from the Superintendent of Documents (Federal stock number 029- 005-0014-1), U.S. Government Printing Office, Washington, D.C. 20402. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors.
- d. Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor or his/her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:
 1. that the payroll for the payroll period contains the information required to be maintained under paragraph 2b of this Section V and that such information is correct and complete;
 2. that such laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in the Regulations, 29 CFR 3;

3. that each laborer or mechanic has been paid not less than the applicable wage rate and fringe benefits or cash equivalent for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.
- e. The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 2d of this Section V.
- f. The falsification of any of the above certifications may subject the contractor to civil or criminal prosecution under 18 U.S.C. 1001 and 31 U.S.C. 231.
- g. The contractor or subcontractor shall make the records required under paragraph 2b of this Section V available for inspection, copying, or transcription by authorized representatives of the SHA, the FHWA, or the DOL, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the SHA, the FHWA, the DOL, or all may, after written notice to the contractor, sponsor, applicant, or owner, take such actions as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

VI. RECORD OF MATERIALS, SUPPLIES, AND LABOR

(As of May 22, 2007, Form FHWA-47 is no longer required.)

VII. SUBLETTING OR ASSIGNING THE CONTRACT

1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the State. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635).
 - a. "Its own organization" shall be construed to include only workers employed and paid directly by the prime contractor and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor, assignee, or agent of the prime contractor.
 - b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid on the contract as a whole and in general are to be limited to minor components of the overall contract.
2. The contract amount upon which the requirements set forth in paragraph 1 of Section VII is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.
3. The contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the SHA contracting officer determines is necessary to assure the performance of the contract.
4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the SHA contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the SHA has assured that each subcontract is evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract.

VIII. SAFETY: ACCIDENT PREVENTION

1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the SHA contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.
2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her

health or safety, as determined under construction safety and health standards (29 CFR 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).

3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 333).

IX. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by Engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, the following notice shall be posted on each Federal-aid highway project (23 CFR 635) in one or more places where it is readily available to all persons concerned with the project:

NOTICE TO ALL PERSONNEL ENGAGED ON FEDERAL-AID HIGHWAY PROJECTS

18 U.S.C. 1020 reads as follows:

"Whoever, being an officer, agent, or employee of the United States, or of any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 1, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined not more than \$10,000 or imprisoned not more than 5 years or both."

X. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT

(Applicable to all Federal-aid construction contracts and to all related subcontracts of \$100,000 or more.)

By submission of this bid or the execution of this contract, or subcontract, as appropriate, the bidder, Federal-aid construction contractor, or subcontractor, as appropriate, will be deemed to have stipulated as follows:

1. That any facility that is or will be utilized in the performance of this contract, unless such contract is exempt under the Clean Air Act, as amended (42 U.S.C. 1857 *et seq.*, as amended by Pub.L. 91-604), and under the Federal Water Pollution Control Act, as amended (33 U.S.C. 1251 *et seq.*, as amended by Pub.L. 92-500), Executive Order 11738, and regulations in implementation thereof (40 CFR 15) is not listed, on the date of contract award, on the U.S. Environmental Protection Agency (EPA) List of Violating Facilities pursuant to 40 CFR 15.20.
2. That the firm agrees to comply and remain in compliance with all the requirements of Section 114 of the Clean Air Act and Section 308 of the Federal Water Pollution Control Act and all regulations and guidelines listed thereunder.
3. That the firm shall promptly notify the SHA of the receipt of any communication from the Director, Office of Federal Activities, EPA, indicating that a facility that is or will be utilized for the contract is under consideration to be listed on the EPA List of Violating Facilities.
4. That the firm agrees to include or cause to be included the requirements of paragraph 1 through 4 of this Section X in every nonexempt subcontract, and further agrees to take such action as the government may direct as a means of enforcing such requirements.

XI. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

1. **Instructions for Certification - Primary Covered Transactions:**

(Applicable to all Federal-aid contracts - 49 CFR 29)

- a. By signing and submitting this proposal, the prospective primary participant is providing the certification set out below.
- b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this covered transaction. The prospective participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective primary participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction.
- c. The certification in this clause is a material representation of fact upon which reliance was placed when the department or agency determined to enter into this transaction. If it is later determined that the prospective primary participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause of default.
- d. The prospective primary participant shall provide immediate written notice to the department or agency to whom this proposal is submitted if any time the prospective primary participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- e. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the department or agency to which this proposal is submitted for assistance in obtaining a copy of those regulations.
- f. The prospective primary participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction.
- g. The prospective primary participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," provided by the department or agency entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.
- h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the nonprocurement portion of the "Lists of Parties Excluded From Federal Procurement or Nonprocurement Programs" (Nonprocurement List) which is compiled by the General Services Administration.
- i. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- j. Except for transactions authorized under paragraph f of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

* * * * *

**Certification Regarding Debarment, Suspension, Ineligibility and
Voluntary Exclusion--Primary Covered Transactions**

1. The prospective primary participant certifies to the best of its knowledge and belief, that it and its principals:
 - a. Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
 - b. Have not within a 3-year period preceding this proposal been convicted of or had a civil judgement rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;

Contract No. 08-0F3504

- c. Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph 1b of this certification; and
 - d. Have not within a 3-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
2. Where the prospective primary participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

* * * * *

2. Instructions for Certification - Lower Tier Covered Transactions:

(Applicable to all subcontracts, purchase orders and other lower tier transactions of \$25,000 or more - 49 CFR 29)

- a. By signing and submitting this proposal, the prospective lower tier is providing the certification set out below.
- b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department, or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.
- c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances.
- d. The terms "covered transaction," "debarred," "suspended," "ineligible," "primary covered transaction," "participant," "person," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of rules implementing Executive Order 12549. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations.
- e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.
- f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.
- g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the Nonprocurement List.
- h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

* * * * *

Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Covered Transactions:

- 1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.

2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

* * * * *

XII. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

(Applicable to all Federal-aid construction contracts and to all related subcontracts which exceed \$100,000 - 49 CFR 20)

1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:
 - a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
 - b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.
2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.
3. The prospective participant also agrees by submitting his or her bid or proposal that he or she shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such recipients shall certify and disclose accordingly.

7-1.50C Female and Minority Goals

To comply with Section II, "Nondiscrimination," of "Required Contract Provisions Federal-Aid Construction Contracts," the Department is including in Section 7-1.50C, "Female and Minority Goals," female and minority utilization goals for Federal-aid construction contracts and subcontracts that exceed \$10,000.

The nationwide goal for female utilization is 6.9 percent.

The goals for minority utilization [45 Fed Reg 65984 (10/3/1980)] are as follows:

Minority Utilization Goals

Economic Area		Goal (Percent)
174	Redding CA: Non-SMSA Counties: CA Lassen; CA Modoc; CA Plumas; CA Shasta; CA Siskiyou; CA Tehama	6.8
175	Eureka, CA Non-SMSA Counties: CA Del Norte; CA Humboldt; CA Trinity	6.6
176	San Francisco-Oakland-San Jose, CA: SMSA Counties: 7120 Salinas-Seaside-Monterey, CA CA Monterey 7360 San Francisco-Oakland CA Alameda; CA Contra Costa; CA Marin; CA San Francisco; CA San Mateo 7400 San Jose, CA CA Santa Clara, CA 7485 Santa Cruz, CA CA Santa Cruz 7500 Santa Rosa CA Sonoma 8720 Vallejo-Fairfield-Napa, CA CA Napa; CA Solano Non-SMSA Counties: CA Lake; CA Mendocino; CA San Benito	28.9 25.6 19.6 14.9 9.1 17.1 23.2
177	Sacramento, CA: SMSA Counties: 6920 Sacramento, CA CA Placer; CA Sacramento; CA Yolo Non-SMSA Counties CA Butte; CA Colusa; CA El Dorado; CA Glenn; CA Nevada; CA Sierra; CA Sutter; CA Yuba	16.1 14.3
178	Stockton-Modesto, CA: SMSA Counties: 5170 Modesto, CA CA Stanislaus 8120 Stockton, CA CA San Joaquin Non-SMSA Counties CA Alpine; CA Amador; CA Calaveras; CA Mariposa; CA Merced; CA Toulumne	12.3 24.3 19.8
179	Fresno-Bakersfield, CA SMSA Counties: 0680 Bakersfield, CA CA Kern 2840 Fresno, CA CA Fresno Non-SMSA Counties: CA Kings; CA Madera; CA Tulare	19.1 26.1 23.6
180	Los Angeles, CA: SMSA Counties: 0360 Anaheim-Santa Ana-Garden Grove, CA CA Orange 4480 Los Angeles-Long Beach, CA CA Los Angeles 6000 Oxnard-Simi Valley-Ventura, CA CA Ventura 6780 Riverside-San Bernardino-Ontario, CA	11.9 28.3 21.5 19.0

	CA Riverside; CA San Bernardino 7480 Santa Barbara-Santa Maria-Lompoc, CA	19.7
	CA Santa Barbara Non-SMSA Counties CA Inyo; CA Mono; CA San Luis Obispo	24.6
181	San Diego, CA: SMSA Counties 7320 San Diego, CA	16.9
	CA San Diego Non-SMSA Counties CA Imperial	18.2

For each July during which work is performed under the contract, you and each non-material-supplier subcontractor with a subcontract of \$10,000 or more must complete Form FHWA PR-1391 (Appendix C to 23 CFR 230). Submit the forms by August 15.

7-1.50D Training

Section 7-1.50D, "Training," applies if a training goal is specified in the special provisions.

As part of your equal opportunity affirmative action program, provide on-the-job training to develop full journeymen in the types of trades or job classifications involved.

You have primary responsibility for meeting this training goal.

If you subcontract a contract part, determine how many trainees or apprentices are to be trained by the subcontractor.

Include these training requirements in your subcontract.

Where feasible, 25 percent of apprentices or trainees in each occupation must be in their 1st year of apprenticeship or training.

Distribute the number of apprentices or trainees among the work classifications on the basis of your needs and the availability of journeymen in the various classifications within a reasonable recruitment area.

Before starting work, submit to the Department:

1. Number of apprentices or trainees to be trained for each classification
2. Training program to be used
3. Training starting date for each classification

Obtain the Department's approval for this submitted information before you start work. The Department credits you for each apprentice or trainee you employ on the work who is currently enrolled or becomes enrolled in an approved program.

The primary objective of Section 7-1.50D, "Training," is to train and upgrade minorities and women toward journeyman status. Make every effort to enroll minority and women apprentices or trainees, such as conducting systematic and direct recruitment through public and private sources likely to yield minority and women apprentices or trainees, to the extent they are available within a reasonable recruitment area. Show that you have made the efforts. In making these efforts, do not discriminate against any applicant for training.

Do not employ as an apprentice or trainee an employee:

1. In any classification in which the employee has successfully completed a training course leading to journeyman status or in which the employee has been employed as a journeyman
2. Who is not registered in a program approved by the State's State Administrator of Apprenticeship

Ask the employee if the employee has successfully completed a training course leading to journeyman status or has been employed as a journeyman. Your records must show the employee's answers to the questions.

In your training program, establish the minimum length and training type for each classification. The Department and FHWA approves a program if one of the following is met:

1. It is calculated to:
 - 1.1. Meet the your equal employment opportunity responsibilities
 - 1.2. Qualify the average apprentice or trainee for journeyman status in the classification involved by the end of the training period

Add:

9-1.053 PERFORMANCE FAILURE WITHHOLDS

During each estimate period you fail to comply with a contract part, including submittal of a document as specified, the Department withholds a part of the progress payment. The documents include quality control plans, schedules, traffic control plans, and water pollution control submittals.

For 1 performance failure, the Department withholds 25 percent of the progress payment but does not withhold more than 10 percent of the total bid.

For multiple performance failures, the Department withholds 100 percent of the progress payment but does not withhold more than 10 percent of the total bid.

The Department returns performance-failure withholds in the progress payment following the correction of noncompliance.

Add:

9-1.055 PENALTY WITHHOLDS

Penalties include fines and damages that are proposed, assessed, or levied against you or the Department by a governmental agency or citizen lawsuit. Penalties are also payments made or costs incurred in settling alleged permit violations of Federal, State, or local laws, regulations, or requirements. The cost incurred may include the amount spent for mitigation or correcting a violation.

If you or the Department is assessed a penalty, the Department may withhold the penalty amount until the penalty disposition has been resolved. The Department may withhold penalty funds and notify you within 15 days of the withhold. If the penalty amount is less than the amount being withheld from progress payments for retentions, the Department will not withhold the penalty amount.

If the penalty is resolved for less than the amount withheld, the Department pays interest at a rate of 6 percent per year on the excess withhold. If the penalty is not resolved, the withhold becomes a deduction.

Instead of the withhold, you may provide a bond payable to the Department of Transportation equal to the highest estimated liability for any disputed penalties proposed.

Add:

9-1.057 PROGRESS WITHHOLDS FOR FEDERAL-AID CONTRACTS

Section 9-1.057, "Progress Withholds for Federal-Aid Contracts," applies to a Federal-aid contract.

The Department withholds 10 percent of a partial payment for noncompliant progress. Noncompliant progress occurs when:

1. Total days to date exceed 75 percent of the revised contract working days
2. Percent of working days elapsed exceeds the percent of value of work completed by more than 15 percent

The Engineer determines the percent of working days elapsed by dividing the total days to date by the revised contract working days and converting the quotient to a percentage.

The Engineer determines the percent of value of work completed by summing payments made to date and the amount due on the current progress estimate, dividing this sum by the current total estimated value of the work, and converting the quotient to a percentage. These amounts are shown on the Progress Payment Voucher.

When the percent of working days elapsed minus the percent of value of work completed is less than or equal to 15 percent, the Department returns the withhold in the next progress payment.

In Section 9-1.06 replace the 3rd paragraph with:

For a non-Federal-aid project, the Department retains 10 percent of the estimated value of the work done and 10 percent of the value of materials estimated to have been furnished and delivered and unused or furnished and stored as part security for the fulfillment of the contract by the Contractor, except that at any time after 20 percent of the work has been completed, if the Engineer finds that satisfactory progress is being made, the Department may reduce the total amount being retained from payment pursuant to the above requirements to 5 percent of the total estimated value of the work and materials and may also reduce the amount retained from any of the remaining partial payments to 5 percent of the estimated value of the work and materials. In addition, on any partial payment made after 95 percent of the work has been completed, the Department may reduce the amount retained from payment pursuant to the requirements of this Section 9-1.06, to such lesser amount as the Department determines is adequate security for the fulfillment of the balance of the work and other requirements of the

1. Asphalt binder
2. Asphalt modifier
3. Crumb rubber modifier (CRM)

The combined asphalt binder and asphalt modifier must be 80.0 ± 2.0 percent by weight of the asphalt rubber binder.

Asphalt Modifier

Asphalt modifier must be a resinous, high flash point, and aromatic hydrocarbon, and comply with:

Asphalt Modifier for Asphalt Rubber Binder

Quality Characteristic	ASTM	Specification
Viscosity, m^2/s ($\times 10^{-6}$) at 100 °C	D 445	$X \pm 3^a$
Flash Point, CL.O.C., °C	D 92	207 minimum
Molecular Analysis		
Asphaltenes, percent by mass	D 2007	0.1 maximum
Aromatics, percent by mass	D 2007	55 minimum

Note:

^a The symbol "X" is the proposed asphalt modifier viscosity. "X" must be between 19 and 36. A change in "X" requires a new asphalt rubber binder design.

Asphalt modifier must be from 2.0 percent to 6.0 percent by weight of the asphalt binder in the asphalt rubber binder.

Crumb Rubber Modifier

CRM consists of a ground or granulated combination of scrap tire CRM and high natural CRM. CRM must be 75.0 ± 2.0 percent scrap tire CRM and 25.0 ± 2.0 percent high natural CRM by total weight of CRM. Scrap tire CRM must be from any combination of automobile tires, truck tires, or tire buffings.

Sample and test scrap tire CRM and high natural CRM separately. CRM must comply with:

Crumb Rubber Modifier for Asphalt Rubber Binder

Quality Characteristic	Test Method	Specification
Scrap tire CRM gradation (% passing No. 8 sieve)	LP-10	100
High natural CRM gradation (% passing No. 10 sieve)	LP-10	100
Wire in CRM (% max.)	LP-10	0.01
Fabric in CRM (% max.)	LP-10	0.05
CRM particle length (inch max.) ^a	--	3/16
CRM specific gravity ^a	CT 208	1.1 – 1.2
Natural rubber content in high natural CRM (%) ^a	ASTM D 297	40.0 – 48.0

Note:

^a Test at mix design and for Certificate of Compliance.

Only use CRM ground and granulated at ambient temperature. If steel and fiber are cryogenically separated, it must occur before grinding and granulating. Only use cryogenically produced CRM particles that can be ground or granulated and not pass through the grinder or granulator.

CRM must be dry, free-flowing particles that do not stick together. CRM must not cause foaming when combined with the asphalt binder and asphalt modifier. You may add calcium carbonate or talc up to 3 percent by weight of CRM.

Asphalt Rubber Binder Design and Profile

Submit in writing an asphalt rubber binder design and profile. In the design, designate the asphalt, asphalt modifier, and CRM and their proportions. The profile is not a specification and only serves to indicate expected trends in asphalt rubber binder properties during binder production. The profile must include the same component sources for the asphalt rubber binder used.

Design the asphalt rubber binder from testing you perform for each quality characteristic and for the reaction temperatures expected during production. The 24-hour (1,440-minute) interaction period determines the design profile. At a minimum, mix asphalt rubber binder components, take samples, and perform and record the following tests:

Asphalt Rubber Binder Reaction Design Profile

Test	Minutes of Reaction ^a							Limits
	45	60	90	120	240	360	1440	
Cone penetration @ 77 °F, 0.10-mm (ASTM D 217)	X ^b				X		X	25 - 70
Resilience @ 77 °F, percent rebound (ASTM D 5329)	X				X		X	18 min.
Field softening point, °F (ASTM D 36)	X				X		X	125 - 165
Viscosity, centipoises (LP-11)	X	X	X	X	X	X	X	1,500 - 4,000

Notes:

^a Six hours (360 minutes) after CRM addition, reduce the oven temperature to 275 °F for a period of 16 hours. After the 16-hour (1320 minutes) cool-down after CRM addition, reheat the binder to the reaction temperature expected during production for sampling and testing at 24 hours (1440 minutes).

^b "X" denotes required testing

Asphalt Rubber Binder

After interacting for a minimum of 45 minutes, asphalt rubber binder must comply with:

Asphalt Rubber Binder

Quality Characteristic	Test for Quality Control or Acceptance	Test Method	Specification	
			Minimum	Maximum
Cone penetration @ 77 °F, 0.10-mm	Acceptance	ASTM D 217	25	70
Resilience @ 77 °F, percent rebound	Acceptance	ASTM D 5329	18	--
Field softening point, °F	Acceptance	ASTM D 36	125	165
Viscosity @ 350 °F, centipoises	Quality Control	LP-11	1,500	4,000

39-1.02E Aggregate

Aggregate must be clean and free from deleterious substances. Aggregate:

1. Retained on the No. 4 sieve is coarse
2. Passing the No. 4 sieve is fine
3. Added and passing the No. 30 sieve is supplemental fine, including:
 - 3.1. Hydrated lime
 - 3.2. Portland cement
 - 3.3. Fines from dust collectors

The special provisions specify the aggregate gradation for each HMA type.

The specified aggregate gradation is before the addition of asphalt binder and includes supplemental fines. The Engineer tests for aggregate grading under California Test 202, modified by California Test 105 if there is a difference in specific gravity of 0.2 or more between the coarse and fine parts of different aggregate blends.

Choose a sieve size target value (TV) within each target value limit presented in the aggregate gradation tables.

**Aggregate Gradation
(Percentage Passing)
HMA Types A and B**

3/4-inch HMA Types A and B

Sieve Sizes	Target Value Limits	Allowable Tolerance
1"	100	—
3/4"	90 - 100	TV ±5
1/2"	70 - 90	TV ±6
No. 4	45 - 55	TV ±7
No. 8	32 - 40	TV ±5
No. 30	12 - 21	TV ±4
No. 200	2 - 7	TV ±2

1/2-inch HMA Types A and B

Sieve Sizes	Target Value Limits	Allowable Tolerance
3/4"	100	—
1/2"	95 - 99	TV ±6
3/8"	75 - 95	TV ±6
No. 4	55 - 66	TV ±7
No. 8	38 - 49	TV ±5
No. 30	15 - 27	TV ±4
No. 200	2 - 8	TV ±2

3/8-inch HMA Types A and B

Sieve Sizes	Target Value Limits	Allowable Tolerance
1/2"	100	—
3/8"	95 - 100	TV ±6
No. 4	58 - 72	TV ±7
No. 8	34 - 48	TV ±6
No. 30	18 - 32	TV ±5
No. 200	2 - 9	TV ±2

No. 4 HMA Types A and B

Sieve Sizes	Target Value Limits	Allowable Tolerance
3/8"	100	—
No. 4	95 - 100	TV ±7
No. 8	72 - 77	TV ±7
No. 30	37 - 43	TV ±7
No. 200	2 - 12	TV ±4

Rubberized Hot Mix Asphalt - Gap Graded (RHMA-G)

3/4-inch RHMA-G

Sieve Sizes	Target Value Limits	Allowable Tolerance
1"	100	—
3/4"	95 - 100	TV ±5
1/2"	83 - 87	TV ±6
3/8"	65 - 70	TV ±6
No. 4	28 - 42	TV ±7
No. 8	14 - 22	TV ±5
No. 200	0 - 6	TV ±2

1/2-inch RHMA-G

Sieve Sizes	Target Value Limits	Allowable Tolerance
3/4"	100	—
1/2"	90 - 100	TV ±6
3/8"	83 - 87	TV ±6
No. 4	28 - 42	TV ±7
No. 8	14 - 22	TV ±5
No. 200	0 - 6	TV ±2

Open Graded Friction Course (OGFC)

1-inch OGFC

Sieve Sizes	Target Value Limits	Allowable Tolerance
1 1/2"	100	—
1"	99 - 100	TV ±5
3/4"	85 - 96	TV ±5
1/2"	55 - 71	TV ±6
No. 4	10 - 25	TV ±7
No. 8	6 - 16	TV ±5
No. 200	1 - 6	TV ±2

1/2-inch OGFC

Sieve Sizes	Target Value Limits	Allowable Tolerance
3/4"	100	—
1/2"	95 - 100	TV ±6
3/8"	78 - 89	TV ±6
No. 4	28 - 37	TV ±7
No. 8	7 - 18	TV ±5
No. 30	0 - 10	TV ±4
No. 200	0 - 3	TV ±2

3/8-inch OGFC

Sieve Sizes	Target Value Limits	Allowable Tolerance
1/2"	100	—
3/8"	90 - 100	TV ±6
No. 4	29 - 36	TV ±7
No. 8	7 - 18	TV ±6
No. 30	0 - 10	TV ±5
No. 200	0 - 3	TV ±2

Before the addition of asphalt binder and lime treatment, aggregate must comply with:

Aggregate Quality

Quality Characteristic	Test Method	HMA Type			
		A	B	RHMA-G	OGFC
Percent of crushed particles	CT 205				
Coarse aggregate (% min.)					
One fractured face		90	25	--	90
Two fractured faces		75	--	90	75
Fine aggregate (% min.)					
(Passing No. 4 sieve and retained on No. 8 sieve.)					
One fractured face		70	20	70	90
Los Angeles Rattler (% max.)	CT 211				
Loss at 100 Rev.		12	--	12	12
Loss at 500 Rev.		45	50	40	40
Sand equivalent (min.) ^a	CT 217	47	42	47	--
Fine aggregate angularity (% min.) ^b	AASHTO T 304 Method A	45	45	45	--
Flat and elongated particles (% max. by weight @ 5:1)	ASTM D 4791	10	10	10	10
K _c factor (max.)	CT 303	1.7	1.7	1.7	--
K _f factor (max.)	CT 303	1.7	1.7	1.7	--

Notes:

^a Reported value must be the average of 3 tests from a single sample.

^b The Engineer waives this specification if HMA contains less than 10 percent of nonmanufactured sand by weight of total aggregate.

39-1.02F Reclaimed Asphalt Pavement

You may produce HMA using reclaimed asphalt pavement (RAP). HMA produced using RAP must comply with the specifications for HMA except aggregate quality specifications do not apply to RAP. You may substitute RAP aggregate for a part of the virgin aggregate in HMA in a quantity not exceeding 15 percent of the aggregate blend. Do not use RAP in OGFC and RHMA-G.

Assign the substitution rate of RAP aggregate for virgin aggregate with the job mix formula (JMF) submittal. The JMF must include the percent of RAP used. If you change your assigned RAP aggregate substitution rate by more than 5 percent (within the 15 percent limit), submit a new JMF.

Process RAP from asphalt concrete. You may process and stockpile RAP throughout the project's life. Prevent material contamination and segregation. Store RAP in stockpiles on smooth surfaces free of debris and organic material. Processed RAP stockpiles must consist only of homogeneous RAP.

39-1.03 HOT MIX ASPHALT MIX DESIGN REQUIREMENTS

39-1.03A General

A mix design consists of performing California Test 367 and laboratory procedures on combinations of aggregate gradations and asphalt binder contents to determine the optimum binder content (OBC) and HMA mixture qualities. If RAP is used, use Laboratory Procedure LP-9. The result of the mix design becomes the proposed JMF.

Use Form CEM-3512 to document aggregate quality and mix design data. Use Form CEM-3511 to present the JMF.

Laboratories testing aggregate qualities and preparing the mix design and JMF must be qualified under the Department's Independent Assurance Program. Take samples under California Test 125.

The Engineer reviews the aggregate qualities, mix design, and JMF and verifies and accepts the JMF.

You may change the JMF during production. Do not use the changed JMF until the Engineer accepts it. Except when adjusting the JMF in compliance with Section 39-1.03E, "Job Mix Formula Verification," perform a new mix design and submit in writing a new JMF submittal for changing any of the following:

1. Target asphalt binder percentage
2. Asphalt binder supplier
3. Asphalt rubber binder supplier
4. Component materials used in asphalt rubber binder or percentage of any component materials
5. Combined aggregate gradation
6. Aggregate sources

7. Substitution rate for RAP aggregate of more than 5 percent
8. Any material in the JMF

For OGFC, submit in writing a complete JMF submittal except asphalt binder content. The Engineer determines the asphalt binder content under California Test 368 within 20 days of your complete JMF submittal and provides you a Form CEM-3513.

39-1.03B Hot Mix Asphalt For Job Mix Formula

Determine the proposed JMF from a mix design that complies with:

Hot Mix Asphalt for Job Mix Formula

Quality Characteristic	Test Method	HMA Type		
		A	B	RHMA-G
Air voids content (%)	CT 367 ^a	4.0	4.0	Special Provisions
Voids in mineral aggregate (% min.)	LP-2			
No. 4 grading		17.0	17.0	--
3/8" grading		15.0	15.0	--
1/2" grading		14.0	14.0	18.0 – 23.0 ^b
3/4" grading	13.0	13.0	18.0 – 23.0 ^b	
Voids filled with asphalt (%)	LP-3			
No. 4 grading		76.0 – 80.0	76.0 – 80.0	Note d
3/8" grading		73.0 – 76.0	73.0 – 76.0	
1/2" grading		65.0 – 75.0	65.0 – 75.0	
3/4" grading	65.0 – 75.0	65.0 – 75.0		
Dust proportion	LP-4			
No. 4 and 3/8" gradings		0.9 – 2.0	0.9 – 2.0	Note d
1/2" and 3/4" gradings		0.6 – 1.3	0.6 – 1.3	
Stabilometer value (min.) ^c	CT 366			
No. 4 and 3/8" gradings		30	30	--
1/2" and 3/4" gradings		37	35	23

Notes:

^a Calculate the air voids content of each specimen using California Test 309 and Lab Procedure LP-1. Modify California Test 367, Paragraph C5, to use the exact air voids content specified in the selection of OBC.

^b Voids in mineral aggregate for RHMA-G must be within this range.

^c Modify California Test 304, Part 2.B.2.c: "After compaction in the compactor, cool to 140 °± 5 °F by allowing the briquettes to cool at room temperature for 0.5-hour, then place the briquettes in the oven at 140 °F for a minimum of 2 hours and not more than 3 hours."

^d Report this value in the JMF submittal.

For stability, prepare 3 briquettes separately at the proposed JMF and test for compliance. Report the average of 3 tests. Prepare new briquettes and test if the range of stability for the 3 briquettes is more than 12 points. The average air void content may vary from the specified air void content by ±0.5 percent.

You may use the briquettes used for stability testing to determine bulk specific gravity under CT 308. If you use the same briquettes and tests using bulk specific gravity fail, you may prepare 3 new briquettes and determine a new bulk specific gravity. If you choose to determine bulk specific gravity with new briquettes and your tests fail, you may not test again using the stability briquettes.

39-1.03C Job Mix Formula Submittal

Each JMF submittal must consist of:

1. Proposed JMF on Form CEM-3511
2. Mix design documentation on Form CEM-3512 dated within 12 months of submittal
3. JMF verification on Form CEM-3513 dated within 12 months of production start, if applicable
4. Materials Safety Data Sheets (MSDS) for:
 - 4.1. Asphalt binder
 - 4.2. Base asphalt binder used in asphalt rubber binder

- 4.3. CRM and asphalt modifier used in asphalt rubber binder
- 4.4. Blended asphalt rubber binder mixture
- 4.5. Supplemental fine aggregate except fines from dust collectors
- 4.6. Antistrip additives

If the JMF must be verified or if the Engineer requests, submit samples of the following materials in labeled containers weighing no more than 50 pounds each (notify the Engineer at least 2 business days before sampling materials):

1. Coarse, fine, and supplemental fine aggregate from stockpiles, cold feed belts, or hot bins. Samples must include at least 120 pounds for each coarse aggregate, 80 pounds for each fine aggregate, and 10 pounds for each type of supplemental fines. The Department combines these aggregate samples to comply with the JMF target values submitted on Form CEM-3511.
2. RAP from stockpiles or RAP system. Samples must be at least 60 pounds.
3. Asphalt binder from the binder supplier. Samples must be in two 1-quart cylindrical shaped cans with open top and friction lids.
4. Asphalt rubber binder with the components blended in the proportions to be used. Samples must be in four 1-quart cylindrical shaped cans with open top and friction lids.

39-1.03D Job Mix Formula Review

The Engineer reviews each mix design and proposed JMF within 5 business days from the complete JMF submittal. The review consists of reviewing the mix design procedures and comparing the proposed JMF with the specifications.

The Engineer may verify aggregate qualities during this review period.

39-1.03E Job Mix Formula Verification

If you cannot submit a Department-verified JMF on Form CEM-3513 dated within 12 months before HMA production, the Engineer verifies the JMF.

Based on your testing and production experience, you may submit on Form CEM-3511 an adjusted JMF before the Engineer's verification testing. JMF adjustments may include a change in the:

1. Asphalt binder content target value up to ± 0.6 percent from the optimum binder content value submitted on Form CEM-3512 except do not adjust the target value for asphalt rubber binder for RHMA-G below 7.0 percent
2. Aggregate gradation target values within the target value limits specified in the aggregate gradation tables

Test samples from the HMA plant to be used to determine possible JMF adjustments.

For HMA Type A, Type B, and RHMA-G, the Engineer verifies the JMF from samples taken from HMA produced by the plant to be used. The Engineer verifies each proposed JMF within 20 days of receiving a complete JMF submittal and verification samples. Verification is testing for compliance with the specifications for:

1. Aggregate quality
2. Aggregate gradation (JMF TV \pm tolerance)
3. Asphalt binder content (JMF TV \pm tolerance)
4. HMA quality specified in the table Hot Mix Asphalt for Job Mix Formula except:
 - 4.1. Air voids content (design value ± 2.0 percent)
 - 4.2. Voids filled with asphalt (report only if an adjustment for asphalt binder content target value is less than ± 0.3 percent from optimum binder content)
 - 4.3. Dust proportion (report only if an adjustment for asphalt binder content target value is less than ± 0.3 percent from optimum binder content)

If you request in writing, the Engineer verifies RHMA-G quality requirements within 3 business days of sampling. In the Engineer's presence, under California Test 125, and from the same production run, take samples of:

1. Aggregate
2. Asphalt binder
3. RAP
4. HMA

Sample aggregate from cold feed belts or hot bins. Sample RAP from the RAP system. Sample HMA from any of the following locations:

1. The plant
2. A truck
3. A windrow
4. Behind a paver

You may sample from a different project including a non-Department project if you make arrangements for the Engineer to be present during sampling.

For aggregate, RAP, and HMA, split the samples into at least 4 parts and label their containers. Submit 3 split parts to the Engineer and use 1 part for your testing.

The Engineer prepares 3 briquettes from a single split sample. To verify the JMF for stability, the Engineer tests the 3 briquettes and reports the average of 3 tests. The Engineer prepares new briquettes if the range of stability for the 3 briquettes is more than 12 points.

The Engineer may use the briquettes used for stability testing to determine bulk specific gravity under CT 308. If the Engineer uses the same briquettes and the tests using bulk specific gravity fail, the Engineer may prepare 3 new briquettes and determine a new bulk specific gravity. If the Engineer chooses to determine bulk specific gravity with new briquettes and the Engineer's tests fail, the Engineer may not test again using the stability briquettes.

If the Engineer verifies the JMF, the Engineer provides you a Form CEM-3513.

If the Engineer's tests on plant-produced samples do not verify the JMF, the Engineer notifies you in writing and you must submit a new JMF submittal or submit an adjusted JMF based on your testing. JMF adjustments may include a change in the:

1. Asphalt binder content target value up to ± 0.6 percent from the optimum binder content value submitted on Form CEM-3512 except do not adjust the target value for asphalt rubber binder for RHMA-G below 7.0 percent
2. Aggregate gradation target values within the target value limits specified in the aggregate gradation tables

You may adjust the JMF only once due to a failed verification test. An adjusted JMF requires a new Form CEM-3511 and verification of a plant-produced sample.

The Engineer reverifies the JMF if HMA production has stopped for longer than 30 days and the verified JMF is older than 12 months.

For each HMA type and aggregate size specified, the Engineer verifies at the State's expense up to 2 proposed JMF including a JMF adjusted after verification failure. The Engineer deducts \$3,000 from payments for each verification exceeding this limit. This deduction does not apply to verifications initiated by the Engineer or if a JMF expires while HMA production is stopped longer than 30 days.

39-1.03F Job Mix Formula Acceptance

You may start HMA production if:

1. The Engineer's review of the JMF shows compliance with the specifications.
2. The Department has verified the JMF within 12 months before HMA production.
3. The Engineer accepts the verified JMF.

39-1.04 CONTRACTOR QUALITY CONTROL

39-1.04A General

Establish, maintain, and change a quality control system to ensure materials and work comply with the specifications. Submit quality control test results to the Engineer within 3 days of a request except when QC / QA is specified.

39-1.04B Prepaving Conference

Meet with the Engineer at a prepaving conference at a mutually agreed time and place. Discuss methods of performing the production and paving work.

39-1.04C Asphalt Rubber Binder

Take asphalt rubber binder samples from the feed line connecting the asphalt rubber binder tank to the HMA plant. Sample and test asphalt rubber binder under Laboratory Procedure LP-11.

Test asphalt rubber binder for compliance with the viscosity specifications in Section 39-1.02, "Materials." During asphalt rubber binder production and HMA production using asphalt rubber binder, measure viscosity every hour with not

less than 1 reading for each asphalt rubber binder batch. Log measurements with corresponding time and asphalt rubber binder temperature. Submit the log daily in writing.

Submit a Certificate of Compliance under Section 6-1.07, "Certificates of Compliance." With the Certificate of Compliance, submit test results in writing for CRM and asphalt modifier with each truckload delivered to the HMA plant. A Certificate of Compliance for asphalt modifier must not represent more than 5,000 pounds. Use an AASHTO-certified laboratory for testing.

Sample and test gradation and wire and fabric content of CRM once per 10,000 pounds of scrap tire CRM and once per 3,400 pounds of high natural CRM. Sample and test scrap tire CRM and high natural CRM separately.

Submit certified weight slips in writing for the CRM and asphalt modifier furnished.

39-1.04D Aggregate

Determine the aggregate moisture content and RAP moisture content in continuous mixing plants at least twice a day during production and adjust the plant controller. Determine the RAP moisture content in batch mixing plants at least twice a day during production and adjust the plant controller.

39-1.04E Reclaimed Asphalt Pavement

Perform RAP quality control testing each day.

Sample RAP once daily and determine the RAP aggregate gradation under Laboratory Procedure LP-9 and submit the results to the Engineer in writing with the combined aggregate gradation.

39-1.04F Cores

For Standard and QC / QA projects, take 4-inch or 6-inch diameter cores at least once every 5 business days. Take 1 core for every 250 tons of HMA from random locations the Engineer designates. Take cores in the Engineer's presence and backfill and compact holes with material authorized by the Engineer. Before submitting a core to the Engineer, mark it with the core's location and place it in a protective container.

If a core is damaged, replace it with a core taken within 1 foot longitudinally from the original core. Relocate any core located within 1 foot of a rumble strip to 1 foot transversely away from the rumble strip.

39-1.04G Briquettes

Prepare 3 briquettes separately for each stability determination. Report the average of 3 tests. Prepare new briquettes and test if the range of stability for the 3 briquettes is more than 12 points.

You may use the briquettes used for stability testing to determine bulk specific gravity under CT 308. If you use the same briquettes and tests using bulk specific gravity fail, you may prepare 3 new briquettes and determine a new bulk specific gravity. If you choose to determine bulk specific gravity with new briquettes and your tests fail, you may not test again using the stability briquettes.

39-1.05 ENGINEER'S ACCEPTANCE

The Engineer's acceptance of HMA is specified in the sections for each HMA construction process.

The Engineer samples materials for testing under California Test 125 and the applicable test method. Sampling must be statistically-based and random.

The Engineer takes HMA and aggregate samples during production and splits each sample into 2 parts. The Engineer tests 1 part to verify quality control test results and reserves and stores the remaining part. If you request, the Engineer splits samples and provides you with a part.

The Engineer accepts HMA based on:

1. Accepted JMF
2. Accepted QCP for Standard and QC / QA
3. Compliance with the HMA Acceptance tables
4. Acceptance of a lot for QC / QA
5. Visual inspection

The Engineer prepares 3 briquettes separately for each stability determination. The Engineer reports the average of 3 tests. The Engineer prepares new briquettes and test if the range of stability for the 3 briquettes is more than 12 points.

The Engineer may use the briquettes used for stability testing to determine bulk specific gravity under CT 308. If the Engineer uses the same briquettes and the tests using bulk specific gravity fail, the Engineer may prepare 3 new briquettes and determine a new bulk specific gravity. If the Engineer chooses to determine bulk specific gravity with new briquettes and the Engineer tests fail, the Engineer may not test again using the stability briquettes.

39-1.06 DISPUTE RESOLUTION

You and the Engineer must work together to avoid potential conflicts and to resolve disputes regarding test result discrepancies. Notify the Engineer in writing within 5 days of receiving a test result if you dispute the test result.

If you or the Engineer dispute each other's test results, submit written quality control test results and copies of paperwork including worksheets used to determine the disputed test results to the Engineer. An Independent Third Party (ITP) performs referee testing. Before the ITP participates in a dispute resolution, the ITP must be accredited under the Department's Independent Assurance Program. The ITP must be independent of the project. By mutual agreement, the ITP is chosen from:

1. A Department laboratory
2. A Department laboratory in a district or region not in the district or region the project is located
3. The Transportation Laboratory
4. A laboratory not currently employed by you or your HMA producer

If split quality control or acceptance samples are not available, the ITP uses any available material representing the disputed HMA for evaluation.

39-1.07 PRODUCTION START-UP EVALUATION

The Engineer evaluates HMA production and placement at production start-up.

Within the first 750 tons produced on the first day of HMA production, in the Engineer's presence and from the same production run, take samples of:

1. Aggregate
2. Asphalt binder
3. RAP
4. HMA

Sample aggregate from cold feed belts or hot bins. Take RAP samples from the RAP system. Sample HMA under California Test 125. For aggregate, RAP, and HMA, split the samples into at least 4 parts and label their containers. Submit 3 split parts to the Engineer and keep 1 part.

For Standard and QC / QA projects, you and the Engineer must test the split samples for compliance with specifications. You and the Engineer must report test results in writing within 3 business days of sampling.

For Standard and QC / QA projects, take 4-inch or 6-inch diameter cores within the first 750 tons on the first day of HMA production. For each core, the Engineer reports the bulk specific gravity determined under California Test 308, Method A in addition to the percent of maximum theoretical density. You may test for in-place density at the core locations and include them in your production tests for percent of maximum theoretical density.

39-1.08 PRODUCTION

39-1.08A General

Produce HMA in a batch mixing plant or a continuous mixing plant. Proportion aggregate by hot or cold feed control.

HMA plants must be Department-qualified. Before production, the HMA plant must have a current qualification under the Department's Materials Plant Quality Program.

During production, you may adjust:

1. Hot or cold feed proportion controls for virgin aggregate and RAP
2. The set point for asphalt binder content

39-1.08B Mixing

Mix HMA ingredients into a homogeneous mixture of coated aggregates.

Asphalt binder must be between 275 °F and 375 °F when mixed with aggregate.

Asphalt rubber binder must be between 350 °F and 425 °F when mixed with aggregate.

Aggregate must not be more than 325 °F when mixed with asphalt binder. Aggregate temperature specifications do not apply when you use RAP.

HMA with or without RAP must not be more than 325 °F.

39-1.08C Asphalt Rubber Binder

Deliver scrap tire CRM and high natural CRM in separate bags.

Either proportion and mix asphalt binder, asphalt modifier, and CRM simultaneously or premix the asphalt binder and asphalt modifier before adding CRM. If you premix asphalt binder and asphalt modifier, the asphalt binder must be between 350 °F and 425 °F when you add asphalt modifier. Mix them for at least 20 minutes. When you add CRM, the asphalt binder and asphalt modifier must be between 350 °F and 425 °F.

Do not use asphalt rubber binder during the first 45 minutes of the reaction period. During this period, the asphalt rubber binder mixture must be between 350 °F and the lower of 425 °F or 10 °F below the asphalt binder's flash point indicated in the MSDS.

If any asphalt rubber binder is not used within 4 hours after the reaction period, discontinue heating. If the asphalt rubber binder drops below 350 °F, reheat before use. If you add more scrap tire CRM to the reheated asphalt rubber binder, the binder must undergo a 45-minute reaction period. The added scrap tire CRM must not exceed 10 percent of the total asphalt rubber binder weight. Reheated and reacted asphalt rubber binder must comply with the viscosity specifications for asphalt rubber binder in Section 39-1.02, "Materials." Do not reheat asphalt rubber binder more than twice.

39-1.09 SUBGRADE, TACK COAT, AND GEOSYNTHETIC PAVEMENT INTERLAYER

39-1.09A General

Prepare subgrade or apply tack coat to surfaces receiving HMA. If specified, place geosynthetic pavement interlayer over a coat of asphalt binder.

39-1.09B Subgrade

Subgrade to receive HMA must comply with the compaction and elevation tolerance specifications in the sections for the material involved. Subgrade must be free of loose and extraneous material. If HMA is paved on existing base or pavement, remove loose paving particles, dirt, and other extraneous material by any means including flushing and sweeping.

39-1.09C Tack Coat

Apply tack coat:

1. To existing pavement including planed surfaces
2. Between HMA layers
3. To vertical surfaces of:
 - 3.1. Curbs
 - 3.2. Gutters
 - 3.3. Construction joints

Before placing HMA, apply tack coat in 1 application at the minimum residual rate specified for the condition of the underlying surface:

Tack Coat Application Rates for HMA Type A, Type B, and RHMA-G

HMA Overlay over:	Minimum Residual Rates (gallons per square yard)		
	CSS1/CSS1h, SS1/SS1h and QS1h/CQS1h Asphaltic Emulsion	CRS1/CRS2, RS1/RS2 and QS1/CQS1 Asphaltic Emulsion	Asphalt Binder and PMRS2/PMCRS2 and PMRS2h/PMCRS2h Asphaltic Emulsion
New HMA (between layers)	0.02	0.03	0.02
Existing AC and PCC pavement	0.03	0.04	0.03
Planed pavement	0.05	0.06	0.04

Tack Coat Application Rates for OGFC

OGFC over:	Minimum Residual Rates (gallons per square yard)		
	CSS1/CSS1h, SS1/SS1h and QS1h/CQS1h Asphaltic Emulsion	CRS1/CRS2, RS1/RS2 and QS1/CQS1 Asphaltic Emulsion	Asphalt Binder and PMRS2/PMCRS2 and PMRS2h/PMCRS2h Asphaltic Emulsion
New HMA	0.03	0.04	0.03
Existing AC and PCC pavement	0.05	0.06	0.04
Planed pavement	0.06	0.07	0.05

Apply to vertical surfaces with a residual tack coat rate that will thoroughly coat the vertical face without running off.

If you request in writing and the Engineer authorizes, you may change tack coat rates.

Immediately in advance of placing HMA, apply additional tack coat to damaged areas or where loose or extraneous material is removed.

Close areas receiving tack coat to traffic. Do not track tack coat onto pavement surfaces beyond the job site.

Asphalt binder tack coat must be between 285 °F and 350 °F when applied.

39-1.09D Geosynthetic Pavement Interlayer

Before placing the geosynthetic pavement interlayer and asphalt binder:

1. Repair cracks 1/4 inch and wider, spalls, and holes in the pavement. The State pays for this repair work under Section 4-1.03D, "Extra Work."
2. Clean the pavement of loose and extraneous material.

Immediately before placing the interlayer, apply 0.25 gallon ± 0.03 gallon of asphalt binder per square yard of interlayer or until the fabric is saturated. Apply asphalt binder the width of the geosynthetic pavement interlayer plus 3 inches on each side. At interlayer overlaps, apply asphalt binder on the lower interlayer the same overlap distance as the upper interlayer.

Align and place the interlayer with no overlapping wrinkles, except a wrinkle that overlaps may remain if it is less than 1/2 inch thick. If the overlapping wrinkle is more than 1/2 inch thick, cut the wrinkle out and overlap the interlayer no more than 2 inches.

The minimum HMA thickness over the interlayer must be 0.12 foot thick including conform tapers. Do not place the interlayer on a wet or frozen surface.

Overlap the interlayer borders between 2 inches and 4 inches. In the direction of paving, overlap the following roll with the preceding roll at any break.

You may use rolling equipment to correct distortions or wrinkles in the interlayer.

If asphalt binder tracked onto the interlayer or brought to the surface by construction equipment causes interlayer displacement, cover it with a small quantity of HMA.

Before placing HMA on the interlayer, do not expose the interlayer to:

1. Traffic except for crossings under traffic control and only after you place a small HMA quantity
2. Sharp turns from construction equipment
3. Damaging elements

Pave HMA on the interlayer during the same work shift.

39-1.10 Spreading And Compacting Equipment

Paving equipment for spreading must be:

1. Self-propelled
2. Mechanical
3. Equipped with a screed or strike-off assembly that can distribute HMA the full width of a traffic lane
4. Equipped with a full-width compacting device
5. Equipped with automatic screed controls and sensing devices that control the thickness, longitudinal grade, and transverse screed slope

Install and maintain grade and slope references.

The screed must produce a uniform HMA surface texture without tearing, shoving, or gouging.

The paver must not leave marks such as ridges and indentations unless you can eliminate them by rolling.

Rollers must be equipped with a system that prevents HMA from sticking to the wheels. You may use a parting agent that does not damage the HMA or impede the bonding of layers.

In areas inaccessible to spreading and compacting equipment:

1. Spread the HMA by any means to obtain the specified lines, grades and cross sections.
2. Use a pneumatic tamper, plate compactor, or equivalent to achieve thorough compaction.

39-1.11 Transporting, Spreading, And Compacting

Do not pave HMA on a wet pavement or frozen surface.

You may deposit HMA in a windrow and load it in the paver if:

1. Paver is equipped with a hopper that automatically feeds the screed
2. Loading equipment can pick up the windrowed material and deposit it in the paver hopper without damaging base material
3. Activities for deposit, pick-up, loading, and paving are continuous
4. HMA temperature in the windrow does not fall below 260 °F

You may pave HMA in 1 or more layers on areas less than 5 feet wide and outside the traveled way including shoulders. You may use mechanical equipment other than a paver for these areas. The equipment must produce a uniform smoothness and texture.

HMA handled, spread, or windrowed must not stain the finished surface of any improvement including pavement.

Do not use petroleum products such as kerosene or diesel fuel to release HMA from trucks, spreaders, or compactors.

HMA must be free of:

1. Segregation
2. Coarse or fine aggregate pockets
3. Hardened lumps

Longitudinal joints in the top layer must match specified lane edges. Alternate longitudinal joint offsets in lower layers at least 0.5 foot from each side of the specified lane edges. You may request in writing other longitudinal joint placement patterns.

Until the adjoining through lane's top layer has been paved, do not pave the top layer of:

1. Shoulders
2. Tapers
3. Transitions
4. Road connections
5. Private drives
6. Curve widenings
7. Chain control lanes
8. Turnouts
9. Left turn pockets

If the number of lanes change, pave each through lane's top layer before paving a changing lane's top layer. Simultaneous to paving a through lane's top layer, you may pave an adjoining area's top layer including shoulders. Do not operate spreading equipment on any area's top layer until completing final compaction.

If HMA (leveling) is specified, fill and level irregularities and ruts with HMA before spreading HMA over base, existing surfaces, or bridge decks. You may use mechanical equipment other than a paver for these areas. The equipment must produce a uniform smoothness and texture. HMA used to change an existing surface's cross slope or profile is not HMA (leveling).

If placing HMA against the edge of existing pavement, sawcut or grind the pavement straight and vertical along the joint and remove extraneous material without damaging the surface remaining in place. If placing HMA against the edge of a longitudinal or transverse construction joint and the joint is damaged or not placed to a neat line, sawcut or grind the pavement straight and vertical along the joint and remove extraneous material without damaging the surface remaining in place. Repair or remove and replace damaged pavement at your expense.

Rolling must leave the completed surface compacted and smooth without tearing, cracking, or shoving. Complete finish rolling activities before the pavement surface temperature is:

1. Below 150 °F for HMA with unmodified binder
2. Below 140 °F for HMA with modified binder
3. Below 200 °F for RHMA-G

If a vibratory roller is used as a finish roller, turn the vibrator off.

Do not use a pneumatic tired roller to compact RHMA-G.

For Standard and QC/QA, if a 3/4-inch aggregate grading is specified, you may use a 1/2-inch aggregate grading if the total layer thickness is between 0.125 foot and 0.20 foot thick.

Spread and compact HMA under Section 39-3.03, "Spreading and Compacting Equipment," and Section 39-3.04, "Transporting, Spreading, and Compacting," if either:

1. Total paved thickness is less than 0.15 foot.
2. Total paved thickness is less than 0.20 foot and a 3/4-inch aggregate grading is specified and used.
3. You spread and compact at:
 - 3.1. Asphalt concrete surfacing replacement areas
 - 3.2. Leveling courses
 - 3.3. Detours not included in the final roadway prism
 - 3.4. Areas the Engineer determines conventional compaction and compaction measurement methods are impeded

Do not allow traffic on new HMA pavement until its mid-depth temperature is below 160 °F.

If you request in writing and the Engineer authorizes, you may cool HMA Type A and Type B with water when rolling activities are complete. Apply water under Section 17, "Watering."

Spread sand at a rate between 1 pound and 2 pounds per square yard on new RHMA-G, RHMA-O, and RHMA-O-HB pavement when finish rolling is complete. Sand must be free of clay or organic matter. Sand must comply with Section 90-3.03, "Fine Aggregate Grading." Keep traffic off the pavement until spreading sand is complete.

39-1.12 SMOOTHNESS

39-1.12A General

Determine HMA smoothness with a profilograph and a straightedge.

Smoothness specifications do not apply to OGFC placed on existing pavement not constructed under the same project.

If portland cement concrete is placed on HMA:

1. Cold plane the HMA finished surface to within specified tolerances if it is higher than the grade specified by the Engineer.
2. Remove and replace HMA if the finished surface is lower than 0.05 foot below the grade specified by the Engineer.

39-1.12B Straightedge

The HMA pavement top layer must not vary from the lower edge of a 12-foot long straightedge:

1. More than 0.01 foot when the straight edge is laid parallel with the centerline
2. More than 0.02 foot when the straightedge is laid perpendicular to the centerline and extends from edge to edge of a traffic lane
3. More than 0.02 foot when the straightedge is laid within 24 feet of a pavement conform

39-1.12C Profilograph

Under California Test 526, determine the zero (null) blanking band Profile Index (PI_0) and must-grinds on the top layer of HMA Type A, Type B, and RHMA-G pavement. Take 2 profiles within each traffic lane, 3 feet from and parallel with the edge of each lane.

A must-grind is a deviation of 0.3 inch or more in a length of 25 feet. You must correct must-grinds.

For OGFC, only determine must-grinds when placed over HMA constructed under the same project. The top layer of the underlying HMA must comply with the smoothness specifications before placing OGFC.

Profile pavement in the Engineer's presence. Choose the time of profiling.

On tangents and horizontal curves with a centerline radius of curvature 2,000 feet or more, the PI_0 must be at most 3 inches per 0.1-mile section.

On horizontal curves with a centerline radius of curvature between 1,000 feet and 2,000 feet including pavement within the superelevation transitions, the PI_0 must be at most 6 inches per 0.1-mile section.

Before the Engineer accepts HMA pavement for smoothness, submit written final profilograms.

Submit 1 electronic copy of profile information in Microsoft Excel and 1 electronic copy of longitudinal pavement profiles in ".erd" format or other ProVAL compatible format to the Engineer and to:

Smoothness@dot.ca.gov

The following HMA pavement areas do not require a PI_0 . You must measure these areas with a 12-foot straightedge and determine must-grinds with a profilograph:

1. New HMA with a total thickness less than or equal to 0.25 foot
2. HMA sections of city or county streets and roads, turn lanes and collector lanes that are less than 1,500 feet in length

The following HMA pavement areas do not require a PI_0 . You must measure these areas with a 12-foot straightedge:

1. Horizontal curves with a centerline radius of curvature less than 1,000 feet including pavement within the superelevation transitions of those curves
2. Within 12 feet of a transverse joint separating the pavement from:
 - 2.1. Existing pavement not constructed under the same project
 - 2.2. A bridge deck or approach slab
3. Exit ramp termini, truck weigh stations, and weigh-in-motion areas
4. If steep grades and superelevation rates greater than 6 percent are present on:
 - 4.1. Ramps
 - 4.2. Connectors
5. Turn lanes and areas around manholes or drainage transitions
6. Acceleration and deceleration lanes for at-grade intersections
7. Shoulders and miscellaneous areas
8. HMA pavement within 3 feet from and parallel to the construction joints formed between curbs, gutters, or existing pavement

39-1.12D Smoothness Correction

If the top layer of HMA Type A, Type B, or RHMA-G pavement does not comply with the smoothness specifications, grind the pavement to within tolerances, remove and replace it, or place an overlay of HMA. The Engineer must authorize your choice of correction before the work begins.

Remove and replace the areas of OGFC not in compliance with the must-grind and straightedge specifications, except you may grind OGFC for correcting smoothness:

1. At a transverse joint separating the pavement from pavement not constructed under the same project
2. Within 12 feet of a transverse joint separating the pavement from a bridge deck or approach slab

Corrected HMA pavement areas must be uniform rectangles with edges:

1. Parallel to the nearest HMA pavement edge or lane line
2. Perpendicular to the pavement centerline

After correcting for smoothness, measure the corrected HMA pavement surface with a profilograph and a 12-foot straightedge until the pavement is within specified tolerances. If a must-grind area or straightedged pavement cannot be corrected to within specified tolerances, remove and replace the pavement.

On ground areas not overlaid with OGFC, apply fog seal coat under Section 37-1, "Seal Coats."

39-1.13 MISCELLANEOUS AREAS AND DIKES

Miscellaneous areas are outside the traveled way and include:

1. Median areas not including inside shoulders
2. Island areas
3. Sidewalks

4. Gutters
5. Gutter flares
6. Ditches
7. Overside drains
8. Aprons at the ends of drainage structures

Spread miscellaneous areas in 1 layer and compact to the specified lines and grades.
For miscellaneous areas and dikes:

1. Do not submit a JMF.
2. Choose the 3/8-inch or 1/2-inch HMA Type A and Type B aggregate gradations.
3. Minimum asphalt binder content must be 6.8 percent for 3/8-inch aggregate and 6.0 percent for 1/2-inch aggregate. If you request in writing and the Engineer authorizes, you may reduce the minimum asphalt binder content.
4. Choose asphalt binder Grade PG 70-10 or the same grade specified for HMA.

39-1.14 SHOULDER RUMBLE STRIP

Construct shoulder rumble strips by rolling or grinding indentations in the top layer of new HMA surfacing.

Select the method and equipment for constructing ground-in indentations.

Do not construct shoulder rumble strips on structures or approach slabs.

Construct rumble strips within 2 inches of the specified alignment. Roller or grinding equipment must be equipped with a sighting device enabling the operator to maintain the rumble strip alignment.

Rolled-in indentations must not vary from the specified dimensions by more than 10 percent.

Ground-in indentations must comply with the specified dimensions within 0.06 inch in depth or 10 percent in length and width.

The Engineer orders grinding or removal and replacement of noncompliant rumble strips to bring them within specified tolerances. Ground surface areas must be neat and uniform in appearance.

The grinding equipment must be equipped with a vacuum attachment to remove residue.

Dispose of removed material under Section 7-1.13, "Disposal of Material Outside the Highway Right of Way."

On ground areas, apply fog seal coat under Section 37-1, "Seal Coats."

39-2 STANDARD

39-2.01 DESCRIPTION

If HMA is specified as Standard, construct it under Section 39-1, "General," this Section 39-2, "Standard," and Section 39-5, "Measurement and Payment."

39-2.02 CONTRACTOR QUALITY CONTROL

39-2.02A Quality Control Plan

Establish, implement, and maintain a Quality Control Plan (QCP) for HMA. The QCP must describe the organization and procedures you will use to:

1. Control the quality characteristics
2. Determine when corrective actions are needed (action limits)
3. Implement corrective actions

When you submit the proposed JMF, submit the written QCP. You and the Engineer must discuss the QCP during the prepaving conference.

The QCP must address the elements affecting HMA quality including:

1. Aggregate
2. Asphalt binder
3. Additives
4. Production
5. Paving

39-2.02B Quality Control Testing

Perform sampling and testing at the specified frequency for the following quality characteristics:

Minimum Quality Control – Standard

Quality Characteristic	Test Method	Minimum Sampling and Testing Frequency	HMA Type			
			A	B	RHMA-G	OGFC
Aggregate gradation ^a	CT 202	1 per 750 tons and any remaining part	JMF ± Tolerance ^b			
Sand equivalent (min.) ^c	CT 217		47	42	47	--
Asphalt binder content (%)	CT 379 or 382		JMF ± 0.45	JMF ± 0.45	JMF ± 0.50	JMF +0.50 -0.70
HMA moisture content (% max.)	CT 226 or CT 370	1 per 2,500 tons but not less than 1 per paving day	1.0	1.0	1.0	1.0
Percent of maximum theoretical density (%) ^{d, e}	Quality control plan	2 per business day (min.)	91 - 97	91 - 97	91 - 97	--
Stabilometer value (min.) ^{c, f} No. 4 and 3/8" gradings 1/2" and 3/4" gradings	CT 366	One per 4,000 tons or 2 per 5 business days, whichever is more	30	30	--	--
			37	35	23	--
Air voids content (%) ^{c, g}	CT 367	more	4 ± 2	4 ± 2	Specification ± 2	--
Aggregate moisture content at continuous mixing plants and RAP moisture content at continuous mixing plants and batch mixing plants ^h	CT 226 or CT 370	2 per day during production	--	--	--	--
Percent of crushed particles coarse aggregate (% min.) One fractured face Two fractured faces Fine aggregate (% min) (Passing No. 4 sieve and retained on No. 8 sieve.) One fractured face	CT 205	As necessary and designated in the QCP. At least once per project	90	25	--	90
			75	--	90	75
			70	20	70	90
Los Angeles Rattler (% max.) Loss at 100 rev. Loss at 500 rev.	CT 211		12 45	-- 50	12 40	12 40

Flat and elongated particles (% max. by weight @ 5:1)	ASTM D 4791		Report only	Report only	Report only	Report only
Fine aggregate angularity (% min.)	AASHTO T 304, Method A		Report only	Report only	Report only	--
Voids filled with asphalt (%) ⁱ No. 4 grading 3/8" grading 1/2" grading 3/4" grading	LP-3		76.0 – 80.0 73.0 – 76.0 65.0 – 75.0 65.0 – 75.0	76.0 – 80.0 73.0 – 76.0 65.0 – 75.0 65.0 – 75.0	Report only	--
Voids in mineral aggregate (% min.) ⁱ No. 4 grading 3/8" grading 1/2" grading 3/4" grading	LP-2		17.0 15.0 14.0 13.0	17.0 15.0 14.0 13.0	-- -- 18.0 – 23.0 ^j 18.0 – 23.0 ^j	--
Dust proportion ¹ No. 4 and 3/8" gradings 1/2" and 3/4" gradings	LP-4		0.9 – 2.0 0.6 – 1.3	0.9 – 2.0 0.6 – 1.3	Report only	--
Smoothness	Section 39-1.12	--	12-foot straightedge, must-grind, and PI ₀	12-foot straightedge, must-grind, and PI ₀	12-foot straightedge, must-grind, and PI ₀	12-foot straightedge and must-grind
Asphalt rubber binder viscosity @ 350 °F, centipoises	Section 39-1.02D	--	--	--	1,500 – 4,000	1,500 – 4,000
Crumb rubber modifier	Section 39-1.02D	--	--	--	Section 39-1.02D	Section 39-1.02D

Notes:

^a Determine combined aggregate gradation containing RAP under Laboratory Procedure LP-9.

^b The tolerances must comply with the allowable tolerances in Section 39-1.02E, "Aggregate."

^c Report the average of 3 tests from a single split sample.

^d Required for HMA Type A, Type B, and RHMA-G if the total paved thickness is at least 0.15 foot.

^e Determine maximum theoretical density (California Test 309) at the frequency specified for Test Maximum Density under California Test 375, Part 5.D.

^f Modify California Test 304, Part 2.B.2.c: "After compaction in the mechanical compactor, cool to 140 °F ± 5 °F by allowing the briquettes to cool at room temperature for 0.5 hour, then place the briquettes in the oven at 140 °F for a minimum of 2 hours and not more than 3 hours."

^g Determine the bulk specific gravity of each lab-compacted briquette under California Test 308, Method A, and theoretical maximum specific gravity under California Test 309.

^h For adjusting the plant controller at the HMA plant.

ⁱ Report only if the adjustment for asphalt binder content target value is less than ± 0.3 percent from OBC.

^j Voids in mineral aggregate for RHMA-G must be within this range.

For any single quality characteristic except smoothness, if 2 consecutive quality control test results do not comply with the action limits or specifications:

1. Stop production.
2. Notify the Engineer in writing.
3. Take corrective action.
4. Demonstrate compliance with the specifications before resuming production and placement on the State highway.

39-2.03 ENGINEER'S ACCEPTANCE

39-2.03A Testing

The Engineer samples for acceptance testing and tests for:

HMA Acceptance - Standard

Quality Characteristic	Test Method	HMA Type			
		A	B	RHMA-G	OGFC
Aggregate gradation ^a	CT 202	JMF ± Tolerance ^c	JMF ± Tolerance ^c	JMF ± Tolerance ^c	JMF ± Tolerance ^c
Sieve 3/4" 1/2" 3/8"					
1/2" X ^b					
3/8" X					
No. 4 X					
No. 8 X X X					
No. 200 X X X					
Sand equivalent (min.) ^d	CT 217	47	42	47	--
Asphalt binder content (%)	CT 379 or 382	JMF ± 0.45	JMF ± 0.45	JMF ± 0.5	JMF +0.50 -0.70
HMA moisture content (% max.)	CT 226 or CT 370	1.0	1.0	1.0	1.0
Percent of maximum theoretical density (%) ^{e,f}	CT 375	91 – 97	91 – 97	91 – 97	--
Stabilometer value (min.) ^{d, g}	CT 366	30	30	--	--
No. 4 and 3/8" gradings					
1/2" and 3/4" gradings		37	35	23	--
Air voids content (%) ^{d, h}	CT 367	4 ± 2	4 ± 2	Specification ± 2	--
Percent of crushed particles	CT 205	90	25	--	90
Coarse aggregate (% min.)					
One fractured face					
Two fractured faces					
Fine aggregate (% min)	70	20	70	90	90
(Passing No. 4 sieve and retained on No. 8 sieve.)					
One fractured face					
Los Angeles Rattler (% max.)	CT 211	12	--	12	12
Loss at 100 rev.					
Loss at 500 rev.		45	50	40	40
Fine aggregate angularity (% min.)	AASHTO T 304, Method A	Report only	Report only	Report only	--
Flat and elongated particles (%, max. by weight @ 5:1)	ASTM D 4791	Report only	Report only	Report only	Report only
Voids filled with asphalt (%) ⁱ	LP-3	76.0 – 80.0	76.0 – 80.0	Report only	--
No. 4 grading					
3/8" grading					
1/2" grading					
3/4" grading		65.0 – 75.0	65.0 – 75.0		
Voids in mineral aggregate (% min.) ⁱ	LP-2	17.0	17.0	--	--
No. 4 grading					
3/8" grading					
1/2" grading					
3/4" grading		13.0	13.0	18.0 – 23.0 ^j	18.0 – 23.0 ^j
Dust proportion ⁱ	LP-4	0.9 – 2.0	0.9 – 2.0	Report only	--
No. 4 and 3/8" gradings					
1/2" and 3/4" gradings		0.6 – 1.3	0.6 – 1.3		
Smoothness	Section 39-1.12	12-foot straightedge, must-grind, and PI ₀	12-foot straightedge, must-grind, and PI ₀	12-foot straightedge, must-grind, and PI ₀	12-foot straightedge and must-grind

Asphalt binder	Various	Section 92	Section 92	Section 92	Section 92
Asphalt rubber binder	Various	--	--	Section 92-1.02(C) and Section 39-1.02D	Section 92-1.02(C) and Section 39-1.02D
Asphalt modifier	Various	--	--	Section 39-1.02D	Section 39-1.02D
Crumb rubber modifier	Various	--	--	Section 39-1.02D	Section 39-1.02D

^a The Engineer determines combined aggregate gradations containing RAP under Laboratory Procedure LP-9.

^b "X" denotes the sieves the Engineer considers for the specified aggregate gradation.

^c The tolerances must comply with the allowable tolerances in Section 39-1.02E, "Aggregate."

^d The Engineer reports the average of 3 tests from a single split sample.

^e The Engineer determines percent of maximum theoretical density if the total paved thickness is at least 0.15 foot under California Test 375 except the Engineer uses:

1. California Test 308, Method A, to determine in-place density of each core instead of using the nuclear gauge in Part 4, "Determining In-Place Density By The Nuclear Density Device."
2. California Test 309 to determine maximum theoretical density instead of calculating test maximum density in Part 5, "Determining Test Maximum Density."

^f The Engineer determines maximum theoretical density (California Test 309) at the frequency specified for Test Maximum Density under California Test 375, Part 5.D.

^g Modify California Test 304, Part 2.B.2.c: "After compaction in the mechanical compactor, cool to 140 °F ±5 °F by allowing the briquettes to cool at room temperature for 0.5 hour, then place the briquettes in the oven at 140 °F for a minimum of 2 hours and not more than 3 hours."

^h The Engineer determines the bulk specific gravity of each lab-compacted briquette under California Test 308, Method A, and theoretical maximum specific gravity under California Test 309.

ⁱ Report only if the adjustment for asphalt binder content target value is less than ± 0.3 percent from OBC.

^j Voids in mineral aggregate for RHMA-G must be within this range.

No single test result may represent more than the smaller of 750 tons or 1 day's production.

For any single quality characteristic except smoothness, if 2 consecutive acceptance test results do not comply with the specifications:

1. Stop production.
2. Take corrective action.
3. In the Engineer's presence, take samples and split each sample into 4 parts. Test 1 part for compliance with the specifications and submit 3 parts to the Engineer. The Engineer tests 1 part for compliance with the specifications and reserves and stores 2 parts.
4. Demonstrate compliance with the specifications before resuming production and placement on the State highway.

The Engineer tests the core you take from each 250 tons of HMA production. The Engineer determines the percent of maximum theoretical density for each core by determining the core's density and dividing by the maximum theoretical density.

If the total paved thickness is at least 0.15 foot and any layer is less than 0.15 foot, the Engineer determines the percent of maximum theoretical density from cores taken from the final layer measured the full depth of the total paved HMA thickness.

For percent of maximum theoretical density, the Engineer determines a deduction for each test result outside the specifications in compliance with:

Reduced Payment Factors for Percent of Maximum Theoretical Density

HMA Type A and B and RHMA-G Percent of Maximum Theoretical Density	Reduced Payment Factor	HMA Type A and B and RHMA-G Percent of Maximum Theoretical Density	Reduced Payment Factor
91.0	0.0000	97.0	0.0000
90.9	0.0125	97.1	0.0125
90.8	0.0250	97.2	0.0250
90.7	0.0375	97.3	0.0375
90.6	0.0500	97.4	0.0500
90.5	0.0625	97.5	0.0625
90.4	0.0750	97.6	0.0750
90.3	0.0875	97.7	0.0875
90.2	0.1000	97.8	0.1000
90.1	0.1125	97.9	0.1125
90.0	0.1250	98.0	0.1250
89.9	0.1375	98.1	0.1375
89.8	0.1500	98.2	0.1500
89.7	0.1625	98.3	0.1625
89.6	0.1750	98.4	0.1750
89.5	0.1875	98.5	0.1875
89.4	0.2000	98.6	0.2000
89.3	0.2125	98.7	0.2125
89.2	0.2250	98.8	0.2250
89.1	0.2375	98.9	0.2375
89.0	0.2500	99.0	0.2500
< 89.0	Remove and Replace	> 99.0	Remove and Replace

39-2.04 TRANSPORTING, SPREADING, AND COMPACTING

Determine the number of rollers needed to obtain the specified density and surface finish.

39-3 METHOD

39-3.01 DESCRIPTION

If HMA is specified as Method, construct it under Section 39-1, "General," this Section 39-3, "Method," and Section 39-5, "Measurement and Payment."

39-3.02 ENGINEER'S ACCEPTANCE

39-3.02A Testing

The Engineer samples for acceptance testing and tests for:

HMA Acceptance - Method

Quality Characteristic	Test Method	HMA Type			
		A	B	RHMA-G	OGFC
Aggregate gradation ^a	CT 202	JMF ± Tolerance ^b			
Sand equivalent (min.) ^c	CT 217	47	42	47	--
Asphalt binder content (%)	CT 379 or 382	JMF ± 0.45	JMF ± 0.45	JMF ± 0.5	JMF +0.50 -0.70
HMA moisture content (% max.)	CT 226 or CT 370	1.0	1.0	1.0	1.0
Stabilometer value (min.) ^{c, d}	CT 366				
No. 4 and 3/8" gradings		30	30	--	--
1/2" and 3/4" gradings		37	35	23	--
Percent of crushed particles	CT 205				
Coarse aggregate (% min.)					
One fractured face		90	25	--	90
Two fractured faces		75	--	90	75
Fine aggregate (% min) (Passing No. 4 sieve and retained on No. 8 sieve.)					
One fractured face		70	20	70	90
Los Angeles Rattler (% max.)	CT 211				
Loss at 100 rev.		12	--	12	12
Loss at 500 rev.		45	50	40	40
Air voids content (%) ^{c, e}	CT 367	4 ± 2	4 ± 2	Specification ± 2	--
Fine aggregate angularity (% min.)	AASHTO T 304, Method A	Report only	Report only	Report only	--
Flat and elongated particles (% max. by weight @ 5:1)	ASTM D 4791	Report only	Report only	Report only	Report only
Voids filled with asphalt (%) ^f	LP-3			Report only	--
No. 4 grading		76.0 – 80.0	76.0 – 80.0		
3/8" grading		73.0 – 76.0	73.0 – 76.0		
1/2" grading		65.0 – 75.0	65.0 – 75.0		
3/4" grading		65.0 – 75.0	65.0 – 75.0		
Voids in mineral aggregate (% min.) ^f	LP-2				--
No. 4 grading		17.0	17.0	--	
3/8" grading		15.0	15.0	--	
1/2" grading		14.0	14.0	18.0 – 23.0 ^g	
3/4" grading		13.0	13.0	18.0 – 23.0 ^g	
Dust proportion ^f	LP-4			Report only	--
No. 4 and 3/8" gradings		0.9 – 2.0	0.9 – 2.0		
1/2" and 3/4" gradings		0.6 – 1.3	0.6 – 1.3		
Smoothness	Section 39-1.12	12-foot straightedge and must-grind			
Asphalt binder	Various	Section 92	Section 92	Section 92	Section 92
Asphalt rubber binder	Various	--	--	Section 92-	Section 92-

				1.02(C) and Section 39- 1.02D	1.02(C) and Section 39- 1.02D
Asphalt modifier	Various	--	--	Section 39- 1.02D	Section 39- 1.02D
Crumb rubber modifier	Various	--	--	Section 39- 1.02D	Section 39- 1.02D

^aThe Engineer determines combined aggregate gradations containing RAP under Laboratory Procedure LP-9.

^bThe tolerances must comply with the allowable tolerances in Section 39-1.02E, "Aggregate."

^cThe Engineer reports the average of 3 tests from a single split sample.

^dModify California Test 304, Part 2.B.2.c: "After compaction in the mechanical compactor, cool to 140 °F ±5 °F by allowing the briquettes to cool at room temperature for 0.5 hour, then place the briquettes in the oven at 140 °F for a minimum of 2 hours and not more than 3 hours."

^eThe Engineer determines the bulk specific gravity of each lab-compacted briquette under California Test 308, Method A, and theoretical maximum specific gravity under California Test 309.

^fReport only if the adjustment for asphalt binder content target value is less than ± 0.3 percent from OBC.

^g voids in mineral aggregate for RHMA-G must be within this range.

No single test result may represent more than the smaller of 750 tons or 1 day's production.

For any single quality characteristic except smoothness, if 2 consecutive acceptance test results do not comply with the specifications:

1. Stop production.
2. Take corrective action.
3. In the Engineer's presence, take samples and split each sample into 4 parts. Test 1 part for compliance with the specifications and submit 3 parts to the Engineer. The Engineer tests 1 part for compliance with the specifications and reserves and stores 2 parts.
4. Demonstrate compliance with the specifications before resuming production and placement on the State highway.

39-3.03 SPREADING AND COMPACTING EQUIPMENT

Each paver spreading HMA Type A and Type B must be followed by 3 rollers:

1. One vibratory roller specifically designed to compact HMA. The roller must be capable of at least 2,500 vibrations per minute and must be equipped with amplitude and frequency controls. The roller's gross static weight must be at least 7.5 tons.
2. One oscillating type pneumatic-tired roller at least 4 feet wide. Pneumatic tires must be of equal size, diameter, type, and ply. The tires must be inflated to 60 psi minimum and maintained so that the air pressure does not vary more than 5 psi.
3. One steel-tired, 2-axle tandem roller. The roller's gross static weight must be at least 7.5 tons.

Each roller must have a separate operator. Rollers must be self-propelled and reversible.

Compact RHMA-G under the specifications for compacting HMA Type A and Type B except do not use pneumatic-tired rollers.

Compact OGFC with steel-tired, 2-axle tandem rollers. If placing over 300 tons of OGFC per hour, use at least 3 rollers for each paver. If placing less than 300 tons of OGFC per hour, use at least 2 rollers for each paver. Each roller must weigh between 126 pounds to 172 pounds per linear inch of drum width. Turn the vibrator off.

39-3.04 TRANSPORTING, SPREADING, AND COMPACTING

Pave HMA in maximum 0.25-foot thick compacted layers.

If the surface to be paved is both in sunlight and shade, pavement surface temperatures are taken in the shade.

Spread HMA Type A and Type B only if atmospheric and surface temperatures are:

Minimum Atmospheric and Surface Temperatures

Compacted Layer Thickness, feet	Minimum Atmospheric and Surface Temperatures			
	Atmospheric, ° F		Surface, ° F	
	Unmodified Asphalt Binder	Modified Asphalt Binder ^a	Unmodified Asphalt Binder	Modified Asphalt Binder ^a
< 0.15	55	50	60	55
0.15 – 0.25	45	45	50	50

Note:

^a Except asphalt rubber binder.

If the asphalt binder for HMA Type A and Type B is:

1. Unmodified asphalt binder, complete:
 - 1.1. First coverage of breakdown compaction before the surface temperature drops below 250 °F
 - 1.2. Breakdown and intermediate compaction before the surface temperature drops below 200 °F
 - 1.3. Finish compaction before the surface temperature drops below 150 °F
2. Modified asphalt binder, complete:
 - 2.1. First coverage of breakdown compaction before the surface temperature drops below 240 °F
 - 2.2. Breakdown and intermediate compaction before the surface temperature drops below 180 °F
 - 2.3. Finish compaction before the surface temperature drops below 140 °F

For RHMA-G:

1. Only spread and compact if the atmospheric temperature is at least 55 °F and the surface temperature is at least 60 °F.
2. Complete the first coverage of breakdown compaction before the surface temperature drops below 280 °F.
3. Complete breakdown and intermediate compaction before the surface temperature drops below 250 °F.
4. Complete finish compaction before the surface temperature drops below 200 °F.
5. If the atmospheric temperature is below 70 °F, cover loads in trucks with tarpaulins. The tarpaulins must completely cover the exposed load until you transfer the mixture to the paver's hopper or to the pavement surface.

For OGFC with unmodified asphalt binder:

1. Only spread and compact if the atmospheric temperature is at least 55 °F and the surface temperature is at least 60 °F.
2. Complete first coverage using 2 rollers before the surface temperature drops below 240 °F.
3. Complete all compaction before the surface temperature drops below 200 °F.
4. If the atmospheric temperature is below 70 °F, cover loads in trucks with tarpaulins. The tarpaulins must completely cover the exposed load until you transfer the mixture to the paver's hopper or to the pavement surface.

For OGFC with modified asphalt binder except asphalt rubber binder:

1. Only spread and compact if the atmospheric temperature is at least 50 °F and the surface temperature is at least 50 °F.
2. Complete first coverage using 2 rollers before the surface temperature drops below 240 °F.
3. Complete all compaction before the surface temperature drops below 180 °F.
4. If the atmospheric temperature is below 70 °F, cover loads in trucks with tarpaulins. The tarpaulins must completely cover the exposed load until you transfer the mixture to the paver's hopper or to the pavement surface.

For RHMA-O and RHMA-O-HB:

1. Only spread and compact if the atmospheric temperature is at least 55 °F and surface temperature is at least 60 °F.
2. Complete the 1st coverage using 2 rollers before the surface temperature drops below 280 °F.
3. Complete compaction before the surface temperature drops below 250 °F.

4. If the atmospheric temperature is below 70 °F, cover loads in trucks with tarpaulins. The tarpaulins must completely cover the exposed load until the mixture is transferred to the paver's hopper or to the pavement surface.

For RHMA-G and OGFC, tarpaulins are not required if the time from discharge to truck until transfer to the paver's hopper or the pavement surface is less than 30 minutes.

HMA compaction coverage is the number of passes needed to cover the paving width. A pass is 1 roller's movement parallel to the paving in either direction. Overlapping passes are part of the coverage being made and are not a subsequent coverage. Do not start a coverage until completing the prior coverage.

Start rolling at the lower edge and progress toward the highest part.

Perform breakdown compaction of each layer of HMA Type A, Type B, and RHMA-G with 3 coverages using a vibratory roller. The speed of the vibratory roller in miles per hour must not exceed the vibrations per minute divided by 1,000. If the HMA layer thickness is less than 0.08 foot, turn the vibrator off. The Engineer may order fewer coverages if the HMA layer thickness is less than 0.15 foot.

Perform intermediate compaction of each layer of HMA Type A and Type B with 3 coverages using a pneumatic-tired roller at a speed not to exceed 5 mph.

Perform finish compaction of HMA Type A, Type B, and RHMA-G with 1 coverage using a steel-tired roller.

Compact OGFC with 2 coverages using steel-tired rollers.

39-4 QUALITY CONTROL / QUALITY ASSURANCE

39-4.01 DESCRIPTION

If HMA is specified as Quality Control / Quality Assurance, construct it under Section 39-1, "General," this Section 39-4, "Quality Control / Quality Assurance," and Section 39-5, "Measurement and Payment."

39-4.02 GENERAL

The QC / QA construction process consists of:

1. Establishing, maintaining, and changing if needed a quality control system providing assurance the HMA complies with the specifications
2. Sampling and testing at specified intervals, or sublots, to demonstrate compliance and to control process
3. The Engineer sampling and testing at specified intervals to verify testing process and HMA quality
4. The Engineer using test results, statistical evaluation of verified quality control tests, and inspection to accept HMA for payment

A lot is a quantity of HMA. The Engineer designates a new lot when:

1. 20 sublots are complete
2. The JMF changes
3. Production stops for more than 30 days

Each lot consists of no more than 20 sublots. A subplot is 750 tons except HMA paved at day's end greater than 250 tons is a subplot. If HMA paved at day's end is less than 250 tons, you may either make this quantity a subplot or include it in the previous subplot's test results for statistical evaluation.

39-4.03 CONTRACTOR QUALITY CONTROL

39-4.03A General

Use a composite quality factor, QF_C , and individual quality factors, QF_{QCi} , to control your process and evaluate quality control program. For quality characteristics without quality factors, use your quality control plan's action limits to control process.

Control HMA quality including:

1. Materials
2. Proportioning
3. Spreading and compacting
4. Finished roadway surface

Develop, implement, and maintain a quality control program that includes:

1. Inspection

2. Sampling
3. Testing

39-4.03B Quality Control Plan

With the JMF submittal, submit a written Quality Control Plan (QCP). The QCP must comply with the Department's Quality Control Manual for Hot Mix Asphalt Production and Placement. Discuss the QCP with the Engineer during the prepaving conference.

The Engineer reviews each QCP within 5 business days from the submittal. Hold HMA production until the Engineer accepts the QCP in writing. The Engineer's QCP acceptance does not mean your compliance with the QCP will result in acceptable HMA. Section 39-1.05, "Engineer's Acceptance," specifies HMA acceptance.

The QCP must include the name and qualifications of a Quality Control Manager. The Quality Control Manager administers the QCP and during paving must be at the job site within 3 hours of receiving notice. The Quality Control Manager must not be any of the following on the project:

1. Foreman
2. Production or paving crewmember
3. Inspector
4. Tester

The QCP must include action limits and details of corrective action you will take if a test result for any quality characteristic falls outside an action limit.

As work progresses, you must submit a written QCP supplement to change quality control procedures, personnel, tester qualification status, or laboratory accreditation status.

39-4.03C Quality Control Inspection, Sampling, And Testing

Sample, test, inspect, and manage HMA quality control.

Provide a roadway inspector while HMA paving activities are in progress. Provide a plant inspector during HMA production.

Inspectors must comply with the Department's Quality Control Manual for Hot Mix Asphalt Production and Placement.

Provide a testing laboratory and personnel for quality control testing. Provide the Engineer unrestricted access to the quality control activities. Before providing services for the project, the Engineer reviews, accredits, and qualifies the testing laboratory and personnel under the Department's Independent Assurance Program.

The minimum random sampling and testing for quality control is:

Minimum Quality Control – QC / QA

Quality Characteristic	Test Method	Minimum Sampling and Testing Frequency	HMA Type			Location of Sampling	Max. Reporting Time Allowance
			A	B	RHMA-G		
Aggregate gradation ^a	CT 202	1 per 750 tons	JMF ± Tolerance ^b	JMF ± Tolerance ^b	JMF ± Tolerance ^b	CT 125	24 hours
Asphalt binder content (%)	CT 379 or 382		JMF ±0.45	JMF ±0.45	JMF ±0.5	Loose Mix Behind Paver See CT 125	
Percent of maximum theoretical density (%) ^{c, d}	QC Plan		92 - 96	92 - 96	91 - 96	QC Plan	
Aggregate moisture content at continuous mixing plants and RAP moisture content at continuous mixing plants and batch mixing plants ^e	CT 226 or CT 370	2 per day during production	--	--	--	Stock-piles or cold feed belts	--
Sand equivalent (min.) ^f	CT 217	1 per 750 tons	47	42	47	CT 125	24 hours
HMA moisture content (% max.)	CT 226 or CT 370	1 per 2,500 tons but not less than 1 per paving day	1.0	1.0	1.0	Loose Mix Behind Paver See CT 125	24 hours
Stabilometer Value (min.) ^{f, h} No. 4 and 3/8" gradings 1/2" and 3/4" gradings	CT 366	1 per 4,000 tons or 2 per 5 business days, whichever is more	30	30	--		48 hours
			37	35	23		
Air voids content (%) ^{f, h}	CT 367		4 ± 2	4 ± 2	Specification ± 2		

Percent of crushed particles coarse aggregate (% min.) One fractured face Two fractured faces Fine aggregate (% min) (Passing No. 4 sieve and retained on No. 8 sieve.) One fractured face	CT 205	As necessary and designated in QCP. At least once per project.	90	25	--	CT 125	48 hours
Los Angeles Rattler (% max.) Loss at 100 rev. Loss at 500 rev.	CT 211		75	--	90		
Fine aggregate angularity (% min.)	AASHTO T 304, Method A		70	20	70		
Flat and elongated particle (% max. by mass @ 5:1)	ASTM D 4791		12	--	12	CT 125	
Voids filled with asphalt (%) ⁱ No. 4 grading 3/8" grading 1/2" grading 3/4" grading	LP-2		45	50	40		
Voids in mineral aggregate (% min.) ⁱ No. 4 grading 3/8" grading 1/2" grading 3/4" grading	LP-3		Report only	Report only	Report only	CT 125	
Dust proportion ¹ No. 4 and 3/8" gradings 1/2" and 3/4" gradings	LP-4		76.0 – 80.0 73.0 – 76.0 65.0 – 75.0 65.0 – 75.0	76.0 – 80.0 73.0 – 76.0 65.0 – 75.0 65.0 – 75.0	Report only	LP-2	
Smoothness	Section 39-1.12		17.0 15.0 14.0 13.0	17.0 15.0 14.0 13.0	-- -- 18.0 – 23.0 ^j 18.0 – 23.0 ^j	LP-3	
Asphalt rubber binder viscosity @ 350 °F, centipoises	Section 39-1.02D		0.9 – 2.0 0.6 – 1.3	0.9 – 2.0 0.6 – 1.3	Report only	LP-4	
Crumb rubber modifier	Section 39-1.02D		--	--	--	--	
		12-foot straight-edge, must-grind, and PI ₀	12-foot straight-edge, must-grind, and PI ₀	12-foot straight-edge, must-grind, and PI ₀	--		

Notes:

^a Determine combined aggregate gradation containing RAP under Laboratory Procedure LP-9.

^b The tolerances must comply with the allowable tolerances in Section 39-1.02E, "Aggregate."

^c Required for HMA Type A, Type B, and RHMA-G if the total paved thickness is at least 0.15 foot.

^d Determine maximum theoretical density (California Test 309) at the frequency specified for test maximum density under California Test 375, Part 5 D.

^e For adjusting the plant controller at the HMA plant.

^f Report the average of 3 tests from a single split sample.

^g Modify California Test 304, Part 2.B.2.c: "After compaction in the mechanical compactor, cool to 140 °F ± 5 °F by allowing the briquettes to cool at room temperature for 0.5 hour, then place the briquettes in the oven at 140 °F for a minimum of 2 hours and not more than 3 hours."

^h Determine the bulk specific gravity of each lab-compacted briquette under California Test 308, Method A, and theoretical maximum specific gravity under California Test 309.

ⁱ Report only if the adjustment for asphalt binder content target value is less than ± 0.3 percent from OBC.

^j Voids in mineral aggregate for RHMA-G must be within this range.

Within the specified reporting time, submit written test results including:

1. Sampling location, quantity, and time
2. Testing results
3. Supporting data and calculations

If test results for any quality characteristic are beyond the action limits in the QCP, take corrective actions. Document the corrective actions taken in the inspection records under Section 39-4.03E, "Records of Inspection and Testing."

Stop production, notify the Engineer in writing, take corrective action, and demonstrate compliance with the specifications before resuming production and placement on the State highway if:

1. A lot's composite quality factor, Q_{FC} , or an individual quality factor, Q_{FCi} for $i = 3, 4, \text{ or } 5$, is below 0.90 determined under Section 39-4.03F, "Statistical Evaluation"
2. An individual quality factor, Q_{FCi} for $i = 1 \text{ or } 2$, is below 0.75
3. Quality characteristics for which a quality factor, Q_{FCi} , is not determined has 2 consecutive acceptance or quality control tests not in compliance with the specifications

39-4.03D Charts And Records

Record sampling and testing results for quality control on forms provided in the "Quality Control Manual for Hot Mix Asphalt Production and Placement," or on forms you submit with the QCP. The QCP must also include form posting locations and submittal times.

Submit quality control test results using the Department's statistical evaluation program, HMAPay, available at

www.dot.ca.gov/hq/construc/hma/index.htm

39-4.03E Records Of Inspection And Testing

During HMA production, submit in writing a daily:

1. HMA Construction Daily Record of Inspection. Also make this record available at the HMA plant and job site each day.
2. HMA Inspection and Testing Summary. Include in the summary:
 - 2.1. Test forms with the testers' signatures and Quality Control Manager's initials.
 - 2.2. Inspection forms with the inspectors' signatures and Quality Control Manager's initials.
 - 2.3. A list and explanation of deviations from the specifications or regular practices.
 - 2.4. A signed statement by the Quality Control Manager that says:

"It is hereby certified that the information contained in this record is accurate, and that information, tests, or calculations documented herein comply with the specifications of the contract and the standards set forth in the testing procedures. Exceptions to this certification are documented as part of this record."

Retain for inspection the records generated as part of quality control including inspection, sampling, and testing for at least 3 years after final acceptance.

39-4.03F Statistical Evaluation

General

Determine a lot's composite quality factor, QF_C , and the individual quality factors, QF_{QC_i} . Perform statistical evaluation calculations to determine these quality factors based on quality control test results for:

1. Aggregate gradation
2. Asphalt binder content
3. Percent of maximum theoretical density

The Engineer grants a waiver and you must use 1.0 as the individual quality factor for percent of maximum theoretical density, QF_{QCS} , for HMA paved in:

1. Areas where the total paved thickness is less than 0.15 foot
2. Areas where the total paved thickness is less than 0.20 foot and a 3/4-inch grading is specified and used
3. Dig outs
4. Leveling courses
5. Detours not part of the finished roadway prism
6. Areas where, in the opinion of the Engineer, compaction or compaction measurement by conventional methods is impeded

Statistical Evaluation Calculations

Use the Variability-Unknown / Standard Deviation Method to determine the percentage of a lot not in compliance with the specifications. The number of significant figures used in the calculations must comply with AASHTO R-11, Absolute Method.

Determine the percentage of work not in compliance with the specification limits for each quality characteristic as follows:

1. Calculate the arithmetic mean (\bar{X}) of the test values

$$\bar{X} = \frac{\sum x}{n}$$

where:

x = individual test values
 n = number of test values

2. Calculate the standard deviation

$$s = \sqrt{\frac{n(\sum x^2) - (\sum x)^2}{n(n-1)}}$$

where:

$\sum(x^2)$ = sum of the squares of individual test values
 $(\sum x)^2$ = sum of the individual test values squared
 n = number of test values

3. Calculate the upper quality index (Q_u)

$$Q_u = \frac{USL - \bar{X}}{s}$$

where:

USL = target value plus the production tolerance or upper specification limit
 s = standard deviation
 \bar{X} = arithmetic mean

4. Calculate the lower quality index (Q_L);

$$Q_L = \frac{\bar{X} - LSL}{s}$$

where:

LSL = target value minus production tolerance or lower specification limit
 s = standard deviation
 \bar{X} = arithmetic mean

- From the table, Upper Quality Index Q_U or Lower Quality Index Q_L , of this Section 39-4.03F, "Statistical Evaluation", determine P_U ;

where:

P_U = the estimated percentage of work outside the USL.
 $P_U = 0$, when USL is not specified.

- From the table, Upper Quality Index Q_U or Lower Quality Index Q_L , of this Section 39-4.03F, "Statistical Evaluation," determine P_L ;

where:

P_L = the estimated percentage of work outside the LSL.
 $P_L = 0$, when LSL is not specified.

- Calculate the total estimated percentage of work outside the USL and LSL, percent defective

$$\text{Percent defective} = P_U + P_L$$

P_U and P_L are determined from:

P _U or P _L	Upper Quality Index Q _U or Lower Quality Index Q _L												
	Sample Size (n)												
	5	6	7	8	9	10-11	12-14	15-17	18-22	23-29	30-42	43-66	>66
0	1.72	1.88	1.99	2.07	2.13	2.20	2.28	2.34	2.39	2.44	2.48	2.51	2.56
1	1.64	1.75	1.82	1.88	1.91	1.96	2.01	2.04	2.07	2.09	2.12	2.14	2.16
2	1.58	1.66	1.72	1.75	1.78	1.81	1.84	1.87	1.89	1.91	1.93	1.94	1.95
3	1.52	1.59	1.63	1.66	1.68	1.71	1.73	1.75	1.76	1.78	1.79	1.80	1.81
4	1.47	1.52	1.56	1.58	1.60	1.62	1.64	1.65	1.66	1.67	1.68	1.69	1.70
5	1.42	1.47	1.49	1.51	1.52	1.54	1.55	1.56	1.57	1.58	1.59	1.59	1.60
6	1.38	1.41	1.43	1.45	1.46	1.47	1.48	1.49	1.50	1.50	1.51	1.51	1.52
7	1.33	1.36	1.38	1.39	1.40	1.41	1.41	1.42	1.43	1.43	1.44	1.44	1.44
8	1.29	1.31	1.33	1.33	1.34	1.35	1.35	1.36	1.36	1.37	1.37	1.37	1.38
9	1.25	1.27	1.28	1.28	1.29	1.29	1.30	1.30	1.30	1.31	1.31	1.31	1.31
10	1.21	1.23	1.23	1.24	1.24	1.24	1.25	1.25	1.25	1.25	1.25	1.26	1.26
11	1.18	1.18	1.19	1.19	1.19	1.19	1.20	1.20	1.20	1.20	1.20	1.20	1.20
12	1.14	1.14	1.15	1.15	1.15	1.15	1.15	1.15	1.15	1.15	1.15	1.15	1.15
13	1.10	1.10	1.10	1.10	1.10	1.10	1.11	1.11	1.11	1.11	1.11	1.11	1.11
14	1.07	1.07	1.07	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
15	1.03	1.03	1.03	1.03	1.02	1.02	1.02	1.02	1.02	1.02	1.02	1.02	1.02
16	1.00	0.99	0.99	0.99	0.99	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98
17	0.97	0.96	0.95	0.95	0.95	0.95	0.94	0.94	0.94	0.94	0.94	0.94	0.94
18	0.93	0.92	0.92	0.92	0.91	0.91	0.91	0.91	0.90	0.90	0.90	0.90	0.90
19	0.90	0.89	0.88	0.88	0.88	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87
20	0.87	0.86	0.85	0.85	0.84	0.84	0.84	0.83	0.83	0.83	0.83	0.83	0.83
21	0.84	0.82	0.82	0.81	0.81	0.81	0.80	0.80	0.80	0.80	0.80	0.80	0.79
22	0.81	0.79	0.79	0.78	0.78	0.77	0.77	0.77	0.76	0.76	0.76	0.76	0.76
23	0.77	0.76	0.75	0.75	0.74	0.74	0.74	0.73	0.73	0.73	0.73	0.73	0.73
24	0.74	0.73	0.72	0.72	0.71	0.71	0.70	0.70	0.70	0.70	0.70	0.70	0.70
25	0.71	0.70	0.69	0.69	0.68	0.68	0.67	0.67	0.67	0.67	0.67	0.67	0.66
26	0.68	0.67	0.67	0.65	0.65	0.65	0.64	0.64	0.64	0.64	0.64	0.64	0.63
27	0.65	0.64	0.63	0.62	0.62	0.62	0.61	0.61	0.61	0.61	0.61	0.61	0.60
28	0.62	0.61	0.60	0.59	0.59	0.59	0.58	0.58	0.58	0.58	0.58	0.58	0.57
29	0.59	0.58	0.57	0.57	0.56	0.56	0.55	0.55	0.55	0.55	0.55	0.55	0.54
30	0.56	0.55	0.54	0.54	0.53	0.53	0.52	0.52	0.52	0.52	0.52	0.52	0.52
31	0.53	0.52	0.51	0.51	0.50	0.50	0.50	0.49	0.49	0.49	0.49	0.49	0.49
32	0.50	0.49	0.48	0.48	0.48	0.47	0.47	0.47	0.46	0.46	0.46	0.46	0.46
33	0.47	0.48	0.45	0.45	0.45	0.44	0.44	0.44	0.44	0.43	0.43	0.43	0.43
34	0.45	0.43	0.43	0.42	0.42	0.42	0.41	0.41	0.41	0.41	0.41	0.41	0.40
35	0.42	0.40	0.40	0.39	0.39	0.39	0.38	0.38	0.38	0.38	0.38	0.38	0.38
36	0.39	0.38	0.37	0.37	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36	0.36
37	0.36	0.35	0.34	0.34	0.34	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.32
38	0.33	0.32	0.32	0.31	0.31	0.31	0.30	0.30	0.30	0.30	0.30	0.30	0.30
39	0.30	0.30	0.29	0.28	0.28	0.28	0.28	0.28	0.28	0.28	0.28	0.28	0.28
40	0.28	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25
41	0.25	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23
42	0.23	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20	0.20
43	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18	0.18
44	0.16	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15
45	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13
46	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10
47	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08	0.08
48	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05
49	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03
50	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

1. If the value of Q_U or Q_L does not correspond to a value in the table, use the next lower value.
2. If Q_U or Q_L are negative values, P_U or P_L is equal to 100 minus the table value for P_U or P_L.

Quality Factor Determination

Determine individual quality factors, QF_{QC_i} , using percent defective = $P_U + P_L$ and:

Quality Factor	Quality Factors												
	Maximum Allowable Percent Defective ($P_U + P_L$)												
	Sample Size (n)												
	5	6	7	8	9	10-11	12-14	15-17	18-22	23-29	30-42	43-66	>66
1.05				0	0	0	0	0	0	0	0	0	0
1.04			0	1	3	5	4	4	4	3	3	3	3
1.03		0	2	4	6	8	7	7	6	5	5	4	4
1.02		1	3	6	9	11	10	9	8	7	7	6	6
1.01	0	2	5	8	11	13	12	11	10	9	8	8	7
1.00	22	20	18	17	16	15	14	13	12	11	10	9	8
0.99	24	22	20	19	18	17	16	15	14	13	11	10	9
0.98	26	24	22	21	20	19	18	16	15	14	13	12	10
0.97	28	26	24	23	22	21	19	18	17	16	14	13	12
0.96	30	28	26	25	24	22	21	19	18	17	16	14	13
0.95	32	29	28	26	25	24	22	21	20	18	17	16	14
0.94	33	31	29	28	27	25	24	22	21	20	18	17	15
0.93	35	33	31	29	28	27	25	24	22	21	20	18	16
0.92	37	34	32	31	30	28	27	25	24	22	21	19	18
0.91	38	36	34	32	31	30	28	26	25	24	22	21	19
0.90	39	37	35	34	33	31	29	28	26	25	23	22	20
0.89	41	38	37	35	34	32	31	29	28	26	25	23	21
0.88	42	40	38	36	35	34	32	30	29	27	26	24	22
0.87	43	41	39	38	37	35	33	32	30	29	27	25	23
0.86	45	42	41	39	38	36	34	33	31	30	28	26	24
0.85	46	44	42	40	39	38	36	34	33	31	29	28	25
0.84	47	45	43	42	40	39	37	35	34	32	30	29	27
0.83	49	46	44	43	42	40	38	36	35	33	31	30	28
0.82	50	47	46	44	43	41	39	38	36	34	33	31	29
0.81	51	49	47	45	44	42	41	39	37	36	34	32	30
0.80	52	50	48	46	45	44	42	40	38	37	35	33	31
0.79	54	51	49	48	46	45	43	41	39	38	36	34	32
0.78	55	52	50	49	48	46	44	42	41	39	37	35	33
0.77	56	54	52	50	49	47	45	43	42	40	38	36	34
0.76	57	55	53	51	50	48	46	44	43	41	39	37	35
0.75	58	56	54	52	51	49	47	46	44	42	40	38	36
Reject	60	57	55	53	52	51	48	47	45	43	41	40	37
	61	58	56	55	53	52	50	48	46	44	43	41	38
	62	59	57	56	54	53	51	49	47	45	44	42	39
	63	61	58	57	55	54	52	50	48	47	45	43	40
	64	62	60	58	57	55	53	51	49	48	46	44	41

Reject Values Greater Than Those Shown Above

Notes:

- To obtain a quality factor when the estimated percent outside specification limits from table, "Upper Quality Index Q_U or Lower Quality Index Q_L ," does not correspond to a value in the table, use the next larger value.

Compute the composite of single quality factors, QF_C , for a lot using:

$$QF_C = \sum_{i=1}^5 w_i QF_{QC_i}$$

where:

- QF_C = the composite quality factor for the lot rounded to 2 decimal places.
- QF_{QC_i} = the quality factor for the individual quality characteristic.
- w = the weighting factor listed in the table HMA Acceptance – QC / QA.

$i =$ the quality characteristic index number in the table HMA Acceptance – QC / QA.

39-4.04 ENGINEER'S QUALITY ASSURANCE

39-4.04A General

The Engineer assures quality by:

1. Reviewing mix designs and proposed JMF
2. Inspecting procedures
3. Conducting oversight of quality control inspection and records
4. Verification sampling and testing during production and paving

39-4.04B Verification Sampling And Testing

General

The Engineer samples:

1. Aggregate to verify gradation
2. HMA to verify asphalt binder content

Verification

For aggregate gradation and asphalt binder content, the ratio of verification testing frequency to the minimum quality control testing frequency is 1:5. The Engineer performs at least 3 verification tests per lot.

Using the t-test, the Engineer compares quality control test results for aggregate gradation and asphalt binder content with corresponding verification test results. The Engineer uses the average and standard deviation of up to 20 sequential sublots for the comparison. When there are less than 20 sequential sublots, the Engineer uses the maximum number of sequential sublots available. The 21st sublot becomes the 1st sublot ($n = 1$) in the next lot.

The t-value for a group of test data is computed as follows:

$$t = \frac{|\bar{X}_c - \bar{X}_v|}{S_p \sqrt{\frac{1}{n_c} + \frac{1}{n_v}}} \quad \text{and} \quad S_p^2 = \frac{S_c^2(n_c - 1) + S_v^2(n_v - 1)}{n_c + n_v - 2}$$

where:

$n_c =$ Number of quality control tests (2 minimum, 20 maximum).

$n_v =$ Number of verification tests (minimum of 1 required).

$\bar{X}_c =$ Mean of quality control tests.

$\bar{X}_v =$ Mean of verification tests.

$S_p =$ Pooled standard deviation (When $n_v = 1$, $S_p = S_c$).

$S_c =$ Standard deviation of quality control tests.

$S_v =$ Standard deviation of verification tests (when $n_v > 1$).

The comparison of quality control test results and the verification test results is at a level of significance of $\alpha = 0.025$. The Engineer computes t and compares it to the critical t-value, t_{crit} , from:

Critical T-Value

Degrees of freedom (n_c+n_v-2)	t_{crit} (for $\alpha = 0.025$)	Degrees of freedom (n_c+n_v-2)	t_{crit} (for $\alpha = 0.025$)
1	24.452	18	2.445
2	6.205	19	2.433
3	4.177	20	2.423
4	3.495	21	2.414
5	3.163	22	2.405
6	2.969	23	2.398
7	2.841	24	2.391
8	2.752	25	2.385
9	2.685	26	2.379
10	2.634	27	2.373
11	2.593	28	2.368
12	2.560	29	2.364
13	2.533	30	2.360
14	2.510	40	2.329
15	2.490	60	2.299
16	2.473	120	2.270
17	2.458	∞	2.241

If the t-value computed is less than or equal to t_{crit} , quality control test results are verified.

If the t-value computed is greater than t_{crit} and both \bar{X}_v and \bar{X}_c comply with acceptance specifications, the quality control tests are verified. You may continue to produce and place HMA with the following allowable differences:

1. $|\bar{X}_v - \bar{X}_c| \leq 1.0$ percent for any grading
2. $|\bar{X}_v - \bar{X}_c| \leq 0.1$ percent for asphalt binder content

If the t-value computed is greater than t_{crit} and the $|\bar{X}_v - \bar{X}_c|$ for grading and asphalt binder content are greater than the allowable differences, quality control test results are not verified and:

1. The Engineer notifies you in writing.
2. You and the Engineer must investigate why the difference exist.
3. If the reason for the difference cannot be found and corrected, the Engineer's test results are used for acceptance and pay.

39-4.05 ENGINEER'S ACCEPTANCE

39-4.05A Testing

The Engineer samples for acceptance testing and tests for:

HMA Acceptance – QC / QA

Index (i)	Quality Characteristic				Weight -ing Factor (w)	Test Method	HMA Type		
							A	B	RHMA-G
	Aggregate gradation ^a					CT 202	JMF ± Tolerance ^c		
	Sieve	3/4"	1/2"	3/8"					
1	1/2"	X ^b	--	--	0.05				
1	3/8"	--	X	--	0.05				
1	No. 4	--	--	X	0.05				
2	No. 8	X	X	X	0.10				
3	No. 200	X	X	X	0.15				
4	Asphalt binder content (%)				0.30	CT 379 or 382	JMF ± 0.45	JMF ± 0.45	JMF ± 0.5
5	Percent of maximum theoretical density (%) ^{d, e}				0.40	CT 375	92 – 96	92 – 96	91 – 96
	Sand equivalent (min.) ^f					CT 217	47	42	47
	Stabilometer value (min.) ^{f, g}					CT 366			
	No. 4 and 3/8" gradings						30	30	--
	1/2" and 3/4" gradings						37	35	23
	Air voids content (%) ^{f, h}					CT 367	4 ± 2	4 ± 2	Specification ± 2
	Percent of crushed particles coarse aggregate (% min.)					CT 205			
	One fractured face						90	25	--
	Two fractured faces						70	--	90
	Fine aggregate (% min.) (Passing No. 4 sieve and retained on No. 8 sieve.)								
	One fractured face						70	20	70
	HMA moisture content (% max.)					CT 226 or CT 370	1.0	1.0	1.0
	Los Angeles Rattler (% max.)					CT 211			
	Loss at 100 rev.						12	--	12
	Loss at 500 rev.						45	50	45
	Fine aggregate angularity (% min.)					AASHTO T 304, Method A	Report only	Report only	Report only
	Flat and elongated particle (% max. by mass @ 5:1)					ASTM D 4791	Report only	Report only	Report only
	Voids in mineral aggregate (% min.) ⁱ								(Note j)
	No. 4 grading						17.0	17.0	--
	3/8" grading					LP-2	15.0	15.0	--
	1/2" grading						14.0	14.0	18.0 - 23.0
	3/4" grading						13.0	13.0	18.0 - 23.0
	Voids filled with asphalt (%) ⁱ								
	No. 4 grading					LP-3	76.0 - 80.0	76.0 - 80.0	Report only
	3/8" grading						73.0 - 76.0	73.0 - 76.0	
	1/2" grading						65.0 - 75.0	65.0 - 75.0	
	3/4" grading						65.0 - 75.0	65.0 - 75.0	
	Dust proportion ⁱ					LP-4			
	No. 4 and 3/8" gradings						0.9 - 2.0	0.9 – 2.0	Report only
	1/2" and 3/4" gradings						0.6 - 1.3	0.6 – 1.3	

	Smoothness		Section 39-1.12	12-foot straight-edge, must-grind, and PI ₀	12-foot straight-edge, must-grind, and PI ₀	12-foot straight-edge, must-grind, and PI ₀
	Asphalt binder		Various	Section 92	Section 92	Section 92
	Asphalt rubber binder		Various	--	--	Section 92-1.02(C) and Section 39-1.02D
	Asphalt modifier		Various	--	--	Section 39-1.02D
	Crumb rubber modifier		Various	--	--	Section 39-1.02D

Notes:

^a The Engineer determines combined aggregate gradations containing RAP under Laboratory Procedure LP-9.

^b "X" denotes the sieves the Engineer considers for the specified aggregate gradation.

^c The tolerances must comply with the allowable tolerances in Section 39-1.02E, "Aggregate."

^d The Engineer determines percent of maximum theoretical density if the total paved thickness is at least 0.15 foot under California Test 375 except the Engineer uses:

1. California Test 308, Method A, to determine in-place density of each core instead of using the nuclear gauge in Part 4, "Determining In-Place Density By The Nuclear Density Device."
2. California Test 309 to determine maximum theoretical density instead of calculating test maximum density in Part 5, "Determining Test Maximum Density."

^e The Engineer determines maximum theoretical density (California Test 309) at the frequency specified for Test Maximum Density under California Test 375, Part 5.D.

^f The Engineer reports the average of 3 tests from a single split sample.

^g Modify California Test 304, Part 2.B.2.c: "After compaction in the mechanical compactor, cool to 140 °F ± 5 °F by allowing the briquettes to cool at room temperature for 0.5 hour, then place the briquettes in the oven at 140 °F for a minimum of 2 hours and not more than 3 hours."

^h The Engineer determines the bulk specific gravity of each lab-compacted briquette under California Test 308, Method A, and theoretical maximum specific gravity under California Test 309.

ⁱ Report only if the adjustment for asphalt binder content target value is less than ± 0.3 percent from OBC.

^j Voids in mineral aggregate for RHMA-G must be within this range.

The Engineer determines the percent of maximum theoretical density from the average density of 3 cores you take from every 750 tons of production or part thereof divided by the maximum theoretical density.

If the total paved thickness is at least 0.15 foot and any layer is less than 0.15 foot, the Engineer determines the percent of maximum theoretical density from cores taken from the final layer measured the full depth of the total paved HMA thickness.

The Engineer stops production and terminates a lot if:

1. The lot's composite quality factor, Q_{FC}, or an individual quality factor, Q_{FQCi} for i = 3, 4, or 5, is below 0.90 determined under Section 39-4.03F, "Statistical Evaluation"
2. An individual quality factor, Q_{FQCi} for i = 1 or 2, is below 0.75
3. Quality characteristics for which a quality factor, Q_{FQCi}, is not determined has 2 consecutive acceptance or quality control tests not in compliance with the specifications

For any single quality characteristic for which a quality factor, Q_{FQCi}, is not determined, except smoothness, if 2 consecutive acceptance test results do not comply with specifications:

1. Stop production.
2. Take corrective action.
3. In the Engineer's presence, take samples and split each sample into 4 parts. Test 1 part for compliance with the specifications and submit 3 parts to the Engineer. The Engineer tests 1 part for compliance with the specifications and reserves and stores 2 parts.

4. Demonstrate compliance with the specifications before resuming production and placement on the State highway.

39-4.05B Statistical Evaluation, Determination Of Quality Factors And Acceptance

Statistical Evaluation and Determination of Quality Factors

To determine the individual quality factor, QF_{QCi} , for any quality factor $i = 1$ through 5 or a lot's composite quality factor, QF_C , for acceptance and payment adjustment, the Engineer uses the evaluation specifications under Section 39-4.03F, "Statistical Evaluation," and:

1. Verified quality control test results for aggregate gradation
2. Verified quality control test results for asphalt binder content
3. The Engineer's test results for percent of maximum theoretical density

Lot Acceptance Based on Quality Factors

The Engineer accepts a lot based on the quality factors determined for aggregate gradation and asphalt binder content, QF_{QCi} for $i = 1$ through 4, using the total number of verified quality control test result values and the total percent defective ($P_U + P_L$).

The Engineer accepts a lot based on the quality factor determined for maximum theoretical density, QF_{QC5} , using the total number of test result values from cores and the total percent defective ($P_U + P_L$).

The Engineer calculates the quality factor for the lot, QF_C , which is a composite of weighted individual quality factors, QF_{QCi} , determined for each quality characteristic in the table "HMA Acceptance – QC / QA" in Section 39-4.05A, "Testing."

The Engineer accepts a lot based on quality factors if:

1. The current composite quality factor, QF_C , is 0.90 or greater
2. Each individual quality factor, QF_{QCi} for $i = 3, 4,$ and 5 , is 0.90 or greater
3. Each individual quality factor, QF_{QCi} for $i = 1$ and 2 , is 0.75 or greater

No single quality characteristic test may represent more than the smaller of 750 tons or 1 day's production.

Payment Adjustment

If a lot is accepted, the Engineer adjusts payment with the following formula:

$$PA = \sum_{i=1}^n HMA CP * w_i * [QF_{QCi} * (HMATT - WHMATT) + WHMATT] - (HMA CP * HMATT)$$

where:

PA =	Payment adjustment rounded to 2 decimal places.
HMA CP =	HMA contract price.
HMATT =	HMA total tons represented in the lot.
WHMATT _i =	Total tons of waived quality characteristic HMA.
QF _{QCi} =	Running quality factor for the individual quality characteristic. QF _{QCi} for $i = 1$ through 4 must be from verified Contractor's QC results. QF _{QC5} must be determined from the Engineer's results on cores taken for percent of maximum theoretical density determination.
w =	Weighting factor listed in the HMA acceptance table.
i =	Quality characteristic index number in the HMA acceptance table.

If the payment adjustment is a negative value, the Engineer deducts this amount from payment. If the payment adjustment is a positive value, the Engineer adds this amount to payment.

The 21st subplot becomes the 1st subplot ($n = 1$) in the next lot. When the 21st sequential subplot becomes the 1st subplot, the previous 20 sequential sublots become a lot for which the Engineer determines a quality factor. The Engineer uses this quality factor to pay for the HMA in the lot. If the next lot consists of less than 8 sublots, these sublots must be added to the previous lot for quality factor determination using 21 to 27 sublots.

39-4.05C Dispute Resolution

For a lot, if you or the Engineer dispute any quality factor, QF_{QCi} , or verification test result, every subplot in that lot must be retested.

Referee tests must be performed under the specifications for acceptance testing.

Any quality factor, QF_{QC_i} , must be determined using the referee tests.

For any quality factor, QF_{QC_i} , for $i = 1$ through 5, dispute resolution:

1. If the difference between the quality factors for QF_{QC_i} using the referee test result and the disputed test result is less than or equal to 0.01, the original test result is correct.
2. If the difference between the quality factor for QF_{QC_i} using the referee test result and the disputed test result is more than 0.01, the quality factor determined from the referee tests supersedes the previously determined quality factor.

39-5 MEASUREMENT AND PAYMENT

39-5.01 MEASUREMENT

The contract item for HMA is measured by weight. The weight of each HMA mixture designated in the Engineer's Estimate must be the combined mixture weight.

If tack coat, asphalt binder, and asphaltic emulsion are paid with separate contract items, their contract items are measured under Section 92, "Asphalts," or Section 94, "Asphaltic Emulsions," as the case may be.

If recorded batch weights are printed automatically, the contract item for HMA is measured by using the printed batch weights, provided:

1. Total aggregate and supplemental fine aggregate weight per batch is printed. If supplemental fine aggregate is weighed cumulatively with the aggregate, the total aggregate batch weight must include the supplemental fine aggregate weight.
2. Total asphalt binder weight per batch is printed.
3. Each truckload's zero tolerance weight is printed before weighing the first batch and after weighing the last batch.
4. Time, date, mix number, load number and truck identification is correlated with a load slip.
5. A copy of the recorded batch weights is certified by a licensed weighmaster and submitted to the Engineer.

The contract item for placing HMA dike is measured by the linear foot along the completed length. The contract item for placing HMA in miscellaneous areas is measured as the in-place compacted area in square yards. In addition to the quantities measured on a linear foot or square yard basis, the HMA for dike and miscellaneous areas are measured by weight.

The contract item for shoulder rumble strips is measured by the station along each shoulder on which the rumble strips are constructed without deductions for gaps between indentations.

The contract item for geosynthetic pavement interlayer is measured by the square yard for the actual pavement area covered.

39-5.02 PAYMENT

The contract prices paid per ton for hot mix asphalt as designated in the Engineer's Estimate include full compensation for furnishing all labor, materials, tools, equipment, and incidentals for doing all the work involved in constructing hot mix asphalt, complete in place, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

If HMA is specified to comply with Section 39-4, "Quality Control / Quality Assurance," the Engineer adjusts payment under that section.

Full compensation for the Quality Control Plan and prepaving conference is included in the contract prices paid per ton for hot mix asphalt as designated in the Engineer's Estimate and no additional compensation will be allowed therefor.

Full compensation for performing and submitting mix designs and for Contractor sampling, testing, inspection, testing facilities, and preparation and submittal of results is included in the contract prices paid per ton for HMA as designated in the Engineer's Estimate and no additional compensation will be allowed therefor.

Full compensation for reclaimed asphalt pavement is included in the contract prices paid per ton for HMA as designated in the Engineer's Estimate and no additional compensation will be allowed therefor.

The contract price paid per ton for hot mix asphalt (leveling) includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals for doing all the work involved in hot mix asphalt (leveling), complete in place, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

The contract prices paid per station for rumble strips as designated in the Engineer's Estimate include full compensation for furnishing all labor, materials, tools, equipment, and incidentals for doing all the work involved in constructing rumble strips, including fog seal coat, complete in place, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer.

The State will pay for HMA dike at the contract price per linear foot for place HMA dike and by the ton for HMA. The contract prices paid per linear foot for place hot mix asphalt dike as designated in the Engineer's Estimate include full compensation for furnishing all labor, tools, equipment, and incidentals, and for doing all the work involved in placing HMA

In Section 51-1.12F in the 6th paragraph, replace the table with:

Movement Rating (MR)	Seal Type
MR ≤ 1 inch	Type A or Type B
1 inch < MR ≤ 2 inches	Type B
2 inches < MR ≤ 4 inches	Joint Seal Assembly (Strip Seal)
MR > 4 inches	Joint Seal Assembly (Modular Unit) or Seismic Joint

In Section 51-1.12F(3)(a) replace the 1st and 2nd paragraphs with:

The sealant must consist of a 2-component silicone sealant that will withstand up to ±50 percent movement. Silicone sealants must be tested under California Test 435 and must comply with the following:

Specification	Requirement
Modulus at 150 percent elongation	8-75 psi
Recovery	21/32 inch max.
Notch Test	Notched or loss of bond 1/4 inch, max.
Water Resistance	Notched or loss of bond 1/4 inch, max.
Ultraviolet Exposure ASTM Designation: G 154, Table X2.1, Cycle 2.	No more than slight checking or cracking.
Cone Penetration	4.5-12.0 mm

In Section 51-1.12F(3)(a) delete the 3rd and 8th paragraphs.

In Section 51-1.12F(3)(a) replace the 10th paragraph with:

A Certificate of Compliance accompanied by a certified test report must be furnished for each batch of silicone sealant in conformance with the provisions in Section 6-1.07, "Certificates of Compliance."

In Section 51-1.12F(3)(b) replace the 2nd paragraph with:

The preformed elastomeric joint seal must conform to the requirements in ASTM D 2628 and the following:

1. The seal must consist of a multichannel, nonporous, homogeneous material furnished in a finished extruded form.
2. The minimum depth of the seal measured at the contact surface must be at least 95 percent of the minimum uncompressed width of the seal as designated by the manufacturer.
3. When tested in conformance with the requirements in California Test 673 for Type B seals, joint seals must provide a movement rating (MR) of not less than that shown on the plans.
4. The top and bottom edges of the joint seal must maintain continuous contact with the sides of the groove over the entire range of joint movement.
5. The seal must be furnished full length for each joint with no more than 1 shop splice in any 60-foot length of seal.
6. The Contractor must demonstrate the adequacy of the procedures to be used in the work before installing seals in the joints.
7. One field splice per joint may be made at locations and by methods approved by the Engineer. The seals are to be manufactured full length for the intended joint, then cut at the approved splice section and rematched before splicing. The Contractor must submit splicing details prepared by the joint seal manufacturer for approval before beginning splicing work.
8. Shop splices and field splices must have no visible offset of exterior surfaces and must show no evidence of bond failure.
9. At all open ends of the seal that would admit water or debris, each cell must be filled to a depth of 3 inches with commercial quality open cell polyurethane foam or closed by other means subject to approval by the Engineer.

In Section 51-1.12F(3)(b) replace the 7th paragraph with:

The joint seal must be installed full length for each joint with equipment that does not twist or distort the seal, elongate the seal longitudinally, or otherwise cause damage to the seal or to the concrete forming the groove.

In Section 51-1.12F(3)(b) in the 11th paragraph, replace the 1st sentence with:

Samples of the prefabricated joint seals, not less than 3 feet in length, will be taken by the Engineer from each lot of material.

In Section 51-1.12H(1) in the 6th paragraph, replace the 4th and 5th sentences with:

Each ply of fabric shall have a breaking strength of not less than 800 pounds per inch of width in each thread direction when 3" x 36" samples are tested on split drum grips. The bond between double plies shall have a minimum peel strength of 20 pounds per inch.

In Section 51-1.12H(1) in the 8th paragraph in the table, replace the hardness (Type A) requirements with:

Hardness (Type A)	D 2240 with 2kg mass.	55 ±5
-------------------	-----------------------	-------

In Section 51-1.12H(2) in the 1st paragraph in item A, replace the 1st and 2nd sentences with:

The bearings shall consist of alternating steel laminates and internal elastomer laminates with top and bottom elastomer covers. Steel laminates shall have a nominal thickness of 0.075 inch (14 gage).

In Section 51-1.135 replace the 1st paragraph with:

Mortar shall be composed of cementitious material, sand, and water proportioned and mixed as specified in this Section 51-1.135.

In Section 51-1.135 replace the 3rd paragraph with:

The proportion of cementitious material to sand, measured by volume, shall be 1 to 2 unless otherwise specified.

In Section 51-1.17 in 4th paragraph, replace the 3rd sentence with:

The surfaces shall have a profile trace showing no high points in excess of 0.25 inch, and the portions of the surfaces within the traveled way shall have a profile count of 5 or less in any 100 foot section.

Add:

51-1.17A Deck Crack Treatment

The Contractor shall use all means necessary to minimize the development of shrinkage cracks.

The Contractor shall remove all equipment and materials from the deck and clean the surface as necessary for the Engineer to measure the surface crack intensity. Surface crack intensity will be determined by the Engineer after completion of concrete cure, before prestressing, and before the release of falsework. In any 500 square foot portion of deck within the limits of the new concrete deck, should the intensity of cracking be such that there are more than 16 feet of cracks whose width at any location exceeds 0.02 inch, the deck shall be treated with methacrylate resin. The area of deck to be treated shall have a width that extends for the entire width of new deck inside the concrete barriers and a length that extends at least 5 feet beyond the furthest single continuous crack outside the 500 square foot portion, measured from where that crack exceeds 0.02 inch in width, as determined by the Engineer.

Deck crack treatment shall include furnishing, testing, and application of methacrylate resin and sand. If grinding is required, deck treatment shall take place before grinding.

51-1.17A(1) Submittals

Before starting deck treatment, the Contractor shall submit plans in conformance with Section 5-1.02, "Plans and Working Drawings," for the following:

1. Public safety plan for the use of methacrylate resin
2. Placement plan for the construction operation

The plans shall identify materials, equipment, and methods to be used.
 The public safety plan for the use of methacrylate resin shall include details for the following:

1. Shipping
2. Storage
3. Handling
4. Disposal of residual methacrylate resin and the containers

The placement plan for construction shall include the following:

1. Schedule of deck treatment for each bridge. The schedule shall be consistent with "Maintaining Traffic" of the special provisions and shall include time for the Engineer to perform California Test 342.
2. Methods and materials to be used, including the following:
 - 2.1. Description of equipment for applying the resin
 - 2.2. Description of equipment for applying the sand
 - 2.3. Gel time range and final cure time for the resin

If the measures proposed in the safety plan are inadequate to provide for public safety associated with the use of methacrylate resin, the Engineer will reject the plan and direct the Contractor to revise the plan. Directions for revisions will be in writing and include detailed comments. The Engineer will notify the Contractor of the approval or rejection of a submitted or revised plan within 15 days of receipt of that plan.

In the event the Engineer fails to complete the review within the time allowed, and if, in the opinion of the Engineer, completion of the work is delayed or interfered with by reason of the Engineer's delay in completing the review, the Contractor will be compensated for any resulting loss, and an extension of time will be granted, in the same manner as provided for in Section 8-1.09, "Right of Way Delays."

51-1.17A(2) Materials

Before using methacrylate resin, a Material Safety Data Sheet shall be submitted for each shipment of resin.

Methacrylate resin shall be low odor and have a high molecular weight. Before adding initiator, the resin shall have a maximum volatile content of 30 percent when tested in conformance with the requirements in ASTM Designation: D 2369, and shall conform to the following:

PROPERTY	REQUIREMENT	TEST METHOD
* Viscosity	25 cP, maximum, (Brookfield RVT with UL adaptor, 50 RPM at 77°F	ASTM D 2196
* Specific Gravity	0.90 minimum, at 77°F	ASTM D 1475
* Flash Point	180°F, minimum	ASTM D 3278
* Vapor Pressure	1.0 mm Hg, maximum, at 77°F	ASTM D 323
Tack-free Time	400 minutes, maximum at 25°C	Specimen prepared per California Test 551
PCC Saturated Surface-Dry Bond Strength	3.5 MPa, minimum at 24 hours and 21±1°C	California Test 551
* Test shall be performed before adding initiator.		

51-1.17A(3) Testing

The Contractor shall allow 20 days for sampling and testing by the Engineer of the methacrylate resin before proposed use. If bulk resin is to be used, the Contractor shall notify the Engineer in writing at least 15 days before the delivery of the bulk resin to the job site. Bulk resin is any resin stored in containers in excess of 55 gallons.

Before starting production treatment, the Contractor shall treat a test area of approximately 500 square feet that is within the project limits and at a location approved by the Engineer. When available the test area shall be outside of the traveled way. Weather and pavement conditions during the test treatment shall be similar to those expected on the deck. Equipment used for testing shall be similar to those used for deck treating operations.

During test and production deck treatment, test tiles shall be used to evaluate the resin cure time. The Contractor shall coat at least one 4" x 4" commercial quality smooth glazed tile for each batch of methacrylate resin. The coated tile shall be placed adjacent to the corresponding treated area. Sand shall not be applied to the test tiles.

The acceptance criteria for a treated area is as follows:

1. The test tiles are dry to the touch.
2. The treated deck surface is tack free (non-oily).
3. The sand cover adheres and resists brushing by hand.
4. Excess sand has been removed by vacuuming or sweeping.
5. The coefficient of friction is at least 0.35 when tested in conformance with California Test 342.

Deck treatment on the test area shall demonstrate that the methods and materials meet the acceptance criteria and that the production work will be completed within the specified time for maintaining traffic.

If a test or production area fails to meet the acceptance criteria, as determined by the Engineer, the treatment will be rejected, and the treatment shall be removed and replaced until the area complies with the acceptance criteria.

51-1.17A(4) Construction

Equipment shall be fitted with suitable traps, filters, drip pans, or other devices as necessary to prevent oil or other deleterious material from being deposited on the deck.

Before deck treatment with methacrylate resin, the bridge deck surface shall be cleaned by abrasive blasting, and all loose material shall be blown from visible cracks using high-pressure air. Concrete curing seals shall be cleaned from the deck surface to be treated, and the deck shall be dry when blast cleaning is performed. If the deck surface becomes contaminated at any time before placing the resin, the deck surface shall be cleaned by abrasive blasting.

Where abrasive blasting is being performed within 10 feet of a lane occupied by public traffic, the residue including dust shall be removed immediately after contact between the abrasive and the surface being treated. The removal shall be by a vacuum attachment operating concurrently with the abrasive blasting operation.

A compatible promoter/initiator system shall be capable of providing the resin gel time range shown on the placement plan. Gel time shall be adjusted to compensate for the changes in temperature throughout treatment application.

Resin shall be applied by machine and by using a two-part resin system with a promoted resin for one part and an initiated resin for the other part. This two-part resin system shall be combined at equal volumes to the spray bars through separate positive displacement pumps. Combining of the 2 components shall be by either static in-line mixers or by external intersecting spray fans. The pump pressure at the spray bars shall not be great enough to cause appreciable atomization of the resin. Compressed air shall not be used to produce the spray. A shroud shall be used to enclose the spray bar apparatus.

At the Contractor's option, manual application may be used. For manual application, (1) the quantity of resin mixed with promoter and initiator shall be limited to 5 gallons at a time, and (2) the resin shall be distributed by squeegees and brooms within 10 minutes after application.

The Contractor shall apply methacrylate resin only to the specified area. Barriers, railing, joints, and drainage facilities shall be adequately protected to prevent contamination by the treatment material. Contaminated items shall be repaired at the Contractor's expense.

The relative humidity shall be less than 90 percent at the time of treatment. The prepared area shall be dry and the surface temperature shall be at least 50 °F and not more than 100 °F when the resin is applied. The rate of application of promoted/initiated resin shall be approximately 90 square feet per gallon; the exact rate shall be determined by the Engineer.

The deck surfaces to be treated shall be completely covered with resin so the resin penetrates and fills all cracks. The resin shall be applied within 5 minutes after complete mixing. A significant increase in viscosity shall be cause for rejection. Excess material shall be redistributed by squeegees or brooms within 10 minutes after application. For textured deck surfaces, including grooved surfaces, excess material shall be removed from the texture indentations.

After the resin has been applied, at least 20 minutes shall elapse before applying sand. The sand shall be commercial quality dry blast sand. At least 95 percent of the sand shall pass the No. 8 sieve and at least 95 percent shall be retained on the No. 20 sieve. The sand shall be applied at a rate of approximately 2 pounds per square yard or until refusal as determined by the Engineer.

Traffic will not be allowed on treated areas until the acceptance criteria has been met as determined by the Engineer.

SECTION 75 MISCELLANEOUS METAL

(Issued 01-18-08)

In Section 75-1.03 replace the 13th paragraph with:

Concrete anchorage devices shall be mechanical expansion or resin capsule types installed in drilled holes or cast-in-place insert types. The anchorage devices shall be selected from the Department's Pre-Qualified Products List at:

http://www.dot.ca.gov/hq/esc/approved_products_list

The anchorage devices shall be a complete system, including threaded studs, hex nuts, and cut washers. Thread dimensions for externally threaded concrete anchorage devices prior to zinc coating, shall conform to the requirements in ANSI Standard: B1.1 having Class 2A tolerances or ANSI Standard: B1.13M having Grade 6g tolerances. Thread dimensions for internally threaded concrete anchorage devices shall conform to the requirements in ASTM A 563.

In Section 75-1.03 replace the 18th paragraph with:

Mechanical expansion anchors shall, when installed in accordance with the manufacturer's instructions and these specifications and tested in conformance with the requirements in California Test 681, withstand the application of a sustained tension test load of at least the following values for at least 48 hours with a movement not greater than 0.035 inch:

Stud Diameter (inches)	Sustained Tension Test Load (pounds)
*3/4	5,000
5/8	4,100
1/2	3,200
3/8	2,100
1/4	1,000

* Maximum stud diameter permitted for mechanical expansion anchors.

Resin capsule anchors shall, when installed in accordance with the manufacturer's instructions and these specifications and tested in conformance with the requirements in California Test 681, withstand the application of a sustained tension test load of at least the following values for at least 48 hours with a movement not greater than 0.010 inch:

Stud Diameter (inches)	Sustained Tension Test Load (pounds)
1-1/4	31,000
1	17,900
7/8	14,400
3/4	5,000
5/8	4,100
1/2	3,200
3/8	2,100
1/4	1,000

At least 25 days before use, the Contractor shall submit one sample of each resin capsule anchor per lot to the Transportation Laboratory for testing. A lot of resin capsule anchors is 100 units, or fraction thereof, of the same brand and product name.

In Section 75-1.03 replace the 20th paragraph with:

The Pre-Qualified Products List for concrete anchorage devices has been developed from data previously furnished by suppliers or manufacturers for each type and size. Approval of additional anchorage device types and sizes is contingent upon the Contractor submitting to the Engineer one sample of each type of concrete anchorage device, manufacturer's

SECTION 83 RAILINGS AND BARRIERS

(Issued 09-19-08)

In Section 83-1.02 replace the 7th paragraph with:

Mortar shall conform to the provisions in Section 51-1.135, "Mortar," and shall consist of one part by volume of cementitious material and 3 parts of clean sand.

In Section 83-1.02B in the 24th paragraph in the 8th subparagraph, replace the 1st sentence with:

Anchor cable shall be 3/4 inch preformed, 6 x 19, wire strand core or independent wire rope core (IWRC), galvanized in conformance with the requirements in Federal Specification RR-W-410, right regular lay, manufactured of improved plow steel with a minimum breaking strength of 23 tons.

In Section 83-1.02E in the 6th paragraph, replace the 2nd sentence with:

Cable shall be galvanized in conformance with the requirements in Federal Specification RR-W-410.

In Section 83-1.02I replace the 5th paragraph with:

Where shown on the plans, cables used in the frame shall be 5/16 inch in diameter, wire rope, with a minimum breaking strength of 5,000 pounds and shall be galvanized in conformance with the requirements in Federal Specification RR-W-410.

In Section 83-1.02I replace the 14th paragraph with:

Chain link fabric shall be either 11-gage Type I zinc-coated fabric conforming to the requirements in AASHTO M 181 or 11-gage Type IV polyvinyl chloride (PVC) coated fabric conforming to the requirements in Federal Specification RR-F-191/1.

In Section 83-2.02D(1) replace the 5th paragraph with:

When concrete barriers are to be constructed on existing structures, the dowels shall be bonded in holes drilled in the existing concrete. Drilling of holes and bonding of dowels shall conform to the following:

1. The bonding materials shall be either magnesium phosphate concrete, modified high alumina based concrete or portland cement based concrete. Magnesium phosphate concrete shall be either single component (water activated) or dual component (with a prepackaged liquid activator). Modified high alumina based concrete and portland cement based concrete shall be water activated. Bonding materials shall conform to the following requirements:

Property	Test Method	Requirements
Compressive Strength		
at 3 hours, MPa	California Test 551	21 min.
at 24 hours, MPa	California Test 551	35 min.
Flexure Strength		
at 24 hours, MPa	California Test 551	3.5 min.
Bond Strength: at 24 hours		
SSD Concrete, MPa	California Test 551	2.1 min.
Dry Concrete, MPa	California Test 551	2.8 min.
Water Absorption, %	California Test 551	10 max.
Abrasion Resistance		
at 24 hours, grams	California Test 550	25 max.
Drying Shrinkage at 4 days, %	ASTM Designation: C 596	0.13 max.
Soluble Chlorides by weight, %	California Test 422	0.05 max.
Water Soluble Sulfates by weight, %	California Test 417	0.25 max.

In Section 86-2.08A in the table, replace the traffic signal controller cabinet requirements with:

Traffic Signal	Ungrounded Circuit Conductor	Blk	None	CON-1	6
Controller Cabinet	Grounded Circuit Conductor	Wht	None	CON-2	6

In Section 86-4.06 in the 1st paragraph, replace the 1st sentence with:

Message symbols for pedestrian signal faces shall be white WALKING PERSON and Portland orange UPRAISED HAND conforming to the requirements in the Institute of Transportation Engineers Standards: "Pedestrian Traffic Control Signal Indications" and the "California MUTCD."

In Section 86-4.07 in the 10th paragraph, replace the 2nd sentence with:

The color of "UPRAISED HAND" shall be Portland orange conforming to the requirements of the Institute of Transportation Engineers Standards: "Pedestrian Traffic Control Signal Indications" and the "California MUTCD."

In Section 86-5.01A(5) in section "Elastomeric Sealant" in the 1st paragraph, replace the 2nd sentence with:

Sealant shall be suitable for use in both hot mix asphalt and portland cement concrete.

In Section 86-5.01A(5) in section "Asphatic Emulsion Sealant" in the 1st paragraph, replace the 1st sentence with:

Asphatic emulsion sealant shall conform to the requirements in State Specification 8040-41A-15 and shall be used only for filling slots in hot mix asphalt pavement.

In Section 86-5.01A(5) in section "Hot-Melt Rubberized Asphalt Sealant" in the 1st paragraph, replace the 3rd sentence with:

Sealant shall be suitable for use in both hot mix asphalt and portland cement concrete.

In Section 86-5.01A(5) in section "Hot-Melt Rubberized Asphalt Sealant," replace the 10th paragraph with:

If hot mix asphalt surfacing is to be placed, the loop conductors shall be installed prior to placing the uppermost layer of hot mix asphalt. The conductors shall be installed, as shown on the plans, in the compacted layer of hot mix asphalt immediately below the uppermost layer. Installation details shall be as shown on the plans, except the sealant shall fill the slot flush to the surface.

In Section 86-5.01D replace the 1st paragraph with:

When a foundation for a pressure-sensitive vehicle detector is to be removed, the hole left by removing the detector frame and foundation shall be filled with minor concrete, except the roadway surface shall be reconstructed with material to match existing surfacing. Minor concrete shall conform to the provisions in Section 90-10, "Minor Concrete," except that the concrete shall contain not less than 420 pounds of cementitious material per cubic yard for hot mix asphalt surfaced roadways and not less than 590 pounds of cementitious material per cubic yard for portland cement concrete surfaced roadways.

In Section 86-8.01 replace the 1st paragraph with:

The contract lump sum price or prices paid for signal, ramp metering, flashing beacon, lighting, sign illumination, traffic monitoring station, highway advisory radio systems, closed circuit television systems, or combinations thereof; for modifying or removing those systems; for temporary systems; or the lump sum or unit prices paid for various units of those systems; or the lump sum or per foot price paid for conduit of the various sizes, types and installation methods listed in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in furnishing and installing, modifying, or removing the systems, combinations or units thereof, as shown on the plans, as specified in these specifications and the special provisions, and as directed by the Engineer, including any necessary pull boxes (except when the type required is shown as a separate contract item); excavation and backfill; concrete foundations (except when shown as a separate contract item); pedestrian barricades; furnishing and installing illuminated street name signs; installing sign panels on pedestrian barricades, on flashing beacon standards, and on traffic signal mast

structurally adequate, the concrete may remain in place and the Contractor shall pay to the State \$0.25 for each pound of cementitious material, portland cement, or supplementary cementitious material that is less than the minimum required. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract. The deductions will not be made unless the difference between the contents required and those actually provided exceeds the batching tolerances permitted by Section 90-5, "Proportioning." No deductions will be made based on the results of California Test 518.

The requirements of the preceding paragraph shall not apply to minor concrete or commercial quality concrete.

90-2 MATERIALS

90-2.01 CEMENTITIOUS MATERIALS

Unless otherwise specified, cementitious material shall be either a combination of Type II or Type V portland cement and a supplementary cementitious material, or a blended cement.

Cementitious materials used in cast-in-place concrete for exposed surfaces of like elements of a structure shall be from the same sources and of the same proportions.

Cementitious materials shall be protected from moisture until used. Sacked cementitious materials shall be piled to permit access for tallying, inspecting, and identifying each shipment.

Facilities shall be provided to ensure that cementitious materials meeting this Section 90-2.01 are kept separate from other cementitious materials. Sampling cementitious materials shall be in conformance with California Test 125.

The Contractor shall furnish a Certificate of Compliance for cementitious materials in conformance with the provisions in Section 6-1.07, "Certificates of Compliance." The Certificate of Compliance shall indicate the source by name and location (including country, state, and city). If cementitious material is delivered directly to the job site, the Certificate of Compliance shall be signed by the cementitious material supplier. If the cementitious material is used in ready-mixed concrete or in precast concrete products purchased as such by the Contractor, the Certificate of Compliance shall be signed by the manufacturer of the concrete or product.

90-2.01A Cement

Portland cement shall conform to the requirements in ASTM Designation: C 150 except, using a 10-sample moving average, limestone shall not exceed 2.5 percent. The C_3S content of Type II cement shall not exceed 65 percent.

Blended cement shall conform to the requirements for Portland Blast-Furnace Slag, Cement Type IS (MS) or Portland-Pozzolan Cement, Type IP (MS) in AASHTO Designation: M 240 and shall be comprised of an intimate and uniform blend of Type II or Type V cement and supplementary cementitious material in an amount conforming to the requirements in Section 90-2.01C, "Required Use of Supplementary Cementitious Materials."

In addition, blended cement, Type II portland cement, and Type V portland cement shall conform to the following requirements:

- A. The cement shall not contain more than 0.60-percent by mass of alkalis, calculated as the percentage of Na_2O plus 0.658 times the percentage of K_2O , when determined by methods as required in AASHTO Designation: T 105;
- B. The autoclave expansion shall not exceed 0.50-percent; and
- C. Mortar, containing the cement to be used and Ottawa sand, when tested in conformance with California Test 527, shall not expand in water more than 0.010-percent and shall not contract in air more than 0.048-percent, except that when cement is to be used for precast prestressed concrete piling, precast prestressed concrete members, or steam cured concrete products, the mortar shall not contract in air more than 0.053-percent.

Type III portland cement shall be used only as specified in the special provisions or with the approval of the Engineer. Type III portland cement shall conform to the additional requirements listed above for Type II portland cement, except when tested in conformance with California Test 527, mortar containing Type III portland cement shall not contract in air more than 0.075-percent.

90-2.01B Supplementary Cementitious Materials (SCM)

Fly ash shall conform to the requirements in AASHTO Designation: M 295, Class F, and the following:

- A. Calcium oxide content shall not exceed 10 percent.
- B. The available alkali, as sodium oxide equivalent, shall not exceed 1.5 percent when determined in conformance with the requirements in ASTM Designation: C 311 or the total alkali, as sodium oxide equivalent, shall not exceed 5.0 percent when determined in conformance with the requirements in AASHTO Designation: T 105.
- C. Commingling of fly ash from different sources at uncontrolled ratios is permissible only if the following criteria are satisfied:

1. Sources of fly ash to be commingled shall be on the approved list of materials for use in concrete.
2. Testing of the commingled product is the responsibility of the fly ash supplier.
3. Each fly ash's running average of density shall not differ from any other by more than 0.01-pound per cubic inch at the time of commingling.
4. Each fly ash's running average of loss on ignition shall not differ from any other by more than one percent at the time of commingling.
5. The final product of commingled fly ash shall conform to the requirement in AASHTO Designation: M 295.

Raw or calcined natural pozzolans shall conform to the requirements in AASHTO Designation: M 295, Class N and the following requirements:

- A. Calcium oxide content shall not exceed 10 percent.
- B. The available alkali, as sodium oxide equivalent, shall not exceed 1.5 percent when determined in conformance with the requirements in ASTM Designation: C 311 or the total alkali, as sodium oxide equivalent, shall not exceed 5.0 percent when determined in conformance with the requirements in AASHTO Designation: T 105.

Ground Granulated Blast Furnace Slag (GGBFS) shall conform to the requirements in AASHTO Designation: M 302, Grade 100 or Grade 120.

Silica Fume shall conform to the requirements of AASHTO Designation: M 307, with reduction in mortar expansion of 80 percent, minimum, using the cement from the proposed mix design.

90-2.01C Required Use Of Supplementary Cementitious Materials

The amount of portland cement and SCM used in portland cement concrete shall conform to the minimum cementitious material content provisions in Section 90-1.01, "Description," or Section 90-4.05, "Optional Use of Chemical Admixtures," and the following:

- A. If a blended cement conforming to the provisions in Section 90-2.01A, "Cement," is used, the minimum amount of SCM incorporated into the cement shall conform to the provisions in this Section 90-2.01C.
- B. Fly ash or natural pozzolan, silica fume, or GGBFS shall not be used with Type IP or Type IS cements.

Use of SCMs shall conform to the following:

- A. If fly ash or natural pozzolan is used:
 1. The minimum amount of portland cement shall not be less than 75 percent by weight of the specified minimum cementitious material content.
 2. The minimum amount of fly ash or natural pozzolan shall be:
 - a. Fifteen percent by weight of the total amount of cementitious material if the calcium oxide content of fly ash or natural pozzolan is equal to or less than 2 percent by weight;
 - b. Twenty-five percent by weight of the total amount of cementitious material if the calcium oxide content of fly ash or natural pozzolan is greater than 2 percent by weight.
 3. The total amount of fly ash or natural pozzolan shall not exceed 35 percent by weight of the total amount of cementitious material to be used in the mix. If Section 90-1.01, "Description," specifies a maximum cementitious material content in pounds per cubic yard, the total weight of portland cement and fly ash or natural pozzolan per cubic yard shall not exceed the specified maximum cementitious material content.
- B. If silica fume is used:
 1. The amount of silica fume shall not be less than 10 percent by weight of the total amount of cementitious material.
 2. The amount of portland cement shall not be less than 75 percent by weight of the specified minimum cementitious material content.
 3. If Section 90-1.01, "Description," specifies a maximum cementitious material content in pounds per cubic yard, the total weight of portland cement and silica fume per cubic yard shall not exceed the specified maximum cementitious material content.
- C. If GGBFS is used:

1. The minimum amount of GGBFS shall be either:
 - a. Forty percent of the total cementitious material to be used, if the aggregates used in the concrete are on the Department's list of "Approved Aggregates For Use in Concrete with Reduced Fly Ash."
 - b. No less than 50 percent.
2. The amount of GGBFS shall not exceed 60 percent by weight of the total amount of cementitious materials to be used.

90-2.02 AGGREGATES

Aggregates shall be free from deleterious coatings, clay balls, roots, bark, sticks, rags, and other extraneous material.

The Contractor shall provide safe and suitable facilities, including necessary splitting devices for obtaining samples of aggregates, in conformance with California Test 125.

Aggregates shall be of such character that it will be possible to produce workable concrete within the limits of water content provided in Section 90-6.06, "Amount of Water and Penetration."

Aggregates shall have not more than 10 percent loss when tested for soundness in conformance with the requirements in California Test 214. The soundness requirement for fine aggregate will be waived, provided that the durability index, D_f , of the fine aggregate is 60 or greater when tested for durability in conformance with California Test 229.

If the results of any one or more of the Cleanness Value, Sand Equivalent, or aggregate grading tests do not meet the requirements specified for "Operating Range" but all meet the "Contract Compliance" requirements, the placement of concrete shall be suspended at the completion of the current pour until tests or other information indicate that the next material to be used in the work will comply with the requirements specified for "Operating Range."

If the results of either or both the Cleanness Value and coarse aggregate grading tests do not meet the requirements specified for "Contract Compliance," the concrete that is represented by the tests shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place, and the Contractor shall pay to the State \$3.50 per cubic yard for paving concrete and \$5.50 per cubic yard for all other concrete for the concrete represented by these tests and left in place. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract.

If the results of either or both the Sand Equivalent and fine aggregate grading tests do not meet the requirements specified for "Contract Compliance," the concrete which is represented by the tests shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place, and the Contractor shall pay to the State \$3.50 per cubic yard for paving concrete and \$5.50 per cubic yard for all other concrete for the concrete represented by these tests and left in place. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract.

The 2 preceding paragraphs apply individually to the "Contract Compliance" requirements for coarse aggregate and fine aggregate. When both coarse aggregate and fine aggregate do not conform to the "Contract Compliance" requirements, both paragraphs shall apply. The payments specified in those paragraphs are in addition to any payments made in conformance with the provisions in Section 90-1.01, "Description."

No single Cleanness Value, Sand Equivalent, or aggregate grading test shall represent more than 300 cubic yards of concrete or one day's pour, whichever is smaller.

When the source of an aggregate is changed, the Contractor shall adjust the mix proportions and submit in writing to the Engineer a copy of the mix design before using the aggregates.

90-2.02A Coarse Aggregate

Coarse aggregate shall consist of gravel, crushed gravel, crushed rock, reclaimed aggregate, crushed air-cooled iron blast furnace slag or combinations thereof. Crushed air-cooled blast furnace slag shall not be used in reinforced or prestressed concrete.

Reclaimed aggregate is aggregate that has been recovered from plastic concrete by washing away the cementitious material. Reclaimed aggregate shall conform to all aggregate requirements.

Coarse aggregate shall conform to the following quality requirements:

Tests	California Test	Requirements
Loss in Los Angeles Rattler (after 500 revolutions)	211	45% max.
Cleanness Value		
Operating Range	227	75 min.
Contract Compliance	227	71 min.

In lieu of the above Cleanness Value requirements, a Cleanness Value "Operating Range" limit of 71, minimum, and a Cleanness Value "Contract Compliance" limit of 68, minimum, will be used to determine the acceptability of the coarse aggregate if the Contractor furnishes a Certificate of Compliance, as provided in Section 6-1.07, "Certificates of Compliance," certifying that:

- A. Coarse aggregate sampled at the completion of processing at the aggregate production plant had a Cleanness Value of not less than 82 when tested in conformance with the requirements in California Test 227; and
- B. Prequalification tests performed in conformance with the requirements in California Test 549 indicated that the aggregate would develop a relative strength of not less than 95 percent and would have a relative shrinkage not greater than 105 percent, based on concrete.

90-2.02B Fine Aggregate

Fine aggregate shall consist of natural sand, manufactured sand produced from larger aggregate or a combination thereof. Manufactured sand shall be well graded.

Fine aggregate shall conform to the following quality requirements:

Test	California Test	Requirements
Organic Impurities	213	Satisfactory ^a
Mortar Strengths Relative to Ottawa Sand	515	95%, min.
Sand Equivalent:		
Operating Range	217	75, min.
Contract Compliance	217	71, min.

- a Fine aggregate developing a color darker than the reference standard color solution may be accepted if it is determined by the Engineer, from mortar strength tests, that a darker color is acceptable.

In lieu of the above Sand Equivalent requirements, a Sand Equivalent "Operating Range" limit of 71, minimum, and a Sand Equivalent "Contract Compliance" limit of 68, minimum, will be used to determine the acceptability of the fine aggregate if the Contractor furnishes a Certificate of Compliance, as provided in Section 6-1.07, "Certificates of Compliance," certifying that:

- A. Fine aggregate sampled at the completion of processing at the aggregate production plant had a Sand Equivalent value of not less than 82 when tested by California Test 217; and
- B. Prequalification tests performed in conformance with California Test 549 indicated that the aggregate would develop a relative strength of not less than 95 percent and would have a relative shrinkage not greater than 105 percent, based on concrete.

90-2.03 WATER

In conventionally reinforced concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 1,000 parts per million of chlorides as Cl, when tested in conformance with California Test 422, nor more than 1,300 parts per million of sulfates as SO₄, when tested in conformance with California Test 417. In prestressed concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 650 parts per million of chlorides as Cl, when tested in conformance with California Test 422, nor more than 1,300 parts per million of sulfates as SO₄, when tested in conformance with California Test 417. In no case shall the water contain an amount of impurities that will cause either: 1) a change in the setting time of cement of more than 25 percent when tested in conformance with the requirements in ASTM Designation: C 191 or ASTM Designation: C 266 or 2) a reduction in the compressive strength of mortar at 14 days of more than 5 percent, when tested in conformance with the requirements in ASTM Designation: C 109, when compared to the results obtained with distilled water or deionized water, tested in conformance with the requirements in ASTM Designation: C 109.

In nonreinforced concrete work, the water for curing, for washing aggregates and for mixing shall be free from oil and shall not contain more than 2,000 parts per million of chlorides as Cl, when tested in conformance with California Test 422, or more than 1,500 parts per million of sulfates as SO₄, when tested in conformance with California Test 417.

In addition to the above provisions, water for curing concrete shall not contain impurities in a sufficient amount to cause discoloration of the concrete or produce etching of the surface.

Water reclaimed from mixer wash-out operations may be used in mixing concrete. The water shall not contain coloring agents or more than 300 parts per million of alkalis (Na₂O + 0.658 K₂O) as determined on the filtrate. The specific gravity of the water shall not exceed 1.03 and shall not vary more than ±0.010 during a day's operations.

90-2.04 Admixture Materials

Admixture materials shall conform to the requirements in the following ASTM Designations:

- A. Chemical Admixtures—ASTM Designation: C 494.
- B. Air-entraining Admixtures—ASTM Designation: C 260.

90-3 AGGREGATE GRADINGS

90-3.01 GENERAL

Before beginning concrete work, the Contractor shall submit in writing to the Engineer the gradation of the primary aggregate nominal sizes that the Contractor proposes to furnish. If a primary coarse aggregate or the fine aggregate is separated into 2 or more sizes, the proposed gradation shall consist of the gradation for each individual size, and the proposed proportions of each individual size, combined mathematically to indicate one proposed gradation. The proposed gradation shall meet the grading requirements shown in the table in this section, and shall show the percentage passing each of the sieve sizes used in determining the end result.

The Engineer may waive, in writing, the gradation requirements in this Section 90-3.01 and in Sections 90-3.02, "Coarse Aggregate Grading," 90-3.03, "Fine Aggregate Grading," and 90-3.04, "Combined Aggregate Gradings," if, in the Engineer's opinion, furnishing the gradation is not necessary for the type or amount of concrete work to be constructed.

Gradations proposed by the Contractor shall be within the following percentage passing limits:

Primary Aggregate Nominal Size	Sieve Size	Limits of Proposed Gradation
1 1/2" x 3/4"	1"	19 - 41
1" x No. 4	3/4"	52 - 85
1" x No. 4	3/8"	15 - 38
1/2" x No. 4	3/8"	40 - 78
3/8" x No. 8	3/8"	50 - 85
Fine Aggregate	No. 16	55 - 75
Fine Aggregate	No. 30	34 - 46
Fine Aggregate	No. 50	16 - 29

Should the Contractor change the source of supply, the Contractor shall submit in writing to the Engineer the new gradations before their intended use.

90-3.02 COARSE AGGREGATE GRADING

The grading requirements for coarse aggregates are shown in the following table for each size of coarse aggregate:

Sieve Sizes	Percentage Passing Primary Aggregate Nominal Sizes							
	1 1/2" x 3/4"		1" x No. 4		1/2" x No. 4		3/8" x No. 8	
	Operating Range	Contract Compliance	Operating Range	Contract Compliance	Operating Range	Contract Compliance	Operating Range	Contract Compliance
2"	100	100	—	—	—	—	—	—
1 1/2"	88 - 100	85 - 100	100	100	—	—	—	—
1"	X ±18	X ±25	88 - 100	86 - 100	—	—	—	—
3/4"	0 - 17	0 - 20	X ±15	X ±22	100	100	—	—
1/2"	—	—	—	—	82 - 100	80 - 100	100	100
3/8"	0 - 7	0 - 9	X ±15	X ±22	X ±15	X ±22	X ±15	X ±20
No. 4	—	—	0 - 16	0 - 18	0 - 15	0 - 18	0 - 25	0 - 28
No. 8	—	—	0 - 6	0 - 7	0 - 6	0 - 7	0 - 6	0 - 7

In the above table, the symbol X is the gradation that the Contractor proposes to furnish for the specific sieve size as provided in Section 90-3.01, "General."

Coarse aggregate for the 1 1/2 inch, maximum, combined aggregate grading as provided in Section 90-3.04, "Combined Aggregate Gradings," shall be furnished in 2 or more primary aggregate nominal sizes. Each primary aggregate nominal size may be separated into 2 sizes and stored separately, provided that the combined material conforms to the grading requirements for that particular primary aggregate nominal size.

When the one inch, maximum, combined aggregate grading as provided in Section 90-3.04, "Combined Aggregate Gradings," is to be used, the coarse aggregate may be separated into 2 sizes and stored separately, provided that the combined material shall conform to the grading requirements for the 1" x No. 4 primary aggregate nominal size.

90-3.03 FINE AGGREGATE GRADING

Fine aggregate shall be graded within the following limits:

Sieve Sizes	Percentage Passing	
	Operating Range	Contract Compliance
3/8"	100	100
No. 4	95 - 100	93 - 100
No. 8	65 - 95	61 - 99
No. 16	X ±10	X ±13
No. 30	X ±9	X ±12
No. 50	X ±6	X ±9
No. 100	2 - 12	1 - 15
No. 200	0 - 8	0 - 10

In the above table, the symbol X is the gradation that the Contractor proposes to furnish for the specific sieve size as provided in Section 90-3.01, "General."

In addition to the above required grading analysis, the distribution of the fine aggregate sizes shall be such that the difference between the total percentage passing the No. 16 sieve and the total percentage passing the No. 30 sieve shall be between 10 and 40, and the difference between the percentage passing the No. 30 and No. 50 sieves shall be between 10 and 40.

Fine aggregate may be separated into 2 or more sizes and stored separately, provided that the combined material conforms to the grading requirements specified in this Section 90-3.03.

90-3.04 COMBINED AGGREGATE GRADINGS

Combined aggregate grading limits shall be used only for the design of concrete mixes. Concrete mixes shall be designed so that aggregates are combined in proportions that shall produce a mixture within the grading limits for combined aggregates as specified herein.

The combined aggregate grading, except when otherwise specified in these specifications or the special provisions, shall be either the 1 1/2 inch, maximum grading, or the 1 inch, maximum grading, at the option of the Contractor.

Grading Limits of Combined Aggregates

Sieve Sizes	Percentage Passing			
	1 1/2" Max.	1" Max.	1/2" Max.	3/8" Max.
2"	100	—	—	—
1 1/2"	90 - 100	100	—	—
1"	50 - 86	90 - 100	—	—
3/4"	45 - 75	55 - 100	100	—
1/2"	—	—	90 - 100	100
3/8"	38 - 55	45 - 75	55 - 86	50 - 100
No. 4	30 - 45	35 - 60	45 - 63	45 - 63
No. 8	23 - 38	27 - 45	35 - 49	35 - 49
No. 16	17 - 33	20 - 35	25 - 37	25 - 37
No. 30	10 - 22	12 - 25	15 - 25	15 - 25
No. 50	4 - 10	5 - 15	5 - 15	5 - 15
No. 100	1 - 6	1 - 8	1 - 8	1 - 8
No. 200	0 - 3	0 - 4	0 - 4	0 - 4

Changes from one grading to another shall not be made during the progress of the work unless permitted by the Engineer.

90-4 ADMIXTURES

90-4.01 GENERAL

Admixtures used in portland cement concrete shall conform to and be used in conformance with the provisions in this Section 90-4 and the special provisions. Admixtures shall be used when specified or ordered by the Engineer and may be used at the Contractor's option as provided herein.

Chemical admixtures and air-entraining admixtures containing chlorides as Cl in excess of one percent by weight of admixture, as determined by California Test 415, shall not be used.

Admixtures shall be uniform in properties throughout their use in the work. Should it be found that an admixture as furnished is not uniform in properties, its use shall be discontinued.

If more than one admixture is used, the admixtures shall be compatible with each other so that the desirable effects of all admixtures used will be realized.

Chemical admixtures shall be used in conformance with the manufacturer's written recommendations.

90-4.02 MATERIALS

Admixture materials shall conform to the provisions in Section 90-2.04, "Admixture Materials."

90-4.03 ADMIXTURE APPROVAL

No admixture brand shall be used in the work unless it is on the Department's current list of approved brands for the type of admixture involved.

Admixture brands will be considered for addition to the approved list if the manufacturer of the admixture submits to the Transportation Laboratory a sample of the admixture accompanied by certified test results demonstrating that the admixture complies with the requirements in the appropriate ASTM Designation and these specifications. The sample shall be sufficient to permit performance of all required tests. Approval of admixture brands will be dependent upon a determination as to compliance with the requirements, based on the certified test results submitted, together with tests the Department may elect to perform.

If the Contractor proposes to use an admixture of a brand and type on the current list of approved admixture brands, the Contractor shall furnish a Certificate of Compliance from the manufacturer, as provided in Section 6-1.07, "Certificates of Compliance," certifying that the admixture furnished is the same as that previously approved. If a previously approved admixture is not accompanied by a Certificate of Compliance, the admixture shall not be used in the work until the Engineer has had sufficient time to make the appropriate tests and has approved the admixture for use. The Engineer may take samples for testing at any time, whether or not the admixture has been accompanied by a Certificate of Compliance.

90-4.04 REQUIRED USE OF CHEMICAL ADMIXTURES

If the use of a chemical admixture is specified, the admixture shall be used at the dosage specified, except that if no dosage is specified, the admixture shall be used at the dosage normally recommended by the manufacturer of the admixture.

90-4.05 OPTIONAL USE OF CHEMICAL ADMIXTURES

The Contractor may use Type A or F, water-reducing; Type B, retarding; or Type D or G, water-reducing and retarding admixtures as described in ASTM Designation: C 494 to conserve cementitious material or to facilitate any concrete construction application subject to the following conditions:

- A. If a water-reducing admixture or a water-reducing and retarding admixture is used, the cementitious material content specified or ordered may be reduced by a maximum of 5 percent by weight, except that the resultant cementitious material content shall be not less than 505 pounds per cubic yard; and
- B. When a reduction in cementitious material content is made, the dosage of admixture used shall be the dosage used in determining approval of the admixture.

Unless otherwise specified, a Type C accelerating chemical admixture conforming to the requirements in ASTM Designation: C 494, may be used in portland cement concrete. Inclusion in the mix design submitted for approval will not be required provided that the admixture is added to counteract changing conditions that contribute to delayed setting of the portland cement concrete, and the use or change in dosage of the admixture is approved in writing by the Engineer.

90-4.06 REQUIRED USE OF AIR-ENTRAINING ADMIXTURES

When air-entrainment is specified or ordered by the Engineer, the air-entraining admixture shall be used in amounts to produce a concrete having the specified air content as determined by California Test 504.

90-4.07 OPTIONAL USE OF AIR-ENTRAINING ADMIXTURES

When air-entrainment has not been specified or ordered by the Engineer, the Contractor will be permitted to use an air-entraining admixture to facilitate the use of any construction procedure or equipment provided that the average air content, as determined by California Test 504, of 3 successive tests does not exceed 4 percent, and no single test value exceeds 5.5 percent. If the Contractor elects to use an air-entraining admixture in concrete for pavement, the Contractor shall so indicate at the time the Contractor designates the source of aggregate.

90-4.08 BLANK

90-4.09 BLANK

90-4.10 PROPORTIONING AND DISPENSING LIQUID ADMIXTURES

Chemical admixtures and air-entraining admixtures shall be dispensed in liquid form. Dispensers for liquid admixtures shall have sufficient capacity to measure at one time the prescribed quantity required for each batch of concrete. Each dispenser shall include a graduated measuring unit into which liquid admixtures are measured to within ± 5 percent of the prescribed quantity for each batch. Dispensers shall be located and maintained so that the graduations can be accurately read from the point at which proportioning operations are controlled to permit a visual check of batching accuracy prior to discharge. Each measuring unit shall be clearly marked for the type and quantity of admixture.

Each liquid admixture dispensing system shall be equipped with a sampling device consisting of a valve located in a safe and readily accessible position such that a sample of the admixture may be withdrawn slowly by the Engineer.

If more than one liquid admixture is used in the concrete mix, each liquid admixture shall have a separate measuring unit and shall be dispensed by injecting equipment located in such a manner that the admixtures are not mixed at high concentrations and do not interfere with the effectiveness of each other. When air-entraining admixtures are used in conjunction with other liquid admixtures, the air-entraining admixture shall be the first to be incorporated into the mix, unless it is demonstrated that a different sequence improves performance.

When automatic proportioning devices are required for concrete pavement, dispensers for liquid admixtures shall operate automatically with the batching control equipment. The dispensers shall be equipped with an automatic warning system in good operating condition that will provide a visible or audible signal at the point at which proportioning operations are controlled when the quantity of admixture measured for each batch of concrete varies from the preselected dosage by more than 5 percent, or when the entire contents of the measuring unit are not emptied from the dispenser into each batch of concrete.

Unless liquid admixtures are added to premeasured water for the batch, their discharge into the batch shall be arranged to flow into the stream of water so that the admixtures are well dispersed throughout the batch, except that air-entraining admixtures may be dispensed directly into moist sand in the batching bins provided that adequate control of the air content of the concrete can be maintained.

Liquid admixtures requiring dosages greater than one-half gallon per cubic yard shall be considered to be water when determining the total amount of free water as specified in Section 90-6.06, "Amount of Water and Penetration."

90-4.11 BLANK

90-5 PROPORTIONING

90-5.01 STORAGE OF AGGREGATES

Aggregates shall be stored or stockpiled in such a manner that separation of coarse and fine particles of each size shall be avoided and the various sizes shall not become intermixed before proportioning.

Aggregates shall be stored or stockpiled and handled in a manner that prevent contamination by foreign materials. In addition, storage of aggregates at batching or mixing facilities that are erected subsequent to the award of the contract and that furnish concrete to the project shall conform to the following:

- A. Intermingling of the different sizes of aggregates shall be positively prevented. The Contractor shall take the necessary measures to prevent intermingling. The preventive measures may include, but are not necessarily limited to, physical separation of stockpiles or construction of bulkheads of adequate length and height; and
- B. Contamination of aggregates by contact with the ground shall be positively prevented. The Contractor shall take the necessary measures to prevent contamination. The preventive measures shall include, but are not necessarily limited to, placing aggregates on wooden platforms or on hardened surfaces consisting of portland cement concrete, asphalt concrete, or cement treated material.

In placing aggregates in storage or in moving the aggregates from storage to the weigh hopper of the batching plant, any method that may cause segregation, degradation, or the combining of materials of different gradings that will result in any size of aggregate at the weigh hopper failing to meet the grading requirements, shall be discontinued. Any method of handling aggregates that results in excessive breakage of particles shall be discontinued. The use of suitable devices to reduce impact of falling aggregates may be required by the Engineer.

90-5.02 PROPORTIONING DEVICES

Weighing, measuring, or metering devices used for proportioning materials shall conform to the requirements in Section 9-1.01, "Measurement of Quantities," and this Section 90-5.02. In addition, automatic weighing systems shall comply with the requirements for automatic proportioning devices in Section 90-5.03A, "Proportioning for Pavement." Automatic devices shall be automatic to the extent that the only manual operation required for proportioning the aggregates, cement, and supplementary cementitious material for one batch of concrete is a single operation of a switch or starter.

Proportioning devices shall be tested as frequently as the Engineer may deem necessary to ensure their accuracy.

Weighing equipment shall be insulated against vibration or movement of other operating equipment in the plant. When the plant is in operation, the weight of each batch of material shall not vary from the weight designated by the Engineer by more than the tolerances specified herein.

Equipment for cumulative weighing of aggregate shall have a zero tolerance of ± 0.5 percent of the designated total batch weight of the aggregate. For systems with individual weigh hoppers for the various sizes of aggregate, the zero tolerance shall be ± 0.5 percent of the individual batch weight designated for each size of aggregate. Equipment for cumulative weighing of cement and supplementary cementitious material shall have a zero tolerance of ± 0.5 percent of the designated total batch weight of the cement and supplementary cementitious material. Equipment for weighing cement or supplementary cementitious material separately shall have a zero tolerance of ± 0.5 percent of their designated individual batch weights. Equipment for measuring water shall have a zero tolerance of ± 0.5 percent of its designated weight or volume.

The weight indicated for any batch of material shall not vary from the preselected scale setting by more than the following:

- A. Aggregate weighed cumulatively shall be within 1.0 percent of the designated total batch weight of the aggregate. Aggregates weighed individually shall be within 1.5 percent of their respective designated batch weights; and
- B. Cement shall be 99 to 102 percent of its designated batch weight. When weighed individually, supplementary cementitious material shall be 99 to 102 percent of its designated batch weight. When supplementary cementitious material and cement are permitted to be weighed cumulatively, cement shall be weighed first to 99 to 102 percent of its designated batch weight, and the total for cement and supplementary cementitious material shall be 99 to 102 percent of the sum of their designated batch weights; and
- C. Water shall be within 1.5 percent of its designated weight or volume.

Each scale graduation shall be approximately 0.001 of the total capacity of the scale. The capacity of scales for weighing cement, supplementary cementitious material, or cement plus supplementary cementitious material and aggregates shall not exceed that of commercially available scales having single graduations indicating a weight not exceeding the maximum

permissible weight variation above, except that no scale shall be required having a capacity of less than 1,000 pounds, with one pound graduations.

90-5.03 PROPORTIONING

Proportioning shall consist of dividing the aggregates into the specified sizes, each stored in a separate bin, and combining them with cementitious material and water as provided in these specifications. Aggregates shall be proportioned by weight.

At the time of batching, aggregates shall have been dried or drained sufficiently to result in a stable moisture content such that no visible separation of water from aggregate will take place during transportation from the proportioning plant to the point of mixing. In no event shall the free moisture content of the fine aggregate at the time of batching exceed 8 percent of its saturated, surface-dry weight.

Should separate supplies of aggregate material of the same size group, but of different moisture content or specific gravity or surface characteristics affecting workability, be available at the proportioning plant, withdrawals shall be made from one supply exclusively and the materials therein completely exhausted before starting upon another.

Bulk Type IP (MS) cement shall be weighed in an individual hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer.

Bulk cement and supplementary cementitious material may be weighed in separate, individual weigh hoppers or may be weighed in the same weigh hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer. If the cement and supplementary cementitious material are weighed cumulatively, the cement shall be weighed first.

If cement and supplementary cementitious material are weighed in separate weigh hoppers, the weigh systems for the proportioning of the aggregate, the cement, and the supplementary cementitious material shall be individual and distinct from all other weigh systems. Each weigh system shall be equipped with a hopper, a lever system, and an indicator to constitute an individual and independent material-weighing device. The cement and the supplementary cementitious material shall be discharged into the mixer simultaneously with the aggregate.

The scales and weigh hoppers for bulk weighing cement, supplementary cementitious material, or cement plus supplementary cementitious material shall be separate and distinct from the aggregate weighing equipment.

For batches of one cubic yard or more, the batching equipment shall conform to one of the following combinations:

- A. Separate boxes and separate scale and indicator for weighing each size of aggregate.
- B. Single box and scale indicator for all aggregates.
- C. Single box or separate boxes and automatic weighing mechanism for all aggregates.

In order to check the accuracy of batch weights, the gross weight and tare weight of batch trucks, truck mixers, truck agitators, and non-agitating hauling equipment shall be determined when ordered by the Engineer. The equipment shall be weighed on scales designated by the Engineer.

90-5.03A Proportioning For Pavement

Aggregates and bulk supplementary cementitious material for use in pavement shall be proportioned by weight by means of automatic proportioning devices of approved type conforming to these specifications.

The Contractor shall install and maintain in operating condition an electronically actuated moisture meter that will indicate, on a readily visible scale, changes in the moisture content of the fine aggregate as it is batched within a sensitivity of 0.5 percent by weight of the fine aggregate.

The batching of cement, supplementary cementitious material, or cement plus supplementary cementitious material and aggregate shall be interlocked so that a new batch cannot be started until all weigh hoppers are empty, the proportioning devices are within zero tolerance, and the discharge gates are closed. The interlock shall permit no part of the batch to be discharged until all aggregate hoppers and the cement and supplementary cementitious material hoppers or the cement plus supplementary cementitious material hopper are charged with weights that are within the tolerances specified in Section 90-5.02, "Proportioning Devices."

If interlocks are required for cement and supplementary cementitious material charging mechanisms and cement and supplementary cementitious material are weighed cumulatively, their charging mechanisms shall be interlocked to prevent the introduction of mineral admixture until the weight of cement in the cement weigh hopper is within the tolerances specified in Section 90-5.02, "Proportioning Devices."

If concrete is completely mixed in stationary paving mixers, the supplementary cementitious materials shall be weighed in a separate weigh hopper and the supplementary cementitious material and cement shall be introduced simultaneously into the mixer proportionately with the aggregate. If the Contractor provides certification that the stationary mixer is capable of mixing the cement, supplementary cementitious material, aggregates, and water uniformly before discharge, weighing the supplementary cementitious material cumulatively with the cement is permitted. Certification shall contain the following:

- A. Test results for 2 compressive strength test cylinders of concrete taken within the first one-third and 2 compressive strength test cylinders of concrete taken within the last one-third of the concrete discharged from a single batch from the stationary paving mixer. Strength tests and cylinder preparation will be in conformance with the provisions of Section 90-9, "Compressive Strength";
- B. Calculations demonstrating that the difference in the averages of 2 compressive strengths taken in the first one-third is no greater than 7.5 percent different than the averages of 2 compressive strengths taken in the last one-third of the concrete discharged from a single batch from the stationary paving mixer. Strength tests and cylinder preparation will be in conformance with the provisions of Section 90-9, "Compressive Strength;" and
- C. The mixer rotation speed and time of mixing before discharge that are required to produce a mix that meets the requirements above.

The discharge gate on the cement and supplementary cementitious material hoppers or the cement plus supplementary cementitious material hopper shall be designed to permit regulating the flow of cement, supplementary cementitious material, or cement plus supplementary cementitious material into the aggregate as directed by the Engineer.

If separate weigh boxes are used for each size of aggregate, the discharge gates shall permit regulating the flow of each size of aggregate as directed by the Engineer.

Material discharged from the several bins shall be controlled by gates or by mechanical conveyors. The means of withdrawal from the several bins, and of discharge from the weigh box, shall be interlocked so that not more than one bin can discharge at a time, and so that the weigh box cannot be tripped until the required quantity from each of the several bins has been deposited therein. Should a separate weigh box be used for each size of aggregate, all may be operated and discharged simultaneously.

If the discharge from the several bins is controlled by gates, each gate shall be actuated automatically so that the required mass is discharged into the weigh box, after which the gate shall automatically close and lock.

The automatic weighing system shall be designed so that all proportions required may be set on the weighing controller at the same time.

90-6 MIXING AND TRANSPORTING

90-6.01 GENERAL

Concrete shall be mixed in mechanically operated mixers, except that when permitted by the Engineer, batches not exceeding 1/3 cubic yard may be mixed by hand methods in conformance with the provisions in Section 90-6.05, "Hand-Mixing."

Equipment having components made of aluminum or magnesium alloys that would have contact with plastic concrete during mixing, transporting, or pumping of portland cement concrete shall not be used.

Concrete shall be homogeneous and thoroughly mixed, and there shall be no lumps or evidence of undispersed cementitious material.

Uniformity of concrete mixtures will be determined by differences in penetration as determined by California Test 533, or slump as determined by ASTM Designation: C 143, and by variations in the proportion of coarse aggregate as determined by California Test 529.

When the mix design specifies a penetration value, the difference in penetration, determined by comparing penetration tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed 1/2-inch. When the mix design specifies a slump value, the difference in slump, determined by comparing slump tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed the values given in the table below. Variation in the proportion of coarse aggregate will be determined by comparing the results of tests of 2 samples of mixed concrete from the same batch or truck mixer load and the difference between the 2 results shall not exceed 170 pounds per cubic yard of concrete.

Average Slump	Maximum Permissible Difference
Less than 4"	1"
4" to 6"	1 1/2"
Greater than 6" to 9"	2"

The Contractor shall furnish samples of the freshly mixed concrete and provide satisfactory facilities for obtaining the samples.

90-6.02 MACHINE MIXING

Concrete mixers may be of the revolving drum or the revolving blade type, and the mixing drum or blades shall be operated uniformly at the mixing speed recommended by the manufacturer. Mixers and agitators that have an accumulation of hard concrete or mortar shall not be used.

The temperature of mixed concrete, immediately before placing, shall be not less than 50° F or more than 90° F. Aggregates and water shall be heated or cooled as necessary to produce concrete within these temperature limits. Neither aggregates nor mixing water shall be heated to exceed 150° F. If ice is used to cool the concrete, discharge of the mixer will not be permitted until all ice is melted.

The batch shall be so charged into the mixer that some water will enter in advance of cementitious materials and aggregates. All water shall be in the drum by the end of the first one-fourth of the specified mixing time.

Cementitious materials shall be batched and charged into the mixer by means that will not result either in loss of cementitious materials due to the effect of wind, in accumulation of cementitious materials on surfaces of conveyors or hoppers, or in other conditions that reduce or vary the required quantity of cementitious material in the concrete mixture.

Paving and stationary mixers shall be operated with an automatic timing device. The timing device and discharge mechanism shall be interlocked so that during normal operation no part of the batch will be discharged until the specified mixing time has elapsed.

The total elapsed time between the intermingling of damp aggregates and all cementitious materials and the start of mixing shall not exceed 30 minutes.

The size of batch shall not exceed the manufacturer's guaranteed capacity.

When producing concrete for pavement or base, suitable batch counters shall be installed and maintained in good operating condition at job site batching plants and stationary mixers. The batch counters shall indicate the exact number of batches proportioned and mixed.

Concrete shall be mixed and delivered to the job site by means of one of the following combinations of operations:

- A. Mixed completely in a stationary mixer and the mixed concrete transported to the point of delivery in truck agitators or in nonagitating hauling equipment (central-mixed concrete).
- B. Mixed partially in a stationary mixer, and the mixing completed in a truck mixer (shrink-mixed concrete).
- C. Mixed completely in a truck mixer (transit-mixed concrete).
- D. Mixed completely in a paving mixer.

Agitators may be truck mixers operating at agitating speed or truck agitators. Each mixer and agitator shall have attached thereto in a prominent place a metal plate or plates on which is plainly marked the various uses for which the equipment is designed, the manufacturer's guaranteed capacity of the drum or container in terms of the volume of mixed concrete and the speed of rotation of the mixing drum or blades.

Truck mixers shall be equipped with electrically or mechanically actuated revolution counters by which the number of revolutions of the drum or blades may readily be verified.

When shrink-mixed concrete is furnished, concrete that has been partially mixed at a central plant shall be transferred to a truck mixer and all requirements for transit-mixed concrete shall apply. No credit in the number of revolutions at mixing speed will be allowed for partial mixing in a central plant.

90-6.03 TRANSPORTING MIXED CONCRETE

Mixed concrete may be transported to the delivery point in truck agitators or truck mixers operating at the speed designated by the manufacturer of the equipment as agitating speed, or in non-agitating hauling equipment, provided the consistency and workability of the mixed concrete upon discharge at the delivery point is suitable for adequate placement and consolidation in place, and provided the mixed concrete after hauling to the delivery point conforms to the provisions in Section 90-6.01, "General."

Truck agitators shall be loaded not to exceed the manufacturer's guaranteed capacity and shall maintain the mixed concrete in a thoroughly mixed and uniform mass during hauling.

Bodies of nonagitating hauling equipment shall be constructed so that leakage of the concrete mix, or any part thereof, will not occur at any time.

Concrete hauled in open-top vehicles shall be protected during hauling against rain or against exposure to the sun for more than 20 minutes when the ambient temperature exceeds 75° F.

No additional mixing water shall be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer. If the Engineer authorizes additional water to be incorporated into the concrete, the drum shall be revolved not less than 30 revolutions at mixing speed after the water is added and before discharge is commenced.

The rate of discharge of mixed concrete from truck mixer-agitators shall be controlled by the speed of rotation of the drum in the discharge direction with the discharge gate fully open.

If a truck mixer or agitator is used for transporting concrete to the delivery point, discharge shall be completed within 1.5 hours or before 250 revolutions of the drum or blades, whichever occurs first, after the introduction of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or if the temperature of the concrete is 85° F or above, the time allowed may be less than 1.5 hours. If an admixture is used to retard the set time, the temperature of the concrete shall not exceed 85° F, the time limit shall be 2 hours, and the revolution limitation shall be 300.

If nonagitating hauling equipment is used for transporting concrete to the delivery point, discharge shall be completed within one hour after the addition of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 85° F or above, the time between the introduction of cement to the aggregates and discharge shall not exceed 45 minutes.

Each load of concrete delivered at the job site shall be accompanied by a weighmaster certificate showing the mix identification number, nonrepeating load number, date and time at which the materials were batched, the total amount of water added to the load, and for transit-mixed concrete, the reading of the revolution counter at the time the truck mixer is charged with cement. This weighmaster certificate shall also show the actual scale weights (pounds) for the ingredients batched. Theoretical or target batch weights shall not be used as a substitute for actual scale weights.

Weighmaster certificates shall be provided in printed form, or if approved by the Engineer, the data may be submitted in electronic media. Electronic media shall be presented in a tab-delimited format on a 3 1/2-inch diskette with a capacity of at least 1.4 megabytes. Captured data, for the ingredients represented by each batch shall be "line feed, carriage return" (LFCR) and "one line, separate record" with allowances for sufficient fields to satisfy the amount of data required by these specifications.

The Contractor may furnish a weighmaster certificate accompanied by a separate certificate that lists the actual batch weights or measurements for a load of concrete provided that both certificates are imprinted with the same nonrepeating load number that is unique to the contract and delivered to the jobsite with the load.

Weighmaster certificates furnished by the Contractor shall conform to the provisions in Section 9-1.01, "Measurement of Quantities."

90-6.04 TIME OR AMOUNT OF MIXING

Mixing of concrete in paving or stationary mixers shall continue for the required mixing time after all ingredients, except water and admixture, if added with the water, are in the mixing compartment of the mixer before any part of the batch is released. Transfer time in multiple drum mixers shall not be counted as part of the required mixing time.

The required mixing time, in paving or stationary mixers, of concrete used for concrete structures, except minor structures, shall be not less than 90 seconds or more than 5 minutes, except that when directed by the Engineer in writing, the requirements of the following paragraph shall apply.

The required mixing time, in paving or stationary mixers, except as provided in the preceding paragraph, shall be not less than 50 seconds or more than 5 minutes.

The minimum required revolutions at the mixing speed for transit-mixed concrete shall not be less than that recommended by the mixer manufacturer, but in no case shall the number of revolutions be less than that required to consistently produce concrete conforming to the provisions for uniformity in Section 90-6.01, "General."

When a high range water-reducing admixture is added to the concrete at the job site, the total number of revolutions shall not exceed 300.

90-6.05 HAND-MIXING

Hand-mixed concrete shall be made in batches of not more than 1/3 cubic yard and shall be mixed on a watertight, level platform. The proper amount of coarse aggregate shall be measured in measuring boxes and spread on the platform and the fine aggregate shall be spread on this layer, the 2 layers being not more than one foot in total depth. On this mixture shall be spread the dry cementitious materials and the whole mass turned no fewer than 2 times dry; then sufficient clean water shall be added, evenly distributed, and the whole mass again turned no fewer than 3 times, not including placing in the carriers or forms.

90-6.06 AMOUNT OF WATER AND PENETRATION

The amount of water used in concrete mixes shall be regulated so that the penetration of the concrete as determined by California Test 533 or the slump of the concrete as determined by ASTM Designation: C 143 is within the nominal values shown in the following table. When the penetration or slump of the concrete is found to exceed the nominal values listed, the mixture of subsequent batches shall be adjusted to reduce the penetration or slump to a value within the nominal range shown. Batches of concrete with a penetration or slump exceeding the maximum values listed shall not be used in the work. If Type F or Type G chemical admixtures are added to the mix, the penetration requirements shall not apply and the slump shall not exceed 9 inches after the chemical admixtures are added.

Type of Work	Nominal		Maximum	
	Penetration (inches)	Slump (inches)	Penetration (inches)	Slump (inches)
Concrete Pavement	0 - 1	—	1 1/2	—
Non-reinforced concrete facilities	0 - 1 1/2	—	2	—
Reinforced concrete structures				
Sections over 12 inches thick	0 - 1 1/2	—	2 1/2	—
Sections 12 inches thick or less	0 - 2	—	3	—
Concrete placed under water	—	6 - 8	—	9
Cast-in-place concrete piles	2 1/2 - 3 1/2	5 - 7	4	8

The amount of free water used in concrete shall not exceed 310 pounds per cubic yard, plus 20 pounds for each required 100 pounds of cementitious material in excess of 550 pounds per cubic yard.

The term free water is defined as the total water in the mixture minus the water absorbed by the aggregates in reaching a saturated surface-dry condition.

If there are adverse or difficult conditions that affect the placing of concrete, the above specified penetration and free water content limitations may be exceeded providing the Contractor is granted permission by the Engineer in writing to increase the cementitious material content per cubic yard of concrete. The increase in water and cementitious material shall be at a ratio not to exceed 30 pounds of water per added 100 pounds of cementitious material per cubic yard. Full compensation for additional cementitious material and water added under these conditions shall be considered as included in the contract price paid for the concrete work involved and no additional compensation will be allowed therefor.

The equipment for supplying water to the mixer shall be constructed and arranged so that the amount of water added can be measured accurately. Any method of discharging water into the mixer for a batch shall be accurate within 1.5 percent of the quantity of water required to be added to the mix for any position of the mixer. Tanks used to measure water shall be designed so that water cannot enter while water is being discharged into the mixer and discharge into the mixer shall be made rapidly in one operation without dribbling. All equipment shall be arranged so as to permit checking the amount of water delivered by discharging into measured containers.

90-7 CURING CONCRETE

90-7.01 METHODS OF CURING

Newly placed concrete shall be cured by the methods specified in this Section 90-7.01 and the special provisions.

90-7.01A Water Method

The concrete shall be kept continuously wet by the application of water for a minimum curing period of 7 days after the concrete has been placed.

Cotton mats, rugs, carpets, or earth or sand blankets may be used as a curing medium to retain the moisture during the curing period.

If a curing medium consisting of cotton mats, rugs, carpets, polyethylene sheeting, polyethylene sheeting on burlap, or earth or sand blankets is to be used to retain the moisture, the entire surface of the concrete shall be kept damp by applying water with a nozzle that so atomizes the flow that a mist and not a spray is formed, until the surface of the concrete is covered with the curing medium. The moisture from the nozzle shall not be applied under pressure directly upon the concrete and shall not be allowed to accumulate on the concrete in a quantity sufficient to cause a flow or wash the surface. At the expiration of the curing period, the concrete surfaces shall be cleared of all curing media.

At the option of the Contractor, a curing medium consisting of white opaque polyethylene sheeting extruded onto burlap may be used to cure concrete structures. The polyethylene sheeting shall have a minimum thickness of 4-mil, and shall be extruded onto 10-ounce burlap.

At the option of the Contractor, a curing medium consisting of polyethylene sheeting may be used to cure concrete columns. The polyethylene sheeting shall have a minimum thickness of 10-mil achieved in a single layer of material.

If the Contractor chooses to use polyethylene sheeting or polyethylene sheeting on burlap as a curing medium, these media and any joints therein shall be secured as necessary to provide moisture retention and shall be within 3 inches of the concrete at all points along the surface being cured. When these media are used, the temperature of the concrete shall be monitored during curing. If the temperature of the concrete cannot be maintained below 140° F, use of these curing media shall be disallowed.

When concrete bridge decks and flat slabs are to be cured without the use of a curing medium, the entire surface of the bridge deck or slab shall be kept damp by the application of water with an atomizing nozzle as specified above, until the concrete has set, after which the entire surface of the concrete shall be sprinkled continuously with water for a period of not less than 7 days.

90-7.01B Curing Compound Method

Surfaces of the concrete that are exposed to the air shall be sprayed uniformly with a curing compound.

Curing compounds to be used shall be as follows:

1. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class B, except the resin type shall be poly-alpha-methylstyrene.
2. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class B.
3. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class A.
4. Nonpigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 1, Class B.
5. Nonpigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 1, Class A.
6. Nonpigmented curing compound with fugitive dye conforming to the requirements in ASTM Designation: C 309, Type 1-D, Class A.

The infrared scan for the dried vehicle from curing compound (1) shall match the infrared scan on file at the Transportation Laboratory.

The loss of water for each type of curing compound, when tested in conformance with the requirements in California Test 534, shall not be more than 0.28-pounds per square yard in 24 hours.

The curing compound to be used will be specified elsewhere in these specifications or in the special provisions.

If the use of curing compound is required or permitted elsewhere in these specifications or in the special provisions and no specific kind is specified, any of the curing compounds listed above may be used.

Curing compound shall be applied at a nominal rate of one gallon per 150 square feet, unless otherwise specified.

At any point, the application rate shall be within ± 50 square feet per gallon of the nominal rate specified, and the average application rate shall be within ± 25 square feet per gallon of the nominal rate specified when tested in conformance with the requirements in California Test 535. Runs, sags, thin areas, skips, or holidays in the applied curing compound shall be evidence that the application is not satisfactory.

Curing compounds shall be applied using power operated spray equipment. The power operated spraying equipment shall be equipped with an operational pressure gage and a means of controlling the pressure. Hand spraying of small and irregular areas that are not reasonably accessible to mechanical spraying equipment, in the opinion of the Engineer, may be permitted.

The curing compound shall be applied to the concrete following the surface finishing operation, immediately before the moisture sheen disappears from the surface, but before any drying shrinkage or craze cracks begin to appear. In the event of any drying or cracking of the surface, application of water with an atomizing nozzle as specified in Section 90-7.01A, "Water Method," shall be started immediately and shall be continued until application of the compound is resumed or started; however, the compound shall not be applied over any resulting freestanding water. Should the film of compound be damaged from any cause before the expiration of 7 days after the concrete is placed in the case of structures and 72 hours in the case of pavement, the damaged portion shall be repaired immediately with additional compound.

At the time of use, compounds containing pigments shall be in a thoroughly mixed condition with the pigment uniformly dispersed throughout the vehicle. A paddle shall be used to loosen all settled pigment from the bottom of the container, and a power driven agitator shall be used to disperse the pigment uniformly throughout the vehicle.

Agitation shall not introduce air or other foreign substance into the curing compound.

The manufacturer shall include in the curing compound the necessary additives for control of sagging, pigment settling, leveling, de-emulsification, or other requisite qualities of a satisfactory working material. Pigmented curing compounds shall be manufactured so that the pigment does not settle badly, does not cake or thicken in the container, and does not become granular or curdled. Settlement of pigment shall be a thoroughly wetted, soft, mushy mass permitting the complete and easy vertical penetration of a paddle. Settled pigment shall be easily redispersed, with minimum resistance to the sideways manual motion of the paddle across the bottom of the container, to form a smooth uniform product of the proper consistency.

Curing compounds shall remain sprayable at temperatures above 40° F and shall not be diluted or altered after manufacture.

The curing compound shall be packaged in clean 274-gallon totes, 55-gallon barrels or 5-gallon pails shall be supplied from a suitable storage tank located at the jobsite. The containers shall comply with "Title 49, Code of Federal Regulations, Hazardous Materials Regulations." The 274-gallon totes and the 55-gallon barrels shall have removable lids and airtight fasteners. The 5-gallon pails shall be round and have standard full open head and bail. Lids with bungholes will not be permitted. Settling or separation of solids in containers, except tanks, must be completely redispersed with low speed mixing prior to use, in conformance with these specifications and the manufacturer's recommendations. Mixing shall be accomplished either manually by use of a paddle or by use of a mixing blade driven by a drill motor, at low speed. Mixing blades shall be the type used for mixing paint. On-site storage tanks shall be kept clean and free of contaminants. Each tank shall have a permanent system designed to completely redisperse settled material without introducing air or other foreign

substances.

Steel containers and lids shall be lined with a coating that will prevent destructive action by the compound or chemical agents in the air space above the compound. The coating shall not come off the container or lid as skins. Containers shall be filled in a manner that will prevent skinning. Plastic containers shall not react with the compound.

Each container shall be labeled with the manufacturer's name, kind of curing compound, batch number, volume, date of manufacture, and volatile organic compound (VOC) content. The label shall also warn that the curing compound containing pigment shall be well stirred before use. Precautions concerning the handling and the application of curing compound shall be shown on the label of the curing compound containers in conformance with the Construction Safety Orders and General Industry Safety Orders of the State.

Containers of curing compound shall be labeled to indicate that the contents fully comply with the rules and regulations concerning air pollution control in the State.

When the curing compound is shipped in tanks or tank trucks, a shipping invoice shall accompany each load. The invoice shall contain the same information as that required herein for container labels.

Curing compound will be sampled by the Engineer at the source of supply, at the job site, or at both locations.

Curing compound shall be formulated so as to maintain the specified properties for a minimum of one year. The Engineer may require additional testing before use to determine compliance with these specifications if the compound has not been used within one year or whenever the Engineer has reason to believe the compound is no longer satisfactory.

Tests will be conducted in conformance with the latest ASTM test methods and methods in use by the Transportation Laboratory.

90-7.01C Waterproof Membrane Method

The exposed finished surfaces of concrete shall be sprayed with water, using a nozzle that so atomizes the flow that a mist and not a spray is formed, until the concrete has set, after which the curing membrane, shall be placed. The curing membrane shall remain in place for a period of not less than 72 hours.

Sheeting material for curing concrete shall conform to the requirements in AASHTO Designation: M 171 for white reflective materials.

The sheeting material shall be fabricated into sheets of such width as to provide a complete cover for the entire concrete surface. Joints in the sheets shall be securely cemented together in such a manner as to provide a waterproof joint. The joint seams shall have a minimum lap of 0.33-foot.

The sheets shall be securely weighted down by placing a bank of earth on the edges of the sheets or by other means satisfactory to the Engineer.

Should any portion of the sheets be broken or damaged before the expiration of 72 hours after being placed, the broken or damaged portions shall be immediately repaired with new sheets properly cemented into place.

Sections of membrane that have lost their waterproof qualities or have been damaged to such an extent as to render them unfit for curing the concrete shall not be used.

90-7.01D Forms-In-Place Method

Formed surfaces of concrete may be cured by retaining the forms in place. The forms shall remain in place for a minimum period of 7 days after the concrete has been placed, except that for members over 20 inches in least dimension the forms shall remain in place for a minimum period of 5 days.

Joints in the forms and the joints between the end of forms and concrete shall be kept moisture tight during the curing period. Cracks in the forms and cracks between the forms and the concrete shall be resealed by methods subject to the approval of the Engineer.

90-7.02 CURING PAVEMENT

The entire exposed area of the pavement, including edges, shall be cured by the waterproof membrane method, or curing compound method using curing compound (1) or (2) as the Contractor may elect. Should the side forms be removed before the expiration of 72 hours following the start of curing, the exposed pavement edges shall also be cured. If the pavement is cured by means of the curing compound method, the sawcut and all portions of the curing compound that have been disturbed by sawing operations shall be restored by spraying with additional curing compound.

Curing shall commence as soon as the finishing process provided in Section 40-1.10, "Final Finishing," has been completed. The method selected shall conform to the provisions in Section 90-7.01, "Methods of Curing."

When the curing compound method is used, the compound shall be applied to the entire pavement surface by mechanical sprayers. Spraying equipment shall be of the fully atomizing type equipped with a tank agitator that provides for continual agitation of the curing compound during the time of application. The spray shall be adequately protected against wind, and the nozzles shall be so oriented or moved mechanically transversely as to result in the minimum specified rate of coverage being applied uniformly on exposed faces. Hand spraying of small and irregular areas, and areas inaccessible to mechanical spraying equipment, in the opinion of the Engineer, will be permitted. When the ambient air temperature is above 60° F, the

Contractor shall fog the surface of the concrete with a fine spray of water as specified in Section 90-7.01A, "Water Method." The surface of the pavement shall be kept moist between the hours of 10:00 a.m. and 4:30 p.m. on the day the concrete is placed. However, the fogging done after the curing compound has been applied shall not begin until the compound has set sufficiently to prevent displacement. Fogging shall be discontinued if ordered in writing by the Engineer.

90-7.03 CURING STRUCTURES

Newly placed concrete for cast-in-place structures, other than highway bridge decks, shall be cured by the water method, the forms-in-place method, or, as permitted herein, by the curing compound method, in conformance with the provisions in Section 90-7.01, "Methods of Curing."

The curing compound method using a pigmented curing compound may be used on concrete surfaces of construction joints, surfaces that are to be buried underground, and surfaces where only ordinary surface finish is to be applied and on which a uniform color is not required and that will not be visible from a public traveled way. If the Contractor elects to use the curing compound method on the bottom slab of box girder spans, the curing compound shall be curing compound (1).

The top surface of highway bridge decks shall be cured by both the curing compound method and the water method. The curing compound shall be curing compound (1).

Concrete surfaces of minor structures, as defined in Section 51-1.02, "Minor Structures," shall be cured by the water method, the forms-in-place method or the curing compound method.

When deemed necessary by the Engineer during periods of hot weather, water shall be applied to concrete surfaces being cured by the curing compound method or by the forms-in-place method, until the Engineer determines that a cooling effect is no longer required. Application of water for this purpose will be paid for as extra work as provided in Section 4-1.03D, "Extra Work."

90-7.04 CURING PRECAST CONCRETE MEMBERS

Precast concrete members shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing." Curing shall be provided for the minimum time specified for each method or until the concrete reaches its design strength, whichever is less. Steam curing may also be used for precast members and shall conform to the following provisions:

- A. After placement of the concrete, members shall be held for a minimum 4-hour presteaming period. If the ambient air temperature is below 50° F, steam shall be applied during the presteaming period to hold the air surrounding the member at a temperature between 50° F and 90° F.
- B. To prevent moisture loss on exposed surfaces during the presteaming period, members shall be covered as soon as possible after casting or the exposed surfaces shall be kept wet by fog spray or wet blankets.
- C. Enclosures for steam curing shall allow free circulation of steam about the member and shall be constructed to contain the live steam with a minimum moisture loss. The use of tarpaulins or similar flexible covers will be permitted, provided they are kept in good repair and secured in such a manner as to prevent the loss of steam and moisture.
- D. Steam at the jets shall be at low pressure and in a saturated condition. Steam jets shall not impinge directly on the concrete, test cylinders, or forms. During application of the steam, the temperature rise within the enclosure shall not exceed 40° F per hour. The curing temperature throughout the enclosure shall not exceed 150° F and shall be maintained at a constant level for a sufficient time necessary to develop the required transfer strength. Control cylinders shall be covered to prevent moisture loss and shall be placed in a location where temperature is representative of the average temperature of the enclosure.
- E. Temperature recording devices that will provide an accurate, continuous, permanent record of the curing temperature shall be provided. A minimum of one temperature recording device per 200 feet of continuous bed length will be required for checking temperature.
- F. Members in pretension beds shall be detensioned immediately after the termination of steam curing while the concrete and forms are still warm, or the temperature under the enclosure shall be maintained above 60° F until the stress is transferred to the concrete.
- G. Curing of precast concrete will be considered completed after termination of the steam curing cycle.

90-7.05 CURING PRECAST PRESTRESSED CONCRETE PILES

Newly placed concrete for precast prestressed concrete piles shall be cured in conformance with the provisions in Section 90-7.04, "Curing Precast Concrete Members," except that piles in a corrosive environment shall be cured as follows:

- A. Piles shall be either steam cured or water cured. If water curing is used, the piles shall be kept continuously wet by the application of water in conformance with the provisions in Section 90-7.01A, "Water Method."

- B. If steam curing is used, the steam curing provisions in Section 90-7.04, "Curing Precast Concrete Members," shall apply except that the piles shall be kept continuously wet for their entire length for a period of not less than 3 days, including the holding and steam curing periods.

90-7.06 CURING SLOPE PROTECTION

Concrete slope protection shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing."

Concreted-rock slope protection shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing," with a blanket of earth kept wet for 72 hours, or by sprinkling with a fine spray of water every 2 hours during the daytime for a period of 3 days.

90-7.07 CURING MISCELLANEOUS CONCRETE WORK

Exposed surfaces of curbs shall be cured by pigmented curing compounds as specified in Section 90-7.01B, "Curing Compound Method."

Concrete sidewalks, gutter depressions, island paving, curb ramps, driveways, and other miscellaneous concrete areas shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing."

Shotcrete shall be cured for at least 72 hours by spraying with water, by a moist earth blanket, or by any of the methods provided in Section 90-7.01, "Methods of Curing."

Mortar and grout shall be cured by keeping the surface damp for 3 days.

After placing, the exposed surfaces of sign structure foundations, including pedestal portions, if constructed, shall be cured for at least 72 hours by spraying with water, by a moist earth blanket, or by any of the methods provided in Section 90-7.01, "Methods of Curing."

90-8 PROTECTING CONCRETE

90-8.01 GENERAL

In addition to the provisions in Section 7-1.16, "Contractor's Responsibility for the Work and Materials," the Contractor shall protect concrete as provided in this Section 90-8. If required by the Engineer, the Contractor shall submit a written outline of the proposed methods for protecting the concrete.

The Contractor shall protect concrete from damage from any cause, which shall include, but not be limited to: rain, heat, cold, wind, Contractor's actions, and actions of others.

Concrete shall not be placed on frozen or ice-coated ground or subgrade nor on ice-coated forms, reinforcing steel, structural steel, conduits, precast members, or construction joints.

Under rainy conditions, placing of concrete shall be stopped before the quantity of surface water is sufficient to damage surface mortar or cause a flow or wash of the concrete surface, unless the Contractor provides adequate protection against damage.

Concrete that has been frozen or damaged by other causes, as determined by the Engineer, shall be removed and replaced by the Contractor at the Contractor's expense.

90-8.02 PROTECTING CONCRETE STRUCTURES

Structure concrete and shotcrete used as structure concrete shall be maintained at a temperature of not less than 45° F for 72 hours after placing and at not less than 40° F for an additional 4 days.

90-8.03 PROTECTING CONCRETE PAVEMENT

Pavement concrete shall be maintained at a temperature of not less than 40° F for 72 hours.

Except as provided in Section 7-1.08, "Public Convenience," the Contractor shall protect concrete pavement against construction and other activities that abrade, scar, discolor, reduce texture depth, lower coefficient of friction, or otherwise damage the surface. Stockpiling, drifting, or excessive spillage of soil, gravel, petroleum products, and concrete or asphalt mixes on the surface of concrete pavement is prohibited unless otherwise specified in these specifications, the special provisions or permitted by the Engineer.

If ordered by the Engineer or shown on the plans or specified in the special provisions, pavement crossings shall be constructed for the convenience of public traffic. The material and work necessary for the construction of the crossings, and their subsequent removal and disposal, will be paid for at the contract unit prices for the items of work involved and if there are no contract items for the work involved, payment for pavement crossings will be made by extra work as provided in Section 4-1.03D, "Extra Work." Where public traffic will be required to cross over the new pavement, Type III portland cement may be used in concrete, if permitted in writing by the Engineer. The pavement may be opened to traffic as soon as the concrete has developed a modulus of rupture of 550 pounds per square inch. The modulus of rupture will be determined by California Test 523.

No traffic or Contractor's equipment, except as hereinafter provided, will be permitted on the pavement before a period of 10 days has elapsed after the concrete has been placed, nor before the concrete has developed a modulus of rupture of at least 550 pounds per square inch. Concrete that fails to attain a modulus of rupture of 550 pounds per square inch within 10 days shall not be opened to traffic until directed by the Engineer.

Equipment for sawing weakened plane joints will be permitted on the pavement as specified in Section 40-1.08B, "Weakened Plane Joints."

When requested in writing by the Contractor, the tracks on one side of paving equipment will be permitted on the pavement after a modulus of rupture of 350 pounds per square inch has been attained, provided that:

- A. Unit pressure exerted on the pavement by the paver shall not exceed 20 pounds per square inch;
- B. Tracks with cleats, grousers, or similar protuberances shall be modified or shall travel on planks or equivalent protective material, so that the pavement is not damaged; and
- C. No part of the track shall be closer than one foot from the edge of pavement.

In case of visible cracking of, or other damage to the pavement, operation of the paving equipment on the pavement shall be immediately discontinued.

Damage to the pavement resulting from early use of pavement by the Contractor's equipment as provided above shall be repaired by the Contractor.

The State will furnish the molds and machines for testing the concrete for modulus of rupture, and the Contractor, at the Contractor's expense, shall furnish the material and whatever labor the Engineer may require.

90-9 COMPRESSIVE STRENGTH

90-9.01 GENERAL

Concrete compressive strength requirements consist of a minimum strength that shall be attained before various loads or stresses are applied to the concrete and, for concrete designated by strength, a minimum strength at the age of 28 days or at the age otherwise allowed in Section 90-1.01, "Description." The various strengths required are specified in these specifications or the special provisions or are shown on the plans.

The compressive strength of concrete will be determined from test cylinders that have been fabricated from concrete sampled in conformance with the requirements of California Test 539. Test cylinders will be molded and initially field cured in conformance with California Test 540. Test cylinders will be cured and tested after receipt at the testing laboratory in conformance with the requirements of California Test 521. A strength test shall consist of the average strength of 2 cylinders fabricated from material taken from a single load of concrete, except that, if any cylinder should show evidence of improper sampling, molding, or testing, that cylinder shall be discarded and the strength test shall consist of the strength of the remaining cylinder.

When concrete compressive strength is specified as a prerequisite to applying loads or stresses to a concrete structure or member, test cylinders for other than steam cured concrete will be cured in conformance with Method 1 of California Test 540. The compressive strength of concrete determined for these purposes will be evaluated on the basis of individual tests.

When concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete strength to be used as a basis for acceptance of other than steam cured concrete will be determined from cylinders cured in conformance with Method 1 of California Test 540. If the result of a single compressive strength test at the maximum age specified or allowed is below the specified strength but is 95 percent or more of the specified strength, the Contractor shall make corrective changes, subject to approval of the Engineer, in the mix proportions or in the concrete fabrication procedures, before placing additional concrete, and shall pay to the State \$10 for each in-place cubic yard of concrete represented by the deficient test. If the result of a single compressive strength test at the maximum age specified or allowed is below 95 percent of the specified strength, but is 85 percent or more of the specified strength, the Contractor shall make the corrective changes specified above, and shall pay to the State \$15 for each in-place cubic yard of concrete represented by the deficient test. In addition, such corrective changes shall be made when the compressive strength of concrete tested at 7 days indicates, in the judgment of the Engineer, that the concrete will not attain the required compressive strength at the maximum age specified or allowed. Concrete represented by a single test that indicates a compressive strength of less than 85 percent of the specified 28-day compressive strength will be rejected in conformance with the provisions in Section 6-1.04, "Defective Materials."

If the test result indicates that the compressive strength at the maximum curing age specified or allowed is below the specified strength, but is 85 percent or more of the specified strength, payments to the State as required above shall be made, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength of the concrete placed in the work meets or exceeds the specified 28-day compressive strength. If the test result indicates a compressive strength at the maximum curing age specified or allowed below 85 percent, the concrete represented by that test will be rejected, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer

that the strength and quality of the concrete placed in the work are acceptable. If the evidence consists of tests made on cores taken from the work, the cores shall be obtained and tested in conformance with the requirements in ASTM Designation: C 42.

No single compressive strength test shall represent more than 320 cubic yards.

If a precast concrete member is steam cured, the compressive strength of the concrete will be determined from test cylinders that have been handled and stored in conformance with Method 3 of California Test 540. The compressive strength of steam cured concrete will be evaluated on the basis of individual tests representing specific portions of production. If the concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete shall be considered to be acceptable whenever its compressive strength reaches the specified 28-day compressive strength provided that strength is reached in not more than the maximum number of days specified or allowed after the member is cast.

When concrete is specified by compressive strength, prequalification of materials, mix proportions, mixing equipment, and procedures proposed for use will be required prior to placement of the concrete. Prequalification shall be accomplished by the submission of acceptable certified test data or trial batch reports by the Contractor. Prequalification data shall be based on the use of materials, mix proportions, mixing equipment, procedures, and size of batch proposed for use in the work.

Certified test data, in order to be acceptable, shall indicate that not less than 90 percent of at least 20 consecutive tests exceed the specified strength at the maximum number of cure days specified or allowed, and none of those tests are less than 95 percent of specified strength. Strength tests included in the data shall be the most recent tests made on concrete of the proposed mix design and all shall have been made within one year of the proposed use of the concrete.

Trial batch test reports, in order to be acceptable, shall indicate that the average compressive strength of 5 consecutive concrete cylinders, taken from a single batch, at not more than 28 days (or the maximum age allowed) after molding shall be at least 580 pounds per square inch greater than the specified 28-day compressive strength, and no individual cylinder shall have a strength less than the specified strength at the maximum age specified or allowed. Data contained in the report shall be from trial batches that were produced within one year of the proposed use of specified strength concrete in the project. Whenever air-entrainment is required, the air content of trial batches shall be equal to or greater than the air content specified for the concrete without reduction due to tolerances.

Tests shall be performed in conformance with either the appropriate California Test methods or the comparable ASTM test methods. Equipment employed in testing shall be in good condition and shall be properly calibrated. If the tests are performed during the life of the contract, the Engineer shall be notified sufficiently in advance of performing the tests in order to witness the test procedures.

The certified test data and trial batch test reports shall include the following information:

- A. Date of mixing.
- B. Mixing equipment and procedures used.
- C. The size of batch in cubic yards and the weight, type, and source of all ingredients used.
- D. Penetration or slump (if the concrete will be placed under water or placed in cast-in-place concrete piles) of the concrete.
- E. The air content of the concrete if an air-entraining admixture is used.
- F. The age at time of testing and strength of all concrete cylinders tested.

Certified test data and trial batch test reports shall be signed by an official of the firm that performed the tests.

When approved by the Engineer, concrete from trial batches may be used in the work at locations where concrete of a lower quality is required and the concrete will be paid for as the type or class of concrete required at that location.

After materials, mix proportions, mixing equipment, and procedures for concrete have been prequalified for use, additional prequalification by testing of trial batches will be required prior to making changes that, in the judgment of the Engineer, could result in a strength of concrete below that specified.

The Contractor's attention is directed to the time required to test trial batches and the Contractor shall be responsible for production of trial batches at a sufficiently early date so that the progress of the work is not delayed.

When precast concrete members are manufactured at the plant of an established manufacturer of precast concrete members, the mix proportions of the concrete shall be determined by the Contractor, and a trial batch and prequalification of the materials, mix proportions, mixing equipment, and procedures will not be required.

90-10 MINOR CONCRETE

90-10.01 GENERAL

Concrete for minor structures, slope paving, curbs, sidewalks and other concrete work, when designated as minor concrete on the plans, in the specifications, or in the contract item, shall conform to the provisions specified herein.

The Engineer, at the Engineer's discretion, will inspect and test the facilities, materials and methods for producing the concrete to ensure that minor concrete of the quality suitable for use in the work is obtained.

90-10.02 MATERIALS

Minor concrete shall conform to the following requirements:

90-10.02A Cementitious Material

Cementitious material shall conform to the provisions in Section 90-1.01, "Description."

90-10.02B Aggregate

Aggregate shall be clean and free from deleterious coatings, clay balls, roots, and other extraneous materials.

Use of crushed concrete or reclaimed aggregate is acceptable only if the aggregate satisfies all aggregate requirements.

The Contractor shall submit to the Engineer for approval, a grading of the combined aggregate proposed for use in the minor concrete. After acceptance of the grading, aggregate furnished for minor concrete shall conform to that grading, unless a change is authorized in writing by the Engineer.

The Engineer may require the Contractor to furnish periodic test reports of the aggregate grading furnished. The maximum size of aggregate used shall be at the option of the Contractor, but in no case shall the maximum size be larger than 1 1/2-inch or smaller than 3/4-inch.

The Engineer may waive, in writing, the gradation requirements in this Section 90-10.02B, if, in the Engineer's opinion, the furnishing of the gradation is not necessary for the type or amount of concrete work to be constructed.

90-10.02C Water

Water used for washing, mixing, and curing shall be free from oil, salts, and other impurities that would discolor or etch the surface or have an adverse affect on the quality of the concrete.

90-10.02D Admixtures

The use of admixtures shall conform to the provisions in Section 90-4, "Admixtures."

90-10.03 PRODUCTION

Cementitious material, water, aggregate, and admixtures shall be stored, proportioned, mixed, transported, and discharged in conformance with recognized standards of good practice that will result in concrete that is thoroughly and uniformly mixed, that is suitable for the use intended, and that conforms to requirements specified herein. Recognized standards of good practice are outlined in various industry publications such as are issued by American Concrete Institute, AASHTO, or the Department.

The cementitious material content of minor concrete shall conform to the provisions in Section 90-1.01, "Description."

The amount of water used shall result in a consistency of concrete conforming to the provisions in Section 90-6.06, "Amount of Water and Penetration." Additional mixing water shall not be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer.

Discharge of ready-mixed concrete from the transporting vehicle shall be made while the concrete is still plastic and before stiffening occurs. An elapsed time of 1.5 hours (one hour in non-agitating hauling equipment), or more than 250 revolutions of the drum or blades, after the introduction of the cementitious material to the aggregates, or a temperature of concrete of more than 90° F will be considered conditions contributing to the quick stiffening of concrete. The Contractor shall take whatever action is necessary to eliminate quick stiffening, except that the addition of water will not be permitted.

The required mixing time in stationary mixers shall be not less than 50 seconds or more than 5 minutes.

The minimum required revolutions at mixing speed for transit-mixed concrete shall be not less than that recommended by the mixer manufacturer, and shall be increased, if necessary, to produce thoroughly and uniformly mixed concrete.

When a high range water-reducing admixture is added to the concrete at the job site, the total number of revolutions shall not exceed 300.

Each load of ready-mixed concrete shall be accompanied by a weighmaster certificate that shall be delivered to the Engineer at the discharge location of the concrete, unless otherwise directed by the Engineer. The weighmaster certificate shall be clearly marked with the date and time of day when the load left the batching plant and, if hauled in truck mixers or agitators, the time the mixing cycle started.

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," shall be furnished to the Engineer, prior to placing minor concrete from a source not previously used on the contract, stating that minor concrete to be furnished meets contract requirements, including minimum cementitious material content specified.

90-10.04 CURING MINOR CONCRETE

Curing minor concrete shall conform to the provisions in Section 90-7, "Curing Concrete."

Performance Graded Asphalt Binder

Property	AASHTO Test Method	Specification				
		Grade				
		PG 58-22 ^a	PG 64-10	PG 64-16	PG 64-28	PG 70-10
Original Binder						
Flash Point, Minimum °C	T 48	230	230	230	230	230
Solubility, Minimum % ^b	T 44	99	99	99	99	99
Viscosity at 135°C, ^c Maximum, Pa·s	T 316	3.0	3.0	3.0	3.0	3.0
Dynamic Shear, Test Temp. at 10 rad/s, °C Minimum G*/sin(delta), kPa	T 315	58 1.00	64 1.00	64 1.00	64 1.00	70 1.00
RTFO Test, ^e Mass Loss, Maximum, %	T 240	1.00	1.00	1.00	1.00	1.00
RTFO Test Aged Binder						
Dynamic Shear, Test Temp. at 10 rad/s, °C Minimum G*/sin(delta), kPa	T 315	58 2.20	64 2.20	64 2.20	64 2.20	70 2.20
Ductility at 25°C Minimum, cm	T 51	75	75	75	75	75
PAV ^f Aging, Temperature, °C	R 28	100	100	100	100	110
RTFO Test and PAV Aged Binder						
Dynamic Shear, Test Temp. at 10 rad/s, °C Maximum G*/sin(delta), kPa	T 315	22 ^d 5000	31 ^d 5000	28 ^d 5000	22 ^d 5000	34 ^d 5000
Creep Stiffness, Test Temperature, °C Maximum S-value, Mpa Minimum M-value	T 313	-12 300 0.300	0 300 0.300	-6 300 0.300	-18 300 0.300	0 300 0.300

Notes:

- a. Use as asphalt rubber base stock for high mountain and high desert area.
- b. The Engineer waives this specification if the supplier is a Quality Supplier as defined by the Department's "Certification Program for Suppliers of Asphalt."
- c. The Engineer waives this specification if the supplier certifies the asphalt binder can be adequately pumped and mixed at temperatures meeting applicable safety standards.
- d. Test the sample at 3°C higher if it fails at the specified test temperature. G*/sin(delta) remains 5000 kPa maximum.
- e. "RTFO Test" means the asphaltic residue obtained using the Rolling Thin Film Oven Test, AASHTO Test Method T 240 or ASTM Designation: D 2872. The residue from mass change determination may be used for other tests.
- f. "PAV" means Pressurized Aging Vessel.

Performance graded polymer modified asphalt binder (PG Polymer Modified) is:

Performance Graded Polymer Modified Asphalt Binder ^a

Property	AASHTO Test Method	Specification Grade		
		PG 58-34 PM	PG 64-28 PM	PG 76-22 PM
Original Binder				
Flash Point, Minimum °C	T 48	230	230	230
Solubility, Minimum % ^b	T 44 ^c	98.5	98.5	98.5
Viscosity at 135°C, ^d Maximum, Pa·s	T 316	3.0	3.0	3.0
Dynamic Shear, Test Temp. at 10 rad/s, °C Minimum G*/sin(delta), kPa	T 315	58 1.00	64 1.00	76 1.00
RTFO Test, Mass Loss, Maximum, %	T 240	1.00	1.00	1.00
RTFO Test Aged Binder				
Dynamic Shear, Test Temp. at 10 rad/s, °C Minimum G*/sin(delta), kPa	T 315	58 2.20	64 2.20	76 2.20
Dynamic Shear, Test Temp. at 10 rad/s, °C Maximum (delta), %	T 315	Note e 80	Note e 80	Note e 80
Elastic Recovery ^f , Test Temp., °C Minimum recovery, %	T 301	25 75	25 75	25 65
PAV ^g Aging, Temperature, °C	R 28	100	100	110
RTFO Test and PAV Aged Binder				
Dynamic Shear, Test Temp. at 10 rad/s, °C Maximum G*/sin(delta), kPa	T 315	16 5000	22 5000	31 5000
Creep Stiffness, Test Temperature, °C Maximum S-value, MPa Minimum M-value	T 313	-24 300 0.300	-18 300 0.300	-12 300 0.300

Notes:

- a. Do not modify PG Polymer Modified using acid modification.
- b. The Engineer waives this specification if the supplier is a Quality Supplier as defined by the Department's "Certification Program for Suppliers of Asphalt."
- c. The Department allows ASTM D 5546 instead of AASHTO T 44
- d. The Engineer waives this specification if the supplier certifies the asphalt binder can be adequately pumped and mixed at temperatures meeting applicable safety standards.
- e. Test temperature is the temperature at which G*/sin(delta) is 2.2 kPa. A graph of log G*/sin(delta) plotted against temperature may be used to determine the test temperature when G*/sin(delta) is 2.2 kPa. A graph of (delta) versus temperature may be used to determine delta at the temperature when G*/sin(delta) is 2.2 kPa. The Engineer also accepts direct measurement of (delta) at the temperature when G*/sin(delta) is 2.2 kPa.
- f. Tests without a force ductility clamp may be performed.
- g. "PAV" means Pressurized Aging Vessel.

SAMPLING

Provide a sampling device in the asphalt feed line connecting the plant storage tanks to the asphalt weighing system or spray bar. Make the sampling device accessible between 24 and 30 inches above the platform. Provide a receptacle for flushing the sampling device.

Include with the sampling device a valve:

1. Between 1/2 and 3/4 inch in diameter

