

**DEPARTMENT OF TRANSPORTATION**

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30<sup>th</sup> Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

TTY 711



*Flex your power!  
Be energy efficient!*

April 26, 2013

08-Riv-74-63.0/67.5 and 80.3/R92.3

08-1C4304

Project ID 0812000312

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN RIVERSIDE COUNTY NEAR IDYLLWILD AND PALM DESERT FROM HURKEY CREEK BRIDGE TO 0.5 MILE WEST OF MORRIS RANCH ROAD AND FROM 0.2 MILE WEST OF PINYON DRIVE TO 1.4 MILES SOUTH OF CAHUILLA WAY.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Thursday, May 2, 2013.

This addendum is being issued to revise the Project Plans, *Notice to Bidders and Special Provisions*, and the *Bid Book*.

Project plan sheets 2, 5 and 6 are replaced and attached for substitution for the like-numbered sheets.

Project plan sheets 3A and 3B are added and attached for addition to the project plans.

In the Special Provisions, Section 39-1.16, "CENTERLINE RUMBLE STRIPS," is added as attached.

In the *Bid book*, in the "Bid Item List," Items 8, 10, and 12 are revised, Items 17, 18, 19 and 20 are added and Item 16 is deleted as attached.

To *Bid book* holders:

In the *Bid book*, the "Bid Item List" is replaced as attached. The attached Bid Item List is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the *Bid book*.

Submit bids in the *Bid book* you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

Addendum No. 1  
Page 2  
April 26, 2013

08-Riv-74-63.0/67.5 and 80.3/R92.3  
08-1C4304  
Project ID 0812000312

This addendum and attachments are available for the Contractors' download on the Web site:

**[http://www.dot.ca.gov/hq/esc/oe/project\\_ads\\_addenda/08/08-1C4304](http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/08/08-1C4304)**

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

  
fa BASEM MUALLEM  
District Director

Attachments

Replace section 39-1.16 with:

**39-1.16 CENTERLINE RUMBLE STRIPS**

**39-1.16A General**

Construct centerline rumble strips in the top layer of HMA surfacing by ground-in method.

**39-1.16B Materials**

Not Used

**39-1.16C Construction**

Select the method and equipment for constructing ground-in indentations.

Do not construct rumble strips on structures or approach slabs. Do not construct centerline rumble strips where crossroads or driveways are present

Construct centerline rumble strips within 1 inch of the specified alignment. The grinding equipment must be equipped with a sighting device enabling the operator to maintain the rumble strip alignment.

Indentations must comply with the specified dimensions within 0.06 inch in depth and 5 percent in length and width.

The Engineer orders grinding or removal and replacement of noncompliant centerline rumble strips to bring them within specified tolerances. Ground surface areas must be neat and uniform in appearance.

The grinding equipment must be equipped with a vacuum attachment to remove residue from the roadbed.

Dispose of removed material.

On ground areas, apply fog seal coat under section 37-2.

**39-1.16D Payment**

Centerline rumble strips are measured by the station along the length of the rumble strips without deductions for gaps between indentations.

**BID ITEM LIST  
08-1C4304**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	070030	LEAD COMPLIANCE PLAN	LS	LUMP SUM	LUMP SUM	
2	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
3	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
4	128651	PORTABLE CHANGEABLE MESSAGE SIGN (EA)	EA	2		
5	130100	JOB SITE MANAGEMENT	LS	LUMP SUM	LUMP SUM	
6	130200	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM	LUMP SUM	
7	150722	REMOVE PAVEMENT MARKER	EA	1,450		
8	153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	19,700		
9	390095	REPLACE ASPHALT CONCRETE SURFACING	CY	370		
10	390132	HOT MIX ASPHALT (TYPE A)	TON	16,900		
11	394060	DATA CORE	LS	LUMP SUM	LUMP SUM	
12	397005	TACK COAT	TON	33		
13	840515	THERMOPLASTIC PAVEMENT MARKING	SQFT	220		
14	840560	THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	LF	291,000		
15	850122	PAVEMENT MARKER (RETROREFLECTIVE-RECESSED)	EA	7,370		
16	BLANK					
17	390010	PREPAVING PROFILOGRAPH	LS	LUMP SUM	LUMP SUM	
18	390020	PREPAVING GRINDING DAY	EA	3		
19	025633	CENTERLINE RUMBLE STRIP (GROUND-IN INDENTATIONS)	STA	620		
20	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

**TOTAL BID:**

**\$**

---