

DEPARTMENT OF TRANSPORTATION

ES-OE MS #43
1727 30TH Street, 2ND Floor
Sacramento, CA 95816



May 10, 2001

08-SBd-15,40-69.2/74.1, 0.0/0.2
08-350724
DPS-C020(004)N

Addendum No. 2

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in SAN BERNARDINO COUNTY IN BARSTOW FROM 0.5 MILE NORTH OF THE LENWOOD ROAD OVERCROSSING TO THE ROUTE 15/40 SEPARATION.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on May 24, 2001.

This addendum is being issued to revise the Notice to Contractors and Special Provisions.

In the Special Provisions, "TABLE OF CONTENTS," is revised as attached.

In the Special Provisions, Section 10-1.29, "EARTHWORK," is revised as attached.

To Proposal and Contract book holders:

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by confirmed facsimile to all book holders to ensure that each receives it.

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief
Plans, Specifications & Estimates Branch
Office of Office Engineer

Attachments

TABLE OF CONTENTS

| | |
|--|----|
| NOTICE TO CONTRACTORS..... | 1 |
| COPY OF ENGINEER'S ESTIMATE | 3 |
| SPECIAL PROVISIONS | 10 |
| SECTION 1. SPECIFICATIONS AND PLANS..... | 10 |
| SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS..... | 10 |
| 2-1.01 GENERAL..... | 10 |
| 2-1.015 FEDERAL LOBBYING RESTRICTIONS..... | 10 |
| 2-1.02 DISADVANTAGED BUSINESS ENTERPRISE (DBE)..... | 11 |
| 2-1.02A DBE GOAL FOR THIS PROJECT | 12 |
| 2-1.02B SUBMISSION OF DBE INFORMATION | 13 |
| SECTION 3. AWARD AND EXECUTION OF CONTRACT..... | 14 |
| SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES | 14 |
| SECTION 5. GENERAL | 14 |
| SECTION 5-1. MISCELLANEOUS | 14 |
| 5-1.00 PLANS AND WORKING DRAWINGS | 14 |
| 5-1.002 LABORATORY | 15 |
| 5-1.003 EXAMINATION OF PLANS, SPECIFICATIONS, CONTRACT, AND SITE OF WORK | 15 |
| 5-1.004 DIFFERING SITE CONDITIONS..... | 15 |
| 5-1.005 CONTRACT BONDS | 15 |
| 5-1.006 EXCAVATION SAFETY PLANS | 15 |
| 5-1.007 COST REDUCTION INCENTIVE..... | 16 |
| 5-1.01 LABOR NONDISCRIMINATION..... | 16 |
| 5-1.02 LABOR CODE REQUIREMENTS | 16 |
| 5-1.03 CONTRACTOR'S LICENSING LAWS | 19 |
| 5-1.035 INDEMNIFICATION AND INSURANCE..... | 19 |
| 5-1.04 ARBITRATION | 22 |
| 5-1.05 NOTICE OF POTENTIAL CLAIM..... | 22 |
| 5-1.06 PARTIAL PAYMENTS | 22 |
| 5-1.07 PAYMENT OF WITHHELD FUNDS | 23 |
| 5-1.08 FINAL PAYMENT AND CLAIMS..... | 23 |
| 5-1.09 INTEREST ON PAYMENTS | 25 |
| 5-1.10 PUBLIC SAFETY | 25 |
| 5-1.11 SURFACE MINING AND RECLAMATION ACT | 26 |
| 5-1.12 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES..... | 26 |
| 5-1.13 FINAL PAY QUANTITIES | 27 |
| 5-1.14 YEAR 2000 COMPLIANCE..... | 27 |
| 5-1.145 BUY AMERICA REQUIREMENTS..... | 27 |
| 5-1.15 SUBCONTRACTOR AND DBE RECORDS | 27 |
| 5-1.152 DBE CERTIFICATION STATUS | 28 |
| 5-1.155 PERFORMANCE OF DBE SUBCONTRACTORS AND SUPPLIERS | 28 |
| 5-1.16 SUBCONTRACTING | 28 |
| 5-1.162 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS | 29 |
| 5-1.164 PROMPT PAYMENT OF WITHHELD FUNDS TO SUBCONTRACTORS | 29 |
| 5-1.17 PARTNERING | 29 |
| 5-1.174 VALUE ANALYSIS | 30 |
| 5-1.18 FORCE ACCOUNT PAYMENT | 30 |
| 5-1.19 COMPENSATION ADJUSTMENTS FOR PRICE INDEX FLUCTUATIONS | 31 |
| 5-1.20 AREAS FOR CONTRACTOR'S USE | 32 |
| 5-1.21 PAYMENTS | 32 |
| 5-1.22 SOUND CONTROL REQUIREMENTS | 33 |
| 5-1.23 PALEONTOLOGICAL RESOURCES (FOSSILS) | 33 |
| 5-1.24 ENDANGERED SPECIES PROTECTION | 33 |
| 5-1.25 BORROW, DISPOSAL AND MATERIAL SITES | 35 |
| 5-1.26 AERIALLY DEPOSITED LEAD | 35 |

| | |
|---|----|
| SECTION 6. (BLANK)..... | 35 |
| SECTION 7. (BLANK)..... | 35 |
| SECTION 8. MATERIALS | 35 |
| SECTION 8-1. MISCELLANEOUS | 35 |
| 8-1.01 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS | 35 |
| PAVEMENT MARKERS, PERMANENT TYPE..... | 36 |
| PAVEMENT MARKERS, TEMPORARY TYPE..... | 36 |
| STRIPING AND PAVEMENT MARKING MATERIALS | 37 |
| CLASS 1 DELINEATORS..... | 37 |
| CHANNELIZERS | 38 |
| CONICAL DELINEATORS, 42"..... | 38 |
| OBJECT MARKERS..... | 38 |
| TEMPORARY RAILING (TYPE K) REFLECTORS AND CONCRETE BARRIER MARKERS | 38 |
| THRIE BEAM BARRIER MARKERS..... | 38 |
| CONCRETE BARRIER DELINEATORS, 16" | 39 |
| CONCRETE BARRIER-MOUNTED MINI-DRUM (10 1/2" x14 1/4" x22 3/4") | 39 |
| SOUND WALL DELINEATOR | 39 |
| GUARD RAILING DELINEATOR..... | 39 |
| RETROREFLECTIVE SHEETING..... | 39 |
| SIGN SUBSTRATE FOR CONSTRUCTION AREA SIGNS | 40 |
| 8-1.02 STATE-FURNISHED MATERIALS | 40 |
| 8-1.03 SLAG AGGREGATE..... | 40 |
| 8-1.04 ENGINEERING FABRICS..... | 42 |
| SECTION 8-2. CONCRETE..... | 42 |
| 8-2.01 PORTLAND CEMENT CONCRETE..... | 42 |
| 8-3.02 WELDING QUALITY CONTROL | 52 |
| SECTION 9. (BLANK)..... | 56 |
| SECTION 10. CONSTRUCTION DETAILS..... | 56 |
| SECTION 10-1. GENERAL | 56 |
| 10-1.01 CONSTRUCTION PROJECT INFORMATION SIGNS | 56 |
| 10-1.02 ORDER OF WORK..... | 56 |
| 10-1.03 WATER POLLUTION CONTROL | 57 |
| STORM WATER POLLUTION PREVENTION PLAN PREPARATION, APPROVAL AND UPDATES | 58 |
| SCHEQUE OF VALUES..... | 60 |
| SWPPP IMPLEMENTATION | 60 |
| MAINTENANCE | 60 |
| PAYMENT | 61 |
| 10-1.04 TEMPORARY FENCE | 62 |
| 10-1.05 PRESERVATION OF PROPERTY | 62 |
| 10-1.06 COOPERATION | 62 |
| 10-1.07 PROGRESS SCHEDULE (CRITICAL PATH)..... | 62 |
| DEFINITIONS..... | 63 |
| MATERIALS (COMPUTER SYSTEM) | 63 |
| GENERAL | 64 |
| PRE-CONSTRUCTION SCHEDULING CONFERENCE | 66 |
| NETWORK DIAGRAM AND PROJECT SCHEDULE REPORTS | 66 |
| BASELINE SCHEDULE REQUIREMENTS | 67 |
| MONTHLY SCHEDULE UPDATES..... | 68 |
| SCHEDULE REVISIONS..... | 68 |
| SCHEDULE TIME ADJUSTMENT..... | 68 |
| FINAL SCHEDULE UPDATE | 69 |
| PAYMENT | 69 |
| RETENTION | 69 |
| 10-1.08 OVERHEAD | 69 |
| 10-1.09 OBSTRUCTIONS | 71 |
| 10-1.10 DUST CONTROL | 71 |

| | |
|---|----|
| 10-1.11 MOBILIZATION | 71 |
| 10-1.12 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES | 72 |
| 10-1.13 CONSTRUCTION AREA SIGNS | 72 |
| 10-1.14 MAINTAINING TRAFFIC..... | 73 |
| 10-1.15 CLOSURE REQUIREMENTS AND CONDITIONS | 76 |
| CLOSURE SCHEDULE | 76 |
| CONTINGENCY PLAN | 76 |
| LATE REOPENING OF CLOSURES | 76 |
| COMPENSATION | 77 |
| 10-1.16 CONSTRUCTION ZONE ENHANCED ENFORCEMENT | 77 |
| 10-1.17 TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE..... | 78 |
| STATIONARY LANE CLOSURE | 78 |
| MOVING LANE CLOSURE | 78 |
| PAYMENT | 79 |
| 10-1.18 TEMPORARY PAVEMENT DELINEATION | 79 |
| 10-1.19 PORTABLE CHANGEABLE MESSAGE SIGN..... | 81 |
| 10-1.20 TEMPORARY RAILING | 81 |
| 10-1.21 CHANNELIZER | 82 |
| 10-1.22 RELOCATE TEMPORARY RAILING (TYPE K) | 82 |
| 10-1.23 RELOCATE TEMPORARY CRASH CUSHION ARRAY (TU21)..... | 82 |
| 10-1.24 TEMPORARY CRASH CUSHION MODULE..... | 83 |
| GENERAL | 83 |
| MATERIALS..... | 83 |
| INSTALLATION | 84 |
| MEASUREMENT AND PAYMENT | 84 |
| 10-1.25 EXISTING HIGHWAY FACILITIES | 84 |
| 10-1.25A REMOVE FENCE | 84 |
| 10-1.25B REMOVE METAL BEAM GUARD RAILING | 84 |
| 10-1.25C REMOVE FLARE END SECTION | 85 |
| 10-1.25D REMOVE PAINTED TRAFFIC STRIPES..... | 85 |
| 10-1.25E REMOVE THERMOPLASTIC TRAFFIC STRIPE AND THERMOPLASTIC PAVEMENT MARKING | 85 |
| 10-1.25F REMOVE PAVEMENT MARKER | 85 |
| 10-1.25G REMOVE ROADSIDE SIGNS AND SIGN PANEL | 85 |
| 10-1.25H REMOVE AND SALVAGE SIGN STRUCTURE..... | 86 |
| 10-1.25I REMOVE AND SALVAGE OVERHEAD SIGN PANEL AND PANEL FRAME | 86 |
| 10-1.25J REMOVE SIGN OVERLAY..... | 86 |
| 10-1.25K REMOVE PIPE | 86 |
| 10-1.25L REMOVE HEADWALL | 86 |
| 10-1.25M REMOVE SEWER MANHOLE | 86 |
| 10-1.25N REMOVE SEWER PIPE..... | 86 |
| 10-1.25O REMOVE CONCRETE DRAINAGE INLET | 86 |
| 10-1.25P RECONSTRUCT SIGN STRUCTURE..... | 86 |
| 10-1.25Q RESET ROADSIDE SIGNS..... | 87 |
| 10-1.25R RELOCATE FENCE (TYPE BW, 6-STRAND, METAL POST)(SPECIAL) | 87 |
| 10-1.25S RELOCATE CRASH CUSHION | 87 |
| 10-1.25T RELOCATE SIGN PANEL..... | 87 |
| 10-1.25U RELOCATE METAL BEAM GUARD RAILING..... | 87 |
| 10-1.25V RELOCATE ROADSIDE SIGN | 88 |
| 10-1.25W ADJUST INLETS | 88 |
| 10-1.25X COLD PLANE ASPHALT CONCRETE PAVEMENT | 88 |
| 10-1.25Y REMOVE CONCRETE..... | 89 |
| 10-1.25Z REMOVE CRASH CUSHION | 89 |
| 10-1.26 RELOCATE ROADSIDE SIGN (STRAP AND SADDLE BRACKET METHOD)..... | 89 |
| 10-1.27 CLEARING AND GRUBBING..... | 89 |
| 10-1.28 WATERING | 90 |
| 10-1.29 EARTHWORK..... | 90 |
| 10-1.30 MATERIAL CONTAINING AERIALLY DEPOSITED LEAD | 90 |
| LEAD COMPLIANCE PLAN | 90 |

| | |
|--|-----|
| 10-1.31 EROSION CONTROL (TYPE D)..... | 90 |
| MATERIALS..... | 91 |
| APPLICATION | 92 |
| MEASUREMENT AND PAYMENT | 92 |
| 10-1.32 FINISHING ROADWAY..... | 93 |
| 10-1.33 AGGREGATE SUBBASE..... | 93 |
| 10-1.34 AGGREGATE BASES..... | 93 |
| 10-1.35 LEAN CONCRETE BASE | 94 |
| 10-1.36 ASPHALT CONCRETE | 94 |
| 10-1.37 LIME TREATED AGGREGATES..... | 98 |
| GENERAL..... | 98 |
| MATERIALS..... | 98 |
| PROPORTIONING | 99 |
| MIXING AND STORAGE..... | 101 |
| PRODUCTION DATA COLLECTION..... | 101 |
| CONTRACTOR QUALITY CONTROL..... | 101 |
| PAYMENT | 102 |
| 10-1.38 ASPHALT CONCRETE (MISCELLANEOUS AREAS)..... | 102 |
| 10-1.39 RUMBLE STRIP | 103 |
| 10-1.40 PILING | 103 |
| 10-1.41 CONCRETE STRUCTURES..... | 105 |
| 10-1.42 SOUND WALL | 106 |
| DESCRIPTION..... | 106 |
| SOUND WALL (MASONRY BLOCK)..... | 106 |
| 10-1.43 REINFORCEMENT | 108 |
| 10-1.44 SIGN STRUCTURES..... | 113 |
| 10-1.45 ROADSIDE SIGNS..... | 113 |
| 10-1.46 INSTALL FRAMED SIGN PANEL..... | 114 |
| 10-1.47 INSTALL SIGN OVERLAY | 114 |
| 10-1.48 ALTERNATIVE PIPE | 114 |
| 10-1.49 REINFORCED CONCRETE PIPE..... | 114 |
| 10-1.50 CORRUGATED STEEL PIPE..... | 115 |
| 10-1.51 OVERTSIDE DRAINS..... | 115 |
| 10-1.52 OVERTSIDE DRAIN | 115 |
| 10-1.53 MISCELLANEOUS FACILITIES..... | 115 |
| 10-1.54 SLOPE PROTECTION | 115 |
| 10-1.55 SLOPE PAVING | 115 |
| 10-1.56 MISCELLANEOUS CONCRETE CONSTRUCTION | 115 |
| 10-1.57 MISCELLANEOUS IRON AND STEEL..... | 115 |
| 10-1.58 DELINEATORS | 115 |
| 10-1.59 METAL BEAM GUARD RAILING | 116 |
| 10-1.60 TERMINAL SYSTEM (TYPE SRT)..... | 116 |
| 10-1.61 TERMINAL ANCHOR ASSEMBLY (TYPE CA) | 117 |
| 10-1.62 CABLE RAILING | 117 |
| 10-1.63 CONCRETE BARRIER(TYPE 27SV) | 117 |
| 10-L.64 CONCRETE BARRIER (TYPE K) | 117 |
| 10-1.65 THERMOPLASTIC TRAFFIC STRIPES AND PAVEMENT MARKINGS..... | 117 |
| 10-1.66 PAVEMENT MARKERS | 118 |
| SECTION 10-2. (BLANK) | 118 |
| SECTION 10-3. SIGNALS, LIGHTING AND ELECTRICAL SYSTEMS..... | 118 |
| 10-3.01 DESCRIPTION | 118 |
| 10-3.02 COST BREAK-DOWN | 118 |
| 10-3.03 FOUNDATIONS | 119 |
| 10-3.04 STANDARDS, STEEL PEDESTALS AND POSTS..... | 119 |
| 10-3.05 CONDUIT | 119 |
| 10-3.06 PULL BOXES | 119 |

| | |
|---|------------|
| 10-3.07 TRAFFIC PULL BOXES | 120 |
| 10-3.08 CONDUCTORS AND WIRING..... | 120 |
| 10-3.09 BONDING AND GROUNDING | 120 |
| 10-3.10 TESTING..... | 120 |
| 10-3.11 DETECTORS | 121 |
| 10-3.12 LUMINAIRES..... | 121 |
| 10-3.13 REMOVING, REINSTALLING OR SALVAGING ELECTRICAL EQUIPMENT..... | 121 |
| 10-3.14 PAYMENT | 121 |
| SECTION 11-1. QUALITY CONTROL / QUALITY ASSURANCE | 121 |
| SECTION 39: ASPHALT CONCRETE..... | 121 |
| 39-1 GENERAL | 121 |
| 39-1.01 DESCRIPTION | 122 |
| 39-2 MATERIALS..... | 122 |
| 39-2.01 ASPHALTS | 122 |
| 39-2.02 AGGREGATE | 122 |
| 39-2.03 ASPHALT CONCRETE MIXTURE | 123 |
| 39-2.04 PAVEMENT REINFORCING FABRIC | 124 |
| 39-3 ASPHALT CONCRETE MIX DESIGN PROPOSAL AND REVIEW | 124 |
| 39-3.01 CONTRACTOR MIX DESIGN PROPOSAL | 124 |
| 39-3.02 ENGINEER REVIEW OF ASPHALT CONCRETE MIX DESIGN | 125 |
| 39-4 CONTRACTOR QUALITY CONTROL..... | 126 |
| 39-4.01 GENERAL..... | 126 |
| 39-4.02 QUALITY CONTROL PLAN | 126 |
| 39-4.03 CONTRACTOR QUALITY CONTROL INSPECTION, SAMPLING, AND TESTING..... | 126 |
| 39-4.04 CONTRACTOR PROCESS CONTROL | 127 |
| 39-4.05 CONTRACTOR QUALITY CONTROL..... | 129 |
| 39-4.06 CHARTS AND RECORDS..... | 129 |
| 39-4.06A Compliance Charts..... | 129 |
| 39-4.06B Records of Inspection and Testing..... | 130 |
| 39-5 ENGINEER QUALITY ASSURANCE | 130 |
| 39-5.01 GENERAL..... | 130 |
| 39-5.02 SAMPLING AND TESTING FOR VERIFICATION..... | 130 |
| 39-5.03 VERIFICATION | 131 |
| 39-6 DISPUTE RESOLUTION | 132 |
| 39-6.01 GENERAL..... | 132 |
| 39-6.02 DURING THE ASPHALT CONCRETE MIX DESIGN REVIEW | 133 |
| 39-6.03 DURING THE PRODUCTION START-UP EVALUATION | 133 |
| 39-6.04 DURING PRODUCTION | 133 |
| 39-7 STORING, PROPORTIONING AND MIXING MATERIALS..... | 134 |
| 39-7.01 STORAGE | 134 |
| 39-7.01A Aggregate Cold Storage..... | 134 |
| 39-7.01B Aggregate Hot Storage..... | 134 |
| 39-7.01C Asphalt Binder Storage | 134 |
| 39-7.02 DRYING | 135 |
| 39-7.03 PROPORTIONING | 135 |
| 39-7.03A Proportioning for Batch Mixing | 135 |
| 39-7.03A(1) Batching Tolerances..... | 135 |
| 39-7.03A(2) Automatic Controls | 136 |
| 39-7.03B Proportioning for Continuous Mixing | 136 |
| 39-7.05 MIXING..... | 137 |
| 39-7.05A Batch Mixing | 137 |
| 39-7.05B Continuous Mixing | 138 |
| 39-7.06 ASPHALT CONCRETE STORAGE | 138 |
| 39-7.07 ASPHALT CONCRETE PLANTS | 138 |
| 39-8 SUBGRADE, PRIME COAT, PAINT BINDER (TACK COAT), AND PAVEMENT REINFORCING FABRIC | 138 |
| 39-8.01 SUBGRADE | 138 |
| 39-8.02 PRIME COAT AND PAINT BINDER (TACK COAT)..... | 139 |

| | |
|---|-----|
| 39-8.03 PAVEMENT REINFORCING FABRIC | 139 |
| 39-9 SPREADING AND COMPACTING EQUIPMENT..... | 140 |
| 39-9.01 SPREADING EQUIPMENT | 140 |
| 39-9.02 COMPACTING EQUIPMENT | 140 |
| 39-10 SPREADING AND COMPACTING | 140 |
| 39-10.01 GENERAL REQUIREMENTS | 140 |
| 39-10.02 PRODUCTION START-UP EVALUATION AND NUCLEAR DENSITY TEST STRIPS | 141 |
| 39-10.02A Production Start-Up Evaluation..... | 141 |
| 39-10.02B Nuclear Density Test Strip..... | 142 |
| 39-10.03 SPREADING | 143 |
| 39-10.04 COMPACTING | 143 |
| 39-11 ACCEPTANCE OF WORK | 144 |
| 39-11.01 GENERAL..... | 144 |
| 39-11.02 STATISTICAL EVALUATION AND DETERMINATION OF PAY FACTOR | 144 |
| 39-11.02A General..... | 144 |
| 39-11.02B Statistical Evaluation | 145 |
| 39-11.02C Pay Factor Determination and Compensation Adjustment..... | 146 |
| 39-12 MEASUREMENT AND PAYMENT | 149 |
| 39-12.01 MEASUREMENT | 149 |
| 39-12.02 PAYMENT | 150 |
| SECTION 12. (BLANK)..... | 151 |
| SECTION 13. (BLANK)..... | 151 |
| SECTION 14 FEDERAL REQUIREMENTS FOR FEDERAL-AID CONSTRUCTION PROJECTS | 152 |
| FEDERAL REQUIREMENT TRAINING SPECIAL PROVISIONS | 171 |

10-1.29 EARTHWORK

Earthwork shall conform to the provisions in Section 19, "Earthwork," of the Standard Specifications and these special provisions.

Surplus excavated material shall become the property of the Contractor and shall be disposed of outside the highway right of way.

Full compensation for disposing of surplus excavated material shall be considered as included in the contract price paid per cubic yard for roadway excavation and no additional compensation will be made.