

DEPARTMENT OF TRANSPORTATION
DIVISION OF ENGINEERING SERVICES
 OFFICE ENGINEER, MS 43
 1727 30TH STREET
 P.O. BOX 168041
 SACRAMENTO, CA 95816-8041
 FAX (916) 227-6214
 TTY (916) 227-8454



Flex your power!
Be energy efficient!

**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

January 24, 2007

10-Mpa-49-0.5/29.0
 10-0M2904

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in MARIPOSA COUNTY FROM MADERA COUNTY LINE TO ROUTE 140.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on January 31, 2007.

This addendum is being issued to revise the Project Plans, the Notice to Contractors and Special Provisions, and the Proposal and Contract.

On Project Plan Sheet No. 5, under "SEAL COAT ITEMS," "SCREENINGS (MEDIUM FINE)," is revised to read "SCREENINGS (MEDIUM)."

In the Special Provisions, Section 10-1.035, "STREET SWEEPING," is added as attached.

In the Special Provisions, Section 10-1.12, "Seal Coat," subsection "MATERIALS," subsection "Polymer Modified Asphaltic Emulsion," the eighth paragraph is revised as follows:

"The percentage composition by mass of screenings shall conform to the following grading:"

Medium 9.5-mm max. size	
Sieve Sizes	Percentage Passing
19.0-mm	—
12.5-mm	100
9.5-mm	85-100
4.75-mm	0-15
2.36-mm	0-5
1.18-mm	—
600-µm	—
75-µm	0-2

Addendum No. 1
Page 2
January 24, 2007

10-Mpa-49-0.5/29.0
10-0M2904

In the Proposal and Contract, the Engineer's Estimate Item 14 is added and Item 11 is deleted as attached.

To Proposal and Contract book holders:

Replace page 3 of the Engineer's Estimate in the Proposal with the attached revised page 3 of the Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the NOTICE TO CONTRACTORS section of the Notice to Contractors and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by confirmed facsimile to all book holders to ensure that each receives it. A copy of this addendum and the modified wage rates are available for the contractor's use on the Internet Site:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

MALCOLM DOUGHERTY
District Director
District 6 Central Region

Attachments

10-1.035 STREET SWEEPING

Street sweeping shall be conducted where sediment is tracked from the job site onto paved roads, as described in the approved Water Pollution Control Program (WPCP) in accordance with "Water Pollution Control" of these special provisions, and as directed by the Engineer.

Street sweeping shall be one of the water pollution control practices for sediment control. The WPCP shall include the use of street sweeping. Street sweeping shall be performed in accordance with Section 4, SC-7 in the Construction Site Best Management Practices Manual of the Caltrans Storm Water Quality Handbooks.

The number of street sweepers shall be as designated in the approved WPCP. The Contractor shall maintain at least one sweeper on the job site at all times during the period that sweeping work is required. Sweepers shall be self-loading, motorized, and shall have spray nozzles. Sweepers may include a vacuum apparatus.

Street sweeping shall start at the beginning of clearing and grubbing and shall continue until completion of the project, or as directed by the Engineer. Street sweeping shall be performed immediately after soil disturbing activities occur or offsite tracking of material is observed. Street sweeping shall be performed so that dust is minimized. If dust generation is excessive or sediment pickup is ineffective as determined by the Engineer, the use of water or a vacuum will be required.

At the option of the Contractor, collected material may be temporarily stockpiled in accordance with the approved WPCP. Collected material shall be disposed of at least once per week.

Material collected during street sweeping operations shall be disposed of in conformance with Section 7-1.13, "Disposal of Material Outside The Highway Right Of Way," of the Standard Specifications.

MEASUREMENT AND PAYMENT

The contract lump sum price paid for street sweeping shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in street sweeping, including disposal of collected material, as shown on the plans, as specified in the Standard Specifications, these special provisions, and as directed by the Engineer.

**ENGINEER'S ESTIMATE
10-0M2904**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	074016	CONSTRUCTION SITE MANAGEMENT	LS	LUMP SUM	LUMP SUM	
2	074017	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM	LUMP SUM	
3	074041	STREET SWEEPING	LS	LUMP SUM	LUMP SUM	
4 (S)	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
5 (S)	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
6 (S)	128650	PORTABLE CHANGEABLE MESSAGE SIGN	LS	LUMP SUM	LUMP SUM	
7 (S)	150715	REMOVE THERMOPLASTIC PAVEMENT MARKING	M2	75		
8	365001	SAND COVER	TONN	680		
9	374010	ASPHALTIC EMULSION (FLUSH COAT)	TONN	90		
10	374492	ASPHALTIC EMULSION (POLYMER MODIFIED)	TONN	540		
11	BLANK					
12 (S)	840515	THERMOPLASTIC PAVEMENT MARKING	M2	75		
13 (S)	840656	PAINT TRAFFIC STRIPE (2-COAT)	M	72 300		
14	375022	SCREENINGS (MEDIUM)	TONN	4570		

TOTAL BID: _____