

**DEPARTMENT OF TRANSPORTATION**

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30<sup>th</sup> Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

www.dot.ca.gov/hq/esc/oe



*Serious Drought.  
Help save water!*

September 2, 2015

10-Cal-26-8.8/9.1

10-0V2904

Project ID 1000020457

ACHSSTP-P026(030)E

Addendum No. 2

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN CALAVERAS COUNTY NEAR VALLEY SPRINGS FROM 0.1 MILE WEST OF ST ANDREWS ROAD TO 0.1 MILE EAST OF COUNTRY VIEW DRIVE, and Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Thursday, September 10, 2015.

This addendum is being issued to revise the project plans, the *Notice to Bidders and Special Provisions* and the *Bid* book.

Project plan sheets 1, 2, 4, and 17 are replaced and attached for substitution for the like-numbered sheets.

Project plan sheets 8A and 38A are added and attached for addition to the project plans.

Project plan sheet 38 is deleted.

In the *Notice to Bidders and Special Provisions*, in the "STANDARD PLANS LIST," the following Standard Plans are added as follows:

"RSP P74 and T65"

In the *Notice to Bidders and Special Provisions*, in the "STANDARD PLANS LIST," the following Standard Plan is deleted as follows:

"RSP P75."

In the Special Provisions, Section 5-1.36D, is replaced as attached.

In the Special Provisions, Section 14-1.02A, is added as attached.

In the Special Provisions, Section 14-6.02, is added as attached.

Addendum No. 2  
Page 2  
September 2, 2015

10-Cal-26-8.8/9.1  
10-0V2904  
Project ID 1000020457  
ACHSSTP-P026(030)E

In the *Bid* book, in the "Bid Item List," Items 66 and 67 are added.

In the *Bid* book, in the "Bid Item List," Item 65 is deleted.

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

**[http://www.dot.ca.gov/hq/esc/oe/electronic\\_bidding/electronic\\_bidding.html](http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html)**

Inform subcontractors and suppliers as necessary.

This addendum, EBS addendum file and attachments are available for the Contractors' download on the Web site:

**[http://www.dot.ca.gov/hq/esc/oe/project\\_ads\\_addenda/10/10-0V2904](http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/10/10-0V2904)**

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



SHARRI BENDER EHLERT  
District Director  
District 6 Central Region

Attachments

**Add to section 5-1.36D:**

Installation of the utilities shown in the following table requires coordination with your activities. Make the necessary arrangements with the utility company through the Engineer and submit a schedule:

1. Verified by a representative of the utility company
2. Allowing at least the time shown for the utility owner to complete its work

**Utility Relocation and Contractor-Arranged Time for the Relocation**

Utility	Utility address	Location	Days
Alpine Gas	Alpine Natural Gas PO Box 550 Valley Springs, CA 95252 Attn: Mike Lamond Phone: (209)-772-3006	Route 26 Station 105+41 Route 26 Station 110+42	7

**Add to section 14-1.02A:**

An ESA exists on this project.

Take the management measures shown in the following table for the corresponding ESA shown. Any access to an ESA other than that shown is prohibited.

**ESA Management**

Identification	Location	Management measures
Riparian	South of route 26, 50 feet from edge of pavement, from station 108+50 to station 115+00	Before start of work, protect the ESA by installing type ESA temporary fence.

**Replace section 14-6.02 with:**

**14-6.02 SPECIES PROTECTION**

**14-6.02A General**

Section 14-6.02 includes specifications for protecting regulated species or their habitat.

This project is within or near habitat for regulated species shown in the following table:

Species Name
Raptors

The Department anticipates nesting or attempted nesting by migratory and nongame birds from February 15 to September 1.

**14-6.02B Material**

Not Used

**14-6.02C Construction**

**14-6.02C(1) General**

Not Used

**14-6.02C(2) Protective Radius**

Upon discovery of a regulated species, stop construction activities within a 100 feet radius of the discovery or as defined in the table below. Immediately notify the Engineer. Do not resume activities until receiving notification from the Engineer.

Regulated species name	Protective radius
Raptors	300 ft

**14-6.02C(3) Protocols**

Not Used

**14-6.02C(4) Biological Resource Information**

Implement the following biological resource information requirements.

1. Request Migratory Bird Treaty Act (MBTA) surveys 15 days before beginning construction activities. No work is to begin without receiving biological clearance from the Engineer.
2. Workers must receive Biological Resource Information training before performing on-site work. Workers include laborers, tradesmen, material suppliers, equipment maintenance personnel, supervisors, foremen, office personnel, food vendors, and other personnel who stay on the job site longer than thirty minutes.

**14-6.02C(5) Protection Measures**

Within the project limits, implement the following protection measures:

1. All construction-related access must be kept within project limits and to existing highway and associated paved or graded shoulders or other designated areas clearly marked on the ground.
2. All food-related trash must be disposed of in closed garbage containers provided by you and the containers must be emptied weekly.
3. Pets and firearms are prohibited on work site.
4. Staging areas must be cleared by a Department Biologist 15 days prior to construction. Do not begin work until authorized.
5. Request nesting bird survey 15 days before the proposed start date of any construction-related activities. The Engineer may approve the work if a survey of the jobsite by the Department's biologist shows an absence of nesting birds.
6. If approved, you must commence requested activities within 15 days of the nesting bird survey completion. If you fail to commence the activities within 15 days or if there is a halt to the activities with a delay of more than 15 days, another nesting bird survey must be performed by the Department's biologist before these activities can recommence.
7. If nesting migratory birds are found during pre-construction survey, the appropriate no-work buffer must be established around nest/burrow. No work may commence within the buffer until authorized.
8. If an occupied nest is discovered, during construction, stop work within the protective radius immediately and notify the Engineer. Do not disturb birds or nests occupied by birds, hatchlings or eggs. Do not resume work until authorized.
9. A qualified Biologist will monitor the active nest and tree removal during construction activities to ensure that no interference with nesting activities occurs.
10. Notify the Engineer 7 days prior to tree removal,

**14-6.02C(6) Monitoring Schedule**

Monitor according to the following schedule:

Monitoring type	Schedule
Nesting bird	Daily
Tree removal	Daily

**14-6.02D Payment**

Not Used

**BID ITEM LIST  
10-0V2904**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
61	839584	ALTERNATIVE IN-LINE TERMINAL SYSTEM	EA	2		
62	840515	THERMOPLASTIC PAVEMENT MARKING	SQFT	280		
63	840560	THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	LF	4,810		
64	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	160		
65	BLANK					
66	141000	TEMPORARY FENCE (TYPE ESA)	LF	650		
67	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

**TOTAL BID:**

**\$**

---