

**DEPARTMENT OF TRANSPORTATION**

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30<sup>th</sup> Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

www.dot.ca.gov/hq/esc/oe



*Serious Drought.  
Help save water!*

August 15, 2014

10-Mer,Sta,SJ-5-32.2/32.5, 0.0/28.1, 0.0/R12.4

10-0V6604

Project ID 1000020667

ACNHPI-005-5(143)417E

Addendum No. 3

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN MERCED, STANISLAUS, AND SAN JOAQUIN COUNTIES NEAR LATHROP FROM GARZAS CREEK BRIDGE TO TOM PAINE SLOUGH BRIDGE.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Wednesday, September 3, 2014.

This addendum is being issued to revise the project plans, the *Notice to Bidders and Special Provisions*, the *Bid* book, and the Federal Minimum Wages with Modification Number 19 dated 08/08/2014.

Project plan sheet 2 is replaced and attached for substitution for the like-numbered sheet.

In the *Notice to Bidders*, the tenth paragraph is replaced as follows:

"Bids must be on a unit price basis."

In the *Notice to Bidders*, the eleventh paragraph is replaced as follows:

"Complete the work within 190 working days."

In the *Notice to Bidders*, the twelfth paragraph is deleted.

In the *Special Provisions*, Section 8, is deleted.

In the *Special Provisions*, Section 12-4.02A, the ninth paragraph is replaced as follows:

"The maximum length of the work area inside a lane closure other than one-way reversing traffic-control lane closure is 1.5 miles. Work area is as shown."

In the *Bid* book, the "Bid Item List," is replaced as attached.

Addendum No. 3  
Page 2  
August 15, 2014

10-Mer, Sta, SJ-5-32.2/32.5, 0.0/28.1, 0.0/R12.4  
10-0V6604  
Project ID 1000020667  
ACNHPI-005-5(143)417E

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

**[http://www.dot.ca.gov/hq/esc/oe/electronic\\_bidding/electronic\\_bidding.html](http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html)**

Inform subcontractors and suppliers as necessary.

This addendum, EBS addendum file, attachments and the modified wage rates are available for the Contractors' download on the Web site:

**[http://www.dot.ca.gov/hq/esc/oe/project\\_ads\\_addenda/10/10-0V6604](http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/10/10-0V6604)**

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



SHARRI BENDER EHLERT  
District Director  
District 6 Central Region

Attachments

**BID ITEM LIST****10-0V6604**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	070030	LEAD COMPLIANCE PLAN	LS	LUMP SUM	LUMP SUM	
2	080050	PROGRESS SCHEDULE (CRITICAL PATH METHOD)	LS	LUMP SUM	LUMP SUM	
3	090100	TIME-RELATED OVERHEAD (WDAY)	WDAY	190		
4	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
5	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
6	120165	CHANNELIZER (SURFACE MOUNTED)	EA	920		
7	128652	PORTABLE CHANGEABLE MESSAGE SIGN (LS)	LS	LUMP SUM	LUMP SUM	
8	129000	TEMPORARY RAILING (TYPE K)	LF	35,300		
9	129100	TEMPORARY CRASH CUSHION MODULE	EA	860		
10	130100	JOB SITE MANAGEMENT	LS	LUMP SUM	LUMP SUM	
11	130200	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM	LUMP SUM	
12	130620	TEMPORARY DRAINAGE INLET PROTECTION	EA	11		
13	130900	TEMPORARY CONCRETE WASHOUT	LS	LUMP SUM	LUMP SUM	
14	141103	REMOVE YELLOW THERMOPLASTIC TRAFFIC STRIPE (HAZARDOUS WASTE)	LF	476,000		
15	141120	TREATED WOOD WASTE	LB	208,000		
16	150661	REMOVE GUARDRAIL	LF	13,200		
17	150714	REMOVE THERMOPLASTIC TRAFFIC STRIPE	LF	65,400		
18	150715	REMOVE THERMOPLASTIC PAVEMENT MARKING	SQFT	5,250		
19	150722	REMOVE PAVEMENT MARKER	EA	25,600		
20	150771	REMOVE ASPHALT CONCRETE DIKE	LF	249,000		

**BID ITEM LIST****10-0V6604**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
21	150772	REMOVE CURB	LF	3,610		
22	150854	REMOVE CONCRETE PAVEMENT (CY)	CY	900		
23	152422	ADJUST MONUMENT COVER	EA	83		
24	152439	ADJUST FRAME AND GRATE TO GRADE	EA	11		
25	153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	366,000		
26	156590	REMOVE CRASH CUSHION (SAND FILLED)	EA	11		
27	160102	CLEARING AND GRUBBING (LS)	LS	LUMP SUM	LUMP SUM	
28	190185	SHOULDER BACKING	TON	29,000		
29	280015	LEAN CONCRETE BASE RAPID SETTING	CY	280		
30	360200	BASE BOND BREAKER	SQYD	1,630		
31	390011	PREPAVING INERTIAL PROFILER	LS	LUMP SUM	LUMP SUM	
32	390132	HOT MIX ASPHALT (TYPE A)	TON	71,600		
33	390137	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	TON	263,000		
34	394053	SHOULDER RUMBLE STRIP (HMA,GROUND-IN INDENTATIONS)	STA	8,040		
35	394060	DATA CORE	LS	LUMP SUM	LUMP SUM	
36	394073	PLACE HOT MIX ASPHALT DIKE (TYPE A)	LF	112,000		
37	394074	PLACE HOT MIX ASPHALT DIKE (TYPE C)	LF	1,820		
38	394076	PLACE HOT MIX ASPHALT DIKE (TYPE E)	LF	136,000		
39	397005	TACK COAT	TON	840		
40	401055	JOINTED PLAIN CONCRETE PAVEMENT (RSC)	CY	630		

**BID ITEM LIST****10-0V6604**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
41	414242	ISOLATION JOINT SEAL (PREFORMED COMPRESSION)	LF	1,270		
42	510081	AGGREGATE BASE (APPROACH SLAB)	CY	76		
43	510087	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	CY	759		
44	510800	PAVING NOTCH EXTENSION	CF	362		
45	519081	JOINT SEAL (MR 1/2")	LF	262		
46	519088	JOINT SEAL (MR 1")	LF	376		
47	691900	FLUME DOWNDRAIN	LF	20		
48	692101	TAPERED INLET	EA	1		
49	692361	FLUME ANCHOR ASSEMBLY	EA	1		
50	730020	MINOR CONCRETE (CURB) (CY)	CY	39		
51	820118	GUARD RAILING DELINEATOR	EA	880		
52	820134	OBJECT MARKER (TYPE P)	EA	120		
53	820151	OBJECT MARKER (TYPE L-1)	EA	120		
54	832007	MIDWEST GUARDRAIL SYSTEM (WOOD POST)	LF	5,070		
55	839221	DOUBLE MIDWEST GUARDRAIL SYSTEM (WOOD POST)	LF	10,200		
56	027577	CONCRETE BARRIER (TRANSITION)	LF	450		
57	839543	TRANSITION RAILING (TYPE WB-31)	EA	120		
58	839561	RAIL TENSIONING ASSEMBLY	EA	48		
59	839581	END ANCHOR ASSEMBLY (TYPE SFT)	EA	10		
60	839584	ALTERNATIVE IN-LINE TERMINAL SYSTEM	EA	13		

**BID ITEM LIST****10-0V6604**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
61	839585	ALTERNATIVE FLARED TERMINAL SYSTEM	EA	64		
62	027578	ALTERNATIVE CRASH CUSHION SYSTEM	EA	49		
63	840504	4" THERMOPLASTIC TRAFFIC STRIPE	LF	965,000		
64	840506	8" THERMOPLASTIC TRAFFIC STRIPE	LF	53,000		
65	840508	8" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 12-3)	LF	7,600		
66	840515	THERMOPLASTIC PAVEMENT MARKING	SQFT	5,250		
67	840525	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12)	LF	439,000		
68	840526	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 17-7)	LF	6,460		
69	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	25,600		
70	860090	MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION	LS	LUMP SUM	LUMP SUM	
71	027579	MODIFY VEHICLE CLASSIFICATION STATION	LS	LUMP SUM	LUMP SUM	
72	860931	TRAFFIC MONITORING STATION (LOCATION 1)	LS	LUMP SUM	LUMP SUM	
73	860932	TRAFFIC MONITORING STATION (LOCATION 2)	LS	LUMP SUM	LUMP SUM	
74	860933	TRAFFIC MONITORING STATION (LOCATION 3)	LS	LUMP SUM	LUMP SUM	
75	860934	TRAFFIC MONITORING STATION (LOCATION 4)	LS	LUMP SUM	LUMP SUM	
76	860935	TRAFFIC MONITORING STATION (LOCATION 5)	LS	LUMP SUM	LUMP SUM	
77	861503	MODIFY LIGHTING	LS	LUMP SUM	LUMP SUM	
78	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

**TOTAL BID:****\$**