

DEPARTMENT OF TRANSPORTATION
DIVISION OF ENGINEERING SERVICES
OFFICE ENGINEER
1727 30th Street MS-43
P.O. BOX 168041
SACRAMENTO, CA 95816-8041
FAX (916) 227-6214
TTY 711



*Flex your power!
Be energy efficient!*

October 21, 2011

10-SJ-99-29.0/30.8
10-0V8704
Project ID 1000020425
NH-P099(552)E

Addendum No. 2

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN SAN JOAQUIN COUNTY IN LODI FROM 0.5 MILE NORTH OF HARNEY LANE OVERCROSSING TO EAST PINE STREET OVERCROSSING..

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Tuesday, November 1, 2011.

This addendum is being issued to revise the Project Plans, the Notice to Bidders and Special Provisions, and the Bid book.

Project Plan Sheets 2, 15, and 16 are revised. Copies of the revised sheets are attached for substitution for the like-numbered sheets.

In the Special Provisions, Section 10-1.01, "ORDER OF WORK," the following paragraph is added after the first paragraph.

"All individual slab replacement work shall be done prior to grind and groove of concrete pavement."

Addendum No. 2
Page 2
October 21, 2011

10-SJ-99-29.0/30.8
10-0V8704
Project ID 1000020425
NH-P099(552)E

In the Bid book, in the "Bid Item List," Items 14, 15, 21, and 22 are revised.

To Bid book holders:

Replace pages 3 and 4 of the "Bid Item List" in the Bid book with the attached revised pages.3 and 4 of the Bid Item List. The revised Bid Item List is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This addendum and attachments are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/10/10-0V8704

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



SHARRI BENDER EHLERT
Interim District Director
District 6 Central Region

Attachments

BID ITEM LIST
10-0V8704

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	074016	CONSTRUCTION SITE MANAGEMENT	LS	LUMP SUM	LUMP SUM	
2	074017	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM	LUMP SUM	
3	074042	TEMPORARY CONCRETE WASHOUT (PORTABLE)	LS	LUMP SUM	LUMP SUM	
4	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
5	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
6	128650	PORTABLE CHANGEABLE MESSAGE SIGN	LS	LUMP SUM	LUMP SUM	
7	150662	REMOVE METAL BEAM GUARD RAILING	LF	1,470		
8	150715	REMOVE THERMOPLASTIC PAVEMENT MARKING	SQFT	560		
9	150771	REMOVE ASPHALT CONCRETE DIKE	LF	10,200		
10	153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	29,500		
11	156590	REMOVE CRASH CUSHION (SAND FILLED)	EA	2		
12	190110	LEAD COMPLIANCE PLAN	LS	LUMP SUM	LUMP SUM	
13	260201	CLASS 2 AGGREGATE BASE	CY	88		
14	374207	CRACK TREATMENT	LNMI	4.1		
15	390132	HOT MIX ASPHALT (TYPE A)	TON	4,430		
16	394050	RUMBLE STRIP	STA	190		
17	394073	PLACE HOT MIX ASPHALT DIKE (TYPE A)	LF	900		
18	394076	PLACE HOT MIX ASPHALT DIKE (TYPE E)	LF	3,540		
19	394077	PLACE HOT MIX ASPHALT DIKE (TYPE F)	LF	5,760		
20	397005	TACK COAT	TON	13		

BID ITEM LIST
10-0V8704

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
21	406050	DOWEL BAR (DRILL AND BOND)	LF	3,570		
22	411105	INDIVIDUAL SLAB REPLACEMENT (RSC)	CY	1,730		
23	021840	GRIND AND GROOVE EXISTING CONCRETE PAVEMENT	SQYD	27,000		
24	510502	MINOR CONCRETE (MINOR STRUCTURE)	CY	2		
25	731530	MINOR CONCRETE (TEXTURED PAVING)	SQFT	4,760		
26	820108	DELINEATOR (CLASS 2)	EA	18		
27	820151	OBJECT MARKER (TYPE L-1)	EA	6		
28	832001	METAL BEAM GUARD RAILING	LF	640		
29	021841	DOUBLE METAL BEAM GUARD RAILING	LF	50		
30	839302	SINGLE THRIE BEAM BARRIER (WOOD POST)	LF	220		
31	839541	TRANSITION RAILING (TYPE WB)	EA	5		
32	839561	RAIL TENSIONING ASSEMBLY	EA	3		
33	839581	END ANCHOR ASSEMBLY (TYPE SFT)	EA	2		
34	839585	ALTERNATIVE FLARED TERMINAL SYSTEM	EA	2		
35	021842	ALTERNATIVE CRASH CUSHION SYSTEM	EA	3		
36	839701	CONCRETE BARRIER (TYPE 60)	LF	160		
37	840504	4" THERMOPLASTIC TRAFFIC STRIPE	LF	19,700		
38	840506	8" THERMOPLASTIC TRAFFIC STRIPE	LF	1,010		
39	840515	THERMOPLASTIC PAVEMENT MARKING	SQFT	430		
40	840525	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12)	LF	9,240		