

# **INFORMATION HANDOUT**

**For Contract No. 10-0W8004**

**At 10-Tuo-Toulumne-27.4**

**Identified by**

**Project ID 101200063**

## **MATERIALS INFORMATION**

Summary of Foundation Recommendation Reports dated May 29, 2013.

Amendment to Foundation Report for Slope Stabilization (Issue date January 7, 2014)

Alternative in line terminal system

## Memorandum

*Flex your power!  
Be energy efficient!*

**To:** MR. GARY JOE  
Branch Chief  
Structure Design  
Bridge Design North  
Branch 17

Attention: AE Tern

**Date:** May 29, 2013

**File:** 10-Tuo-120  
PM 27.4  
EA: 10-0W8001  
EFIS: 1012000063  
Slope Stabilization

**From:** DEPARTMENT OF TRANSPORTATION  
DIVISION OF ENGINEERING SERVICES  
GEOTECHNICAL SERVICES – MS 5

**Subject:** Foundation Report

### Introduction

As requested, the Office of Geotechnical Design North (OGDN) is providing a Foundation Report (FR) for the slope stabilization project situated on the New Priest Grade at PM 27.4, State Route (SR) 120, in Tuolumne County. The slope stabilization project proposes to install soil nails stabilizing an existing Hilfiker wall that is slowly creeping down the embankment slope during the winter months.

### Project Description

The site is located on SR 120 in Tuolumne County, on the New Priest Grade between the towns of Moccasin to the west and Big Oak Flat to the east. This portion of SR 120 is a two-lane highway with many curves. At this location (PM 27.4), the roadway is about 24-foot in width with a two-foot paved shoulder on the WB side and a four-foot paved shoulder on the EB side. A Metal Beam Guardrail is situated adjacent to the EB side of the roadway, between the highway and the existing Hilfiker wall. A Vicinity Map and Aerial Photograph are provided on Plate 1.

According to as-built documents, the subject Hilfiker wall and other similar walls situated between PM R24.2 and PM 29.0 were constructed to widen SR 120 to accommodate longer vehicles reaching Yosemite National Park after the Ferguson Slide closed Highway 140 in 2006. In general, the Hilfiker wall was constructed with vertical panels composed of 4-gauge welded wire on 4-inch spacing and ¼-inch mesh backing. The vertical panels are visible from the outside face of the wall and vary between 18-inch and four-foot in height. Each vertical panel is connected to a horizontal panel of similar design. No information for the length of the

horizontal panels and wall thickness is available. It is presumably our anticipation that the horizontal panels span the entire wall thickness and that the maximum wall thickness is 10 feet.

Through verbal communications with Mr. Cliff Rice, Caltrans Construction Supervisor, the wall was constructed using surplus materials from the Ferguson Slide temporary bridge abutment construction. The wall is maximum 82-feet in length, extending from Station 10+73.76 to Station 11+48.88. The wall was constructed in four lifts/rows with the face of each row set about 1- to 2-foot behind its adjacent lower row, resulting a battered wall face of approximately 1/2:1 (h:v) through four rows. The bottom row is four-foot in height and each successive upper row is 18-inch to two-foot in height. With four total rows and one-foot of additional gravel at the top the total wall height is about eleven-foot.

The project proposes to stabilize the wall utilizing soil nails. Our office recommends the use of 20-foot long nails to extend through the existing Hilfiker wall into the native bedrock. It is recommended that the nails be spaced five-foot horizontally in each row. Vertical spacing is set as 2 to 2.5-ft to accommodate the existing wall construction. Plates 2 and 3 (attached) depict the Plan View and Profile View of the wall.

### Field Investigation and Testing Program

An investigation including field reconnaissance, review of historic and recent aerial photography and subsurface sampling was performed for this project. One mud-rotary boring was drilled at the site to determine the subsurface conditions for the soil nail wall design.

### Laboratory Testing Program

Unconfined Compressive Strength (UCS) testing was performed on rock cores collected during the subsurface investigation. Test results are summarized in Table 1. UCS values in the table may not be representative of the subsurface conditions of the site as only limited samples were suitable to be submitted for testing.

**Table 1 Rock Unconfined Compressive Strength**

<i>Boring</i>	<i>Depth (ft)</i>	<i>Elevation (ft)</i>	<i>UCS(pounds per square inch)</i>
R-12-001	17	1908	2435
R-12-001	22.5	1902.5	3055**
R-12-001	30	1895	*
R-12-001	35	1890	2640**
R-12-001	41	1884	5534

\*Sample fell apart while preparing for testing – Not suitable for testing

\*\*Test specimen length/diameter ratio was no in compliance with test method

## **Climate**

Information regarding the climate in the project area is provided by the Western Regional Climate Center period of record from 1948 to 2012. The closest station in proximity to the project location is at Groveland 2 (Station #043669). The average annual total precipitation is 36.18 inches. The majority of this precipitation falls between October and May. The average daily minimum temperature ranges from 30.1° F in January to 56° F in July, and the average daily maximum temperature ranges from 51.4° F in December to 91.2° F in July. Yearly updates are available at the Western Regional Climate Center web site.

## **Topography and Drainage**

Based on the USGS Topographic Map of the Moccasin Quadrangle, 1987 (Plate 3) and our field investigation, the project is situated in an area of steep topography ranging in elevations from about 1750-foot above mean sea level in Grizzly Gulch below the site to about 2250-foot on the ridge above the project location. The town of Moccasin and the Moccasin Reservoir are situated to the southwest of the project location. The general drainage of the area is through Grizzly Gulch toward the southwest into Moccasin reservoir. Surface drainage is handled through a series of drainage swales adjacent to the cut slopes into drop inlets and culverts, letting out through oversized drains at the base of the embankment slopes.

## **Site Geology**

According to the Geologic Map of the Chinese Camp and Moccasin quadrangles, Tuolumne County, California (USGS, 1976), the bedrock that outcrops in the cut slope adjacent to the eastbound lane consists of the Calaveras Formation (Pzcv) which is an albite-epidot-actinolite greenschist which is a fine-grained metavolcanic rock with an andesite composition. This unit was originally deposited as volcanic flows that have been sub-sequentially metamorphosed.

The geology of the boring coincided with the geologic map and consisted of 6-inches of asphalt concrete overlying about 8-inches of aggregate base rock (A.B.). The roadway section overlies about four-feet of artificial fill that consisted of silty CLAY that was orange-brown, moist to wet and contained mostly fines with some fine to coarse SAND and some fine to coarse rounded gravel. Trace cobbles were encountered. Under the fill was weathered METAVOLCANIC BEDROCK that was orange, and brown, to a depth of about 30-feet bgs where fresh, unweathered bedrock was encountered.

## **Seismic Recommendations**

Based on the *Caltrans Seismic Design Procedure*, the following active faults could seismically impact the project site. The Caltrans ARS Online Tool was used to estimate the Peak Ground

Acceleration (pga) at the site with an estimated average shear wave velocity ( $V_{S30}$ ) of 2500 ft/sec (760 m/s) for the rock mass at the site. The estimated pga is 0.2g.

**Table 2 Active Faults**

<i>Fault Name</i>	<i>Fault ID</i>	<i>Fault Type</i>	<i>Moment magnitude of maximum credible earthquake</i>	<i>Distance from fault to project site (miles)</i>
Foothills Fault System (Bowie Flat Fault)	419	N	6.3	13
San Andreas (Santa Cruz Mts)	158	SS	8	96
San Andreas (Peninsula)	134	SS	8	107

### **Design Criteria of Soil Nails**

The design for the soil nail stabilized Hilfiker wall was analyzed using Slope/W, which is part of the Geostudio 2007 suite (Version 7.2) from Geo-Slope, LLC. A two dimensional model was developed based on the existing wall/slope geometry. Engineering parameters for rock and other materials were based on field observation of the adjacent cut-slope in conjunction with laboratory analysis and the program Roclab. Plate 4 is a conceptual cross section showing the anticipated wall location and subsurface conditions.

The existing slope/wall was modeled such that when dry (during the summer months), the wall would have a Factor of Safety (FOS) of just above one. When wet (during the winter months) the FOS falls to just below one. With three rows of soil nails installed in the top three lifts of the existing wall, the minimum FOS is increased to 1.56 with a static loading and high water table. The minimum FOS is 1.16 with seismic loading and high water table. Plate 5 shows the satisfying FOS of the Hilfiker wall that is stabilized with soil nails.

The following criteria were used in the analysis:

1. Minimum factor of safety for static loading,  $FOS_{static} = 1.5$ , and for seismic loading,  $FOS_{seismic} = 1.1$
2. Maximum design wall height = 11-ft
3. Maximum horizontal and vertical spacing of nails = 5.0-foot horizontal and 2 to 2.5-foot vertical
4. Inclination angle of the nails to the horizontal = 15 degrees
5. Minimum diameter of drilled hole = 6.0-inch
6. Maximum vertical distance from bottom of wall to the bottom row of soil nails = 5-foot.

7. Three zones are recommended for design and construction control using the following parameters:

Fill of Existing Wall:

Total unit weight,  $\gamma = 130$  pcf  
Friction angle,  $\phi = 35^\circ$   
Cohesion,  $c = 0$  psf

Weathered Rock:

Total unit weight,  $\gamma = 120$  pcf  
Friction angle,  $\phi = 28^\circ$   
Cohesion,  $c = 200$  psf  
Design Pullout Resistance,  $Q_d = 3280$  lb/lf

Fresh Rock:

Total unit weight,  $\gamma = 150$  pcf  
Friction angle,  $\phi = 35$   
Cohesion,  $c = 500$  psf  
Design Pullout Resistance,  $Q_d = 4863$  lb/lf

8. Minimum Punching shear capacity = 35 kips
9. Nail Bar Size Diameter = 1.13-inch (#9)
10. Maximum vertical distance between top of wall and the top most row of soil nails = 2-foot
11. Minimum embedment length of soil nails from face of wall = 20-foot

### Stability Testing

For the purpose of stability and load testing, it is recommended that the entire wall be treated as a single zone.

### Nail Verification Testing

In the event of failing verification tests, Geotechnical Design North should be contacted as soon as possible to determine the cause of failure and provide guidance.

### Nail Proof Testing

Approximately five nail proof tests are anticipated (10% of production nails). When we are provided with a copy of the General Plan we will provide a wall elevation view showing the recommended locations of the proof tests.

## **Construction Considerations**

The typical sequence of excavation, nail installation and facing installation shall follow the Caltrans 2010 Standard Plans and Specifications and the Special Provisions for this project.

### **A. Construction Staging**

Construction should commence during the dry season so as the FOS of the existing wall is at its highest.

The construction should be staged such that the top row of anchors is installed first, prior to drilling equipment accessing the top of the wall. The following two lifts can then be installed in successive order from top down. Trench plate may be used to minimize damage to the top of the wall, the roadway and to bridge the interface between the wall and roadway paving, while placing the top row of nails.

### **B. Excavation and Drilling Difficulties**

Drilling in very hard rock is anticipated. It is anticipated that caving may occur in moderately to highly fractured rock. The drill holes may need casing where this condition is encountered. The Contractor should utilize an appropriate drilling method and/or equipment to mitigate such ground conditions.

Drilling through the existing Hilfiker Wall will necessitate the use of casing to prevent caving, limit grout migration and aid with progression of the hole until native earth materials are encountered.

### **C. Grout and Test Nail**

Due to the existence of moderately to highly fractured rock material at the project site, some loss of grout material may occur during the grouting operation. If such situation occurs, a representative of Geotechnical Services should be contacted for further recommendations.

## **Project Information**

Standard Special Provisions SSP-280, "Project Information", discloses to bidders and contractors a list of pertinent information available for their inspection prior to bid opening. The following is an excerpt for SSP-280 disclosing information originating from Geotechnical Services. Items listed to be included in the Information Handout will be provided in Acrobat (.pdf) format to addressee(s) of this report via electronic mail.

*Data and information attached with the project plans are:*

A. None

Data and information included in the Information Handout provided to the bidders and contractors are:

A. Foundation Report for Soil Nail Retaining Wall dated May 29, 2013

Data and Information available for observation at the Transportation Laboratory:


A. Cores

### Pertinent Reports and Investigations


The following presents a list of references used in preparation of this report.

- Caltrans, Project Plans for Construction on State Highway in Tuolumne County on Priest Grade at Various Locations, Contract No. 10-0P7704, February 27, 2008.
- Caltrans, Email Recommendations for Repair at 10-Mpa-49 PM 27.4, May, 2011.
- Caltrans, District Preliminary Geotechnical Design Report, June, 14 2012.
- Western Regional Climate Center for 1989-2007.
- Topographic Map of the Moccasin Quadrangle, United States Geological Survey, 1987
- Morgan, B.A., 1976, Geologic map of the Chinese Camp and Moccasin quadrangles, Tuolumne County, California: U.S. Geological Survey, Miscellaneous Field Studies Map MF-840, scale 1:24000

If you have any questions or comments, please call Brandon Badeker at (916) 227-1046, or Thomas Song at (916) 227-1057.



BRANDON BADEKER, CEG  
Engineering Geologist  
Geotechnical Design - North



THOMAS SONG, P.E.  
Transportation Engineer, Civil  
Geotechnical Design - North

Attachments:

MR. GARY JOE  
May 29, 2013  
Page 8



10-Tuo-120 PM 27.4  
Soil Nail Wall  
EA: 10-0W8001  
EFIS: 1012000063

- Plate 1: Vicinity Map/Aerial Photograph
- Plate 2: Plan View
- Plate 3: Wall Profile
- Plate 4: Slope Analysis Cross Section
- Plate 5: Cross Sections – Final Configuration

C: District Project Manager, Jes Padda  
GS Corporate, Shira Rajendra  
Structure Construction RE Pending File ([RE\\_pending\\_file@dot.ca.gov](mailto:RE_pending_file@dot.ca.gov))  
DES Office Engineer, Office of PS&E, John Stayton  
District Material Engineer, Dave Dhillon  
GS File Room ([gs\\_file\\_room@dot.ca.gov](mailto:gs_file_room@dot.ca.gov))

## Appendix A

### Figures



Maps adapted from Google Maps, 2013

CALTRANS



Division of Engineering Services  
 Geotechnical Services  
 Office of Geotechnical Design - North


EA: 10-0W8001

Date: May, 2013

## Vicinity Map/Aerial Photograph

Plate 1

10-Tuo-120 PM 27.4  
 Slope Stabilization



EA: 10-0W8001

Date: May, 2013

Plate 2

**Plan View**

**10-Tuo-120 PM 27.4**  
**Slope Stabilization**


CALTRANS



Division of Engineering Services  
Geotechnical Services  
Office of Geotechnical Design - North

← To Chinese Camp

To Groveland →



11+00 12+00

Reinforcement not shown for clarity

**ELEVATION**  
1" = 20'

LEGEND:  
■ Indicates Soil Nail

Plate 3

**Wall Profile**


**10-Tuo-120 PM 27.4**  
**Slope Stabilization**

EA: 10-0W8001

Date: May, 2013

CALTRANS  
Division of Engineering Services  
Geotechnical Services  
Office of Geotechnical Design - North





CALTRANS



Division of Engineering Services  
Geotechnical Services  
Office of Geotechnical Design - North

EA: 10-0W8001


Date: May, 2013

# Slope Analysis Cross Section

Plate 4


10-Tuo-120 PM 27.4  
Slope Stabilization

1.334



Dry Months Stability – FOS<sub>seismic</sub> = 1.334

1.165



Wet Months Stability – FOS<sub>seismic</sub> = 1.165

Scale: 1" = 20'

CALTRANS



Division of Engineering Services  
 Geotechnical Services  
 Office of Geotechnical Design - North

EA: 10-0W8001

Date: May, 2013

### Cross Sections – Final Configuration

Plate 5

10-Tuo-120 PM 27.4  
 Slope Stabilization

## Appendix B

### Laboratory Testing Information



**DIVISION OF  
ENGINEERING SERVICES  
OFFICE OF GEOTECHNICAL SUPPORT  
GEOTECHNICAL LABORATORY**  
5900 Folsom Boulevard  
Sacramento, CA 95819

**Date: 5/2/2013**

**To: Brandon Badeker / GDN**

**From: Lilibeth C. Purta / (916) 227-5239**

**RE: Laboratory Test Report -- EA: 10-0W8001  
Project: 1012000062  
GL 13-015**

---


**Final test results.**

**Note: All remaining test specimens will be disposed of in 30 calendar days from the release date of the final test results.**










**Test Summary**

Counter: 2432  
 Elapsed Time: 00:00:59  
 Operator: AZM  
 Sample: R-12-001-2  
 Resident Engineer:  
 Ticket: GL# 13-015  
 E.A. NUMBER: 10-0W8001  
 Procedure Name: Cores test for Soil  
 Start Date: 4/25/2013  
 Start Time: 5:29:38 PM  
 End Date: 4/25/2013  
 End Time: 5:30:37 PM  
 Workstation: D1K00YB1  
 Tested By: AZM  
 Lab: Q13-017

**Test Results**

Specimen Gage Length: 5.5400 in  
 Diameter: 2.3700 in  
 Area: 4.4115 in<sup>2</sup>  
 Maximum Load: 10740 lbf  
 Compressive Strength: 2435 psi






**Test Summary**

Counter: 2433  
 Elapsed Time: 00:01:19  
 Operator: AZM  
 Sample: R-12-001-3  
 Resident Engineer: AZM  
 Ticket: GL# 13-015  
 E.A.NUMBER: 10-0W8001  
 Procedure Name: Cores test for Soil  
 Start Date: 4/25/2013  
 Start Time: 5:37:11 PM  
 End Date: 4/25/2013  
 End Time: 5:38:30 PM  
 Workstation: D1K00YB1  
 Tested By: AZM  
 Lab: Q13-018

**Test Results**

Specimen Gage Length: 4.5600 in  
 Diameter: 2.3700 in  
 Area: 4.4115 in<sup>2</sup>  
 Maximum Load: 13476 lbf  
 Compressive Strength: 3055 psi






**Test Summary**

Counter: 2434  
 Elapsed Time: 00:01:05  
 Operator: AZM  
 Sample: R-12-001-5  
 Resident Engineer:  
 Ticket: GL# 13-015  
 E.A.NUMBER: 10-0W8001  
 Procedure Name: Cores test for Soil  
 Start Date: 4/25/2013  
 Start Time: 5:45:25 PM  
 End Date: 4/25/2013  
 End Time: 5:46:30 PM  
 Workstation: D1K00YB1  
 Tested By: AZM  
 Lab: Q13-020

**Test Results**

Specimen Gage Length: 4.4500 in  
 Diameter: 2.3500 in  
 Area: 4.3374 in<sup>2</sup>  
 Maximum Load: 11451 lbf  
 Compressive Strength: 2640 psi





**Test Summary**

Counter: 2435  
 Elapsed Time: 00:02:29  
 Operator: AZM  
 Sample: R-12-001-6  
 Resident Engineer:  
 Ticket: GL# 13-015  
 E.A. NUMBER: 10-0W8001  
 Procedure Name: Cores test for Soil  
 Start Date: 4/25/2013  
 Start Time: 6:00:08 PM  
 End Date: 4/25/2013  
 End Time: 6:02:37 PM  
 Workstation: D1K00YB1  
 Tested By: AZM  
 Lab: Q13-021

**Test Results**

Specimen Gage Length: 5.5100 in  
 Diameter: 2.3400 in  
 Area: 4.3005 in<sup>2</sup>  
 Maximum Load: 23801 lbf  
 Compressive Strength: 5534 psi





Division of Engineering Services  
Geotechnical Laboratory

# Point Load Strength Index

Dist-EA: 10-0W8001

Dist-Co-Rte-PM: TUO-120-27.4/

GI Tracking No.: 13-015

Report Date: May 2, 2013

Sample ID	Test Type	Length, L (mm)	Width, W (mm)	Initial Distance Between Contact Points, D (mm)	Final Distance Between Contact Points, D' (mm)	Equivalent Diameter, De (mm)	Failure Load, P (lbs)	Uncorrected Point Load Strength Index Is (psi)	Point Load Strength Index Is (50) (psi)	Remarks
R-12-001_4	A-L		59.7	39.5	35	51.58	3046.56	738.8	749	



R-12-001\_4

No Image Available

No Image Available

No Image Available

Test Type Abbreviations: D- Diametral, A - Axial, B - Block, I - Irregular Lump

Orientation of Load Direction (if anisotropic): P - Perpendicular to plane of weakness, L - Parallel to plane of weakness

---

Appendix C  
Slope/W Analysis

# SLOPE/W Analysis

Report generated using GeoStudio 2007, version 7.21. Copyright © 1991-2013 GEO-SLOPE International Ltd.

## File Information

Revision Number: 54  
Last Edited By: Badeker, Brandon H@DOT  
Date: 5/23/2013  
Time: 11:25:13 AM  
File Name: Wall Analysis Final Dry.gsz  
Directory: N:\RGE\Geotech North\BBadeker\10-TUO-120 PM 27.6\  
Last Solved Date: 5/23/2013  
Last Solved Time: 11:25:16 AM

## Project Settings

Length(L) Units: feet  
Time(t) Units: Seconds  
Force(F) Units: lbf  
Pressure(p) Units: psf  
Strength Units: psf  
Unit Weight of Water: 62.4 pcf  
View: 2D

## Analysis Settings

### SLOPE/W Analysis

Kind: SLOPE/W  
Method: Morgenstern-Price  
Settings  
    Side Function  
        Interslice force function option: Half-Sine  
    PWP Conditions Source: (none)  
Slip Surface  
    Direction of movement: Right to Left  
    Use Passive Mode: No  
    Slip Surface Option: Entry and Exit  
    Critical slip surfaces saved: 1  
    Optimize Critical Slip Surface Location: No  
Tension Crack  
    Tension Crack Option: Tension Crack Line  
    Percentage Wet: 1  
    Tension Crack Fluid Unit Weight: 62.4 pcf  
FOS Distribution

FOS Calculation Option: Constant  
Advanced  
Number of Slices: 30  
Optimization Tolerance: 0.01  
Minimum Slip Surface Depth: 0.1 ft  
Optimization Maximum Iterations: 2000  
Optimization Convergence Tolerance: 1e-007  
Starting Optimization Points: 8  
Ending Optimization Points: 16  
Complete Passes per Insertion: 1  
Driving Side Maximum Convex Angle: 5 °  
Resisting Side Maximum Convex Angle: 1 °

## Materials

### Wall Fill

Model: Mohr-Coulomb  
Unit Weight: 135 pcf  
Cohesion: 0 psf  
Phi: 40 °  
Phi-B: 0 °

### Roadway Section

Model: Mohr-Coulomb  
Unit Weight: 120 pcf  
Cohesion: 0 psf  
Phi: 32 °  
Phi-B: 0 °

### Colluvium

Model: Mohr-Coulomb  
Unit Weight: 110 pcf  
Cohesion: 50 psf  
Phi: 25 °  
Phi-B: 0 °

### Weathered Bedrock

Model: Mohr-Coulomb  
Unit Weight: 120 pcf  
Cohesion: 200 psf  
Phi: 28 °  
Phi-B: 0 °

### Fresh Bedrock

Model: Mohr-Coulomb  
Unit Weight: 150 pcf

Cohesion: 500 psf  
Phi: 35 °  
Phi-B: 0 °

## Slip Surface Entry and Exit

Left Projection: Range  
Left-Zone Left Coordinate: (3, 7) ft  
Left-Zone Right Coordinate: (8, 12) ft  
Left-Zone Increment: 4  
Right Projection: Point  
Right Coordinate: (24, 23) ft  
Right-Zone Increment: 4  
Radius Increments: 4

## Slip Surface Limits

Left Coordinate: (-7, -3) ft  
Right Coordinate: (50.275862, 27.689655) ft

## Surcharge Loads

### Surcharge Load 1

Surcharge (Unit Weight): 240 pcf  
Direction: Vertical

#### Coordinates

	X (ft)	Y (ft)
	24.011414	24.000013
	46	23

## Seismic Loads

Horz Seismic Load: 0.2  
Ignore seismic load in strength: No

## Reinforcements

### Reinforcement 1

Type: Nail  
Outside Point: (12.000218, 21.002016) ft  
Inside Point: (31.548115, 15.764173) ft

Slip Surface Intersection: (22.25, 18.256) ft  
Total Length: 20.237472 ft  
Reinforcement Direction: 165 °  
Applied Load Option: Variable  
F of S Dependent: No  
Bond Diameter: 0.5 ft  
Bond Safety Factor: 1.5  
Bond Skin Friction: 1500 psf  
Bond Resistance: 314.15927 lbs/ft  
Nail Spacing: 5 ft  
Bar Capacity: 10000 lbs  
Bar Safety Factor: 1  
Bar Load: 2000 lbs  
Load Distribution: Even along reinf.  
Shear Capacity: 0 lbs  
Shear Safety Factor: 1  
Shear Option: Parallel to Slip  
Shear Load: 0 lbs  
Applied Load: 2000 lbs  
Nail Load Used: 2000 lbs  
Resisting Force Used: 314.16 lbs/ft  
Available Bond Length: 9.6263 ft  
Required Bond Length: 6.3662 ft  
Governing Component: Bar

## Reinforcement 2

Type: Nail  
Outside Point: (10.9999, 19.000092) ft  
Inside Point: (30.525276, 13.768283) ft  
Slip Surface Intersection: (21.102, 16.293) ft  
Total Length: 20.214157 ft  
Reinforcement Direction: 165 °  
Applied Load Option: Variable  
F of S Dependent: No  
Bond Diameter: 0.31830989 ft  
Bond Safety Factor: 1.5  
Bond Skin Friction: 1500 psf  
Bond Resistance: 200 lbs/ft  
Nail Spacing: 5 ft  
Bar Capacity: 10000 lbs  
Bar Safety Factor: 1  
Bar Load: 2000 lbs  
Load Distribution: Even along reinf.  
Shear Capacity: 0 lbs  
Shear Safety Factor: 1  
Shear Option: Parallel to Slip  
Shear Load: 0 lbs  
Applied Load: 2000 lbs

Nail Load Used: 1951.2 lbs  
Resisting Force Used: 200 lbs/ft  
Available Bond Length: 9.7558 ft  
Required Bond Length: 9.7558 ft  
Governing Component: Bond

### Reinforcement 3

Type: Nail  
Outside Point: (9.183397, 16.702264) ft  
Inside Point: (28.501913, 11.525883) ft  
Slip Surface Intersection: (19.328, 13.984) ft  
Total Length: 20 ft  
Reinforcement Direction: 165 °  
Applied Load Option: Variable  
F of S Dependent: No  
Bond Diameter: 0.31830989 ft  
Bond Safety Factor: 1.5  
Bond Skin Friction: 1500 psf  
Bond Resistance: 200 lbs/ft  
Nail Spacing: 5 ft  
Bar Capacity: 10000 lbs  
Bar Safety Factor: 1  
Bar Load: 2000 lbs  
Load Distribution: Even along reinf.  
Shear Capacity: 0 lbs  
Shear Safety Factor: 1  
Shear Option: Parallel to Slip  
Shear Load: 0 lbs  
Applied Load: 2000 lbs  
Nail Load Used: 1899.4 lbs  
Resisting Force Used: 200 lbs/ft  
Available Bond Length: 9.4971 ft  
Required Bond Length: 9.4971 ft  
Governing Component: Bond

### Tension Crack Line

	X (ft)	Y (ft)
	6	10
	10	12
	17	12
	24	23

## Regions

	Material	Points	Area (ft <sup>2</sup> )
Region 1	Wall Fill	1,2,3,4,5,6,7,8,9,10,11,21,12,15	117.5
Region 2	Colluvium	1,13,14,15	60
Region 3	Weathered Bedrock	15,14,16,17,18,19,20,21,12	276
Region 4	Roadway Section	11,21,20,22,23	34
Region 5	Fresh Bedrock	23,24,25,26,27,28,16,17,18,19,20,22	1070.5

## Points

	X (ft)	Y (ft)
Point 1	8	12
Point 2	8	16
Point 3	9	16
Point 4	9	18
Point 5	11	18
Point 6	11	20
Point 7	12	20
Point 8	12	22
Point 9	13	22
Point 10	14	23
Point 11	24	23
Point 12	17	12
Point 13	-7	-3
Point 14	-3	-3
Point 15	12	12
Point 16	9	-3
Point 17	22	10
Point 18	25	12
Point 19	30	16
Point 20	36	21
Point 21	23	21
Point 22	46	21
Point 23	46	22
Point 24	47	21
Point 25	48	22

Point 26	54	37
Point 27	60	39
Point 28	60	-3

## Critical Slip Surfaces

	Slip Surface	FOS	Center (ft)	Radius (ft)	Entry (ft)	Exit (ft)
1	4	1.334	(3.797, 27.736)	20.751	(24, 23)	(3, 7)

## Slices of Slip Surface: 4

	Slip Surface	X (ft)	Y (ft)	PWP (psf)	Base Normal Stress (psf)	Frictional Strength (psf)	Cohesive Strength (psf)
1	4	3.3565845	6.9924375	0	39.311437	18.331224	50
2	4	4.0697535	6.989571	0	111.75907	52.11411	50
3	4	4.7829225	7.011239	0	179.79591	83.840209	50
4	4	5.4960915	7.057519	0	244.44722	113.98761	50
5	4	6.20926	7.1285765	0	306.51479	142.93019	50
6	4	6.9224285	7.2246695	0	366.60492	170.95068	50
7	4	7.6395065	7.3469605	0	374.67191	199.21659	200
8	4	8.5	7.531305	0	885.69734	470.93363	200
9	4	9.3333335	7.7400015	0	1109.1542	589.74777	200
10	4	9.9999985	7.9367415	0	1073.1091	570.58224	200
11	4	10.6666665	8.1581545	0	1044.8068	555.5336	200
12	4	11.5	8.475106	0	1253.555	666.52699	200
13	4	12.5	8.9061965	0	1455.0795	773.67951	200
14	4	13.5	9.4019405	0	1443.1359	767.32895	200
15	4	14.375	9.8888465	0	1433.5018	762.20644	200
16	4	15.125	10.355545	0	1378.2721	732.84026	200
17	4	15.875	10.868505	0	1316.0405	699.75116	200
18	4	16.625	11.432105	0	1244.8447	661.89568	200
19	4	17.3333335	12.01418	0	1158.6366	616.058	200
20	4	18	12.614285	0	1066.707	567.17817	200
21	4	18.6666665	13.270035	0	966.2818	513.78115	200
22	4	19.3333335	13.98944	0	857.24452	455.805	200
23	4	20	14.78318	0	729.42043	387.83972	200

24	4	20.666665	15.66608	0	594.35719	316.02533	200
25	4	21.333335	16.65976	0	452.65219	240.67944	200
26	4	22	17.798115	0	283.60587	150.79592	200
27	4	22.666665	19.1405	0	98.95037	52.612845	200
28	4	23.21199	20.43615	0	-34.483703	-18.33531	200
29	4	23.71199	22	0	51.266134	32.034636	0

# Memorandum

*Flex your power!  
Be energy efficient!*

**To:** Rene Coria  
Bridge Design Branch 17

**Date:** January 7, 2014

**File:** 10-TUO-120 PM 27.4  
EA 10-0W8001  
1012000063

Attention:

**From:** DEPARTMENT OF TRANSPORTATION  
DIVISION OF ENGINEERING SERVICES  
Geotechnical Services  
Office of Geotechnical Design – South 1  
Branch A

**Subject:** Amendment to Foundation Report for Slope Stabilization (Issue Date: May 29, 2013)

In response to the request from the Office of Bridge Design, the Office of Geotechnical Design South 1 (OGDS1) prepared this amendment to change the slope stabilization method from a soil nail wall to a soldier pile cantilever wall, and provide geotechnical recommendations for the proposed wall. This change was proposed by as a result of constructability review and field observation of existing Hilfiker wall performed in December 2014. The bulging and out of plumb of exiting wall and very wet and soft condition of the fill materials behind the wall rendered the originally recommended and planned soil nail wall difficult to construct.

The recommendations and construction consideration for the design of the soil nail wall presented in the report issued on May 29, 2013 are superseded by this amendment.

## Recommendations

Based on the foundation report and subsurface exploration performed on November 16 2012, following engineering properties should be used to estimate earth pressure coefficient and corresponding lateral earth pressure for the proposed wall design.

Depth <sup>(1)</sup> (ft)	Soil Type	Unit Weight (lb/ft <sup>3</sup> )	Friction Angle (degree)	Cohesion (lb/ft <sup>2</sup> )
0 to 10	Fill <sup>(2)</sup>	125	28	0
10 to 25	Weathered <sup>(3)</sup> Rock	120	28	200
25 to	Rock	150	35	500

(1) Depth starts from existing ground at the proposed wall location.

(2) According to Caltrans Construction, the existing walls constructed from extra materials from the Ferguson Slide temporary bridge abutments.

(3) Weathered rock properties should be used for design purpose only and hard excavation through this material should be anticipated.

The above engineering parameters have been assumed to arrive at a conservative design and must be used for design purpose only. These conservatively assumed values cannot be used for the selection of equipment and construction method.

Design wall height is assumed to be 10 feet and the diameter of drilled hole should be at least 4 inches larger than the greatest dimension of H-beam.

### **Construction Consideration**

Section 49-4.03B Drilled Holes through Rock Material and Pile Substitutions:

Based on LOTB, hard excavation through weathered and fresh rock materials during pile installation should be expected.

If you have any question regarding this report, please contact Seungwoon Han.

RENE CORIA

1/7/2014

Page 3


EA 10-0W8001

1012000063





A handwritten signature in black ink, appearing to read "Seungwoon Han", written over a horizontal line.


Seungwoon Han, Ph.D, P.E.  
Transportation Engineer




TRAFFIC →




OPTIONAL FLARED INSTALLATION  
25:1 maximum flare rate



Post #1 Connection Detail



Impact Head Connection Detail



SECTION A-A  
Post #2

ITEM	QTY	BILL OF MATERIALS	ITEM NO.
A	1	IMPACT HEAD	S3000
B	1	W-BEAM GUARDRAIL END SECTION, 12 Ga.	MGS-SF1303
C	1	FIRST POST TOP (6X6X $\frac{1}{2}$ Tube)	TPHP1A
D	1	FIRST POST BOTTOM (6' W6X15)	TPHP1B
E	1	SECOND POST ASSEMBLY TOP	UHP2A
F	1	SECOND POST ASSEMBLY BOTTOM	HP3B
G	1	BEARING PLATE	E750
H	1	CABLE ANCHOR BOX	S760
J	1	BCT CABLE ANCHOR ASSEMBLY	E770

HARDWARE (ALL DIMENSIONS IN INCHES)			
a	2	5/16 x 1 HEX BOLT GRD 5	B5160104A
b	4	5/16 WASHER	W0516
c	2	5/16 HEX NUT	N0516
d	9	5/8 Dia. x 1 1/4 SPLICE BOLT (POST #2)	B580122
e	1	5/8 Dia. x 9 HEX BOLT GRD 5	B580904A
f	3	5/8 WASHER	W050
g	10	5/8 Dia. H.G.R NUT	N050
h	1	3/4 Dia. x 8 1/2 HEX BOLT GRD A449	B340854A
j	1	3/4 Dia. HEX NUT	N030
k	2	1 ANCHOR CABLE HEX NUT	N100
l	2	1 ANCHOR CABLE WASHER	W100
m	8	CABLE ANCHOR BOX SHOULDER BOLT	SB58A
n	8	1/2 A325 STRUCTURAL NUT	N055A
o	16	1 1/16 OD x 9/16 ID A325 STR. WASHER	W050A

GENERAL NOTES:

- All bolts, nuts, cable assemblies, cable anchors and bearing plates shall be galvanized.
- The lower sections of the Posts 1&2 shall not protrude more than 4 in above the ground (measured along a 5' cord). Site grading may be necessary to meet this requirement.
- The lower sections of the hinged posts should not be driven with the upper post attached. If the post is placed in a drilled hole, the backfill material must be satisfactorily compacted to prevent settlement.
- When competent rock is encountered, a 12"  $\varnothing$  post hole, 20 in. deep cored into the rock surface may be used if approved by the engineer for post 1. Granular material will be placed in the bottom of the hole, approximately 2.5" deep to provide drainage. The first post can be field cut to length, placed in the hole and backfilled with suitable backfill. The soil plate may be trimmed if required.
- A site evaluation should be considered if there is less than 25' between the outlet side of the terminal and any adjacent driving lane.
- The breakaway cable assembly must be taut. A locking device (vice grips or channel lock pliers) should be used to prevent the cable from twisting when tightening nuts.




SKT-SP-MGS Terminal  
Midwest Guardrail System  
31" Top of Rail

Drawing Name: SKT-SP-S-MGS  
Scale: None

Sheet: 1  
Date: 02/24/10  
By: JRR  
Rev: 0


Find No.	QTY	No.	Description	UOM
1	1	BSI-1310027-00	XLITE, CRIMPED POST HOLES, GALV	EA
2	1	BSI-1012066-00	POST II, X-LITE, GALV	EA
3	3	BSI-1012078-00	LINE POST, X-LITE, GALV	EA
4	1	BSI-1012103-00	IMPACT HEAD, X-LITE, GALV	EA
5	1	BSI-1012093-00	SLIDER PANEL, FRONT, X-LITE, GALV	EA
6	1	BSI-1012090-00	Slider Bracket, X-Lite	EA
7	1	BSI-1012096-00	BACK SLIDER PANEL, X-LITE, GALV	EA
8	1	BSI-1102001-KT	Ground Strut Kit, X-Lite	EA
9	1	BSI-1012104-00	Cable Anchor Assembly, X-Lite	EA
10	2	KD80123	Kit, X-Tension Shear Bolt,	EA
11	1	BSI-1102027-00	WASHER, SQUARE, X-LITE, GALV	EA
12	4	B090534	W-Beam Composite Blockout Bin,	EA
13	16	4001115	Guardrail Bolt 5/8-11x 1 1/4	EA
14	2	2000464	Bolt CH 5/8-11x1 1/2 Gr5 MGal	EA
15	4	2000465	Bolt CH 5/8-11x9 Gr5 MGal	EA
16	22	4001116	Guardrail Nut Recessed 5/8-11	EA
17	1	2001580	Wshr 1 F436 Structural Gal	EA
18	3	4000443	W-Beam Guardrail RWM02a	EA
19	1	BSI-1106016-KT	X-Lite Soil Plate Kit	EA
20	1	BSI-1303005-00	Bracket, X-Lite, Cable Retenti	EA
21	1	BSI-1310016-KT	Transition Kit, MGS, X-Lite	EA
22	1	BSI-1310024-00	XLITE, CRIMPED POST SLOTS, GALV	EA
23	1	MANXLT	X-Lite Tangent Installation	EA



- INSTALL SLIDER PANEL, FRONT (ITEM 5) TO FIRST W-BEAM GUARDRAIL PANEL USING ITEMS 13 & 16. HEX NUTS TO BE ON TRAFFIC SIDE.
- INSTALL SLIDER BRACKET (ITEM 6) TO SECOND W-BEAM GUARDRAIL PANEL USING ITEMS 13 & 16.
- AFTER STEPS 1 & 2 SECURE FIRST AND SECOND W-BEAM GUARDRAIL PANEL USING ITEMS 7, 13 & 16. HEX NUTS TO BE ON TRAFFIC SIDE.
- SLOT ON POSTS 1 AND 2 TO FACE GUARDRAIL PANEL.
- IF ROCK OR STIFF SOIL IS ENCOUNTERED, THE POST AND SOIL PLATE MAY BE INSTALLED BY AUGERING AND BACKFILLING THE HOLE. EXTRA CARE MUST BE TAKEN TO PREVENT SETTLEMENT OR LATERAL DISPLACEMENT OF THE POST. BACKFILL MATERIAL SHALL BE COMPACTED TO OPTIMUM COMPACTION.
- IF ROCK IS ENCOUNTERED, THE SOIL PLATE MAY BE MODIFIED IF APPROVED BY THE PROJECT ENGINEER.

© 2010 BARRIER SYSTEMS INC. THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF BARRIER SYSTEMS INC. ANY REPRODUCTION IN PART OR WHOLE WITHOUT THE WRITTEN PERMISSION OF BARRIER SYSTEMS INC. IS PROHIBITED.		UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES. TOLERANCES ARE: FRACTIONS DECIMAL ANGLES ±1/16 .XX ±.03 ±1/2° .XXX ±.010		INTERPRET DIMENSIONS AND TOLERANCES PER ASME Y14.5-1994		<b>BARRIER SYSTEMS</b> A LINDSAY TRANSPORTATION SOLUTIONS COMPANY 3333 Vaca Valley Parkway Ste 800 Vacaville, CA 95688 Tel: 888-800-3691 www.barriersystemsinc.com	
<b>APPROVALS</b> DRAWN BY: JMT DRAWN DATE: 10/09/2013 APPR'D BY: GAD APPR'D DATE: 10/09/13				THIRD ANGLE PROJECTION DO NOT SCALE DRAWING		TITLE: <b>X-LITE SYSTEM ASSEMBLY, TANGENT, TRANSITION TO MGS</b> SIZE: B DWG NO.: XLTSUS-MGS SCALE: 1:40 SHEET: 1 OF 2	
		B 2220 01/23/14 A 2165 11/13/13 0 2151 10/09/13		REV ECN# DATE		REV. B	

Doc. B100108



ITEM NO.	PART NUMBER	DESCRIPTION	QTY	UOM
1	BSI-1301252-KT	X-Tension Terminal Comp, 31 in	1	EACH
2	K070202	X-Tension Hardware Kit, GT.	1	EACH
3	K070206	X-Tension System Hardware Kit,	1	EACH
4	K070210	X-Tension GT Guardrail	1	EACH
5	B061100	BSL I-Beam Post, Middle, X350	1	EACH
6	MANXT1	X-TENSION Installation Manual	1	EACH

- NOTES: UNLESS OTHERWISE SPECIFIED.
- SYSTEM TO BE INSTALLED PER MANUFACTURER SPECIFICATIONS.
  - ONLY TIGHTEN THE CABLE ASSEMBLIES USING THE NUTS AT THE CABLE BRACKET (SEE DETAIL 'D'). DO NOT TIGHTEN THE CABLES AT THE FRONT OF THE GROUND ANCHOR.
  - WHEN DRIVING STEEL POST, ENSURE THAT A DRIVING CAP WITH TIMBER OR PLASTIC INSERT IS USED TO PREVENT DAMAGE TO THE GALVANIZING TO THE TOP OF THE POST.

<small>©2012 BARRIER SYSTEMS INC. THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF BARRIER SYSTEMS INC. ANY REPRODUCTION IN PART OR WHOLE WITHOUT THE WRITTEN PERMISSION OF BARRIER SYSTEMS INC. IS PROHIBITED.</small>		<small>UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES. TOLERANCES ARE:</small> <small>FRACTIONS DECIMAL ANGLES</small> <small>± 1/16 .003 ± .03 ± 1/2°</small> <small>XXX ± .010</small> <small>INTERPRET DIMENSIONS AND TOLERANCES PER ASME Y14.5-1994</small>	
<b>APPROVALS</b>			
DRAWN BY:	NMV	THIRD ANGLE PROJECTION	
DRAWN DATE:	2/08/13		
APPR'D BY:	JMT		
APPR'D DATE:	2/08/13		

		<small>BARRIER SYSTEMS INC. 3333 Voco Valley Parkway, Ste 800 Vacaville, CA 95688 Tel: 800-800-5691 www.barriersystemsinc.com</small>	
<b>TITLE</b> X-TENSION GUARDRAIL TERMINAL SYSTEM STEEL POST WITH COMPOSITE BLOCKOUT 31" RAIL HEIGHT			
SIZE	DWG NO.	REV.	
B		B	
SCALE	1:50	SHEET	1 OF 1