

DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30th Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

www.dot.ca.gov/hq/esc/oe*Flex your power!
Be energy efficient!*

March 11, 2014

10-SJ-4-14.2/15.9
10-0X3804
Project ID 1012000263

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN SAN JOAQUIN COUNTY IN STOCKTON FROM CORDES RANCH ROAD UNDERCROSSING TO ROUTE 5/4 SEPARATION.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Wednesday, March 26, 2014.

This addendum is being issued to revise the *Notice to Bidders and Special Provisions* and the *Bid* book.

In the *Special Provisions*, Section 39-1.35, is added as attached.

In the *Bid* book, in the "Bid Item List," Item 27 is added.

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html

Inform subcontractors and suppliers as necessary.

This addendum, EBS addendum file, and attachments are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/10/10-0X3804

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

A handwritten signature in blue ink that reads "Sharris Bender Ehlert".

SHARRI BENDER EHLERT
District Director
District 6 Central Region

Attachments

Replace section 39-1.35 with:

39-1.35 INTELLIGENT COMPACTION FOR HOT MIX ASPHALT

39-1.35A General

39-1.35A(1) Summary

Section 39-1.35 includes specifications for compaction of HMA using intelligent compaction. Intelligent compaction uses vibratory rollers equipped with measurement devices and a documentation system that produce data for standardized software Veda. For Veda, go to www.intelligentcompaction.com. Use Veda software to analyze the data for coverage uniformity, HMA temperature, and intelligent compaction measurement values.

Use intelligent compaction rollers for breakdown and intermediate compaction. Do not collect intelligent compaction measurement values for stiffness when the compacted HMA layer is 0.15 foot or less.

Create project layout files for the intelligent compaction system from the project plans.

39-1.35A(2) Definitions

California Coordinate System of 1983 (CCS83): A set of 6 geographic zones or coordinate systems designed for specific regions of the State of California, the boundaries of which follow county lines. CCS83 is based on NAD83. When a project crosses state plane zone boundaries, a single zone will be used for the entire project.

Coordinated Universal Time (UTC): A time measurement system commonly referred to as Greenwich Mean Time (GMT) based on a 24-hour time scale from the mean solar time at the Earth's prime meridian (zero degrees longitude) located near Greenwich, England.

Foot: Unit of measurement equal to U.S. survey foot.

Geodetic Coordinates: A coordinate system to describe a position in longitude, latitude, and altitude above the imaginary ellipsoid surface based on a specific geodetic datum. The NAD83 datum is required for use with CCS83 State Plane Coordinates.

Global Positioning System (GPS): A space-based satellite navigation system that provides location and time information in all weather, anywhere on or near the Earth to determine the location in geodetic coordinates. GPS refers to all GPS-related signals including US GPS, and other Global Navigation Satellite Systems (GNSS). GPS satellite signals are subject to interference from canyons, buildings, trees or even fencing. Not all locations are suitable for GPS techniques, and it is your responsibility to determine if the site conditions are practical for GPS, and to notify the Engineer if they are not.

GPS Base Station: A single ground-based system consisting of a GPS receiver, GPS antenna, and telemetry equipment (typically radio and radio antenna or cellular phone) to provide L1/L2 differential GPS correction signals to other GPS receivers.

GPS Rover: A portable L1/L2 GPS antenna, mount, and receiver with telemetry equipment for Real Time in-situ point measurements.

GPS Correction Service Subscription: A service that can be subscribed to receive differential GPS correction signals for higher accuracy GPS positioning without the need of a GPS Base Station. Signals are normally received via cellular wireless data services. Examples of GPS correction service subscriptions are: Trimble VRS™, Leica Smart RTK™, Topcon TopNet™ or OmniSTAR™.

GPS Site Calibration or Localization: A process to establish a relationship between the observed GPS coordinates and the known grid coordinates.

Grid: A Cartesian system of XY (or North-East) coordinates utilizing the California State Plane Coordinates, known as the California Coordinate System of 1983 (CCS 83).

Intelligent Compaction Measurement Value (ICMV): A generic term for all intelligent compaction measurements in units specific to each roller manufacturer.

CONTRACT NO. 10-0X3804
ADDED PER ADDENDUM NO. 1 DATED MARCH 11, 2014

Network Real Time Kinematic (Network RTK): A system that uses multiple bases in real-time to provide high-accuracy GPS positioning within the coverage area that is generally larger than that covered by a single GPS base station.

Real Time Kinematic Global Positioning System (RTK-GPS): A system based on the use of carrier phase measurements of the available GPS signals where a single GPS base station or RTK network provides the corrections in order to achieve centimeter-level accuracy in real time.

39-1.35A(3) Submittals

39-1.35A(3)(a) General

Not used

39-1.35A(3)(b) Just-In-Time Training

At the time of JMF submittal, submit a list of names participating in the just-in-time training. Identify each participant's name, employer, title, and role in intelligent compaction.

39-1.35A(3)(c) GPS Site Calibration or Localization Report and Check Testing

Submit GPS site calibration or localization report and check testing results for intelligent compaction rollers within 1 business day of calibration or check testing.

39-1.35A(3)(d) Data and Software Analysis Results

39-1.35A(3)(d)(i) General

Within 1 business day of HMA placement submit:

1. Electronic data from intelligent compaction rollers in file format readable by Veda
2. Hardcopy and Adobe pdf file of the HMA compaction quality control report from data analysis performed using Veda software.
3. Post processed Veda data file type *.icp used for creating the HMA compaction quality control report

When a test strip is required submit:

1. Test strip data including:
 - 1.1. Nuclear gage density per location
 - 1.2. GPS measured coordinates per location
 - 1.3. Nuclear gage correlation to core densities
2. All passes compaction curves from Veda
3. All passes correlation analysis report from Veda

39-1.35A(3)(d)(ii) Data

Submit intelligent compaction information and data elements using Veda. You may combine roller data for multiple rollers operating in echelon into a section file.

Name the intelligent compaction data file using:

YYYYMMDD_TTCCRRR_D_L_W_B_E_X_PT_Data

where:

YYYY = year

MM = Month, leading zero

DD = Day of month, leading zero

TT = District, leading zero

CCC = County, 2 or 3 letter abbreviation as shown in section 1-1.08

RRR = Route number, no leading zeros

D = Traffic direction as NB, SB, WB, or EB

L = Lane number from left to right in direction of travel

B = Beginning station to the nearest foot (i.e., 10+20) or beginning post mile to the nearest hundredth (i.e., 25.06) no leading zero

E = Ending station to the nearest foot (i.e., 14+20) or ending post mile to the nearest hundredth (i.e., 28.06) no leading zero

X = HMA layer number, 1, 2 ... etc.

PT = Pavement Type (i.e., HMA, RHMA, HMA-O, RHMA-O, RHMA-G, etc.)

Use the following header information for each intelligent compaction data file or section:

Item No.	Description
1	Section Title
2	Machine Manufacture
3	Machine Type
4	Machine Model
5	Drum Width (inch)
6	Drum Diameter (inch)
7	Machine Weight (ton)
8	Name index of intelligent compaction measurement values (IC-MV)
9	Unit index for IC-MV
10	Reporting resolution for independent IC-MVs – 90 degrees to the roller moving direction (mm)
11	Reporting resolution for independent IC-MVs – in the roller moving direction (mm)
12	CCS83 Zone
13	Offset to UTC (hrs)
14	Number of IC data points

note:

IC-MV = Intelligent Compaction – Measurement Value

Use the following data field names for each intelligent compaction data point:

Item No.	Data Field Name	Example of Data
1	Date Stamp (YYYYMMDD)	20080701
2	Time Stamp (HHMMSS.SS -military format)	090504.00 (9 hr 5 min. 4.00 s.)
3	Longitude (decimal degrees or degrees minutes-seconds)	94.85920403
4	Latitude (decimal degrees or degrees-minutes-seconds)	45.22777335
5	Easting (Foot)	6,096,666.000
6	Northing (Foot)	1,524,166.650
7	Elevation (Foot)	339.9450
8	Roller pass number	2
9	Direction index	1 forward, 2 reverse
10	Roller speed (mph)	2.0
11	Vibration on	1 for yes, 2 for no
12	Frequency (vpm)	3500.0
13	Amplitude (inch)	0.0236
14	Surface temperature (°F)	270
15	Intelligent compaction measurement values	20.0

Provide either items 3 and 4 or items 5 and 6. The GPS coordinate for each intelligent compaction data point recorded in data files must be at the center of the front drum.

The size of data mesh after post processing must be less than 1.5 feet by 1.5 feet in the X and Y directions.

39-1.35A(3)(d)(iii) Software Analysis Results

Analyze the intelligent compaction data daily using Veda and include target values for passes, HMA temperature, and intelligent compaction measurement values. For a fixed interval report use interval length of 100 feet.

For each day of production, prepare a HMA compaction quality control report that includes:

1. Final coverage histogram
2. Final coverage fixed interval report
3. All passes histogram
4. Color layout plots of:
 - 4.1. Roller passes
 - 4.2. HMA temperature for first coverage of breakdown compaction.
 - 4.3. HMA temperature for final coverage of intermediate compaction.
 - 4.4. Intelligent compaction measurement value for final coverage of intermediate compaction when required.

Plots must be scaled to be legible and may be 11 by 17 inches.

Name the post processed Veda data file using:

YYYYMMDD_TTCCRRR_D_L_W_B_E_X_PT. _Veda

where:

YYYY = year

MM = Month, leading zero

DD = Day of month, leading zero

TT = District, leading zero

CCC = County, 2 or 3 letter abbreviation as shown in section 1-1.08

RRR = Route number, no leading zeros

D = Traffic direction as NB, SB, WB, or EB

L = Lane number from left to right in direction of travel

B = Beginning station to the nearest foot (i.e., 10+20) or beginning post mile to the nearest hundredth (i.e., 25.06) no leading zero

E = Ending station to the nearest foot (i.e., 14+20) or ending post mile to the nearest hundredth (i.e., 28.06) no leading zero

X = HMA layer number, 1, 2 ...etc.

PT = Pavement Type (i.e., HMA, RHMA, HMA-O, RHMA-O, RHMA-G, etc.)

39-1.35A(4) Quality Control and Assurance

39-1.35A(4)(a) General

Not Used

39-1.35A(4)(b) Technical Representative

A technical representative from the roller manufacturer must be on site during the initial setup and verification testing of the intelligent compaction rollers and first 2 days of production. If requested, the roller representative must assist the Engineer with data management using Veda including intelligent compaction data input and processing.

39-1.35A(4)(c) Just-in-Time Training

Provide just-in-time training onsite or near the project site for your personnel and Department project personnel. Schedule the just-in-time training with the Engineer at a mutually agreed time and place. Provide training materials for 4 Department personnel. Provide an enclosed facility with electrical availability for visual presentations.

The training must be at least 4 hours in duration and include the following topics:

1. Background information for the specific intelligent compaction system to be used
2. Setup and checks for intelligent compaction system including:
 - 2.1. GPS receiver
 - 2.2. GPS base-station
 - 2.3. GPS rovers
 - 2.4. Rollers
3. Operation of the intelligent compaction system on the rollers:
 - 3.1. Setup data collection
 - 3.2. Start/stop of data recording
 - 3.3. On-board display options
4. Transferring raw intelligent compaction data from the rollers via USB connections
5. Operation of vendor's software to open and view raw intelligent compaction data files and exporting all-passes and proofing data files in Veda-compatible format
6. Operation of Veda software to:
 - 6.1. Import the exported all-passes and proofing data files
 - 6.2. Inspect the intelligent compaction maps
 - 6.3. Input point test data
 - 6.4. Perform statistical analysis
 - 6.5. Produce reports for project requirements
7. Coverage uniformity requirements
8. When a test strip is required, method for establishing target intelligent compaction measurement value.

The following personnel must attend the just-in-time training:

1. Project Manager
2. Superintendent
3. Technical representative for intelligent compaction rollers
4. Intelligent Compaction Quality Control Technicians
5. Roller Operators
5. HMA paving foreman

39-1.35A(4)(d) Quality Control

30-6.01A(4)(d)(i) General

Intelligent compaction provides quality control for Method compaction under section 39-3 by monitoring:

1. Number of roller passes
2. HMA temperature for first coverage of breakdown compaction
3. HMA temperature at the completion of intermediate compaction

When HMA thickness is greater than 0.15 foot, intelligent compaction provides quality control method for the intelligent compaction measurement value that is correlated to the specified HMA target density.

Intelligent compaction measurement values are report only and not used for compaction acceptance.

30-1.35(4)(d)(ii) Test Strip

If the HMA layer thickness is greater than 0.15 foot, on the first day of placement of each layer of HMA construct a test strip at least 600 feet long to determine the compaction curve. The compaction curve must be created by Veda and relate the number of roller passes to intelligent compaction measurement values. Nuclear gages must be correlated with density cores under Part 2 of California Test 375.

After each roller pass, use a nuclear gage to estimate the density of the material and a GPS rover to measure the positions of at least 10 locations uniformly spaced throughout the test strip. Record the density reading, the number of roller passes, and GPS coordinates for each location. Continue roller passes and collecting nuclear gage density readings until the density remains constant or decreases.

The estimated target density must be the peak of the nuclear gage density readings within the compaction temperature range for the HMA mixture. The target intelligent compaction measurement value is the point when the increase in the intelligent compaction measurement value of the material between passes is less than 5 percent on the compaction curve.

Use the Veda generated correlation analysis report to establish production target intelligent compaction measurement value based on specified target density (% Gmm) that meets the specified in-place compaction requirements. Correlation analysis report is the linear regression between intelligent compaction measurement value and percent of density.

39-1.35A(4)(d)(iii) Quality Control Technician

During HMA compaction provide a quality control technician to be responsible full time for:

1. GPS site calibration or localization and upload to all GPS receivers
2. GPS check testing for the intelligent compaction rollers and rovers
3. Accuracy verification of the temperature sensor by comparing to a NIST traceable standard. The equipment temperature sensor measurement must be within +/- 3 degrees F of NIST traceable standard.
4. Test section construction to establish target compaction pass counts and target values for the stiffness of the HMA using nuclear gauges, pavement cores, and intelligent compaction rollers
5. Construction operation monitoring of the intelligent compaction rollers
6. Quality control testing for pavement temperature and compaction.
7. Intelligent compaction data back up twice per day
8. Data downloading from rollers at the end of the work shift
9. On a daily basis analyze the data from the intelligent compaction rollers using Veda and produce a daily compaction quality control report

39-1.35B MATERIALS

Not Used

39-1.35C CONSTRUCTION

39-1.35C(1) General

Before the start of production upload the project plan file into the intelligent compaction data analysis software and depending on the roller manufacture, the on-board intelligent compaction computer.

39-1.35C(2) Equipment

39-1.35C(2)(a) Intelligent Compaction Rollers

In addition to the requirements of section 39, each intelligent compaction roller must:

1. Be self-propelled double-drum vibratory rollers equipped with accelerometers mounted in or about the drum to measure the interactions between the rollers and compacted materials in order to evaluate the applied compaction effort
2. Be equipped with non-contact temperature sensors for measuring pavement surface temperatures.
3. Produce intelligent compaction measurement values that represent the stiffness of the materials based on the vibration of the roller drums and the resulting response from the materials
4. Have mounted GPS receiver, antenna, and telemetry equipment to monitor the drum locations and track the number of passes
5. Include an integrated on-board documentation system capable of displaying real-time color-coded maps of intelligent compaction measurement values including location, number of passes, pavement surface temperatures, speeds, vibration frequencies and amplitudes of drums
6. Have a graphical user interface
7. Have capability of transferring the intelligent compaction data by means of a USB port

39-1.35C(2)(b) Global Positioning System

GPS must be real time kinematic using one of the following:

1. GPS Base station
2. Network real time kinematic (RTK)
3. Satellite based augmentation station system

GPS devices for this project must be set to the same consistent datum, coordinate system, CCS83 zone, and site calibration or localization. The CCS83 zone must be set to zone no. 3.

39-1.35C(2)(b)(i) Correction Signal Source

Provide either a GPS base station correction signal or a GPS correction service subscription. The GPS correction signal must be received by the GPS receivers on the intelligent compaction roller and the rovers during operations with a survey tolerance of not greater than 0.15 foot in both X and Y horizontal directions.

39-1.35C(2)(b)(ii) GPS Site Calibration or Localization and Check Testing

At least 2 business days before start of production, perform a GPS site calibration or localization to the survey control points indicated on the Project Control Map in the project plans. Perform a GPS site calibration or localization whenever the GPS base station is moved to a new location.

Before the start of daily production and using the same datum, conduct testing for the proper setup of the GPS, intelligent compaction rollers, and the GPS rover:

1. On a location nearby or within the project limits, the GPS base station, if required by the GPS, must be established and the intelligent compaction rollers and the GPS rover must be tied into the same base station
2. Verify that the roller and rover are working properly and that there is a connection with the base station
3. Verify the intelligent compaction roller GPS coordinates by:
 - 3.1. Stopping the intelligent compaction roller at a location
 - 3.2. Marking the location of both ends of the roller drum on the surface with a tee
 - 3.3. Recording the GPS measurements from the IC roller ensuring the distance offsets are applied so that the GPS coordinate is at the center of the front drum
 - 3.3. Moving the intelligent compaction roller from the marked location
 - 3.4. Finding the mid-point of the two marked ends of the roller and mark this location on the surface. This marked location is the theoretical center of the front drum.
 - 3.5. Using the GPS rover to measure GPS coordinates of the marked location and record the GPS measurements.
 - 3.6. Computing the difference between recorded intelligent compaction roller GPS coordinates and GPS rover recorded GPS measured coordinates. The differences of the coordinates in grid must be within 0.5 foot in both the horizontal axes X and Y.

39-1.35C(3) Compacting

During HMA compaction, monitor each roller's intelligent compaction graphical user interface display for roller passes and HMA temperature. When HMA layer thickness is greater than 0.15 foot, monitor the interface display for intelligent compaction measurement value.

39-1.35C(3)(i) Roller Coverage, HMA Temperature, and Intelligent Compaction Measurement Value

At least 90 percent coverage of the construction area must meet or exceed the number of roller passes specified. When the daily HMA compaction quality control report shows the specified roller passes are not met, take corrective action and notify the Engineer of action taken.

When the roller HMA temperature sensor indicates compaction temperatures are below specified temperatures take immediate corrective action.

At least 95 percent of the construction area must comply with the specified temperatures. When the daily HMA compaction quality control report indicates less than 95 percent of the construction area is completed after HMA is below the minimum specified temperature, implement corrective action before the next HMA placement day and notify the Engineer.

For HMA thickness greater than 0.15 foot, monitor the intelligent compaction measurement value against the target value established in the test strip. If intelligent compaction measurement value is 10 percent or more below the target value, verify that HMA compaction complies with density specified requirements with a nuclear gage.

If the daily average intelligent compaction measurement value is 20 percent or more below the target measurement value, establish an intelligent compaction measurement value using a test strip.

For HMA greater than 0.15 foot in layer thickness, when the daily average intelligent compaction measurement meets or exceeds the target value and density is verified, then the corrective action for number of passes and temperature is not required.

39-1.35D PAYMENT

Not used

BID ITEM LIST

10-0X3804

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
21	397005	TACK COAT	TON	32		
22	840515	THERMOPLASTIC PAVEMENT MARKING	SQFT	5,300		
23	840560	THERMOPLASTIC TRAFFIC STRIPE (SPRAYABLE)	LF	44,000		
24	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	1,040		
25	860090	MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION	LS	LUMP SUM	LUMP SUM	
26	861502	MODIFY SIGNAL	LS	LUMP SUM	LUMP SUM	
27	390030	INTELLIGENT COMPACTION	LS	LUMP SUM	LUMP SUM	

TOTAL BID:

\$
