


Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
10	SJ	99	18.5/20.8 29.3/33.7	38	65

 3/10/16
 REGISTERED CIVIL ENGINEER DATE

4-4-16
 PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

REGISTERED PROFESSIONAL ENGINEER
 RICHARD J. BOYER
 No. 75844
 Exp. 6/30/16
 CIVIL
 STATE OF CALIFORNIA

ROADWAY ITEMS

Loc No	PM	LOCATION	HMA (TYPE A)	TACK COAT	CI 2 AB	ROADWAY EXCAVATION	IMPORT BORROW	MINOR Conc (TEXTURED PAVING)	SLOPE PAVING CONCRETE
			TON	TON	CY	CY	CY	CY	CY
1	18.5	NB 99 TO FREMONT St OFF RAMP (GORE)			27	54		27	
2	18.8	WB 04 TO NB 99 ON RAMP (GORE)			33	66		33	
3	19.1	NB 99 TO FREMONT St OFF RAMP (GORE)			13	25		13	
4	19.3	FREMONT STREET (GORE PAVING)							
		NB 99 TO FREMONT St OFF RAMP			9	18		9	
		NB 99 TO FREMONT St OFF RAMP (LOOP)			16	31		16	
		SB 99 TO FREMONT St OFF RAMP			46	92		46	
5	20.3	SB 99 TO FREMONT St OFF RAMP (LOOP)			29	57		29	
		WATERLOO ROAD (GORE PAVING)							
		SB 99 TO WATERLOO Rd OFF RAMP (LOOP)			10	21		10	
		SB 99 TO WATERLOO Rd OFF RAMP			14	29		14	
6	20.8	NB 99 TO WATERLOO Rd OFF RAMP			11	22		11	
		CHEROKEE ROAD (GORE PAVING)							
		SB 99 TO CHEROKEE Rd OFF RAMP (LOOP)			8	16		8	
		SB 99 TO CHERPKEE Rd OFF RAMP			17	35		17	
7	29.3	NB 99 TO CHEROKEE Rd OFF RAMP (LOOP)			13	21		13	
		NB 99 TO CHEROKEE Rd OFF RAMP			17	33		17	
		KETTLEMAN LANE (GORE/SLOPE PAVING)							
		SB 99 FROM KETTLEMAN LANE ON RAMP (GORE)			37	73		37	
8	30.5	SB 99 TO KETTLEMAN LANE OFF RAMP (GORE)			37	73		37	
		SB 99 FROM KETTLEMAN LANE ON RAMP (MVP)	30	0.1	22	29			
		NB 99 TO KETTLEMAN LANE OFF RAMP (MVP)	30	0.1	22	29			
		NB 99 FROM KETTLEMAN LANE ON RAMP (MVP)	30	0.1	22	29			
9	30.7	E LODI AVENUE							
		NB 99 (SLOPE PAVING)				11.38	15.04		16.4
10	31.0	SB 99 (SLOOP PAVING)				19.41	7.22		8.1
		E PINE STREET							
11	31.0	NB 99 (SLOPE PAVING)				27.68	3.74		13.8
		SB 99 (SLOOP PAVING)				25.55	4.56		13.9
12	32.5	ROUTE 12/99 Sep (VICTOR Rd)							
		NB 99 (SLOPE PAVING)				20.1	40.6		26.5
13	33.7	SB 99 (SLOOP PAVING)				96.99	25.44		29.5
		E LOCKFORD STREET							
14	31.0	NB 99 (SLOPE PAVING)				14.6	14.57		17.1
		SB 99 (SLOOP PAVING)				18.95	18.24		20.5
15	32.5	WOODBIDGE ROAD							
		NB 99 (SLOPE PAVING)				34.01	2		9.4
16	32.5	SB 99 (SLOOP PAVING)				18.39			19.3
		NB 99 AT WOODBRIDGE Rd (MVP)	30	0.1	22	29			
17	33.7	ACAMPO ROAD							
		NB 99 (SLOPE PAVING)				32.93	1.27		22.1
18	33.7	SB 99 (SLOOP PAVING)				13.96	8.3		10.0
		SB 99 FROM ACAMPO Rd ON RAMP (MVP)	30	0.1	22	29			
19	33.7	SB 99 TO ACAMPO Rd OFF RAMP (MVP)	30	0.1	22	29			
		DIKE PAD				9.6			
20	33.7	FROM DIKE QUANTITIES				10.2			
		TOTAL	199.8	0.6	469	1174	141	337	207

NOTES:

- * - QUANTITY INCLUDED IN ROADWAY ITEMS TABLE.
- (N) - NOT A SEPARATE PAY ITEM, FOR INFORMATION ONLY.
- SEE CONSTRUCTION DETAILS FOR MORE INFORMATION
- ON VEGETATION CONTROL (MINOR CONCRETE).

ABBREVIATIONS:

- CCTV - CLOSED CIRCUIT TELEVISION CAMERA
 MVDS - MICROWAVE VEHICLE DETECTION SYSTEM
 RWIS - ROADSIDE WEATHER INFORMATION SYSTEM
 TMS - TRAFFIC MONITORING STATION
 N/O - NORTH OFF
 S/O - SOUTH OFF

3 TEMPORARY DRAINAGE INLET PROTECTION

SHEET	LOCATION	EA
L-7	ROUTE 99 Loc. 8 PM 30.5 50' Rt	1
L-7	ROUTE 99 Loc. 8 PM 30.5 42' Lt	1
L-7	ROUTE 99 Loc. 9 PM 30.75 50' Lt	1
L-7	ROUTE 99 Loc. 9 PM 30.75 42' Rt	1
TOTAL		4

DIKE QUANTITIES

Loc No	PM	LOCATION	PLACE HMA DIKE (TYPE E)	HMA
			LF	TON
7	29.3	NB ON RAMP FROM KETTLEMAN LN	131	3.4
13	33.7	SB ON RAMP FROM ACAMPO RD	131	3.4
13	33.7	SB OFF RAMP TO ACAMPO RD	131	3.4
TOTAL			393	10.2*

3 REPLACED PER ADDENDUM No. 3 DATED SEPTEMBER 6, 2016

SUMMARY OF QUANTITIES Q-1