

DEPARTMENT OF TRANSPORTATION

ESC/OE MS #43
1727 30TH Street, 2ND Floor
Sacramento, CA 95816



July 6, 2000

10-Sta-99-R21.2/R26.3
10-499504

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for highway planting on State highway in STANISLAUS COUNTY IN AND NEAR MODESTO FROM 0.2 km SOUTH OF HATCH ROAD OVERCROSSING TO 0.6 km NORTH OF HATCH ROAD OVERCROSSING AND FROM 0.3 km SOUTH OF CROWS LANDING OVERCROSSING TO 0.2 km NORTH OF L STREET OVERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on July 19, 2000.

This addendum is being issued to revise the Notice to Contractors and Special Provisions.

In the Special Provisions, Section 10-1.01A, "MATERIAL CONTAINING AERIALY DEPOSITED LEAD," is added as attached.

To Proposal and Contract book holders:

INDICATE RECEIPT OF THIS ADDENDUM BY FILLING IN THE NUMBER OF THIS ADDENDUM IN THE SPACE PROVIDED ON THE SIGNATURE PAGE OF THE PROPOSAL.

SUBMIT BIDS IN THE PROPOSAL AND CONTRACT BOOK YOU NOW POSSESS. HOLDERS WHO HAVE ALREADY MAILED THEIR BOOK WILL BE CONTACTED TO ARRANGE FOR THE RETURN OF THEIR BOOK.

INFORM SUBCONTRACTORS AND SUPPLIERS AS NECESSARY.

This office is sending this addendum by confirmed facsimile to all book holders to ensure that each receives it.

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

NICK YAMBAO, Chief
Office of Plans, Specifications & Estimates
Division of Office Engineer

Attachment

10-1. 01A MATERIAL CONTAINING AERIALY DEPOSITED LEAD

This work shall consist of handling soil contaminated by aerially deposited lead in conformance with the Standard Specifications and these special provisions.

Aerially deposited lead is typically found within the top 0.6-m of material in unpaved areas within the highway right of way. Levels of lead found near the project limits range from less than 30.84 to 48.44 mg/kg total lead, as analyzed by EPA Test Method 6010 or EPA Test Method 7000 series.

After the Contractor has completed handling materials containing aerially deposited lead, in conformance with the plans, Standard Specifications, and these special provisions, the Contractor shall have no responsibility for such materials in place and shall not be obligated for further cleanup, removal, or remedial actions for such materials.

Handling material containing aerially deposited lead shall be in conformance with all the rules and regulations of agencies including, but not limited to, the following:

California Division of Occupational Safety and Health Administration (Cal-OSHA)
California Regional Water Quality Control Board, Region #5 Central Valley.

The Contractor shall procure all permits and licenses, pay all charges and fees, except as otherwise provided in these special provisions, and give all notices necessary and incidental to the due and lawful prosecution of the work.

Full compensation for conforming to the requirements of this section, (except for the Lead Compliance Plan) shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

HEALTH AND SAFETY

The Contractor shall prepare a project specific Lead Compliance Plan to prevent or minimize worker exposure to lead contamination in soil. Attention is directed to Title 8, California Code of Regulations, Section 1532.1, "Lead," for specific Cal-OSHA requirements when working with lead.

The Lead Compliance Plan shall contain all of the elements listed in Title 8, California Code of Regulations, Section 1532.1(e)(2)(B). Before submission to the Engineer, the Lead Compliance Plan shall be approved by an Industrial Hygienist certified in Comprehensive Practice by the American Board of Industrial Hygiene. The Plan shall be submitted to the Engineer at least 7 days prior to beginning work in areas containing aerially deposited lead.

Prior to performing work in areas containing lead, personnel who have no prior training, including State personnel, shall complete a safety training program provided by the Contractor, that meets the requirements of Title 8, California Code of Regulations, Section 1532.1, "Lead," and the Contractor's Lead Compliance Program.

Personal protective equipment, training, washing facilities, and medical surveillance required by the Contractor's Lead Compliance Plan shall be supplied to State personnel by the Contractor. The number of State personnel will be 2.

Full compensation for Lead Compliance Plan shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

SOIL HANDLING

Handling of soils containing aerially deposited lead shall result in no visible dust migration. The Contractor shall have a dust palliative available at all times while handling soils in work areas containing aerially deposited lead.

The Contractor shall separate soil from vegetation and the soils shall remain on site.

Surplus soil excavated from areas containing aerially deposited lead shall remain in the area of soil disturbance. The surplus soil shall not be disposed of outside the highway right of way.

Full compensation for handling soil contaminated with aerially deposited lead, except as otherwise provided, shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.