

**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that Caltrans does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders and non-bidder packages, write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone and fax number, P.O. Box and street address so that you can receive addenda.

Note: Addenda information is NOT included with the electronic documents available via electronic file transfer. Only bidder or non-bidder package holders listed with the Caltrans Plans and Bid Documents section as described above will receive addenda information.



STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS
AND
SPECIAL PROVISIONS

FOR HIGHWAY PLANTING ON STATE HIGHWAY IN

**STANISLAUS COUNTY IN AND NEAR MODESTO FROM 0.2 km SOUTH OF HATCH ROAD OVERCROSSING
TO 0.6 km NORTH OF HATCH ROAD OVERCROSSING AND FROM 0.3 km SOUTH OF CROWS LANDING
OVERCROSSING TO 0.2 km NORTH OF L STREET OVERCROSSING**

DISTRICT 10, ROUTE 99

**For Use in Connection with Standard Specifications Dated JULY 1999, Standard Plans Dated JULY 1999, and Labor
Surcharge and Equipment Rental Rates.**

CONTRACT NO. 10-499504

10-Sta-99-R 21.2/R 26.3

Bids Open: July 19, 2000
Dated: June 19, 2000

IMPORTANT SPECIAL NOTICES

- **SURETY 2000**

Caltrans is conducting a pilot program in cooperation with Surety 2000, to test electronic bond verification systems. The purpose of the pilot program is to test the use of Surety 2000 for verifying a bidder's bond electronically.

Surety 2000 is an Internet-based surety verification and security system, developed in conjunction with the surety industry. Surety agents may contact Surety 2000 at 1-800-660-3263.

Bidders are encouraged to participate in the pilot program. To participate, the bidder is asked to provide the "Authorization Code" provided by Surety 2000, on a separate sheet, together with the standard bidder's bond required by the specifications. The bidder's surety agent may obtain the "Authorization Code" from Surety 2000.

The Department will use the "Authorization Code" to access the Surety 2000 database, and independently verify the actual bidder's bond and document the functioning of the Surety 2000 system.

"Authorization Codes" will be used only to verify bidder's bonds, and only as part of the pilot program. The use of "Authorization Codes" will not be accepted in lieu of the bidder's bond or other bidder's security required in the specifications during the pilot study.

The function of the Surety 2000 system is to provide an easier way for Contractors to protect their bid security, and to discourage fraud. This system is available to all California admitted sureties and surety agents.

The results of the pilot study will be tabulated, and at some time in the future, the Department may consider accepting electronic bidder's bond verification in lieu of the bidder's bond specified.

TABLE OF CONTENTS

NOTICE TO CONTRACTORS.....	1
COPY OF ENGINEER'S ESTIMATE	3
SPECIAL PROVISIONS	5
SECTION 1. SPECIFICATIONS AND PLANS.....	5
SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS.....	5
2-1.01 GENERAL.....	5
2-1.02 DISABLED VETERAN BUSINESS ENTERPRISE (DVBE).....	5
2-1.03 DVBE GOAL FOR THIS PROJECT	6
2-1.04 SUBMISSION OF DVBE INFORMATION	6
2-1.05 SMALL BUSINESS PREFERENCE.....	7
2-1.06 CALIFORNIA COMPANY PREFERENCE	8
SECTION 3. AWARD AND EXECUTION OF CONTRACT.....	8
SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES	9
SECTION 5. GENERAL	9
SECTION 5-1. MISCELLANEOUS	9
5-1.01 PLANS AND WORKING DRAWINGS	9
5-1.015 LABORATORY	9
5-1.02 LABOR NONDISCRIMINATION.....	9
5-1.03 INTEREST ON PAYMENTS	10
5-1.04 PUBLIC SAFETY	10
5-1.05 SURFACE MINING AND RECLAMATION ACT.....	11
5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES.....	11
5-1.07 YEAR 2000 COMPLIANCE.....	11
5-1.08 SUBCONTRACTOR AND DVBE RECORDS.....	12
5-1.086 PERFORMANCE OF DVBE SUBCONTRACTORS AND SUPPLIERS	12
5-1.09 SUBCONTRACTING	12
5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS	13
5-1.11 AREAS FOR CONTRACTOR'S USE	13
5-1.12 PAYMENTS	13
SECTION 6. (BLANK).....	14
SECTION 7. (BLANK).....	14
SECTION 8. MATERIALS	14
SECTION 8-1. MISCELLANEOUS	14
8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS	14
8-1.02 APPROVED TRAFFIC PRODUCTS.....	20
PAVEMENT MARKERS, PERMANENT TYPE.....	20
PAVEMENT MARKERS, TEMPORARY TYPE.....	21
STRIPING AND PAVEMENT MARKING MATERIALS	21
CLASS 1 DELINEATORS.....	22
CHANNELIZERS	22
CONICAL DELINEATORS, 1070 mm.....	22
OBJECT MARKERS.....	22
TEMPORARY RAILING (TYPE K) REFLECTORS AND CONCRETE BARRIER MARKERS	23
THRIE BEAM BARRIER MARKERS.....	23
CONCRETE BARRIER DELINEATORS, 400 mm	23
CONCRETE BARRIER-MOUNTED MINI-DRUM (260 mm x 360 mm x 570 mm)	23
SOUND WALL DELINEATOR.....	23
GUARD RAILING DELINEATOR.....	23
RETROREFLECTIVE SHEETING	24
SIGN SUBSTRATE FOR CONSTRUCTION AREA SIGNS	24
8-1.03 STATE-FURNISHED MATERIALS	25
SECTION 8-2. (BLANK)	25
SECTION 8-3. WELDING	25
8-3.01 WELDING ELECTRODES	25

SECTION 9. (BLANK).....	25
SECTION 10. CONSTRUCTION DETAILS.....	25
SECTION 10-1. GENERAL.....	25
10-1.00 CONSTRUCTION PROJECT INFORMATION SIGNS	25
10-1.01 ORDER OF WORK.....	25
10-1.02 WATER POLLUTION CONTROL.....	26
STORM WATER POLLUTION PREVENTION PLAN PREPARATION, APPROVAL AND UPDATES	27
SCHEDULE OF VALUES.....	28
SWPPP IMPLEMENTATION	28
MAINTENANCE	29
PAYMENT	29
10-1.03 PRESERVATION OF PROPERTY	30
10-1.04 DAMAGE REPAIR.....	30
10-1.05 PROGRESS SCHEDULE	31
10-1.06 OBSTRUCTIONS	31
10-1.07 MOBILIZATION	31
10-1.08 CONSTRUCTION AREA SIGNS	31
10-1.09 MAINTAINING TRAFFIC.....	32
10-1.10 CLOSURE REQUIREMENTS AND CONDITIONS	33
CLOSURE SCHEDULE	33
CONTINGENCY PLAN	34
LATE REOPENING OF CLOSURES	34
COMPENSATION	34
10-1.11 TRAFFIC CONTROL SYSTEM FOR RAMP CLOSURES	34
10-1.12 PORTABLE CHANGEABLE MESSAGE SIGN.....	35
10-1.13 TEMPORARY CRASH CUSHION MODULE.....	35
GENERAL.....	35
MATERIALS.....	35
INSTALLATION	36
MEASUREMENT AND PAYMENT	36
10-1.14 CHAIN LINK GATE.....	36
SECTION 10-2 HIGHWAY PLANTING AND IRRIGATION SYSTEMS	36
10-2.01 GENERAL.....	36
PROGRESS INSPECTIONS.....	37
10-2.02 EXISTING HIGHWAY PLANTING	37
MAINTAIN EXISTING PLANTS.....	37
REMOVE EXISTING PLANTS FOR TRENCHING	38
10-2.03 EXISTING HIGHWAY IRRIGATION FACILITIES.....	38
LOCATE EXISTING CROSSEOVERS AND CONDUITS.....	38
CHECK AND TEST EXISTING IRRIGATION FACILITIES.....	38
MAINTAIN EXISTING IRRIGATION FACILITIES	39
REMOVE EXISTING IRRIGATION FACILITIES.....	39
SALVAGE EXISTING IRRIGATION FACILITIES.....	39
10-2.04 HIGHWAY PLANTING.....	39
ROADSIDE CLEARING	40
PESTICIDES	41
PREPARING PLANTING AREAS	41
PREPARE HOLES	41
PLANTING.....	42
ROOT PROTECTOR	42
PLANT ESTABLISHMENT WORK.....	42

10-2.05 IRRIGATION SYSTEMS	43
VALVE BOXES	43
IRRIGATION SYSTEMS FUNCTIONAL TEST	43
PIPE	43
TESTING BACKFLOW PREVENTERS	43
SPRINKLERS.....	44
CHECK VALVES	44
FILTER ASSEMBLY UNIT	44
FINAL IRRIGATION SYSTEM CHECK	44
SECTION 11. (BLANK).....	45
SECTION 12. (BLANK).....	45
SECTION 13. RELATIONS WITH RAILROAD.....	45

STANDARD PLANS LIST

The Standard Plan sheets applicable to this contract include, but are not limited to those indicated below. The Revised Standard Plans (RSP) and New Standard Plans (NSP) which apply to this contract are included as individual sheets of the project plans.

A10A	Abbreviations
A10B	Symbols
A85	Chain Link Fence
H1	Planting and Irrigation - Abbreviations
H2	Planting and Irrigation - Symbols
H3	Planting and Irrigation Details
H4	Planting and Irrigation Details
H5	Planting and Irrigation Details
H6	Planting and Irrigation Details
H7	Planting and Irrigation Details
H8	Planting and Irrigation Details
T1A	Temporary Crash Cushion, Sand Filled (Unidirectional)
T1B	Temporary Crash Cushion, Sand Filled (Bidirectional)
T2	Temporary Crash Cushion, Sand Filled (Shoulder Installations)
T3	Temporary Railing (Type K)
T7	Construction Project Funding Identification Signs
T10	Traffic Control System for Lane Closure On Freeways and Expressways
T14	Traffic Control System for Ramp Closure
RS1	Roadside Signs, Typical Installation Details No. 1
RS2	Roadside Signs - Wood Post, Typical Installation Details No. 2
RS4	Roadside Signs, Typical Installation Details No. 4

State Project with DVBE Goals (03-08-00)

DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS

CONTRACT NO. 10-499504

10-Sta-99-R 21.2/R 26.3

Sealed proposals for the work shown on the plans entitled:

Contract No. 10-499504

STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROJECT PLANS FOR HIGHWAY PLANTING ON STATE HIGHWAY IN STANISLAUS COUNTY IN AND NEAR MODESTO FROM 0.2 km SOUTH OF HATCH ROAD OVERCROSSING TO 0.6 km NORTH OF HATCH ROAD OVERCROSSING AND FROM 0.3 km SOUTH OF CROWS LANDING OVERCROSSING TO 0.2 km NORTH OF L STREET OVERCROSSING

will be received at the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, CA 95814, until 2 o'clock p.m. on July 19, 2000, at which time they will be publicly opened and read in Room 0100 at the same address.

Proposal forms for this work are included in a separate book entitled:

STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROPOSAL AND CONTRACT FOR HIGHWAY PLANTING ON STATE HIGHWAY IN STANISLAUS COUNTY IN AND NEAR MODESTO FROM 0.2 km SOUTH OF HATCH ROAD OVERCROSSING TO 0.6 km NORTH OF HATCH ROAD OVERCROSSING AND FROM 0.3 km SOUTH OF CROWS LANDING OVERCROSSING TO 0.2 km NORTH OF L STREET OVERCROSSING

General work description: Highway Planting and Irrigation.

This project has a goal of 3 percent disabled veteran business enterprise (DVBE) participation.

No prebid meeting is scheduled for this project.

Bids are required for the entire work described herein.

At the time this contract is awarded, the Contractor shall possess either a Class A license or a Class C-27 license.

The Contractor must also be properly licensed at the time the bid is submitted, except that on a joint venture bid a joint venture license may be obtained by a combination of licenses after bid opening but before award in conformance with Business and Professions Code, Section 7029.1.

This contract is subject to state contract nondiscrimination and compliance requirements pursuant to Government Code, Section 12990.

Preference will be granted to bidders properly certified as a "Small Business" as determined by the Department of General Services, Office of Small Business Certification and Resources at the time of bid opening in conformance with the provisions in Section 2-1.05, "Small Business Preference," of the special provisions, and Section 1896 et seq, Title 2, California Code of Regulations. A form for requesting a "Small Business" preference is included with the bid documents. Applications for status as a "Small Business" must be submitted to the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814, Telephone No. (916) 322-5060.

A reciprocal preference will be granted to "California company" bidders in conformance with Section 6107 of the Public Contract Code. (See Sections 2 and 3 of the special provisions.) A form for indicating whether bidders are or are not a "California company" is included in the bid documents and is to be filled in and signed by all bidders.

The Caltrans Central Region Construction Office is located at 850 L Street, Fresno CA 93721-2615. The District Duty Senior for this project can be reached at (209)948-7849, or by fax at (209)948-7358. The Department will consider bidder inquiries only when a completed Bidder Inquiry Form is submitted. The Bidder Inquiry Form is available on the Internet at <http://www.dot.ca.gov/dist6/construction>. To the extent feasible and at the discretion of the Department, completed Bidder Inquiry Forms submitted for consideration will be investigated, and responses will be posted on the Internet at <http://www.dot.ca.gov/dist6/construction>.

Project plans, special provisions, and proposal forms for bidding this project can only be obtained at the Department of Transportation, Plans and Bid Documents, Room 0200, MS #26, Transportation Building, 1120 N Street, Sacramento, California 95814, FAX No. (916) 654-7028, Telephone No. (916) 654-4490. Use FAX orders to expedite orders for project plans, special provisions and proposal forms. FAX orders must include credit card charge number, card expiration date and authorizing signature. Project plans, special provisions, and proposal forms may be seen at the above Department of Transportation office and at the offices of the District Directors of Transportation at Irvine, Oakland, and the district in which the work is situated. Standard Specifications and Standard Plans are available through the State of California, Department of Transportation, Publications Unit, 1900 Royal Oaks Drive, Sacramento, CA 95815, Telephone No. (916) 445-3520.

Cross sections for this project are not available.

The successful bidder shall furnish a payment bond and a performance bond.

Pursuant to Section 1773 of the Labor Code, the general prevailing wage rates in the county, or counties, in which the work is to be done have been determined by the Director of the California Department of Industrial Relations. These wages are set forth in the General Prevailing Wage Rates for this project, available at the Labor Compliance Office at the offices of the District Director of Transportation for the district in which the work is situated, and available from the California Department of Industrial Relations' Internet Web Site at: <http://www.dir.ca.gov>. Future effective general prevailing wage rates which

Contract No. «Dist»-«Contract_No»

have been predetermined and are on file with the Department of Industrial Relations are referenced but not printed in the general prevailing wage rates.

DEPARTMENT OF TRANSPORTATION

Deputy Director Transportation Engineering

Dated June 19, 2000

GAB

COPY OF ENGINEER'S ESTIMATE
(NOT TO BE USED FOR BIDDING PURPOSES)
10-499504

Item	Item Code	Item	Unit of Measure	Estimated Quantity
1	074019	PREPARE STORM WATER POLLUTION PREVENTION PLAN	LS	LUMP SUM
2	074020	WATER POLLUTION CONTROL	LS	LUMP SUM
3 (S)	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM
4 (S)	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM
5 (S)	128650	PORTABLE CHANGEABLE MESSAGE SIGN	LS	LUMP SUM
6	200002	ROADSIDE CLEARING	LS	LUMP SUM
7	202011	MULCH	M3	930
8	202030	COMMERCIAL FERTILIZER (GRANULAR)	KG	500
9	202032	COMMERCIAL FERTILIZER (TABLET)	EA	1290
10	204001	PLANT (GROUP A)	EA	730
11	204002	PLANT (GROUP B)	EA	290
12	204008	PLANT (GROUP H)	EA	101 300
13	204098	MAINTAIN EXISTING PLANTS	LS	LUMP SUM
14	204099	PLANT ESTABLISHMENT WORK	LS	LUMP SUM
15	205061	ROOT PROTECTOR	EA	39
16	206560	CONTROL AND NEUTRAL CONDUCTORS	LS	LUMP SUM
17	206612	32 MM ELECTRIC REMOTE CONTROL VALVE	EA	22
18	206613	40 MM ELECTRIC REMOTE CONTROL VALVE	EA	75
19	206614	50 MM ELECTRIC REMOTE CONTROL VALVE	EA	29
20 (F)	208249	20 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	3312

Item	Item Code	Item	Unit of Measure	Estimated Quantity
21 (F)	208250	25 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	2153
22 (F)	208251	32 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	1447
23 (F)	208252	40 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	890
24 (F)	208253	50 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	4896
25 (F)	208255	75 MM PLASTIC PIPE (PR 200) (SUPPLY LINE)	M	862
26 (F)	208288	50 MM PLASTIC PIPE (PR 315) (SUPPLY LINE)	M	126
27	208461	SPRINKLER (TYPE A-1)	EA	410
28	208462	SPRINKLER (TYPE A-2)	EA	20
29	208471	SPRINKLER (TYPE B-1)	EA	70
30	208472	SPRINKLER (TYPE B-2)	EA	20
31	208483	SPRINKLER (TYPE C-3)	EA	650
32	208493	75 MM GATE VALVE	EA	57
33	018793	50 MM FILTER ASSEMBLY UNIT	EA	8
34	208670	CHECK VALVE	EA	18
35	018794	SWING CHECK VALVE	EA	1
36	208798	200 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	M	188
37	208800	300 MM WELDED STEEL PIPE CONDUIT (6.35 MM THICK)	M	18
38	802585	1.2 M CHAIN LINK GATE (TYPE CL-1.8)	EA	4
39	999990	MOBILIZATION	LS	LUMP SUM

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISIONS

Annexed to Contract No. 10-499504

SECTION 1. SPECIFICATIONS AND PLANS

The work embraced herein shall conform to the provisions in the Standard Specifications dated July 1999, and the Standard Plans dated July 1999, of the Department of Transportation insofar as the same may apply, and these special provisions.

Amendments to the Standard Specifications set forth in these special provisions shall be considered as part of the Standard Specifications for the purposes set forth in Section 5-1.04, "Coordination and Interpretation of Plans, Standard Specifications and Special Provisions," of the Standard Specifications. Whenever either the term "Standard Specifications are amended" or the term "Standard Specifications are amended" is used in the special provisions, the indented text or table following the term shall be considered an amendment to the Standard Specifications. In case of conflict between such amendments and the Standard Specifications, the amendments shall take precedence over and be used in lieu of the conflicting portions.

In case of conflict between the Standard Specifications and these special provisions, the special provisions shall take precedence over and shall be used in lieu of the conflicting portions.

SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS

2-1.01 GENERAL

The bidder's attention is directed to the provisions in Section 2, "Proposal Requirements and Conditions," of the Standard Specifications and these special provisions for the requirements and conditions which the bidder must observe in the preparation of the proposal form and the submission of the bid.

In addition to the subcontractors required to be listed in conformance with Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications, each proposal shall have listed therein the name and address of each DVBE subcontractor to be used for credit in meeting the goal, and to whom the bidder proposes to directly subcontract portions of the work. The list of subcontractors shall also set forth the portion of work that will be performed by each subcontractor listed. A sheet for listing the subcontractors is included in the Proposal.

The Bidder's Bond form mentioned in the last paragraph in Section 2-1.07, "Proposal Guaranty," of the Standard Specifications will be found following the signature page of the Proposal.

In conformance with Public Contract Code Section 7106, a Noncollusion Affidavit is included in the Proposal. Signing the Proposal shall also constitute signature of the Noncollusion Affidavit.

Submit request for substitution of an "or equal" item, and the data substantiating the request to the Department of Transportation, Central Region Construction, P.O. Box 12616, Fresno, CA 93778, so that the request is received by the Department by close of business on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening.

2-1.02 DISABLED VETERAN BUSINESS ENTERPRISE (DVBE)

Section 10115 of the Public Contract Code requires the Department to implement provisions to establish a goal for Disabled Veterans Business Enterprise (DVBE) in contracts.

It is the policy of the Department that Disabled Veteran Business Enterprise (DVBE) shall have the maximum opportunity to participate in the performance of contracts financed solely with state funds. The Contractor shall ensure that DVBEs have the maximum opportunity to participate in the performance of this contract and shall take all necessary and reasonable steps for this assurance. The Contractor shall not discriminate on the basis of race, color, national origin, or sex in the award and performance of subcontracts. Failure to carry out the requirements of this paragraph shall constitute a breach of contract and may result in termination of this contract or other remedy the Department may deem appropriate.

Bidder's attention is directed to the following:

- A. "Disabled Veteran Business Enterprise" (DVBE) means a business concern certified as a DVBE by the Office of Small Business Certification and Resources, Department of General Services.
- B. A DVBE may participate as a prime contractor, subcontractor, joint venture partner with a prime or subcontractor, or vendor of material or supplies.
- C. Credit for DVBE prime contractors will be 100 percent.
- D. A DVBE joint venture partner must be responsible for specific contract items of work, or portions thereof. Responsibility means actually performing, managing and supervising the work with its own forces. The DVBE joint venture partner must share in the ownership, control, management responsibilities, risks and profits of the joint venture. The DVBE joint venturer must submit the joint venture agreement with the Caltrans Bidder DVBE Information form required in Section 2-1.04, "Submission of DVBE Information," elsewhere in these special provisions.
- E. A DVBE must perform a commercially useful function, i.e., must be responsible for the execution of a distinct element of the work and must carry out its responsibility by actually performing, managing and supervising the work.
- F. Credit for DVBE vendors of materials or supplies is limited to 60 percent of the amount to be paid to the vendor for the material unless the vendor manufactures or substantially alters the goods.
- G. Credit for trucking by DVBEs will be as follows:
 - 1. One hundred percent of the amount to be paid when a DVBE trucker will perform the trucking with his/her own trucks, tractors and employees.
 - 2. Twenty percent of the amount to be paid to DVBE trucking brokers who do not have a "certified roster."
 - 3. One hundred percent of the amount to be paid to DVBE trucking brokers who have signed agreements that all trucking will be performed by DVBE truckers if credit is toward the DVBE goal, a "certified roster" showing that all trucks are owned by DVBEs, and a signed statement on the "certified roster" that indicates that 100 percent of revenue paid by the broker will be paid to the DVBEs listed on the "certified roster."
 - 4. Twenty percent of the amount to be paid to trucking brokers who are not a DVBE but who have signed agreements with DVBE truckers assuring that at least 20 percent of the trucking will be performed by DVBE truckers if credit is toward the DVBE goal, a "certified roster" showing that at least 20 percent of the number of trucks are owned by DVBE truckers, and a signed statement on the "certified roster" that indicates that at least 20 percent of the revenue paid by the broker will be paid to the DVBEs listed on the "certified roster."

The "certified roster" referred to herein shall conform to the requirements in Section 2-1.04, "Submission Of DVBE Information," elsewhere in these special provisions.

- H. DVBEs and DVBE joint venture partners must be certified DVBEs as determined by the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814, on the date bids for the project are opened before credit may be allowed toward the DVBE goal. It is the Contractor's responsibility to verify that DVBEs are certified.
- I. Noncompliance by the Contractor with these requirements constitutes a breach of this contract and may result in termination of the contract or other appropriate remedy for a breach of this contract.

2-1.03 DVBE GOAL FOR THIS PROJECT

The Department has established the following goal for Disabled Veteran Business Enterprise (DVBE) participation for this project:

Disabled Veteran Business Enterprise (DVBE): 3 percent.

It is the bidder's responsibility to make a sufficient portion of the work available to subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DVBE subcontractors and suppliers, so as to assure meeting the goal for DVBE participation.

The Office of Small Business Certification and Resources, Department of General Services, may be contacted at (916) 322-5060 or visit their internet web site at <http://www.osmb.dgs.ca.gov/> for program information and certification status. The Department's Business Enterprise Program may also be contacted at (916) 227-9599 or the internet web site at <http://www.dot.ca.gov/hq/bep/>.

2-1.04 SUBMISSION OF DVBE INFORMATION

The required DVBE information shall be submitted on the "CALTRANS BIDDER - DVBE INFORMATION" form included in the Proposal. If this information is not submitted with the bid, the DVBE information forms shall be removed from the documents prior to submitting the bid.

It is the bidder's responsibility to make enough work available to DVBEs and to select those portions of the work or material needs consistent with the available DVBEs to meet the goal for DVBE participation or to provide information to establish that, prior to bidding, the bidder made adequate good faith efforts to do so.

If the DVBE information is not submitted with the bid, the apparent successful bidder (low bidder), the second low bidder and the third low bidder shall submit the DVBE information to the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, California 95814 so the information is received by the Department no later than 4:00 p.m. on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening. DVBE information sent by U.S. Postal Service certified mail with return receipt and certificate of mailing and mailed on or before the third day, not including Saturdays, Sundays and legal holidays, following bid opening will be accepted even if it is received after the fourth day following bid opening. Failure to submit the required DVBE information by the time specified will be grounds for finding the bid or proposal nonresponsive. Other bidders need not submit DVBE information unless requested to do so by the Department.

The bidder's DVBE information shall establish that good faith efforts to meet the DVBE goal have been made. To establish good faith efforts, the bidder shall demonstrate that the goal will be met or that, prior to bidding, adequate good faith efforts to meet the goal were made.

Bidders are cautioned that even though their submittal indicates they will meet the stated DVBE goal, their submittal should also include their adequate good faith efforts information along with their DVBE goal information to protect their eligibility for award of the contract in the event the Department, in its review, finds that the goal has not been met.

The bidder's DVBE information shall include the names of DVBE firms that will participate, with a complete description of work or supplies to be provided by each, the dollar value of each DVBE transaction, and a written confirmation from the DVBE that it is participating in the contract. A copy of the DVBE's quote will serve as written confirmation that the DVBE is participating in the contract. When 100 percent of a contract item of work is not to be performed or furnished by a DVBE, a description of the exact portion of that work to be performed or furnished by that DVBE shall be included in the DVBE information, including the planned location of that work. The work that a DVBE prime contractor has committed to performing with its own forces as well as the work that it has committed to be performed by DVBE subcontractors, suppliers and trucking companies will count toward the goal.

If credit for trucking by a DVBE trucking broker is shown on the bidder's information as 100 percent of the revenue to be paid by the broker is to be paid to DVBE truckers, a "certified roster" of the broker's trucks to be used must be included. The "certified roster" must indicate that all the trucks are owned by certified DVBEs and must show the DVBE truck numbers, owner's name, Public Utilities Commission Cal-T numbers, and the DVBE certification numbers. The roster must indicate that all revenue paid by the broker will be paid to DVBEs listed on the "certified roster".

If credit for trucking by a trucking broker who is not a DVBE is shown in the bidder's information, a "certified roster" of the broker's trucks to be used must be included. The "certified roster" must indicate that at least 20 percent of the broker's trucks are owned by certified DVBEs and must show the DVBE truck numbers, owner's name, Public Utilities Commission Cal-T numbers, and the DVBE certification number. The roster must indicate that at least 20 percent of the revenue paid by the broker will be paid to DVBEs listed on the "certified roster".

A bidder shall be deemed to have made good faith efforts upon submittal, within time limits specified by the Department, of documentary evidence that all of the following actions were taken:

- A. Contact was made with the Office of Small Business Certification and Resources (OSBCR), Department of General Services or their web site at <http://www.osmb.dgs.ca.gov/> to identify Disabled Veteran Business Enterprises.
- B. Advertising was published in trade media and media focusing on Disabled Veteran Business Enterprises, unless time limits imposed by the Department do not permit that advertising.
- C. Invitations to bid were submitted to potential Disabled Veteran Business Enterprise contractors.
- D. Available Disabled Veteran Business Enterprises were considered.

2-1.05 SMALL BUSINESS PREFERENCE

Attention is directed to "Award and Execution of Contract" of these special provisions.

Attention is also directed to the Small Business Procurement and Contract Act, Government Code Section 14835, et seq and Title 2, California Code of Regulations, Section 1896, et seq.

Bidders who wish to be classified as a Small Business under the provisions of those laws and regulations, shall be certified as Small Business by the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814.

To request Small Business Preference, bidders shall fill out and sign the Request for Small Business Preference form in the Proposal and shall attach a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form. The bidder's signature on the Request for Small Business Preference certifies, under penalty of perjury, that the bidder is certified as Small Business at the time of bid opening and further certifies, under penalty of perjury, that under the following conditions, at least 50 percent of the subcontractors to be utilized on the project are either

certified Small Business or have applied for Small Business certification by bid opening date and are subsequently granted Small Business certification.

The conditions requiring the aforementioned 50 percent level of subcontracting by Small Business subcontractors apply if:

- A. The lowest responsible bid for the project exceeds \$100,000; and
- B. The project work to be performed requires a Class A or a Class B contractor's license; and
- C. Two or more subcontractors will be used.

If the above conditions apply and Small Business Preference is granted in the award of the contract, the 50 percent Small Business subcontractor utilization level shall be maintained throughout the life of the contract.

2-1.06 CALIFORNIA COMPANY PREFERENCE

Attention is directed to "Award and Execution of Contract" of these special provisions.

In conformance with the requirements of Section 6107 of the Public Contract Code, a "California company" will be granted a reciprocal preference for bid comparison purposes as against a nonresident contractor from any state that gives or requires a preference to be given contractors from that state on its public entity construction contracts.

A "California company" means a sole proprietorship, partnership, joint venture, corporation, or other business entity that was a licensed California contractor on the date when bids for the public contract were opened and meets one of the following:

- A. Has its principal place of business in California.
- B. Has its principal place of business in a state in which there is no local contractor preference on construction contracts.
- C. Has its principal place of business in a state in which there is a local contractor construction preference and the contractor has paid not less than \$5000 in sales or use taxes to California for construction related activity for each of the five years immediately preceding the submission of the bid.

To carry out the "California company" reciprocal preference requirements of Section 6107 of the Public Contract Code, all bidders shall fill out and sign the California Company Preference form in the Proposal. The bidder's signature on the California Company Preference form certifies, under penalty of perjury, that the bidder is or is not a "California company" and if not, the amount of the preference applied by the state of the nonresident Contractor.

A nonresident Contractor shall disclose any and all bid preferences provided to the nonresident Contractor by the state or country in which the nonresident Contractor has its principal place of business.

Proposals without the California Company Preference form filled out and signed may be rejected.

SECTION 3. AWARD AND EXECUTION OF CONTRACT

The bidder's attention is directed to the provisions in Section 3, "Award and Execution of Contract," of the Standard Specifications and these special provisions for the requirements and conditions concerning award and execution of contract.

The award of the contract, if it be awarded, will be to the lowest responsible bidder whose proposal complies with all the requirements prescribed and who has met the goal for DVBE participation or has demonstrated, to the satisfaction of the Department, adequate good faith efforts to do so. Meeting the goal for DVBE participation or demonstrating, to the satisfaction of the Department, adequate good faith efforts to do so is a condition for being eligible for award of contract.

A "Payee Data Record" form will be included in the contract documents to be executed by the successful bidder. The purpose of the form is to facilitate the collection of taxpayer identification data. The form shall be completed and returned to the Department by the successful bidder with the executed contract and contract bonds. For the purposes of the form, vendor shall be deemed to mean the successful bidder. The form is not to be completed for subcontractors or suppliers. Failure to complete and return the "Payee Data Record" form to the Department as provided herein will result in the retention of 20 percent of payments due the contractor and penalties of up to \$20,000. This retention of payments for failure to complete the "Payee Data Record" form is in addition to any other retention of payments due the Contractor.

Attention is also directed to "Small Business Preference" of these special provisions. Any bidder who is certified as a Small Business by the Department of General Services, Office of Small Business Certification and Resources will be allowed a preference in the award of this contract, if it be awarded, under the following conditions:

- A. The apparent low bidder is not certified as a Small Business, or has not filled out and signed the Request for Small Business Preference included with the bid documents and attached a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form; and

- B. The bidder filled out and signed the Request for Small Business Preference form included with the bid documents and attached a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form.

The small business preference will be a reduction in the bid submitted by the small business contractor, for bid comparison purposes, by an amount equal to 5 percent of the amount bid by the apparent low bidder, the amount not to exceed \$50,000. If this reduction results in the small business contractor becoming the low bidder, then the contract will be awarded to the small business contractor on the basis of the actual bid of the small business contractor notwithstanding the reduced bid price used for bid comparison purposes.

Attention is also directed to "California Company Preference" of these special provisions.

The amount of the California company reciprocal preference shall be equal to the amount of the preference applied by the state of the nonresident contractor with the lowest responsive bid, except where the "California company" is eligible for a California Small Business Preference, in which case the preference applied shall be the greater of the two, but not both.

If the bidder submitting the lowest responsive bid is not a "California company" and with the benefit of the reciprocal preference, a "California company's" responsive bid is equal to or less than the original lowest responsive bid, the "California company" will be awarded the contract at its submitted bid price except as provided below.

Small business bidders shall have precedence over nonsmall business bidders in that the application of the "California company" preference for which nonsmall business bidders may be eligible shall not result in the denial of the award to a small business bidder.

SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES

Attention is directed to the provisions in Section 8-1.03, "Beginning of Work," in Section 8-1.06, "Time of Completion," and in Section 8-1.07, "Liquidated Damages," of the Standard Specifications and these special provisions.

The Contractor shall begin work within 15 calendar days after the contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department of Transportation.

This work shall be diligently prosecuted to completion before the expiration of **380 WORKING DAYS** beginning on the fifteenth calendar day after approval of the contract.

The Contractor shall pay to the State of California the sum of \$250 per day, for each and every calendar day's delay in finishing the work in excess of the number of working days prescribed above.

SECTION 5. GENERAL

SECTION 5-1. MISCELLANEOUS

5-1.01 PLANS AND WORKING DRAWINGS

When the specifications require working drawings to be submitted to the Division of Structure Design, the drawings shall be submitted to: Division of Structure Design, Documents Unit, Mail Station 9, 1801 30th Street, Sacramento, CA 95816, Telephone 916 227-8252.

5-1.015 LABORATORY

When a reference is made in the specifications to the "Laboratory," the reference shall mean the Division of Materials Engineering and Testing Services and the Division of Structural Foundations of the Department of Transportation, or established laboratories of the various Districts of the Department, or other laboratories authorized by the Department to test materials and work involved in the contract. When a reference is made in the specifications to the "Transportation Laboratory," the reference shall mean the Division of Materials Engineering and Testing Services and the Division of Structural Foundations, located at 5900 Folsom Boulevard, Sacramento, CA 95819, Telephone (916) 227-7000.

5-1.02 LABOR NONDISCRIMINATION

Attention is directed to the following Notice that is required by Chapter 5 of Division 4 of Title 2, California Code of Regulations.

**NOTICE OF REQUIREMENT FOR NONDISCRIMINATION PROGRAM
(GOV. CODE, SECTION 12990)**

Your attention is called to the "Nondiscrimination Clause", set forth in Section 7-1.01A(4), "Labor Nondiscrimination," of the Standard Specifications, which is applicable to all nonexempt State contracts and subcontracts, and to the "Standard California Nondiscrimination Construction Contract Specifications" set forth therein. The specifications are applicable to all nonexempt State construction contracts and subcontracts of \$5000 or more.

5-1.03 INTEREST ON PAYMENTS

Interest shall be payable on progress payments, payments after acceptance, final payments, extra work payments, and claim payments as follows:

- A. Unpaid progress payments, payment after acceptance, and final payments shall begin to accrue interest 30 days after the Engineer prepares the payment estimate.
- B. Unpaid extra work bills shall begin to accrue interest 30 days after preparation of the first pay estimate following receipt of a properly submitted and undisputed extra work bill. To be properly submitted, the bill must be submitted within 7 days of the performance of the extra work and in conformance with the provisions in Section 9-1.03C, "Records," and Section 9-1.06, "Partial Payments," of the Standard Specifications. An undisputed extra work bill not submitted within 7 days of performance of the extra work will begin to accrue interest 30 days after the preparation of the second pay estimate following submittal of the bill.
- C. The rate of interest payable for unpaid progress payments, payments after acceptance, final payments, and extra work payments shall be 10 percent per annum.
- D. The rate of interest payable on a claim, protest or dispute ultimately allowed under this contract shall be 6 percent per annum. Interest shall begin to accrue 61 days after the Contractor submits to the Engineer information in sufficient detail to enable the Engineer to ascertain the basis and amount of said claim, protest or dispute.

The rate of interest payable on any award in arbitration shall be 6 percent per annum if allowed under the provisions of Civil Code Section 3289.

5-1.04 PUBLIC SAFETY

The Contractor shall provide for the safety of traffic and the public in conformance with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications and these special provisions.

The Contractor shall install temporary railing (Type K) between a lane open to public traffic and an excavation, obstacle or storage area when the following conditions exist:

- A. Excavations.—The near edge of the excavation is 3.6 m or less from the edge of the lane, except:
 - 1. Excavations covered with sheet steel or concrete covers of adequate thickness to prevent accidental entry by traffic or the public.
 - 2. Excavations less than 0.3-m deep.
 - 3. Trenches less than 0.3-m wide for irrigation pipe or electrical conduit, or excavations less than 0.3-m in diameter.
 - 4. Excavations parallel to the lane for the purpose of pavement widening or reconstruction.
 - 5. Excavations in side slopes, where the slope is steeper than 1:4 (vertical:horizontal).
 - 6. Excavations protected by existing barrier or railing.
- B. Temporarily Unprotected Permanent Obstacles.—The work includes the installation of a fixed obstacle together with a protective system, such as a sign structure together with protective railing, and the Contractor elects to install the obstacle prior to installing the protective system; or the Contractor, for the Contractor's convenience and with permission of the Engineer, removes a portion of an existing protective railing at an obstacle and does not replace such railing complete in place during the same day.
- C. Storage Areas.—Material or equipment is stored within 3.6 m of the lane and the storage is not otherwise prohibited by the provisions of the Standard Specifications and these special provisions.

The approach end of temporary railing (Type K), installed in conformance with the provisions in this section "Public Safety" and in Section 7-1.09, "Public Safety," of the Standard Specifications, shall be offset a minimum of 4.6 m from the edge of the traffic lane open to public traffic. The temporary railing shall be installed on a skew toward the edge of the traffic lane of not more than 0.3-m transversely to 3 m longitudinally with respect to the edge of the traffic lane. If the 4.6-m

minimum offset cannot be achieved, the temporary railing shall be installed on the 10 to 1 skew to obtain the maximum available offset between the approach end of the railing and the edge of the traffic lane, and an array of temporary crash cushion modules shall be installed at the approach end of the temporary railing.

Temporary railing (Type K) shall conform to the provisions in Section 12-3.08, "Temporary Railing (Type K)," of the Standard Specifications. Temporary railing (Type K), conforming to the details shown on 1999 Standard Plan T3, may be used. Temporary railing (Type K) fabricated prior to January 1, 1993, and conforming to 1988 Standard Plan B11-30 may be used, provided the fabrication date is printed on the required Certificate of Compliance.

Temporary crash cushion modules shall conform to the provisions in "Temporary Crash Cushion Module" of these special provisions.

Except for installing, maintaining and removing traffic control devices, whenever work is performed or equipment is operated in the following work areas, the Contractor shall close the adjacent traffic lane unless otherwise provided in the Standard Specifications and these special provisions:

Approach Speed of Public Traffic (Posted Limit) (Kilometers Per Hour)	Work Areas
Over 72 (45 Miles Per Hour)	Within 1.8 m of a traffic lane but not on a traffic lane
56 to 72 (35 to 45 Miles Per Hour)	Within 0.9-m of a traffic lane but not on a traffic lane

The lane closure provisions of this section shall not apply if the work area is protected by permanent or temporary railing or barrier.

When traffic cones or delineators are used to delineate a temporary edge of a traffic lane, the line of cones or delineators shall be considered to be the edge of the traffic lane, however, the Contractor shall not reduce the width of an existing lane to less than 3 m without written approval from the Engineer.

When work is not in progress on a trench or other excavation that required closure of an adjacent lane, the traffic cones or portable delineators used for the lane closure shall be placed off of and adjacent to the edge of the traveled way. The spacing of the cones or delineators shall be not more than the spacing used for the lane closure.

Suspended loads or equipment shall not be moved nor positioned over public traffic or pedestrians.

Full compensation for conforming to the provisions in this section "Public Safety," including furnishing and installing temporary railing (Type K) and temporary crash cushion modules, shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

5-1.05 SURFACE MINING AND RECLAMATION ACT

Attention is directed to the Surface Mining and Reclamation Act of 1975, commencing in Public Resources Code, Mining and Geology, Section 2710, which establishes regulations pertinent to surface mining operations.

Material from mining operations furnished for this project shall only come from permitted sites in compliance with the Surface Mining and Reclamation Act of 1975.

The requirements of this section shall apply to materials furnished for the project, except for acquisition of materials in conformance with the provisions in Section 4-1.05, "Use of Materials Found on the Work," of the Standard Specifications.

5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES

When the presence of asbestos or hazardous substances are not shown on the plans or indicated in the specifications and the Contractor encounters materials which the Contractor reasonably believes to be asbestos or a hazardous substance as defined in Section 25914.1 of the Health and Safety Code, and the asbestos or hazardous substance has not been rendered harmless, the Contractor may continue work in unaffected areas reasonably believed to be safe. The Contractor shall immediately cease work in the affected area and report the condition to the Engineer in writing.

In conformance with Section 25914.1 of the Health and Safety Code, removal of asbestos or hazardous substances including exploratory work to identify and determine the extent of the asbestos or hazardous substance will be performed by separate contract.

If delay of work in the area delays the current controlling operation, the delay will be considered a right of way delay and the Contractor will be compensated for the delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

5-1.07 YEAR 2000 COMPLIANCE

This contract is subject to Year 2000 Compliance for automated devices in the State of California.

Year 2000 compliance for automated devices in the State of California is achieved when embedded functions have or create no logical or mathematical inconsistencies when dealing with dates prior to and beyond 1999. The year 2000 is

recognized and processed as a leap year. The product shall operate accurately in the manner in which the product was intended for date operation without requiring manual intervention.

The Contractor shall provide the Engineer a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for all automated devices furnished for the project.

5-1.08 SUBCONTRACTOR AND DVBE RECORDS

The Contractor shall maintain records of all subcontracts entered into with certified DVBE subcontractors and records of materials purchased from certified DVBE suppliers. The records shall show the name and business address of each DVBE subcontractor or vendor and the total dollar amount actually paid each DVBE subcontractor or vendor.

Upon completion of the contract, a summary of these records shall be prepared on Form CEM-2402 (S) and certified correct by the Contractor or the Contractor's authorized representative, and shall be furnished to the Engineer.

5-1.086 PERFORMANCE OF DVBE SUBCONTRACTORS AND SUPPLIERS

The DVBEs listed by the Contractor in response to the provisions in Section 2-1.04, "Submission of DVBE Information," and Section 3, "Award and Execution of Contract," of these special provisions, which are determined by the Department to be certified DVBEs, shall perform the work and supply the materials for which they are listed, unless the Contractor has received prior written authorization to perform the work with other forces or to obtain the materials from other sources.

Authorization to utilize other forces or sources of materials may be requested for the following reasons:

- A. The listed DVBE, after having had a reasonable opportunity to do so, fails or refuses to execute a written contract, when the written contract, based upon the general terms, conditions, plans and specifications for the project, or on the terms of the subcontractor's or supplier's written bid, is presented by the Contractor.
- B. The listed DVBE becomes bankrupt or insolvent.
- C. The listed DVBE fails or refuses to perform the subcontract or furnish the listed materials.
- D. The Contractor stipulated that a bond was a condition of executing a subcontract and the listed DVBE subcontractor fails or refuses to meet the bond requirements of the Contractor.
- E. The work performed by the listed subcontractor is substantially unsatisfactory and is not in substantial conformance with the plans and specifications or the subcontractor is substantially delaying or disrupting the progress of the work.
- F. The listed DVBE subcontractor is not licensed pursuant to the Contractor's License Law.
- G. It would be in the best interest of the State.

The Contractor shall not be entitled to payment for the work or material unless it is performed or supplied by the listed DVBE or by other forces (including those of the Contractor) pursuant to prior written authorization of the Engineer.

5-1.09 SUBCONTRACTING

Attention is directed to the provisions in Section 8-1.01, "Subcontracting," of the Standard Specifications, Section 2, "Proposal Requirements and Conditions," Section 2-1.04, "Submission of DVBE Information," and Section 3, "Award and Execution of Contract," of these special provisions and these special provisions.

Pursuant to the provisions in Section 1777.1 of the Labor Code, the Labor Commissioner publishes and distributes a list of contractors ineligible to perform work as a subcontractor on a public works project. This list of debarred contractors is available from the Department of Industrial Relations web site at:

<http://www.dir.ca.gov/DLSE/Debar.html>.

The DVBE information furnished under Section 3-1.01A, "DVBE Information," of these special provisions is in addition to the subcontractor information required to be furnished in Section 8-1.01, "Subcontracting," and Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications.

Section 10115 of the Public Contract Code requires the Department to implement provisions to establish a goal for Disabled Veteran Business Enterprise (DVBE) participation in highway contracts that are State funded. As a part of this requirement:

- A. No substitution of a DVBE subcontractor shall be made at any time without the written consent of the Department, and
- B. If a DVBE subcontractor is unable to perform successfully and is to be replaced, the Contractor shall make good faith efforts to replace the original DVBE subcontractor with another DVBE subcontractor.

The provisions in Section 2-1.02, "Disabled Veteran Business Enterprise (DVBE)," of these special provisions that DVBEs shall be certified on the date bids are opened does not apply to DVBE substitutions after award of the contract.

5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS

Attention is directed to the provisions in Sections 10262 and 10262.5 of the Public Contract Code and Section 7108.5 of the Business and Professions Code concerning prompt payment to subcontractors.

5-1.11 AREAS FOR CONTRACTOR'S USE

Attention is directed to the provisions in Section 7-1.19, "Rights in Land and Improvements," of the Standard Specifications and these special provisions.

The highway right of way shall be used only for purposes that are necessary to perform the required work. The Contractor shall not occupy the right of way, or allow others to occupy the right of way, for purposes which are not necessary to perform the required work.

No State-owned parcels adjacent to the right of way are available for the exclusive use of the Contractor within the contract limits. The Contractor shall secure, at the Contractor's own expense, areas required for plant sites, storage of equipment or materials, or for other purposes.

No area is available within the contract limits for the exclusive use of the Contractor. However, temporary storage of equipment and materials on State property may be arranged with the Engineer, subject to the prior demands of State maintenance forces and to other contract requirements. Use of the Contractor's work areas and other State-owned property shall be at the Contractor's own risk, and the State shall not be held liable for damage to or loss of materials or equipment located within such areas.

5-1.12 PAYMENTS

Attention is directed to Sections 9-1.06, "Partial Payments," and 9-1.07, "Payment After Acceptance," of the Standard Specifications and these special provisions.

For the purpose of making partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications, the amount set forth for the contract items of work hereinafter listed shall be deemed to be the maximum value of the contract item of work which will be recognized for progress payment purposes:

Roadside Clearing \$20,000

After acceptance of the contract pursuant to the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, the amount, if any, payable for a contract item of work in excess of the maximum value for progress payment purposes hereinabove listed for the item, will be included for payment in the first estimate made after acceptance of the contract.

In determining the partial payments to be made to the Contractor, only the following listed materials will be considered for inclusion in the payment as materials furnished but not incorporated in the work:

- A. Valves
- B. Pipe (Irrigation Systems)
- C. Sprinklers

SECTION 6. (BLANK)

SECTION 7. (BLANK)

SECTION 8. MATERIALS

SECTION 8-1. MISCELLANEOUS

8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS

Only materials and products conforming to the requirements of the specifications shall be incorporated in the work. When metric materials and products are not available, and when approved by the Engineer, and at no cost to the State, materials and products in the inch-pound (Imperial) system which are of equal quality and of the required properties and characteristics for the purpose intended, may be substituted for the equivalent metric materials and products, subject to the following provisions:

- A. Materials and products shown on the plans or in the special provisions as being equivalent may be substituted for the metric materials and products specified or detailed on the plans.
- B. Before other non-metric materials and products will be considered for use the Contractor shall furnish, at the Contractor's expense, evidence satisfactory to the Engineer that the materials and products proposed for use are equal to or better than the materials and products specified or detailed on the plans. The burden of proof as to the quality and suitability of substitutions shall be upon the Contractor and the Contractor shall furnish necessary information as required by the Engineer. The Engineer will be the sole judge as to the quality and suitability of the substituted materials and products and the Engineer's decision will be final.
- C. When the Contractor elects to substitute non-metric materials and products, including materials and products shown on the plans or in the special provisions as being equivalent, the list of sources of material as specified in Section 6-1.01, "Source of Supply and Quality of Materials," of the Standard Specification shall include a list of substitutions to be made and contract items involved. In addition, for a change in design or details the Contractor shall submit plans and working drawings in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications.

Unless otherwise specified, the following substitutions of materials and products will be allowed:

SUBSTITUTION TABLE FOR SIZES OF HIGH STRENGTH STEEL FASTENERS

ASTM Designation: A 325M

METRIC SIZE SHOWN ON THE PLANS mm x thread pitch	IMPERIAL SIZE TO BE SUBSTITUTED inch
M16 x 2	5/8
M20 x 2.5	3/4
M22 x 2.5	7/8
M24 x 3	1
M27 x 3	1-1/8
M30 x 3.5	1-1/4
M36 x 4	1-1/2

SUBSTITUTION TABLE FOR PLAIN WIRE REINFORCEMENT, ASTM Designation: A 82

METRIC SIZE SHOWN ON THE PLANS mm ²	US CUSTOMARY UNITS SIZE TO BE SUBSTITUTED inch ² x 100
MW9	W1.4
MW10	W1.6
MW13	W2.0
MW15	W2.3
MW19	W2.9
MW20	W3.1
MW22	W3.5
MW25	W3.9, except W3.5 in piles only
MW26	W4.0
MW30	W4.7
MW32	W5.0
MW35	W5.4
MW40	W6.2
MW45	W6.5
MW50	W7.8
MW55	W8.5, except W8.0 in piles only
MW60	W9.3
MW70	W10.9, except W11.0 in piles only
MW80	W12.4
MW90	W14.0
MW100	W15.5

SUBSTITUTION TABLE FOR BAR REINFORCEMENT

METRIC BAR DESIGNATION NUMBER SHOWN ON THE PLANS	EQUIVALENT IMPERIAL BAR DESIGNATION NUMBER TO BE SUBSTITUTED
13	4
16	5
19	6
22	7
25	8
29	9
32	10
36	11
43	14
57	18

No adjustment will be required in spacing or total number of reinforcing bars due to a difference in minimum yield strength between metric and non-metric bars.

The sizes in the following tables of materials and products are exact conversions of metric sizes of materials and products and are listed as acceptable equivalents:

CONVERSION TABLE FOR SIZES OF:

- (1) STEEL FASTENERS FOR GENERAL APPLICATIONS, ASTM Designation: A 307 or AASHTO Designation: M 314, Grade 36 or 55, and
 (2) HIGH STRENGTH STEEL FASTENERS, ASTM Designation: A 325 or A 449

METRIC SIZE SHOWN ON THE PLANS mm	EQUIVALENT IMPERIAL SIZE inch
6, or 6.35	1/4
8 or 7.94	5/16
10, or 9.52	3/8
11, or 11.11	7/16
13 or 12.70	1/2
14, or 14.29	9/16
16, or 15.88	5/8
19, or 19.05	3/4
22, or 22.22	7/8
24, 25, or 25.40	1
29, or 28.58	1-1/8
32, or 31.75	1-1/4
35, or 34.93	1-3/8
38 or 38.10	1-1/2
44, or 44.45	1-3/4
51, or 50.80	2
57, or 57.15	2-1/4
64, or 63.50	2-1/2
70 or 69.85	2-3/4
76, or 76.20	3
83, or 82.55	3-1/4
89 or 88.90	3-1/2
95, or 95.25	3-3/4
102, or 101.60	4

CONVERSION TABLE FOR NOMINAL THICKNESS OF SHEET METAL

UNCOATED HOT AND COLD ROLLED SHEETS		HOT-DIPPED ZINC COATED SHEETS (GALVANIZED)	
METRIC THICKNESS SHOWN ON THE PLANS	EQUIVALENT US STANDARD GAGE	METRIC THICKNESS SHOWN ON THE PLANS	EQUIVALENT GALVANIZED SHEET GAGE
mm	inch	mm	inch
7.94	0.3125	4.270	0.1681
6.07	0.2391	3.891	0.1532
5.69	0.2242	3.510	0.1382
5.31	0.2092	3.132	0.1233
4.94	0.1943	2.753	0.1084
4.55	0.1793	2.372	0.0934
4.18	0.1644	1.994	0.0785
3.80	0.1495	1.803	0.0710
3.42	0.1345	1.613	0.0635
3.04	0.1196	1.461	0.0575
2.66	0.1046	1.311	0.0516
2.28	0.0897	1.158	0.0456
1.90	0.0747	1.006 or 1.016	0.0396
1.71	0.0673	0.930	0.0366
1.52	0.0598	0.853	0.0336
1.37	0.0538	0.777	0.0306
1.21	0.0478	0.701	0.0276
1.06	0.0418	0.627	0.0247
0.91	0.0359	0.551	0.0217
0.84	0.0329	0.513	0.0202
0.76	0.0299	0.475	0.0187
0.68	0.0269	-----	-----
0.61	0.0239	-----	-----
0.53	0.0209	-----	-----
0.45	0.0179	-----	-----
0.42	0.0164	-----	-----
0.38	0.0149	-----	-----

CONVERSION TABLE FOR WIRE

METRIC THICKNESS SHOWN ON THE PLANS mm	EQUIVALENT USA STEEL WIRE THICKNESS inch	GAGE NO.
6.20	0.244	3
5.72	0.225	4
5.26	0.207	5
4.88	0.192	6
4.50	0.177	7
4.11	0.162	8
3.76	0.148	9
3.43	0.135	10
3.05	0.120	11
2.69	0.106	12
2.34	0.092	13
2.03	0.080	14
1.83	0.072	15
1.57	0.062	16
1.37	0.054	17
1.22	0.048	18
1.04	0.041	19
0.89	0.035	20

CONVERSION TABLE FOR PIPE PILES

METRIC SIZE SHOWN ON THE PLANS mm x mm	EQUIVALENT IMPERIAL SIZE inch x inch
PP 360 x 4.55	NPS 14 x 0.179
PP 360 x 6.35	NPS 14 x 0.250
PP 360 x 9.53	NPS 14 x 0.375
PP 360 x 11.12	NPS 14 x 0.438
PP 406 x 12.70	NPS 16 x 0.500
PP 460 x T	NPS 18 x T"
PP 508 x T	NPS 20 x T"
PP 559 x T	NPS 22 x T"
PP 610 x T	NPS 24 x T"
PP 660 x T	NPS 26 x T"
PP 711 x T	NPS 28 x T"
PP 762 x T	NPS 30 x T"
PP 813 x T	NPS 32 x T"
PP 864 x T	NPS 34 x T"
PP 914 x T	NPS 36 x T"
PP 965 x T	NPS 38 x T"
PP 1016 x T	NPS 40 x T"
PP 1067 x T	NPS 42 x T"
PP 1118 x T	NPS 44 x T"
PP 1219 x T	NPS 48 x T"
PP 1524 x T	NPS 60 x T"

The thickness in inches (T") represents an exact conversion of the metric thickness in millimeters (T).

CONVERSION TABLE FOR STRUCTURAL TIMBER AND LUMBER

METRIC MINIMUM DRESSED DRY, SHOWN ON THE PLANS mm x mm	METRIC MINIMUM DRESSED GREEN, SHOWN ON THE PLANS mm x mm	EQUIVALENT NOMINAL US SIZE inch x inch
19x89	20x90	1x4
38x89	40x90	2x4
64x89	65x90	3x4
89x89	90x90	4x4
140x140	143x143	6x6
140x184	143x190	6x8
184x184	190x190	8x8
235x235	241x241	10x10
286x286	292x292	12x12

CONVERSION TABLE FOR NAILS AND SPIKES

METRIC COMMON NAIL, SHOWN ON THE PLANS Length, mm Diameter, mm	METRIC BOX NAIL, SHOWN ON THE PLANS Length, mm Diameter, mm	METRIC SPIKE, SHOWN ON THE PLANS Length, mm Diameter, mm	EQUIVALENT IMPERIAL SIZE Penny-weight
50.80 2.87	50.80 2.51	————	6d
63.50 3.33	63.50 2.87	————	8d
76.20 3.76	76.20 3.25	76.20 4.88	10d
82.55 3.76	82.55 3.25	82.55 4.88	12d
88.90 4.11	88.90 3.43	88.90 5.26	16d
101.60 4.88	101.60 3.76	101.60 5.72	20d
114.30 5.26	114.30 3.76	114.30 6.20	30d
127.00 5.72	127.00 4.11	127.00 6.68	40d
————	————	139.70 7.19	50d
————	————	152.40 7.19	60d

CONVERSION TABLE FOR IRRIGATION COMPONENTS

METRIC WATER METERS, TRUCK LOADING STANDPIPES, VALVES, BACKFLOW PREVENTERS, FLOW SENSORS, WYE STRAINERS, FILTER ASSEMBLY UNITS, PIPE SUPPLY LINES, AND PIPE IRRIGATION SUPPLY LINES SHOWN ON THE PLANS DIAMETER NOMINAL (DN) mm	EQUIVALENT NOMINAL US SIZE inch
15	1/2
20	3/4
25	1
32	1-1/4
40	1-1/2
50	2
65	2-1/2
75	3
100	4
150	6
200	8
250	10
300	12
350	14
400	16

8-1.02 APPROVED TRAFFIC PRODUCTS

The Department maintains the following list of Approved Traffic Products. The Engineer shall not be precluded from sampling and testing products on the list of Approved Traffic Products.

The manufacturer of products on the list of Approved Traffic Products shall furnish the Engineer a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each type of traffic product supplied.

Signing and delineation materials and products shall not be used in the work unless the material or product is on the list of Approved Traffic Products.

Materials and products may be added to the list of Approved Traffic Products if the manufacturer submits a New Product Information Form to the New Product Coordinator at the Transportation Laboratory. Upon a Departmental request for samples, sufficient samples shall be submitted to permit performance of required tests. Approval of materials or products will depend upon compliance with the specifications and tests the Department may elect to perform.

PAVEMENT MARKERS, PERMANENT TYPE

Retroreflective

- A. Apex, Model 921 (100 mm x 100 mm)
- B. Ray-O-Lite, Models SS (100 mm x 100 mm), RS (100 mm x 100 mm) and AA (100 mm x 100 mm)
- C. Stimsonite, Models 88 (100 mm x 100 mm), 911 (100 mm x 100 mm), 953 (70 mm x 114 mm)
- D. 3M Series 290 (89 mm x 100 mm)

Retroreflective With Abrasion Resistant Surface (ARS)

- A. Ray-O-Lite "AA" ARS (100 mm x 100 mm)
- B. Stimsonite, Models 911 (100 mm x 100 mm), 953 (70 mm x 114 mm)
- C. 3M Series 290 (89 mm x 100 mm)

Retroreflective With Abrasion Resistant Surface (ARS)

(Used for recessed applications)

- A. Stimsonite, Model 948 (58 mm x 119 mm)
 - B. Ray-O-Lite, Model 2002 (58 mm x 117 mm)
 - C. Stimsonite, Model 944SB (51 mm x 100 mm)*
 - D. Ray-O-Lite, Model 2004 ARS (51 mm x 100 mm)*
- *For use only in 114 mm wide (older) recessed slots

Non-Reflective For Use With Epoxy Adhesive, 100 mm Round

- A. Apex Universal (Ceramic)
- B. Highway Ceramics, Inc. (Ceramic)

Non-Reflective For Use With Bitumen Adhesive, 100 mm Round

- A. Apex Universal (Ceramic)
- B. Apex Universal, Model 929 (ABS)
- C. Elgin Molded Plastics, "Empco-Lite" Model 900 (ABS)
- D. Highway Ceramics, Inc. (Ceramic)
- E. Hi-Way Safety, Inc., Models P20-2000W and 2001Y (ABS)
- F. Interstate Sales, "Diamond Back" (ABS) and (Polypropylene)
- G. Alpine Products, D-Dot (ABS)
- H. Road Creations, Model RCB4NR (Acrylic)

PAVEMENT MARKERS, TEMPORARY TYPE**Temporary Markers For Long Term Day/Night Use (6 months or less)**

- A. Apex Universal, Model 924 (100 mm x 100 mm)
- B. Davidson Plastics Corp., Model 3.0 (100 mm x 100 mm)
- C. Elgin Molded Plastics, "Empco-Lite" Model 901 (100 mm x 100 mm)
- D. Road Creations, Model R41C (100 mm x 100 mm)
- E. Vega Molded Products "Temporary Road Marker" (75 mm x 100 mm)

Temporary Markers For Short Term Day/Night Use (14 days or less)

(For seal coat or chip seal applications, clear protective covers are required)

- A. Apex Universal, Model 932
- B. Davidson Plastics, Models T.O.M., T.R.P.M., and "HH" (High Heat)
- C. Hi-Way Safety, Inc., Model 1280/1281

STRIPING AND PAVEMENT MARKING MATERIALS**Permanent Traffic Striping and Pavement Marking Tape**

- A. Advanced Traffic Marking, Series 300 and 400
- B. Brite-Line, Series 1000
- C. Swarco Industries, "Director 35" (For transverse application only)
- D. Swarco Industries, "Director 60"
- E. 3M, "Stamark" Series 380 and 5730
- F. 3M, "Stamark" Series 420 (For transverse application only)

Temporary (Removable) Striping and Pavement Marking Tape (6 months or less)

- A. Brite-Line, Series 100
- B. P.B. Laminations, Aztec, Grade 102
- C. Swarco Industries, "Director-2"
- D. 3M, "Stamark," Series 620
- E. 3M Series A145 Removable Black Line Mask
(Black Tape: For use only on Asphalt Concrete Surfaces)
- F. Advanced Traffic Marking Black "Hide-A-Line"
(Black Tape: For use only on Asphalt Concrete Surfaces)

Preformed Thermoplastic (Heated in place)

- A. Flint Trading, "Premark" and "Premark 20/20 Flex"
- B. Pavemark, "Hotape"

Removable Traffic Paint

- A. Belpro, Series 250/252 and No. 93 Remover

CLASS 1 DELINEATORS

One Piece Driveable Flexible Type, 1700 mm

- A. Carsonite, Curve-Flex CFRM-400
- B. Carsonite, Roadmarker CRM-375
- C. Davidson Plastics, "Flexi-Guide Models 400 and 566"
- D. FlexStake, Model 654TM
- E. GreenLine Models HWD1-66 and CGD1-66
- F. J. Miller Industries, Model JMI-375 (with soil anchor)

Special Use Flexible Type, 1700 mm

- A. Carsonite, "Survivor" (with 450 mm U-Channel base)
- B. FlexStake, Model 604
- C. GreenLine Models HWD and CGD (with 450 mm U-Channel base)
- D. Safe-Hit with 200 mm pavement anchor (SH248-GP1)
- E. Safe-Hit with 380 mm soil anchor (SH248-GP2) and with 450 mm soil anchor (SH248-GP3)

Surface Mount Flexible Type, 1200 mm

- A. Bent Manufacturing Company, "Masterflex" Model MF-180EX-48
- B. Carsonite, "Super Duck II"
- C. FlexStake, Surface Mount, Models 704 and 754TM

CHANNELIZERS

Surface Mount Type, 900 mm

- A. Bent Manufacturing Company, "Masterflex" Models MF-360-36 (Round) and MF-180-36 (Flat)
- B. Carsonite, "Super Duck" (Flat SDF-436, Round SDR-336)
- C. Carsonite, "Super Duck II" Model SDCF203601MB "The Channelizer"
- D. Davidson Plastics, Flex-Guide Models FG300LD and FG300UR
- E. FlexStake, Surface Mount, Models 703 and 753TM
- F. GreenLine, Model SMD-36
- G. Hi-Way Safety, Inc. "Channel Guide Channelizer" Model CGC36
- H. The Line Connection, "Dura-Post" Model DP36-3 (Permanent)
- I. The Line Connection, "Dura-Post" Model DP36-3C (Temporary)
- J. Repo, Models 300 and 400
- K. Safe-Hit, Guide Post, Model SH236SMA

CONICAL DELINEATORS, 1070 mm

(For 700 mm Traffic Cones, see Standard Specifications)

- A. Bent Manufacturing Company "T-Top"
- B. Plastic Safety Systems "Navigator-42"
- C. Roadmaker Company "Stacker"
- D. Traffix Devices "Grabber"

OBJECT MARKERS

Type "K", 450 mm

- A. Carsonite, Model SMD-615
- B. FlexStake, Model 701KM
- C. Repo, Models 300 and 400
- D. Safe-Hit, Model SH718SMA
- E. The Line Connection, Model DP21-4K

Type "K-4" / "Q", 600 mm

(Shown as Type "Q" in the Traffic Manual)

- A. Bent Manufacturing "Masterflex" Model MF-360-24
- B. Carsonite, Super Duck II
- C. FlexStake, Model 701KM
- D. Repo, Models 300 and 400
- E. Safe-Hit, Models SH8 24SMA_WA and SH8 24GP3_WA
- F. The Line Connection, Model DP21-4Q

TEMPORARY RAILING (TYPE K) REFLECTORS AND CONCRETE BARRIER MARKERS

Impactable Type

- A. ARTUK, "FB"
- B. Davidson Plastics, Model PCBM-12
- C. Duraflex Corp., "Flexx 2020" and "Electriflexx"
- D. Hi-Way Safety, Inc., Model GMKRM100

Non-Impactable Type

- A. ARTUK, JD Series
- B. Stimsonite, Model 967 (with 83 mm Acrylic cube corner reflector)
- C. Stimsonite, Model 967LS
- D. Vega Molded Products, Models GBM and JD

THREE BEAM BARRIER MARKERS

(For use to the left of traffic)

- A. Duraflex Corp., "Railrider"
- B. Davidson Plastics, "Mini" (75 mm x 254 mm)

CONCRETE BARRIER DELINEATORS, 400 mm

(For use to the right of traffic. When mounted on top of barrier, places top of reflective element at 1200 mm)

- A. Davidson Plastics, Model PCBM T-16
- B. Safe-Hit, Model SH216RBM

CONCRETE BARRIER-MOUNTED MINI-DRUM (260 mm x 360 mm x 570 mm)

- A. Stinson Equipment Company "SaddleMarker"

SOUND WALL DELINEATOR

(Applied to a vertical surface. Top of reflective element at 1200 mm)

- A. Davidson Plastics, PCBM S-36

GUARD RAILING DELINEATOR

(Top of reflective element at 1200 mm above plane of roadway)

Wood Post Type, 686 mm

- A. Carsonite, Model 427
- B. Davidson Plastics FG 427 and FG 527
- C. FlexStake, Model 102 GR
- D. GreenLine GRD 27
- E. J. Miller Model JMI-375G
- F. Safe-Hit, Model SH227GRD

Steel Post Type

- A. Carsonite, Model CFGR-327 with CFGRBK300 Mounting Bracket

RETROREFLECTIVE SHEETING

Channelizers, Barrier Markers, and Delineators

- A. 3M, High Intensity
- B. Reflexite, PC-1000 Metalized Polycarbonate
- C. Reflexite, AC-1000 Acrylic
- D. Reflexite, AP-1000 Metalized Polyester
- E. Reflexite, AR-1000 Abrasion Resistant Coating
- F. Stimsonite, Series 6200 (For rigid substrate devices only)

Traffic Cones, 330 mm Sleeves

- A. Reflexite SB (Polyester), Vinyl or "TR" (Semi-transparent)

Traffic Cones, 100 mm and 150 mm Sleeves

- A. 3M Series 3840
- B. Reflexite Vinyl, "TR" (Semi-transparent) or "Conformalite"

Barrels and Drums

- A. Reflexite, "Super High Intensity" or "High Impact Drum Sheeting"
- B. 3M Series 3810

Barricades: Type I, Engineer Grade

- A. American Decal, Adcolite
- B. Avery Dennison, 1500 and 1600
- C. 3M, Scotchlite, Series CW

Barricades: Type II, Super Engineer Grade

- A. Avery Dennison, "Fasign" 2500 Series
- B. Kiwalite Type II
- C. Nikkalite 1800 Series

Signs: Type II, Super Engineer Grade

- A. Avery Dennison, "Fasign" 2500 Series
- B. Kiwalite, Type II
- C. Nikkalite 1800 Series

Signs: Type III, High-Intensity Grade

- A. 3M Series 3800
- B. Nippon Carbide, Nikkalite Brand Ultralite Grade II

Signs: Type IV, High-Intensity Prismatic Grade

- A. Stimsonite Series 6200

Signs: Type VII, High-Intensity Prismatic Grade

- A. 3M Series 3900

Signs: Type VI, Roll-Up Signs

- A. Reflexite, Vinyl (Orange), Reflexite "SuperBright" (Fluorescent orange)
- B. 3M Series RS34 (Orange) and RS20 (Fluorescent orange)

SIGN SUBSTRATE FOR CONSTRUCTION AREA SIGNS

Aluminum

Fiberglass Reinforced Plastic (FRP)

- A. Sequentia, "Polyplate"
- B. Fiber-Brite

8-1.03 STATE-FURNISHED MATERIALS

Attention is directed to Section 6-1.02, "State-Furnished Materials," of the Standard Specifications and these special provisions.

Padlocks for the chain link gates will be furnished to the Contractor.

SECTION 8-2. (BLANK)

SECTION 8-3. WELDING

8-3.01 WELDING ELECTRODES

Flux core welding electrodes conforming to the requirements of AWS A5.20 E6XT-4 or E7XT-4 shall not be used to perform any type of welding for this project.

SECTION 9. (BLANK)

SECTION 10. CONSTRUCTION DETAILS

SECTION 10-1. GENERAL

10-1.00 CONSTRUCTION PROJECT INFORMATION SIGNS

Before any major physical construction work readily visible to highway users is started on this contract, the Contractor shall furnish and erect 2 Type 2 Construction Project Information signs at the locations designated by the Engineer.

The signs and overlays shall be of a type and material consistent with the estimated time of completion of the project and shall conform to the details shown on the plans.

The sign letters, border and the Department's construction logos shall conform to the colors (non-reflective) and details shown on the plans, and shall be on a white background (non-reflective). The colors blue and orange shall conform to PR Color Number 3 and Number 6, The sign message to be used for fund types shall consist of the following, in the order shown:

FEDERAL HIGHWAY TRUST FUNDS
STATE HIGHWAY FUNDS

The sign message to be used for type of work shall consist of the following:

ROADSIDE WORK

The sign message to be used for the Year of Completion of Project Construction will be furnished by the Engineer. The Contractor shall furnish and install the "Year" sign overlay within 10 working days of notification of the year date to be used.

The letter sizes to be used shall be as shown on the plans. The information shown on the signs shall be limited to that shown on the plans.

The signs shall be kept clean and in good repair by the Contractor.

Upon completion of the work, the signs shall be removed and disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13 of the Standard Specifications.

Full compensation for furnishing, erecting, maintaining, and removing and disposing of the construction project information signs shall be considered as included in the contract lump sum price paid for construction area signs and no additional compensation will be allowed therefor.

10-1.01 ORDER OF WORK

Order of work shall conform to the provisions in Section 5-1.05, "Order of Work," of the Standard Specifications and these special provisions.

Within 30 days after the contract has been approved, the Contractor shall furnish the Engineer a statement from the vendor that the order for the plants required for this contract, including inspection plants, has been received and accepted by the vendor. The statement from the vendor shall include the names, sizes, and quantities of plants ordered and the anticipated date of delivery.

The Contractor shall place orders for replacement plants with the vendor at the appropriate time so that the roots of the replacement plants are not in a root-bound condition.

Contract No. «Dist»-«Contract_No»

Attention is directed to Section 9-1.06, "Partial Payments," of the Standard Specifications. For progress payment purposes, the Department will retain 50 percent of the estimated value of highway planting work done until a statement from the vendor that the order for the plants required for this contract has been submitted to the Engineer.

Attention is directed to "Maintain Existing Plants" of these special provisions regarding checking for deficiencies of existing plants that are to remain in place, prior to the start of irrigation work.

Attention is directed to "Irrigation Systems Functional Test" of these special provisions, regarding restrictions for planting operations.

Attention is directed to "Locate Existing Crossovers and Conduits" of these special provisions regarding locating existing irrigation water line crossovers and conduits shown on the plans to be incorporated in the new work. Existing irrigation water line crossovers and conduits shall be located prior to performing work on the irrigation system.

Unless otherwise shown on the plans or specified in these special provisions, conduits to be jacked or drilled for water line crossovers and sprinkler control crossovers shall be installed prior to the installation of other pipe supply lines.

Attention is directed to "Existing Highway Irrigation Facilities" of these special provisions regarding the checking of existing irrigation facilities that are to remain in place, prior to the start of any irrigation work.

10-1.02 WATER POLLUTION CONTROL

Water pollution control work shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications and these special provisions.

This project shall conform to the requirements of General Construction Activity Storm Water Permit No. CAS000002 issued by the State Water Resources Control Board. This General Permit, hereafter referred to as the "Permit," regulates storm water discharges associated with construction activities.

Water pollution control work shall conform to the requirements in the Construction Contractor's Guide and Specifications of the Caltrans Storm Water Quality Handbooks, dated April 1997, and addenda thereto issued up to, and including, the date of advertisement of the project, hereafter referred to as the "Handbook." Copies of the Handbook and the General Permit may be obtained from the Department of Transportation, Material Operations Branch, Publication Distribution Unit, 1900 Royal Oaks Drive, Sacramento, California 95815, Telephone: (916) 445-3520.

The Contractor shall know and fully comply with the applicable provisions of the Handbook, Permit, and Federal, State, and local regulations that govern the Contractor's operations and storm water discharges from both the project site and areas of disturbance outside the project limits during construction. The Contractor shall maintain a copy of the Permit at the project site and shall make the Permit available during construction.

Unless arrangements for disturbance of areas outside the project limits are made by the Department and made part of the contract, it is expressly agreed that the Department assumes no responsibility whatsoever to the Contractor or property owner with respect to any arrangements made between the Contractor and property owner to allow disturbance of areas outside the project limits.

The Contractor shall be responsible for the costs and for liabilities imposed by law as a result of the Contractor's failure to comply with the provisions set forth in this section "Water Pollution Control", including but not limited to, compliance with the applicable provisions of the Handbook, Permit and Federal, State and local regulations. For the purposes of this paragraph, costs and liabilities include, but are not limited to, fines, penalties, and damages whether assessed against the State or the Contractor, including those levied under the Federal Clean Water Act and the State Porter Cologne Water Quality Act.

In addition to the remedies authorized by law, some of the money due the Contractor under the contract, as determined by the Department, may be retained by the State of California until disposition has been made of the costs and liabilities.

The retention of money due the Contractor shall be subject to the following:

- A. The Department will give the Contractor 30 days notice of the Department's intention to retain funds from partial payments which may become due to the Contractor prior to acceptance of the contract. Retention of funds from payments made after acceptance of the contract may be made without prior notice to the Contractor.
- B. No retention of additional amounts out of partial payments will be made if the amount to be retained does not exceed the amount being withheld from partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications.
- C. If the Department has retained funds and it is subsequently determined that the State is not subject to the costs and liabilities in connection with the matter for which the retention was made, the Department shall be liable for interest on the amount retained at the legal rate of interest for the period of the retention.

Conformance with the provisions of this section "Water Pollution Control" shall not relieve the Contractor from the Contractor's responsibilities, as provided in Section 7, "Legal Relations and Responsibilities," of the Standard Specifications.

At reasonable times and upon presentation of credentials and other documents as may be required by law, the Contractor shall allow authorized agents of the California Regional Water Quality Control Board, State Water Resources Control Board, United States Environmental Protection Agency and the local storm water management agency to:

- A. Enter upon the construction site and the Contractor's facilities pertinent to the work;
- B. Have access to and copy records that must be kept as specified in the Permit;
- C. Inspect the construction site and related soil stabilization practices and sediment control measures; and
- D. Sample or monitor for the purpose of ensuring compliance with the Permit.

The Contractor shall notify the Engineer immediately upon request from the regulatory agencies to enter, inspect, sample, monitor or otherwise access the project site or the Contractor's records.

STORM WATER POLLUTION PREVENTION PLAN PREPARATION, APPROVAL AND UPDATES

As part of the water pollution control work, a Storm Water Pollution Prevention Plan, hereafter referred to as the "SWPPP," is required for this contract. The SWPPP shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications, the requirements in the Handbook, the requirements of the Permit, and these special provisions. Upon the Engineer's approval of the SWPPP, the SWPPP shall be deemed to fulfill the provisions in Section 7-1.01G of the Standard Specifications for development and submittal of a Water Pollution Control Program.

No work having potential to cause water pollution, as determined by the Engineer, shall be performed until the SWPPP has been approved by the Engineer.

Within 30 days after the approval of the contract, the Contractor shall submit 3 copies of the SWPPP to the Engineer. The Engineer will have 5 days to review the SWPPP. If revisions are required, as determined by the Engineer, the Contractor shall revise and resubmit the SWPPP within 5 days of receipt of the Engineer's comments. The Engineer will have 5 days to review the revisions. Upon the Engineer's approval of the SWPPP, 3 additional copies of the SWPPP, incorporating the required changes, shall be submitted to the Engineer. In order to allow construction activities to proceed, the Engineer may conditionally approve the SWPPP while minor revisions are being completed.

The SWPPP shall identify pollution sources that may adversely affect the quality of storm water discharges associated with the project and shall identify water pollution control measures, hereafter referred to as control measures, to be constructed, implemented, and maintained in order to reduce to the extent feasible pollutants in storm water discharges from the construction site both during and after construction is completed under this contract.

The SWPPP shall incorporate control measures in the following categories:

- A. Soil stabilization practices;
- B. Sediment control practices;
- C. Sediment tracking control practices;
- D. Wind erosion control practices; and
- E. Non-storm water management and waste management and disposal control practices.

Specific objectives and minimum requirements for each category of control measures are contained in the Handbook.

The Contractor shall consider the objectives and minimum requirements presented in the Handbook for each of the above categories. When minimum requirements are listed for any category, the Contractor shall incorporate into the SWPPP and implement on the project, one or more of the listed minimum controls required in order to meet the pollution control objectives for the category. In addition, the Contractor shall consider other control measures presented in the Handbook and shall incorporate into the SWPPP and implement on the project the control measures necessary to meet the objectives of the SWPPP. The Contractor shall document the selection process in conformance with the procedure specified in the Handbook.

The SWPPP shall include, but not limited to, the following items as described in the Handbook and Permit:

- A. Source Identification;
- B. Erosion and Sediment Controls;
- C. Non-Storm Water Management;
- D. Waste Management and Disposal;
- E. Maintenance, Inspection and Repair;
- F. Training;
- G. List of Contractors and Subcontractors;
- H. Post-Construction Storm Water Management;
- I. Preparer;
- J. A copy of the NOI submitted by the Department for this project;
- K. Copy of the NOI;
- L. BMP Consideration Checklist;
- M. SWPPP Checklist;

- N. Schedule of Values; and
- O. Water Pollution Control Drawings.

The Contractor shall amend the SWPPP, graphically and in narrative form, whenever there is a change in construction activities or operations which may affect the discharge of significant quantities of pollutants to surface waters, ground waters, municipal storm drain systems or when deemed necessary by the Engineer. The SWPPP shall be amended if the SWPPP is in violation of any condition of the Permit, or has not effectively achieved the objective of reducing pollutants in storm water discharges. Amendments shall show additional control measures or revised operations, including those in areas not shown in the initially approved SWPPP, which are required on the project to control water pollution effectively. Amendments to the SWPPP shall be submitted for review and approval by the Engineer in the same manner specified for the initially approved SWPPP. Approved amendments shall be dated and logged in the SWPPP. Upon approval of the amendment, the Contractor shall implement the additional control measures or revised operations.

The Contractor shall keep a copy of the SWPPP and approved amendments at the project site. The SWPPP shall be made available upon request of a representative of the Regional Water Quality Control Board, State Water Resources Control Board, United States Environmental Protection Agency or the local storm water management agency. Requests by the public shall be directed to the Engineer.

By June 15 of each year, the Contractor shall submit an annual certification to the Engineer stating conformance with the requirements governing the Permit. If the project is in non-compliance at any time, the Contractor shall make a written report to the Engineer within 15 days of identification of non-compliance.

SCHEDULE OF VALUES

The Contractor shall submit with the SWPPP, for approval by the Engineer, a schedule of values detailing the cost breakdown of the contract lump sum item for water pollution control. The schedule of values shall reflect the items of work, quantities, and costs for the control measures shown in the SWPPP, except for critical temporary controls and permanent control measures which are shown on the project plans and for which there is a contract item of work. Adjustments in the items of work and quantities listed in the schedule of values shall be made when required to address approved amendments to the SWPPP.

The sum of the amounts for the units of work listed in the schedule of values shall be equal to the contract lump sum price for water pollution control.

If approved in writing by the Engineer, the schedule of values will be used to determine progress payments for water pollution control during the progress of the work. The schedule of values will be used as the basis for calculating any adjustment in compensation for the contract item for water pollution control due to changes in the work ordered by the Engineer.

SWPPP IMPLEMENTATION

Upon approval of the SWPPP, the Contractor shall be responsible throughout the duration of the project for installing, constructing, inspecting, and maintaining the control measures included in the SWPPP and any amendments thereto and for removing and disposing of temporary control measures. Unless otherwise directed by the Engineer or specified in these special provisions, the Contractor's responsibility for SWPPP implementation shall continue throughout any temporary suspension of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications. Requirements for installation, construction, inspection, maintenance, removal, and disposal of control measures are specified in the Handbook and these special provisions.

Soil stabilization practices and sediment control measures, including minimum requirements, shall be provided throughout the winter season, defined as between November 1 and March 15

Implementation of soil stabilization practices and sediment control measures for soil-disturbed areas on the project site shall be completed, except as provided for below, not later than 20 days prior to the beginning of the winter season or upon start of applicable construction activities for projects which begin either during or within 20 days of the winter season.

Throughout the winter season, the active, soil-disturbed area of the project site shall be not more than 2 hectares. The Engineer may approve, on a case-by-case basis, expansions of the active, soil-disturbed area limit. The Contractor shall demonstrate the ability and preparedness to fully deploy soil stabilization practices and sediment control measures to protect soil-disturbed areas on the project site before the onset of precipitation. A quantity of soil stabilization and sediment control materials shall be maintained on site equal to 100 percent of that sufficient to protect unprotected, soil-disturbed areas on the project site. A detailed plan for the mobilization of sufficient labor and equipment shall be maintained to fully deploy control measures required to protect unprotected, soil-disturbed areas on the project site prior to the onset of precipitation. A current inventory of control measure materials and the detailed mobilization plan shall be included as part of the SWPPP.

Throughout the winter season, soil-disturbed areas of the project site shall be considered to be nonactive whenever soil disturbing activities are expected to be discontinued for a period of 20 or more days and the areas are fully protected. Areas that will become nonactive either during the winter season or within 20 days thereof shall be fully protected with soil

stabilization practices and sediment control measures within 10 days of the discontinuance of soil disturbing activities or prior to the onset of precipitation, whichever is first to occur.

Throughout the winter season, active soil-disturbed areas of the project site shall be fully protected at the end of each day with soil stabilization practices and sediment control measures unless fair weather is predicted through the following work day. The weather forecast shall be monitored by the Contractor on a daily basis. The National Weather Service forecast shall be used. An alternative weather forecast proposed by the Contractor may be used if approved by the Engineer. If precipitation is predicted prior to the end of the following work day, construction scheduling shall be modified, as required, and functioning control measures shall be deployed prior to the onset of the precipitation.

The Contractor shall implement, year-round and throughout the duration of the project, control measures included in the SWPPP for sediment tracking, wind erosion, non-storm water management and waste management and disposal.

The Engineer may order the suspension of construction operations which create water pollution if the Contractor fails to conform to the provisions of this section "Water Pollution Control" as determined by the Engineer.

MAINTENANCE

To ensure the proper implementation and functioning of control measures, the Contractor shall regularly inspect and maintain the construction site for the control measures identified in the SWPPP. The Contractor shall identify corrective actions and time needed to address any deficient measures or reinitiate any measures that have been discontinued.

The construction site inspection checklist provided in the Handbook shall be used to ensure that the necessary measures are being properly implemented, and to ensure that the control measures are functioning adequately. One copy of each site inspection record shall be submitted to the Engineer.

During the winter season, inspections of the construction site shall be conducted by the Contractor to identify deficient measures, as follows:

- A. Prior to a forecast storm;
- B. After any precipitation which causes runoff capable of carrying sediment from the construction site;
- C. At 24 hour intervals during extended precipitation events; and
- D. Routinely, at a minimum of once every 2 weeks.

If the Contractor or the Engineer identifies a deficiency in the deployment or functioning of an identified control measure, the deficiency shall be corrected immediately. The deficiency may be corrected at a later date and time if requested by the Contractor and approved by the Engineer in writing, but not later than the onset of subsequent precipitation. The correction of deficiencies shall be at no additional cost to the State.

PAYMENT

The contract lump sum price paid for prepare storm water pollution prevention plan shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals for doing all the work involved in developing, preparing, obtaining approval of, revising, and amending the SWPPP, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Attention is directed to Section 9-1.06, "Partial Payments," and Section 9-1.07, "Payment After Acceptance," of the Standard Specifications. Payments for prepare storm water pollution prevention plan will be made as follows:

- A. After the SWPPP has been approved by the Engineer, 75 percent of the contract item price for prepare storm water pollution prevention plan will be included in the monthly partial payment estimate; and
- B. After acceptance of the contract pursuant to Section 7-1.17, "Acceptance of Contract," payment for the remaining 25 percent of the contract item price for prepare storm water pollution prevention plan will be made in conformance with the provisions in Section 9-1.07.

The contract lump sum price paid for water pollution control shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing, constructing, maintaining, removing, and disposing of control measures, except those shown on the plans and for which there is a contract item of work, and excluding developing, preparing, obtaining approval of, revising, and amending the SWPPP, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Changes in control measures required by an approved amendment to the SWPPP, except changes to those control measures shown on the plans and for which there is a contract item of work, will be considered extra work as provided in Section 4-1.03D of the Standard Specifications and the following:

- A. If the control measure is listed in the approved SWPPP schedule of values, an adjustment in compensation for the contract item for water pollution control will be made by applying the increase or decrease in quantities to the

approved schedule of values. No adjustment of compensation will be made to the unit price listed for items in the schedule of values due to any increase or decrease in the quantities, regardless of the reason for the increase or decrease. The provisions in Section 4-1.03B, "Increased or Decreased Quantities," of the Standard Specifications shall not apply to items listed in the schedule of values.

- B. If the control measure is not listed in the approved SWPPP schedule of values, payment will be made by force account.

Those control measures which are shown on the plans and for which there is a contract item of work will be measured and paid for as that contract item of work.

The Engineer will retain an amount equal to 25 percent of the estimated value of the contract work performed during estimate periods in which the Contractor fails to conform to the provisions of this section "Water Pollution Control" as determined by the Engineer.

Retentions for failure to conform to the provisions in this section "Water Pollution Control" shall be in addition to the other retentions provided for in the contract. The amounts retained for failure of the Contractor to conform to the provisions in this section will be released for payment on the next monthly estimate for partial payment following the date that an approved SWPPP has been implemented and maintained, and water pollution is adequately controlled, as determined by the Engineer.

10-1.03 PRESERVATION OF PROPERTY

Attention is directed to Section 7-1.11, "Preservation of Property," of the Standard Specifications and these special provisions.

Existing trees, shrubs and other plants, that are not to be removed as shown on the plans or specified in these special provisions, and are injured or damaged by reason of the Contractor's operations, shall be replaced by the Contractor. The minimum size of tree and shrub replacement shall be No. 15 container. Replacement of Carpobrotus ground cover plants shall be from cuttings and shall be planted 300 mm on center. Replacement planting shall conform to the requirements in Section 20-4.07, "Replacement," of the Standard Specifications. The Contractor shall water replacement plants in conformance with the provisions in Section 20-4.06, "Watering," of the Standard Specifications.

Damaged or injured plants shall be removed and disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13 of the Standard Specifications. At the option of the Contractor, removed trees and shrubs may be reduced to chips. The chipped material shall be spread within the highway right of way at locations designated by the Engineer.

Replacement planting of injured or damaged trees, shrubs, and other plants shall be completed prior to the start of the plant establishment period. Replacement planting shall conform to the provisions in Section 20-4.05, "Planting," of the Standard Specifications.

10-1.04 DAMAGE REPAIR

Attention is directed to Section 7-1.16, "Contractor's Responsibility for the Work and Materials," and Section 7-1.165, "Damage by Storm, Flood, Tsunami or Earthquake," of the Standard Specifications and these special provisions.

Damage to slopes or other existing facilities occurring prior to the performance of the work provided for in this contract shall be repaired or reconstructed by the Contractor, as directed by the Engineer. Damage repair will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Storm damage caused by a change in the runoff pattern from that which existed on the day the Notice to Contractors for this project is dated and was the result of work by others within the right of way shall be repaired as directed by the Engineer. The total cost of ordered repair work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Damage to slopes or other facilities occurring after start of work and before start of plant establishment period shall be repaired or reconstructed by the Contractor in conformance with the provisions in Section 7-1.16, "Contractor's Responsibility for the Work and Materials," of the Standard Specifications.

Damage to slopes, plants, irrigation systems and other highway facilities occurring as a result of rain during the plant establishment period shall be repaired by the Contractor, when directed by the Engineer. The cost of the repairs which exceed the accumulated sum of \$8,700 will be borne equally by the State and the Contractor. The division of cost will be made by determining the cost of repairs in conformance with the provisions in Section 9-1.03, "Force Account Payment," of the Standard Specifications, and paying to the Contractor one-half of the cost which exceeds the sum of \$8,700.

When as a result of freezing conditions (as defined herein) during the plant establishment period, plants have died or, in the opinion of the Engineer, have deteriorated to a point beyond which the plants will not mature as typical examples of their species, the Engineer may direct replacement of the affected plants. The total cost of ordered plant replacement work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. A freezing condition, for the purpose

of this specification, occurs when the temperature at or near the affected area has been officially recorded below 0°C and plants have been killed or damaged to the degree described above.

When, as a result of drought conditions (as defined herein) during the plant establishment period, plants have died or, in the opinion of the Engineer, have deteriorated to a point beyond which the plants will not mature as typical examples of their species, the Engineer may direct replacement of the affected plants. The total cost of ordered plant replacements, after water has been restricted or stopped, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. Restriction or shutoff of available water shall not relieve the Contractor from performing other contract work. A drought condition occurs when the Department, or its supplier, restricts or stops delivery of water to the Contractor to the degree that plants have died or deteriorated as described above.

When the provisions in Section 7-1.165, "Damage by Storm, Flood, Tsunami or Earthquake," of the Standard Specifications are applicable, the provisions above for payment of costs for repair of damage due to rain, freezing conditions and drought shall not apply.

10-1.05 PROGRESS SCHEDULE

Progress schedules are required for this contract and shall be submitted in conformance with the provisions in Section 8-1.04, "Progress Schedule," of the Standard Specifications.

10-1.06 OBSTRUCTIONS

Attention is directed to Section 8-1.10, "Utility and Non-Highway Facilities," and Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Attention is directed to the existence of certain underground facilities that may require special precautions be taken by the Contractor to protect the health, safety and welfare of workers and of the public. Facilities requiring special precautions include, but are not limited to: conductors of petroleum products, oxygen, chlorine, and toxic or flammable gases; natural gas in pipelines greater than 150 mm in diameter or pipelines operating at pressures greater than 415 kPa (gage); underground electric supply system conductors or cables, with potential to ground of more than 300 V, either directly buried or in a duct or conduit which do not have concentric grounded or other effectively grounded metal shields or sheaths.

The Contractor shall notify the Engineer and the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to performing any excavation or other work close to any underground pipeline, conduit, duct, wire or other structure. Regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	1-800-642-2444 1-800-227-2600
Underground Service Alert-Southern California (USA)	1-800-422-4133 1-800-227-2600

10-1.07 MOBILIZATION

Mobilization shall conform to the provisions in Section 11, "Mobilization," of the Standard Specifications.

10-1.08 CONSTRUCTION AREA SIGNS

Construction area signs shall be furnished, installed, maintained, and removed when no longer required in conformance with the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to the provisions in "Approved Traffic Products" of these special provisions. Type II retroreflective sheeting shall not be used on construction area sign panels.

Attention is directed to "Construction Project Information Signs" of these special provisions regarding the number and type of construction project information signs to be furnished, erected, maintained, and removed and disposed of.

The Contractor shall notify the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to commencing excavation for construction area sign posts. The regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	1-800-642-2444 1-800-227-2600
Underground Service Alert-Southern California (USA)	1-800-422-4133 1-800-227-2600

Excavations required to install construction area signs shall be performed by hand methods without the use of power equipment, except that power equipment may be used if it is determined there are no utility facilities in the area of the proposed post holes.

Sign substrates for stationary mounted construction area signs may be fabricated from fiberglass reinforced plastic as specified under "Approved Traffic Products" of these special provisions.

10-1.09 MAINTAINING TRAFFIC

Attention is directed to Sections 7-1.08, "Public Convenience," 7-1.09, "Public Safety," and 12, "Construction Area Traffic Control Devices," of the Standard Specifications and to the provisions in "Public Safety" of these special provisions and these special provisions. Nothing in these special provisions shall be construed as relieving the Contractor from the responsibilities specified in Section 7-1.09.

Ramp closures shall conform to the provisions in section "Traffic Control System for Ramp Closures" of these special provisions.

No work that would require a lane closure shall be performed.

Personal vehicles of the Contractor's employees shall not be parked on the traveled way or shoulders including any section closed to public traffic.

Whenever vehicles or equipment are parked on the shoulder within 1.8 m of a traffic lane, the shoulder area shall be closed as shown on the plans.

Ramps shall be closed only during the hours shown on the charts included in this section "Maintaining Traffic." Except work required under Sections 7-1.08 and 7-1.09, work that interferes with public traffic shall be performed only during the hours shown for lane closures.

Designated legal holidays are: January 1st, the third Monday in February, the last Monday in May, July 4th, the first Monday in September, November 11th, Thanksgiving Day, and December 25th. When a designated legal holiday falls on a Sunday, the following Monday shall be a designated legal holiday. When November 11th falls on a Saturday, the preceding Friday shall be a designated legal holiday.

Minor deviations from the requirements of this section concerning hours of work which do not significantly change the cost of the work may be permitted upon the written request of the Contractor, if in the opinion of the Engineer, public traffic will be better served and the work expedited. These deviations shall not be adopted by the Contractor until the Engineer has approved the deviations in writing. All other modifications will be made by contract change order.

Chart No. 1 Ramp Requirements																									
Location: Route 99 - Northbound On-ramp from Hatch/Joyce																									
FROM HOUR TO HOUR	a.m.												p.m.												
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	1	1	1	1	1	1																	1	1	1
Fridays	1	1	1	1	1	1																			
Saturdays																									
Sundays																					1	1	1	1	1
Day before designated legal holiday																									
Designated legal holidays																									

Legend:

☐ 1 Ramp may be closed

☐ No work that interferes with public traffic will be allowed

REMARKS:

Chart No. 2 Ramp Requirements																									
Location: Route 99 - Northbound Off-ramp and Southbound On-ramp from Tuolumne Blvd.																									
FROM HOUR TO HOUR	a.m.												p.m.												
	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Mondays through Thursdays	1	1	1	1	1	1															1	1	1	1	1
Fridays	1	1	1	1	1	1																			
Saturdays																									
Sundays																					1	1	1	1	1
Day before designated legal holiday																									
Designated legal holidays																									

Legend:

☐ 1 Ramp may be closed

☐ No work that interferes with public traffic will be allowed

REMARKS:

10-1.10 CLOSURE REQUIREMENTS AND CONDITIONS

Closures shall conform to the provisions in "Maintaining Traffic" of these special provisions and these special provisions.

The term closure, as used herein, is defined as the closure of a ramp within a single traffic control system.

CLOSURE SCHEDULE

By Noon Monday, the Contractor shall submit a written schedule of planned closures for the following week period, defined as Friday Noon through the following Friday Noon.

The Closure Schedule shall show the locations and times when the proposed closures are to be in effect. The Contractor shall use the Closure Schedule request forms furnished by the Engineer. Closure Schedules submitted to the Engineer with incomplete, unintelligible or inaccurate information will be returned for correction and resubmittal. The Contractor will be notified of disapproved closures or closures that require coordination with other parties as a condition of approval.

Contract No. «Dist»-«Contract_No»

Amendments to the Closure Schedule, including adding additional closures, shall be submitted to the Engineer, in writing, at least 3 working days in advance of a planned closure. Approval of amendments to the Closure Schedule will be at the discretion of the Engineer.

The Contractor shall confirm, in writing, all scheduled closures by no later than 8:00 a.m. 3 working days prior to the date on which the closure is to be made. Approval or denial of scheduled closures will be made no later than 4:00 p.m. 2 working days prior to the date on which the closure is to be made. Closures not confirmed or approved will not be allowed.

Confirmed closures that are cancelled due to unsuitable weather may be rescheduled at the discretion of the Engineer for the following working day.

CONTINGENCY PLAN

The Contractor shall prepare a contingency plan for reopening closures to public traffic. The Contractor shall submit the contingency plan for a given operation to the Engineer within one working day of the Engineer's request.

LATE REOPENING OF CLOSURES

If a closure is not reopened to public traffic by the specified time, work shall be suspended in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications. The Contractor shall not make any further closures until the Engineer has accepted a work plan, submitted by the Contractor, that will insure that future closures will be reopened to public traffic at the specified time. The Engineer will have 2 working days to accept or reject the Contractor's proposed work plan. The Contractor will not be entitled to any compensation for the suspension of work resulting from the late reopening of closures.

COMPENSATION

The Contractor shall notify the Engineer of any delay in the Contractor's operations due to the following conditions, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of those conditions, and the Contractor's loss due to that delay could not have been avoided by rescheduling the affected closure or by judicious handling of forces, equipment and plant, the delay will be considered a right of way delay within the meaning of Section 8-1.09, "Right of Way Delays," and compensation for the delay will be determined in conformance with the provisions in Section 8-1.09:

- A. The Contractor's proposed Closure Schedule is denied and his planned closures are within the time frame allowed for closures in "Maintaining Traffic" of these special provisions, except that the Contractor will not be entitled to any compensation for amendments to the Closure Schedule that are not approved.
- B. The Contractor is denied a confirmed closure.

Should the Engineer direct the Contractor to remove a closure prior to the time designated in the approved Closure Schedule, any delay to the Contractor's schedule due to removal of the closure will be considered a right of way delay within the meaning of Section 8-1.09, "Right of Way Delays," and compensation for the delay will be determined in conformance with the provisions in Section 8-1.09.

10-1.11 TRAFFIC CONTROL SYSTEM FOR RAMP CLOSURES

At the times and locations specified under "Maintaining Traffic" of these special provisions, ramps shall be closed in conformance with the details shown on the plans, the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications, and these special provisions.

The provisions in this section will not relieve the Contractor of the responsibility to provide additional devices or take measures as may be necessary to comply with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications.

If components used for closing a ramp are displaced or cease to operate or function as specified, from any cause, during the progress of the work, the Contractor shall immediately repair the components to the original condition or replace the components and shall restore the components to the original location.

When ramp closures are made for work periods only, at the end of each work period, components used for the ramp closure, except portable delineators placed along open trenches or excavation adjacent to the traveled way, shall be removed from the traveled way and shoulder. If the Contractor so elects, the components may be stored at selected central locations designated by the Engineer within the limits of the highway right of way.

Full compensation for providing the ramp closures shown on the plans (including signs) shall be considered as included in the contract prices paid for the various items of work and no separate payment will be made therefor.

10-1.12 PORTABLE CHANGEABLE MESSAGE SIGN

Two portable changeable message signs shall be furnished, placed, operated, and maintained for each lane closure at those locations shown on the plans or where designated by the Engineer in conformance with the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

At the Contractor's option, one of the portable changeable message signs may be truck mounted.

All portable changeable message signs will be paid for by a lump sum price.

The contract lump sum price paid for portable changeable message signs shall include full compensation for furnishing all labor, material, tools, equipment, and incidentals, and for doing all the work involved in furnishing, placing, operating, maintaining, repairing, replacing, transporting from location to location, and removing the portable changeable message signs, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.13 TEMPORARY CRASH CUSHION MODULE

This work shall consist of furnishing, installing, and maintaining sand filled temporary crash cushion modules in groupings or arrays at each location shown on the plans, as specified in these special provisions or where designated by the Engineer. The grouping or array of sand filled modules shall form a complete sand filled temporary crash cushion in conformance with the details shown on the plans and these special provisions.

Attention is directed to "Public Safety" of these special provisions.

GENERAL

Whenever the work or the Contractor's operations establishes a fixed obstacle, the exposed fixed obstacle shall be protected with a sand filled temporary crash cushion. The sand filled temporary crash cushion shall be in place prior to opening the lanes adjacent to the fixed obstacle to public traffic.

Sand filled temporary crash cushions shall be maintained in place at each location, including times when work is not actively in progress. Sand filled temporary crash cushions may be removed during a work period for access to the work provided that the exposed fixed obstacle is 4.6 m or more from a lane carrying public traffic and the temporary crash cushion is reset to protect the obstacle prior to the end of the work period in which the fixed obstacle was exposed. When no longer required, as determined by the Engineer, sand filled temporary crash cushions shall be removed from the site of the work.

MATERIALS

At the Contractor's option, the modules for use in sand filled temporary crash cushions shall be either Energite III Inertial Modules, Fitch Inertial Modules or Traffix Sand Barrels manufactured after March 31, 1997, or equal:

- A. Energite III Inertial Modules, manufactured by Energy Absorption Systems, Inc., One East Wacker Drive, Chicago, IL 60601-2076, Telephone 1-312-467-6750, FAX 1-800-770-6755.
 - 1. Distributor (Northern): Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828, Telephone 1-800-884-8274, FAX 1-916-387-9734
 - 2. Distributor (Southern): Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, CA 92805, Telephone 1-800-222-8274, FAX 1-714-937-1070.
- B. Fitch Inertial Modules, manufactured by Roadway Safety Service, Inc., 1050 North Rand Road, Wauconda, IL 60084, Telephone 1-800-426-0839, FAX 1-847-487-9820.
 - 1.. Distributor (Northern): Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828, Telephone 1-800-884-8274, FAX 1-916-387-9734
 - 2. Distributor (Southern): Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, CA 92805, Telephone 1-800-222-8274, FAX 1-714-937-1070.
- C. Traffix Sand Barrels, manufactured by Traffix Devices, Inc., 220 Calle Pintosco, San Clemente, CA 92672, Telephone 1-949-361-5663, FAX 1-949-361-9205.
 - 1. Russ Enterprises, Inc., 1533 Berger Drive, San Jose, CA 95112, Telephone 1-408-287-4303, FAX 1-408-287-1929.
 - 2. Statewide Safety, P.O. Box 1440, Pismo Beach, CA 93448, Telephone 1-800-559-7080, FAX 1-805-929-5786.

Modules contained in each temporary crash cushion shall be of the same type at each location. The color of the modules shall be the standard yellow color, as furnished by the vendor, with black lids. The modules shall exhibit good workmanship free from structural flaws and objectionable surface defects. The modules need not be new. Good used undamaged modules

conforming to color and quality of the types specified herein may be utilized. If used Fitch modules requiring a seal are furnished, the top edge of the seal shall be securely fastened to the wall of the module by a continuous strip of heavy duty tape.

Modules shall be filled with sand in conformance with the manufacturer's directions, and to the sand capacity in kilograms for each module shown on the plans. Sand for filling the modules shall be clean washed concrete sand of commercial quality. At the time of placing in the modules, the sand shall contain not more than 7 percent water as determined by California Test 226.

Modules damaged due to the Contractor's operations shall be repaired immediately by the Contractor at the Contractor's expense. Modules damaged beyond repair, as determined by the Engineer, due to the Contractor's operations shall be removed and replaced by the Contractor at the Contractor's expense.

INSTALLATION

Temporary crash cushion modules shall be placed on movable pallets or frames conforming to the dimensions shown on the plans. The pallets or frames shall provide a full bearing base beneath the modules. The modules and supporting pallets or frames shall not be moved by sliding or skidding along the pavement or bridge deck.

A Type R or P marker panel shall be attached to the front of the crash cushion as shown on the plans, when the closest point of the crash cushion array is within 3.6 m of the traveled way. The marker panel, when required, shall be firmly fastened to the crash cushion with commercial quality hardware or by other methods determined by the Engineer.

At the completion of the project, temporary crash cushion modules, sand filling, pallets or frames, and marker panels shall become the property of the Contractor and shall be removed from the site of the work. Temporary crash cushion modules shall not be installed in the permanent work.

MEASUREMENT AND PAYMENT

Temporary crash cushion modules placed in conformance with the provisions in "Public Safety" of these special provisions will not be measured nor paid for.

10-1.14 CHAIN LINK GATE

Chain link gates shall be Type CL-1.8 conforming to the provisions in Section 80, "Fences," of the Standard Specifications and these special provisions.

Gates shall be installed in existing fences at the locations shown on the plans. Gate installations shall be complete with gate post, latch post, concrete footings, braces, truss rods, and hardware. Gate and latch posts shall be braced to the next existing line post as shown on the plans.

At each gate location, an existing line post shall be removed and the new gate installed so that the gate is centered on the post hole of the removed post. Holes resulting from the removal of line posts shall be backfilled.

Gate mounting and latching hardware shall not contain open-end slots for the fastening bolts.

Chain link fabric for gates shall be of the same mesh size as the existing fence in which the gates are installed.

Openings made in existing fences for installation of gates shall be closed during the working day in which the openings are made and when work is not in progress. Temporary closures shall be made with the existing fence fabric or with additional 1.83-m chain link fabric as directed by the Engineer.

Full compensation for making the openings in existing fences, for temporary closing of the openings (including furnishing additional fence fabric if necessary), and for new posts, footings, hardware, braces, and truss rods shall be considered as included in the contract unit price paid for 1.2-m chain link gate (Type CL-1.8) and no additional compensation will be allowed therefor.

SECTION 10-2 HIGHWAY PLANTING AND IRRIGATION SYSTEMS

10-2.01 GENERAL

The work performed in connection with highway planting and irrigation systems shall conform to the provisions in Section 20, "Erosion Control and Highway Planting," of the Standard Specifications and these special provisions.

The Contractor shall notify the Engineer not less than 72 hours prior to requiring initial access to the existing irrigation controllers. When the Engineer determines that access to the controllers is required at other times, arrangements will be made to provide this access.

When fluctuations of water pressure and water supply are encountered during normal working hours, plants shall be watered at other times, as often, and in sufficient amounts as conditions may require to keep the soil and plant roots moist during the life of the contract.

Full compensation for watering plants outside normal working hours shall be considered as included in the contract unit prices paid for the plants involved and the contract lump sum price paid for plant establishment work and no additional compensation will be allowed therefor.

PROGRESS INSPECTIONS

Progress inspections will be performed by the Engineer for completed highway planting and irrigation system work at designated stages during the life of the contract.

Progress inspections will not relieve the Contractor of responsibility for installation in conformance with the special provisions, plans and Standard Specifications. Work within an area shall not progress beyond each stage until the inspection has been completed, corrective work has been performed, and the work is approved, unless otherwise permitted by the Engineer.

The requirements for progress inspections will not preclude additional inspections of work by the Engineer at other times during the life of the contract.

The Contractor shall notify the Engineer, in writing, at least 4 working days prior to completion of the work for each stage of an area and shall allow a minimum of 3 working days for the inspection.

Progress inspections will be performed at the following stages of work:

- A. During pressure testing of the pipelines on the supply side of control valves.
- B. During testing of low voltage conductors.
- C. Before planting begins and after completion of the work specified for planting in Section 20-4.03, "Preparing Planting Areas," of the Standard Specifications.
- D. Before plant establishment work begins and after completion of the work specified for planting in Section 20-4.05, "Planting," of the Standard Specifications.
- E. At intervals of one month during the plant establishment period.

10-2.02 EXISTING HIGHWAY PLANTING

In addition to the provisions in Section 20 of the Standard Specifications, work performed in connection with existing highway planting shall be in conformance with the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Replacement planting shall conform to the requirements specified under "Preservation of Property" of these special provisions.

MAINTAIN EXISTING PLANTS

Existing plants Sta. 232+40 to Sta. 243+10 right and left and Sta. 246+00 to Sta. 264+00 left, shall be maintained throughout the life of the contract in conformance with these special provisions.

Existing plants and plant basins to be maintained shall be inspected for deficiencies by the Contractor in the presence of the Engineer. Deficiencies requiring corrective action shall include, but are not necessarily limited to, dead, diseased, or unhealthy plants, missing plant stakes and tree ties, and inadequate plant basins. The inspection shall be completed within 10 working days after the start of work.

When directed by the Engineer, deficiencies found during the inspection shall be corrected within 10 working days after the inspection. Correction of deficiencies, as directed by the Engineer, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

After initial deficiencies have been corrected as directed by the Engineer, the Contractor shall continue to maintain existing plants as often as necessary to maintain the area in a neat appearance. The work shall include but not limited to the following:

- A. Weed growth shall be killed before the weeds reach the seed stage of growth or exceed 150 mm in length.
- B. Trash, debris and weeds shall be removed from existing planting areas. Weeds shall be killed prior to removal. Trash, debris and weed removal in ground cover areas shall extend beyond the outer limits of ground cover areas to the adjacent edges of paving, fences and proposed plants and planting areas, and 2-m diameter area centered at each existing tree and shrub outside of existing ground cover areas.
- C. Existing plant basins shall be kept well formed and free of silt. If existing plant basins require repairs, and the plant basins contain mulch, the mulch shall be replaced after the plant basins have been repaired.
- D. When a portion of a new automatic irrigation system is completed, the existing plants to be watered by that portion of the irrigation system shall be watered automatically.
- E. Pesticides for maintaining existing plants shall conform to the provisions in "Pesticides" of these special provisions.

If after completion of the initial inspection and correction of deficiencies, the Engineer determines that existing plants show signs of failure to grow, or are so injured or damaged as to render the plants unsuitable for the purpose intended, the existing plants shall be replaced. Removal, disposal and replacement of the existing plants, shall be in conformance with the provisions in "Preservation of Property" of these special provisions.

REMOVE EXISTING PLANTS FOR TRENCHING

Removing existing plants for trenching shall conform to the provisions in Section 20-5.026, "Remove Existing Plants for Trenching," of the Standard Specifications and these special provisions.

Removing existing plants for trenching work shall consist of removing and replacing ground cover, pruning trees and shrubs within trench locations, applying preemergents and disposing of removed ground cover and prunings.

Replacement of removed ground cover within the maximum 1.8-m width, as specified in Section 20-5.026, "Remove Existing Plants for Trenching," of the Standard Specifications, will be required, except for trenches within 1.8-m of fences, curbs, dikes or shoulders.

Trees and shrubs adjacent to dikes, walks, fences, guard railing, and pavement edges may be pruned back 3 m from these facilities to facilitate trenching work. When trenching is to be performed adjacent to other trees and shrubs that cannot be avoided, the trees and shrubs may be pruned upon receipt of prior written approval of the Engineer.

Pruning shall include removal of deadwood, suckers, and broken or bruised branches 25 mm or larger in diameter. Pruning shall conform to the provisions in Section 20-4.055, "Pruning," of the Standard Specifications.

Removed ground cover and pruned materials shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications. At the Contractor's option, removed ground cover and prunings may be reduced to chips. Chipped materials shall be spread within the highway right of way where designated by the Engineer.

Shrubs adjacent to dikes, fences, guard railing, and the edge of pavement within the 3-m pruned area designated above, that in the opinion of the Engineer should be removed after pruning, shall be removed and disposed of. Removing and disposing of the shrubs not otherwise provided for will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

One application of a pre-emergent pesticide shall be applied to trenched areas in existing ground cover areas and to trenched areas adjacent to fences, curbs, dikes and shoulders. The Engineer will determine when the pre-emergent pesticide shall be applied.

10-2.03 EXISTING HIGHWAY IRRIGATION FACILITIES

The work performed in connection with the various existing highway irrigation system facilities shall conform to the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Water shall be maintained in conformance with the provisions in Section 20-5.025, "Maintain Existing Water Supply," of the Standard Specifications.

LOCATE EXISTING CROSSEOVERS AND CONDUITS

Existing crossovers and conduits shown on the plans to be incorporated in the new work shall be located in conformance with the provisions for locating conduits in Section 20-5.03B, "Conduit for Irrigation Crossovers," of the Standard Specifications.

Unless otherwise directed by the Engineer, existing crossovers and conduits shown on the plans to be incorporated in the new work shall be located prior to performing work on irrigation systems.

If debris is encountered in the ends of conduits, the debris shall be removed prior to performing other work in the conduits. Removal of debris within the first one meter in these conduits shall be at the Contractor's expense. If debris is encountered in the conduits more than one meter from the ends of the conduits, the additional debris shall be removed as directed by the Engineer and the removal work will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

CHECK AND TEST EXISTING IRRIGATION FACILITIES

Existing irrigation facilities that are to remain or to be relocated, and that are to be part of the new irrigation system except for existing valves not in use as shown on plans, shall be checked for missing or damaged components, and for proper operation prior to performing irrigation system work.

A written list of existing irrigation system deficiencies shall be submitted to the Engineer within 5 working days after checking the existing facilities.

Deficiencies found during checking of the existing facilities shall be corrected as directed by the Engineer. Corrective work ordered by the Engineer will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Existing backflow preventers shall be tested in conformance with the provisions in "Irrigation Systems" of these special provisions.

Length of watering cycles for use of potable water from water meters for checking or testing existing irrigation facilities shall be as determined by the Engineer.

Repairs to the existing irrigation facilities ordered by the Engineer after checking and testing the facilities, and further repairs required thereafter as ordered by the Engineer, except as otherwise provided for under "Maintain Existing Irrigation Facilities" of these special provisions, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

MAINTAIN EXISTING IRRIGATION FACILITIES

Existing irrigation facilities shall be maintained throughout the life of the contract. Prior to the start of maintaining existing irrigation facilities work, the facilities shall be checked for proper operation, and repaired in conformance with the provisions in "Check and Test Existing Irrigation Facilities" of these special provisions.

After the existing facilities have been checked and repaired, the Contractor shall be responsible for the routine maintenance of existing irrigation systems. The work shall include, but not limited to, checking irrigation systems for proper operation and adjusting, repairing or replacing valves, valve boxes, sprinklers, risers, swing joints, wye strainers, valve assembly units, and filter assembly units.

The Contractor will not be responsible for maintaining existing water meters, underground pipe supply lines, control and neutral conductors, and electrical conduits. Except as otherwise specified in section "Existing Highway Irrigation Facilities" of these special provisions, repair work to these facilities ordered by the Engineer will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Existing automatic irrigation systems shall be operated automatically during the life of the contract, except manual operation will be allowed for the work during plant replacement, fertilization, weed germination, and the repair of irrigation facilities.

Irrigation controllers shall be programmed by the Contractor for seasonal water requirements. During winter seasons irrigation systems shall be operated automatically a minimum of 2 minutes every 2 weeks.

Irrigation systems and facilities shall be checked for proper operation at least once every 30 days. When required, as determined by the Engineer, adjusting, repairing or replacing irrigation facilities shall be completed within 5 working days after checking the irrigation systems. Except as provided in these special provisions, repair and replacement of irrigation facilities shall conform to the provisions in "Existing Highway Irrigation Facilities" of these special provisions.

Except as provided in these special provisions, full compensation for maintaining existing irrigation facilities, including checking irrigation facilities, shall be considered as included in the contract prices paid per meter for the various sizes of plastic pipe (supply line) involved and no separate payment will be made therefor.

REMOVE EXISTING IRRIGATION FACILITIES

Existing irrigation facilities to be removed, shall be removed and disposed of. Facilities that are more than 150 mm below finished grade may be abandoned in place. Removed facilities shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Immediately after disconnecting an existing irrigation facility to be removed or abandoned from an existing facility to remain, the remaining facility shall be capped.

SALVAGE EXISTING IRRIGATION FACILITIES

Existing remote control irrigation valves, where shown on the plans to be removed, shall be salvaged.

The Engineer shall be given written notification of the intent to salvage existing irrigation facilities a minimum of 72 hours prior to salvaging these facilities.

Salvaged irrigation facilities shall remain the property of the State and shall be delivered to Caltrans Modesto Maintenance Station, 908 N. Emerald, Modesto, CA 95351.

A list of salvaged facilities, including the quantity and size of each item salvaged, shall be included with each delivery.

10-2.04 HIGHWAY PLANTING

The work performed in connection with highway planting shall conform to the provisions in Section 20-4, "Highway Planting," of the Standard Specifications and these special provisions.

Mulch

Mulch shall consist of either wood chips or tree bark or a combination of both.

Commercial fertilizer (granular) shall be a pelleted or granular form and shall fall within the following guaranteed chemical analysis range:

Ingredient	Percentage
Nitrogen	12
Phosphoric Acid	12
Water Soluble Potash	12

Commercial fertilizer (slow release) shall be a pelleted or granular form, shall be slow release, and shall fall within the following guaranteed chemical analysis :

Ingredient	Percentage
Nitrogen	19
Phosphoric Acid	6
Water Soluble Potash	12

Commercial fertilizer (tablet) shall be slow release and shall be in tablet form. Each tablet, as shown in the Plant List of the plans, shall have a mass of $21 \text{ g} \pm 1 \text{ g}$, and shall have the following guaranteed chemical analysis:

Ingredient	Percentage
Nitrogen	20
Phosphoric Acid	10
Water Soluble Potash	5

At the option of the Contractor, two 10.5-g tablets may be used in place of each 21-g tablet designated on the plans or specified in these special provisions. Regardless of the tablet size used, each tablet shall be the slow release type and shall have the same guaranteed chemical analysis as specified for the 21-g tablets. Each 10.5-g tablet shall have a mass of $10.5 \text{ g} \pm 0.5\text{-g}$.

ROADSIDE CLEARING

Roadside clearing shall be performed from Sta. 232+40 to Sta. 243+10 right and left, and Sta. 240+00 to Sta. 264+00 left.

Prior to preparing planting areas, or commencing irrigation trenching operations for planting areas, trash and debris shall be removed from roadside clearing areas a distance of 3 m beyond the edges of those areas. At locations where proposed planting areas are 3.6 m or more from the edges of dikes, curbs, sidewalks, fences, walls, paved shoulders and existing planting to remain or to be maintained, the clearing limit shall be 2 m beyond the outer limits of the proposed planting area.

In addition to removing trash and debris, the project area shall be cleared as specified herein:

- A. Weeds shall be killed and removed within planting areas where plants are to be planted in groups or rows 4.6 m or less apart and from within an area extending 2 m beyond the outer limits of the groups or rows of plants.
- B. Weeds shall be killed and removed within an area 2 m in diameter centered at each plant location where the plants are to be planted more than 4.6 m apart and are located outside of ground cover areas.
- C. Weeds outside of mulched areas, plant basins, and ground cover shall be controlled by mowing.
- D. Existing ground cover shall be killed and removed from within an area 2 m in diameter centered at each proposed plant location within existing ground cover areas.
- E. Disposal of weeds killed during the initial roadside clearing will not be required, unless otherwise directed by the Engineer. When directed by the Engineer, killed weeds shall be disposed of and the disposal will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

After the initial roadside clearing is complete, additional roadside clearing work shall be performed as necessary to maintain the areas, as specified above, in a neat appearance until the start of the plant establishment period. This work shall include the following:

- A. Trash and debris shall be removed.
- B. Rodents shall be controlled.
- C. Weed growth shall be killed before the weeds reach the seed stage of growth or exceed 150 mm in length.
- D. Existing ground cover shall be killed and removed from within the 2-m diameter areas specified for each proposed plant location within the existing ground cover areas.
- E. Weeds in plant basins, including basin walls, shall be removed by hand pulling, after the plants have been planted.

- F. Areas outside the areas specified to be cleared of weeds shall be mowed.

Weed Control

Weed control shall also conform to the following:

- A. Stolon type weeds shall be killed with glyphosate.
- B. Tumbleweeds shall be removed by hand pulling before the tumbleweeds reach a height of 150 mm.
- C. Removed weeds and ground cover shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.
- D. Areas to be mowed shall be mowed when weed height exceeds 300 mm. Weeds shall be mowed to a height of 150 mm or less, but not less than 50 mm.
- E. Disposal of mowed material and killed weeds after initial roadside clearing will not be required, unless otherwise directed by the Engineer. When directed by the Engineer, mowed material and killed weeds shall be disposed of and the disposal will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

PESTICIDES

Pesticides used to control weeds shall conform to the provisions in Section 20-4.026, "Pesticides," of the Standard Specifications. Except as otherwise provided in these special provisions, pesticide use shall be limited to the following materials:

Cacodylic Acid
Dichlobenil (Preemergent)
Diquat
Glyphosate
Isoxaben (Preemergent)
Sethoxydim
Oryzalin (Preemergent)
Pendimethalin (Preemergent)
Prodiamine (Preemergent)
Trifluralin (Preemergent)
Ammonium Sulfate
Magnesium Chloride

Granular forms of Oxadiazon or Dichlobenil shall be applied in areas to be covered with mulch.

Preemergents shall be applied prior to the application of mulch. Once the preemergent is applied to the mulch areas, mulch applications shall be completed in that area on the same working day.

Glyphosate shall be used to kill stolon type weeds.

Prior to the application of preemergents, ground cover plants shall have been planted a minimum of 3 days and shall have been thoroughly watered.

A minimum of 100 days shall elapse between applications of preemergents.

Except for ground cover plants, preemergents shall not be applied within 450 mm of plants .

Ammonium sulfate and magnesium chloride shall be used only in areas planted to *Carpobrotus* or *Delosperma*. Ammonium sulfate and magnesium chloride shall not be applied in a manner that allows the pesticides to come in contact with trees or shrubs.

If the Contractor elects to request the use of other pesticides on this project, the request shall be submitted, in writing, to the Engineer not less than 10 working days prior to the intended use of the other pesticides. Except for the pesticides listed in these special provisions, no pesticides shall be used or applied without prior written approval of the Engineer.

Pesticides shall not be applied within the limits of the plant basins. Pesticides shall not be applied in a manner that allows the pesticides to come in contact with the foliage and woody parts of the plants.

PREPARING PLANTING AREAS

Plants adjacent to drainage ditches shall be located so that after construction of the basins, no portion of the basin walls shall be less than the minimum distance shown on the plans for each plant involved.

PREPARE HOLES

Holes for plants shall be excavated to the minimum dimensions shown on the plans.

Root protectors shall be installed in plant holes requiring root protectors, in conformance with the details shown on the plans and the provisions in "Root Protectors" of these special provisions and the provisions in Section 20-4.05, "Planting," of the Standard Specifications.

Backfill material for plant holes shall be a mixture of soil and soil amendment. Application rates for soil amendment shall be shown on the Plant List. Backfill material shall be thoroughly mixed and uniformly distributed throughout the entire depth of the plant hole without clods and lumps.

Full compensation for preparing holes and for furnishing and mixing soil amendment shall be considered as included in the contract unit prices paid for the plants involved and no separate payment will be made therefor.

PLANTING

Commercial fertilizer shall be applied or placed at the time of planting and at the rates shown on the plans.

A granular pre-emergent shall be applied to areas to be covered with mulch outside of plant basins in conformance with the provisions in "Pesticides" of these special provisions.

Mulch placed in areas outside of plant basins shall be spread to a depth of not less than 75 mm.

Mulch shall be spread from the outside of the proposed plant basin to the adjacent edges of shoulders, dikes, curbs, sidewalks, walls, fences, and existing plantings. If the proposed plant material is 3.6 m or more from the adjacent edges of shoulders, dikes, curbs, sidewalks, walls, fences, and other existing plantings, the mulch shall be spread 1 m beyond the outside edge of the proposed plant basins.

Mulch shall not be placed within one meter of the center line of earthen drainage ditches, within one meter of the edge of paved ditches, and within one meter of the center line of drainage flow lines.

Attention is directed to "Irrigation Systems Functional Test" of these special provisions regarding functional tests of the irrigation systems. Planting shall not be performed in an area until the functional test has been completed for the irrigation system serving that area.

Quantities of commercial fertilizer tablets will be measured by the tablet as determined from actual count in place. Each 21-g tablet will be counted as one tablet. Each 10.5-g tablet will be counted as a half tablet.

Full compensation for furnishing and applying commercial fertilizer (slow release), pesticides, and tree stakes shall be considered as included in the contract unit prices paid for the various items of plants involved and no separate payment will be made therefor.

ROOT PROTECTOR

Root protectors shall be installed in conformance with the details shown on the plans, the provisions in Section 20-2.13B, "Root Protector," and Section 20-4, "Highway Planting," of the Standard Specifications and these special provisions.

PLANT ESTABLISHMENT WORK

The plant establishment period shall be Type 1 and shall be 60 working days within the 60 day plant establishment areas shown on the plans, 250 working days within the remaining project area.

Weeds within plant basins, including basin walls and ground cover, shall be controlled by hand pulling.

Weeds within mulched areas and ground cover, but outside of plant basins, shall be controlled by killing.

Weeds outside of mulched areas, plant basins, new ground cover and paved areas shall be controlled by mowing. At locations where proposed planting areas are 3.6 m or more from the edges of existing plantings to remain and from shoulders, dikes, curbs, sidewalks, fences, and walls, the mowing limit shall be 2 m beyond the outer limits of the proposed planting area.

Weeds within , pavement, curbs, sidewalk, and other surfaced areas shall be controlled by killing.

Except as specified in these special provisions, disposal of mowed material will not be required unless ordered by the Engineer. Disposal of mowed material, as directed by the Engineer, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

After 125 working days of the 250 day plant establishment period have been completed, replacement of plants, shall be No. 5 size for No. one size plants; No. 15 size for No. 5 size plants; and other plant replacement plants shall be the same size as originally specified.

Previously installed filters shall be removed, cleaned and reinstalled at least 15 days prior to the completion of the plant establishment period.

The final inspection shall be performed in conformance with the provisions in Section 5-1.13, "Final Inspection," of the Standard Specifications and shall be completed a minimum of 20 working days before the estimated completion of the contract.

10-2.05 IRRIGATION SYSTEMS

Irrigation systems shall be furnished and installed in conformance with the provisions in Section 20-5, "Irrigation Systems," of the Standard Specifications, except materials containing asbestos fibers shall not be used.

Attention is directed to the provisions in "Obstructions" of these special provisions, regarding work over or adjacent to existing underground facilities. Excavation for proposed irrigation facilities shall not be started until the existing underground facilities have been located.

Only pipeline trenches and excavation pits for supply lines being supplied from one water service point shall be open at one time. After pressure testing is complete, trenches and pits excavated for pipe supply lines, being supplied from one water service point, shall be backfilled prior to commencing excavations for pipe supply lines being supplied from another water service point.

Gate valves, 75 mm and larger in size, shall be furnished with a square lug and shall be operated by use of long shank keys. Prior to acceptance of the contract, 3 long shank keys shall be delivered to the Engineer.

VALVE BOXES

Valve boxes shall conform to the provisions in Section 20-2.24, "Valve Boxes," of the Standard Specifications, except as otherwise provided herein.

Valve boxes shall be precast portland cement concrete,

Covers for concrete valve boxes shall be concrete, cast iron or steel. Cast iron and steel covers shall be hinged with brass hinge pins for valve boxes containing valves smaller than 50 mm.

Valve boxes shall be identified on the top surface of the covers by stenciling with paint the appropriate abbreviations for the irrigation facilities contained in the valve boxes as shown on the plans. Valve boxes that contain remote control valves shall be identified by the appropriate letters and numbers (controller and station numbers). The letters and numbers shall be 50 mm in height. The stenciling paint shall be a commercial quality, epoxy resin base paint of a color which contrasts with the valve box covers.

IRRIGATION SYSTEMS FUNCTIONAL TEST

Functional tests for the irrigation controllers and associated automatic irrigation systems shall conform to the provisions in Section 20-5.027J, "Testing," of the Standard Specifications and these special provisions.

Tests shall demonstrate to the Engineer, through one complete cycle of the irrigation controllers in the automatic mode, that the associated automatic components of the irrigation systems operate properly. If automatic components of the irrigation systems fail a functional test, these components shall be repaired at the Contractor's expense and the testing repeated until satisfactory operation is obtained.

Associated automatic components shall include, but not be limited to remote control valves.

Upon completion of work on an irrigation system, including correction of deficiencies and satisfactory functional tests for the systems involved, the plants to be planted in the area watered by the irrigation system may be planted provided the planting areas have been prepared as specified in these special provisions.

PIPE

Plastic Pipe

Plastic pipe supply lines shall be polyvinyl chloride (PVC) 1120 or 1220 pressure rated pipe with the minimum pressure rating (PR) shown on the plans.

Plastic pipe supply lines shall have solvent cemented type joints. Primers shall be used on the solvent cemented type joints.

Fittings for plastic pipe supply lines with a pressure rating (PR) of 315 shall be Schedule 80.

TESTING BACKFLOW PREVENTERS

Existing backflow preventers shall be tested for proper operation in conformance with the provisions in Section 20-5.03J, "Check and Test Backflow Preventers," of the Standard Specifications and these special provisions.

Existing backflow preventers shall be tested, and repaired if required, when existing irrigation facilities are checked.

Repair of existing backflow preventers will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications when ordered by the Engineer, except damage caused by the Contractor's operations.

Existing backflow preventers shall be retested one year after the satisfactory completion of the previous test or 10 days prior to completion of the plant establishment period, whichever occurs first.

Testing existing backflow preventers will be paid for in conformance with the provisions in "Checking and Testing Existing Irrigation Facilities" of these special provisions.

SPRINKLERS

Sprinklers shall conform to the type, pattern, material, and operating characteristics listed in the "Sprinkler Schedule" shown on the plans.

Flexible hose risers shall be ultraviolet (UV) resistant, black in color and shall conform to the details shown on the plans.

Sprinklers (Type B-1) and Sprinklers (Type B-2) shall have an in-line check valve device placed on the side or bottom inlet. The device shall be installed as recommended by the manufacturer of the device.

In-line check valves shall be Schedule 80 PVC with a 12.7 mm male x 12.7 mm female pipe thread. In-line check valves shall be preset at the factory for a pressure of 34 kPa and shall be adjustable to 96 kPa.

Full compensation for in-line check valves shall be considered as included in the contract unit price paid for Sprinklers (Type B-1) and Sprinklers (Type B-2) and no separate payment will be made.

CHECK VALVES

Check valves shall be PVC with a solid 18-8 stainless steel spring and valve stem. Check valves shall be adjustable from 34 kPa to 96 kPa.

SWING CHECK VALVE

Swing check valves shall be PVC with a pressure rating of 862 kPa. Swing check valves shall retain back pressure at 862 kPa.

FILTER ASSEMBLY UNIT

A filter assembly unit shall consist of a filter housing, a reusable filter cartridge, a ball valve, fittings, pipe, and valve box as shown on the plans.

Filter assembly units shall withstand a cold water working pressure of 1034 kPa.

Pressure loss through the filter assembly units shall not exceed the following:

FILTER ELEMENT SIZE (Millimeters)	MAX FLOW RATE (Liters Per Minute)	PRESSURE LOSS AT MAX FLOW (kPa)
40	167	14.6
50	499	24.8

Filter housings shall be manufactured of reinforced polypropylene plastic.

Filter cartridges shall be reusable stainless steel and shall be capable of 130 µm size mesh filtration.

Ball valves in filter assembly units shall be polyvinyl chloride (PVC). The ball seats shall be high molecular weight-high density polyethylene.

FINAL IRRIGATION SYSTEM CHECK

A final check of existing and new irrigation facilities shall be performed not more than 20 working days prior to acceptance of the contract.

The length of watering cycles using potable water measured by water meters for the final check of irrigation facilities will be determined by the Engineer.

Remote control valves connected to existing irrigation controllers shall be checked for automatic performance when the controllers are in automatic mode.

Unsatisfactory performance of irrigation facilities installed or modified by the Contractor shall be repaired and rechecked at the Contractor's expense until satisfactory performance is obtained, as determined by the Engineer.

Repair or replacement of existing irrigation facilities due to unsatisfactory performance shall conform to the provisions in "Existing Highway Irrigation Facilities" of these special provisions.

Nothing in this section "Final Irrigation System Check" shall relieve the Contractor of full responsibility for making good or repairing defective work or materials found before the formal written acceptance of the entire contract by the Director.

Full compensation for checking the irrigation systems prior to the acceptance of the contract shall be considered as included in the contract lump sum price paid for plant establishment work and no additional compensation will be allowed therefor.

SECTION 11. (BLANK)

SECTION 12. (BLANK)

SECTION 13. RELATIONS WITH RAILROAD

13-1.01 GENERAL. - The Contractor's attention is directed to the track and right of way of the Union Pacific Railroad Company adjacent to State Route within the limits of the project.

The Contractor shall conduct his operations in such a manner as to prevent any debris from dropping onto same.

In accordance with Section 7-1.12, "Responsibility for Damage" of the Standard Specifications, the Contractor shall be responsible for all damage to Railroad tracks, appurtenances and facilities thereto and to Railroad equipment operating on such track, resulting from his operations.

No men or equipment shall trespass on Railroad right of way within the limits of the project.