


DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
11	SD	5,8,15,52,94,805	Var	101	116

Renee M. Anderson  
 REGISTERED CIVIL ENGINEER  
 DATE 9-26-11  
 4-30-12  
 PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER  
 RENE E ANDERSON  
 No. 61040  
 Exp. 12/31/12  
 CIVIL  
 STATE OF CALIFORNIA

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.




**MAIN STREET UC**

Bridge No. 57-0363R/L Rte 8 Post Mile 14.59  
1" = 40'

**QUANTITIES**

BRIDGE NO. 57-0363R/L

AGGREGATE BASE (APPROACH SLAB)	49	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	292	CY
PAVING NOTCH EXTENSION	166	CF
CORE CONCRETE (2")	20	LF
JOINT SEAL (MR 1/2")	222	LF



**CAMINO DEL REY UC**


Bridge No. 57-0889R/L Rte 15 Post Mile 41.82  
1" = 40'

**QUANTITIES**

BRIDGE NO. 57-0889R/L

AGGREGATE BASE (APPROACH SLAB)	58	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	350	CY
CORE CONCRETE (2")	24	LF
JOINT SEAL (MR 1")	264	LF

- LEGEND:**
- Indicates Existing Structure
  - Indicates location of existing Joint Seal removal, clean Expansion Joint, and placement of new Joint Seal.
  - ▨ Indicates Limits of Approach Slab Type R(30D)
  - ▩ Indicates Limits of Approach Slab Type R(30S)
  - ① Existing Approach Slab
  - ② Limits of Paving Notch Extension
  - X Structure Location, see Joint Seal Table on "JOINT SEAL DETAILS" sheet.




**EL CAJON OH**

Bridge No. 57-0362 Rte 8 Post Mile 13.66  
1" = 40'

**QUANTITIES**

BRIDGE NO. 57-0362

AGGREGATE BASE (APPROACH SLAB)	37	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	227	CY
CORE CONCRETE (2")	12	LF
JOINT SEAL (MR 1 1/2")	222	LF



**LAWRENCE WELK DRIVE UC**

Bridge No. 57-0894L Rte 15 Post Mile 39.35  
1" = 40'

**QUANTITIES**

BRIDGE NO. 57-0894L

AGGREGATE BASE (APPROACH SLAB)	23	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	135	CY
PAVING NOTCH EXTENSION	72	CF
CLEAN EXPANSION JOINT	52	LF
CORE CONCRETE (2")	8	LF
JOINT SEAL (MR 2")	148	LF

NOTE:  
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DESIGN	BY D. Azzam	CHECKED R. Anderson	LOAD & RESISTANCE FACTOR DESIGN	LIVE LOADING: HL93 W/"LOW-BOY"; PERMIT DESIGN VEHICLE
DETAILS	BY R. Kirkland	CHECKED R. Anderson	LAYOUT	BY D. Azzam
QUANTITIES	BY D. Azzam	CHECKED R. Anderson	SPECIFICATIONS	BY T. Nedwick

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION


DIVISION OF ENGINEERING SERVICES  
STRUCTURE DESIGN  
DESIGN BRANCH 10

BRIDGE NO. Varies  
POST MILE Varies

**APPROACH SLAB REHABILITATION**  
**GENERAL PLAN NO. 7**

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
11	SD	5,8,15,52,94,805	Var	102	116

Renee M. Anderson 9-26-11  
 REGISTERED CIVIL ENGINEER DATE  
 4-30-12  
 PLANS APPROVAL DATE  
 The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.



**COUNTRY CLUB LANE UC**


Bridge No. 57-0819L Rte 15 Post Mile 33.57  
1" = 40'

27

**QUANTITIES**

BRIDGE NO. 57-0819L

- AGGREGATE BASE (APPROACH SLAB) 17 CY
- STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R) 102 CY
- PAVING NOTCH EXTENSION 52 CF
- CORE CONCRETE (2") 6 LF
- JOINT SEAL (MR 1") 69 LF



**PROSPECT AVE UC (E52/S125 CONNECTOR)**


Bridge No. 57-1024G Rte 52 Post Mile 15.16  
1" = 40'

29

**QUANTITIES**

BRIDGE NO. 57-1024G

- AGGREGATE BASE (APPROACH SLAB) 17 CY
- STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R) 104 CY
- PAVING NOTCH EXTENSION 60 CF
- CORE CONCRETE (2") 6 LF
- JOINT SEAL (MR 2") 80 LF



**ROCK SPRINGS ROAD UC**


Bridge No. 57-0817R Rte 15 Post Mile 31.99  
1" = 40'

28

**QUANTITIES**

BRIDGE NO. 57-0817R

- AGGREGATE BASE (APPROACH SLAB) 25 CY
- STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R) 148 CY
- PAVING NOTCH EXTENSION 92 CF
- CLEAN EXPANSION JOINT 66 LF
- CORE CONCRETE (2") 8 LF
- JOINT SEAL (MR 1") 192 LF



**E52-N805/SAN CLEMENTE CREEK BRIDGE**

Bridge No. 57-0753G Rte 52 Post Mile 3.36  
1" = 40'

30

**QUANTITIES**

BRIDGE NO. 57-0753G

- AGGREGATE BASE (APPROACH SLAB) 15 CY
- STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R) 91 CY
- PAVING NOTCH EXTENSION 48 CF
- CORE CONCRETE (2") 3 LF
- JOINT SEAL (MR 1/2") 64 LF

**LEGEND:**

- Indicates Existing Structure
- Indicates location of existing Joint Seal removal, clean Expansion Joint, and placement of new Joint Seal.
- ▨ Indicates Limits of Approach Slab Type R(30D)
- ① Existing Approach Slab
- ② Limits of Paving Notch Extension
- X Structure Location, see Joint Seal Table on "JOINT SEAL DETAILS" sheet.

NOTE:  
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DESIGN	BY D. Azzam	CHECKED R. Anderson	LOAD & RESISTANCE FACTOR DESIGN	LIVE LOADING: HL93 W/"LOW-BOY"; PERMIT DESIGN VEHICLE
DETAILS	BY R. Kirkland	CHECKED R. Anderson	LAYOUT	BY D. Azzam
QUANTITIES	BY D. Azzam	CHECKED R. Anderson	SPECIFICATIONS	BY T. Nedwick

STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES STRUCTURE DESIGN

BRIDGE NO. Varies


POST MILE Varies

DESIGN BRANCH 10

APPROACH SLAB REHABILITATION

GENERAL PLAN NO. 8

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
11	SD	5,8,15,52,94,805	Var	103	116
<b>Renee M. Anderson</b> REGISTERED CIVIL ENGINEER			9-26-11 DATE		
4-30-12 PLANS APPROVAL DATE					
<small>The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.</small>					




**GENESEE AVENUE UC**  
 Bridge No. 57-0744R Rte 52 Post Mile 2.29  
 1" = 40'

31

**QUANTITIES**  
 BRIDGE NO. 57-0744R

AGGREGATE BASE (APPROACH SLAB)	28	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	165	CY
PAVING NOTCH EXTENSION	102	CF
CORE CONCRETE (2")	6	LF
JOINT SEAL (MR 1")	136	LF




**W52-N5 CONNECTOR OH**  
 Bridge No. 57-0523F Rte 52 Post Mile 0.37  
 1" = 40'

33

**QUANTITIES**  
 BRIDGE NO. 57-0523F

AGGREGATE BASE (APPROACH SLAB)	9	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	54	CY
PAVING NOTCH EXTENSION	31	CF
CORE CONCRETE (2")	3	LF
JOINT SEAL (MR 1")	42	LF




**REGENTS ROAD UC**  
 Bridge No. 57-0743R Rte 52 Post Mile 1.35  
 1" = 40'

32

**QUANTITIES**  
 BRIDGE NO. 57-0743R

AGGREGATE BASE (APPROACH SLAB)	17	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	104	CY
PAVING NOTCH EXTENSION	59	CF
CORE CONCRETE (2")	6	LF
JOINT SEAL (MR 1/2")	40	LF
JOINT SEAL (MR 1")	40	LF

NOTE:  
 THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.



**KENWOOD DRIVE UC**  
 Bridge No. 57-0572L Rte 94 Post Mile 11.80  
 1" = 40'

34

**QUANTITIES**  
 BRIDGE NO. 57-0572L

AGGREGATE BASE (APPROACH SLAB)	19	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	116	CY
PAVING NOTCH EXTENSION	63	CF
CORE CONCRETE (2")	6	LF
JOINT SEAL (MR 1")	84	LF

- LEGEND:
- Indicates Existing Structure
  - Indicates location of existing Joint Seal removal, clean Expansion Joint, and placement of new Joint Seal.
  - ▨ Indicates Limits of Approach Slab Type R(30D)
  - ① Existing Approach Slab
  - ② Limits of Paving Notch Extension
  - X Structure Location, see Joint Seal Table on "JOINT SEAL DETAILS" sheet.

DESIGN	BY D. Azzam	CHECKED R. Anderson	LOAD & RESISTANCE FACTOR DESIGN	LIVE LOADING: HL93 W/"LOW-BOY"; PERMIT DESIGN VEHICLE
DETAILS	BY R. Kirkland	CHECKED R. Anderson	LAYOUT	BY D. Azzam
QUANTITIES	BY D. Azzam	CHECKED R. Anderson	SPECIFICATIONS	BY T. Nedwick


STATE OF CALIFORNIA  
 DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES  
 STRUCTURE DESIGN  
**DESIGN BRANCH 10**

BRIDGE NO. Varies  
 POST MILE Varies

**APPROACH SLAB REHABILITATION  
 GENERAL PLAN NO. 9**


DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
11	SD	5,8,15,21,94,805	Var	104	116
Renee M. Anderson REGISTERED CIVIL ENGINEER			9-26-11 DATE		
4-30-12 PLANS APPROVAL DATE					
The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.					



**W94-S805 CONNECTOR UC**  
 Bridge No. 57-0663R Rte 94 Post Mile 4.00  
 1" = 40'

**QUANTITIES**  
 BRIDGE NO. 57-0663R


AGGREGATE BASE (APPROACH SLAB)	19	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	113	CY
PAVING NOTCH EXTENSION	58	CF
CLEAN EXPANSION JOINT	40	LF
CORE CONCRETE (2")	6	LF
JOINT SEAL (MR 1/2")	37	LF
JOINT SEAL (MR 1")	77	LF



**W94-S15 CONNECTOR OC**  
 Bridge No. 57-0350F Rte 94 Post Mile 3.08  
 1" = 40'

**QUANTITIES**  
 BRIDGE NO. 57-0350F


AGGREGATE BASE (APPROACH SLAB)	20	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	117	CY
CORE CONCRETE (2")	6	LF
JOINT SEAL (MR 1")	89	LF



**CHOLLAS CREEK BRIDGE**  
 Bridge No. 57-0107L Rte 94 Post Mile 3.36  
 1" = 40'

**QUANTITIES**  
 BRIDGE NO. 57-0107L

AGGREGATE BASE (APPROACH SLAB)	46	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	274	CY
PAVING NOTCH EXTENSION	133	CF
CORE CONCRETE (2")	12	LF
JOINT SEAL (MR 1/2")	179	LF



**32ND STREET UC**  
 Bridge No. 57-0361 Rte 94 Post Mile 2.68  
 1" = 40'

**QUANTITIES**  
 BRIDGE NO. 57-0361

AGGREGATE BASE (APPROACH SLAB)	39	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	237	CY
PAVING NOTCH EXTENSION	120	CF
CORE CONCRETE (2")	12	LF
JOINT SEAL (MR 1/2")	160	LF

- LEGEND:**
- Indicates Existing Structure
  - Indicates location of existing Joint Seal removal, clean Expansion Joint, and placement of new Joint Seal.
  - ▨ Indicates Limits of Approach Slab Type R(30D)
  - ▨ Indicates Limits of Approach Slab Type R(30S)
  - ① Existing Approach Slab
  - ② Limits of Paving Notch Extension
  - X Structure Location, see Joint Seal Table on "JOINT SEAL DETAILS" sheet.

NOTE:  
 THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DESIGN	BY D. Azzam	CHECKED R. Anderson	LOAD & RESISTANCE FACTOR DESIGN	LIVE LOADING: HL93 W/"LOW-BOY"; PERMIT DESIGN VEHICLE
DETAILS	BY R. Kirkland	CHECKED R. Anderson	LAYOUT	BY D. Azzam
QUANTITIES	BY D. Azzam	CHECKED R. Anderson	SPECIFICATIONS	BY T. Nedwick

STATE OF CALIFORNIA  
 DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES  
 STRUCTURE DESIGN  
**DESIGN BRANCH 10**

BRIDGE NO. Varies  
 POST MILE Varies

**APPROACH SLAB REHABILITATION**  
**GENERAL PLAN NO. 10**


DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
11	SD	5,8,15,52,94,805	Var	105	116

*Renee M. Anderson* 9-26-11  
REGISTERED CIVIL ENGINEER DATE

4-30-12  
PLANS APPROVAL DATE

RENEE ANDERSON  
No. 61040  
Exp. 12/31/12  
CIVIL  
STATE OF CALIFORNIA

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.



**W94-N5 CONNECTOR OC**


Bridge No. 57-0430F Rte 94 Post Mile 1.46  
1" = 40'

39

**QUANTITIES**

BRIDGE NO. 57-0430F

AGGREGATE BASE (APPROACH SLAB)	24	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	144	CY
PAVING NOTCH EXTENSION	129	CF
CORE CONCRETE (2")	9	LF
JOINT SEAL (MR 1/2")	172	LF



**ROUTE 805/ 15 SEPARATION**

Bridge No. 57-0611R Rte 805 PM 14.59  
1" = 40'

40

**QUANTITIES**

BRIDGE NO. 57-0611R

AGGREGATE BASE (APPROACH SLAB)	28	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	168	CY
PAVING NOTCH EXTENSION	87	CF
CLEAN EXPANSION JOINT	57	LF
CORE CONCRETE (2")	8	LF
JOINT SEAL (MR 1 1/2")	174	LF

LEGEND:

- Indicates Existing Structure
- Indicates location of existing Joint Seal removal, clean Expansion Joint, and placement of new Joint Seal.
- ▨ Indicates Limits of Approach Slab Type R(30D)
- ① Existing Approach Slab
- ② Limits of Paving Notch Extension
- X Structure Location, see Joint Seal Table on "JOINT SEAL DETAILS" sheet.

NOTE:  
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DESIGN ENGINEER <i>Daniel T. Adams</i>	DESIGN	BY: D. Azzam	CHECKED: R. Anderson	LOAD & RESISTANCE FACTOR DESIGN	LIVE LOADING: HL93 W/"LOW-BOY"; PERMIT DESIGN VEHICLE
	DETAILS	BY: R. Kirkland	CHECKED: R. Anderson	LAYOUT	BY: D. Azzam
	QUANTITIES	BY: D. Azzam	CHECKED: R. Anderson	SPECIFICATIONS	BY: T. Nedwick

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES  
STRUCTURE DESIGN  
DESIGN BRANCH 10

BRIDGE NO.	Varies
POST MILE	Varies


**APPROACH SLAB REHABILITATION  
GENERAL PLAN NO. 11**

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
11	SD	5,8,15,52,94,805	Var	106	116

Renee M. Anderson 9-26-11  
 REGISTERED CIVIL ENGINEER DATE  
 4-30-12  
 PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER  
 RENEE ANDERSON  
 No. 61040  
 Exp. 12/31/12  
 CIVIL  
 STATE OF CALIFORNIA


The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.



**HOME AVENUE UC**  
 Bridge No. 57-0671L Rte 805 PM 13.95  
 1" = 40'

**QUANTITIES**  
 BRIDGE NO. 57-0671L


AGGREGATE BASE (APPROACH SLAB)	25	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	148	CY
PAVING NOTCH EXTENSION	78	CF
CLEAN EXPANSION JOINT	55	LF
CORE CONCRETE (2")	8	LF
JOINT SEAL (MR 1")	160	LF



**DIVISION STREET UC**  
 Bridge No. 57-0646 Rte 805 Post Mile 11.14  
 1" = 40'

**QUANTITIES**  
 BRIDGE NO. 57-0646

AGGREGATE BASE (APPROACH SLAB)	30	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	180	CY
PAVING NOTCH EXTENSION	92	CF
CLEAN EXPANSION JOINT	89	LF
CORE CONCRETE (2")	12	LF
JOINT SEAL (MR 1")	205	LF



**47TH STREET UC**  
 Bridge No. 57-0647 Rte 805 Post Mile 11.36  
 1" = 40'

**QUANTITIES**  
 BRIDGE NO. 57-0647

AGGREGATE BASE (APPROACH SLAB)	10	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	59	CY
PAVING NOTCH EXTENSION	32	CF
CLEAN EXPANSION JOINT	133	LF
CORE CONCRETE (2")	5	LF
JOINT SEAL (MR 1 1/2")	176	LF

- LEGEND:**
- Indicates Existing Structure
  - Indicates location of existing Joint Seal removal, clean Expansion Joint, and placement of new Joint Seal.
  - ▨ Indicates Limits of Approach Slab Type R(30D)
  - ① Existing Approach Slab
  - ② Limits of Paving Notch Extension
  - X Structure Location, see Joint Seal Table on "JOINT SEAL DETAILS" sheet.

NOTE:  
 THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DESIGN	BY R. Anderson	CHECKED D. AZZAM	LOAD & RESISTANCE FACTOR DESIGN	LIVE LOADING: HL93 W/"LOW-BOY"; PERMIT DESIGN VEHICLE
DETAILS	BY R. Kirkland	CHECKED D. AZZAM	LAYOUT	BY R. Anderson
QUANTITIES	BY R. Anderson	CHECKED D. AZZAM	SPECIFICATIONS	BY T. Nedwick

STATE OF CALIFORNIA  
 DEPARTMENT OF TRANSPORTATION  
 DIVISION OF ENGINEERING SERVICES  
 STRUCTURE DESIGN  
**DESIGN BRANCH 10**

BRIDGE NO. Varies  
 POST MILE Varies  
**APPROACH SLAB REHABILITATION**  
**GENERAL PLAN NO. 12**

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
11	SD	5,8,15,52,94,805	Var	107	116

<i>Renee M. Anderson</i>		9-26-11
REGISTERED CIVIL ENGINEER	DATE	
4-30-12		
PLANS APPROVAL DATE		


REGISTERED PROFESSIONAL ENGINEER	RENEE ANDERSON
No. 61040	Exp. 12/31/12
CIVIL	

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

### QUANTITIES

BRIDGE NO. 57-0640R/L

AGGREGATE BASE (APPROACH SLAB)	21	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	124	CY
PAVING NOTCH EXTENSION	70	CF
CLEAN EXPANSION JOINT	275	LF
CORE CONCRETE (2")	11	LF
JOINT SEAL (MR 1")	366	LF




### 8TH STREET UC

Bridge No. 57-0644 Rte 805 Post Mile 10.61  
1" = 40'

### QUANTITIES

BRIDGE NO. 57-0644

AGGREGATE BASE (APPROACH SLAB)	38	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	226	CY
PAVING NOTCH EXTENSION	130	CF
CORE CONCRETE (2")	15	LF
JOINT SEAL (MR 1/2")	171	LF




### EUCLID AVENUE UC

Bridge No. 57-0640R/L Rte No. 805 Post Mile 9.19  
1" = 40'

### LEGEND:

- Indicates Existing Structure
- Indicates location of existing Joint Seal removal, clean Expansion Joint, and placement of new Joint Seal.
- ▨ Indicates Limits of Approach Slab Type R(30D)
- ① Existing Approach Slab
- ② Limits of Paving Notch Extension
- X Structure Location, see Joint Seal Table on "JOINT SEAL DETAILS" sheet.




### PLAZA BOULEVARD UC

Bridge No. 57-0643 Rte 805 Post Mile 10.28  
1" = 40'

### QUANTITIES

BRIDGE NO. 57-0643

AGGREGATE BASE (APPROACH SLAB)	59	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	356	CY
PAVING NOTCH EXTENSION	200	CF
CORE CONCRETE (2")	24	LF
JOINT SEAL (MR 1/2")	267	LF



### SWEETWATER ROAD UC

Bridge No. 57-0639R/L Rte 805 Post Mile 9.05  
1" = 40'

### QUANTITIES

BRIDGE NO. 57-0639R/L

AGGREGATE BASE (APPROACH SLAB)	39	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	236	CY
PAVING NOTCH EXTENSION	173	CF
CLEAN EXPANSION JOINT	191	LF
CORE CONCRETE (2")	12	LF
JOINT SEAL (MR 1")	420	LF

NOTE:  
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DESIGN	BY R. Anderson	CHECKED D. AZZAM	LOAD & RESISTANCE FACTOR DESIGN	LIVE LOADING: HL93 W/"LOW-BOY"; PERMIT DESIGN VEHICLE
DETAILS	BY R. Kirkland	CHECKED D. AZZAM	LAYOUT	BY R. Anderson
QUANTITIES	BY R. Anderson	CHECKED D. AZZAM	SPECIFICATIONS	BY T. Nedwick

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES  
STRUCTURE DESIGN  
DESIGN BRANCH 10

BRIDGE NO. Varies


POST MILE Varies

## APPROACH SLAB REHABILITATION

### GENERAL PLAN NO. 13



DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
11	SD	5,8,15,52, 94,805	Var	109	116
<i>Renee M. Anderson</i> REGISTERED CIVIL ENGINEER			9-26-11 DATE		
4-30-12 PLANS APPROVAL DATE					
<small>The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.</small>					




### TELEGRAPH CANYON ROAD UC

Bridge No. 57-0635R/L Rte 805 Post Mile 6.06  
1" = 40'

#### QUANTITIES

BRIDGE NO. 57-0635R/L

AGGREGATE BASE (APPROACH SLAB)	37	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	220	CY
CORE CONCRETE (2")	12	LF
JOINT SEAL (MR 1/2")	150	LF




### MAIN STREET UC (OTAY VALLEY ROAD)

Bridge No. 57-0632R/L Rte 805 Post Mile 3.65  
1" = 40'

#### QUANTITIES

BRIDGE NO. 57-0632R/L

AGGREGATE BASE (APPROACH SLAB)	23	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	136	CY
CLEAN EXPANSION JOINT	98	LF
CORE CONCRETE (2")	11	LF
JOINT SEAL (MR 1")	201	LF



### NAPLES STREET UC


Bridge No. 57-0634L Rte 805 Post Mile 5.54  
1" = 40'

#### QUANTITIES

BRIDGE NO. 57-0634L

NOTE:  
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

AGGREGATE BASE (APPROACH SLAB)	24	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	144	CY
CORE CONCRETE (2")	9	LF
JOINT SEAL (MR 1/2")	109	LF



### OTAY RIVER BRIDGE

Bridge No. 57-0631R/L Rte 805 Post Mile 3.34  
1" = 40'

#### QUANTITIES

BRIDGE NO. 57-0631R/L

AGGREGATE BASE (APPROACH SLAB)	85	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	511	CY
PAVING NOTCH EXTENSION	270	CF
CORE CONCRETE (2")	30	LF
JOINT SEAL (MR 1 1/2")	350	LF

- LEGEND:
- Indicates Existing Structure
  - Indicates location of existing Joint Seal removal, clean Expansion Joint, and placement of new Joint Seal.
  - ▨ Indicates Limits of Approach Slab Type R(30D)
  - ① Existing Approach Slab
  - ② Limits of Paving Notch Extension
  - ③ Paving Notch Extension not required
  - X Structure Location, see Joint Seal Table on "JOINT SEAL DETAILS" sheet.

DESIGN	BY R. Anderson	CHECKED D. AZZAM	LOAD & RESISTANCE FACTOR DESIGN	LIVE LOADING: HL93 W/"LOW-BOY"; PERMIT DESIGN VEHICLE
DETAILS	BY R. Kirkland	CHECKED D. AZZAM	LAYOUT	BY R. Anderson
QUANTITIES	BY R. Anderson	CHECKED D. AZZAM	SPECIFICATIONS	BY T. Nedwick

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION


DIVISION OF ENGINEERING SERVICES  
STRUCTURE DESIGN  
DESIGN BRANCH 10

BRIDGE NO. Varies

POST MILE Varies

APPROACH SLAB REHABILITATION  
GENERAL PLAN NO. 15

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
11	SD	5,8,15,52,94,805	Var	110	116
<b>Renee M. Anderson</b> REGISTERED CIVIL ENGINEER			9-26-11 DATE		
4-30-12 PLANS APPROVAL DATE					
<small>The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.</small>					



**DEL SOL BOULEVARD UC**

Bridge No. 57-0854R/L Rte 805 Post Mile 2.17  
 1" = 40'

55


**QUANTITIES**

BRIDGE NO. 57-0854R/L

AGGREGATE BASE (APPROACH SLAB)	20	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	122	CY
PAVING NOTCH EXTENSION	65	CF
CLEAN EXPANSION JOINT	202	LF
CORE CONCRETE (2")	8	LF
JOINT SEAL (MR 1")	290	LF

**LEGEND:**

- Indicates Existing Structure
- Indicates location of existing Joint Seal removal, clean Expansion Joint, and placement of new Joint Seal.
- Indicates Limits of Approach Slab Type R(30D)
- ① Existing Approach Slab
- ② Limits of Paving Notch Extension
- X Structure Location, see Joint Seal Table on "JOINT SEAL DETAILS" sheet.



**SAN YSIDRO BOULEVARD UC**

Bridge No. 57-0776R/L Rte 805 Post Mile 0.65  
 1" = 40'

56

**QUANTITIES**

BRIDGE NO. 57-0776R/L

AGGREGATE BASE (APPROACH SLAB)	67	CY
STRUCTURAL CONCRETE, APPROACH SLAB (TYPE R)	400	CY
PAVING NOTCH EXTENSION	213	CF
CORE CONCRETE (2")	24	LF
JOINT SEAL (MR 1/2")	275	LF

NOTE:  
 THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DESIGN	BY R. Anderson	CHECKED D. AZZAM	LOAD & RESISTANCE FACTOR DESIGN	LIVE LOADING: HL93 W/"LOW-BOY"; PERMIT DESIGN VEHICLE
DETAILS	BY R. Kirkland	CHECKED D. AZZAM	LAYOUT	BY R. Anderson
QUANTITIES	BY R. Anderson	CHECKED D. AZZAM	SPECIFICATIONS	BY T. Nedwick

STATE OF CALIFORNIA  
 DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES  
 STRUCTURE DESIGN  
**DESIGN BRANCH 10**

BRIDGE NO. Varies  
 POST MILE Varies  
**APPROACH SLAB REHABILITATION**  
**GENERAL PLAN NO. 16**

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
11	SD	5,8,15,52,94,805	Var	111	116

*Renee M. Anderson* 9-26-11  
REGISTERED CIVIL ENGINEER DATE

4-30-12  
PLANS APPROVAL DATE

*Renee Anderson*  
No. 61040  
Exp. 12/31/12  
CIVIL  
STATE OF CALIFORNIA

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

### JOINT SEAL TABLE

STRUCTURE LOCATION	ROUTE	BRIDGE NUMBER	LOCATION		JOINT SEAL TYPE	MINIMUM "MR" (in)	LENGTH (ft)	EXISTING WATERSTOP	APPROX. DEPTH TO CLEAN EXP. JOINT SEAL (in)
			Abut						
1	5	57-0587L	Abut 1	-	-	-	-	-	-
			Abut 4	PN	A	1/2	44	NO	12
2	5	57-0005R	Abut 1	BB	A	1/2	67.5	NO	12
			Abut 4	EB	A	1/2	67.5	NO	12
3	5	57-0583R	Abut 1	PN	B	1 1/2	67	NO	12
			Abut 7	PN	A	1	67	NO	12
4	5	57-0007R	Abut 1	PN	A	1/2	14	NO	12
			Abut 4	PN	A	1/2	22	NO	12
5	5	57-0581L	Abut 1	-	-	-	-	-	-
			Abut 9	EB	A	1/2	67	NO	12
6	5	57-0713R	Abut 1	-	-	-	-	-	-
			Abut 7	EB	B	2	90	YES	12
7	5	57-0125	Abut 1	BB	A	1/2	12	NO	12
			Abut 4	EB	A	1/2	32	NO	12
8	5	57-0277	Abut 1	BB	A	1/2	12	NO	12
			Abut 4	EB	A	1/2	36	NO	12
9	5	57-0274	Abut 1	BB	A	1/2	23	NO	12
			Abut 2	-	-	-	-	-	-
10	5	57-0275	Abut 1	BB	A	1/2	23	NO	12
			Abut 2	EB	A	1/2	68	NO	12
11	5	57-0263	Abut 1	BB	A	1/2	27	NO	12
			Abut 13	EB	A	1/2	24	NO	12
12	5	57-0246	Abut 1	BB	A	1/2	27	NO	12
			Abut 8	EB	A	1/2	24	NO	12
13	8	57-0692L	Abut 1	BB	A	1/2	45	NO	12
			Abut 6	EB	A	1/2	45	NO	12
14	8	57-0690L	Abut 1	-	-	-	-	-	-
			Abut 2	EB	A	1/2	40	NO	12
15	8	57-0688L	Abut 1	BW	A	1/2	40	NO	12
			Abut 4	-	-	-	-	-	-
16	8	57-0528L	Abut 1	BW	A	1/2	43	NO	12
			Abut 4	BW	A	1/2	43	NO	12
		57-0528R	Abut 1	BW	A	1/2	62	NO	12
			Abut 4	BW	A	1/2	62	NO	12
17	8	57-0539L	Abut 1	BB	A	1/2	40	NO	12
			Abut 4	EB	A	1/2	40	NO	12
		57-0539R	Abut 1	BB	A	1/2	40	NO	12
			Abut 4	EB	A	1/2	40	NO	12

### JOINT SEAL TABLE

STRUCTURE LOCATION	ROUTE	BRIDGE NUMBER	LOCATION		JOINT SEAL TYPE	MINIMUM "MR" (in)	LENGTH (ft)	EXISTING WATERSTOP	APPROX. DEPTH TO CLEAN EXP. JOINT SEAL (in)
			Abut						
18	8	57-0534L	Abut 1	BB	B	1/2	66	NO	12
			Abut 4	EB	B	1/2	66	NO	12
		57-0534R	Abut 1	BB	B	1/2	66	NO	12
			Abut 4	EB	B	1/2	66	NO	12
19	8	57-0462L	Abut 1	BB	A	1/2	51	NO	12
			Abut 4	EB	A	1/2	57	NO	12
		57-0462R	Abut 1	BB	A	1/2	52	NO	12
			Abut 4	EB	A	1/2	48	NO	12
20	8	57-0474L	Abut 1	BB	A	1/2	39	NO	12
21	8	57-0366R	Abut 1	BB	A	1/2	23	NO	12
			Abut 2	-	-	-	-	-	-
22	8	57-0364	Abut 1	BB	A	1/2	46	NO	12
			Abut 2	EB	A	1/2	36	NO	12
23	8	57-0363L	Abut 1	BB	A	1/2	70	NO	12
			Abut 2	EB	A	1/2	12	NO	12
		57-0363R	Abut 1	BB	A	1/2	70	NO	12
			Abut 2	EB	A	1/2	70	NO	12
24	8	57-0362	Abut 1	BB	B	1 1/2	111	NO	12
			Abut 5	EB	B	1 1/2	111	NO	12
25	15	57-0889L	Abut 1	BB	A	1	66	NO	12
			Abut 2	EB	A	1	66	NO	12
		57-0889R	Abut 1	BB	A	1	66	NO	12
			Abut 2	EB	A	1	66	NO	12
26	15	57-0894L	Abut 1	BB	B	2	78	NO	12
			Abut 2	EB	B	2	70	NO	12
27	15	57-0819L	Abut 1	BB	A	1	69	NO	12
			Abut 2	-	-	-	-	-	-
28	15	57-0817R	Abut 1	BB	A	1	96	NO	12
			Abut 2	EB	A	1	96	NO	12
29	52	57-1024G	Abut 1	BB	B	2	40	NO	12
			Abut 2	EB	B	2	40	NO	12
30	52	57-0753G	Abut 1	BB	A	1/2	32	NO	12
			Abut 2	EB	A	1/2	32	NO	12

LEGEND:  
BB = Begin Bridge  
EB = End Bridge  
JSA = Joint Seal Assembly  
PN = Paving Notch  
BW = Backwall

NOTE:  
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DESIGN	BY R. Anderson	CHECKED D. Azzam
DETAILS	BY R. Kirkland	CHECKED D. Azzam
QUANTITIES	BY R. Anderson	CHECKED D. Azzam

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES  
STRUCTURE DESIGN  
DESIGN BRANCH 10

BRIDGE NO. Varies  
POST MILE Varies

APPROACH SLAB REHABILITATION  
JOINT SEAL DETAILS NO.1

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
11	SD	5,8,15,52,94,805	Var	112	116

*Renee M. Anderson* 9-26-11  
REGISTERED CIVIL ENGINEER DATE

4-30-12  
PLANS APPROVAL DATE

*Renee Anderson*  
No. 61040  
Exp. 12/31/12  
CIVIL  
STATE OF CALIFORNIA

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

JOINT SEAL TABLE									
STRUCTURE LOCATION	ROUTE	BRIDGE NUMBER	LOCATION		JOINT SEAL TYPE	MINIMUM "MR" (in)	LENGTH (ft)	EXISTING WATERSTOP	APPROX. DEPTH TO CLEAN EXP. JOINT SEAL (in)
			Abut	BB					
31	52	57-0744R	Abut 1	BB	A	1	65	NO	12
			Abut 4	EB	A	1	71	NO	12
32	52	57-0743R	Abut 1	BB	A	1/2	40	NO	12
			Abut 2	EB	A	1	40	NO	12
33	52	57-0523F	Abut 1	BB	A	1	21	NO	12
			Abut 4	EB	A	1	21	NO	12
34	94	57-0572L	Abut 1	BB	A	1	42	NO	12
			Abut 2	EB	A	1	42	NO	12
35	94	57-0663R	Abut 1	BB	A	1	77	NO	12
			Abut 2	EB	A	1/2	37	NO	12
36	94	57-0107L	Abut 1	BB	A	1/2	94	NO	12
			Abut 3	EB	A	1/2	85	NO	12
37	94	57-0350F	Abut 1	BB	A	1	44.5	YES	12
			Abut 4	EB	A	1	44.5	YES	12
38	94	57-0361	Abut 1	BB	A	1/2	80	NO	12
			Abut 2	EB	A	1/2	80	NO	12
39	94	57-0430F	Abut 1	BB	A	1/2	67	NO	12
			Abut 3	EB	A	1/2	105	NO	12
40	805	57-0611R	Abut 1	BB	B	1 1/2	87	NO	12
			Abut 5	EB	B	1 1/2	87	NO	12
41	805	57-0671L	Abut 1	BB	A	1	80	NO	12
			Abut 2	EB	A	1	80	NO	12
42	805	57-0647L	Abut 1	BB	B	1 1/2	88	NO	12
			Abut 3	EB	B	1 1/2	88	NO	12
43	805	57-0646	Abut 1	-	-	-	-	-	-
			Abut 2	EB	A	1	205	NO	12
44	805	57-0644	Abut 1	BB	A	1/2	85.5	NO	12
			Abut 2	EB	A	1/2	85.5	NO	12
45	805	57-0643L	Abut 1	BB	A	1/2	85	NO	12
			Abut 2	EB	A	1/2	85	NO	12
45	805	57-0643R	Abut 1	BB	A	1/2	12	NO	12
			Abut 2	EB	A	1/2	85	NO	12
46	805	57-0640L	Abut 1	BB	A	1	80	NO	12
			Abut 4	EB	A	1	72	NO	12
46	805	57-0640R	Abut 1	BB	A	1	121	NO	12
			Abut 4	EB	A	1	93	NO	12


JOINT SEAL TABLE										
STRUCTURE LOCATION	ROUTE	BRIDGE NUMBER	LOCATION		JOINT SEAL TYPE	MINIMUM "MR" (in)	LENGTH (ft)	EXISTING WATERSTOP	APPROX. DEPTH TO CLEAN EXP. JOINT SEAL (in)	
			Abut	BB						
47	805	57-0639L	Abut 1	BB	A	1	105	NO	12	
			Abut 4	EB	A	1	105	NO	12	
		57-0639R	Abut 1	BB	A	1	105	NO	12	
			Abut 4	EB	A	1	105	NO	12	
48	805	57-0746L	Abut 1	BB	A	1	92	NO	12	
			Abut 3	EB	A	1	107	NO	12	
		57-0746R	Abut 1	-	-	-	-	-	-	-
			Abut 3	EB	A	1	118	NO	12	
49	805	57-0638L	Abut 1	BB	A	1	92	NO	12	
			Abut 6	EB	A	1	82	NO	12	
		57-0638R	Abut 1	BB	A	1	128	NO	12	
			Abut 6	EB	A	1	128	NO	12	
50	805	57-0637R	Abut 1	BB	A	1	112	NO	12	
			Abut 4	EB	A	1	126	NO	12	
51	805	57-0635L	Abut 1	-	-	-	-	-	-	
			Abut 3	EB	A	1/2	36	NO	12	
		57-0635R	Abut 1	BB	A	1/2	75	NO	12	
			Abut 3	EB	A	1/2	39	NO	12	
52	805	57-0634L	Abut 1	BB	A	1/2	67	NO	12	
			Abut 2	EB	A	1/2	42	NO	12	
53	805	57-0632L	Abut 1	BB	A	1	67	NO	12	
			Abut 2	EB	A	1	67	-	-	
		57-0632R	Abut 1	-	-	-	-	NO	12	
			Abut 2	EB	A	1	67	NO	12	
54	805	57-0631L	Abut 1	BB	A	1 1/2	87.5	NO	12	
			Abut 5	EB	A	1 1/2	87.5	NO	12	
		57-0631R	Abut 1	BB	A	1 1/2	87.5	NO	12	
			Abut 5	EB	A	1 1/2	87.5	NO	12	
55	805	57-0854L	Abut 1	-	-	-	-	-	-	
			Abut 2	EB	A	1	106.8	NO	12	
		57-0854R	Abut 1	BB	A	1	98.3	NO	12	
			Abut 2	EB	A	1	84.2	NO	12	
56	805	57-0776L	Abut 1	BB	A	1/2	68.7	NO	12	
			Abut 2	EB	A	1/2	68.7	NO	12	
		57-0776R	Abut 1	BB	A	1/2	68.7	NO	12	
			Abut 2	EB	A	1/2	68.7	NO	12	

LEGEND:  
BB = Begin Bridge  
EB = End Bridge  
JSA = Joint Seal Assembly  
PN = Paving Notch  
BW = Backwall

NOTE:  
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.


STRUCTURES DESIGN DETAIL SHEET (ENGLISH) (REV. 09-01-10)	DESIGN	BY R. Anderson	CHECKED D. Azzam	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	DIVISION OF ENGINEERING SERVICES STRUCTURE DESIGN DESIGN BRANCH 10	BRIDGE NO.	APPROACH SLAB REHABILITATION JOINT SEAL DETAILS NO. 2			
	DETAILS	BY R. Kirkland	CHECKED D. Azzam			Varies				
	QUANTITIES	BY R. Anderson	CHECKED D. Azzam			Varies				
ORIGINAL SCALE IN INCHES FOR REDUCED PLANS					UNIT: 3589	PROJECT NUMBER & PHASE: 11000201841	CONTRACT NO.: 11-238601	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES	SHEET 18 OF 22

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
11	SD	5,8,15,52, 94,805	Var	113	116
Renee M. Anderson		9-26-11		REGISTERED CIVIL ENGINEER DATE	
4-30-12		PLANS APPROVAL DATE			
<small>The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.</small>					



**JOINT REPAIR DETAIL**

Reinforcement may be encountered during deck concrete removal and is to remain undamaged.



**BARRIER RAIL**

**JOINT SEAL AT LOW SIDE OF DECK**

Note: Details shown for illustration purposes only.  
For use only where deck joint matches the sidewalk, curb or barrier rail joint.

**NOTES:**

The following notes apply to JOINT SEAL TYPE A:


Install Joint Seal (MR = 1/2") or Silicone Joint Seal 3" up into curb or barrier rail on the low side of the deck where deck joint aligns with curb or barrier rail joint.

For details not shown see RSP 


The following notes apply to JOINT SEAL TYPE B:

- 1) Seal must satisfy both minimum Movement Rating (MR) and minimum W1 requirements.
- 2) Minimum W1 is the calculated maximum width of the joint based on field measurements. After the joints have been cleaned, minimum W1 is to be recalculated by the Engineer.
- 3) W1 shall be the smaller of the values determined as follows:
  - A) 0.85 times the manufacturer's designed minimum uncompressed width of the seal.
  - B) The width of the seal on the third successive test cycle of the pressure deflection test, when compressed to an average pressure of 3.0 PSI.
- 4) Bend Type B joint seal 6 inches up into curb or rail on the low side of the deck where deck joint matches curb or rail joint.


For details not shown see RSP 




**DIAPHRAGM ABUTMENT**




**ABUTMENT WITH BACKWALL AND PAVING NOTCH**



**ABUTMENT WITH BACKWALL**



**HINGE**



**BENT OR PIER**

**JOINT SEAL LOCATION**

NO SCALE

NOTE:  
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DESIGN BY R. Anderson CHECKED D. Azzam DETAILS BY R. Kirkland CHECKED D. Azzam QUANTITIES BY R. Anderson CHECKED D. Azzam	<b>STATE OF CALIFORNIA</b> DEPARTMENT OF TRANSPORTATION	DIVISION OF ENGINEERING SERVICES STRUCTURE DESIGN <b>DESIGN BRANCH 10</b>	BRIDGE NO.	<b>APPROACH SLAB REHABILITATION</b> <b>JOINT SEAL DETAILS NO. 3</b>
			Varies	
			POST MILE	
UNIT: 3589 PROJECT NUMBER & PHASE: 11000201841			CONTRACT NO.: 11-238601	DISREGARD PRINTS BEARING EARLIER REVISION DATES
ORIGINAL SCALE IN INCHES FOR REDUCED PLANS			REVISION DATES: 4/08/11, 9/23/11, 1/24/12	SHEET 19 OF 22

USERNAME => s128843 DATE PLOTTED => 02-MAY-2012 TIME PLOTTED => 15:53


DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
11	SD	5,8,15,52,94,805	Var	114	116

Rene Anderson 9-26-11  
REGISTERED CIVIL ENGINEER DATE


4-30-12  
PLANS APPROVAL DATE

Rene Anderson  
No. 61040  
Exp. 12/31/12  
CIVIL  
STATE OF CALIFORNIA

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.




**WITHOUT APPROACH SLAB REPLACEMENT**




**WITH APPROACH SLAB REPLACEMENT**

**CONCRETE OVERLAY REMOVAL & REPLACEMENT DETAIL**

no scale



**WITHOUT APPROACH SLAB REPLACEMENT**



**WITH APPROACH SLAB REPLACEMENT**


**NEW CONCRETE OVERLAY PLACEMENT DETAIL**

no scale

DECK REPAIR TABLE			
STRUCTURE LOCATION	BRIDGE NUMBER	APPROXIMATE AREA DAMAGED (PERCENT)	APPROXIMATE DEPTH (INCHES)
17	57-0539L	10	3
	57-0539R	10	3
18	57-0534L	10	3
	57-0534R	10	3
19	57-0462L	10	3
	57-0462R	10	3


NOTE: THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

Locations to be determined by the Engineer. For details see "DECK OVERLAY DETAIL".



**DECK OVERLAY AT BARRIER**

no scale



**DECK OVERLAY DETAIL**

Note: Location will be determined by the Engineer. Reinforcement may be encountered during deck concrete removal and is to remain undamaged.

NO SCALE

**DECK REPAIR NOTES:**

- Existing reinforcement shall be protected in place during unsound concrete removal and patching operations.
- It is the responsibility of the Contractor to repair any reinforcement that is accidentally cut by saw cutting operations.
- When existing transverse reinforcement is exposed in the deck surface, saw cutting may be waived with the approval of the Engineer.
- The saw cut depth shall not exceed 1/2 inch or the concrete cover over the top steel reinforcing bars, whichever is less.
- Remove unsound concrete to expose sound, hard concrete substrate. Replace with rapid setting concrete patch if depth of patch is greater than or equal to 3 inches. If depth of patch is less than 3 inches, then replace with polyester concrete.
- Repair deck prior to placing polyester overlay.

DESIGN	BY	R. Anderson	CHECKED	D. Azzam	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	DIVISION OF ENGINEERING SERVICES STRUCTURE DESIGN DESIGN BRANCH 10	BRIDGE NO.	Varies	APPROACH SLAB REHABILITATION DECK OVERLAY DETAILS	
	DETAILS	BY	R. Kirkland	CHECKED			R. Anderson	POST MILE		Varies
	QUANTITIES	BY	R. Anderson	CHECKED			D. Azzam	Varies		Varies

STRUCTURES DESIGN DETAIL SHEET (ENGLISH) (REV. 09-01-10)

ORIGINAL SCALE IN INCHES FOR REDUCED PLANS

0 1 2 3

UNIT: 3589  
PROJECT NUMBER & PHASE: 11000201841  
CONTRACT NO.: 11-238601

DISREGARD PRINTS BEARING EARLIER REVISION DATES



REVISION DATES	SHEET	OF
8/08/11 9/23/11 1/24/12	20	22

FILE => 11-238601qjntd+20.dgn

DIST.	COUNTY	ROUTE	MILE POST TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
11	SD	5,8,15,52,94,805	Var	115	116


Renee M. Anderson 9-26-11  
 REGISTERED ENGINEER - CIVIL  
 No. 61040  
 Exp. 12/31/12  
 CIVIL  
 STATE OF CALIFORNIA

4-30-12  
 PLANS APPROVAL DATE  
 The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.




**STRUCTURE APPROACH - END STAGGER DETAIL**


APPROACH SLAB TRANSVERSE CONTACT JOINT		
APPROACH SKEW	WITH AC ROADWAY PAVEMENT	WITH PCC ROADWAY PAVEMENT
< 10°	Parallel to face of paving notch	Parallel to face of paving notch
10° - 45°	Parallel to face of P N use (Detail A)	Stagger lines 24' to 36' apart
> 45°	Parallel to face of P N use (Detail A)	Stagger at each lane line




**SECTION A-A**




**SECTION C-C**




**LONGITUDINAL CONSTRUCTION JOINT ALTERNATIVES**



**DETAIL A**




**DETAIL C**




**BAR CHAIR DETAIL**


NOTE: For details not shown, see "Section A-A".



**TIE DETAIL**



**DETAIL B**



\*(TO BE USED WITH TYPE 25 OR TYPE 27 CONCRETE BARRIER) \*(TO BE USED WITH TYPE 732 OR TYPE 736 CONCRETE BARRIER)

- NOTES:**
- For details not shown or noted, see Structure Plans. Adjust bar reinforcement to clear a sawcut for sealed joint, when required.
  - Space to avoid existing prestress anchorages and main reinforcement.
  - Longitudinal construction joints, when permitted by the Engineer, shall be located on lane lines.
  - Transverse contact joint shall be a minimum of 5'-0" from an existing or constructed weakened plane joint.
  - For transverse contact joint with new PCC paving, refer to Standard Plan P10.
  - Couplers are required for stage construction.
  - End angle or plate at beginning of barrier transition, end of wingwall or end of structure approach as applicable.
  - One Concrete Core (2" Diameter x 18" long) per each approach slab lane. The exact location of coring will be determined by the engineer.

NOTE:  
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

REVISED STANDARD DRAWING			
RELEASE DATE <b>3/14/05</b>	DESIGN BY <b>M. TRAFFALIS</b>	CHECKED <b>E. THORKILDSEN</b>	RELEASED BY <b>[Signature]</b>
FILE NO. <b>xs3-140e</b>	DETAILS BY <b>R. YEE</b>	CHECKED <b>E. THORKILDSEN</b>	OFFICE CHIEF <b>[Signature]</b>
	SUBMITTED BY <b>M. HA</b>	DRAWING DATE <b>8/92</b>	

Added Note 8

STATE OF CALIFORNIA  
DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES







BRIDGE NO.  
Varies  
MILE POST  
Varies

**APPROACH SLAB REHABILITATION**  
**STRUCTURE APPROACH TYPE R(30D)**

DIST.	COUNTY	ROUTE	MILE POST TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
11	SD	5,8,15,52,94,805	Var	116	116

Renee M. Anderson 9-26-11  
 REGISTERED ENGINEER - CIVIL  
 No. 61040  
 Exp. 12/31/12  
 CIVIL  
 STATE OF CALIFORNIA

4-30-12  
 PLANS APPROVAL DATE  
 The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.



APPROACH SLAB TRANSVERSE CONTACT JOINT		
APPROACH SKEW	WITH AC ROADWAY PAVEMENT	WITH PCC ROADWAY PAVEMENT
< 10°	Parallel to face of paving notch	Parallel to face of paving notch
10° - 45°	Parallel to face of P N use (Detail A)	Stagger lines 24' to 36' apart
> 45°	Parallel to face of P N use (Detail A)	Stagger at each lane line

- NOTES:**
- Sealed joint, for M.R. see Structure Plans. Adjust bar reinforcement to clear a sawcut for sealed joint, when required.
  - Longitudinal construction joints, when permitted by Engineer, shall be located on lane lines.
  - Transverse contact joint shall be a minimum of 5'-0" from an existing or constructed weakened plane joint.
  - For transverse contact joint with new PCC paving, refer to Standard Plan P10.
  - Couplers are required for stage construction.
  - End angle or plate at beginning of barrier transition, end of wingwall or end of structure approach as applicable.
  - One Concrete Core (2" Diameter x 18" long) per each approach slab lane. The exact location of coring will be determined by the engineer.

NOTE:  
 THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

REVISED STANDARD DRAWING			
RELEASE DATE 3/14/05	DESIGN BY M. TRAFFALIS	CHECKED E. THORKILDSEN	RELEASED BY
FILE NO. xs3-130e	DETAILS BY R. YEE	CHECKED E. THORKILDSEN	
	SUBMITTED BY M. HA	DRAWING DATE 8/92	OFFICE CHIEF

Added Note 7

STATE OF CALIFORNIA  
 DEPARTMENT OF TRANSPORTATION  
 DIVISION OF ENGINEERING SERVICES

BRIDGE NO.  
 Varies  
 MILE POST  
 Varies  
**APPROACH SLAB REHABILITATION**  
**STRUCTURE APPROACH TYPE R(30S)**