

DEPARTMENT OF TRANSPORTATION
DIVISION OF ENGINEERING SERVICES
OFFICE ENGINEER, MS 43
1727 30TH STREET
P.O. BOX 168041
SACRAMENTO, CA 95816-8041
FAX (916) 227-6214
TTY (916) 227-8454



Flex your power!
Be energy efficient!

**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

November 7, 2008

11-SD-52-26.1/28.6
11-2T0104
STPL-6211(077)

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in SAN DIEGO COUNTY IN SANTEE FROM CUYAMACA STREET OVERHEAD TO MAGNOLIA AVENUE UNDERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on November 20, 2008.

This addendum is being issued to revise the Project Plans, Special Provisions and the Federal Minimum Wages with Modification Number 14 dated October 3, 2008.

Project Plan Sheets 57 and 58 are revised. Half-sized copies of the revised sheets are attached for substitution for the like-numbered sheets.

In the Special Provisions, Section 10-1.02, "ORDER OF WORK," the fourteenth paragraph and its table is deleted.

In the Special Provisions, Section 10-1.61, "SEALING JOINTS," the subsections "ARCHITECTURAL FINISH (EXPOSED AGGREGATE)", "TEST PANEL", "COLORS", "CURING", and "MEASUREMENT AND PAYMENT" are deleted.

In the Special Provisions, Section 10-1.61A, "ARCHITECTURAL FINISH (EXPOSED AGGREGATE)" is added as follows:

"10-1.61A ARCHITECTURAL FINISH (EXPOSED AGGREGATE)

Exposed aggregate architectural finish on concrete surfaces shall conform to the details shown on the plans and the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

The matrix of cement and fine aggregate shall be removed from the surface of the concrete by water jetting, coarse brooming, abrasive blasting, or a combination of these procedures to expose coarse aggregate to a depth of approximately 6 mm to 12 mm from the formed or floated surface. Removal methods shall not dislodge or loosen the coarse aggregate from embedment in the concrete matrix. At the option of the Contractor, a commercial quality, water-resistant set retarder manufactured for the intended use may be used. Exposed aggregate finish shall have cement film, discoloring agents, dirt, dust, grease, loose concrete and other foreign material removed and shall be uniform in appearance.

11-SD-52-26.1/28.6
11-2T0104
STPL-6211(077)

TEST PANEL

A test panel at least 1.25 m x 1.25 m in size shall be successfully completed at a location approved by the Engineer before beginning work on architectural finishes. The test panel shall be constructed and finished with the materials, tools, equipment and methods to be used in constructing the architectural finish. If ordered by the Engineer, additional test panels shall be constructed and finished until the specified finish, texture and color are obtained, as determined by the Engineer.

The test panel approved by the Engineer shall be used as the standard of comparison in determining acceptability of architectural finish applied to concrete surfaces.

COLORS

Integrally colored concrete shall conform to "Colored Concrete" of these special provisions.

CURING

Precast panels shall be cured in conformance with the provisions in Section 90-7.01D, "Forms-In-Place Method," or 90-7.04, "Curing Precast Concrete Members," of the Standard Specifications. Seals or curing compounds shall not be used on exposed aggregate finish.

MEASUREMENT AND PAYMENT

Full compensation for exposed aggregate architectural finish on precast panels shall be considered as included in the contract price paid per square meter for earth retaining structures and no separate payment will be made therefor."

To BID book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the NOTICE TO BIDDERS section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the BID book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by GSO overnight mail to all book holders to ensure that each receives it. A copy of this addendum and the modified wage rates are available for the contractor's use on the Website:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html

If you are not a BID book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

Original Signed By

ROBERT E. TRAVIS, Chief
Office of Plans, Specifications & Estimates
Division of Engineering Services - Office Engineer

Attachment