

DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30th Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

www.dot.ca.gov/hq/esc/oe

*Flex your power!
Be energy efficient!*

August 2, 2013

12-Ora-91-8.1/9.3, 10.1

12-0C5604

Project ID 1200000078

Addendum No. 2

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN ORANGE COUNTY IN ANAHEIM FROM 0.3 MILE WEST OF TUSTIN AVENUE OVERCROSSING TO 0.3 MILE EAST OF 91/55 SEPARATION AND AT LAKEVIEW AVENUE OVERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Thursday, August 8, 2013.

This addendum is being issued to revise the *Notice to Bidders and Special Provisions and Information Handout*.

In the Special Provisions, Section 2, "BIDDING," the additional section 2-1.06B to the Supplemental Project Information is replaced as attached.

In the Special Provisions, Section 14-6.02, "SPECIES PROTECTION," is replaced as attached.

The *Information Handout*, "BAT MITIGATION PLAN," is added as attached.

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the *Bid* book.

Submit bids in the *Bid* book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

Addendum No. 2
Page 2
August 2, 2013

12-Ora-91-8.1/9.3, 10.1
12-0C5604
Project ID 1200000078

This addendum and attachments are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/12/12-0C5604

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



REBECCA D. HARNAGEL
Chief, Office of Plans, Specifications & Estimates
Office Engineer
Division of Engineering Services

Attachments

Add to section 2-1.06B:

The Department makes the following supplemental project information available:

Supplemental Project Information

Means	Description
Included in the <i>Information Handout</i>	Geotechnical Design Report for Retaining Walls, dated January 4, 2013 Geotechnical Design Report for Retaining Walls #454, 497, and 519, dated January 18, 2013 Foundation Report for Santa Ana River Bridge (Widen), dated December 13, 2012 Final Hydraulic Report, dated August 3, 2012 Caltrans Falsework Manual dated December 2011, Memo C-19-1. Aerially Deposited Lead Site Investigation Material Report City of Anaheim Service Confirmation OH Sign Foundation Report Storm Water Information Handout California Water Board Section 401 Water Quality Standards Certification United States Army Corps of Engineers, Nationwide Permit No. 14 Orange County Flood Control District Permit California Department of Fish & Wildlife Streambed Alteration Agreement Bat Mitigation Plan
Available as specified in the <i>Standard Specifications</i>	Bridge as-built drawings
Included with the project plans	Logs of test borings

Replace section 14-6.02 with:

14-6.02 SPECIES PROTECTION

14-6.02A General

Section 14-6.02 includes specifications for protecting regulated species or their habitat.

This project is within or near habitat for regulated species shown in the following table:

Species Name
Bat Species
Nesting Bird Species

14-6.02B Material

Not Used

14-6.02C Construction

14-6.02C(1) General

Not Used

14-6.02C(2) Protective Radius

Upon discovery of a regulated species (i.e. bats and nesting birds) stop construction activities within a 100 foot radius of the discovery. Immediately notify the Engineer. Do not resume activities until receiving notification from the Engineer.

14-6.02C(3) Protocols

Not Used

14-6.02C(4) Biological Resource Information

Not Used

14-6.02C(5) Protection Measures

Within species protection area 1, implement the following protection measures:

1. Species Protection Area 1 is designated as the bridge structure in the project area.
2. Wildlife exclusion devices and alternative bat habitat (concrete panels) will be installed on the bridge structure in the project area. Exclusion devices will be located within the structure hinges and concrete panels will be located on the southwestern portion of the bridge on the eastbound girders. Movement, tampering, or modifications to exclusion devices and/or concrete panels are prohibited unless authorized by the Engineer. If the contractor causes any damage to exclusion devices or concrete panels the contractor will be responsible for all costs incurred.
3. Cofferdam and Pile Driving operations on pier 13-17 shall not be performed between April 15-August 31.
4. The Contractor shall notify the Engineer 30 days prior to beginning any bridge work.
5. Notify the Engineer immediately if damage to exclusion devices or concrete panels is caused or noticed.
6. All bat exclusion devices shall be removed when no longer required as directed by the Engineer
7. Within 15 days of approval of the contract, the Contractor shall meet with the Engineer and Department's designated Biologist to discuss environmental issues.

14-6.02C(6) Monitoring Schedule

Not Used

14-6.02D Payment

Not Used