

Addendum No. 1
Page 2
March 2, 2007

12-Ora-55-28.1
12-0H2104
ACNH-P055(049)E

In the Proposal and Contract, the Engineer's Estimate Items 41 and 42 are added and Item 40 is deleted as attached.

To Proposal and Contract book holders:

Replace page 4 of the Engineer's Estimate in the Proposal with the attached revised pages 4 and 4A of the Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the NOTICE TO CONTRACTORS section of the Notice to Contractors and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by DHL overnight mail to Proposal and Contract book holders to ensure that each receives it. A copy of this addendum and the modified wage rates are available for the contractor's use on the Internet Site:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief
Office of Plans, Specifications & Estimates
Division of Engineering Services - Office Engineer

Attachments

REMOVE POOL

Pools and spas, where shown on the plans and as specified in these special provisions to be removed, shall be removed.

Prior to the removal of the pools and spas, Contractor shall coordinate and arrange the work with the Engineer.

Full compensation for removal and demolition of pools and spas shall be considered as included in Contract lump sum price paid for remove pool. This price shall include full compensation for furnishing all labor, materials, imported borrow, tools, equipment, and incidentals for doing all the work involved in removing pools, spas, appurtenances, components, cuts, fills, embankment, excavation, compaction, slope grading and re-grading and disposal of material to outside state right of way as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Material from removal of pools and spas shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications or as directed by the Engineer.

Demolition of Existing Residential Pool Structures

There are two existing residential pool structures as shown on the plans located at 4039 and 4045 Maple Tree Drive.

These pools shall be demolished and the resulting voids filled with compacted fill as part of this project.

All work done for demolition and backfilling of existing residential pool structure shall be paid for at lump sum price and no other compensation shall be allowed.

The demolition shall take place as to protect the fill material and native formational material located behind the pool walls under the former house pads.

Demolition shall include the pools and spas with all plaster, concrete, reinforced concrete, rebar, tile, piping and plumbing, electrical wiring, reinforced pool decking flatwork and all remaining associated materials not removed during previously completed residential housing demolition.

It may be necessary to demolish the pools in two stages. The side of the pool closest to the hinge point of the slope may be demolished to accommodate temporary access to construct the upper wall and the upslope wall side of the pool may be left in place to minimize erosion during upper wall construction. Once the upper wall has been constructed the remainder of the pool structure shall be removed and the void resulting from the removal of the pool shall be backfilled with compacted fill as part of the re-grading of the slope area above the upper wall.

The fill material shall consist of either on-site excavated soils or approved imported borrow. All of the demolished materials shall become property of the Contractor and shall be disposed of outside the State Right of Way.

The grading limit behind the pool shall extend at least to a 45 degree inclined plan extending up and away from the bottom of the upslope wall of the pool.

The final grading limits behind the removed pool structures shall be determined by the Engineer.

7-1.12B(4)(a) General

- The Contractor shall carry General Liability and Umbrella or Excess Liability Insurance covering all operations by or on behalf of the Contractor providing insurance for bodily injury liability and property damage liability for the following limits and including coverage for:

1. Premises, operations, and mobile equipment
2. Products and completed operations
3. Broad form property damage (including completed operations)
4. Explosion, collapse, and underground hazards
5. Personal injury
6. Contractual liability

7-1.12B(4)(b) Liability Limits/Additional Insureds

- The limits of liability shall be at least the amounts shown in the following table:

Total Bid	For Each Occurrence ¹	Aggregate for Products/Completed Operation	General Aggregate ²	Umbrella or Excess Liability ³
≤\$1,000,000	\$1,000,000	\$2,000,000	\$2,000,000	\$5,000,000
>\$1,000,000 ≤\$5,000,000	\$1,000,000	\$2,000,000	\$2,000,000	\$10,000,000
>\$5,000,000 ≤\$25,000,000	\$2,000,000	\$2,000,000	\$4,000,000	\$15,000,000
>\$25,000,000	\$2,000,000	\$2,000,000	\$4,000,000	\$25,000,000
1. Combined single limit for bodily injury and property damage. 2. This limit shall apply separately to the Contractor's work under this contract. 3. The umbrella or excess policy shall contain a clause stating that it takes effect (drops down) in the event the primary limits are impaired or exhausted.				

- The Contractor shall not require certified Small Business subcontractors to carry Liability Insurance that exceeds the limits in the table above. Notwithstanding the limits specified herein, at the option of the Contractor, the liability insurance limits for certified Small Business subcontractors of any tier may be less than those limits specified in the table. For Small Business subcontracts, "Total Bid" shall be interpreted as the amount of subcontracted work to a certified Small Business.

- The State, including its officers, directors, agents (excluding agents who are design professionals), and employees, shall be named as additional insureds under the General Liability and Umbrella Liability Policies with respect to liability arising out of or connected with work or operations performed by or on behalf of the Contractor under this contract. Coverage for such additional insureds does not extend to liability:

1. Arising from any defective or substandard condition of the roadway which existed at or before the time the Contractor started work, unless such condition has been changed by the work or the scope of the work requires the Contractor to maintain existing roadway facilities and the claim arises from the Contractor's failure to maintain;
2. For claims occurring after the work is completed and accepted unless these claims are directly related to alleged acts or omissions of the Contractor that occurred during the course of the work; or
3. To the extent prohibited by Insurance Code Section 11580.04.

- Additional insured coverage shall be provided by a policy provision or by an endorsement providing coverage at least as broad as Additional Insured (Form B) endorsement form CG 2010, as published by the Insurance Services Office (ISO), or other form designated by the Department.

ENGINEER'S ESTIMATE**12-0H2104**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
21	010874	GEOSYNTHETIC FABRIC	M2	20 000		
22 (S)	010875	EROSION CONTROL (TYPE BFM)	M2	17 000		
23	260301	CLASS 3 AGGREGATE BASE	M3	110		
24	390102	ASPHALT CONCRETE (TYPE A)	TONN	460		
25	394046	PLACE ASPHALT CONCRETE DIKE (TYPE D)	M	150		
26 (S)	500050	TIEBACK ANCHOR	EA	342		
27 (F)	510414	CLASS 1 CONCRETE (BACKFILL)	M3	630		
28 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	M3	4.8		
29 (F)	575004	TIMBER LAGGING	M3	240		
30 (S)	040896	CLEAN AND PAINT STEEL SOLDIER PILING	LS	LUMP SUM	LUMP SUM	
31	650069	450 MM REINFORCED CONCRETE PIPE	M	150		
32	010876	200 MM PLASTIC PIPE	M	250		
33	010877	250 MM PLASTIC PIPE	M	500		
34	010878	100 MM PLASTIC PIPE (SLOTTED)	M	3300		
35	010879	150 MM PLASTIC PIPE	M	230		
36	010880	100 MM PLASTIC PIPE	M	800		
37 (F)	750001	MISCELLANEOUS IRON AND STEEL	KG	740		
38	010881	PIEZOMETRIC MONITORING WELL	EA	4		
39	010882	INCLINOMETER MONITORING SYSTEM	EA	6		
40	BLANK					

ENGINEER'S ESTIMATE
12-0H2104

41	011521	REMOVE POOL	LS	LUMP SUM	LUMP SUM	
42	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

TOTAL BID: _____