

150 mm (6") Min Typ -

ŭ

Direction of Travel

- 300 mm (I2") Max

(See Note 6)


ARRAY 'U22'

Approach speed 100 km/h (62 mph) or less

Sand Filled Module 13 mm (1/2") Min ₩-50 mm (2") Min Tvp Surface-Downward Slope Greater Than 5% 5% Max AC or Epoxy Mortar Base to New Slope ELEVATION

SLOPED SEAT DETAIL

(See Note 4)



PAINTING DETAIL

(See Note 5)

NOTES

- (xxx) indicates module location and mass of sand in kilograms (weight of sand in pounds) modules. Module spacing is based on the greater diameter of the modules.
- 2. All sand masses (weights) are nominal.
- 3. Each module is to contain amount of sand indicated, supported according to the manufacturer's instructions.
- 4. Modules shall be placed on asphalt concrete, epoxy mortar or concrete surface. Modules to be placed on surfacing with greater than 5% downward slope shall be seated as shown.
- 5. Mass of sand and outline of each module shall be painted on the surface at each module location.
- 6. Module blocking, epoxied to the deck surface, is required for all modules placed on bridge decks. Two acceptable alternatives are shown. Other alternatives recommended by the manufacturer and approved by the Engineer will be accepted.
- 7. Place the top of the Type R marker panel 25 mm (I") below the module lid.

STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION

CRASH CUSHION. SAND FILLED (UNIDIRECTIONAL)

These "Standard Plans for Construction of Local Streets and Roads" contain units in two systems of measurement: International System of Units (SI or "metric") and United States Standard Measures shown in the parentheses (). The measurements expressed in the two systems are not necessarily equal or interchangeable. See the "Foreword" at the beginning of this publication.

NO SCALE

A81B

