

## INVERT PAVING DETAIL (FIELD VERIFY) EYE HOOK AND CHAIN LINK EXIST \_ IN CSP -GRAVEL BAGS TEMP CULVERT \* TEMP CULVERT \* TEMPORARY GRAVEL INVERT PAVING BAG HEAD WALL AT INLET Exact location & dimensions 42.42.42.42 to be determined by the Engineer TEMPORARY CULVERT INSTALLATION IN CORRUGATED METAL PIPE \* CONTRACTOR OPTION LOCATION AND SIZE

## CONSTRUCTION NOTES:

- 1. Welded wire fabric (WWF) shall be tied to studs or tack welded to culvert
- 2. The studs shall be placed 3 inches on center transversly (circumferentially)
- 3. The concrete shall be rounded with 3 inch radius on a 1:1 bevel at the inlet & outlet

COUNTY

PLANS APPROVAL DATE

REGISTERED CIVIL ENGINEER DATE

The State of California or its officers or agents shall not be responsible for the accuracy or

mpleteness of electronic copies of this plan sheet

CIVIL

TEMPORARY DEWATERING DETAIL

FIELD

X STANDARD DRAWING STATE OF BRIDGE NO. CORRUGATED METAL CULVERT DIVISION OF X **CALIFORNIA** FILE xs17-060-2 **ENGINEERING SERVICES DETAILS FOR INVERT REPAIR** DEPARTMENT OF TRANSPORTATION PPROVAL DATE July 2011 DS OSD 2147A (ENGLISH STANDARD DRAWING "XS" BORDER REV. (02-02-11) DISREGARD PRINTS BEARING EARLIER REVISION DATES ORIGINAL SCALE IN INCHES FOR REDUCED PLANS PROJECT NUMBER & PHASE: X CONTRACT NO.: X

FILE => \$REQUEST