DIST.	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS

REGISTERED ENGINEER - CIVIL

PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER No. Exp. CIVIL STATE OF CALIFORNIA

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

TABLE OF PILE SPACING: CLASS 45 - CONCRETE PILES

DESIGN H	6'	8'	10'	12'	14'	16'	18'	20'	22'	24'	26'	28'	30'	32'
W	6'-9"	7'-0"	7'-6"	8'-3"	9'-3"	10'-3"	11'-0"	12'-0"	13'-0"	14'-3"	16'-3"	16'-9"	18'-0"	20'-6"
C	2'-9"	2'-9"	3'-0"	3'-3"	3'-6"	4'-0"	4'-3"	4'-9"	5'-0"	5'-6"	6'-3"	6'-9"	7'-3"	7'-9"
B	4'-0"	4'-3"	4'-6"	5'-0"	5'-9"	6'-3"	6'-9"	7'-3"	8'-0"	8'-9"	10'-0"	10'-0"	10'-9"	12'-9"
F	1'-6"	1'-6"	1'-6"	1'-9"	1'-9"	2'-0"	2'-6"	2'-9"	3'-0"	3'-0"	3'-3"	3'-6"	3'-9"	4'-0"
M	1'-3"	1'-3"	1'-6"	1'-9"	2'-0"	2'-6"	2'-9"	3'-3"	3'-6"	4'-0"	4'-9"	5'-3"	5'-9"	6'-3"
N	2'-6"	2'-9"	3'-0"	3'-6"	4'-3"	4'-9"	5'-3"	5'-9"	6'-6"	7'-3"	8'-6"	8'-6"	9'-3"	11'-3"
ROW 1	16'-0"	14'-0"	12'-0"	10'-0"	8'-0"	6'-6"	5'-6"	4'-6"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"	4'-0"
ROW 2	24'-0"	21'-0"	18'-0"	15'-0"	14'-0"	13'-0"	11'-0"	9'-0"	8'-0"	12'-0"	10'-0"	6'-0"	4'-0"	4'-0"
ROW 3										8'-0"	5'-0"	4'-0"	4'-0"	6'-0"
ROW 4														6'-0"
CONFIGURATION	I	I	I	I	I	I	I	I	I	II	II	II	II	III

TABLE 1: TABLE OF REINFORCING STEEL DIMENSIONS AND DATA

	STEM WITH HAUNCH													
DESIGN H	6'	8'	10'	12'	14'	16'	18'	20'	22'	24'	26'	28'	30'	32'
STEM BATTER	0	1/2 :12	1/2 :12	1/2 :12	1/2 :12	1/2 :12	1/2 :12	1/2 :12	1/2 :12	5/8 :12	3/4 :12	7/8 :12	1 :12	1 :12
STEM THICKNESS @ TOP	1'-6"	1'-6"	1'-6"	1'-6"	1'-6"	1'-6"	1'-6"	1'-6"	1'-6"	1'-6"	1'-6"	1'-6"	1'-6"	1'-6"
STEM THICKNESS @ HAUNCH	1'-0"	1'-0"	1'-0"	1'-0"	1'-0"	1'-0"	1'-0"	1'-0"	1'-0"	1'-0"	1'-0"	1'-0"	1'-0"	1'-0"
(a) BARS				*6 @ 18**	*7 @ 18**	*8 @ 18**	*9 @ 18**	*10 @ 18**	*8 @ 9*	*8 @ 9*	*7 @ 6*	*10 @ 12**	*9 @ 9*	*11 @ 12**
X				CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT
Y				8'-0"	6'-6"	7'-6"	8'-6"	9'-6"	9'-6"	11'-0"	11'-6"	13'-0"	14'-0"	15'-6"
(b) BARS	*5 @ 12	*5 @ 12	*5 @ 9	*6 @ 18**	*7 @ 18**	*8 @ 18**	*9 @ 18**	*10 @ 18**	*8 @ 9*	*8 @ 9*	*7 @ 6*	*10 @ 12**	*9 @ 9*	*11 @ 12**
X	CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT
Y	CONT	CONT	CONT	CONT	10'-6"	13'-0"	15'-0"	17'-6"	19'-6"	21'-0"	18'-6"	19'-0"	25'-6"	23'-6"
(c) BARS					*6 @ 18	*6 @ 18	*6 @ 18	*6 @ 18	*6 @ 18	*6 @ 18	*6 @ 12	*7 @ 12	*7 @ 18	*7 @ 12
(d) BARS	*5 @ 12	*5 @ 12	*5 @ 12	*5 @ 12	*5 @ 12	*5 @ 12	*5 @ 9	*5 @ 9	*6 @ 9	*5 @ 6	*7 @ 9	*7 @ 9	*6 @ 6	*7 @ 6
TOTAL (e) BARS	6 *5	6 *5	6 *5	6 *5	8 *5	8 *5	10 *5	10 *5	10 *5	10 *5	12 *5	12 *5	12 *5	14 *5
TOTAL (f) BARS	6 *5	6 *5	6 *5	6 *5	6 *5	8 *5	8 *5	8 *5	8 *5	10 *5	10 *5	10 *5	12 *5	12 *5

TABLE 2: TABLE OF REINFORCING STEEL DIMENSIONS AND DATA

	STEM WITH HAUNCH							STEM WITHOUT HAUNCH						
DESIGN H	6'	8'	10'	12'	14'	16'	18'	20'	22'	24'	26'	28'	30'	32'
BATTER	0	0	0	0	0	0	0	0	0	0	1/4 :12	1/2 :12	1/2 :12	1/2 :12
STEM THICKNESS @ TOP	1'-6"	1'-6"	1'-6"	1'-6"	1'-6"	1'-6"	1'-6"	1'-6"	2'-0"	2'-0"	2'-0"	2'-0"	2'-0"	2'-0"
STEM THICKNESS @ HAUNCH	1'-0"	1'-0"	1'-0"	1'-0"	1'-0"	1'-3"	1'-3"							
(a) BARS				*6 @ 12**	*5 @ 6*	*9 @ 18**	*9 @ 12**	*9 @ 12**	*9 @ 12**	*7 @ 6*	*7 @ 6*	*7 @ 6*	*9 @ 9*	*11 @ 12**
X				CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT
Y				5'-6"	5'-6"	8'-6"	8'-6"	8'-6"	8'-6"	9'-6"	11'-0"	12'-6"	13'-6"	14'-6"
(b) BARS	*5 @ 12	*5 @ 9	*6 @ 9	*6 @ 12**	*5 @ 6*	*9 @ 18**	*9 @ 12**	*9 @ 12**	*9 @ 12**	*7 @ 6*	*7 @ 6*	*7 @ 6*	*9 @ 9*	*11 @ 12**
X	CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT	CONT
Y	CONT	CONT	CONT	CONT	CONT	11'-6"	11'-6"	12'-0"	12'-0"	17'-6"	20'-0"	21'-6"	24'-0"	24'-0"
(c) BARS						*7 @ 18	*7 @ 12	*7 @ 12	*7 @ 12	*6 @ 12	*6 @ 12	*6 @ 12	*7 @ 18	*7 @ 12
(d) BARS	*5 @ 12	*5 @ 12	*5 @ 12	*5 @ 12	*5 @ 12	*5 @ 12	*5 @ 9	*5 @ 9	*6 @ 9	*5 @ 6	*7 @ 9	*7 @ 9	*6 @ 6	*7 @ 6
TOTAL (e) BARS	6 *5	6 *5	6 *5	6 *5	8 *5	8 *5	10 *5	10 *5	10 *5	10 *5	12 *5	12 *5	12 *5	14 *5
TOTAL (f) BARS	6 *5	6 *5	6 *5	6 *5	6 *5	8 *5	8 *5	8 *5	8 *5	10 *5	10 *5	10 *5	12 *5	12 *5

CONT = CONTINUOUS
* = (a) AND (b) ARE BUNDLED TOGETHER.
** = ALTERNATE (a) AND (b) BARS AS SHOWN IN DETAIL A.

DESIGN DATA

DESIGN: LOAD FACTOR DESIGN (LFD)

CONCRETE: REINFORCED CONCRETE, f'c = 3600 psi
fy = 60000 psi

LOADING CASE:

LEVEL GROUND WITH 240 psf LIVE LOAD SURCHARGE AND 16' SOUNDWALL.

SEISMIC LOAD = 0.3 DEAD LOAD
WIND LOAD = 30 psf
DEAD LOAD OF SOUNDWALL = 1414 lb/lf
DEAD LOAD OF BARRIER = 372 lb/lf

SEISMIC LOAD: SOIL

Kh = 0.3g
Kv = 0.0
Kae : MONONOBE-OKABE METHOD

SOIL: Ø = 34° γ = 120 pcf

EQUIVALENT FLUID PRESSURE:
= 36 pcf FOR DETERMINATION OF TOE PRESSURE
= 27 pcf FOR DETERMINATION OF HEEL PRESSURE

LOAD COMBINATIONS:

GROUP A : βD + 1.7 E + 1.7 SC
GROUP B : βD + 1.7 E + 1.3 W
GROUP C :
STEM : 1.0 D + 1.0 E + 1.0 EQD + 1.0 EQE
FOOTING : D + PYM

WHERE : β = 1.0 OR 1.3 WHICHEVER CONTROLS DESIGN
D = DEAD LOAD
E = LATERAL EARTH PRESSURE
SC = LIVE LOAD SURCHARGE
W = WIND LOAD
EQD = SEISMIC DEAD LOAD
EQE = SEISMIC LATERAL EARTH PRESSURE
PYM = PROBABLE YIELD MOMENT (1.3 X NOMINAL YIELD MOMENT OF STEM)

GENERAL NOTES

1. CLASS 45-CONCRETE PILES WERE USED FOR THE DESIGN.
2. PILE BATTER SHOWN ARE 1:3.
3. MINIMUM DISTANCE BETWEEN CENTER PILE AND EDGE OF FOOTING IS 1'-6".
4. REDUCTION FACTORS:
   GROUPS A & B : Ø = 0.75
   GROUP C : Ø = 1.0
5. LATERAL RESISTANCE OF EACH PILE:
   GROUPS A & B : = 30 kip
   GROUP C : = 40 kip
6. MAXIMUM SPACING BETWEEN PILES IS SHOWN IN THE TABLE. REDUCE TO SUIT THE LENGTH OF FOOTING.
7. MINIMUM DISTANCE BETWEEN ANY TWO PILES IS 3'-0".
8. LIMIT OF NO SPLICING FOR REBARS = 3 TIMES OF THE BOTTOM THICKNESS OF THE STEM.

STANDARD DRAWING

RELEASE DATE 12/1/05	DESIGN	BY MADON SAH	CHECKED OVERCOMER HOR	RELEASED BY
	DETAILS	BY R YEE	CHECKED J.C. MOESE	
FILE NO. xs14-320-1e	SUBMITTED	BY OVERCOMER HOR	DRAWING DATE 12/1/05	OFFICE CHIEF

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

BRIDGE NO.
POST MILE

RETAINING WALL TYPE 1SWBP - DETAIL NO. 1

DS OSD 2147A (REV. X/XX/XX)

ORIGINAL SCALE IN INCHES FOR REDUCED PLANS 0 1 2 3

CU
EA

DISREGARD PRINTS BEARING EARLIER REVISION DATES

REVISION DATES (PRELIMINARY STAGE ONLY) SHEET OF

USERNAME => rwu

xs14-320-1e.dgn

DATE PLOTTED => 24-MAR-2006 TIME PLOTTED => 13:25