

**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that Caltrans does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders and non-bidder packages, write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone and fax number, P.O. Box and street address so that you can receive addenda.

Note: Addenda information is NOT included with the electronic documents available via electronic file transfer. Only bidder or non-bidder package holders listed with the Caltrans Plans and Bid Documents section as described above will receive addenda information.



STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS
AND
SPECIAL PROVISIONS
FOR BUILDING CONSTRUCTION
IN

**SOLANO COUNTY IN BENICIA AT THE TRI BRIDGE
MAINTENANCE STATION ON INDUSTRIAL WAY**

DISTRICT 04, ROUTE 680

For use in Connection with Standard Specifications **DATED**
JULY, 1995, Standard Plans **DATED** **JULY, 1997**, and Labor
Surcharge And Equipment Rental Rates.

CONTRACT NO. 04-006074

04-Sol-680-2.4

Bids Open: July 27, 1999

Dated: June 28, 1999

OSD

TABLE OF CONTENTS

NOTICE TO CONTRACTORS.....	1
COPY OF ENGINEER'S ESTIMATE.....	3
SPECIAL PROVISIONS.....	4
SECTION 1. SPECIFICATIONS AND PLANS.....	4
SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS.....	4
2-1.01 GENERAL.....	4
2-1.02 DISABLED VETERAN BUSINESS ENTERPRISE (DVBE).....	4
2-1.03 DVBE GOAL FOR THIS PROJECT.....	5
2-1.04 SMALL BUSINESS PREFERENCE.....	5
2-1.05 CALIFORNIA COMPANY PREFERENCE.....	6
SECTION 3. SUBMISSION OF DVBE INFORMATION AND AWARD AND EXECUTION OF CONTRACT..	6
3-1.01 GENERAL.....	6
3-1.01A DVBE INFORMATION.....	6
3-1.01B AWARD OF CONTRACT.....	7
SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES.....	8
SECTION 5. GENERAL.....	8
SECTION 5-1. MISCELLANEOUS.....	8
5-1.00 PLANS AND WORKING DRAWINGS.....	8
5-1.003 TRANSPORTATION LABORATORY.....	8
5-1.005 CONTRACT BONDS.....	9
5-1.01 LABOR NONDISCRIMINATION.....	9
5-1.02 LABOR CODE REQUIREMENTS.....	9
5-1.023 INDEMNIFICATION AND INSURANCE.....	11
5-1.025 ARBITRATION.....	14
5-1.03 PAYMENT OF WITHHELD FUNDS.....	14
5-1.04 INTEREST ON PAYMENTS.....	14
5-1.05 PUBLIC SAFETY.....	15
5-1.06 SURFACE MINING AND RECLAMATION ACT.....	16
5-1.07 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES.....	16
5-1.08 YEAR 2000 COMPLIANCE.....	16
5-1.09 DVBE RECORDS.....	17
5-1.095 PERFORMANCE OF DVBE SUBCONTRACTORS AND SUPPLIERS.....	17
5-1.097 SUBCONTRACTING.....	17
5-1.10 AREAS FOR CONTRACTOR'S USE.....	18
5-1.11 FORCE ACCOUNT PAYMENT.....	18
5-1.12 OVERHEAD.....	18
5-1.13 PAYMENTS.....	18
5-1.14 SOUND CONTROL REQUIREMENTS.....	18
5-1.15 HIGHWAY CONSTRUCTION EQUIPMENT.....	19
SECTION 6. (BLANK).....	19
SECTION 7. (BLANK).....	19
SECTION 8. MATERIALS.....	19
SECTION 8-1. MISCELLANEOUS.....	19
8-1.01 STATE-FURNISHED MATERIALS.....	19
SECTION 8-2. (BLANK).....	19
SECTION 8-3. WELDING.....	19
8-3.01 WELDING ELECTRODES.....	19
SECTION 9. (BLANK).....	19
SECTION 10. CONSTRUCTION DETAILS.....	19
SECTION 10-1. GENERAL.....	19
10-1.00 ESCROW OF BID DOCUMENTATION.....	19

10-1.01	RESTRICTED AREA.....	21
10-1.02	WATER POLLUTION CONTROL.....	21
10-1.03	TEMPORARY SILT FENCE.....	25
10-1.04	DUST CONTROL.....	25
10-1.05	MOBILIZATION.....	25
10-1.06	EARTHWORK.....	25
10-1.07	ASPHALT CONCRETE.....	26
SECTION 11.	(BLANK).....	26
SECTION 12.	BUILDING WORK.....	26
SECTION 12-1.	GENERAL REQUIREMENTS.....	26
12-1.01	SCOPE.....	26
12-1.02	ORDER OF WORK.....	26
12-1.03	ABBREVIATIONS.....	26
12-1.04	GUARANTEE.....	27
12-1.05	AREAS FOR CONTRACTOR'S USE.....	27
12-1.06	COOPERATION.....	27
12-1.07	SUBMITTALS.....	27
12-1.08	PROGRESS SCHEDULE.....	28
12-1.09	SCHEDULE OF VALUES.....	28
12-1.10	INSPECTION.....	28
12-1.11	OBSTRUCTIONS.....	28
12-1.12	PRESERVATION OF PROPERTY.....	29
12-1.13	UTILITY CONNECTION.....	29
12-1.14	TEMPORARY UTILITIES.....	29
12-1.15	SANITARY FACILITIES.....	30
12-1.16	MEASUREMENT AND PAYMENT.....	30
12-1.17	FIELD ENGINEERING.....	30
12-1.18	SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS.....	30
SECTION 12-2.	SITWORK.....	40
12-2.01	RELOCATING MATERIALS AND EQUIPMENT.....	40
12-2.02	LEAD ABATEMENT.--.....	41
12-2.03	EARTHWORK FOR BUILDING WORK.....	43
12-2.04	AGGREGATE BASE.....	45
12-2.05	FREE DRAINING GRANULAR MATERIAL.....	46
12-2.06	EARTH ANCHOR TIE-DOWNS.....	46
12-2.07	PAINTED PAVEMENT MARKINGS.....	47
12-2.08	PARKING BUMPERS.....	48
12-2.09	DISABLED PARKING AND AUTHORIZATION SIGNS.....	49
12-2.10	DECONTAMINATION TRAILER INSTALLATION.....	49
SECTION 12-3.	CONCRETE AND REINFORCEMENT.....	50
12-3.01	CAST-IN-PLACE CONCRETE.....	50
SECTION 12-4.	(BLANK).....	54
SECTION 12-5.	METALS.....	54
12-5.01	WELDED WIRE MESH.....	54
12-5.02	ALUMINUM HANDRAIL AND GUARDRAIL.....	54
SECTION 12-6.	WOOD AND PLASTICS.....	56
12-6.01	ROUGH CARPENTRY.....	56
SECTIONS 12-7 AND 12-8.	(BLANK).....	58
SECTION 12-9.	FINISHES.....	58
12-9.01	PAINTING.....	58
SECTIONS 12-10 THROUGH 12-12.	(BLANK).....	60
SECTION 12-13.	SPECIAL CONSTRUCTION.....	60
12-13.01	CANOPY COVER.....	60
SECTION 12-14.	(BLANK).....	61
SECTION 12-15.	MECHANICAL.....	61
12-15.01	MECHANICAL WORK.....	61

12-15.02	PIPE, FITTINGS AND VALVES.....	62
SECTION 12-16.	ELECTRICAL.....	66
12-16.01	ELECTRICAL WORK.....	66
12-16.02	BASIC MATERIALS AND METHODS.....	67
12-16.03	ELECTRICAL EQUIPMENT.....	72

STANDARD PLANS LIST

The Standard Plan sheets applicable to this contract include, but are not limited to those indicated below. The Revised Standard Plans (RSP) and New Standard Plans (NSP) which apply to this contract are included as individual sheets of the project plans.

A10A	Abbreviations
A10B	Symbols
A62A	Excavation and Backfill - Miscellaneous Details
A87	Curbs, Dikes and Driveways

State project with DVBE goals, 10-22-98

DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS

CONTRACT NO. 04-006074

04-Sol-680-2.4

Sealed proposals for the work shown on the plans entitled:

**STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROJECT
PLANS FOR BUILDING CONSTRUCTION IN SOLANO COUNTY IN BENICIA AT
THE TRI BRIDGE MAINTENANCE STATION ON INDUSTRIAL WAY**

will be received at the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, CA 95814, until 2 o'clock p.m. on July 27, 1999, at which time they will be publicly opened and read in Room 0100 at the same address.

Proposal forms for this work are included in a separate book entitled:

**STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROPOSAL AND
CONTRACT FOR BUILDING CONSTRUCTION IN SOLANO COUNTY IN BENICIA
AT THE TRI BRIDGE MAINTENANCE STATION ON INDUSTRIAL WAY**

General work description: Maintenance station construction.

This project has a goal of 3 percent disabled veteran business enterprise (DVBE) participation.

No pre-bid meeting is scheduled for this project.

Contract No. 04-006074

Bids are required for the entire work described herein.

At the time this contract is awarded, the Contractor shall possess either a Class A or Class B license.

The Contractor must also be properly licensed at the time the bid is submitted, except that on a joint venture bid a joint venture license may be obtained by a combination of licenses after bid opening but before award in accordance with Business and Professions Code, Section 7029.1.

This contract is subject to state contract nondiscrimination and compliance requirements pursuant to Government Code, Section 12990.

Preference will be granted to bidders properly certified as a "Small Business" as determined by the Department of General Services, Office of Small Business Certification and Resources at the time of bid opening in accordance with the provisions in Section 2-1.04, "Small Business Preference," of the special provisions, and Section 1896 et seq, Title 2, California Code of Regulations. A form for requesting a "Small Business" preference is included with the bid documents. Applications for status as a "Small Business" must be submitted to the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814, Telephone No. (916) 322-5060.

A reciprocal preference will be granted to "California company" bidders in accordance with Section 6107 of the Public Contract Code. (See Sections 2 and 3 of the special provisions.) A form for indicating whether bidders are or are not a "California company" is included in the bid documents and is to be filled in and signed by all bidders.

Project plans, special provisions, and proposal forms for bidding this project can only be obtained at the Department of Transportation, Plans and Bid Documents, Room 0200, Transportation Building, 1120 N Street, MS #26, Sacramento, California 95814, FAX No. (916) 654-7028, Telephone No. (916) 654-4490. Use FAX orders to expedite orders for project plans, special provisions and proposal forms. FAX orders must include credit card charge number, card expiration date and authorizing signature. Project plans, special provisions, and proposal forms may be seen at the above Department of Transportation office and at the offices of the District Directors of Transportation at Irvine, Oakland, and the district in which the work is situated. Standard Specifications and Standard Plans are available through the State of California, Department of Transportation, Publications Unit, 1900 Royal Oaks Drive, Sacramento, CA 95815, Telephone No. (916) 445-3520.

Cross sections for this project are not available.

The successful bidder shall furnish a payment bond and a performance bond.

Pursuant to Section 1773 of the Labor Code, the general prevailing wage rates in the county, or counties, in which the work is to be done have been determined by the Director of the California Department of Industrial Relations. These wages are set forth in the General Prevailing Wage Rates for this project, available at the Labor Compliance Office at the offices of the District Director of Transportation for the district in which the work is situated, and available from the California Department of Industrial Relations' Internet Web Site at: <http://www.dir.ca.gov>. Future effective general prevailing wage rates which have been predetermined and are on file with the Department of Industrial Relations are referenced but not printed in the general prevailing wage rates.

DEPARTMENT OF TRANSPORTATION

Deputy Director Transportation Engineering

Dated June 28, 1999

RS

COPY OF ENGINEER'S ESTIMATE
 (NOT TO BE USED FOR BIDDING PURPOSES)
04-006074

Item	Item Code	Item	Unit of Measure	Estimated Quantity
1	074029	TEMPORARY SILT FENCE	M	160
2	190101	ROADWAY EXCAVATION	M3	550
3	390102	ASPHALT CONCRETE (TYPE A)	TONN	550

Contract No. <Dist>-<Contract_No>

4	394040	PLACE ASPHALT CONCRETE DIKE (TYPE A)	M	95
5	994650	BUILDING WORK	LS	LUMP SUM
6	999990	MOBILIZATION	LS	LUMP SUM

DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISIONS

Annexed to Contract No. 04-006074

SECTION 1. SPECIFICATIONS AND PLANS

The work embraced herein shall conform to the provisions in the Standard Specifications dated July, 1995, and the Standard Plans dated July, 1997, of the Department of Transportation insofar as the same may apply and these special provisions.

Amendments to the Standard Specifications set forth in these special provisions shall be considered as part of the Standard Specifications for the purposes set forth in Section 5-1.04, "Coordination and Interpretation of Plans, Standard Specifications and Special Provisions," of the Standard Specifications. Whenever either the term "Standard Specifications is amended" or the term "Standard Specifications are amended" is used in the special provisions, the indented text following said term shall be considered an amendment to the Standard Specifications. In case of conflict between such amendments and the Standard Specifications, the amendments shall take precedence over and be used in lieu of the conflicting portions.

In case of conflict between the Standard Specifications and these special provisions, the special provisions shall take precedence over and be used in lieu of the conflicting portions.

SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS

2-1.01 GENERAL

The bidder's attention is directed to the provisions in Section 2, "Proposal Requirements and Conditions," of the Standard Specifications and these special provisions for the requirements and conditions which the bidder must observe in the preparation of the proposal form and the submission of the bid.

In addition to the subcontractors required to be listed in accordance with Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications, each proposal shall have listed therein the name and address of each DVBE subcontractor to be used for credit in meeting the goal, and to whom the bidder proposes to directly subcontract portions of the work. The list of subcontractors shall also set forth the portion of work that will be done by each subcontractor listed. A sheet for listing the subcontractors is included in the Proposal.

The form of Bidder's Bond mentioned in the last paragraph in Section 2-1.07, "Proposal Guaranty," of the Standard Specifications will be found following the signature page of the Proposal.

In accordance with Public Contract Code Section 7106, a Noncollusion Affidavit is included in the Proposal. Signing the Proposal shall also constitute signature of the Noncollusion Affidavit.

2-1.02 DISABLED VETERAN BUSINESS ENTERPRISE (DVBE)

Section 10115 of the Public Contract Code requires the Department to implement provisions to establish a goal for Disabled Veterans Business Enterprise (DVBE) in contracts.

It is the policy of the Department that Disabled Veteran Business Enterprise (DVBE) shall have the maximum opportunity to participate in the performance of contracts financed solely with state funds. The Contractor shall ensure that DVBEs have the maximum opportunity to participate in the performance of this contract and shall take all necessary and reasonable steps for this assurance. The Contractor shall not discriminate on the basis of race, color, national origin, or sex in the award and performance of subcontracts. Failure to carry out the requirements of this paragraph shall constitute a breach of contract and may result in termination of this contract or other remedy the Department may deem appropriate.

Bidder's attention is directed to the following:

(a) "Disabled Veteran Business Enterprise" (DVBE) means a business concern certified as a DVBE by the Office of Small Business Certification and Resources, Department of General Services.

(b) A DVBE may participate as a prime contractor, subcontractor, joint venture partner with a prime or subcontractor, or vendor of material or supplies;

(c) Credit for DVBE prime contractors will be 100 percent.

(d) A DVBE joint venture partner must be responsible for specific contract items of work, or portions thereof. Responsibility means actually performing, managing and supervising the work with its own forces. The DVBE joint venture partner must share in the ownership, control, management responsibilities, risks and profits of the joint venture. The DVBE joint venturer must submit the joint venture agreement with the Caltrans Bidder DVBE Information form required in Section 3-1.01A, "DVBE Information," elsewhere in these special provisions;

(e) A DVBE must perform a commercially useful function, i.e., must be responsible for the execution of a distinct element of the work and must carry out its responsibility by actually performing, managing and supervising the work;

(f) Credit for DVBE vendors of materials or supplies is limited to 60 percent of the amount to be paid to the vendor for the material unless the vendor manufactures or substantially alters the goods;

(g) Credit for trucking by DVBEs will be as follows:

(1) One hundred percent of the amount to be paid when a DVBE trucker will perform the trucking with his/her own trucks, tractors and employees;

(2) Twenty percent of the amount to be paid to DVBE trucking brokers who do not have a "certified roster";

(3) One hundred percent of the amount to be paid to DVBE trucking brokers who have:

a. signed agreements that all trucking will be performed by DVBE truckers if credit is toward the DVBE goal;

b. a "certified roster" showing that all trucks are owned by DVBEs; and

c. a signed statement on the "certified roster" that indicates that 100 percent of revenue paid by the broker will be paid to the DVBEs listed on the "certified roster".

(4) Twenty percent of the amount to be paid to trucking brokers who are not a DVBE but who have:

a. signed agreements with DVBE truckers assuring that at least 20 percent of the trucking will be performed by DVBE truckers if credit is toward the DVBE goal;

b. a "certified roster" showing that at least 20 percent of the number of trucks are owned by DVBE truckers; and

c. a signed statement on the "certified roster" that indicates that at least 20 percent of the revenue paid by the broker will be paid to the DVBEs listed on the "certified roster".

The "certified roster" referred to herein shall conform to the requirements in Section 3-1.01A, "DVBE Information," elsewhere in these special provisions;

(h) DVBEs and DVBE joint venture partners must be certified DVBEs as determined by the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814, on the date bids for the project are opened before credit may be allowed toward the DVBE goal.

It is the Contractor's responsibility to verify that DVBEs are certified;

(i) Noncompliance by the Contractor with these requirements constitutes a breach of this contract and may result in termination of the contract or other appropriate remedy for a breach of this contract.

2-1.03 DVBE GOAL FOR THIS PROJECT

The Department has established the following goal for Disabled Veteran Business Enterprise (DVBE) participation for this project:

Disabled Veteran Business Enterprise (DVBE), 3 percent.

It is the bidder's responsibility to make a sufficient portion of the work available to subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DVBE subcontractors and suppliers, so as to assure meeting the goal for DVBE participation.

The Office of Small Business Certification and Resources, Department of General Services, may be contacted at (916) 322-5060 or visit their internet web site at <http://www.osmb.dgs.ca.gov/> for program information and certification status. The Department's Business Enterprise Program may also be contacted at (916) 227-9599 or the internet web site at <http://www.dot.ca.gov/hq/bep/>.

2-1.04 SMALL BUSINESS PREFERENCE

Attention is directed to "Submission of DVBE Information and Award and Execution of Contract" elsewhere in these special provisions.

Attention is also directed to the Small Business Procurement and Contract Act, Government Code Section 14835, et seq and Title 2, California Code of Regulations, Section 1896, et seq.

Bidders who wish to be classified as a Small Business under the provisions of those laws and regulations, shall be certified as Small Business by the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814.

To request Small Business Preference, bidders shall fill out and sign the Request for Small Business Preference form in the Proposal and shall attach a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form. The bidder's signature on the Request for Small Business Preference certifies, under penalty of perjury, that the bidder is certified as Small Business at the time of bid opening and further

Contract No. <Dist>-<Contract_No>

certifies, under penalty of perjury, that under the following conditions, at least 50 percent of the subcontractors to be utilized on the project are either certified Small Business or have applied for Small Business certification by bid opening date and are subsequently granted Small Business certification.

The conditions requiring the aforementioned 50 percent level of subcontracting by Small Business subcontractors apply if:

1. The lowest responsible bid for the project exceeds \$100 000; and
2. The project work to be performed requires a Class A or a Class B contractor's license; and
3. Two or more subcontractors will be used.

If the above conditions apply and Small Business Preference is granted in the award of the contract, the 50 percent Small Business subcontractor utilization level shall be maintained throughout the life of the contract.

2-1.05 CALIFORNIA COMPANY PREFERENCE

Attention is directed to "Award and Execution of Contract" of these special provisions.

In accordance with the requirements of Section 6107 of the Public Contract Code, a "California company" will be granted a reciprocal preference for bid comparison purposes as against a nonresident contractor from any state that gives or requires a preference to be given contractors from that state on its public entity construction contracts.

A "California company" means a sole proprietorship, partnership, joint venture, corporation, or other business entity that was a licensed California contractor on the date when bids for the public contract were opened and meets one of the following:

- (1) Has its principal place of business in California.
- (2) Has its principal place of business in a state in which there is no local contractor preference on construction contracts.
- (3) Has its principal place of business in a state in which there is a local contractor construction preference and the contractor has paid not less than \$5000 in sales or use taxes to California for construction related activity for each of the five years immediately preceding the submission of the bid.

To carry out the "California company" reciprocal preference requirements of Section 6107 of the Public Contract Code, all bidders shall fill out and sign the California Company Preference form in the Proposal. The bidder's signature on the California Company Preference form certifies, under penalty of perjury, that the bidder is or is not a "California company" and if not, the amount of the preference applied by the state of the nonresident Contractor.

A nonresident Contractor shall disclose any and all bid preferences provided to the nonresident Contractor by the state or country in which the nonresident Contractor has its principal place of business.

Proposals without the California Company Preference form filled out and signed may be rejected.

SECTION 3. SUBMISSION OF DVBE INFORMATION AND AWARD AND EXECUTION OF CONTRACT

3-1.01 GENERAL

The bidder's attention is directed to the provisions in Section 3, "Award and Execution of Contract," of the Standard Specifications and these special

provisions for the requirements and conditions concerning submittal of DVBE information and award and execution of contract.

The required DVBE information shall be submitted on the "CALTRANS BIDDER - DVBE INFORMATION" form included in the Proposal. If this information is not submitted with the bid, the DVBE information forms shall be removed from the documents prior to submitting the bid.

It is the bidder's responsibility to meet the goal for DVBE participation or to provide information to establish that, prior to bidding, the bidder made a good faith effort to do so.

3-1.01A DVBE INFORMATION

If the DVBE information is not submitted with the bid, the apparent successful bidder (low bidder), the second low bidder and the third low bidder shall submit the DVBE information to the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, California 95814 so the information is received by the Department no later than 4:00 p.m. on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening. DVBE information sent by U.S. Postal Service certified mail with return receipt and certificate of mailing and mailed on or before the third day, not including Saturdays, Sundays and legal holidays, following bid opening will be accepted even if it is received after the fourth day following bid opening. Failure to submit the required DVBE information by the time specified will be grounds for finding the bid or proposal nonresponsive. Other bidders need not submit DVBE information unless requested to do so by the Department.

The bidder's DVBE information shall establish that the DVBE goal will be met or that a good faith effort to meet the goal has been made.

Bidders are cautioned that even though their submittal indicates they will meet the stated DVBE goal, their submittal should also include their good faith efforts information along with their DVBE goal information to protect their eligibility for award of the contract in the event the Department, in its review, finds that the goal has not been met.

The information to show that the DVBE goal will be met shall include the names of DVBEs and DVBE joint venture partners to be used, with a complete description of work or supplies to be provided by each and the dollar value of each DVBE transaction. When 100 percent of a contract item of work is not to be performed or furnished by a DVBE, a description of the exact portion of that work to be performed or furnished by that DVBE shall be included in the DVBE information, including the planned location of that work. (Note: DVBE subcontractors to whom the bidder proposes to directly subcontract portions of the work are to be named in the bid. - See Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications and Section 2-1.01, "General," of these special provisions, regarding listing of proposed subcontractors).

If credit for trucking by a DVBE trucking broker is shown on the bidder's information as 100 percent of the revenue to be paid by the broker is to be paid to DVBE truckers, a "certified roster" of the broker's trucks to be used must be included. The "certified roster" must indicate that all the trucks are owned by certified DVBEs and must show the DVBE truck numbers, owner's name, Public Utilities Commission Cal-T numbers, and the DVBE certification numbers. The roster must indicate that all revenue paid by the broker will be paid to DVBEs listed on the "certified roster".

If credit for trucking by a trucking broker who is not a DVBE is shown in the bidder's information, a "certified roster" of the broker's trucks to be used must be included. The "certified roster" must indicate that at least 20 percent of the broker's trucks are owned by certified DVBEs and must show the DVBE truck numbers, owner's name, Public Utilities Commission Cal-T numbers,

and the DVBE certification number. The roster must indicate that at least 20 percent of the revenue paid by the broker will be paid to DVBEs listed on the "certified roster".

A bidder shall be deemed to have made good faith efforts upon submittal, within time limits specified by the Department, of documentary evidence that all of the following actions were taken:

(1) Contact was made with the Office of Small Business Certification and Resources (OSBCR), Department of General Services or their web site at <http://www.osmb.dgs.ca.gov/> to identify Disabled Veteran Business Enterprises.

(2) Advertising was published in trade media and media focusing on Disabled Veteran Business Enterprises, unless time limits imposed by the Department do not permit that advertising.

(3) Invitations to bid were submitted to potential Disabled Veteran Business Enterprise contractors.

(4) Available Disabled Veteran Business Enterprises were considered.

3-1.01B AWARD OF CONTRACT

The award of contract, if it be awarded, will be to the lowest responsible bidder whose proposal complies with all the requirements prescribed and who has met the goal for DVBE participation or has demonstrated, to the satisfaction of the Department, good faith effort to do so. Meeting the goal for DVBE participation or demonstrating, to the satisfaction of the Department, good faith efforts to do so is a condition for being eligible for award of contract.

A "Vendor Data Record" form will be included in the contract documents to be executed by the successful bidder. The purpose of the form is to facilitate the collection of taxpayer identification data. The form shall be completed and returned to the Department by the successful bidder with the executed contract and contract bonds. For the purposes of the form, vendor shall be deemed to mean the successful bidder. The form is not to be completed for subcontractors or suppliers. Failure to complete and return the "Vendor Data Record" form to the Department as provided herein will result in the retention of 20 percent of payments due the contractor and penalties of up to \$20 000. This retention of payments for failure to complete the "Vendor Data Record" form is in addition to any other retention of payments due the Contractor.

Attention is also directed to "Small Business Preference" of these special provisions. Any bidder who is certified as a Small Business by the Department of General Services, Office of Small Business Certification and Resources will be allowed a preference in the award of this contract, if it be awarded, under the following conditions:

(1) The apparent low bidder is not certified as a Small Business, or has not filled out and signed the Request for Small Business Preference included with the bid documents and attached a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form; and

(2) The bidder filled out and signed the Request for Small Business Preference form included with the bid documents and attached a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form.

The small business preference will be a reduction in the bid submitted by the small business contractor, for bid comparison purposes, by an amount equal

to 5 percent of the amount bid by the apparent low bidder, the amount not to exceed \$50 000. If this reduction results in the small business contractor becoming the low bidder, then the contract will be awarded to the small business contractor on the basis of the actual bid of the small business contractor notwithstanding the reduced bid price used for bid comparison purposes.

Attention is also directed to "California Company Preference" of these special provisions.

The amount of the California company reciprocal preference shall be equal to the amount of the preference applied by the state of the nonresident contractor with the lowest responsive bid, except where the "California company" is eligible for a California Small Business Preference, in which case the preference applied shall be the greater of the two, but not both.

If the bidder submitting the lowest responsive bid is not a "California company" and with the benefit of the reciprocal preference, a "California company's" responsive bid is equal to or less than the original lowest responsive bid, the "California company" will be awarded the contract at its submitted bid price except as provided below.

Small business bidders shall have precedence over nonsmall business bidders in that the application of the "California company" preference for which nonsmall business bidders may be eligible shall not result in the denial of the award to a small business bidder.

SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES

Attention is directed to the provisions in Section 8-1.03, "Beginning of Work," in Section 8-1.06, "Time of Completion," and in Section 8-1.07, "Liquidated Damages," of the Standard Specifications and these special provisions.

The Contractor shall begin work within 15 calendar days after the contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department of Transportation.

This work shall be diligently prosecuted to completion before the expiration of

70 WORKING DAYS

beginning on the fifteenth calendar day after approval of the contract.

The Contractor shall pay to the State of California the sum of \$2500 per day, for each and every calendar day's delay in finishing the work in excess of the number of working days prescribed above.

SECTION 5. GENERAL

SECTION 5-1. MISCELLANEOUS

5-1.00 PLANS AND WORKING DRAWINGS

When the specifications require working drawings to be submitted to the Office of Structure Design, the drawings shall be submitted to: Office of Structure Design, Documents Unit, P.O. Box 942874, Mail Station 9, Sacramento, CA 94274-0001 (1801 30th Street, Sacramento, CA 95816), Telephone (916) 227-8252.

5-1.003 TRANSPORTATION LABORATORY

Section 1-1.25, "Laboratory," of the Standard Specifications is amended to read:

1-1.25 Laboratory.—The Office of Materials and Foundations of the Department of Transportation, or established laboratories of the various Districts of the Department, or other laboratories authorized by the Department to test materials and work involved in the contract. When a reference is made in the specifications to the "Transportation Laboratory," the reference shall mean the Office of Materials and Foundations, located at 5900 Folsom Boulevard, Sacramento, CA 95819.

The telephone number of the "Transportation Laboratory" is (916) 227-7000.

5-1.005 CONTRACT BONDS

Attention is directed to Section 3-1.02, "Contract Bonds," of the Standard Specifications and these special provisions.

The payment bond shall be in a sum not less than the following:

1. One hundred percent of the total amount payable by the terms of the contract when the total amount payable does not equal or exceed five million dollars (\$5 000 000).
2. Fifty percent of the total amount payable by the terms of the contract when the total amount payable is not less than five million dollars (\$5 000 000) and does not exceed ten million dollars (\$10 000 000).
3. Twenty-five percent of the total amount payable by the terms of the contract when the total amount payable exceeds ten million dollars (\$10 000 000).

5-1.01 LABOR NONDISCRIMINATION

Attention is directed to the following Notice that is required by Chapter 5 of Division 4 of Title 2, California Code of Regulations.

**NOTICE OF REQUIREMENT FOR NONDISCRIMINATION PROGRAM
(GOV. CODE, SECTION 12990)**

Your attention is called to the "Nondiscrimination Clause", set forth in Section 7-1.01A(4), "Labor Nondiscrimination," of the Standard Specifications, which is applicable to all nonexempt state contracts and subcontracts, and to the "Standard California Nondiscrimination Construction Contract Specifications" set forth therein. The Specifications are applicable to all nonexempt state construction contracts and subcontracts of \$5000 or more.

5-1.02 LABOR CODE REQUIREMENTS

Section 7-1.01A(1), "Hours of Labor," of the Standard Specifications is amended to read:

7-1.01A(1) Hours of Labor.— Eight hours labor constitutes a legal day's work. The Contractor or any subcontractor under the Contractor shall forfeit, as a penalty to the State of California, \$25 for each worker employed in the execution of the contract by the respective Contractor or subcontractor for each calendar day during which that worker is required or permitted to work more than 8 hours in any one calendar day and 40 hours in any one calendar week in violation of the provisions of the Labor Code, and in particular, Section 1810 to Section 1815, thereof, inclusive, except that work performed

by employees of Contractors in excess of 8 hours per day, and 40 hours during any one week, shall be permitted upon compensation for all hours worked in excess of 8 hours per day at not less than one and one-half times the basic rate of pay, as provided in Section 1815 thereof.

Section 7-1.01A(2), "Prevailing Wage," of the Standard Specifications is amended to read:

7-1.01A(2) Prevailing Wage.— The Contractor and any subcontractor under the Contractor shall comply with Labor Code Sections 1774 and 1775. Pursuant to Section 1775, the Contractor and any subcontractor under the Contractor shall forfeit to the State or political subdivision on whose behalf the contract is made or awarded a penalty of not more than fifty dollars (\$50) for each calendar day, or portion thereof, for each worker paid less than the prevailing rates as determined by the Director of Industrial Relations for the work or craft in which the worker is employed for any public work done under the contract by the Contractor or by any subcontractor under the Contractor in violation of the provisions of the Labor Code and in particular, Labor Code Sections 1770 to 1780, inclusive. The amount of this forfeiture shall be determined by the Labor Commissioner and shall be based on consideration of the mistake, inadvertence, or neglect of the Contractor or subcontractor in failing to pay the correct rate of prevailing wages, or the previous record of the Contractor or subcontractor in meeting their respective prevailing wage obligations, or the willful failure by the Contractor or subcontractor to pay the correct rates of prevailing wages. A mistake, inadvertence, or neglect in failing to pay the correct rate of prevailing wages is not excusable if the Contractor or subcontractor had knowledge of the obligations under the Labor Code. In addition to the penalty and pursuant to Labor Code Section 1775, the difference between the prevailing wage rates and the amount paid to each worker for each calendar day or portion thereof for which each worker was paid less than the prevailing wage rate shall be paid to each worker by the Contractor or subcontractor. If a worker employed by a subcontractor on a public works project is not paid the general prevailing per diem wages by the subcontractor, the prime contractor of the project is not liable for the penalties described above unless the prime contractor had knowledge of that failure of the subcontractor to pay the specified prevailing rate of wages to those workers or unless the prime contractor fails to comply with all of the following requirements:

1. The contract executed between the contractor and the subcontractor for the performance of work on the public works project shall include a copy of the provisions of Sections 1771, 1775, 1776, 1777.5, 1813, and 1815 of the Labor Code.
2. The contractor shall monitor the payment of the specified general prevailing rate of per diem wages by the subcontractor to the employees, by periodic review of the certified payroll records of the subcontractor.
3. Upon becoming aware of the subcontractor's failure to pay the specified prevailing rate of wages to the subcontractor's workers, the contractor shall diligently take corrective action to halt or rectify the failure, including, but not limited to, retaining sufficient funds due the subcontractor for work performed on the public works project.
4. Prior to making final payment to the subcontractor for work performed on the public works project, the contractor shall obtain an affidavit signed under penalty of perjury from the subcontractor that the subcontractor has paid the specified general prevailing rate of per diem

wages to the subcontractor's employees on the public works project and any amounts due pursuant to Section 1813 of the Labor Code.

Pursuant to Section 1775 of the Labor Code, the Division of Labor Standards Enforcement shall notify the Contractor on a public works project within 15 days of the receipt by the Division of Labor Standards Enforcement of a complaint of the failure of a subcontractor on that public works project to pay workers the general prevailing rate of per diem wages. If the Division of Labor Standards Enforcement determines that employees of a subcontractor were not paid the general prevailing rate of per diem wages and if the Department did not retain sufficient money under the contract to pay those employees the balance of wages owed under the general prevailing rate of per diem wages, the contractor shall withhold an amount of moneys due the subcontractor sufficient to pay those employees the general prevailing rate of per diem wages if requested by the Division of Labor Standards Enforcement. The Contractor shall pay any money retained from and owed to a subcontractor upon receipt of notification by the Division of Labor Standards Enforcement that the wage complaint has been resolved. If notice of the resolution of the wage complaint has not been received by the Contractor within 180 days of the filing of a valid notice of completion or acceptance of the public works project, whichever occurs later, the Contractor shall pay all moneys retained from the subcontractor to the Department. These moneys shall be retained by the Department pending the final decision of an enforcement action.

Pursuant to the provisions of Section 1773 of the Labor Code, the Department has obtained the general prevailing rate of wages (which rate includes employer payments for health and welfare, pension, vacation, travel time, and subsistence pay as provided for in Section 1773.8 of the Labor Code, apprenticeship or other training programs authorized by Section 3093 of the Labor Code, and similar purposes) applicable to the work to be done, for straight time, overtime, Saturday, Sunday and holiday work. The holiday wage rate listed shall be applicable to all holidays recognized in the collective bargaining agreement of the particular craft, classification or type of workmen concerned. The general prevailing wage rates and any applicable changes to these wage rates are available at the Labor Compliance Office at the offices of the District Director of Transportation for the district in which the work is situated. For work situated in District 9, the wage rates are available at the Labor Compliance Office at the offices of the District Director of Transportation for District 6, located at Fresno. General prevailing wage rates are also available from the California Department of Industrial Relations' Internet Web Site at: <http://www.dir.ca.gov>.

The wage rates determined by the Director of Industrial Relations for the project refer to expiration dates. Prevailing wage determinations with a single asterisk after the expiration date are in effect on the date of advertisement for bids and are good for the life of the contract. Prevailing wage determinations with double asterisks after the expiration date indicate that the wage rate to be paid for work performed after this date has been determined. If work is to extend past this date, the new rate shall be paid and incorporated in the contract. The Contractor shall contact the Department of Industrial Relations as indicated in the wage rate determinations to obtain predetermined wage changes.

Pursuant to Section 1773.2 of the Labor Code, general prevailing wage rates shall be posted by the Contractor at a prominent place at the site of the work.

Changes in general prevailing wage determinations which conform to Labor Code Section 1773.6 and Title 8 California Code of Regulations Section 16204 shall apply to the project when issued by the Director of Industrial Relations

at least 10 days prior to the date of the Notice to Contractors for the project.

The State will not recognize any claim for additional compensation because of the payment by the Contractor of any wage rate in excess of the prevailing wage rate set forth in the contract. The possibility of wage increases is one of the elements to be considered by the Contractor in determining the bid, and will not under any circumstances be considered as the basis of a claim against the State on the contract.

7-1.01A(2)(a) Travel and Subsistence Payments.— Attention is directed to the requirements of Section 1773.8 of the Labor Code. The Contractor shall make travel and subsistence payments to each workman, needed to execute the work, in accordance with the requirements in Labor Code Section 1773.8.

The first and second paragraphs of Section 7-1.01A(3), "Payroll Records," of the Standard Specifications are amended to read:

7-1.01A(3) Payroll Records.— Attention is directed to the provisions of Labor Code Section 1776, a portion of which is quoted below. Regulations implementing Labor Code Section 1776 are located in Sections 16016 through 16019 and Sections 16207.10 through 16207.19 of Title 8, California Code of Regulations.

"1776. (a) Each contractor and subcontractor shall keep accurate payroll records, showing the name, address, social security number, work classification, straight time and overtime hours worked each day and week, and the actual per diem wages paid to each journeyman, apprentice, worker, or other employee employed by him or her in connection with the public work. Each payroll record shall contain or be verified by a written declaration that it is made under penalty of perjury, stating both of the following:

- (1) The information contained in the payroll record is true and correct.
- (2) The employer has complied with the requirements of Sections 1771, 1811, and 1815 for any work performed by his or her employees on the public works project.

"(b) The payroll records enumerated under subdivision (a) shall be certified and shall be available for inspection at all reasonable hours at the principal office of the contractor on the following basis:

(1) A certified copy of an employee's payroll record shall be made available for inspection or furnished to the employee or his or her authorized representative on request.

(2) A certified copy of all payroll records enumerated in subdivision (a) shall be made available for inspection or furnished upon request to a representative of the body awarding the contract, the Division of Labor Standards Enforcement, and the Division of Apprenticeship Standards of the Department of Industrial Relations.

(3) A certified copy of all payroll records enumerated in subdivision (a) shall be made available upon request by the public for inspection or for copies thereof. However, a request by the public shall be made through either the body awarding the contract, the Division of Apprenticeship Standards, or the Division of Labor Standards Enforcement. If the requested payroll records have not been provided pursuant to paragraph (2), the requesting party shall, prior to being provided the records, reimburse the costs of preparation by the contractor, subcontractors, and the entity

through which the request was made. The public shall not be given access to the records at the principal office of the contractor.

"(c) The certified payroll records shall be on forms provided by the Division of Labor Standards Enforcement or shall contain the same information as the forms provided by the division.

"(d) A contractor or subcontractor shall file a certified copy of the records enumerated in subdivision (a) with the entity that requested the records within 10 days after receipt of a written request.

"(e) Any copy of records made available for inspection as copies and furnished upon request to the public or any public agency by the awarding body, the Division of Apprenticeship Standards, or the Division of Labor Standards Enforcement shall be marked or obliterated in a manner so as to prevent disclosure of an individual's name, address, and social security number. The name and address of the contractor awarded the contract or the subcontractor performing the contract shall not be marked or obliterated.

"(f) The contractor shall inform the body awarding the contract of the location of the records enumerated under subdivision (a), including the street address, city and county, and shall, within five working days, provide a notice of a change of location and address.

"(g) The contractor or subcontractor shall have 10 days in which to comply subsequent to receipt of a written notice requesting the records enumerated in subdivision (a). In the event that the contractor or subcontractor fails to comply within the 10-day period, he or she shall, as a penalty to the state or political subdivision on whose behalf the contract is made or awarded, forfeit twenty-five dollars (\$25) for each calendar day, or portion thereof, for each worker, until strict compliance is effectuated. Upon the request of the Division of Apprenticeship Standards or the Division of Labor Standards Enforcement, these penalties shall be withheld from progress payments then due. A contractor is not subject to a penalty assessment pursuant to this section due to the failure of a subcontractor to comply with this section."

The penalties specified in subdivision (g) of Labor Code Section 1776 for noncompliance with the provisions of Section 1776 may be deducted from any moneys due or which may become due to the Contractor.

5-1.023 INDEMNIFICATION AND INSURANCE

Section 7-1.12, "Responsibility for Damage," of the Standard Specifications is deleted. All references to Section 7-1.12 in the Contract documents shall be deemed to mean Sections 7-1.121, "Indemnification," and 7-1.122, "Insurance," as added below.

The Standard Specifications is amended by adding the following Section 7-1.121, "Indemnification," and Section 7-1.122, "Insurance," before Section 7-1.125, "Legal Action Against the Department":

7-1.121 Indemnification.—With the exception that this section shall in no event be construed to require indemnification by the Contractor to a greater extent than permitted by law, the Contractor shall defend, indemnify and save harmless the State, including its officers, directors, agents (excluding agents who are design professionals), and employees, and each of them (Indemnitees), from any and all claims, demands, causes of action, damages, costs, expenses, actual attorneys' fees, losses or liabilities, in law or in equity, of every kind and nature whatsoever (Claims), arising out of or in connection with the Contractor's performance of this contract for:

- A. Bodily injury including, but not limited to, bodily injury, sickness or disease, emotional injury or death to persons, including, but not limited to, the public, any employees or agents of the Contractor, State, Department, or any other contractor and;
- B. Damage to property of anyone including loss of use thereof;

caused or alleged to be caused in whole or in part by any negligent or otherwise legally actionable act or omission of the Contractor or anyone directly or indirectly employed by the Contractor or anyone for whose acts the Contractor may be liable.

Except as otherwise provided by law, the indemnification provisions above shall apply regardless of the existence or degree of fault of Indemnitees. The Contractor, however, shall not be obligated to indemnify Indemnitees for Claims arising from conduct delineated in Civil Code section 2782. Further, the Contractor's indemnity obligation shall not extend to Claims to the extent they arise from any defective or substandard condition of the roadway which existed at or prior to the time the Contractor commenced work, unless this condition has been changed by the work or the scope of the work requires the Contractor to maintain existing Roadway facilities and the claim arises from the Contractor's failure to maintain. The Contractor's indemnity obligation shall extend to Claims arising after the work is completed and accepted only if these Claims are directly related to alleged acts or omissions of the Contractor which occurred during the course of the work. No inspection by the Department, its employees or agents shall be deemed a waiver by the Department of full compliance with the requirements of this section.

The Contractor's obligation to defend and indemnify shall not be excused because of the Contractor's inability to evaluate liability or because the Contractor evaluates liability and determines that the Contractor is not liable to the claimant. The Contractor will respond within 30 days to the tender of any claim for defense and indemnity by the State, unless this time has been extended by the State. If the Contractor fails to accept or reject a tender of defense and indemnity within 30 days, in addition to any other remedy authorized by law, so much of the money due the Contractor under and by virtue of the contract as shall reasonably be considered necessary by the Department, may be retained by the State until disposition has been made of the claim or suit for damages, or until the Contractor accepts or rejects the tender of defense, whichever occurs first.

With respect to third party claims against the Contractor, the Contractor waives any and all rights of any type to express or implied indemnity against the State, its directors, officers, employees, or agents (excluding agents who are design professionals).

7-1.122 Insurance.—Insurance shall conform to the following requirements:

7-1.122A Casualty Insurance.—The Contractor shall, at the Contractor's expense, procure and maintain insurance on all of its operations with companies acceptable to the Department as follows. All insurance shall be kept in full force and effect from the beginning of the work through final acceptance by the State. In addition, the Contractor shall maintain completed operations coverage with a carrier acceptable to the Department through the expiration of the patent deficiency in construction statute of repose set forth in Section 337.1 of the Code of Civil Procedure.

7-1.122A(1) Workers' Compensation and Employer's Liability Insurance.—Workers' Compensation insurance shall be provided as

Contract No. <Dist>-<Contract_No>

specified in Section 7-1.01A(6), "Workers' Compensation." Employer's Liability Insurance shall be provided in amounts not less than:

- (a) \$1 000 000 for each accident for bodily injury by accident.
- (b) \$1 000 000 policy limit for bodily injury by disease.
- (c) \$1 000 000 for each employee for bodily injury by disease.

If there is an exposure of injury to the Contractors' employees under the U.S. Longshoremen's and Harbor Workers' Compensation Act, the Jones Act or under laws, regulations or statutes applicable to maritime employees, coverage shall be included for such injuries or claims.

7-1.122A(2) Liability Insurance.—The Contractor shall carry General Liability and Umbrella or Excess Liability Insurance covering all operations by or on behalf of the Contractor providing insurance for bodily injury liability, and property damage liability for the limits of liability indicated below and including coverage for:

- (a) premises, operations and mobile equipment
- (b) products and completed operations
- (c) broad form property damage (including completed operations)
- (d) explosion, collapse and underground hazards
- (e) personal injury
- (f) contractual liability

7-1.122A(3) Liability Limits/Additional Insureds.—The limits of liability shall be at least:

- (a) \$1 000 000 for each occurrence (combined single limit for bodily injury and property damage).
- (b) \$2 000 000 aggregate for products-completed operations.
- (c) \$2 000 000 general aggregate. This general aggregate limit shall apply separately to the Contractor's work under this Agreement.
- (d) \$5 000 000 umbrella or excess liability. For projects over \$25 000 000 only, an additional \$10 000 000 umbrella or excess liability (for a total of \$15 000 000). Umbrella or excess policy shall include products liability completed operations coverage and may be subject to \$5 000 000 or \$15 000 000 aggregate limits. Further, the umbrella or excess policy shall contain a clause stating that it takes effect (drops down) in the event the primary limits are impaired or exhausted.

The State and the Department, including their officers, directors, agents (excluding agents who are design professionals), and State employees, shall be named as additional insureds under the General Liability and Umbrella Liability Policies with respect to liability arising out of or connected with work or operations performed by or on behalf of the Contractor under this contract. Coverage for such additional insureds shall not extend to liability:

- (1) arising from any defective or substandard condition of the Roadway which existed at or prior to the time the Contractor commenced work, unless such condition has been changed by the work or the scope of the work requires the Contractor to maintain existing

Roadway facilities and the claim arises from the Contractor's failure to maintain; or

- (2) for claims occurring after the work is completed and accepted unless these claims are directly related to alleged acts or omissions of the Contractor which occurred during the course of the work; or
- (3) to the extent prohibited by Section 11580.04 of the Insurance Code.

The policy shall stipulate that the insurance afforded the additional insureds shall apply as primary insurance. Any other insurance or self insurance maintained by the Department or State will be excess only and shall not be called upon to contribute with this insurance. Such additional insured coverage shall be provided by a policy provision or by an endorsement providing coverage at least as broad as Additional Insured (Form B) endorsement form CG 2010, as published by the Insurance Services Office (ISO).

7-1.122B Automobile Liability Insurance.—The Contractor shall carry automobile liability insurance, including coverage for all owned, hired and non-owned automobiles. The primary limits of liability shall be not less than \$1 000 000 combined single limit each accident for bodily injury and property damage. The umbrella or excess liability coverage required under Section 7-1.122A(3), "Liability Limits/Additional Insureds," shall also apply to automobile liability.

7-1.122C Policy Forms, Endorsements and Certificates.—The Contractor's General Liability Insurance shall be provided under Commercial General Liability policy form no. CG0001 as published by the Insurance Services Office (ISO) or under a policy form at least as broad as policy form no. CG0001.

Evidence of insurance in a form acceptable to the Department, including the required "additional insured" endorsements, shall be furnished by the Contractor to the Department at or prior to the pre-construction conference. The evidence of insurance shall provide that there will be no cancellation, lapse, or reduction of coverage without thirty (30) days' prior written notice to the Department. Certificates of Insurance, as evidence of required insurance, for the General Liability, Auto Liability and Umbrella-Excess Liability policies shall set forth deductible amounts applicable to each policy and all exclusions which are added by endorsement to each policy. The Department may expressly allow deductible clauses, which it does not consider excessive, overly broad, or harmful to the interests of the State. Standard ISO form CG 0001 or similar exclusions will be allowed provided they are not inconsistent with the requirements of this section. Allowance of any additional exclusions is at the discretion of the Department. Regardless of the allowance of exclusions or deductions by the Department, the Contractor shall be responsible for any deductible amount and shall warrant that the coverage provided to the Department is consistent with the requirements of this section.

7-1.122D Enforcement.—The Department may take any steps as are necessary to assure Contractor's compliance with its obligations. Should any insurance policy lapse or be canceled during the contract period the Contractor shall, within thirty (30) days prior to the effective expiration or cancellation date, furnish the Department with evidence of renewal or replacement of the policy. Failure to continuously maintain insurance coverage as herein provided is a material breach of contract. In the event the Contractor fails to maintain any insurance coverage required, the Department may, but is not

required to, maintain this coverage and charge the expense to the Contractor or terminate this Agreement. The required insurance shall be subject to the approval of Department, but any acceptance of insurance certificates by the Department shall in no way limit or relieve the Contractor of the Contractor's duties and responsibilities under the Contract to indemnify, defend and hold harmless the State, its officers, agents, and employees. Insurance coverage in the minimum amounts set forth herein shall not be construed to relieve the Contractor for liability in excess of such coverage, nor shall it preclude the State from taking other actions as is available to it under any other provision of the contract or law. Failure of the Department to enforce in a timely manner any of the provisions of this section shall not act as a waiver to enforcement of any of these provisions at a later date.

7-1.122E Self-Insurance.—Self-insurance programs and self-insured retentions in insurance policies are subject to separate annual review and approval by the State of evidence of the Contractor's financial capacity to respond. Additionally, self-insurance programs or retentions must provide the State with at least the same protection from liability and defense of suits as would be afforded by first-dollar insurance.

7-1.122F Miscellaneous.—Nothing contained in the Contract is intended to make the public or any member thereof a third party beneficiary of the Insurance or Indemnity provisions of these Standard Specifications, nor is any term, condition or other provision of the Contract intended to establish a standard of care owed to the public or any member thereof.

5-1.025 ARBITRATION

The last paragraph in Section 9-1.10, "Arbitration," of the Standard Specifications, is amended to read:

Arbitration shall be initiated by a Complaint in Arbitration made in compliance with the requirements of those regulations. A Complaint in Arbitration by the Contractor shall be made not later than 90 days after the date of service in person or by mail on the Contractor of the final written decision by the Department on the claim.

5-1.03 PAYMENT OF WITHHELD FUNDS

Section 9-1.065, "Payment of Withheld Funds," of the Standard Specifications, is amended by adding the following after the third paragraph:

Alternatively, and subject to the approval of the Department, the payment of retentions earned may be deposited directly with a person licensed under Division 6 (commencing with Section 17000) of the Financial Code as the escrow agent. Upon written request of an escrow agent that has not been approved by the Department under subdivision (c) of Section 10263 of the Public Contract Code, the Department will provide written notice to that escrow agent within 10 business days of receipt of the request indicating the reason or reasons for not approving that escrow agent. The payments will be deposited in a trust account with a Federally chartered bank or savings association within 24 hours of receipt by the escrow agent. The Contractor shall not place any retentions with the escrow agent in excess of the coverage provided to that escrow agent pursuant to subdivision (b) of Section 17314 of the Financial Code. In all respects not inconsistent with subdivision (c) of Section 10263 of the Public Contract Code, the remaining provisions of Section 10263 of the

Public Contract Code shall apply to escrow agents acting pursuant to subdivision (c) of Section 10263 of the Public Contract Code.

5-1.04 INTEREST ON PAYMENTS

Interest shall be payable on progress payments, payments after acceptance, final payments, extra work payments and claim payments as follows:

1. Unpaid progress payments, payment after acceptance and final payments shall begin to accrue interest 30 days after the Engineer prepares the payment estimate.
2. Unpaid extra work bills shall begin to accrue interest 30 days after preparation of the first pay estimate following the receipt of a properly submitted and undisputed extra work bill. To be properly submitted, the bill must be submitted within 7 days of the performance of the extra work and in accordance with the requirements of Section 9-1.03C, "Records," and Section 9-1.06, "Partial Payments," of the Standard Specifications. An undisputed extra work bill not submitted within 7 days of performance of the extra work will begin to accrue interest 30 days after the preparation of the second pay estimate following submittal of the bill.
3. The rate of interest payable for unpaid progress payments, payments after acceptance, final payments and extra work payments shall be 10 percent per annum.
4. The rate of interest payable on a claim, protest or dispute ultimately allowed under this contract shall be 6 percent per annum. Interest shall begin to accrue 61 days after the Contractor submits to the Engineer information in sufficient detail to enable the Engineer to ascertain the basis and amount of said claim, protest or dispute.

The rate of interest payable on any award in arbitration shall be 6 percent per annum if allowed under the provisions of Civil Code Section 3289.

5-1.05 PUBLIC SAFETY

The Contractor shall provide for the safety of traffic and the public in conformance with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications and these special provisions.

The Contractor shall install temporary railing (Type K) between a lane open to public traffic and an excavation, obstacle, or storage area when the following conditions exist:

- (1) Excavations.—The near edge of the excavation is 3.6 m or less from the edge of the lane, except:
 - (a) Excavations covered with sheet steel or concrete covers of adequate thickness to prevent accidental entry by traffic or the public.
 - (b) Excavations less than 0.3-m deep.
 - (c) Trenches less than 0.3-m wide for irrigation pipe or electrical conduit, or excavations less than 0.3-m in diameter.
 - (d) Excavations parallel to the lane for the purpose of pavement widening or reconstruction.
 - (e) Excavations in side slopes, where the slope is steeper than 1:4 (vertical:horizontal).
 - (f) Excavations protected by existing barrier or railing.
- (2) Temporarily Unprotected Permanent Obstacles.—The work includes the installation of a fixed obstacle together with a protective system, such as a sign structure together with protective railing, and the Contractor

elects to install the obstacle prior to installing the protective system; or the Contractor, for the Contractor's convenience and with permission of the Engineer, removes a portion of an existing protective railing at an obstacle and does not replace such railing complete in place during the same day.

- (3) Storage Areas.—Material or equipment is stored within 3.6 m of the lane and the storage is not otherwise prohibited by the provisions of the Standard Specifications and these special provisions.

The approach end of temporary railing (Type K), installed in conformance with the provisions in this section "Public Safety" and in Section 7-1.09, "Public Safety," of the Standard Specifications, shall be offset a minimum of 4.6 m from the edge of the traffic lane open to public traffic. The temporary railing shall be installed on a skew toward the edge of the traffic lane of not more than 0.3-m transversely to 3 m longitudinally with respect to the edge of the traffic lane. If the 4.6-m minimum offset cannot be achieved, the temporary railing shall be installed on the 10 to 1 skew to obtain the maximum available offset between the approach end of the railing and the edge of the traffic lane, and an array of temporary crash cushion modules shall be installed at the approach end of the temporary railing.

Temporary railing (Type K) shall conform to the provisions in Section 12-3.08, "Temporary Railing (Type K)," of the Standard Specifications. Temporary railing (Type K), conforming to the details shown on 1995 Standard Plan T3 or 1992 Standard Plan T3, may be used. Temporary railing (Type K) fabricated prior to January 1, 1993, and conforming to 1988 Standard Plan B11-30 may be used, provided the fabrication date is printed on the required Certificate of Compliance.

The fourteenth paragraph of Section 12-3.08, "Temporary Railing (Type K)," of the Standard Specifications is amended to read:

Each rail unit placed within 3 m of a traffic lane shall have a reflector installed on top of the rail as directed by the Engineer. A Type P marker panel shall also be installed at each end of railing installed adjacent to a two-lane, two-way highway and at the end facing traffic of railing installed adjacent to a one-way roadbed. If the railing is placed on a skew, the marker shall be installed at the end of the skew nearest the traveled way. Type P marker panels shall conform to the provisions in Section 82, "Markers and Delineators," except that the Contractor shall furnish the marker panels.

Reflectors on temporary railing (Type K) shall conform to the provisions in "Approved Traffic Products" of these special provisions.

Temporary crash cushion modules shall conform to the provisions in "Temporary Crash Cushion Module" of these special provisions.

Except for installing, maintaining and removing traffic control devices, whenever work is performed or equipment is operated in the following work areas the Contractor shall close the adjacent traffic lane unless otherwise provided in the Standard Specifications and these special provisions:

Approach speed of public traffic (Posted Limit) (Kilometers Per Hour)	Work Areas
Over 72 (45 Miles Per Hour)	Within 1.8 m of a traffic lane but not on a traffic lane
56 to 72 (35 to 45 Miles Per Hour)	Within 0.9-m of a traffic lane but not on a traffic lane

The lane closure provisions of this section shall not apply if the work area is protected by permanent or temporary railing or barrier.

When traffic cones or delineators are used to delineate a temporary edge of traffic lane, the line of cones or delineators shall be considered to be the edge of traffic lane, however, the Contractor shall not reduce the width of an existing lane to less than 3 m without written approval from the Engineer.

When work is not in progress on a trench or other excavation that required closure of an adjacent lane, the traffic cones or portable delineators used for the lane closure shall be placed off of and adjacent to the edge of the traveled way. The spacing of the cones or delineators shall be not more than the spacing used for the lane closure.

Suspended loads or equipment shall not be moved nor positioned over public traffic or pedestrians.

Full compensation for conforming to the provisions in this section "Public Safety," including furnishing and installing temporary railing (Type K) and temporary crash cushion modules, shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

5-1.06 SURFACE MINING AND RECLAMATION ACT

Attention is directed to the Surface Mining and Reclamation Act of 1975, commencing in Public Resources Code, Mining and Geology, Section 2710, which establishes regulations pertinent to surface mining operations.

Material from mining operations furnished for this project shall only come from permitted sites in compliance with the Surface Mining and Reclamation Act of 1975.

The requirements of this section shall apply to all materials furnished for the project, except for acquisition of materials in conformance with Section 4-1.05, "Use of Materials Found on the Work," of the Standard Specifications.

5-1.07 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES

When the presence of asbestos or hazardous substances are not shown on the plans or indicated in the specifications and the Contractor encounters materials which the Contractor reasonably believes to be asbestos or a hazardous substance as defined in Section 25914.1 of the Health and Safety Code, and the asbestos or hazardous substance has not been rendered harmless, the Contractor may continue work in unaffected areas reasonably believed to be safe, and shall immediately cease work in the affected area and report the condition to the Engineer in writing.

In accordance with Section 25914.1 of the Health and Safety Code, all such removal of asbestos or hazardous substances including any exploratory work to identify and determine the extent of the asbestos or hazardous substance will be performed by separate contract.

If delay of work in the area delays the current controlling operation, the delay will be considered a right of way delay and the Contractor will be compensated for the delay as provided in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

5-1.08 YEAR 2000 COMPLIANCE

This contract is subject to Year 2000 Compliance for automated devices in the State of California. Year 2000 compliance is defined as follows:

Year 2000 compliance for automated devices in the State of California is achieved when embedded functions have or create no logical or mathematical inconsistencies when dealing with dates prior to and beyond 1999. The year

2000 is recognized and processed as a leap year. The product must also operate accurately in the manner in which it was intended for date operation without requiring manual intervention.

The Contractor shall provide the Engineer a Certificate of Compliance from the manufacturer in accordance with the provisions of Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for all automated devices furnished for the project.

5-1.09 DVBE RECORDS

The Contractor shall maintain records of all subcontracts entered into with certified DVBE subcontractors and records of materials purchased from certified DVBE suppliers. The records shall show the name and business address of each DVBE subcontractor or vendor and the total dollar amount actually paid each DVBE subcontractor or vendor.

Upon completion of the contract, a summary of these records shall be prepared on Form CEM-2402 and certified correct by the Contractor or the Contractor's authorized representative, and shall be furnished to the Engineer.

5-1.095 PERFORMANCE OF DVBE SUBCONTRACTORS AND SUPPLIERS

The DVBEs listed by the Contractor in response to the requirements in Section 3, "Submission of DVBE Information and Award and Execution of Contract," in these special provisions, which are determined by the Department to be certified DVBEs, shall perform the work and supply the materials for which they are listed unless the Contractor has received prior written authorization to perform the work with other forces or to obtain the materials from other sources.

Authorization to utilize other forces or sources of materials may be requested for the following reasons:

- (1) The listed DVBE, after having had a reasonable opportunity to do so, fails or refuses to execute a written contract, when the written contract, based upon the general terms, conditions, plans and specifications for the project, or on the terms of the subcontractor's or supplier's written bid, is presented by the Contractor.
- (2) The listed DVBE becomes bankrupt or insolvent.
- (3) The listed DVBE fails or refuses to perform the subcontract or furnish the listed materials.
- (4) The Contractor stipulated that a bond was a condition of executing a subcontract and the listed DVBE subcontractor fails or refuses to meet the bond requirements of the Contractor.
- (5) The work performed by the listed subcontractor is substantially unsatisfactory and is not in substantial accordance with the plans and specifications, or the subcontractor is substantially delaying or disrupting the progress of the work.
- (6) The listed DVBE subcontractor is not licensed pursuant to the Contractor's License Law.
- (7) It would be in the best interest of the State.

The Contractor shall not be entitled to any payment for the work or material unless it is performed or supplied by the listed DVBE or by other forces (including those of the Contractor) pursuant to prior written authorization of the Engineer.

5-1.097 SUBCONTRACTING

Attention is directed to the provisions in Section 8-1.01, "Subcontracting," of the Standard Specifications, Section 2, "Proposal Requirements and Contract No. <Dist>-<Contract_No>

Conditions," and Section 3, "Submission of DVBE Information and Award and Execution of Contract," elsewhere in these special provisions and these special provisions.

The first sentence of the third paragraph of Section 8-1.01 of the Standard specifications shall not apply to this contract.

Section 8-1.01 of the Standard Specifications is amended by adding the following before the sixth paragraph:

Pursuant to the provisions of Section 6109 of the Public Contract Code, the Contractor shall not perform work on a public works project with a subcontractor who is ineligible to perform work on the public works project pursuant to Section 1777.1 or 1777.7 of the Labor Code.

Pursuant to the provisions of Section 1777.1 of the Labor Code, the Labor Commissioner publishes and distributes a list of contractors ineligible to perform work as a subcontractor on a public works project. This list of debarred contractors is available from the Department of Industrial Relations web site at http://www.dir.ca.gov/dir/Labor_law/DLSE/Debar.html.

The DVBE information furnished under Section 3-1.01A, "DVBE Information," of these special provisions is in addition to the subcontractor information required to be furnished under said Section 8-1.01, "Subcontracting," and Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications.

Section 10115 of the Public Contract Code requires the Department to implement provisions to establish a goal for Disabled Veteran Business Enterprise (DVBE) participation in highway contracts that are state funded. As a part of this requirement:

1. No substitution of a DVBE subcontractor shall be made at any time without the written consent of the Department, and
2. If a DVBE subcontractor is unable to perform successfully and is to be replaced, the Contractor will be required to make good faith efforts to replace the original DVBE subcontractor with another DVBE subcontractor.

The requirement in Section 2-1.02, "Disabled Veteran Business Enterprise (DVBE)," of these special provisions that DVBEs must be certified on the date bids are opened does not apply to DVBE substitutions after award of the contract.

5-1.10 AREAS FOR CONTRACTOR'S USE

Attention is directed to the requirements specified in Section 7-1.19, "Rights in Land and Improvements," of the Standard Specifications and these special provisions.

The highway right of way shall be used only for purposes that are necessary to perform the required work. The Contractor shall not occupy the right of way, or allow others to occupy the right of way, for purposes which are not necessary to perform the required work.

There are no State-owned parcels adjacent to the right of way for the exclusive use of the Contractor within the contract limits. The Contractor shall secure, at the Contractor's own expense, any area required for plant sites, storage of equipment or materials, or for other purposes.

No area is available within the contract limits for the exclusive use of the Contractor. However, temporary storage of equipment and materials on State property may be arranged with the Engineer, subject to the prior demands of State maintenance forces and to all other contract requirements. Use of the Contractor's work areas and other State-owned property shall be at the Contractor's own risk, and the State shall not be held liable for any damage to or loss of materials or equipment located within such areas.

5-1.11 FORCE ACCOUNT PAYMENT

The second, third and fourth paragraphs of Section 9-1.03A, "Work Performed by Contractor," of the Standard Specifications, shall not apply.

To the total of the direct costs computed as provided in Sections 9-1.03A(1), "Labor," 9-1.03A(2), "Materials," and 9-1.03A(3), "Equipment Rental," of the Standard Specifications, there will be added a markup of 25 percent to the cost of labor, 10 percent to the cost of materials, and 10 percent to the equipment rental.

The above markups shall constitute full compensation for all overhead costs for work performed on a force account basis. These overhead costs shall be deemed to include all items of expense not specifically designated as cost or equipment rental in Sections 9-1.03A(1), "Labor," 9-1.03A(2), "Materials," and 9-1.03A(3), "Equipment Rental," of the Standard Specifications. The total payment made as provided above and in the first paragraph of Section 9-1.03A, "Work Performed by Contractor," shall be deemed to be the actual cost of the work performed on a force account basis, and shall constitute full compensation therefor.

When extra work to be paid for on a force account basis is performed by a subcontractor, approved in accordance with the provisions in Section 8-1.01, "Subcontracting," of the Standard Specifications, an additional markup of 5 percent will be added to the total cost of said extra work including all markups specified in this section "Force Account Payment". Said additional 5 percent markup shall reimburse the Contractor for additional administrative costs, and no other additional payment will be made by reason of performance of the extra work by a subcontractor.

5-1.12 OVERHEAD

The Contractor will be compensated for overhead in accordance with these special provisions.

Attention is directed to "Force Account Payment," "Progress Schedule," and "Adjustments of Overhead Costs" of these special provisions and the Standard Specifications.

Full compensation for overhead shall be considered as included in the various items of work and no additional compensation will be allowed therefor.

5-1.13 PAYMENTS

Attention is directed to Sections 9-1.06, "Partial Payments," and 9-1.07, "Payment After Acceptance," of the Standard Specifications and these special provisions.

No partial payment will be made for any materials on hand which are furnished but not incorporated in the work.

5-1.14 SOUND CONTROL REQUIREMENTS

Sound control shall conform to the provisions in Section 7-1.01I, "Sound Control Requirements," of the Standard Specifications and these special provisions.

The noise level from the Contractor's operations, between the hours of 9:00 p.m. and 6:00 a.m., shall not exceed 86 dbA at a distance of 15 m. This requirement in no way relieves the Contractor from responsibility for complying with local ordinances regulating noise level.

The noise level requirement shall apply to the equipment on the job or related to the job, including but not limited to trucks, transit mixers or transient equipment that may or may not be owned by the Contractor. The use of loud sound

signals shall be avoided in favor of light warnings except those required by safety laws for the protection of personnel.

Full compensation for conforming to the requirements of this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

5-1.15 HIGHWAY CONSTRUCTION EQUIPMENT

The first paragraph of Section 7-1.01D, "Vehicle Code," of the Standard Specifications is amended to read:

Pursuant to the authority contained in Section 591 of the Vehicle Code, the Department has determined that, within such areas as are within the limits of the project and are open to public traffic, the following requirements of the Vehicle Code will apply: the lighting requirements in Section 25803; the brake requirements in Chapter 3, Division 12; the splash apron requirements in Section 27600; and, when operated on completed or existing treated base, surfacing, pavement or structures, except as otherwise provided in Section 7-1.02, "Load Limitations," the weight limitation requirements contained in Division 15.

SECTION 6. (BLANK)

SECTION 7. (BLANK)

SECTION 8. MATERIALS

SECTION 8-1. MISCELLANEOUS

8-1.01 STATE-FURNISHED MATERIALS

Attention is directed to Section 6-1.02, "State-Furnished Materials," of the Standard Specifications and these special provisions.

The following materials will be furnished to the Contractor:

Decontamination trailers (2), including steel jack supports
Sand hopper
Office/Crew Room Modular Building, including installation
Locker/Restroom Modular Building, including installation

Attention is directed to Section 12-2.01, "Relocating Materials and Equipment," elsewhere in these special provisions.

SECTION 8-2. (BLANK)

SECTION 8-3. WELDING

8-3.01 WELDING ELECTRODES

Flux core welding electrodes conforming to the requirements of AWS A5.20 E6XT-4 or E7XT-4 shall not be used to perform any type of welding for this project.

SECTION 9. (BLANK)

SECTION 10. CONSTRUCTION DETAILS

SECTION 10-1. GENERAL

10-1.00 ESCROW OF BID DOCUMENTATION

Bid documentation shall consist of all documentary and calculated information generated by the Contractor in preparation of the bid. The bid documentation shall conform to the requirements in these special provisions, and shall be submitted to the Department and held in escrow for the duration of the contract.

In the resolution of disputes involving the project, the escrowed bid documents will be the only documents accepted from the Contractor regarding preparation of the bid.

In signing the proposal, the bidder certifies that the material submitted for escrow constitutes all the documentary information used in preparation of the bid and that he has personally examined the contents of the container and that they are complete.

The bidder shall include with the proposal, the identification of the bidder's representative authorized to present the bid documentation and the persons responsible for preparing the bidder's estimate.

Nothing in the bid documentation shall be construed to change or modify the terms or conditions of the contract.

Escrowed bid documentation will not be used for pre-award evaluation of the Contractor's anticipated methods of construction, nor to assess the Contractor's qualifications for performing the work.

Bid documentation shall clearly itemize the Contractor's estimated costs of performing the work. The documentation submitted shall be complete and so detailed as to allow for an in-depth analysis of the Contractor's estimate.

The bid documentation shall include, but not be limited to: quantity takeoffs; rate schedules for the direct costs and costs for labor (by craft), plant and equipment ownership and operation, permanent and expendable materials, insurance and subcontracted work; estimated construction schedules, including sequence and duration and development of production rates; quotations from subcontractors and suppliers; estimates of field and home office overhead; contingency and margin for each contract item of work; and other reports, calculations and information used by the bidder to arrive at the estimate submitted with the proposal.

The Contractor shall also submit bid documentation for each subcontractor whose total subcontract exceeds \$250,000. Subcontractor bid documentation shall be enclosed with the Contractor's submittal. The examination of subcontractors' bid documentation will be accomplished in the same manner as for the Contractor's bid documentation. If a subcontractor is replaced, bid documentation for the new subcontractor shall be submitted for review and escrow before authorization for the substitution will be granted. Upon request of a subcontractor, the bid documentation from that subcontractor shall be reviewed only by the subcontractor and the Department.

If the bidder is a joint venture, the bid documentation shall include the joint venture agreement, the joint venture estimate comparison and final reconciliation of the joint venture estimate.

Copies of the proposals submitted by the first, second and third low bidders will be provided to the respective bidders for inclusion in the bid documentation to be escrowed.

The first, second, and third apparent low bidders shall present the bid documentation for escrow at the District 04 Office, 111 Grand Avenue, Room 12-816, Oakland, CA, on the first Monday, at 1:00 p.m., following the time indicated in the "Notice to Contractors" for the opening of bids.

Bid documentation shall be submitted in a sealed container, clearly marked with the bidder's name, date of submittal, project contract number and the words, "Bid Documentation for Escrow."

Failure to submit the actual and complete bid documentation as specified herein within the time specified shall be cause for rejection of the proposal.

Upon submittal, the bid documentation of the apparent low bidder will be examined and inventoried by the duly designated representatives of the Contractor and the Department to ensure that the bid documentation is authentic, legible, and in accordance with the terms of this section "Escrow of Bid Documentation." The examination will not include review of, nor will it constitute approval of, proposed construction methods, estimating assumptions or interpretation of the contract. The examination will not alter any conditions or terms of the contract. The acceptance or rejection by the Department that the submitted bid documents are in compliance with this section "Escrow of Bid Documentation" shall be completed within 48 hours of the time the bid documentation is submitted by the Contractor.

At the completion of the examination, the bid documents will be sealed and jointly deposited at an agreed commercial bank.

Bid documentation submitted by the second and third apparent low bidders will be jointly deposited at agreed commercial banks. If the apparent low bid is withdrawn or rejected, the bid documentation of the second low bidder will be examined and inventoried in the manner specified above, then sealed and deposited again in escrow. If the second low bid is withdrawn or rejected, the bid documentation of the third low bidder will be examined and inventoried in the manner specified above, then sealed and deposited again in escrow. Upon execution and final approval of the contract or rejection of all bids, the bid documentation will be returned to any remaining unsuccessful bidders.

The escrowed bid documentation may be examined by the designated representatives of both the Department and the Contractor, at any time deemed necessary by either the Department or the Contractor to assist in the negotiation of price adjustments and change orders, or in the settlement of claims or disputes.

If requested by a Disputes Review Board, the escrowed bid documentation may be utilized to assist the Board in its recommendations.

The bid documentation submitted by the Contractor will be held in escrow until the contract has been completed, the ultimate resolution of all disputes and claims has been achieved and receipt of final payment has been accepted by the Contractor. The escrowed bid documentation will then be released from escrow to the Contractor.

The bid documentation submitted by the bidder is, and shall remain, the property of the bidder, and is subject to only joint review by the Department and the bidder. The Department stipulates and expressly acknowledges that the submitted bid documentation constitutes trade secrets and will not be deemed public records. This acknowledgment is based on the Department's express understanding that the information contained in the bid documentation is not known outside the bidder's business, is known only to a limited extent and only by a limited number of employees of the bidder, is safeguarded while in the bidder's possession, is extremely valuable to the bidder and could be extremely valuable to the bidder's competitors by virtue of it reflecting the bidder's contemplated techniques of construction. The Department acknowledges that the bid documentation includes a compilation of information used in the bidder's business, intended to give the bidder an opportunity to obtain an advantage over competitors who do not know of or use the contents of the documentation. The Department agrees to safeguard the bid documentation, and all information contained therein, against disclosure, including disclosure of subcontractor bid documentation to the Contractor and other subcontractors to the fullest extent

permitted by law. However, in the event of arbitration or litigation, the bid documentation shall be subject to discovery, and the Department assumes no responsibility for safeguarding the bid documentation unless the Contractor has obtained an appropriate protective order issued by the arbitrator or the court.

Full compensation for preparing the bid documentation, presenting it for escrow and reviewing it for escrow and upon request of the Engineer shall be considered as included in the contract prices paid for the various items of work, and no additional compensation will be allowed therefor.

The direct cost of depositing the bid documentation in escrow at the agreed commercial bank will be paid by the State.

10-1.01 RESTRICTED AREA

The Contractor's attention is directed to the designated Restricted Area, as shown on the plans. The exact location of the boundaries of Restricted Area shall be established by the Engineer.

Prior to beginning work, the Restricted Area shall be clearly marked in the field such that the ESA boundaries are obvious to equipment operators. The purpose of marking the Restricted Area boundaries is to prevent encroachment upon the Restricted Area. The boundaries shall be checked periodically and the markings repaired or replaced as necessary during construction.

Within the boundaries of the Restricted Area, as shown on the plans, as directed by the Engineer, there shall be no vehicles or equipment parked or stored. No vehicles or equipment are to enter the Restricted Area and there shall be no activities by the Contractor or any type of construction. These areas are protected and no entry by the Contractor for any purpose will be permitted unless specifically authorized in writing by the Engineer. The Contractor shall take measures to ensure that his forces do not enter or disturb these areas, including giving written notice to his employees and subcontractors.

Full compensation for conforming to the provisions in this section shall be considered as included in the prices paid for the various contract items of work and no additional compensation will be allowed therefor.

10-1.02 WATER POLLUTION CONTROL

Water pollution control work shall conform to the requirements in Section 7-1.01G, "Water Pollution," of the Standard Specifications, and these special provisions.

Water pollution control work shall conform to the requirements in the Construction Contractor's Guide and Specifications of the Caltrans Storm Water Quality Handbooks, dated April 1997, and addenda thereto issued up to and including the date of advertisement of the project, hereafter referred to as the "Handbook." Copies of the Handbook may be obtained from the Department of Transportation, Material Operations Branch, Publication Distribution Unit, 1900 Royal Oaks Drive, Sacramento, California 95815, Telephone: (916) 445-3520.

Copies of the Handbook are also available for review at 111 Grand Avenue, Oakland, California 94601. Please call the Toll Bridge Program Duty Senior, telephone number (510) 286-5549, to reserve a copy of the Handbook at least 24 hours in advance.

The Contractor shall become fully informed of, and comply with the applicable provisions of the Handbook and Federal, State and local regulations that govern the Contractor's operations and storm water discharges from both the project site and areas of disturbance outside the project limits during construction.

Unless arrangements for disturbance of areas outside the project limits are made by the Department and made part of the contract, it is expressly agreed that the Department assumes no responsibility to the Contractor or property owner whatsoever with respect to any arrangements made between the Contractor and property owner to allow disturbance of areas outside the project limits.

Contract No. <Dist>-<Contract_No>

The Contractor shall be responsible for the costs and for any liability imposed by law as a result of the Contractor's failure to comply with the requirements set forth in this section "Water Pollution Control" including, but not limited to, compliance with the applicable provisions of the Handbook and Federal, State and local regulations. For the purposes of this paragraph, costs and liabilities include but are not limited to fines, penalties and damages whether assessed against the State or the Contractor, including those levied under the Federal Clean Water Act and the State Porter Cologne Water Quality Act.

In addition to any remedy authorized by law, so much of the money due the Contractor under the contract that shall be considered necessary by the Department may be retained by the State of California until disposition has been made of the costs and liabilities.

The retention of money due the Contractor shall be subject to the following:

1. The Department will give the Contractor 30 days notice of its intention to retain funds from any partial payment which may become due to the Contractor prior to acceptance of the contract. Retention of funds from any payment made after acceptance of the contract may be made without prior notice to the Contractor.
2. No retention of additional amounts out of partial payments will be made if the amount to be retained does not exceed the amount being withheld from partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications.
3. If the Department has retained funds and it is subsequently determined that the State is not subject to the costs and liabilities in connection with the matter for which the retention was made, the Department shall be liable for interest on the amount retained at the legal rate of interest for the period of the retention.

Conformance with the requirements of this section "Water Pollution Control," shall not relieve the Contractor from the Contractor's responsibilities, as provided in Sections 7-1.11, "Preservation of Property," 7-1.121, "Indemnification," and 7-1.122, "Insurance," of the Standard Specifications.

WATER POLLUTION CONTROL PROGRAM PREPARATION, APPROVAL AND UPDATES

As part of the water pollution control work, a Water Pollution Control Program, hereafter referred to as the "WPCP," is required for this contract. The WPCP shall conform to the requirements in Section 7-1.01G, "Water Pollution," of the Standard Specifications, the requirements in the Handbook, and these special provisions.

No work having potential to cause water pollution, as determined by the Engineer, shall be performed until the WPCP has been approved by the Engineer.

Within 21 days after the approval of the contract, the Contractor shall submit 3 copies of the WPCP to the Engineer. The Contractor shall allow 7 days for the Engineer to review the WPCP. If revisions are required, as determined by the Engineer, the Contractor shall revise and resubmit the WPCP within 7 days of receipt of the Engineer's comments and shall allow 7 days for the Engineer to review the revisions. Upon the Engineer's approval of the WPCP, 3 additional copies of the WPCP incorporating the required changes shall be submitted to the Engineer. Minor changes or clarifications to the initial submittal may be made and attached as amendments to the WPCP.

The objectives of the WPCP shall be to identify pollution sources that may adversely affect the quality of storm water discharges associated with the project and to identify, construct, implement and maintain water pollution control measures, hereafter referred to as control measures, to reduce to the

extent feasible pollutants in storm water discharges from the construction site during construction under this contract.

The WPCP shall incorporate control measures in the following categories:

1. Soil stabilization practices;
2. Sediment control practices;
3. Sediment tracking control practices;
4. Wind erosion control practices; and
5. Nonstorm water management and waste management and disposal control practices.

Specific objectives and minimum requirements for each category of control measures are contained in the Handbook.

The Contractor shall consider the objectives and minimum requirements presented in the Handbook for each of the above categories. The special minimum requirements listed below supersede the minimum requirements listed in the Handbook for the same category. When minimum requirements are listed for any category, the Contractor shall incorporate into the WPCP, and implement on the project, the listed minimum controls required in order to meet the pollution control objectives for the category. In addition, the Contractor shall consider other control measures presented in the Handbook and shall incorporate into the WPCP and implement on the project the control measures necessary to meet the objectives of the WPCP. The Contractor shall document the selection process in accordance with the procedure specified in the Handbook. The following special minimum requirements are established:

Category:	Minimum Requirements:
Non-Storm Water and Waste Management Controls	CD7(2) Dewatering, CD8(2) Paving Operations, CD10(2) Material Delivery and Storage, CD11(2) Material Use, CD12(2) Spill Prevention and Control, CD13(2) Solid Waste Management, CD15(2) Contaminated Soil Management, CD16(2) Concrete Waste Management, CD17(2) Sanitary/Septic Waste Management, CD18(2) Vehicle and Equipment Cleaning, CD19(2) Vehicle and Equipment Fueling, CD20(2) Vehicle and Equipment Maintenance, CD22(2) Scheduling, CD44(2) Illicit Discharge/Illegal Dumping Reporting
Erosion & Sediment Source Controls	CD22(2) Scheduling, CD26B(2) Geotextiles, Mats/Plastic Covers & Erosion Control Blankets,
Wind Erosion Controls	CD22(2) Scheduling, CD26B(2) Geotextiles, Mats/Plastic Covers & Erosion Control Blankets,
Sediment Treatment Controls	CD22(2) Scheduling, CD29A(2) Stabilized Construction Entrance, CD41(2) Sediment Traps

The following contract items of work, as shown on the project plans, shall be incorporated into the WPCP as critical temporary control measures: Temporary Silt Fence. The Contractor shall consider other control measures to supplement these critical temporary control measures when necessary to meet the pollution control objectives of the WPCP.

The WPCP shall include, but not be limited to, the following items as described in the Handbook:

1. Project description and Contractor's certification;
2. Project information;
3. Pollution sources, control measures, and water pollution control drawings;
and
4. Amendments, if any.

The Contractor shall amend the WPCP, graphically and in narrative form, whenever there is a change in construction activities or operations which may affect the discharge of significant quantities of pollutants to surface waters, ground waters, municipal storm drain systems, or when deemed necessary by the Engineer. The WPCP shall also be amended if the WPCP has not achieved the objective of reducing pollutants in storm water discharges. Amendments shall show additional control measures or revised operations, including those in areas not shown in the initially approved WPCP, which are required on the project to control water pollution effectively. Amendments to the WPCP shall be submitted for review and approval by the Engineer in the same manner specified for the initially approved WPCP. Amendments shall be dated and attached to the on-site WPCP document.

The Contractor shall keep a copy of the WPCP, together with updates, revisions and amendments at the project site.

WPCP IMPLEMENTATION

Upon approval of the WPCP, the Contractor shall be responsible throughout the duration of the project for installing, constructing, inspecting and maintaining the control measures included in the WPCP and any amendments thereto and for removing and disposing of temporary control measures. Unless otherwise directed by the Engineer or specified in these special provisions, the Contractor's responsibility for WPCP implementation shall continue throughout any temporary suspension of work ordered in accordance with Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications. Requirements for installation, construction, inspection, maintenance, removal and disposal of control measures are specified in the Handbook and these special provisions.

Soil stabilization practices and sediment control measures, including minimum requirements, shall be provided throughout the winter season, defined as between October 1st and May 1st.

Implementation of soil stabilization practices and sediment control measures for soil-disturbed areas of the project site shall be completed, except as provided for below, no later than 20 days prior to the beginning of the winter season or upon start of applicable construction activities for projects which begin either during or within 20 days of the winter season.

Throughout the winter season, the active, soil-disturbed area of the project site shall be no more than 2 hectares. The Engineer may approve, on a case-by-case basis, expansions of the active, soil-disturbed area limit. The Contractor shall demonstrate the ability and preparedness to fully deploy soil stabilization practices and sediment control measures to protect soil-disturbed areas of the project site before the onset of precipitation. The Contractor shall maintain a quantity of soil stabilization and sediment control materials on site equal to 100 percent of that sufficient to protect unprotected, soil-disturbed areas on

the project site and shall maintain a detailed plan for the mobilization of sufficient labor and equipment to fully deploy control measures required to protect unprotected, soil-disturbed areas on the project site prior to the onset of precipitation. The Contractor shall include a current inventory of control measure materials and the detailed mobilization plan as part of the WPCP.

Throughout the winter season, soil-disturbed areas of the project site shall be considered to be nonactive whenever soil disturbing activities are expected to be discontinued for a period of 20 or more days and the areas are fully protected. Areas that will become nonactive either during the winter season or within 20 days thereof shall be fully protected with soil stabilization practices and sediment control measures within 10 days of the discontinuance of soil disturbing activities or prior to the onset of precipitation, whichever is first to occur.

Throughout the winter season, active soil-disturbed areas of the project site shall be fully protected at the end of each day with soil stabilization practices and sediment control measures unless fair weather is predicted through the following work day. The weather forecast shall be monitored by the Contractor on a daily basis. The National Weather Service forecast shall be used, or an alternative weather forecast proposed by the Contractor may be used if approved by the Engineer. If precipitation is predicted prior to the end of the following work day, construction scheduling shall be modified, as required, and the Contractor shall deploy functioning control measures prior to the onset of the precipitation.

The Contractor shall implement, year-round and throughout the duration of the project, control measures included in the WPCP for sediment tracking, wind erosion, nonstorm water management and waste management and disposal.

The Engineer may order the suspension of construction operations which create water pollution if the Contractor fails to conform to the requirements of this section "Water Pollution Control" as determined by the Engineer.

MAINTENANCE

To ensure the proper implementation and functioning of control measures, the Contractor shall regularly inspect and maintain the construction site for the control measures identified in the WPCP. The Contractor shall identify corrective actions and time frames to address any deficient measures or reinstate any measures that have been discontinued.

The construction site inspection checklist provided in the Handbook shall be used to ensure that the necessary measures are being properly implemented, and to ensure that the control measures are functioning adequately. The Contractor shall submit one copy of each site inspection record to the Engineer.

Inspections of the construction site shall be conducted by the Contractor to identify deficient measures, as follows:

1. Prior to a forecast storm;
2. After each precipitation event ;
3. At 24 hour intervals during extended precipitation events; and
4. Routinely, every week.

If the Contractor or the Engineer identifies a deficiency in the deployment or functioning of an identified control measure, the deficiency shall be corrected by the Contractor immediately, or by a later date and time if requested by the Contractor and approved by the Engineer in writing, but not later than the onset of subsequent precipitation events. The correction of deficiencies shall be at no additional cost to the State.

PAYMENT

Full compensation for conforming to the requirements of this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

Those control measures which are shown on the project plans and for which there is a contract item of work will be measured and paid for as that item of work.

The Engineer will retain an amount equal to 25 percent of the estimated value of the contract work performed during estimate periods in which the Contractor fails to conform to the requirements of this section "Water Pollution Control" as determined by the Engineer.

Retentions for failure to conform to the requirements of this section "Water Pollution Control" shall be in addition to the other retentions provided for in the contract. The amounts retained for failure of the Contractor to conform to the requirements of this section will be released for payment on the next monthly estimate for partial payment following the date that a WPCP has been implemented and maintained, and water pollution is adequately controlled, as determined by the Engineer.

10-1.03 TEMPORARY SILT FENCE

Temporary silt fence shall conform to the details shown on the plans and these special provisions.

Temporary silt fence shall be furnished, installed, maintained at the locations shown on the plans.

Preparation shall conform to the requirements in Section 20-3.02, "Preparation," of the Standard Specifications.

Attention is directed to "Water Pollution Control" elsewhere in these special provisions.

MATERIALS.—Materials shall conform to Section 20-2, "Materials," of the Standard Specifications and one of the following:

Temporary silt fence shall be a prefabricated silt fence with a minimum woven polypropylene fabric width of 900 mm and a minimum tensile strength of 0.44-kN, conforming to ASTM Designation: D 4632.

INSTALLATION.—Temporary silt fence shall be installed as shown on the plans and as follows:

When joints are necessary, the temporary silt fence shall overlap a minimum of 150 mm with both posts tied together.

Temporary silt fences shall be maintained to provide for adequate sediment holding capacity. Sediment deposits shall be removed after each precipitation event. Removed sediment shall be deposited within the soil stockpile, as shown on the plans, in such a way that it is not subject to erosion by wind or water, or as directed by the Engineer.

Damage to the silt fence resulting from the weather or the Contractor's activities shall be immediately repaired. The silt fence shall not be removed from the project, except for replacement due to damage or ineffectiveness.

Holes, depressions or any other ground disturbance caused by the removal of the temporary silt fence shall be backfilled and repaired in accordance with the provisions in the second paragraph of Section 15-1.02, "Preservation of Property," of the Standard Specifications.

MEASUREMENT AND PAYMENT.—The quantity of temporary silt fence to be paid for will be determined by the meter from actual measurements, the measurements to be made parallel with the ground slope along the line of the completed temporary silt fence, deducting the widths of openings.

The contract price paid per meter for temporary silt fence shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in installing temporary silt fence, complete in place, including trench excavation and backfill, and maintenance of temporary silt fence, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Temporary silt fence placed at location other than as shown on the project plans or directed by the Engineer, in accordance with the Contractor's Water Pollution Control Program, will not be measured and will be paid for as specified in "Water Pollution Control" elsewhere in these special provisions.

No adjustment of compensation will be made for any increase or decrease in the quantities of temporary silt fence required, regardless of the reason for the increase or decrease. The provisions in Section 4-1.03B, "Increased or Decreased Quantities," shall not apply to temporary silt fence.

10-1.04 DUST CONTROL

Dust control shall conform to the provisions in Section 10, "Dust Control," of the Standard Specifications.

10-1.05 MOBILIZATION

Mobilization shall conform to the provisions in Section 11, "Mobilization," of the Standard Specifications.

10-1.06 EARTHWORK

Earthwork shall conform to the provisions in Section 19, "Earthwork," of the Standard Specifications and these special provisions.

Surplus excavated material shall become the property of the Contractor and shall be disposed of outside the highway right of way in accordance with the provisions in Section 7-1.13 of the Standard Specifications.

Where a portion of existing surfacing is to be removed, the outline of the area to be removed shall be cut on a neat line with a power-driven saw to a minimum depth of 50 mm before removing the surfacing. Full compensation for cutting existing surfacing shall be considered as included in the contract price paid per cubic meter for roadway excavation and no additional compensation will be allowed therefor.

10-1.07 ASPHALT CONCRETE

Asphalt concrete shall be Type A and shall conform to the provisions in Section 39, "Asphalt Concrete," of the Standard Specifications and these special provisions.

The amount of asphalt binder used in asphalt concrete placed in dikes, gutters, gutter flares, overside drains and aprons at the ends of drainage structures shall be increased one percent by mass of the aggregate over the amount of asphalt binder determined for use in asphalt concrete placed on the traveled way.

Aggregate for asphalt concrete dikes shall conform to the 9.5-mm, maximum grading as specified in Section 39-2.02, "Aggregate," of the Standard Specifications.

If the Contractor selects the batch mixing method, asphalt concrete shall be produced by the automatic batch mixing method as provided in Section 39-3.03A(2), "Automatic Proportioning," of the Standard Specifications.

SECTION 11. (BLANK)

SECTION 12. BUILDING WORK

SECTION 12-1. GENERAL REQUIREMENTS

12-1.01 SCOPE

Building work described herein and as shown on the plans shall conform to the requirements of these special provisions and Sections 1 through 9 of the Standard Specifications. Sections 10 through 95 of the Standard Specifications shall not apply to the work in this Section 12 except when specific reference is made thereto.

The building work to be done consists, in general, of constructing a wood framed platform, guardrails, and canopies; installing 2 State-furnished decontamination trailers and a sand hopper; connecting water, sewer, and electrical services to a State-furnished Office/Crew Room Modular Building, a State-furnished Locker/Restroom Modular Building, and 2 State-furnished decontamination trailers; including related mechanical and electrical work; and such other items or details, not mentioned above, that are required by the plans, Standard Specifications, or these special provisions shall be performed, placed, constructed or installed at the Tri Bridge Maintenance Station.

12-1.02 ORDER OF WORK

Order of work shall conform to the provisions in Section 5-1.05, "Order of Work," of the Standard Specifications and these special provisions.

The first order of work shall be to prepare the site, including grading and utilities, for the installation of the Office/Crew Room Modular Building and Locker/Restroom Modular Building which will be delivered on October 1, 1999.

Except as otherwise specified, other work may proceed at the Contractor's discretion.

The installation of the Office/Crew Room Modular Building and Locker/Restroom Modular Building will be performed under separate contract and will take approximately 2 weeks from delivery.

The platforms and canopies shall not be constructed until the Office/Crew Room Modular Building and Locker/Restroom Modular Building are installed.

12-1.03 ABBREVIATIONS

Section 1-1.02, "Abbreviations," of the Standard Specifications is amended by adding the following:

AAMA	American Architectural Manufacturers' Association
ACI	American Concrete Institute
AGA	American Gas Association
AITC	American Institute of Timber Construction
AMCA	Air Movement and Control Association
APA	American Plywood Association
ARI	American Refrigeration Institute
ASHRAE	American Society of Heating, Refrigeration and Air Conditioning Engineers
CS	Commercial Standards (US Department of Commerce)
ESO	Electrical Safety Orders
	Contract No. <Dist>-<Contract_No>

FGMA	Flat Glass Marketing Association
FM	Factory Mutual
FS	Federal Specification
ICBO	International Conference of Building Officials
NAAMM	National Association of Architectural Metal Manufacturers
NBFU	National Board Fire Underwriters
NEC	National Electrical Code
NFPA	National Fire Protection Association
PEI	Porcelain Enamel Institute
PS	Product Standard (US Department of Commerce)
RIS	Redwood Inspection Service
SCPI	Structural Clay Products Institute
SMACNA	Sheet Metal and Air Conditioning Contractors' National Association
SSPC	Steel Structures Paint Council
TCA	Tile Council of America
TPI	Truss Plate Institute
UBC	Uniform Building Code
UL	Underwriters Laboratories, Inc.
WCLIB	West Coast Lumber Inspection Bureau (stamped WCLB)
WCLB	Grade stamp for WCLIB
WIC	Woodwork Institute of California
WWPA	Western Wood Products' Association

When reference is made to the Uniform Building Code (UBC) on the plans or in the special provisions, it shall be the 1994 Uniform Building Code as amended by the 1995 Title 24 California Building Standards Code.

12-1.04 GUARANTEE

The Contractor hereby unconditionally guarantees that the building work will be done in accordance with the requirements of the contract, and further guarantees the building work of the contract to be and remain free of defects in workmanship and materials for a period of one year from the date of acceptance of the contract, unless a longer guarantee period is required elsewhere in these special provisions. The Contractor hereby agrees to repair or replace any and all building work, together with any other adjacent work which may be displaced in so doing, that may prove to be not in accordance with the requirements of the contract or that may be defective in its workmanship or material within the guarantee period specified, without any expense whatsoever to the Department, ordinary wear and tear and unusual abuse or neglect excepted.

The performance bond for the contract, or a portion thereof, in the sum equal to one-half the contract price of the building work, shall remain in full force and effect during the guarantee period.

The Contractor further agrees, that within 10 calendar days after being notified in writing by the Department of any building work not in accordance with the requirements of the contract or any defects in the building work, he shall commence and prosecute with due diligence all work necessary to fulfill the terms of this guarantee, and shall complete the work within a reasonable period of time, and, in the event he fails to comply, he does hereby authorize the Department to proceed to have such work done at the Contractor's expense and he shall honor and pay the cost and charges therefor upon demand. The Department shall be entitled to all costs and expenses, including reasonable attorney's fees, necessarily incurred upon the Contractor's refusal to honor and pay the above costs and charges.

12-1.05 AREAS FOR CONTRACTOR'S USE

No area is available within the contract limits for the exclusive use of the Contractor. The Contractor shall arrange with the Engineer for areas to store equipment and materials within the work area.

12-1.06 COOPERATION

Attention is directed to Sections 7-1.14, "Cooperation," and 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications and these special provisions.

Work by State forces will be in progress within the contract limits during the working period for this contract.

The Contractor shall comply with all security policies and normal working hours of the State concerning the Tri Bridge Maintenance Station.

The Contractor shall coordinate his operations with those of the Modular Building Installer.

The Contractor shall plan his work to minimize interference with State forces and the public. Interruptions to any services for the purpose of making or breaking a connection shall be made only after consultation with and for such time periods as directed by the Engineer.

12-1.07 SUBMITTALS

Working drawings, material lists, descriptive data, samples and other submittals specified in these special provisions shall be submitted for approval in accordance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications and these special provisions.

Unless otherwise permitted in writing by the Engineer, all submittals required by these special provisions shall be submitted within 35 days after the contract has been approved.

Attention is directed to the provisions in Section 5-1.01, "Authority of Engineer," of the Standard Specifications. The Engineer may request submittals for materials or products where submittals have not been specified in these special provisions, or may request that additional information be included in specified submittals, as necessary to determine the quality or acceptability of such materials or products.

Attention is directed to Section 6-1.05, "Trade Names and Alternatives," of the Standard Specifications. The second indented paragraph of the first paragraph of said Section 6-1.05 is amended to read:

Whenever the specifications permit the substitution of a similar or equivalent material or article, no test or action relating to the approval of such substituted material will be made until the request for substitution is made in writing by the Contractor accompanied by complete data as to the equality of the material or article proposed. Such request shall be made within 35 days after the date the contract has been approved and in ample time to permit approval without delaying the work, but need not be made in less than 35 days after award of the contract.

Work requiring the submittal of working drawings, material lists, descriptive data, samples, or other submittals shall not begin prior to approval of said submittal by the Engineer. Except as otherwise specified, fifteen working days shall be allowed for approval or return for correction of each submittal or resubmittal. Should the Engineer fail to complete his review within the time specified and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in review, an extension of time commensurate with the delay in completion of the work thus

caused will be granted as provided in Section 8-1.07, "Liquidated Damages," of the Standard Specifications.

Submittals shall be delivered to the locations indicated in these special provisions. If a specific location is not indicated, the submittal shall be delivered to the Office of Structure Design, Documents Unit, Fourth Floor, Mail Station 9, 1801 30th Street, Sacramento, California 95816, telephone (916) 227-8252, or the submittals shall be mailed to the Office of Structure Design, Documents Unit, Mail Station 9, P. O. Box 942874, Sacramento, California 94274-0001.

Each submission of drawings, material lists and descriptive data shall consist of at least 5 copies. Two copies will be returned to the Contractor either approved for use or returned for correction and resubmittal.

Each separate item submitted shall bear a descriptive title, the name of the project, district, county, and contract number. Plans and detailed drawings shall be not larger than 559 mm x 914 mm.

The material list shall be complete as to name of manufacturer, catalog number, size, capacity, finish, all pertinent ratings, and identification symbols used on the plans and in the special provisions for each unit.

Parts lists and service instructions packaged with or accompanying the equipment installed in the work shall be delivered to the Engineer at the jobsite. Required operating and maintenance instructions shall be submitted in triplicate.

Manufacturer's warranties for products installed in the work shall be delivered to the Engineer at the jobsite.

Unapproved samples and samples not incorporated in the work shall be removed from State property, when directed by the Engineer.

12-1.08 PROGRESS SCHEDULE

A progress schedule shall be submitted in duplicate for the building work in accordance with the requirements in Section 8-1.04, "Progress Schedule," of the Standard Specifications.

12-1.09 SCHEDULE OF VALUES

The Contractor shall prepare and submit to the Engineer 2 copies of a Schedule of Values covering each lump sum item for building work. The Schedule of Values, showing the value of each kind of work, shall be acceptable to the Engineer before any partial payment estimate is prepared.

The sum of the items listed in the Schedule of Values shall equal the contract lump sum price for building work. Overhead and profit shall not be listed. Bond premium, temporary construction facilities, plant, and other such items will not be paid for under the various building work items and shall be included in the mobilization bid item for the entire project.

12-1.10 INSPECTION

All items covered or all stages of work that are not to remain observable must be inspected and approved before progress of work conceals portions to be inspected. The Contractor shall notify the Engineer not less than 72 hours in advance of when such inspection is needed.

12-1.11 OBSTRUCTIONS

Attention is directed to Sections 7-1.11, "Preservation of Property," 7-1.12, "Responsibility for Damage," 7-1.16, "Contractor's Responsibility for the Work and Materials," and 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications.

The Contractor shall notify the Engineer and the appropriate regional notification center for operators of subsurface installations at least 5 working days prior to performing any excavation or other work close to any underground pipeline, conduit, duct, wire or other structure. Regional notification centers include but are not limited to the following:

Underground Service Alert
Northern California (USA)
Telephone: 1(800)642-2444

Underground Service Alert
Southern California (USA)
Telephone: 1(800)422-4133

South Shore Utility
Coordinating Council (DIGS)
Telephone: 1(800)541-3447

Western Utilities
Underground Alert, Inc.
Telephone: 1(800)424-3447

12-1.12 PRESERVATION OF PROPERTY

Attention is directed to Sections 7-1.11, "Preservation of Property," 7-1.12, "Responsibility for Damage," 7-1.16, "Contractor's Responsibility for the Work and Materials," and 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications.

Operations shall be conducted in such a manner that existing facilities, surfacing, installations, and utilities which are to remain in place will not be damaged. Temporary surfacing, facilities, utilities and installations shall also be protected until they are no longer required. The Contractor, at his expense shall furnish and install piling, sheet piling, cribbing, bulkheads, shores, or whatever means may be necessary to adequately support material carrying such facilities, or to support the facilities themselves and shall maintain such support until they are no longer needed.

12-1.13 UTILITY CONNECTION

The Contractor shall make all arrangements, and obtain all permits and licenses required for the extension of and connection to each utility service applicable to this project, shall furnish all labor and materials necessary for such extensions which are not performed or provided by the utility, and shall furnish and install any intermediate equipment required by the serving utilities.

Upon written request by the Contractor, the State will pay all utility permits, licenses, connection charges, and excess length charges directly to the utility. Such request shall be submitted not less than 15 days before service connections are required.

The costs incurred by the Contractor for the extensions of utilities beyond the limits shown on the plans, and in furnishing and installing any intermediate equipment required by the serving utilities, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Full compensation for any costs incurred by the Contractor to obtain the permits and licenses shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

12-1.14 TEMPORARY UTILITIES

The Contractor may obtain electrical power and water from existing State electrical power and water outlets within the contract limits free of charge for contract operations where such utilities exist, provided that such utility services are in service and are not required by the State for other purposes and subject to the provisions in the section "Cooperation" of these special provisions.

The Contractor shall make his own arrangements to obtain any additional electrical power and water or other utilities required for his operations and shall make and maintain the necessary service connections at his own expense.

When existing utility systems are being modified, periods of shutdown will be determined by the Engineer.

The Contractor shall provide adequate temporary lighting to perform the work and allow the Engineer to inspect the project as each portion is completed.

The Contractor shall provide and pay for telephone service he may require. State telephone facilities shall not be used.

12-1.15 SANITARY FACILITIES

When operational, State sanitary facilities will be available for use by the Contractor's employees, during normal State working hours. Tools shall not be cleaned nor shall cleaning liquids be disposed of in State sanitary facilities or sewers.

12-1.16 MEASUREMENT AND PAYMENT

The contract lump sum price paid for building work shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in constructing the building work, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for any incidental materials and labor, not shown on the plans or specified, which are necessary to complete the buildings and appurtenances shall be considered as included in the contract lump sum price paid for building work and no additional compensation will be allowed therefor.

12-1.17 FIELD ENGINEERING

This section specifies administrative and procedural requirements for field engineering services to be performed by the Contractor.

Lines and grades.--Attention is directed to Section 5-1.07 "Lines and Grades," of the Standard Specifications.

Such stakes or marks will be set by the Engineer as he determines to be necessary to establish the lines and grades required for the completion of the work shown on the plans and as specified in these special provisions. In general, these will consist of the primary vertical and horizontal control points.

Stakes and marks set by the Engineer shall be carefully preserved by the Contractor. In case such stakes and marks are destroyed or damaged they will be replaced at the Engineer's earliest convenience. The Contractor will be charged for the cost of necessary replacement or restoration of such stakes and marks which in the judgment of the Engineer were carelessly or willfully destroyed or damaged by the Contractor's operations. This charge will be deducted from any moneys due or to become due the Contractor.

All other stakes or marks required to establish the lines and grades required for the completion of the work shall be the responsibility of the Contractor.

Existing utilities and equipment.--The existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning sitework, the Contractor shall investigate and verify the existence and location of underground utilities and other construction.

Prior to construction, the Contractor shall verify the location and invert elevation at points of connection of sanitary and septic sewers, storm sewer, and water or fire service piping.

Surveys for layout and performance.--The Contractor shall perform all surveys for layout and performance, reduce field notes, and make all necessary calculations and drawings necessary to carry out the work.

The Contractor shall locate and layout site improvements, and other work requiring field engineering services, including pavements, stakes for grading, fill and topsoil placement, utility slopes and invert elevations by instrumentation and similar appropriate means.

Batter boards shall be located and laid out for structures, building foundations, column grids and locations, floor levels and, control lines and levels required for mechanical and electrical work.

Survey accuracy and tolerances.--The tolerances generally applicable in setting survey stakes for foundations, slabs, and underground work shall not exceed the following:

Survey Stakes or Markers	Tolerance
Rough grading or excavation	30 mm
Trimming or preparation of subgrade for roadways	15 mm
Roadway surfacing, steel or concrete pipe	6 mm
Structures or building construction	3 mm

Such tolerance shall not supersede stricter tolerances required by the plans or special provisions, and shall not otherwise relieve the Contractor of responsibility for measurements in compliance therein.

12-1.18 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS

Only materials and products conforming to the requirements of the specifications shall be incorporated in the work. When metric materials and products are not available, and when approved by the Engineer, and at no cost to the State, materials and products in the inch-pound (imperial) system which are of equal quality and of the required properties and characteristics for the purpose intended, may be substituted for the equivalent metric materials and products, subject to the following requirements:

Materials and products shown on the plans or in the special provisions as being equivalent may be substituted for the metric materials and products specified or detailed on the plans.

Before other non-metric materials and products will be considered for use the Contractor shall furnish, at the Contractor's expense, evidence satisfactory to the Engineer that the materials and products proposed for use are equal to or better than the materials and products specified or detailed on the plans. The burden of proof as to the quality and suitability of substitutions shall be upon the Contractor and the Contractor shall furnish all information necessary as required to the Engineer. The Engineer will be

the sole judge as to the quality and suitability of the substituted materials and products and the Engineer's decision shall be final.

When the Contractor elects to substitute non-metric materials and products, including materials and products shown on the plans or in the special provisions as being equivalent, a list of substitutions to be made shall be submitted for approval.

The following substitutions of materials and products will be allowed:

SUBSTITUTION TABLE FOR SIZES OF HIGH STRENGTH STEEL FASTENERS, ASTM Designation: A 325M	
METRIC SIZE SHOWN ON THE PLANS mm x thread pitch	IMPERIAL SIZE TO BE SUBSTITUTED inch
M16 x 2	5/8
M20 x 2.5	3/4
M22 x 2.5	7/8
M24 x 3	1
M27 x 3	1-1/8
M30 x 3.5	1-1/4
M36 x 4	1-1/2

SUBSTITUTION TABLE FOR REINFORCEMENT	
METRIC BAR DESIGNATION NUMBER AS SHOWN ON THE PLANS	IMPERIAL BAR DESIGNATION NUMBER TO BE SUBSTITUTED
10	3
13	4
16	5
19	6
22	7
25	8
29	9
32	10
36	11
43	14
57	18

SUBSTITUTION TABLE FOR WELDED PLAIN
WIRE REINFORCEMENT, ASTM DESIGNATION:
A 185

	US CUSTOMARY UNITS SIZE TO BE SUBSTITUTED inch ² x 100
MW9	W1.4
MW10	W1.6
MW13	W2.0
MW15	W2.3
MW19	W2.9
MW20	W3.1
MW22	W3.5
MW25	W3.9, except W3.5 in piles only
MW26	W4.0
MW30	W4.7
MW32	W5.0
MW35	W5.4
MW40	W6.2
MW45	W6.5
MW50	W7.8
MW55	W8.5, except W8.0 in piles only
MW60	W9.3
MW70	W10.9, except W11.0 in piles only
MW80	W12.4
MW90	W14.0
MW100	W15.5

The sizes in the following tables of materials and products are exact conversions of metric sizes of materials and products and are listed as acceptable equivalents:

CONVERSION TABLE FOR SIZES OF: (1) STEEL FASTENERS FOR GENERAL APPLICATIONS, ASTM Designation: A 307 or AASHTO Designation: M 314, Grade 36 or 55, and (2) HIGH STRENGTH STEEL FASTENERS, ASTM Designation: A 325 or A 449	
DIAMETER	
METRIC SIZE SHOWN ON THE PLANS mm	EQUIVALENT IMPERIAL SIZE inch
6, or 6.35	1/4
8 or 7.94	5/16
10, or 9.52	3/8
11, or 11.11	7/16
13 or 12.70	1/2
14, or 14.29	9/16
16, or 15.88	5/8
19, or 19.05	3/4
22, or 22.22	7/8
24, 25, or 25.40	1
29, or 28.58	1-1/8
32, or 31.75	1-1/4
35, or 34.93	1-3/8
38 or 38.10	1-1/2
44, or 44.45	1-3/4
51, or 50.80	2
57, or 57.15	2-1/4
64, or 63.50	2-1/2
70 or 69.85	2-3/4
76, or 76.20	3
83, or 82.55	3-1/4
89 or 88.90	3-1/2
95, or 95.25	3-3/4
102, or 101.60	4

CONVERSION TABLE FOR NOMINAL THICKNESS OF SHEET METAL			
UNCOATED HOT AND COLD ROLLED SHEETS		HOT-DIPPED ZINC COATED (GALVANIZED) SHEETS	
METRIC THICKNESS SHOWN ON THE PLANS mm	EQUIVALENT US STANDARD GAGE inch	METRIC THICKNESS SHOWN ON THE PLANS mm	EQUIVALENT GALVANIZED SHEET GAGE inch
7.94	0.3125		
6.07	0.2391		
5.69	0.2242		
5.31	0.2092		
4.94	0.1943		
4.55	0.1793		
4.18	0.1644	4.270	0.1681
3.80	0.1495	3.891	0.1532
3.42	0.1345	3.510	0.1382
3.04	0.1196	3.132	0.1233
2.66	0.1046	2.753	0.1084
2.28	0.0897	2.372	0.0934
1.90	0.0747	1.994	0.0785
1.71	0.0673	1.803	0.0710
1.52	0.0598	1.613	0.0635
1.37	0.0538	1.461	0.0575
1.21	0.0478	1.311	0.0516
1.06	0.0418	1.158	0.0456
0.91	0.0359	1.006 or 1.016	0.0396
0.84	0.0329	0.930	0.0366
0.76	0.0299	0.853	0.0336
0.68	0.0269	0.777	0.0306
0.61	0.0239	0.701	0.0276
0.53	0.0209	0.627	0.0247
0.45	0.0179	0.551	0.0217
0.42	0.0164	0.513	0.0202
0.38	0.0149	0.475	0.0187

CONVERSION TABLE FOR WIRE		
METRIC THICKNESS SHOWN ON THE PLANS	EQUIVALENT USA STEEL WIRE THICKNESS	GAGE NO.
mm	inch	
6.20	0.244	3
5.72	0.225	4
5.26	0.207	5
4.88	0.192	6
4.50	0.177	7
4.11	0.162	8
3.76	0.148	9
3.43	0.135	10
3.05	0.120	11
2.69	0.106	12
2.34	0.092	13
2.03	0.080	14
1.83	0.072	15
1.57	0.062	16
1.37	0.054	17
1.22	0.048	18
1.04	0.041	19
0.89	0.035	20

CONVERSION TABLE FOR LUMBER	
METRIC NOMINAL SURFACE DRY SIZE	EQUIVALENT NOMINAL SURFACE DRY U S SIZE
mm	inch
51	2
102	4
152	6
203	8
254	10
305	12

CONVERSION TABLE FOR PLYWOOD	
METRIC mm	ENGLISH inch
6.4	1/4
7.9	5/16
9.5	3/8
11.1	7/16
11.9	15/32
12.7	1/2
15.1	19/32
15.9	5/8
18.3	23/32
19.1	3/4
22.2	7/8
25.4	1
28.6	1 1/8

CONVERSION TABLE FOR INSULATION R-VALUE	
METRIC (m ² K/W)	ENGLISH (HR FT ² F/BTU)
0.5	3
0.7	4
1.4	8
1.9	11
2.3	13
2.5	14
3.3	19
5.3	30

CONVERSION TABLE FOR VAPOR TRANSMISSION RATING	
METRIC (Perm-m)	ENGLISH (perm-inch)
0.29	0.02

CONVERSION TABLE FOR LOW PRESSURE	
METRIC (Pa)	ENGLISH (Inches of Water Column)
30	0.125
60	0.25
120	0.50
145	0.60
175	0.70
185	0.75
200	0.80
250	1.00
310	1.25

CONVERSION TABLE FOR PRESSURE	
METRIC (kPa)	ENGLISH (psi)
10	1.5
210	30
280	40
350	50
690	100
860	125
1040	150
1100	160
1210	175
1380	200
1730	250
2070	300
2170	315
2410	350
2590	375
2760	400
4830	700
5170	750
5520	800
13800	2000
17200	2500
20700	3000
27600	4000
34500	5000
137900	20000

CONVERSION TABLE FOR MIL THICKNESS	
METRIC (mm)	ENGLISH (inch/1000)
0.10	4
0.10	5
0.50	20
0.75	30
1.00	40

CONVERSION TABLE FOR HVAC DUCTING.	
METRIC (mm)	ENGLISH (inch)
100	4
125	5
150	6
175	7
200	8
225	9
250	10
300	12
360	14
410	16
460	18
510	20
560	22
610	24
660	26
710	28
760	30

CONVERSION TABLE FOR MECHANICAL PIPING		
METRIC (GSP, PVC, BSP, DUCTILE IRON)	METRIC (mm)	ENGLISH (inch)
NPS 1/2	15	1/2
NPS 3/4	20	3/4
NPS 1	25	1
NPS 1 1/4	32	1 1/4
NPS 1 1/2	40	1 1/2
NPS 2	50	2
NPS 2 1/2	65	2 1/2
NPS 3	75	3
NPS 4	100	4
NPS 6	150	6

CONVERSION TABLE FOR LUBRICATION PIPING TUBING WALL THICKNESS	
METRIC (mm)	ENGLISH (inch)
2.1	0.083
0.9	0.035

CONVERSION TABLE FOR HOSE/TUBING SIZES O. D.	
METRIC (mm)	ENGLISH (inch)
6	1/4
10	3/8
13	1/2
16	5/8
19	3/4
22	7/8
25	1

CONVERSION TABLE FOR DRUM SIZES			
METRIC		ENGLISH	
L	kg	gallons	pounds
205	180	55	400
60	55	16	120
	16	5	35

CONVERSION TABLE FOR POWER	
METRIC (kW)	ENGLISH (HP)
0.037	1/20
0.075	1/10
0.18	1/4
0.25	1/3
0.37	1/2
0.55	3/4
0.75	1
1.1	1 1/2
1.5	2
2.2	3
3.7	5
5.5	7 1/2
7.5	10
11	15
15	20
18.5	25
22	30
30	40
37	50
45	60
55	75
75	100
90	120
110	150

CONVERSION TABLE FOR IMPELLER BALANCE		
SYNCHRONOUS RPM	METRIC (g mm/kg)	ENGLISH (ounce- inch/pound)
720	94	0.059
900	73	0.046
1200	54	0.034
1800	41	0.026
3600	17	0.011

CONVERSION TABLE FOR ELECTRICAL CONDUIT	
METRIC SIZE SHOWN ON THE PLANS mm	EQUIVALENT IMPERIAL SIZE inch
16	1/2
21	3/4
27	1
35	1 1/4
41	1 1/2
53	2
103	4

SECTION 12- 2. SITEWORK

12-2.01 RELOCATING MATERIALS AND EQUIPMENT

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of relocating existing materials and equipment in accordance with the details shown on the plans and these special provisions.

A sand hopper and decontamination trailer shall be relocated from the Carquinez Maintenance Facility (707) 648-4118.

A decontamination trailer shall be relocated from the Benicia-Martinez Maintenance Facility (707) 746-6730.

Submittals.--Prior to relocating the sand hopper, the Contractor shall submit for approval to the Engineer at the jobsite, a Sand Hopper Relocation Plan. The sand hopper is an oversized load. The relocation plan shall show details of dismantling and reassembling the sand hopper.

The sand hopper has lead based paint. If paint removal is part of the relocation plan, paint removal shall conform to Section 12-2 "Lead Abatement" of these special provisions.

PART 2.- PRODUCTS (Not applicable)

PART 3.- EXECUTION

RELOCATION.--

General.--Materials or equipment to be relocated shall be removed carefully to avoid damage to the materials or equipment or to the materials or equipment which are to remain. Assemblies to be relocated which require dismantling for removal shall be matchmarked before dismantling.

The Contractor shall notify the Engineer prior to the relocation work in order that the materials or equipment may be inspected for existing damage.

Materials or equipment to be relocated shall have all adhering concrete, mastics, earth or other deleterious materials removed and shall have all exterior surfaces cleaned.

Materials or equipment which are damaged by the Contractor's operations shall be replaced or restored to match the condition of the materials or equipment prior to the beginning of the Contractor's operations. Replacement or

restoration of damaged materials or equipment shall be at the Contractor's expense.

Connections, anchorages and fasteners for relocated materials and equipment shall match existing and shall be furnished and installed by the Contractor. Assemblies which have been dismantled shall be reassembled to match the existing installation. Relocated materials and equipment shall be installed as required for new work.

Modifications to wiring and plumbing to accommodate relocated items shall be as shown on the plans. Ends of piping and conduits to be abandoned shall be capped.

Surfaces that are exposed to view upon removal or relocation of materials or equipment shall be patched. Bumps shall be removed and depressions filled, and the surface finished to match the existing surfaces. Depressions in concrete less than 25 mm deep shall be deepened to 25 mm minimum depth before filling with cement mortar.

DISPOSAL.--

General.--Materials from existing facilities to be reused in the work, in the opinion of the Engineer, is unsuitable for use shall become the property of the Contractor and disposed of as provided in Section 7-1.13, "Disposal of Material Outside of the Highway Right of Way." of the Standard Specifications. The unsuitable material shall be replaced as ordered by the Engineer and will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications.

12-2.02 LEAD ABATEMENT.--

PART 1.- GENERAL

SUMMARY.--

Scope.--The work shall consist of procedures for removal, repair, and disposal of lead based materials which are designation on the plans or specified in these special provisions to be removed and disposed of.

Where existing lead based materials are to be removed during demolition, construction or alterations, such material shall be treated as hazardous waste, and shall be removed, hauled and disposed of in accordance with all applicable Federal, State and local laws and ordinances.

SUBMITTALS.--

Health and safety.--A Code of Safe Practices, an Injury and Illness Prevention Program, and a Hazard Communication Program in accordance with the provisions of Construction Safety Orders 1509 and 1510 shall be submitted for approval.

QUALITY ASSURANCE.--

Codes and standards.--Codes which govern removal and disposal of materials containing lead include, but are not limited to the following:

1. California Health and Safety Code, Division 20, Chapter 6.5, "Hazardous Waste Control Act."
2. California Code of Regulations, Title 22, Division 4, Chapter 30, "Minimum Standards for Management of Hazardous and Extremely Hazardous Material."

3. California Code of Regulations, Title 8, General Industry Safety Order, Section 1532.1, Lead.
4. Occupational Safety and Health Administration, Part 26 (amended), of Title 29 of the Code of Federal Regulations.

Compliance program.--The Contractor shall submit the compliance programs required in subsection (e)(2), "Compliance Program," of said Section 1532.1, "Lead," to the Engineer for approval before starting removal work on the project and at such times when revisions to the program are ordered by the Engineer. The compliance programs shall be prepared by an industrial hygienist certified by the American Council of Industrial Hygiene. The Engineer will notify the Contractor of the approval or rejection of any submitted or revised compliance program in not more than 10 working days.

If measures being taken by the Contractor are inadequate to provide for worker safety and the containment and collection of residue from existing paint systems, the Engineer will direct the Contractor to revise his operations and the compliance program. Such directions will be in writing and will specify the items of work for which the Contractor's compliance programs are inadequate. No further work shall be performed on said items until the compliance programs are adequate and, if required, a revised compliance program has been approved.

The State will not be liable to the Contractor for failure to approve all or any portion of an originally submitted or revised compliance program for worker safety and the containment and collection of residue from existing paint systems, nor for any delays to the work due to the Contractor's failure to submit an acceptable compliance program.

Field sampling.--The Contractor shall furnish sampling and testing programs for air and soil as applicable. The programs shall be prepared and carried out by an industrial hygienist certified by the American Council of Industrial Hygiene. The number and location of the samples shall be designated by the Engineer.

Air samples, if required, shall be collected during removal operations to measure concentrations of heavy metals and total particulate matter in the ambient air as PM-10 (particulate matter with an aerodynamic diameter less than or equal to 10 micrometers). Air samples shall be collected and analyzed in accordance with the Code of Federal Regulations 40 CFR PART 50. Appendix J, except as follows:

1. Air samples shall be Reference or Equivalent Method PM-10 Samplers as designated by the U. S. Environmental Agency and in accordance with requirements of 40 CFR PART 53.
2. Sampling time each day shall coincide with the time of removal operations but the duration of sampling shall be not less than 8 hours.
3. Immediately following analysis for PM-10, all samples will be analyzed for heavy metal content in accordance with 40 CFR PART 50, Appendix G.

A minimum of 4 soil samples shall be collected before start of work which disturbs the existing paint system, and a minimum of 4 soil samples shall be collected within 36 hours following completion of the work which disturbs the existing paint system. A soil sample shall consist of 5 plugs, each 20 mm diameter and 15 mm deep, taken at each corner and center of a 0.30 meter square area. Soil samples shall be analyzed for total lead, total chromium and total zinc in accordance with Method 3050 in "Test Methods for Evaluating Solid Waste,

Physical/Chemical Methods, SW-846" by the United States Environmental Protection Agency.

Sample analysis results shall be submitted in triplicate to the Engineer within 10 days after sampling. Sample analysis reports shall be prepared by the certified hygienist and include the following information:

For both air and soil sample analysis results, the date and sample location of sample collection, sample number, contract number, and facility name as shown on the contract plans will be required.

For air sample analysis results, the following will be required:

1. Start time, end time and duration of sample collection.
2. Start time and end times of cleaning on the day of sample collection.
3. Concentrations of PM-10 expressed as micrograms PM-10 per standard cubic meter of air.
4. Concentrations of heavy metals expressed as micrograms per standard cubic meter of air.

For soil sample analysis results, the concentrations of heavy metal expressed as parts million will be required.

PART 2.- PRODUCTS (Not applicable.)

PART 3.- EXECUTION

REMOVAL.--

Notification.--The Contractor shall notify the Engineer 3 working days in advance of commencement of removal operations of material containing lead or lead based materials.

Method of removal.--Painted materials shall be removed using the wet process removal equipment and methods, to a depth required to remove all paint and provide clean substrate suitable for a new finish.

Removed material and water used for removal shall be collected. Removed material shall be separated from water using approved filters.

Handling.--The Contractor shall comply with all Federal, State, and local regulations for the removal of material containing lead prior to demolition, shall place such removed material in approved plastic containers (double ply, 0.15 mm minimum thickness, plastic bags) with caution labels affixed to said bags. Such caution labels shall have conspicuous, legible lettering which spells out the following, or equivalent warning:

**CAUTION
CONTAINS LEAD**

Temporary storage on the ground of material and residue produced when the existing paint system is disturbed will not be permitted. Material and residue shall be stored in leak proof containers and shall be handled in such a manner that no spillage will occur.

At the option of the Contractor, the removed lead based materials may be placed directly into a roll off or drop box which shall have the same caution label affixed on all sides.

Safety measures.--The Contractor shall comply with all Federal, State and local requirements for safety which shall include providing employees with coveralls (preferably disposable plastic coated), rubber gloves (to be discarded after use), rubber boots (to be washed thoroughly after use), and respirators.

The Contractor shall be responsible for verifying that all employees, who are involved in removal operations, wear the required protective devices during removal operations.

DISPOSAL.--

Transporting.--All haulers of hazardous waste material shall be currently registered with the State Department of Health Services (DOHS), and shall have a U.S. Environmental Protection Agency Identification Number (U.S. EPA I.D. Number). All vehicles used to transport hazardous waste material shall have affixed to the vehicle a valid Certificate of Compliance issued by DOHS. If a roll off or drop box is utilized, both the drop box and the transporting vehicle must have a valid Certificate of Compliance issued by DOHS.

Disposal.--The Engineer will obtain the required EPA generator identification numbers, and will sign the hazardous waste manifests.

All material and residue produced during removal operations shall be tested and disposed of by the Contractor in California at an approved Class 1 disposal facility in accordance with the requirements of the disposal facility operator.

The Contractor shall notify the proper authorities at the disposal site in advance of delivery of hazardous waste containing lead to the disposal site.

12-2.03 EARTHWORK FOR BUILDING WORK

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of performing earthwork for building work in accordance with the details shown on the plans and these special provisions.

Earthwork for building work shall consist of excavation for footings, foundations; backfilling; trenching and backfilling for pipes and conduits; and any other earthwork, not mentioned, but necessary to complete the building work.

Attention is directed to the requirements of "Field Engineering" in Section 12-1, "General Requirements," of these special provisions.

QUALITY ASSURANCE.--

Samples.--Samples of sand weighing not less than 11 kg, shall be submitted to the Engineer at the jobsite for approval.

SITE CONDITIONS.--

Existing underground piping and conduit.--The location of existing underground piping and conduit is based on the best records available. Before beginning work, the Contractor shall accurately locate the piping and conduit involved in the work. If the location of the existing piping or conduit deviates from the location shown on the plans by more than 1.5 meters, or, if no elevations are indicated and the piping or conduit is more than 0.9 meter below grade, the cost of the additional excavation, backfill, piping or conduit, and removal and replacement of concrete, if any, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Existing surfaced or planted areas.--Existing surfaced or planted areas that are removed, broken or damaged by the Contractor's operations shall be restored to their original condition except as otherwise shown on the plans or specified herein. Restoration materials shall be equal to or better than the original materials.

PART 2.- PRODUCTS

BACKFILL MATERIALS.--

Structure backfill.--

Structure and trench backfill shall be free of organic and other deleterious material and shall be suitable for the required compaction. Gravel without sand matrix shall not be used except as free draining granular material beneath slabs and footings.

Sand.--

Sand shall be clean, washed sand, free from clay or organic material graded such that 100 percent passes the 6 mm sieve, 90 percent to 100 percent passes the 4.75 mm sieve and not more than 5 percent passes the 75 µm sieve size.

PART 3.- EXECUTION

PREPARATION.--

Sawcutting.--Prior to excavation or trenching, existing surfacing shall be removed to saw cut lines, or to existing wood dividers or expansion joints, if any. The saw cut shall be to a neat line and have a depth not less than 25 mm. Surfacing shall be replaced to match the thickness, grades and finish of the adjacent surrounding surfaces.

EXCAVATION.--

Footing excavation.--The footing depths shown on the plans shall be changed to suit field conditions when directed by the Engineer. Solid rock at or near required depths shall not be disturbed. Unsuitable material shall be excavated down to firm bearing as directed by the Engineer. Work and materials required because of excavation in excess of the depths shown on the plans, when such excavation has been ordered by the Engineer, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

Limits of the excavation shall allow for adequate working space for installing materials and as required for safety of personnel. Such working space excavation shall be replaced in kind and compacted at the Contractor's expense.

Overdepth excavation for footings shall be backfilled with concrete or such other material recommended by the Contractor and approved by the Engineer. Relative compaction shall be not less than 95 percent.

Excavation for pipes and conduits.--Pipes or conduits in the same trench shall have a minimum clear distance between pipes or conduits of 150 mm. Pipes or conduits shall have not less than 0.75 meter of cover from top of pipes or conduits to finished grade unless otherwise shown on the plans or specified.

Trenching shall be of sufficient depth to permit placing a minimum depth of 100 mm of compacted sand under all pipes and conduits.

Dewatering.--Excavations shall be kept clear of standing water. Water shall be removed by pumping if necessary. Water removed from excavation shall be carried away from the building site and disposed of in a manner that will not harm State or adjacent property.

BACKFILLING.--

General.--Backfill shall be placed and compacted in horizontal layers, not more than 150 mm thick prior to compaction, and to the lines and grades shown on the plans or to original ground.

Structure backfill.--After structures are in place and forms are removed, wood and other debris shall be removed from excavations before placing backfill.

Unless approved in writing by the Engineer, compaction of structure or select backfill by jetting or ponding shall not be permitted.

Backfilling pipes and conduits.--Backfill placed under pipe and conduits shall be compacted sand, 100 mm minimum depth. Backfill material placed to a level 150 mm above tops of pipes and conduits shall be sand or fine earth and particles shall not exceed 13 mm in greatest dimension. For wrapped, coated, or plastic pipe or conduits, sand shall be used for backfill. Backfill material placed higher than 150 mm above tops of pipes or conduits shall consist of material free of stones or lumps exceeding 100 mm in greatest dimension except:

(a) The top 300 mm of backfill under roads, walks or paving shall consist of aggregate base material.

COMPACTION.--

General.--Relative compaction shall be determined in accordance with California Test 216 or 231.

Unless otherwise noted below, all backfill shall be compacted to a relative compaction of 90 percent.

Compact original ground.--Original ground within 400 mm of the top of asphalt concrete surfacing shall be compacted to a relative compaction of not less than 95 percent.

Trench backfill.--Trench backfill placed beneath slabs or paved areas shall be compacted to a relative compaction of not less than 95 percent.

DISPOSAL.--

Surplus material.--Surplus material from the excavation shall be removed and disposed of outside the right-of-way in accordance with Section 7-1.13 of the Standard Specifications.

FIELD QUALITY CONTROL.--

Inspection.--When the excavation is substantially completed to grade, the Contractor shall notify the Engineer. No concrete shall be placed until the foundation has been approved by the Engineer.

Testing.--The State will conduct compaction tests during the backfilling and compacting operations.

12-2.04 AGGREGATE BASE

PART 1.-GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing, spreading and compacting aggregate base in accordance with the details shown on the plans and these special provisions.

PART 2.-PRODUCTS

Aggregate base.--

Aggregate base shall be commercial quality aggregates consisting of broken stone; crushed gravel; natural, clean, rough-surfaced gravel and sand; or a combination thereof.

Aggregate base shall conform to the following grading as determined by California Test 202:

Sieve or Screen Size	Percentage Passing
25 mm	100
19 mm	90 - 100
4.75 mm	35 - 60
6 µm	10 - 30
75 µm	2 - 9

Aggregate base shall also conform to the following quality requirements:

Tests	Califor nia Test No.	Test Requireme nts
Durability Index	229	35 Min.
Resistance (R-Value)	301	78 Min.
Sand Equivalent	217	22 Min.

PART 3.-EXECUTION

SPREADING AND COMPACTING.--

Spreading.--Aggregate base shall be placed and compacted to the lines and grades shown on the plans.

Spreading and compacting shall be performed by methods that will produce a uniform base, free from pockets of coarse or fine material.

Compaction.--Relative compaction of each layer of compacted base material shall be not less than 95 percent, as determined by California Test 216 or 231.

Contract No. <Dist>-<Contract_No>

12-2.05 FREE DRAINING GRANULAR MATERIAL

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and placing free draining granular material beneath slabs in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS

Free draining granular material.--

Free draining granular material shall be clean, hard, durable, free-draining rock. The material gradation shall be such that all passes the 25 mm screen, and not more than 5 percent passes the 4.75 mm sieve as determined by California Test 202. Granular material shall be free from organic material, clay balls or other deleterious substances.

PART 3.- EXECUTION.--

SPREADING AND CONSOLIDATING.--

General.--Free draining granular material shall be placed, spread and consolidated by tamping or vibrating.

12-2.06 EARTH ANCHOR TIE-DOWNS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing earth anchor tie-downs for the decontamination trailers, in accordance with the details shown on the plans and these special provisions.

Earth anchor tie-downs shall include earth anchors, steel straps, slotted bolts, stabilizer plates, and other accessories and components, not mentioned, which are required for a complete installation. All components shall be galvanized.

Design criteria.-- Earth anchor tie-downs shall be rated for a minimum allowable load of 13 175 N applied at approximately 45 degrees from the horizontal.

SUBMITTALS.--

Product Data.--Manufacturer's technical product data, and installation instructions shall be submitted for approval.

Product data shall include the manufacturer's name and a complete material description of all components of the system.

WORKING Drawings.--Working drawings showing the layout and details of the installation shall be submitted for approval.

Working drawings shall show the shape, size, thickness, and method of attachment for each component used in the work.

Contract No. <Dist>-<Contract_No>

QUALITY ASSURANCE.--

Certificates of Compliance.--Certificates of compliance shall be furnished for the earth anchor tie-downs in accordance with the requirements specified in Section 4-1.04, "Certificates of Compliance," of the General Conditions.

PART 2.- PRODUCTS

Earth anchor.--

Earth anchor shall be double helix auger type. Rod and helix shall conform to ASTM Designation: A 36.

Accessories.--

Tie-down strap and stabilizer plate shall be as recommended by the manufacturer.

Bolts.--

Split bolts shall be slotted to accept tie-down strap and shall conform to ASTM Designation: A 307.

All other bolts shall conform to ASTM Designation: A 325.

PART 3.- EXECUTION.--

INSTALLATION.--

General.--Installation of the earth anchor tie-downs shall be as recommended by the manufacturer.

Tie-down straps shall be installed snug at an angle of approximately 45 degrees.

12-2.07 PAINTED PAVEMENT MARKINGS

PART 1.- GENERAL.--

Scope.--This work shall consist of furnishing and applying paint for pavement markings for day and overnight parking stalls in accordance with the details shown on the plans and these special provisions.

Pavement markings include, but are not limited to, word and symbol markings, and parking stall markings.

PART 2.- PRODUCTS.--

Paint.--

Paint shall be top commercial quality for pavement marking, formulated for the use intended, and manufactured by a nationally recognized manufacturer of paint and other coating products.

The kind of paint to be used (solvent or water borne) shall be determined by the Contractor, based on local air pollution control regulations and weather conditions.

PART 3.- EXECUTION.--

ALIGNMENT AND LAYOUT.--All necessary alignment and layout work shall be performed by the Contractor, in a manner that will not damage the pavement.

Unless otherwise shown on the plans, the width of parking stall markings shall be 102 mm.

EQUIPMENT AND OPERATION.--Mechanical means shall be used to paint pavement markings.

All equipment used in the application of paint shall produce pavement markings of uniform quality.

All spray equipment shall be the proper type and of adequate capacity for the work involved.

Air atomized spray equipment shall be equipped with oil and water extractors and pressure regulators, and shall have adequate air volume and compressor recovery capacity. Spray gun tip needle assemblies and orifices shall be the proper size.

Rapid dry paint shall be applied only with airless type equipment.

Stencils and hand spray equipment shall be used to paint word and symbol markings. Stencils shall be furnished by the Contractor. The stencil layout shall conform to the dimensions shown on the plans.

SURFACE PREPARATION.--Surfaces which are to receive paint shall be cleaned of all dirt and loose material.

APPLICATION.--Paint shall be applied only on dry surfaces, and only during periods of favorable weather, in accordance with the manufacturer's recommendations.

On new surfacing, paint shall be applied in 2 coats. The first coat shall be dry before application of the second coat is applied.

On existing surfacing, paint shall be applied in one coat.

Completed pavement markings shall have clean and well-defined edges, and shall conform to the dimensions shown on the plans or as specified in these special provisions.

Drips, oversprays, improper markings, and paint material tracked by traffic shall be immediately removed from the pavement by methods approved by the Engineer. All such removal shall be at the Contractor's expense.

If used, striping tape shall be applied in accordance with the manufacturer's specifications.

APPLICATION RATES.--Each application of paint shall be applied at the rates recommended by the paint manufacturer for the type of surface involved.

PROTECTION.--Newly placed pavement markings shall be protected from damage by traffic or other causes until the paint is thoroughly dry.

DISABLED ACCESSIBLE PARKING STALL SYMBOL.--Each parking space reserved for persons with physical disabilities shall have a minimum 914 mm x 914 mm surface identification with the international symbol of accessibility. The symbol and border shall be white and the background shall be blue conforming to Federal Standard 595a, Color No. 15090.

12-2.08 PARKING BUMPERS

PART 1.- GENERAL

Scope.--This work shall consist of furnishing and installing precast concrete parking bumpers in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS

Parking bumpers.--

Parking bumpers shall be commercially available precast parking bumpers.

Parking bumpers shall be 1220 mm long, nominal 200 mm wide and 150 mm high with both top longitudinal corners continuously chamfered, and anchor holes 230 mm from each end.

PART 3.- EXECUTION

Layout.--Arrangement of parking bumpers shall be coordinated with the layout of parking stalls and traffic aisles, providing the proper angle to engage wheels and proper location to prevent overtravel of vehicles.

Parking bumpers shall be anchored with two 19 mm diameter reinforcing bars 380 mm in length. The reinforcing bars shall be installed such that the top of the bars is flush with the top of the parking bumper.

12-2.09 DISABLED PARKING AND AUTHORIZATION SIGNS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing disabled parking and authorization signs in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data and sign fastening details shall be submitted for approval.

PART 2.- PRODUCTS

Disabled parking stall identification sign.--

Disabled parking stall identification sign shall be a metal sign with baked enamel finish and the international symbol of accessibility. Sign background shall be blue and shall conform to Federal Standard 595a, Color No. 15090. Symbol, lettering and border shall be white and shall conform to Federal Standard 595a, Color No. 17886.

Van accessible sign.--

Van accessible sign shall be a metal sign with baked enamel finish and the international symbol of accessibility. Sign background shall be blue and shall conform to Federal Standard 595a, Color No. 15090. Lettering and border shall be white and shall conform to Federal Standard 595a, Color No. 17886.

Disabled authorization sign.--

Disabled authorization sign shall be a metal sign with baked enamel finish. Sign background shall be blue and shall conform to Federal Standard 595a, Color No. 15090. Lettering and border shall be white and shall conform to Federal Standard 595a, Color No. 17886. Lettering shall be not less than 25 mm in height and shall read as shown on the plans.

Support post.--

Support post shall be commercial quality, standard weight, galvanized steel pipe. Pipe diameter shall be 35 mm.

Fastening hardware.--

Fastening hardware shall be galvanized or cadmium plated.

Concrete.--

Concrete for support posts shall be commercial quality concrete, proportioned to provide a workable mix suitable for the intended use, with not less than 300 kilograms of cement per cubic meter.

PART 3.- EXECUTION

Installation.--Support posts shall be placed in holes excavated to the depth and cross-section shown on the plans. Posts shall be set vertical and shall be firmly embedded in concrete backfill. The top of the concrete backfill around the post shall be crowned to drain water.

Support posts shall be fitted with a rainproof top.

Sign shall be fastened rigidly and securely to the support post.

The Engineer will provide the Contractor with the necessary information for the disabled authorization sign.

12-2.10 DECONTAMINATION TRAILER INSTALLATION

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of installing decontamination trailers; furnishing and installing earth anchor tie-downs, including related mechanical and electrical work, in accordance with the details shown on the plans and these special provisions.

PART 2.- PRODUCTS

Decontamination trailers.--

Decontamination trailers, including steel jack supports, will be State-furnished as provided under "State-Furnished Materials" in Section 8, "Materials," of these special conditions.

Earth anchor tie-downs.--

Earth anchor tie-downs shall conform to the requirements specified under "Earth Anchor Tie-Downs" in this Section 12-2, of these special provisions.

PART 3.- EXECUTION.--

INSTALLATION.--

General.--Decontamination trailers shall be installed level, with steel jack supports, and earth anchor tie-downs as shown on the plans.

Decontamination trailers shall be connected to water, sewer, and electrical services as shown on the plans.

SECTION 12-3. CONCRETE AND REINFORCEMENT

12-3.01 CAST-IN-PLACE CONCRETE

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of constructing cast-in-place concrete facilities in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data for admixtures shall be submitted for approval.

Descriptive data shall be delivered to the Engineer at the jobsite.

QUALITY ASSURANCE.--

Certificates of Compliance.--Certificates of Compliance shall be furnished for cement, reinforcement, and admixtures in accordance with the requirements specified in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications.

PART 2.- PRODUCTS

CONCRETE MIXES.--

Concrete (structural work).--

Commercial quality concrete shall be proportioned to provide a workable mix suitable for the intended use; shall have not less than 350 kg/m³ of cement; 0 to 50 mm penetration, inclusive, as determined by California Test 533.

CONCRETE MATERIALS.--

Cement.--

Cement shall conform to ASTM Designation: C 150, Types II, or III portland cement.

Aggregates.--

Aggregates shall be free from deleterious coatings, clay balls and other extraneous materials.

Admixtures.--

Admixtures used in portland cement concrete shall be included on the Department's current list of approved admixtures, and shall conform to ASTM Designation: C 494, Types A, B, D, F or G for chemical admixtures; ASTM Designation: C 260 for air-entraining admixtures; and ASTM Designation: C 618 for mineral admixtures, except loss on ignition shall not exceed 4 percent. Properties of admixtures shall be uniform in each lot.

FORM MATERIALS.--

Forms for unexposed finish concrete.--

Forms for unexposed finish concrete surfaces shall be plywood, lumber, metal or other acceptable material.

Form ties.--

Form ties shall be factory fabricated, removable or snapoff metal ties for use as necessary to prevent spreading of forms during concrete placement.

Form oil.--

Form oil shall be commercial quality form oil which will permit the ready release of the forms and will not discolor the concrete.

REINFORCING MATERIALS.--

Bar reinforcement.--

Bar reinforcement shall conform to ASTM Designation: A 615/A 615M, Grade 420, or ASTM Designation: A 706/A 706M.

Bar supports.--

Bar supports for reinforcement shall be precast mortar blocks or ferrous metal chairs, spacers, metal hangers, supporting wires, and other approved devices of sufficient strength to resist crushing under applied loads.

RELATED MATERIALS.--

Anchor bolts, nuts, and washers.--

Nonheaded anchor bolts shall conform to ASTM Designation: A 36M, with a minimum hook length of 6.2 diameters.

Headed anchor bolts shall conform to ASTM Designation: A 307.

Nuts shall conform to ASTM Designation: A 563M, Grade A.

Washers for anchor bolts shall be commercial quality.

Mortar.--

Mortar shall consist of one part cement to 2 parts clean sand and only enough water to permit placing and packing.

Curing compound.--

Curing compound shall be a non-pigmented curing compound with fugitive dye conforming to the requirements of ASTM Designation: C 309, Type 1-D, Class A.

ADMIXTURES.--

General.--Admixtures shall be used when specified or ordered by the Engineer and may be used at the Contractor's option to conserve cement or to facilitate any construction operation.

Calcium chloride shall not be used in any concrete containing reinforcement or other embedded items.

Admixtures shall be combined with concrete materials by methods that produce uniform properties throughout the concrete.

If more than one admixture is used, said admixtures shall be compatible with each other so that the desirable effects of all admixtures will be realized.

Mineral admixtures may be used to replace up to 15 percent of Type II portland cement provided the weight of mineral admixture used is not less than the weight of cement replaced. Mineral admixtures shall not be used to replace Type IP (MS) Modified or Type III cements. Chemical admixtures may be used to reduce up to 5 percent of the portland cement except that the cement content shall not be less than 300 kg/m³. When both chemical and mineral admixtures are used with Type II cement, the weight of cement replaced by mineral admixture may be considered as cement in determining the resulting cement content.

Mineral admixtures will be required in the manufacture of concrete containing aggregates that are determined to be "deleterious" or "potentially deleterious" when tested in accordance with ASTM Designation: C 289. The use of mineral admixture in such concrete shall conform to the requirements in this section except that the use of set retarding admixtures will not be permitted.

When the use of a chemical admixture is specified or is ordered by the Engineer, the admixture shall be used at the rate specified or ordered. If no rate is specified or ordered, or if the Contractor uses a chemical admixture for his own convenience, the admixture shall be used at the dosage normally recommended by the admixture manufacturer.

Chemical admixtures and air-entraining admixtures shall be dispensed in liquid form. Dispensers shall have sufficient capacity to measure at one time the total quantity required for each batch. If more than one liquid admixture is used in the concrete, a separate measuring unit shall be provided for each liquid admixture and dispensing shall be such that the admixtures are not mixed at high concentrations. Unless liquid admixtures are added to premeasured water for the batch, they shall be discharged to flow into the stream of water so that the admixtures are well dispersed throughout the batch.

BAR REINFORCING STEEL.--

Bending.--Reinforcing steel bars shall accurately conform to the dimensions shown on the plans.

Bars shall be bent or straightened in a manner that will not crack or break the material. Bars with kinks or improper bends shall not be used.

Hooks, bends and splices shall conform to the provisions of the Building Code Requirements for Reinforced Concrete of the American Concrete Institute.

MIXING AND TRANSPORTING CONCRETE.--

General.--When a truck mixer or agitator is used for transporting concrete to the delivery point, discharge shall be complete within 1 1/2 hours, or before 250 revolutions of the drum or blades, whichever comes first, after the introduction of cement to the aggregates.

Truck mixers or agitator shall be equipped with electrically or mechanically actuated revolution counters by which the number of revolutions of the drum or blades may readily be verified. The counters shall be of the continuous-registering type, which accurately register the number of revolutions and shall be mounted on the truck so that the Engineer may safely and conveniently inspect

them from alongside the truck. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C or above, a time less than 1 1/2 hours may be required.

When non-agitating hauling equipment is used for transporting concrete to the delivery point, discharge shall be complete within one hour after the introduction of cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C, or above, the time between the introduction of cement to the aggregates and discharge shall not exceed 45 minutes.

Each load of concrete for the work shall be accompanied by a trip ticket, a copy of which shall be delivered to the Engineer at the jobsite. The trip ticket shall show volume of concrete, weight of cement and aggregates, quantity of each admixture, quantity of water including water added at the jobsite, time of day the concrete is batched, and revolution counter readings on transit mix trucks at the times the truck is charged and unloaded.

PART 3.- EXECUTION

PREPARATION.--

Existing concrete construction.--Where fresh concrete joins existing or previously placed concrete or masonry, the contact surfaces of the existing or previously placed material shall be roughened, cleaned, flushed with water and allowed to dry to a surface dry condition immediately prior to placing the fresh concrete. The roughened surface shall be no smoother than a wood trowelled surface. Cleaning of the contact surfaces shall remove laitance, curing compounds, debris, dirt and such other substances or materials which would prevent bonding of the fresh concrete.

Abrasive blast methods shall be used to clean horizontal construction joints to the extent that clean aggregate is exposed.

Exposed reinforcing steel located at the contact surfaces which is to be encased in the fresh concrete shall be cleaned to remove any substance or material that would prevent bonding of the fresh concrete.

Forms.--Forms shall be mortar tight, true to the dimensions, lines, and grades shown on the plans, securely fastened and supported, and of adequate rigidity to prevent distortion during placing of concrete.

Form fasteners shall be removable without chipping, spalling, heating or otherwise damaging the concrete surface. Form ties shall be removed to a depth of at least 25 mm below the surface of the concrete.

The inside surfaces of forms shall be cleaned of all dirt, mortar and foreign material. Forms shall be thoroughly coated with form oil prior to use.

Anchorage and embedded items shall be placed and rigidly secured at their planned locations prior to placing concrete.

Placing reinforcing steel.--Reinforcing steel bars shall be accurately placed to the dimensions shown on the plans.

Bar reinforcement conforming to ASTM Designation: A 615/A 615M, Grade 420, or A 706//A 706M shall be lapped at least 45 diameters.

Bars shall be firmly and securely held in position by means of wiring and approved bar supports. The spacing of supports and ties shall prevent displacement of the reinforcing or crushing of supports.

Tie wire shall be clear of concrete formwork and concrete surfaces.

All reinforcing steel shall be in place and inspected before concrete placement begins. Placing of bars on fresh layers of concrete will not be permitted.

PLACING CONCRETE.--

General.--Concrete shall be placed and consolidated by means of internal vibrators to form dense, homogeneous concrete free of voids and rock pockets.

Forms and subgrade shall be thoroughly moistened with water immediately before placing concrete.

Concrete shall be placed as nearly as possible to its final location and the use of vibrators for extensive shifting of the concrete will not be permitted.

Concrete shall be deposited and consolidated in a continuous operation within limits of construction joints, until the placing of the panel or section is completed.

FINISHING CONCRETE SURFACES.--

Finishing unformed surfaces.--The surface shall be floated with wooden floats.

The floated surface shall be trowelled with steel trowels. Troweling shall form a dense, smooth and true finish. Walkways, pedestrian ramps, stairs and outdoor slabs for pedestrian traffic shall be given a non-slip broom finish unless a different finish is called for on the plans or in these special provisions.

The application of cement dust coat will not be permitted.

Finishing formed surfaces.--Formed concrete surfaces shall be finished by filling holes or depressions in the surface, repairing all rock pockets, and removing fins. All surfaces of formed concrete exposed to view shall have stains and discolorations removed, unsightly bulges removed, and all areas which do not exhibit the required smooth, even surface of uniform texture and appearance shall be sanded with power sanders or other approved abrasive means until smooth, even surfaces of uniform texture and appearance are obtained.

Cement mortar, patching and finishing materials used to finish exposed surfaces of concrete shall closely match the color of surrounding surfaces.

CURING CONCRETE.--

General.--Freshly placed concrete shall be protected from premature drying and excessive cold or hot temperatures.

Concrete surfaces shall be kept moist for a period of at least 5 days by leaving the forms in place or by covering the exposed surfaces using moist rugs, cotton mats or other curing materials approved by the Engineer.

PROTECTING CONCRETE.--

General.--Concrete shall not be placed on frozen or frost covered surfaces.

Concrete shall be protected from damage due to rain, freezing or inclement weather, and shall be maintained at a temperature of not less than 4°C for 72 hours. When required by the Engineer, the Contractor shall provide a written outline of his proposed methods of protecting concrete.

SECTION 12-4. (BLANK)

SECTION 12-5. METALS

12-5.01 WELDED WIRE MESH

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing welded wire mesh in accordance with the details shown on the plans and these special provisions.

Related work.--Wood guardrail shall conform to the requirements specified under "Rough Carpentry" in Section 12-6, "Wood and Plastic," of these special provisions.

SUBMITTALS.--

Product Data.--Manufacturer's technical product data shall be submitted for approval.

PART 2.- PRODUCTS

Welded wire mesh.--

Welded wire mesh shall be commercial quality welded wire mesh, 2.03 mm (14-gage) diameter wire, with openings 50 mm wide x 100 mm high. Mesh shall be hot-dipped galvanized after welding.

PART 3.- EXECUTION.--

INSTALLATION.--

General.--Mesh shall be install snug and stapled to the framing members. Battens shall be nailed to the framing members over the mesh as shown on the plans.

12-5.02 ALUMINUM HANDRAIL AND GUARDRAIL

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of fabricating, furnishing and installing aluminum handrails and guardrail systems in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product data.--Manufacturer's descriptive data for products and processes used in handrails and guardrail systems shall be submitted for approval.

Working drawings.--Working drawings of handrails and guardrails shall be submitted for approval.

Working drawings shall show fabrication and installation for each type of handrail and railing system required including plans, elevations, sections, profiles of rails, fittings, connections and anchors.

Samples.--Two 150 mm long samples of each distinctly different railing member, including handrails, top rails, posts and balusters, shall be submitted for approval.

QUALITY ASSURANCE.--

Single source responsibility.--Handrails and guardrail systems of each type and material shall be obtained from a single manufacturer.

DELIVERY, STORAGE AND HANDLING.--

Storage.--Handrails and guardrail systems shall be stored in clean, dry location, away from uncured concrete and masonry, protected from damage of any kind. Handrails and guardrail systems shall be covered with waterproof paper, tarpaulin, or polyethylene sheeting. Allow for air circulation.

PART 2.- PRODUCTS

MATERIALS.--

Railing elements.--

Railing elements shall conform to ASTM Designation: B 429, Type 6061-T6 aluminum alloy pipe, 4 mm wall thickness and 38 mm diameter.

Brackets, flanges, fittings and anchors.--

Brackets, flanges, fittings and anchors shall be the manufacturer's standard for interconnection of handrail and railing members to other work.

Fasteners.--

Fasteners shall be the same basic metal as the fastened metal. Corrosive metals and metals that are incompatible with the metals joined shall not be used.

Concealed fasteners shall be used for interconnections of handrail and guardrail components and for their attachments to other work except where exposed fasteners are unavoidable or are the standard fastening method for handrail and guardrail systems indicated.

Exposed fasteners shall be Phillips flat head screws unless otherwise noted on the plans.

FABRICATION.--

General.--Handrails and railing systems shall be fabricated to the dimensions and details shown on the plans.

Items shall be preassembled in the shop to the greatest extent possible to minimize field splicing and assembly. Units shall be disassembled only as necessary for shipping and handling.

Returns shall be made at free ends of handrailing to bring the pipe to within 6 mm of the wall. Ends of railing elements shall be capped. Concealed weeps shall be provided at low points.

Expansion joints shall have pipe sleeves.

Changes in direction of railing members shall be formed by bending members, insertion of prefabricated elbow fittings, radius bends, or by mitering. Elbow bends shall be by using mitered joints.

Welding shall be by the tungsten inert gas arc welding method or the consumable electrode inert gas method. Welding processes that require the use of flux will not be permitted.

All welds shall conform to the requirements of Section 8.15, "Quality of Welds," of the American Welding Society publication No. AWS D 1.1, "Structural Welding Code."

Exposed welds shall be ground smooth and flush.

FINISHES.--

Anodizing.--After fabrication, exposed surfaces of aluminum shall be given a clear anodic oxide coating conforming to the requirements of ASTM Designation: B 580, Type B, Architectural Class I. Surfaces to be coated shall be free of scratches, porosity, inclusions, roll and die marks, cold-shuts, and cracks that will adversely affect the appearance and performance of the anodic coatings.

PART 3.- EXECUTION

INSTALLATION.--

General.--The handrailing shall be erected to line and grade without welding in the field. Installation shall be in accordance with the manufacturer's recommendations. Posts shall be within 3 mm of vertical.

Exposed connections shall be accurately fitted to form tight, hairline joints.

The location of expansion joints shall be in accordance with the manufacturer's recommendation except that joints shall be spaced not closer than 4.6 meter apart and shall be coordinated with joint locations in the support structure.

Railing connections.--Railing ends shall be anchored with manufacturer's standard fittings designed for this purpose, unless otherwise shown on the plans.

Handrails shall be secured with the manufacturer's standard wall brackets and fittings, unless otherwise shown on the plans.

CLEANING.--

General.--Paint, dirt, stains and grout shall be removed without marring or scratching the aluminum surfaces. Solvents and cleaning compounds shall be chemically compatible with the anodic coating and aluminum.

PROTECTION.--

General.--Finishes shall be protected from damage during constructions by use of temporary protective coverings. Coverings are to be removed upon completion of the work.

Finishes damaged during installation and construction shall be restored so that no evidence remains of construction work.

SECTION 12-6. WOOD AND PLASTICS

12-6.01 ROUGH CARPENTRY

PART 1.- GENERAL

Contract No. <Dist>-<Contract_No>

SUMMARY.--

Scope.--This work shall consist of furnishing and installing materials and performing rough carpentry work including wood framing, decking, railing, stairs, and ramps in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product Data.--Manufacturer's material data and installation instructions shall be submitted for framing hardware.

Wood treatment data.--Chemical treatment manufacturer's instructions shall be submitted for the handling, sorting, installation, and finishing of treated materials.

For each type of preservative treatment used, certification by treating plant shall include type of preservative solution and pressure process used, net amount of preservative retained and conformance with the applicable standards of the American Wood Preservers Association.

DELIVERY, HANDLING AND STORAGE.--

Delivery and storage.--Materials shall be kept under cover and dry. All materials shall be protected from exposure to weather and contact with damp or wet surfaces with blocking and stickers. All lumber, plywood and other panels shall be stacked in such a manner to provide air circulation within and around the stacks.

PART 2.- PRODUCTS

LUMBER.--

General.--Lumber shall be manufactured to comply with PS 20, "American Softwood Lumber Standard," and with applicable grading rules of inspection.

Softwood lumber shall be quality grade stamped or shall be accompanied by a certificate of inspection. Inspection certificates or grade stamps shall indicate compliance with the grading requirements of WWPA, WCLIB, RIS, or other approved lumber inspection agencies.

All lumber used shall be nominal sized and dressed S4S unless otherwise specified in these special provisions.

Framing lumber shall be solid stock lumber, Douglas Fir-Larch, and the grades indicated under WCLIB or WWPA rules. Moisture content shall not exceed 19 percent and shall be grade stamped "S-Dry."

DIMENSION LUMBER.--

Except as otherwise shown on the plans, lumber shall have the following grades.

Vertical framing lumber.--

Vertical framing lumber, nominal 51 mm x 51 mm through 102 mm x 102 mm, shall be Construction grade or better.

Vertical framing lumber, nominal 51 mm x 152 mm through 102 mm x 152 mm shall be No. 2 or better.

Horizontal framing lumber.--

Horizontal framing lumber, nominal 51 mm x 102 mm and wider, including joists, shall be No. 2 or better.

Horizontal framing lumber, nominal 102 mm x 102 mm and wider, including joist, shall be No. 1 or better.

Miscellaneous lumber.--

Miscellaneous lumber for support or attachment of other work including rooftop equipment curbs and support bases, cant strips, bucks, nailers, blocking, furring, grounds, stripping and similar members shall be not less than No. 2 or better.

Lumber in contact with concrete or masonry construction shall be pressure treated Douglas Fir or foundation grade Redwood, No. 2 or better.

Trim.--

Exterior trim shall be No. 1 Douglas Fir or Hem Fir.

PLYWOOD PANELS.--

General.--Plywood panels shall comply with Voluntary Product Standard PS1, "U. S. Product Standard for Construction and Industrial Plywood." or American Plywood Association (APA), "Performance Standards and Policies for Structural Use Panels."

Plywood panels shall be Group 1 unless otherwise noted.

Each panel shall be factory marked with APA or other trademark evidencing compliance with grade requirements.

Plywood flooring.--

Plywood flooring shall be APA RATED SHEATHING, Exterior. Span rating shall conform to the joist spacing shown on the plans. Thickness shall be as shown on the plans.

MISCELLANEOUS MATERIALS.--

Rough Carpentry Hardware.--

Steel plates and rolled sections shall be mild, weldable steel, conforming to AISI grades 1016 through 1030 except 1017.

Nails, screws, bolts, nuts, washers shall be commercial quality. Exposed fasteners shall be hot dipped galvanized, aluminum or stainless steel.

Joist hangers, clips and other standard framing hardware shall be ICBO approved, commercial quality, galvanized sheet steel or hot dipped galvanized, of the size shown on the plans.

Concrete pier blocks.--

Concrete pier blocks shall commercial quality manufactured concrete pier blocks.

WOOD TREATMENT BY PRESSURE PROCESS.--

Preservative treatment.--

Preservative treatment shall be copper naphthenate, pentachlorophenol or water-borne arsenicals (ACA, CCA or ACZA).

PART 3.- EXECUTION

INSTALLATION.--

Wood framing.--Wood framing shall be in accordance with Chapter 23 of the Uniform Building Code as amended the 1995 Title 24 California Building Standard Code.

Framing members shall be of sizes and spacing shown on the plans. Unless otherwise shown on the plans, structural members shall not be spliced between supports.

Wood framing shall be accurately cut and assembled to provide closely fitted members. Framing shall be erected true to the lines and grades shown on the plans and shall be rigidly secured in place as shown and as required by recognized standards. Bracing shall be placed wherever necessary to support all loads on the structure during erection.

The size and spacing of fasteners and the edge distance for nails shall be as shown on the plans.

Nailing schedule shall be as shown on the plans and shall comply with the Uniform Building Code.

Stair framing.--Stair framing members shall be of the size and spacing shown on the plans.

Stringers shall be notched to receive treads, risers and supports. Effective depth remaining shall be not less than 89 mm.

Construction panels.--Construction panels shall be attached to the framing as shown on the plans and these special provisions.

Subflooring shall be glued and nailed to the framing system.

Floor sheathing shall be screwed to the framing system and shall be continuous over 2 or more supports. Panels shall be installed with the long dimension across the supports, with end joints staggered 1.25 mm.

SECTIONS 12-7 AND 12-8. (BLANK)

SECTION 12-9. FINISHES

12-9.01 PAINTING

GENERAL.--This work shall consist of preparing surfaces to receive coatings, and furnishing and applying coatings, in accordance with the schedules and details shown on the plans, and these special provisions.

The coatings specified in this section are in addition to any factory finishes, shop priming, or surface treatment specified elsewhere in these special provisions.

SUBMITTALS.--Manufacturer's descriptive data, a materials list, and color samples shall be submitted for approval.

Product descriptive data shall include product description, manufacturer's recommendations for product mixing, thinning, tinting, handling, site environmental requirements, product application and drying time.

Materials list shall include manufacturer's name, trade name, and product numbers for each type coating to be applied.

Color samples shall be manufacturer's color cards, approximately 50 mm x 75 mm, for each color of coating.

REGULATORY REQUIREMENTS.--Coatings and applications shall conform to the rules for control of volatile organic compound emissions adopted by the air quality control district in the air basin in which the coatings are applied.

SITE ENVIRONMENTAL REQUIREMENTS.--Coatings shall not be applied when the air temperature is below 10°C (20°C for varnishes) or when the relative humidity exceeds 75 percent.

The surface to be coated shall be maintained at a minimum temperature of 7°C for a period of 24 hours prior to, and 48 hours after the application of the coating. Heating facilities shall be provided when necessary.

A minimum lighting level of 865 lux, measured 1 m from the surface to be coated, shall be provided while surfaces are being prepared for coatings and during coating applications.

DELIVERY, STORAGE, AND HANDLING.--Products shall be delivered to the site in sealed, labeled containers and stored in a well ventilated area at an ambient air temperature of not less than 7°C. Container labeling shall include manufacturer's name, type of coating, trade name, color designation, drying time, and instructions for tinting, mixing, and thinning.

MAINTENANCE STOCK.--Upon completion of coating work, a full 3.8 liter container of each type and color of finish coat and stain used shall be delivered to the location at the project site designated by the Engineer. Containers shall be tightly sealed and labeled with color, texture, and room locations where used, in addition to the manufacturer's standard product label.

PRODUCTS.--

GENERAL.--The products shall be the best quality grade coatings of the specified types as regularly manufactured by nationally recognized paint and varnish manufacturers that have not less than 10 years experience in manufacturing paints and varnishes. Products that do not bear the manufacturer's identification as the best quality grade product shall not be used. Products for each coating system shall be by a single manufacturer and shall not contain lead type pigments.

Thinners, shellac, fillers, patching compounds, coloring tint, and other products required to achieve the specified finish shall be the manufacturer's best quality and shall be used as recommended.

EXECUTION.--

INSPECTION.--Surfaces to be coated at the jobsite shall be approved by the Engineer prior to the application of coatings. The Contractor shall notify the Engineer at least 3 working days prior to the application of coatings.

SURFACE PREPARATION.--Surfaces scheduled to be coated shall be prepared in accordance with the following, except that the surfaces not specified herein shall be prepared as recommended by the coating manufacturer.

GENERAL.--Hardware, cover plates, light fixture trim, and similar items shall be removed prior to preparing surfaces for coating. Following the application of the finish coating, the removed items shall be reinstalled in their original locations.

WOOD.--Oil and grease shall be removed by solvent wash. Mildew shall be removed by mildew wash. Surfaces to be coated shall be cleaned of all dirt, excess material, or filler by hand cleaning. Smooth surfaced wood shall be sanded lightly.

A sealer composed of equal parts of shellac and alcohol shall be spot applied to knots, sap, pitch, tar, creosote, and other bleeding substances.

After the application of the prime coat, all nail holes, cracks, open joints, dents, scars, and surface irregularities shall be filled, hand cleaned, and spot primed to provide smooth surfaces for the application of finish coats.

DEFINITIONS.--

HAND CLEANING.--Removal of dirt, loose rust, mill scale, excess base material, filler, aluminum oxide, chalking paint, peeling paint, or paint which is not firmly bonded to the surfaces by using hand or powered wire brushes, hand scraping tools, power grinders, or sandpaper and removal of all loose particles and dust prior to coating.

MILDEW WASH.--Removal of mildew by scrubbing with a solution of detergent, hypochlorite-type household bleach, and warm water, and removal of all solution and residues with clean water.

SOLVENT WASH.--Removal of oil, grease, wax, dirt, or other foreign matter by using solvents, such as mineral spirits or xylol, or other approved cleaning compounds.

PROTECTION.--The Contractor shall provide protective devices, such as tarps, screens or covers, as necessary to prevent damage to the work and to other property or persons from all cleaning and painting operations.

Paint or paint stains on surfaces not designated to be painted shall be removed by the Contractor at his expense and the original surface restored to the satisfaction of the Engineer.

APPLICATION.--

GENERAL.--Coatings shall be applied in accordance with the printed instructions and at the application rates recommended by the manufacturer to achieve the dry film thickness specified in these special provisions.

Mixing, thinning and tinting shall conform to the manufacturer's printed instructions. Thinning will be allowed only when recommended by the manufacturer.

Coatings shall be applied only when surfaces are dry and properly prepared.

Cleaning and painting shall be scheduled so that dust and other contaminants from the cleaning process will not fall on wet, newly coated surfaces.

Materials required to be coated shall have coatings applied to all exposed surfaces.

APPLICATION SURFACE FINISH.--Each coat shall be applied to a uniform finish. Finished surfaces shall be free of surface deviations and imperfections such as skips, cloudiness, spotting, holidays, laps, brush marks, runs, sags, curtains,

ropiness, improper cutting in, overspray, drips, ridges, waves, and variations in color and texture.

Each application of a multiple application finish system shall closely resemble the final color coat, except each application shall provide enough contrast in shade to distinguish the separate applications.

WORK REQUIRED BETWEEN APPLICATIONS.--Each application of material shall be cured in accordance with the coating manufacturer's recommendations before applying the succeeding coating. Enamels and clear finishes shall be lightly sanded, dusted, and wiped clean between applications.

Stain blocking primer shall be spot applied whenever stains bleed through the previous application of a coating.

TIMING OF APPLICATIONS.--The first application of the specified coating system shall be applied prior to any deterioration of the newly prepared surface. Additional prime coats shall be applied as soon as drying time of the preceding coat permits.

APPLICATION METHODS.--Coatings shall be applied by brush, roller or spray. Rollers shall be of a type which do not leave a stippled texture in the paint film. Extension handles for rollers shall not be greater than 2 m in length.

If spray methods are used, surface deviations and imperfections such as, overspray, thickness deviations, lap marks, and orange peel shall be considered as evidence that the work is unsatisfactory and the Contractor shall apply the remainder of the coating by brush or roller, as approved by the Engineer.

BACKPRIMING.--The first application of the specified coating system shall be applied to all wood surfaces (face, back, edges, and ends) of wood materials that are not factory coated, immediately upon delivery to the project site.

CLEANING.--Upon completion of all operations, the coated surfaces shall be thoroughly cleaned of dust, dirt, grease, or other unsightly materials or substances.

Surfaces marred or damaged as a result of the Contractor's operations shall be repaired, at his expense, to match the condition of the surfaces prior to the beginning of the Contractor's operations.

COATING SYSTEMS.--The surfaces to be coated shall be as shown on the plans and as specified elsewhere in these special provisions. When a coating system is not shown or specified for a surface to be finish coated, the coating system to be used shall be as specified for the substrate material. The number of applications specified for each coating system listed herein is a minimum. Additional coats shall be applied if necessary to obtain a uniform color, texture, appearance, or required dry film thickness.

SYSTEM 1- WOOD, PAINTED.--

- 1 prime coat: alkyd, exterior wood primer
- 2 finish coats: acrylic, exterior enamel, semi-gloss

COLOR SCHEDULE.--Colors shall be from the manufacturer's standard color palette.

SLIP RESISTANT SURFACING.--Ramp surfaces shown on the plans to be slip resistant shall have an evenly broadcast of silica sand immediately after the application of the first finish coat.

SECTIONS 12-10 THROUGH 12-12. (BLANK)

SECTION 12-13. SPECIAL CONSTRUCTION

12-13.01 CANOPY COVER

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing an aluminum framed canopies with fabric covering in accordance with the details shown on the plans and these special provisions.

SUBMITTALS.--

Product Data.--Manufacturer's product data, standard fabric color palette, and installation instructions shall be submitted for approval.

Product data shall include the manufacturer's name and a complete material description of all components of the system.

Fabric covering color will be selected from the manufacturer's standard color palette.

Samples.--Three samples of the fabric approximately 300 mm x 300 mm shall be submitted.

Working Drawings.--Working drawings showing the layout and details of the installation shall be submitted for approval.

Working drawings shall show the shape, size, thickness, and method of attachment for each component used in the work.

PART 2.- PRODUCTS

Framing.--

Framing elements shall be Schedule 40 aluminum pipe conforming to ASTM Designation: B 429, Type 6061-T6 alloy.

Fasteners.--

Fasteners shall be the aluminum.

Fabric.--

Fabric shall be woven vinyl-coated polyester mesh fabric, resistant to ultraviolet light, mildew and water. Fabric shall have approximately 30 percent openness factor and weight approximately 275 grams per square meter. Fabric shall be flame retardant.

FABRICATION.--

General.--Canopy frames shall be fabricated to the dimensions and details shown on the approved shop plans.

Items shall be preassembled in the shop to the greatest extent possible to minimize field splicing and assembly. Units shall be disassembled only as necessary for shipping and handling.

Welding shall be by the tungsten inert gas arc welding method or the consumable electrode inert gas method. Welding processes that require the use of flux will not be permitted.

All welds shall conform to the requirements of Section 8.15, "Quality of Welds," of the American Welding Society publication No. AWS D 1.1, "Structural Welding Code."

Exposed welds shall be ground smooth and flush.

PART 3.- EXECUTION.--

INSTALLATION.--

General.--Canopy frames shall be installed true and plumb, and shall be free of twists, kinks, and dents.

Canopy frames and fabric covering shall be installed as shown on the approved shop drawings.

SECTION 12-14. (BLANK)

SECTION 12-15. MECHANICAL

12-15.01 MECHANICAL WORK

GENERAL.--

Scope.--This work shall consist of performing mechanical work in accordance with the details shown on the plans and these special provisions.

Mechanical work shall include furnishing all labor, materials, equipment and services required for providing plumbing systems.

Earthwork, foundations, sheet metal, painting, electrical, and such other work incidental and necessary to the proper installation and operation of the mechanical work shall be in accordance with the requirements specified for similar type work elsewhere in these special provisions.

System layouts are generally diagrammatic and location of equipment is approximate. Exact routing of pipes and location of equipment is to be governed by structural conditions and obstructions. Equipment requiring maintenance and inspection is to be readily accessible.

SUBMITTALS.--

Product data.--A list of materials and equipment to be installed, manufacturer's descriptive data, and such other data as may be requested by the Engineer shall be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions for plumbing fixtures, and component layout shall be included where applicable.

Manufacturer's descriptive data shall be submitted for the following:

- Pipe
- Valves
- Cleanouts
- Hose and fittings

QUALITY ASSURANCE.--

Codes and standards.--Mechanical work, including equipment, materials and installation, shall conform to the California Building Standards Code, Title 24, and to the California Code of Regulations, Title 8, Chapter 4, Division of Industrial Safety (DIS).

WARRANTY.--

Warranties and guarantees.--Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

12-15.02 PIPE, FITTINGS AND VALVES

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing pipes, fittings and valves in accordance with the details shown on the plans and these special provisions. Pipe, fittings and valves shall include such plumbing and piping accessories and appurtenances, not mentioned, that are required for the proper installation and operation of the plumbing and piping systems.

The pipe sizes shown on the plans are nominal pipe size (NPS). No change in the pipe size shown on the plans shall be permitted without written permission from the Engineer.

The pipe and fitting classes and material descriptions shall be as specified herein. No change in class or description shall be permitted without written permission from the Engineer.

QUALITY ASSURANCE.--

Codes and standards.--Pipe, fittings and valves shall be installed in accordance with the requirements in the latest edition of the Uniform Plumbing Code, the manufacturer's recommendations and the requirements specified herein.

PART 2.- PRODUCTS

MATERIALS.--

PIPE AND FITTINGS --

Class	Description
--------------	--------------------

A1.--

Schedule 40 galvanized steel pipe conforming to ASTM Designation: A 53, with 1040 kPa galvanized malleable iron banded screwed fittings and galvanized steel couplings. The weight of the zinc coating shall be not less than 90 percent of that specified in ASTM Designation: A 53.

C1.--

Hub and plain end cast iron soil pipe with neoprene gaskets conforming to Cast Iron Soil Pipe Institute's Standard 301. Pipe, fittings and gaskets shall be of one manufacturer.

C2.--

Hubless cast iron soil pipe with neoprene gaskets, corrugated stainless steel shields and stainless steel clamps conforming to Cast Iron Soil Pipe Institute's Standard 301. Joint materials shall be furnished by pipe manufacturer.

P1.--

Polyvinyl chloride (PVC) gravity sewer plastic pipe and fittings conforming to ASTM Designation: D 3034, Standard Dimension Ratio (SDR) 35, with integral bell and bell and spigot rubber gasketed joints or conforming to ASTM Designation: D2665 with solvent welded fittings. Rubber gaskets shall conform to ASTM Designation: F 477. Stainless steel clamps with rubber boots shall not be used.

P2.--

Polyvinyl chloride (PVC) plastic pipe and fittings conforming to ASTM Designation: D 2241, Type I, Grade 1, Standard Dimension Ratio (SDR) 21, rated for 1380 kPa working pressure at 23°C, National Sanitation Foundation approved. Pipe shall have bell ends conforming to ASTM Designation: D 3139 with triple edge rubber sealing ring. For pipe sizes NPS 2 diameter and smaller, plain end pipe with solvent welded fittings ASTM Designation: D 2241, Type I, Grade 1, Standard Dimension Ratio (SDR) 21, rated for 1380 kPa may be used.

P3.--

Polyvinyl chloride (PVC) standard weight pipe and fittings, Schedule 40, conforming to ASTM Designation: D 1785. Pipe shall meet or exceed requirements of National Sanitation Foundation Standard No. 14. Pipe shall have bell ends conforming to ASTM Designation: D 2672. For pipe sizes NPS 3 and smaller, plain end pipe with solvent welded fittings conforming to ASTM Designation: D 2241, may be used.

Unions (for steel pipe).--

Unions (for steel pipe) shall be 1730 kPa, threaded malleable iron, ground joint, brass to iron seat, galvanized or black to match piping.

VALVES.--

Gate valve (NPS 2 1/2 and smaller).--

Gate valve (NPS 2 1/2 and smaller) shall be bronze body and trim, removable bonnet and non rising stem, Class 125 and same size as pipe in which installed. Gate valve shall be Crane, 438; Nibco Scott, T-113; Jenkins, 370; or equal.

Gate valve in nonferrous water piping systems may be solder joint type with bronze body and trim. Valve shall be Kitz, 59; Nibco Scott, S-113; Jenkins, 1240; or equal.

FAUCET AND HYDRANTS.--

Hose faucet.--

Hose faucet shall be compression type, angle pattern, wall flange at exterior locations, tee handle, NPS 3/4 female thread with hose end, rough chrome or nickel plated finish for locations inside building, rough brass finish for others. Hose faucet shall be supplied with an integral or nonremovable threaded outlet vacuum breaker which meets the requirements of

the American Society of Sanitary Engineering (ASSE) Standard: 1011. Hose faucet shall be Nibco, No. 63VB; Chicago, No. 13T; or equal.

CLEANOUTS.--

Cleanout to grade.--

Cleanout to grade shall be cast iron ferrule type. Plug shall be countersunk brass or bronze with tapered threads. Cleanout to grade shall be Wade, No. W-8450; Smith, 4420; Zurn, No 1440; or equal.

MISCELLANEOUS ITEMS.--

Pipe wrapping tape and primer.--

Pipe wrapping tape shall be pressure sensitive polyvinyl chloride or pressure sensitive polyethylene tape having nominal thickness of 0.50 mm. Wrapping tape shall be Polyken, 922; Manville, Trantex VID-20; Scotchrap, 51; or equal.

Pipe wrapping primer shall be compatible with the pipe wrapping tape used.

Hose.--

Hose shall be FDA approved for drinking water, textile braid reinforced with an abrasive resistant cover. The hose shall have a minimum bend radius of 3 times the hose diameter and shall be rated for a working pressure of 1200 kPa. The hose ends shall be stainless steel rated for the same working pressure as the hose with ends to match the pipe inlet and modular building inlet. One end shall include a union for easy removal.

PART 3.- EXECUTION

INSTALLATION.--

INSTALLATION OF PIPES AND FITTINGS.--

Pipe and fittings.--Pipe and fittings shall be installed in accordance with the following designated uses:

Designated Use	Pipe and Fitting Class
Domestic water underground within 1.5 m of the building	A1
Domestic water underground 1.5 m beyond the building	P2 or P3
Sanitary drain piping above ground in building	C1, or C2
Sanitary drain and vent piping underground within 1.5 m of the building	P1
Sanitary drain pipe, 1.5 m beyond the building	P1

Installing piping.--Water piping shall be installed generally level, free of traps and bends, and arranged to conform to the building requirements.

Drainage pipe shall be run as straight as possible and shall have easy bends with long turns.

Wye fittings and 1/8 or 1/16 bends shall be used where possible. Long sweep bends and combination Wye and 1/8 bends may be used only for the connection of branch pipes to fixtures and on vertical runs of pipe.

Water pipe near sewers.--Water pipe shall not be installed below sewer pipe in the same trench or at any crossing, or below sewer pipe in parallel trenches less than 3 m apart.

When a water pipe crosses above a sewer pipe, a vertical separation of at least 300 mm between the top of the sewer and the bottom of the water pipe shall be maintained.

When water and sewer pipe is installed in the same trench, the water pipe shall be on a solid shelf at least 300 mm above the top of the sewer pipe and 300 mm to one side.

Pipe sleeves.--The Contractor shall provide sleeves, inserts and openings necessary for the installation of pipe, fittings and valves. Damage to surrounding surfaces shall be patched to match existing.

PVC pipe sleeves shall be provided where each pipe passes through concrete floors, footings, walls or ceilings. Inside diameter of sleeves shall be at least 20 mm larger than outside diameter of pipe. Sleeves shall be installed to provide at least 10 mm space all around pipe the full depth of concrete. Space between pipes and pipe sleeves shall be caulked watertight.

Cutting pipe.--All pipe shall be cut straight and true and the ends shall be reamed to the full inside diameter of the pipe after cutting.

Damaged pipe.--Pipe that is cracked, bent or otherwise damaged shall be removed from the work.

Pipe joints and connections.--Joints in threaded steel pipe shall be made with teflon tape or a pipe joint compound that is nonhardening and noncorrosive, placed on the pipe and not in the fittings.

The use of thread cement or caulking on threaded joints will not be permitted. Threaded joints shall be made tight. Long screw or other packed joints will not be permitted. Any leaky joints shall be remade with new material.

Cleaning and closing pipe.--The interior of all pipe shall be cleaned before installation. All openings shall be capped or plugged as soon as the pipe is installed to prevent the entrance of any materials. The caps or plugs shall remain in place until their removal is necessary for completion of the installation.

Wrapping and coating steel pipe.--Steel pipe buried in the ground shall be wrapped or shall be plastic coated as specified herein:

1. Wrapped steel pipe shall be thoroughly cleaned and primed as recommended by the tape manufacturer.
2. Tapes shall be tightly applied with 1/2 uniform lap, free from wrinkles and voids with approved wrapping machines and experienced operators to provide not less than 1.00 mm thickness.
3. Plastic coating on steel pipe shall be factory applied. Coating imperfections and damage shall be repaired to the satisfaction of the Engineer.

4. Field joints, fittings and valves for wrapped and plastic coated steel pipe shall be covered to provide continuous protection by puttying and double wrapping with 0.50 mm thick tape. Wrapping at joints shall extend a minimum of 150 mm over the adjacent pipe covering. Width of tape for wrapping fittings shall not exceed 50 mm. Adequate tension shall be applied so tape will conform closely to contours of fittings. Putty tape insulation compounds approved by the Engineer shall be used to fill voids and provide a smooth even surface for the application of the tape wrap.

Wrapped or coated pipe, fittings, and filed joints shall be approved by the Engineer after assembly. Piping shall be placed on temporary blocks to allow for inspection. Deficiencies shall be repaired to the satisfaction of the Engineer before backfilling or closing in.

Thrust blocks.--Thrust blocks shall be formed by pouring concrete between pipe and trench wall. Thrust blocks shall be sized and so placed as to take all thrusts created by maximum internal water pressure.

Plastic pipe underground shall be provided with thrust blocks and clamps at changes in direction of piping, connections or branches from mains NPS 2 and larger, and all capped connections.

INSTALLATION OF CLEANOUTS.--

Cleanouts.--A concrete pad 0.5 m long and 100 mm thick shall be placed across the full width of trench under cleanout Wye or 1/8 bend. Cast iron soil pipe (C1 or C2) and fittings shall be used from Wye to surface. Required clearance around cleanouts shall be maintained.

Cleanout risers outside of a building installed in a surface other than concrete shall terminate in a cleanout to grade. Cleanout to grade shall terminate in a valve box with cover marked "CO-SS". Top of box shall be set flush with finished grade. Cleanout plug shall be 100 mm below grade and shall be located in the box to provide sufficient room for rodding.

Cleanout risers installed in tile and concrete floors, including building aprons and sidewalks, shall terminate in a cleanout through floor.

INSTALLATION OF MISCELLANEOUS ITEMS.--

Chlorination.--All domestic water piping and facilities shall be flushed and chlorinated by disinfecting solutions.

Calcium hypochlorite granules or tablets, if used, shall not be applied in the dry form, but shall first be dissolved into a solution before application.

The Contractor shall take adequate precautions in handling chlorine so as not to endanger workmen or damage materials. All pipes and fittings shall be completely filled with water containing a minimum of 50 ppm available chlorine. Each outlet in the system shall be opened and water run to waste until a strong chlorine test is obtained. The line shall then be closed and the chlorine solution allowed to remain in the system for a minimum of 24 hours so that the line shall contain no less than 25 ppm chlorine throughout. After the retention period, the system shall be drained, flushed and refilled with fresh water.

FIELD QUALITY CONTROL.--

Testing.--The Contractor shall test piping at completion of roughing in, before backfilling, and at other times as directed by the Engineer.

The system shall be tested as a single unit, or in sections as approved by the Engineer. The Contractor shall furnish necessary materials, test pumps,

instruments and labor and notify the Engineer at least 3 working days in advance of testing. After testing, the Contractor shall repair all leaks and retest to determine that leaks have been stopped. Surplus water shall be disposed of after testing as directed by the Engineer.

The Contractor shall take precautions to prevent joints from drawing while pipes and appurtenances are being tested. The Contractor shall repair damage to pipes and appurtenances or to other structures resulting from or caused by tests.

General tests.--All piping shall be tested after assembly and prior to backfill, pipe wrapping, connecting fixtures, wrapping joints and covering the pipe. Systems shall show no loss in pressure or visible leaks.

The Contractor shall test systems according to the following schedule for a period of not less than 4 hours:

Test Schedule		
Piping System	Test Pressure	Test Media
Sanitary sewer and vent	250 mm head	Water
Water	860 kPa	Water

During testing of water systems, valves shall be closed and pipeline filled with water. Provisions shall be made for release of air.

Sanitary sewers shall be cleared of obstructions before testing for leakage. The pipe shall be proved clear of obstructions by pulling an appropriate size inflatable plug through the pipe. The plug shall be moved slowly through the pipe with a tag line. The Contractor shall remove or repair any obstructions or irregularities.

Sanitary sewer pipes beyond 1.5 m perpendicular to the building shall be tested for leakage for a period of not less than 4 hours by filling with water to an elevation of 1.2 m above average invert of sewer or to top of manholes where less than 1.2 m deep. The system shall show no visible leaks. The sewer may be tested in sections with testing water progressively passed down the sewer as feasible. Water shall be released at a rate that will not create water hammer or surge in plugged sections of sewer.

SECTION 12-16. ELECTRICAL

12-16.01 ELECTRICAL WORK

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of performing electrical work in accordance with the details shown on the plans and these special provisions.

Electrical work shall include furnishing all labor, materials, equipment and services required to construct and install the complete electrical system shown on the plans and the work of installing electrical connections specified elsewhere in these special provisions.

System layouts are generally diagrammatic and location of equipment is approximate. Exact routing of conduits and other facilities and location of

equipment is to be governed by structural conditions and other obstructions, and shall be coordinated with the work of other trades. Equipment requiring maintenance and inspection shall be located where it is readily accessible for the performance of such maintenance and inspection.

Related work.--Earthwork, foundations, sheet metal, painting, mechanical and such other work incidental to and necessary for the proper installation and operation of the electrical work shall be done in accordance with the requirements specified for similar work elsewhere in these special provisions.

CLOSEOUT SUBMITTALS.--

Operation and maintenance manuals.--Prior to the completion of the contract, 3 identified copies of the operation and maintenance instructions with parts lists for the equipment specified herein shall be delivered to the Engineer at the jobsite. The instructions and parts lists shall be in a bound manual form and shall be complete and adequate for the equipment installed. Inadequate or incomplete material will be returned. The Contractor shall resubmit adequate and complete manuals at no expense to the State.

QUALITY ASSURANCE.--

Codes and standards.--All work performed and materials installed shall be in accordance with the National Electrical Code; the California Building Standards Code, Title 24, Part 3, "California Electrical Code," and the California Code of Regulations, Title 8, Chapter 4, "Electrical Safety Orders," and all local ordinances.

Warranties and guarantees.--Manufacturer's warranties and guarantees for materials or equipment used in the work shall be delivered to the Engineer at the jobsite prior to acceptance of the contract.

TESTING.--

After the electrical system installation work has been completed, the electrical system shall be tested in the presence of the Engineer to demonstrate that the electrical system functions properly. The Contractor shall make necessary repairs, replacements, adjustments and retests at his expense.

12-16.02 BASIC MATERIALS AND METHODS

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing conduits, conductors, fittings, and wiring devices in accordance with the details shown on the plans and these special provisions.

Conduits, conductors, fittings, and wiring devices shall include those accessories and appurtenances, not mentioned, that are required for the proper installation and operation of the electrical system.

SUBMITTALS.--

Product data.--A list of materials and equipment to be installed, manufacturer's descriptive data, and such other data as may be requested by the Engineer shall be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions for recessed junction and pull boxes, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

PART 2.- PRODUCTS

CONDUITS AND FITTINGS.--

Rigid steel conduit and fittings.--

Rigid steel conduit shall be threaded, full weight rigid steel, hot-dip galvanized inside and outside with steel or malleable iron fittings. Fittings shall be threaded unless otherwise specified or shown on the plans.

Split or three-piece couplings shall be electroplated, malleable cast iron couplings.

Insulated grounding bushings shall be threaded malleable cast iron body with plastic insulated throat and steel, lay-in ground lug with compression screw.

Insulated metallic bushings shall be threaded malleable cast iron body with plastic insulated throat.

Electrical metallic tubing (EMT) and fittings.--

Electrical metallic tubing shall be formed of cold rolled strip steel, electrical resistance welded continuously along the longitudinal seam with zinc coating outside and enamel or lacquer coating inside.

Couplings shall be electroplated, rain and concrete tight, gland compression type, steel body couplings with malleable iron nuts.

Connectors shall be electroplated, rain and concrete tight, gland compression type, steel body connectors with male hub, malleable iron nut and insulated plastic throat.

Flexible metallic conduit and fittings.--

Flexible metallic conduit shall be fabricated in continuous lengths from galvanized steel strip, spirally wound and formed to provide an interlocking design.

Fittings shall be electroplated screw-in type with malleable cast iron body and threaded male hub with insulated throat.

Liquid tight flexible metallic conduit and fittings.--

Liquid tight flexible metallic conduit shall be fabricated in continuous length from galvanized sheet steel, spirally wound and formed to provide an interlocking design with an extruded polyvinyl chloride cover.

Fittings shall be electroplated, malleable cast iron body, with cap nut, grounding ferrule, and connector body with insulated throat.

CONDUCTORS.--

Conductors.--

Conductors shall be stranded copper wire.

Conductor insulation types unless otherwise shown or specified, shall be as follows:

1. Conductors shall be type XHHW in wet and outdoor locations.
2. Conductors shall be type THHN in dry locations.

Wire connections and devices.--

Wire connections and devices shall be pressure or compression type, except that connectors for No. 10 AWG and smaller conductors in dry locations may be preinsulated spring-pressure type.

ELECTRICAL BOXES.--

Outlet, device and junction boxes.--

Unless otherwise shown or specified, boxes shall be galvanized steel boxes with knock-outs and shall be the size and configuration best suited to the application indicated on the plans. Minimum size of outlet, receptacle, switch or junction boxes shall be 100 mm square by 40 mm deep, except that switch boxes for the installation of single switches and outlet boxes for flush-mounted light fixtures shall be 50 mm by 75 mm by 40 mm deep.

Cast metal boxes shall be cast iron boxes with threaded hubs and shall be of the size and configuration best suited to the application shown on the plans.

Flush-mounted boxes shall have stainless steel covers, 1 mm thick. Cover screws shall be metal with finish to match cover finish.

Unless otherwise shown or specified, surface-mounted boxes shall have galvanized steel covers with metal screws.

Weatherproof junction boxes shall have cast metal covers with gaskets.

Weatherproof switch and receptacle boxes shall have gasketed covers with gasketed hinged flaps to cover switches and receptacles.

Underground pull boxes.--

Pull boxes shall be high density reinforced concrete box with ultraviolet inhibitor polyethylene etched face anchored in concrete and fiberglass cover with hold down bolts. The polyethylene and fiberglass material shall be fire resistant and show no appreciable change in physical properties with exposure to the weather. No. 3 1/2 pull box shall be Brooks Products, No. 3 1/2; Christy Concrete Products, N9; or equal. No. 5 pull box shall be Brooks Products No. 5; Christy Concrete Products, N30; or equal.

Traffic rated pull boxes shall be high density reinforced concrete box with steel cover with hold down bolts and bonding strap. Pull box and cover

shall be designed for H20 loading. No. 3 1/2 pull box shall be 250 mm by 430 mm and No. 5 pull box shall be 320 mm by 610 mm.

MISCELLANEOUS MATERIALS.--

Warning Tape.--

Warning tape shall be 100 mm wide and contain the printed warning "CAUTION ELECTRICAL CONDUIT" in bold 19 mm black letters at 760 mm intervals on bright orange or yellow background. The printed warning shall be non-erasable when submerged under water and resistant to insects, acids, alkali, and other corrosive elements in the soil. The tape shall have a tensile strength of not less than 70 kg per 100 mm wide strip and shall have a minimum elongation of 700 percent before breaking.

Pull ropes.--

Pull ropes shall be nylon or polypropylene with a minimum tensile strength of 225 kg.

Watertight conduit plugs.--

Watertight conduit plugs shall be a hollow or solid stem expansion plugs complete with inner and outer white polypropylene compression plates and red thermoplastic rubber seal. Seal material shall be non-stick type rubber resistant to oils, salt, and alkaline substances normally available at the construction sites.

Anchorage devices.--

Anchorage devices shall be corrosion resistant, toggle bolts, wood screws, bolts, machine screws, studs, expansion shields, and expansion anchors and inserts.

Electrical supporting devices.--

Electrical supporting devices shall be one hole conduit clamps with clamp backs, hot-dipped galvanized, malleable cast iron.

Construction channel shall be 41 mm x 41 mm, 2.66 mm (12-gage) galvanized steel channel with 13 mm diameter bolt holes, 40 mm on center in the base of the channel.

Ground rod(s).--

Ground rod(s) shall be a 19 mm (minimum) galvanized or copper clad steel rod, 3 meters long.

PART 3.- EXECUTION

INSTALLATION.--

Conduit, general.--Rigid steel conduit shall be used unless otherwise shown on the plans or specified in these special provisions.

Electrical metallic tubing may be used in furred spaces and for exposed work indoors above the switch height.

Unless otherwise specified or shown on the plans, flexible metal conduit shall be used to connect equipment subject to vibration in dry locations.

Unless otherwise specified or shown on the plans, liquid-tight flexible metal conduit shall be used to connect equipment subject to vibration in wet locations.

Conduit installation.--Conduit trade sizes are shown on the plans. No deviation from the conduit size shown on the plans will be permitted without written permission from the Engineer.

Conduit shall be concealed unless otherwise shown on the plans.

Conduits shall be tightly covered and well protected during construction using metallic bushings and bushing "pennies" to seal open ends.

Rigid non-metallic conduit bends of 30 degrees or greater shall be factory-made long radius sweeps. Bends less than 30 degrees shall be made using an approved heat box.

A pull rope shall be installed in all empty conduits. At least one meter of pull rope shall be doubled back into the conduit at each termination.

Locations of conduit runs shall be planned in advance of the installation and coordinated with the ductwork, plumbing, ceiling and wall construction in the same areas and shall not unnecessarily cross other conduits or pipe, nor prevent removal of ceiling tiles or panels, nor block access to mechanical or electrical equipment.

Where practical, conduits shall be installed in groups in parallel, vertical or horizontal runs and at elevations that avoid unnecessary offsets.

Exposed conduit shall be installed parallel and at right angles to the building lines.

Conduits shall not be placed closer than 300 mm from a parallel hot water or steam pipe or 75 mm from such lines crossing perpendicular to the runs.

All raceway systems shall be secured to the building structures using specified fasteners, clamps and hangers.

Single conduit runs shall be supported by using one hole pipe clamps. Where run horizontally on walls in damp or wet locations, conduit shall be installed with "clamp backs" to space conduit off the surface.

Multiple conduit runs shall be supported with construction channel secured to the building structure. Conduits shall be fastened to construction channel with channel compatible pipe clamps.

Raceways of different types shall be joined using approved couplings or transition fittings.

Expansion couplings shall be installed where conduit crosses a building separation or expansion joint.

All floor and wall penetrations shall be sealed water-tight.

Conduit terminations.--Rigid steel conduits shall be securely fastened to cabinets, boxes and gutters using 2 locknuts and specified insulating metallic bushing. Electrical metallic tubing shall be securely fastened to cabinets, boxes and gutters using specified connectors. Conduit terminations at exposed weatherproof enclosures and cast outlet boxes shall be made watertight using specified hubs.

Grounding bushings with bonding jumpers shall be installed on all type of conduits terminating at concentric knockouts and on all conduits containing service conductors, grounding electrode conductor, and conductors feeding separate buildings.

Warning Tape.--Warning tape shall be placed over each conduit in a trench. Each warning tape shall be centered over the conduit and shall be placed over the 150 mm layer of sand covering the conduit as described elsewhere in these special provisions.

Conductor and cable installation.--Conductors shall not be installed in conduit until all work of any nature that may cause injury is completed. Care

shall be taken in pulling conductors that insulation is not damaged. An approved non-petroleum base and insulating type pulling compound shall be used as needed.

All cables shall be installed and tested in accordance with manufacturer's recommendations.

Splices and joints shall be insulated with insulation equivalent to that of the conductor.

Provide 155 mm of slack at each outlet and device connection. If the outlet or device is not at the end of a run of wire, connection shall be made with correctly colored pigtails tapped to the runs with splices as specified herein.

Branch circuit conductors in panelboards and load centers shall be neatly trained along a path from the breaker terminals to their exit point. The conductors shall have ample length to transverse the path without strain, but shall not be so long as to require coiling, doubling back, or cramming. The path shall transverse the panelboard gutter spaces without entering a gutter containing service conductors and, unless otherwise shown on the plans, without entering the gutter space of any panelboard feeder.

All pressure type connectors and lugs shall be retightened after the initial set.

Splices in underground pull boxes and similar locations shall be made watertight.

Junction boxes in furred or accessible ceiling spaces shall be identified with felt-tip pen denoting the circuits contained in the box.

Conductor identification.--The neutral and equipment grounding conductors shall be identified as follows:

Neutral conductor shall have a white or natural gray insulation except that conductors No. 4 and larger may be identified by distinctive white marker such as paint or white tape at each termination.

Equipment grounding conductor shall be bare or insulated. If insulated, equipment grounding conductors shall have green or green with one or more yellow stripes insulation over its entire length except that conductors No. 4 and larger may be permanently identified by distinctive green markers such as paint or green tape over its entire exposed insulation.

Feeder and branch circuit ungrounded conductors shall be color coded by continuously colored insulation, except conductors No. 6 AWG or larger may be color coded by colored tape at each connection and where accessible. Ungrounded conductor color coding shall be as follows:

SYSTEM	COLOR CODE
120/240V-Single phase	Black, blue

Where more than one branch circuit enters or leaves a conduit, panel, gutter, or junction box, each conductor shall be identified by its panelboard and circuit number. All control conductors including control conductors of manufacturer supplied and field wired control devices shall be identified at each termination with the wire numbers shown on the plans, approved working drawings, and as directed by the Engineer where deemed necessary. Identification shall be made with one of the following:

1. Adhesive backed paper or cloth wrap-around markers with clear, heat shrinkable tubing sealed over either type of marker.
2. Self-laminating wrap around type, printable, transparent, permanent heat bonding type thermoplastic film markers.
3. Pre-printed, white, heat-shrinkable tubing.

Each terminal block shall have a molded marking strip attached with screws. The identifying numbers of the terminating conductors, as shown on the plans or on the submittal drawings, shall be engraved in the marking strip.

Outlet, device and junction box installation.--Where one or more threaded steel conduits are required to connect to an outlet, device, or junction box, the box shall be a cast metal box with threaded hubs. Unless otherwise shown on the plans or specified in these special provisions, all other boxes shall be sheet steel boxes. Weatherproof outlet, device and junction boxes shall have cast metal covers with gaskets. Unless otherwise shown on the plans or specified in these special provisions, all other boxes shall have standard galvanized covers.

All boxes shall finish flush with building walls, ceiling and floors except where exposed work is called for.

Raised device covers (plaster rings) shall be installed on all boxes concealed in concrete, masonry or stud walls.

No unused openings shall be left in any box. Knockout seals shall be installed as required to close openings.

Outlet, device, and junction boxes shall be installed at the locations and elevations shown on the plans or specified herein. Adjustments to locations may be made as required by structural conditions and to suit coordination requirements of other trades.

Boxes installed in metal stud walls shall be equipped with brackets designed for attaching directly to the studs or shall be mounted on heavy gauge galvanized steel, snap-in box supports.

Underground pull box installation.--Electrical pull box covers or lids shall be marked "ELECTRICAL." Telephone service pull box covers or lids shall have plain, unmarked covers.

The bottom of pull boxes shall be bedded in 155 mm of clean, crushed rock or gravel and shall be grouted with 40 mm thick grout prior to installation of conductors. Grout shall be sloped to a 25 mm PVC pipe drain hole. Conduit shall be sealed in place with grout.

Top of pull boxes shall be flush with surrounding grade or top of curb. In unpaved areas where pull box is not immediately adjacent to and protected by a concrete foundation, pole or other protective construction, the top of pull box shall be set at plus 30 mm above surrounding grade. Pull boxes shown on the plans in the vicinity of curbs shall be placed adjacent to the back of curb.

Ground rod(s) installation.--The ground rod(s) shall be driven vertically until the top is 155 mm above the surrounding surface. When vertical penetration of the ground rod cannot be obtained, an equivalent horizontal grounding system, approved by the Engineer, shall be installed.

Anchorage.--Hangers, brackets, conduit straps, supports, and electrical equipment shall be rigidly and securely fastened to surfaces by means of toggle bolts on hollow masonry; expansion shields and machine screws, or expansion anchors and studs or standard preset inserts on concrete or solid masonry; machine screws or bolts on metal surfaces; and wood or lag screws on wood construction.

Anchorage devices shall be installed in accordance with the anchorage manufacturer's recommendations.

Mounting heights.--Electrical system components shall be mounted at the mounting heights shown on the plans. The mounting height dimensions shall be measured above the finished floor to the bottom of the device or component.

12-16.03 ELECTRICAL EQUIPMENT

PART 1.- GENERAL

SUMMARY.--

Scope.--This work shall consist of furnishing and installing disconnect switches and related accessories in accordance with the details shown on the plans and these special provisions.

Related work.--Anchorage devices shall be as specified under "Basic Materials and Methods" elsewhere in this Section 12-16.

SUBMITTALS.--

Product data.--A list of materials and equipment to be installed, manufacturer's descriptive data, and such other data as may be requested by the Engineer shall be submitted for approval.

Manufacturer's descriptive data shall include complete description, performance data and installation instructions for the materials and equipment specified herein. Control and wiring diagrams, rough-in dimensions, and component layout shall be included where applicable. All control and power conductors on the shop drawings shall be identified with wire numbers.

PART 2.- PRODUCTS

PANELBOARDS.--

Circuit breaker.--

Circuit breaker shall be 240-volt, 250 amperes, 2-pole. The circuit breaker shall be 250 amperes frame, 250 amperes trip. Circuit breaker shall be Square D, Type KA; or equal; and shall fit existing switchboard.

SWITCHES.--

Disconnect switch.--

Disconnect switch shall be 2-pole, 240-volt, AC, 100-ampere, in a NEMA-3R enclosure. The disconnect switch shall be Square D, Catalog No. FA 100 RB; General Electric, Catalog No. TQC 100R; or equal.

MISCELLANEOUS MATERIALS.--

Nameplates.--

Nameplates shall be laminated phenolic plastic with white core and black front and back. Nameplate inscription shall be in capitals letters etched through the outer layer of the nameplate material.

Plywood backing panels.--

Plywood backing panels for mounting electrical or telephone equipment shall be 19 mm, APA plywood panels, C-D PLUGGED and touch-sanded, Exposure 1.

Paint.--

Plywood backing panels shall receive the following paint system: one prime coat, alkyd, interior wood primer and 2 finish coats, acrylic, interior enamel, semi-gloss.

PART 3.- EXECUTION

INSTALLATION.--

Plywood backing board.--Plywood backing board shall be securely fastened to walls or other vertical framing.

Surface to be coated shall be cleaned of all dirt, excess materials, of filler by hand cleaning.

Coatings shall be applied in accordance with the manufacturer's instructions. Each coat shall be applied to a uniform finish, free of skips, brush marks, laps or other imperfections.

Existing panelboards.--Provide new circuit breakers, where required to match existing type unless otherwise shown on the plans. Provide mounting hardware, bus straps, and related materials for proper circuit breaker installation. Provide new panelboard identification nameplate with designation as shown for each panelboard. Remove existing nameplates where applicable. Provide new typewritten circuit directory reflecting changes made under the Contract.

Equipment identification.--Equipment shall be identified with nameplates fastened with self-tapping, cadmium-plated screws or nickel-plated bolts.

Nameplate inscriptions shall be as shown on the plans.