

**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that Caltrans does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders and non-bidder packages, write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone and fax number, P.O. Box and street address so that you can receive addenda.

Note: Addenda information is NOT included with the electronic documents available via electronic file transfer. Only bidder or non-bidder package holders listed with the Caltrans Plans and Bid Documents section as described above will receive addenda information.



STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS
AND
SPECIAL PROVISIONS
FOR CONSTRUCTION ON STATE HIGHWAY IN
SAN FRANCISCO COUNTY AT THE SAN FRANCISCO-OAKLAND BAY BRIDGE

DISTRICT 04, ROUTE 80

For Use in Connection with Standard Specifications Dated JULY 1999, Standard Plans Dated JULY 1999, and Labor Surcharge and Equipment Rental Rates.

CONTRACT NO. 04-004894
04-SF-80-13.2/14.2

Bids Open: December 12, 2000
Dated: November 13, 2000

OSD

IMPORTANT SPECIAL NOTICES

- **SURETY 2000**

Caltrans is conducting a pilot program in cooperation with Surety 2000, to test electronic bond verification systems. The purpose of the pilot program is to test the use of Surety 2000 for verifying a bidder's bond electronically.

Surety 2000 is an Internet-based surety verification and security system, developed in conjunction with the surety industry. Surety agents may contact Surety 2000 at 1-800-660-3263.

Bidders are encouraged to participate in the pilot program. To participate, the bidder is asked to provide the "Authorization Code" provided by Surety 2000, on a separate sheet, together with the standard bidder's bond required by the specifications. The bidder's surety agent may obtain the "Authorization Code" from Surety 2000.

The Department will use the "Authorization Code" to access the Surety 2000 database, and independently verify the actual bidder's bond and document the functioning of the Surety 2000 system.

"Authorization Codes" will be used only to verify bidder's bonds, and only as part of the pilot program. The use of "Authorization Codes" will not be accepted in lieu of the bidder's bond or other bidder's security required in the specifications during the pilot study.

The function of the Surety 2000 system is to provide an easier way for Contractors to protect their bid security, and to discourage fraud. This system is available to all California admitted sureties and surety agents.

The results of the pilot study will be tabulated, and at some time in the future, the Department may consider accepting electronic bidder's bond verification in lieu of the bidder's bond specified.

TABLE OF CONTENTS

NOTICE TO CONTRACTORS.....	1
COPY OF ENGINEER'S ESTIMATE	3
SPECIAL PROVISIONS	4
SECTION 1. SPECIFICATIONS AND PLANS.....	4
SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS.....	4
2-1.01 GENERAL.....	4
2-1.02 DISABLED VETERAN BUSINESS ENTERPRISE (DVBE).....	4
2-1.03 DVBE GOAL FOR THIS PROJECT	5
2-1.04 SUBMISSION OF DVBE INFORMATION	6
2-1.05 SMALL BUSINESS PREFERENCE.....	6
2-1.06 CALIFORNIA COMPANY PREFERENCE	7
2-1.07 ESCROW OF BID DOCUMENTATION.....	7
SECTION 3. AWARD AND EXECUTION OF CONTRACT.....	9
SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES	10
SECTION 5. GENERAL	10
SECTION 5-1. MISCELLANEOUS	10
5-1.01 PLANS AND WORKING DRAWINGS	10
5-1.011 EXAMINATION OF PLANS, SPECIFICATIONS, CONTRACT, AND SITE OF WORK	10
5-1.012 DIFFERING SITE CONDITIONS.....	10
5-1.015 LABORATORY	11
5-1.017 CONTRACT BONDS	11
5-1.02 LABOR NONDISCRIMINATION	11
5-1.03 INTEREST ON PAYMENTS	11
5-1.031 FINAL PAYMENT AND CLAIMS.....	12
5-1.04 PUBLIC SAFETY	12
5-1.05 SURFACE MINING AND RECLAMATION ACT.....	13
5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES.....	13
5-1.07 YEAR 2000 COMPLIANCE.....	13
5-1.08 SUBCONTRACTOR AND DVBE RECORDS.....	13
5-1.086 PERFORMANCE OF DVBE SUBCONTRACTORS AND SUPPLIERS	13
5-1.09 SUBCONTRACTING.....	14
5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS	14
5-1.11 PARTNERING	15
5-1.116 COST REDUCTION INCENTIVE.....	15
5-1.12 PLANS AND WORKING DRAWINGS	15
5-1.13 FORCE ACCOUNT PAYMENT.....	15
5-1.14 OVERHEAD	16
5-1.15 COST REDUCTION INCENTIVE PROPOSAL	17
5-1.16 TIDAL CONDITIONS AND ELEVATION DATUM.....	17
5-1.17 PAYMENTS	17
5-1.18 RELATIONS WITH U.S. COAST GUARD	17
5-1.19 RELATIONS WITH SAN FRANCISCO BAY CONSERVATION DEVELOPMENT COMMISSION (BCDC).....	18
5-1.20 AREAS FOR CONTRACTOR'S USE.....	18
5-1.21 UTILITIES.....	18
5-1.22 SANITARY PROVISIONS.....	19
5-1.23 BRIDGE TOLLS	19
5-1.24 ACCESS TO PROJECT SITE.....	19
5-1.25 PERMITS AND LICENSES	19
5-1.26 LOADS ON EXISTING STRUCTURES	19
5-1.27 SUNKEN DEBRIS REMOVAL	19
5-1.28 NAVIGATION REQUIREMENTS	19
SECTION 6. (BLANK).....	20
SECTION 7. (BLANK).....	20

SECTION 8. MATERIALS	20
SECTION 8-1. MISCELLANEOUS	20
8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS	20
8-1.02 APPROVED TRAFFIC PRODUCTS	27
PAVEMENT MARKERS, PERMANENT TYPE	27
PAVEMENT MARKERS, TEMPORARY TYPE	27
STRIPING AND PAVEMENT MARKING MATERIAL	28
CLASS 1 DELINEATORS.....	28
CHANNELIZERS	29
CONICAL DELINEATORS, 1070 mm.....	29
OBJECT MARKERS.....	29
TEMPORARY RAILING (TYPE K) REFLECTORS AND CONCRETE BARRIER MARKERS	29
THRIE BEAM BARRIER MARKERS.....	30
CONCRETE BARRIER DELINEATORS, 400 mm	30
CONCRETE BARRIER-MOUNTED MINI-DRUM (260 mm x 360 mm x 570 mm)	30
SOUND WALL DELINEATOR	30
GUARD RAILING DELINEATOR.....	30
RETROREFLECTIVE SHEETING	30
SPECIALTY SIGN (All Plastic)	31
SIGN SUBSTRATE FOR CONSTRUCTION AREA SIGNS	31
SECTION 8-2. (BLANK)	31
SECTION 8-3. WELDING	31
8-3.01 WELDING ELECTRODES	31
8-3.02 WELDING QUALITY CONTROL	31
SECTION 9. DESCRIPTION OF BRIDGE WORK.....	35
SECTION 10. CONSTRUCTION DETAILS.....	36
SECTION 10-1. GENERAL	36
10-1.01 ORDER OF WORK.....	36
10-1.02 COOPERATION	36
10-1.03 ELECTRONIC MOBILE DAILY DIARY SYSTEM DATA DELIVERY	36
DATA CONTENT REQUIREMENTS.....	36
DATA DELIVERY REQUIREMENTS.....	39
10-1.04 NON-STORM WATER DISCHARGES.	41
SPILL CONTINGENCY	41
LIQUIDS, RESIDUES AND DEBRIS.....	41
MEASUREMENT AND PAYMENT	41
10-1.05 WATER POLLUTION CONTROL.....	41
WATER POLLUTION CONTROL PROGRAM PREPARATION, APPROVAL AND UPDATES	42
WPCP IMPLEMENTATION	43
MAINTENANCE	44
PAYMENT	44
10-1.06 PROGRESS SCHEDULE (CRITICAL PATH).....	45
10-1.07 OBSTRUCTIONS	45
10-1.08 MOBILIZATION	45
10-1.09 TRANSPORTATION FOR THE ENGINEER	45
10-1.10 ESTABLISH MARINE ACCESS	46
10-1.11 CONSTRUCTION AREA SIGNS	46
10-1.12 MAINTAINING TRAFFIC.....	47
10-1.13 TEMPORARY CRASH CUSHION MODULE.....	47
GENERAL	47
MATERIALS.....	47
INSTALLATION	48
MEASUREMENT AND PAYMENT	48

10-1.14	EXISTING HIGHWAY FACILITIES	48
10-1.15	BRIDGE REMOVAL.....	48
10-1.16	REINFORCED, RECYCLED PLASTIC OR COMPOSITE PLASTIC LUMBER.....	49
	WORKING DRAWINGS.....	49
	MATERIALS AND FABRICATION FOR RRP LUMBER	49
	MATERIALS AND FABRICATION FOR CP LUMBER.....	50
	PHYSICAL PROPERTY REQUIREMENTS.....	51
	CHOCKS AND FILLER BLOCKS	52
	MEASUREMENT AND PAYMENT	52
10-1.17	MISCELLANEOUS METAL (BRIDGE).....	52

STANDARD PLANS LIST

The Standard Plan sheets applicable to this contract include, but are not limited to those indicated below. The Revised Standard Plans (RSP) and New Standard Plans (NSP) which apply to this contract are included as individual sheets of the project plans.

A10A	Abbreviations
A10B	Symbols

DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS

CONTRACT NO. 04-004894

04-SF-80-13.2/14.2

Sealed proposals for the work shown on the plans entitled:

**STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROJECT PLANS FOR CONSTRUCTION
ON STATE HIGHWAY IN SAN FRANCISCO COUNTY AT THE SAN FRANCISCO-OAKLAND BAY BRIDGE**

will be received at the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, CA 95814, until 2 o'clock p.m. on December 12, 2000, at which time they will be publicly opened and read in Room 0100 at the same address.

Proposal forms for this work are included in a separate book entitled:

**STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROPOSAL AND CONTRACT FOR
CONSTRUCTION ON STATE HIGHWAY IN SAN FRANCISCO COUNTY AT THE SAN FRANCISCO-
OAKLAND BAY BRIDGE**

General work description: REPAIR FENDERS AT PIERS G & H (E2, E3, E4 & E5).

This project has a goal of 3 percent disabled veteran business enterprise (DVBE) participation.

No prebid meeting is scheduled for this project.

Bids are required for the entire work described herein.

At the time this contract is awarded, the Contractor shall possess either a Class A license or one of the following Class C licenses: C-51

The Contractor must also be properly licensed at the time the bid is submitted, except that on a joint venture bid a joint venture license may be obtained by a combination of licenses after bid opening but before award in conformance with Business and Professions Code, Section 7029.1.

This contract is subject to state contract nondiscrimination and compliance requirements pursuant to Government Code, Section 12990.

Preference will be granted to bidders properly certified as a "Small Business" as determined by the Department of General Services, Office of Small Business Certification and Resources at the time of bid opening in conformance with the provisions in Section 2-1.05, "Small Business Preference," of the special provisions, and Section 1896 et seq, Title 2, California Code of Regulations. A form for requesting a "Small Business" preference is included with the bid documents. Applications for status as a "Small Business" must be submitted to the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814, Telephone No. (916) 322-5060.

A reciprocal preference will be granted to "California company" bidders in conformance with Section 6107 of the Public Contract Code. (See Sections 2 and 3 of the special provisions.) A form for indicating whether bidders are or are not a "California company" is included in the bid documents and is to be filled in and signed by all bidders.

Project plans, special provisions, and proposal forms for bidding this project can only be obtained at the Department of Transportation, Plans and Bid Documents, Room 0200, MS #26, Transportation Building, 1120 N Street, Sacramento, California 95814, FAX No. (916) 654-7028, Telephone No. (916) 654-4490. Use FAX orders to expedite orders for project

Contract No. 04-004894

plans, special provisions and proposal forms. FAX orders must include credit card charge number, card expiration date and authorizing signature. Project plans, special provisions, and proposal forms may be seen at the above Department of Transportation office and at the offices of the District Directors of Transportation at Irvine, Oakland, and the district in which the work is situated. Standard Specifications and Standard Plans are available through the State of California, Department of Transportation, Publications Unit, 1900 Royal Oaks Drive, Sacramento, CA 95815, Telephone No. (916) 445-3520.

Cross sections for this project are not available.

The successful bidder shall furnish a payment bond and a performance bond.

Pursuant to Section 1773 of the Labor Code, the general prevailing wage rates in the county, or counties, in which the work is to be done have been determined by the Director of the California Department of Industrial Relations. These wages are set forth in the General Prevailing Wage Rates for this project, available at the Labor Compliance Office at the offices of the District Director of Transportation for the district in which the work is situated, and available from the California Department of Industrial Relations' Internet Web Site at: <http://www.dir.ca.gov>. Future effective general prevailing wage rates which have been predetermined and are on file with the Department of Industrial Relations are referenced but not printed in the general prevailing wage rates.

DEPARTMENT OF TRANSPORTATION

Deputy Director Transportation Engineering

Dated November 13, 2000

RRG

COPY OF ENGINEER'S ESTIMATE
(NOT TO BE USED FOR BIDDING PURPOSES)
04-004894

Item	Item Code	Item	Unit of Measure	Estimated Quantity
1	020028	ELECTRONIC MOBILE DAILY DIARY COMPUTER SYSTEM DATA DELIVERY	LS	LUMP SUM
2	020029	ESTABLISH MARINE ACCESS	LS	LUMP SUM
3	070018	TIME RELATED OVERHEAD	WDAY	100
4	157560	BRIDGE REMOVAL (PORTION)	LS	LUMP SUM
5 (F)	048394	FURNISH AND INSTALL RRP OR CP LUMBER	M3	270
6 (S-F)	750501	MISCELLANEOUS METAL (BRIDGE)	KG	98 000
7	999990	MOBILIZATION	LS	LUMP SUM

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISIONS

Annexed to Contract No. 04-004894

SECTION 1. SPECIFICATIONS AND PLANS

The work embraced herein shall conform to the provisions in the Standard Specifications dated July 1999, and the Standard Plans dated July 1999, of the Department of Transportation insofar as the same may apply, and these special provisions.

Amendments to the Standard Specifications set forth in these special provisions shall be considered as part of the Standard Specifications for the purposes set forth in Section 5-1.04, "Coordination and Interpretation of Plans, Standard Specifications and Special Provisions," of the Standard Specifications. Whenever either the term "Standard Specifications is amended" or the term "Standard Specifications are amended" is used in the special provisions, the indented text or table following the term shall be considered an amendment to the Standard Specifications. In case of conflict between such amendments and the Standard Specifications, the amendments shall take precedence over and be used in lieu of the conflicting portions.

In case of conflict between the Standard Specifications and these special provisions, the special provisions shall take precedence over and shall be used in lieu of the conflicting portions.

SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS

2-1.01 GENERAL

The bidder's attention is directed to the provisions in Section 2, "Proposal Requirements and Conditions," of the Standard Specifications and these special provisions for the requirements and conditions which the bidder must observe in the preparation of the proposal form and the submission of the bid.

In addition to the subcontractors required to be listed in conformance with Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications, each proposal shall have listed therein the name and address of each DVBE subcontractor to be used for credit in meeting the goal, and to whom the bidder proposes to directly subcontract portions of the work. The list of subcontractors shall also set forth the portion of work that will be performed by each subcontractor listed. A sheet for listing the subcontractors is included in the Proposal.

The Bidder's Bond form mentioned in the last paragraph in Section 2-1.07, "Proposal Guaranty," of the Standard Specifications will be found following the signature page of the Proposal.

In conformance with Public Contract Code Section 7106, a Noncollusion Affidavit is included in the Proposal. Signing the Proposal shall also constitute signature of the Noncollusion Affidavit.

Submit request for substitution of an "or equal" item, and the data substantiating the request to the Department of Transportation, Division Of Construction - Duty Senior, Mail Station: 3 - B, 111 Grand Avenue / P. O. Box 23660, Oakland, Ca 94623-0660, so that the request is received by the Department by close of business on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening.

2-1.02 DISABLED VETERAN BUSINESS ENTERPRISE (DVBE)

Section 10115 of the Public Contract Code requires the Department to implement provisions to establish a goal for Disabled Veterans Business Enterprise (DVBE) in contracts.

It is the policy of the Department that Disabled Veteran Business Enterprise (DVBE) shall have the maximum opportunity to participate in the performance of contracts financed solely with state funds. The Contractor shall ensure that DVBEs have the maximum opportunity to participate in the performance of this contract and shall take all necessary and reasonable steps for this assurance. The Contractor shall not discriminate on the basis of race, color, national origin, or sex in the award and performance of subcontracts. Failure to carry out the requirements of this paragraph shall constitute a breach of contract and may result in termination of this contract or other remedy the Department may deem appropriate.

Bidder's attention is directed to the following:

- A. "Disabled Veteran Business Enterprise" (DVBE) means a business concern certified as a DVBE by the Office of Small Business Certification and Resources, Department of General Services.
- B. A DVBE may participate as a prime contractor, subcontractor, joint venture partner with a prime or subcontractor, or vendor of material or supplies.
- C. Credit for DVBE prime contractors will be 100 percent.
- D. A DVBE joint venture partner must be responsible for specific contract items of work, or portions thereof. Responsibility means actually performing, managing and supervising the work with its own forces. The DVBE joint venture partner must share in the ownership, control, management responsibilities, risks and profits of the joint venture. The DVBE joint venturer must submit the joint venture agreement with the Caltrans Bidder DVBE Information form required in Section 2-1.04, "Submission of DVBE Information," elsewhere in these special provisions.
- E. A DVBE must perform a commercially useful function, i.e., must be responsible for the execution of a distinct element of the work and must carry out its responsibility by actually performing, managing and supervising the work.
- F. Credit for DVBE vendors of materials or supplies is limited to 60 percent of the amount to be paid to the vendor for the material unless the vendor manufactures or substantially alters the goods.
- G. Credit for trucking by DVBEs will be as follows:
 - 1. One hundred percent of the amount to be paid when a DVBE trucker will perform the trucking with his/her own trucks, tractors and employees.
 - 2. Twenty percent of the amount to be paid to DVBE trucking brokers who do not have a "certified roster."
 - 3. One hundred percent of the amount to be paid to DVBE trucking brokers who have signed agreements that all trucking will be performed by DVBE truckers if credit is toward the DVBE goal, a "certified roster" showing that all trucks are owned by DVBEs, and a signed statement on the "certified roster" that indicates that 100 percent of revenue paid by the broker will be paid to the DVBEs listed on the "certified roster."
 - 4. Twenty percent of the amount to be paid to trucking brokers who are not a DVBE but who have signed agreements with DVBE truckers assuring that at least 20 percent of the trucking will be performed by DVBE truckers if credit is toward the DVBE goal, a "certified roster" showing that at least 20 percent of the number of trucks are owned by DVBE truckers, and a signed statement on the "certified roster" that indicates that at least 20 percent of the revenue paid by the broker will be paid to the DVBEs listed on the "certified roster."

The "certified roster" referred to herein shall conform to the requirements in Section 2-1.04, "Submission Of DVBE Information," elsewhere in these special provisions.

- H. DVBEs and DVBE joint venture partners must be certified DVBEs as determined by the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814, on the date bids for the project are opened before credit may be allowed toward the DVBE goal. It is the Contractor's responsibility to verify that DVBEs are certified.
- I. Noncompliance by the Contractor with these requirements constitutes a breach of this contract and may result in termination of the contract or other appropriate remedy for a breach of this contract.

2-1.03 DVBE GOAL FOR THIS PROJECT

The Department has established the following goal for Disabled Veteran Business Enterprise (DVBE) participation for this project:

Disabled Veteran Business Enterprise (DVBE): 3 percent.

It is the bidder's responsibility to make a sufficient portion of the work available to subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DVBE subcontractors and suppliers, so as to assure meeting the goal for DVBE participation.

The Office of Small Business Certification and Resources, Department of General Services, may be contacted at (916) 322-5060 or visit their internet web site at <http://www.osmb.dgs.ca.gov/> for program information and certification status. The Department's Business Enterprise Program may also be contacted at (916) 227-9599 or the internet web site at <http://www.dot.ca.gov/hq/bep/>.

2-1.04 SUBMISSION OF DVBE INFORMATION

The required DVBE information shall be submitted on the "CALTRANS BIDDER - DVBE INFORMATION" form included in the Proposal. If this information is not submitted with the bid, the DVBE information forms shall be removed from the documents prior to submitting the bid.

It is the bidder's responsibility to make enough work available to DVBEs and to select those portions of the work or material needs consistent with the available DVBEs to meet the goal for DVBE participation or to provide information to establish that, prior to bidding, the bidder made adequate good faith efforts to do so.

If the DVBE information is not submitted with the bid, the apparent successful bidder (low bidder), the second low bidder and the third low bidder shall submit the DVBE information to the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, California 95814 so the information is received by the Department no later than 4:00 p.m. on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening. DVBE information sent by U.S. Postal Service certified mail with return receipt and certificate of mailing and mailed on or before the third day, not including Saturdays, Sundays and legal holidays, following bid opening will be accepted even if it is received after the fourth day following bid opening. Failure to submit the required DVBE information by the time specified will be grounds for finding the bid or proposal nonresponsive. Other bidders need not submit DVBE information unless requested to do so by the Department.

The bidder's DVBE information shall establish that good faith efforts to meet the DVBE goal have been made. To establish good faith efforts, the bidder shall demonstrate that the goal will be met or that, prior to bidding, adequate good faith efforts to meet the goal were made.

Bidders are cautioned that even though their submittal indicates they will meet the stated DVBE goal, their submittal should also include their adequate good faith efforts information along with their DVBE goal information to protect their eligibility for award of the contract in the event the Department, in its review, finds that the goal has not been met.

The bidder's DVBE information shall include the names of DVBE firms that will participate, with a complete description of work or supplies to be provided by each, the dollar value of each DVBE transaction, and a written confirmation from the DVBE that it is participating in the contract. A copy of the DVBE's quote will serve as written confirmation that the DVBE is participating in the contract. When 100 percent of a contract item of work is not to be performed or furnished by a DVBE, a description of the exact portion of that work to be performed or furnished by that DVBE shall be included in the DVBE information, including the planned location of that work. The work that a DVBE prime contractor has committed to performing with its own forces as well as the work that it has committed to be performed by DVBE subcontractors, suppliers and trucking companies will count toward the goal.

If credit for trucking by a DVBE trucking broker is shown on the bidder's information as 100 percent of the revenue to be paid by the broker is to be paid to DVBE truckers, a "certified roster" of the broker's trucks to be used must be included. The "certified roster" must indicate that all the trucks are owned by certified DVBEs and must show the DVBE truck numbers, owner's name, Public Utilities Commission Cal-T numbers, and the DVBE certification numbers. The roster must indicate that all revenue paid by the broker will be paid to DVBEs listed on the "certified roster".

If credit for trucking by a trucking broker who is not a DVBE is shown in the bidder's information, a "certified roster" of the broker's trucks to be used must be included. The "certified roster" must indicate that at least 20 percent of the broker's trucks are owned by certified DVBEs and must show the DVBE truck numbers, owner's name, Public Utilities Commission Cal-T numbers, and the DVBE certification number. The roster must indicate that at least 20 percent of the revenue paid by the broker will be paid to DVBEs listed on the "certified roster".

A bidder shall be deemed to have made good faith efforts upon submittal, within time limits specified by the Department, of documentary evidence that all of the following actions were taken:

- A. Contact was made with the Office of Small Business Certification and Resources (OSBCR), Department of General Services or their web site at <http://www.osmb.dgs.ca.gov/> to identify Disabled Veteran Business Enterprises.
- B. Advertising was published in trade media and media focusing on Disabled Veteran Business Enterprises, unless time limits imposed by the Department do not permit that advertising.
- C. Invitations to bid were submitted to potential Disabled Veteran Business Enterprise contractors.
- D. Available Disabled Veteran Business Enterprises were considered.

2-1.05 SMALL BUSINESS PREFERENCE

Attention is directed to "Award and Execution of Contract" of these special provisions.

Attention is also directed to the Small Business Procurement and Contract Act, Government Code Section 14835, et seq and Title 2, California Code of Regulations, Section 1896, et seq.

Bidders who wish to be classified as a Small Business under the provisions of those laws and regulations, shall be certified as Small Business by the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814.

To request Small Business Preference, bidders shall fill out and sign the Request for Small Business Preference form in the Proposal and shall attach a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form. The bidder's signature on the Request for Small Business Preference certifies, under penalty of perjury, that the bidder is certified as Small Business at the time of bid opening and further certifies, under penalty of perjury, that under the following conditions, at least 50 percent of the subcontractors to be utilized on the project are either certified Small Business or have applied for Small Business certification by bid opening date and are subsequently granted Small Business certification.

The conditions requiring the aforementioned 50 percent level of subcontracting by Small Business subcontractors apply if:

- A. The lowest responsible bid for the project exceeds \$100,000; and
- B. The project work to be performed requires a Class A or a Class B contractor's license; and
- C. Two or more subcontractors will be used.

If the above conditions apply and Small Business Preference is granted in the award of the contract, the 50 percent Small Business subcontractor utilization level shall be maintained throughout the life of the contract.

2-1.06 CALIFORNIA COMPANY PREFERENCE

Attention is directed to "Award and Execution of Contract" of these special provisions.

In conformance with the requirements of Section 6107 of the Public Contract Code, a "California company" will be granted a reciprocal preference for bid comparison purposes as against a nonresident contractor from any state that gives or requires a preference to be given contractors from that state on its public entity construction contracts.

A "California company" means a sole proprietorship, partnership, joint venture, corporation, or other business entity that was a licensed California contractor on the date when bids for the public contract were opened and meets one of the following:

- A. Has its principal place of business in California.
- B. Has its principal place of business in a state in which there is no local contractor preference on construction contracts.
- C. Has its principal place of business in a state in which there is a local contractor construction preference and the contractor has paid not less than \$5000 in sales or use taxes to California for construction related activity for each of the five years immediately preceding the submission of the bid.

To carry out the "California company" reciprocal preference requirements of Section 6107 of the Public Contract Code, all bidders shall fill out and sign the California Company Preference form in the Proposal. The bidder's signature on the California Company Preference form certifies, under penalty of perjury, that the bidder is or is not a "California company" and if not, the amount of the preference applied by the state of the nonresident Contractor.

A nonresident Contractor shall disclose any and all bid preferences provided to the nonresident Contractor by the state or country in which the nonresident Contractor has its principal place of business.

Proposals without the California Company Preference form filled out and signed may be rejected.

2-1.07 ESCROW OF BID DOCUMENTATION

Bid documentation shall consist of all documentary and calculated information generated by the Contractor in preparation of the bid. The bid documentation shall conform to the requirements in these special provisions, and shall be submitted to the Department and held in escrow for the duration of the contract.

In the resolution of disputes involving the project, the escrowed bid documents will be the only documents accepted from the Contractor regarding preparation of the bid.

In signing the proposal, the bidder certifies that the material submitted for escrow constitutes all the documentary information used in preparation of the bid and that he has personally examined the contents of the container and that they are complete.

Nothing in the bid documentation shall be construed to change or modify the terms or conditions of the contract.

Escrowed bid documentation will not be used for pre-award evaluation of the Contractor's anticipated methods of construction, nor to assess the Contractor's qualifications for performing the work.

Bid documentation shall clearly itemize the Contractor's estimated costs of performing the work. The documentation submitted shall be complete and so detailed as to allow for an in-depth analysis of the Contractor's estimate.

The bid documentation shall include, but not be limited to: quantity takeoffs; rate schedules for the direct costs and the time- and nontime-related indirect costs for labor (by craft), plant and equipment ownership and operation, permanent and expendable materials, insurance and subcontracted work; estimated construction schedules, including sequence and duration and development of production rates; quotations from subcontractors and suppliers; estimates of field and home office overhead; contingency and margin for each contract item of work; and other reports, calculations and information used by the bidder to arrive at the estimate submitted with the proposal.

The Contractor shall also submit bid documentation for each subcontractor whose total subcontract exceeds \$250,000. Subcontractor bid documentation shall be enclosed with the Contractor's submittal. The examination of subcontractors' bid documentation will be accomplished in the same manner as for the Contractor's bid documentation. If a subcontractor is replaced, bid documentation for the new subcontractor shall be submitted for review and escrow before authorization for the substitution will be granted. Upon request of a subcontractor, the bid documentation from that subcontractor shall be reviewed only by the subcontractor and the Department.

If the bidder is a joint venture, the bid documentation shall include the joint venture agreement, the joint venture estimate comparison and final reconciliation of the joint venture estimate.

Copies of the proposals submitted by the first, second and third low bidders will be provided to the respective bidders for inclusion in the bid documentation to be escrowed.

(For projects in southern districts: change address; and change day to first Wednesday, due to Thursday bid openings.)

The first, second, and third apparent low bidders shall present the bid documentation for escrow at the District 04 Office, 111 Grand Avenue, Room 12-820, Oakland, CA, on the first Monday, at 1:00 p.m., following the time indicated in the "Notice to Contractors" for the opening of bids.

Bid documentation shall be submitted in a sealed container, clearly marked with the bidder's name, date of submittal, project contract number and the words, "Bid Documentation for Escrow."

Failure to submit the actual and complete bid documentation as specified herein within the time specified shall be cause for rejection of the proposal.

Upon submittal, the bid documentation of the apparent low bidder will be examined and inventoried by the duly designated representatives of the Contractor and the Department to ensure that the bid documentation is authentic, legible, and in accordance with the terms of this section "Escrow of Bid Documentation." The examination will not include review of, nor will it constitute approval of, proposed construction methods, estimating assumptions or interpretation of the contract. The examination will not alter any conditions or terms of the contract. The acceptance or rejection by the Department that the submitted bid documents are in compliance with this section "Escrow of Bid Documentation" shall be completed within 48 hours of the time the bid documentation is submitted by the Contractor.

At the completion of the examination, the bid documents will be sealed and jointly deposited at an agreed commercial bank.

Bid documentation submitted by the second and third apparent low bidders will be jointly deposited at agreed commercial banks. If the apparent low bid is withdrawn or rejected, the bid documentation of the second low bidder will be examined and inventoried in the manner specified above, then sealed and deposited again in escrow. If the second low bid is withdrawn or rejected, the bid documentation of the third low bidder will be examined and inventoried in the manner specified above, then sealed and deposited again in escrow. Upon execution and final approval of the contract or rejection of all bids, the bid documentation will be returned to any remaining unsuccessful bidders.

The escrowed bid documentation may be examined by the designated representatives of both the Department and the Contractor, at any time deemed necessary by either the Department or the Contractor to assist in the negotiation of price adjustments and change orders, or in the settlement of claims or disputes.

If requested by a Disputes Review Board, the escrowed bid documentation may be utilized to assist the Board in its recommendations.

The bid documentation submitted by the Contractor will be held in escrow until the contract has been completed, the ultimate resolution of all disputes and claims has been achieved and receipt of final payment has been accepted by the Contractor. The escrowed bid documentation will then be released from escrow to the Contractor.

The bid documentation submitted by the bidder is, and shall remain, the property of the bidder, and is subject to only joint review by the Department and the bidder. The Department stipulates and expressly acknowledges that the submitted bid documentation constitutes trade secrets and will not be deemed public records. This acknowledgment is based on the Department's express understanding that the information contained in the bid documentation is not known outside the bidder's business, is known only to a limited extent and only by a limited number of employees of the bidder, is safeguarded while in the bidder's possession, is extremely valuable to the bidder and could be extremely valuable to the bidder's competitors by virtue of it reflecting the bidder's contemplated techniques of construction. The Department acknowledges that the bid documentation includes a compilation of information used in the bidder's business, intended to give the bidder an opportunity to obtain an advantage over competitors who do not know of or use the contents of the documentation. The Department agrees to safeguard the bid documentation, and all information contained therein, against disclosure, including disclosure of subcontractor bid documentation to the Contractor and other subcontractors to the fullest extent permitted by law. However, in the event of arbitration or litigation, the bid documentation shall be subject to discovery, and the

Department assumes no responsibility for safeguarding the bid documentation unless the Contractor has obtained an appropriate protective order issued by the arbitrator or the court.

Full compensation for preparing the bid documentation, presenting it for escrow and reviewing it for escrow and upon request of the Engineer shall be considered as included in the contract prices paid for the various items of work, and no additional compensation will be allowed therefor.

The direct cost of depositing the bid documentation in escrow at the agreed commercial bank will be paid by the State.

SECTION 3. AWARD AND EXECUTION OF CONTRACT

The bidder's attention is directed to the provisions in Section 3, "Award and Execution of Contract," of the Standard Specifications and these special provisions for the requirements and conditions concerning award and execution of contract.

Each of the two bonds required in Section 3-1.02, "Contract Bonds," of the Standard Specifications shall be in a sum equal to 100 percent of the contract price.

The award of the contract, if it be awarded, will be to the lowest responsible bidder whose proposal complies with all the requirements prescribed and who has met the goal for DVBE participation or has demonstrated, to the satisfaction of the Department, adequate good faith efforts to do so. Meeting the goal for DVBE participation or demonstrating, to the satisfaction of the Department, adequate good faith efforts to do so is a condition for being eligible for award of contract.

A "Payee Data Record" form will be included in the contract documents to be executed by the successful bidder. The purpose of the form is to facilitate the collection of taxpayer identification data. The form shall be completed and returned to the Department by the successful bidder with the executed contract and contract bonds. For the purposes of the form, payee shall be deemed to mean the successful bidder. The form is not to be completed for subcontractors or suppliers. Failure to complete and return the "Payee Data Record" form to the Department as provided herein will result in the retention of 20 percent of payments due the contractor and penalties of up to \$20,000. This retention of payments for failure to complete the "Payee Data Record" form is in addition to any other retention of payments due the Contractor.

Attention is also directed to "Small Business Preference" of these special provisions. Any bidder who is certified as a Small Business by the Department of General Services, Office of Small Business Certification and Resources will be allowed a preference in the award of this contract, if it be awarded, under the following conditions:

- A. The apparent low bidder is not certified as a Small Business, or has not filled out and signed the Request for Small Business Preference included with the bid documents and attached a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form; and
- B. The bidder filled out and signed the Request for Small Business Preference form included with the bid documents and attached a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form.

The small business preference will be a reduction in the bid submitted by the small business contractor, for bid comparison purposes, by an amount equal to 5 percent of the amount bid by the apparent low bidder, the amount not to exceed \$50,000. If this reduction results in the small business contractor becoming the low bidder, then the contract will be awarded to the small business contractor on the basis of the actual bid of the small business contractor notwithstanding the reduced bid price used for bid comparison purposes.

Attention is also directed to "California Company Preference" of these special provisions.

The amount of the California company reciprocal preference shall be equal to the amount of the preference applied by the state of the nonresident contractor with the lowest responsive bid, except where the "California company" is eligible for a California Small Business Preference, in which case the preference applied shall be the greater of the two, but not both.

If the bidder submitting the lowest responsive bid is not a "California company" and with the benefit of the reciprocal preference, a "California company's" responsive bid is equal to or less than the original lowest responsive bid, the "California company" will be awarded the contract at its submitted bid price except as provided below.

Small business bidders shall have precedence over non-small business bidders in that the application of the "California company" preference for which non-small business bidders may be eligible shall not result in the denial of the award to a small business bidder.

SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES

Attention is directed to the provisions in Section 8-1.03, "Beginning of Work," in Section 8-1.06, "Time of Completion," and in Section 8-1.07, "Liquidated Damages," of the Standard Specifications and these special provisions.

The Contractor shall begin work within 15 calendar days after the contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department of Transportation.

This work shall be diligently prosecuted to completion before the expiration of **100 WORKING DAYS** beginning on the fifteenth calendar day after approval of the contract.

The Contractor shall pay to the State of California the sum of \$300 per day, for each and every calendar day's delay in finishing the work in excess of the number of working days prescribed above.

SECTION 5. GENERAL

SECTION 5-1. MISCELLANEOUS

5-1.01 PLANS AND WORKING DRAWINGS

When the specifications require working drawings to be submitted to the Division of Structure Design, the drawings shall be submitted to: Division of Structure Design, Documents Unit, Mail Station 9, 1801 30th Street, Sacramento, CA 95816, Telephone 916 227-8252.

5-1.011 EXAMINATION OF PLANS, SPECIFICATIONS, CONTRACT, AND SITE OF WORK

The second paragraph of Section 2-1.03, "Examination of Plans, Specifications, Contract, and Site of Work," of the Standard Specifications is amended to read:

- Where the Department has made investigations of site conditions, including subsurface conditions in areas where work is to be performed under the contract, or in other areas, some of which may constitute possible local material sources, bidders or Contractors may, upon written request, inspect the records of the Department as to those investigations subject to and upon the conditions hereinafter set forth.

Attention is directed to "Differing Site Conditions" of these special provisions regarding physical conditions at the site which may differ from those indicated in "Materials Information," log of test borings or other geotechnical information obtained by the Department's investigation of site conditions.

5-1.012 DIFFERING SITE CONDITIONS

Attention is directed to Section 5-1.116, "Differing Site Conditions," of the Standard Specifications.

During the progress of the work, if subsurface or latent conditions are encountered at the site differing materially from those indicated in the "Materials Information," log of test borings, other geotechnical data obtained by the Department's investigation of subsurface conditions, or an examination of the conditions above ground at the site, the party discovering those conditions shall promptly notify the other party in writing of the specific differing conditions before they are disturbed and before the affected work is performed.

The Contractor will be allowed 15 days from the notification of the Engineer's determination of whether or not an adjustment of the contract is warranted, in which to file a notice of potential claim in conformance with the provisions of Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications and as specified herein; otherwise the decision of the Engineer shall be deemed to have been accepted by the Contractor as correct. The notice of potential claim shall set forth in what respects the Contractor's position differs from the Engineer's determination and provide any additional information obtained by the Contractor, including but not limited to additional geotechnical data. The notice of potential claim shall be accompanied by the Contractor's certification that the following were made in preparation of the bid: a review of the contract, a review of the "Materials Information," a review of the log of test borings and other records of geotechnical data to the extent they were made available to bidders prior to the opening of bids, and an examination of the conditions above ground at the site. Supplementary information, obtained by the Contractor subsequent to the filing of the notice of potential claim, shall be submitted to the Engineer in an expeditious manner.

5-1.015 LABORATORY

When a reference is made in the specifications to the "Laboratory," the reference shall mean the Division of Materials Engineering and Testing Services and the Division of Structural Foundations of the Department of Transportation, or established laboratories of the various Districts of the Department, or other laboratories authorized by the Department to test materials and work involved in the contract. When a reference is made in the specifications to the "Transportation Laboratory," the reference shall mean the Division of Materials Engineering and Testing Services and the Division of Structural Foundations, located at 5900 Folsom Boulevard, Sacramento, CA 95819, Telephone (916) 227-7000.

5-1.017 CONTRACT BONDS

Attention is directed to Section 3-1.02, "Contract Bonds," of the Standard Specifications and these special provisions. The payment bond shall be in a sum not less than the following:

- A. One hundred percent of the total amount payable by the terms of the contract when the total amount payable does not equal or exceed five million dollars (\$5,000,000).
- B. Fifty percent of the total amount payable by the terms of the contract when the total amount payable is not less than five million dollars (\$5,000,000) and does not exceed ten million dollars (\$10,000,000).
- C. Twenty-five percent of the total amount payable by the terms of the contract when the total amount payable exceeds ten million dollars (\$10,000,000).

5-1.02 LABOR NONDISCRIMINATION

Attention is directed to the following Notice that is required by Chapter 5 of Division 4 of Title 2, California Code of Regulations.

NOTICE OF REQUIREMENT FOR NONDISCRIMINATION PROGRAM (GOV. CODE, SECTION 12990)

Your attention is called to the "Nondiscrimination Clause", set forth in Section 7-1.01A(4), "Labor Nondiscrimination," of the Standard Specifications, which is applicable to all nonexempt State contracts and subcontracts, and to the "Standard California Nondiscrimination Construction Contract Specifications" set forth therein. The specifications are applicable to all nonexempt State construction contracts and subcontracts of \$5000 or more.

5-1.03 INTEREST ON PAYMENTS

Interest shall be payable on progress payments, payments after acceptance, final payments, extra work payments, and claim payments as follows:

- A. Unpaid progress payments, payment after acceptance, and final payments shall begin to accrue interest 30 days after the Engineer prepares the payment estimate.
- B. Unpaid extra work bills shall begin to accrue interest 30 days after preparation of the first pay estimate following receipt of a properly submitted and undisputed extra work bill. To be properly submitted, the bill must be submitted within 7 days of the performance of the extra work and in conformance with the provisions in Section 9-1.03C, "Records," and Section 9-1.06, "Partial Payments," of the Standard Specifications. An undisputed extra work bill not submitted within 7 days of performance of the extra work will begin to accrue interest 30 days after the preparation of the second pay estimate following submittal of the bill.
- C. The rate of interest payable for unpaid progress payments, payments after acceptance, final payments, and extra work payments shall be 10 percent per annum.
- D. The rate of interest payable on a claim, protest or dispute ultimately allowed under this contract shall be 6 percent per annum. Interest shall begin to accrue 61 days after the Contractor submits to the Engineer information in sufficient detail to enable the Engineer to ascertain the basis and amount of said claim, protest or dispute.

The rate of interest payable on any award in arbitration shall be 6 percent per annum if allowed under the provisions of Civil Code Section 3289.

5-1.031 FINAL PAYMENT AND CLAIMS

Attention is directed to Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications.

The District that administers the contract shall submit a claim position letter to the Contractor within 135 days after acceptance of the contract. After receipt of the claim position letter from the District, or 135 days after acceptance of the contract, whichever occurs first, the Contractor may request a meeting with the person or board designated by the District Director to review claims that remain in dispute. If the Contractor requests a meeting, the review person or board shall meet with the Contractor within 45 days after the request is received.

5-1.04 PUBLIC SAFETY

The Contractor shall provide for the safety of traffic and the public in conformance with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications and these special provisions.

The Contractor shall install temporary railing (Type K) between a lane open to public traffic and an excavation, obstacle or storage area when the following conditions exist:

- A. Excavations.—The near edge of the excavation is 3.6 m or less from the edge of the lane, except:
 - 1. Excavations covered with sheet steel or concrete covers of adequate thickness to prevent accidental entry by traffic or the public.
 - 2. Excavations less than 0.3-m deep.
 - 3. Trenches less than 0.3-m wide for irrigation pipe or electrical conduit, or excavations less than 0.3-m in diameter.
 - 4. Excavations parallel to the lane for the purpose of pavement widening or reconstruction.
 - 5. Excavations in side slopes, where the slope is steeper than 1:4 (vertical:horizontal).
 - 6. Excavations protected by existing barrier or railing.
- B. Temporarily Unprotected Permanent Obstacles.—The work includes the installation of a fixed obstacle together with a protective system, such as a sign structure together with protective railing, and the Contractor elects to install the obstacle prior to installing the protective system; or the Contractor, for the Contractor's convenience and with permission of the Engineer, removes a portion of an existing protective railing at an obstacle and does not replace such railing complete in place during the same day.
- C. Storage Areas.—Material or equipment is stored within 3.6 m of the lane and the storage is not otherwise prohibited by the provisions of the Standard Specifications and these special provisions.

The approach end of temporary railing (Type K), installed in conformance with the provisions in this section "Public Safety" and in Section 7-1.09, "Public Safety," of the Standard Specifications, shall be offset a minimum of 4.6 m from the edge of the traffic lane open to public traffic. The temporary railing shall be installed on a skew toward the edge of the traffic lane of not more than 0.3-m transversely to 3 m longitudinally with respect to the edge of the traffic lane. If the 4.6-m minimum offset cannot be achieved, the temporary railing shall be installed on the 10 to 1 skew to obtain the maximum available offset between the approach end of the railing and the edge of the traffic lane, and an array of temporary crash cushion modules shall be installed at the approach end of the temporary railing.

Temporary railing (Type K) shall conform to the provisions in Section 12-3.08, "Temporary Railing (Type K)," of the Standard Specifications. Temporary railing (Type K), conforming to the details shown on 1999 Standard Plan T3, may be used. Temporary railing (Type K) fabricated prior to January 1, 1993, and conforming to 1988 Standard Plan B11-30 may be used, provided the fabrication date is printed on the required Certificate of Compliance.

Temporary crash cushion modules shall conform to the provisions in "Temporary Crash Cushion Module" of these special provisions.

Except for installing, maintaining and removing traffic control devices, whenever work is performed or equipment is operated in the following work areas, the Contractor shall close the adjacent traffic lane unless otherwise provided in the Standard Specifications and these special provisions:

Approach Speed of Public Traffic (Posted Limit) (Kilometers Per Hour)	Work Areas
Over 72 (45 Miles Per Hour)	Within 1.8 m of a traffic lane but not on a traffic lane
56 to 72 (35 to 45 Miles Per Hour)	Within 0.9-m of a traffic lane but not on a traffic lane

The lane closure provisions of this section shall not apply if the work area is protected by permanent or temporary railing or barrier.

When traffic cones or delineators are used to delineate a temporary edge of a traffic lane, the line of cones or delineators shall be considered to be the edge of the traffic lane, however, the Contractor shall not reduce the width of an existing lane to less than 3 m without written approval from the Engineer.

When work is not in progress on a trench or other excavation that required closure of an adjacent lane, the traffic cones or portable delineators used for the lane closure shall be placed off of and adjacent to the edge of the traveled way. The spacing of the cones or delineators shall be not more than the spacing used for the lane closure.

Suspended loads or equipment shall not be moved nor positioned over public traffic or pedestrians.

Full compensation for conforming to the provisions in this section "Public Safety," including furnishing and installing temporary railing (Type K) and temporary crash cushion modules, shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

5-1.05 SURFACE MINING AND RECLAMATION ACT

Attention is directed to the Surface Mining and Reclamation Act of 1975, commencing in Public Resources Code, Mining and Geology, Section 2710, which establishes regulations pertinent to surface mining operations, and to California Public Contract Code Section 10295.5.

Material from mining operations furnished for this project shall only come from permitted sites in compliance with California Public Contract Code Section 10295.5.

The requirements of this section shall apply to materials furnished for the project, except for acquisition of materials in conformance with the provisions in Section 4-1.05, "Use of Materials Found on the Work," of the Standard Specifications.

5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES

When the presence of asbestos or hazardous substances are not shown on the plans or indicated in the specifications and the Contractor encounters materials which the Contractor reasonably believes to be asbestos or a hazardous substance as defined in Section 25914.1 of the Health and Safety Code, and the asbestos or hazardous substance has not been rendered harmless, the Contractor may continue work in unaffected areas reasonably believed to be safe. The Contractor shall immediately cease work in the affected area and report the condition to the Engineer in writing.

In conformance with Section 25914.1 of the Health and Safety Code, removal of asbestos or hazardous substances including exploratory work to identify and determine the extent of the asbestos or hazardous substance will be performed by separate contract.

If delay of work in the area delays the current controlling operation, the delay will be considered a right of way delay and the Contractor will be compensated for the delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

5-1.07 YEAR 2000 COMPLIANCE

This contract is subject to Year 2000 Compliance for automated devices in the State of California.

Year 2000 compliance for automated devices in the State of California is achieved when embedded functions have or create no logical or mathematical inconsistencies when dealing with dates prior to and beyond 1999. The year 2000 is recognized and processed as a leap year. The product shall operate accurately in the manner in which the product was intended for date operation without requiring manual intervention.

The Contractor shall provide the Engineer a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for all automated devices furnished for the project.

5-1.08 SUBCONTRACTOR AND DVBE RECORDS

The Contractor shall maintain records of all subcontracts entered into with certified DVBE subcontractors and records of materials purchased from certified DVBE suppliers. The records shall show the name and business address of each DVBE subcontractor or vendor and the total dollar amount actually paid each DVBE subcontractor or vendor.

Upon completion of the contract, a summary of these records shall be prepared on Form CEM-2402 (S) and certified correct by the Contractor or the Contractor's authorized representative, and shall be furnished to the Engineer.

5-1.086 PERFORMANCE OF DVBE SUBCONTRACTORS AND SUPPLIERS

The DVBEs listed by the Contractor in response to the provisions in Section 2-1.04, "Submission of DVBE Information," and Section 3, "Award and Execution of Contract," of these special provisions, which are determined by the Department to be certified DVBEs, shall perform the work and supply the materials for which they are listed, unless the Contractor has received prior written authorization to perform the work with other forces or to obtain the materials from other sources.

Authorization to utilize other forces or sources of materials may be requested for the following reasons:

- A. The listed DVBE, after having had a reasonable opportunity to do so, fails or refuses to execute a written contract, when the written contract, based upon the general terms, conditions, plans and specifications for the project, or on the terms of the subcontractor's or supplier's written bid, is presented by the Contractor.
- B. The listed DVBE becomes bankrupt or insolvent.
- C. The listed DVBE fails or refuses to perform the subcontract or furnish the listed materials.
- D. The Contractor stipulated that a bond was a condition of executing a subcontract and the listed DVBE subcontractor fails or refuses to meet the bond requirements of the Contractor.
- E. The work performed by the listed subcontractor is substantially unsatisfactory and is not in substantial conformance with the plans and specifications or the subcontractor is substantially delaying or disrupting the progress of the work.
- F. The listed DVBE subcontractor is not licensed pursuant to the Contractor's License Law.
- G. It would be in the best interest of the State.

The Contractor shall not be entitled to payment for the work or material unless it is performed or supplied by the listed DVBE or by other forces (including those of the Contractor) pursuant to prior written authorization of the Engineer.

5-1.09 SUBCONTRACTING

Attention is directed to the provisions in Section 8-1.01, "Subcontracting," of the Standard Specifications, Section 2, "Proposal Requirements and Conditions," Section 2-1.04, "Submission of DVBE Information," and Section 3, "Award and Execution of Contract," of these special provisions and these special provisions.

Pursuant to the provisions in Section 1777.1 of the Labor Code, the Labor Commissioner publishes and distributes a list of contractors ineligible to perform work as a subcontractor on a public works project. This list of debarred contractors is available from the Department of Industrial Relations web site at:

<http://www.dir.ca.gov/DLSE/Debar.html>.

The DVBE information furnished under Section 3-1.01A, "DVBE Information," of these special provisions is in addition to the subcontractor information required to be furnished in Section 8-1.01, "Subcontracting," and Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications.

Section 10115 of the Public Contract Code requires the Department to implement provisions to establish a goal for Disabled Veteran Business Enterprise (DVBE) participation in highway contracts that are State funded. As a part of this requirement:

- A. No substitution of a DVBE subcontractor shall be made at any time without the written consent of the Department, and
- B. If a DVBE subcontractor is unable to perform successfully and is to be replaced, the Contractor shall make good faith efforts to replace the original DVBE subcontractor with another DVBE subcontractor.

The provisions in Section 2-1.02, "Disabled Veteran Business Enterprise (DVBE)," of these special provisions that DVBEs shall be certified on the date bids are opened does not apply to DVBE substitutions after award of the contract.

5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS

Attention is directed to the provisions in Sections 10262 and 10262.5 of the Public Contract Code and Section 7108.5 of the Business and Professions Code concerning prompt payment to subcontractors.

5-1.11 PARTNERING

The State will promote the formation of a "Partnering" relationship with the Contractor in order to effectively complete the contract to the benefit of both parties. The purpose of this relationship will be to maintain cooperative communication and mutually resolve conflicts at the lowest possible management level.

The Contractor may request the formation of such a "Partnering" relationship by submitting a request in writing to the Engineer after approval of the contract. If the Contractor's request for "Partnering" is approved by the Engineer, scheduling of a "Partnering" workshop, selecting the "Partnering" facilitator and workshop site, and other administrative details shall be as agreed to by both parties.

The costs involved in providing a facilitator and a workshop site will be borne equally by the State and the Contractor. The Contractor shall pay all compensation for the wages and expenses of the facilitator and of the expenses for obtaining the workshop site. The State's share of such costs will be reimbursed to the Contractor in a change order written by the Engineer. Markups will not be added. All other costs associated with the "Partnering" relationship will be borne separately by the party incurring the costs.

The establishment of a "Partnering" relationship will not change or modify the terms and conditions of the contract and will not relieve either party of the legal requirements of the contract.

5-1.116 COST REDUCTION INCENTIVE

Attention is directed to Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications.

Prior to preparing a cost reduction proposal, the Contractor shall request a meeting with the Engineer to discuss the proposal in concept and to determine the merit of the cost reduction proposal. Items of discussion will also include permit issues, impact on other projects, impact on the project schedule, peer reviews, and review times required by the Department and other agencies.

5-1.12 PLANS AND WORKING DRAWINGS

When the specifications require working drawings to be submitted to the Engineer, the drawings shall be submitted to: Office of Resident Engineer, 280 Beale St., San Francisco, CA 94105 Attention: Resident Engineer, 04-004894.

5-1.13 FORCE ACCOUNT PAYMENT

The second, third and fourth paragraphs of Section 9-1.03A, "Work Performed by Contractor," of the Standard Specifications, shall not apply.

To the total of the direct costs for work performed on a force account basis, computed as provided in Sections 9-1.03A(1), "Labor," 9-1.03A(2), "Materials," and 9-1.03A(3), "Equipment Rental," of the Standard Specifications, there will be added a markup of 28 percent to the cost of labor, 10 percent to the cost of materials, and 10 percent to the equipment rental. These markups shall be applied to all work performed on a force account basis, regardless of whether the work revises the current contract completion date.

The above markups, together with payments made for time related overhead pursuant to "Overhead" of these special provisions, shall constitute full compensation for all overhead costs for work performed on a force account basis. These overhead costs shall be deemed to include all items of expense not specifically designated as cost or equipment rental in Sections 9-1.03A(1), "Labor," 9-1.03A(2), "Materials," and 9-1.03A(3), "Equipment Rental," of the Standard Specifications. The total payment made as provided above and in the first paragraph of Section 9-1.03A, "Work Performed by Contractor," shall be deemed to be the actual cost of the work performed on a force account basis, and shall constitute full compensation therefor. Full compensation for all overhead costs for work performed on a force account basis, and for which no adjustment is made to the quantity of time related overhead pursuant to "Overhead" of these special provisions, shall be considered as included in the markups specified above, and no additional compensation will be allowed therefor.

When extra work to be paid for on a force account basis is performed by a subcontractor, approved in accordance with the provisions in Section 8-1.01, "Subcontracting," of the Standard Specifications, an additional markup of 7 percent will be added to the total cost of said extra work including all markups specified in this section "Force Account Payment". Said additional 7 percent markup shall reimburse the Contractor for additional administrative costs, and no other additional payment will be made by reason of performance of the extra work by a subcontractor.

5-1.14 OVERHEAD

The Contractor will be compensated for overhead in accordance with these special provisions.

Attention is directed to "Force Account Payment" and "Progress Schedule (Critical Path)" of these special provisions.

Section 9-1.08, "Adjustment of Overhead Costs," of the Standard Specifications shall not apply.

Time related overhead shall consist of those overhead costs, including field and home office overhead, that are in proportion to the time required to complete the work. Time related overhead costs shall not include costs that are not related to time, including but not limited to mobilization, licenses, permits, and any other charges incurred only once during duration of the contract.

The quantity of time related overhead to be measured for payment will be the number of working days specified in "Beginning of Work, Time of Completion and Liquidated Damages" of these special provisions, adjusted only as a result of suspensions and adjustments of time which revise the current contract completion date and which are also any of the following:

- A. suspensions of work ordered in accordance with Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications, except:
 - 1. suspensions ordered due to the failure on the part of the Contractor to carry out orders given, or to perform any provision of the contract; and
 - 2. suspensions ordered due to unsuitable weather conditions;
- B. extensions of time granted by the State in accordance with the provisions of the fifth paragraph of Section 8-1.07, "Liquidated Damages," of the Standard Specifications; or
- C. reductions in contract time set forth in approved contract change orders, in accordance with Section 4-1.03, "Changes," of the Standard Specifications.

The contract price paid per working day for time related overhead shall include full compensation for time related overhead measured for payment as specified above, incurred by the Contractor and by any joint venture partner, subcontractor, supplier or other party associated with the Contractor.

No adjustment in compensation will be made for any increase or decrease in the quantities of time related overhead required, regardless of the reason for the increase or decrease. The provisions in Sections 4-1.03B, "Increased or Decreased Quantities" and 4-1.03C, "Changes in Character of the Work," of the Standard Specifications, shall not apply to time related overhead.

For the purpose of making partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications, the number of working days to be paid for time related overhead in each monthly estimate will be the number of working days specified above to be measured for payment that occurred during that monthly estimate period. The amount earned per day for time related overhead shall be the contract unit price for time related overhead, or 15 percent of the original contract amount divided by the number of working days specified in "Beginning of Work, Time of Completion and Liquidated Damages" of these special provisions, whichever is the lesser.

After acceptance of the contract pursuant to Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, the amount, if any, of the contract item price for time related overhead not yet paid will be included for payment in the first estimate made after acceptance of the contract in accordance with Section 9-1.07, "Payment after Acceptance," of the Standard Specifications. For progress payment purposes, the number of working days to be paid for time related overhead in each monthly estimate will be the number of working days specified above to be measured for payment that the Contractor performed work on the current controlling operation or operations as specified in Section 8-1.06, "Time of Completion," of the Standard Specifications. Working days specified above to be measured for payment, on which the Contractor did not perform work on the controlling operation or operations will be measured and included for payment in the first estimate made in accordance with Section 9-1.07, "Payment After Acceptance," of the Standard Specifications. Full compensation for all overhead costs, including overhead costs for increases in the quantity of contract items of work; other than time related overhead measured and paid for as specified above, and other than overhead costs included in the markups specified in "Force Account Payment" of these special provisions; shall be considered as included in the various items of work and no additional compensation will be allowed therefor.

5-1.15 COST REDUCTION INCENTIVE PROPOSAL

Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications is amended by adding the following paragraph:

Prior to preparing a cost reduction proposal, the Contractor shall request a meeting with the Engineer to discuss the proposal in concept and to determine whether the cost reduction proposal will be considered by the Department. Items of discussion will also include permit issues, impact on other projects, impact on the project schedule, traffic considerations, safety, health issues, design criteria, and review times required by the Department and other agencies. Determination by the Engineer that a cost reduction proposal will not be considered will be deemed rejection of the proposal.

5-1.16 TIDAL CONDITIONS AND ELEVATION DATUM

Attention is directed to Section 2-1.03, "Examination of Plans, Specifications, Contract, and Site of Work."

Tidal conditions may present significant problems in constructing the work as depicted in the contract plans. Tidal fluctuations may be severe and different from those shown in published tidal and current data due to differences in datum, winter runoff and other causes. Strong currents exist over portions of the project site. Limited time periods of slack water may restrict diving and other underwater activities.

The Contractor is responsible for being knowledgeable of such tidal difficulties, and no payment will be made by the State for any costs incurred by the Contractor in connection with the variations in actual tidal or current conditions during the course of this contract. Any reference to Mean Higher High and Mean Lower Low tides shall be understood to be an estimate used for permit purposes, actual mean tide data shall be determined by the Contractor.

All vertical control data are based on the National Geodetic Vertical Datum (NGVD) of 1929.

5-1.17 PAYMENTS

Attention is directed to Sections 9-1.06, "Partial Payments," and 9-1.07, "Payment After Acceptance," of the Standard Specifications and these special provisions.

For the purpose of making partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications, the amount set forth for the contract items of work hereinafter listed shall be deemed to be the maximum value of the contract item of work which will be recognized for progress payment purposes:

A. Electronic Mobile Daily Diary Computer System Data Delivery	\$1800.00
B. Bridge Removal (Portion)	\$533,000.00
C. Establish Marine Access	\$173,800.00

After acceptance of the contract pursuant to the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, the amount, if any, payable for a contract item of work in excess of the maximum value for progress payment purposes hereinabove listed for the item, will be included for payment in the first estimate made after acceptance of the contract.

In determining the partial payments to be made to the Contractor, only the following listed materials will be considered for inclusion in the payment as materials furnished but not incorporated in the work:

- A. Miscellaneous Metal (Bridge)

5-1.18 RELATIONS WITH U.S. COAST GUARD

The location of the San Francisco-Oakland Bay Bridge is within an area controlled by the U.S. Coast Guard. The U.S. Coast Guard had authorized the seismic retrofit as repairs in kind in accordance with 33CFR 115.40 in letters dated September 11, 1996 and October 24, 1996. The Contractor acting on behalf of the Department shall be fully informed of all rules, regulations and conditions that may govern the Contractor's operations in said area and shall conduct the Contractor's work accordingly. Further information is included in the U.S. Coast Guard Checklist.

An informational handout entitled, "16591," dated 6/23/99 is available to the Contractor.

Copies of the Checklist may be obtained at the Department of Transportation, Plans and Bid Documents, Room 0200, Transportation Building, 1120 N Street, P.O. Box 942874, Sacramento, California 94274-0001, Telephone No. (916) 654-4490, and are available for inspection at the Toll Bridge Program Duty Senior at District 04 Office, 111 Grand Avenue, Oakland, California 94612, telephone number (510) 286-5549, e-mail address duty_senior_tollbridge_district04@dot.ca.gov.

Attention is directed to Sections 7-1.11, "Preservation of Property," and 7-1.12, "Responsibility for Damage," of the Standard Specifications.

The Contractor's attention is directed to the following conditions which are among those established by the U.S. Coast Guard in the Preconstruction Checklist and their work authorization for this project:

- A. Navigation.--The Contractor's operations shall conform to the U.S. Coast Guard Commandant Instruction M16672.2C.
- B. Aids to Navigation.--The Contractor, acting on behalf of the Department, shall coordinate with the U.S. Coast Guard Commander (POW), Telephone (510) 437-2983 for written authorization at least 60 days prior to any relocation or temporary removal of any aids to navigation within or near any areas involved with dredging or construction. In addition, the Contractor shall not obstruct, willfully damage, make fast to, or interfere with any aid to navigation.

Any debris, material, plant or machinery that incidentally dropped into the waters of the Bay during the progress of work, which may present a hazard or which may obstruct navigation shall be promptly recovered or removed in accordance with the conditions specified in the Preconstruction Checklist.

Attention is directed to Section 8-1.06, "Time of Completion," of the Standard Specifications. Days during which the Contractor's operations are restricted in the navigation channel by others shall be considered to be nonworking days if, in the opinion of the Engineer, these restrictions cause a delay in the current controlling operation or operations.

Full compensation for conforming to the above requirements shall be considered as included in the prices paid for the various contract items of work and no additional compensation will be allowed therefor.

5-1.19 RELATIONS WITH SAN FRANCISCO BAY CONSERVATION DEVELOPMENT COMMISSION (BCDC)

The location of the San Francisco-Oakland Bay Bridge is within an area controlled by the BCDC. Permit has been issued covering work to be performed under this contract. The Contractor shall be fully informed of all rules, regulations and conditions of the permit that may govern the Contractor's operations in said area and shall conduct the Contractor's work accordingly. Said document shall be considered a part of, and shall become, an integral part of the special provisions and contract for this project.

Copies of the Permit may be obtained at the Department of Transportation, Plans and Bid Documents, Room 0200, Transportation Building, 1120 N Street, P.O. Box 942874, Sacramento, California 94274-0001, Telephone No. (916)654-4490, and are available for inspection at the Toll Bridge Program Duty Senior at District 04 Office, 111 Grand Avenue, Oakland, California 94612, e-mail address duty_senior_tollbridge_district04@dot.ca.gov, telephone number (510) 286-5549.

Any modifications to the permit which are proposed by the Contractor shall be submitted in writing to the Engineer for transmittal to the BCDC for their consideration.

When the Contractor is notified by the Engineer that a modification to the permit is under consideration, no work will be allowed on the proposed modification until the Department takes action on the proposed modification. Any modifications to any agreement between the Department of Transportation and BCDC shall be fully binding on the Contractor, and the provisions of this section shall be made a part of every subcontract executed pursuant to this contract.

Full compensation for conforming to the above requirements shall be considered as included in the prices paid for the various contract items of work and no additional compensation will be allowed therefor.

5-1.20 AREAS FOR CONTRACTOR'S USE

No area is available within the contract limits for the exclusive use of the Contractor. However, temporary storage of equipment and materials atop the pier footings may be arranged with the Engineer, subject to the prior demands of State maintenance forces and to other contract requirements. Use of the Contractor's work areas and other State-owned property shall be at the Contractor's own risk. The State shall not be held liable for damage to or loss of materials or equipment located within these areas.

The Contractor shall remove the equipment, materials, and rubbish from the work areas and other State-owned property which the Contractor occupies and shall leave the areas in a presentable condition, in conformance with the provisions in Section 4-1.02, "Final Cleaning Up," of the Standard Specifications.

The Contractor shall secure, at the Contractor's own expense, areas required for storage of plant, equipment, and materials, or for other purposes if sufficient area is not available to the Contractor within the contract limits.

5-1.21 UTILITIES

The Contractor shall make arrangements to obtain electrical power, water or compressed air or other utilities required for the Contractor's operations and shall make and maintain the necessary service connections at the Contractor's own expense. The Contractor shall not use any existing utilities on the Bay Bridge or within the contract limits, unless approved in writing by the Engineer.

5-1.22 SANITARY PROVISIONS

State sanitary facilities will not be available for use by the Contractor's employees.

5-1.23 BRIDGE TOLLS

Toll-free passage on the San Francisco-Oakland Bay Bridge will be granted only for cars, trucks and special construction equipment which are clearly marked on the exterior with the Contractor's identification and which are being operated by the Contractor exclusively for the project, and which are used for the purpose of transporting materials and workers directly to and from the project site.

The Contractor shall make application to the Engineer in advance for toll-free passage. The Contractor will be held accountable for the proper use of passes issued, and upon completion of the work, shall return unused passes to the Engineer.

Attention is directed to Section 23302, "Evasion of Toll," of the Vehicle Code.

5-1.24 ACCESS TO PROJECT SITE

Prospective bidders may make arrangements to visit the project site by contacting the Toll Bridge Duty Senior, 111 Grand Avenue, Oakland, telephone (510)286-5549, or e-mail (duty_senior_tollbridge_district04@dot.ca.gov).

5-1.25 PERMITS AND LICENSES

Attention is directed to Section 7-1.04, "Permits and Licenses," of the Standard Specifications and these special provisions.

The Department has obtained the following permits for this project:

- A. BCDC (Ten Years Permit M 76-37)
- B. Army Corp of Engineers (Army Nationwide Permit 3)
- C. U.S. Coast Guard (file no. 04221-004891 04-SF-80-8.2/8.8)
- D. CA Dept of Fish and Game

Copies of these permits can be obtained at the Department of Transportation, Plans and Bid Documents Section, MS 26, 1120 N Street, Room 200, Sacramento, CA 95814, Telephone 916-654-4490 or may be seen at the office of the Toll Bridge Duty Senior, 111 Grand Avenue, Oakland, telephone (510)286-5549 and e-mail duty_senior_tollbridge_district04@dot.ca.gov.

Full compensation for conforming to the requirements in these permits shall be considered as included in the prices paid for the various contract items of work and no additional compensation will be allowed therefor.

5-1.26 LOADS ON EXISTING STRUCTURES

Anchoring to the bottom of the San Francisco Bay will not be permitted. No lines for anchoring equipment shall be attached to the existing structure except with prior written approval of the Engineer. Such approval, if granted, shall in no way relieve the Contractor of his responsibility for preservation of property as specified in Section 7-1.11, "Preservation of Property," of the Standard Specifications. Attention is directed to "Navigation Requirements" elsewhere in these special provisions.

5-1.27 SUNKEN DEBRIS REMOVAL

Should the Contractor during the progress of the work, sink, lose, or throw overboard any material, plant or machinery into the waters of the Bay, he shall recover or remove such debris immediately.

The Contractor shall give immediate notice to proper authorities and shall mark the location of the fallen debris with U.S. Coast Guard-approved lighted buoys until such debris are removed. Attention is directed to Section "Relations with the U.S. Coast Guard" of these special provisions regarding specific conditions in connection with obstructions to navigation.

5-1.28 NAVIGATION REQUIREMENTS

Attention is directed to Section 7-1.01, "Laws to be Observed," of the Standard Specifications and these special provisions.

The proposed work at San Francisco-Oakland Bay Bridge is located over navigable water. The Contractor shall comply with all requirements of the United States Coast Guard (USGC), as provided elsewhere in these special provisions, or other authorities having jurisdiction thereof with respect to the manner in which he conducts his operations.

Work shall be such that free navigation of the waterway, navigable depths and channel widths are not impaired, except as otherwise allowed by the USCG.

When working on, adjacent to or affecting navigable waters, the Contractor shall provide and monitor not less than one marine radiotelephone capable of transmitting and receiving on Channels 13 and 16, and shall provide maintain and operate such lights, signals and other warning devices as may be required by the District Commandant of the USCG.

Work shall be such that free navigation of the waterway, navigable depths and channel widths are not impaired, except as otherwise allowed by the USCG.

The Contractor shall provide the name and telephone number of the project superintendent to the USCG Bridge Section, Building 10, Room 214, Coast Guard Island, Alameda, CA 94501 5100, Telephone No. (415)437-3514.

Within 15 days prior to beginning work at Piers E2-E5, or within, adjacent to or affecting the navigable waters, the Contractor shall notify the Engineer in writing, along with a drawing, of his proposed method for anchoring barges.

Working drawings complete with location plans, proposed methods of construction and schedules of operations within, adjacent to and affecting navigable waters insofar as the details affect the character of the finished work and for compliance with the regulations of the USCG shall be submitted to the Engineer for approval.

The submittals shall include, but not be limited to, size and location of equipment, anchoring, buoys, warning devices, lights and any other equipment or information required by the Engineer.

Attention is directed to Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications.

Approval of the working drawings by the Engineer will be contingent upon the drawings being satisfactory to the USCG. Work shall not start until the Engineer has reviewed and approved the drawings.

The Engineer will transmit the Contractor's proposal to the Coast Guard for approval. The Contractor shall not anchor any barges until his procedure has been approved by the Coast Guard.

The Contractor shall allow three weeks after complete drawings and all support data are submitted for the Engineer's review and approval.

In the event that the required Coast Guard approval, in the opinion of the Engineer, delays the Contractor's operations, the Contractor will be granted a time extension commensurate with the delay as provided in Section 8-1.07, "Liquidated Damages."

The Contractor may revise approved drawings provided sufficient time is allowed for the Engineer's review and approval before construction is started on the revised portions. Such additional time will not be more than that which was originally allowed.

The Contractor shall keep proper warning devices and lights each night between the hours of sunset and sunrise and whenever required to provide safe navigation for ships, upon all floating equipment connected with the work and upon buoys which are of such size and in such locations as to endanger or obstruct navigation. All floating equipment and anchors must be marked in accordance with Coast Guard Regulations CG-169.

Should the Contractor during the progress of the work, sink, lose, or throw overboard any material, plant, machinery or floatable debris which may be dangerous to or which will obstruct navigation, he shall immediately recover or remove such obstruction. The Contractor shall give immediate notice to the proper authorities and if required, shall mark or buoy such obstructions until they can be removed. Should he neglect or delay compliance with the above requirements, such obstructions shall be removed by the State and the cost of such removal will be deducted from any monies due to the Contractor or may be recovered under this bond.

Compliance on the part of the Contractor with the requirements of this Section shall not be construed as relieving the Contractor from his full responsibility for protecting and guarding the work from injury or damages from any cause as specified under Section 7-1.16, "Responsibility for the Work and Materials," of the Standard Specifications.

Full compensation for conforming to the requirements of this Section shall be considered as included in the contract prices paid for the various items of work involved and no separate payment will be made therefor.

SECTION 6. (BLANK)

SECTION 7. (BLANK)

SECTION 8. MATERIALS

SECTION 8-1. MISCELLANEOUS

8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS

Only materials and products conforming to the requirements of the specifications shall be incorporated in the work. When metric materials and products are not available, and when approved by the Engineer, and at no cost to the State, materials and products in the inch-pound (Imperial) system which are of equal quality and of the required properties and characteristics for the purpose intended, may be substituted for the equivalent metric materials and products, subject to the following provisions:

- A. Materials and products shown on the plans or in the special provisions as being equivalent may be substituted for the metric materials and products specified or detailed on the plans.
- B. Before other non-metric materials and products will be considered for use the Contractor shall furnish, at the Contractor's expense, evidence satisfactory to the Engineer that the materials and products proposed for use are equal to or better than the materials and products specified or detailed on the plans. The burden of proof as to the quality and suitability of substitutions shall be upon the Contractor and the Contractor shall furnish necessary information as required by the Engineer. The Engineer will be the sole judge as to the quality and suitability of the substituted materials and products and the Engineer's decision will be final.
- C. When the Contractor elects to substitute non-metric materials and products, including materials and products shown on the plans or in the special provisions as being equivalent, the list of sources of material as specified in Section 6-1.01, "Source of Supply and Quality of Materials," of the Standard Specification shall include a list of substitutions to be made and contract items involved. In addition, for a change in design or details the Contractor shall submit plans and working drawings in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications.

Unless otherwise specified, the following substitutions of materials and products will be allowed:

SUBSTITUTION TABLE FOR SIZES OF HIGH STRENGTH STEEL FASTENERS

ASTM Designation: A 325M

METRIC SIZE SHOWN ON THE PLANS mm x thread pitch	IMPERIAL SIZE TO BE SUBSTITUTED inch
M16 x 2	5/8
M20 x 2.5	3/4
M22 x 2.5	7/8
M24 x 3	1
M27 x 3	1-1/8
M30 x 3.5	1-1/4
M36 x 4	1-1/2

SUBSTITUTION TABLE FOR PLAIN WIRE REINFORCEMENT, ASTM Designation: A 82

METRIC SIZE SHOWN ON THE PLANS mm ²	US CUSTOMARY UNITS SIZE TO BE SUBSTITUTED inch ² x 100
MW9	W1.4
MW10	W1.6
MW13	W2.0
MW15	W2.3
MW19	W2.9
MW20	W3.1
MW22	W3.5
MW25	W3.9, except W3.5 in piles only
MW26	W4.0
MW30	W4.7
MW32	W5.0
MW35	W5.4
MW40	W6.2
MW45	W6.5
MW50	W7.8
MW55	W8.5, except W8.0 in piles only
MW60	W9.3
MW70	W10.9, except W11.0 in piles only
MW80	W12.4
MW90	W14.0
MW100	W15.5

SUBSTITUTION TABLE FOR BAR REINFORCEMENT

METRIC BAR DESIGNATION NUMBER SHOWN ON THE PLANS	EQUIVALENT IMPERIAL BAR DESIGNATION NUMBER TO BE SUBSTITUTED
13	4
16	5
19	6
22	7
25	8
29	9
32	10
36	11
43	14
57	18

No adjustment will be required in spacing or total number of reinforcing bars due to a difference in minimum yield strength between metric and non-metric bars.

The sizes in the following tables of materials and products are exact conversions of metric sizes of materials and products and are listed as acceptable equivalents:

CONVERSION TABLE FOR SIZES OF:

- (1) STEEL FASTENERS FOR GENERAL APPLICATIONS, ASTM Designation: A 307 or AASHTO Designation: M 314, Grade 36 or 55, and
- (2) HIGH STRENGTH STEEL FASTENERS, ASTM Designation: A 325 or A 449

METRIC SIZE SHOWN ON THE PLANS mm	EQUIVALENT IMPERIAL SIZE inch
6, or 6.35	1/4
8 or 7.94	5/16
10, or 9.52	3/8
11, or 11.11	7/16
13 or 12.70	1/2
14, or 14.29	9/16
16, or 15.88	5/8
19, or 19.05	3/4
22, or 22.22	7/8
24, 25, or 25.40	1
29, or 28.58	1-1/8
32, or 31.75	1-1/4
35, or 34.93	1-3/8
38 or 38.10	1-1/2
44, or 44.45	1-3/4
51, or 50.80	2
57, or 57.15	2-1/4
64, or 63.50	2-1/2
70 or 69.85	2-3/4
76, or 76.20	3
83, or 82.55	3-1/4
89 or 88.90	3-1/2
95, or 95.25	3-3/4
102, or 101.60	4

CONVERSION TABLE FOR NOMINAL THICKNESS OF SHEET METAL

UNCOATED HOT AND COLD ROLLED SHEETS		HOT-DIPPED ZINC COATED SHEETS (GALVANIZED)	
METRIC THICKNESS SHOWN ON THE PLANS	EQUIVALENT US STANDARD GAGE	METRIC THICKNESS SHOWN ON THE PLANS	EQUIVALENT GALVANIZED SHEET GAGE
mm	inch	mm	inch
7.94	0.3125	4.270	0.1681
6.07	0.2391	3.891	0.1532
5.69	0.2242	3.510	0.1382
5.31	0.2092	3.132	0.1233
4.94	0.1943	2.753	0.1084
4.55	0.1793	2.372	0.0934
4.18	0.1644	1.994	0.0785
3.80	0.1495	1.803	0.0710
3.42	0.1345	1.613	0.0635
3.04	0.1196	1.461	0.0575
2.66	0.1046	1.311	0.0516
2.28	0.0897	1.158	0.0456
1.90	0.0747	1.006 or 1.016	0.0396
1.71	0.0673	0.930	0.0366
1.52	0.0598	0.853	0.0336
1.37	0.0538	0.777	0.0306
1.21	0.0478	0.701	0.0276
1.06	0.0418	0.627	0.0247
0.91	0.0359	0.551	0.0217
0.84	0.0329	0.513	0.0202
0.76	0.0299	0.475	0.0187
0.68	0.0269	-----	-----
0.61	0.0239	-----	-----
0.53	0.0209	-----	-----
0.45	0.0179	-----	-----
0.42	0.0164	-----	-----
0.38	0.0149	-----	-----

CONVERSION TABLE FOR WIRE

METRIC THICKNESS SHOWN ON THE PLANS mm	EQUIVALENT USA STEEL WIRE THICKNESS inch	GAGE NO.
6.20	0.244	3
5.72	0.225	4
5.26	0.207	5
4.88	0.192	6
4.50	0.177	7
4.11	0.162	8
3.76	0.148	9
3.43	0.135	10
3.05	0.120	11
2.69	0.106	12
2.34	0.092	13
2.03	0.080	14
1.83	0.072	15
1.57	0.062	16
1.37	0.054	17
1.22	0.048	18
1.04	0.041	19
0.89	0.035	20

CONVERSION TABLE FOR PIPE PILES

METRIC SIZE SHOWN ON THE PLANS mm x mm	EQUIVALENT IMPERIAL SIZE inch x inch
PP 360 x 4.55	NPS 14 x 0.179
PP 360 x 6.35	NPS 14 x 0.250
PP 360 x 9.53	NPS 14 x 0.375
PP 360 x 11.12	NPS 14 x 0.438
PP 406 x 12.70	NPS 16 x 0.500
PP 460 x T	NPS 18 x T"
PP 508 x T	NPS 20 x T"
PP 559 x T	NPS 22 x T"
PP 610 x T	NPS 24 x T"
PP 660 x T	NPS 26 x T"
PP 711 x T	NPS 28 x T"
PP 762 x T	NPS 30 x T"
PP 813 x T	NPS 32 x T"
PP 864 x T	NPS 34 x T"
PP 914 x T	NPS 36 x T"
PP 965 x T	NPS 38 x T"
PP 1016 x T	NPS 40 x T"
PP 1067 x T	NPS 42 x T"
PP 1118 x T	NPS 44 x T"
PP 1219 x T	NPS 48 x T"
PP 1524 x T	NPS 60 x T"

The thickness in inches (T") represents an exact conversion of the metric thickness in millimeters (T).

CONVERSION TABLE FOR STRUCTURAL TIMBER AND LUMBER

METRIC MINIMUM DRESSED DRY, SHOWN ON THE PLANS mm x mm	METRIC MINIMUM DRESSED GREEN, SHOWN ON THE PLANS mm x mm	EQUIVALENT NOMINAL US SIZE inch x inch
19x89	20x90	1x4
38x89	40x90	2x4
64x89	65x90	3x4
89x89	90x90	4x4
140x140	143x143	6x6
140x184	143x190	6x8
184x184	190x190	8x8
235x235	241x241	10x10
286x286	292x292	12x12

CONVERSION TABLE FOR NAILS AND SPIKES

METRIC COMMON NAIL, SHOWN ON THE PLANS Length, mm Diameter, mm	METRIC BOX NAIL, SHOWN ON THE PLANS Length, mm Diameter, mm	METRIC SPIKE, SHOWN ON THE PLANS Length, mm Diameter, mm	EQUIVALENT IMPERIAL SIZE Penny-weight
50.80 2.87	50.80 2.51	————	6d
63.50 3.33	63.50 2.87	————	8d
76.20 3.76	76.20 3.25	76.20 4.88	10d
82.55 3.76	82.55 3.25	82.55 4.88	12d
88.90 4.11	88.90 3.43	88.90 5.26	16d
101.60 4.88	101.60 3.76	101.60 5.72	20d
114.30 5.26	114.30 3.76	114.30 6.20	30d
127.00 5.72	127.00 4.11	127.00 6.68	40d
————	————	139.70 7.19	50d
————	————	152.40 7.19	60d

CONVERSION TABLE FOR IRRIGATION COMPONENTS

METRIC WATER METERS, TRUCK LOADING STANDPIPES, VALVES, BACKFLOW PREVENTERS, FLOW SENSORS, WYE STRAINERS, FILTER ASSEMBLY UNITS, PIPE SUPPLY LINES, AND PIPE IRRIGATION SUPPLY LINES SHOWN ON THE PLANS DIAMETER NOMINAL (DN) mm	EQUIVALENT NOMINAL US SIZE inch
15	1/2
20	3/4
25	1
32	1-1/4
40	1-1/2
50	2
65	2-1/2
75	3
100	4
150	6
200	8
250	10
300	12
350	14
400	16

8-1.02 APPROVED TRAFFIC PRODUCTS

The Department maintains the following list of Approved Traffic Products. The Engineer shall not be precluded from sampling and testing products on the list of Approved Traffic Products.

The manufacturer of products on the list of Approved Traffic Products shall furnish the Engineer a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each type of traffic product supplied.

Signing and delineation materials and products shall not be used in the work unless the material or product is on the list of Approved Traffic Products.

Materials and products may be added to the list of Approved Traffic Products if the manufacturer submits a New Product Information Form to the New Product Coordinator at the Transportation Laboratory. Upon a Departmental request for samples, sufficient samples shall be submitted to permit performance of required tests. Approval of materials or products will depend upon compliance with the specifications and tests the Department may elect to perform.

PAVEMENT MARKERS, PERMANENT TYPE

Retroreflective

- A. Apex, Model 921 (100 mm x 100 mm)
- B. Ray-O-Lite, Models SS (100 mm x 100 mm), RS (100 mm x 100 mm) and AA (100 mm x 100 mm)
- C. Stimsonite, Models 88 (100 mm x 100 mm), 911 (100 mm x 100 mm), 953 (70 mm x 114 mm)
- D. 3M Series 290 (89 mm x 100 mm)

Retroreflective With Abrasion Resistant Surface (ARS)

- A. Ray-O-Lite "AA" ARS (100 mm x 100 mm)
- B. Stimsonite, Models 911 (100 mm x 100 mm), 953 (70 mm x 114 mm)
- C. 3M Series 290 (89 mm x 100 mm)

Retroreflective With Abrasion Resistant Surface (ARS)

(Used for recessed applications)

- A. Stimsonite, Model 948 (58 mm x 119 mm)
- B. Ray-O-Lite, Model 2002 (58 mm x 117 mm)
- C. Stimsonite, Model 944SB (51 mm x 100 mm)*
- D. Ray-O-Lite, Model 2004 ARS (51 mm x 100 mm)*

*For use only in 114 mm wide (older) recessed slots

Non-Reflective For Use With Epoxy Adhesive, 100 mm Round

- A. Apex Universal (Ceramic)
- B. Highway Ceramics, Inc. (Ceramic)

Non-Reflective For Use With Bitumen Adhesive, 100 mm Round

- A. Alpine Products, "D-Dot" and "ANR" (ABS)
- B. Apex Universal (Ceramic)
- C. Apex Universal, Model 929 (ABS)
- D. Elgin Molded Plastics, "Empco-Lite" Model 900 (ABS)
- E. Highway Ceramics, Inc. (Ceramic)
- F. Hi-Way Safety, Inc., Models P20-2000W and 2001Y (ABS)
- G. Interstate Sales, "Diamond Back" (ABS) and (Polypropylene)
- H. Road Creations, Model RCB4NR (Acrylic)
- I. Zumar Industries, "Titan TM40A" (ABS)

PAVEMENT MARKERS, TEMPORARY TYPE

Temporary Markers For Long Term Day/Night Use (6 months or less)

- A. Apex Universal, Model 924 (100 mm x 100 mm)
- B. Davidson Plastics Corp., Model 3.0 (100 mm x 100 mm)
- C. Elgin Molded Plastics, "Empco-Lite" Model 901 (100 mm x 100 mm)
- D. Road Creations, Model R41C (100 mm x 100 mm)
- E. Vega Molded Products "Temporary Road Marker" (75 mm x 100 mm)

Temporary Markers For Short Term Day/Night Use (14 days or less)

(For seal coat or chip seal applications, clear protective covers are required)

- A. Apex Universal, Model 932
- B. Davidson Plastics, Models T.O.M., T.R.P.M., and "HH" (High Heat)
- C. Hi-Way Safety, Inc., Model 1280/1281

STRIPING AND PAVEMENT MARKING MATERIAL

Permanent Traffic Striping and Pavement Marking Tape

- A. Advanced Traffic Marking, Series 300 and 400
- B. Brite-Line, Series 1000
- C. Brite-Line "DeltaLine XRP"
- D. Swarco Industries, "Director 35" (For transverse application only)
- E. Swarco Industries, "Director 60"
- F. 3M, "Stamark" Series 380 and 5730
- G. 3M, "Stamark" Series 420 (For transverse application only)

Temporary (Removable) Striping and Pavement Marking Tape (6 months or less)

- A. Advanced Traffic Marking, Series 200
- B. Brite-Line, Series 100
- C. P.B. Laminations, Aztec, Grade 102
- D. Swarco Industries, "Director-2"
- E. 3M, "Stamark," Series 620
- F. 3M Series A145 Removable Black Line Mask
(Black Tape: For use only on Asphalt Concrete Surfaces)
- G. Advanced Traffic Marking Black "Hide-A-Line"

(Black Tape: For use only on Asphalt Concrete Surfaces)

- H. Brite-Line "BTR" Black Removable Tape
(Black Tape: For use only on Asphalt Concrete Surfaces)

Preformed Thermoplastic (Heated in place)

- A. Flint Trading, "Premark" and "Premark 20/20 Flex"
- B. Pavemark, "Hotape"

Removable Traffic Paint

- A. Belpro, Series 250/252 and No. 93 Remover

Ceramic Surfacing Laminate, 150 mm x 150 mm

- A. Safeline Industries/Highway Ceramics, Inc.

CLASS 1 DELINEATORS

One Piece Driveable Flexible Type, 1700 mm

- A. Carsonite, Curve-Flex CFRM-400
- B. Carsonite, Roadmarker CRM-375
- C. Davidson Plastics, "Flexi-Guide Models 400 and 566"
- D. FlexStake, Model 654 TM
- E. GreenLine Models HWD1-66 and CGD1-66
- F. J. Miller Industries, Model JMI-375 (with soil anchor)

Special Use Flexible Type, 1700 mm

- A. Carsonite, "Survivor" (with 450 mm U-Channel base)
- B. FlexStake, Model 604
- C. GreenLine Models HWD and CGD (with 450 mm U-Channel base)
- D. Safe-Hit with 200 mm pavement anchor (SH248-GP1)
- E. Safe-Hit with 380 mm soil anchor (SH248-GP2) and with 450 mm soil anchor (SH248-GP3)

Surface Mount Flexible Type, 1200 mm

- A. Bent Manufacturing Company, Masterflex Model MF-180EX-48
- B. Carsonite, "Super Duck II"
- C. FlexStake, Surface Mount, Models 704 and 754 TM

CHANNELIZERS

Surface Mount Type, 900 mm

- A. Bent Manufacturing Company, Masterflex Models MF-360-36 (Round) and MF-180-36 (Flat)
- B. Carsonite, "Super Duck" (Flat SDF-436, Round SDR-336)
- C. Carsonite, "Super Duck II" Model SDCF203601MB "The Channelizer"
- D. Davidson Plastics, Flex-Guide Models FG300LD and FG300UR
- E. FlexStake, Surface Mount, Models 703 and 753 TM
- F. GreenLine, Model SMD-36
- G. Hi-Way Safety, Inc. "Channel Guide Channelizer" Model CGC36
- H. The Line Connection, "Dura-Post" Model DP36-3 (Permanent)
- I. The Line Connection, "Dura-Post" Model DP36-3C (Temporary)
- J. Repo, Models 300 and 400
- K. Safe-Hit, Guide Post, Model SH236SMA

CONICAL DELINEATORS, 1070 mm

(For 700 mm Traffic Cones, see Standard Specifications)

- A. Bent Manufacturing Company "T-Top"
- B. Plastic Safety Systems "Navigator-42"
- C. Roadmaker Company "Stacker"
- D. Traffix Devices "Grabber"

OBJECT MARKERS

Type "K", 450 mm

- A. Carsonite, Model SMD-615
- B. FlexStake, Model 701 KM
- C. Repo, Models 300 and 400
- D. Safe-Hit, Model SH718SMA
- E. The Line Connection, Model DP21-4K

Type "K-4" / "Q" Object Markers, 600 mm

- A. Bent Manufacturing "Masterflex" Model MF-360-24
- B. Carsonite, Super Duck II
- C. FlexStake, Model 701KM
- D. Repo, Models 300 and 400
- E. Safe-Hit, Models SH8 24SMA_WA and SH8 24GP3_WA
- F. The Line Connection, Model DP21-4Q

TEMPORARY RAILING (TYPE K) REFLECTORS AND CONCRETE BARRIER MARKERS

Impactable Type

- A. ARTUK, "FB"
- B. Davidson Plastics, Model PCBM-12
- C. Duraflex Corp., "Flexx 2020" and "Electriflexx"
- D. Hi-Way Safety, Inc., Model GMKRM100

Non-Impactable Type

- A. ARTUK, JD Series
- B. Stimsonite, Model 967 (with 83 mm Acrylic cube corner reflector)
- C. Stimsonite, Model 967LS
- D. Vega Molded Products, Models GBM and JD

THREE BEAM BARRIER MARKERS

(For use to the left of traffic)

- A. Duraflex Corp., "Railrider"
- B. Davidson Plastics, "Mini" (75 mm x 254 mm)

CONCRETE BARRIER DELINEATORS, 400 mm

(For use to the right of traffic. When mounted on top of barrier, places top of reflective element at 1200 mm)

- A. Davidson Plastics, Model PCBM T-16
- B. Safe-Hit, Model SH216RBM
- C. Sun-Lab Technology, "Safety Guide Light, Model TM," 130 mm x 130 mm x 80 mm

CONCRETE BARRIER-MOUNTED MINI-DRUM (260 mm x 360 mm x 570 mm)

- A. Stinson Equipment Company "SaddleMarker"

SOUND WALL DELINEATOR

(Applied vertically. Place top of 75 mm x 300 mm reflective element at 1200 mm above roadway)

- A. Davidson Plastics, PCBM S-36
- B. Sun-Lab Technology, "Safety Guide Light, Model SM12," 130 mm x 130 mm x 80 mm

GUARD RAILING DELINEATOR

(Top of reflective element at 1200 mm above plane of roadway)

Wood Post Type, 686 mm

- A. Carsonite, Model 427
- B. Davidson Plastics FG 427 and FG 527
- C. FlexStake, Model 102 GR
- D. GreenLine GRD 27

- E. J. Miller Model JMI-375G
- F. Safe-Hit, Model SH227GRD

Steel Post Type

- A. Carsonite, Model CFGR-327 with CFGRBK300 Mounting Bracket

RETROREFLECTIVE SHEETING

Channelizers, Barrier Markers, and Delineators

- A. 3M, High Intensity
- B. Reflexite, PC-1000 Metalized Polycarbonate
- C. Reflexite, AC-1000 Acrylic
- D. Reflexite, AP-1000 Metalized Polyester
- E. Reflexite, AR-1000 Abrasion Resistant Coating
- F. Stimsonite, Series 6200 (For rigid substrate devices only)

Traffic Cones, 330 mm Sleeves

- A. Reflexite SB (Polyester), Vinyl or "TR" (Semi-transparent)

Traffic Cones, 100 mm and 150 mm Sleeves

- A. 3M Series 3840
- B. Reflexite Vinyl, "TR" (Semi-transparent) or "Conformalite"

Barrels and Drums

- A. Reflexite, "Super High Intensity" or "High Impact Drum Sheeting"
- B. 3M Series 3810

Barricades: Type I, Engineer Grade

- A. American Decal, Adcolite
- B. Avery Dennison, 1500 and 1600
- C. 3M, Scotchlite, Series CW

Barricades: Type II, Super Engineer Grade

- A. Avery Dennison, "Fasign" 2500 Series
- B. Kiwalite Type II
- C. Nikkalite 1800 Series

Signs: Type II, Super Engineer Grade

- A. Avery Dennison, "Fasign" 2500 Series
- B. Kiwalite, Type II
- C. Nikkalite 1800 Series

Signs: Type III, High-Intensity Grade

- A. 3M Series 3800
- B. Nippon Carbide, Nikkalite Brand Ultralite Grade II

Signs: Type IV, High-Intensity Prismatic Grade

- A. Avery Dennison T-6500 (Formerly Stimsonite Series 6200)

Signs: Type VII, High-Intensity Prismatic Grade

- A. 3M Series 3900

Signs: Type VI, Roll-Up Signs

- A. Reflexite, Vinyl (Orange), Reflexite "SuperBright" (Fluorescent orange)
- B. 3M Series RS34 (Orange) and RS20 (Fluorescent orange)

SPECIALTY SIGN (All Plastic)

- A. All Sign Products, STOP Sign, 750 mm

SIGN SUBSTRATE FOR CONSTRUCTION AREA SIGNS

Aluminum

Fiberglass Reinforced Plastic (FRP)

- A. Sequentia, "Polyplate"
- B. Fiber-Brite

SECTION 8-2. (BLANK)

SECTION 8-3. WELDING

8-3.01 WELDING ELECTRODES

Flux core welding electrodes conforming to the requirements of AWS A5.20 E6XT-4 or E7XT-4 shall not be used to perform any type of welding for this project.

8-3.02 WELDING QUALITY CONTROL

Welding quality control shall conform to the requirements in the AWS welding codes, the Standard Specifications, and these special provisions.

Welding quality control shall apply when any work is welded in conformance with the provisions in Section 49, "Piling," Section 52, "Reinforcement," Section 55, "Steel Structures," Section 56-1, "Overhead Sign Structures," Section 75-1.035, "Bridge Joint Restrainer Units," or Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications.

Wherever reference is made to the following AWS welding codes in the Standard Specifications, on the plans or in these special provisions, the year of adoption for these codes shall be as listed:

AWS Code	Year of Adoption
D1.1	1998
D1.4	1992
D1.5	1995
D1.5 (metric only)	1996

All requirements of the AWS welding codes shall apply unless specified otherwise in the Standard Specifications, on the plans or in these special provisions. Wherever the abbreviation AWS is used, it shall be equivalent to the abbreviations ANSI/AWS or ANSI/AASHTO/AWS.

The welding of all fracture critical members (FCMs) shall conform to the provisions specified in the Fracture Control Plan (FCP) and herein.

The Contractor shall designate in writing a welding Quality Control Manager (QCM). The QCM shall be responsible directly to the Contractor for the quality of welding, including materials and workmanship, performed by the Contractor and all subcontractors.

The QCM shall be the sole individual responsible to the Contractor for submitting, receiving, and approving all correspondence, required submittals, and reports to and from the Engineer.

The QCM shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project. The QCM may be an employee of the Contractor.

Welding inspection personnel or nondestructive testing (NDT) firms to be used in the work shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project, except for the following conditions:

- A. The welding is performed at a permanent fabrication facility which is certified under the AISC Quality Certification Program, Category Cbr, Major Steel Bridges.
- B. The welding is performed at a permanent fabrication facility which is certified under the AISC Quality Certification Program, Category Sbd, Conventional Steel Building Structures. This condition shall apply only for work welded in

conformance with the provisions in Section 56-1, "Overhead Sign Structures" or Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications.

For welding performed at such certified facilities, the inspection personnel or NDT firms may be employed or compensated by the fabrication facility performing the welding.

Prior to submitting the Welding Quality Control Plan (WQCP) required herein, a pre-welding meeting between the Engineer, Contractor and any welding subcontractors or entities hired by these subcontractors to be used in the work, shall be held to discuss the requirements for the WQCP.

Prior to performing any welding, the Contractor shall submit to the Engineer, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, 3 copies of a separate WQCP for each item of work for which welding is to be performed. As a minimum, each WQCP shall include the following:

- A. The name of the welding firm and the NDT firm to be used;
- B. A manual prepared by the NDT firm that shall include equipment, testing procedures, code of safe practices, the Written Practice of the NDT firm, and the names, qualifications and documentation of certifications for all personnel to be used;
- C. The name of the QCM and the names, qualifications and documentation of certifications for all Quality Control (QC) Inspectors and Assistant Quality Control Inspectors to be used;
- D. An organizational chart showing all QC personnel and their assigned QC responsibilities;
- E. The methods and frequencies for performing all required quality control procedures, including QC inspection forms to be used, as required by the specifications including:
 - 1. all visual inspections;
 - 2. all NDT including radiographic geometry, penetrameter and shim selection, film quality, film processing, radiograph identification and marking system, and film interpretation and reports; and
 - 3. calibration procedures and calibration frequency for all NDT equipment;
- F. A system for the identification and tracking of all welds, NDT and any required repairs, and a procedure for the reinspection of any repaired welds. The system shall have provisions for 1) permanently identifying each weld and the person who performed the weld, 2) placing all identification and tracking information on each radiograph and 3) a method of reporting nonconforming welds to the Engineer;
- G. Standard procedures for performing noncritical repair welds. Noncritical repair welds are defined as welds to deposit additional weld beads or layers to compensate for insufficient weld size and to fill limited excavations that were performed to remove unacceptable edge or surface discontinuities, rollover or undercut. The depth of these excavations shall not exceed 65 percent of the specified weld size;
- H. The welding procedure specification (WPS), including documentation of all supporting Procedure Qualification Record (PQR) tests performed, and the name of the testing laboratory who performed the tests, to verify the acceptability of the WPS. The submitted WPS shall be within the allowable period of effectiveness;
- I. Documentation of all certifications for welders for each weld process and position that will be used. Certifications shall list the electrodes used, test position, base metal and thickness, tests performed, and the witnessing authority. All certifications shall be within the allowable period of effectiveness; and
- J. One copy each of all AWS welding codes and the FCP which are applicable to the welding to be performed. These codes and the FCP shall become the permanent property of the Department.
- K. Example forms to be used for Certificates of Compliance, daily production logs, and daily reports.

The Engineer shall have 10 working days to review the WQCP submittal after a complete plan has been received. No welding shall be performed until the WQCP is approved in writing by the Engineer. Should the Engineer fail to complete the review within this time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the WQCP, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

An amended WQCP or addendum shall be submitted to, and approved in writing by the Engineer, for any proposed revisions to the approved WQCP. An amended WQCP or addendum will be required for any revisions to the WQCP, including but not limited to a revised WPS, additional welders, changes in NDT firms or procedures, QC or NDT personnel, or updated systems for tracking and identifying welds. The Engineer shall have 3 working days to complete the review of the amended WQCP or addendum. Work that is affected by any of the proposed revisions shall not be performed until the amended WQCP or addendum has been approved. Should the Engineer fail to complete the review within this time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the amended WQCP or addendum, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

After final approval of the WQCP, amended WQCP, or addendum, the Contractor shall submit 7 copies to the Engineer of each of these approved documents.

It is expressly understood that the Engineer's approval of the Contractor's WQCP shall not relieve the Contractor of any responsibility under the contract for the successful completion of the work in conformity with the requirements of the plans and specifications. The Engineer's approval shall not constitute a waiver of any of the requirements of the plans and specifications nor relieve the Contractor of any obligation thereunder, and defective work, materials and equipment may be rejected notwithstanding approval of the WQCP.

A daily production log for welding shall be kept by the QCM for each day that welding is performed. The log shall clearly indicate the locations of all welding, and shall include the welders' names, amount of welding performed, any problems or deficiencies discovered, and any testing or repair work performed, at each location. The daily report from each Quality Control Inspector shall also be included in the log.

The following items shall be included in a Welding Report that is to be submitted to the Engineer within 7 days following the performance of any welding:

- A. Reports of all visual weld inspections and NDT;
- B. Radiographs and radiographic reports, and other required NDT reports;
- C. Documentation that the Contractor has evaluated all radiographs and other nondestructive tests, corrected all rejectable deficiencies, and all repaired welds have been reexamined by the required NDT and found acceptable; and
- D. Daily production log.

All radiographic envelopes shall have clearly written on the outside of the envelope the following information: name of the QCM, name of the nondestructive testing firm, name of the radiographer, date, contract number, complete part description, and all included weld numbers or a report number, as detailed in the WQCP. In addition, all innerleaves shall have clearly written on them the part description and all included weld numbers, as detailed in the WQCP.

All reports regarding NDT, including radiographs, shall be signed by both the NDT technician and the person that performed the review, and then submitted directly to the QCM for review and signature prior to submittal to the Engineer. Corresponding names shall be clearly printed or typewritten next to all signatures.

The Engineer will review the Welding Report to determine if the Contractor is in conformance with the WQCP. Except for steel piling, the Engineer shall be allowed 7 days to review the report and respond in writing after a complete Welding Report has been received. The review time for steel piling shall be as specified in "Piling" of these special provisions. Prior to receiving notification from the Engineer of the Contractor's conformance with the WQCP, the Contractor may encase in concrete or cover any welds for which a Welding Report has been submitted. However, should the Contractor elect to encase or cover those welds prior to receiving notification from the Engineer, it is expressly understood that the Contractor shall not be relieved of the responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Any material not conforming to these requirements will be subject to rejection. Should the Contractor elect to wait to encase or cover any welds pending notification by the Engineer, and should the Engineer fail to complete the review and provide notification within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in notification, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

Sections 6.1.2 through 6.1.4.3 of AWS D 1.1, Sections 7.1.1 and 7.1.2 of AWS D 1.4, and Sections 6.1.1.1 through 6.1.3.3 of AWS D 1.5 are replaced with the following:

Quality Control (QC) shall be the responsibility of the Contractor. As a minimum, the Contractor shall perform inspection and testing prior to welding, during welding and after welding as specified in this section and additionally as necessary to ensure that materials and workmanship conform to the requirements of the contract documents.

The Quality Control (QC) Inspector shall be the duly designated person who performs inspection, testing, and quality matters for all welding.

Quality Assurance (QA) is the prerogative of the Engineer. The QA Inspector is the duly designated person who acts for and on behalf of the Engineer.

All QC Inspectors shall be responsible for quality control acceptance or rejection of materials and workmanship, and shall be currently certified as AWS Certified Welding Inspectors (CWI) in conformance with the requirements in AWS QC1, "Standard and Guide for Qualification of Welding Inspectors."

The QC Inspector may be assisted by an Assistant QC Inspector provided that this individual is currently certified as an AWS Certified Associate Welding Inspector (CAWI) in conformance with the requirements in AWS QC1, "Standard and Guide for Qualification of Welding Inspectors," or has equivalent qualifications. The QC Inspector shall monitor the Assistant QC Inspector's work, and shall be responsible for signing all reports.

When the term "Inspector" is used without further qualification, it shall refer to the QC Inspector.

Section 6.14.6, "Personnel Qualification," of AWS D 1.1, Section 7.7.6, "Personnel Qualification," of AWS D 1.4, and Section 6.1.3.4, "Personnel Qualification," of AWS D 1.5 are replaced with the following:

Personnel performing NDT shall be qualified in conformance with the requirements in the current edition of the American Society for Nondestructive Testing (ASNT) Recommended Practice No. SNT-TC-1A and the Written Practice of the NDT firm. The Written Practice of the NDT firm shall meet or exceed the requirements of the current edition of the ASNT Recommended Practice No. SNT-TC-1A. Only individuals who are 1) qualified for NDT Level II, or 2) Level III technicians who have been directly certified by the ASNT and are authorized to perform the work of Level II technicians, shall perform NDT, review the results, and prepare the written reports.

Section 6.5.4, "Scope of Examination," of AWS D 1.1 and Section 7.5.4 of AWS D 1.4 are replaced with the following:

The QC Inspector shall inspect and approve the joint preparation, assembly practice, welding techniques, and performance of each welder, welding operator, and tack welder to make certain that the applicable requirements of this code and the approved WPS are met.

Section 6.5.4 of AWS D 1.5 is replaced with the following:

The QC Inspector shall inspect and approve the joint preparation, assembly practice, welding techniques, and performance of each welder, welding operator, and tack welder to make certain that the applicable requirements of this code and the approved WPS are met. The QC Inspector shall examine the work to make certain that it meets the requirements of section 3 and 9.21. The size and contour of welds shall be measured using suitable gages. Visual inspection for cracks in welds and base metal, and for other discontinuities should be aided by strong light magnifiers, or such other devices as may be helpful. Acceptance criteria different from those specified in this code may be used when approved by the Engineer.

The Engineer shall have the authority to verify the qualifications or certifications of any welder, Quality Control Inspector, or NDT personnel to specified levels by retests or other means.

A sufficient number of QC Inspectors shall be provided to ensure continuous inspection when any welding is being performed. Continuous inspection, as a minimum, shall include (1) having QC Inspectors continually present on all shifts when any welding is being performed, or (2) having a QC Inspector within such close proximity of all welding operations that inspections by the QC Inspector of each operation, at each welding location, shall not lapse for a period exceeding 30 minutes.

Inspection and approval of the joint preparation, assembly practice, welding techniques, and performance of each welder, welding operator, and tack welder shall be documented by the QC Inspector on a daily basis for each day that welding is performed.

The QC Inspector shall provide reports to the QCM on a daily basis for each day that welding is performed.

Except for noncritical weld repairs, base metal repairs, or any other type of repairs not submitted in the WQCP, the Engineer shall be notified immediately in writing when any welding problems or deficiencies are discovered and also of the proposed repair procedures to correct them. The Engineer shall have 5 working days to review these procedures. No remedial work shall begin until the repair procedures are approved in writing by the Engineer. Should the Engineer fail to complete the review within this time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the proposed repair procedures, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

When joint details that are not prequalified by the applicable AWS codes are proposed for use in the work, all welders using these details shall perform a qualification test plate using the approved WPS variables and the joint detail to be used in production. The test plate shall be the maximum thickness to be used in production. The test plate shall be mechanically or radiographically tested as directed by the Engineer. Mechanical and radiographic testing and acceptance criteria shall be as specified in the applicable AWS codes.

The period of effectiveness for a welder's or welding operator's qualification shall be a maximum of 3 years for the same weld process, welding position, and weld type. A valid qualification at the beginning of work on a contract will be acceptable for the entire period of the contract, as long as the welder's work remains satisfactory.

All qualification tests for welders, welding operators, and WPSs used in welding operations will be witnessed by the Engineer.

Section 6.6.5, "Nonspecified Nondestructive Testing Other Than Visual," of AWS D 1.1, Section 6.6.5 of AWS D 1.4 and Section 6.6.5 of AWS D 1.5 shall not apply.

For any welding, the Engineer may direct the Contractor to perform NDT that is in addition to the visual inspection or NDT specified in the AWS welding codes, in the Standard Specifications or in these special provisions. Additional NDT required by the Engineer, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. Should any welding deficiencies be discovered by this additional NDT, the cost of the testing will not be paid for as extra work and shall be at the Contractor's expense.

All required repair work to correct welding deficiencies, whether discovered by the required visual inspection or NDT, or by additional NDT directed by the Engineer, and any associated delays or expenses caused to the Contractor by performing these repairs, shall be at the Contractor's expense.

At the completion of all welding, the QCM shall sign and furnish to the Engineer, a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each item of work for which welding was performed. The certificate shall state that all of the materials and workmanship incorporated in the work, and all required tests and inspections of this work, have been performed in conformance with the details shown on the plans and the provisions of the Standard Specifications and these special provisions.

Full compensation for conforming to the requirements of this section shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

SECTION 9. DESCRIPTION OF BRIDGE WORK

The bridge work to be done consists, in general, of rehabilitating portions of the existing fenders at Piers E1 through E5 at the locations and as shown on the plans.

SAN FRANCISCO – OAKLAND BAY BRIDGE
EAST BAY SPANS
Bridge No. 33-25

SECTION 10. CONSTRUCTION DETAILS

SECTION 10-1. GENERAL

10-1.01 ORDER OF WORK

Order of work shall conform to the provisions in Section 5-1.05, "Order of Work," of the Standard Specifications and these special provisions.

The first order of work shall be to order the reinforced, recycled plastic lumber, or the composite plastic lumber.

Attention is directed to "Relations With Coast Guard" elsewhere in these special provisions regarding required notifications to the Captain of the Port, and the publication: "Notice to Mariners".

Attention is directed to "Navigation Requirements" elsewhere in these special provisions regarding required submittal of working drawings.

The Contractor shall notify the Engineer, in writing, not less than 15 days in advance, indicating the date he intends to begin work.

10-1.02 COOPERATION

Attention is directed to Section 7-1.14, "Cooperation," and Section 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications and these special provisions.

It is anticipated that work will be in progress by other contractors within or adjacent to the project limits of this contract.

Contracts which may be in progress during the working period of this contract include, but are not limited to, the following:

1. Pile Installation Demonstration (EA 04-012081)
2. Interim East Bay Retrofit (EA 04-043004).
3. Seismic retrofitting of SFOBB West Span Towers and Superstructure (EA 04-0435U4).
4. Seismic retrofitting of SFOBB West Span Anchors and W1 (EA 04-043554)

Progress schedules for the above contracts and other work, when available, may be inspected by the Contractor. Such progress schedules are tentative and no guarantee can be made that such schedules are accurate.

Work by State forces will also be in progress within the contract limits during the working period for this contract.

The Contractor's operations shall be subject to coordination with the work conducted by other contractors and by State forces. The Contractor shall participate in weekly work planning discussions with bridge operations and maintenance personnel for the purpose of coordinating his work with that of other contractors and State forces.

10-1.03 ELECTRONIC MOBILE DAILY DIARY SYSTEM DATA DELIVERY

Attention is directed to Sections 5-1.10, "Equipment and Plants," and 7-1.01A(3), "Payroll Records," of the Standard Specifications, and these special provisions.

The Contractor shall submit to the Engineer a list of each piece of equipment and its identifying number, type, make, model and rate code in accordance with the Department of Transportation publication entitled "Labor Surcharge and Equipment Rental Rate" which is in effect on the date the work is performed, and the names, labor rates and work classifications for all field personnel employed by the Contractor and all subcontractors in connection with the public work, together with such additional information as is identified below. This information shall be updated and submitted to the Engineer weekly through the life of the project.

This personnel information will only be used for this mobile daily diary computer system and it will not relieve the Contractor and subcontractors from all the payroll records requirements as required by Section 7-1.01A(3), "Payroll Records," of the Standard Specifications.

The Contractor shall provide the personnel and equipment information not later than 11 days after the contract award for its own personnel and equipment, and not later than 5 days before start of work by any subcontractor for the labor and equipment data of that subcontractor.

The minimum data to be furnished shall comply with the following specifications:

DATA CONTENT REQUIREMENTS.

- A. The Contractor shall provide the following basic information for itself and for each subcontractor that will be used on the contract:

Caltrans contract ID	Alphanumeric; up to 15 characters.
Company name.	Alphanumeric; up to 30 characters.
Federal tax ID	Alphanumeric; up to 10 characters.
State contractor license	Alphanumeric; up to 20 characters.
Company type (prime or sub)	Alphanumeric; up to 10 characters.
Address (line 1).	Alphanumeric; up to 30 characters.
Address (line 2).	Alphanumeric; up to 30 characters.
Address (city).	Alphanumeric; up to 30 chars.
Address (2-letter state code).	Alphanumeric; up to 2 characters.
Address (zip code)	Alphanumeric; up to 14 characters.
Contact FirstNname.	Alphanumeric; up to 15 characters
Contact LastName	Alphanumeric; up to 20 characters
Telephone number (with area code).	Alphanumeric; up to 20 characters.
Company code: short company name.	Alphanumeric; up to 10 characters.
Type of work (Department-supplied codes)	Alphanumeric; up to 30 characters
DBE status (Department-supplied codes)	Alphanumeric; up to 20 characters.
Ethnicity for DBE status (Department-supplied codes).	Alphanumeric; up to 20 characters.
List of laborers to be used on this contract (detail specified below).	
List of equipment to be used on this contract (detail specified below).	

For example, one such set of information for a company might be:

04-072359
 XYZ CONSTRUCTION, INC.
 94-2991040
 AL1649T
 SUB
 1240 9TH STREET
 SUITE 600
 OAKLAND
 CA

94612
JOHN
SMITH
(510) 834-9999
XYZ
PAVING
MBE
BLACK

B. The Contractor shall provide the following information for each laborer who will be used on the contract:

Caltrans contract ID	Alphanumeric; up to 15 characters.
Company code (as defined above).	Alphanumeric; up to 10 characters.
Employee ID	Alphanumeric; up to 10 characters.
Last name.	Alphanumeric; up to 20 characters.
First name.	Alphanumeric; up to 15 characters.
Middle name.	Alphanumeric; up to 15 characters.
Suffix	Alphanumeric; up to 15 characters
Labor trade (Department-provided codes).	Alphanumeric; up to 10 characters.
Labor classification (Department-provided codes).	Alphanumeric; up to 10 characters.
Regular hourly rate.	Alphanumeric; up to (6,2)
Overtime hourly rate.	Alphanumeric; up to (6,2)
Doubletime hourly rate	Alphanumeric; up to (6,2)
Standby hourly rate.	Alphanumeric; up to (6,2)
Ethnicity (Department-provided codes).	Alphanumeric; up to 20 characters.
Gender.	Alphanumeric; up to 1 characters.

For example, one such set of information might be:

04-072359
XYZ
1249
GONZALEZ
HECTOR
VINCENT
JR.
OPR
JNY
12.50
18.75
25.00
0.00
HISPANIC
M

- C. The Contractor shall provide the following information for each piece of equipment that will be used on the contract:

Caltrans contract ID	Alphanumeric; up to 15 characters.
Company code (as defined above).	Alphanumeric; up to 10 characters.
Company's equipment ID number.	Alphanumeric; up to 10 characters.
Company's equipment description.	Alphanumeric; up to 60 characters.
Equipment type (from Department ratebook).	Alphanumeric; up to 60 characters.
Equipment make (from Department ratebook).	Alphanumeric; up to 60 characters.
Equipment model (from Department ratebook).	Alphanumeric; up to 60 characters.
Equipment rate code (from Department ratebook).	Alphanumeric; up to 10 characters
Regular hourly rate.	Alphanumeric; up to (6,2)
Overtime hourly rate.	Alphanumeric; up to (6,2)
Standby hourly rate	Alphanumeric; up to (6,2)
Idle hourly rate.	Alphanumeric; up to (6,2)
Rental flag.	Alphanumeric; up to 1 character.

For example, one such set of information might be:

04-072359

XYZ

B043

CAT TRACTOR D-6C

TRACC

CAT

D-6C

3645

75.00

75.00

0.00

0.00

N

DATA DELIVERY REQUIREMENTS.

- A. All data described in "Data Requirements" of this section shall be delivered to the Department electronically, on 3 1/2" floppy disks compatible with the Microsoft Windows operating system. The Contractor shall provide a weekly disk and hard copy of the required correct updated personnel and equipment information for the Contractor and all the subcontractors and verified correct by the Engineer.
- B. Data of each type described in the previous section (contractor, labor, and equipment information) will be delivered separately, each type in one or more files on floppy disk. Any given file may contain information from one contractor or from multiple contractors, but only one type of data (contractor, labor, or equipment information).
- C. The file format for all files delivered to Caltrans shall be standard comma-delimited, plain text files. This type of file (often called "CSV") is the most standard type for interchange of formatted data; it can be created and read by all desktop spreadsheet and desktop database applications. Characteristics of this type of file are:
 1. All data is in the form of plain ASCII characters.
 2. Each row of data (company, person, equipment) is delimited by a carriage return character.
 3. Within rows, each column (field) of data is delimited by a comma character.

D. The files shall have the following columns (i.e., each row shall have the following fields):

1. Contractor info: 17 columns (fields) as specified in "Data Requirements #1", above.
2. Labor info: 15 columns (fields) as specified in "Data Requirements #2", above.
3. Equipment info: 13 columns (fields) as specified in "Data Requirements #3", above.

For every one type of file, columns (fields) must be in the order specified under "Data Requirements", above. All columns (fields) described under "Data Requirements" must be present for all rows, even if some column (field) values are empty. The first row of each file must contain column headers (in plain text).

E. Column (field) contents must conform to the data type and length requirements described in the "Data Requirement" section, above. In addition, column (field) data must conform to the following restrictions:

1. All data shall be uppercase.
2. Company type shall be either "PRIME" or "SUB".
3. Labor trade and classification codes must conform to a list of standard codes that will be supplied by Department.
4. Contractor type of work codes and DBE status codes must conform to a list of standard codes that will be supplied by Department.
5. Ethnicity codes must conform to standard codes that will be supplied by Department.
6. Data in the "gender" column must be either "M" or "F".
7. Data in the "rental equipment" column must be either "Y" or "N".
8. Equipment owner's description may not be omitted. (The description, together with the equipment number, is how the equipment will be identified in the field.) Include manufacturer, rated capacity & trade description
9. Equipment type, make, model, and ratebook code shall conform to the Department of Transportation Publication entitled "Labor Surcharge and Equipment Rental Rate", which is in effect on the date the work is performed. If the equipment in question does not have an entry in the book then alternate, descriptive entries may be made in these fields as directed by the Engineer.

F. The name of each file must indicate its contents, e.g., "labor.csv" for laborers, "equipment.csv" for equipment, and "contractor.csv" for contractors. Each floppy disk supplied to Caltrans must be accompanied by a printed list of the files it contains with a brief description of the contents of each file.

PAYMENT.

Payment for providing electronic mobile daily diary computer system data delivery will be made on a lump sum basis. The lump sum bid price for electronic mobile daily diary computer system data delivery will be made according to the following schedule:

The Contractor will receive not more than 30 per cent per month of the total bid price for electronic mobile daily diary computer system data delivery .

After the completion of the work, 100 per cent payment will be made for electronic mobile daily diary computer system data delivery less the permanent deduction, if any, for failure to deliver complete weekly electronic mobile daily diary computer system data in each month.

The contract lump sum price paid for electronic mobile daily diary computer system data delivery shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in electronic mobile daily diary computer system data delivery as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The Department will retain an amount equal to 25 percent of the estimated value of the work performed during the first estimate period in which the Contractor fails to submit electronic mobile daily diary computer system data delivery conforming to the requirements of this section, as determined by the Engineer. Thereafter, on subsequent successive estimate periods the percentage the Department will retain will be increased at the rate of 25 percent per estimate period in which acceptable electronic mobile daily diary computer system data have not been submitted to the Engineer. Retentions for failure to submit acceptable electronic mobile daily diary computer system data shall be additional to all other retentions provided for in the contract. The retention for failure to submit acceptable electronic mobile daily diary computer system data will be released for payment on the next monthly estimate for partial payment following the date that acceptable electronic mobile daily diary computer system data is submitted to the Engineer.

The adjustment provisions in Section 4-1.03, "Changes," of the Standard Specifications, shall not apply to the item of electronic mobile daily diary computer system data delivery. Adjustments in compensation for electronic mobile daily diary computer system data delivery will not be made for any increased or decreased work ordered by the Engineer in furnishing electronic mobile daily diary computer system data.

10-1.04 NON-STORM WATER DISCHARGES.

Non-storm water discharges shall conform to the requirements in Section 7-1.01G, "Water Pollution" of the Standard Specifications and these special provisions

Conformance with the requirements of this section shall in no way relieve the Contractor from the Contractor's responsibilities, as provided in Section 7-1.11, "Preservation of Property," and Section 7-1.12, "Responsibility for Damage," of the Standard Specifications.

SPILL CONTINGENCY

The Contractor shall prepare and submit to the Engineer a contingency plan for the management of spills or leaks of any materials or wastes that may impact the water quality of the San Francisco Bay

The spill contingency plan shall be incorporated within the Water Pollution Control Plan (WPCP), as specified in "Water Pollution Control" of these special provisions.

The contingency plan shall include instructions and procedures for reporting spills, and a list of spill containment and collection materials and equipment to be maintained onsite. The contingency plan shall be reviewed and updated at least every 90 calendar days.

LIQUIDS, RESIDUES AND DEBRIS

Attention is directed to "Bridge Removal (Portion)," "Miscellaneous Metal Bridge," "Reinforced Recycled Plastic Or Composite Plastic Lumber," and "Sunken Debris Removal" of these special provisions.

The control and disposal of liquids, residues, and debris associated with "Bridge Removal (Portion)," "Miscellaneous Metal Bridge," "Reinforced Recycled Plastic Or Composite Plastic Lumber," and "Sunken Debris Removal," shall be described within the WPCP, as specified in "Water Pollution Control" of these special provisions. The WPCP shall, at a minimum, depict and describe the procedural and structural methods of detaining, collecting, and disposing of all slurries, liquids, residues, and debris associated with the operations. Sufficient redundancy shall be incorporated into the procedural and structural methods such that the liquids, residues, and debris are not conveyed into or become present in the San Francisco Bay or other water bodies.

MEASUREMENT AND PAYMENT

Full compensation for conforming to the requirements of this section shall be considered as included in the prices paid for the various contract items of work affected by this section and no additional compensation will be allowed therefor.

10-1.05 WATER POLLUTION CONTROL

Water pollution control work shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications and these special provisions.

This project shall conform to the requirements of General Construction Activity Storm Water Permit No. CAS000002 and Caltrans Statewide Storm Water Permit No. CAS000003 issued by the State Water Resources Control Board. These permits, hereafter referred to as the "Permit," regulates storm water discharges associated with construction activities. Water pollution control work shall conform to the requirements in the Construction Contractor's Guide and Specifications of the Caltrans Storm Water Quality Handbooks, dated April 1997, and addenda thereto issued up to and including the date of advertisement of the project, hereafter referred to as the "Handbook." Copies of the Handbook may be obtained from the Department of Transportation, Material Operations Branch, Publication Distribution Unit, 1900 Royal Oaks Drive, Sacramento, California 95815, Telephone: (916) 445-3520.

Copies of the Handbook, and the Permit are also available for review at 111 Grand Avenue Oakland, California 94601. Please call the Toll Bridge Duty Senior, telephone number (510) 286-5549, e-mail address duty_senior_tollbridge_district04@dot.ca.gov to reserve a copy of the document at least 24 hours in advance.

The Contractor shall know and fully comply with the applicable provisions of the Handbook and Federal, State, and local regulations that govern the Contractor's operations and discharges from both the project site and areas of disturbance outside the project limits during construction.

Unless arrangements for disturbance of areas outside the project limits are made by the Department and made part of the contract, it is expressly agreed that the Department assumes no responsibility whatsoever to the Contractor or property owner with respect to any arrangements made between the Contractor and property owner to allow disturbance of areas outside the project limits.

The Contractor shall be responsible for the costs and for liabilities imposed by law as a result of the Contractor's failure to comply with the requirements set forth in this section "Water Pollution Control" including, but not limited to, compliance with the applicable provisions of the Handbook and Federal, State, and local regulations. For the purposes of this paragraph, costs and liabilities include, but are not limited to, fines, penalties, and damages whether assessed against the State or the Contractor, including those levied under the Federal Clean Water Act and the State Porter Cologne Water Quality Act.

In addition to the remedy authorized by law, an amount of the monies due to the Contractor under the contract may be retained by the Department until full compliance with the contract documents and disposition has been made of the costs and liabilities.

The retention of money due the Contractor shall be subject to the following:

- A. The Department will give the Contractor 30 days notice of the Department's intention to retain funds from partial payments which may become due to the Contractor prior to acceptance of the contract. Retention of funds from payments made after acceptance of the contract may be made without prior notice to the Contractor.
- B. No retention of additional amounts out of partial payments will be made if the amount to be retained does not exceed the amount being withheld from partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications.
- C. If the Department has retained funds and it is subsequently determined that the State is not subject to the costs and liabilities in connection with the matter for which the retention was made, the Department shall be liable for interest on the amount retained at the legal rate of interest for the period of the retention.

Conformance with the provisions in this section "Water Pollution Control" shall not relieve the Contractor from the Contractor's responsibilities as provided in Section 7, "Legal Relations and Responsibilities," of the Standard Specifications.

WATER POLLUTION CONTROL PROGRAM PREPARATION, APPROVAL AND UPDATES

As part of the water pollution control work, a Water Pollution Control Program, hereafter referred to as the "WPCP," is required for this contract. The WPCP shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications, the requirements in the Handbook, and these special provisions.

No work having potential to cause water pollution, as determined by the Engineer, shall be performed until the WPCP has been approved by the Engineer.

Within 30 days after the approval of the contract, the Contractor shall submit 3 copies of the WPCP to the Engineer. The Engineer will have 10 days to review the WPCP. If revisions are required, as determined by the Engineer, the Contractor shall revise and resubmit the WPCP within 7 days of receipt of the Engineer's comments. The Engineer will have 7 days to review the revisions. Upon the Engineer's approval of the WPCP, 3 additional copies of the WPCP incorporating the required changes shall be submitted to the Engineer. Minor changes or clarifications to the initial submittal may be made and attached as amendments to the WPCP. In order to allow construction activities to proceed, the Engineer may conditionally approve the WPCP while minor revisions or amendments are being completed.

The WPCP shall identify pollution sources that may adversely affect the quality of discharges associated with the project and shall identify water pollution control measures, hereafter referred to as control measures, to be constructed, implemented, and maintained in order to reduce to the extent feasible pollutants in discharges from the construction site during construction under this contract.

The WPCP shall incorporate control measures in the following categories:

- A. Nonstorm water management and waste management and disposal control practices.

Specific objectives and minimum requirements for each category of control measures are contained in the Handbook.

The Contractor shall consider the objectives and minimum requirements presented in the Handbook for each of the above categories. The special minimum requirements listed below supersede the minimum requirements listed in the Handbook for the same category. When minimum requirements are listed for any category, the Contractor shall incorporate into the WPCP, and implement on the project, the listed minimum controls required in order to meet the pollution control objectives for the category. In addition, the Contractor shall consider other control measures presented in the Handbook and shall incorporate into the WPCP and implement on the project the control measures necessary to meet the objectives of the WPCP. The Contractor shall document the selection process in conformance with the procedure specified in the Handbook. The following special minimum requirements are established:

Category	Minimum Requirement(s)
Non-Storm Water and Waste Management and Disposal Control Practices	CD11 Material Use
	CD12 Spill Prevention and Control
	CD13 Solid Waste Management
	CD14 Hazardous Waste Management
	CD17 Sanitary / Septic Waste Management
	CD18 Vehicle and Equipment Cleaning
	CD19 Vehicle and Equipment Fueling
	CD20 Vehicle and Equipment Maintenance
	CD44 Illicit Discharge / Illegal Dumping Reporting
	CD46 Liquid Waste Management

The Contractor shall consider other control measures to supplement these critical temporary control measures when necessary to meet the pollution control objectives of the WPCP.

The WPCP shall include, but not be limited to, the following items as described in the Handbook:

- A. Project description and Contractor's certification;
- B. Project information;
- C. Pollution sources, control measures, and water pollution control drawings; and
- D. Amendments, if any.

The Contractor shall amend the WPCP, graphically and in narrative form, whenever there is a change in construction activities or operations which may affect the discharge of significant quantities of pollutants to surface waters, ground waters, municipal storm drain systems or when deemed necessary by the Engineer. The WPCP shall be amended if the WPCP has not achieved the objective of reducing pollutants in storm water discharges. Amendments shall show additional control measures or revised operations, including those in areas not shown in the initially approved WPCP, which are required on the project to control water pollution effectively. Amendments to the WPCP shall be submitted for review and approval by the Engineer in the same manner specified for the initially approved WPCP. Amendments shall be dated and attached to the on-site WPCP document.

The Contractor shall keep a copy of the WPCP, together with updates, revisions and amendments at the project site.

WPCP IMPLEMENTATION

Upon approval of the WPCP, the Contractor shall be responsible throughout the duration of the project for installing, constructing, inspecting, and maintaining the control measures included in the WPCP and any amendments thereto and for removing and disposing of temporary control measures. Unless otherwise directed by the Engineer or specified in these special provisions, the Contractor's responsibility for WPCP implementation shall continue throughout any temporary suspension of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications. Requirements for installation, construction, inspection, maintenance, removal, and disposal of control measures are specified in the Handbook and these special provisions.

Soil stabilization practices and sediment control measures, including minimum requirements, shall be provided throughout the project .

Implementation of soil stabilization practices and sediment control measures for soil-disturbed areas on the project site shall be completed, except as provided for below, not later than 20 days prior to the beginning of the winter season or upon start of applicable construction activities for projects which begin either during or within 20 days of the winter season.

Throughout the winter season, the active, soil-disturbed area of the project site shall be not more than 1.9 hectares. The Engineer may approve, on a case-by-case basis, expansions of the active, soil-disturbed area limit. The Contractor shall demonstrate the ability and preparedness to fully deploy soil stabilization practices and sediment control measures to protect soil-disturbed areas on the project site before the onset of precipitation. A quantity of soil stabilization and sediment control materials shall be maintained on site equal to 100 percent of that sufficient to protect unprotected, soil-disturbed areas on the project site. A detailed plan for the mobilization of sufficient labor and equipment shall be maintained to fully deploy control measures required to protect unprotected, soil-disturbed areas on the project site prior to the onset of precipitation. A current inventory of control measure materials and the detailed mobilization plan shall be included as part of the WPCP.

Throughout the winter season, soil-disturbed areas on the project site shall be considered to be nonactive whenever soil disturbing activities are expected to be discontinued for a period of 20 or more days and the areas are fully protected. Areas that will become nonactive either during the winter season or within 20 days thereof shall be fully protected with soil stabilization practices and sediment control measures within 10 days of the discontinuance of soil disturbing activities or prior to the onset of precipitation, whichever is first to occur.

Throughout the winter season, active soil-disturbed areas of the project site shall be fully protected at the end of each day with soil stabilization practices and sediment control measures unless fair weather is predicted through the following work day. The weather forecast shall be monitored by the Contractor on a daily basis. The National Weather Service forecast shall be used. An alternative weather forecast proposed by the Contractor may be used if approved by the Engineer. If precipitation is predicted prior to the end of the following work day, construction scheduling shall be modified, as required, and functioning control measures shall be deployed prior to the onset of the precipitation.

The Contractor shall implement, year-round and throughout the duration of the project, control measures included in the WPCP for nonstorm water management, and waste management and disposal.

The Engineer may order the suspension of construction operations which create water pollution if the Contractor fails to conform to the provisions in this section "Water Pollution Control" as determined by the Engineer.

MAINTENANCE

To ensure the proper implementation and functioning of control measures, the Contractor shall regularly inspect and maintain the construction site for the control measures identified in the WPCP. The Contractor shall identify corrective actions and time needed to address any deficient measures or reinstate any measures that have been discontinued.

The construction site inspection checklist provided in the Handbook shall be used to ensure that the necessary measures are being properly implemented, and to ensure that the control measures are functioning adequately. One copy of each site inspection record shall be submitted to the Engineer.

Inspections of the construction site shall be conducted by the Contractor to identify deficient measures, as follows:

- A. Prior to a forecast storm;
- B. After each storm event;
- C. At 24-hour intervals during extended precipitation events; and
- D. Routinely, at a minimum of once every week.

If the Contractor or the Engineer identifies a deficiency in the deployment or functioning of an identified control measure, the deficiency shall be corrected immediately. The deficiency may be corrected at a later date and time if requested by the Contractor and approved by the Engineer in writing, but not later than the onset of subsequent precipitation events. The correction of deficiencies shall be at no additional cost to the State.

PAYMENT

Full compensation for conforming to the provisions in this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

Those control measures which are shown on the plans and for which there is a contract item of work will be measured and paid for as that contract item of work.

The Engineer will retain an amount equal to 25 percent of the estimated value of the contract work performed during estimate periods in which the Contractor fails to conform to the provisions in this section "Water Pollution Control" as determined by the Engineer.

Retentions for failure to conform to the provisions in this section "Water Pollution Control" shall be in addition to the other retentions provided for in the contract. The amounts retained for failure of the Contractor to conform to the provisions in this section will be released for payment on the next monthly estimate for partial payment following the date that a WPCP has been implemented and maintained and water pollution is adequately controlled, as determined by the Engineer.

10-1.06 PROGRESS SCHEDULE (CRITICAL PATH)

The Contractor shall submit to the Engineer for acceptance a baseline progress schedule within 5 working days of contract award. The schedule shall show the order in which the Contractor proposes to carry out the work, with logical links shown between the time-scaled work activities and calculations made using the Critical Path Method (CPM) to determine the controlling operations. The baseline progress schedule shall conform to the time and order of work requirements of the contract.

The schedule work activities shall include, but are not limited to: delivery and review of submittals, mobilization of equipment, procurement of materials, contract milestones and constraints, interfaces with outside entities, contract item work, and final cleanup. The dates on which the Contractor plans to start the work activities and the calculated completion dates for those activities shall be shown. Each activity in the schedule shall be identified with a clear and legible description. Each activity, with the exception of the start and end milestones, shall have as a minimum at least one predecessor and one successor. Activities shall have a duration of not less than one working day nor more than 20 working days, unless otherwise approved by the Engineer.

The Contractor may furnish the schedule on a form of the Contractor's choice. With each schedule submittal, the Contractor shall provide one set of originally-plotted time-scaled network diagrams. The diagrams shall be 11 inches x 17 inches in size. In addition, if a computer program is used to generate the schedule, the Contractor shall submit one 3.5-inch, 1.44 megabyte computer diskette, containing the schedule data.

The work shall be executed in the sequence indicated in the accepted baseline schedule and subsequent accepted updates and revisions. The Contractor shall be responsible for assuring that work sequences are logical and that the network shows a coordinated plan for completion of the work. Failure of the Contractor to include in the schedule any element of work required for the performance of the contract shall not relieve the Contractor from completing all work within the time limit specified for completion of the contract. Omissions or errors in any element of work, activity or logic, discovered by either the Contractor or the Engineer, shall be corrected by the Contractor at the next scheduled update or revision.

When there are significant changes in the order or duration of work activities, the Contractor shall submit a current update and a revised schedule. The update schedule shall include the status of completion of the project just prior to the date of the significant change. The revised schedule shall be the current update revised to include the change. The Contractor shall state in writing the reasons for the change, including revisions to activities, logic, and duration's. On or before Monday of each week, the Contractor shall submit an updated schedule showing the work completed as of the Friday of the previous week and the work remaining to be performed. Updated and revised schedules shall be submitted in the same manner as the baseline schedule.

Subsequent to the time that submittal of a progress schedule is required in accordance with these specifications, no progress payments will be made for any work until a satisfactory schedule has been submitted to the Engineer.

Full compensation for progress schedule (critical path) shall be considered as included in the contract prices paid for the various items of work involved, and no additional compensation will be allowed therefor.

10-1.07 OBSTRUCTIONS

Attention is directed to Section 8-1.10, "Utility and Non-Highway Facilities," Section 15, "Existing Highway Facilities," and Section 51-1.19, "Utility Facilities," of the Standard Specifications and these special provisions.

The Contractor's attention is directed to the existence of underwater cables for the facilities of Pacific Gas & Electric Company, Pacific Bell, and MCI, and to the existence of an underground sewer line, all in the vicinity of the work. Other underwater facilities may exist.

10-1.08 MOBILIZATION

Mobilization shall conform to the provisions in Section 11, "Mobilization," of the Standard Specifications.

10-1.09 TRANSPORTATION FOR THE ENGINEER

Attention is directed to Section 5-1.08, "Inspection," of the Standard Specifications. The Engineer and all authorized representatives of the State, acting within the scope of their duties in connection with the work under this contract, shall be permitted at all times to ride as passengers without charge on any boats operated by or for the Contractor, for the transportation of personnel, in connection with the work under this contract. It is agreed that such rides will be taken only on boats which are making trips in connection with the Contractor's operations, and that special trips solely for the benefit of the Engineer or other State representatives will not be required.

Full compensation for conforming to the requirements of this section shall be considered as included in the contract prices paid for the various items of work and no additional compensation will be allowed therefor.

10-1.10 ESTABLISH MARINE ACCESS

This work shall consist of the preparatory work and operations necessary to provide marine access to the job site for personnel, equipment, supplies and incidentals, including furnishing, erecting, maintaining and removing barges, trestles and other facilities. This work shall be separate from and in addition to the work specified in Section 11, "Mobilization," of the Standard Specifications.

The Contractor shall submit, for approval by the Engineer, a schedule of values detailing the cost breakdown of the contract lump sum item for establish marine access. The schedule of values shall reflect the items, work, quantities and costs required to establish marine access to the job site. The Contractor shall be responsible for the accuracy of the quantities and costs used in the schedule of values submitted for approval.

The sum of the amounts for the items and work listed in the schedule of values shall be equal to the contract lump sum price for establish marine access. Changes in the schedule of values, due to changes by the Contractor in the items and work listed, shall not result in a change in the contract lump sum price for establish marine access.

The schedule of values for establish marine access shall be submitted to the Engineer within the time required for submittal of the Interim Baseline Schedule, as specified in "Progress Schedule (Critical Path)" of these special provisions. The items and work listed in the schedule of values shall be designated in the resource loading required in the Baseline Schedule required in "Progress Schedule (Critical Path)" of these special provisions.

The schedule of values will be used only to determine progress payments for establish marine access during the progress of the work. No partial payment for establish marine access will be made until the schedule of values is approved in writing by the Engineer.

The contract lump sum price paid for establish marine access shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in establishing marine access to the job site, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The adjustment provisions in Section 4-1.03C, "Changes," of the Standard Specifications shall not apply to the contract lump sum price for establish marine access. Full compensation for damages due to delays shall be considered as included in the payments made in accordance with "Overhead" of these special provisions and Section 8-1.09, "Right of Way Delays," of the Standard Specifications and additional compensation will be allowed therefor.

When other contract items are adjusted as provided in Section 4-1.03, "Changes," of the Standard Specifications, the costs of establishing marine access to the job site will be deemed to have been recovered by the Contractor through the payments made for establish marine access, and will be excluded from consideration in determining compensation for the adjustments.

10-1.11 CONSTRUCTION AREA SIGNS

Construction area signs shall be furnished, installed, maintained, and removed when no longer required in conformance with the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to the provisions in "Approved Traffic Products" of these special provisions. Type II retroreflective sheeting shall not be used on construction area sign panels.

The Contractor shall notify the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to commencing excavation for construction area sign posts. The regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	1-800-642-2444 1-800-227-2600
Underground Service Alert-Southern California (USA)	1-800-422-4133 1-800-227-2600

Excavations required to install construction area signs shall be performed by hand methods without the use of power equipment, except that power equipment may be used if it is determined there are no utility facilities in the area of the proposed post holes.

Sign substrates for stationary mounted construction area signs may be fabricated from fiberglass reinforced plastic as specified under "Approved Traffic Products" of these special provisions.

10-1.12 MAINTAINING TRAFFIC

Attention is directed to Sections 7-1.08, "Public Convenience," 7-1.09, "Public Safety," and 12, "Construction Area Traffic Control Devices," of the Standard Specifications and to the provisions in "Public Safety" of these special provisions and these special provisions. Nothing in these special provisions shall be construed as relieving the Contractor from the responsibilities specified in Section 7-1.09.

No work that would require a lane closure shall be performed.

Personal vehicles of the Contractor's employees shall not be parked on the traveled way or shoulders, including any section closed to public traffic.

10-1.13 TEMPORARY CRASH CUSHION MODULE

This work shall consist of furnishing, installing, and maintaining sand filled temporary crash cushion modules in groupings or arrays at each location shown on the plans, as specified in these special provisions or where designated by the Engineer. The grouping or array of sand filled modules shall form a complete sand filled temporary crash cushion in conformance with the details shown on the plans and these special provisions.

Attention is directed to "Public Safety" of these special provisions.

GENERAL

Whenever the work or the Contractor's operations establishes a fixed obstacle, the exposed fixed obstacle shall be protected with a sand filled temporary crash cushion. The sand filled temporary crash cushion shall be in place prior to opening the lanes adjacent to the fixed obstacle to public traffic.

Sand filled temporary crash cushions shall be maintained in place at each location, including times when work is not actively in progress. Sand filled temporary crash cushions may be removed during a work period for access to the work provided that the exposed fixed obstacle is 4.6 m or more from a lane carrying public traffic and the temporary crash cushion is reset to protect the obstacle prior to the end of the work period in which the fixed obstacle was exposed. When no longer required, as determined by the Engineer, sand filled temporary crash cushions shall be removed from the site of the work.

MATERIALS

At the Contractor's option, the modules for use in sand filled temporary crash cushions shall be either Energite III Inertial Modules, Fitch Inertial Modules or Traffix Sand Barrels manufactured after March 31, 1997, or equal:

- A. Energite III Inertial Modules, manufactured by Energy Absorption Systems, Inc., One East Wacker Drive, Chicago, IL 60601-2076, Telephone 1-312-467-6750, FAX 1-800-770-6755.
 - 1. Distributor (Northern): Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828, Telephone 1-800-884-8274, FAX 1-916-387-9734
 - 2. Distributor (Southern): Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, CA 92805, Telephone 1-800-222-8274, FAX 1-714-937-1070.
- B. Fitch Inertial Modules, manufactured by Roadway Safety Service, Inc., 1050 North Rand Road, Wauconda, IL 60084, Telephone 1-800-426-0839, FAX 1-847-487-9820.
 - 1.. Distributor (Northern): Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828, Telephone 1-800-884-8274, FAX 1-916-387-9734
 - 2. Distributor (Southern): Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, CA 92805, Telephone 1-800-222-8274, FAX 1-714-937-1070.
- C. Traffix Sand Barrels, manufactured by Traffix Devices, Inc., 220 Calle Pintoresco, San Clemente, CA 92672, Telephone 1-949-361-5663, FAX 1-949-361-9205.
 - 1. Russ Enterprises, Inc., 1533 Berger Drive, San Jose, CA 95112, Telephone 1-408-287-4303, FAX 1-408-287-1929.
 - 2. Statewide Safety, P.O. Box 1440, Pismo Beach, CA 93448, Telephone 1-800-559-7080, FAX 1-805-929-5786.

Modules contained in each temporary crash cushion shall be of the same type at each location. The color of the modules shall be the standard yellow color, as furnished by the vendor, with black lids. The modules shall exhibit good workmanship free from structural flaws and objectionable surface defects. The modules need not be new. Good used undamaged modules conforming to color and quality of the types specified herein may be utilized. If used Fitch modules requiring a seal are furnished, the top edge of the seal shall be securely fastened to the wall of the module by a continuous strip of heavy duty tape.

Modules shall be filled with sand in conformance with the manufacturer's directions, and to the sand capacity in kilograms for each module shown on the plans. Sand for filling the modules shall be clean washed concrete sand of commercial quality. At the time of placing in the modules, the sand shall contain not more than 7 percent water as determined by California Test 226.

Modules damaged due to the Contractor's operations shall be repaired immediately by the Contractor at the Contractor's expense. Modules damaged beyond repair, as determined by the Engineer, due to the Contractor's operations shall be removed and replaced by the Contractor at the Contractor's expense.

INSTALLATION

Temporary crash cushion modules shall be placed on movable pallets or frames conforming to the dimensions shown on the plans. The pallets or frames shall provide a full bearing base beneath the modules. The modules and supporting pallets or frames shall not be moved by sliding or skidding along the pavement or bridge deck.

A Type R or P marker panel shall be attached to the front of the crash cushion as shown on the plans, when the closest point of the crash cushion array is within 3.6 m of the traveled way. The marker panel, when required, shall be firmly fastened to the crash cushion with commercial quality hardware or by other methods determined by the Engineer.

At the completion of the project, temporary crash cushion modules, sand filling, pallets or frames, and marker panels shall become the property of the Contractor and shall be removed from the site of the work. Temporary crash cushion modules shall not be installed in the permanent work.

MEASUREMENT AND PAYMENT

Temporary crash cushion modules placed in conformance with the provisions in "Public Safety" of these special provisions will not be measured nor paid for.

10-1.14 EXISTING HIGHWAY FACILITIES

The work performed in connection with various existing highway facilities shall conform to the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Plans of the existing bridges may be requested by fax from the Office of Structure Maintenance and Investigations, 1801 30th Street, Sacramento, CA, Fax (916) 227-8357.

Plans of the existing bridges available to the Contractor are reproductions of the original contract plans with significant changes noted and working drawings and do not necessarily show normal construction tolerances and variances. Where dimensions of new construction required by this contract are dependent on the dimensions of the existing bridges, the Contractor shall verify the controlling field dimensions and shall be responsible for adjusting dimensions of the work to fit existing conditions.

10-1.15 BRIDGE REMOVAL

Removing portions of bridges shall conform to the provisions in Section 15-4, "Bridge Removal," of the Standard Specifications and these special provisions.

Bridge removal (portion) shall consist of removing portions of the existing timber fender system as shown on the plans.

All removed materials that are not to be salvaged or used in the reconstruction shall become the property of the Contractor and shall be disposed outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Attention is directed to "Navigation Requirements" of these special provisions regarding debris and floatable materials.

The removal of the existing timbers at any pier shall occur concurrently with the installation of the new fender materials there. The time during which the faces of the concrete pier aprons or the pier sides are exposed shall be as short as possible.

10-1.16 REINFORCED, RECYCLED PLASTIC OR COMPOSITE PLASTIC LUMBER

Reinforced, Recycled Plastic (RRP) or Composite Plastic (CP) lumber shall consist of furnishing and installing RRP or CP lumber, and hardware assemblies as shown on the plans and as specified in these special provisions.

Recycled plastic shall meet the requirements of a recycled product. Recycled product shall be defined as all materials, goods, and supplies, no less than 50 percent of the total weight of which consists of secondary and post consumer waste with not less than 10 percent of its total weight consisting of post consumer waste. Post consumer waste is defined as a finished material which would have been disposed of as a solid waste, having completed its life cycle as a consumer item, and does not include manufacturing waste. Secondary waste is defined as fragments of finished products or finished products of a manufacturing process, which has converted a resource into a commodity of real economic value, and includes post consumer waste, but does not include excess virgin resources of the manufacturing process.

The cross-sectional dimensions of the plastic lumber shall not vary more than ± 13 mm nor shall the length vary more than ± 25 mm from the dimensions shown on the plans.

RRP and CP lumber that is damaged shall be replaced by the Contractor and at the Contractor's expense.

WORKING DRAWINGS

The Contractor shall submit working drawings to the Engineer in accordance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications and these special provisions.

The working drawings shall be 279 mm x 432 mm in size and each drawing shall include the job site name of the structure as shown on the contract plans, District-County-Route, bridge number, and contract number. The working drawings shall show complete details of component layout and attachment details and shall be supplemented by manufacturer's material test reports, manufacturer's performance data, and two copies of the printed literature for the product.

For initial review, 5 sets of drawings shall be submitted. After the working drawings have been approved by the Engineer, between 6 and 12 sets, as requested by the Engineer, shall be submitted to the Engineer for use during construction.

The Engineer will require 3 weeks to review the working drawings after a complete set has been received, as determined by the Engineer. Should the Engineer fail to complete his review within the time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in the working drawings review, the delay will be considered a right of way delay as specified in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

After installation of the RRP and CP lumber is complete at all locations, the Contractor shall submit one set of reduced prints on 10 kilogram (minimum) bond paper, 279 mm x 432 mm inches in size, of the corrected original tracings of all working drawings. The Contractor shall submit microfilms of these corrected original tracings to the Engineer in conformance the following:

- A. At the completion of said work, one set of reduced prints on 10 kilogram (minimum) bond paper, 279 mm x 432 mm in size, of the corrected original tracings of all working drawings for each structure shall be furnished to the Engineer. Reduced prints of drawings which are common to more than one structure shall be submitted for each structure. An index prepared specifically for the drawings for each structure containing sheet numbers and titles shall be included on the first reduced print in the set for each structure. Reduced prints for each structure shall be arranged in the order of drawing numbers shown in the index.
- B. The edge of the corrected original tracing image shall be clearly visible and visually parallel with the edges of the page. A clear, legible symbol shall be provided as near to the upper left side of each page as is feasible within the original print to show the amount of reduction and a horizontal and vertical scale shall be provided on each reduced print to facilitate enlargement to original scale.

MATERIALS AND FABRICATION FOR RRP LUMBER

The plastic for RRP lumber shall be a mixture of one or more of the following thermoplastics: high density polyethylene, medium density polyethylene, low density polyethylene, or high density polypropylene. The lumber shall be mixed with appropriate colorants to produce a black or dark brown color, and with ultra violet inhibitors and antioxidants so that the resulting plastic portion of the product meets the physical property requirements specified herein. RRP lumber shall consist of a dense outer skin, not less than 5 mm thick, surrounding a less dense core.

The RRP lumber shall be produced continuously and homogeneously without joints and with the cross-sectional dimensions within 13 mm of those shown on the plans. Any interior voids in the lumber shall not exceed 13 mm diameter. At an exposed end of the member, there shall not be more than one void greater than 25 mm in diameter, and no more than 4 voids greater than 6 mm in diameter. RRP lumber shall have a smooth outer skin with a minimum of exposed voids and shall be straight and true, free of twist, curvature, bulging and other undesirable deformations.

RRP lumber shall be reinforced with fiberglass reinforcing elements. The reinforcing elements shall extend continuously through the length of the member, without splices. During the casting or extruding process, reinforcing elements must be held firmly in the position indicated by the manufacturer. Each piece of RRP lumber shall be permanently marked with the manufacturer's name.

RRP lumber shall be cut, beveled, drilled, countersunk, and otherwise fabricated in accordance with the manufacturer's recommendations by technicians who are skilled and experienced in the trade. Fabrication shall be done in the manufacturer's facilities to the greatest extent possible.

RRP lumber shall be shipped in a manner that will minimize scratching or damage to outer surfaces. RRP lumber shall be stacked on dunnage above ground such that it may be readily inspected, and stored in a manner that will avoid undue injury. RRP lumber shall be handled with rope slings. Sharp instruments shall not be used in handling the lumber. RRP lumber damaged in shipping or handling will be rejected.

MATERIALS AND FABRICATION FOR CP LUMBER.

The plastic for the shell of CP lumber shall be produced from polyester or epoxy resin reinforced with E glass and shall be mixed with the appropriate colorants, ultraviolet inhibitors and antioxidants, so that the resulting plastic shell meets the physical property requirements specified herein.

The core material for CP lumber shall be a lightweight aggregate polymer concrete meeting physical property requirements described herein.

The CP lumber shall be produced continuously and homogeneously without joints and with the cross-sectional dimensions within 13 mm of those shown on the plans. The CP lumber shall be seamless with a smooth outer surface and shall be straight and true, free of twist, curvature, bulging and other undesirable deformation. Any interior voids in the core material shall not exceed 13 mm diameter. Each piece of CP lumber shall be permanently marked with the manufacturer's name.

CP lumber shall be cut, beveled, drilled, countersunk, and otherwise fabricated in accordance with the manufacturer's recommendations and by technicians who are skilled and experienced in this trade. Fabrication shall be done in the manufacturer's facilities to the greatest extent possible.

Cut ends of the CP lumber shall be sealed with a cap securely held in place with an adhesive recommended by the manufacturer. The adhesive shall show no more than a 10% decrease in strength when tested in accordance with ASTM Designation: D3164 following two cycles of exposure in accordance with ASTM Designation: D1183, Procedure D. The procedure shall be modified so that the cold temperature phase of the procedure shall be at -20°+3°C and the high temperature phase shall be at 60°+3°C.

CP lumber shall be coated with a black (Federal Standard 595B No. 37030) or dark brown (Federal Standard 595B No. 30097) coating to a minimum dry film thickness of 1.5 mils. No visible color change in the coating shall occur when tested in accordance with ASTM Designation: D4329 using UVB-313 bulbs operating at a UV intensity of 0.47 W/m² measured at 310 nm for 100 cycles. The cycle shall be 4 hours of ultraviolet (UV) exposure at 60°C and 4 hours of condensate (CON) exposure at 40°C. The coating shall have a minimum initial adhesion value of 1 MPa when tested in accordance with ASTM Designation: D4541. The coating shall show no more than a 10% decrease in its initial adhesion strength following two exposure cycles in accordance with ASTM Designation : D1183, Procedure D as modified above.

CP lumber shall be shipped in a manner that will minimize scratching or damage to outer surfaces. CP lumber shall be stacked on dunnage above ground so that it may be readily inspected and shall be stored in a manner that will avoid undue injury. CP lumber shall be handled with rope slings. Sharp instruments shall not be used in handling the lumber. CP lumber damaged in shipping or handling will be rejected.

PHYSICAL PROPERTY REQUIREMENTS

The RRP and CP lumber shall have physical properties as listed in the following table:

PROPERTY	TEST	REQUIREMENT	
		RRP	CP
Density	ASTM D792, Procedure A; ASTM E12	Skin: 880-1010 kg/m ³ Core: 720-880 kg/m ³	Shell: 1760 kg/m ³ , min.
Water Absorption	ASTM D570 (maximum weight increase)	Skin: 0.5% max. at 24 hrs. Core: 1.0% max. at 2 hrs 3.0% max at 24 hrs.	Shell: 0.1% max. at 2 hrs. 0.2 % max. at 24 hrs.
Brittleness	ASTM D746	Skin: No break at -40°C at 267 m-N/m	Shell: No break at -45°C at 267 m-N/m
Impact Resistance	ASTM D746, Modified	Skin: 214 m-N/m, min.	Shell: 1334 m-N/m, min.
Hardness	ASTM D2240	Skin: 45-75 (Shore D)	Shell: 45-75 (Shore D)
Ultraviolet Deterioration	ASTM D4329 UVB-313 (See Note 1)	Skin: For 500 hrs. exposure: Shore D durometer hardness shall not change more than 1%	Shell: 2000 hrs. exposure: less than 10% loss if structural strength (See Note 2)
Abrasion	ASTM D4060	Skin: Weight loss:<0.5 g wear index: 2.5-3.0 cycles: 10,000 wheel: CS17 load: 1 kg	
Chemical Resistance	ASTM D543	Sea Water < 1.5% weight increase Gasoline < 7.5% weight increase No. 2 Diesel < 6.0% weight increase	
Stiffness, minimum lb-in ² (for rectangular sections, value specified is for the weak axis)		1.40 x 10 ⁸ for 8 x 10 lumber 1.52 x 10 ⁸ for 8 x 12 lumber 2.76 x 10 ⁸ for 10 x 10 lumber 3.38x 10 ⁸ for 10 x 12 lumber 4.60 x 10 ⁸ for 12 x 12 lumber	4.54 x 10 ⁸ for 8 x 10 lumber 5.41 x 10 ⁸ for 8 x 12 lumber 8.74 x 10 ⁸ for 10 x 10 lumber 10.4 x 10 ⁸ for 10 x 12 lumber 17.9 x 10 ⁸ for 12 x 12 lumber
Ignition Temperature	ASTM D1929-91a	over 343°F	over 343°F
Marine Borers		total resistance	total resistance
Dry Rot		total resistance	total resistance
Shrinkage/Swelling		negligible	negligible

Note 1: ASTM D4329 using UVB 313 bulbs operating at a UV intensity of 0.47 W/m² /nm measured at 310 nm. The exposure cycle shall be 4 hours of ultraviolet (UV) exposure at 60°C and 4 hours condensate (CON) exposure at 40°C.

Note 2: The exposure cycle shall be the same as in Note 1. Structural values to be measured:

ASTM D638 - tensile strength, tensile modulus

ASTM D790 - flexural strength, flexural modulus

ASTM D256 - Izod impact

The fiberglass reinforcing elements for the RRP lumber shall have the following properties:

PROPERTY	TEST	REQUIRE-MENT
Flexural Strength	ASTM D790	483 MPa, min.
Compression Modulus	ASTM D695	276 MPa, min.
Tensile Strength	ASTM D638	483 MPa, min.

The core for the CP lumber shall have the following properties:

PROPERTY	REQUIRE-MENT
Density	1760 kg/m ³ , min.
28 Day Compressive Strength	35 MPa, min.

All hardware shall be stainless steel anchor devices as shown on the plans. All couplings, bolts and lag bolts, shall be ASTM A 276, Type 316 stainless steel.

CHOCKS AND FILLER BLOCKS

Unreinforced Recycled Plastic (RP) may be used in lieu of RRP for chocks and filler blocks, when RRP lumber is used as the fender material. This material shall meet all of the requirements for RRP except that the fiberglass reinforcement is deleted.

MEASUREMENT AND PAYMENT

RRP, CP and RP lumber will be measured by cubic meter. The contract price paid per cubic meter for furnish and install RRP or CP lumber shall include full compensation for furnishing all labor, materials including all hardware, anchor devices, couplings, bolts, and lag bolts, tools, equipment and incidentals, and for doing all work involved in furnishing and installing RRP, CP and RP lumber, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.17 MISCELLANEOUS METAL (BRIDGE)

Miscellaneous metal (bridge) shall conform to the provisions for miscellaneous bridge metal in Section 75, "Miscellaneous Metal," of the Standard Specifications and these special provisions.

Walers, corner frames and braces, including stiffeners and splice plates shall conform to the requirements of ASTM Designation: A36 steel.

The walers shall be heat curved by the manufacturer in his shop.

The holes in the inner flanges of the inner walers (only) may be field drilled. No other method than drilling shall be allowed for making these holes. All other holes in the walers, corner frames and braces shall be drilled in the shop before galvanizing.

No field cutting or field welding of steel will be allowed.

Holes in the new steel members shall be bored 3 mm larger in diameter than the bolt.

The bare metal surfaces resulting from the field drilled holes and any damaged areas of the galvanizing on any of the steel parts shall be repaired as specified in Section 75-1.05 of the Standard Specifications.

Attention is directed to "Welding Quality Control" of these special provisions.

Miscellaneous metal (bridge) shall consist of the miscellaneous bridge metal items listed in Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications, and the following:

- A. Walers, corner frames, braces, shims and other related hardware
- B. Boarding ladders
- C. Fastening bolts including lag bolts, concrete anchorage devices and threaded rods, nuts, washers and other connecting and attachment hardware

Immediately before placing corner frames, braces, shims, or other steel members directly against existing concrete surfaces, the Contractor shall thoroughly clean the surfaces of the concrete and the steel to be in contact, and shall apply a coating of non-sag polysulfide or polyurethane caulking conforming to the provisions in Federal Specification TT-S-230, Type II, to the contact areas.

Cast-in-place inserts shall be the ferrule loop type.

All metal parts of anchorage devices shall be fabricated from stainless steel conforming to the requirements of ASTM Designation: A 276, Type 304 or 316.