




**PROJECT SCOPE SUMMARY REPORT
(STRUCTURE REHABILITATION)**
To Request Programming in the 2012
SHOPP and Provide Project Approval

01-DN 101 & 199-PM VARIOUS
01-0A100K
EFIS #: 0112000023
Seismic Retrofit
Program 20.10.201.113
December, 2011



IN DEL NORTE COUNTY AT VARIOUS LOCATIONS ON US 101 & 199

I have reviewed the 'right of way' information contained in this Project Scope Summary Report and the RW Data Sheet attached hereto, and find the data to be complete, and accurate:

[Signature]
KAREN HAWKINS
NORTH REGION DIVISION CHIEF - RIGHT OF WAY

APPROVAL RECOMMENDED:
[Signature]
KEVIN CHURCH
PROJECT MANAGER

APPROVAL RECOMMENDED:
[Signature]
ROYAL MCCARTHY
DISTRICT PROGRAM ADVISOR

APPROVED:

[Signature]
CHARLES C. FIELDER
District Director

Date

12/7/11


This Project Scope Summary Report-Seismic Retrofit has been prepared under the direction of the following registered civil engineer. The registered civil engineer attests to the technical information contained herein and the engineering data upon which recommendations, conclusions, and decisions are based.



Jeffrey Pimentel, PE
Registered Civil Engineer



DATE



1. INTRODUCTION AND BACKGROUND

Advance Planning has prepared this Project Scope Summary Report (PSSR) for a seismic retrofit project that consists of 5 bridge locations along United States, US 101 and US 199 in Del Norte County. These bridges are the Railroad Avenue Overcrossing #01-0063 (101-PM R28.32), Smith River Overflow Bridge #01-0046 (101-PM 35.77), Rowdy Creek Bridge #01-0023 (101-PM 39.63), SR 199/101 Connector Overcrossing #01-0058F (199-PM T0.51) and the Middle Fork Smith River Bridge #01-0044 (199-PM R17.06).

See Attachment A for the Project Map

Work on each bridge varies from removing column flares, installing column shells, installing anchor piles behind abutments, installing a seat extender, completing infill walls and replacing cross-frames. See Section 6 Alternatives for specific work at each location.

See Attachment J for the Cost estimate and specific work items included in this project.

Project Limits	<i>01-DN-101</i>
	01-0063: PM R28.32
	01-0046: PM 35.77
	01-0023: PM 39.63
	<i>01-DN-199</i>
01-0058F: PM T0.51	
01-0044: PM R17.06	
Construction Costs:	\$10,726,000 (2011)
Right of way Costs:	\$3,318,000 (2011) \$4,091,000 (2016)
Funding Source:	SHOPP 201.113
Number of Alternatives:	2 (Includes No Build)
Recommended Alternative (for programming and scheduling):	Build Alternative
Type of Facility	01-0063: Freeway (OC County Rd)
	01-0046: Expressway
	01-0023: Expressway
	01-0058F: Conventional
01-0044: Conventional	
Number of Structures:	5
Anticipated Environmental Definitiation/Document:	CEQA- IS/Mitigated ND NEPA-CE

2. RECOMMENDATION

It is recommended that the Build Alternative be programmed into the 2012 SHOPP cycle in the 201.113 program. The “no build” alternative does not meet the purpose and need of the project. The total project cost for Build Alternative has been estimated at \$14,044,000 (2011).

3. PURPOSE AND NEED STATEMENT

Need:

These bridges were identified in the Structure Replacement and Improvement Needs (STRAIN) Report as bridges with seismic vulnerabilities. This project will repair the seismic deficiencies and improve the structural integrity during a seismic event.

Purpose:

The purpose of this project is to improve the integrity of the structures by performing a seismic retrofit on the five bridges identified in the scope of work.

4. EXISTING FACILITY, DEFICIENCIES AND TRAFFIC DATA

4A. Roadway Geometric Information

Facility (1)	Minimum	Facility Type	Through Traffic Lanes (2)			Paved Shoulder Width (3)		Median (4)	Shoulder is a Bicycle Lane (5)	Other Bicycle Lane Width (6)	Bicycle Route (7)	Facilities Adjacent to the Roadbed (8)
			No. of Lanes	Lane Width	Type (Flex, Rigid, Composite)	Left	Right					
Railroad Ave OC PM R28.32 #01-0063	NA	County Rd	2	12'	NA	8'	8'	0'	N	NA	Y	--
			2	12'		8'	8'	0'				
			2	12'		8'	8'	n/a				
Smith River Overflow PM 35.77 #01-0046	NA	Exp	2	12'	NA	8'	8'	2'	N	NA	Y	--
			2	12'		8'	8'	2'				
			2	12'		8'	8'	n/a				
Rowdy Creek PM 39.63 #01-0023	NA	Exp	2	12'	NA	8'	8'	0'	N	NA	Y	--
			2	12'		8'	8'	0'				
			2	12'		8'	8'	n/a				
199/101 OC PM T0.51 #01-0058F	NA	Conv	2	12'	NA	10'	5'	0'	N	NA	Y	--
			2	12'		10'	5'	0'				
			2	12'		8'	4'	n/a				
Middle Fork Smith River PM R17.06 #01-0044	NA	Conv	4	12'	NA	4'	4'	4.5'	N	NA	Y	--
			4	12'		4'	4'	4.5'				
			4	12'		8'	8'	n/a				

4B. Condition of Existing Facility:

(1) Pedestrian Facility Data

The bridges have no pedestrian facilities.

(2) Bicycle Facility Data

Most of US 101 throughout the District (from Route 1 at Leggett to the California/Oregon State Line) is legislatively designated as the “Pacific Coast Bike Route”. The Route Concept Report indicates Caltrans is interested in upgrading shoulders to better accommodate bicycle traffic. Non-motorized needs were considered, however due to the project scope being limited to seismic retrofits, widening shoulders is not included in the project.

The Route Concept Report for US 199 indicates Caltrans is interested in widening shoulders when feasible to better accommodate bicycle traffic and STAA trucks. Non-motorized needs were considered, however due to the project scope being limited to seismic retrofits, widening shoulders is not included in the project.

4C. Structures Information

Railroad Avenue OC

The 199/101 Connector Overcrossing was built in 1971 and is a continuous 2-span CIP/PS concrete box girder, with the abutments founded on driven PC/PS concrete piles and the bent founded on RC spread footings.

Smith River Overflow

The Smith River Overflow Bridge was built in 1955 (widened in 2007) and is a continuous 10-span CIP/RC flat slab founded on driven RC piles.

Rowdy Creek

The Rowdy Creek Bridge was built in 1951 (widened in 1991) and is a simply supported 2-span plate girder, with a CIP/RC deck founded on RC spread footing.

US 199/US101 Connector Overcrossing

The 199/101 Connector Overcrossing was built in 1971 and is a continuous 2-span CIP/PS concrete box girder founded on driven PC/PS concrete piles.

Middle Fork Smith River

The Middle Fork Smith River Bridge was built in 1965 (widened in 1976) and is a continuous 5-span CIP/RC box girder, with an AC overlay, founded on RC spread footings.

Table: Structure Data

Structures	Facility Type	Width Between Curbs (ft)		Replace Bridge Railings	Vertical Clearance		Work Identified in STRAIN	Replace Bridge Approach Rail	Replace Bridge Approach Slab	#		
		Exist	3R Sid		Prop	Exist					3R Sid	Prop
#01-0063												
Railroad Ave OC PM R28.32	County Road-Overcrossing Freeway	40.6	n/a	40.6	N	17.2	16.5	17.2	Y	N	N	n/a
#01-0046												
Smith River Overflow PM 35.77	Expressway	47.6	n/a	47.6	N	n/a	n/a	n/a	Y	N	N	n/a
#01-0023												
Rowdy Creek PM 39.63	Expressway	40.6	n/a	40.6	N	n/a	n/a	n/a	Y	N	N	n/a
#01-0058F												
199/101 OC PM T0.51	Conventional	39.6	n/a	39.6	N	17.7	16.5	17.7	Y	N	N	n/a
#01-0044												
Middle Fork Smith River PM R17.06	Conventional	61	n/a	61	N	n/a	n/a	--	Y	N	N	n/a

4D. Vehicle Traffic Data

Table: Traffic Volume Data

PM	Facility Type	Base ADT (2010)	Construction Year ADT (2013)	10-yr ADT (2023)	20-yr ADT (2033)	D %	DH Trucks %	10-yr TI	20-yr TI
#01-0063	County Rd-Overcrossing	10,900	11,400	13,000	14,700	60	5.0	9.0	10.0
PM R28.07/R28.57	Freeway								
#01-0046	Expressway	6,900	7,210	8,250	9,280	60	4.0	8.5	9.8
Smith River Overflow									
PM 35.52/36.02									
#01-0023	Expressway	6,900	7,210	8,250	9,280	60	4.0	8.5	9.8
Rowdy Creek									
PM 39.38/39.88									
#01-0058F	Conventional	2,300	2,370	2,600	2,830	60	10.0	8.5	9.0
199/101 OC									
PM L0.506/L0.684									
#01-0044	Conventional	3,100	3,190	3,500	3,810	60	12.0	9.0	9.5
Middle Fork									
Smith River									
PM R16.81/R17.31									

The above Traffic Forecasting Data was provided by the Office of Travel Forecasting and Modeling.

Table: Traffic Collision Data

PM	Facility Type	Actual (COL/MVM)			Statewide Average (COL/MVM)		
		Fatal	F+I	Total	Fatal	F+I	Total
#01-0063	County Rd-Overcrossing	0	0.2	0.4	0.017	0.18	0.39
Railroad Ave OC	Freeway						
PM R28.07/R28.57							
#01-0046	Expressway	0.146	0.29	0.73	0.025	0.27	0.6
Smith River Overflow							
PM 35.52/36.02							
#01-0023	Expressway	0.157	0.79	1.42	0.025	0.27	0.6
Rowdy Creek							
PM 39.38/39.88							
#01-0058F	Expressway	0**	0**	0**	0.007**	0.2**	0.55**
199/101 OC							
PM L0.506/L0.684							
#01-0044	Expressway	0	0	0.36	0.014	0.39	1.1
Middle Fork							
Smith River							
PM R16.81/R17.31							

**Rates are in Collisions per million vehicle (MV)

The data on the previous page was obtained by performing a 5-year TASAS collision analysis. The information was collected between July 1, 2005 and June 30, 2010. The report analyzed collisions for each bridge segment.

No patterns of collisions were identified by Traffic Safety at any of the bridges.

The following summarizes the rates and types of collisions that were identified at each bridge location:

Railroad Avenue OC

From TASAS Table B, this 0.5 mile highway segment has an actual total collision rate of 0.40, which is 1.03 times greater than the statewide average for similar highway facilities. The actual fatal collision rate is less than the statewide average for similar highway facilities. The actual fatal+injury (F+I) collision rate is 0.20, which is 1.1 times greater than the statewide average for similar highway facilities.

Of the reported 4 collisions, 0 resulted in fatality, 2 resulted in injury, and 2 were “property damage only”. Three of these collisions occurred on a “dry” road surface and 1 occurred on a “snowy/icy” road surface. One out of the 4 collisions was a “sideswipe” type collision, 1 was a “broadside”, 1 was a “hit object”, and 1 was an “overturn” type collision. The primary collision factors for these collisions consisted of the following: 2 “improper turn”, 1 “speeding”, and 1 “not stated”.

Smith River Overflow

From TASAS Table B, this 0.5 mile highway segment has an actual total collision rate of 0.73, which is 1.2 times greater than the statewide average for similar highway facilities. The actual fatal collision rate is 0.146, which is 5.8 times greater than the statewide average for similar highway facilities. The actual fatal+injury (F+I) collision rate is 0.29, which is 1.1 times greater than the statewide average for similar highway facilities.

Of the reported 5 collisions, 1 resulted in fatality, 1 resulted in injury, and 3 were “property damage only”. Three of these collisions occurred on a “dry” road surface, 1 occurred on a “wet” road surface, and 1 occurred on a “snowy/icy” road surface. Three of the 5 collisions were “sideswipe” type collisions and 2 collisions were “hit object” type collisions. The primary collision factors for these collisions consisted of the following: 2 “improper turn”, 1 “speeding”, 1 “unknown”, and 1 “other than driver”.

Rowdy Creek

From TASSAS Table B, this 0.5 mile highway segment has an actual total collision rate of 1.42, which is 2.4 times greater than the statewide average for similar highway facilities. The actual fatal collision rate is 0.157, which is 6.3 times greater than the statewide average for similar highway facilities. The actual fatal+injury (F+I) collision rate is 0.79, which is 2.9 times greater than the statewide average for similar highway facilities.

Of the reported 9 collisions, 1 resulted in fatality, 4 resulted in injury, and 4 were “property damage only”. Seven of these collisions occurred on a “dry” road surface, 1 occurred on a “wet” road surface, and 1 occurred on a “snowy/icy” road surface. Three of the 9 collisions were “broadside” type collisions, 3 were “hit object”, 2 were “rear end”, and 1 was an “overturn” type collision. The primary collision factors for these collisions consisted of the following: 3 “improper turn”, 2 “speeding”, 2 “failure to yield”, 1 “influence of alcohol”, and 1 “other than driver”.

To address the high collision rates in this segment the Office of Traffic Safety has initiated/completed the following projects:

- Designated as a Daylight Headlight Section (work order issued, sign to be installed in 2011).
- Increased roadway shoulder width and installed rumble strips, PM 39.6/43.7
- (01-491404, Completed 8/2/11).
- Signs in vicinity have been replaced with retro-reflective panels.

US 199/US 101 Connector Overcrossing

From TASSAS Table B, this 0.18 mile highway segment has an actual total collision rate which is less than the statewide average for similar highway facilities. The actual fatal collision rate is less than the statewide average for similar highway facilities. The actual fatal+injury (F+I) collision rate is less than the statewide average for similar highway facilities.

Middle Fork Smith River

From TASSAS Table B, this 0.5 mile highway segment has an actual total collision rate of 0.36, which is less than the statewide average for similar highway facilities. The actual fatal collision rate is less than the statewide average for similar highway facilities. The actual fatal+injury (F+I) collision rate is less than the statewide average for similar highway facilities.

The reported 1 collision was “property damage only”. This collision occurred on a snowy/icy surface. This was a “hit object” type collision. The primary collision factor was “speeding”.

5. CORRIDOR AND SYSTEM COORDINATION

5A. US 101 (Bridge #01-0023, 01-0046, 01-0063)

The Route Concept Report (RCR) (2002) indicates the concept for US 101 from the Washington Boulevard Interchange (PM 27.6) to the Oregon Border is 4-lane freeway/expressway. Designation currently varies from freeway, expressway and conventional within this segment. Bringing Segment PM 31.3/46.5 up to a 4-lane freeway/expressway is not within the scope of a Seismic Retrofit project.

The concept for rehabilitation for ADT over 6,000 for two lane cross sections is to provide 40-foot wide roadway when feasible. However, rehabilitation standards allow the roadway cross-section to be a minimum of 32-feet. All bridges within this segment meet the concept width.

The RCR states that shoulder widening to accommodate non-motorized traffic is desirable. Non-motorized needs were considered, however due to the project scope being limited to seismic retrofits, widening shoulders is not included in the project.

5B. US 199 (Bridge #01-0058F, 01-0044):

The Route Concept Report (RCR) (1999) indicates the concept for US 199 from the Junction with US 101 to the Oregon Border is a two-lane conventional highway with intermittent passing lanes. The 199/101 Connector Overcrossing is located within RCR Segment 1, which is a 2-lane conventional section. Middle Fork Smith River Bridge is located within RCR Segment 2, which is a 4-lane conventional section.

The concept for rehabilitation for ADT ranging from 3,000- 6,000 is to provide a 40-foot wide roadway when feasible, to safely accommodate STAA trucks. However, rehabilitation standards allow the roadway cross-section to be a minimum of 28-feet. The Middle Fork Smith River exceeds both the concept and minimum widths. The 101/199 Connector Overcrossing meets the minimum width.

The RCR states that shoulder widening to accommodate STAA trucks and bicycles is desirable. Non-motorized & STAA needs were considered, however due to the project scope being limited to seismic retrofits, widening shoulders is not included in the project.

6. ALTERNATIVES

6A. Retrofit Strategy:

Alternative 1 – Build Alternative

The retrofit strategy is as follows at each bridge:

Railroad Avenue OC

Install 4-foot diameter cast-in-drilled-hole (CIDH) anchor piles behind the abutments (two at each abutment). The pile heads will be tied to the end diaphragm through steel pipes and high strength rods.

From underneath the overcrossing the existing column flares will be removed and the column flare reinforcements cut. Excavation around column to the footing will occur in order to install full length column casing. A non-structural column flare around casing for aesthetic purpose will be installed to match existing columns, leaving a 4” gap between the soffit of the bridge and the new column.

Smith River Overflow

A seat extender will be placed at the hinge in span 5 with four shallow steel members bolted through the deck to the short span.

Rowdy Creek

The existing cross-frames at the support locations will be removed and replaced. Rivets and stiffeners will be removed using a cutting torch and small areas of the existing bridge will need to be blast cleaned and painted.

US 199/SR 101 Connector Overcrossing

Install 4-foot diameter cast-in-drilled-hole (CIDH) anchor piles behind the abutments (two at each abutment). The pile heads will be tied to the end diaphragm through steel pipes and high strength rods.

From underneath the overcrossing the existing column flares will be removed and the column flare reinforcements cut. Excavation around column to the footing will occur in order to install full length column casing. A column flare around casing for aesthetic purpose will be installed to match existing columns, leaving a 4” gap between the soffit of the bridge and the new column.

Middle Fork Smith River

Install 4-foot diameter cast-in-drilled-hole (CIDH) anchor piles behind the abutments (two at each abutment). The pile heads will be tied to the end diaphragm through steel pipes and high strength rods.

Add concrete to the outside of the left bridge piers to match the right bridge pier thickness. Complete concrete infill walls in between the left and right bridge. Permanently install steel plates for confinement of the infill walls and columns.

**See Attachment B for the Project Layouts for Alternative 1.
See Attachment D for the Structures Advance Planning Study &
STRAIN Report.**

Alternative 2 - No Build

The no build alternative does not meet the purpose and need for the project. By not performing the retrofit, the structural integrity of the bridges would not be improved.

6B. Design Exceptions:

Since all work at this location is being completed to the substructure, Heidi Sykes and Jim Deluca both agreed (discussed on 10/28/11) that addressing nonstandard geometric features is beyond the scope of this project. Therefore, a design exception fact sheet was not prepared to address the non-standard shoulder width at the Middle Fork Smith River Bridge.

6C. Environmental Compliance:

A Preliminary Environmental Assessment Report (PEAR) has been prepared for this project. The PEAR indicates that an Initial Study with a Mitigated Negative Declaration for CEQA and a Categorical Exclusion for NEPA will be needed, which will take 24–30 months to complete.

The following biological permits are anticipated:

- Clean Water Act 404 Permit
- Clean Water Act 401 Permit
- 1600 Streambed Alteration Agreement

In addition to the permits above, a Coastal Development Permit will be required as four of the five bridges are located within the Coastal Zone. The Middle Fork Smith River Bridge is not located within the Coastal Zone.

Mitigation will be required for impacts to wetlands, riparian vegetation, water quality, fisheries, and other habitat. The Right of Way Data Sheet and cost estimates include the purchase of 12 acres for the purpose of riparian mitigation (3 acres of disturbed riparian at a mitigation ratio of 4:1).

See Attachment I for the Preliminary Environmental Assessment Report.

6D. Sea Level Rise

State guidance on Sea level rise is still in development. However, according to Pacific Institute mapping, the bridges in this project are not located where sea level rise will occur.

6E. Hazardous Waste

The Initial Site Assessment recommends a consultant perform surveys of the bridge sites for issues related to asbestos and lead paint in bridge components, and Aerially Deposited Lead (ADL) in soil that will be disturbed during work.

An Air Quality National Emission Standards for Hazardous Air Pollutants (NESHAP) permit will be required for each bridge.

Note that Rowdy Creek will require blast cleaning.

The complete ISA is located in Attachment E.

6F. Hazardous waste disposal site required? If yes, where are sites?

Surveys of hazardous waste discussed in Section 6E will be initiated when the project has entered the 0 Phase to determine if a hazardous waste disposal site will be necessary.

6G. Other Agencies Involved (Permits/Approvals)

County of Del Norte: An encroachment permit will be required for the southeast portion of the overcrossing on Railroad Avenue.

6H. Materials and or disposal site needs and availability?

No significant amount of soil will need to be disposed of off-site and excavated soil will become property of the contractor.

6I. Highway planting and irrigation:

Highway planting is warranted for this project.

See Attachment H for a copy of the Landscape Architecture Assessment Sheet.

6J. Storm Water Compliance:

The Storm Water Data Report form states that the project will cause minimal soil disturbance incidental to accessing the column footing, temporary access road, anchor piles and staging areas. The amount of disturbed soil is expected to be less than 1 acre. No impaired water bodies exist within the project limits.

See Attachment G for a copy of the Storm Water Data Report.

Construction site BMP's involve a contractor prepared and implemented Water Pollution Control Plan (WPCP) that will include temporary construction BMP's as a means of controlling storm water runoff during construction.

6K. Right of way Issues:

See Attachment C for a copy of the Right of Way Data Sheet.

6L. Railroad Involvement:

None. No railroads exist within the project area.

6M. Utility Involvement:

No utility relocation or removal is anticipated; however utility verifications will be required.

6N. Prolonged temporary ramp closures:

The project does not involve ramp closures.

6O. Local and Regional Input:

Due to the scope of the project being limited to seismic retrofits only, local and regional input was not solicited.

6P. What are the consequences of not doing this entire project?

By not completing the project, the bridges will not be seismically retrofitted and the structural integrity of the bridges would not be improved as identified by the Structures Maintenance & Investigations (SM&I) list of outstanding work.

6Q. Concurrent Projects:

Dr Fine Bridge, located approximately 0.4 miles from the Smith River Overflow bridge, is programmed for replacement (EA #01-43640) and is scheduled to be complete in 2020.

Patrick Creek Bridge, located approximately 3 miles from the Middle Fork Smith River Bridge, is programmed for realignment and widening/replacement (EA#01-47940) and is scheduled to be complete in 2018.

Widening of the Patrick Creek Narrows (PM 22.7/23.0), approximately 5 miles from the Middle Fork Smith River Bridge, is programmed (EA# 01-45000) and is scheduled to be complete in 2015.

Middle Fork Wall (PM 24.6), approximately 7 miles from the Middle Fork Smith River Bridge, is scheduled to be constructed and completed by 2017 (EA# 01-0B320).

7. TRANSPORTATION MANAGEMENT

7A. Transportation Management Plan:

The Transportation Management Plan (TMP) provided on October 28, 2011 states that no significant traffic impacts are anticipated provided the recommendations within the TMP are incorporated.

All Bridges

- One closure, on each route, is permitted within the project limits.
- The W11-1 vehicular traffic sign (bicycle symbol) and the W16-1 supplemental plaque (SHARE THE ROAD) shall be placed, in each direction of travel, prior to the construction zone.
- A minimum of one PCMS in advance of both ends of the construction site shall be required to notify the public of the closures related to this project. One of the displayed messages shall read, “WATCH FOR BIKES”

See Attachment F for a copy of the TMP and details for each bridge.

7B. Vehicle Detection Systems

No vehicle detection system will be incorporated.

8. ENVIRONMENTAL DETERMINATION/DOCUMENT

A Preliminary Environmental Assessment Report was prepared for this project.

The expected environmental document is an Initial Study with a Mitigated Negative Declaration for CEQA and a Categorical Exclusion for NEPA.

Expected permits include Clean Water Act 404 Permit, Clean Water Act 401 Permit, 1600 Streambed Alteration Agreement, and a Coastal Development Permit.

See Attachment I for the Preliminary Environmental Assessment Report.

9. FUNDING/SCHEDULING

9A. Cost Estimate:

The preferred alternative is Alternative 1 at a cost of \$14,044,000 million (in the 2012 SHOPP 201.113 program). This includes \$10,017,000 (2011) for construction costs and \$3,318,000 (2011) for Right of Way costs. This estimate includes \$1,371,000 for Railroad Avenue OC, \$972,000 for Smith River Overflow, \$1,480,000 for Rowdy Creek, \$1,513,000 for the SR 199/SR 101 Connector Overcrossing and \$8,601,000 for Middle Fork Smith River. Costs associated with environmental, right of way, landscape architecture, and storm water pollution prevention were distributed equally among the bridges for this PSSR cost estimate. Further evaluation will be needed in the next stage of the project to determine appropriate distribution of costs to each bridge.

See Attachment J for the complete cost estimate.

9B. Project Support:

See Attachment L: Programming Sheet

9C. Project Schedule:

Milestones	Delivery Date (Month, Day, Year)
Begin Environmental	6/1/2012
Begin Project Report	5/1/2012
Circulate ED	10/1/2013
PA & ED	7/1/2014
Bridge Site Data to Structures	1/1/2013
Right of Way Maps	2/1/2014
Draft PS&E	8/1/2015
Project PS&E	12/1/2015
Right of way Certification	3/1/2016
Ready to List	3/15/2016
HQ Advertise	7/15/2016
Approve Contract	12/15/2016
Contract Acceptance	8/1/2018

10. FEDERAL COORDINATION

No FHWA action required for this project.

11. SCOPING TEAM FIELD REVIEW ATTENDANCE ROSTER:

A field review was completed on September 7, 2011 by Jeffrey Pimentel and Katie Beach.

12. REVIEWS

Project Reviewed by:

District Maintenance	<u>Royal McCarthy</u>	Date <u>11/18/11</u>
District Safety	<u>Steve Hughes</u>	Date <u>11/18/11</u>
HQ Division of Design	<u>Heidi Sykes & Jim Deluca</u>	Date <u>11/18/11</u>
HQ Program Advisor	<u>Michael Johnson</u>	Date <u>11/18/11</u>
District Advanced Planning	<u>Ilene Poindexter</u>	Date <u>11/17/11</u>


13. LIST OF ATTACHMENTS

A.	Project Map
B.	Layouts
C.	R/W Data Sheet
D.	Structures Advance Planning Study
E.	Initial Site Assessment (ISA)
F.	Transportation Management Plan (TMP)
G.	Storm Water Data Report
H.	Landscape Architecture Assessment Form
I.	Environmental Document (PEAR)
J.	Cost Estimate
K.	Programming Sheet

ATTACHMENT A
Project Map

Del Norte Seismic Retrofit Location Map


OREGON



EA 01-0A 100K
EFIS #: 0112000023
DN-101 & 199-Various

ATTACHMENT B
Layouts

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans
 FUNCTIONAL SUPERVISOR
 CALCULATED BY
 DESIGNED BY
 CHECKED BY
 REVISED BY
 DATE REVISED



Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET TOTAL SHEETS
1	DN	101	R28.32	1 1

REGISTERED CIVIL ENGINEER DATE _____
 PLANS APPROVAL DATE _____
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



Railroad Avenue Overcrossing
01-DN-101-R28.32
 01-0063

DESIGN STUDY ONLY

LEGEND

- Existing R/W and APN Lines
- Environmental Study Limits
- Proposed TCE: County Road

Scale
 1" = 100'

BORDER LAST REVISED 4/11/2008

RELATIVE BORDER SCALE IS IN INCHES

USERNAME => BUSER
 DGN FILE => BREQEST

CU 00000

EA 000000

LAST REVISION DATE PLOTTED => \$DATE
 00-00-00 TIME PLOTTED => \$TIME

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans
 FUNCTIONAL SUPERVISOR
 CALCULATED, DESIGNED BY
 CHECKED BY
 REVISED BY
 DATE REVISED

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
1	DN	101	35.77	1	1

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

REGISTERED PROFESSIONAL ENGINEER
 No. _____
 Exp. _____
 CIVIL
 STATE OF CALIFORNIA

**Smith River
 Overflow Bridge
 01-DN-101-35.77**

01-0046



LEGEND

- Existing R/W and APN Lines
- Environmental Study Limits

Scale
 1:50

BORDER LAST REVISED 4/11/2008

RELATIVE BORDER SCALE IS IN INCHES



USERNAME => #USER
 DGN FILE => #REQUEST

CU 00000

EA 000000

LAST REVISION DATE PLOTTED => DATE
 00-00-00 TIME PLOTTED => TIME

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans
 FUNCTIONAL SUPERVISOR
 CALCULATED BY
 DESIGNED BY
 CHECKED BY
 REVISED BY
 DATE REVISED



Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
1	DN	101	39.63	1	1

REGISTERED CIVIL ENGINEER DATE _____
 PLANS APPROVAL DATE _____

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.




Rowdy Creek Bridge
01-DN-101-39.63
 01-0023

DESIGN STUDY ONLY
 Scale 1:100

LEGEND

- Existing R/W and APN Lines
- Environmental Study Limits

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans
 FUNCTIONAL SUPERVISOR
 CALCULATED BY
 DESIGNED BY
 CHECKED BY
 REVISED BY
 DATE REVISED



DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
1	DN	199/101	TO.51	1	1

REGISTERED CIVIL ENGINEER DATE _____

PLANS APPROVAL DATE _____

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

REGISTERED PROFESSIONAL ENGINEER
 NO. _____
 EXP. _____
 CIVIL
 STATE OF CALIFORNIA

**US 199/US 101
 Connector Overcrossing
 01-DN-199-T0.51
 01-0058F**

DESIGN STUDY ONLY



LEGEND

- Existing R/W and APN Lines
- Environmental Study Limits

Scale
 1:100

BORDER LAST REVISED 4/11/2008

RELATIVE BORDER SCALE IS IN INCHES

USERNAME => USER
 DGN FILE => BREQUEST

CU 00000

EA 000000

LAST REVISION DATE PLOTTED => DATE
 00-00-00 TIME PLOTTED => TIME

ATTACHMENT C
R/W Data Sheet

Memorandum

*Flex your power!
Be energy efficient!*

To: MS. ILENE POINDEXTER
D1 Advanced Planning Senior
Department of Transportation, District 1

Date: November 30, 2011

File: 01-DN-C0999
E.A. 0A100K
Alternate No. 1 of 1 - Bridge
Seismic Retrofit

Attention KATIE BEACH
Project Engineer

From: KAREN E. HAWKINS,
Assistant Chief
North Region Right of Way
Eureka/Redding

Seismic Retrofit of Five
Bridges in Del Norte
County on Routes 101 &
199

Subject: Current Estimated Right of Way Costs

We have completed an estimate of the right of way costs for the above referenced project based on information received from you on October 19, 2011. The attached estimate is based on the following assumptions and limiting conditions:

Acquisition: No work will be performed outside the State's right of way.

Permits: Four permits will be required. These include a 1602, CDP, 404 and 401.

Mitigation: Up to 12 acres of off-site mitigation will be required for impacts to riparian areas.

Right of Way Lead Time will require a minimum of 20 months after we receive project first appraisal maps, utility conflict maps, and the necessary environmental clearance and freeway agreements have been approved and obtained. Additionally a minimum of 3 months will be required after receiving the last appraisal map to Right of Way for certification. Shorter lead times will require either more right of way resources or an increased number of condemnation suits to be filed. Either of these actions may reflect adversely on the District's other programs or our public image generally.


KAREN E. HAWKINS,
Assistant Chief
North Region Right of Way
Eureka/Redding

Attachments:
Right of Way Data Sheet

cc: KEVIN CHURCH



Date: November 16, 2011

01-DN-101 & 199-C0999
 E.A. 0A100K
 BH Bridge - Rehabilitation bridge seismic retrofit

1. Right of Way Cost Estimate: Alternate No. 1-1 - Bridge Seismic Retrofit

	Current Value Future Use	Escalation Rate	Escalated Value
A. Total Acquisition Cost	\$0		\$0
B. Mitigation acquisition & credits	\$3,240,000	5%	\$3,994,973
C. Project Development Permit Fees	\$78,000	5%	\$96,175
Subtotal	\$3,318,000		\$4,091,148
D. Utility Relocation (State Share) (Owner's share: _____ \$0)	\$0		\$0
E. Relocation Assistance (RAP)	\$0		\$0
F. Clearance/Demolition	\$0		\$0
H. Title & Escrow	\$0		\$0
I. Total Estimated Right of Way Cost	\$3,318,000		Rounded \$4,091,000
J. Construction Contract Work	March 1, 2016		

2. Current Date of Right of Way Certification

3. Parcel Data:

Type	Dual/Adpor	Utilities U4 - 1	RR Involvements
X	0	0	None X
A	0	-2	C&M Agrmt
B	1	-3	Svc Contract
C	0	-4	Easements
D	0	U5 - 7	Rights of Entry
		-8	Clauses
Total	1	-9	

Misc. RW Work

Areas:		
R/W:	N/A	N/A
Excess:	N/A	N/A
Mitigation:	N/A	No
No. Excess Pcls:	0	

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
RIGHT OF WAY DATA SHEET

4. Are there any major items of construction contract work?
Yes _____ No X
5. Provide a general description of the right of way and excess lands required (zoning, use, major improvements, critical or sensitive parcels, etc.).
No right of way required.
6. Are any properties acquired for this project expected to be rented, leased, or sold?
Yes _____ No X
7. Is there an effect on assessed valuation? Yes _____ Not Significant _____
No X
8. Are utility facilities or rights of way affected? Yes X No _____
Utility relocations are not anticipated; however, utility verifications will be required.
Name of Utility Companies Requiring Verification Only:
City of Crescent City - Water Blue Star - Gas
City of Crescent City - Electric Smith River Community Services District - Water
City of Crescent City - Sewer County of Del Norte - Public Works
Frontier Communications - Telephone
Charter Communications - CATV
Pacific Power & Light - Electric
9. Are railroad facilities or rights of way affected? Yes _____ No X
10. Were any previously unidentified sites with hazardous waste and/or material found?
Yes _____ None Evident X
11. Are RAP displacements required? Yes _____ No X
No. of single family _____ No. of business/nonprofit _____
No. of multi-family _____ No. of farms _____
Based on Draft/Final Relocation Impact Statement/Study dated N/A
it is anticipated that sufficient replacement housing (will/will not) be available without
Last Resort Housing.
12. Are there material borrow and/or disposal sites required?
Yes _____ No X
13. Are there potential relinquishments and/or abandonments?
Yes _____ No X
14. Are there any existing and/or potential airspace sites?
Yes _____ No X
15. What type of mitigation is required for the project?
12 acres of riparian mitigation will be required.
16. Indicate the anticipated Right of Way schedule and lead time requirements. (Discuss if district proposes less than PMCS lead time and/or if significant pressures for project advancement are anticipated.)

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
RIGHT OF WAY DATA SHEET

Right of Way Lead Time will require a minimum of 20 months after we receive first appraisal maps, utility conflict maps, and the necessary environmental clearance and freeway agreements have been approved and obtained. Additionally a minimum of 3 months will be required after receiving the last appraisal map to Right of way for certification.

17. Is it anticipated that Caltrans will perform all Right of Way work?
Yes X No

Evaluation Prepared By:

Right of Way:


JEREMIAH JOYNER

Date 12-1-11

Reviewed By:

RW Project Coordinator:


ROBERT CLOSE

Date 12-1-11

I have personally reviewed this Right of Way Data Sheet and all supporting information. I certify that the probable Highest and Best Use, estimated values, escalation rates, and assumptions are reasonable and proper, subject to the limiting conditions set forth, and I find this Data Sheet to be complete and current.

RECOMMENDED FOR APPROVAL

APPROVED:


DAVE McCANNELS,
Senior Right of Way Agent
Project Delivery Branch
EUREKA


KAREN E. HAWKINS,
Assistant Chief
North Region Right of Way
Eureka/Redding

Date 12/2/11

Date 12/2/11

ATTACHMENT D
Structure Replacement And Improvement Needs Report (STRAIN)
&
Structures Advance Planning Study

STRUCTURE REPLACEMENT AND IMPROVEMENT NEEDS REPORT

District : 01

Bridge Number : 01 0023 Total Length: 63.4 Permit Rating: P P P P P Suff Rating : 95.40
 Feat Intersected: ROWDY CREEK Total Width : 13.3 Rail Rating : 1100 Approach Width: 12.2
 Structure Name : ROWDY CREEK Location : 01-DN-101-39.63

Item	Recom. Date	Project Type	Urgency Factor	Cost	Status	Tech. rank
1	07/01/2001	70 - Seismic-Retrofit	2 years	\$420,500	1-Initiated	0.17

Project Details :

1 Tall steel girder may require x-bracing. Priority 4. Final Score 0.165.

Bridge Number : 01 0025 Total Length: 41.8 Permit Rating: P P P P P Suff Rating : 70.00
 Feat Intersected: PANTHER CREEK Total Width : 9.9 Rail Rating : 0000 Approach Width: 12.2
 Structure Name : PANTHER CREEK Location : 01-DN-101-8.34

Item	Recom. Date	Project Type	Urgency Factor	Cost	Status	Tech. rank
1	02/10/1984	62 - Railing-Upgrade	2 years	\$177,120	2-Programmed	1.29
2	09/06/2011	70 - Seismic-Retrofit	4 years	\$207,500	0-Proposed	

Project Details :

1 F1-03 / F2-0 / F3-5 / Rail Type-MBGR. Replace the bridge rail.
 2 High skew, liquefiable soil, Raymond Step Tapered Piles. Final score 1.4

Bridge Number : 01 0028 Total Length: 621.2 Permit Rating: P P P P P Suff Rating : 50.00
 Feat Intersected: KLAMATH RIVER Total Width : 10.4 Rail Rating : 0110 Approach Width: 12.2
 Structure Name : KLAMATH RIVER Location : 01-DN-101-R4.04

Item	Recom. Date	Project Type	Urgency Factor	Cost	Status	Tech. rank
1	07/10/2001	11 - Super-Rehab	6 years	\$3,750,000	2-Programmed	44.27

Project Details :

1 Remove and reconstruct the hinge in Span 8. The concrete of the seat and diaphragm at this location has been cracking and failing for the past 20 years leaving the rebar in the hinge and the pipe seat extenders to support the span. The hinge in Spans 2 and 11 is in the early stages of deterioration and failure. Both of these should be removed and reconstructed.

SMS15010

STRUCTURE REPLACEMENT AND IMPROVEMENT NEEDS REPORT

DEC, 2011

Page 3 of 46

District : 01

Bridge Number : 01 0044 Total Length: 170.7 Permit Rating: PPPGG Suff Rating : 67.00
 Feat Intersected: MIDDLE FORK SMITH RIVER Total Width : 18.9 Rail Rating : 0011 Approach Width: 18.3
 Structure Name : MIDDLE FORK SMITH RIVER Location : 01-DN-199-R17.06

Item	Recom. Date	Project Type	Urgency Factor	Cost	Status	Tech. rank
1	07/01/2002	70 - Seismic-Retrofit	2 years	\$1,560,500	1-Initiated	0.22

Project Details :

1 Large gap behind abutments. Priority 4. Final Score 0.22.

Bridge Number : 01 0046 Total Length: 86.3 Permit Rating: P P P P P Suff Rating : 89.60
 Feat Intersected: SMITH RIVER OVERFLOW Total Width : 15.2 Rail Rating : 1111 Approach Width: 15.5
 Structure Name : SMITH RIVER OVERFLOW Location : 01-DN-101-35.77

Item	Recom. Date	Project Type	Urgency Factor	Cost	Status	Tech. rank
1	01/16/2007	70 - Seismic-Retrofit	2 years	\$653,500	1-Initiated	10.07

Project Details :

1 Slab bridge with in-span hinge. Short seat hinge, thin pier wall supporting shallow superstructure. Priority 2 & 4. Final Score 10.065.

I revised the cost to \$653,500. Previous cost was \$427,000 which did not provide the proper estimate of \$500/sq meter of deck area. tf

Bridge Number : 01 0058F Total Length: 111.6 Permit Rating: P P P P P Suff Rating : 98.20
 Feat Intersected: U.S. 101 (@ PM R30.81) Total Width : 12.8 Rail Rating : 0011 Approach Width: 11.9
 Structure Name : S199-S101 CONNECTOR OC Location : 01-DN-199-T.51

Item	Recom. Date	Project Type	Urgency Factor	Cost	Status	Tech. rank
1	07/01/2002	70 - Seismic-Retrofit	2 years	\$692,000	1-Initiated	0.40

Project Details :

1 Columns flare steel into superstructure, non-ductile columns. Priority 4. Final Score 0.396.

STRUCTURE REPLACEMENT AND IMPROVEMENT NEEDS REPORT

District : 01

Bridge Number : 01 0063 Total Length: 115.8 Permit Rating: P P P P P Suff Rating : 99.70
 Feat Intersected: U.S. HIGHWAY 101 Total Width : 12.7 Rail Rating : 0111 Approach Width: 12.2
 Structure Name : RAILROAD AVENUE OC Location : 01-DN-101-R28.32

Item	Recom. Date	Project Type	Urgency Factor	Cost	Status	Tech. rank
1	07/01/2000	70 - Seismic-Retrofit	2 years	\$736,000	1-Initiated	0.40

Project Details :

1 Columns flare steel into superstructure, non-ductile columns. Priority 4. Final Score 0.396.

Bridge Number : 04 0007 Total Length: 48.8 Permit Rating: P P P P P Suff Rating : 77.30
 Feat Intersected: OHMAN CREEK Total Width : 9.4 Rail Rating : 0010 Approach Width: 7.3
 Structure Name : OHMAN CREEK Location : 01-HUM-254-.88

Item	Recom. Date	Project Type	Urgency Factor	Cost	Status	Tech. rank
1	02/10/1984	62 - Railing-Upgrade	2 years	\$200,080	2-Programmed	9.79

Project Details :

1 F1-10 / F2-0 / F3-2 / Rail Type-WOOD

Bridge Number : 04 0008 Total Length: 36.6 Permit Rating: P P P G G Suff Rating : 74.60
 Feat Intersected: ELK CREEK Total Width : 9.3 Rail Rating : 0000 Approach Width: 7.3
 Structure Name : ELK CREEK Location : 01-HUM-254-10.43

Item	Recom. Date	Project Type	Urgency Factor	Cost	Status	Tech. rank
1	02/10/1984	62 - Railing-Upgrade	2 years	\$159,080	2-Programmed	0.81

Project Details :

1 F1-03 / F2-0 / F3-5 / Rail Type-C.WIN

Bridge Number : 04 0009 Total Length: 48.8 Permit Rating: P P P P P Suff Rating : 75.00
 Feat Intersected: BRIDGE CREEK Total Width : 9.6 Rail Rating : 0011 Approach Width: 7.3
 Structure Name : BRIDGE CREEK Location : 01-HUM-254-10.8 FUNCTIONALLY OBSOLETE

Item	Recom. Date	Project Type	Urgency Factor	Cost	Status	Tech. rank
1	02/10/1984	62 - Railing-Upgrade	2 years	\$200,080	2-Programmed	8.14

Project Details :

1 F1-10 / F2-0 / F3-1 / Rail Type-WOOD

M e m o r a n d u m

To: ILENE POINDEXTER, Chief
Advance Planning Branch
District 01

Date: September 9, 2011

File: 01-DN-101/199
Various

Attn: Jeffrey Pimentel

EA 01-0A100K

From: GUDMUND SETBERG, Chief
Bridge Design Branch 2
Office of Structure Design North
Division of Engineering Services, MS 9-4/81



Subject: PID Level Planning Study

This memo has been prepared in response to the request for planning study information sent to Moe Amine during the month of August 2011. This memo and the attached drawings/details summarize the findings of our review of the structures included in project EA 01-0A100K.

Due to the limited time allowed for these studies, the Office of Structure Design (OSD) was not able to perform in-depth review of the As-Built, determine soil and seismic properties, or perform the seismic analysis needed to provide optimal retrofit strategies. To date OSD efforts include brief reviews of: As-Built records, Structure Maintenance Bridge Records, draft seismic design spectrums and draft foundation information. Based on our findings, the following work is recommended:

Smith River Overflow (01-0046):

- Place seat extenders at the hinge in span 5. The seat extender retrofit will most likely consist of 4 relatively shallow steel members bolted through the deck to the short span side (north side) of the hinge. Drilling and bolting through the deck will require intermittent traffic control. It is estimated that 3 days of traffic control will be needed in each direction for a total of 6 days.
- Cost estimate for hinge Retrofit: \$105,000

Rowdy Creek Bridge (01-0023):

- Remove existing cross-frames and place new cross-frames at support locations (Total four locations). This work requires access to the top of Pier 2 and may require a scaffold to be built at the top of the pier for work access. Additionally, rivets and stiffeners will need to be removed using a cutting torch and small areas of the existing will need to be blast cleaned and painted. Traffic control is expected to be very minor.

- Cost estimate for cross-frame strengthening: \$490,000

Railroad Ave OC (01-0063) and S199-S101 Connector (01-0058F):

- Remove column flares and cut column flare reinforcement. Excavate around each column down to the top of the footing. Install full length column casings around each column and grout. The new column casings shall match the existing column flare with a 4” gap under the bridge soffit.
- Install 4 ft diameter anchor piles behind the abutments (total 2 for each abutment). The pile heads will be tied to the end diaphragm through steel pipes and high strength rods. One lane traffic control is required and is expected to last 2 – 3 months.
- Cost estimate for both bridges: \$780,000

Middle Fork Smith River (01-0044):

- Review of this bridge indicates that it may perform fairly well in a seismic event and may not need any retrofit work. However, this difficult to determine without more refined analysis. The Office of Structure Design (OSD) recommends that additional analysis be performed to determine if this bridge can be removed from the seismic retrofit list. The timeframe for this type of analysis is 4 months from the time a request to proceed with the analysis is received from the District. In the interim the following work is recommended: Install 4 ft diameter anchor piles behind the abutments (total 2 for each abutment). The pile heads will be tied to the end diaphragm through steel pipes and high strength rods. One lane traffic control is required and is expected to last approximately 2 months.
- Cost estimate for Anchor Pile Retrofit: \$400,000

The cost estimates shown above include 10% for TR0, 10% for mobilization and 40% for contingencies, but do not include traffic control or any District items. The project scope and cost estimates are built on a number of assumptions and should be considered preliminary.

If you have any questions or if you need additional information regarding these studies, please contact Gudmund Setberg at (916) 227-8282.

Attachment


c: TOstrom – Office of Bridge Design North
MAmini – Technical Liaison Engineer
ETadese – Project Coordination Engineer
TFujioka – Office of Structure Maintenance and Investigation
JBabcock – Office of Structure Construction

Anchor Pile Details for Railroad Ave, 199/100 OC, & Middle Fork Smith River


DIST.	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
09	Los, Mer	6,14, 395	Var	23	39

J. Selleg
 REGISTERED ENGINEER - CIVIL
 6-17-96
 PLANS APPROVAL DATE

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.



GIRDER LAYOUT



DETAIL D

- Notes:
1. For Section A-A, see "Abutment Details No. 1" sheet
 2. For Section D-D, see "Abutment Details No. 2" sheet.
 3. For Detail B see "Bent 1 Details" sheet.
 4. For Detail C see "Bent 2 Details" sheet.

GENERAL NOTES
LOAD FACTOR DESIGN

DESIGN: BRIDGE DESIGN SPECIFICATIONS (1983 AASHTO with Interims and Revisions by CALTRANS)

SEISMIC LOADING: Peak Rock Acceleration = 0.7 g
Depth of Alluvium = >150 ft.

REINFORCED CONCRETE: Existing (Assumed for Retrofit)
 $f'_c = 44,000 \text{ psi}$
 $f'_c = 5,000 \text{ psi}$
New Construction
 $f_y = 60,000 \text{ psi}$
 $f'_c = 3,250 \text{ psi}$

STRUCTURAL STEEL: ASTM A361
 $f_y = 36,000 \text{ psi}$

NOTE:
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

EARTHQUAKE RETROFIT PROJECT NO. SR 397
LOS ANGELES AQUEDUCT
ABUTMENT LAYOUT

DESIGN	J. Gushard Selleg, J.S.	CHECKED	R. J. Moran	DATE	1-95
DRAWN	M. J. S.	CHECKED	R. J. Moran	DATE	7-96
QUANTITIES	M. K. Kambouze	CHECKED	R. J. Moran	DATE	1-96


STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

DIVISION OF STRUCTURES
STRUCTURE DESIGN 5

BRIDGE NO.
49-14
POST MILES
65.6

CU 09
EA 272101

DATE	2	1
REVISIONS		



- Remove column flare and cut flare reinforcement
- Install full length column casing. Column casing shall be flared to match existing column with 4" gap under the soffit of the bridge
- Install anchor piles (see attached detail) pile $\phi = 4'$


DESIGN SECTION 5 Design Engineer: <i>[Signature]</i> Checker: <i>[Signature]</i>		TRANSPORTATION AGENCY RAILROAD AVENUE OVERCROSSING LOCATED APPROX. 2 MILES N. OF THE N. CITY LIMIT OF ESCROW CITY IN DEL NORTE COUNTY	
GENERAL PLAN SHEET NO. 28.3 DATE: 01-63		PROJECT NO. 01-0576-04 SHEET NO. 28.3 DATE: 01-63	

Roady Creek Bridge 01-0023

Sheet 1/2

P1D Level 1 APS Quantities

No calculations were performed, but it is anticipated that X-bracing at supports needs to be beefed up. that is 4 rows of braces x 3 braces each




Total 20 - 3/8 HS bolts per brace

Total of 240 bolts

spot blast, clean and paint exist structure


= 10 SF per location x 32 locations = 320 SF



PILE DATA

LOCATION	DESIGN LOADING (SERVICE LOAD)	SPECIFIED TIP ELEVATION
ABUT. 1	100 TONS	14
ABUT. 3	100 TONS	14

ELEVATION
1"=20"



PLAN
1"=20'

APPROXIMATE QUANTITIES

BRIDGE REMOVAL (PORTION)	LONG SQM
RECONSTRUCT STRUCTURAL STEEL GIRDERS	151 SF
16" CAST-IN-DRILLED-HOLE CONCRETE PILING	81 LF
DRILL AND SOHD DONEL	24 LF
WATERSTOP	24 LF
JOINT SEAL (MR 1/2")	24 LF


FINAL PAY QUANTITIES

STRUCTURE EXCAVATION (TYPE D)	CU
STRUCTURE BACKFILL (BRIDGE)	56
STRUCTURAL CONCRETE, (BRIDGE)	36
BAR REINFORCING STEEL, (BRIDGE)	247
MISCELLANEOUS METAL, (BRIDGE)	16,900
CONCRETE BARRIERS (TYPE 25)	1,200

NOTE:
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

For Construction Sequence see "Girder Details" sheet.
For General Notes see "Typical Section" sheet.

Remove existing cross-frames and place new cross-frames and stiffeners at support locations at roadway. See attached detail.



TYPICAL SECTION
1"=5'


AS BUILT
CORRECTIONS B
CONTRACT NO. 01-197144
DATE 2-26-81

AS BUILT
CORRECTIONS B
CONTRACT NO. 01-197144
DATE 2-26-81

INDEX TO PLANS

SHEET NO.	TITLE
I	GENERAL PLAN
II	FOUNDATION PLAN
III	ABUTMENT
IV	ABUTMENT JOINT DETAILS
V	TYPICAL SECTION
VI	BEARING DETAILS
VII	LOG OF TEST BORINGS
VIII	LOG OF TEST BORINGS (AS BUILT)
IX	STANDARD PLANS DATED JANUARY 1988
A82-C	EXCAVATION AND BACKFILL - BRIDGE
DD-1	BRIDGE DETAILS
DD-2	BRIDGE DETAILS
DD-3	BRIDGE DETAILS
DD-4	BRIDGE DETAILS
DD-5	BRIDGE DETAILS
DD-6	BRIDGE DETAILS
DD-7	BRIDGE DETAILS
DD-8	BRIDGE DETAILS
DD-9	BRIDGE DETAILS
DD-10	BRIDGE DETAILS
DD-11	BRIDGE DETAILS
DD-12	BRIDGE DETAILS
DD-13	BRIDGE DETAILS
DD-14	BRIDGE DETAILS
DD-15	BRIDGE DETAILS
DD-16	BRIDGE DETAILS
DD-17	BRIDGE DETAILS
DD-18	BRIDGE DETAILS
DD-19	BRIDGE DETAILS
DD-20	BRIDGE DETAILS
DD-21	BRIDGE DETAILS
DD-22	BRIDGE DETAILS
DD-23	BRIDGE DETAILS
DD-24	BRIDGE DETAILS
DD-25	BRIDGE DETAILS
DD-26	BRIDGE DETAILS
DD-27	BRIDGE DETAILS
DD-28	BRIDGE DETAILS
DD-29	BRIDGE DETAILS
DD-30	BRIDGE DETAILS
DD-31	BRIDGE DETAILS
DD-32	BRIDGE DETAILS
DD-33	BRIDGE DETAILS
DD-34	BRIDGE DETAILS
DD-35	BRIDGE DETAILS
DD-36	BRIDGE DETAILS
DD-37	BRIDGE DETAILS
DD-38	BRIDGE DETAILS
DD-39	BRIDGE DETAILS
DD-40	BRIDGE DETAILS
DD-41	BRIDGE DETAILS
DD-42	BRIDGE DETAILS
DD-43	BRIDGE DETAILS
DD-44	BRIDGE DETAILS
DD-45	BRIDGE DETAILS
DD-46	BRIDGE DETAILS
DD-47	BRIDGE DETAILS
DD-48	BRIDGE DETAILS
DD-49	BRIDGE DETAILS
DD-50	BRIDGE DETAILS
DD-51	BRIDGE DETAILS
DD-52	BRIDGE DETAILS
DD-53	BRIDGE DETAILS
DD-54	BRIDGE DETAILS
DD-55	BRIDGE DETAILS
DD-56	BRIDGE DETAILS
DD-57	BRIDGE DETAILS
DD-58	BRIDGE DETAILS
DD-59	BRIDGE DETAILS
DD-60	BRIDGE DETAILS
DD-61	BRIDGE DETAILS
DD-62	BRIDGE DETAILS
DD-63	BRIDGE DETAILS
DD-64	BRIDGE DETAILS
DD-65	BRIDGE DETAILS
DD-66	BRIDGE DETAILS
DD-67	BRIDGE DETAILS
DD-68	BRIDGE DETAILS
DD-69	BRIDGE DETAILS
DD-70	BRIDGE DETAILS
DD-71	BRIDGE DETAILS
DD-72	BRIDGE DETAILS
DD-73	BRIDGE DETAILS
DD-74	BRIDGE DETAILS
DD-75	BRIDGE DETAILS
DD-76	BRIDGE DETAILS
DD-77	BRIDGE DETAILS
DD-78	BRIDGE DETAILS
DD-79	BRIDGE DETAILS
DD-80	BRIDGE DETAILS
DD-81	BRIDGE DETAILS
DD-82	BRIDGE DETAILS
DD-83	BRIDGE DETAILS
DD-84	BRIDGE DETAILS
DD-85	BRIDGE DETAILS
DD-86	BRIDGE DETAILS
DD-87	BRIDGE DETAILS
DD-88	BRIDGE DETAILS
DD-89	BRIDGE DETAILS
DD-90	BRIDGE DETAILS
DD-91	BRIDGE DETAILS
DD-92	BRIDGE DETAILS
DD-93	BRIDGE DETAILS
DD-94	BRIDGE DETAILS
DD-95	BRIDGE DETAILS
DD-96	BRIDGE DETAILS
DD-97	BRIDGE DETAILS
DD-98	BRIDGE DETAILS
DD-99	BRIDGE DETAILS
DD-100	BRIDGE DETAILS

DESIGN	M. Ketal 5/89	D. Valle 7/89	DESIGN FACTOR	LIVE LOADS: HS20-44 AND ALTERNATIVE AND POINT DESIGN LOAD	STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	DIVISION OF STRUCTURES STRUCTURE DESIGN 5	BRIDGE NO. 1-23	ROWDY CREEK BRIDGE (WIDEN)
DETAILS	B.H. Svaboda 5-89	D. Valle 7/89	LAYOUT	M. Ketal 5/89	DESIGNED BY: D. Valle 7/89	POST MILE 39.63	GENERAL PLAN	
DESIGN ENGINEER	B.H. Svaboda	12-89	SPECIFICATIONS	2-89	APPROVED BY: [Signature]	CU 01 EA 197141	STANDARD PRINTS BEARING EARLIER REVISION DATES	
QUANTITIES	B.H. Svaboda	12-89					SHEET 1 OF 9	



- Remove column flare and cut flare reinforcement.
- Install full length column casing. Column casing shall be flared to match existing column with 4" gap under the soffit.
- Install anchor piles (see attached detail) pile $\phi = 4'$

QUANTITY CALCULATIONS

DC-CRM 4801 (OLD HCS) REV 11/92 T&E 35300

SHEET _____ OF _____

JOB STAMP

01-0A 100K
Smith River overflow
01-0046

ITEN Hinge seat extension
UN Detail


DESIGN BY G. SETBERG
CHK BY

FILE NO
SEQUENTIATION

YES
NO

DATE 9/5/11
DATE

1 1/4" Ø bolts thru 1.75"
core hole. Total 4 each
assembly (see note)



Note: Chip deck to provide room for nuts and washers
Provide 1/4" x 4" washer, nut and lock nut
at the bottom. Weld 1/2" x 4" x 4" plate to
top of bolt.

DESIGNED BY

DATE


APPROVED BY

NO AS BUILT CORRECTIONS
 CONTRACT NO. 01-0314
 TRANSFER DATE: 8-14-2008
 FIELD CORRECTION DATE: 05-25-2007
 CORRECTING TRANSFORMED BY: EM C. INOYANO
 FIELD CORRECTING BY:



DIST	COUNTY	ROUTE	KILOMETER POST TOTAL PROJECT	SHEET No.	TOTAL SHEETS
01	DN	101	57.6,72.9	61	84

M. Akkari 11-18-02
 REGISTERED CIVIL ENGINEER
 2-22-05
 PLANS APPROVAL DATE
 The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.
 Caltrans now has a web site. To get to the web site, go to: <http://www.dot.ca.gov>




ELEVATION
1:250

SMITH RIVER OVERFLOW (WIDEN) BR NO 01-0046

QUANTITIES		
CLEAN BRIDGE DECK	85.3	m ²
BRIDGE REMOVAL (PORTION), LOCATION 1	272	m ²
STRUCTURE EXCAVATION (BRIDGE)	40	m ³
STRUCTURE BACKFILL (BRIDGE)	246	m ³
FURNISH STEEL PIPE PILING (640 MM)	36	EA
DRIVE STEEL PIPE PILE (610 MM)	87	m
FURNISH PILING (CLASS 400)	592	m
DRIVE PILE (CLASS 400)	60	m ³
STRUCTURAL CONCRETE, BRIDGE FOOTING	279	m ³
STRUCTURAL CONCRETE, BRIDGE	155	m ³
REFINISH BRIDGE DECK	51	100 kg
BAR REINFORCING STEEL (BRIDGE)	4	000 kg
BAR REINFORCING STEEL (EPOXY COATED) (BRIDGE)	853	m ²
TREAT BRIDGE DECK	427	L
FURNISH BRIDGE DECK TREATMENT MATERIAL (LOW ODSR)	1	450 kg
MISCELLANEOUS METAL (BRIDGE)	127	m
TUBULAR BICYCLE RAILING	187	m
CONCRETE BARRIER (TYPE 732)		

* See Road Plans




TYPICAL SECTION
1:80

NOTES:

- ① Paint "Smith River Overflow Bridge".
- ② Paint "Br. No. 01-0046".
- ③ Temporary Railing (Type K), see "Road Plans".
- ④ Match existing cross slope.
- ⑤ Remove existing Curb and Guard Railing.
- ⑥ Refinish Bridge Deck.
- ⑦ For Hydrologic Summary, see "Foundation Plan" sheet.
- ⑧ Limit of methacrylate treatment.
- ⑨ Metal Beam Guard Rail, see "Road Plans".

For General Notes and Index to Plans, see "Index to Plans" sheet.

ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE SHOWN



PLAN
1:250

NOTE:
THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

LEGEND:

- Indicates limits of Bridge Removal (Portion)
- Indicates Existing Structure

GUDMUND SETBERG DESIGN ENGINEER STRUCTURES DESIGN GENERAL PLAN SHEET (METRIC) (REV. 4/20/00)	DESIGN BY: M. Saberi	CHECKED BY: M. Friedheim	LOAD FACTOR DESIGN	LIVE LOADING: HS20-44 AND ALTERNATIVE AND PERMIT DESIGN LOAD	BRIDGE NO. 01-0046 KILOMETER POST 57.61	SMITH RIVER OVERFLOW BRIDGE (WIDEN) GENERAL PLAN
	DETAILS BY: E. Mantevirgin	CHECKED BY: M. Friedheim / N. Nguyen	LAYOUT	BY: M. Saberi		
	QUANTITIES BY: S. Kapicka	CHECKED BY: N. Nguyen	SPECIFICATIONS	BY: J. Strooban	CHECKED BY: J. Strooban	

ORIGINAL SCALE IS MILLIMETERS FOR REDUCED PLANS

CU 01 EA 293131

DATE: 11-18-02

TIME POSTED: 11:00:31
 DATE POSTED: 03-26-08


NOTE:

▨ Limit of concrete

□ Limit of steel plate

EA 01-0A100

Br. No. 01-0044




TYPICAL SECTION

Scale: 1"=10'

Middle Fork Smith River

Additional Structures Work at Middle Fork Smith River (Not included in original APS)

DIST	COUNTY	ROUTE	POST
01	DN	199	R17



PIER RETROFIT(Typ)
NO SCALE

Note

All hardware to be galvanized
steel plates to be painted or galvanized

01-0044

DESIGNED BY	DATE	2	PLANNING STUDY	
DRAWN BY	DATE 10-7-11		MIDDLE FORK SMITH RIVER	
CHECKED BY X	DATE X		BRIDGE NO. RET	UNIT: 3577
APPROVED X	DATE X		PROJECT NUMBER & PHASE: 011200023	

Additional Structures Work at Middle Fork Smith River (Not included in original APS)

Additional Structures Work at Middle Fork
Smith River (Not included in original APS)

PID ESTIMATE

Revised - August 30, 2011

RCV'D BY: RWP

IN EST: 10/12/2011
OUT EST: 10/18/2011

BRIDGE: Mid Fork Smith River Bridge

BR. No.: 01-0044

DISTRICT: 01

TYPE: CIP/PS Box girder

RTE: 199

CU: 01-0A100K

CO: DN

EA: 01-0A100K

PM: R17.06

LENGTH: _____ **WIDTH:** _____ **AREA (SF)=** _____

DESIGN SECTION: _____ **EST. NO.** 1

OF STRUCTURES IN PROJECT : 1 **COST INDEX:** 297

PRICES BY : TNC **DATE:** _____

PRICES CHECKED BY : _____ **DATE:** _____

QUANTITIES BY: Jiffey Lee **DATE:** 10/7/2011

CONTRACT ITEMS	TYPE	UNIT	QUANTITY	PRICE	AMOUNT
CORE CONCRETE, 1 1/4" D/A	LF		2,076	\$45.00	\$93,420.00
STRUCTURAL CONCRETE (Bridge)	CY		92	\$1,500.00	\$138,416.67
DRILL AND BOND DOWEL #6(Chehhah Adhesive)	LF		8,398		\$0.00
BAR REINFORCING STEEL (Bridge)	LB		55,948	\$2.10	\$117,491.22
FURNISH STRUCTURAL STEEL	LB		217,038		\$0.00
ERECT STRUCTURAL STEEL (INCL. PAINT)	LB		217,038		\$0.00
MISCELLANEOUS METAL (BRIDGE)	LB		217,038	\$12.00	\$2,604,457.80
DRILL AND BOND DOWEL (CHEMICAL ADHESIVE)	EA		6,576	\$35.00	\$230,160.00
					\$0.00
					\$0.00
SUBTOTAL					\$3,183,946
TIME RELATED OVERHEAD					\$318,395
MOBILIZATION (@ 10 %)					\$389,149
SUBTOTAL BRIDGE ITEMS					\$3,891,489
CONTINGENCIES @ 40%					\$1,556,596
BRIDGE TOTAL COST					\$5,448,085
COST PER SQ. FOOT					\$0.00
BRIDGE REMOVAL (CONTINGENCIES INCL.)					\$0
WORK BY RAILROAD OR UTILITY FORCES					\$0
GRAND TOTAL					\$5,448,085
BUDGET ESTIMATE AS OF				10/18/11	\$5,448,000

- ROUTING**
1. DES SECTION
 2. OFFICE OF BRIDGE DESIGN - NORTH
 3. OFFICE OF BRIDGE DESIGN - CENTRAL
 4. OFFICE OF BRIDGE DESIGN - SOUTH
 5. OFFICE OF BRIDGE DESIGN - WEST
 6. OFFICE OF BRIDGE DESIGN SOUTHERN CALIFORNIA

COMMENTS: Revise unit for Drill and Bond (Chemical Adhesive)
Misc Metal replaces Structural Steel
Revised quantity for Misc Metal (Bridge) per the Designer


ATTACHMENT E
Initial Site Assessment (ISA)

Memorandum

To: Katie Beach, Transportation Engineer
District 1 Advance Planning

Date: November 2, 2011

File No.: 1-DN-101/199-VAR
01-0A100K
01 1200 0023
DN Seismic Retrofits

From: Steve Werner 
North Region Office of Environmental Engineering—North

Subject: Initial Site Assessment

An Initial Site Assessment (ISA) for the seismic retrofits project referenced above was conducted after receiving your October 11, 2011, request. The ISA was based on the information provided in your request memorandum and a revised scope of work for the Middle Fork Smith River Bridge (Br. No. 01-044) received by e-mail.

Based on the information provided, the ISA found that the project has possible hazardous waste issues related to asbestos and lead paint in bridge components, and Aerially Deposited Lead (ADL) in soil that will be disturbed during the proposed work.

It will be necessary to have a consultant perform surveys of the bridge sites for issues related to the hazardous waste issues noted above. When preliminary bridge plans are available and the project has entered the zero phase, it is recommended that the Project Engineer contact this office so that we can arrange to have the surveys completed.

Due to the nature of the work outlined in your ISA request, it appears that an air quality NESHAP permit will be required for each bridge. For the purposes of determining the appropriate environmental documents required for the project, the work site(s) should not be considered to be on the *Hazardous Waste and Substances Site List (Correse List)*.

If there are any changes to the scope of the project, please send an e-mail or letter describing the changes so that they may be evaluated for possible hazardous waste issues that could affect your project. Communications may also be directed to me at (707) 445-6658.

cc: 1-SWerner 2-File

E-mail copies to: Steve Werner
Environmental

SSW/ks

ATTACHMENT F
Transportation Management Plan (TMP)

TRANSPORTATION MANAGEMENT PLAN

To: KATIE BEACH
Design Engineer
District 1 Advance Planning

Date: October 28, 2011
File: DN-101, 199 PM VAR
EA: 01-0A100K
EFIS: 0112000023

Seismic Retrofit-5 Bridges

From: TROY ARSENEAU, Chief
District 1 Office of Traffic Operations

Project Information

Location: In Del Norte County, along Routes 101 and 199, at 5 locations.

Type of Work: Seismic retrofits.

Anticipated Traffic Control: One-way reversible traffic control
Lane reduction
Intermittent closure
Shoulder closure

Estimated Maximum Delay: 5 minutes during reversing traffic control.
Minimal during lane reduction traffic control.
20 minutes during any intermittent closures.

Peak Hour Traffic Volumes: 810 vph

Lane Requirement Charts : Included

Work During Night Hours: Possible, but improbable.

Number of Working Days: TBD

PSR Date: December/2011

RTL Date: TBD

District Traffic Manager/ TMP Manager: Troy Arseneau (707) 445-6377

TMP Coordinator: Marie Brady (707) 445-6689

Anticipated Traffic Impacts

Significant traffic impacts are not anticipated provided that the following recommendations and requirements are incorporated into the project. In conformance with Deputy Directive-60, District Lane Closure Review Committee approval is not required for projects with anticipated traffic delay less than 30 minutes.

Recommendation

A request for an updated Transportation Management Plan shall be made during the design phase.

Hours of Work

- See Chart Nos. 1 through 4 for work hour restrictions.
- The full width of the traveled way shall be open for use by public traffic for the following Special Days:

Event	Event Date	Special Days
Sea Cruise	Second Weekend in October	Friday through Monday

The contractor shall verify the actual dates for this Special Event. See Chart No. 5 "Lane Closure Restrictions for Designated Legal Holidays and Special Days" for work day restrictions.

Public Notice

- Upon receipt of notice that the roadway width, including paved shoulder, for a direction of travel will be narrowed to less than 16 ft, the Resident Engineer shall promptly notify the HQ Construction Liaison Jay Horton at (916) 322-4957.
- The District Public Information Office, (707) 445-6444, shall be contacted two weeks in advance of the start of construction.
- Any emergency service agency whose ability to respond to incidents will be affected by any lane closure must be notified prior to that closure.
- Impacts to tribal land during the construction phase shall be coordinated with the affected local tribal government and other entities during the design phase. Contact Kathleen Sartorius, District 1 Native American Liaison, (707) 441-5815.
- Closures on the Railroad Ave. OC (#01-0063) shall be coordinated with Del Norte County's Road Division at (707) 464-7238.
- Work shall be coordinated with the local busing system (including school buses and public systems) to minimize impact on their bus schedules.

- The Resident Engineer shall provide information to residents and businesses before and during project work that may represent a negative impact on commerce and travel surrounding the zone of construction.

Traffic Control

- One closure, on each route, is permitted within the project limits.
- The W11-1 vehicular traffic sign (bicycle symbol) and the W16-1 supplemental plaque (SHARE THE ROAD) shall be placed, in each direction of travel, prior to the construction zone.
- At the Railroad Ave. OC (#01-0063), consider using stop signs to control traffic (for guidance see Typical Application 11 in the January 21, 2011 CA MUTCD Chapter 6H).
- One-way traffic control shall be in conformance with the Caltrans Standard Plan T-13, "TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE ON TWO LANE CONVENTIONAL HIGHWAYS."
 - A minimum of 14 ft of paved roadway shall be open for use by public traffic.
 - Supplemental funds shall be provided in the event the Resident Engineer decides to utilize advance flaggers. All flaggers shall have continuous radio contact with personnel in the work area.
- Work that requires a lane closure shall be in conformance with the Caltrans Standard Plan T-10, "TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE ON FREEWAYS AND EXPRESSWAYS."
 - A minimum of 14 ft of paved roadway, in each direction of travel, shall be open for use by public traffic.
- Work that occurs within 15 ft of the traveled way shall require a shoulder closure in conformance with the Caltrans Standard Plan T-10, "TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE ON FREEWAYS AND EXPRESSWAYS."
- During bridge deck drilling and/or bolting at the Smith River Overflow Bridge (#01-0046), when one-way control is in effect, the road may be closed and public traffic stopped for periods not to exceed 10 min. After each closure, all accumulated traffic shall be allowed to pass through the work before another closure is made.

- A minimum of one PCMS in advance of both ends of the construction site shall be required to notify the public of the closures related to this project. One of the displayed messages shall read, “WATCH FOR BIKES”.
- Access to side roads and residences shall be maintained at all times. When work or traffic queues extend through an intersection, additional traffic control will be required at the intersection.
- Bicyclists shall be accommodated through the work zone. During reversing traffic control, bicyclists shall be instructed to join the vehicle queue. During lane reduction traffic control, bicyclists shall be provided space adjacent to the open traffic lane to traverse through the work zone.
- If persons with disabilities (e.g. hearing, visual, or mobility) are found to use this facility, the temporary traffic control measures mentioned in the January 21, 2011 CA MUTCD Chapter 6D shall be incorporated to accommodate disabled pedestrians through the work zone.
- COZEEP is recommended for this project based on risk factors associated with this project and the COZEEP Guidelines (CA DOT Construction Manual Section 2-215A). The associated risk factors include: workers exposed to traffic, night construction activities, speed management, and significant truck volumes.
- The following projects are anticipated to have closures within this project’s work limits and shall be included in SSP 07-850: 01-0A3904 (Bridge Rehab) and 01-436404 (Dr. Fine Bridge Replacement).

Contingency Plan

The contractor shall prepare a contingency plan for reopening closures to public traffic. The Contractor shall submit the contingency plan for a given operation to the Engineer within one working day of the Engineer’s request. Contingencies for unanticipated delays, emergencies, etc. shall be coordinated between the RE and the Contractor.

Approval

Approved by:


 Transportation Management Plan Coordinator

Approved by:


 District Traffic/ TMP Manager

TAA/jml

CC: 1)TAArseneau, 2)JCandalot

1)RMMartinelli, 2) NBraafadt 3)File

IPoindexter

JPimentel

KChurch

JMcGee

AJones

Chart No. 1
Multilane Conventional Highway Lane Requirements

County: Del Norte

Route/Direction: 199 NB/SB

PM: 17.1

Closure Limits: The Middle Fork Smith River (#01-0044).

FROM HOUR TO HOUR	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mondays through Thursdays	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Fridays	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1									
Saturdays																									
Sundays																					1	1	1	1	1

Legend:

1 Provide at least one 14 ft through highway lane open in direction of travel. The maximum length of a traffic control closure is 700 ft.

No lane and/or shoulder closures allowed.

REMARKS:

- The full width of the traveled way shall be open for use by public traffic when construction operations are not actively in progress.
- Maintain access to the vista point at PM 17.3.

**Chart No. 2
 Connector Lane Requirements**

County: Del Norte	Route/Direction: 199 SB												PM: T0.5																	
Closure Limits: SB 101/199 Connector																														
FROM HOUR TO HOUR						24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mondays through Thursdays						1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Fridays						1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1							
Saturdays																														
Sundays																														

Legend:

1 Provide at least one 14 ft connector lane open in direction of travel. The maximum length of a traffic control closure is 500 ft.

No lane and/or shoulder closures allowed.

REMARKS: The full width of the traveled way shall be open for use by public traffic when construction operations are not actively in progress.

**Chart No. 3
 Expressway Lane Requirements**

County: Del Norte	Route/Direction: 101 NB/SB												PM: 35.8 and 39.6																			
Closure Limits: The Smith River Overflow Bridge (#01-0046) and the Rowdy Creek Bridge (#01-0023).																																
FROM HOUR TO HOUR						24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24		
Mondays through Thursdays						R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	
Fridays						R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R	R								
Saturdays																																
Sundays																																

Legend:

R Provide at least one 14 ft through traffic lane for use by both directions of travel (Reversing Control). The maximum length of a reversing control closure is 400 ft.

No lane/shoulder closures allowed.

REMARKS:

- The full width of the traveled way shall be open for use by public traffic when construction operations are not actively in progress.
- Regarding the Smith River Overflow Bridge (#01-0046), maintain access to the Tolowa Dunes State Park at PM 36.0.
- Regarding the Rowdy Creek Bridge (#01-0023), maintain access to Rowdy Creek Rd. at PM 39.7 and the Smith River Tribal Office at PM 39.6.

Chart No. 4
Local Road Lane Requirements

County: Del Norte	Route/Direction: 101 NB/SB	PM: R28.3
Closure Limits: Railroad Ave. OC (#01-0063).		
FROM HOUR TO HOUR	24	1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24
Mondays through Thursdays	R	R R
Fridays	R	R R
Saturdays		
Sundays		R R

Legend:

- R Provide at least one 14 ft through traffic lane for use by both directions of travel (Reversing Control).
- The maximum length of a reversing control closure is 500 ft.
- No lane/shoulder closures allowed.

REMARKS:

1. The full width of the traveled way shall be open for use by public traffic when construction operations are not actively in progress.
2. Maintain access to Connor Way and Pine Grove Rd.

ATTACHMENT G
Storm Water Data Report

APPENDIX E

Short Form - Storm Water Data Report



Dist-County-Route: 01-DN-VARIOUS
Post Mile Limits: VARIOUS (See Project Description)
Project Type: Seismic Retrofit
Project ID (or EA): 0A100K
Program Identification: 201.113
Phase: PID PA/ED
 PS&E

Regional Water Quality Control Board(s): North Coast RWQCB

1. Is the project required to consider incorporating Treatment BMPs? Yes No
2. Does the project disturb 5 or more acres of soil? Yes No
3. Does the project disturb more than 1 acre of soil and not qualify for the Rainfall Erosivity Waiver? Yes No
4. Does the project potentially create permanent water quality impacts? Yes No
5. Does the project require a notification of ADL reuse Yes No

If the answer to any of the preceding questions is "Yes", prepare a Long Form – Storm Water Data Report.

Estimate Construction Start Date: 2013 Construction Completion Date: 2014

Separate Dewatering Permit (if yes, permit number) Yes Permit # _____ No

Erosivity Waiver Yes Date: _____ No

This Short Form – Storm Water Data Report has been prepared under the direction of the following Licensed Person. The Licensed Person attests to the technical information contained herein and the data upon which recommendations, conclusions, and decisions are based. Professional Engineer or Landscape Architect stamp required at PS&E.

 11/17/11
Jeffrey Pimmel, Registered Project Engineer Date
I have reviewed the stormwater quality design issues and find this report to be complete, current and accurate:

11/18/11
 Date
Sheila Enright, District/Regional SW Coordinator or Designee

[Stamp Required for PS&E only]

APPENDIX E

Short Form - Storm Water Data Report

1. Project Description

- This seismic retrofit project consists of 5 locations along Hwy 101 & Hwy 199. Work on each bridge varies from removing column flares, installing column shells, installing anchor piles behind abutments, installing a seat extender, and replacing cross-frames. The structures included in the project are Railroad Avenue Overcrossing #01-0063 (101-PM R28.32), Smith River Overflow Bridge #01-0046 (101-PM 35.77), Rowdy Creek Bridge #01-0023 (101-PM 39.63), SR 199/101 Connector Overcrossing #01-0058F (199-PM TO.51) and the Middle Fork Smith River Bridge #01-0044 (199-PM 17.06).
- The project will cause minimal soil disturbance incidental to accessing the column footing, anchor pile CIDH, temporary access road and staging areas. Disturbed soil area is anticipated to be less than 1 acre.
- No TMDLs or 303(d) water bodies are within the project limits.

2. Construction Site BMPs

- Due to the minimal soil disturbance (<1 acres), a contractor prepared and Implemented Water Pollution Control Plan (WPCP) will be required during the construction phase. The WPCP will include temporary construction BMPs as a means of controlling storm water runoff that may occur during construction activities.
- The project will likely be constructed during the non-rainy season. Temporary construction site BMPs will be deployed under a contractor prepared WPCP. Anticipated temporary water pollution control bid items are: Prepare WPCP, Construction Site Management, Temporary Fiber Roll, Temporary Concrete Washout and Additional Water Pollution Control funds included in Supplemental Work. Temporary construction site BMP costs have been estimated at \$299,600 using Method 1, Percentage of Total Construction Cost as shown in Appendix F of the PPDG and calculated as 2.5% of total construction cost. Additional temporary construction BMP's may be included in the design phase.
- The attached Construction Site BMP Consideration form documents construction concurrence in accordance with North Region directives.

3. Required Attachments¹

- Vicinity Map
- Evaluation Documentation Form
- Construction Site BMP Consideration Form

¹ Additional attachments may be required as applicable or directed by the District/Regional Design Storm Water Coordinator (e.g. BMP line item estimate, DPP, CS checklists, etc).

Construction Site BMP Consideration Form

DATE: 11/07/11

Project ID (or EA): 01-0A100K

Project Evaluation Process for the Consideration of Construction Site BMPs

NO.	CRITERIA	YES ✓	NO ✓	SUPPLEMENTAL INFORMATION
1.	Will construction of the project result in areas of disturbed soil as defined by the Project Planning and Design Guide (PPDG)?	✓		If Yes, Construction Site BMPs for Soil Stabilization (SS) will be required. Complete CS-1, Part 1. Continue to 2. If No, Continue to 3.
2.	Is there a potential for disturbed soil areas within the project to discharge to storm drain inlets, drainage ditches, areas outside the right-of-way, etc?	✓		If Yes, Construction Site BMPs for Sediment Control (SC) will be required. Complete CS-1, Part 2. Continue to 3.
3.	Is there a potential for sediment or construction related materials and wastes to be tracked offsite and deposited on private or public paved roads by construction vehicles and equipment?	✓		If Yes, Construction Site BMPs for Tracking Control (TC) will be required. Complete CS-1, Part 3. Continue to 4.
4.	Is there a potential for wind to transport soil and dust offsite during the period of construction?	✓		If Yes, Construction Site BMPs for Wind Erosion Control (WE) will be required. Complete CS-1, Part 4. Continue to 5.
5.	Is dewatering anticipated or will construction activities occur within or adjacent to a live channel or stream?	✓		If Yes, Construction Site BMPs for Non-Storm Water Management (NS) will be required. Complete CS-1, Part 5. Continue to 6.
6.	Will construction include saw-cutting, grinding, drilling, concrete or mortar mixing, hydro-demolition, blasting, sandblasting, painting, paving, or other activities that produce residues?	✓		If Yes, Construction Site BMPs for Non-Storm Water Management (NS) will be required. Complete CS-1, Parts 5 & 6. Continue to 7.
7.	Are stockpiles of soil, construction related materials, and/or wastes anticipated?	✓		If Yes, Construction Site BMPs for Waste Management and Materials Pollution Control (WM) will be required. Complete CS-1, Part 6. Continue to 8.
8.	Is there a potential for construction related materials and wastes to have direct contact with precipitation; stormwater run-on, or stormwater runoff; be dispersed by wind; be dumped and/or spilled into storm drain systems?	✓		If Yes, Construction Site BMPs for Waste Management and Materials Pollution Control (WM) will be required. Complete CS-1, Part 6. Continue to 9.
9.	End of checklist.	✓		Document for Project Files by completing this form, and attaching it to the SWDR.

PE to initialize after concurrence with Construction (PS&E only)

Date



ATTACHMENT H
Landscape Architecture Assessment Sheet



TO: Katie Beach	CO: DN	RTE: 101 & 199	KP:	PM: variousx
FROM: Ron Flory	DISTRICT: 01	DATE: 11-9-11		
Unit/Senior TE Name: 03-382/Ron Flory	EA: 01-0A100	various		
Project Manager: Kevin Church				
PROJECT SEPARATION: X Landscape as part of roadway work EA <input type="checkbox"/> Landscape under separate EA (Follow-up)	PROJECT: Seismic Retrofit 5 Bridges			
	TYPE: SHOPP			
	PROJECT MILESTONE: PID			

PROJECT DESCRIPTION:

The project proposes to seismically retrofit five bridges in Del Norte County. The following bridges will have the following work completed: 1. Smith River Overflow - Seed Extended on Hinge, 2. Rowdy Creek - X-Bracing at Support Locations, 3. Railroad Avenue OC - Remove Column Flare, 4. Middle Fork Smith River - Install Anchor Piles at Abutments, 5. SR 199/SR 101 Connector OC - Install Anchor Piles at Abutments & Remove column Flare.

AREA (M2) FOR HIGHWAY PLANTING: N/A
AREA (M2) FOR EROSION CONTROL: 10,000sf
PLANT COUNT FOR MITIGATION PLANTING: 300

LANDSCAPE FREEWAY STATUS: Yes No
HIGHWAY PLANTING IS: Warranted Not Warranted
SCENIC HIGHWAY STATUS: Officially Designated Eligible
REVEGETATION REQUIRED? Permit Required Offset of Visual Impact
BIOLOGIST CONTACT: Not Designated Other (Forest Service, BLM, etc.)
DATE OF CONTACT: None yet. _____

ADJACENCY TO BILLBOARDS:

Project area is adjacent to outdoor advertising. Project area is not adjacent to outdoor advertising.

WATER AND POWER AVAILABILITY: N/A

DESIGN FOR MAINTENANCE SAFETY: N/A

CONTEXT SENSITIVITY:
 It is determined that the project will involve consideration of highway aesthetics and will require further evaluations pertaining to specific roadside enhancements.
 No unforeseen issues with highway aesthetics Other _____

COOPERATIVE MAINTENANCE AGREEMENTS:

Project may involve additional tasks indicated

<input type="checkbox"/> Visual Simulation	<input checked="" type="checkbox"/> Erosion Control	<input checked="" type="checkbox"/> SWPPP/NPDES
<input type="checkbox"/> Highway Planting	<input checked="" type="checkbox"/> Field Visit	<input checked="" type="checkbox"/> Context Sensitive Solutions/Aesthetics
<input type="checkbox"/> Contour Grading	<input type="checkbox"/> Cost Estimate	<input type="checkbox"/> Landscape Evaluation



**NORTH REGION
LANDSCAPE ARCHITECTURE ASSESSMENT SHEET**
03-LAND-0002 (Rev. 3/03)

COST INFORMATION:	
<input checked="" type="checkbox"/> Highway Planting, Irrigation, and/or Mitigation	\$ 15,000
<input checked="" type="checkbox"/> 2-year Reveg Establishment	\$5,000
<input checked="" type="checkbox"/> Erosion Control	\$10,000
<input type="checkbox"/> Slope Protection	\$
<input type="checkbox"/> Aesthetic Treatment	\$
TOTAL	\$ 30,000 /ft²


OTHER RELATED INFORMATION:

Landscape Architecture Resource Estimate: See attached.

PREPARED BY:  DATE: 11/9/11 CONCURRED BY: _____ DATE: _____
(Project Manager)

APPROVED BY:  DATE: 11.9.11
(Landscape Architecture or Engineering Services Branch Chief)

ATTACHMENT I
Environmental Document (PEAR)



Mini-Preliminary Environmental Analysis Report

Caltrans

Project Information

District 01 County DN Route 101/199 Post Mile Various EA 01-0A100
 Project ID#: 0100020010
 Project Title: Del Norte Bridges Seismic Retrofit
 Project Manager: Kevin Church Phone #: 707.445.6440
 Design Manager: Ilene Poindexter Phone #: 707.441.3969
 Design Engineer: Katie Beach Phone #: 707.441.2044
 Environmental Manager: Gary Berrigan Phone #: 707.441.5730

Project Description

The California Department of Transportation (Caltrans) proposes to seismically retrofit five bridges in Del Norte County, three bridges on U.S. Route 101 and two bridges on U.S. Route 199.

Project Purpose and Need: As a result of the Area Bridge Maintenance Engineer's biennial bridge inspections, these five bridges were identified as being in need of retrofitting, and placed on the Structures Maintenance & Investigations (SM&I) list. The project would complete outstanding seismic retrofit work on the five bridges, and meet existing California seismic standards.

Description of Work

Below is a table of the bridges which are included in the project. All work and staging for this project is expected to be within the proposed ESL shown on the attached project layouts.

Location	Bridge #	Bridge Name	Seismic Work to be Completed
DN-101-PM 35.77	01-0046	Smith River Overflow	Seat Extended at Hinge
DN-101-PM 39.63	01-0023	Rowdy Creek	X-Bracing at Support Locations
DN-101-PM R28.32	01-0063	Railroad Avenue OC	Remove Column Flare Install Column Casings Install Anchor Piles at Abutments
DN-199-PM 17.06	01-0044	Middle Fork Smith River	Install Anchor Piles at Abutments
DN-199-PM T0.51	01-0058F	SR 199/SR 101 Connector OC	Install Anchor Piles at Abutments Install Column Casings Remove Column Flare

Funding

State Federal

Anticipated Environmental Approval

CEQA

Mitigated Negative Declaration/Mitigated

NEPA

Categorical Exclusion

Summary Statement

In order to identify environmental issues, constraints, costs and resource needs, a mini-PEAR was prepared for the project. It is important to note that all technical studies will be deferred to the Capital phases of the project. There is a possibility of significant impacts to biological, cultural and other environmental resources. To move the proposed project to the next programming phase, potential environmental concerns were noted and resource estimates were provided to meet the aggressive schedule and limited resources available.

It is anticipated that an Initial Study with a Mitigated Negative Declaration and Categorical Exclusion would apply to this project. Based on existing workload and available resources, it is anticipated to take 24 to 30 months to meet PA&ED after a complete Environmental Study Request (ESR) is submitted and the project is assigned. An assignment should be made on later than February of a given year in order to complete spring botanical surveys.

Special Considerations

Biological: Known and potential resources within and adjacent to the proposed project that may be affected include: U.S. and State jurisdictional waters and wetlands, special-status plants and special-status animals. Due to the variety of listed and sensitive species (plants, birds, mammals, and amphibians), multiple seasonally appropriate studies, plus further research and coordination with resource agencies would be needed in order to determine presence or absence within the project area. Depending on the outcome of the surveys, a Section 7 consultation under the Federal Endangered Species Act may be necessary with the US Fish and Wildlife Service (USFWS). The bridge work over waterways may require a Section 7 consultation with the National Oceanic and Atmospheric Administration (NOAA), including hydroacoustic analysis. It's likely that a wetland delineation also will be needed. In addition to the federal consultation, the California Department of Fish and Game may need to administer authority if there is any "take" according to the California Endangered Species Act.

Under the current scope of the project, the following other biological permits are anticipated:

- A Clean Water Act 404 Permit issued by the U.S. Army Corps of Engineers (USACE)
- A Clean Water Act 401 Certification issued by the Regional Water Quality Control Board(RWQCB)
- A California Department of Fish and Game 1600 Streambed Alteration Agreement

Archaeology: Prehistoric, and possibly historic, archaeological surveys would be required. Native American consultation would be required. Additionally, an extended Phase I archaeological investigation may be required if resources are identified that cannot be avoided. A geoarchaeological investigation may be required dependent on the nature and extent of project excavation, the results of archaeological surveys and Native American

consultation. In addition, the unique location of elements of the project has a moderate potential for cultural resources.

Noise: A noise analysis would be necessary to evaluate potential environmental impacts of construction noise on sensitive receptors, including residents close to the project locations.

Water Quality: A water quality assessment would need to be prepared for this project. Temporary and permanent BMPs would be included in the contract.

Hazardous Waste: An ISA will be required for each location that is part of this project.

Coastal Zone: Four of the bridges are in the coastal zone, and a coastal development permit would be required.

Wild and Scenic River: Potential impacts to the wild and Scenic Smith River will need to be addressed.

Mitigation

Mitigation will be required for impacts to wetlands, riparian vegetation, water quality, fisheries and other habitat. There is the potential to impact up to one acre of riparian habitat at each of three bridge locations that could require a mitigation ratio of 4:1.


Disclaimer

This report is not an environmental document. Preliminary analysis, determinations, and estimates of mitigation costs are based on the project description provided in this report. The estimates and conclusions provided are very approximate and are based on brief and cursory analysis. This report is to provide a very preliminary level of environmental discussion to supplement the Project Initiation Document. Future action will require details regarding the project scope, potential alternatives, a full project description, construction scenario, purpose and need statement, plans and complete ESR.

Review and Approval

I confirm that environmental cost, scope, and schedule have been satisfactorily completed and that the PEAR meets all C&H&M requirements. Also, if the project is scoped as a routine EA, complex EA, or EIS, I verify that the HOD/EA Coordinator has concurred in the Class of Action.

Approved by:



Environmental Manager

Date: 12.05.11



Project Manager

Date: 12-5/11

Attachment D: PEAR Environmental Commitments Cost Estimate

Standard PSR Only

(Prepare a separate form for each viable alternative described in the Project Study Report)

PART 1 PROJECT INFORMATION

rev. 11/08

District-County-Route-Post Mile 01-DN-101/199-Var	EA: 01-0A100K
Project Description: Seismic Retrofit of five bridges in Del Norte County	
Form completed by (Name/District Office): Gary Berrigan, North Region Environmental	
Project Manager: Kevin Church	
Phone Number: 445.6440	
Date: November 15, 2011	

PART 2 PERMITS AND AGREEMENTS

	Permits and Agreements (\$\$)
<input checked="" type="checkbox"/> Fish and Game 1602 Agreement	25000
<input checked="" type="checkbox"/> Coastal Development Permit	3000
<input type="checkbox"/> State Lands Agreement	
<input checked="" type="checkbox"/> Section 401 Water Quality Certification	50000
<input checked="" type="checkbox"/> Section 404 Permit – Nationwide (U.S. Army Corps)	0
<input type="checkbox"/> Section 404 Permit – Individual (U.S. Army Corps)	
<input type="checkbox"/> Section 10 Navigable Waters Permit (U.S. Army Corps)	
<input type="checkbox"/> Section 9 Permit (U.S. Coast Guard)	
<input type="checkbox"/> Other:	
Total (enter zeros if no cost)	78000

PART 3. ENVIRONMENTAL COMMITMENTS FOR PERMANENT IMPACTS

To complete the following information:

- Report costs in \$1,000s.
- Include all costs to complete the commitment:
 - Capital outlay and staff support. Refer to Estimated Resources by WBS Code. For example, if you estimated 80 hours for biological monitoring (WBS 235.35 Long Term Mitigation Monitoring), convert those hours to a dollar amount for this entry. For current conversion rates from PY to dollars, see the Project Manager.
 - Cost of right of way or easements.
 - If compensatory mitigation is anticipated (for wetlands, for example), insert a range for purchasing credits in a mitigation bank.
 - Long-term monitoring and reporting
 - Any follow-up maintenance
 - Use current costs; the Project Manager will add an appropriate escalation factor.
 - This is an estimating tool, so a range is not only acceptable, but advisable.

Environmental Commitments Alternative		
	Estimated Cost in \$1,000's	Notes
Noise abatement or mitigation	75	Hydroacoustic
Special landscaping	30	
Archaeological resources	30	Rancheria
Biological resources	75	Fisheries
Historical resources		
Scenic resources	20	Scenic By Way
Wetland/riparian resources	30	
Res./bus. relocations		
Other:		
Total (enter zeros if no cost)	260	

ATTACHMENT J
Cost Estimate

Del Norte Seismic Retrofit

Project Study Report-Cost Estimate



01-DN-101 & 199

PM Various

EA 01-0A100K

Program Code 201.113

PROJECT DESCRIPTION:

LIMITS: In Del Norte County at various bridge location on US 101 & US 199

PROPOSED IMPROVEMENT (SCOPE): This is Seismic retrofit project that proposes various improvements at each bridge.

Seismic Retrofit

TOTAL ROADWAY ITEMS	\$3,501,000
TOTAL STRUCTURE ITEMS	\$7,223,000
SUBTOTAL CONSTRUCTION COSTS	\$10,724,000
TOTAL RIGHT OF WAY ITEMS (2011)	\$3,318,000
TOTAL PROJECT CAPITAL OUTLAY COSTS CALL	\$14,042,000
Project Total (2011)	\$14,044,000

Summary By Bridge

<i>Railroad Avenue Overcrossing</i>	
TOTAL ROADWAY ITEMS	\$424,000
TOTAL STRUCTURE ITEMS	\$390,000
SUBTOTAL CONSTRUCTION COSTS	\$814,000
TOTAL RIGHT OF WAY ITEMS	\$663,600
TOTAL PROJECT CAPITAL OUTLAY COSTS	\$1,477,600
CALL	\$1,478,000
<i>Smith River Overflow</i>	
TOTAL ROADWAY ITEMS	\$203,000
TOTAL STRUCTURE ITEMS	\$105,000
SUBTOTAL CONSTRUCTION COSTS	\$308,000
TOTAL RIGHT OF WAY ITEMS	\$663,600
TOTAL PROJECT CAPITAL OUTLAY COSTS	\$971,600
CALL	\$972,000
<i>Rowdy Creek</i>	
TOTAL ROADWAY ITEMS	\$326,000
TOTAL STRUCTURE ITEMS	\$490,000
SUBTOTAL CONSTRUCTION COSTS	\$816,000
TOTAL RIGHT OF WAY ITEMS	\$663,600
TOTAL PROJECT CAPITAL OUTLAY COSTS	\$1,479,600
CALL	\$1,480,000
<i>199/101 Connector OC</i>	
TOTAL ROADWAY ITEMS	\$459,000
TOTAL STRUCTURE ITEMS	\$390,000
SUBTOTAL CONSTRUCTION COSTS	\$849,000
TOTAL RIGHT OF WAY ITEMS	\$663,600
TOTAL PROJECT CAPITAL OUTLAY COSTS	\$1,512,600
CALL	\$1,513,000
<i>Middle Fork Smith River</i>	
TOTAL ROADWAY ITEMS	\$2,089,000
TOTAL STRUCTURE ITEMS	\$5,848,000
SUBTOTAL CONSTRUCTION COSTS	\$7,937,000
TOTAL RIGHT OF WAY ITEMS	\$663,600
TOTAL PROJECT CAPITAL OUTLAY COSTS	\$8,600,600
CALL	\$8,601,000

Project Study Report-Cost Estimate



01-DN-101

PM 28.07/25.57

EA 01-0A100K

Program Code 201.113

PROJECT DESCRIPTION:

LIMITS: In Del Norte County on US 101 at Railroad Avenue Overcrossing (#01-0063)

PROPOSED IMPROVEMENT (SCOPE): This is Seismic retrofit project that proposes to install 4-foot diameter cast-in-drilled-hole (CIDH) anchor piles behind the abutments (two at each abutment) from the bridge deck. The pile heads will be tied to the end diaphragm through steel pipes and high strength rods. From underneath the overcrossing the column flares will be removed and the column flare reinforcements cut. Excavation around column to the footing will occur in order to install full length column casing. The column casing will be flared to match existing column with 4" gap under the soffit of the bridge.

Seismic Retrofit

SUMMARY OF ESTIMATED 2011 COST

TOTAL ROADWAY ITEMS	\$424,000
TOTAL STRUCTURE ITEMS	\$390,000
SUBTOTAL CONSTRUCTION COSTS	\$814,000
TOTAL RIGHT OF WAY ITEMS (2011)	\$663,600
TOTAL PROJECT CAPITAL OUTLAY COSTS	\$1,477,600
CALL	\$1,478,000

Reviewed by District Program Manager

Date 7 Dec 2011

Approved by Project Manager

Date 12/7/11

for Kevin Church

1. ROADWAY ITEMS

Section 1 Earthwork	Quantity	Unit	Unit Price	Item Cost
			Subtotal Earthwork	\$0

Section 2 Pavement Structural Section	Quantity	Unit	Unit Price**	Item Cost
Replace Concrete Pavement	1.60	TON	\$2,000	\$3,200
			Subtotal Pavement Structural Section	\$3,200

Section 3 Drainage	Quantity	Unit	Unit Price	Item Cost
			Subtotal Drainage	\$0

Section 4 Specialty Items	Quantity	Unit	Unit Price	Item Cost
Construction Site BMP's	1	LS	\$35,500	\$35,500
Erosion Control	1	LS	\$2,000	\$2,000
Highway Planning	1	LS	\$3,000	\$3,000
2-Year Reveg Establishment	1	LS	\$1,000	\$1,000
Environmental Commitments (Noise, Landscape, archeological,et	1	LS	\$52,000	\$52,000
Prepare Storm Water Pollution Prevention Plan	1	LS	\$240	\$240
Remove Metal Beam Guard Rail	300	LF	\$15	\$4,500
Metal Beam Guard Rail	300	LF	\$80	\$24,000
Temporary Crash Cushion	2	LS	\$20,000	\$20,000
Temporary Rail (Type K)	300	LF	\$60	\$18,000
			Subtotal Specialty Items	\$160,240

Section 5 Traffic Items	Quantity	Unit	Unit Price	Item Cost
Portable Changeable Message Sign (PCMS)	4	EA	\$7,000	\$28,000
Construction Area Signs	1	LS	\$10,000	\$10,000
			Subtotal Traffic Items	\$38,000
			SUBTOTAL Items 1-5	\$201,440

Traffic Additions (Added in "TOTAL SECTIONS 1 thru 5)				
Traffic Control System	1	LS	(6% of Roadway & Structures Subtotal)	\$35,500
Maintain Traffic	1	LS	(7% of Roadway & Structures Subtotal)	\$41,500

Time Related Overhead (Added in "TOTAL SECTIONS 1 thru 5)				
RO	1	LS	(10% of Roadway Subtotal)	\$20,200

TOTAL SECTIONS 1 thru 5	\$278,440
--------------------------------	------------------

Section 6 Minor Items	
	\$278,440 x (5%) =
	(Subtotal Sections 1 thru 5)
TOTAL MINOR ITEMS	\$13,922
	Subtotal Sections 1 thru 6

Section 7 Roadway Mobilization	
	\$292,362 x (15%) =
	(Subtotal Sections 1 thru 6)
TOTAL ROADWAY MOBILIZATION	\$43,854

Section 8 Roadway Additions	Quantity	Unit	Unit Price	Item Cost
Supplemental Work				
	\$292,362 x (5%) =			\$14,618
	(Subtotal Sections 1 thru 6)			
Contingencies				
	\$292,362 x (25%) =			\$73,091
	(Subtotal Sections 1 thru 6)			
TOTAL ROADWAY ADDITIONS				\$87,709
			Subtotal Section 7 & 8	\$131,563

TOTAL ROADWAY ITEMS	\$424,000
----------------------------	------------------

II. STRUCTURES ITEMS

Bridge Name Railroad Avenue Overcrossing #01-0063
 Structure Type C/P/PS Slab
Total Structure Cost = \$390,000
 (10% for TRC, 10% for mobilization, and 40% for contingency included in structures estimate)

SUBTOTAL STRUCTURES ITEMS \$390,000
 (Sum of Total Cost for Structures)

Railroad Related Costs:

SUBTOTAL RAILROAD ITEMS \$0

TOTAL STRUCTURES ITEMS \$390,000

III. RIGHT OF WAY ITEMS (2011 Costs)

A. Acquisition, including excess lands,	\$0
B. Mitigation acquisition & credits	\$648,000
C. Project Development Permit Fees	\$15,600
D. Utility Relocation (State share)	\$0
E. Relocation Assistance (RAP)	\$0
F. Clearance/Demolition	\$0
G. Title and Escrow Fees	\$0

TOTAL RIGHT OF WAY ITEMS \$663,600

Anticipated Date of Right of Way Certification March 1, 2016
 Escalated Right of Way Costs \$818,200

F. Construction Contract Work

Estimate Prepared By: Katie Beach Phone # 707-441-2044

Estimate Checked By: Jeffrey Pimentel Phone # 707-445-6358

Smith River Overflow #01-0046

Project Study Report-Cost Estimate



01-DN-101
PM 35.52/36.02
EA 01-0A100K
Program Code 201.113

PROJECT DESCRIPTION:

LIMITS: In Del Norte County on US 101 at Smith River Overflow Bridge (#01-0046)

PROPOSED IMPROVEMENT (SCOPE): This is Seismic retrofit project that proposes to place a seat extender at the hinge in span 5 with four shallow steel members bolted through the deck to the short span

Seismic Retrofit

SUMMARY OF ESTIMATED 2011 COST

TOTAL ROADWAY ITEMS	\$203,000
TOTAL STRUCTURE ITEMS	\$105,000
SUBTOTAL CONSTRUCTION COSTS	\$308,000
TOTAL RIGHT OF WAY ITEMS (2011)	\$663,600
TOTAL PROJECT CAPITAL OUTLAY COSTS	\$971,600
CALL	\$972,000

Reviewed by District Program Manager

Date 27 Dec 2011

Approved by Project Manager

Date 12/01/11

for Kevin Church

1. ROADWAY ITEMS

Section 1 Earthwork	Quantity	Unit	Unit Price	Item Cost
			Subtotal Earthwork	\$0

Section 2 Pavement Structural Section	Quantity	Unit	Unit Price**	Item Cost
			Subtotal Pavement Structural Section	\$0

Section 3 Drainage	Quantity	Unit	Unit Price	Item Cost
			Subtotal Drainage	\$0

Section 4 Specialty Items	Quantity	Unit	Unit Price	Item Cost
Erosion Control	1	LS	\$2,000	\$2,000
Highway Planting	1	LS	\$3,000	\$3,000
2-Year Reveg Establishment	1	LS	\$1,000	\$1,000
Construction Site BMP's	1	LS	\$23,300	\$23,300
Environmental Commitments (Noise, Landscape, archeological,et	1	LS	\$52,000	\$52,000
Prepare Storm Water Pollution Prevention Plan	1	LS	\$240	\$240
Subtotal Specialty Items				\$81,540

Section 5 Traffic Items	Quantity	Unit	Unit Price	Item Cost
Thermoplastic Striping (4")	10	FT	\$2,000	\$20
Pavement Marker (Retroreflective)	6	EA	\$6,000	\$36
Portable Changeable Message Sign (PCMS)	2	EA	\$7,000	\$14,000
Construction Area Signs	1	LS	\$5,000	\$5,000
Subtotal Traffic Items				\$19,056
SUBTOTAL Items 1-5				\$100,596

Traffic Additions (Added in "TOTAL SECTIONS 1 thru 5)				
Traffic Control System	1	LS	(6% of Roadway & Structures Subtotal)	\$12,400
Maintain Traffic	1	LS	(7% of Roadway & Structures Subtotal)	\$14,400

Time Related Overhead (Added in "TOTAL SECTIONS 1 thru 5)	1	LS	(10% of Roadway Subtotal)	\$10,100
---	---	----	---------------------------	----------

TOTAL SECTIONS 1 thru 5	\$137,496
--------------------------------	------------------

Section 6 Minor Items	
\$137,496 x (5%) =	\$6,875
(Subtotal Sections 1 thru 5)	
TOTAL MINOR ITEMS	\$6,875

Subtotal Sections 1 thru 6 \$144,371

Section 7 Roadway Mobilization	
\$144,371 x (10%) =	\$14,437
(Subtotal Sections 1 thru 6)	
TOTAL ROADWAY MOBILIZATION	\$14,437

Section 8 Roadway Additions	Quantity	Unit	Unit Price	Item Cost
Supplemental Work				
		\$144,371 x (5%) =		\$7,219
		(Subtotal Sections 1 thru 6)		
Contingencies				
		\$144,371 x (25%) =		\$36,093
		(Subtotal Sections 1 thru 6)		
TOTAL ROADWAY ADDITIONS				\$43,311
		Subtotal Section 7 & 8		\$57,748

TOTAL ROADWAY ITEMS \$203,000

II. STRUCTURES ITEMS

Bridge Name Smith River Overflow #01-0046
 Structure Type CIP/RC Slab
Total Structure Cost = \$105,000
 (10% for TRQ, 10% for mobilization, and 40% for contingency included in structures estimate)

SUBTOTAL STRUCTURES ITEMS \$105,000
 (Sum of Total Cost for Structures)

Railroad Related Costs:

SUBTOTAL RAILROAD ITEMS \$0

TOTAL STRUCTURES ITEMS \$105,000

III. RIGHT OF WAY ITEMS (2011 Costs)

- A. Acquisition, including excess lands, \$0
- B. Mitigation acquisition & credits \$648,000
- C. Project Development Permit Fees \$15,600
- D. Utility Relocation (State share) \$0
- E. Relocation Assistance (RAP) \$0
- F. Clearance/Demolition \$0
- G. Title and Escrow Fees \$0

TOTAL RIGHT OF WAY ITEMS \$663,600

Anticipated Date of Right of Way Certification March 1, 2016
 Escalated Right of Way Costs \$818,200

F. Construction Contract Work

Estimate Prepared By: Katie Beach Phone # 707-441-2044

Estimate Checked By: Jeffrey Pimentel Phone # 707-445-6358

Rowdy Creek Bridge #01-0023

Project Study Report-Cost Estimate



01-DN-101
PM 39.38/39.88
EA 01-0A100K
Program Code 201.113

PROJECT DESCRIPTION:

LIMITS: In Del Norte County on US 101 at Rowdy Creek Bridge (#01-0023)

PROPOSED IMPROVEMENT (SCOPE): The existing cross-frames at the support locations will be removed and replaced. Rivets and stiffeners will be removed using a cutting torch and small areas of the existing will need to be blast cleaned and painted.

Seismic Retrofit

SUMMARY OF ESTIMATED 2011 COST

TOTAL ROADWAY ITEMS	\$326,000
TOTAL STRUCTURE ITEMS	\$490,000
SUBTOTAL CONSTRUCTION COSTS	\$816,000
TOTAL RIGHT OF WAY ITEMS (2011)	\$663,600
TOTAL PROJECT CAPITAL OUTLAY COSTS	\$1,479,600
CALL	\$1,480,000

Reviewed by District Program Manager

Date 7 Dec 2011

Approved by Project Manager

Date 12/7/11

for Kevin Church

1. ROADWAY ITEMS

Section 1 Earthwork Clearing & Grubbing	Quantity	Unit	Unit Price	Item Cost
	1	LS	\$15,000	\$15,000
			Subtotal Earthwork	\$15,000

Section 2 Pavement Structural Section	Quantity	Unit	Unit Price**	Item Cost
			Subtotal Pavement Structural Section	\$0

Section 3 Drainage	Quantity	Unit	Unit Price	Item Cost
			Subtotal Drainage	\$0

Section 4 Specialty Items	Quantity	Unit	Unit Price	Item Cost
Construction Site BMP's	1	LS	\$35,800	\$35,800
Erosion Control	1	LS	\$2,000	\$2,000
Highway Planning	1	LS	\$3,000	\$3,000
2-Year Reveg Establishment	1	LS	\$1,000	\$1,000
Environmental Commitments (Noise, Landscape, archeological,et	1	LS	\$52,000	\$52,000
Prepare Storm Water Pollution Prevention Plan	1	LS	\$240	\$240
			Subtotal Specialty Items	\$94,040

Section 5 Traffic Items	Quantity	Unit	Unit Price	Item Cost
Portable Changeable Message Sign (PCMS)	2	EA	\$7,000	\$14,000
Construction Area Signs	1	LS	\$5,000	\$5,000
			Subtotal Traffic Items	\$19,000
			SUBTOTAL Items 1-5	\$128,040

Traffic Additions (Added in "TOTAL SECTIONS 1 thru 5)	Quantity	Unit	Unit Price	Item Cost
Traffic Control System	1	LS	(6% of Roadway & Structures Subtotal)	\$37,100
Maintain Traffic	1	LS	(7% of Roadway & Structures Subtotal)	\$43,300

Time Related Overhead (Added in "TOTAL SECTIONS 1 thru 5)	Quantity	Unit	Unit Price	Item Cost
TRO	1	LS	(10% of Roadway Subtotal)	\$12,900

TOTAL SECTIONS 1 thru 5	\$221,340
--------------------------------	------------------

Section 6 Minor Items				
			\$221,340 x (5%) =	\$11,067
			(Subtotal Sections 1 thru 5)	
			TOTAL MINOR ITEMS	\$11,067

Subtotal Sections 1 thru 6 \$232,407

Section 7 Roadway Mobilization				
			\$232,407 x (10%) =	\$23,241
			(Subtotal Sections 1 thru 6)	
			TOTAL ROADWAY MOBILIZATION	\$23,241

Section 8 Roadway Additions

Quantity	Unit	Unit Price	Item Cost
	Supplemental Work	\$232,407 x (5%) =	\$11,620
		(Subtotal Sections 1 thru 6)	

Contingencies \$232,407 x (25%) =

(Subtotal Sections 1 thru 6) \$58,102

TOTAL ROADWAY ADDITIONS \$69,722

Subtotal Section 7 & 8 \$92,963

TOTAL ROADWAY ITEMS	\$326,000
----------------------------	------------------

II. STRUCTURES ITEMS

Bridge Name Rowdy Creek #01-0023
 Structure Type C/P/RC Slab
Total Structure Cost = \$490,000
 (10% for TRQ, 10% for mobilization, and 40% for contingency included in structures estimate)

SUBTOTAL STRUCTURES ITEMS \$490,000
 (Sum of Total Cost for Structures)

Railroad Related Costs:

SUBTOTAL RAILROAD ITEMS \$0

TOTAL STRUCTURES ITEMS \$490,000

III. RIGHT OF WAY ITEMS (2011 Costs)

- A. Acquisition, including excess lands, \$0
- B. Mitigation acquisition & credits \$648,000
- C. Project Development Permit Fees \$15,600
- D. Utility Relocation (State share) \$0
- E. Relocation Assistance (RAP) \$0
- F. Clearance/Demolition \$0
- G. Title and Escrow Fees \$0

TOTAL RIGHT OF WAY ITEMS \$663,600

Anticipated Date of Right of Way Certification March 1, 2016
 Escalated Right of Way Costs \$818,200

F. Construction Contract Work

Estimate Prepared By: Katie Beach Phone # 707-441-2044

Estimate Checked By: Jeffrey Pimentel Phone # 707-445-6358

101/199 Connector Overcrossing #01-0058F

Project Study Report-Cost Estimate



Caltrans

01-DN-199

PML0.506/L0.684

EA 01-0A100K

Program Code 201.113

PROJECT DESCRIPTION:

LIMITS: In Del Norte County at the US 101/US 199 Connector OC (#01-0058F)

PROPOSED IMPROVEMENT (SCOPE): This is Seismic retrofit project that proposes to install 4-foot diameter cast-in-drilled-hole (CIDH) anchor piles behind the abutments (two at each abutment) from the bridge deck. The pile heads will be tied to the end diaphragm through steel pipes and high strength rods. From underneath the overcrossing the column flares will be removed and the column flare reinforcements cut. Excavation around column to the footing will occur in order to install full length column casing. The column casing will be flared to match existing column with 4" gap under the soffit of the bridge.

Seismic Retrofit

SUMMARY OF ESTIMATED 2011 COST

TOTAL ROADWAY ITEMS	\$459,000
TOTAL STRUCTURE ITEMS	\$390,000
SUBTOTAL CONSTRUCTION COSTS	\$849,000
TOTAL RIGHT OF WAY ITEMS (2011)	\$663,600
TOTAL PROJECT CAPITAL OUTLAY COSTS	\$1,512,600
CALL	\$1,513,000

Reviewed by District Program Manager

Date 8 Dec 2011

Approved by Project Manager

Date 12/7/11

for Kevin Church

1. ROADWAY ITEMS

Section 1 Earthwork	Quantity	Unit	Unit Price	Item Cost
			Subtotal Earthwork	\$0

Section 2 Pavement Structural Section	Quantity	Unit	Unit Price**	Item Cost
Replace Concrete Pavement	1.60	TON	\$2,000	\$3,200
			Subtotal Pavement Structural Section	\$3,200

Section 3 Drainage	Quantity	Unit	Unit Price	Item Cost
			Subtotal Drainage	\$0

Section 4 Specialty Items	Quantity	Unit	Unit Price	Item Cost
Construction Site BMP's	1	LS	\$36,200	\$36,200
Erosion Control	1	LS	\$2,000	\$2,000
Highway Planning	1	LS	\$3,000	\$3,000
2-Year Reveg Establishment	1	LS	\$1,000	\$1,000
Environmental Commitments (Noise, Landscape, archeological,et	1	LS	\$52,000	\$52,000
Prepare Storm Water Pollution Prevention Plan	1	LS	\$240	\$240
Remove Metal Beam Guard Rail	300	LF	\$15	\$4,500
Metal Beam Guard Rail	300	LF	\$80	\$24,000
Temporary Crash Cushion	2	LS	\$20,000	\$20,000
Temporary Rail (Type K)	300	LF	\$60	\$18,000
			Subtotal Specialty Items	\$160,940

Section 5 Traffic Items	Quantity	Unit	Unit Price	Item Cost
Portable Changeable Message Sign (PCMS)	3	EA	\$7,000	\$21,000
Construction Area Signs	1	LS	\$7,500	\$7,500
			Subtotal Traffic Items	\$28,500
			SUBTOTAL Items 1-5	\$192,640

Traffic Additions (Added in "TOTAL SECTIONS 1 thru 5)	Quantity	Unit	Unit Price	Item Cost
Traffic Control System	1	LS	(6% of Roadway & Structures Subtotal)	\$35,000
Maintain Traffic	1	LS	(7% of Roadway & Structures Subtotal)	\$40,800

Time Related Overhead (Added in "TOTAL SECTIONS 1 thru 5)	Quantity	Unit	Unit Price	Item Cost
TRO	1	LS	(10% of Roadway Subtotal)	\$19,300

TOTAL SECTIONS 1 thru 5	\$287,740
--------------------------------	------------------

Section 6 Minor Items					
				\$287,740 x (5%) =	\$14,387
			(Subtotal Sections 1 thru 5)		
			TOTAL MINOR ITEMS		\$14,387
			Subtotal Sections 1 thru 6		\$302,127

Section 7 Roadway Mobilization					
				\$302,127 x (15%) =	\$45,319
			(Subtotal Sections 1 thru 6)		
			TOTAL ROADWAY MOBILIZATION		\$45,319

Section 8 Roadway Additions	Quantity	Unit	Unit Price	Item Cost
	Supplemental Work			
			\$302,127 x (5%) =	\$15,106
			(Subtotal Sections 1 thru 6)	
	Contingencies			
			\$302,127 x (25%) =	\$75,532
			(Subtotal Sections 1 thru 6)	

		\$ Per Hour	Hours Per Day	Work Days	
COZEEP setups @ \$100 per Hour Working 10 Hour Days		\$100	9	16.5	\$14,850
COZEEP setups @ \$200 per Hour Working 10 Hour Nights		\$200	9	3.3	\$5,940
			TOTAL ROADWAY ADDITIONS		\$111,428

Subtotal Section 7 & 8	\$156,747
TOTAL ROADWAY ITEMS	\$459,000

II. STRUCTURES ITEMS

Bridge Name US 199/101 Overcrossing #01-0058F
 Structure Type CIP/PS Slab
Total Structure Cost = \$390,000
 (10% for TRQ, 10% for mobilization, and 40% for contingency included in structures estimate)

SUBTOTAL STRUCTURES ITEMS \$390,000
 (Sum of Total Cost for Structures)

Railroad Related Costs:

SUBTOTAL RAILROAD ITEMS \$0

TOTAL STRUCTURES ITEMS \$390,000

III. RIGHT OF WAY ITEMS (2011 Costs)

A. Acquisition, including excess lands,	\$0
B. Mitigation acquisition & credits	\$648,000
C. Project Development Permit Fees	\$15,600
D. Utility Relocation (State share)	\$0
E. Relocation Assistance (RAP)	\$0
F. Clearance/Demolition	\$0
G. Title and Escrow Fees	\$0

TOTAL RIGHT OF WAY ITEMS \$663,600

Anticipated Date of Right of Way Certification March 1, 2016
 Escalated Right of Way Costs \$818,200

Estimate Prepared By: Katie Beach Phone # 707-441-2044

Estimate Checked By: Jeffrey Pimentel Phone # 707-445-6358

Project Study Report-Cost Estimate



01-DN-199
PMR16 8/R17.31
EA 01-0A100K
Program Code 201.113

PROJECT DESCRIPTION:

LIMITS: In Del Norte County on US 101 at Middle Fork Smith River Bridge (#01-0044)

PROPOSED IMPROVEMENT (SCOPE): This is Seismic retrofit project that proposes to install 4-foot diameter cast-in-drilled-hole (CIDH) anchor piles behind the abutments (two at each abutment) from the bridge deck. The pile heads will be tied to the end diaphragm through steel pipes and high strength rods. Beneath the bridge add concrete to thinner portions of left bridge and complete concrete infill walls in between the left and right bridge. Install steel plates for confinement

Seismic Retrofit

SUMMARY OF ESTIMATED 2011 COST

TOTAL ROADWAY ITEMS	\$2,089,000
TOTAL STRUCTURE ITEMS	\$5,848,000
SUBTOTAL CONSTRUCTION COSTS	\$7,937,000
TOTAL RIGHT OF WAY ITEMS (2011)	\$663,600
TOTAL PROJECT CAPITAL OUTLAY COSTS	\$8,600,600
CALL	\$8,601,000

Reviewed by District Program Manager

Date

7 Dec 2011

Approved by Project Manager

Date

12/7/11

for Kevin Church

1. ROADWAY ITEMS

Section 1 Earthwork	Quantity	Unit	Unit Price	Item Cost
Cleaning & Grubbing	1	LS	\$100,000	\$100,000
Roadway Excavation	907	CY	\$22	\$19,954
Subtotal Earthwork				\$119,954

Section 2 Pavement Structural Section	Quantity	Unit	Unit Price**	Item Cost
Replace Asphalt Concrete Pavement	1.60	TON	\$600	\$960
Class 2 Aggregate Base-Access Road	1,000	CY	\$75,000	\$75,000
Rock Slope protection fabric (Class 8) (Access Entrance)	102	SOYD	\$5,00	\$511
Rock Slope protection fabric (Class 10) (Access Rd)	1,140	SOYD	\$5,00	\$5,700
Subtotal Pavement Structural Section				\$82,171

Section 3 Drainage	Quantity	Unit	Unit Price	Item Cost
Subtotal Drainage				\$0

Section 4 Specialty Items	Quantity	Unit	Unit Price	Item Cost
Erosion Control	1	LS	\$2,000	\$2,000
Highway Planting	1	LS	\$3,000	\$3,000
2-Year Reveg Establishment	1	LS	\$1,000	\$1,000
Construction Site BMP's	1	LS	\$205,500	\$205,500
Environmental Commitments (Noise, Landscape, archeological)	1	LS	\$52,000	\$52,000
Prepare Storm Water Pollution Prevention Plan	1	LS	\$240	\$240
Subtotal Specialty Items				\$263,740

Section 5 Traffic Items	Quantity	Unit	Unit Price	Item Cost
Portable Changeable Message Sign (PCMS)	2	EA	\$7,000	\$14,000
Construction Area Signs	1	LS	\$5,000	\$5,000
Subtotal Traffic Items				\$19,000
SUBTOTAL Items 1-5				\$484,865

Traffic Additions (Added in "TOTAL SECTIONS 1 thru 5)	Quantity	Unit	Unit Price	Item Cost
Traffic Control System	1	LS	(6% Item Subtotal)	\$380,000
Maintain Traffic	1	LS	(7% Item Subtotal)	\$443,400

Time Related Overhead (Added in "TOTAL SECTIONS 1 thru 5)	Quantity	Unit	Unit Price	Item Cost
TRO	1	LS	(10% of Roadway Subtotal)	\$48,500

TOTAL SECTIONS 1 thru 5	\$1,356,765
--------------------------------	--------------------

Section 6 Minor Items	
\$1,356,765 x (5%) =	\$67,838
(Subtotal Sections 1 thru 5)	
TOTAL MINOR ITEMS	\$67,838
Subtotal Sections 1 thru 6	\$1,424,603

Section 7 Roadway Mobilization	
\$1,424,603 x (15%) =	\$213,691
(Subtotal Sections 1 thru 6)	

Section 8 Roadway Additions				
	Quantity	Unit	Unit Price	Item Cost
	Supplemental Work			
			\$1,424,603 x (5%) =	\$71,230
			(Subtotal Sections 1 thru 6)	
	Contingencies			
			\$1,424,603 x (25%) =	\$356,151
			(Subtotal Sections 1 thru 6)	

	\$ Per Hour	Hours Per Day	Work Days	
COZEEP setups @ \$100 per Hour Working 10 Hour Days	\$100	10	16.5	\$16,500
COZEEP setups @ \$200 per Hour Working 10 Hour Nights	\$200	10	3.3	\$6,600
			TOTAL ROADWAY ADDITIONS	\$450,481
			Subtotal Section 7 & 8	\$664,172

TOTAL ROADWAY ITEMS	\$2,089,000
----------------------------	--------------------

II. STRUCTURES ITEMS

Bridge Name Middle Fork Smith River #01-0044
 Structure Type CIP/RC Box Girder
Total Structure Cost = \$5,848,000
 (10% for TRQ, 10% for mobilization, and 40% for contingency included in structures estimate)

SUBTOTAL STRUCTURES ITEMS \$5,848,000
 (Sum of Total Cost for Structures)

Railroad Related Costs:

SUBTOTAL RAILROAD ITEMS \$0

TOTAL STRUCTURES ITEMS \$5,848,000

III. RIGHT OF WAY ITEMS (2011 Costs)

- A. Acquisition, including excess lands, \$0
- B. Mitigation acquisition & credits \$648,000
- C. Project Development Permit Fees \$15,600
- D. Utility Relocation (State share) \$0
- E. Relocation Assistance (RAP) \$0
- F. Clearance/Demolition \$0
- G. Title and Escrow Fees \$0

TOTAL RIGHT OF WAY ITEMS \$663,600

F. Construction Contract Work

Anticipated Date of Right of Way Certification March 1, 2016
 Escalated Right of Way Costs \$818,200

Estimate Prepared By: Katie Beach Phone # 707-441-2044

Estimate Checked By: Jeffrey Pimentel Phone # 707-445-6358

ATTACHMENT K
Programming Sheet

PROGRAMMING SHEET

Project Manager: Kevin Church
Date: 07-Dec-11

01-DN-101/199-VAR
 EA 01-0A100
 2010201113 Bridge Seismic Retrofit

PROJECT SCHEDULE

MILESTONE	DATE
Begin Environmental Document (M020)	6/1/2012
Begin Project Report (M040) (Begin Design of Project)	5/1/2012
Circulate Environmental Document (M120)	10/1/2013
Project Approval & Environmental Document (M200)	7/1/2014
District Submits Bridge Site Data to Structures (M221)	1/1/2013
Right of Way Maps (M224)	2/1/2014
Draft Structures Plans, Specifications & Estimate (M378)	8/1/2015
Project Plans, Specifications & Estimate (M380)	12/1/2015
Right of Way Certification (M410)	3/1/2016
Ready to List (M460)	3/15/2016
HQ Advertise (M480)	7/15/2016
Approve Construction Contract (M500)	12/15/2016
Contract Acceptance (M600)	8/1/2018

Escalation Factors Used: Capital: 3.5% **2011 COSTS**
 Support: 1.5% Const: \$ 10,724
 RW: \$3,318

PROJECT COSTS BY SB45 CATEGORY

CAPITAL COSTS	11/12	12/13	13/14	14/15	15/16	16/17	FUTURE	TOTAL
Right of Way	\$ -	\$ -	\$ -	\$ -	\$ 5,532	\$ -	\$ -	\$ 4,091
Construction	\$ -	\$ -	\$ -	\$ -	\$ 12,225	\$ -	\$ -	\$ 12,225
CAPITAL TOTAL								\$ 16,316

SUPPORT COSTS	11/12	12/13	13/14	14/15	15/16	16/17	FUTURE	TOTAL
Environmental	\$ 108	\$ 633	\$ 332	\$ 85	\$ 61	\$ -	\$ -	\$ 1,219
Design	\$ -	\$ -	\$ 395	\$ 745	\$ 467	\$ 99	\$ -	\$ 1,706
Right of Way	\$ -	\$ -	\$ 31	\$ 11	\$ 10	\$ 8	\$ 23	\$ 84
Construction	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 604	\$ 1,534	\$ 2,139
SUPPORT COSTS								\$ 5,147
TOTAL PROJECT COSTS								\$ 21,464

SUPPORT TO CAPITAL RATIO/% 32%

SUPPORT PY'S by DIVISION

Number of Hours in a PY: 1758

PROJECT SUPPORT IN PY'S	11/12	12/13	13/14	14/15	15/16	16/17	FUTURE	TOTAL
Transportation Planning	0.21	2.20	1.41	0.99	0.63	0.09	0.59	6.1
District Design	0.35	1.28	1.96	2.25	1.73	0.42	0.79	8.8
Right of Way	0.01	0.02	0.11	0.43	0.19	0.01	0.02	0.8
District Construction	0.02	0.12	0.19	0.09	0.17	1.19	2.85	4.6
DES Design	0.15	0.80	1.44	1.64	0.63	0.58	0.67	5.9
DES Construction	0.00	0.02	0.03	0.03	0.01	1.84	3.86	5.8
TOTAL	0.74	4.45	5.15	5.43	3.36	4.13	8.78	32.0

Comments: