



DIST	COUNTY	ROUTE	KILOMETER TOTAL PROJECT	POST PROJECT	SHEET No	TOTAL SHEETS
04	SF	80	13.2/13.9		123R1	1204

12-6-04
 PLANS APPROVAL DATE

PB POWER, Inc.
 A Parsons Brinckerhoff Company
 303 Second St., Suite 700N
 San Francisco, CA 94107-1317

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

Caltrans now has a web site! To get to the web site, go to <http://www.dot.ca.gov>

- SHEET NOTES:**
- ① 4#10 + #10 G single conductors.
 - ② Deleted.
 - ③ conductors spliced inside junction box PB-2A located inside girder.
 - ④ For SAS Superstructure roadway westbound lighting schedule, see sheet E-82.
 - ⑤ The Contractor shall extend and coil 5 meters of cable in manhole 25. All cables shall be tagged with circuit numbers as shown. For location of manhole 25, see sheet E-11.
 - ⑥ Light pole, luminaires and lowering device are state furnished and installed by contractor.

- NOTES:**
- 1. References:
 - For pull box schedule, see sheet E-83.
 - For circuit and conduit/cable tray schedules, see sheets starting at E-401.

REQUEST FOR INFORMATION NOT ADDRESSED IN THIS CCO REMAIN IN FORCE

MARK	DATE	DESCRIPTIONS	BY	CH'D	CCO#
①	02/19/08	ELECTRICAL MODIFICATIONS	MP	RR	42
REVISIONS					

CONTRACT CHANGE ORDER NO. _____
 SHEET _____ OF _____

FOR REVISION ONLY

DETAILS
SAS SUPERSTRUCTURE ROADWAY WESTBOUND
480 V ROADWAY LIGHTING WIRING DIAGRAM
 NO SCALE

DATE PLOTTED => 3/17/2008
 TIME PLOTTED => 4:28:21 PM
 LAST REVISION 00-00-00