DIST	COUNTY	ROUTE	KILOMETER POST TOTAL PROJECT	SHEET No	TOTAL SHEETS
04	SF,Ala	80	12.2/14.3 0.0/4.0	407a 10S44	1204

Caltrans Metric

Syn Yee Chin 03/08/10
REGISTERED ELECTRICAL ENGINEER DATE

05-06-2010
PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER SYN YEE CHIN No. 18186 Exp. 09/30/2011 ELECTRICAL STATE OF CALIFORNIA

PB AMERICAS, Inc.
A Parsons Brinckerhoff Company
303 Second St., Suite 700N
San Francisco, CA 94107-1317

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

Caltrans now has a web site! To get to the web site, go to http://www.dot.ca.gov

REQUEST FOR INFORMATION NOT ADDRESSED IN THIS CCO REMAIN IN FORCE

MARK	DATE	DESCRIPTIONS	BY	CH'D	CCO#
0	03/08/10	MEP INTEGRATION	SYC	FW	110

REVISIONS

CONTRACT CHANGE ORDER NO._____
SHEET _____ OF _____

Conduit/Tray No:	7676B
Reference:	E-836
Size:	103
Type:	Liquidtight flex metal conduit
From:	TOS Splice Cable Tray (Hinge EE)
To:	2T43
Total Fill (mm2):	0.00
Remarks:	
Allowable Fill (mm2):	3275.44
Description of Changes:	

Included Cable No.	Conductor Type	Area (mm2)
Pull Rope	Soft-Fiber Polyester	0.00

Conduit/Tray No:	7681
Reference:	E-836
Size:	103
Type:	Liquidtight flex metal conduit
From:	2T13
To:	15 kV Splice Cable Tray (Hinge EE)
Total Fill (mm2):	2780.99
Remarks:	
Allowable Fill (mm2):	3275.44
Description of Changes:	

Included Cable No.	Conductor Type	Area (mm2)
2392	3-1/C #4/0, 15 KV, EPR insulation	2780.99
Pull Rope	Soft-Fiber Polyester	0.00

Conduit/Tray No:	7926A
Reference:	E-836
Size:	103
Type:	Liquidtight flex metal conduit
From:	2T12
To:	15 kV Splice Cable Tray (Hinge DE)
Total Fill (mm2):	2780.99
Remarks:	
Allowable Fill (mm2):	3275.44
Description of Changes:	

Included Cable No.	Conductor Type	Area (mm2)
2392	3-1/C #4/0, 15 KV, EPR insulation	2780.99
Pull Rope	Soft-Fiber Polyester	0.00

Conduit/Tray No:	7926B
Reference:	E-836
Size:	103
Type:	Liquidtight flex metal conduit
From:	15 kV Splice Cable Tray (Hinge DE)
To:	2T12
Total Fill (mm2):	2780.99
Remarks:	
Allowable Fill (mm2):	3275.44
Description of Changes:	

Included Cable No.	Conductor Type	Area (mm2)
2392	3-1/C #4/0, 15 KV, EPR insulation	2780.99
Pull Rope	Soft-Fiber Polyester	0.00

NEW
CONDUIT AND TRAY SCHEDULE

E-1043

THIS PLAN ACCURATE FOR ELECTRICAL WORK ONLY.

REVISED BY	DATE REVISED
SYC	01/10
FW	01/10

CALCULATED/DESIGNED BY: SYC DATE 01/10
CHECKED BY: FW

DESIGN OVERSIGHT
BEHZAD GOLEMOHAMMADI

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION
Caltrans

LAST REVISION 00-00-00
DATE PLOTTED => 06-MAY-2010
TIME PLOTTED => 18:48