

Caltrans

Metrio

DIST	COUNTY	ROUTE	KILOMETER TOTAL PROJECT	POST TOTAL PROJECT	SHEET NO	TOTAL SHEETS
04	SF, Alameda	80	12.2/14.3	0.0/4.0	407a	1204

Syn Yee Chin

03/08/10

REGISTERED ELECTRICAL ENGINEER

DATE

05-06-2010

PLANS APPROVAL DATE

PB AMERICAS, Inc.

A Parsons Brinckerhoff Company

303 Second St., Suite 700N

San Francisco, CA 94107-1317

THE STATE OF CALIFORNIA

REGISTERED PROFESSIONAL ENGINEER

SYN YEE CHIN

No. 18186

Exp. 09/30/2011

ELECTRICAL

STATE OF CALIFORNIA

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

Caltrans now has a web site. To get to the web site, go to <http://www.dot.ca.gov>

- NOTES:
- This plan sheet is a record drawing from Skyway Structures contract. The Contractor shall verify the existing installation. See sheet EE-269 from Skyway Structures, Contract No. 04-012024.
 - The installed components shall not be limited to the ones listed below, but shall be a complete installation. For details, see Bridge Structures Girder Westbound, typical Details sheets.
 - Furnish and install the 15kV cables into existing cable tray shown on this drawing. See sheets E-664 and E-665.
 - Furnish and install the TOS fiber optic cables into existing cable tray and conduits shown on this drawing. Pull a 72 fiber in the main tray and terminate in the splice closure. See sheets E-978 through E-981.
 - Inspect for system ground continuity. See sheets E-666 and E-667.
 - All cable trays, conduits and equipment shown on this drawing are existing. Bold ones are to be used for pulling cable.

- SHEET NOTES:
- Furnish and install splice cable tray as shown on sheet E-663, plan detail 2.
 - Mount splice cable tray between diaphragms, and secure properly. See sheet E-663, section detail 4.
 - Contractor shall locate the splice cable tray at Station 67+91 as shown on E-604.
 - Furnish and install 12 fiber optic cables from Fiber Optic Splice Closure to Controller Cabinet. Route via pull box PB-2B. Coil 3m of cable inside Controller Cabinet for connections by others. The coiled end of the fiber optic cables shall be terminated with mated connectors. See sheets E-972 and E-973.
 - Pull and terminate 50 pair telephone cable in Telephone Terminal Box. See sheets E-960, E-962 and E-964.


REQUEST FOR INFORMATION NOT ADDRESSED IN THIS CCO REMAIN IN FORCE					
0	03/08/10	MEP INTEGRATION	SYC	FW	110
MARK	DATE	DESCRIPTIONS	BY	CH'D	CCO#
REVISIONS					

CONTRACT CHANGE ORDER NO. _____
SHEET _____ OF _____

DETAILS
BRIDGE STRUCTURES GIRDER WESTBOUND
SKYWAY STRUCTURES-SERVICE PLATFORM #12W
SCALE AS NOTED

THIS PLAN ACCURATE FOR ELECTRICAL WORK ONLY.

FOR REDUCED PLANS ORIGINAL SCALE IS IN MILLIMETERS



DGN FILE => 04-0120f1_E-641.dgn
USERNAME => ilorico

CU 04251

EA 0120F1

DATE PLOTTED => 06-MAY-2010
TIME PLOTTED => 18:06
LAST REVISION
00-00-00