

**CONTRACT CHANGE ORDER**

Change Requested by: Engineer

CCO: 201 Suppl. No. 0 Contract No. 04 - 0120F4 Road SF-80-13.2/13.9 FED. AID LOC.:

To: **AMERICAN BRIDGE/FLUOR ENTERPRISES INC A JOINT VENTURE**

You are directed to make the following changes from the plans and specifications or do the following described work not included in the plans and specifications for this contract. **NOTE: This change order is not effective until approved by the Engineer.**

Description of work to be done, estimate of quantities and prices to be paid. (Segregate between additional work at contract price, agreed price and force account.) Unless otherwise stated, rates for rental of equipment cover only such time as equipment is actually used and no allowance will be made for idle time. This last percentage shown is the net accumulated increase or decrease from the original quantity in the Engineer's Estimate.

**Extra Work at Lump Sum:**

- Remove existing railings as noted and install modified permanent safety railings on Tower Façades for elevator landings at E.89.95m, E.127.85m, and E.139.85m.
- Between the South and East shafts of the Tower at E.143.85m, remove the existing railing and install a modified permanent safety railing similar to that shown for E.139.85m on plan sheet 938S6.
- Provide additional padeyes at Tower Façade elevations.
- Post "Not For Tie-Off" on a stainless steel plaque above the grabrail at all Tower Façade elevations.
- Provide two 8ft-6in long by 12in wide fiberglass ladders at each Tower strut elevation.

All new galvanized exterior surfaces shall be cleaned and painted in accordance with Special Provisions Section 10-1.66 "CLEAN AND PAINT SIGN STRUCTURES." All new non-galvanized exterior surfaces and any areas of damaged existing paint shall be cleaned, primed, and finish painted in accordance with Special Provisions Section 10-1.69 "CLEAN AND PAINT STRUCTURAL STEEL."

The following revised plan sheets detail the changes addressed in this change order: 938S6, 938S7, and 938S8 (of 1204) as shown on sheets 2 through 4 of this change order.


The handrail fabrication work shall be performed in accordance with the requirements of Special Provisions Section 10-1.73, "Miscellaneous Metal (Bridge)," except that subsection "Welding Quality Control," of section 8-3.01 "Welding" shall not apply.


For this work, the Contractor will receive a lump sum price of \$299,556.00. This sum constitutes full and complete compensation for furnishing all labor, material, tools and incidentals including all markups by reason of this change.

Extra Work at Lump Sum.....\$299,556.00

Estimated Cost: Increase  Decrease  \$299,556.00

By reason of this order the time of completion will be adjusted as follows: 0 Days


<b>Submitted by</b>		<b>0 Days</b>	
Signature		Resident Engineer	Kannu Balan, Senior T.E.
			Date 12-14-11

<b>Approval Recommended by</b>			
Signature		Supervising Transportation Engineer	William Casey, Sup. T.E.
			Date 12-20-11

<b>Engineer Approval by</b>			
Signature		Supervising Transportation Engineer	William Casey, Sup. T.E.
			Date 1-9-12

We the undersigned contractor, have given careful consideration to the change proposed and agree, if this proposal is approved, that we will provide all equipment, furnish the materials, except as otherwise be noted above, and perform all services necessary for the work above specified, and will accept as full payment therefor the prices shown above.

**NOTE: If you, the contractor, do not sign acceptance of this order, your attention is directed to the requirements of the specifications as to proceeding with the ordered work and filing a written protest within the time therein specified.**

<b>Contractor Acceptance by</b>		
Signature		(Print name and title)
		BRIAN A. PETERSEN - PROJECT DIRECTOR
		Date 06 JUN 12