Special Provisions Section 10-1.40 "Epoxy Asphalt Concrete Surfacing," subsection "Materials," the second paragraph of subsection "Production Trials" is revised as follows:

The Contractor shall demonstrate his production operations by applying bond coat and placing at least two paving passes of epoxy asphalt concrete surfacing. The total thickness of the paving shall ~~be~~ vary between 16 and 50 mm, or as otherwise directed by the Engineer. The location for the paving pass will be the Caltrans maintenance roadway located at the Toll Plaza of the San Francisco-Oakland Bay Bridge. The paving passes shall not begin until the area involved has been prepared in the same manner specified in "Epoxy Asphalt Bond Coat" elsewhere in this specification. Both passes shall be contiguous to each other and a minimum of 3.65 m wide by not less than 50 m long. During the production trials, the Contractor shall demonstrate his ability to make satisfactory ~~longitudinal and~~ transverse construction joints by stopping the placing operations approximately at the mid-point of the test strip, preparing the construction joint, then resuming the placing operations after a one hour waiting period; and making satisfactory longitudinal joints by making an inclined saw cut on the lane boundary and removing approximately 75 mm or poorly compacted epoxy asphalt spillover material.

REGISTERED PROFESSIONAL ENGINEER
MARWAN N. NADER
No. C 054426
Exp. 12/15
CIVIL
STATE OF CALIFORNIA