2010

Annual Average Daily Truck Traffic on the California State Highway System

Compiled by
Traffic and Vehicle Data Systems

State of California
Business, Transportation and Housing Agency
Department of Transportation

Prepared in cooperation with the
U.S. Department of Transportation
Federal Highway Administration

PREFACE

The annual average daily truck traffic is shown for selected locations on the State Highway System. Truck traffic is classified by number of axles. The two-axle class includes 11/2-ton trucks with dual rear tires and excludes pickups and vans with only four tires. Total vehicle AADT for the same year is taken from the Traffic Volumes on California State Highways booklet also published by the California Department of Transportation.

Annual average daily truck traffic is the total truck traffic volume divided by 365 days. Truck counting is done throughout the state in a program of continuous truck count sampling. The sampling includes a partial day, 24-hour, 7-day and continuous vehicle classification counts. The partial day and 24-hour counts are usually made on high volume, urban highways. The 7-day counts are made on low volume, rural highways. The counts are usually taken only once in the year. About one-sixth of the locations are counted annually. The resulting counts are adjusted to an estimate of annual average daily truck traffic by compensating for seasonal influence, weekly variation, and other variables that may be present. Annual average daily truck traffic is necessary for presenting a statewide picture of truck flow, evaluating truck trends, planning and designing highways and for other purposes.

The column entitled "Year Ver/Est" indicates the year the truck percents were either verified (V) or estimated (E). It represents the year the truck percentages were verified (counted continuously or quarterly) or estimated. Selected points on a route will be counted and the ones in between will be estimated. At some locations, truck volumes are static and no new counts are made until there is a change in traffic on the route. All truck AADT's listed are for 2010.

California State Highways are listed in legislative route number order. The legislative route number is the same as the signed route number in most cases.

Each count location is identified by the post mile value corresponding to that point on the highway. The post mile values increase from the beginning of a route within a county to the next county line. The post mile values start over again at each county line. Post mile values increase usually from south to north or west to east depending on the general direction the route follows within the state.

The post mile at a given location will remain the same year after year except in a few cases when the route was relocated/redesignated. When a section of road is relocated, new post miles (usually noted by an alphabetical prefix such as "R" or "M") are established for it. If relocation results in a change in length, "post mile equations" are introduced so that post miles on the remainder of the route within the county will remain unchanged. Post mile equations are not shown on this listing.

A leg is given for each count location and is denoted by an A, B or O. For traffic volumes purposes, a highway intersection or interchange has two legs. According to ascending post miles (route direction) and a post mile reference at the center of the intersection or interchange, B = back leg, A = ahead leg, and O = traffic volume is equal for the back and ahead legs.

Truck AADT's are shown as two-way traffic. Equivalent axle loading (EAL) are calculated to represent two-way travel.

Data compiled by:

Division of Traffic Operations, Office of System Planning Management
Traffic Data Branch
(916) 654-3072

Price: $15.00

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
001	12	ORA	R .129	A	DANA POINT, JCT. RTE. 5	37,000	2,301	6.22	781	1,089	308	123	33.93	47.32	13.39	5.36	215	03E
001	12	ORA	R .78	A	DANA POINT, DOHENY PARK ROAD	39,000	1,899	4.87	644	899	254	102	33.93	47.32	13.39	5.36	178	03E
001	12	ORA	9.418	B	LAGUNA BEACH, JCT. RTE. 133 NORTH	36,000	626	1.74	245	288	58	36	39.08	45.98	9.20	5.75	56	03E
001	12	ORA	9.418	A	LAGUNA BEACH, JCT. RTE. 133 NORTH	40,000	696	1.74	272	320	64	40	39.08	45.98	9.20	5.75	62	03E
001	12	ORA	19.797	B	NEWPORT BEACH, JCT. RTE. 55, NEWPORT BOULEVARD	46,000	524	1.14	403	73	24	24	76.92	13.85	4.62	4.62	33	00E
001	12	ORA	19.797	A	NEWPORT BEACH, JCT. RTE. 55, NEWPORT BOULEVARD	40,000	320	0.80	220	50	10	40	68.75	15.63	3.13	12.50	28	00E
001	12	ORA	21.549	B	SANTA ANA RIVER BRIDGE	32,000	224	0.70	154	35	7	28	68.75	15.63	3.13	12.50	19	00E
001	12	ORA	23.739	B	HUNTINGTON BEACH, JCT. RTE. 39 NORTH, BEACH BOULEVARD	35,000	280	0.80	193	44	9	35	68.75	15.63	3.13	12.50	24	00E
001	07	LA	0	A	LOS ANGELES/ORANGE COUNTY LINE	41,500	556	1.34	480	37	11	28	86.27	6.67	2.01	5.05	31	07V
001	07	LA	1.973	B	LONG BEACH, JCT. RTE. 22, SEVENTH STREET	26,000	697	2.68	493	111	29	64	70.75	15.98	4.09	9.18	54	05V
001	07	LA	1.973	A	LONG BEACH, JCT. RTE. 22, SEVENTH STREET	34,500	1,080	3.13	645	125	41	269	59.69	11.54	3.82	24.95	133	05V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
001	07	LA	3.557	B	LONG BEACH, LAKEWOOD BOULEVARD	32,500	683	2.10	408	79	26	170	59.69	11.54	3.82	24.95	84	07E
001	07	LA	3.557	A	LONG BEACH, LAKEWOOD BOULEVARD	40,000	684	1.71	605	48	9	22	88.47	7.01	1.25	3.27	35	07V
001	07	LA	7.288	B	LONG BEACH, JCT. RTE. 710, LONG BEACH FREEWAY	35,000	2,107	6.02	1,260	395	48	404	59.81	18.75	2.27	19.17	227	05V
001	07	LA	7.288	A	LONG BEACH, JCT. RTE. 710, LONG BEACH FREEWAY	33,500	6,372	19.02	1,430	1,225	136	3,580	22.44	19.23	2.14	56.19	1,418	04V
001	07	LA	8.266	B	LONG BEACH, JCT. RTE. 103, TERMINAL ISLAND FREEWAY	29,500	6,469	21.93	1,103	1,560	214	3,592	17.05	24.11	3.31	55.53	1,453	07V
001	07	LA	8.266	A	LONG BEACH, JCT. RTE. 103, TERMINAL ISLAND FREEWAY	26,000	6,414	24.67	1,003	2,134	221	3,056	15.64	33.27	3.44	47.65	1,318	05V
001	07	LA	11.61	B	LOS ANGELES, JCT. RTE. 110, HARBOR FREEWAY	36,000	1,768	4.91	947	305	60	455	53.58	17.24	3.42	25.76	227	05V
001	07	LA	11.61	A	LOS ANGELES, JCT. RTE. 110, HARBOR FREEWAY	55,000	2,970	5.40	1,784	552	105	529	60.08	18.57	3.53	17.82	311	05V
001	07	LA	13.1	A	LOS ANGELES, JCT. RTE. 213, WESTERN AVENUE	61,000	2,891	4.74	1,827	413	85	566	63.19	14.29	2.93	19.59	310	05V
001	07	LA	16.005	B	TORRANCE, JCT. RTE. 107, HAWTHORNE BOULEVARD	39,000	1,427	3.66	1,051	229	71	76	73.63	16.03	4.98	5.36	95	05V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
001	07	LA	16.005	A	TORRANCE, JCT. RTE. 107, HAWTHORNE BOULEVARD	40,500	1,349	3.33	1,028	181	86	54	76.20	13.39	6.41	4.00	84	05V
001	07	LA	21.919	B	MANHATTAN BEACH, ARTESIA BOULEVARD	46,000	1,532	3.33	1,167	205	98	61	76.20	13.39	6.41	4.00	95	05E
001	07	LA	21.919	A	MANHATTAN BEACH, ARTESIA BOULEVARD	45,000	1,499	3.33	1,142	201	96	60	76.20	13.39	6.41	4.00	93	05E
001	07	LA	25.924	B	LOS ANGELES, JCT. RTE. 105, GLENN ANDERSON FREEWAY	66,000	2,033	3.08	1,393	189	84	367	68.50	9.32	4.13	18.05	205	05V
001	07	LA	27.363	A	LOS ANGELES, LOS ANGELES INTERNATIONAL AIRPORT, VIA LINCOLN BOULEVARD	31,000	670	2.16	563	47	20	39	84.09	7.03	2.99	5.89	40	05E
001	07	LA	29.084	A	LOS ANGELES, MANCHESTER AVENUE	47,000	1,015	2.16	854	71	30	60	84.09	7.03	2.99	5.89	62	05E
001	07	LA	31.29	B	LOS ANGELES, JCT. RTE. 90, MARINA FREEWAY	44,000	950	2.16	799	67	28	56	84.09	7.03	2.99	5.89	58	05V
001	07	LA	31.29	A	LOS ANGELES, JCT. RTE. 90, MARINA FREEWAY	54,000	1,355	2.51	1,098	86	43	128	81.05	6.33	3.18	9.44	97	05V
001	07	LA	R 34.576	B	SANTA MONICA, JCT. RTE. 10, SANTA MONICA FREEWAY	48,000	1,469	3.06	1,114	169	43	143	75.81	11.52	2.96	9.71	110	05V
001	07	LA	35.17	O	SANTA MONICA, MCCLURE TUNNEL	58,000	3,149	5.43	2,247	375	53	474	71.35	11.92	1.69	15.04	284	05V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
001	07	LA	40.769	B	JCT. RTE. 27, TOPANGA CANYON BOULEVARD	53,000	1,426	2.69	1,123	170	33	101	78.76	11.89	2.30	7.05	95	05V
001	07	LA	40.769	A	JCT. RTE. 27, TOPANGA CANYON BOULEVARD	44,000	1,338	3.04	1,104	142	21	71	82.48	10.64	1.58	5.30	79	05V
001	07	LA	59.901	B	MALIBU, JCT. RTE. 23, DECKER CANYON ROAD	13,900	755	5.43	599	71	9	76	79.35	9.38	1.20	10.07	55	05V
001	07	LA	59.901	A	MALIBU, JCT. RTE. 23, DECKER CANYON ROAD	13,500	733	5.43	582	69	9	74	79.35	9.38	1.20	10.07	54	05E
001	07	VEN	9.866	O	CALLEGUAS CREEK	12,000	782	6.52	483	161	92	47	61.73	20.55	11.74	5.98	61	05V
001	07	VEN	R 15.053	B	OXNARD, PLEASANT VALLEY ROAD/RICE AVENUE	14,500	948	6.54	555	174	58	160	58.58	18.38	6.11	16.93	99	05V
001	07	VEN	17.626	B	OXNARD, SAVIERS ROAD	13,900	482	3.47	350	40	16	75	72.63	8.33	3.41	15.63	44	06V
001	07	VEN	18.154	B	OXNARD, JCT. RTE. 34, FIFTH STREET	30,500	949	3.11	714	94	34	108	75.21	9.92	3.54	11.33	76	06V
001	07	VEN	18.154	A	OXNARD, JCT. RTE. 34, FIFTH STREET	32,000	1,037	3.24	773	111	28	125	74.58	10.66	2.68	12.08	85	06V
001	07	VEN	20.14	B	OXNARD, JCT. RTE. 232, VINEYARD AVENUE	37,000	1,154	3.12	861	123	31	139	74.58	10.66	2.68	12.08	94	06E
001	07	VEN	20.14	A	OXNARD, JCT. RTE. 232, VINEYARD AVENUE	25,500	747	2.93	557	80	20	90	74.58	10.66	2.68	12.08	61	06E
001	07	VEN	21.075	B	OXNARD, JCT. RTE. 101, VENTURA FREEWAY	25,500	699	2.74	521	75	19	84	74.58	10.66	2.68	12.08	57	06E
001	07	VEN	21.25	A	OXNARD, JCT. RTE. 101, VENTURA FREEWAY	4,850	432	8.91	249	44	40	99	57.75	10.12	9.29	22.84	53	07V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
001	07	VEN	27.675	A	SEACLIFF COLONY, JCT. RTE. 101, VENTURA FREEWAY	720	68	9.41	36	7	10	15	52.77	10.59	14.48	22.16	9	07E
001	05	SB	R 0	A	LAS CRUCES, JCT. RTE. 101; MOBIL OIL PIER	7,000	707	10.10	332	35	27	313	47.00	4.90	3.80	44.30	127	10E
001	05	SB	19.251	B	LOMPOC, SOUTH JCT. RTE. 246	7,300	803	11.00	350	52	35	365	43.60	6.50	4.40	45.50	148	10E
001	05	SB	19.251	A	LOMPOC, SOUTH JCT. RTE. 246	12,500	888	7.10	519	108	46	215	58.40	12.20	5.20	24.20	109	10E
001	05	SB	20.565	B	LOMPOC, NORTH JCT. RTE. 246	12,500	813	6.50	536	107	21	149	65.90	13.20	2.60	18.30	83	10E
001	05	SB	20.565	A	LOMPOC, NORTH JCT. RTE. 246	12,900	516	4.00	335	68	14	99	65.00	13.10	2.70	19.20	54	10E
001	05	SB	22.519	B	LOMPOC, SANTA YNEZ RIVER BRIDGE	25,000	1,400	5.60	790	172	24	414	56.40	12.30	1.70	29.60	190	10E
001	05	SB	R 23.296	A	LOMPOC/CASMALIA ROAD	19,000	213	1.12	142	21	16	34	66.67	9.86	7.51	15.96	21	10V
001	05	SB	M 29.891	B	VANDENBERG AIR FORCE BASE	15,400	708	4.60	428	66	45	169	60.40	9.30	6.40	23.90	86	10E
001	05	SB	M 29.891	A	VANDENBERG AIR FORCE BASE	14,000	630	4.50	374	57	44	156	59.30	9.00	7.00	24.70	79	10E
001	05	SB	M 36.189	B	JCT. RTE. 135, VANDENBURG, NORTH	14,000	616	4.40	317	83	38	178	51.50	13.40	6.20	28.90	86	10E
001	05	SB	R 34.777	B	ORCUTT, JCT. RTE. 135 NORTH	15,500	682	4.40	268	125	50	239	39.30	18.30	7.40	35.00	111	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
001	05	SB	R 34.777	A	ORCUTT, JCT. RTE. 135 NORTH	2,500	436	17.45	190	74	26	146	43.55	16.91	6.02	33.52	68	10E
001	05	SB	41.81	A	CASMALIA ROAD	2,100	212	10.10	141	21	15	34	66.67	10.01	7.30	16.02	21	10V
001	05	SB	49.199	B	GUADALUPE, JCT. RTE. 166 EAST	2,100	237	11.27	151	24	16	46	63.85	9.93	6.96	19.26	26	10E
001	05	SB	49.199	A	GUADALUPE, JCT. RTE. 166 EAST	5,800	331	5.70	207	84	6	34	62.40	25.50	1.80	10.30	28	10E
001	05	SLO	10.9	B	HALCYON ROAD	6,200	301	4.86	37	75	40	149	12.28	25.00	13.16	49.56	65	10E
001	05	SLO	10.9	A	HALCYON ROAD	7,000	1,106	15.80	404	117	101	484	36.50	10.60	9.10	43.80	207	10E
001	05	SLO	16.73	B	SOUTH JCT. RTE. 101	9,400	207	2.20	139	19	9	39	67.30	9.30	4.50	18.90	21	10E
001	05	SLO	16.77	A	SAN LUIS OBISPO, NORTH JCT. RTE. 101	28,400	738	2.60	496	151	20	72	67.20	20.40	2.70	9.70	59	10E
001	05	SLO	17.874	B	HIGHLAND DRIVE	25,000	625	2.50	419	126	20	61	67.00	20.10	3.20	9.70	50	10E
001	05	SLO	17.874	A	HIGHLAND DRIVE	22,000	814	3.70	537	65	49	163	66.00	8.00	6.00	20.00	88	10E
001	05	SLO	27.883	B	BAYWOOD PARK ROAD	19,000	760	4.00	522	66	46	125	68.70	8.70	6.10	16.50	74	10E
001	05	SLO	27.883	A	BAYWOOD PARK ROAD	23,500	1,034	4.40	688	119	54	174	66.50	11.50	5.20	16.80	103	10E
001	05	SLO	30.135	B	JCT. RTE. 41 NORTHEAST	24,500	735	3.00	524	73	37	101	71.30	9.90	5.10	13.70	65	10E
001	05	SLO	30.135	A	JCT. RTE. 41 NORTHEAST	18,300	622	3.40	470	60	44	48	75.60	9.60	7.10	7.70	45	10E
001	05	SLO	45.99	B	JCT. RTE. 46	7,800	420	5.39	317	46	12	45	75.50	11.00	2.90	10.60	33	10E
001	05	SLO	45.99	A	JCT. RTE. 46	10,000	438	4.38	284	60	40	54	64.75	13.75	9.09	12.42	40	10E
001	05	SLO	56.39	B	HEARST CASTLE STATE PARK	5,200	223	4.28	155	26	26	16	69.70	11.52	11.52	7.27	17	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
001	05	MON	18.91	O	KIRK CREEK	2,000	4	0.20	3	1	0	1	66.70	16.60	0.00	16.70	1	03E
001	05	MON	46.595	O	BIG SUR RIVER BRIDGE	3,800	38	1.00	32	2	2	2	85.00	5.00	5.00	5.00	2	03E
001	05	MON	62.972	O	BIG SUR, GARRAPATA CREEK BRIDGE	4,300	17	0.40	13	2	1	1	75.00	12.50	4.20	8.30	1	03E
001	05	MON	72.921	B	CARMEL VALLEY ROAD, CARMEL, SOUTH	14,000	364	2.60	276	39	12	36	75.90	10.80	3.40	9.90	27	03E
001	05	MON	72.921	A	CARMEL VALLEY ROAD, CARMEL, SOUTH	33,300	1,299	3.90	908	281	58	52	69.90	21.60	4.50	4.00	84	03E
001	05	MON	75.135	B	JCT. RTE. 68, CARMEL-PACIFIC GROVE	44,900	1,437	3.20	977	290	112	57	68.00	20.20	7.80	4.00	97	03E
001	05	MON	75.135	A	JCT. RTE. 68, CARMEL-PACIFIC GROVE	54,000	1,350	2.50	836	328	120	66	61.90	24.30	8.90	4.90	100	03E
001	05	MON	R 78.119	B	MONTEREY, JCT. RTE. 68 EAST	80,000	2,560	3.20	1,664	589	177	131	65.00	23.00	6.90	5.10	184	03E
001	05	MON	R 78.119	A	MONTEREY, JCT. RTE. 68 EAST	60,000	2,280	3.80	1,423	401	84	372	62.40	17.60	3.70	16.30	227	03E
001	05	MON	R 79.357	B	SEASIDE, JCT. RTE. 218	71,000	2,769	3.90	1,695	487	100	487	61.20	17.60	3.60	17.60	287	03E
001	05	MON	R 79.357	A	SEASIDE, JCT. RTE. 218	70,000	2,940	4.20	1,646	512	109	673	56.00	17.40	3.70	22.90	353	03E
001	05	MON	R 80.679	A	ORD VILLAGE INTERCHANGE	82,000	3,526	4.30	1,915	677	88	846	54.30	19.20	2.50	24.00	434	03E
001	05	MON	R 89.185	O	SALINAS RIVER BRIDGE, CASTROVILLE, SOUTH	45,000	2,880	6.40	1,172	334	86	1,287	40.70	11.60	3.00	44.70	528	03E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
001	05	MON	R 90.979	B	CASTROVILLE, JCT. RTE. 156 WEST	45,000	3,600	8.00	1,228	522	180	1,670	34.10	14.50	5.00	46.40	694	03E
001	05	MON	R 90.979	A	CASTROVILLE, JCT. RTE. 156 WEST	17,000	1,377	8.10	618	183	59	516	44.90	13.30	4.30	37.50	225	03E
001	05	MON	T 92.213	A	CASTROVILLE, JCT. RTE. 183	30,000	2,880	9.60	1,397	346	84	1,054	48.50	12.00	2.90	36.60	457	03E
001	05	MON	T 101.04	B	SALINAS/PAJARO ROADS	33,500	3,283	9.80	1,546	414	98	1,225	47.10	12.60	3.00	37.30	529	03E
001	05	MON	T 101.04	A	SALINAS/PAJARO ROADS	34,000	3,434	10.10	1,628	402	106	1,298	47.40	11.70	3.10	37.80	557	03E
001	05	SCR	R .716	B	JCT. RTE. 129	35,000	3,045	8.70	1,373	381	88	1,203	45.10	12.50	2.90	39.50	511	03E
001	05	SCR	R .716	A	JCT. RTE. 129	39,000	2,730	7.00	1,553	328	44	805	56.90	12.00	1.60	29.50	369	03E
001	05	SCR	R 2.683	B	JCT. RTE. 152	30,000	2,340	7.80	1,404	241	75	620	60.00	10.30	3.20	26.50	296	03E
001	05	SCR	R 2.683	A	JCT. RTE. 152	53,000	2,491	4.70	1,659	316	47	468	66.60	12.70	1.90	18.80	256	03E
001	05	SCR	14.864	A	SOQUEL AVENUE	97,000	3,298	3.40	2,167	488	92	551	65.70	14.80	2.80	16.70	324	03E
001	05	SCR	16.821	B	SANTA CRUZ, JCT. RTE. 17 NORTH	86,000	1,978	2.30	1,315	237	45	380	66.50	12.00	2.30	19.20	206	03E
001	05	SCR	16.821	A	SANTA CRUZ, JCT. RTE. 17 NORTH	60,000	2,760	4.60	1,617	345	69	729	58.60	12.50	2.50	26.40	350	03E
001	05	SCR	20.611	A	SANTA CRUZ, NORTH CITY LIMITS	12,300	886	7.20	422	167	5	291	47.60	18.90	0.60	32.90	131	03E
001	05	SCR	30.44	B	LANDING/SWANTON ROADS	7,400	266	3.60	125	13	6	122	47.00	4.80	2.30	45.90	49	98E
001	04	SM	18.189	B	JCT. RTE. 84 EAST	5,700	288	5.06	144	8	2	134	50.15	2.74	0.61	46.50	52	04V
001	04	SM	18.189	A	JCT. RTE. 84 EAST	5,700	439	7.70	211	61	9	158	48.03	13.98	1.97	36.02	69	04V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
001	04	SM	26.432	B	MIRAMONTES POINT ROAD	7,700	386	5.01	236	29	6	115	61.22	7.48	1.59	29.71	51	04V
001	04	SM	29.036	B	HALF MOON BAY, JCT. RTE. 92 EAST	28,500	752	2.64	474	58	11	210	62.98	7.71	1.41	27.89	96	04V
001	04	SM	29.036	A	HALF MOON BAY, JCT. RTE. 92 EAST	27,000	859	3.18	474	157	56	172	55.13	18.30	6.53	20.05	99	04V
001	04	SM	35.334	B	VALLEMAR/ETHELDORE STREETS	13,900	1,056	7.60	710	132	63	150	67.26	12.53	6.00	14.21	98	04V
001	04	SM	40.959	A	PACIFICA, LINDA MAR BOULEVARD	28,500	770	2.70	468	161	30	111	60.72	20.86	3.94	14.48	74	07V
001	04	SM	R 43.464	B	PACIFICA, SHARP PARK ROAD INTERCHANGE	44,500	894	2.01	564	115	74	141	63.05	12.90	8.29	15.76	90	04V
001	04	SM	R46.722	B	DALY CITY, JCT. RTE. 35	40,500	802	1.98	503	171	22	107	62.71	21.28	2.69	13.33	73	04V
001	04	SM	R 46.722	A	DALY CITY, JCT. RTE. 35	64,000	1,082	1.69	610	104	10	358	56.40	9.63	0.91	33.06	156	07V
001	04	SM	R 47.802	B	SOUTH JCT. RTE. 280	71,000	440	0.62	340	51	5	44	77.19	11.62	1.10	10.09	33	04V
001	04	SM	R 48.359	A	NORTH JCT. RTE. 280	95,000	1,302	1.37	883	199	39	181	67.82	15.29	2.99	13.90	117	08V
001	04	SF	1.897	A	SAN FRANCISCO, JCT. RTE. 35	70,000	1,120	1.60	763	58	41	258	68.15	5.20	3.64	23.01	127	04V
001	04	SF	4.05	B	SAN FRANCISCO, LINCOLN WAY	70,000	1,092	1.56	748	113	11	220	68.50	10.37	0.99	20.14	114	04V
001	04	SF	7.077	B	MANZANITA, JCT. RTE. 101	64,000	1,408	2.20	1,098	149	31	130	78.00	10.60	2.20	9.20	102	01E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
001	04	MRN	0	A	MANZANITA, JCT. RTE. 101	32,500	741	2.28	570	97	16	58	76.94	13.15	2.12	7.78	51	04V
001	04	MRN	0.65	B	TAMALPAIS JUNCTION, ALMONTE BOULEVARD	32,500	484	1.49	301	58	21	104	62.18	11.97	4.41	21.43	55	04V
001	04	MRN	3.35	A	SOUTH JCT. PANORAMIC HIGHWAY	3,700	30	0.82	28	2	0	0	93.10	6.90	0.00	0.00	1	04V
001	04	MRN	17.2	B	BOLINAS ROAD	2,300	35	1.52	22	7	2	4	63.16	21.05	5.26	10.53	3	04V
001	04	MRN	26.509	A	SIR FRANCIS DRAKE BOULEVARD, SOUTH	3,000	131	4.37	100	21	0	10	76.06	16.20	0.00	7.75	9	01V
001	04	MRN	45.36	A	TOMALES/PETALUMA ROADS	1,250	26	2.10	14	4	0	8	53.70	16.70	0.00	29.60	4	01E
001	04	SON	0.19	B	VALLEY FORD ROAD	1,050	36	3.43	34	2	0	0	94.44	5.56	0.00	0.00	1	01V
001	04	SON	5.38	A	BODEGA HIGHWAY	6,400	399	6.24	353	23	6	17	88.55	5.73	1.53	4.20	21	01V
001	04	SON	20.1	B	JCT. RTE. 116 EAST	2,150	59	2.76	47	3	0	9	79.31	5.17	0.00	15.52	5	01V
001	04	SON	20.1	A	JCT. RTE. 116 EAST	2,700	157	5.80	86	44	5	22	54.90	28.00	3.10	14.00	15	01E
001	04	SON	R 33.038	A	FORT ROSS, FORT ROSS ROAD	1,700	105	6.20	45	30	0	30	42.80	28.30	0.00	28.90	15	01E
001	04	SON	48.112	B	STEWARTS POINT/SKAGGS SPRINGS ROAD	1,600	164	10.25	100	35	0	29	60.98	21.14	0.00	17.89	17	01V
001	04	SON	48.112	A	STEWARTS POINT/SKAGGS SPRINGS ROAD	1,650	164	9.93	104	34	0	26	63.19	20.83	0.00	15.97	16	01V
001	01	MEN	5.09	B	FISH ROCK ROAD	2,550	115	4.50	73	24	0	18	63.19	20.83	0.00	15.97	11	01E
001	01	MEN	5.09	A	FISH ROCK ROAD	1,950	98	5.00	50	25	6	18	50.53	25.26	6.32	17.89	11	01E
001	01	MEN	40.273	B	JCT. RTE. 128 EAST	1,100	124	11.30	50	29	10	34	40.28	23.61	8.33	27.78	18	01E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
001	01	MEN	40.273	A	JCT. RTE. 128 EAST	3,200	220	6.88	80	50	20	70	36.36	22.73	9.09	31.82	34	05E
001	01	MEN	59.803	B	JCT. RTE. 20 EAST	19,600	880	4.49	636	106	32	106	72.29	12.05	3.61	12.05	73	05E
001	01	MEN	59.803	A	JCT. RTE. 20 EAST	21,000	622	2.96	377	123	35	88	60.56	19.72	5.63	14.08	60	05E
001	01	MEN	90.874	B	JCT. RTE. 211 NORTH	800	121	15.17	36	18	13	54	29.63	14.81	11.11	44.44	23	05E
001	01	MEN	105.578	B	LEGGETT, JCT. RTE. 101	630	95	15.00	28	14	11	42	29.63	14.81	11.11	44.44	18	05E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
002	07	LA	3.645	B	LOS ANGELES, JCT. RTE. 405, SAN DIEGO FREEWAY	51,000	1,209	2.37	1,073	51	13	71	88.77	4.25	1.09	5.89	69	06V
002	07	LA	10.896	A	LOS ANGELES, HIGHLAND AVENUE	39,000	991	2.54	816	69	18	88	82.32	6.98	1.83	8.87	68	06E
002	07	LA	12.74	B	LOS ANGELES, JCT. RTE. 101, HOLLYWOOD FREEWAY	57,000	1,448	2.54	1,192	101	26	128	82.32	6.98	1.83	8.87	99	06V
002	07	LA	12.75	A	LOS ANGELES, JCT. RTE. 101, HOLLYWOOD FREEWAY	26,500	1,094	4.13	832	82	16	165	76.09	7.45	1.42	15.04	96	06V
002	07	LA	15.143	B	LOS ANGELES, JCT. RTE. 5, GOLDEN STATE FREEWAY INTERCHANGE	56,000	1,523	2.72	1,024	144	31	324	67.26	9.44	2.01	21.29	165	10E
002	07	LA	15.143	A	LOS ANGELES, JCT. RTE. 5, GOLDEN STATE FREEWAY INTERCHANGE	152,000	3,329	2.19	2,426	384	62	456	72.88	11.55	1.87	13.70	287	10E
002	07	LA	16.008	A	LOS ANGELES, SAN FERNANDO ROAD INTERCHANGE	145,000	3,176	2.19	2,315	367	59	435	72.88	11.55	1.87	13.70	274	10E
002	07	LA	R 18.814	B	LOS ANGELES, JCT. RTE. 134, VENTURA FREEWAY INTERCHANGE	147,000	3,219	2.19	2,346	372	60	441	72.88	11.55	1.87	13.70	277	10E
002	07	LA	R 18.814	A	LOS ANGELES, JCT. RTE. 134, VENTURA FREEWAY INTERCHANGE	119,000	1,309	1.10	715	231	93	271	54.59	17.66	7.07	20.68	153	10E
002	07	LA	R 22.939	B	LA CANADA-FLINTRIDGE, JCT. RTE. 210, FOOTHILL FREEWAY INTERCHANGE	108,000	1,188	1.10	649	210	84	246	54.59	17.66	7.07	20.68	139	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
002	07	LA	R 23.438	B	LA CANADA-FLINTRIDGE, FOOTHILL BOULEVARD	12,500	138	1.10	75	24	10	29	54.59	17.66	7.07	20.68	16	10E
002	07	LA	24.463	A	FLINTRIDGE, EAST JCT. RTE. 210, VIA ANGELES CREST HIGHWAY	13,500	309	2.29	269	25	7	7	87.20	8.14	2.28	2.38	15	06V
002	07	LA	38.37	A	MOUNT WILSON ROAD	290	15	5.24	7	5	1	2	45.26	31.83	8.72	14.19	2	06E
002	07	LA	64.085	B	ISLIP SADDLE, JCT. RTE. 39 SOUTH (CLOSED)	160	8	4.92	4	2	1	1	51.69	26.22	9.76	12.33	1	06E
002	07	LA	64.085	A	ISLIP SADDLE, JCT. RTE. 39 SOUTH (CLOSED)	160	8	4.92	4	2	1	1	51.69	26.22	9.76	12.33	1	06E
002	07	LA	77.39	B	BLUE RIDGE ROAD	200	9	4.61	5	2	1	1	58.13	20.62	10.79	10.46	1	06E
002	07	LA	77.39	A	BLUE RIDGE ROAD	340	15	4.29	10	2	2	1	64.56	15.01	11.83	8.60	1	06E
002	08	SBD	6.358	B	JCT. RTE. 138	7,000	279	3.98	198	26	36	19	70.99	9.41	12.87	6.73	21	06E
002	02	TRI	L0	A	JCT. RTE. 36	320	18	5.77	4	6	1	7	23.10	30.70	7.70	38.50	3	09E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
003	02	TRI	6.22	B	MORGAN HILL ROAD	670	38	5.63	12	7	4	15	30.36	19.70	10.49	39.44	7	09E
003	02	TRI	6.22	A	MORGAN HILL ROAD	660	37	5.63	9	5	3	20	24.21	13.68	8.42	53.68	8	09E
003	02	TRI	7.2	O	HAYFORK	2,050	89	4.34	29	24	2	34	32.58	26.97	2.25	38.20	15	09V
003	02	TRI	L 30.89	B	WEAVERVILLE, NORTH JCT. RTE. 299	1,450	102	7.03	13	39	2	48	12.75	38.24	1.96	47.06	21	09V
003	02	TRI	30.86	A	WEAVERVILLE, NORTH JCT. RTE. 299	3,500	187	5.34	32	30	8	117	17.18	15.95	4.29	62.58	45	09V
003	02	TRI	31.94	B	COUNTY DUMP ROAD	3,050	163	5.34	28	26	7	102	17.18	15.95	4.29	62.58	40	09V
003	02	TRI	31.94	A	COUNTY DUMP ROAD	3,150	225	7.15	39	60	17	109	17.20	26.75	7.64	48.41	47	09E
003	02	TRI	37.9	B	RUSH CREEK ROAD	1,250	112	8.96	60	17	5	30	53.57	15.18	4.46	26.79	15	09V
003	02	TRI	37.9	A	RUSH CREEK ROAD	1,100	101	9.21	35	23	7	37	34.48	22.41	6.90	36.21	17	09E
003	02	TRI	59.64	O	TRINITY CENTER STATE HIGHWAY MAINTENANCE STATION	630	58	9.21	20	13	4	21	34.48	22.41	6.90	36.21	10	09V
003	02	TRI	R 79.501	B	U. S. FOREST SERVICE ROAD	200	18	9.21	6	4	1	7	34.48	22.41	6.90	36.21	3	09E
003	02	TRI	T 85.068	O	TRINITY/SISKIYOU COUNTY LINE	190	10	5.34	1	5	0	4	12.96	50.00	1.85	35.19	2	10E
003	02	SIS	0.408	O	TRINITY/SISKIYOU COUNTY LINE	190	10	5.34	1	5	0	4	12.96	50.00	1.85	35.19	2	10E
003	02	SIS	6.955	A	GAZELLE ROAD	310	21	6.87	8	5	0	7	39.04	24.56	1.75	34.65	3	10E
003	02	SIS	8.8	B	CALLAHAN	380	24	6.33	9	6	0	8	39.04	24.56	1.75	34.65	4	10E
003	02	SIS	8.8	A	CALLAHAN	410	26	6.33	10	6	0	9	39.04	24.56	1.75	34.65	4	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
003	02	SIS	21	B	ETNA, MAIN STREET	1,350	76	5.63	27	16	1	31	35.92	21.56	1.67	40.85	13	10E
003	02	SIS	R 21	A	ETNA, MAIN STREET	1,300	64	4.92	21	12	1	30	32.79	18.56	1.60	47.06	12	10E
003	02	SIS	21.472	A	COLLIER WAY	2,250	95	4.22	28	15	1	51	29.67	15.56	1.52	53.26	20	10E
003	02	SIS	32.2	B	FORT JONES, SCOTT RIVER ROAD	2,750	122	4.42	33	20	2	67	26.96	16.43	1.78	54.83	26	10E
003	02	SIS	32.2	A	FORT JONES, SCOTT RIVER ROAD	4,450	206	4.62	50	36	4	116	24.24	17.30	2.05	56.41	46	10E
003	02	SIS	38.258	B	MOFFETT CREEK ROAD	2,850	137	4.82	29	25	3	79	21.53	18.17	2.31	57.98	31	10E
003	02	SIS	44.67	O	FOREST MOUNTAIN RANCH	2,900	140	4.82	30	25	3	81	21.53	18.17	2.31	57.98	32	10E
003	02	SIS	R 47.264	B	YREKA, MOONLIT OAKS AVENUE	13,800	741	5.37	222	146	72	301	29.98	19.73	9.70	40.59	136	10E
003	02	SIS	L 47.264	A	YREKA, MOONLIT OAKS AVENUE	10,100	586	5.80	177	164	46	199	30.29	27.93	7.85	33.93	97	10E
003	02	SIS	L 48.164	A	YREKA, OBERLIN ROAD	9,900	475	4.80	160	131	31	154	33.64	27.53	6.52	32.32	75	08E
003	02	SIS	L 49.207	A	YREKA, CENTER STREET	9,300	364	3.91	105	95	23	141	28.80	26.00	6.40	38.80	64	10E
003	02	SIS	L 49.871	B	YREKA, JCT. RTE. 263 NORTH	4,800	196	4.09	71	38	12	76	36.05	19.31	6.01	38.63	34	10E
003	02	SIS	L 49.871	A	YREKA, JCT. RTE. 263 NORTH	4,650	202	4.35	71	37	13	81	35.06	18.39	6.32	40.23	36	10E
003	02	SIS	R 47.38	A	YREKA, JCT. RTE. 5	3,450	210	6.09	55	34	3	118	26.24	16.40	1.40	55.96	46	10E
003	02	SIS	R 48.955	A	YREKA, AGER ROAD	3,200	162	5.06	45	27	3	87	27.86	16.94	1.76	53.44	35	10E
003	02	SIS	R 49.454	A	YREKA, PHILIPE LANE	3,000	121	4.03	36	21	3	62	29.48	17.48	2.11	50.93	25	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
003	02	SIS	53.22	B	MONTAGUE, GRENADA ROAD	2,800	84	2.99	26	15	2	41	31.10	18.02	2.47	48.41	17	10E
003	02	SIS	53.22	A	MONTAGUE, GRENADA ROAD	2,750	144	5.24	38	20	4	81	26.55	14.00	2.97	56.48	32	10E
003	02	SIS	54.187	B	MONTAGUE, EAST CITY LIMITS	1,000	33	3.27	9	5	1	19	26.55	14.00	2.97	56.48	7	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
004	04	CC	0	A	HERCULES, JCT. RTE. 80	41,000	2,554	6.23	927	220	99	1,308	36.29	8.61	3.87	51.22	518	00V
004	04	CC	12.667	B	JCT. RTE. 680	85,000	4,097	4.82	2,051	438	177	1,431	50.07	10.69	4.31	34.93	632	02V
004	04	CC	12.667	A	JCT. RTE. 680	81,000	4,123	5.09	2,266	508	136	1,213	54.96	12.31	3.29	29.43	565	02V
004	04	CC	R 14.668	B	CONCORD, JCT. RTE. 242	78,000	5,273	6.76	1,983	847	143	2,301	37.60	16.06	2.71	43.63	962	00V
004	04	CC	R 14.668	A	CONCORD, JCT. RTE. 242	90,000	5,634	6.26	2,258	653	151	2,572	40.08	11.59	2.68	45.65	1,049	00V
004	04	CC	R 18.83	B	PORT CHICAGO HIGHWAY EAST	144,000	7,445	5.17	3,403	1,165	649	2,228	45.71	15.65	8.72	29.93	1,090	03V
004	04	CC	R 18.83	A	PORT CHICAGO HIGHWAY EAST	130,000	7,176	5.52	2,757	997	265	3,157	38.42	13.90	3.69	43.99	1,316	00V
004	04	CC	R 20.102	A	BAILEY ROAD	128,000	5,888	4.60	2,440	680	237	2,531	41.44	11.55	4.02	42.99	1,056	00V
004	04	CC	31.13	A	JCT. RTE. 160	20,700	1,112	5.37	502	110	45	455	45.14	9.92	4.06	40.88	191	00V
004	04	CC	R 44.367	B	BYRON HIGHWAY	19,500	3,005	15.41	602	141	64	2,198	20.02	4.70	2.12	73.16	802	00V
004	04	CC	R 44.367	A	BYRON HIGHWAY	18,700	2,710	14.49	709	135	111	1,755	26.16	4.97	4.10	64.76	659	00V
004	04	CC	46.46	A	DISCOVERY BAY BOULEVARD	8,100	1,119	13.82	384	132	78	525	34.34	11.81	6.96	46.89	218	00V
004	10	SJ	0	A	CONTRA COSTA/SAN JOAQUIN COUNTY LINE	7,900	893	11.30	161	171	29	531	18.00	19.20	3.30	59.50	209	96V
004	10	SJ	5.96	B	TRACY BOULEVARD	7,900	901	11.40	153	181	29	538	17.00	20.10	3.20	59.70	212	96E
004	10	SJ	5.96	A	TRACY BOULEVARD	7,700	886	11.50	142	185	27	532	16.00	20.90	3.00	60.10	209	96V
004	10	SJ	10.49	B	INLAND DRIVE	7,900	774	9.80	84	184	39	466	10.90	23.80	5.10	60.20	186	96V
004	10	SJ	10.49	A	INLAND DRIVE	8,500	1,037	12.20	83	189	43	723	8.00	18.20	4.10	69.70	276	96V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
004	10	SJ	11.68	B	MAYBECK ROAD	8,500	986	11.60	127	202	37	619	12.90	20.50	3.80	62.80	242	96E
004	10	SJ	11.68	A	MAYBECK ROAD	8,600	937	10.90	166	213	32	527	17.70	22.70	3.40	56.20	212	96V
004	10	SJ	T 14.045	B	ROBERTS ISLAND ROAD	8,200	1,082	13.19	190	221	26	645	17.60	20.40	2.40	59.60	253	96V
004	10	SJ	T 14.045	A	ROBERTS ISLAND ROAD	10,600	1,314	12.40	260	277	30	746	19.80	21.10	2.30	56.80	296	96E
004	10	SJ	15.09	B	FRESNO AVENUE	10,700	1,220	11.40	184	311	40	684	15.10	25.50	3.30	56.10	277	96V
004	10	SJ	15.09	A	FRESNO AVENUE	13,000	1,820	14.00	235	448	64	1,074	12.90	24.60	3.50	59.00	429	96E
004	10	SJ	15.912	B	STOCKTON, SOUTH JCT. RTE. 5	24,900	4,109	16.50	436	970	148	2,556	10.60	23.60	3.60	62.20	1,008	96V
004	10	SJ	T 15.318	A	STOCKTON, SOUTH JCT. RTE. 5	14,700	1,646	11.20	150	451	87	958	9.10	27.40	5.30	58.20	390	96V
004	10	SJ	R 16.059	B	STOCKTON, NORTH JCT RTE 5	15,400	770	5.00	163	119	22	467	21.20	15.40	2.80	60.60	181	88E
004	10	SJ	R 16.059	A	STOCKTON, NORTH JCT RTE 5	78,000	7,488	9.60	2,456	1,063	427	3,542	32.80	14.20	5.70	47.30	1,469	88E
004	10	SJ	R 17.052	B	STANISLAUS STREET	78,000	7,488	9.60	2,456	1,063	427	3,542	32.80	14.20	5.70	47.30	1,469	88V
004	10	SJ	R 19.44	B	SOUTH JCT. RTE. 99	89,000	11,392	12.80	1,663	4,352	490	4,887	14.60	38.20	4.30	42.90	2,217	96V
004	10	SJ	19.75	A	SOUTH JCT. RTE. 99	8,500	485	5.70	112	92	49	233	23.00	19.00	10.00	48.00	100	01V
004	10	SJ	33.1	B	FARMINGTON	4,500	288	6.41	69	55	23	141	24.00	19.00	8.00	49.00	60	01V
004	10	SJ	33.1	A	FARMINGTON	4,550	287	6.30	68	64	23	131	23.80	22.40	8.00	45.80	57	01E
004	10	STA	R 8.885	O	STANISLAUS/CALAVERAS COUNTY LINE	5,200	233	4.49	68	44	21	100	29.00	19.00	9.00	43.00	44	01V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
004	10	CAL	R 0	O	STANISLAUS/CALAVERAS COUNTY LINE	5,200	233	4.49	68	44	21	100	29.00	19.00	9.00	43.00	44	01V
004	10	CAL	R 21.09	B	ANGELS CAMP, JCT. RTE. 49	5,900	236	4.00	47	40	28	120	20.00	17.00	12.00	51.00	51	01V
004	10	CAL	21.38	A	ANGELS CAMP, JCT. RTE. 49	5,800	232	4.00	56	67	21	88	24.00	29.00	9.00	38.00	42	01V
004	10	CAL	26.22	B	VALLECITO	5,200	338	6.50	83	104	43	108	24.50	30.80	12.70	32.00	56	01V
004	10	CAL	26.22	A	VALLECITO	6,200	409	6.59	94	119	53	143	23.00	29.00	13.00	35.00	71	01V
004	10	CAL	29.62	B	BIG TREES/TOMBELL ROADS	8,100	405	5.00	118	119	58	110	29.10	29.50	14.25	27.15	62	01E
004	10	CAL	29.62	A	BIG TREES/TOMBELL ROADS	8,750	438	5.00	145	118	53	123	33.00	27.00	12.00	28.00	66	01V
004	10	CAL	R42.62	B	MORAN ROAD EAST JUNCTION	6,600	264	4.00	50	98	34	82	19.00	37.00	13.00	31.00	44	01V
004	10	CAL	44.497	B	BIG TREES STATE PARK	3,550	249	7.00	45	102	10	92	18.00	41.00	4.00	37.00	44	01V
004	10	CAL	44.497	A	BIG TREES STATE PARK	2,800	197	7.02	26	83	10	79	13.00	42.00	5.00	40.00	37	01V
004	10	CAL	49.57	B	MEKO DRIVE	1,500	127	8.48	13	57	5	52	10.00	45.00	4.00	41.00	24	01E
004	10	CAL	R 65.865	O	CALAVERAS/ALPINE COUNTY LINE	1,300	26	2.00	9	8	3	7	33.00	32.00	10.00	25.00	4	01V
004	10	ALP	R 0	O	CALAVERAS/ALPINE COUNTY LINE	1,300	26	2.00	9	8	3	7	33.00	32.00	10.00	25.00	4	01V
004	10	ALP	31.677	B	BULLION, JCT. RTE. 89	560	23	4.10	8	5	1	9	34.60	23.60	4.60	37.20	4	96V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
005	11	SD	R .878	A	SOUTH JCT. RTE. 805	40,500	1,539	3.80	810	197	15	517	52.60	12.80	1.00	33.60	227	83V
005	11	SD	4.632	B	JCT. RTE. 75 WEST	120,000	5,040	4.20	3,236	610	151	1,043	64.20	12.10	3.00	20.70	551	78V
005	11	SD	4.632	A	JCT. RTE. 75 WEST	148,000	5,476	3.70	3,078	887	263	1,249	56.20	16.20	4.80	22.80	659	83V
005	11	SD	R 11.129	B	8TH STREET	172,000	8,600	5.00	4,360	1,376	456	2,408	50.70	16.00	5.30	28.00	1,177	85V
005	11	SD	R 12.647	B	JCT. RTE. 15 NORTH	190,000	9,500	5.00	4,817	1,520	504	2,660	50.70	16.00	5.30	28.00	1,300	85E
005	11	SD	R 12.647	A	JCT. RTE. 15 NORTH	153,000	6,273	4.10	3,532	903	289	1,549	56.30	14.40	4.60	24.70	784	85V
005	11	SD	R 14.077	B	SAN DIEGO, JCT. RTE. 75 SOUTH	160,000	6,560	4.10	3,693	945	302	1,620	56.30	14.40	4.60	24.70	819	85E
005	11	SD	R 14.077	A	SAN DIEGO, JCT. RTE. 75 SOUTH	163,000	6,520	4.00	3,984	782	254	1,500	61.10	12.00	3.90	23.00	766	78E
005	11	SD	R 15.036	B	SAN DIEGO, JCT. RTE. 94	163,000	6,194	3.80	3,785	743	242	1,425	61.10	12.00	3.90	23.00	728	78V
005	11	SD	R 15.036	A	SAN DIEGO, JCT. RTE. 94	208,000	8,320	4.00	5,799	915	241	1,364	69.70	11.00	2.90	16.40	793	87V
005	11	SD	R 16.069	B	SAN DIEGO, JCT. RTE. 163	208,000	7,696	3.70	5,095	770	285	1,547	66.20	10.00	3.70	20.10	825	78E
005	11	SD	R 16.069	A	SAN DIEGO, JCT. RTE. 163	199,000	8,159	4.10	5,124	726	228	2,081	62.80	8.90	2.80	25.50	998	85V
005	11	SD	R 20.056	B	JCT. RTE. 8/CAMINO DEL RIO	199,000	8,159	4.10	5,124	726	228	2,081	62.80	8.90	2.80	25.50	998	85V
005	11	SD	R 20.056	A	JCT. RTE. 8/CAMINO DEL RIO	199,000	6,766	3.40	4,466	677	291	1,333	66.00	10.00	4.30	19.70	721	84V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
005	11	SD	R 23.476	B	SAN DIEGO, BALBOA AVENUE	160,000	7,200	4.50	4,752	720	310	1,418	66.00	10.00	4.30	19.70	767	84E
005	11	SD	R 23.476	A	SAN DIEGO, BALBOA AVENUE	143,000	5,720	4.00	3,381	641	183	1,516	59.10	11.20	3.20	26.50	727	78V
005	11	SD	R 25.947	A	JCT. RTE. 52 EAST	176,000	7,216	4.10	4,084	758	310	2,064	56.60	10.50	4.30	28.60	970	87V
005	11	SD	R 30.682	A	SAN DIEGO, NORTH JCT. RTE. 805	148,000	5,624	3.80	2,475	422	180	2,548	44.00	7.50	3.20	45.30	1,031	00E
005	11	SD	R 42.712	B	LEUCADIA BOULEVARD	208,000	9,381	4.51	3,752	752	371	4,506	40.00	8.02	3.95	48.03	1,810	10V
005	11	SD	R 51.201	B	JCT. RTE. 78 EAST	198,000	9,524	4.81	3,733	743	371	4,676	39.20	7.80	3.90	49.10	1,867	07V
005	11	SD	R 51.201	A	JCT. RTE. 78 EAST	191,000	9,168	4.80	3,594	715	358	4,501	39.20	7.80	3.90	49.10	1,797	07E
005	11	SD	R 53.43	A	MISSION AVENUE	167,000	9,987	5.98	3,915	779	389	4,904	39.20	7.80	3.90	49.10	1,958	07E
005	11	SD	R 71.377	B	BASILONE ROAD	133,000	9,616	7.23	3,769	750	375	4,721	39.20	7.80	3.90	49.10	1,885	07E
005	12	ORA	0	A	SAN DIEGO/ORANGE COUNTY LINE	139,000	10,036	7.22	4,416	754	321	4,546	44.00	7.51	3.20	45.30	1,839	00E
005	12	ORA	6.78	B	JCT RTE 1	243,000	10,328	4.25	4,519	753	323	4,733	43.75	7.29	3.13	45.83	1,908	00E
005	12	ORA	9.604	B	SAN JUAN CAPISTRANO, JCT. RTE. 74	248,000	10,590	4.27	4,633	772	331	4,853	43.75	7.29	3.13	45.83	1,956	00E
005	12	ORA	9.604	A	SAN JUAN CAPISTRANO, JCT. RTE. 74	265,000	10,547	3.98	4,614	769	330	4,834	43.75	7.29	3.13	45.83	1,948	00E
005	12	ORA	13.776	A	CROWN VALLEY PARKWAY INTERCHANGE	272,000	9,520	3.50	4,165	694	298	4,363	43.75	7.29	3.13	45.83	1,759	00E
005	12	ORA	21.304	B	JCT. RTE. 405, SANTA ANA FREEWAY	275,000	9,268	3.37	4,055	676	290	4,248	43.75	7.29	3.13	45.83	1,712	00E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
005	12	ORA	23.12	B	IRVINE, JCT. RTE. 133	199,000	10,945	5.50	4,843	1,070	476	4,554	44.25	9.78	4.35	41.61	1,909	08E
005	12	ORA	23.12	A	IRVINE, JCT. RTE. 133	242,000	13,310	5.50	5,890	1,302	579	5,538	44.25	9.78	4.35	41.61	2,322	08V
005	12	ORA	30.263	B	TUSTIN, JCT. RTE. 55, COSTA MESA FREEWAY	277,000	15,235	5.50	6,741	1,490	663	6,339	44.25	9.78	4.35	41.61	2,657	08E
005	12	ORA	30.263	A	TUSTIN, JCT. RTE. 55, COSTA MESA FREEWAY	324,000	17,820	5.50	7,885	1,743	775	7,415	44.25	9.78	4.35	41.61	3,108	08E
005	12	ORA	34	B	SANTA ANA, JCT. RTES. 22 AND 57, GARDEN GROVE/ORANGE FREEWAYS	357,000	19,635	5.50	8,688	1,920	854	8,170	44.25	9.78	4.35	41.61	3,425	08E
005	12	ORA	34	A	SANTA ANA, JCT. RTES. 22 AND 57, GARDEN GROVE/ORANGE FREEWAYS	279,000	19,530	7.00	10,370	2,500	1,211	5,449	53.10	12.80	6.20	27.90	2,651	83E
005	12	ORA	34.942	A	ORANGE, CHAPMAN AVENUE	247,000	17,290	7.00	9,475	2,230	1,124	4,461	54.80	12.90	6.50	25.80	2,241	83E
005	12	ORA	36.258	B	KATELLA AVENUE	235,000	22,325	9.50	14,065	1,853	1,072	5,336	63.00	8.30	4.80	23.90	2,661	82V
005	12	ORA	36.258	A	KATELLA AVENUE	259,000	24,864	9.60	15,391	2,064	1,492	5,918	61.90	8.30	6.00	23.80	2,990	82E
005	12	ORA	38.915	B	LINCOLN AVENUE	272,000	25,840	9.50	15,943	2,119	1,550	6,227	61.70	8.20	6.00	24.10	3,129	82E
005	12	ORA	38.915	A	LINCOLN AVENUE	262,000	25,152	9.60	15,670	2,138	1,509	5,835	62.30	8.50	6.00	23.20	2,980	82E
005	12	ORA	42.1	B	FULLERTON, JCT. RTE. 91, RIVERSIDE/ARTESIA FREEWAYS	240,000	14,880	6.20	7,886	1,711	417	4,866	53.00	11.50	2.80	32.70	2,173	91E
005	12	ORA	42.1	A	FULLERTON, JCT. RTE. 91, RIVERSIDE/ARTESIA FREEWAYS	240,000	22,440	9.35	10,275	1,685	1,102	9,378	45.79	7.51	4.91	41.79	3,912	03E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
005	12	ORA	43.43	O	JCT. RTE. 39; BEACH BOULEVARD	168,000	15,708	9.35	7,193	1,180	771	6,564	45.79	7.51	4.91	41.79	2,738	03E
005	07	LA	0	A	ORANGE/LOS ANGELES COUNTY LINE	168,000	14,246	8.48	6,922	1,061	695	5,567	48.59	7.45	4.88	39.08	2,363	10E
005	07	LA	6.848	B	SANTA FE SPRINGS, JCT. RTE. 605, SAN GABRIEL RIVER FREEWAY	185,000	13,542	7.32	6,580	1,009	661	5,292	48.59	7.45	4.88	39.08	2,246	10E
005	07	LA	6.848	A	SANTA FE SPRINGS, JCT. RTE. 605, SAN GABRIEL RIVER FREEWAY	226,000	15,097	6.68	6,917	1,815	545	5,820	45.82	12.02	3.61	38.55	2,497	10V
005	07	LA	10.876	A	COMMERCE, GARFIELD AVENUE INTERCHANGE	216,000	17,410	8.06	7,958	1,455	883	7,114	45.71	8.36	5.07	40.86	2,997	10E
005	07	LA	13.784	B	COMMERCE, JCT. RTE. 710, LONG BEACH FREEWAY	227,000	17,593	7.75	8,042	1,471	892	7,188	45.71	8.36	5.07	40.86	3,028	10E
005	07	LA	13.784	A	COMMERCE, JCT. RTE. 710, LONG BEACH FREEWAY	252,000	14,692	5.83	5,410	1,834	522	6,927	36.82	12.48	3.55	47.15	2,825	10E
005	07	LA	16.474	B	LOS ANGELES, JCT. RTE. 60, POMONA FREEWAY	259,000	14,841	5.73	5,464	1,852	527	6,998	36.82	12.48	3.55	47.15	2,853	10V
005	07	LA	16.474	A	LOS ANGELES, JCT. RTE. 60, POMONA FREEWAY	234,000	14,087	6.02	4,697	1,593	471	7,327	33.34	11.31	3.34	52.01	2,908	10E
005	07	LA	18.452	B	LOS ANGELES, JCT. RTE. 10, SAN BERNARDINO FREEWAY	229,000	13,946	6.09	4,163	1,414	437	7,932	29.85	10.14	3.13	56.88	3,077	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
005	07	LA	18.452	A	LOS ANGELES, JCT. RTE. 10, SAN BERNARDINO FREEWAY	235,000	13,254	5.64	3,495	1,189	387	8,183	26.37	8.97	2.92	61.74	3,112	10E
005	07	LA	20.444	B	LOS ANGELES, JCT. RTE. 110, PASADENA FREEWAY	224,000	13,126	5.86	3,461	1,177	383	8,104	26.37	8.97	2.92	61.74	3,082	10E
005	07	LA	20.444	A	LOS ANGELES, JCT. RTE. 110, PASADENA FREEWAY	286,000	13,127	4.59	3,462	1,177	383	8,105	26.37	8.97	2.92	61.74	3,082	10E
005	07	LA	22.548	B	LOS ANGELES, JCT. RTE. 2, GLENDALE FREEWAY	281,000	13,123	4.67	3,461	1,177	383	8,102	26.37	8.97	2.92	61.74	3,081	10E
005	07	LA	22.548	A	LOS ANGELES, JCT. RTE. 2, GLENDALE FREEWAY	239,000	16,037	6.71	4,229	1,439	468	9,901	26.37	8.97	2.92	61.74	3,765	10E
005	07	LA	25.781	B	LOS ANGELES, COLORADO BOULEVARD EXTENSION INTERCHANGE	254,000	16,129	6.35	4,253	1,447	471	9,958	26.37	8.97	2.92	61.74	3,787	10V
005	07	LA	27.08	B	LOS ANGELES, JCT. RTE. 134, VENTURA FREEWAY	263,000	16,201	6.16	4,272	1,453	473	10,002	26.37	8.97	2.92	61.74	3,803	10E
005	07	LA	27.08	A	LOS ANGELES, JCT. RTE. 134, VENTURA FREEWAY	240,000	16,560	6.90	4,536	1,820	790	9,414	27.39	10.99	4.77	56.85	3,690	10E
005	07	LA	36.358	B	LOS ANGELES, JCT. RTE. 170, HOLLYWOOD FREEWAY	184,000	14,922	8.11	4,048	1,522	677	8,673	27.13	10.20	4.54	58.12	3,373	10E
005	07	LA	36.358	A	LOS ANGELES, JCT. RTE. 170, HOLLYWOOD FREEWAY	291,000	20,574	7.07	5,530	1,936	887	12,219	26.88	9.41	4.31	59.39	4,718	10E
005	07	LA	39.361	B	LOS ANGELES, JCT. RTE. 118, RONALD REAGAN FREEWAY	276,000	20,562	7.45	5,476	1,775	839	12,473	26.63	8.63	4.08	60.66	4,781	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
005	07	LA	41.597	B	LOS ANGELES, JCT. RTE. 405, SAN DIEGO FREEWAY	137,000	11,220	8.19	3,043	890	300	6,988	27.12	7.93	2.67	62.28	2,643	10V
005	07	LA	41.597	A	LOS ANGELES, JCT. RTE. 405, SAN DIEGO FREEWAY	275,000	16,720	6.08	5,573	1,493	527	9,127	33.33	8.93	3.15	54.59	3,559	10E
005	07	LA	R 44.014	A	LOS ANGELES, JCT. RTE. 210, FOOTHILL FREEWAY	278,000	21,795	7.84	6,432	1,953	721	12,689	29.51	8.96	3.31	58.22	4,888	10E
005	07	LA	R 45.584	A	JCT. RTE. 14, ANTELOPE VALLEY FREEWAY	197,000	18,617	9.45	4,531	495	205	13,386	24.34	2.66	1.10	71.90	4,852	10E
005	07	LA	R 53.565	B	SANTA CLARITA, SOUTH JCT. RTE. 126, MAGIC MOUNTAIN PARKWAY INTERCHANGE	147,000	18,257	12.42	4,444	486	201	13,127	24.34	2.66	1.10	71.90	4,759	10E
005	07	LA	R 55.48	B	SANTA CLARITA, NORTH JCT. RTE. 126, HENRY MAYO DRIVE INTERCHANGE	122,000	17,897	14.67	4,356	476	197	12,868	24.34	2.66	1.10	71.90	4,665	10E
005	07	LA	R 55.48	A	SANTA CLARITA, NORTH JCT. RTE. 126, HENRY MAYO DRIVE INTERCHANGE	108,000	17,053	15.79	4,151	454	188	12,261	24.34	2.66	1.10	71.90	4,445	10E
005	07	LA	R 81.487	B	SOUTH JCT. RTE. 138, ROUTE 138 FREEWAY INTERCHANGE	72,000	16,726	23.23	4,031	500	236	11,959	24.10	2.99	1.41	71.50	4,348	10E
005	07	LA	R 82.103	A	NORTH JCT. RTE. 138, ROUTE 138 FREEWAY INTERCHANGE	73,000	16,067	22.01	3,787	596	333	11,353	23.57	3.71	2.07	70.66	4,153	10E
005	07	LA	R 88.605	O	LOS ANGELES/KERN COUNTY LINE	70,000	15,904	22.72	3,726	619	356	11,201	23.43	3.89	2.24	70.43	4,104	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
005	06	KER	R 0	O	LOS ANGELES/KERN COUNTY LINE	70,000	15,904	22.72	3,726	619	356	11,201	23.43	3.89	2.24	70.43	4,104	10E
005	06	KER	R 15.858	B	JCT. RTE. 99 NORTH	138,000	33,368	24.18	6,697	1,475	931	24,265	20.07	4.42	2.79	72.72	8,878	08V
005	06	KER	R 15.858	A	JCT. RTE. 99 NORTH	57,000	13,783	24.18	3,001	597	396	9,790	21.77	4.33	2.87	71.03	3,596	08E
005	06	KER	19.612	A	JCT. RTE. 166	28,500	6,891	24.18	1,500	298	198	4,895	21.77	4.33	2.87	71.03	1,798	08E
005	06	KER	38.793	B	JCT. RTE. 119	30,000	6,531	21.77	1,422	283	187	4,639	21.77	4.33	2.87	71.03	1,704	07E
005	06	KER	38.793	A	JCT. RTE. 119	30,500	6,640	21.77	1,446	288	191	4,716	21.77	4.33	2.87	71.03	1,732	07E
005	06	KER	41.193	B	JCT. RTE. 43	30,500	7,469	24.49	1,626	323	214	5,305	21.77	4.33	2.87	71.03	1,948	07E
005	06	KER	41.193	A	JCT. RTE. 43	31,000	6,749	21.77	1,469	292	194	4,794	21.77	4.33	2.87	71.03	1,761	07E
005	06	KER	52.145	B	JCT. RTE. 58	33,000	10,002	30.31	1,856	258	155	7,734	18.56	2.58	1.55	77.32	2,780	06E
005	06	KER	52.145	A	JCT. RTE. 58	36,000	10,962	30.45	1,918	329	219	8,496	17.50	3.00	2.00	77.50	3,061	05E
005	06	KER	73.017	B	JCT. RTE. 46	36,500	11,487	31.47	1,608	689	345	8,845	14.00	6.00	3.00	77.00	3,222	05E
005	06	KER	73.017	A	JCT. RTE. 46	30,500	9,723	31.88	1,361	583	292	7,487	14.00	6.00	3.00	77.00	2,727	05E
005	06	KIN	16.595	B	JCT. RTE. 41	31,500	9,608	30.50	1,441	576	288	7,302	15.00	6.00	3.00	76.00	2,665	04E
005	06	KIN	16.595	A	JCT. RTE. 41	31,500	9,450	30.00	1,418	567	284	7,182	15.00	6.00	3.00	76.00	2,621	04E
005	06	FRE	14.873	B	JCT. RTE. 198	34,500	10,674	30.94	1,815	374	267	8,219	17.00	3.50	2.50	77.00	2,973	05E
005	06	FRE	14.873	A	JCT. RTE. 198	37,500	11,081	29.55	1,995	332	222	8,532	18.00	3.00	2.00	77.00	3,077	05E
005	06	FRE	17.964	B	JCT. RTE. 33 SOUTH, JCT. RTE. 145 NORTH	37,500	11,081	29.55	1,884	332	222	8,643	17.00	3.00	2.00	78.00	3,111	05E
005	06	FRE	17.964	A	JCT. RTE. 33 SOUTH, JCT. RTE. 145 NORTH	37,500	11,085	29.56	1,774	388	277	8,646	16.00	3.50	2.50	78.00	3,121	05E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
005	10	MER	6.28	B	JCT. RTE. 165 NORTH	35,000	9,982	28.52	1,943	343	211	7,484	19.47	3.44	2.11	74.97	2,713	04E
005	10	MER	6.28	A	JCT. RTE. 165 NORTH	31,000	8,841	28.52	1,721	304	187	6,628	19.47	3.44	2.11	74.97	2,402	04E
005	10	MER	17.578	A	JCT. RTE. 152	31,000	7,741	24.97	1,059	179	92	6,411	13.68	2.31	1.19	82.82	2,279	07V
005	10	MER	21.839	A	JCT. RTE. 33	34,000	11,370	33.44	1,925	227	113	9,103	16.93	2.00	0.99	80.06	3,245	07E
005	10	MER	32.391	A	JCT. RTE. 140 EAST	35,000	8,680	24.80	1,429	181	102	6,968	16.46	2.09	1.17	80.28	2,486	04E
005	10	SJ	0.68	B	JCT. RTE. 580 WEST	37,400	9,275	24.80	1,530	195	111	7,439	16.50	2.10	1.20	80.20	2,654	04E
005	10	SJ	0.68	A	JCT. RTE. 580 WEST	37,400	9,275	24.80	1,530	195	111	7,439	16.50	2.10	1.20	80.20	2,654	04E
005	10	SJ	3.444	A	JCT. RTE. 132	22,800	5,654	24.80	933	119	68	4,535	16.50	2.10	1.20	80.20	1,618	04E
005	10	SJ	6.467	A	JCT. RTE. 33 SOUTH	22,000	7,625	34.66	1,233	246	124	6,021	16.17	3.23	1.63	78.97	2,161	07E
005	10	SJ	R 11.801	B	OLD ROUTE 50; 11TH STREET	22,000	7,249	32.95	1,428	188	94	5,538	19.70	2.60	1.30	76.40	1,992	04E
005	10	SJ	R 12.623	A	JCT. RTE. 205 WEST	152,000	40,128	26.40	4,254	2,488	1,284	32,102	10.60	6.20	3.20	80.00	*****	96E
005	10	SJ	R 14.834	A	JCT. RTE. 120 EAST	100,000	25,900	25.90	2,823	1,632	777	20,668	10.90	6.30	3.00	79.80	7,494	96E
005	10	SJ	R 20.951	B	FRENCH CAMP OVERCROSSING	96,000	24,480	25.50	2,717	1,567	710	19,486	11.10	6.40	2.90	79.60	7,066	96E
005	10	SJ	R 20.951	A	FRENCH CAMP OVERCROSSING	100,000	25,000	25.00	2,850	1,625	700	19,825	11.40	6.50	2.80	79.30	7,192	96E
005	10	SJ	25.365	B	STOCKTON, JCT. RTE. 4	131,000	32,095	24.50	3,755	2,118	867	25,355	11.70	6.60	2.70	79.00	9,201	96E
005	10	SJ	25.365	A	STOCKTON, JCT. RTE. 4	140,000	33,600	24.00	4,032	2,218	840	26,510	12.00	6.60	2.50	78.90	9,615	96E
005	10	SJ	26.185	A	STOCKTON, JCT. RTE. 4	140,000	32,900	23.50	4,047	2,204	790	25,859	12.30	6.70	2.40	78.60	9,382	96E
005	10	SJ	29.99	A	STOCKTON, MARCH LANE	119,000	27,370	23.00	3,449	1,861	630	21,431	12.60	6.80	2.30	78.30	7,778	96E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
005	10	SJ	32.664	A	STOCKTON, HAMMER LANE	96,000	21,696	22.60	2,777	1,497	477	16,945	12.80	6.90	2.20	78.10	6,151	96E
005	10	SJ	39.573	B	JCT. RTE. 12	77,000	12,620	16.39	2,933	461	207	9,020	23.24	3.65	1.64	71.47	3,287	04E
005	10	SJ	39.573	A	JCT. RTE. 12	53,000	10,839	20.45	2,779	391	176	7,492	25.64	3.61	1.62	69.12	2,744	07V
005	10	SJ	47.602	A	WALNUT GROVE ROAD	53,000	12,137	22.90	3,008	436	201	8,492	24.78	3.59	1.66	69.97	3,105	06V
005	03	SAC	0.018	A	SAN JOAQUIN/SACRAMENTO COUNTY LINE	54,000	13,144	24.34	3,055	480	216	9,394	23.24	3.65	1.64	71.47	3,424	04E
005	03	SAC	16.147	A	SACRAMENTO, POCKET/MEADOWVIEW ROADS	101,000	13,342	13.21	3,101	487	219	9,536	23.24	3.65	1.64	71.47	3,475	04E
005	03	SAC	22.565	B	SACRAMENTO, JCT. RTE. 50	143,000	13,728	9.60	3,350	810	329	9,239	24.40	5.90	2.40	67.30	3,428	87E
005	03	SAC	23.799	A	SACRAMENTO, I STREET	186,000	17,856	9.60	4,160	1,071	482	12,142	23.30	6.00	2.70	68.00	4,504	87E
005	03	SAC	26.722	B	SACRAMENTO, JCT. RTE. 80	159,000	15,264	9.60	3,724	901	366	10,273	24.40	5.90	2.40	67.30	3,811	86V
005	03	SAC	26.722	A	SACRAMENTO, JCT. RTE. 80	152,000	12,282	8.08	3,338	640	346	7,958	27.18	5.21	2.82	64.79	2,972	07E
005	03	SAC	29.907	B	SACRAMENTO, JCT. RTE. 99 NORTH	108,000	12,474	11.55	3,390	650	352	8,082	27.18	5.21	2.82	64.79	3,018	07E
005	03	SAC	29.907	A	SACRAMENTO, JCT. RTE. 99 NORTH	75,000	8,513	11.35	2,258	430	236	5,590	26.52	5.05	2.77	65.67	2,082	08V
005	03	SAC	32.734	A	SACRAMENTO, AIRPORT BOULEVARD INTERCHANGE	50,000	7,935	15.87	2,046	417	238	5,233	25.78	5.26	3.00	65.95	1,950	09V
005	03	YOL	R 6.51	B	WOODLAND, EAST MAIN STREET	44,000	9,143	20.78	2,445	479	254	5,965	26.74	5.24	2.78	65.24	2,225	07E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
005	03	YOL	R 6.51	A	WOODLAND, EAST MAIN STREET	32,000	6,650	20.78	1,778	348	185	4,338	26.74	5.24	2.78	65.24	1,618	07E
005	03	YOL	R 7.086	A	WOODLAND, JCT. RTE. 113	34,000	7,905	23.25	704	885	568	5,749	8.90	11.20	7.19	72.72	2,173	08E
005	03	YOL	R 22.61	B	JCT. RTE. 505 SOUTH	22,200	5,939	26.75	359	595	436	4,549	6.05	10.02	7.34	76.59	1,701	10E
005	03	YOL	R 22.61	A	JCT. RTE. 505 SOUTH	33,000	9,445	28.62	2,032	605	413	6,395	21.51	6.41	4.37	67.71	2,394	07V
005	03	COL	R 17.975	B	WILLIAMS, E STREET	28,500	6,814	23.91	552	602	405	5,255	8.10	8.83	5.94	77.12	1,947	10V
005	03	COL	R 18.722	B	JCT. RTE. 20	28,000	8,142	29.08	1,366	512	379	5,883	16.78	6.29	4.66	72.26	2,180	06E
005	03	COL	R 18.722	A	JCT. RTE. 20	25,500	7,288	28.58	1,696	155	72	5,365	23.27	2.12	0.99	73.62	1,935	07E
005	03	GLE	R 9.872	B	WILLOWS, JCT. RTE. 162	25,500	7,104	27.86	1,792	144	65	5,103	25.23	2.03	0.91	71.83	1,846	10V
005	03	GLE	R 9.872	A	WILLOWS, JCT. RTE. 162	26,500	7,574	28.58	1,762	161	75	5,575	23.27	2.13	0.99	73.61	2,011	07V
005	03	GLE	R 25.529	B	JCT. RTE. 32 EAST	25,500	7,288	28.58	1,696	155	72	5,365	23.27	2.12	0.99	73.62	1,935	07E
005	03	GLE	R 25.529	A	JCT. RTE. 32 EAST	24,600	6,231	25.33	391	307	160	5,374	6.27	4.92	2.57	86.25	1,919	06E
005	03	GLE	R 28.821	O	GLENN/TEHAMA COUNTY LINE	24,500	6,088	24.85	382	300	156	5,251	6.27	4.92	2.57	86.25	1,875	10E
005	02	TEH	R 0	O	GLENN/TEHAMA COUNTY LINE	24,500	6,088	24.85	382	300	156	5,251	6.27	4.92	2.57	86.25	1,875	10E
005	02	TEH	R 5.769	A	LIBERAL AVENUE	24,500	5,985	24.43	401	341	232	5,011	6.70	5.69	3.88	83.73	1,808	10E
005	02	TEH	R 7.486	A	SOUTH AVENUE	23,300	5,585	23.97	352	208	107	4,918	6.31	3.73	1.91	88.05	1,744	10E
005	02	TEH	R 8.975	A	CORNING ROAD	23,900	5,370	22.47	277	249	128	4,716	5.15	4.64	2.38	87.83	1,678	10E
005	02	TEH	R 10.969	A	FINNELL AVENUE	24,200	5,075	20.97	331	194	103	4,447	6.52	3.83	2.02	87.63	1,579	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
005	02	TEH	R 13.965	A	GYLE ROAD	23,100	5,052	21.87	336	186	96	4,434	6.65	3.68	1.91	87.76	1,573	10E
005	02	TEH	R 19.781	A	FLORES AVENUE	23,800	5,196	21.83	345	191	99	4,560	6.64	3.68	1.91	87.76	1,617	10E
005	02	TEH	R 24.871	A	RED BLUFF, SOUTH MAIN STREET	27,000	6,010	22.26	487	214	155	5,153	8.11	3.56	2.58	85.74	1,837	10E
005	02	TEH	R 24.942	A	RED BLUFF, DIAMOND AVENUE INTERCHANGE	30,000	6,099	20.33	506	180	157	5,256	8.30	2.95	2.57	86.18	1,871	10E
005	02	TEH	R 26.525	A	RED BLUFF, JCT. RTE. 36	38,000	7,224	19.01	601	211	160	6,252	8.32	2.92	2.22	86.54	2,221	10E
005	02	TEH	R 28.377	A	NORTH RED BLUFF	39,500	7,355	18.62	630	221	134	6,371	8.56	3.00	1.82	86.62	2,260	10E
005	02	TEH	31.043	A	WILCOX ROAD	39,000	7,359	18.87	631	221	122	6,385	8.58	3.00	1.66	86.76	2,263	10E
005	02	TEH	32.236	A	JELLYS FERRY ROAD	37,500	7,324	19.53	634	193	103	6,394	8.66	2.63	1.41	87.30	2,261	10E
005	02	TEH	36.371	A	HOOKER CREEK ROAD	37,000	7,063	19.09	619	178	81	6,186	8.76	2.52	1.14	87.58	2,184	10E
005	02	TEH	38.716	B	SUNSET HILLS DRIVE	37,000	7,060	19.08	1,641	309	154	4,955	23.25	4.38	2.18	70.19	1,818	10V
005	02	TEH	42.115	O	TEHAMA/SHASTA COUNTY LINE	43,000	7,237	16.83	659	190	82	6,306	9.11	2.62	1.13	87.14	2,228	10E
005	02	SHA	0	O	TEHAMA/SHASTA COUNTY LINE	43,000	7,237	16.83	659	190	82	6,306	9.11	2.62	1.13	87.14	2,228	10E
005	02	SHA	0.909	A	FOURTH STREET	45,500	7,230	15.89	625	273	244	6,088	8.64	3.78	3.38	84.20	2,183	10E
005	02	SHA	1.907	A	NORTH COTTONWOOD	51,000	7,303	14.32	617	412	221	6,053	8.45	5.64	3.02	82.89	2,180	10E
005	02	SHA	R 3.83	A	JCT. RTE. 273 NORTH	40,500	6,634	16.38	561	374	200	5,498	8.46	5.64	3.02	82.88	1,980	10E
005	02	SHA	R 4.289	A	ANDERSON, DESCHUTES ROAD	50,000	6,320	12.64	507	356	191	5,266	8.02	5.63	3.03	83.32	1,895	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
005	02	SHA	R 5.294	A	ANDERSON, BALLS FERRY ROAD	41,500	5,134	12.37	432	360	145	4,196	8.42	7.02	2.83	81.73	1,517	10E
005	02	SHA	R 5.64	A	ANDERSON, NORTH STREET	49,500	6,173	12.47	598	427	156	4,993	9.68	6.91	2.52	80.89	1,806	10E
005	02	SHA	R 6.743	A	RIVERSIDE AVENUE	49,500	6,282	12.69	498	452	156	5,176	7.93	7.19	2.48	82.40	1,868	10E
005	02	SHA	R 9.772	A	KNIGHTON ROAD	51,000	6,487	12.72	514	466	162	5,345	7.92	7.19	2.49	82.40	1,929	10E
005	02	SHA	R 12.152	A	CHURN CREEK ROAD	52,000	6,536	12.57	563	393	144	5,435	8.62	6.01	2.21	83.16	1,952	10E
005	02	SHA	R 15.448	A	REDDING, JCT. RTE. 44	52,000	6,838	13.15	733	599	285	5,221	10.72	8.76	4.17	76.35	1,924	10E
005	02	SHA	R 17.322	A	REDDING, JCT. RTE. 299	39,000	6,533	16.75	555	340	127	5,511	8.50	5.21	1.94	84.35	1,971	10E
005	02	SHA	R 18.068	A	REDDING, TWINVIEW BOULEVARD	33,000	6,069	18.39	513	466	214	4,875	8.46	7.68	3.53	80.33	1,774	10E
005	02	SHA	R 18.481	A	REDDING, JCT. RTE. 273	41,000	5,871	14.32	493	268	101	5,008	8.40	4.56	1.72	85.30	1,785	10V
005	02	SHA	R 19.402	A	REDDING, OASIS ROAD	33,500	5,651	16.87	531	464	263	4,393	9.40	8.21	4.66	77.74	1,616	10E
005	02	SHA	R 20.995	A	PINE GROVE	29,500	5,505	18.66	401	452	257	4,395	7.29	8.21	4.67	79.83	1,610	10E
005	02	SHA	R 22.144	A	JCT. RTE. 151 WEST	22,100	5,406	24.46	445	175	100	4,687	8.23	3.23	1.85	86.70	1,663	10E
005	02	SHA	R 24.082	A	MOUNTAIN GATE	20,500	5,209	25.41	423	144	58	4,584	8.12	2.76	1.11	88.00	1,618	10V
005	02	SHA	R 26.035	A	FAWNDALE	19,700	5,209	26.44	432	218	97	4,462	8.30	4.18	1.87	85.65	1,589	10E
005	02	SHA	R 27.632	A	BRIDGE BAY	19,300	5,207	26.98	417	208	104	4,478	8.00	4.00	2.00	86.00	1,594	10E
005	02	SHA	R 29.315	A	TURNTABLE BAY ROAD	19,200	5,205	27.11	416	208	104	4,476	8.00	4.00	2.00	86.00	1,593	10E
005	02	SHA	R 32.159	A	O' BRIEN	18,400	5,205	28.29	416	208	104	4,476	8.00	4.00	2.00	86.00	1,593	10E
005	02	SHA	R 36.825	A	GILMAN ROAD	17,900	5,205	29.08	416	208	104	4,476	8.00	4.00	2.00	86.00	1,593	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
005	02	SHA	R 41.053	A	ANTLER	17,400	5,177	29.75	414	207	104	4,452	8.00	4.00	2.00	86.00	1,585	10E
005	02	SHA	R 42.316	A	LAKEHEAD	17,200	5,194	30.20	416	208	104	4,467	8.00	4.00	2.00	86.00	1,590	10E
005	02	SHA	52.9	A	GIBSON	17,000	5,195	30.56	390	208	104	4,494	7.50	4.00	2.00	86.50	1,599	10E
005	02	SHA	57.41	A	SIMS ROAD	17,100	5,195	30.38	403	208	104	4,481	7.75	4.00	2.00	86.25	1,594	10E
005	02	SHA	59.35	A	FLUME CREEK	17,100	5,195	30.38	403	208	104	4,481	7.75	4.00	2.00	86.25	1,594	10E
005	02	SHA	60.508	A	CONANT ROAD	17,100	5,195	30.38	403	208	104	4,481	7.75	4.00	2.00	86.25	1,594	09E
005	02	SHA	61.745	A	SWEETBRIER AVENUE	17,100	5,195	30.38	400	208	104	4,481	7.70	4.00	2.00	86.25	1,594	10E
005	02	SHA	63.583	A	CASTELLA	17,300	5,202	30.07	416	208	104	4,474	8.00	4.00	2.00	86.00	1,593	10E
005	02	SHA	65.413	A	SODA CREEK ROAD	17,500	5,210	29.77	417	208	104	4,481	8.00	4.00	2.00	86.00	1,595	10E
005	02	SHA	66.842	A	CASTLE CRAGS DRIVE	18,000	5,215	28.97	428	209	104	4,474	8.20	4.00	2.00	85.80	1,593	10E
005	02	SHA	67.019	O	SHASTA/SISKIYOU COUNTY LINE	18,000	5,215	28.97	428	209	104	4,474	8.20	4.00	2.00	85.80	1,593	10E
005	02	SIS	0	O	SHASTA/SISKIYOU COUNTY LINE	18,000	5,215	28.97	428	209	104	4,474	8.20	4.00	2.00	85.80	1,593	10E
005	02	SIS	0.685	A	SOUTH DUNSMUIR	17,200	5,189	30.17	431	208	104	4,447	8.30	4.00	2.00	85.70	1,584	10E
005	02	SIS	2.514	A	CENTRAL DUNSMUIR	18,400	5,191	28.21	457	208	104	4,423	8.80	4.00	2.00	85.20	1,576	10E
005	02	SIS	3.841	A	DUNSMUIR, DUNSMUIR AVENUE	19,000	5,191	27.32	453	207	103	4,428	8.73	3.98	1.99	85.30	1,578	10E
005	02	SIS	5.899	A	MOTT AVENUE	19,500	5,191	26.62	457	208	104	4,423	8.80	4.00	2.00	85.20	1,576	10E
005	02	SIS	R 8.475	A	JCT. RTE. 89 EAST	19,400	5,100	26.29	408	204	102	4,386	8.00	4.00	2.00	86.00	1,561	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
005	02	SIS	R 10.485	A	MOUNT SHASTA, LAKE STREET	19,800	5,057	25.54	406	184	61	4,406	8.03	3.64	1.21	87.13	1,560	10V
005	02	SIS	R 12.062	A	NORTH MOUNT SHASTA	23,200	5,113	22.04	409	205	102	4,397	8.00	4.00	2.00	86.00	1,565	10E
005	02	SIS	R 13.184	A	ABRAMS LAKE ROAD	22,200	5,051	22.75	404	202	101	4,344	8.00	4.00	2.00	86.00	1,546	10E
005	02	SIS	R 15.339	A	DEETZ ROAD	22,500	5,101	22.67	408	204	102	4,387	8.00	4.00	2.00	86.00	1,562	10E
005	02	SIS	R 17.441	A	SOUTH WEED	21,700	5,080	23.41	457	203	102	4,318	9.00	4.00	2.00	85.00	1,539	10E
005	02	SIS	R 19.07	A	JCT. RTE. 97 NORTH	14,000	3,942	28.16	315	158	79	3,390	8.00	4.00	2.00	86.00	1,207	10E
005	02	SIS	R 19.856	A	JCT. RTE. 265	15,300	3,966	25.92	317	198	119	3,331	8.00	5.00	3.00	84.00	1,196	10E
005	02	SIS	R 22.999	A	EDGEWOOD	14,500	3,892	26.84	311	195	117	3,269	8.00	5.00	3.00	84.00	1,174	10E
005	02	SIS	R 25.345	A	WEED AIRPORT NB OFF	14,600	3,894	26.67	312	195	117	3,271	8.00	5.00	3.00	84.00	1,175	10E
005	02	SIS	R 31.178	A	LOUIE ROAD	14,700	3,896	26.50	312	195	117	3,273	8.00	5.00	3.00	84.00	1,175	10E
005	02	SIS	R 38.207	A	GRENADA	16,200	3,967	24.49	317	179	129	3,342	8.00	4.50	3.25	84.25	1,200	10E
005	02	SIS	R 42.508	A	KILLGORE HILLS ROAD	16,600	4,001	24.10	320	180	130	3,371	8.00	4.50	3.25	84.25	1,210	10E
005	02	SIS	R 45.62	A	SOUTH YREKA	15,800	3,959	25.06	325	178	129	3,328	8.20	4.50	3.25	84.05	1,195	10E
005	02	SIS	R 47.563	A	YREKA, MINER STREET	15,000	3,851	25.67	316	173	125	3,237	8.20	4.50	3.25	84.05	1,162	10E
005	02	SIS	R 48.239	A	YREKA, JCT. RTE. 3	14,800	3,841	25.95	307	173	123	3,238	8.00	4.50	3.20	84.30	1,162	10E
005	02	SIS	R 58.326	A	JCT. RTE. 96 WEST	13,800	3,665	26.56	293	165	117	3,090	8.00	4.50	3.20	84.30	1,109	10E
005	02	SIS	R 61.553	A	HENLEY WAY	14,000	3,821	27.29	306	164	118	3,233	8.00	4.30	3.10	84.60	1,159	10E
005	02	SIS	R 62.921	A	DITCH CREEK ROAD	14,000	3,821	27.29	191	153	76	3,401	5.00	4.00	2.00	89.00	1,205	10E
005	02	SIS	R 65.517	A	BAILEY HILL ROAD RT	13,400	3,806	28.40	181	118	85	3,422	4.76	3.10	2.23	89.91	1,210	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
005	02	SIS	R 68.328	A	HILT ROAD	14,800	3,805	25.71	181	118	85	3,421	4.76	3.10	2.23	89.91	1,210	10V
005	02	SIS	R 69.293	B	OREGON STATE LINE	14,800	3,805	25.71	181	118	85	3,421	4.76	3.10	2.23	89.91	1,210	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
006	09	INY	0	A	JCT. RTE. 395	3,550	426	12.00	55	17	0	354	12.90	4.00	0.00	83.10	126	96V
006	09	INY	R 3.952	A	SILVER CANYON ROAD	1,900	437	23.00	83	64	54	236	18.99	14.65	12.36	54.00	98	08V
006	09	MNO	25.715	B	BENTON STATION, JCT. RTE. 120 WEST	1,000	230	23.00	53	12	2	163	23.00	5.00	1.00	71.00	59	92E
006	09	MNO	25.715	A	BENTON STATION, JCT. RTE. 120 WEST	960	230	24.00	55	16	2	156	24.00	7.00	1.00	68.00	58	92E
006	09	MNO	32.29	B	NEVADA STATE LINE	850	196	23.00	53	12	4	127	27.00	6.00	2.00	65.00	47	90E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
007	11	IMP	1.188	B	CALEXICO, JCT RTE 98	6,959	1,719	24.70	258	292	34	1,135	15.01	16.99	1.98	66.03	432	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
008	11	SD	T .407	A	SAN DIEGO, SUNSET CLIFFS BOULEVARD	10,500	105	1.00	86	8	3	8	82.30	7.40	2.90	7.40	7	78E
008	11	SD	L 2.379	B	JCT RTE 5 LT LANES	102,000	1,224	1.20	1,038	87	9	91	84.80	7.10	0.70	7.40	77	78V
008	11	SD	L 2.379	A	JCT RTE 5 LT LANES	132,000	3,696	2.80	2,473	532	159	532	66.90	14.40	4.30	14.40	342	83V
008	11	SD	2.41	B	SAN DIEGO, JCT. RTE. 163	200,000	5,400	2.70	4,180	583	135	502	77.40	10.80	2.50	9.30	393	83E
008	11	SD	2.41	A	SAN DIEGO, JCT. RTE. 163	204,000	5,712	2.80	4,461	571	137	543	78.10	10.00	2.40	9.50	416	83E
008	11	SD	4.378	B	SAN DIEGO, JCT. RTE. 805	193,000	6,176	3.20	4,638	611	210	716	75.10	9.90	3.40	11.60	496	83E
008	11	SD	5.638	B	JCT. RTE. 15	240,000	7,200	3.00	4,212	914	302	1,771	58.50	12.70	4.20	24.60	887	83V
008	11	SD	5.638	A	JCT. RTE. 15	213,000	7,455	3.50	4,771	857	335	1,491	64.00	11.50	4.50	20.00	809	84E
008	11	SD	10.57	B	FLETCHER PARKWAY	189,000	6,993	3.70	4,182	888	245	1,678	59.80	12.70	3.50	24.00	843	84V
008	11	SD	10.57	A	FLETCHER PARKWAY	173,000	7,612	4.40	4,301	1,172	388	1,751	56.50	15.40	5.10	23.00	919	78V
008	11	SD	15.8	B	EL CAJON, JCT. RTE. 67 NORTH	165,000	7,755	4.70	4,180	1,016	357	2,202	53.90	13.10	4.60	28.40	1,052	78V
008	11	SD	15.8	A	EL CAJON, JCT. RTE. 67 NORTH	131,000	3,799	2.90	2,105	429	133	1,132	55.40	11.30	3.50	29.80	523	78V
008	11	SD	R 18.727	A	GREENFIELD DRIVE	77,000	5,313	6.90	2,800	414	128	1,971	52.70	7.80	2.40	37.10	835	86V
008	11	SD	R 37.831	B	JCT. RTE. 79 NORTH, JAPATUL VALLEY ROAD	25,000	3,000	12.00	1,179	177	90	1,554	39.30	5.90	3.00	51.80	607	86E
008	11	SD	R 37.831	A	JCT. RTE. 79 NORTH, JAPATUL VALLEY ROAD	19,600	2,666	13.60	866	208	77	1,514	32.50	7.80	2.90	56.80	583	00E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
008	11	SD	R 51.98	B	CAMERON ROAD	15,500	1,969	12.70	826	93	40	1,010	41.95	4.72	2.03	51.30	392	10V
008	11	SD	R 65.904	B	JCT. RTE. 94 SOUTH	14,200	1,972	13.89	706	91	45	1,131	35.78	4.59	2.29	57.34	430	05V
008	11	SD	R 65.904	A	JCT. RTE. 94 SOUTH	13,700	1,940	14.16	694	89	44	1,112	35.78	4.59	2.29	57.34	423	05V
008	11	IMP	R 10.01	B	JCT. RTE. 98	13,500	1,877	13.90	672	86	43	1,076	35.80	4.60	2.30	57.30	409	05E
008	11	IMP	R 10.01	A	JCT. RTE. 98	11,900	1,654	13.90	592	76	38	948	35.80	4.60	2.30	57.30	360	05E
008	11	IMP	R 23.48	A	DUNAWAY ROAD	12,200	1,608	13.18	499	81	32	996	31.03	5.04	1.99	61.94	373	10V
008	11	IMP	R 29.933	B	DREW ROAD	12,200	1,981	16.24	587	92	37	1,266	29.63	4.63	1.85	63.89	471	05E
008	11	IMP	R 37.972	B	JCT. RTE. 86	32,000	3,424	10.70	1,103	188	75	2,058	32.20	5.50	2.20	60.10	777	05E
008	11	IMP	R 37.972	A	JCT. RTE. 86	34,500	3,509	10.17	1,131	192	77	2,109	32.24	5.46	2.19	60.11	796	05E
008	11	IMP	R 40.944	B	JCT. RTE. 111	32,000	2,752	8.60	628	149	47	1,928	22.81	5.41	1.71	70.07	708	10V
008	11	IMP	R 40.944	A	JCT. RTE. 111	18,400	4,232	23.00	1,083	279	110	2,759	25.60	6.60	2.60	65.20	1,032	00E
008	11	IMP	R 53.497	B	JCT. RTE. 115 NORTH	11,300	3,390	30.00	868	224	88	2,210	25.60	6.60	2.60	65.20	826	00E
008	11	IMP	R 53.497	A	JCT. RTE. 115 NORTH	11,900	3,154	26.50	807	208	82	2,056	25.60	6.60	2.60	65.20	769	00E
008	11	IMP	R 65.752	B	EAST JCT. RTE. 98 WEST	11,900	3,154	26.50	807	208	82	2,056	25.60	6.60	2.60	65.20	769	00E
008	11	IMP	R 65.752	A	EAST JCT. RTE. 98 WEST	13,800	3,312	24.00	848	219	86	2,159	25.60	6.60	2.60	65.20	807	00E
008	11	IMP	R 96.546	B	4TH AVENUE	21,100	1,637	7.76	303	120	85	1,129	18.51	7.31	5.21	68.96	424	06V
008	11	IMP	R 96.986	B	ARIZONA STATE LINE	16,300	3,162	19.40	809	209	82	2,062	25.60	6.60	2.60	65.20	771	00E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
009	05	SCR	0.046	A	SANTA CRUZ, JCT. RTE. 1	24,700	1,531	6.20	937	257	38	299	61.20	16.80	2.50	19.50	165	95V
009	05	SCR	0.63	B	SANTA CRUZ, NORTH CITY LIMITS	5,000	110	2.20	104	6	0	0	94.70	5.30	0.00	0.00	4	98E
009	05	SCR	6.46	B	FELTON, GRAHAM HILL ROAD	12,200	695	5.70	357	79	1	258	51.30	11.40	0.20	37.10	109	98E
009	05	SCR	6.46	A	FELTON, GRAHAM HILL ROAD	21,100	886	4.20	638	169	19	59	72.00	19.10	2.20	6.70	61	98E
009	05	SCR	13.037	B	BOULDER CREEK, SOUTH JCT. RTE. 236	12,300	554	4.50	523	27	2	2	94.40	4.90	0.30	0.40	22	95V
009	05	SCR	13.037	A	BOULDER CREEK, SOUTH JCT. RTE. 236	16,200	599	3.70	580	17	0	2	96.80	2.80	0.00	0.40	23	95V
009	05	SCR	27.094	B	JCT. RTE. 35	2,800	56	2.00	48	8	0	0	86.60	13.40	0.00	0.00	2	01E
009	04	SCL	0	A	JCT. RTE. 35	2,700	16	0.58	10	6	0	0	65.38	34.62	0.00	0.00	1	01V
009	04	SCL	R 7.4	B	SARATOGA, JCT. RTE. 85 NORTH	13,800	356	2.58	311	45	0	0	87.38	12.62	0.00	0.00	15	01V
009	04	SCL	7.4	A	SARATOGA, JCT. RTE. 85 NORTH	12,400	430	3.47	329	72	13	16	76.55	16.63	3.01	3.81	26	01V
009	04	SCL	11.448	B	LOS GATOS, JCT. RTE. 17	34,000	1,102	3.24	780	203	35	84	70.81	18.43	3.17	7.59	80	01V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
010S	07	LA	19.714	O	BUSWAY; EAST LA CITY LIMITS	8,000	838	10.47	686	81	70	1	81.88	9.61	8.40	0.12	42	09V
010	07	LA	R 2.155	A	SANTA MONICA, JCT. RTE. 1, LINCOLN BOULEVARD INTERCHANGE	141,000	3,553	2.52	2,719	367	156	312	76.52	10.33	4.38	8.77	260	10E
010	07	LA	R 5.454	B	LOS ANGELES, JCT. RTE. 405, SAN DIEGO FREEWAY INTERCHANGE	237,000	4,622	1.95	3,537	477	202	405	76.52	10.33	4.38	8.77	337	10E
010	07	LA	R 5.454	A	LOS ANGELES, JCT. RTE. 405, SAN DIEGO FREEWAY INTERCHANGE	259,000	8,754	3.38	5,683	1,127	324	1,621	64.92	12.87	3.70	18.52	909	10E
010	07	LA	R 8.965	B	LOS ANGELES, JCT. RTE. 187, VENICE BOULEVARD INTERCHANGE	262,000	8,856	3.38	5,749	1,140	328	1,640	64.92	12.87	3.70	18.52	920	10E
010	07	LA	R 8.965	A	LOS ANGELES, JCT. RTE. 187, VENICE BOULEVARD INTERCHANGE	266,000	8,991	3.38	5,837	1,157	333	1,665	64.92	12.87	3.70	18.52	934	10E
010	07	LA	R 11.698	O	LOS ANGELES, 10TH AVENUE	288,000	9,734	3.38	6,319	1,253	360	1,803	64.92	12.87	3.70	18.52	1,011	10E
010	07	LA	14.836	B	LOS ANGELES, JCT. RTE. 110, HARBOR FREEWAY INTERCHANGE	311,000	10,512	3.38	6,824	1,353	389	1,947	64.92	12.87	3.70	18.52	1,092	10E
010	07	LA	14.836	A	LOS ANGELES, JCT. RTE. 110, HARBOR FREEWAY INTERCHANGE	244,000	13,786	5.65	7,473	2,058	612	3,642	54.21	14.93	4.44	26.42	1,797	10E
010	07	LA	16.025	A	SAN PEDRO STREET (BELOW)	276,000	15,594	5.65	8,454	2,328	692	4,120	54.21	14.93	4.44	26.42	2,033	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
010	07	LA	S 0	A	LOS ANGELES, JCT. RTE. 101, SANTA ANA FREEWAY INTERCHANGE	93,000	2,279	2.45	1,276	239	55	709	55.98	10.48	2.42	31.12	319	10E
010	07	LA	S .655	B	LOS ANGELES, JCT. RTE. 5, GOLDEN STATE FREEWAY INTERCHANGE	93,000	2,279	2.45	1,276	239	55	709	55.98	10.48	2.42	31.12	319	10E
010	07	LA	18.394	A	LOS ANGELES, JCT. RTE. 5, GOLDEN STATE FREEWAY INTERCHANGE	214,000	7,469	3.49	3,149	952	362	3,006	42.16	12.74	4.85	40.25	1,288	10E
010	07	LA	19.668	O	EAST LOS ANGELES CITY LIMITS	236,000	7,623	3.23	3,214	971	370	3,068	42.16	12.74	4.85	40.25	1,315	10E
010	07	LA	21.382	B	MONTEREY PARK, JCT. RTE. 710, LONG BEACH FREEWAY INTERCHANGE	225,000	7,740	3.44	3,263	986	375	3,115	42.16	12.74	4.85	40.25	1,335	10E
010	07	LA	21.382	A	MONTEREY PARK, JCT. RTE. 710, LONG BEACH FREEWAY INTERCHANGE	207,000	10,516	5.08	4,978	1,187	395	3,955	47.34	11.29	3.76	37.61	1,706	10E
010	07	LA	24.32	O	ALMANSOR AVE	214,000	10,871	5.08	5,146	1,227	409	4,089	47.34	11.29	3.76	37.61	1,764	10E
010	07	LA	24.831	A	MONTEREY PARK, NEW AVENUE INTERCHANGE	219,000	11,125	5.08	5,267	1,256	418	4,184	47.34	11.29	3.76	37.61	1,805	10E
010	07	LA	26.857	B	EL MONTE, JCT. RTE. 164, ROSEMEAD BOULEVARD	218,000	11,074	5.08	5,242	1,250	416	4,165	47.34	11.29	3.76	37.61	1,797	10E
010	07	LA	26.857	A	EL MONTE, JCT. RTE. 164, ROSEMEAD BOULEVARD	203,000	10,312	5.08	4,882	1,164	388	3,878	47.34	11.29	3.76	37.61	1,673	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
010	07	LA	31.151	B	BALDWIN PARK, JCT. RTE. 605, SAN GABRIEL RIVER FREEWAY INTERCHANGE	226,000	11,481	5.08	5,435	1,296	432	4,318	47.34	11.29	3.76	37.61	1,863	10E
010	07	LA	31.151	A	BALDWIN PARK, JCT. RTE. 605, SAN GABRIEL RIVER FREEWAY INTERCHANGE	240,000	15,480	6.45	5,636	1,212	732	7,899	36.41	7.83	4.73	51.03	3,142	10E
010	07	LA	36.5	B	WEST COVINA, AZUSA AVENUE INTERCHANGE	223,000	15,922	7.14	5,797	1,247	753	8,125	36.41	7.83	4.73	51.03	3,231	10E
010	07	LA	42.443	B	POMONA, JCT. RTES. 57/71, ORANGE/CHINO VALLEY FREEWAYS INTERCHANGE	204,000	15,994	7.84	5,823	1,252	757	8,162	36.41	7.83	4.73	51.03	3,246	10E
010	07	LA	42.443	A	POMONA, JCT. RTES. 57/71, ORANGE/CHINO VALLEY FREEWAYS INTERCHANGE	245,000	16,489	6.73	4,520	1,705	770	9,494	27.41	10.34	4.67	57.58	3,704	10E
010	07	LA	47.737	B	POMONA, INDIAN HILL BOULEVARD INTERCHANGE	245,000	16,170	6.60	4,432	1,672	755	9,311	27.41	10.34	4.67	57.58	3,632	10V
010	07	LA	48.265	O	LOS ANGELES/SAN BERNARDINO COUNTY LINE	246,000	16,113	6.55	4,417	1,666	752	9,278	27.41	10.34	4.67	57.58	3,619	10E
010	08	SBD	0	O	LOS ANGELES/SAN BERNARDINO COUNTY LINE	246,000	16,113	6.55	4,417	1,666	752	9,278	27.41	10.34	4.67	57.58	3,619	10E
010	08	SBD	1.229	B	MONTCLAIR, CENTRAL AVENUE	246,000	16,334	6.64	4,752	1,553	590	9,439	29.09	9.51	3.61	57.79	3,652	05E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
010	08	SBD	1.229	A	MONTCLAIR, CENTRAL AVENUE	246,000	16,334	6.64	4,752	1,553	590	9,439	29.09	9.51	3.61	57.79	3,652	05E
010	08	SBD	3.468	B	UPLAND, JCT. RTE. 83	248,000	16,591	6.69	4,826	1,578	599	9,588	29.09	9.51	3.61	57.79	3,710	05E
010	08	SBD	3.468	A	UPLAND, JCT. RTE. 83	239,000	15,989	6.69	4,651	1,521	577	9,240	29.09	9.51	3.61	57.79	3,575	05E
010	08	SBD	9.936	B	ONTARIO, JCT. RTE. 15	245,300	16,411	6.69	4,774	1,561	592	9,484	29.09	9.51	3.61	57.79	3,670	05E
010	08	SBD	9.936	A	ONTARIO, JCT. RTE. 15	245,300	25,094	10.23	6,389	2,557	730	15,418	25.46	10.19	2.91	61.44	5,885	06E
010	08	SBD	11.132	B	ETIWANDA AVENUE	245,300	25,094	10.23	6,389	2,557	730	15,418	25.46	10.19	2.91	61.44	5,885	06E
010	08	SBD	11.132	A	ETIWANDA AVENUE	210,000	21,483	10.23	5,470	2,189	625	13,199	25.46	10.19	2.91	61.44	5,038	06V
010	08	SBD	13.169	B	FONTANA, CHERRY AVENUE	210,000	21,609	10.29	5,761	2,195	637	13,015	26.66	10.16	2.95	60.23	4,987	08V
010	08	SBD	R 18.492	B	BLOOMINGTON, CEDAR AVENUE	198,000	20,255	10.23	4,904	2,117	595	12,637	24.21	10.45	2.94	62.39	4,814	06E
010	08	SBD	R 18.492	A	BLOOMINGTON, CEDAR AVENUE	192,000	19,546	10.18	4,887	1,955	586	12,119	25.00	10.00	3.00	62.00	4,618	06E
010	08	SBD	20.965	B	PEPPER AVENUE	193,000	19,493	10.10	4,776	1,852	585	12,281	24.50	9.50	3.00	63.00	4,660	06E
010	08	SBD	20.965	A	PEPPER AVENUE	194,000	19,400	10.00	4,753	1,746	576	12,319	24.50	9.00	2.97	63.50	4,662	06E
010	08	SBD	R 23.248	B	COLTON, MOUNT VERNON AVENUE	200,000	19,780	9.89	4,846	1,780	593	12,560	24.50	9.00	3.00	63.50	4,754	06E
010	08	SBD	R 24.24	B	COLTON, JCT. RTE. 215	196,000	21,756	11.10	8,050	2,828	805	10,073	37.00	13.00	3.70	46.30	4,135	84E
010	08	SBD	R 24.24	A	COLTON, JCT. RTE. 215	226,000	24,860	11.00	10,168	3,008	870	10,814	40.90	12.10	3.50	43.50	4,491	84V
010	08	SBD	27.296	B	MOUNTAIN VIEW AVENUE	194,000	25,608	13.20	10,474	3,099	896	11,139	40.90	12.10	3.50	43.50	4,626	84E
010	08	SBD	27.296	A	MOUNTAIN VIEW AVENUE	190,000	23,370	12.30	9,605	2,337	771	10,657	41.10	10.00	3.30	45.60	4,341	84E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
010	08	SBD	29.313	B	JCT. RTE. 30	185,300	22,236	12.00	8,961	2,023	1,156	10,095	40.30	9.10	5.20	45.40	4,152	89E
010	08	SBD	29.313	A	JCT. RTE. 30	172,500	20,700	12.00	8,342	1,884	1,076	9,398	40.30	9.10	5.20	45.40	3,866	89E
010	08	SBD	30.899	B	REDLANDS, JCT. RTE. 38 NORTH	172,500	17,940	10.40	7,732	1,704	897	7,607	43.10	9.50	5.00	42.40	3,184	85V
010	08	SBD	30.899	A	REDLANDS, JCT. RTE. 38 NORTH	145,000	17,400	12.00	7,012	1,583	905	7,900	40.30	9.10	5.20	45.40	3,250	86E
010	08	SBD	35.5	B	YUCAIPA BOULEVARD	136,000	17,680	13.00	6,559	1,644	530	8,946	37.10	9.30	3.00	50.60	3,545	86E
010	08	SBD	35.5	A	YUCAIPA BOULEVARD	110,000	17,600	16.00	5,984	1,056	352	10,208	34.00	6.00	2.00	58.00	3,880	86V
010	08	RIV	R 3.048	A	CHERRY VALLEY BOULEVARD	91,000	11,921	13.10	3,612	656	262	7,391	30.30	5.50	2.20	62.00	2,775	91V
010	08	RIV	6.67	B	JCT. RTE. 60 WEST	88,000	11,880	13.50	3,362	677	618	7,223	28.30	5.70	5.20	60.80	2,763	85V
010	08	RIV	6.67	A	JCT. RTE. 60 WEST	122,000	16,470	13.50	6,604	955	692	8,219	40.10	5.80	4.20	49.90	3,256	85E
010	08	RIV	7.574	A	BEAUMONT, JCT. RTE. 79 SOUTH	124,000	17,980	14.50	6,329	1,295	809	9,547	35.20	7.20	4.50	53.10	3,753	85E
010	08	RIV	11.333	B	BANNING, SUNSET AVENUE	125,000	17,875	14.30	5,577	1,466	822	10,010	31.20	8.20	4.60	56.00	3,904	85V
010	08	RIV	R 14.76	B	EAST RAMSEY STREET	108,000	17,280	16.00	3,283	1,365	864	11,768	19.00	7.90	5.00	68.10	4,427	86E
010	08	RIV	R 14.76	A	EAST RAMSEY STREET	111,000	20,313	18.30	2,844	1,625	1,219	14,625	14.00	8.00	6.00	72.00	5,474	86V
010	08	RIV	R 25.201	B	JCT. RTE. 111	91,000	17,290	19.00	2,766	1,383	1,037	12,103	16.00	8.00	6.00	70.00	4,552	86E
010	08	RIV	R 25.201	A	JCT. RTE. 111	79,000	17,301	21.90	4,844	1,038	692	10,727	28.00	6.00	4.00	62.00	4,068	86E
010	08	RIV	29.691	B	JCT. RTE. 62 NORTH	79,000	17,301	21.90	5,017	900	450	10,934	29.00	5.20	2.60	63.20	4,097	84E
010	08	RIV	29.691	A	JCT. RTE. 62 NORTH	77,000	20,174	26.20	5,306	767	545	13,557	26.30	3.80	2.70	67.20	5,014	84E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
010	08	RIV	33.129	B	INDIAN AVENUE	77,000	19,250	25.00	3,831	770	558	14,091	19.90	4.00	2.90	73.20	5,148	84E
010	08	RIV	33.129	A	INDIAN AVENUE	79,000	18,644	23.60	2,908	746	466	14,524	15.60	4.00	2.50	77.90	5,250	84E
010	08	RIV	R 52.342	B	JEFFERSON STREE/INDIO BOULEVARD	81,000	26,325	32.50	4,080	711	527	21,007	15.50	2.70	2.00	79.80	7,533	83V
010	08	RIV	R 52.342	A	JEFFERSON STREE/INDIO BOULEVARD	66,000	22,308	33.80	3,413	848	535	17,512	15.30	3.80	2.40	78.50	6,318	83V
010	08	RIV	R 57.831	B	INDIO, JCT. RTE. 86 SOUTH	51,000	15,922	31.22	2,159	357	201	13,206	13.56	2.24	1.26	82.94	4,694	04E
010	08	RIV	R 57.831	A	INDIO, JCT. RTE. 86 SOUTH	24,000	8,309	34.62	1,080	166	100	6,963	13.00	2.00	1.20	83.80	2,470	04E
010	08	RIV	R 58.89	A	DILLON ROAD	22,000	8,716	39.62	1,140	169	96	7,311	13.08	1.94	1.10	83.88	2,592	04V
010	08	RIV	R105.087	B	JCT. RTE. 177 NORTH	22,500	8,876	39.45	1,161	172	98	7,445	13.08	1.94	1.10	83.88	2,639	04E
010	08	RIV	R105.087	A	JCT. RTE. 177 NORTH	21,000	9,116	43.41	1,179	177	100	7,659	12.93	1.94	1.10	84.02	2,715	04E
010	08	RIV	R 149.15	B	JCT. RTE. 78 SOUTH	22,000	8,626	39.21	1,115	167	95	7,248	12.93	1.94	1.10	84.02	2,569	04E
010	08	RIV	R 149.15	A	JCT. RTE. 78 SOUTH	23,500	8,813	37.50	1,165	196	108	7,344	13.22	2.22	1.22	83.33	2,608	04E
010	08	RIV	R154.167	B	JCT. RTE. 95 NORTH	24,000	8,503	35.43	1,124	189	104	7,086	13.22	2.22	1.22	83.33	2,517	04E
010	08	RIV	R154.167	A	JCT. RTE. 95 NORTH	25,000	9,038	36.15	1,226	202	114	7,496	13.56	2.24	1.26	82.94	2,664	04E
010	08	RIV	R156.492	B	ARIZONA STATE LINE	25,000	9,020	36.08	1,223	202	114	7,481	13.56	2.24	1.26	82.94	2,659	04E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
012	04	SON	9.23	A	SEBASTOPOL, JCT. RTE. 116	24,500	992	4.05	826	102	23	42	83.25	10.24	2.28	4.24	56	99V
012	04	SON	9.54	B	SEBASTOPOL EAST CITY LIMITS	23,000	964	4.19	698	121	19	126	72.45	12.51	1.94	13.09	82	99V
012	04	SON	R 14.45	A	SANTA ROSA, STONY POINT ROAD	63,000	1,896	3.01	961	337	131	466	50.69	17.79	6.92	24.60	245	02V
012	04	SON	R 16.039	B	SANTA ROSA, JCT. RTE. 101	75,000	2,550	3.40	1,433	525	138	454	56.20	20.60	5.40	17.80	275	96V
012	04	SON	R 16.039	A	SANTA ROSA, JCT. RTE. 101	74,000	1,783	2.41	1,021	265	79	418	57.25	14.89	4.42	23.45	216	05V
012	04	SON	T 17.53	B	SANTA ROSA, FARMERS LANE	62,000	1,488	2.40	966	281	31	210	64.90	18.90	2.10	14.10	137	96V
012	04	SON	20.1	A	SANTA ROSA, CALISTOGA ROAD	29,000	1,334	4.60	671	224	51	388	50.30	16.80	3.80	29.10	185	96V
012	04	SON	27.03	B	KENWOOD, WARM SPRINGS ROAD	15,100	619	4.10	405	89	19	107	65.40	14.30	3.00	17.30	62	96V
012	04	SON	30.65	A	ARNOLD DRIVE	14,100	572	4.06	322	105	42	103	56.28	18.44	7.31	17.97	63	02V
012	04	SON	37.505	B	SONOMA, FIRST STREET WEST	14,600	518	3.55	336	62	32	87	64.92	12.03	6.27	16.78	52	02V
012	04	SON	41.36	B	JCT. RTE. 121	6,400	217	3.39	103	19	16	78	47.58	8.81	7.49	36.12	35	02V
012	04	NAP	0	A	JCT. RTE. 29, NAPA, SOUTH	25,500	2,027	7.95	629	185	123	1,091	31.01	9.11	6.06	53.82	434	02V
012	04	NAP	0.24	A	KELLY ROAD	34,000	2,618	7.70	956	228	76	1,358	36.51	8.72	2.92	51.86	534	02V
012	04	SOL	R 2.794	B	JCT. RTE. 80	32,500	2,340	7.20	719	214	118	1,290	30.71	9.13	5.05	55.11	507	02V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
012	04	SOL	L 1.801	A	JCT. RTE. 80	32,000	1,629	5.09	415	136	33	1,046	25.47	8.32	2.00	64.22	393	99V
012	04	SOL	7.16	B	SCANDIA ROAD/LAWLER RANCH	19,400	1,874	9.66	515	250	98	1,011	27.48	13.34	5.23	53.96	404	02V
012	04	SOL	8.89	B	SCALLY ROAD	13,800	2,423	17.56	505	404	126	1,389	20.84	16.66	5.19	57.32	553	02V
012	04	SOL	19.169	B	JCT. RTE. 113 NORTH	10,300	1,136	11.03	110	66	56	905	9.66	5.78	4.93	79.63	330	05V
012	04	SOL	19.169	A	JCT. RTE. 113 NORTH	14,100	1,345	9.54	216	41	24	1,064	16.07	3.05	1.79	79.09	382	05V
012	04	SOL	26.276	B	JCT. RTE. 84 NORTH	18,500	1,654	8.94	324	126	41	1,163	19.57	7.60	2.50	70.33	430	05V
012	04	SOL	26.276	A	JCT. RTE. 84 NORTH	19,800	1,998	10.09	384	91	41	1,481	19.23	4.57	2.06	74.14	539	05V
012	03	SAC	0	A	SOLANO/SACRAMENTO COUNTY LINE	21,000	2,856	13.60	411	617	97	1,731	14.40	21.60	3.40	60.60	683	95E
012	03	SAC	0.571	A	JCT. RTE. 160	17,100	2,480	14.50	357	508	84	1,530	14.40	20.50	3.40	61.70	599	95V
012	03	SAC	6.2	O	SACRAMENTO/SAN JOAQUIN COUNTY LINE	15,000	2,115	14.10	231	427	80	1,377	10.90	20.20	3.80	65.10	534	96V
012	10	SJ	0	O	SACRAMENTO/SAN JOAQUIN COUNTY LINE	15,000	2,115	14.10	231	427	80	1,377	10.90	20.20	3.80	65.10	534	96V
012	10	SJ	10.167	B	JCT. RTE. 5	16,400	2,280	13.90	244	353	71	1,612	10.70	15.50	3.10	70.70	608	96V
012	10	SJ	10.167	A	JCT. RTE. 5	15,000	2,295	15.30	381	367	71	1,476	16.60	16.00	3.10	64.30	567	96E
012	10	SJ	15.155	B	LOWER SACRAMENTO ROAD	12,200	1,086	8.90	206	195	46	639	19.00	18.00	4.20	58.80	252	96V
012	10	SJ	15.155	A	LOWER SACRAMENTO ROAD	23,500	2,092	8.90	425	527	117	1,023	20.30	25.20	5.60	48.90	433	96E
012	10	SJ	16.44	B	SOUTH HAM LANE	35,000	3,150	9.00	680	1,021	189	1,260	21.60	32.40	6.00	40.00	580	96V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
012	10	SJ	16.931	A	LODI, SOUTH HUTCHINS STREET	26,000	2,444	9.40	650	653	144	997	26.60	26.70	5.90	40.80	448	96E
012	10	SJ	17.95	B	LODI, CHEROKEE LANE	24,000	2,352	9.80	746	492	113	1,002	31.70	20.90	4.80	42.60	434	96E
012	10	SJ	18.07	B	LODI, JCT. RTE. 99	19,700	2,009	10.20	737	305	74	892	36.70	15.20	3.70	44.40	372	95E
012	10	SJ	18.08	A	LODI, JCT. RTE. 99	10,500	630	6.00	158	226	32	215	25.10	35.80	5.00	34.10	105	96V
012	10	SJ	20.9	B	VICTOR BRUELLA ROAD	9,000	513	5.70	108	201	30	174	21.00	39.20	5.80	34.00	87	96V
012	10	SJ	20.9	A	VICTOR BRUELLA ROAD	7,800	398	5.10	107	129	22	140	27.00	32.30	5.50	35.20	67	96V
012	10	SJ	L 23.286	B	LOCKEFORD, JCT. RTE. 88	6,600	449	6.80	93	75	14	267	20.70	16.60	3.20	59.50	104	96V
012	10	SJ	23.168	A	LOCKEFORD, JCT. RTE. 88	7,200	518	7.20	129	136	20	233	24.90	26.30	3.90	44.90	100	96V
012	10	CAL	9.927	B	VALLEY SPRINGS, JCT. RTE. 26 SOUTH	8,600	543	6.31	149	174	21	199	27.50	32.10	3.80	36.60	93	96V
012	10	CAL	9.927	A	VALLEY SPRINGS, JCT. RTE. 26 SOUTH	6,800	415	6.10	129	162	17	107	31.00	39.10	4.00	25.90	59	96V
012	10	CAL	13.872	B	TOYON, JCT. RTE. 26 NORTH	7,000	420	6.00	125	159	17	119	29.80	37.90	4.00	28.30	63	96V
012	10	CAL	18.201	B	SAN ANDREAS, JCT. RTE. 49	7,600	509	6.70	201	166	15	128	39.40	32.60	2.90	25.10	69	96V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
013	04	ALA	4.262	A	OAKLAND, JCT. RTE. 580	46,500	535	1.15	477	38	8	11	89.25	7.11	1.56	2.08	25	00V
013	04	ALA	7.397	B	OAKLAND, PARK BOULEVARD	57,000	604	1.06	482	75	6	42	79.81	12.34	0.96	6.89	39	00V
013	04	ALA	7.397	A	OAKLAND, PARK BOULEVARD	57,000	827	1.45	667	87	13	60	80.62	10.50	1.61	7.27	54	00V
013	04	ALA	R 9.621	B	OAKLAND, JCT. RTE. 24	70,000	1,260	1.80	869	249	18	124	68.98	19.76	1.39	9.88	99	00V
013	04	ALA	R 9.621	A	OAKLAND, JCT. RTE. 24	19,600	172	0.88	142	24	4	2	82.52	14.08	2.43	0.97	8	03V
013	04	ALA	13.178	B	JCT. RTE. 123	26,000	562	2.16	433	75	17	37	77.05	13.43	2.99	6.53	37	00V
013	04	ALA	13.178	A	JCT. RTE. 123	34,000	653	1.92	450	106	23	74	68.92	16.22	3.47	11.39	54	02V
013	04	ALA	13.931	B	BERKELEY, JCT. RTE. 80	36,000	1,530	4.25	920	195	54	361	60.10	12.76	3.55	23.60	183	02V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
014	07	LA	R 24.788	A	SB OFF TO SB RTE 5 & JCT. RTE. 5, GOLDEN STATE FREEWAY INTERCHANGE	160,000	7,680	4.80	3,811	653	417	2,799	49.62	8.50	5.43	36.45	1,220	10E
014	07	LA	R 54.543	B	ANGELES FOREST HIGHWAY INTERCHANGE	95,000	4,313	4.54	1,843	424	292	1,755	42.72	9.83	6.76	40.69	752	10V
014	07	LA	R 59.803	B	PALMDALE, SOUTH JCT. RTE. 138, PALMDALE BOULEVARD	77,000	3,889	5.05	1,507	353	223	1,806	38.75	9.08	5.73	46.43	741	10E
014	07	LA	R 59.803	A	PALMDALE, SOUTH JCT. RTE. 138, PALMDALE BOULEVARD	86,000	3,053	3.55	1,062	255	144	1,593	34.79	8.34	4.71	52.17	631	10E
014	07	LA	R 74.003	B	NORTH JCT. RTE. 138; AVENUE D INTERCHANGE	36,500	2,212	6.06	682	168	81	1,281	30.82	7.59	3.68	57.91	493	10V
014	07	LA	R 74.003	A	NORTH JCT. RTE. 138; AVENUE D INTERCHANGE	34,500	1,880	5.45	579	143	69	1,089	30.82	7.59	3.68	57.91	419	10E
014	06	KER	R 0	A	AVENUE A INTERCHANGE, LOS ANGELES/KERN COUNTY LINE	31,000	1,879	6.06	579	143	69	1,088	30.82	7.59	3.68	57.91	419	10E
014	06	KER	L 17.384	B	JCT. RTE. 58	18,300	3,294	18.00	593	198	66	2,438	18.00	6.00	2.00	74.00	890	04E
014	06	KER	16.07	A	JCT. RTE. 58	17,800	1,780	10.00	392	71	53	1,264	22.00	4.00	3.00	71.00	464	04E
014	06	KER	21.29	A	RANDSBURG CUT-OFF ROAD,CALIFORNIA CITY/BAKERSFIELD ROAD	6,400	1,155	18.05	254	185	116	601	22.00	16.00	10.00	52.00	250	08E
014	06	KER	57.767	B	FREEMAN JUNCTION, JCT. RTE. 178 WEST	5,400	1,026	19.00	123	56	26	821	12.00	5.50	2.50	80.00	297	08E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
014	06	KER	57.767	A	FREEMAN JUNCTION, JCT. RTE. 178 WEST	5,400	1,018	18.85	150	75	53	740	14.75	7.37	5.19	72.69	275	08E
014	06	KER	64.559	B	HOMESTEAD NORTH JUNCTION, JCT. RTE. 395	3,050	555	18.20	135	88	61	271	24.32	15.86	10.99	48.83	115	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
015	11	SD	2.226	B	JCT. RTE. 94	116,000	5,916	5.10	3,029	1,006	296	1,585	51.20	17.00	5.00	26.80	789	85V
015	11	SD	R 3.367	B	JCT. RTE. 805	109,000	5,559	5.10	2,846	945	278	1,490	51.20	17.00	5.00	26.80	741	85E
015	11	SD	R 3.367	A	JCT. RTE. 805	159,000	3,498	2.20	2,526	357	108	507	72.20	10.20	3.10	14.50	312	85V
015	11	SD	R 6.132	B	JCT. RTE. 8	162,000	3,564	2.20	2,573	367	110	513	72.20	10.30	3.10	14.40	317	85E
015	11	SD	R 6.132	A	JCT. RTE. 8	200,000	9,960	4.98	6,219	712	234	2,794	62.44	7.15	2.35	28.05	1,281	07V
015	11	SD	M 12.124	A	JCT. RTE. 163	296,000	11,041	3.73	6,784	795	305	3,158	61.44	7.20	2.76	28.60	1,445	07E
015	11	SD	M 14.285	B	SAN DIEGO, MIRAMAR/ POMERADO ROADS	293,000	11,017	3.76	6,769	793	304	3,151	61.44	7.20	2.76	28.60	1,442	07E
015	11	SD	M 14.285	A	SAN DIEGO, MIRAMAR/ POMERADO ROADS	275,000	10,725	3.90	6,285	1,126	418	2,896	58.60	10.50	3.90	27.00	1,384	85V
015	11	SD	M 18.176	B	SAN DIEGO, POWAY ROAD	236,000	16,756	7.10	8,177	1,893	938	5,747	48.80	11.30	5.60	34.30	2,581	96E
015	11	SD	M 18.176	A	SAN DIEGO, POWAY ROAD	208,000	14,768	7.10	7,207	1,669	827	5,065	48.80	11.30	5.60	34.30	2,275	96E
015	11	SD	M 27.65	A	ESCONDIDO, SOUTH JUNCTION OF CENTRE CITY PARKWAY	176,000	12,496	7.10	6,098	1,412	700	4,286	48.80	11.30	5.60	34.30	1,925	96E
015	11	SD	R 30.627	B	VALLEY PARKWAY	181,000	12,851	7.10	6,271	1,452	720	4,408	48.80	11.30	5.60	34.30	1,980	96E
015	11	SD	R 31.517	B	JCT. RTE. 78	194,000	13,774	7.10	6,722	1,556	771	4,724	48.80	11.30	5.60	34.30	2,122	96E
015	11	SD	R 31.517	A	JCT. RTE. 78	128,000	12,928	10.10	5,714	1,112	672	5,430	44.20	8.60	5.20	42.00	2,274	80V
015	11	SD	R 36.636	A	DEER SPRINGS ROAD	120,000	15,840	13.20	5,592	1,283	665	8,300	35.30	8.10	4.20	52.40	3,275	86V
015	11	SD	R 46.491	B	JCT. RTE. 76	110,000	11,253	10.23	3,581	895	384	6,394	31.82	7.95	3.41	56.82	2,470	00E
015	11	SD	R 46.491	A	JCT. RTE. 76	116,000	9,442	8.14	3,068	720	320	5,335	32.49	7.63	3.39	56.50	2,061	00E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
015	08	RIV	R 0	A	SAN DIEGO/RIVERSIDE COUNTY LINE	134,000	9,045	6.75	3,377	644	274	4,750	37.34	7.12	3.03	52.51	1,856	04V
015	08	RIV	3.436	B	SOUTH JCT. RTE. 79	134,000	9,045	6.75	3,377	644	274	4,750	37.34	7.12	3.03	52.51	1,856	04E
015	08	RIV	3.436	A	SOUTH JCT. RTE. 79	152,000	10,716	7.05	4,001	763	325	5,627	37.34	7.12	3.03	52.51	2,199	04E
015	08	RIV	6.623	B	NORTH JCT RTE. 79	163,000	10,709	6.57	3,999	762	324	5,623	37.34	7.12	3.03	52.51	2,198	04E
015	08	RIV	8.737	B	JCT. RTE. 215 NORTH	182,000	10,101	5.55	3,772	719	306	5,304	37.34	7.12	3.03	52.51	2,073	04E
015	08	RIV	8.737	A	JCT. RTE. 215 NORTH	107,000	9,630	9.00	4,340	773	392	4,125	45.07	8.03	4.07	42.83	1,704	06E
015	08	RIV	15.071	B	BAXTER ROAD	120,000	10,440	8.70	4,698	846	418	4,479	45.00	8.10	4.00	42.90	1,849	06E
015	08	RIV	20.948	B	MAIN STREET	120,000	11,040	9.20	4,968	894	442	4,736	45.00	8.10	4.00	42.90	1,955	06E
015	08	RIV	22.277	B	JCT. RTE. 74	117,000	9,617	8.22	4,846	647	309	3,815	50.39	6.73	3.21	39.67	1,591	08V
015	08	RIV	22.277	A	JCT. RTE. 74	111,000	11,655	10.50	5,245	944	474	4,992	45.00	8.10	4.07	42.83	2,062	06E
015	08	RIV	41.501	B	JCT. RTE. 91	185,000	10,379	5.61	3,614	1,300	839	4,626	34.82	12.53	8.08	44.57	1,965	00E
015	08	RIV	44.66	O	FOURTH ST, NORCO	150,000	17,190	11.46	5,974	2,195	1,341	7,680	34.75	12.77	7.80	44.68	3,258	00E
015	08	RIV	51.474	A	JCT. RTE. 60	214,000	17,548	8.20	6,098	2,241	1,369	7,840	34.75	12.77	7.80	44.68	3,326	00E
015	08	SBD	2.389	A	JCT. RTE. 10	198,000	20,493	10.35	6,183	1,246	508	12,556	30.17	6.08	2.48	61.27	4,738	06E
015	08	SBD	5.306	B	JCT. RTE. 66	187,000	18,794	10.05	5,670	1,143	466	11,515	30.17	6.08	2.48	61.27	4,345	06E
015	08	SBD	5.306	A	JCT. RTE. 66	164,000	17,089	10.42	5,156	1,039	424	10,470	30.17	6.08	2.48	61.27	3,951	06V
015	08	SBD	16.374	B	JCT. RTE. 215	122,000	13,969	11.45	4,388	847	323	8,412	31.41	6.06	2.31	60.22	3,181	08V
015	08	SBD	R 13.779	A	JCT. RTE. 215	152,000	20,961	13.79	6,079	1,174	503	13,205	29.00	5.60	2.40	63.00	4,950	04E
015	08	SBD	31.813	B	JCT. RTE. 395 NORTH	124,000	16,777	13.53	3,891	1,134	409	11,343	23.19	6.76	2.44	67.61	4,214	00E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
015	08	SBD	31.813	A	JCT. RTE. 395 NORTH	101,000	15,786	15.63	3,662	1,073	379	10,671	23.20	6.80	2.40	67.60	3,964	00E
015	08	SBD	40.509	B	JCT. RTE. 18 SOUTH	85,000	15,360	18.07	3,551	1,040	367	10,400	23.12	6.77	2.39	67.71	3,862	00E
015	08	SBD	40.509	A	JCT. RTE. 18 SOUTH	86,000	14,680	17.07	3,403	995	357	9,927	23.18	6.78	2.43	67.62	3,688	00E
015	08	SBD	43.488	A	VICTORVILLE, JCT. RTE. 18 SOUTHEAST	60,000	14,196	23.66	3,288	960	348	9,599	23.16	6.76	2.45	67.62	3,566	00E
015	08	SBD	68.77	B	BARSTOW, LENWOOD ROAD	55,000	13,745	24.99	3,194	935	331	9,286	23.24	6.80	2.41	67.56	3,450	00E
015	08	SBD	68.77	A	BARSTOW, LENWOOD ROAD	58,000	13,868	23.91	3,223	943	334	9,369	23.24	6.80	2.41	67.56	3,481	01E
015	08	SBD	74.418	B	BARSTOW, JCT. RTE. 40 EAST	65,000	12,786	19.67	2,965	864	309	8,647	23.19	6.76	2.42	67.63	3,212	01E
015	08	SBD	74.418	A	BARSTOW, JCT. RTE. 40 EAST	46,000	7,682	16.70	1,989	213	101	5,378	25.89	2.77	1.32	70.01	1,959	05E
015	08	SBD	76.883	B	JCT. RTE. 58 WEST	46,000	7,820	17.00	2,025	217	103	5,475	25.89	2.77	1.32	70.01	1,995	05E
015	08	SBD	76.883	A	JCT. RTE. 58 WEST	46,000	7,539	16.39	1,538	176	84	5,741	20.40	2.33	1.11	76.15	2,063	08V
015	08	SBD	R 87.26	O	YERMO INSPECTION STATION	37,500	7,425	19.80	1,922	206	98	5,198	25.89	2.77	1.32	70.01	1,894	05E
015	08	SBD	R136.574	B	BAKER, JCT. RTE. 127	33,000	6,600	20.00	1,284	321	182	4,813	19.45	4.86	2.76	72.93	1,762	01E
015	08	SBD	R136.574	A	BAKER, JCT. RTE. 127	32,000	6,733	21.04	1,310	327	186	4,910	19.45	4.86	2.76	72.93	1,797	01E
015	08	SBD	176.459	B	NIPTON ROAD	38,500	6,915	17.96	1,770	227	90	4,827	25.60	3.28	1.30	69.81	1,761	01E
015	08	SBD	186.238	B	NEVADA STATE LINE	39,500	7,094	17.96	1,816	233	92	4,952	25.60	3.28	1.30	69.81	1,807	01E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
016	03	COL	0	A	JCT. RTE. 20	590	84	14.17	25	10	10	40	29.41	11.76	11.76	47.06	17	00E
016	03	YOL	7.146	A	RUMSEY, MANZANITA AVENUE	1,100	80	7.27	18	20	16	26	22.50	25.00	20.00	32.50	14	07E
016	03	YOL	31.867	B	JCT. RTE. 505	13,600	1,548	11.38	493	158	109	789	31.85	10.19	7.01	50.96	320	00E
016	03	YOL	32.226	A	JCT. RTE. 505	7,500	750	10.00	214	87	47	402	28.57	11.61	6.25	53.57	161	00E
016	03	YOL	40.57	B	WEST MAIN STREET	11,000	959	8.72	320	128	102	409	33.33	13.33	10.67	42.67	179	00E
016	03	YOL	R 40.57	A	WEST MAIN STREET	7,300	780	10.69	269	112	62	337	34.53	14.39	7.91	43.17	145	00E
016	03	YOL	R 43.42	B	JCT. RTES. 5/50	4,000	512	12.80	139	64	32	277	27.08	12.50	6.25	54.17	111	00E
016	03	SAC	T 1.658	A	JCT. RTES. 5/50	55,000	4,950	9.00	1,544	1,386	594	1,426	31.20	28.00	12.00	28.80	761	96E
016	03	SAC	3.015	B	SACRAMENTO, FLORIN-PERKINS ROAD	11,500	1,035	9.00	323	291	123	298	31.20	28.10	11.90	28.80	159	96E
016	03	SAC	R 11.474	B	SACRAMENTO, SUNRISE BOULEVARD	9,200	828	9.00	258	232	99	239	31.20	28.00	11.90	28.90	127	96E
016	03	SAC	R 16.805	A	LATROBE ROAD	16,500	743	4.50	344	112	90	197	46.30	15.10	12.10	26.50	104	96E
016	10	AMA	9.093	B	JCT. RTE. 124 SOUTH	8,000	617	7.71	194	133	30	260	31.40	21.60	4.80	42.20	113	97E
016	10	AMA	9.373	B	CENTRAL HOUSE, JCT. RTE. 49	8,500	646	7.60	203	140	30	273	31.40	21.70	4.70	42.20	119	97E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
017	05	SCR	0	A	SANTA CRUZ, JCT. RTE. 1	65,000	1,775	2.73	978	215	44	538	55.10	12.10	2.50	30.30	246	03E
017	04	SCL	0.108	B	JCT. RTE. 35 NORTHWEST	52,000	1,602	3.08	778	132	45	647	48.54	8.27	2.81	40.38	269	04V
017	04	SCL	0.108	A	JCT. RTE. 35 NORTHWEST	52,000	1,570	3.02	763	127	47	633	48.59	8.12	2.98	40.31	264	04V
017	04	SCL	4.06	B	BEAR CREEK ROAD	56,000	1,898	3.39	733	176	42	947	38.63	9.29	2.19	49.89	375	01V
017	04	SCL	7.073	A	LOS GATOS, JCT. RTE. 9 WEST	84,000	4,645	5.53	2,544	779	127	1,194	54.77	16.78	2.74	25.70	591	04V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
018	08	SBD	T 6.179	A	SAN BERNARDINO, JCT. RTE. 30	28,000	2,968	10.60	1,997	33	181	757	67.30	1.10	6.10	25.50	361	84E
018	08	SBD	T 7.548	A	SAN BERNARDINO, 40TH STREET	16,900	1,420	8.40	1,140	14	85	180	80.30	1.00	6.00	12.70	116	84E
018	08	SBD	T 8.264	A	SAN BERNARDINO, SIERRA WAY	16,500	1,683	10.20	1,363	17	98	205	81.00	1.00	5.80	12.20	134	84E
018	08	SBD	9.15	A	WATERMAN CANYON ROAD	16,000	1,632	10.20	1,335	16	95	186	81.80	1.00	5.80	11.40	126	84E
018	08	SBD	R 17.732	B	JCT. RTE. 138 NORTH	16,000	2,096	13.10	1,715	21	122	239	81.80	1.00	5.80	11.40	162	84V
018	08	SBD	R 17.732	A	JCT. RTE. 138 NORTH	8,000	1,824	22.80	1,598	13	80	133	87.60	0.70	4.40	7.30	115	84E
018	08	SBD	20.612	A	JCT. RTE. 189 NORTH	8,000	1,456	18.20	1,275	10	64	106	87.60	0.70	4.40	7.30	92	84E
018	08	SBD	24.712	B	JCT. RTE. 173 NORTH	10,000	1,730	17.30	1,538	7	62	123	88.90	0.40	3.60	7.10	106	84E
018	08	SBD	24.712	A	JCT. RTE. 173 NORTH	8,000	1,048	13.10	918	9	61	60	87.60	0.90	5.80	5.70	63	84E
018	08	SBD	25.81	A	KUFFEL CANYON ROAD	7,000	903	12.90	814	16	24	49	90.10	1.80	2.70	5.40	50	84E
018	08	SBD	31.651	B	WEST JCT. RTE. 330	7,000	889	12.70	801	15	24	49	90.10	1.70	2.70	5.50	50	84E
018	08	SBD	31.651	A	WEST JCT. RTE. 330	7,000	672	9.60	586	6	14	66	87.20	0.90	2.10	9.80	46	84E
018	08	SBD	31.903	A	JCT. RTE. 330 SOUTH	10,300	742	7.20	588	42	8	105	79.20	5.60	1.10	14.10	62	89V
018	08	SBD	34.52	B	GREEN VALLEY LAKE ROAD	7,400	836	11.30	740	8	14	74	88.50	0.90	1.70	8.90	54	84E
018	08	SBD	44.319	B	JCT. RTE. 38 NORTHEAST	6,000	660	11.00	543	15	13	90	82.20	2.30	1.90	13.60	53	88E
018	08	SBD	44.319	A	JCT. RTE. 38 NORTHEAST	4,700	588	12.50	456	48	0	84	77.50	8.20	0.00	14.30	49	88V
018	08	SBD	53.917	B	JCT. RTE. 38 EAST	15,600	1,716	11.00	1,304	69	51	292	76.00	4.00	3.00	17.00	160	88E
018	08	SBD	54.537	A	JCT. RTE. 38 WEST	4,900	627	12.80	420	55	0	152	67.00	8.80	0.00	24.20	72	92V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
018	08	SBD	58.44	B	BALDWIN LAKE ROAD	2,300	182	7.90	144	16	0	21	79.20	9.00	0.00	11.80	14	91E
018	08	SBD	58.44	A	BALDWIN LAKE ROAD	2,600	328	12.60	206	46	0	76	62.90	13.90	0.00	23.20	38	88V
018	08	SBD	73.783	B	LUCERNE VALLEY, JCT. RTE. 247	5,200	931	17.90	199	33	47	653	21.40	3.50	5.00	70.10	242	87E
018	08	SBD	73.783	A	LUCERNE VALLEY, JCT. RTE. 247	8,700	1,636	18.80	599	31	13	993	36.60	1.90	0.80	60.70	368	91E
018	08	SBD	84.325	B	BEAR VALLEY CUTOFF	9,700	1,892	19.50	681	38	19	1,154	36.00	2.00	1.00	61.00	428	90E
018	08	SBD	84.325	A	BEAR VALLEY CUTOFF	5,000	745	14.90	365	29	15	336	49.00	3.90	2.00	45.10	134	87E
018	08	SBD	94.39	B	APPLE VALLEY ROAD	30,000	3,510	11.70	2,569	70	53	818	73.20	2.00	1.50	23.30	386	93V
018	08	SBD	94.39	A	APPLE VALLEY ROAD	44,000	5,236	11.90	4,115	141	31	948	78.60	2.70	0.60	18.10	489	93V
018	08	SBD	96.571	B	VICTORVILLE, NORTH JCT RTE 15, BARSTOW FREEWAYJCT. RTE. 15	26,500	1,988	7.50	1,378	111	34	465	69.30	5.60	1.70	23.40	224	92V
018	08	SBD	R 96.577	A	VICTORVILLE, NORTH JCT RTE 15, BARSTOW FREEWAYJCT. RTE. 15	40,000	3,520	8.80	2,158	137	320	905	61.30	3.90	9.10	25.70	447	92V
018	08	SBD	100.956	B	JCT. RTE. 395	19,500	1,521	7.80	771	108	0	642	50.70	7.10	0.00	42.20	258	93V
018	08	SBD	100.956	A	JCT. RTE. 395	8,500	627	7.38	217	83	69	258	34.67	13.25	10.94	41.14	114	03E
018	07	LA	4.5	B	JCT. RTE. 138, PEARBLOSSOM/ANTELOPE HIGHWAY	5,200	504	9.69	175	67	55	207	34.67	13.25	10.94	41.14	92	02V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
019	07	LA	6.052	B	BELLFLOWER, JCT. RTE. 91, ARTESIA FREEWAY	48,000	1,070	2.23	775	115	30	150	72.41	10.75	2.80	14.04	94	06V
019	07	LA	6.052	A	BELLFLOWER, JCT. RTE. 91, ARTESIA FREEWAY	29,500	776	2.63	550	96	20	111	70.85	12.31	2.53	14.31	69	06V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
020	01	MEN	R 0	A	JCT. RTE. 1, FORT BRAGG, SOUTH	8,500	853	10.04	295	153	3	401	34.58	17.98	0.41	47.03	163	05E
020	01	MEN	17.285	A	CHAMBERLAIN CREEK	2,500	404	16.15	96	96	77	135	23.81	23.81	19.05	33.33	70	05E
020	01	MEN	R 33.159	B	NORTH JCT. RTE. 101	6,200	670	10.80	236	143	68	223	35.19	21.30	10.19	33.33	108	03E
020	01	LAK	8.319	B	JCT. RTE. 29 SOUTH	8,700	754	8.67	265	110	71	309	35.09	14.62	9.36	40.94	136	05E
020	01	LAK	8.319	A	JCT. RTE. 29 SOUTH	8,400	838	9.98	272	125	91	351	32.43	14.86	10.81	41.89	155	05E
020	01	LAK	12.199	B	LUCERNE CUTOFF	8,400	836	9.95	271	124	90	350	32.43	14.86	10.81	41.89	155	05E
020	01	LAK	12.199	A	LUCERNE CUTOFF	11,800	970	8.22	315	144	105	406	32.43	14.86	10.81	41.89	180	05E
020	01	LAK	18.53	B	LUCERNE, EAST; BELL RAY AVENUE	9,000	925	10.28	300	137	100	387	32.43	14.86	10.81	41.89	171	05E
020	01	LAK	31.62	B	JCT. RTE. 53 SOUTH	8,000	988	12.35	424	121	79	364	42.94	12.27	7.98	36.81	163	06E
020	01	LAK	31.62	A	JCT. RTE. 53 SOUTH	6,800	840	12.35	361	103	67	309	42.94	12.27	7.98	36.81	139	06E
020	03	COL	3.451	B	JCT. RTE. 16 SOUTH	5,200	757	14.55	325	93	60	279	42.94	12.27	7.98	36.81	125	06E
020	03	COL	3.451	A	JCT. RTE. 16 SOUTH	4,800	509	10.61	84	46	33	346	16.58	9.08	6.46	67.89	131	07E
020	03	COL	R 22.12	B	WILLIAMS, JCT. RTE. 5	5,900	626	10.61	104	57	40	425	16.58	9.08	6.46	67.89	161	07E
020	03	COL	R 22.12	A	WILLIAMS, JCT. RTE. 5	3,700	703	19.00	296	47	29	331	42.10	6.70	4.10	47.10	133	86E
020	03	COL	31.091	B	COLUSA, JCT. RTE. 45 NORTH	15,000	1,200	8.00	505	83	49	563	42.10	6.90	4.10	46.90	227	83E
020	03	COL	31.091	A	COLUSA, JCT. RTE. 45 NORTH	20,400	1,428	7.00	600	99	56	674	42.00	6.90	3.90	47.20	271	83E
020	03	COL	32.29	A	COLUSA, FREMONT STREET	11,000	770	7.00	323	54	30	363	42.00	7.00	3.90	47.10	146	86E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
020	03	SUT	9.176	B	ACACIA AVENUE	7,700	646	8.39	257	101	39	250	39.77	15.56	6.02	38.64	110	07E
020	03	SUT	9.176	A	ACACIA AVENUE	9,400	466	4.96	127	84	22	233	27.25	18.03	4.72	50.00	96	10V
020	03	SUT	R 15.598	B	JCT. RTE. 99	34,500	2,070	6.00	940	315	52	764	45.40	15.20	2.50	36.90	333	86E
020	03	SUT	15.573	A	JCT. RTE. 99	37,500	1,763	4.70	860	261	39	603	48.80	14.80	2.20	34.20	268	86E
020	03	SUT	17.057	O	SUTTER/YUBA COUNTY LINE	40,500	1,944	4.80	914	288	66	677	47.00	14.80	3.40	34.80	302	86V
020	03	YUB	0	O	SUTTER/YUBA COUNTY LINE	40,500	1,944	4.80	914	288	66	677	47.00	14.80	3.40	34.80	302	86V
020	03	YUB	0.989	B	MARYSVILLE, SOUTH JCT. RTE. 70	32,000	2,240	7.00	1,145	284	105	706	51.10	12.70	4.70	31.50	325	86E
020	03	YUB	1.472	A	NORTH JCT. RTE. 70	22,500	2,081	9.25	605	363	242	871	29.07	17.44	11.63	41.86	391	00E
020	03	YUB	R 1.98	B	MARYSVILLE, BUCHANAN STREET	19,200	1,908	9.94	555	333	222	799	29.07	17.44	11.63	41.86	358	00E
020	03	YUB	R 7.018	A	HALLWOOD BOULEVARD	10,700	754	7.05	167	226	152	209	22.09	29.97	20.16	27.72	121	10V
020	03	NEV	R 12.24	A	GRASS VALLEY, JCT. RTE. 49	43,500	3,045	7.00	1,523	305	305	914	50.00	10.00	10.00	30.00	442	86E
020	03	NEV	R 12.92	O	JCT. RTE. 174	34,500	2,243	6.50	1,077	224	269	673	48.00	10.00	12.00	30.00	330	85E
020	03	NEV	R 14.797	A	BRUNSWICK ROAD	32,500	1,950	6.00	975	195	195	585	50.00	10.00	10.00	30.00	283	83E
020	03	NEV	R 17.398	B	NEVADA CITY, EAST JCT. RTE. 49	17,000	901	5.30	472	137	12	280	52.40	15.20	1.30	31.10	127	86V
020	03	NEV	R 17.398	A	NEVADA CITY, EAST JCT. RTE. 49	6,100	642	10.52	290	113	63	176	45.10	17.65	9.80	27.45	91	00E
020	03	NEV	31.834	B	WASHINGTON ROAD	4,000	618	15.45	279	109	61	170	45.10	17.65	9.80	27.45	87	00E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
020	03	NEV	45.661	B	JCT RTE 80	2,600	276	10.63	97	49	32	97	35.29	17.65	11.76	35.29	46	00E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
022	07	LA	0	A	LONG BEACH, JCT. RTE. 1, PACIFIC COAST HIGHWAY	56,000	1,215	2.17	936	102	12	165	77.00	8.40	1.01	13.59	101	06V
022	12	ORA	R .65	B	JCT. RTE. 405	96,000	2,496	2.60	1,922	210	25	339	77.00	8.40	1.01	13.59	207	06E
022	12	ORA	R .66	A	JCT. RTE. 405	138,000	12,006	8.70	8,152	1,585	696	1,573	67.90	13.20	5.80	13.10	1,076	81E
022	12	ORA	R 3.587	B	GARDEN GROVE, JCT. RTE. 39	163,000	7,987	4.90	5,463	1,038	455	1,030	68.40	13.00	5.70	12.90	709	82E
022	12	ORA	R 3.587	A	GARDEN GROVE, JCT. RTE. 39	190,000	9,310	4.90	6,396	1,154	512	1,248	68.70	12.40	5.50	13.40	836	82E
022	12	ORA	R 7.829	B	GARDEN GROVE, HARBOR BOULEVARD	216,000	10,368	4.80	7,102	1,306	612	1,348	68.50	12.60	5.90	13.00	924	82E
022	12	ORA	R 7.829	A	GARDEN GROVE, HARBOR BOULEVARD	231,000	10,857	4.70	7,361	1,379	630	1,487	67.80	12.70	5.80	13.70	990	82E
022	12	ORA	R 10.478	B	SANTA ANA, JCT. RTES. 5 AND 57; SANTA ANA/ ORANGE FREEWAYS	254,000	11,430	4.50	7,738	1,520	583	1,589	67.70	13.30	5.10	13.90	1,045	82E
022	12	ORA	R 10.478	A	SANTA ANA, JCT. RTES. 5 AND 57; SANTA ANA/ ORANGE FREEWAYS	144,000	6,480	4.50	3,869	1,030	499	1,082	59.70	15.90	7.70	16.70	677	82E
022	12	ORA	R 13.164	B	JCT. RTE. 55, COSTA MESA FREEWAY	118,000	4,012	3.40	2,335	610	253	814	58.20	15.20	6.30	20.30	456	82V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
023	07	LA	0	A	JCT. RTE. 1, PACIFIC COAST HIGHWAY	640	10	1.60	10	0	0	0	100.00	0.00	0.00	0.00	0	06E
023	07	VEN	R 2.258	B	THOUSAND OAKS, TRIUNFO CANYON ROAD	16,000	534	3.34	381	67	14	72	71.35	12.54	2.66	13.45	46	06V
023	07	VEN	R 2.258	A	THOUSAND OAKS, TRIUNFO CANYON ROAD	23,000	593	2.58	390	74	31	98	65.81	12.40	5.22	16.58	59	06E
023	07	VEN	R 3.32	B	THOUSAND OAKS, JCT. RTE. 101, VENTURA FREEWAY INTERCHANGE	40,000	728	1.82	439	89	57	143	60.26	12.25	7.78	19.71	81	06V
023	07	VEN	R 3.339	A	THOUSAND OAKS, JCT. RTE. 101, VENTURA FREEWAY INTERCHANGE	106,000	2,788	2.63	1,952	476	200	160	70.03	17.07	7.16	5.74	197	10V
023	07	VEN	R 11.432	B	MOORPARK, JCT. RTE. 118, RONALD REAGAN FREEWAY INTERCHANGE; CONTINUE VIA NEW LOS ANGELES AVENUE	67,000	2,700	4.03	1,891	461	193	155	70.03	17.07	7.16	5.74	190	10E
023	07	VEN	T 12.26	B	MOORPARK, JCT. RTE. 118, NEW LOS ANGELES AVE	39,500	5,976	15.13	1,802	630	407	3,136	30.16	10.55	6.81	52.48	1,263	06V
023	07	VEN	R 12.9	A	MOORPARK, JCT. RTE. 118, NEW LOS ANGELES AVE	13,600	2,097	15.42	485	371	181	1,060	23.11	17.70	8.62	50.57	443	06V
023	07	VEN	14.607	B	SPRING ROAD	4,400	431	9.80	61	107	40	223	14.15	24.83	9.28	51.74	95	09V
023	07	VEN	14.607	A	SPRING ROAD	10,000	482	4.82	85	111	59	227	17.63	23.03	12.24	47.10	100	09V
023	07	VEN	16.8	A	GRIMES CANYON ROAD	6,100	1,223	20.05	272	89	45	817	22.24	7.26	3.72	66.78	306	06V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
023	07	VEN	24.165	B	FILLMORE, JCT. RTE. 126, VENTURA STREET	8,800	1,204	13.68	330	56	39	779	27.42	4.65	3.24	64.69	291	06V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
024	04	ALA	R 1.847	A	OAKLAND, JCT. RTES. 580 AND 980	152,000	3,770	2.48	2,318	625	135	692	61.49	16.58	3.57	18.35	397	00V
024	04	ALA	R 5.117	B	OAKLAND, JCT. RTE. 13	147,000	4,101	2.79	2,392	573	144	992	58.33	13.97	3.51	24.20	500	00V
024	04	ALA	R 5.117	A	OAKLAND, JCT. RTE. 13	148,000	2,975	2.01	1,871	301	91	712	62.89	10.13	3.05	23.93	352	03V
024	04	ALA	R 5.887	O	OAKLAND, CALDECOTT TUNNEL	155,000	3,503	2.26	2,394	373	132	604	68.35	10.64	3.76	17.25	346	02V
024	04	CC	R 2.319	A	CAMINO PABLO	163,000	4,075	2.50	2,262	538	167	1,108	55.50	13.20	4.10	27.20	535	97E
024	04	CC	R 7.656	B	LAFAYETTE, PLEASANT HILL ROAD	178,000	4,450	2.50	2,554	596	200	1,099	57.40	13.40	4.50	24.70	553	97E
024	04	CC	R 7.656	A	LAFAYETTE, PLEASANT HILL ROAD	179,000	6,265	3.50	3,396	720	219	1,930	54.20	11.50	3.50	30.80	883	97E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
025	05	MON	0	A	JCT. RTE. 198	200	50	25.00	26	11	0	12	52.90	22.80	0.00	24.30	6	98E
025	05	SBT	7.3	A	BITTER WATER/KING CITY ROAD	500	45	9.08	34	2	2	6	76.60	4.60	4.70	14.10	4	03E
025	05	SBT	21.47	B	JCT. RTE. 146 WEST	450	39	8.77	30	1	2	6	77.40	3.20	4.90	14.50	4	03E
025	05	SBT	21.47	A	JCT. RTE. 146 WEST	500	1	0.10	1	0	0	0	100.00	0.00	0.00	0.00	0	03E
025	05	SBT	39.533	B	PAICINES, PANOCHE ROAD	730	82	11.30	49	11	2	21	59.20	13.20	2.60	25.00	10	03E
025	05	SBT	L 52.233	B	HOLLISTER, SAN FELIPE ROAD&BOLSA	18,000	1,818	10.10	545	196	91	985	30.00	10.80	5.00	54.20	390	03E
025	05	SBT	51.454	A	HOLLISTER, SAN FELIPE ROAD&BOLSA	17,000	1,666	9.80	486	173	83	923	29.20	10.40	5.00	55.40	364	03E
025	04	SCL	2.528	B	GILROY, JCT RTE 101	22,400	1,458	6.51	772	190	99	398	52.93	13.00	6.77	27.30	196	01V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
026	10	SJ	1.11	B	JCT. RTE. 99	9,300	828	8.90	129	225	31	443	15.60	27.20	3.70	53.50	183	96E
026	10	SJ	1.11	A	JCT. RTE. 99	15,500	1,721	11.10	299	267	71	1,084	17.40	15.50	4.10	63.00	419	96E
026	10	SJ	1.897	B	CARDINAL AVENUE	13,500	1,350	10.00	235	209	55	851	17.40	15.50	4.10	63.00	329	96V
026	10	SJ	1.897	A	CARDINAL AVENUE	11,700	866	7.40	216	172	30	448	24.90	19.90	3.50	51.70	182	96E
026	10	SJ	6.85	B	JACKTONE ROAD	6,900	428	6.20	119	108	14	187	27.80	25.30	3.20	43.70	81	96V
026	10	SJ	6.85	A	JACKTONE ROAD	6,600	455	6.90	110	117	15	213	24.20	25.70	3.20	46.90	90	96V
026	10	SJ	11.08	B	LINDEN, FLOOD ROAD/FRONT STREET	5,400	378	7.00	91	82	8	197	24.20	21.70	2.00	52.10	80	96V
026	10	SJ	11.08	A	LINDEN, FLOOD ROAD/FRONT STREET	5,500	237	4.30	22	43	10	162	9.30	18.20	4.10	68.40	62	97V
026	10	SJ	15.06	B	ESCALON/BELLOTA ROAD	5,500	446	8.10	113	121	14	198	25.40	27.20	3.10	44.30	85	96V
026	10	SJ	15.06	A	ESCALON/BELLOTA ROAD	5,400	362	6.70	67	87	14	195	18.40	23.90	3.80	53.90	80	96V
026	10	CAL	R 4.379	B	JENNY LIND ROAD	4,000	272	6.80	37	50	9	176	13.70	18.40	3.20	64.70	68	96V
026	10	CAL	R 4.379	A	JENNY LIND ROAD	5,400	340	6.30	39	82	13	206	11.60	24.00	3.70	60.70	82	96V
026	10	CAL	8.53	B	LA CONTENTA COUNTRY CLUB ENTRANCE	10,600	572	5.40	63	120	17	372	11.00	20.90	3.00	65.10	144	96E
026	10	CAL	8.53	A	LA CONTENTA COUNTRY CLUB ENTRANCE	11,500	518	4.50	53	92	12	361	10.30	17.70	2.30	69.70	137	96V
026	10	CAL	10.302	B	VALLEY SPRINGS, JCT. RTE. 12	11,000	473	4.30	53	85	13	322	11.30	18.00	2.70	68.00	123	96E
026	10	CAL	10.435	A	VALLEY SPRINGS, JCT. RTE. 12	1,850	93	5.00	49	28	3	13	52.80	29.90	3.20	14.10	9	96V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
026	10	CAL	18.069	B	MOKELUMNE HILL, JCT. RTE. 49	1,900	84	4.43	37	21	3	23	43.50	25.50	3.50	27.50	12	96V
026	10	CAL	18.069	A	MOKELUMNE HILL, JCT. RTE. 49	2,100	96	4.59	26	22	3	46	26.60	22.50	3.50	47.40	19	96V
026	10	CAL	26.797	B	RIDGE ROAD	1,200	74	6.19	18	20	3	32	24.80	27.60	4.30	43.30	14	96V
026	10	CAL	26.797	A	RIDGE ROAD	1,350	69	5.10	12	31	3	23	17.60	44.80	3.80	33.80	12	96V
026	10	CAL	32.65	B	GLENCO, ASSOCIATED OFFICE ROAD	1,450	75	5.20	11	31	3	30	14.90	40.70	4.00	40.40	14	96E
026	10	CAL	32.65	A	GLENCO, ASSOCIATED OFFICE ROAD	700	36	5.20	4	13	1	17	12.20	36.50	3.60	47.70	7	96V
026	10	CAL	34.77	B	WINTON ROAD	1,750	74	4.20	6	23	3	41	8.70	31.60	4.00	55.70	17	96V
026	10	CAL	34.77	A	WINTON ROAD	1,950	74	3.80	7	22	3	42	8.80	30.20	4.00	57.00	17	96V
026	10	AMA	4.644	B	JCT. RTE. 88	2,850	174	6.10	15	60	7	92	8.70	34.50	3.90	52.90	39	96V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
027	07	LA	0	A	JCT. RTE. 1, PACIFIC COAST HIGHWAY	14,700	245	1.67	194	37	7	7	79.19	15.19	2.75	2.87	14	06V
027	07	LA	12.276	B	LOS ANGELES, VENTURA BOULEVARD	31,000	688	2.22	537	119	21	11	78.00	17.27	3.11	1.62	37	06V
027	07	LA	12.43	B	LOS ANGELES, JCT. RTE. 101, VENTURA FREEWAY	62,000	2,120	3.42	1,571	305	79	165	74.10	14.40	3.73	7.77	152	06E
027	07	LA	12.43	A	LOS ANGELES, JCT. RTE. 101, VENTURA FREEWAY	49,500	1,599	3.23	1,122	184	70	223	70.20	11.53	4.35	13.92	143	06V
027	07	LA	20.062	B	LOS ANGELES, JCT. RTE. 118, RONALD REAGAN FREEWAY	42,500	2,057	4.84	1,284	196	89	489	62.41	9.51	4.32	23.76	245	06V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
028	03	PLA	0.085	A	TAHOE CITY, JCT. RTE. 89	12,400	448	3.61	279	80	51	38	62.21	17.94	11.45	8.40	38	07E
028	03	PLA	4.25	A	LARDIN WAY	8,300	300	3.61	187	54	34	25	62.21	17.94	11.45	8.40	25	07E
028	03	PLA	9.34	B	KINGS BEACH, JCT. RTE. 267 NORTH	14,300	516	3.61	321	93	59	43	62.21	17.94	11.45	8.40	43	07E
028	03	PLA	9.34	A	KINGS BEACH, JCT. RTE. 267 NORTH	15,800	570	3.61	355	102	65	48	62.21	17.94	11.45	8.40	48	07E
028	03	PLA	11	B	CAL-NEVA DRIVE	13,200	477	3.61	297	86	55	40	62.21	17.94	11.45	8.40	40	07V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
029	04	SOL	0	A	VALLEJO, JCT. RTE. 80	8,500	321	3.78	183	31	20	87	57.10	9.68	6.13	27.10	42	02V
029	04	SOL	2.066	B	VALLEJO, MAINE STREET	12,300	459	3.73	338	44	19	59	73.53	9.56	4.04	12.87	39	02V
029	04	SOL	2.066	A	VALLEJO, MAINE STREET	12,400	474	3.82	352	45	21	56	74.33	9.45	4.46	11.76	39	02V
029	04	SOL	2.82	B	VALLEJO, TENNESSEE STREET	18,100	498	2.75	386	65	21	27	77.44	12.96	4.21	5.39	32	02V
029	04	SOL	2.82	A	VALLEJO, TENNESSEE STREET	14,000	522	3.73	414	54	12	42	79.35	10.41	2.28	7.97	36	02V
029	04	SOL	4.732	B	LEWIS BROWN DR	21,100	707	3.35	462	97	36	113	65.28	13.71	5.03	15.97	69	02V
029	04	SOL	4.732	A	LEWIS BROWN DR	27,000	2,144	7.94	778	233	59	1,074	36.31	10.86	2.75	50.08	428	99V
029	04	SOL	5.955	B	SOLANO/NAPA COUNTY LINE	29,500	2,041	6.92	912	258	54	817	44.67	12.63	2.67	40.02	345	02V
029	04	NAP	4.706	B	JCT. RTE. 12 EAST	40,000	2,780	6.95	1,074	291	86	1,329	38.62	10.48	3.08	47.82	536	02V
029	04	NAP	4.706	A	JCT. RTE. 12 EAST	59,000	3,705	6.28	1,679	480	80	1,466	45.31	12.96	2.16	39.56	620	02V
029	04	NAP	R 6.196	A	JCT. RTE. 221 NORTH	43,500	3,258	7.49	1,412	485	78	1,283	43.34	14.90	2.40	39.37	548	02V
029	04	NAP	R 8.657	A	JCT. RTE. 121 SOUTH	45,500	2,730	6.00	1,040	529	182	979	38.08	19.38	6.67	35.87	450	99V
029	04	NAP	10.305	A	NAPA, JCT. RTE. 121 NORTH	54,000	2,624	4.86	1,169	456	113	885	44.56	17.38	4.32	33.73	405	99V
029	04	NAP	11.548	A	FIRST STREET	59,000	1,988	3.37	828	342	76	743	41.63	17.19	3.83	37.35	328	99V
029	04	NAP	24.595	B	RUTHERFORD, JCT. RTE. 128 EAST	23,100	1,435	6.21	689	179	53	514	48.01	12.46	3.70	35.82	226	08V
029	04	NAP	24.595	A	RUTHERFORD, JCT. RTE. 128 EAST	20,600	1,485	7.21	721	210	46	509	48.53	14.14	3.08	34.25	227	08V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
029	04	NAP	28.75	A	ST. HELENA, ADAMS STREET	17,200	1,156	6.72	772	106	21	256	66.81	9.16	1.85	22.18	128	02V
029	04	NAP	36.893	B	CALISTOGA, JCT. RTE. 128 NORTHWEST	13,200	801	6.07	523	80	17	181	65.35	9.93	2.14	22.57	91	02V
029	04	NAP	36.893	A	CALISTOGA, JCT. RTE. 128 NORTHWEST	9,100	290	3.19	178	25	1	86	61.49	8.66	0.30	29.55	38	99V
029	04	NAP	37.902	B	CALISTOGA, SILVERADO TRAIL	4,600	189	4.11	144	16	2	27	76.24	8.29	1.10	14.36	16	08V
029	04	NAP	37.902	A	CALISTOGA, SILVERADO TRAIL	4,600	417	9.07	194	136	10	76	46.62	32.58	2.51	18.30	47	08V
029	01	LAK	5.811	B	MIDDLETOWN, JCT. RTE. 175	11,100	738	6.65	538	54	22	124	72.92	7.33	2.98	16.77	70	07E
029	01	LAK	5.811	A	MIDDLETOWN, JCT. RTE. 175	11,200	745	6.65	543	55	22	125	72.92	7.33	2.98	16.77	70	07E
029	01	LAK	20.31	B	JCT. RTE. 53 NORTH	10,900	725	6.65	529	53	22	122	72.92	7.33	2.98	16.77	69	07E
029	01	LAK	20.31	A	JCT. RTE. 53 NORTH	10,900	725	6.65	529	53	22	122	72.92	7.33	2.98	16.77	69	07E
029	01	LAK	31.05	B	JCT. RTE. 175	9,100	605	6.65	441	44	18	101	72.92	7.33	2.98	16.77	57	07E
029	01	LAK	31.05	A	JCT. RTE. 175	9,500	622	6.55	454	46	19	104	72.92	7.33	2.98	16.77	59	07E
029	01	LAK	R 40.14	B	JCT. RTE. 175	12,500	831	6.65	606	61	25	139	72.92	7.33	2.98	16.77	78	07V
029	01	LAK	R 40.14	A	JCT. RTE. 175	14,600	971	6.65	708	71	29	163	72.92	7.33	2.98	16.77	92	07E
029	01	LAK	52.539	B	JCT. RTE. 20, UPPER LAKE	5,900	392	6.65	286	29	12	66	72.92	7.33	2.98	16.77	37	07E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
032	03	GLE	L 0	A	JCT. RTE. 5	5,600	687	12.26	211	95	63	317	30.77	13.85	9.23	46.15	135	00E
032	03	GLE	9.626	B	JCT. RTE. 45 SOUTH	8,600	746	8.67	230	103	69	344	30.77	13.85	9.23	46.15	146	00E
032	03	GLE	9.626	A	JCT. RTE. 45 SOUTH	11,300	877	7.76	317	116	106	338	36.14	13.25	12.05	38.55	154	00E
032	03	BUT	7.79	B	WEST SACRAMENTO AVENUE	19,200	843	4.39	337	225	112	169	40.00	26.67	13.33	20.00	107	00E
032	03	BUT	7.79	A	WEST SACRAMENTO AVENUE	21,500	1,178	5.48	393	295	196	295	33.33	25.00	16.67	25.00	171	00E
032	03	BUT	10.187	B	CHICO, JCT. RTE. 99	33,800	1,548	4.58	516	387	258	387	33.33	25.00	16.67	25.00	225	00E
032	03	BUT	10.187	A	CHICO, JCT. RTE. 99	38,000	2,660	7.00	1,764	237	77	583	66.30	8.90	2.90	21.90	296	83E
032	03	BUT	11.27	A	CHICO, EL MONTE AVENUE	13,600	480	3.53	293	67	27	93	61.11	13.89	5.56	19.44	52	83E
032	02	TEH	0	A	BUTTE/TEHAMA COUNTY LINE	1,000	95	9.50	11	20	3	61	11.58	21.05	3.16	64.21	24	10V
032	02	TEH	R 24.876	B	JCT. RTE. 36	1,000	70	7.00	11	15	3	41	15.71	21.43	4.29	58.57	16	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
033	07	VEN	0	A	VENTURA, JCT. RTE. 101, VENTURA FREEWAY INTERCHANGE	41,000	992	2.42	787	115	28	62	79.30	11.61	2.84	6.25	64	10E
033	07	VEN	R 4.046	O	VENTURA, VENTURA AVENUE	27,500	869	3.16	689	101	25	54	79.30	11.61	2.84	6.25	56	10V
033	07	VEN	11.2	B	WEST JCT. RTE. 150, BALDWIN ROAD; ROUTE BREAK AHEAD	21,400	805	3.76	321	263	125	96	39.89	32.64	15.55	11.93	87	10E
033	07	VEN	11.21	A	WEST JCT. RTE. 150, BALDWIN ROAD; ROUTE BREAK AHEAD	11,500	353	3.07	195	78	19	61	55.10	22.22	5.49	17.19	38	10E
033	07	VEN	11.961	A	EL ROBLAR DRIVE	3,400	113	3.31	44	20	3	46	39.17	17.71	2.35	40.77	20	10E
033	07	VEN	13.35	O	LOS PADRES NATIONAL FOREST BOUNDARY	2,100	67	3.21	18	12	4	33	27.03	18.49	5.23	49.25	14	10E
033	07	VEN	30.219	O	SESPE GORGE MAINTENANCE STATION	460	37	8.03	5	4	1	28	12.97	10.11	2.39	74.53	10	10E
033	07	VEN	57.508	B	VENTURA/SANTA BARBARA COUNTY LINE	470	83	17.56	37	15	13	18	44.85	18.05	15.54	21.55	11	10E
033	05	SLO	2.775	B	JCT. RTE. 166 WEST	740	78	10.50	49	9	2	19	62.20	11.00	2.40	24.40	9	10E
033	05	SLO	2.802	A	JCT. RTE. 166 WEST	3,700	925	24.99	604	35	12	274	65.32	3.77	1.29	29.62	121	10E
033	06	KER	R 11.555	B	MARICOPA, JCT. RTE. 166 EAST	3,500	775	22.14	220	48	36	471	28.39	6.19	4.65	60.77	180	10V
033	06	KER	R 11.555	A	MARICOPA, JCT. RTE. 166 EAST	4,750	544	11.46	182	52	34	277	33.40	9.49	6.26	50.85	112	08E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
033	06	KER	17.889	B	TAFT, JCT. RTE. 119 EAST	6,500	845	13.00	282	80	54	429	33.33	9.52	6.35	50.79	173	06E
033	06	KER	17.889	A	TAFT, JCT. RTE. 119 EAST	5,350	696	13.00	232	66	44	353	33.33	9.52	6.35	50.79	142	06E
033	06	KER	19.129	B	LINCOLN/10TH STREETS	11,000	1,055	9.59	745	99	37	174	70.59	9.41	3.53	16.47	101	06E
033	06	KER	19.129	A	LINCOLN/10TH STREETS	11,000	1,055	9.59	745	99	37	174	70.59	9.41	3.53	16.47	101	06E
033	06	KER	23.41	B	MIDWAY ROAD	10,400	2,496	24.00	1,572	200	225	499	63.00	8.00	9.00	20.00	279	04E
033	06	KER	23.41	A	MIDWAY ROAD	3,700	1,422	38.44	1,040	104	46	231	73.17	7.32	3.25	16.26	132	06E
033	06	KER	33.454	B	JCT. RTE. 58 WEST	3,700	786	21.25	462	92	35	197	58.82	11.76	4.41	25.00	98	06E
033	06	KER	33.454	A	JCT. RTE. 58 WEST	2,750	504	18.33	275	64	18	147	54.55	12.73	3.64	29.09	69	06E
033	06	KER	34.285	A	JCT. RTE. 58 EAST	1,400	440	31.43	240	56	16	128	54.55	12.73	3.64	29.09	60	06E
033	06	KER	60.085	B	JCT. RTE. 46	1,150	357	31.00	195	45	13	104	54.55	12.73	3.64	29.09	49	06E
033	06	KER	60.085	A	JCT. RTE. 46	1,650	321	19.44	86	13	11	211	26.75	4.12	3.29	65.84	79	06E
033	06	KIN	7.8	B	REEF CITY, JCT. RTE. 41	1,300	104	8.00	73	3	2	26	70.00	3.00	2.00	25.00	12	04E
033	06	KIN	7.8	A	REEF CITY, JCT. RTE. 41	2,050	359	17.49	87	27	18	227	24.20	7.45	5.05	63.30	86	08V
033	06	FRE	8.02	B	ALPINE/LOST HILLS ROADS	2,100	147	7.00	84	9	1	53	57.00	6.00	1.00	36.00	22	04E
033	06	FRE	8.02	A	ALPINE/LOST HILLS ROADS	1,700	136	8.00	61	11	3	61	45.00	8.00	2.00	45.00	25	04E
033	06	FRE	14.75	B	MERCED AVENUE	7,000	532	7.60	295	62	36	139	55.39	11.70	6.76	26.14	69	08V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
033	06	FRE	15.707	B	COALINGA, JCT. RTE. 198 WEST	6,000	900	15.00	738	27	36	99	82.00	3.00	4.00	11.00	68	04E
033	06	FRE	15.707	A	COALINGA, JCT. RTE. 198 WEST	9,100	1,001	11.00	460	80	40	420	46.00	8.00	4.00	42.00	174	04E
033	06	FRE	16.78	A	COALINGA, PHELPS AVENUE	5,500	550	10.00	308	33	6	204	56.00	6.00	1.00	37.00	85	04E
033	06	FRE	R 18.588	B	GALE AVENUE	4,450	445	10.00	249	18	9	169	56.00	4.00	2.00	38.00	70	04E
033	06	FRE	24.316	B	JCT. RTE. 198 EAST	2,100	378	18.00	132	23	11	212	35.00	6.00	3.00	56.00	81	01V
033	06	FRE	24.316	A	JCT. RTE. 198 EAST	2,100	405	19.29	104	31	13	258	25.58	7.60	3.23	63.59	97	08V
033	06	FRE	R 29	B	JCT. RTE. 145 NORTHEAST, SOUTH JCT. RTE. 5	2,100	399	19.00	191	28	16	163	47.98	7.09	4.05	40.89	68	08E
033	06	FRE	R 39.853	A	NORTH JCT. RTE. 5	1,200	348	29.00	97	31	3	216	28.00	9.00	1.00	62.00	81	04E
033	06	FRE	62.247	B	MENDOTA, JCT. RTE. 180 EAST	5,600	1,624	29.00	438	162	16	1,007	27.00	10.00	1.00	62.00	380	04E
033	06	FRE	62.247	A	MENDOTA, JCT. RTE. 180 EAST	11,800	1,663	14.09	352	337	213	761	21.17	20.26	12.81	45.76	337	10E
033	06	FRE	70.557	B	FIREBAUGH, 8TH STREET	9,700	1,843	19.00	1,106	74	37	627	60.00	4.00	2.00	34.00	267	01V
033	06	FRE	70.557	A	FIREBAUGH, 8TH STREET	8,000	1,520	19.00	806	152	76	486	53.00	10.00	5.00	32.00	221	04E
033	06	FRE	R 79.905	B	BRANNON AVENUE	2,300	391	17.00	184	16	16	176	47.00	4.00	4.00	45.00	71	04E
033	06	FRE	R 79.905	A	BRANNON AVENUE	1,700	527	31.00	242	21	21	242	46.00	4.00	4.00	46.00	97	04E
033	10	MER	R 5.635	B	EAST JCT. RTE. 152	4,700	658	14.00	180	39	11	428	27.40	5.90	1.70	65.00	159	83E
033	10	MER	R 13.238	A	WEST JCT. RTE 152	7,400	2,250	30.40	414	52	115	1,670	18.40	2.30	5.10	74.20	612	88V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
033	10	MER	R 16.643	B	JCT. RTE. 5	9,300	2,641	28.40	325	248	42	2,026	12.30	9.40	1.60	76.70	739	97V
033	10	MER	16.643	A	JCT. RTE. 5	9,300	2,148	23.10	200	189	30	1,729	9.30	8.80	1.40	80.50	625	97V
033	10	MER	26.464	B	NORTH JCT. RTE. 140 EAST	4,300	847	19.70	151	59	25	612	17.80	7.00	2.90	72.30	226	97E
033	10	MER	27.111	A	NORTH JCT. RTE. 140 EAST	7,000	980	14.00	167	78	49	686	17.00	8.00	5.00	70.00	257	98V
033	10	STA	6.838	A	CROWS LANDING, CROWS LANDING/FINK ROADS	3,400	323	9.50	149	70	13	91	46.20	21.70	3.90	28.20	45	79V
033	10	SJ	0.818	B	VERNALIS, JCT. RTE. 132	1,550	321	20.69	161	65	12	83	50.00	20.20	3.80	26.00	42	79E
033	10	SJ	0.818	A	VERNALIS, JCT. RTE. 132	2,900	479	16.51	240	95	20	124	50.10	19.80	4.20	25.90	63	79E
033	10	SJ	4.826	B	JCT. RTE. 5	2,850	467	16.40	234	92	20	121	50.10	19.80	4.20	25.90	61	79E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
034	07	VEN	4.295	A	OXNARD, JCT. RTE. 1, OXNARD BOULEVARD	13,500	736	5.45	475	80	33	148	64.48	10.90	4.47	20.15	80	06V
034	07	VEN	5.285	B	OXNARD, ROSE AVENUE	15,000	2,109	14.06	1,002	445	137	526	47.50	21.10	6.48	24.92	278	06V
034	07	VEN	6.27	A	OXNARD, RICE AVENUE	11,800	944	8.00	442	169	86	248	46.80	17.85	9.06	26.29	129	06V
034	07	VEN	R 13.603	B	CAMARILLO, JCT. RTE. 101, VENTURA FREEWAY	20,100	3,099	15.42	644	919	776	760	20.79	29.66	25.04	24.51	483	06V
034	07	VEN	13.603	A	CAMARILLO, JCT. RTE. 101, VENTURA FREEWAY	20,100	4,022	20.01	960	1,040	882	1,140	23.86	25.86	21.94	28.34	652	06V
034	07	VEN	17.663	B	SOMIS, JCT. RTE. 118, LOS ANGELES AVENUE	12,400	1,758	14.18	602	201	184	771	34.24	11.45	10.48	43.83	333	06V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
035	04	SCL	R .053	A	JCT. RTE. 17	720	56	7.81	52	3	0	1	92.68	4.88	0.00	2.44	2	02V
035	04	SCL	14.1	B	JCT. RTE. 9	920	15	1.59	9	4	2	0	60.87	26.09	13.04	0.00	1	02V
035	04	SCL	14.1	A	JCT. RTE. 9	920	16	1.70	11	0	0	5	71.40	0.00	0.00	28.60	2	96V
035	04	SM	10.518	B	WOODSIDE, JCT. RTE. 84	1,750	80	4.56	43	30	2	4	54.08	37.76	3.06	5.10	6	05V
035	04	SM	23.037	B	JCT. RTE. 92	2,050	27	1.31	24	0	2	2	88.89	0.00	5.56	5.56	2	99V
035	04	SM	L 21.72	A	JCT. RTE. 92	3,050	266	8.73	154	30	2	80	57.89	11.15	0.93	30.03	36	05V
035	04	SM	L 23.037	B	JCT. RTE. 280	3,050	40	1.30	34	2	0	4	85.42	4.17	0.00	10.42	3	05V
035	04	SM	R 23.037	A	JCT. RTE. 280	14,300	139	0.97	102	14	3	20	73.68	9.87	1.97	14.47	12	02V
035	04	SM	R 28.687	B	DALY CITY, JCT. RTE. 1	30,000	330	1.10	242	40	20	28	73.44	11.98	5.99	8.59	25	02V
035	04	SM	R 28.687	A	DALY CITY, JCT. RTE. 1	30,500	317	1.04	256	22	23	16	80.78	6.96	7.24	5.01	20	02V
035	04	SM	30.834	B	JOHN DALY BOULEVARD	28,000	308	1.10	222	44	8	34	71.97	14.33	2.55	11.15	25	08V
035	04	SM	30.834	A	JOHN DALY BOULEVARD	22,700	232	1.02	157	38	4	34	67.61	16.19	1.62	14.57	21	08V
035	04	SF	3.164	B	SAN FRANCISCO, JCT. RTE. 1	23,900	249	1.04	203	21	5	21	81.52	8.33	1.81	8.33	17	02V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
036	01	HUM	0	A	ALTON, JCT. RTE. 101	4,300	785	18.25	301	226	43	215	38.36	28.77	5.48	27.40	112	06E
036	01	HUM	2.811	B	HYDESVILLE, ROHNERVILLE ROAD	4,000	789	19.73	303	227	43	216	38.36	28.77	5.48	27.40	112	06E
036	01	HUM	2.811	A	HYDESVILLE, ROHNERVILLE ROAD	4,000	215	5.38	25	30	10	150	11.63	13.95	4.65	69.77	57	06E
036	01	HUM	7.54	O	CARLOTTA, EAST	1,900	163	8.60	19	23	8	114	11.63	13.95	4.65	69.77	43	06E
036	02	TRI	27.23	B	JCT. RTE. 3 NORTH	520	30	5.77	7	7	1	15	23.33	23.33	3.33	50.00	6	09V
036	02	TRI	R 41.139	B	TRINITY/SHASTA COUNTY LINE	300	22	7.43	2	6	1	13	9.79	26.17	3.40	60.64	5	09E
036	02	SHA	0	A	TRINITY/SHASTA COUNTY LINE	300	22	7.36	2	6	1	13	9.79	26.17	3.40	60.64	5	09E
036	02	SHA	8.87	B	PLATINA ROAD	650	59	9.08	17	16	1	25	28.81	27.12	1.69	42.37	11	09V
036	02	SHA	8.87	A	PLATINA ROAD	570	43	7.61	10	13	2	18	24.26	29.73	5.30	40.71	8	09E
036	02	SHA	11.928	B	SHASTA/TEHAMA COUNTY LINE	570	36	6.33	7	11	2	16	19.85	31.76	4.72	43.67	7	09E
036	02	TEH	23.2	B	BOWMAN ROAD	520	29	5.52	10	6	3	10	35.71	19.05	9.52	35.71	5	09E
036	02	TEH	23.2	A	BOWMAN ROAD	470	22	4.73	9	4	3	7	40.23	17.24	11.49	31.03	4	09E
036	02	TEH	39.72	B	BAKER ROAD	3,450	90	2.61	16	11	3	60	17.78	12.22	3.33	66.67	23	09V
036	02	TEH	39.72	A	BAKER ROAD	3,250	186	5.71	75	27	34	50	40.30	14.50	18.30	26.90	27	09E
036	02	TEH	L 39.734	A	NORTH MAIN STREET	6,900	362	5.25	40	46	24	252	11.05	12.71	6.63	69.61	96	09V
036	02	TEH	L 40.87	A	RED BLUFF, CRITTENDEN STREET	9,400	266	2.83	111	25	64	66	41.90	9.30	23.90	24.90	38	09E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
036	02	TEH	L 41.29	B	RED BLUFF, OAK STREET	12,300	271	2.20	146	54	30	41	53.90	19.80	11.10	15.20	29	09E
036	02	TEH	L 41.29	A	RED BLUFF, OAK STREET	20,900	334	1.60	176	68	37	52	52.70	20.40	11.20	15.70	36	09E
036	02	TEH	41.847	B	RED BLUFF, JCT. RTE. 5	21,500	366	1.70	198	72	41	55	54.10	19.70	11.10	15.10	39	09E
036	02	TEH	41.847	A	RED BLUFF, JCT. RTE. 5	19,500	1,326	6.80	362	134	69	761	27.30	10.10	5.20	57.40	298	09E
036	02	TEH	42.79	A	RED BLUFF, CHESTNUT AVENUE	16,200	1,312	8.10	358	126	70	758	27.30	9.60	5.30	57.80	296	09E
036	02	TEH	43.28	B	HOY ROAD	16,200	1,539	9.50	419	149	82	890	27.20	9.70	5.30	57.80	347	09E
036	02	TEH	43.28	A	HOY ROAD	11,700	893	7.63	243	87	47	516	27.20	9.70	5.30	57.80	201	09E
036	02	TEH	44.004	A	JCT. RTE. 99 SOUTH	2,000	136	6.80	12	41	3	80	8.82	30.15	2.21	58.82	32	09V
036	02	TEH	55.26	A	MANTON ROAD	1,200	82	6.82	16	12	4	50	19.36	14.30	5.03	61.31	20	10E
036	02	TEH	58.18	A	PAYNES CREEK	1,100	75	6.82	14	12	4	45	18.67	16.00	5.33	60.00	18	10V
036	02	TEH	83.142	B	MINERAL, JCT. RTE. 172 SOUTHEAST	1,000	104	10.40	32	14	6	52	30.77	13.46	5.77	50.00	21	10V
036	02	TEH	87.681	O	JCT. RTE. 89 NORTH	1,100	83	7.55	23	11	4	45	28.06	13.07	5.00	53.87	18	10E
036	02	TEH	91.253	B	MORGAN SPRINGS, JCT. RTE. 172 SOUTHWEST	700	68	9.71	18	9	3	38	26.71	12.87	4.61	55.81	15	10E
036	02	TEH	99.935	B	JCT. RTE. 32 SOUTHWEST	730	71	9.73	18	9	3	41	25.35	12.68	4.23	57.75	16	10V
036	02	TEH	104.002	B	TEHAMA/PLUMAS COUNTY LINE	1,800	180	10.00	45	27	6	102	25.00	14.80	3.57	56.63	40	10E
036	02	PLU	6.287	B	JCT. RTE. 89	1,800	196	10.89	49	29	7	111	25.00	14.80	3.57	56.63	44	10V
036	02	PLU	6.287	A	JCT. RTE. 89	3,350	362	10.81	81	62	11	208	22.38	17.13	3.04	57.46	82	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
036	02	PLU	8.08	O	FARRAR DRIVE	3,600	300	8.33	58	47	10	186	19.20	15.53	3.21	62.06	72	10E
036	02	PLU	8.84	O	FEATHER RIVER BRIDGE	5,900	268	4.54	47	39	9	172	17.62	14.72	3.29	64.36	66	10E
036	02	PLU	9.18	O	CHESTER, MELISSA AVENUE	5,100	237	4.65	38	33	8	158	16.03	13.92	3.38	66.67	60	10V
036	02	PLU	R 13.93	A	BIG SPRINGS ROAD	1,900	142	7.47	23	20	5	94	16.20	14.08	3.52	66.20	36	10E
036	02	PLU	18.421	O	PLUMAS/LASSEN COUNTY LINE	2,300	142	6.17	23	20	5	94	16.20	14.08	3.52	66.20	36	10E
036	02	LAS	0	O	PLUMAS/LASSEN COUNTY LINE	2,300	142	6.17	23	20	5	94	16.20	14.08	3.52	66.20	36	10E
036	02	LAS	0.76	B	JCT. RTE. 147 SOUTH	1,900	142	7.47	23	20	5	94	16.20	14.08	3.52	66.20	36	10E
036	02	LAS	3.706	B	WESTWOOD, COUNTY ROAD A 21	2,300	172	7.48	55	20	8	89	31.98	11.63	4.65	51.74	36	10V
036	02	LAS	3.706	A	WESTWOOD, COUNTY ROAD A 21	2,400	180	7.50	57	21	8	94	31.67	11.67	4.44	52.22	38	10E
036	02	LAS	R 19.196	B	JCT. RTE. 44 NORTHWEST	2,400	191	7.96	77	25	8	81	40.31	13.09	4.19	42.41	34	10V
036	02	LAS	R 19.196	A	JCT. RTE. 44 NORTHWEST	3,750	499	13.31	99	47	24	329	19.84	9.42	4.81	65.93	125	10V
036	02	LAS	22.06	A	EAGLE LAKE ROAD	5,300	409	7.72	57	34	13	305	13.94	8.31	3.18	74.57	112	10V
036	02	LAS	25.05	A	SUSANVILLE, PACIFIC STREET	12,400	485	3.91	58	38	18	371	11.96	7.84	3.71	76.49	136	10E
036	02	LAS	25.356	A	SUSANVILLE, JCT. RTE. 139 NORTH	14,500	597	4.12	60	43	25	469	10.03	7.19	4.18	78.60	172	10E
036	02	LAS	25.94	B	RIVERSIDE DRIVE	14,500	655	4.52	60	45	28	522	9.16	6.87	4.27	79.69	190	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
036	02	LAS	R 26.22	A	SUSANVILLE, JOHNSTONVILLE ROAD	9,500	712	7.49	61	48	32	571	8.57	6.74	4.49	80.20	208	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
037	04	MRN	R 11.2	A	NOVATO, JCT. RTE. 101	35,000	1,288	3.68	464	127	49	648	36.05	9.83	3.78	50.34	259	05V
037	04	MRN	14.473	B	PETALUMA CREEK	34,500	1,280	3.71	596	101	41	542	46.55	7.90	3.19	42.37	223	02V
037	04	SON	3.9	B	JCT. RTE. 121 NORTH	44,000	1,993	4.53	403	109	60	1,421	20.23	5.45	3.00	71.31	523	05V
037	04	SON	3.9	A	JCT. RTE. 121 NORTH	33,500	2,164	6.46	396	94	48	1,625	18.30	4.35	2.24	75.11	590	05V
037	04	SOL	R 7.213	B	WALNUT AVENUE	33,500	4,204	12.55	1,498	337	149	2,220	35.64	8.02	3.54	52.80	871	02V
037	04	SOL	R 11.73	B	JCT. RTE. 80	97,000	5,684	5.86	1,087	381	129	4,087	19.12	6.70	2.27	71.91	1,502	05V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
038	08	SBD	0	A	REDLANDS, JCT. RTE. 10	23,000	2,070	9.00	1,346	352	83	290	65.00	17.00	4.00	14.00	192	86V
038	08	SBD	R 9.72	A	SAN BERNARDINO NATIONAL FOREST BOUNDARY	5,500	495	9.00	342	45	0	109	69.00	9.00	0.00	22.00	54	92E
038	08	SBD	14.99	B	VALLEY OF THE FALLS DRIVE	5,500	699	12.70	480	64	0	155	68.70	9.10	0.00	22.20	76	92V
038	08	SBD	14.99	A	VALLEY OF THE FALLS DRIVE	3,900	507	13.00	350	46	0	112	69.00	9.00	0.00	22.00	55	92V
038	08	SBD	48.16	A	BIG BEAR CITY, BIG BEAR BOULEVARD	12,000	1,560	13.00	1,232	78	0	250	79.00	5.00	0.00	16.00	137	92E
038	08	SBD	49.52	B	JCT. RTE. 18	14,800	2,516	17.00	1,985	111	8	413	78.90	4.40	0.30	16.40	223	92V
038	08	SBD	49.53	A	JCT. RTE. 18	4,000	400	10.00	260	43	0	97	65.10	10.70	0.00	24.20	47	92V
038	08	SBD	59.396	B	BIG BEAR DAM, JCT. RTE. 18	1,600	195	12.20	152	30	0	13	77.70	15.50	0.00	6.80	13	92V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
039	12	ORA	0	A	HUNTINGTON BEACH, JCT. RTE. 1	26,000	562	2.16	424	65	16	57	75.36	11.59	2.90	10.14	43	00E
039	12	ORA	3.12	B	HUNTINGTON BEACH, MAIN STREET/ELLIS AVENUE	61,000	824	1.35	543	112	56	112	65.91	13.64	6.82	13.64	76	00E
039	12	ORA	3.12	A	HUNTINGTON BEACH, MAIN STREET/ELLIS AVENUE	65,000	702	1.08	463	96	48	96	65.91	13.64	6.82	13.64	65	00E
039	12	ORA	5.8	B	HUNTINGTON BEACH, JCT. RTE. 405, SAN DIEGO FREEWAY	72,000	1,274	1.77	845	126	76	227	66.34	9.90	5.94	17.82	131	00E
039	12	ORA	5.8	A	HUNTINGTON BEACH, JCT. RTE. 405, SAN DIEGO FREEWAY	77,000	1,317	1.71	874	130	78	235	66.34	9.90	5.94	17.82	135	00E
039	12	ORA	8.478	B	WESTMINSTER, JCT. RTE. 22, GARDEN GROVE FREEWAY	67,000	1,635	2.44	1,095	212	77	251	66.95	12.99	4.68	15.38	156	00E
039	12	ORA	8.478	A	WESTMINSTER, JCT. RTE. 22, GARDEN GROVE FREEWAY	65,000	1,638	2.52	1,055	231	92	260	64.39	14.12	5.61	15.88	161	00E
039	12	ORA	12.685	B	ANAHEIM, LINCOLN AVENUE	57,000	1,414	2.48	910	200	79	225	64.35	14.14	5.62	15.89	139	98E
039	12	ORA	12.685	A	ANAHEIM, LINCOLN AVENUE	59,000	1,758	2.98	1,130	190	86	352	64.30	10.78	4.90	20.02	191	00E
039	12	ORA	14.378	B	BUENA PARK, JCT. RTE. 91, ARTESIA FREEWAY	57,000	1,385	2.43	810	213	91	271	58.49	15.36	6.56	19.59	155	00E
039	12	ORA	14.378	A	BUENA PARK, JCT. RTE. 91, ARTESIA FREEWAY	51,000	1,030	2.02	603	158	65	204	58.56	15.32	6.31	19.82	116	98E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
039	12	ORA	19.168	B	LA HABRA, JCT. RTE. 90 EAST	44,000	2,288	5.20	1,563	169	55	501	68.30	7.40	2.40	21.90	251	89V
039	12	ORA	19.168	A	LA HABRA, JCT. RTE. 90 EAST	39,000	1,404	3.60	1,154	107	44	100	82.20	7.60	3.10	7.10	91	89V
039	12	ORA	20.719	B	LA HABRA, JCT. RTE. 72	28,000	924	3.30	681	85	30	128	73.70	9.20	3.20	13.90	80	89V
039	12	ORA	22.6	B	HARBOR BOULEVARD	31,000	930	3.00	640	128	53	109	68.80	13.80	5.70	11.70	80	89V
039	07	LA	17.813	A	SAN GABRIEL RIVER BRIDGE	1,900	88	4.62	63	17	4	4	71.22	18.88	4.84	5.06	6	06V
039	07	LA	25.71	B	EAST FORK ROAD	1,550	72	4.62	51	14	3	4	71.22	18.88	4.84	5.06	5	06E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
040	08	SBD	0	A	BARSTOW, JCT. RTE. 15	18,000	7,560	42.00	828	110	57	6,565	10.95	1.46	0.76	86.84	2,312	06E
040	08	SBD	R 7.181	B	A STREET	16,200	5,955	36.76	652	87	45	5,171	10.95	1.46	0.76	86.84	1,821	06E
040	08	SBD	R 7.181	A	A STREET	14,000	5,880	42.00	644	86	45	5,106	10.95	1.46	0.76	86.84	1,799	06E
040	08	SBD	R 12.191	B	AIRPORT ROAD	14,000	5,880	42.00	644	86	45	5,106	10.95	1.46	0.76	86.84	1,799	06E
040	08	SBD	R 18.446	A	WEST NEWBERRY ROAD	12,600	5,988	47.52	607	81	47	5,253	10.14	1.35	0.78	87.73	1,848	08V
040	08	SBD	R132.739	A	JCT. RTE. 95 NORTH	15,000	6,375	42.50	698	93	48	5,536	10.95	1.46	0.76	86.84	1,950	06E
040	08	SBD	R139.117	A	PARK ROAD	12,700	5,652	44.50	619	83	43	4,908	10.95	1.46	0.76	86.84	1,729	06E
040	08	SBD	R143.764	B	JCT. RTE. 95 SOUTH	14,600	6,716	46.00	735	81	51	5,843	10.95	1.20	0.76	87.00	2,057	06E
040	08	SBD	R143.764	A	JCT. RTE. 95 SOUTH	12,000	6,456	53.80	707	90	53	5,606	10.95	1.40	0.82	86.84	1,975	06E
040	08	SBD	R154.643	B	ARIZONA STATE LINE	12,400	6,671	53.80	730	93	55	5,793	10.95	1.40	0.82	86.84	2,041	06E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
041	05	SLO	0	A	MORRO BAY, JCT. RTE. 1	6,000	252	4.20	177	23	23	29	70.40	9.00	9.00	11.60	22	10E
041	05	SLO	15.894	B	ATASCADERO, JCT. RTE. 101	10,100	404	4.00	256	40	44	64	63.30	9.90	10.90	15.90	41	10E
041	05	SLO	15.894	A	ATASCADERO, JCT. RTE. 101	11,000	396	3.60	236	66	28	66	59.50	16.70	7.10	16.70	41	10E
041	05	SLO	27.975	B	JCT. RTE. 229 SOUTH (TO CRESTON)	1,900	67	3.50	42	0	0	25	63.20	0.00	0.00	36.80	10	10E
041	05	SLO	27.975	A	JCT. RTE. 229 SOUTH (TO CRESTON)	2,300	108	4.70	66	0	0	42	61.50	0.00	0.00	38.50	17	10E
041	05	SLO	41.159	B	MC MILLAN CANYON ROAD	780	205	26.30	178	8	0	19	86.80	4.10	0.00	9.10	14	10E
041	05	SLO	41.159	A	MC MILLAN CANYON ROAD	1,700	211	12.40	164	23	0	23	77.80	11.10	0.00	11.10	16	10E
041	05	SLO	43.81	B	JCT. RTE. 46	900	112	12.40	86	14	0	12	76.50	12.40	0.00	11.10	8	10E
041	05	SLO	43.85	A	JCT. RTE. 46	8,000	816	10.20	298	29	109	381	36.50	3.50	13.30	46.70	161	10E
041	06	KIN	8.098	B	REEF CITY, JCT. RTE. 33	5,600	1,005	17.95	293	110	90	512	29.15	10.95	8.96	50.95	210	10V
041	06	KIN	8.098	A	REEF CITY, JCT. RTE. 33	6,400	930	14.53	342	96	85	407	36.77	10.32	9.14	43.76	174	10V
041	06	KIN	16.275	B	JCT. RTE. 5	6,400	930	14.53	342	96	85	407	36.77	10.32	9.14	43.76	174	10V
041	06	KIN	20.08	B	QUAIL AVENUE	5,600	1,018	18.18	267	200	134	417	26.23	19.65	13.16	40.96	191	10E
041	06	KIN	R 37.792	B	JACKSON AVENUE	7,500	1,490	19.87	442	141	73	834	29.66	9.46	4.90	55.97	327	10E
041	06	KIN	R 39.962	B	JCT RTE 198	7,700	1,232	16.00	641	62	37	493	52.00	5.00	3.00	40.00	204	04E
041	06	KIN	R 39.962	A	JCT RTE 198	14,100	1,833	13.00	568	147	147	971	31.00	8.00	8.00	53.00	390	01V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
041	06	KIN	R 42.148	A	BELLI CORNER, HANFORD-ARMONA ROAD	19,700	2,561	13.00	1,204	230	230	896	47.00	9.00	9.00	35.00	406	01E
041	06	KIN	R 48.283	B	EXCELSIOR AVE; KINGS/FRESNO COUNTY LINE	15,700	2,512	16.00	980	201	151	1,181	39.00	8.00	6.00	47.00	482	01E
041	06	FRE	R 0	A	EXCELSIOR AVE; KINGS/FRESNO COUNTY LINE	16,300	2,782	17.07	1,432	117	89	1,144	51.49	4.20	3.20	41.11	469	10E
041	06	FRE	R 23.736	B	FRESNO, DIVISADERO STREET	93,500	3,740	4.00	2,618	449	150	524	70.00	12.00	4.00	14.00	336	04E
041	06	FRE	R 24.527	A	FRESNO, JCT. RTE. 180S	122,000	4,880	4.00	3,416	586	146	732	70.00	12.00	3.00	15.00	447	04E
041	06	FRE	R 25.266	A	FRESNO, MC KINLEY AVENUE	121,000	4,840	4.00	3,098	436	145	1,162	64.00	9.00	3.00	24.00	571	04E
041	06	FRE	R 30.447	B	FRESNO, HERNDON AVENUE	93,000	4,650	5.00	2,325	930	465	930	50.00	20.00	10.00	20.00	556	04E
041	06	FRE	R 30.447	A	FRESNO, HERNDON AVENUE	64,000	3,200	5.00	2,048	288	96	768	64.00	9.00	3.00	24.00	377	04E
041	06	FRE	R 31.683	A	FRESNO, FRIANT ROAD	48,500	2,963	6.11	2,410	165	112	276	81.35	5.57	3.78	9.31	211	08V
041	06	MAD	9.25	B	JCT. RTE. 145 WEST	13,500	1,350	10.00	959	122	108	162	71.00	9.00	8.00	12.00	117	04E
041	06	MAD	9.25	A	JCT. RTE. 145 WEST	14,500	1,402	9.67	995	126	112	168	71.00	9.00	8.00	12.00	121	04V
041	06	MAD	17.91	B	COUNTY ROAD 200	17,000	510	3.00	327	87	43	53	64.12	17.06	8.43	10.39	44	10V
041	06	MAD	38.889	B	YOSEMITE FORKS, BASS LAKE ROAD	10,300	852	8.27	448	209	107	88	52.58	24.53	12.56	10.33	81	10V
041	06	MAD	38.889	A	YOSEMITE FORKS, BASS LAKE ROAD	6,200	513	8.27	364	103	21	26	71.00	20.00	4.00	5.00	34	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
041	06	MPA	4.918	B	FISH CAMP, ENTRANCE TO YOSEMITE NATIONAL PARK	1,650	116	7.00	89	12	7	8	77.00	10.00	6.00	7.00	8	04E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
043	06	KER	0.111	A	JCT. RTE. 119	5,500	1,110	20.18	430	120	80	480	38.74	10.81	7.21	43.24	203	06E
043	06	KER	1.9	B	JCT. RTE. 5	5,500	1,110	20.18	430	120	80	480	38.74	10.81	7.21	43.24	203	06V
043	06	KER	1.9	A	JCT. RTE. 5	5,400	1,110	20.56	430	120	80	480	38.74	10.81	7.21	43.24	203	06E
043	06	KER	8.112	B	JCT. RTE. 58 EAST	5,500	1,110	20.18	430	120	80	480	38.74	10.81	7.21	43.24	203	06E
043	06	KER	8.112	A	JCT. RTE. 58 EAST	9,000	1,816	20.18	704	196	131	785	38.74	10.81	7.21	43.24	333	06E
043	06	KER	9.162	A	JCT. RTE. 58 WEST	4,700	1,351	28.75	685	137	59	470	50.72	10.14	4.35	34.78	207	06V
043	06	KER	15.89	B	CENTRAL VALLEY HIGHWAY	3,300	528	16.00	312	21	26	169	59.00	4.00	5.00	32.00	75	04E
043	06	KER	15.89	A	CENTRAL VALLEY HIGHWAY	10,000	1,000	10.00	580	50	70	300	58.00	5.00	7.00	30.00	139	04E
043	06	KER	R 21.289	B	WASCO AVENUE	10,800	972	9.00	642	87	39	204	66.00	9.00	4.00	21.00	107	04E
043	06	KER	R 21.289	A	WASCO AVENUE	10,500	1,155	11.00	716	104	58	277	62.00	9.00	5.00	24.00	139	04E
043	06	KER	R 25.125	B	JCT. RTE. 46	6,300	756	12.00	431	83	68	174	57.00	11.00	9.00	23.00	93	03E
043	06	KER	25.187	A	JCT. RTE. 46	3,700	629	17.00	352	63	50	164	56.00	10.00	8.00	26.00	82	04E
043	06	TUL	7.76	B	AVENUE 56	2,900	812	28.00	414	24	16	357	51.00	3.00	2.00	44.00	142	01E
043	06	TUL	22.133	B	CORCORAN, RAILROAD DRIVE	3,900	892	22.87	172	122	57	541	19.28	13.68	6.39	60.65	212	08V
043	06	KIN	1.456	B	JCT. RTE. 137	5,200	1,456	28.00	233	116	44	1,063	16.00	8.00	3.00	73.00	392	99E
043	06	KIN	1.456	A	JCT. RTE. 137	4,100	1,148	28.00	138	80	34	895	12.00	7.00	3.00	78.00	326	08E
043	06	KIN	10.359	B	KANSAS AVENUE	7,300	876	12.00	237	140	44	456	27.00	16.00	5.00	52.00	185	01E
043	06	KIN	10.359	A	KANSAS AVENUE	5,500	550	10.00	127	66	28	330	23.00	12.00	5.00	60.00	128	01E
043	06	KIN	18.238	B	JCT. RTE. 198	8,600	1,865	21.69	948	59	189	669	50.83	3.16	10.13	35.87	297	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
043	06	KIN	18.429	B	LACEY BOULEVARD	10,300	1,648	16.00	709	214	82	643	43.00	13.00	5.00	39.00	278	01E
043	06	KIN	22.272	A	10TH AVENUE	10,400	1,828	17.58	1,197	122	70	439	65.48	6.67	3.83	24.02	215	10V
043	06	FRE	8.34	B	NEBRASKA AVENUE	12,200	2,440	20.00	708	220	98	1,415	29.00	9.00	4.00	58.00	548	01E
043	06	FRE	8.34	A	NEBRASKA AVENUE	13,200	1,848	14.00	517	222	92	1,016	28.00	12.00	5.00	55.00	403	01E
043	06	FRE	9.308	B	JCT. RTE. 99; SELMA, WEST	18,500	2,590	14.00	751	311	104	1,425	29.00	12.00	4.00	55.00	562	01E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
044	02	SHA	L .54	A	END INDEP ALIGN RT LNS	37,500	300	0.80	127	51	14	109	42.23	16.89	4.59	36.29	49	10E
044	02	SHA	L .852	A	REDDING, BUTTE STREET	49,000	348	0.71	153	60	18	117	43.93	17.18	5.13	33.76	54	10E
044	02	SHA	L 1.808	B	REDDING, JCT. RTE. 5	49,000	348	0.71	154	59	19	116	44.29	16.89	5.48	33.33	54	10E
044	02	SHA	R 0	A	REDDING, JCT. RTE. 5	48,000	566	1.18	180	137	31	218	31.86	24.21	5.41	38.52	99	10E
044	02	SHA	R .134	A	HILLTOP DRIVE	33,500	566	1.69	184	153	27	203	32.48	27.01	4.72	35.80	95	10E
044	02	SHA	R 1.239	A	REDDING, VICTOR AVENUE	32,500	569	1.75	265	122	21	162	46.49	21.40	3.68	28.42	79	10V
044	02	SHA	R 2.131	A	SHASTA VIEW DRIVE	20,500	554	2.70	215	128	18	193	38.88	23.04	3.20	34.88	89	10E
044	02	SHA	R 3.627	A	AIRPORT ROAD	15,800	1,270	8.04	362	67	44	797	28.50	5.28	3.46	62.76	300	09V
044	02	SHA	R 10.77	B	MILLVILLE PLAINS	5,400	399	7.39	92	43	11	253	23.04	10.69	2.85	63.42	96	09V
044	02	SHA	R 10.77	A	MILLVILLE PLAINS	4,000	234	5.85	36	45	15	138	15.44	19.12	6.62	58.82	55	09E
044	02	SHA	R 19.01	B	DERSCH ROAD	3,500	194	5.55	30	37	13	114	15.57	18.85	6.56	59.02	46	09E
044	02	SHA	R 19.01	A	DERSCH ROAD	4,300	289	6.73	57	59	9	164	19.61	20.26	3.27	56.86	65	09V
044	02	SHA	R 27.83	A	SHINGLETOWN	3,700	274	7.41	94	58	13	109	34.26	21.30	4.63	39.81	48	10E
044	02	SHA	42.818	B	VIOLA	1,200	97	8.08	29	13	5	50	29.90	13.40	5.15	51.55	20	10V
044	02	SHA	42.818	A	VIOLA	1,200	92	7.67	20	16	4	52	21.74	17.39	4.35	56.52	21	10E
044	02	SHA	R 49.353	A	LASSEN VOLCANIC NATIONAL PARK	1,200	90	7.50	15	18	4	53	16.67	20.00	4.44	58.89	21	10E
044	02	SHA	62.685	B	JCT. RTE. 89 NORTHWEST	1,200	87	7.25	10	19	3	55	11.49	21.84	3.45	63.22	22	10V
044	02	SHA	62.685	A	JCT. RTE. 89 NORTHWEST	1,700	332	19.53	30	30	13	259	9.04	9.04	3.92	78.01	95	10V
044	02	SHA	71.389	O	SHASTA/LASSEN COUNTY LINE	1,800	274	15.22	37	17	10	210	13.50	6.20	3.65	76.64	77	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
044	02	LAS	0	O	SHASTA/LASSEN COUNTY LINE	1,800	274	15.22	37	17	10	210	13.50	6.20	3.65	76.64	77	10E
044	02	LAS	19.29	B	COUNTY ROAD A 21	1,650	274	16.61	37	17	10	210	13.50	6.20	3.65	76.64	77	10V
044	02	LAS	19.29	A	COUNTY ROAD A 21	1,550	194	12.52	22	13	7	152	11.34	6.70	3.61	78.35	55	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
045	03	YOL	0	A	KNIGHTS LANDING, JCT. RTE. 113	860	145	16.86	23	29	19	74	15.86	20.00	13.10	51.03	32	07E
045	03	COL	12.867	B	GRIMES-ARBUCKLE ROAD	1,300	247	19.00	25	30	19	173	10.00	12.11	7.89	70.00	66	07E
045	03	COL	12.867	A	GRIMES-ARBUCKLE ROAD	1,000	190	19.00	19	23	15	133	10.00	12.11	7.89	70.00	51	07E
045	03	COL	19.84	B	JCT. RTE. 20	710	86	12.11	48	9	7	22	55.31	10.88	8.26	25.56	11	07E
045	03	COL	19.85	A	JCT. RTE. 20	6,100	739	12.11	409	80	61	189	55.31	10.88	8.26	25.56	96	07E
045	03	COL	20.08	A	COLUSA, LURLINE AVENUE	7,100	381	5.37	96	76	45	164	25.20	19.95	11.81	43.03	74	10V
045	03	COL	32.06	B	COUNTY ROAD P29	2,100	188	8.95	33	25	7	123	17.55	13.30	3.72	65.43	47	07E
045	03	GLE	3.059	B	JCT. RTE. 162 EAST	2,300	354	15.39	156	42	26	130	44.07	11.86	7.34	36.72	58	07E
045	03	GLE	3.059	A	JCT. RTE. 162 EAST	1,550	124	8.00	34	18	5	67	27.21	14.71	3.68	54.41	27	07E
045	03	GLE	7.527	B	JCT. RTE. 162 WEST	1,550	133	8.59	35	24	5	69	26.03	17.81	4.11	52.05	28	07E
045	03	GLE	7.527	A	JCT. RTE. 162 WEST	2,500	139	5.56	41	24	8	66	29.50	17.27	5.76	47.48	28	07E
045	03	GLE	22.68	B	HAMILTON CITY, WEST FIRST STREET	2,250	125	5.56	37	22	7	59	29.50	17.27	5.76	47.48	25	07E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
046	05	SLO	R .146	A	JCT. RTE. 1, PACIFIC COAST HIGHWAY	3,700	122	3.30	83	19	9	11	67.70	15.60	7.30	9.40	10	10E
046	05	SLO	R 21.969	B	SOUTH JCT. RTE. 101	6,200	439	7.08	285	53	46	54	64.94	12.18	10.53	12.35	40	10V
046	05	SLO	29.761	A	SOUTH JCT. RTE. 101	30,000	2,595	8.65	913	86	58	1,538	35.19	3.33	2.22	59.26	579	10E
046	05	SLO	32.145	A	PASO ROBLES AIRPORT ROAD	18,400	2,214	12.03	1,601	162	149	302	72.29	7.32	6.75	13.64	197	10V
046	05	SLO	48.625	B	JCT. RTE. 41 SOUTH	10,200	2,213	21.70	674	73	39	1,427	30.46	3.30	1.76	64.48	528	10V
046	05	SLO	48.625	A	JCT. RTE. 41 SOUTH	15,000	2,556	17.04	889	96	58	1,511	34.79	3.77	2.27	59.13	570	10E
046	05	SLO	55.106	A	JCT. RTE. 41 NORTHEAST	7,000	1,512	21.60	313	109	133	957	20.70	7.20	8.80	63.30	371	10V
046	06	KER	20.543	B	BLACKWELLS CORNER, JCT. RTE. 33	10,500	1,986	18.91	713	79	52	1,142	35.88	3.99	2.64	57.49	434	07V
046	06	KER	20.543	A	BLACKWELLS CORNER, JCT. RTE. 33	10,500	1,986	18.91	713	79	52	1,142	35.88	3.99	2.64	57.49	434	07E
046	06	KER	32.533	B	JCT. RTE. 5	10,000	1,993	19.93	704	78	47	1,164	35.32	3.91	2.36	58.40	440	10V
046	06	KER	32.533	A	JCT. RTE. 5	6,100	2,379	39.00	404	167	95	1,713	17.00	7.00	4.00	72.00	634	03V
046	06	KER	50.904	B	WASCO, JCT. RTE. 43 SOUTH	8,900	3,026	34.00	878	91	91	1,967	29.00	3.00	3.00	65.00	731	03E
046	06	KER	51.215	A	WASCO, JCT. RTE. 43 NORTH	9,600	3,264	34.00	947	98	98	2,122	29.00	3.00	3.00	65.00	789	04E
046	06	KER	57.785	B	FAMOSO, JCT. RTE. 99	7,700	3,080	40.00	893	92	92	2,002	29.00	3.00	3.00	65.00	744	04E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
047	07	LA	R 0	A	LOS ANGELES, JCT. RTE. 110, HARBOR FREEWAY	50,000	5,510	11.02	1,441	1,655	146	2,268	26.15	30.03	2.65	41.16	1,007	10E
047	07	LA	0.722	A	LOS ANGELES, HARBOR BOULEVARD	48,000	5,290	11.02	1,383	1,589	140	2,177	26.15	30.03	2.65	41.16	966	10V
047	07	LA	3.88	B	LONG BEACH, HEIM LIFT BRIDGE	13,800	7,556	54.75	341	2,900	93	4,222	4.51	38.38	1.23	55.88	1,749	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
049	06	MAD	0	A	OAKHURST, JCT. RTE. 41	13,285	1,063	8.00	702	213	0	149	66.00	20.00	0.00	14.00	96	04E
049	06	MAD	8.235	B	COUNTY ROAD 601	4,300	344	8.00	224	69	3	48	65.00	20.00	1.00	14.00	31	04E
049	06	MAD	8.235	A	COUNTY ROAD 601	3,900	234	6.00	147	47	2	37	63.00	20.00	1.00	16.00	23	04E
049	06	MAD	9.275	O	MADERA/MARIPOSA COUNTY LINE	3,950	174	4.40	167	1	4	2	96.00	0.60	2.30	1.10	7	86E
049	10	MPA	0.332	O	MADERA/MARIPOSA COUNTY LINE	3,950	174	4.40	167	1	4	2	96.00	0.60	2.30	1.10	7	86E
049	10	MPA	18.5	B	MARIPOSA, JCT. RTE. 140	7,900	103	1.30	80	13	0	10	78.10	12.30	0.00	9.60	7	86E
049	10	MPA	18.51	A	MARIPOSA, JCT. RTE. 140	6,600	198	3.00	157	28	0	14	79.10	13.90	0.00	7.00	13	85E
049	10	MPA	44.67	B	COULTERVILLE, JCT. RTE. 132 WEST	680	33	4.90	26	5	0	2	78.00	14.70	0.00	7.30	2	85E
049	10	MPA	44.67	A	COULTERVILLE, JCT. RTE. 132 WEST	750	54	7.20	37	13	0	4	69.40	24.10	0.00	6.50	4	85E
049	10	TUO	R 6.468	B	JCT. RTE. 120	820	63	7.70	32	26	0	5	51.00	41.10	0.00	7.90	5	85E
049	10	TUO	R 8.779	A	JCT. RTE. 120	1,800	184	10.20	69	62	5	48	37.40	33.80	2.90	25.90	25	95V
049	10	TUO	R 11.587	B	SOUTH JCT. RTE. 108; MONTEZUMA ROAD	2,800	233	8.31	45	73	7	109	19.10	31.30	2.90	46.70	47	95V
049	10	TUO	R 11.587	A	SOUTH JCT. RTE. 108; MONTEZUMA ROAD	14,200	852	6.00	128	170	68	486	15.00	20.00	8.00	57.00	198	01V
049	10	TUO	16.48	B	SONORA, EAST JCT. RTE. 108	23,500	2,350	10.00	125	531	103	1,591	5.30	22.60	4.40	67.70	617	97V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
049	10	TUO	17.965	B	SONORA, JCT. RTE. 108U; WASHINGTON STREET	11,500	759	6.60	231	187	36	304	30.50	24.70	4.70	40.10	135	95E
049	10	TUO	17.965	A	SONORA, JCT. RTE. 108U; WASHINGTON STREET	18,300	1,281	7.00	402	277	60	542	31.40	21.60	4.70	42.30	235	95E
049	10	TUO	20.4	A	COLUMBIA WYE	5,050	303	6.00	27	58	97	121	9.00	19.00	32.00	40.00	62	01V
049	10	TUO	23.709	B	RAWHIDE ROAD	5,500	275	5.00	39	88	33	116	14.00	32.00	12.00	42.00	54	01V
049	10	TUO	23.709	A	RAWHIDE ROAD	4,550	273	6.00	41	90	38	104	15.00	33.00	14.00	38.00	51	01V
049	10	CAL	R 0	A	TUOLUMNE/CALAVERAS COUNTY LINE	5,600	224	4.00	52	43	29	101	23.00	19.00	13.00	45.00	45	01V
049	10	CAL	7.21	B	ANGELS CAMP, SOUTH JCT. RTE. 4	9,100	637	7.00	64	185	89	299	10.00	29.00	14.00	47.00	135	01V
049	10	CAL	7.21	A	ANGELS CAMP, SOUTH JCT. RTE. 4	14,500	1,305	9.00	131	378	248	548	10.00	29.00	19.00	42.00	265	01V
049	10	CAL	8.667	B	NORTH JCT. RTE. 4	11,000	484	4.40	130	187	22	145	26.80	38.60	4.60	30.00	75	01E
049	10	CAL	8.667	A	NORTH JCT. RTE. 4	8,700	348	4.00	66	94	28	160	19.00	27.00	8.00	46.00	70	01V
049	10	CAL	18.794	B	MOUNTAIN RANCH ROAD	7,300	365	5.00	55	99	55	157	15.00	27.00	15.00	43.00	73	01V
049	10	CAL	18.794	A	MOUNTAIN RANCH ROAD	10,500	525	5.00	68	163	79	215	13.00	31.00	15.00	41.00	103	01V
049	10	CAL	20.496	B	JCT. RTE. 12 WEST	9,000	549	6.10	82	159	60	247	15.00	29.00	11.00	45.00	112	01V
049	10	CAL	R 20.496	A	JCT. RTE. 12 WEST	4,300	292	6.80	84	103	14	91	28.70	35.30	4.90	31.10	46	96V
049	10	CAL	27.614	B	MOKELUMNE HILL, JCT. RTE. 26	4,100	295	7.19	78	89	12	116	26.30	30.30	4.20	39.20	53	96V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
049	10	CAL	27.614	A	MOKELUMNE HILL, JCT. RTE. 26	6,100	415	6.80	72	122	20	202	17.30	29.30	4.80	48.60	86	96V
049	10	AMA	4.029	B	JACKSON, SOUTH JCT. RTE. 88	18,900	1,739	9.20	633	377	78	650	36.40	21.70	4.50	37.40	293	96V
049	10	AMA	4.029	A	JACKSON, SOUTH JCT. RTE. 88	20,900	1,484	7.10	364	325	59	736	24.50	21.90	4.00	49.60	305	96V
049	10	AMA	5.934	B	MARTELL, NORTH JCT. RTE. 88 WEST	18,100	1,303	7.20	427	331	53	491	32.80	25.40	4.10	37.70	223	96E
049	10	AMA	5.934	A	MARTELL, NORTH JCT. RTE. 88 WEST	12,000	672	5.60	196	182	46	248	29.10	27.10	6.90	36.90	116	96E
049	10	AMA	6.98	A	SUTER CREEK, JCT. RTE. 104 WEST	16,800	958	5.70	286	256	60	355	29.90	26.70	6.30	37.10	165	96V
049	10	AMA	14.723	B	CENTRAL HOUSE, JCT. RTE. 16 WEST	11,000	902	8.20	271	335	14	283	30.00	37.10	1.50	31.40	140	96V
049	10	AMA	14.723	A	CENTRAL HOUSE, JCT. RTE. 16 WEST	11,400	912	8.00	210	328	72	302	23.00	36.00	7.90	33.10	152	96V
049	10	AMA	22.116	O	AMADOR/EL DORADO COUNTY LINE	2,200	208	9.44	152	18	7	32	72.86	8.63	3.14	15.29	19	07E
049	03	ED	0	O	AMADOR/EL DORADO COUNTY LINE	2,200	208	9.44	152	18	7	32	72.86	8.63	3.14	15.29	19	07E
049	03	ED	9.641	A	EL DORADO, PLEASANT VALLEY ROAD	13,500	1,274	9.44	928	110	40	195	72.86	8.63	3.14	15.29	116	07E
049	03	ED	14.856	B	PLACERVILLE, JCT. RTE. 50	10,600	985	9.29	718	85	31	151	72.86	8.63	3.14	15.29	90	07E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
049	03	ED	14.891	A	PLACERVILLE, JCT. RTE. 50	6,800	408	6.00	224	82	24	78	54.90	20.10	6.00	19.00	46	83E
049	03	ED	15.685	B	JCT. RTE. 193 NORTH	5,100	286	5.60	212	21	1	51	74.20	7.50	0.40	17.90	27	84V
049	03	ED	15.685	A	JCT. RTE. 193 NORTH	4,700	169	3.60	141	12	2	13	83.60	7.10	1.40	7.90	11	84V
049	03	ED	22.865	B	COLOMA, JCT. RTE. 153 WEST	2,250	68	3.00	34	5	1	28	50.00	7.40	1.90	40.70	11	88E
049	03	ED	22.865	A	COLOMA, JCT. RTE. 153 WEST	5,400	378	7.00	191	40	10	137	50.50	10.60	2.70	36.20	59	83E
049	03	ED	34.466	B	COOL, JCT. RTE. 193 EAST	3,500	497	14.20	170	136	10	180	34.20	27.40	2.10	36.30	82	89V
049	03	ED	34.466	A	COOL, JCT. RTE. 193 EAST	8,600	628	7.30	242	177	14	194	38.60	28.20	2.30	30.90	94	89V
049	03	PLA	3.208	B	AUBURN, JCT. RTE. 80	14,500	1,173	8.09	763	138	45	226	65.05	11.79	3.87	19.29	124	04E
049	03	PLA	3.208	A	AUBURN, JCT. RTE. 80	32,000	970	3.03	631	114	38	187	65.05	11.79	3.87	19.29	103	04E
049	03	PLA	5.21	B	LUTHER ROAD	33,500	884	2.64	575	104	34	171	65.05	11.79	3.87	19.29	94	04E
049	03	PLA	5.21	A	LUTHER ROAD	48,000	1,214	2.53	790	143	47	234	65.05	11.79	3.87	19.29	128	04E
049	03	PLA	7.427	A	DRY CREEK ROAD	28,000	1,212	4.33	788	143	47	234	65.05	11.79	3.87	19.29	128	04V
049	03	PLA	R 8.973	A	LORENSEN RD	28,500	1,325	4.65	973	87	36	229	73.43	6.57	2.72	17.28	126	10E
049	03	NEV	9.22	B	ALTA SIERRA DRIVE	22,000	1,177	5.35	741	142	51	244	62.93	12.07	4.31	20.69	131	02E
049	03	NEV	R 14.475	B	NEVADA CITY, JCT. RTE. 20	31,000	1,163	3.75	715	143	48	257	61.48	12.30	4.10	22.13	134	00E
049	03	NEV	15.062	A	NEVADA CITY, JCT. RTE. 20	11,100	290	2.61	110	90	60	30	37.93	31.03	20.69	10.34	31	06E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
049	03	YUB	3.59	A	MARYSVILLE ROAD	1,000	70	6.95	46	10	3	12	65.75	13.70	4.11	16.44	7	86E
049	03	SIE	47.44	B	SATTLEY, JCT. RTE. 89	330	31	9.50	8	7	1	16	24.44	22.22	3.33	50.00	7	06E
049	03	SIE	47.45	A	SATTLEY, JCT. RTE. 89	950	90	9.47	22	20	3	45	24.44	22.22	3.33	50.00	19	06E
049	03	SIE	47.86	A	SIERRAVILLE, LEMON CANYON ROAD	1,400	174	12.43	74	22	10	68	42.53	12.64	5.75	39.08	30	09E
049	02	PLU	0	A	SIERRA/PLUMAS COUNTY LINE	880	56	6.36	16	8	1	31	28.57	14.29	1.79	55.36	12	10E
049	02	PLU	3.92	A	DYSON LANE	1,100	58	5.27	16	9	2	31	27.59	15.52	3.45	53.45	12	10E
049	02	PLU	7.5	B	JCT. RTE. 70	1,100	58	5.27	16	9	2	31	27.59	15.52	3.45	53.45	12	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
050	03	YOL	0	A	JCT. RTE. 80 EAST	86,000	5,951	6.92	2,524	561	249	2,617	42.41	9.43	4.18	43.98	1,079	04E
050	03	YOL	2.498	B	JCT. RTE. 84	111,000	6,249	5.63	2,650	589	261	2,748	42.41	9.43	4.18	43.98	1,133	04E
050	03	SAC	L .35	B	SACRAMENTO, JCT. RTE. 5	174,000	7,012	4.03	2,974	661	293	3,084	42.41	9.43	4.18	43.98	1,272	04E
050	03	SAC	L .35	A	SACRAMENTO, JCT. RTE. 5	226,000	6,012	2.66	2,612	610	275	2,515	43.44	10.14	4.58	41.84	1,056	04E
050	03	SAC	L 1.37	A	SACRAMENTO, JCT. RTE. 160 15TH/16TH STREETS	246,000	5,707	2.32	2,479	579	261	2,388	43.44	10.14	4.58	41.84	1,002	04E
050	03	SAC	R 0	A	JCT. RTES. 51/99	216,000	8,014	3.71	4,055	1,255	579	2,125	50.60	15.66	7.23	26.51	1,076	04E
050	03	SAC	R 2.628	B	SACRAMENTO, 65TH STREET	200,000	8,300	4.15	4,200	1,300	600	2,200	50.60	15.66	7.23	26.51	1,114	04E
050	03	SAC	R 2.628	A	SACRAMENTO, 65TH STREET	206,000	8,343	4.05	4,222	1,307	603	2,212	50.60	15.66	7.23	26.51	1,120	04E
050	03	SAC	R 3.674	A	JCT. RTE. 16	179,000	7,840	4.38	4,090	1,214	538	1,998	52.17	15.49	6.86	25.48	1,023	04V
050	03	SAC	12.496	B	SUNRISE BOULEVARD	141,000	7,811	5.54	3,709	1,378	604	2,120	47.49	17.64	7.73	27.14	1,077	02E
050	03	SAC	12.496	A	SUNRISE BOULEVARD	119,000	7,616	6.40	3,046	914	305	3,351	40.00	12.00	4.00	44.00	1,392	83E
050	03	SAC	15.759	A	NIMBUS ROAD	113,000	7,119	6.30	2,947	861	214	3,097	41.40	12.10	3.00	43.50	1,282	83E
050	03	SAC	17.008	B	FOLSOM BOULEVARD/NATOMA	112,000	6,720	6.00	2,822	874	202	2,822	42.00	13.00	3.00	42.00	1,182	83E
050	03	SAC	17.008	A	FOLSOM BOULEVARD/NATOMA	90,000	4,500	5.00	1,544	585	162	2,210	34.30	13.00	3.60	49.10	894	85V
050	03	SAC	21.502	A	SCOTT ROAD	93,000	5,952	6.40	2,542	815	143	2,452	42.70	13.70	2.40	41.20	1,031	83E
050	03	ED	R 10.295	B	EAST SHINGLE SPRINGS	47,500	2,850	6.00	1,217	390	68	1,174	42.70	13.70	2.40	41.20	494	83E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
050	03	ED	R 10.295	A	EAST SHINGLE SPRINGS	47,000	2,820	6.00	1,238	353	65	1,165	43.90	12.50	2.30	41.30	487	83E
050	03	ED	15.829	B	PLACERVILLE, FAIRGROUNDS	52,000	3,120	6.00	1,370	390	72	1,289	43.90	12.50	2.30	41.30	539	83E
050	03	ED	17.667	B	PLACERVILLE, JCT. RTE. 49	45,000	2,700	6.00	1,185	338	62	1,115	43.90	12.50	2.30	41.30	466	83E
050	03	ED	17.667	A	PLACERVILLE, JCT. RTE. 49	40,000	2,400	6.00	967	324	50	1,058	40.30	13.50	2.10	44.10	436	83E
050	03	ED	20.296	B	PLACERVILLE, POINT VIEW DRIVE	25,000	1,550	6.20	620	186	47	698	40.00	12.00	3.00	45.00	287	83E
050	03	ED	R 25.949	B	EAST CAMINO ROAD	17,200	1,204	7.00	470	144	36	554	39.00	12.00	3.00	46.00	226	83E
050	03	ED	R 31.299	A	SLY PARK ROAD	9,700	631	6.50	240	74	20	297	38.10	11.80	3.10	47.00	121	83E
050	03	ED	39.772	B	ICEHOUSE ROAD	12,700	800	6.30	294	105	17	384	36.80	13.10	2.10	48.00	155	83V
050	03	ED	39.772	A	ICEHOUSE ROAD	13,100	537	4.10	294	25	19	200	54.70	4.60	3.50	37.20	84	83V
050	03	ED	70.621	B	JCT. RTE. 89 SOUTH	10,700	332	3.10	172	15	6	138	51.90	4.50	1.90	41.70	56	83V
050	03	ED	70.621	A	JCT. RTE. 89 SOUTH	13,100	406	3.10	207	26	6	166	51.10	6.50	1.60	40.80	68	83V
050	03	ED	75.448	B	SOUTH LAKE TAHOE, JCT. RTE. 89 NORTH	19,000	760	4.00	447	70	15	228	58.80	9.20	2.00	30.00	103	83E
050	03	ED	75.448	A	SOUTH LAKE TAHOE, JCT. RTE. 89 NORTH	33,000	1,320	4.00	1,032	129	20	139	78.20	9.80	1.50	10.50	99	84V
050	03	ED	80.44	B	NEVADA STATE LINE	26,500	822	3.10	686	39	8	89	83.40	4.80	1.00	10.80	59	83V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
051	03	SAC	0	A	SACRAMENTO, JCT. RTES. 50/99	156,000	8,440	5.41	4,382	791	454	2,814	51.92	9.37	5.38	33.34	1,264	04E
051	03	SAC	3.357	B	SACRAMENTO, EXPOSITION BOULEVARD	159,000	5,533	3.48	1,677	932	573	2,351	30.31	16.85	10.35	42.49	1,040	10V
051	03	SAC	3.688	B	SACRAMENTO, JCT. RTE. 160 WEST	117,000	7,102	6.07	3,914	646	363	2,179	55.11	9.09	5.11	30.68	1,002	06E
051	03	SAC	3.688	A	SACRAMENTO, JCT. RTE. 160 WEST	151,000	7,052	4.67	3,661	661	379	2,351	51.92	9.37	5.38	33.34	1,056	04E
051	03	SAC	6.788	A	SACRAMENTO, FULTON AVENUE	137,000	7,809	5.70	4,607	781	156	2,265	59.00	10.00	2.00	29.00	1,037	83E
051	03	SAC	8.86	B	JCT. RTE. 80 WEST	123,000	7,011	5.70	4,151	687	161	2,012	59.20	9.80	2.30	28.70	926	81V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
052	11	SD	0.324	A	JCT. RTE. 5	80,000	2,640	3.30	1,798	383	63	396	68.10	14.50	2.40	15.00	244	87E
052	11	SD	2.292	B	SAN DIEGO, GENESEE AVENUE	79,000	2,607	3.30	1,775	378	63	391	68.10	14.50	2.40	15.00	241	87E
052	11	SD	3.761	B	JCT. RTE. 805	86,000	2,666	3.10	1,853	475	83	256	69.50	17.80	3.10	9.60	209	96E
052	11	SD	8.713	A	SANTO ROAD	78,000	2,028	2.60	1,590	256	37	146	78.40	12.60	1.80	7.20	135	96E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
053	01	LAK	0	A	LOWER LAKE, JCT. RTE. 29	17,500	875	5.00	438	96	9	333	50.00	11.00	1.00	38.00	140	93E
053	01	LAK	7.445	B	JCT. RTE. 20	7,900	498	6.30	243	57	4	194	48.80	11.40	0.90	38.90	81	95E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
054	11	SD	1.88	A	JCT. RTE. 805	126,000	3,276	2.60	2,568	413	59	236	78.40	12.60	1.80	7.20	218	96E
054	11	SD	2.968	B	REO DRIVE	126,000	2,394	1.90	1,877	302	43	172	78.40	12.60	1.80	7.20	159	96E
054	11	SD	T 10.993	A	JCT. RTE. 94	35,500	1,385	3.90	1,006	198	14	168	72.60	14.30	1.00	12.10	113	87V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
055	12	ORA	0	A	TUSTIN, FINLEY AVENUE	47,000	752	1.60	593	105	21	32	78.90	14.00	2.80	4.30	45	81E
055	12	ORA	0.267	A	JCT. RTE. 1	54,000	1,944	3.60	1,376	299	54	214	70.80	15.40	2.80	11.00	157	81E
055	12	ORA	R 5.99	B	JCT. RTE. 405, SAN DIEGO FREEWAY	142,000	4,970	3.50	3,469	825	134	542	69.80	16.60	2.70	10.90	404	79E
055	12	ORA	R 5.99	A	JCT. RTE. 405, SAN DIEGO FREEWAY	232,000	4,872	2.10	2,568	653	341	1,311	52.70	13.40	7.00	26.90	652	84V
055	12	ORA	R 6.99	A	SANTA ANA, MAC ARTHUR BOULEVARD	251,000	14,558	5.80	8,866	2,096	830	2,766	60.90	14.40	5.70	19.00	1,579	84V
055	12	ORA	10.45	B	TUSTIN, JCT. RTE. 5, SANTA ANA FREEWAY	259,000	17,094	6.60	10,051	1,658	923	4,462	58.80	9.70	5.40	26.10	2,179	84V
055	12	ORA	10.45	A	TUSTIN, JCT. RTE. 5, SANTA ANA FREEWAY	243,000	18,711	7.70	10,385	2,058	1,366	4,902	55.50	11.00	7.30	26.20	2,445	83E
055	12	ORA	12.967	B	JCT. RTE. 22 WEST, GARDEN GROVE FREEWAY	251,000	18,825	7.50	10,410	1,995	1,412	5,007	55.30	10.60	7.50	26.60	2,483	83E
055	12	ORA	12.967	A	JCT. RTE. 22 WEST, GARDEN GROVE FREEWAY	251,000	14,809	5.90	8,856	1,540	652	3,761	59.80	10.40	4.40	25.40	1,845	84E
055	12	ORA	13.7	A	CHAPMAN AVENUE	230,000	13,570	5.90	8,115	1,411	597	3,447	59.80	10.40	4.40	25.40	1,691	84E
055	12	ORA	R 17.876	B	JCT RTE 91	213,000	12,567	5.90	7,515	1,307	553	3,192	59.80	10.40	4.40	25.40	1,566	84E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
057	12	ORA	10.83	A	ORANGE, JCT. RTES. 5 AND 22, SANTA ANA/GARDEN GROVE FREEWAYS	220,000	13,508	6.14	4,563	1,101	340	7,505	33.78	8.15	2.52	55.56	2,900	08E
057	12	ORA	15.6	B	ANAHEIM, JCT. RTE. 91, RIVERSIDE FREEWAY	241,000	14,797	6.14	4,998	1,206	373	8,221	33.78	8.15	2.52	55.56	3,177	08E
057	12	ORA	15.6	A	ANAHEIM, JCT. RTE. 91, RIVERSIDE FREEWAY	273,000	16,762	6.14	5,662	1,366	422	9,313	33.78	8.15	2.52	55.56	3,599	08E
057	12	ORA	19.858	B	BREA, JCT. RTE. 90	248,000	15,227	6.14	5,144	1,241	384	8,460	33.78	8.15	2.52	55.56	3,269	08E
057	12	ORA	19.858	A	BREA, JCT. RTE. 90	236,000	14,490	6.14	4,895	1,181	365	8,051	33.78	8.15	2.52	55.56	3,111	08E
057	07	LA	R 0	A	ORANGE/LOS ANGELES COUNTY LINE	205,000	15,621	7.62	5,700	1,240	434	8,246	36.49	7.94	2.78	52.79	3,222	10E
057	07	LA	R 4.518	B	DIAMOND BAR, NORTH JCT. RTE. 60, POMONA FREEWAY INTERCHANGE	201,000	15,316	7.62	5,589	1,216	426	8,085	36.49	7.94	2.78	52.79	3,159	10E
057	07	LA	R 4.518	A	DIAMOND BAR, NORTH JCT. RTE. 60, POMONA FREEWAY INTERCHANGE	125,000	6,525	5.22	2,846	780	277	2,622	43.62	11.95	4.24	40.18	1,117	10E
057	07	LA	R 7.719	B	POMONA, JCT. RTES. 10/71, SAN BERNARDINO/CHINO VALLEY FREEWAYS INTERCHANGE	154,000	8,039	5.22	3,507	961	341	3,230	43.62	11.95	4.24	40.18	1,376	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
057	07	LA	R 7.719	A	POMONA, JCT. RTES. 10/71, SAN BERNARDINO/CHINO VALLEY FREEWAYS INTERCHANGE	163,000	14,344	8.80	6,085	1,047	697	6,515	42.42	7.30	4.86	45.42	2,659	10E
057	07	LA	R 10.272	B	SAN DIMAS, COVINA AVENUE INTERCHANGE	163,000	14,344	8.80	6,085	1,047	697	6,515	42.42	7.30	4.86	45.42	2,659	10E
057	07	LA	R 11.791	B	GLENDORA, JCT. RTE. 210, FOOTHILL FREEWAY INTERCHANGE	144,000	12,672	8.80	5,375	925	616	5,756	42.42	7.30	4.86	45.42	2,350	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
058	05	SLO	0	A	JCT. RTE. 101	7,200	446	6.20	256	48	35	108	57.30	10.70	7.80	24.20	56	10E
058	05	SLO	6.889	B	JCT. RTE. 229 NORTHEAST	925	50	5.40	24	18	0	7	48.80	36.60	0.00	14.60	5	10E
058	05	SLO	6.889	A	JCT. RTE. 229 NORTHEAST	825	116	14.00	59	0	19	39	50.60	0.00	16.10	33.30	18	10E
058	05	SLO	24.544	A	CAMMATTI CREEK	550	95	17.30	46	0	16	33	48.10	0.00	17.30	34.60	15	10E
058	05	SLO	45.2	A	SODA LAKE ROAD	340	72	21.30	56	0	0	16	78.10	0.00	0.00	21.90	7	10E
058	06	KER	15.41	B	JCT. RTE. 33	300	69	23.00	47	9	2	11	68.00	13.00	3.00	16.00	7	03E
058	06	KER	15.42	A	JCT. RTE. 33	1,250	296	23.66	135	40	13	108	45.45	13.64	4.55	36.36	48	06V
058	06	KER	23.748	A	LOKERN ROAD	7,000	2,240	32.00	1,389	112	67	672	62.00	5.00	3.00	30.00	301	03E
058	06	KER	39.96	B	JCT. RTE. 43	6,200	1,275	20.56	517	189	52	517	40.54	14.86	4.05	40.54	221	06V
058	06	KER	39.97	A	JCT. RTE. 43	6,900	1,725	25.00	1,052	121	69	483	61.00	7.00	4.00	28.00	225	03E
058	06	KER	46.1	B	ALLEN ROAD	21,000	4,830	23.00	2,946	338	193	1,352	61.00	7.00	4.00	28.00	629	03E
058	06	KER	46.1	A	ALLEN ROAD	28,000	7,280	26.00	4,950	510	291	1,529	68.00	7.00	4.00	21.00	790	03E
058	06	KER	51.807	B	BAKERSFIELD, REAL ROAD	49,500	10,890	22.00	7,405	762	436	2,287	68.00	7.00	4.00	21.00	1,182	03E
058	06	KER	R 52.36	A	BAKERSFIELD, SOUTH JCT. RTE. 99	68,000	14,960	22.00	4,189	2,842	1,197	6,732	28.00	19.00	8.00	45.00	2,907	03E
058	06	KER	R 55.404	A	COTTONWOOD ROAD	70,000	17,500	25.00	5,250	1,925	1,750	8,575	30.00	11.00	10.00	49.00	3,576	03E
058	06	KER	R 59.44	A	JCT. RTE. 184	27,000	8,473	31.38	2,402	482	169	5,421	28.35	5.69	1.99	63.98	2,024	07E
058	06	KER	75.63	B	JCT RTE 223	19,000	5,837	30.72	1,347	303	119	4,068	23.08	5.19	2.04	69.69	1,496	10V
058	06	KER	75.63	A	JCT RTE 223	19,500	6,119	31.38	1,734	348	122	3,915	28.33	5.69	1.99	63.98	1,461	07E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
058	06	KER	R 90.717	B	JCT. RTE. 202 SOUTHWEST	21,200	6,653	31.38	1,885	379	132	4,257	28.33	5.69	1.99	63.98	1,589	07E
058	06	KER	R 90.717	A	JCT. RTE. 202 SOUTHWEST	20,900	6,558	31.38	1,858	373	131	4,196	28.33	5.69	1.99	63.98	1,566	07E
058	06	KER	R107.465	B	RANDSBURG CUT-OFF ROAD	19,400	6,542	33.72	354	531	447	5,211	5.41	8.11	6.83	79.66	1,925	06V
058	06	KER	M 111.13	B	JCT RTE 14	14,050	4,918	35.00	738	98	49	4,033	15.00	2.00	1.00	82.00	1,433	03E
058	06	KER	R127.636	A	CALIFORNIA CITY BOULEVARD	17,000	6,290	37.00	944	126	63	5,158	15.00	2.00	1.00	82.00	1,833	03E
058	08	SBD	5.4	B	JCT. RTE. 395	12,000	5,875	48.96	881	118	59	4,818	15.00	2.00	1.00	82.00	1,713	03E
058	08	SBD	5.4	A	JCT. RTE. 395	9,700	3,756	38.72	520	65	38	3,132	13.85	1.74	1.01	83.39	1,110	06V
058	08	SBD	R 34.812	B	JCT. RTE. 15	11,500	4,508	39.20	629	78	46	3,755	13.95	1.74	1.01	83.29	1,331	06E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
059	06	MAD	0	A	JCT. RTE. 152	5,900	708	12.00	276	42	21	368	39.00	6.00	3.00	52.00	144	03E
059	10	MER	L 14.78	B	MERCED, JCT. RTE. 99; JCT. RTE. 140	28,000	3,472	12.40	1,389	181	87	1,816	40.00	5.20	2.50	52.30	705	85V
059	10	MER	14.78	A	MERCED, JCT. RTE. 99; JCT. RTE. 140	23,000	1,150	5.00	230	334	219	368	20.00	29.00	19.00	32.00	198	98V
059	10	MER	16.1	A	MERCED, WEST OLIVE AVENUE/SANTA FE DRIVE	8,700	566	6.50	76	165	11	314	13.40	29.10	2.00	55.50	128	97V
059	10	MER	R 28.808	B	TURLOCK ROAD	1,850	227	12.28	25	43	8	151	11.20	18.80	3.60	66.40	58	97V
059	10	MER	R 28.808	A	TURLOCK ROAD	1,400	151	10.80	19	25	4	103	12.60	16.40	2.90	68.10	39	97V
059	10	MER	33.709	B	LA GRANGE ROAD	3,250	423	13.02	16	78	19	310	3.90	18.50	4.40	73.20	117	97V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
060	07	LA	0	A	LOS ANGELES, JCT. RTE. 10, SANTA MONICA FREEWAY, EAST LOS ANGELES INTERCHANGE	169,000	7,791	4.61	2,881	1,121	506	3,283	36.98	14.39	6.49	42.14	1,411	10E
060	07	LA	R .545	A	LOS ANGELES, JCT. RTE. 5, GOLDEN STATE FREEWAY, EAST LOS ANGELES INTERCHANGE	190,000	8,759	4.61	3,239	1,260	568	3,691	36.98	14.39	6.49	42.14	1,586	10E
060	07	LA	R 2.22	O	EAST OF INDIANA ST; ROWAN AVE	207,000	8,839	4.27	3,269	1,272	574	3,725	36.98	14.39	6.49	42.14	1,601	10V
060	07	LA	R 3.27	B	JCT. RTE. 710, LONG BEACH FREEWAY INTERCHANGE	208,000	8,944	4.30	3,307	1,287	580	3,769	36.98	14.39	6.49	42.14	1,620	10E
060	07	LA	R 3.27	A	JCT. RTE. 710, LONG BEACH FREEWAY INTERCHANGE	245,000	16,268	6.64	5,739	2,473	615	7,441	35.28	15.20	3.78	45.74	3,086	10E
060	07	LA	9.509	B	SOUTH EL MONTE, JCT. RTE. 164, ROSEMEAD BOULEVARD INTERCHANGE	229,000	16,419	7.17	5,793	2,496	621	7,510	35.28	15.20	3.78	45.74	3,115	10E
060	07	LA	9.509	A	SOUTH EL MONTE, JCT. RTE. 164, ROSEMEAD BOULEVARD INTERCHANGE	237,000	16,590	7.00	5,853	2,522	627	7,588	35.28	15.20	3.78	45.74	3,147	10E
060	07	LA	11.007	B	SOUTH EL MONTE, PECK ROAD/DURFEE AVENUE INTERCHANGE	240,000	16,800	7.00	5,927	2,554	635	7,684	35.28	15.20	3.78	45.74	3,187	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
060	07	LA	11.711	B	INDUSTRY, JCT. RTE. 605, SAN GABRIEL RIVER FREEWAY INTERCHANGE	235,000	16,967	7.22	5,986	2,579	641	7,761	35.28	15.20	3.78	45.74	3,219	10E
060	07	LA	11.711	A	INDUSTRY, JCT. RTE. 605, SAN GABRIEL RIVER FREEWAY INTERCHANGE	239,000	18,618	7.79	7,602	1,825	482	8,710	40.83	9.80	2.59	46.78	3,510	10E
060	07	LA	20.428	A	ROWLAND HEIGHTS, NOGALES STREET	202,000	19,008	9.41	7,761	1,863	492	8,892	40.83	9.80	2.59	46.78	3,583	10E
060	07	LA	R 23.56	B	DIAMOND BAR, JCT. RTE. 57 SOUTH, ORANGE FREEWAY INTERCHANGE	208,000	19,947	9.59	8,144	1,955	517	9,331	40.83	9.80	2.59	46.78	3,760	10E
060	07	LA	R 23.56	A	DIAMOND BAR, JCT. RTE. 57 SOUTH, ORANGE FREEWAY INTERCHANGE	343,000	23,770	6.93	5,412	2,957	727	14,673	22.77	12.44	3.06	61.73	5,631	10E
060	07	LA	R 25.464	A	DIAMOND BAR, JCT. RTE. 57 NORTH, ORANGE FREEWAY INTERCHANGE	230,000	20,654	8.98	4,703	2,569	632	12,750	22.77	12.44	3.06	61.73	4,893	10E
060	07	LA	R 29.392	B	POMONA, JCT. RTE. 71, CHINO VALLEY FREEWAY INTERCHANGE	218,000	20,645	9.47	4,701	2,568	632	12,744	22.77	12.44	3.06	61.73	4,890	10E
060	07	LA	R 29.392	A	POMONA, JCT. RTE. 71, CHINO VALLEY FREEWAY INTERCHANGE	223,000	26,203	11.75	7,491	2,487	773	15,449	28.59	9.49	2.95	58.96	5,935	10E
060	08	SBD	R 0	A	LOS ANGELES/SAN BERNARDINO COUNTY LINE	223,000	26,203	11.75	7,491	2,487	773	15,449	28.59	9.49	2.95	58.96	5,935	10E
060	08	SBD	R 2.366	B	CENTRAL AVENUE	220,000	26,928	12.24	6,770	2,687	846	16,625	25.14	9.98	3.14	61.74	6,344	04E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
060	08	SBD	R 2.366	A	CENTRAL AVENUE	221,000	27,050	12.24	6,800	2,700	849	16,701	25.14	9.98	3.14	61.74	6,373	04E
060	08	SBD	R 4.58	B	ONTARIO, JCT. RTE. 83	218,000	26,683	12.24	6,708	2,663	838	16,474	25.14	9.98	3.14	61.74	6,286	04E
060	08	SBD	R 4.58	A	ONTARIO, JCT. RTE. 83	222,000	27,173	12.24	6,831	2,712	853	16,777	25.14	9.98	3.14	61.74	6,402	04E
060	08	SBD	R 5.855	A	GROVE AVENUE	215,000	25,671	11.94	7,550	2,541	778	14,802	29.41	9.90	3.03	57.66	5,719	08V
060	08	RIV	R .491	B	JCT. RTE. 15	138,000	19,734	14.30	4,823	2,003	667	12,241	24.44	10.15	3.38	62.03	4,674	00E
060	08	RIV	R .491	A	JCT. RTE. 15	138,000	21,666	15.70	9,208	1,712	585	10,161	42.50	7.90	2.70	46.90	4,071	92V
060	08	RIV	R 1.56	A	VAN BUREN BOULEVARD	138,000	16,698	12.10	9,284	1,720	768	4,926	55.60	10.30	4.60	29.50	2,296	84E
060	08	RIV	R 3.03	B	MISSION BOULEVARD	151,000	19,630	13.00	10,855	1,904	962	5,909	55.30	9.70	4.90	30.10	2,735	84E
060	08	RIV	7.533	B	VALLEY WAY	136,000	17,680	13.00	9,706	1,733	919	5,322	54.90	9.80	5.20	30.10	2,470	84E
060	08	RIV	7.533	A	VALLEY WAY	145,000	17,400	12.00	10,440	1,688	887	4,385	60.00	9.70	5.10	25.20	2,164	84E
060	08	RIV	11.068	B	RIVERSIDE, CRESTMORE AVENUE	150,000	16,500	11.00	9,884	2,426	842	3,350	59.90	14.70	5.10	20.30	1,849	84E
060	08	RIV	R 12.212	A	EAST JCT. RTE. 215	130,000	13,650	10.50	5,870	819	410	6,552	43.00	6.00	3.00	48.00	2,602	96V
060	08	RIV	22.101	B	GILMAN SPRINGS ROAD	53,000	8,480	16.00	2,120	339	339	5,682	25.00	4.00	4.00	67.00	2,116	91E
060	08	RIV	30.495	B	JCT. RTE. 10	44,500	7,254	16.30	1,777	297	261	4,918	24.50	4.10	3.60	67.80	1,825	91V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
061	04	ALA	14.8	A	SAN LEANDRO, JCT. RTE. 112 EAST	21,400	1,134	5.30	485	431	68	150	42.80	38.00	6.00	13.20	118	03V
061	04	ALA	16.07	B	OAKLAND, AIRPORT/HEGENBERGER ROADS	20,200	828	4.10	480	151	72	125	58.03	18.27	8.64	15.06	84	02V
061	04	ALA	16.07	A	OAKLAND, AIRPORT/HEGENBERGER ROADS	20,700	789	3.81	478	143	65	103	60.63	18.10	8.24	13.03	75	02V
061	04	ALA	18.52	A	ALAMEDA, ISLAND DRIVE	38,000	954	2.51	466	137	107	244	48.80	14.41	11.24	25.55	129	03V
061	04	ALA	21.967	B	JCT. RTE. 260 NORTH	16,700	224	1.34	180	30	11	3	80.25	13.45	5.04	1.26	12	02V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
062	08	RIV	0	A	JCT. RTE. 10	19,000	2,622	13.80	1,120	131	100	1,272	42.70	5.00	3.80	48.50	505	89V
062	08	SBD	0	A	RIVERSIDE/SAN BERNARDINO COUNTY LINE	22,000	3,300	15.00	1,940	198	129	1,033	58.80	6.00	3.90	31.30	461	84V
062	08	SBD	12.404	A	YUCCA VALLEY, JCT. RTE. 247 NORTH	28,500	1,682	5.90	1,060	47	47	528	63.00	2.80	2.80	31.40	230	84E
062	08	SBD	34.223	B	29 PALMS/UTAH TRAIL	4,700	432	9.20	287	8	7	130	66.40	1.90	1.70	30.00	57	89V
062	08	RIV	84.965	B	JCT. RTE. 177 SOUTH	500	132	26.30	64	4	7	57	48.80	2.70	5.50	43.00	23	84E
062	08	RIV	84.965	A	JCT. RTE. 177 SOUTH	2,200	154	7.00	54	1	18	81	34.80	0.90	11.60	52.70	33	92E
062	08	SBD	125.761	B	JCT. RTE. 95	1,600	104	6.50	37	1	11	55	35.60	1.00	10.60	52.80	22	92V
062	08	SBD	125.761	A	JCT. RTE. 95	2,700	572	21.20	146	14	8	403	25.60	2.50	1.40	70.50	147	92V
062	08	SBD	142.66	B	ARIZONA STATE LINE	6,000	1,260	21.00	328	38	13	882	26.00	3.00	1.00	70.00	321	92E
062	06	TUL	0	A	TULARE, JCT. RTE. 137	15,400	770	5.00	547	54	15	154	71.00	7.00	2.00	20.00	79	04E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
063	06	TUL	L 7.97	B	VISALIA, NOBLE AVENUE/MINERAL KIN BOULEVARD. WEST JCT. RTE. 198	31,000	1,550	5.00	1,209	140	47	155	78.00	9.00	3.00	10.00	116	04E
063	06	TUL	7.98	A	VISALIA, EAST JCT. RTE. 198	28,800	2,592	9.00	1,892	337	130	233	73.00	13.00	5.00	9.00	197	04E
063	06	TUL	R 8.775	A	VISALIA, JCT. RTE. 216 ON COURT STREET/WEST THIRD AVENUE NEAR LINCOLN OVAL	16,600	1,494	9.00	1,091	194	75	134	73.00	13.00	5.00	9.00	113	04E
063	06	TUL	12.13	B	AVENUE 328	9,500	1,140	12.00	844	80	34	182	74.00	7.00	3.00	16.00	105	03E
063	06	TUL	12.13	A	AVENUE 328	7,800	1,051	13.48	599	53	32	368	57.00	5.00	3.00	35.00	158	02V
063	06	TUL	15.11	A	AVENUE 352; OIL WELL ROAD	6,100	321	5.26	145	52	28	96	45.17	16.20	8.72	29.91	47	08V
063	06	TUL	R 19.187	B	JCT. RTE. 201 EAST	5,700	300	5.26	225	15	9	51	75.00	5.00	3.00	17.00	28	04E
063	06	TUL	R 19.187	A	JCT. RTE. 201 EAST	7,700	616	8.00	474	62	37	43	77.00	10.00	6.00	7.00	43	03E
063	06	TUL	R 25.55	A	AVENUE 432	1,600	156	9.75	74	18	14	50	47.44	11.54	8.97	32.05	24	08V
063	06	TUL	R 30.084	B	TULARE/FRESNO COUNTY LINE	1,800	342	19.00	253	21	14	55	74.00	6.00	4.00	16.00	32	03E
063	06	FRE	0	A	TULARE/FRESNO COUNTY LINE	2,100	260	12.38	120	37	23	80	46.15	14.23	8.85	30.77	39	08V
063	06	FRE	8.362	B	JCT. RTE. 180	710	68	9.58	45	10	6	7	66.18	14.71	8.82	10.29	6	08V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
065	06	KER	R 0	A	JCT. RTE. 99	16,200	3,279	20.24	1,457	229	134	1,459	44.44	6.97	4.09	44.50	595	07E
065	06	KER	23.186	B	JCT. RTE. 155	6,200	2,208	35.61	839	132	66	1,170	38.00	6.00	3.00	53.00	455	03V
065	06	KER	23.186	A	JCT. RTE. 155	8,500	2,550	30.00	995	128	77	1,352	39.00	5.00	3.00	53.00	524	04E
065	06	TUL	R 6.983	B	AVENUE 56	8,600	2,236	26.00	805	112	67	1,252	36.00	5.00	3.00	56.00	480	04E
065	06	TUL	R 6.983	A	AVENUE 56	10,000	2,516	25.16	956	126	75	1,359	38.00	5.00	3.00	54.00	525	02V
065	06	TUL	R 14.073	A	AVENUE 112	10,800	1,506	13.94	462	154	102	787	30.70	10.23	6.78	52.29	317	08V
065	06	TUL	18.163	B	JCT. RTE. 190	15,500	2,635	17.00	1,159	184	132	1,159	44.00	7.00	5.00	44.00	477	04E
065	06	TUL	18.163	A	JCT. RTE. 190	24,700	2,100	8.50	1,160	147	69	723	55.26	6.99	3.30	34.45	314	07E
065	06	TUL	21.83	B	LINDA VISTA AVENUE	21,000	1,785	8.50	986	125	59	615	55.26	6.99	3.30	34.45	267	07E
065	06	TUL	21.83	A	LINDA VISTA AVENUE	20,400	1,734	8.50	958	121	57	597	55.26	6.99	3.30	34.45	259	07V
065	06	TUL	23.333	B	AVENUE 184	20,400	1,714	8.40	998	107	51	558	58.20	6.25	2.98	32.57	245	10V
065	06	TUL	31.546	B	JCT. RTE. 137 WEST	13,300	1,131	8.50	625	79	37	390	55.26	6.99	3.30	34.45	169	07E
065	06	TUL	31.546	A	JCT. RTE. 137 WEST	4,900	720	14.69	377	54	37	253	52.34	7.48	5.07	35.11	111	08V
065	03	PLA	R 4.863	A	ROSEVILLE, JCT. RTE. 80	104,000	15,704	15.10	2,340	2,623	2,167	8,574	14.90	16.70	13.80	54.60	3,600	97E
065	03	PLA	13.783	B	JCT. RTE. 193 EAST	21,700	2,908	13.40	544	480	689	1,195	18.70	16.50	23.70	41.10	577	97E
065	03	PLA	14.806	B	MARKHAM RAVINE BRIDGE	16,800	4,109	24.46	1,766	862	431	1,050	42.99	20.97	10.48	25.56	567	02E
065	03	PLA	14.806	A	MARKHAM RAVINE BRIDGE	16,800	4,514	26.87	1,941	947	473	1,154	42.99	20.97	10.48	25.56	623	02E
065	03	YUB	R 6.884	A	FORTY MILE ROAD	16,200	4,646	28.68	1,997	974	487	1,188	42.99	20.97	10.48	25.56	641	02E
065	03	YUB	R 9.177	B	JCT. RTE. 70	16,900	3,563	21.08	1,532	747	373	911	42.99	20.97	10.48	25.56	491	02E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
066	07	LA	0	A	LA VERNE, BASELINE ROAD	21,600	588	2.72	307	137	95	49	52.20	23.36	16.09	8.35	54	04E
066	07	LA	R .189	A	LA VERNE, JCT. RTE. 210, FOOTHILL FREEWAY	26,500	721	2.72	376	168	116	60	52.20	23.36	16.09	8.35	66	04E
066	07	LA	2.54	B	POMONA, GAREY AVENUE	23,500	639	2.72	334	149	103	53	52.20	23.36	16.09	8.35	59	04V
066	08	SBD	21.37	B	FOURTH STREET	21,500	645	3.00	515	72	19	39	79.90	11.10	2.90	6.10	41	88E
066	08	SBD	21.37	A	FOURTH STREET	19,800	396	2.00	317	44	11	24	80.00	11.10	2.90	6.00	25	88E
066	08	SBD	23.054	B	SAN BERNARDINO, JCT. RTE. 215	17,800	356	2.00	285	39	10	22	80.10	10.90	2.90	6.10	23	88E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
067	11	SD	R 0	A	EL CAJON, JCT. RTE. 8	35,500	2,769	7.80	1,656	385	111	617	59.80	13.90	4.00	22.30	323	86E
067	11	SD	R .306	A	EL CAJON, BROADWAY	80,000	5,360	6.70	3,205	745	214	1,195	59.80	13.90	4.00	22.30	624	86V
067	11	SD	R 1.118	A	BRADLEY AVENUE	74,000	4,958	6.70	2,965	689	198	1,106	59.80	13.90	4.00	22.30	578	86E
067	11	SD	R 2.672	A	WOODSIDE AVENUE	63,000	4,599	7.30	2,778	579	97	1,145	60.40	12.60	2.10	24.90	560	86V
067	11	SD	R 4.832	B	WINTER GARDEN BOULEVARD	51,000	1,326	2.60	801	167	28	330	60.40	12.60	2.10	24.90	161	86E
067	11	SD	R 4.832	A	WINTER GARDEN BOULEVARD	34,000	1,428	4.20	863	179	31	356	60.40	12.50	2.20	24.90	174	86E
067	11	SD	15.2	B	POWAY ROAD	18,100	1,665	9.20	1,082	130	28	425	65.00	7.80	1.70	25.50	201	96E
067	11	SD	15.2	A	POWAY ROAD	24,100	1,306	5.42	858	64	164	219	65.73	4.90	12.59	16.78	136	05V
067	11	SD	24.377	B	RAMONA, JCT. RTE. 78	26,000	1,508	5.80	703	149	23	633	46.60	9.90	1.50	42.00	260	85E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
068	05	MON	0	A	PACIFIC GROVE, ASILOMAR BEACH STATE PARK	3,600	126	3.50	105	18	0	3	83.70	14.00	0.00	2.30	6	03E
068	05	MON	L 4.264	B	JCT. RTE. 1, CARMEL-PACIFIC GROVE	25,400	813	3.20	661	66	22	64	81.30	8.10	2.70	7.90	55	03E
068	05	MON	R 3.948	A	JCT. RTE. 1, CARMEL-PACIFIC GROVE	21,700	543	2.50	383	69	23	68	70.50	12.70	4.20	12.60	47	03E
068	05	MON	6.812	B	JCT. RTE. 218 NORTHWEST	21,600	518	2.40	393	57	1	67	75.90	11.10	0.10	12.90	42	03E
068	05	MON	6.812	A	JCT. RTE. 218 NORTHWEST	22,100	619	2.80	438	89	12	80	70.70	14.40	1.90	13.00	53	03E
068	05	MON	R 17.19	A	RESERVATION ROAD	30,100	1,385	4.60	888	220	57	220	64.10	15.90	4.10	15.90	136	03E
068	05	MON	22.023	B	SALINAS, JCT. RTE. 101	20,000	1,240	6.20	759	174	55	253	61.20	14.00	4.40	20.40	138	03E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
070	03	SUT	R .051	A	JCT. RTE. 99	15,900	1,498	9.42	523	188	98	689	34.92	12.57	6.52	46.00	288	04E
070	03	YUB	R 8.293	B	JCT. RTE. 65 SOUTH	19,800	4,291	21.67	1,533	597	306	1,855	35.73	13.92	7.12	43.23	794	05E
070	03	YUB	R 8.293	A	JCT. RTE. 65 SOUTH	37,500	4,774	12.73	1,706	665	340	2,064	35.73	13.92	7.12	43.23	883	05E
070	03	YUB	13.6	O	YUBA RIVER BRIDGE	59,000	4,632	7.85	1,617	582	302	2,131	34.92	12.57	6.52	46.00	890	04E
070	03	YUB	14.7	B	MARYSVILLE, JCT. RTE. 20	32,000	2,560	8.00	1,029	492	384	655	40.20	19.20	15.00	25.60	364	97E
070	03	YUB	14.71	A	MARYSVILLE, JCT. RTE. 20	14,600	1,964	13.45	912	294	134	624	46.43	14.95	6.83	31.79	294	07E
070	03	YUB	25.822	O	YUBA/BUTTE COUNTY LINE	11,700	1,460	12.48	705	174	99	482	48.29	11.92	6.78	33.01	222	10V
070	03	BUT	0	O	YUBA/BUTTE COUNTY LINE	11,700	1,460	12.48	705	174	99	482	48.29	11.92	6.78	33.01	222	10V
070	03	BUT	13.901	B	OROVILLE, JCT. RTE. 162	14,600	2,162	14.81	823	274	141	923	38.08	12.69	6.54	42.69	393	07E
070	03	BUT	13.901	A	OROVILLE, JCT. RTE. 162	20,600	3,051	14.81	1,162	387	200	1,302	38.08	12.69	6.54	42.69	555	07E
070	03	BUT	20.479	B	JCT. RTE. 149 WEST	22,100	3,273	14.81	1,246	415	214	1,397	38.08	12.69	6.54	42.69	595	07E
070	03	BUT	20.479	A	JCT. RTE. 149 WEST	7,500	1,111	14.81	423	141	73	474	38.08	12.69	6.54	42.69	202	07E
070	03	BUT	21.87	B	JCT. RTE. 191 NORTH	7,500	1,111	14.81	423	141	73	474	38.08	12.69	6.54	42.69	202	07E
070	03	BUT	21.87	A	JCT. RTE. 191 NORTH	2,950	437	14.81	166	55	29	187	38.08	12.69	6.54	42.69	80	07E
070	03	BUT	48.076	O	BUTTE/PLUMAS COUNTY LINE	1,290	151	11.71	43	20	5	83	28.48	13.25	3.31	54.97	33	10V
070	02	PLU	0	O	BUTTE/PLUMAS COUNTY LINE	1,290	151	11.71	43	20	5	83	28.48	13.25	3.31	54.97	33	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
070	02	PLU	33.026	B	JCT. RTE. 89 NORTH	1,250	112	8.96	15	13	4	80	13.39	11.61	3.57	71.43	30	10V
070	02	PLU	33.026	A	JCT. RTE. 89 NORTH	2,800	208	7.43	28	43	6	131	13.46	20.67	2.88	62.98	51	10V
070	02	PLU	41.97	B	COUNTY HOSPITAL ROAD	3,800	236	6.20	27	66	14	128	11.56	27.89	6.12	54.42	53	10E
070	02	PLU	41.97	A	COUNTY HOSPITAL ROAD	5,900	257	4.35	30	72	16	140	11.56	27.89	6.12	54.42	58	10E
070	02	PLU	43.086	B	LAWRENCE STREET, BEGIN COUPLET	4,850	110	2.26	16	31	7	56	14.50	28.50	6.00	51.00	24	10E
070	02	PLU	43.7	A	QUINCY, END COUPLET ON MAIN STREET AT LAWRENCE STREET	8,200	244	2.98	44	68	15	117	18.00	28.00	6.00	48.00	50	10E
070	02	PLU	43.785	A	QUINCY JUNCTION ROAD	8,800	210	2.39	42	55	13	101	20.00	26.00	6.00	48.00	43	10E
070	02	PLU	46.77	B	LA PORTE ROAD	3,500	190	5.43	32	65	7	86	17.03	34.07	3.70	45.20	38	10E
070	02	PLU	46.77	A	LA PORTE ROAD	3,200	185	5.78	38	28	11	107	20.60	15.36	5.99	58.05	42	10E
070	02	PLU	R 66.628	B	JCT. RTE. 89 SOUTH	2,800	180	6.43	42	29	7	102	23.33	16.11	3.89	56.67	40	10V
070	02	PLU	R 66.628	A	JCT. RTE. 89 SOUTH	3,300	177	5.36	28	23	10	116	15.82	12.99	5.65	65.54	45	10V
070	02	PLU	75.332	B	PORTOLA, WEST CITY LIMITS	5,100	224	4.40	46	34	13	130	20.60	15.36	5.99	58.05	51	10E
070	02	PLU	75.96	B	GULLING STREET	7,000	219	3.13	45	34	13	127	20.60	15.36	5.99	58.05	50	10E
070	02	PLU	R 76.6	B	PORTOLA, MEADOW WAY	4,300	221	5.15	52	31	12	126	23.58	13.97	5.25	57.20	50	10E
070	02	PLU	R 76.6	A	PORTOLA, MEADOW WAY	3,900	196	5.03	44	28	3	121	22.41	14.22	1.72	61.64	46	10E
070	02	PLU	R 80.315	A	BECKWOURTH, CALPINE ROAD	3,250	159	4.88	35	23	3	98	22.11	14.74	1.58	61.58	38	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
070	02	PLU	81.65	O	BECKWOURTH STATE HIGHWAY MAINTENANCE STATION	3,300	126	3.82	38	21	6	61	30.16	16.67	4.76	48.41	25	10V
070	02	PLU	92.065	A	JCT. RTE. 49 SOUTH	3,900	178	4.57	23	16	7	131	13.15	9.16	3.98	73.71	49	10E
070	02	PLU	94.28	B	JCT. RTE. 284 NORTH	3,900	178	4.57	39	27	3	110	22.12	14.90	1.44	61.54	42	10E
070	02	PLU	95.964	O	PLUMAS/LASSEN COUNTY LINE	3,950	201	5.09	28	25	3	145	14.12	12.21	1.53	72.14	54	10E
070	02	LAS	0	O	PLUMAS/LASSEN COUNTY LINE	3,950	201	5.09	28	25	3	145	14.12	12.21	1.53	72.14	54	10E
070	02	LAS	0	A	PLUMAS/LASSEN COUNTY LINE	3,950	201	5.09	28	25	3	145	14.12	12.21	1.53	72.14	54	10E
070	02	LAS	3.889	B	JCT. RTE. 395	3,950	201	5.09	29	18	10	144	14.43	8.96	4.98	71.64	54	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
071	07	LA	R .335	A	POMONA, JCT. RTES. 10/57, SAN BERNARDINO/ORANGE FREEWAYS INTERCHANGE	69,000	4,920	7.13	2,343	340	216	2,021	47.62	6.91	4.40	41.07	842	05V
071	07	LA	R 4.31	B	POMONA, JCT. RTE. 60, POMONA FREEWAY INTERCHANGE	70,000	4,711	6.73	1,806	498	343	2,063	38.33	10.58	7.29	43.80	871	05V
071	07	LA	R 4.697	O	LA/SBD CO LINE	92,000	9,421	10.24	3,357	1,001	610	4,452	35.63	10.63	6.48	47.26	1,835	05V
071	08	SBD	R 0	O	LA/SBD CO LINE	92,000	9,421	10.24	3,357	1,001	610	4,452	35.63	10.63	6.48	47.26	1,835	05V
071	08	SBD	R 7.983	B	JCT. RTE. 83 NORTH	57,200	5,011	8.76	2,917	428	214	1,451	58.22	8.55	4.27	28.96	674	08V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
072	12	ORA	11.421	A	LA HABRA, JCT. RTE. 39	36,000	889	2.47	726	67	18	78	81.70	7.57	2.01	8.72	61	06E
072	07	LA	6.662	B	WHITTIER, JCT. RTE. 605, SAN GABRIEL RIVER FREEWAY	41,500	1,428	3.44	1,007	185	62	174	70.54	12.97	4.34	12.15	121	06V
072	07	LA	6.662	A	WHITTIER, JCT. RTE. 605, SAN GABRIEL RIVER FREEWAY	33,500	1,152	3.44	813	149	50	140	70.54	12.97	4.34	12.15	98	06E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
073	12	ORA	10	A	JCT RTE 5	39,200	372	0.95	282	54	8	28	75.68	14.60	2.20	7.44	26	98E
073	12	ORA	16.25	A	EL TORO ROAD	67,000	697	1.04	570	63	21	43	81.84	9.00	2.98	6.17	44	98E
073	12	ORA	R 7.811	B	JCT RTE 405, SAN DIEGO FREEWAY	170,000	3,995	2.35	2,697	539	240	519	67.50	13.50	6.00	13.00	358	01E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
074	12	ORA	0	A	SAN JUAN CAPISTRANO, JCT. RTE. 5	28,000	8,764	31.30	4,189	640	123	3,812	47.80	7.30	1.40	43.50	1,539	82E
074	12	ORA	5.242	B	CONROCK ENTRANCE	15,000	1,755	11.70	497	165	100	993	28.30	9.40	5.70	56.60	390	83V
074	12	ORA	5.242	A	CONROCK ENTRANCE	11,000	352	3.20	251	38	36	27	71.30	10.80	10.30	7.60	27	83E
074	12	ORA	16.599	O	ORANGE/RIVERSIDE COUNTY LINE	9,800	720	7.35	472	59	24	165	65.57	8.20	3.28	22.95	82	01E
074	08	RIV	0	O	ORANGE/RIVERSIDE COUNTY LINE	9,800	720	7.35	472	59	24	165	65.57	8.20	3.28	22.95	82	01E
074	08	RIV	11.825	B	ELSINORE, GRAND AVENUE	10,500	772	7.35	506	63	25	177	65.57	8.20	3.28	22.95	88	01E
074	08	RIV	11.825	A	ELSINORE, GRAND AVENUE	19,000	1,501	7.90	1,133	111	42	215	75.50	7.40	2.80	14.30	130	88V
074	08	RIV	17.239	A	ELSINORE, JCT. RTE. 15	31,500	2,835	9.00	1,987	309	113	425	70.10	10.90	4.00	15.00	261	88E
074	08	RIV	27.53	B	JCT. RTE. 215	21,000	2,520	12.00	1,714	227	126	454	68.00	9.00	5.00	18.00	256	88E
074	08	RIV	27.54	A	JCT. RTE. 215	25,000	2,500	10.00	1,375	200	100	825	55.00	8.00	4.00	33.00	366	86V
074	08	RIV	34.332	B	JCT. RTE. 79 SOUTH	29,000	3,422	11.80	2,081	178	120	1,044	60.80	5.20	3.50	30.50	467	86E
074	08	RIV	34.332	A	JCT. RTE. 79 SOUTH	33,000	3,894	11.80	2,570	202	136	985	66.00	5.20	3.50	25.30	468	86E
074	08	RIV	39.487	B	LYON AVENUE	28,000	3,360	12.00	2,362	316	0	682	70.30	9.40	0.00	20.30	347	86E
074	08	RIV	41.338	B	JCT. RTE. 79 NORTH	29,000	3,480	12.00	2,774	355	0	351	79.70	10.20	0.00	10.10	251	79E
074	08	RIV	41.338	A	JCT. RTE. 79 NORTH	27,000	3,240	12.00	2,534	282	188	237	78.20	8.70	5.80	7.30	224	79E
074	08	RIV	44.74	A	MOUNTAIN STREET	15,500	1,101	7.10	816	89	13	183	74.10	8.10	1.20	16.60	102	91V
074	08	RIV	48.288	B	SAN BERNARDINO NATIONAL FOREST BOUNDARY	4,800	336	7.00	255	27	7	47	76.00	8.00	2.00	14.00	29	90E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
074	08	RIV	59.25	A	JCT. RTE. 243 NORTH	3,300	231	7.00	180	16	7	28	78.00	7.00	3.00	12.00	18	90E
074	08	RIV	71.745	B	JCT. RTE. 371 WEST	2,600	182	7.00	146	13	5	18	80.00	7.00	3.00	10.00	13	90E
074	08	RIV	71.745	A	JCT. RTE. 371 WEST	3,400	238	7.00	195	17	7	19	82.00	7.00	3.00	8.00	16	90E
074	08	RIV	R 96.014	B	PALM DESERT, JCT. RTE. 111	19,000	1,368	7.20	1,141	119	40	68	83.40	8.70	2.90	5.00	80	91V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
075	11	SD	9	A	SAN DIEGO, JCT. RTE. 5	65,000	1,950	3.00	1,502	238	45	166	77.00	12.20	2.30	8.50	138	85V
075	11	SD	18.47	B	CORONADO, POMONA AVENUE	22,000	418	1.90	300	45	12	61	71.80	10.70	2.80	14.70	37	86E
075	11	SD	19.586	B	JCT. RTE. 282 AT 4TH STREET ON ORANGE AVE	26,500	636	2.40	511	77	20	29	80.30	12.10	3.10	4.50	38	84V
075	11	SD	19.586	A	JCT. RTE. 282 AT 4TH STREET ON ORANGE AVE	22,100	751	3.40	485	129	35	102	64.60	17.20	4.60	13.60	69	86E
075	11	SD	R 22.261	B	JCT. RTE. 5	75,000	2,100	2.80	1,357	361	97	286	64.60	17.20	4.60	13.60	194	86V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
076	11	SD	R 0	A	JCT. RTE. 5	49,500	2,178	4.40	1,568	255	74	281	72.00	11.70	3.40	12.90	186	85V
076	11	SD	R 1.156	A	OCEANSIDE, CANYON DRIVE	50,000	2,700	5.40	1,963	221	46	470	72.70	8.20	1.70	17.40	258	86V
076	11	SD	R 3.389	B	OCEANSIDE, EL CAMINO REAL	54,000	2,700	5.00	1,750	251	59	640	64.80	9.30	2.20	23.70	314	86V
076	11	SD	R 9.49	B	VISTA WAY	30,000	2,220	7.40	1,319	155	56	690	59.40	7.00	2.50	31.10	307	96E
076	11	SD	R 9.49	A	VISTA WAY	33,500	2,479	7.40	1,473	174	62	771	59.40	7.00	2.50	31.10	343	96E
076	11	SD	R 17.303	B	JCT. RTE. 15	26,000	3,250	12.50	1,674	254	42	1,281	51.50	7.80	1.30	39.40	530	96E
076	11	SD	R 17.303	A	JCT. RTE. 15	12,600	1,764	14.00	1,369	108	44	243	77.60	6.10	2.50	13.80	148	87E
076	11	SD	32.87	B	VALLEY CENTER ROAD	7,600	1,528	20.10	1,316	28	24	160	86.10	1.80	1.60	10.50	107	87E
076	11	SD	32.87	A	VALLEY CENTER ROAD	4,250	880	20.70	806	4	3	67	91.60	0.50	0.30	7.60	52	87E
076	11	SD	52.319	B	JCT. RTE. 79	1,650	168	10.20	113	27	7	21	67.10	15.80	4.40	12.70	15	87V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
077	04	ALA	0.098	A	OAKLAND, JCT. RTE. 880	21,600	546	2.53	308	102	18	118	56.38	18.74	3.23	21.65	64	03V
077	04	ALA	0.365	A	OAKLAND, EAST 12TH STREET	15,900	281	1.77	196	44	2	39	69.88	15.53	0.62	13.98	25	03V
077	04	ALA	0.452	B	OAKLAND, EAST 14TH STREET	15,900	345	2.17	217	84	6	38	62.78	24.30	1.77	11.14	29	00V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
078	11	SD	0.004	A	OCEANSIDE, JCT. RTE. 5	76,000	3,549	4.67	1,665	359	276	1,249	46.92	10.12	7.77	35.19	563	07E
078	11	SD	1.498	A	OCEANSIDE, EL CAMINO REAL	136,000	6,623	4.87	3,108	670	515	2,331	46.92	10.12	7.77	35.19	1,050	07E
078	11	SD	5.944	B	VISTA, MELROSE DRIVE	131,000	6,773	5.17	3,178	685	526	2,383	46.92	10.12	7.77	35.19	1,074	07E
078	11	SD	5.944	A	VISTA, MELROSE DRIVE	131,000	6,249	4.77	2,932	632	486	2,199	46.92	10.12	7.77	35.19	991	07E
078	11	SD	R 16.539	B	ESCONDIDO, JCT. RTE. 15	162,000	7,371	4.55	3,458	746	573	2,594	46.92	10.12	7.77	35.19	1,169	07V
078	11	SD	R 17.268	B	ESCONDIDO, CENTRE CITY PARKWAY	82,000	4,346	5.30	2,369	409	235	1,334	54.50	9.40	5.40	30.70	615	97E
078	11	SD	N 17.68	B	ESCONDIDO, BROADWAY/LINCOLN PARKWAY	54,000	540	1.00	288	129	83	41	53.40	23.80	15.30	7.50	48	86E
078	11	SD	T 19.094	B	ESCONDIDO ASH STREET	17,900	1,074	6.00	750	132	26	166	69.80	12.30	2.40	15.50	99	96E
078	11	SD	T 19.094	A	ESCONDIDO ASH STREET	22,100	1,326	6.00	926	163	30	207	69.80	12.30	2.30	15.60	123	96E
078	11	SD	18.94	A	ESCONDIDO, GRAND AVENUE	19,500	1,190	6.10	831	146	29	184	69.80	12.30	2.40	15.50	110	96E
078	11	SD	R 27.315	A	BANDY CANYON ROAD	9,100	855	9.40	428	136	52	239	50.10	15.90	6.10	27.90	118	81E
078	11	SD	35.519	B	JCT. RTE. 67 SOUTHWEST	10,400	229	2.20	91	51	10	77	39.80	22.30	4.20	33.70	36	87E
078	11	SD	35.519	A	JCT. RTE. 67 SOUTHWEST	23,100	1,271	5.50	878	145	56	192	69.10	11.40	4.40	15.10	119	87V
078	11	SD	51.108	B	WEST JCT. RTE. 79	5,600	336	6.00	238	39	29	30	70.90	11.60	8.50	9.00	27	93V
078	11	SD	51.108	A	WEST JCT. RTE. 79	4,150	299	7.20	233	36	16	13	78.00	12.20	5.40	4.40	18	88V
078	11	SD	58.133	B	EAST JCT. RTE. 79	4,950	822	16.60	645	103	37	37	78.50	12.50	4.50	4.50	50	88E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
078	11	SD	58.133	A	EAST JCT. RTE. 79	3,850	936	24.30	756	112	33	35	80.80	12.00	3.50	3.70	54	88E
078	11	IMP	13.17	B	JCT. RTE. 86	790	266	33.70	48	0	9	209	17.90	0.00	3.40	78.70	75	81V
078	11	IMP	13.18	A	JCT. RTE. 86	18,200	983	5.40	578	53	31	320	58.80	5.40	3.20	32.60	140	78E
078	11	IMP	13.797	B	BRAWLEY, WEST JCT. RTE. 111	23,200	1,508	6.50	887	80	50	492	58.80	5.30	3.30	32.60	215	78E
078	11	IMP	13.797	A	BRAWLEY, WEST JCT. RTE. 111	21,700	3,277	15.10	1,573	144	33	1,527	48.00	4.40	1.00	46.60	600	78V
078	11	IMP	15.035	B	EAST JCT. RTE. 111	8,100	1,239	15.30	616	59	12	551	49.70	4.80	1.00	44.50	219	78E
078	11	IMP	15.035	A	EAST JCT. RTE. 111	4,200	1,915	45.60	1,238	143	52	482	64.65	7.47	2.72	25.17	230	10V
078	11	IMP	18.651	A	WEST JCT. RTE. 115	3,250	1,017	31.30	239	62	4	712	23.50	6.10	0.40	70.00	260	85V
078	11	IMP	21.023	A	EAST JCT. RTE. 115	1,700	219	12.90	33	22	16	148	15.00	10.00	7.50	67.50	57	93E
078	08	RIV	9.352	B	28TH AVENUE/NEIGHBORS BOULEVARD	1,800	216	12.00	33	21	17	145	15.10	9.80	7.80	67.30	56	93E
078	08	RIV	9.352	A	28TH AVENUE/NEIGHBORS BOULEVARD	2,000	150	7.50	23	15	11	101	15.30	9.70	7.60	67.40	39	93E
078	08	RIV	16.169	B	JCT. RTE. 10	2,900	177	6.10	27	18	13	119	15.00	10.00	7.50	67.50	46	93E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
079	11	SD	L .044	A	JCT. RTE. 8	5,100	383	7.50	286	49	3	45	74.70	12.80	0.80	11.70	30	86V
079	11	SD	14.44	B	SUNRISE HIGHWAY	1,650	165	10.00	156	9	0	0	94.70	5.30	0.00	0.00	6	86E
079	11	SD	14.44	A	SUNRISE HIGHWAY	1,850	170	9.20	161	9	0	0	94.80	5.20	0.00	0.00	6	72E
079	11	SD	20.22	B	JCT. RTE. 78	2,650	87	3.30	83	4	0	0	95.10	4.90	0.00	0.00	3	72E
079	11	SD	20.23	A	JCT. RTE. 78	3,650	409	11.20	285	63	28	34	69.60	15.40	6.80	8.20	32	88V
079	11	SD	27.37	B	JCT. RTE. 76 WEST	2,950	271	9.20	170	38	9	54	62.80	13.90	3.50	19.80	29	87V
079	11	SD	27.37	A	JCT. RTE. 76 WEST	2,650	313	11.80	199	44	20	50	63.60	14.10	6.40	15.90	31	87V
079	11	SD	31.7	A	SAN FELIPE ROAD	1,950	322	16.50	187	8	14	113	58.20	2.40	4.30	35.10	48	72V
079	08	RIV	2.27	B	JCT. RTE. 371 EAST	3,000	498	16.60	395	17	26	60	79.30	3.40	5.30	12.00	40	77E
079	08	RIV	2.27	A	JCT. RTE. 371 EAST	8,100	810	10.00	558	58	62	131	68.90	7.20	7.70	16.20	79	77E
079	08	RIV	R 19.16	B	JCT. RTE. 74	8,000	680	8.50	424	80	13	163	62.40	11.80	1.90	23.90	80	91V
079	08	RIV	25.65	A	JCT. RTE. 74	17,000	1,615	9.50	1,063	202	257	94	65.80	12.50	15.90	5.80	126	87E
079	08	RIV	40.449	B	BEAUMONT, JCT. RTE. 10	27,000	2,808	10.40	1,429	270	90	1,019	50.90	9.60	3.20	36.30	440	91V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
080	04	SF	3.951	A	SAN FRANCISCO, JCT. RTE. 101	173,000	5,017	2.90	2,288	607	186	1,937	45.60	12.10	3.70	38.60	832	94V
080	04	ALA	1.989	B	SAN FRANCISCO-OAKLAND BAY BRIDGE TOLL PLAZA	245,000	6,321	2.58	3,466	451	265	2,138	54.83	7.14	4.19	33.83	939	00V
080	04	ALA	1.989	A	SAN FRANCISCO-OAKLAND BAY BRIDGE TOLL PLAZA	245,000	6,150	2.51	2,747	433	195	2,775	44.66	7.04	3.17	45.13	1,122	03V
080	04	ALA	2.802	B	OAKLAND, JCT. RTE. 580 EAST	145,000	2,567	1.77	1,176	178	100	1,113	45.80	6.94	3.90	43.36	456	00V
080	04	ALA	3.786	A	EMERYVILLE, POWELL STREET	265,000	12,694	4.79	4,822	1,115	470	6,286	37.99	8.78	3.70	49.52	2,509	03V
080	04	ALA	4.582	B	BERKELEY, JCT. RTE. 13 EAST	265,000	12,747	4.81	4,464	1,271	509	6,505	35.02	9.97	3.99	51.03	2,592	00V
080	04	ALA	4.582	A	BERKELEY, JCT. RTE. 13 EAST	262,000	12,497	4.77	4,799	1,096	499	6,104	38.40	8.77	3.99	48.84	2,448	03V
080	04	CC	2.04	B	RICHMOND, JCT. RTE. 123 SOUTH	167,000	5,344	3.20	1,886	572	208	2,677	35.30	10.70	3.90	50.10	1,073	01E
080	04	CC	2.04	A	RICHMOND, JCT. RTE. 123 SOUTH	191,000	6,112	3.20	2,109	593	220	3,190	34.50	9.70	3.60	52.20	1,261	01E
080	04	CC	2.961	B	RICHMOND, SAN PABLO AVENUE	188,000	6,091	3.24	2,121	478	280	3,212	34.82	7.84	4.60	52.74	1,268	00V
080	04	CC	2.961	A	RICHMOND, SAN PABLO AVENUE	194,000	6,887	3.55	2,324	481	241	3,842	33.74	6.98	3.50	55.79	1,487	00V
080	04	CC	5.983	B	RICHMOND, HILLTOP DRIVE	183,000	7,320	4.00	2,723	739	198	3,660	37.20	10.10	2.70	50.00	1,455	01E
080	04	CC	7.597	O	PINOLE, APPIAN WAY	190,000	8,303	4.37	2,545	629	245	4,885	30.65	7.57	2.95	58.84	1,868	00V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
080	04	CC	7.597	B	PINOLE, APPIAN WAY	177,000	7,399	4.18	2,360	481	260	4,299	31.89	6.50	3.51	58.10	1,648	03V
080	04	CC	10.059	B	HERCULES, JCT. RTE. 4 EAST	171,000	7,866	4.60	2,665	589	286	4,326	33.88	7.49	3.63	55.00	1,682	03V
080	04	CC	10.059	A	HERCULES, JCT. RTE. 4 EAST	116,000	6,206	5.35	1,736	477	135	3,857	27.98	7.69	2.18	62.15	1,455	00V
080	04	CC	14.139	B	CARQUINEZ BRIDGE	108,000	5,400	5.00	1,517	437	173	3,272	28.10	8.10	3.20	60.60	1,248	01E
080	04	SOL	1.144	B	VALLEJO, JCT. RTE. 29 NORTHWEST	108,000	5,173	4.79	1,553	409	252	2,959	30.02	7.91	4.88	57.20	1,150	03V
080	04	SOL	1.144	A	VALLEJO, JCT. RTE. 29 NORTHWEST	102,000	5,100	5.00	1,494	413	122	3,070	29.30	8.10	2.40	60.20	1,167	01E
080	04	SOL	2.22	B	VALLEJO, JCT. RTE. 780 SOUTHEAST	110,000	5,126	4.66	1,342	310	215	3,260	26.18	6.05	4.19	63.59	1,232	03V
080	04	SOL	5.634	B	VALLEJO, JCT. RTE. 37 WEST	126,000	6,514	5.17	1,716	463	281	4,053	26.35	7.11	4.32	62.22	1,542	03V
080	04	SOL	5.634	A	VALLEJO, JCT. RTE. 37 WEST	109,000	5,526	5.07	1,746	342	198	3,240	31.59	6.19	3.58	58.64	1,239	02V
080	04	SOL	R 11.976	B	JCT. RTE. 12 WEST	109,000	6,104	5.60	2,014	501	201	3,388	33.00	8.20	3.30	55.50	1,315	01E
080	04	SOL	R 11.976	A	JCT. RTE. 12 WEST	141,000	7,332	5.20	2,119	565	227	4,421	28.90	7.70	3.10	60.30	1,685	01E
080	04	SOL	12.839	B	JCT. RTE. 680 SOUTH	141,000	9,250	6.56	2,328	612	712	5,597	25.17	6.62	7.70	60.51	2,173	00V
080	04	SOL	12.839	A	JCT. RTE. 680 SOUTH	184,000	10,562	5.74	2,732	658	1,012	6,161	25.87	6.23	9.58	58.33	2,430	00V
080	04	SOL	15.815	B	FAIRFIELD, EAST JCT. RTE. 12	198,000	9,128	4.61	2,701	589	435	5,404	29.59	6.45	4.77	59.20	2,077	03V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
080	04	SOL	15.815	A	FAIRFIELD, EAST JCT. RTE. 12	172,000	9,976	5.80	3,013	668	329	5,966	30.20	6.70	3.30	59.80	2,274	01E
080	04	SOL	20.925	B	FAIRFIELD, NORTH TEXAS STREET	157,000	5,762	3.67	1,676	366	212	3,508	29.09	6.36	3.68	60.88	1,334	03V
080	04	SOL	20.925	A	FAIRFIELD, NORTH TEXAS STREET	161,000	8,453	5.25	2,477	659	304	5,013	29.30	7.80	3.60	59.30	1,921	01E
080	04	SOL	R 28.36	B	JCT. RTE. 505 NORTH	140,000	8,960	6.40	2,365	905	305	5,385	26.40	10.10	3.40	60.10	2,069	01E
080	04	SOL	R 28.36	A	JCT. RTE. 505 NORTH	121,000	7,442	6.15	2,334	586	195	4,327	31.36	7.88	2.62	58.14	1,657	00V
080	04	SOL	38.21	B	JCT. RTE. 113 SOUTH	117,000	7,862	6.72	2,287	545	568	4,462	29.09	6.93	7.23	56.75	1,753	00V
080	04	SOL	38.21	A	JCT. RTE. 113 SOUTH	121,000	8,131	6.72	2,561	870	293	4,407	31.50	10.70	3.60	54.20	1,733	01E
080	04	SOL	42.67	B	JCT. RTE. 113 NORTH	121,000	8,107	6.70	2,351	786	332	4,637	29.00	9.70	4.10	57.20	1,803	01E
080	03	YOL	0.237	B	RICHARDS BOULEVARD	125,000	10,963	8.77	3,127	830	377	6,629	28.52	7.57	3.44	60.47	2,528	00E
080	03	YOL	R 9.905	B	WEST SACRAMENTO, JCT. RTE. 50	150,000	11,055	7.37	3,153	837	380	6,685	28.52	7.57	3.44	60.47	2,550	00E
080	03	YOL	R 9.905	A	WEST SACRAMENTO, JCT. RTE. 50	83,000	8,292	9.99	3,100	910	580	3,701	37.39	10.98	7.00	44.63	1,554	06E
080	03	YOL	R 11.228	A	JCT. RTE. 84 EAST	86,000	8,591	9.99	3,212	943	601	3,834	37.39	10.98	7.00	44.63	1,610	06E
080	03	SAC	M 2.554	B	SACRAMENTO, JCT. RTE. 5	84,000	8,005	9.53	2,993	879	560	3,573	37.39	10.98	7.00	44.63	1,501	06V
080	03	SAC	M 2.554	A	SACRAMENTO, JCT. RTE. 5	144,000	8,251	5.73	2,673	1,073	413	4,092	32.40	13.00	5.00	49.60	1,665	06E
080	03	SAC	R 10.989	B	JCT. RTE. 51	117,000	7,488	6.40	2,276	899	270	4,044	30.40	12.00	3.60	54.00	1,597	06E
080	03	SAC	R 10.989	A	JCT. RTE. 51	213,000	8,286	3.89	2,478	597	257	4,955	29.90	7.20	3.10	59.80	1,889	06E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
080	03	SAC	14.454	A	GREENBACK LANE	179,000	8,968	5.01	2,870	584	263	5,253	32.00	6.51	2.93	58.57	2,005	06V
080	03	SAC	16.685	A	ANTELOPE ROAD	168,000	10,147	6.04	3,557	574	267	5,749	35.05	5.66	2.63	56.66	2,200	08V
080	03	PLA	0.268	B	ROSEVILLE, RIVERSIDE DRIVE	165,000	8,547	5.18	2,815	579	249	4,904	32.94	6.77	2.91	57.38	1,880	04E
080	03	PLA	0.268	A	ROSEVILLE, RIVERSIDE DRIVE	158,000	8,327	5.27	2,570	619	381	4,758	30.86	7.43	4.57	57.14	1,844	03E
080	03	PLA	3.07	A	ROSEVILLE, ATLANTIC STREET	157,000	9,043	5.76	2,546	663	265	5,569	28.15	7.33	2.93	61.58	2,110	00E
080	03	PLA	4.16	B	JCT. RTE. 65	147,000	9,085	6.18	2,557	666	266	5,595	28.15	7.33	2.93	61.58	2,120	00E
080	03	PLA	4.16	A	JCT. RTE. 65	114,000	6,338	5.56	1,673	314	167	4,184	26.40	4.95	2.64	66.01	1,555	00E
080	03	PLA	14.301	B	JCT. RTE. 193 WEST	77,000	5,837	7.58	1,541	289	154	3,853	26.40	4.95	2.64	66.01	1,432	00E
080	03	PLA	17.541	B	AUBURN, JCT. RTE. 49	78,000	5,507	7.06	1,796	205	84	3,422	32.61	3.73	1.53	62.14	1,275	04E
080	03	PLA	17.541	A	AUBURN, JCT. RTE. 49	61,000	5,216	8.55	1,701	195	80	3,241	32.61	3.73	1.53	62.14	1,207	04E
080	03	PLA	R 19.465	B	AUBURN RAVINE ROAD	57,000	5,535	9.71	1,805	206	85	3,439	32.61	3.73	1.53	62.14	1,281	04E
080	03	PLA	R 19.465	A	AUBURN RAVINE ROAD	52,000	5,621	10.81	1,833	210	86	3,493	32.61	3.73	1.53	62.14	1,301	04E
080	03	PLA	R 23.429	A	CLIPPER GAP	37,500	5,018	13.38	1,216	159	66	3,577	24.23	3.17	1.32	71.28	1,301	10V
080	03	PLA	33.131	B	COLFAX, JCT. RTE. 174 NORTH	33,500	5,350	15.97	1,484	201	77	3,589	27.73	3.76	1.43	67.08	1,320	00E
080	03	PLA	33.131	A	COLFAX, JCT. RTE. 174 NORTH	27,500	5,211	18.95	1,445	196	75	3,496	27.73	3.76	1.43	67.08	1,286	00E
080	03	NEV	R 59.54	B	Jct. Rte. 20 West	24,000	5,160	21.50	1,431	194	74	3,461	27.73	3.76	1.43	67.08	1,273	00E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
080	03	NEV	R 59.54	A	Jct. Rte. 20 West	25,500	4,802	18.83	1,231	202	71	3,298	25.64	4.21	1.47	68.68	1,210	00E
080	03	NEV	14.164	B	TRUCKEE, JCT. RTE. 89 SOUTH	28,000	5,018	17.92	1,307	187	70	3,454	26.05	3.72	1.40	68.84	1,265	00E
080	03	NEV	14.164	A	TRUCKEE, JCT. RTE. 89 SOUTH	33,500	5,919	17.67	1,493	192	79	4,155	25.22	3.25	1.33	70.20	1,515	04E
080	03	NEV	16.285	A	JCT. RTE. 89 NORTH, JCT. RTE. 267 SOUTH	26,500	4,918	18.56	1,240	160	65	3,452	25.22	3.25	1.33	70.20	1,259	04E
080	03	NEV	20.225	B	UNION HILLS BR OH	20,001	3,510	17.55	664	108	38	2,700	18.93	3.08	1.07	76.92	970	10V
080	03	SIE	1.593	B	NEVADA STATE LINE	27,000	5,011	18.56	1,264	163	67	3,518	25.22	3.25	1.33	70.20	1,283	04E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
082	04	SCL	R 0	A	SAN JOSE, JCT. RTE. 101	55,000	1,650	3.00	1,168	238	78	167	70.80	14.40	4.70	10.10	132	01E
082	04	SCL	6.06	A	SAN JOSE, ALMA AVENUE	22,700	851	3.75	656	95	6	94	77.11	11.12	0.74	11.03	65	00V
082	04	SCL	6.9	B	SAN JOSE, JCT. RTE. 280	15,600	577	3.70	463	84	6	24	80.30	14.50	1.00	4.20	33	01E
082	04	SCL	R 7.717	B	SAN JOSE, JCT. RTE. 87	14,800	488	3.30	441	46	1	0	90.30	9.40	0.30	0.00	20	01E
082	04	SCL	9.904	B	SAN JOSE, JCT. RTE. 880	27,000	994	3.68	481	143	115	256	48.38	14.38	11.52	25.71	135	03V
082	04	SCL	9.904	A	SAN JOSE, JCT. RTE. 880	28,500	909	3.19	646	163	51	48	71.10	17.97	5.63	5.30	62	03V
082	04	SCL	10.343	O	SAN JOSE/SANTA CLARA CITY LIMITS	23,800	952	4.00	636	164	20	132	66.80	17.20	2.10	13.90	86	01E
082	04	SCL	R 11.141	B	SANTA CLARA, BENTON ROAD	18,700	1,201	6.42	801	128	19	253	66.71	10.67	1.56	21.05	130	00V
082	04	SCL	17.035	B	MATHILDA AVENUE	31,500	759	2.41	625	61	6	67	82.30	8.00	0.85	8.85	51	00V
082	04	SCL	18.841	B	MOUNTAIN VIEW, JCT. RTE. 85	44,000	1,175	2.67	949	114	47	65	80.79	9.67	4.02	5.52	73	00V
082	04	SCL	18.841	A	MOUNTAIN VIEW, JCT. RTE. 85	48,500	1,077	2.22	839	103	38	97	77.86	9.61	3.51	9.02	78	00V
082	04	SCL	19.134	A	MOUNTAIN VIEW, JCT. RTE. 237 EAST	45,000	1,157	2.57	901	201	9	46	77.88	17.34	0.80	3.98	67	00V
082	04	SCL	25.45	A	PALO ALTO, EMBARCADERO ROAD	37,500	1,181	3.15	977	123	21	61	82.72	10.42	1.74	5.13	70	00V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
082	04	SCL	26.37	B	SANTA CLARA/SAN MATEO COUNTY LINE	30,000	1,368	4.56	1,012	273	12	71	74.00	19.94	0.90	5.16	87	00V
082	04	SM	3.435	B	JCT. RTE. 84	47,500	1,563	3.29	1,113	191	48	211	71.22	12.22	3.10	13.47	136	03V
082	04	SM	3.435	A	JCT. RTE. 84	36,500	836	2.29	600	114	64	58	71.80	13.63	7.60	6.97	61	03V
082	04	SM	5.15	B	REDWOOD CITY/SAN CARLOS CITY LIMITS	26,000	699	2.69	551	77	22	49	78.81	11.07	3.10	7.02	47	00V
082	04	SM	10.554	B	SAN MATEO, JCT. RTE. 92	39,500	521	1.32	406	73	8	34	77.87	14.02	1.52	6.59	34	03V
082	04	SM	10.554	A	SAN MATEO, JCT. RTE. 92	49,000	676	1.38	550	76	14	37	81.31	11.19	2.05	5.46	41	03V
082	04	SM	16.844	A	MILLBRAE, CENTER STREET	21,100	612	2.90	442	79	22	69	72.26	12.85	3.61	11.29	50	03V
082	04	SM	17.99	A	SAN BRUNO, TAYLOR/SAN MATEO AVENUE	29,000	452	1.56	288	115	22	27	63.78	25.41	4.86	5.95	33	00V
082	04	SM	18.6	A	SAN BRUNO, SAN BRUNO AVENUE	36,000	706	1.96	552	86	18	49	78.24	12.19	2.62	6.95	47	03V
082	04	SM	18.963	B	SAN BRUNO, JCT. RTE. 380	36,000	526	1.46	375	75	12	65	71.23	14.21	2.25	12.31	44	03V
082	04	SM	21.91	B	SOUTH SAN FRANCISCO, HICKEY BOULEVARD	25,000	495	1.98	348	52	14	81	70.30	10.51	2.83	16.36	47	03V
082	04	SF	R .208	B	SAN FRANCISCO, JCT. RTE. 280	22,700	161	0.71	121	26	2	12	74.88	16.43	0.97	7.73	11	00V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
083	08	SBD	R 0	A	JCT. RTE. 71	24,500	4,780	19.51	1,711	661	200	2,209	35.79	13.82	4.18	46.21	912	01V
083	08	SBD	6.413	B	RIVERSIDE DRIVE	23,000	3,418	14.86	1,334	531	142	1,411	39.02	15.55	4.15	41.27	603	08V
083	08	SBD	6.413	A	RIVERSIDE DRIVE	29,000	3,573	12.32	1,276	522	151	1,624	35.71	14.61	4.22	45.45	675	04V
083	08	SBD	7.179	B	ONTARIO, JCT. RTE. 60	39,500	3,579	9.06	1,278	523	151	1,627	35.71	14.61	4.22	45.45	676	04E
083	08	SBD	7.179	A	ONTARIO, JCT. RTE. 60	30,000	1,950	6.50	1,020	127	39	764	52.30	6.50	2.00	39.20	317	84E
083	08	SBD	8.879	B	ONTARIO, MISSION BOULEVARD	25,000	1,450	5.80	680	90	23	657	46.90	6.20	1.60	45.30	262	84E
083	08	SBD	8.879	A	ONTARIO, MISSION BOULEVARD	25,000	1,850	7.40	890	118	83	759	48.10	6.40	4.50	41.00	316	84E
083	08	SBD	11.113	B	UPLAND, JCT. RTE. 10, SAN BERNARDINO FREEWAY	34,500	2,174	6.30	1,035	230	172	737	47.60	10.60	7.90	33.90	337	84E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
084	04	SM	0	A	SAN GREGORIO, JCT. RTE. 1	1,350	59	4.36	51	7	2	0	86.11	11.11	2.78	0.00	3	00V
084	04	SM	14.95	B	WOODSIDE, JCT. RTE. 35	3,200	80	2.50	57	14	4	5	71.30	17.40	5.20	6.10	6	01E
084	04	SM	14.95	A	WOODSIDE, JCT. RTE. 35	4,250	100	2.36	42	41	4	14	41.60	40.80	4.00	13.60	11	00V
084	04	SM	21.537	B	WOODSIDE, JCT. RTE. 280	15,800	458	2.90	362	49	32	15	79.00	10.70	7.00	3.30	27	01E
084	04	SM	24.704	B	REDWOOD CITY, JCT. RTE. 82	38,000	1,102	2.90	800	151	35	116	72.60	13.70	3.20	10.50	87	01E
084	04	SM	25.721	B	MENLO PARK, JCT. RTE. 101	43,500	1,279	2.94	814	140	56	269	63.63	10.95	4.38	21.05	142	00V
084	04	SM	R25.81	A	MENLO PARK, JCT. RTE. 101	26,000	754	2.90	526	85	35	107	69.80	11.30	4.70	14.20	68	01E
084	04	SM	R 27.659	B	JCT. RTE. 114	26,000	884	3.40	469	84	41	290	53.07	9.49	4.65	32.80	130	00V
084	04	SM	R 28.194	B	JCT. RTE. 109	48,000	2,165	4.51	996	200	66	903	46.02	9.23	3.05	41.69	374	00V
084	04	ALA	R 4.884	A	NEWARK BOULEVARD	66,000	1,848	2.80	968	213	72	595	52.40	11.50	3.90	32.20	269	01E
084	04	ALA	R 6.01	B	NORTH JCT. RTE. 880	66,000	2,970	4.50	1,589	303	62	1,016	53.50	10.20	2.10	34.20	443	94V
084	04	ALA	6.923	A	SOUTH JCT RTE 880	29,500	1,033	3.50	810	86	17	121	78.40	8.30	1.60	11.70	81	94V
084	04	ALA	10.82	B	FREMONT, JCT. RTE. 238	22,400	515	2.30	424	18	5	67	82.40	3.50	1.00	13.10	40	94V
084	04	ALA	10.83	A	FREMONT, JCT. RTE. 238	15,200	365	2.40	176	22	2	165	48.20	6.00	0.50	45.30	65	94V
084	04	ALA	17.987	B	JCT. RTE. 680	7,100	163	2.30	37	17	3	106	22.80	10.20	1.80	65.20	40	01E
084	04	ALA	R 17.987	A	JCT. RTE. 680	25,500	408	1.60	357	33	16	2	87.40	8.10	4.00	0.50	19	94V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
084	04	ALA	R 28.714	B	LIVERMORE, WEST JCT RTE 580	21,800	604	2.77	400	80	32	92	66.16	13.23	5.32	15.29	58	00V
084	04	SOL	0.134	A	WEST JCT. RTE. 12	3,200	291	9.10	67	44	8	172	23.00	15.10	2.90	59.00	67	95V
084	04	SOL	0.91	B	AIRPORT ROAD	3,700	352	9.50	19	49	10	274	5.50	13.90	2.80	77.80	101	95V
084	04	SOL	0.91	A	AIRPORT ROAD	1,300	96	7.40	8	16	3	69	8.60	16.40	2.80	72.20	26	95V
084	04	SOL	2.485	B	CACHE SLOUGH FERRY	650	36	5.50	5	7	1	22	14.70	20.60	2.90	61.80	9	95V
084	04	SOL	7.246	B	JCT. RTE. 220 EAST	180	11	6.10	3	1	0	7	22.80	10.10	1.20	65.90	3	95V
084	04	SOL	7.246	A	JCT. RTE. 220 EAST	290	19	6.50	4	2	0	13	21.30	10.60	0.50	67.60	5	95V
084	04	SOL	13.67	O	SOLANO/YOLO COUNTY LINE	440	25	5.60	5	3	0	16	20.70	11.80	1.80	65.70	6	95V
084	03	YOL	9.53	A	CLARKSBURG ROAD	1,250	88	7.00	40	20	12	16	45.70	22.20	13.60	18.50	11	96E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
085	04	SCL	0	A	SAN JOSE, JCT. RTE. 101	42,500	548	1.29	524	8	14	3	95.54	1.41	2.58	0.47	22	01V
085	04	SCL	5.22	B	JCT. RTE. 87	132,000	700	0.53	660	12	20	8	94.25	1.77	2.80	1.18	30	01V
085	04	SCL	5.22	A	JCT. RTE. 87	115,000	541	0.47	496	20	25	0	91.72	3.73	4.55	0.00	23	01V
085	04	SCL	R 10.498	B	JCT. RTE. 17	108,000	270	0.25	256	8	6	0	94.66	3.09	2.25	0.00	11	01V
085	04	SCL	R 10.498	A	JCT. RTE. 17	103,000	567	0.55	519	29	12	7	91.47	5.15	2.09	1.29	25	01V
085	04	SCL	R 17.699	A	CUPERTINO, STEVENS CREEK BOULEVARD	122,000	695	0.57	570	40	34	50	82.06	5.79	4.94	7.20	46	01V
085	04	SCL	R 18.448	A	SUNNYVALE, JCT. RTE. 280	113,000	3,447	3.05	1,317	235	58	1,837	38.21	6.81	1.68	53.30	710	01V
085	04	SCL	R 21.749	B	MOUNTAIN VIEW, JCT. RTE. 82	116,000	2,622	2.26	1,336	355	39	892	50.95	13.54	1.48	34.03	393	01V
085	04	SCL	R 22.163	B	JCT. RTE. 237	109,000	3,008	2.76	1,354	528	74	1,052	45.01	17.56	2.46	34.97	470	04V
085	04	SCL	R 22.163	A	JCT. RTE. 237	89,000	1,700	1.91	1,035	188	37	440	60.90	11.04	2.15	25.91	211	01V
085	04	SCL	R 22.629	A	MOUNTAIN VIEW, EVELYN AVENUE	88,000	1,681	1.91	1,015	97	43	525	60.41	5.79	2.54	31.26	232	01V
085	04	SCL	R 23.867	B	MOUNTAIN VIEW, JCT. RTE. 101	81,000	1,620	2.00	546	125	32	917	33.70	7.70	2.00	56.60	352	01E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
086	11	IMP	R 0	A	JCT. RTE. 111	6,600	429	6.50	312	29	18	71	72.70	6.70	4.10	16.50	41	78V
086	11	IMP	6.006	B	JCT. RTE. 8	21,800	1,308	6.00	903	98	43	264	69.00	7.50	3.30	20.20	138	78E
086	11	IMP	6.006	A	JCT. RTE. 8	29,500	1,859	6.30	1,234	151	41	433	66.40	8.10	2.20	23.30	212	78V
086	11	IMP	L 8.525	B	ADAMS/IMPERIAL AVENUES	18,600	1,228	6.60	743	95	72	318	60.50	7.70	5.90	25.90	155	79V
086	11	IMP	7.308	A	ADAMS/IMPERIAL AVENUES	31,500	1,985	6.30	959	220	36	770	48.30	11.10	1.80	38.80	325	78V
086	11	IMP	15.32	B	KEYSTONE ROAD	13,700	841	6.14	492	81	36	232	58.51	9.58	4.28	27.62	110	06V
086	11	IMP	20.627	B	SOUTH JCT. RTE. 78	11,600	1,181	10.18	444	101	192	444	37.57	8.54	16.23	37.57	206	03E
086	11	IMP	20.627	A	SOUTH JCT. RTE. 78	16,100	860	5.34	277	92	65	425	32.26	10.75	7.53	49.46	174	03E
086	11	IMP	R 27.211	B	WESTMORLAND, B STREET	10,500	2,983	28.41	447	248	597	1,690	15.00	8.33	20.00	56.67	709	03E
086	11	IMP	27.51	B	WESTMORLAND, CENTER STREET	9,800	2,762	28.18	534	61	72	2,094	19.35	2.22	2.62	75.81	757	03E
086	11	IMP	43.559	B	NORTH JCT. RTE. 78	10,600	2,457	23.18	475	55	64	1,863	19.35	2.22	2.62	75.81	674	03E
086	11	IMP	43.559	A	NORTH JCT. RTE. 78	9,600	3,456	36.00	525	231	809	1,890	15.19	6.68	23.40	54.70	811	03E
086	11	IMP	67.824	B	IMPERIAL RIVERSIDE COUNTY LINE	13,500	4,323	32.02	2,081	264	168	1,810	48.14	6.11	3.89	41.86	746	09V
086	08	RIV	5.749	B	JCT. RTE. 195 NORTH	3,000	819	27.30	165	50	25	580	20.10	6.10	3.00	70.80	214	80E
086	08	RIV	5.749	A	JCT. RTE. 195 NORTH	3,150	851	27.00	102	68	9	672	12.00	8.00	1.00	79.00	243	94E
086	08	RIV	12.284	A	66TH AVENUE	5,900	1,593	27.00	191	127	16	1,258	12.00	8.00	1.00	79.00	455	94E
086	08	RIV	17.32	B	AVENUE 56/AIRPORT BOULEVARD	6,200	2,015	32.50	508	109	64	1,334	25.20	5.40	3.20	66.20	497	78E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
086	08	RIV	17.32	A	AVENUE 56/AIRPORT BOULEVARD	5,400	1,404	26.00	386	72	38	908	27.50	5.10	2.70	64.70	339	78E
086	08	RIV	20.515	B	COACHELLA, SOUTH JCT. RTE. 111	18,800	3,854	20.50	1,098	177	104	2,474	28.50	4.60	2.70	64.20	924	78E
086	08	RIV	21.52	B	DILLON ROAD/AVENUE 48	28,000	4,760	17.00	1,476	200	81	3,004	31.00	4.20	1.70	63.10	1,118	78V
086	08	RIV	21.52	A	DILLON ROAD/AVENUE 48	27,000	4,590	17.00	1,478	202	106	2,804	32.20	4.40	2.30	61.10	1,053	78E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
087	04	SCL	0	A	SAN JOSE, JCT. RTE 85	83,000	266	0.32	246	6	12	2	92.65	2.21	4.41	0.74	12	01V
087	04	SCL	2.826	B	CURTNER AVENUE	120,000	2,040	1.70	1,410	349	63	218	69.10	17.10	3.10	10.70	166	95V
087	04	SCL	3.563	A	ALMADEN EXPRESSWAY	136,000	3,482	2.56	1,685	371	191	1,236	48.38	10.65	5.48	35.49	548	01V
087	04	SCL	5.156	B	SAN JOSE, JCT. RTE. 280	155,000	3,705	2.39	2,023	516	194	971	54.60	13.94	5.24	26.22	482	01V
087	04	SCL	5.156	A	SAN JOSE, JCT. RTE. 280	93,000	3,441	3.70	2,471	447	117	406	71.80	13.00	3.40	11.80	285	95V
087	04	SCL	9.22	B	JCT. RTE. 101	67,000	2,010	3.00	1,166	287	141	416	58.00	14.30	7.00	20.70	231	95V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
088	10	SJ	19.174	B	CLEMENTS, JCT. RTE. 12 EAST	14,300	1,058	7.40	164	209	33	652	15.50	19.80	3.10	61.60	255	96E
088	10	SJ	19.174	A	CLEMENTS, JCT. RTE. 12 EAST	14,700	1,323	9.00	165	254	52	852	12.50	19.20	3.90	64.40	331	96V
088	10	AMA	5.527	B	JCT. RTE. 124 NORTH	9,000	775	8.61	120	161	25	469	15.50	20.80	3.20	60.50	184	96V
088	10	AMA	5.527	A	JCT. RTE. 124 NORTH	7,800	576	7.39	85	144	22	325	14.80	25.00	3.80	56.40	132	96V
088	10	AMA	7.389	A	WEST JCT. RTE. 104	8,500	196	2.30	24	59	12	100	12.30	30.30	6.30	51.10	43	97V
088	10	AMA	14.25	B	JCT. RTE. 49	14,400	851	5.91	261	281	25	284	30.64	33.03	2.89	33.43	137	96V
088	10	AMA	14.292	A	JCT. RTE. 49	10,500	578	5.50	155	195	35	192	26.80	33.80	6.10	33.30	95	96V
088	10	AMA	22.69	B	PINE GROVE, RIDGE ROAD	12,100	847	7.00	191	277	37	341	22.60	32.70	4.40	40.30	155	96V
088	10	AMA	22.69	A	PINE GROVE, RIDGE ROAD	20,100	1,166	5.80	231	290	41	604	19.80	24.90	3.50	51.80	249	96V
088	10	AMA	R 26.791	B	JCT RTE 26, RED CORRAL RD	9,700	728	7.50	159	142	15	412	21.80	19.50	2.10	56.60	163	96V
088	10	AMA	R 26.791	A	JCT RTE 26, RED CORRAL RD	7,600	570	7.50	133	113	10	314	23.40	19.80	1.80	55.00	125	96V
088	10	ALP	13.4	B	PICKETTS, WEST JCT. RTE. 89	2,650	209	7.90	41	55	8	104	19.80	26.50	3.90	49.80	44	96V
088	10	ALP	13.4	A	PICKETTS, WEST JCT. RTE. 89	3,250	250	7.70	55	50	7	133	22.00	20.00	2.80	53.20	53	96E
088	10	ALP	25.283	B	NEVADA STATE LINE	3,800	281	7.40	68	38	4	171	24.20	13.50	1.60	60.70	65	96V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
089	09	MNO	0	A	SLINKARD JUNCTION, JCT. RTE. 395	260	18	7.00	12	3	1	2	66.60	16.66	8.00	8.74	2	08V
089	09	MNO	7.596	O	MONO/ALPINE COUNTY LINE	275	13	4.80	4	4	1	4	32.10	29.60	4.70	33.60	2	96V
089	10	ALP	0	O	MONO/ALPINE COUNTY LINE	275	13	4.80	4	4	1	4	32.10	29.60	4.70	33.60	2	96V
089	10	ALP	9.957	B	BULLION, JCT. RTE. 4 WEST	500	27	5.38	11	7	1	8	41.50	25.80	4.50	28.20	4	96V
089	10	ALP	9.957	A	BULLION, JCT. RTE. 4 WEST	820	44	5.41	17	17	1	9	38.90	37.80	3.40	19.90	5	96V
089	10	ALP	21.366	B	PICKETTS, JCT. RTE. 88	1,900	253	13.33	35	42	35	141	13.89	16.67	13.89	55.56	59	06E
089	10	ALP	21.376	A	PICKETTS, JCT. RTE. 88	2,300	307	13.33	43	51	43	171	13.89	16.67	13.89	55.56	72	06E
089	03	ED	0	A	ALPINE/EL DORADO COUNTY LINE; LUTHER PASS (ELEV. 7740)	2,300	307	13.33	43	51	43	171	13.89	16.67	13.89	55.56	72	06E
089	03	ED	8.55	B	JCT. RTE. 50	5,500	338	6.14	125	75	50	88	37.04	22.22	14.81	25.93	49	06E
089	03	ED	8.56	A	JCT. RTE. 50	16,900	272	1.61	203	34	20	16	74.48	12.41	7.24	5.86	19	06E
089	03	ED	11.686	B	FALLEN LEAF LAKE ROAD	3,950	80	2.03	39	22	15	4	48.75	27.50	18.75	5.00	7	10V
089	03	ED	11.686	A	FALLEN LEAF LAKE ROAD	3,800	155	4.09	125	15	10	5	80.52	9.74	6.49	3.25	9	05E
089	03	ED	19.54	A	BLISS MEMORIAL STATE PARK ROAD	3,500	143	4.09	115	14	9	5	80.52	9.74	6.49	3.25	8	06E
089	03	PLA	5.812	B	WARD CREEK BRIDGE	6,500	260	4.00	92	85	64	19	35.44	32.57	24.57	7.42	27	05E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
089	03	PLA	T 8.569	B	TAHOE CITY, JCT. RTE. 28 EAST	11,900	749	6.29	530	110	46	64	70.73	14.63	6.10	8.54	58	06E
089	03	PLA	T 8.569	A	TAHOE CITY, JCT. RTE. 28 EAST	10,600	783	7.39	554	115	48	67	70.73	14.63	6.10	8.54	60	06E
089	03	PLA	13.72	A	SQUAW VALLEY ROAD	10,600	783	7.39	554	115	48	67	70.73	14.63	6.10	8.54	60	06V
089	03	NEV	5.04	B	HOBART MILLS ROAD	1,650	209	12.68	48	68	36	56	23.08	32.69	17.31	26.92	33	06E
089	03	SIE	15.055	B	SIERRAVILLE, JCT. RTE. 49 NORTH	1,850	235	12.68	54	77	41	63	23.08	32.69	17.31	26.92	37	06E
089	03	SIE	15.055	A	SIERRAVILLE, JCT. RTE. 49 NORTH	1,200	160	13.33	36	62	36	27	22.22	38.89	22.22	16.67	22	06E
089	03	SIE	19.958	B	JCT. RTE. 49 WEST	1,200	160	13.33	36	62	36	27	22.22	38.89	22.22	16.67	22	06E
089	03	SIE	19.958	A	JCT. RTE. 49 WEST	980	89	9.09	35	23	2	29	39.00	26.00	2.00	33.00	14	04E
089	02	PLU	0	A	SIERRA/PLUMAS COUNTY LINE	680	51	7.50	26	6	2	17	50.98	11.76	3.92	33.33	8	10V
089	02	PLU	7.08	A	GOLD LAKE ROAD	1,450	40	2.76	19	4	1	16	47.48	10.00	2.50	39.98	7	10V
089	02	PLU	8.71	B	BLAIRSDEN, JCT. RTE. 70	2,000	100	5.00	19	19	6	56	19.00	19.00	6.00	56.00	23	10V
089	02	PLU	8.72	A	BLAIRSDEN, JCT. RTE. 70	2,050	192	9.37	64	38	9	81	33.33	19.79	4.69	42.19	35	10V
089	02	PLU	14.84	A	ARLINGTON ROAD	2,100	274	13.05	42	96	11	125	15.33	35.04	4.01	45.62	55	10V
089	02	PLU	20.22	B	GREENVILLE, GRAND STREET	2,900	271	9.34	42	97	3	129	15.50	35.79	1.11	47.60	55	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
089	02	PLU	20.47	B	GREENVILLE, BECKWOURTH ROAD	2,900	269	9.28	42	96	3	128	15.50	35.79	1.11	47.60	55	10E
089	02	PLU	20.47	A	GREENVILLE, BECKWOURTH ROAD	1,500	197	13.13	19	92	2	84	9.64	46.70	1.02	42.64	38	10V
089	02	PLU	29.589	B	JCT. RTE. 147 NORTH	2,100	199	9.48	37	54	6	102	18.59	27.14	3.02	51.26	42	10V
089	02	PLU	29.589	A	JCT. RTE. 147 NORTH	1,150	152	13.22	15	60	2	75	9.87	39.47	1.32	49.34	32	10V
089	02	PLU	36.655	B	ALMANOR	1,150	150	13.05	15	46	3	87	9.73	30.70	1.80	57.77	35	10E
089	02	PLU	R 42.185	B	JCT. RTE. 36	1,700	219	12.88	21	48	5	145	9.59	21.92	2.28	66.21	56	10V
089	02	TEH	R .01	A	JCT. RTE. 36	290	3	0.94	2	1	0	0	51.63	48.37	0.00	0.00	0	10E
089	02	TEH	4.403	B	JCT. RTE. 44, LASSEN NATIONAL PARK	290	3	0.94	2	1	0	0	51.63	48.37	0.00	0.00	0	10E
089	02	SHA	0	A	JCT. RTE. 44, LASSEN NATIONAL PARK	1,450	295	20.34	22	25	11	237	7.46	8.47	3.73	80.34	86	10V
089	02	SHA	21.719	B	FOUR CORNERS, JCT. RTE. 299	1,700	233	13.73	24	25	10	174	10.11	10.59	4.41	74.89	65	10E
089	02	SHA	21.719	A	FOUR CORNERS, JCT. RTE. 299	1,900	377	19.84	49	87	10	231	13.04	23.03	2.78	61.15	91	10E
089	02	SHA	30	O	LAKE BRITTON ROAD	1,500	296	19.70	26	59	9	203	8.63	20.01	2.94	68.43	78	10E
089	02	SHA	43.345	B	SHASTA/SISKIYOU COUNTY LINE	1,850	362	19.56	15	62	11	274	4.21	16.99	3.10	75.70	102	10E
089	02	SIS	14.34	A	MILITARY PASS ROAD	1,900	375	19.75	26	64	13	272	6.96	16.99	3.44	72.61	103	10E
089	02	SIS	24.75	B	BROADWAY/SOUTHERN AVENUE	2,900	563	19.41	49	147	19	348	8.75	26.16	3.35	61.75	138	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
089	02	SIS	R 34.622	B	JCT. RTE. 5	3,500	489	13.97	42	118	16	313	8.67	24.15	3.23	63.95	123	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
090	07	LA	0.921	A	LOS ANGELES, JCT. RTE. 1, LINCOLN BOULEVARD	31,000	1,032	3.33	640	109	34	248	62.05	10.61	3.27	24.07	123	06E
090	07	LA	1.746	A	LOS ANGELES, CULVER BOULEVARD	65,000	2,457	3.78	1,525	261	80	591	62.05	10.61	3.27	24.07	293	06V
090	07	LA	2.65	B	CULVER CITY, JCT. RTE. 405, SAN DIEGO FREEWAY INTERCHANGE	82,000	3,100	3.78	1,924	329	101	746	62.05	10.61	3.27	24.07	370	06E
090	07	LA	2.65	A	CULVER CITY, JCT. RTE. 405, SAN DIEGO FREEWAY INTERCHANGE	36,000	875	2.43	686	65	5	118	78.44	7.48	0.61	13.47	71	06V
090	07	LA	T 3.278	B	CULVER CITY, SLAUSON AVENUE	36,000	875	2.43	686	65	5	118	78.44	7.48	0.61	13.47	71	06V
090	12	ORA	0.5	A	LA HABRA, JCT. RTE. 39	47,000	3,055	6.50	1,525	272	97	1,161	49.91	8.90	3.19	38.01	493	89V
090	12	ORA	2.497	B	LA HABRA, HARBOR BOULEVARD	47,000	3,619	7.70	1,600	333	94	1,592	44.20	9.20	2.60	44.00	650	89V
090	12	ORA	2.497	A	LA HABRA, HARBOR BOULEVARD	44,000	2,684	6.10	1,479	303	99	803	55.10	11.30	3.70	29.90	371	89V
090	12	ORA	4.391	B	BREA, BREA BOULEVARD	51,000	3,264	6.40	1,831	379	111	943	56.10	11.60	3.40	28.90	441	89V
090	12	ORA	4.391	A	BREA, BREA BOULEVARD	51,000	3,417	6.70	2,067	345	130	875	60.50	10.10	3.80	25.60	425	89V
090	12	ORA	R 5.453	B	BREA, JCT. RTE. 57, ORANGE FREEWAY	68,000	4,148	6.10	2,099	539	137	1,373	50.60	13.00	3.30	33.10	617	89V
090	12	ORA	7.271	B	BREA, JCT. RTE. 142 NORTHEAST	40,000	2,880	7.20	1,809	271	58	743	62.80	9.40	2.00	25.80	353	89V
090	12	ORA	7.271	A	BREA, JCT. RTE. 142 NORTHEAST	29,000	1,421	4.90	929	242	40	210	65.40	17.00	2.80	14.80	133	89V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
090	12	ORA	12.828	B	ANAHEIM, JCT. RTE. 91	54,000	2,700	5.00	1,995	273	59	373	73.90	10.10	2.20	13.80	232	89V
090	12	ORA	12.828	B	ANAHEIM, JCT. RTE. 91	54,000	2,700	5.00	1,995	273	59	373	73.90	10.10	2.20	13.80	232	89V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
091	07	LA	6.354	B	LOS ANGELES, JCT. RTE. 110, HARBOR FREEWAY INTERCHANGE	63,000	3,679	5.84	2,053	343	95	1,189	55.79	9.32	2.58	32.31	528	10E
091	07	LA	R 6.344	A	LOS ANGELES, JCT. RTE. 110, HARBOR FREEWAY INTERCHANGE	192,000	14,726	7.67	8,216	1,372	380	4,758	55.79	9.32	2.58	32.31	2,111	10E
091	07	LA	R 7.426	A	CARSON, AVALON BOULEVARD INTERCHANGE	195,000	14,957	7.67	8,345	1,394	386	4,833	55.79	9.32	2.58	32.31	2,144	10V
091	07	LA	R 11.681	B	LONG BEACH, JCT. RTE. 710, LONG BEACH FREEWAY INTERCHANGE	213,000	16,337	7.67	9,114	1,523	421	5,278	55.79	9.32	2.58	32.31	2,342	10E
091	07	LA	R 11.681	A	LONG BEACH, JCT. RTE. 710, LONG BEACH FREEWAY INTERCHANGE	250,000	19,350	7.74	7,990	2,446	927	7,986	41.29	12.64	4.79	41.27	3,396	10E
091	07	LA	R 13.094	A	LONG BEACH, CHERRY AVENUE INTERCHANGE	250,000	19,350	7.74	7,990	2,446	927	7,986	41.29	12.64	4.79	41.27	3,396	10V
091	07	LA	R 14.618	B	BELLFLOWER, JCT. RTE. 19, LAKEWOOD BOULEVARD INTERCHANGE	247,000	19,118	7.74	7,894	2,417	916	7,890	41.29	12.64	4.79	41.27	3,355	10E
091	07	LA	R 14.618	A	BELLFLOWER, JCT. RTE. 19, LAKEWOOD BOULEVARD INTERCHANGE	237,000	18,344	7.74	7,574	2,319	879	7,571	41.29	12.64	4.79	41.27	3,220	10E
091	07	LA	R 16.941	B	CERRITOS, JCT. RTE. 605, SAN GABRIEL RIVER FREEWAY INTERCHANGE	245,000	18,963	7.74	7,830	2,397	908	7,826	41.29	12.64	4.79	41.27	3,328	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
091	07	LA	R 16.941	A	CERRITOS, JCT. RTE. 605, SAN GABRIEL RIVER FREEWAY INTERCHANGE	270,000	14,526	5.38	6,861	1,893	670	5,103	47.23	13.03	4.61	35.13	2,273	10E
091	07	LA	R 20.741	B	LOS ANGELES/ORANGE COUNTY LINE	232,000	13,990	6.03	6,840	1,700	644	4,807	48.89	12.15	4.60	34.36	2,149	10E
091	12	ORA	R 2.615	B	BUENA PARK, JCT. RTE. 39/BEACH BOULEVARD	266,000	21,493	8.08	8,735	1,741	864	10,153	40.64	8.10	4.02	47.24	4,096	07E
091	12	ORA	R 2.615	A	BUENA PARK, JCT. RTE. 39/BEACH BOULEVARD	276,000	22,301	8.08	9,063	1,806	897	10,535	40.64	8.10	4.02	47.24	4,250	07E
091	12	ORA	R 3.638	A	FULLERTON, JCT. RTE. 5, SANTA ANA FREEWAY	280,000	19,040	6.80	10,529	2,018	1,257	5,236	55.30	10.60	6.60	27.50	2,545	82E
091	12	ORA	3.258	B	FULLERTON, HARBOR BOULEVARD	280,000	19,880	7.10	9,224	1,948	1,928	6,779	46.40	9.80	9.70	34.10	3,124	82E
091	12	ORA	3.258	A	FULLERTON, HARBOR BOULEVARD	270,000	18,360	6.80	8,629	1,873	1,579	6,279	47.00	10.20	8.60	34.20	2,873	82E
091	12	ORA	5.258	B	ANAHEIM, STATE COLLEGE BOULEVARD	261,600	24,067	9.20	11,384	3,418	1,781	7,485	47.30	14.20	7.40	31.10	3,557	82E
091	12	ORA	5.258	A	ANAHEIM, STATE COLLEGE BOULEVARD	256,000	22,272	8.70	10,468	2,984	1,336	7,483	47.00	13.40	6.00	33.60	3,419	82E
091	12	ORA	6.119	A	ANAHEIM, JCT. RTE. 57, ORANGE FREEWAY	223,000	19,401	8.70	6,674	2,949	1,552	8,226	34.40	15.20	8.00	42.40	3,571	84E
091	12	ORA	R 9.187	B	JCT. RTE. 55 SOUTH	230,800	15,002	6.50	8,716	1,275	585	4,426	58.10	8.50	3.90	29.50	2,035	91E
091	12	ORA	R 9.187	A	JCT. RTE. 55 SOUTH	321,000	14,445	4.50	7,800	809	289	5,547	54.00	5.60	2.00	38.40	2,304	91E
091	12	ORA	R 11.54	B	PERALTA, JCT. RTE. 90 WEST	302,000	15,100	5.00	7,550	831	302	6,418	50.00	5.50	2.00	42.50	2,599	91E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
091	12	ORA	R 11.54	A	PERALTA, JCT. RTE. 90 WEST	255,000	12,113	4.75	5,375	826	338	5,573	44.37	6.82	2.79	46.01	2,236	08E
091	08	RIV	R 2.087	B	JCT. RTE. 71 NORTH	253,000	15,104	5.97	6,323	1,171	586	7,025	41.86	7.75	3.88	46.51	2,839	00E
091	08	RIV	R 2.087	A	JCT. RTE. 71 NORTH	256,000	16,666	6.51	7,143	1,190	595	7,738	42.86	7.14	3.57	46.43	3,117	00E
091	08	RIV	6.343	B	CORONA, MAIN STREET	247,000	16,080	6.51	6,892	1,148	574	7,466	42.86	7.14	3.57	46.43	3,007	00E
091	08	RIV	6.343	A	CORONA, MAIN STREET	233,000	14,120	6.06	6,052	1,008	504	6,556	42.86	7.14	3.57	46.43	2,640	00E
091	08	RIV	9.18	B	MC KINLEY STREET	219,000	14,804	6.76	6,345	1,057	529	6,873	42.86	7.14	3.57	46.43	2,768	00E
091	08	RIV	9.18	A	MC KINLEY STREET	209,000	16,072	7.69	6,888	1,148	574	7,462	42.86	7.14	3.57	46.43	3,005	00E
091	08	RIV	11.991	B	RIVERSIDE, LA SIERRA AVENUE	193,000	16,366	8.48	7,014	1,169	584	7,599	42.86	7.14	3.57	46.43	3,061	00E
091	08	RIV	14.079	B	RIVERSIDE, VAN BUREN STREET	186,000	9,300	5.00	6,417	558	372	1,953	69.00	6.00	4.00	21.00	1,004	81E
091	08	RIV	14.079	A	RIVERSIDE, VAN BUREN STREET	173,000	8,650	5.00	5,969	519	346	1,817	69.00	6.00	4.00	21.00	934	81V
091	08	RIV	19.999	B	RIVERSIDE, 14TH STREET	165,000	8,250	5.00	5,693	495	330	1,733	69.00	6.00	4.00	21.00	891	81E
091	08	RIV	21.659	B	RIVERSIDE, JCT. RTE. 60, JCT. RTE. 215 NORTH, RIVERSIDE/ESCONDIDO FREEWAY INTERCHANGE	149,000	7,450	5.00	5,141	447	298	1,565	69.00	6.00	4.00	21.00	805	81E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
092	04	SM	0	A	HALF MOON BAY, JCT. RTE. 1	17,600	649	3.69	272	69	37	270	41.98	10.69	5.74	41.59	114	03V
092	04	SM	5.191	B	JCT. RTE. 35 SOUTH	22,800	841	3.69	353	90	48	350	41.98	10.69	5.74	41.59	148	03E
092	04	SM	5.191	A	JCT. RTE. 35 SOUTH	24,300	1,312	5.40	592	167	5	548	45.10	12.70	0.40	41.80	226	94V
092	04	SM	R 11.208	B	JCT. RTE. 82	86,000	1,978	2.30	1,226	265	26	461	62.00	13.40	1.30	23.30	230	94V
092	04	SM	R 12.143	B	SAN MATEO, JCT. RTE. 101	104,000	2,496	2.40	1,565	295	50	587	62.70	11.80	2.00	23.50	292	94V
092	04	SM	R 12.143	A	SAN MATEO, JCT. RTE. 101	139,000	6,255	4.50	3,228	594	188	2,246	51.60	9.50	3.00	35.90	970	94V
092	04	SM	R 14.443	B	SAN MATEO/HAYWARD BRIDGE	86,000	5,590	6.50	2,767	492	28	2,303	49.50	8.80	0.50	41.20	941	94V
092	04	ALA	6.392	B	HAYWARD, JCT. RTE. 880	100,000	7,000	7.00	3,143	749	315	2,793	44.90	10.70	4.50	39.90	1,189	94V
092	04	ALA	6.392	A	HAYWARD, JCT. RTE. 880	56,000	1,176	2.10	796	168	44	168	67.70	14.30	3.70	14.30	108	94V
092	04	ALA	8.219	B	HAYWARD, JCT. RTES. 185/238	40,000	584	1.46	414	66	19	85	70.89	11.30	3.25	14.55	53	03V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
094	11	SD	1.416	A	BEGIN RTE AT JCT RTE 5 and EB ON FRM "G" ST / 17TH	109,000	3,924	3.60	2,731	279	67	848	69.60	7.10	1.70	21.60	424	86V
094	11	SD	3.172	B	SAN DIEGO, JCT. RTE. 15	146,000	3,942	2.70	3,272	335	91	244	83.00	8.50	2.30	6.20	243	81V
094	11	SD	3.172	A	SAN DIEGO, JCT. RTE. 15	138,000	5,796	4.20	4,695	412	168	522	81.00	7.10	2.90	9.00	407	80E
094	11	SD	4.086	A	SAN DIEGO, JCT. RTE. 805	172,000	6,708	3.90	4,877	651	161	1,020	72.70	9.70	2.40	15.20	606	86E
094	11	SD	7.758	B	COLLEGE AVENUE	145,000	5,655	3.90	4,111	549	136	860	72.70	9.70	2.40	15.20	511	86V
094	11	SD	10.006	B	JCT. RTE. 125	133,000	4,921	3.70	3,509	453	153	807	71.30	9.20	3.10	16.40	465	78V
094	11	SD	T10.11	A	JCT. RTE. 125	86,000	4,300	5.00	2,442	585	120	1,152	56.80	13.60	2.80	26.80	554	96E
094	11	SD	R 13.333	B	AVOCADO BOULEVARD	57,000	2,850	5.00	1,619	388	80	764	56.80	13.60	2.80	26.80	368	96E
094	11	SD	14.86	B	JCT. RTE. 54 NORTH	62,000	2,852	4.60	1,360	337	60	1,095	47.70	11.80	2.10	38.40	465	96E
094	11	SD	14.86	A	JCT. RTE. 54 NORTH	16,400	984	6.00	691	92	41	160	70.20	9.30	4.20	16.30	94	96E
094	11	SD	19.4	B	LYONS VALLEY ROAD	17,000	1,020	6.00	716	95	43	166	70.20	9.30	4.20	16.30	97	96E
094	11	SD	19.4	A	LYONS VALLEY ROAD	10,600	742	7.00	490	76	14	162	66.00	10.30	1.90	21.80	82	96E
094	11	SD	38.97	B	JCT. RTE. 188 SOUTH	5,400	448	8.30	189	29	20	210	42.10	6.50	4.50	46.90	85	96E
094	11	SD	52.15	B	BUCKMAN SPRINGS ROAD	1,750	145	8.30	61	9	7	68	42.10	6.50	4.50	46.90	27	96E
094	11	SD	52.15	A	BUCKMAN SPRINGS ROAD	1,750	275	15.70	148	33	0	94	53.90	11.90	0.00	34.20	41	96E
094	11	SD	65.375	B	JCT. RTE. 8	1,050	165	15.70	89	20	0	56	53.90	11.90	0.00	34.20	24	96E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
095	08	RIV	L .157	A	JCT. RTE. 10	6,200	744	12.00	351	100	25	267	47.20	13.50	3.40	35.90	117	93E
095	08	RIV	0	A	HOBSON WAY	3,200	384	12.00	182	52	14	136	47.30	13.60	3.60	35.50	60	93V
095	08	RIV	10.54	B	PALO VERDE DAM ROAD	1,800	324	18.00	153	44	12	115	47.30	13.60	3.60	35.50	51	93V
095	08	SBD	9.684	B	JCT. RTE. 62	1,450	197	13.60	41	0	0	156	21.00	0.00	0.00	79.00	55	92V
095	08	SBD	9.684	A	JCT. RTE. 62	2,700	680	25.19	138	6	10	526	20.23	0.95	1.51	77.32	188	98V
095	08	SBD	37.3	A	HAVASU LAKE ROAD	5,100	945	18.53	198	28	9	709	21.00	3.00	1.00	75.00	255	98E
095	08	SBD	R 57.207	A	EAST JCT. RTE. 40	5,400	853	15.79	186	29	0	638	21.75	3.41	0.00	74.84	229	94V
095	08	SBD	R 57.244	A	WEST JCT. RTE. 40	3,000	371	12.38	73	7	2	289	19.60	1.90	0.60	77.90	103	94V
095	08	SBD	80.453	B	NEVADA STATE LINE	3,300	396	12.00	79	8	4	305	20.00	2.00	1.00	77.00	109	94E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
096	01	HUM	0	A	WILLOW CREEK, JCT. RTE. 299	2,900	60	2.07	20	10	5	25	33.33	16.67	8.33	41.67	11	06E
096	01	HUM	23.086	B	WEITCHPEC, JCT. RTE. 169	690	63	9.09	21	11	5	26	33.33	16.67	8.33	41.67	11	06E
096	01	HUM	23.086	A	WEITCHPEC, JCT. RTE. 169	450	56	12.50	19	9	5	23	33.33	16.67	8.33	41.67	10	06E
096	02	SIS	23.268	A	SWILLUP CREEK BRIDGE	360	13	3.73	5	0	1	7	35.71	2.38	4.76	57.14	3	10E
096	02	SIS	38.758	A	BENJAMIN CREEK ROAD	540	13	2.43	5	0	1	7	35.71	2.38	4.76	57.14	3	10E
096	02	SIS	41.021	O	INDIAN CREEK BRIDGE	1,150	20	1.71	7	0	1	11	35.71	2.38	4.76	57.14	4	10E
096	02	SIS	41.25	O	HAPPY CAMP, SECOND STREET	1,950	51	2.61	27	11	0	13	53.38	20.86	0.56	25.19	6	10E
096	02	SIS	41.67	B	DAVIS ROAD	1,600	50	3.13	27	10	0	13	53.38	20.86	0.56	25.19	6	10E
096	02	SIS	41.67	A	DAVIS ROAD	880	50	5.68	27	10	0	13	53.38	20.86	0.56	25.19	6	10E
096	02	SIS	R 52.509	B	THOMPSON CREEK BRIDGE	580	27	4.72	10	6	2	10	35.75	22.00	6.25	36.00	5	10E
096	02	SIS	60.757	O	SIEAD MAINTENANCE STATION	570	22	3.86	8	4	1	9	36.36	18.18	4.55	40.91	4	10V
096	02	SIS	71.33	A	SCOTT BAR ROAD	500	20	4.04	11	1	1	7	55.17	5.17	2.59	37.07	3	10E
096	02	SIS	103.418	B	JCT. RTE. 263 SOUTH	800	51	6.38	12	18	1	20	24.33	34.79	2.19	38.69	9	10E
096	02	SIS	103.418	A	JCT. RTE. 263 SOUTH	510	22	4.22	3	6	0	13	11.49	27.36	1.69	59.46	5	10E
096	02	SIS	105.823	B	JCT. RTE. 5	510	22	4.22	3	6	0	13	11.49	27.36	1.69	59.46	5	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
097	02	SIS	L 0	A	WEED, JCT. RTE. 5	10,400	1,072	10.31	59	50	16	947	5.52	4.65	1.50	88.33	336	10E
097	02	SIS	0.05	A	JCT. RTE. 265	7,100	1,089	15.34	51	53	15	970	4.64	4.88	1.38	89.10	344	10E
097	02	SIS	4.43	B	WEED, BIG SPRINGS ROAD	5,500	1,085	19.73	67	46	20	953	6.16	4.22	1.82	87.80	338	10E
097	02	SIS	4.43	A	WEED, BIG SPRINGS ROAD	3,300	1,094	33.14	40	97	28	928	3.62	8.91	2.60	84.87	335	10E
097	02	SIS	20.19	B	GRASS LAKE STATE HIGHWAY MAINTENANCE STATION	3,200	1,081	33.78	53	51	14	963	4.89	4.72	1.33	89.06	341	10E
097	02	SIS	45.248	B	SAMS NECK ROAD	3,150	1,077	34.19	165	33	12	867	15.32	3.06	1.11	80.50	310	10V
097	02	SIS	49.827	O	DORRIS QUARANTINE STATION	3,250	1,079	33.21	69	59	12	940	6.37	5.46	1.08	87.09	334	10E
097	02	SIS	50.89	B	DORRIS, FIRST/MAIN STREETS	4,400	1,087	24.71	71	110	29	877	6.56	10.10	2.64	80.71	319	10E
097	02	SIS	53.809	B	JCT. RTE. 161 EAST	3,950	1,083	27.43	42	51	17	974	3.85	4.71	1.54	89.90	345	10E
097	02	SIS	53.809	A	JCT. RTE. 161 EAST	4,000	1,016	25.41	30	97	38	850	2.94	9.59	3.78	83.68	309	10E
097	02	SIS	54.089	B	OREGON STATE LINE	4,000	1,016	25.41	30	97	38	850	2.94	9.59	3.78	83.69	309	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
098	11	IMP	R .304	A	WEST JCT. RTE. 8	1,550	109	7.00	31	14	11	53	28.60	12.40	10.40	48.60	22	94E
098	11	IMP	22.197	B	DREW ROAD (SUNSET BOULEVARD)	1,900	203	10.70	49	8	9	137	24.10	4.00	4.50	67.40	51	80E
098	11	IMP	22.197	A	DREW ROAD (SUNSET BOULEVARD)	1,950	238	12.20	65	12	11	150	27.50	4.90	4.50	63.10	57	80E
098	11	IMP	31.92	B	CALEXICO, CESAR CHAVEZ BOULEVARD	20,700	1,056	5.10	596	71	27	362	56.40	6.70	2.60	34.30	156	81V
098	11	IMP	32.314	B	JCT. RTE. 111	18,400	1,196	6.50	512	134	47	504	42.80	11.20	3.90	42.10	211	78V
098	11	IMP	32.314	A	JCT. RTE. 111	23,500	893	3.80	545	124	38	187	61.00	13.90	4.20	20.90	101	78V
098	11	IMP	34.46	B	BOWKER ROAD	9,500	1,055	11.10	658	124	5	267	62.40	11.80	0.50	25.30	127	81E
098	11	IMP	34.46	A	BOWKER ROAD	5,000	1,377	27.54	231	169	85	892	16.76	12.29	6.15	64.80	344	04E
098	11	IMP	35.197	B	CALEXICO, COLE ROAD	5,000	2,818	56.36	2,122	65	14	618	75.30	2.29	0.50	21.92	296	08V
098	11	IMP	39.654	B	JCT RTE 7	9,600	1,273	13.26	213	156	78	825	16.76	12.29	6.15	64.80	318	04E
098	11	IMP	39.654	A	JCT RTE 7	2,250	225	10.01	91	27	10	97	40.64	12.01	4.24	43.11	41	07V
098	11	IMP	R 56.884	B	EAST JCT. RTE. 8	1,700	450	26.49	285	18	28	119	63.27	4.08	6.12	26.53	57	04E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
099	06	KER	L .748	A	JCT. RTE. 5	44,000	11,000	25.00	1,650	660	330	8,360	15.00	6.00	3.00	76.00	3,051	05E
099	06	KER	2.732	A	METTLER, JCT. RTE. 166 WEST	45,000	11,250	25.00	1,800	450	338	8,663	16.00	4.00	3.00	77.00	3,143	05E
099	06	KER	13.411	B	JCT. RTE. 223 EAST	47,000	11,750	25.00	1,880	588	353	8,930	16.00	5.00	3.00	76.00	3,253	05E
099	06	KER	17.5	B	JCT. RTE. 119 WEST	54,000	13,084	24.23	3,384	641	270	8,790	25.86	4.90	2.06	67.18	3,250	05V
099	06	KER	22.604	B	BAKERSFIELD, MING AVENUE INTERCHANGE	114,500	10,294	8.99	2,715	447	171	6,961	26.37	4.34	1.66	67.62	2,563	10V
099	06	KER	25.654	B	JCT. RTE. 58 WEST, JCT. RTE. 178 EAST	132,000	27,720	21.00	6,930	1,386	832	1,857	25.00	5.00	3.00	67.00	6,900	05E
099	06	KER	25.654	A	JCT. RTE. 58 WEST, JCT. RTE. 178 EAST	102,500	28,188	27.50	6,765	1,409	564	19,450	24.00	5.00	2.00	69.00	7,160	05E
099	06	KER	R 29.878	B	JCT. RTE. 65	78,000	23,400	30.00	3,744	936	702	18,018	16.00	4.00	3.00	77.00	6,537	04E
099	06	KER	R 29.878	A	JCT. RTE. 65	61,000	18,300	30.00	2,928	732	549	14,091	16.00	4.00	3.00	77.00	5,112	04E
099	06	KER	44.307	B	JCT. RTE. 46	58,000	16,240	28.00	2,761	1,462	974	11,043	17.00	9.00	6.00	68.00	4,184	03V
099	06	KER	44.307	A	JCT. RTE. 46	51,000	13,770	27.00	2,203	551	413	10,603	16.00	4.00	3.00	77.00	3,847	04E
099	06	KER	55.521	B	DELANO, JCT. RTE. 155	49,500	13,860	28.00	2,633	1,802	416	9,009	19.00	13.00	3.00	65.00	3,427	04E
099	06	KER	55.521	A	DELANO, JCT. RTE. 155	46,500	13,020	28.00	2,474	651	391	9,505	19.00	5.00	3.00	73.00	3,483	04E
099	06	TUL	6.148	B	AVENUE 48	43,500	9,200	21.15	1,955	405	246	6,595	21.25	4.40	2.67	71.68	2,417	10V
099	06	TUL	9.712	A	AVENUE 76	38,500	8,131	21.12	1,737	363	247	5,784	21.36	4.46	3.04	71.14	2,126	10E
099	06	TUL	18.429	B	TIPTON, JCT. RTE. 190 EAST	40,500	8,554	21.12	1,827	382	260	6,085	21.36	4.46	3.04	71.14	2,237	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
099	06	TUL	18.429	A	TIPTON, JCT. RTE. 190 EAST	41,000	8,659	21.12	1,850	386	263	6,160	21.36	4.46	3.04	71.14	2,264	10E
099	06	TUL	23.489	B	AVENUE 184	44,500	9,385	21.09	1,999	660	428	6,298	21.30	7.03	4.56	67.11	2,366	10V
099	06	TUL	25.433	B	AVENUE 200	45,500	10,224	22.47	2,184	456	311	7,273	21.36	4.46	3.04	71.14	2,673	08E
099	06	TUL	25.433	A	AVENUE 200	44,500	9,999	22.47	2,136	446	304	7,113	21.36	4.46	3.04	71.14	2,614	08E
099	06	TUL	29.568	B	TULARE, JCT. RTE. 137	51,000	11,460	22.47	2,448	511	348	8,153	21.36	4.46	3.04	71.14	2,997	08E
099	06	TUL	29.568	A	TULARE, JCT. RTE. 137	52,000	9,792	18.83	2,686	588	387	6,131	27.43	6.00	3.95	62.61	2,320	10E
099	06	TUL	R 38.75	B	JCT. RTE. 198 EAST	51,500	9,790	19.01	2,685	587	387	6,130	27.43	6.00	3.95	62.61	2,320	10E
099	06	TUL	R 38.75	A	JCT. RTE. 198 EAST	53,000	11,909	22.47	2,544	531	362	8,472	21.36	4.46	3.04	71.14	3,114	08E
099	06	TUL	R 53.822	B	MENDOCINO AVENUE	55,000	12,359	22.47	2,640	551	376	8,792	21.36	4.46	3.04	71.14	3,232	08E
099	06	TUL	R 53.822	A	MENDOCINO AVENUE	55,000	12,359	22.47	2,640	551	376	8,792	21.36	4.46	3.04	71.14	3,232	08E
099	06	FRE	R .951	A	KINGSBURG, JCT. RTE. 201 EAST	58,000	13,033	22.47	2,784	581	396	9,272	21.36	4.46	3.04	71.14	3,408	08E
099	06	FRE	6.431	B	JCT. RTE. 43 SOUTH	67,000	14,740	22.00	3,148	657	448	10,486	21.36	4.46	3.04	71.14	3,854	07E
099	06	FRE	6.431	A	JCT. RTE. 43 SOUTH	76,500	11,613	15.18	3,329	938	542	6,803	28.67	8.08	4.67	58.58	2,630	10V
099	06	FRE	11.098	B	FOWLER, MERCED STREET	83,550	14,245	17.05	2,728	603	336	10,578	19.15	4.23	2.36	74.26	3,850	08E
099	06	FRE	15.491	A	CHESTNUT AVENUE	73,500	16,170	22.00	3,454	721	492	11,503	21.36	4.46	3.04	71.14	4,228	07E
099	06	FRE	19.29	B	FRESNO, NORTH JCT. RTE. 41	93,000	14,945	16.07	3,192	667	454	10,632	21.36	4.46	3.04	71.14	3,908	07E
099	06	FRE	19.29	A	FRESNO, NORTH JCT. RTE. 41	63,000	14,490	23.00	3,043	1,304	580	9,563	21.00	9.00	4.00	66.00	3,611	04E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
099	06	FRE	20.19	B	FRESNO, SOUTH JCT. RTE. 180	63,000	14,490	23.00	2,898	1,304	725	9,563	20.00	9.00	5.00	66.00	3,627	04E
099	06	FRE	20.19	A	FRESNO, SOUTH JCT. RTE. 180	63,000	12,600	20.00	2,520	1,134	630	8,316	20.00	9.00	5.00	66.00	3,154	04E
099	06	FRE	21.012	B	FRESNO, NORTH JCT. RTE. 180	65,000	13,650	21.00	2,730	1,229	683	9,009	20.00	9.00	5.00	66.00	3,417	04E
099	06	FRE	21.012	A	FRESNO, NORTH JCT. RTE. 180	80,000	13,176	16.47	3,730	841	327	8,280	28.31	6.38	2.48	62.84	3,113	07E
099	06	FRE	24.416	B	FRESNO, CLINTON AVENUE	90,000	12,384	13.76	3,380	708	275	8,021	27.29	5.72	2.22	64.77	2,991	10V
099	06	FRE	24.416	A	FRESNO, CLINTON AVENUE	93,000	14,303	15.38	4,049	913	355	8,988	28.31	6.38	2.48	62.84	3,379	07V
099	06	FRE	30.988	B	HERNDON AVENUE	61,000	13,347	21.88	3,779	852	331	8,387	28.31	6.38	2.48	62.84	3,153	07E
099	06	FRE	31.609	O	FRESNO/MADERA COUNTY LINE	64,000	14,003	21.88	3,964	893	347	8,799	28.31	6.38	2.48	62.84	3,308	07E
099	06	MAD	0	O	FRESNO/MADERA COUNTY LINE	64,000	14,003	21.88	3,964	893	347	8,799	28.31	6.38	2.48	62.84	3,308	07E
099	06	MAD	9.49	B	GATEWAY DRIVE	68,000	14,878	21.88	4,212	949	369	9,349	28.31	6.38	2.48	62.84	3,514	07E
099	06	MAD	9.49	A	GATEWAY DRIVE	62,000	13,566	21.88	3,841	866	336	8,525	28.31	6.38	2.48	62.84	3,205	07E
099	06	MAD	10.268	B	MADERA, JCT. RTE. 145	62,000	13,566	21.88	3,841	866	336	8,525	28.31	6.38	2.48	62.84	3,205	07E
099	06	MAD	10.268	A	MADERA, JCT. RTE. 145	65,000	14,950	23.00	2,990	1,346	748	9,867	20.00	9.00	5.00	66.00	3,743	04E
099	06	MAD	12.752	A	MADERA, AVENUE 16	61,000	14,640	24.00	2,782	732	586	10,541	19.00	5.00	4.00	72.00	3,888	04E
099	06	MAD	22.727	B	CALIFA, JCT. RTE. 152 WEST	52,000	11,960	23.00	2,272	598	478	8,611	19.00	5.00	4.00	72.00	3,176	03V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
099	06	MAD	22.727	A	CALIFA, JCT. RTE. 152 WEST	36,500	9,125	25.00	1,734	456	365	6,570	19.00	5.00	4.00	72.00	2,423	04E
099	06	MAD	26.576	B	JCT. RTE. 233 WEST	37,500	9,750	26.00	1,950	488	390	6,923	20.00	5.00	4.00	71.00	2,559	04E
099	06	MAD	26.576	A	JCT. RTE. 233 WEST	37,000	9,620	26.00	1,828	481	385	6,926	19.00	5.00	4.00	72.00	2,554	04E
099	06	MAD	28.167	B	LE GRAND AVENUE	37,000	9,620	26.00	1,924	481	481	6,734	20.00	5.00	5.00	70.00	2,506	04E
099	06	MAD	28.167	A	LE GRAND AVENUE	38,000	9,880	26.00	1,976	494	494	6,916	20.00	5.00	5.00	70.00	2,573	04E
099	10	MER	13.861	B	MERCED, JCT. RTE. 140 EAST	42,000	11,466	27.30	1,766	505	527	8,668	15.40	4.40	4.60	75.60	3,176	91V
099	10	MER	13.861	A	MERCED, JCT. RTE. 140 EAST	51,000	10,506	20.60	1,723	567	273	7,943	16.40	5.40	2.60	75.60	2,893	91V
099	10	MER	15.799	A	MERCED, JCT. RTE. 140 WEST; JCT. RTE. 59 NORTH	52,000	10,400	20.00	2,080	832	416	7,072	20.00	8.00	4.00	68.00	2,650	89E
099	10	MER	23.462	A	ATWATER, WEST ATWATER BOULEVARD	45,000	11,070	24.60	2,258	686	653	7,472	20.40	6.20	5.90	67.50	2,816	89V
099	10	STA	R6.75	A	TAYLOR ROAD	78,000	12,714	16.30	3,279	669	289	8,478	25.79	5.26	2.27	66.68	3,144	07V
099	10	STA	R 13.263	B	MODESTO, HATCH ROAD/9TH STREET	101,000	12,645	12.52	3,350	674	307	8,315	26.49	5.33	2.43	65.76	3,093	04E
099	10	STA	R 13.263	A	MODESTO, HATCH ROAD/9TH STREET	105,000	12,653	12.05	3,352	674	307	8,321	26.49	5.33	2.43	65.76	3,095	04E
099	10	STA	R 16.121	A	MODESTO, JCT. RTE. 132	121,000	16,335	13.50	4,329	1,225	408	10,373	26.50	7.50	2.50	63.50	3,903	03E
099	10	STA	M 18.52	A	MODESTO, CARPENTER ROAD	127,000	17,145	13.50	4,543	1,286	429	10,887	26.50	7.50	2.50	63.50	4,096	03E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
099	10	STA	R 22.558	B	SALIDA, JCT. RTE. 219 EAST	109,000	14,715	13.50	3,899	1,104	368	9,344	26.50	7.50	2.50	63.50	3,516	03E
099	10	STA	R 22.558	A	SALIDA, JCT. RTE. 219 EAST	110,000	14,850	13.50	3,935	1,114	371	9,430	26.50	7.50	2.50	63.50	3,548	03E
099	10	SJ	1.708	A	MILGEO AVENUE	113,000	15,255	13.50	4,043	1,144	381	9,687	26.50	7.50	2.50	63.50	3,645	03E
099	10	SJ	6.654	B	MANTECA, NORTH JCT. RTE. 120	83,000	11,205	13.50	2,969	840	280	7,115	26.50	7.50	2.50	63.50	2,677	03E
099	10	SJ	6.654	A	MANTECA, NORTH JCT. RTE. 120	66,000	9,775	14.81	2,590	1,202	400	5,583	26.50	12.30	4.09	57.11	2,186	04E
099	10	SJ	11.468	A	TURNER STATION/FRENCH CAMP ROAD	68,000	10,948	16.10	3,646	1,510	538	5,255	33.30	13.79	4.91	48.00	2,159	07V
099	10	SJ	16.698	B	STOCKTON, MARIPOSA ROAD	73,000	9,789	13.41	2,594	1,204	400	5,590	26.50	12.30	4.09	57.11	2,189	04E
099	10	SJ	16.698	A	STOCKTON, MARIPOSA ROAD	87,000	11,484	13.20	3,445	919	459	6,661	30.00	8.00	4.00	58.00	2,571	03E
099	10	SJ	17.216	A	JCT. RTE. 4 EAST	94,000	12,408	13.20	3,722	993	496	7,197	30.00	8.00	4.00	58.00	2,778	03E
099	10	SJ	18.022	A	JCT. RTE. 26 WEST	96,000	12,672	13.20	3,802	1,014	507	7,350	30.00	8.00	4.00	58.00	2,837	03E
099	10	SJ	19.29	A	JCT. RTE. 26 EAST	83,000	11,039	13.30	3,312	883	442	6,403	30.00	8.00	4.00	58.00	2,471	03E
099	10	SJ	20.336	A	JCT. RTE. 88 NORTHEAST	78,000	10,374	13.30	3,112	830	415	6,017	30.00	8.00	4.00	58.00	2,322	03E
099	10	SJ	21.674	B	WILSON WAY	57,000	7,581	13.30	2,274	606	303	4,397	30.00	8.00	4.00	58.00	1,697	03E
099	10	SJ	21.674	A	WILSON WAY	64,000	8,512	13.30	2,554	681	340	4,937	30.00	8.00	4.00	58.00	1,905	03E
099	10	SJ	29.499	B	LODI, JCT. RTE. 12 WEST	59,000	7,847	13.30	2,354	628	314	4,551	30.00	8.00	4.00	58.00	1,756	03E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
099	10	SJ	29.499	A	LODI, JCT. RTE. 12 WEST	65,000	8,710	13.40	3,026	540	281	4,863	34.74	6.20	3.23	55.83	1,875	03E
099	10	SJ	30.974	A	LODI, JCT. RTE. 12 EAST	65,000	8,710	13.40	3,026	540	281	4,863	34.74	6.20	3.23	55.83	1,875	03E
099	10	SJ	35.597	A	JAHANT ROAD	59,000	7,906	13.40	2,747	490	255	4,414	34.74	6.20	3.23	55.83	1,702	03E
099	03	SAC	0.123	A	SAN JOAQUIN/SACRAMENTO COUNTY LINE	60,000	9,036	15.06	3,473	522	232	4,808	38.44	5.78	2.57	53.21	1,862	04E
099	03	SAC	3.525	A	JCT. RTE. 104 EAST	64,000	9,197	14.37	3,535	532	236	4,894	38.44	5.78	2.57	53.21	1,896	04V
099	03	SAC	6.008	A	ARNO ROAD	63,000	7,598	12.06	2,670	435	196	4,297	35.14	5.72	2.58	56.56	1,645	09V
099	03	SAC	12.761	B	ELK GROVE BOULEVARD	65,000	10,010	15.40	3,250	662	307	5,791	32.47	6.61	3.07	57.85	2,218	02E
099	03	SAC	12.761	A	ELK GROVE BOULEVARD	102,000	10,802	10.59	3,507	714	332	6,249	32.47	6.61	3.07	57.85	2,393	02E
099	03	SAC	17.242	B	SACRAMENTO, STOCKTON BOULEVARD	153,000	9,823	6.42	3,032	659	330	5,801	30.87	6.71	3.36	59.06	2,217	00E
099	03	SAC	17.242	A	SACRAMENTO, STOCKTON BOULEVARD	130,000	10,348	7.96	3,211	690	345	6,102	31.03	6.67	3.33	58.97	2,332	00E
099	03	SAC	17.656	A	SACRAMENTO, MACK ROAD	161,000	9,644	5.99	2,962	652	326	5,705	30.71	6.76	3.38	59.16	2,180	00E
099	03	SAC	19.612	A	FLORIN ROAD	179,000	11,599	6.48	3,554	782	391	6,871	30.64	6.74	3.37	59.24	2,624	00E
099	03	SAC	21.944	B	SACRAMENTO, FRUITRIDGE ROAD	172,000	9,804	5.70	3,027	653	326	5,797	30.88	6.66	3.33	59.13	2,214	00E
099	03	SAC	21.944	A	SACRAMENTO, FRUITRIDGE ROAD	191,000	10,085	5.28	3,128	678	334	5,945	31.02	6.72	3.31	58.95	2,272	00E
099	03	SAC	R 24.351	B	JCT. RTES. 50/51/5	212,000	9,561	4.51	2,939	641	315	5,668	30.74	6.70	3.29	59.28	2,164	00E
099	03	SAC	R 32.124	A	JCT. RTES. 50/51/5	51,000	4,748	9.31	2,170	331	160	2,086	45.70	6.98	3.38	43.93	850	07V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
099	03	SAC	35.37	B	ELVERTA ROAD	41,000	4,211	10.27	1,998	269	128	1,816	47.45	6.39	3.04	43.12	740	09V
099	03	SUT	R 8.07	B	JCT. RTE. 70 NORTH	30,500	2,654	8.70	730	449	374	1,101	27.50	16.90	14.10	41.50	502	97V
099	03	SUT	R 8.07	A	JCT. RTE. 70 NORTH	14,600	1,253	8.58	218	109	55	872	17.39	8.70	4.35	69.57	327	02E
099	03	SUT	11.975	B	GARDEN HIGHWAY	14,600	879	6.02	138	71	33	638	15.67	8.04	3.71	72.58	236	05E
099	03	SUT	R 19.688	B	TUDOR, GARDEN HIGHWAY	15,800	858	5.43	136	75	34	613	15.89	8.69	4.02	71.40	228	05E
099	03	SUT	20.991	B	JCT. RTE. 113	13,200	1,241	9.40	385	176	130	550	31.00	14.20	10.50	44.30	239	97E
099	03	SUT	20.991	A	JCT. RTE. 113	15,400	1,571	10.20	573	251	211	536	36.50	16.00	13.40	34.10	259	97E
099	03	SUT	25.62	B	OSWALD ROAD	15,400	1,571	10.20	573	251	211	536	36.50	16.00	13.40	34.10	259	97E
099	03	SUT	25.62	A	OSWALD ROAD	17,200	1,754	10.20	640	279	237	598	36.50	15.90	13.50	34.10	289	97E
099	03	SUT	30.633	B	YUBA CITY, JCT. RTE. 20	29,500	2,714	9.20	991	432	366	925	36.50	15.90	13.50	34.10	447	97E
099	03	SUT	T 30.629	A	YUBA CITY, JCT. RTE. 20	20,500	1,886	9.20	688	300	255	643	36.50	15.90	13.50	34.10	311	97E
099	03	SUT	T 35.96	B	ENCINAL ROAD/LIVE OAK BOULEVARD	17,000	1,564	9.20	571	249	210	535	36.50	15.90	13.40	34.20	258	97E
099	03	SUT	T 35.96	A	ENCINAL ROAD/LIVE OAK BOULEVARD	19,200	1,766	9.20	645	281	238	602	36.50	15.90	13.50	34.10	291	97E
099	03	BUT	0	A	SUTTER/BUTTE COUNTY LINE	14,900	1,077	7.23	165	146	90	675	15.36	13.59	8.35	62.70	265	05E
099	03	BUT	2.79	A	LIVE OAK GRIDLEY ROAD	18,100	1,629	9.00	376	243	155	855	23.10	14.90	9.50	52.50	353	96E
099	03	BUT	4.38	B	GRIDLEY, SPRUCE STREET	22,200	1,998	9.00	462	298	190	1,049	23.10	14.90	9.50	52.50	433	96E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
099	03	BUT	4.38	A	GRIDLEY, SPRUCE STREET	14,500	1,305	9.00	301	194	124	685	23.10	14.90	9.50	52.50	283	96E
099	03	BUT	11.159	B	JCT. RTE. 162 WEST	10,500	1,050	10.00	231	140	106	573	22.00	13.30	10.10	54.60	234	96E
099	03	BUT	11.159	A	JCT. RTE. 162 WEST	10,700	1,070	10.00	235	143	108	583	22.00	13.40	10.10	54.50	238	96E
099	03	BUT	13.161	B	JCT. RTE. 162 EAST	12,500	1,250	10.00	275	166	126	683	22.00	13.30	10.10	54.60	279	96E
099	03	BUT	13.161	A	JCT. RTE. 162 EAST	10,000	1,000	10.00	220	134	101	545	22.00	13.40	10.10	54.50	223	96E
099	03	BUT	21.81	B	JCT. RTE. 149 SOUTHEAST	9,600	960	10.00	160	80	40	680	16.67	8.33	4.17	70.83	253	05E
099	03	BUT	21.81	A	JCT. RTE. 149 SOUTHEAST	24,800	2,592	10.45	1,103	337	173	980	42.54	12.99	6.68	37.79	433	06E
099	03	BUT	R 30.603	B	CHICO, SKYWAY OVERCROSSING	32,500	3,380	10.40	1,437	439	226	1,278	42.52	12.99	6.69	37.80	565	06E
099	03	BUT	R 30.603	A	CHICO, SKYWAY OVERCROSSING	50,000	3,310	6.62	2,199	195	73	842	66.43	5.88	2.22	25.45	396	07E
099	03	BUT	R 32.445	A	CHICO, JCT. RTE. 32 EAST	74,000	4,899	6.62	3,254	288	109	1,247	66.43	5.88	2.22	25.45	587	07E
099	03	BUT	R 34.245	B	CHICO, COHASSET HIGHWAY	59,000	3,988	6.76	2,841	194	75	878	71.25	4.86	1.87	22.02	431	09V
099	03	BUT	R 34.245	A	CHICO, COHASSET HIGHWAY	42,000	2,780	6.62	1,847	163	62	708	66.43	5.88	2.22	25.45	333	07E
099	03	BUT	40.22	A	KEEFER ROAD	11,600	985	8.49	143	74	21	747	14.54	7.54	2.12	75.80	273	07E
099	02	TEH	0	A	BUTTE/TEHAMA COUNTY LINE	11,600	920	7.93	130	63	21	706	14.13	6.85	2.28	76.74	257	10V
099	02	TEH	4.491	A	SOUTH AVENUE	6,400	889	13.89	119	55	23	692	13.39	6.19	2.59	77.84	251	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
099	02	TEH	5.42	A	VINA ROAD	6,800	863	12.69	113	75	22	653	13.13	8.64	2.52	75.71	239	10E
099	02	TEH	11.181	O	SHERMAN STREET	7,000	894	12.77	115	124	26	629	12.86	13.87	2.91	70.36	236	10E
099	02	TEH	19.517	B	KAUFMAN AVENUE	6,900	869	12.59	112	121	25	611	12.92	13.92	2.88	70.28	230	10E
099	02	TEH	19.517	A	KAUFMAN AVENUE	9,300	867	9.32	78	120	25	643	8.96	13.89	2.93	74.22	239	10E
099	02	TEH	24.943	B	JCT. RTE. 36	9,300	867	9.32	117	55	30	665	13.46	6.38	3.49	76.67	243	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
101	07	LA	S 0	A	LOS ANGELES, JCT. RTE. 5, SANTA ANA FREEWAY, EAST LOS ANGELES INTERCHANGE	138,000	5,451	3.95	3,120	602	147	1,583	57.23	11.04	2.69	29.04	732	10E
101	07	LA	S 1.329	B	LOS ANGELES, JCT. RTE. 10, SAN BERNARDINO FREEWAY INTERCHANGE	123,000	4,859	3.95	2,781	536	131	1,411	57.23	11.04	2.69	29.04	653	10E
101	07	LA	0	A	LOS ANGELES, JCT. RTE. 10, SAN BERNARDINO FREEWAY INTERCHANGE	211,000	7,427	3.52	4,647	670	287	1,823	62.57	9.02	3.87	24.54	895	10E
101	07	LA	0.387	A	LOS ANGELES, VIGNES STREET INTERCHANGE	208,000	7,322	3.52	4,581	660	283	1,797	62.57	9.02	3.87	24.54	883	10E
101	07	LA	1.569	B	LOS ANGELES, JCT. RTE. 110, HARBOR/PASADENA FREEWAYS, FOUR LEVEL INTERCHANGE	218,000	7,674	3.52	4,802	692	297	1,883	62.57	9.02	3.87	24.54	925	10E
101	07	LA	1.569	A	LOS ANGELES, JCT. RTE. 110, HARBOR/PASADENA FREEWAYS, FOUR LEVEL INTERCHANGE	266,000	8,938	3.36	5,320	928	450	2,240	59.52	10.38	5.03	25.06	1,111	10V
101	07	LA	2.857	B	LOS ANGELES, JCT. RTE. 2 NORTHEAST, ALVARADO STREET INTERCHANGE	259,000	8,702	3.36	5,122	919	432	2,229	58.86	10.56	4.96	25.62	1,096	10E
101	07	LA	2.857	A	LOS ANGELES, JCT. RTE. 2 NORTHEAST, ALVARADO STREET INTERCHANGE	263,000	10,757	4.09	6,261	1,154	526	2,816	58.20	10.73	4.89	26.18	1,374	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
101	07	LA	5.554	B	LOS ANGELES, JCT. RTE. 2 WEST, SANTA MONICA BOULEVARD INTERCHANGE	216,000	8,834	4.09	5,083	963	426	2,362	57.54	10.90	4.82	26.74	1,144	10E
101	07	LA	5.554	A	LOS ANGELES, JCT. RTE. 2 WEST, SANTA MONICA BOULEVARD INTERCHANGE	190,000	7,771	4.09	4,420	860	369	2,121	56.88	11.07	4.75	27.30	1,020	10E
101	07	LA	7.84	B	LOS ANGELES, HIGHLAND AVENUE INTERCHANGE	225,000	9,203	4.09	5,175	1,034	431	2,564	56.23	11.24	4.68	27.86	1,224	10E
101	07	LA	7.84	A	LOS ANGELES, HIGHLAND AVENUE INTERCHANGE	270,000	11,043	4.09	6,137	1,260	509	3,138	55.57	11.41	4.61	28.42	1,488	10E
101	07	LA	11.747	B	LOS ANGELES, JCT. RTES. 134/170, VENTURA/ HOLLYWOOD FREEWAYS INTERCHANGE	223,000	9,121	4.09	4,948	1,072	408	2,693	54.25	11.75	4.47	29.53	1,261	10E
101	07	LA	11.747	A	LOS ANGELES, JCT. RTES. 134/170, VENTURA/ HOLLYWOOD FREEWAYS INTERCHANGE	280,000	9,912	3.54	5,738	726	282	3,166	57.89	7.32	2.84	31.94	1,401	10V
101	07	LA	17.17	B	LOS ANGELES, JCT. RTE. 405, SAN DIEGO FREEWAY INTERCHANGE	301,000	10,415	3.46	6,029	762	296	3,327	57.89	7.32	2.84	31.94	1,472	10E
101	07	LA	17.17	A	LOS ANGELES, JCT. RTE. 405, SAN DIEGO FREEWAY INTERCHANGE	316,000	15,990	5.06	9,898	1,266	542	4,282	61.90	7.92	3.39	26.78	2,020	10E
101	07	LA	19.99	O	ENCINO AVENUE PEDESTRIAN OVERCROSSING	297,000	15,028	5.06	9,302	1,190	509	4,024	61.90	7.92	3.39	26.78	1,898	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
101	07	LA	25.337	B	LOS ANGELES, JCT. RTE. 27, TOPANGA CANYON BOULEVARD INTERCHANGE	226,000	11,436	5.06	7,079	906	388	3,063	61.90	7.92	3.39	26.78	1,445	10E
101	07	LA	25.337	A	LOS ANGELES, JCT. RTE. 27, TOPANGA CANYON BOULEVARD INTERCHANGE	205,000	10,373	5.06	6,421	822	352	2,778	61.90	7.92	3.39	26.78	1,311	10E
101	07	VEN	0.701	B	THOUSAND OAKS, JCT. RTE. 23 SOUTH, WESTLAKE BOULEVARD INTERCHANGE	168,000	7,241	4.31	3,077	353	176	3,634	42.50	4.88	2.43	50.19	1,420	10E
101	07	VEN	0.701	A	THOUSAND OAKS, JCT. RTE. 23 SOUTH, WESTLAKE BOULEVARD INTERCHANGE	172,000	7,104	4.13	3,019	347	173	3,565	42.50	4.88	2.43	50.19	1,393	10E
101	07	VEN	3.107	B	THOUSAND OAKS, JCT. RTE. 23 NORTH, MOORPARK FREEWAY INTERCHANGE	186,000	6,956	3.74	2,956	339	169	3,491	42.50	4.88	2.43	50.19	1,364	10E
101	07	VEN	3.107	A	THOUSAND OAKS, JCT. RTE. 23 NORTH, MOORPARK FREEWAY INTERCHANGE	178,000	6,248	3.51	2,655	305	152	3,136	42.50	4.88	2.43	50.19	1,225	10E
101	07	VEN	7.885	A	THOUSAND OAKS, WENDY DRIVE INTERCHANGE	127,000	6,160	4.85	2,618	301	150	3,092	42.50	4.88	2.43	50.19	1,208	10V
101	07	VEN	12.298	B	CAMARILLO, PLEASANT VALLEY ROAD INTERCHANGE	127,000	6,160	4.85	2,618	301	150	3,092	42.50	4.88	2.43	50.19	1,208	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
101	07	VEN	13.848	B	CAMARILLO, JCT. RTE. 34, LEWIS ROAD INTERCHANGE	130,000	6,305	4.85	2,680	308	153	3,164	42.50	4.88	2.43	50.19	1,236	10E
101	07	VEN	13.848	A	CAMARILLO, JCT. RTE. 34, LEWIS ROAD INTERCHANGE	138,000	6,652	4.82	3,351	830	229	2,244	50.37	12.47	3.44	33.73	1,001	10E
101	07	VEN	22.006	B	OXNARD, JCT. RTE. 232, VINEYARD AVENUE	132,000	6,085	4.61	3,189	741	245	1,910	52.40	12.18	4.03	31.39	875	10E
101	07	VEN	22.729	A	OXNARD, JCT. RTE. 1 SOUTH, PACIFIC COAST HIGHWAY	143,000	5,520	3.86	3,027	654	262	1,578	54.83	11.84	4.74	28.59	749	10E
101	07	VEN	R 24.645	A	VENTURA, VICTORIA AVENUE INTERCHANGE	117,000	4,961	4.24	2,869	567	279	1,247	57.83	11.42	5.62	25.14	624	10E
101	07	VEN	26.39	B	VENTURA, JCT. RTE. 126, SANTA PAULA FREEWAY INTERCHANGE	88,000	4,708	5.35	2,723	538	265	1,184	57.83	11.42	5.62	25.14	592	10E
101	07	VEN	26.39	A	VENTURA, JCT. RTE. 126, SANTA PAULA FREEWAY INTERCHANGE	119,000	6,438	5.41	2,644	552	304	2,938	41.07	8.58	4.72	45.63	1,202	10E
101	07	VEN	30.906	B	VENTURA, JCT. RTE. 33, OJAI FREEWAY INTERCHANGE	94,000	5,894	6.27	2,265	477	324	2,828	38.43	8.10	5.50	47.98	1,146	10E
101	07	VEN	30.906	A	VENTURA, JCT. RTE. 33, OJAI FREEWAY INTERCHANGE	69,000	5,341	7.74	1,882	402	343	2,713	35.24	7.53	6.43	50.80	1,089	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
101	07	VEN	R 43.622	B	VENTURA/SANTA BARBARA COUNTY LINE	65,000	5,278	8.12	2,047	366	276	2,589	38.78	6.93	5.23	49.06	1,039	10E
101	05	SB	R .634	B	JCT. RTE. 150 EAST	65,000	6,286	9.67	2,560	550	432	2,744	40.72	8.75	6.87	43.66	1,150	10E
101	05	SB	R .634	A	JCT. RTE. 150 EAST	66,000	6,336	9.60	2,579	558	437	2,762	40.70	8.80	6.90	43.60	1,159	10E
101	05	SB	2.64	B	CARPINTERIA, CASITAS PASS ROAD	67,000	6,432	9.60	2,618	566	444	2,804	40.70	8.80	6.90	43.60	1,176	10E
101	05	SB	2.64	A	CARPINTERIA, CASITAS PASS ROAD	67,000	6,432	9.60	2,618	566	444	2,804	40.70	8.80	6.90	43.60	1,176	10E
101	05	SB	9.003	B	MONTECITO, SHEFFIELD DRIVE	76,000	7,296	9.60	2,969	642	503	3,181	40.70	8.80	6.90	43.60	1,334	10E
101	05	SB	9.003	A	MONTECITO, SHEFFIELD DRIVE	80,000	7,680	9.60	3,126	676	530	3,348	40.70	8.80	6.90	43.60	1,405	10E
101	05	SB	11.407	B	SANTA BARBARA, JCT. RTE. 225 WEST	82,000	5,305	6.47	2,653	473	189	1,989	50.00	8.92	3.57	37.50	850	10E
101	05	SB	11.407	A	SANTA BARBARA, JCT. RTE. 225 WEST	87,000	5,203	5.98	2,602	464	186	1,951	50.00	8.92	3.57	37.50	834	10E
101	05	SB	12.754	A	SANTA BARBARA, JCT. RTE. 144	93,000	4,920	5.29	2,460	439	176	1,845	50.00	8.92	3.57	37.50	789	10E
101	05	SB	16.552	B	SANTA BARBARA, JCT. RTE. 225 SOUTHEAST	130,000	5,304	4.08	2,775	456	181	1,892	52.31	8.60	3.41	35.68	818	10V
101	05	SB	16.552	A	SANTA BARBARA, JCT. RTE. 225 SOUTHEAST	131,000	5,423	4.14	2,761	483	148	2,031	50.91	8.91	2.73	37.45	864	10E
101	05	SB	18.364	B	JCT. RTE. 154	130,000	5,382	4.14	1,523	786	269	2,804	28.30	14.60	5.00	52.10	1,133	10E
101	05	SB	18.364	A	JCT. RTE. 154	123,000	5,092	4.14	1,441	738	260	2,653	28.30	14.50	5.10	52.10	1,072	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
101	05	SB	21.414	B	JCT. RTE. 217 SOUTH	110,000	4,554	4.14	1,289	660	232	2,373	28.30	14.50	5.10	52.10	959	10E
101	05	SB	21.414	A	JCT. RTE. 217 SOUTH	80,000	4,184	5.23	1,385	406	209	2,184	33.10	9.70	5.00	52.20	870	10E
101	05	SB	23.711	A	LOS CARNEROS ROAD	57,000	5,187	9.10	1,712	399	373	2,702	33.00	7.70	7.20	52.10	1,084	10E
101	05	SB	24.762	A	STORKE ROAD	34,500	3,381	9.80	950	264	172	1,995	28.10	7.80	5.10	59.00	771	10E
101	05	SB	26.907	A	HOLLISTER AVENUE	32,000	3,536	11.05	1,417	357	189	1,574	40.06	10.09	5.34	44.51	653	10E
101	05	SB	R 48.847	B	LAS CRUCES, JCT. RTE. 1 NORTHWEST	30,000	3,159	10.53	1,249	256	147	1,507	39.54	8.10	4.65	47.71	609	10V
101	05	SB	R 48.847	A	LAS CRUCES, JCT. RTE. 1 NORTHWEST	22,500	3,038	13.50	854	237	173	1,774	28.10	7.80	5.70	58.40	689	10E
101	05	SB	R 57.117	B	BUELLTON, JCT. RTE. 246	22,000	3,124	14.20	843	253	153	1,874	27.00	8.10	4.90	60.00	722	10E
101	05	SB	R 57.117	A	BUELLTON, JCT. RTE. 246	22,000	3,234	14.70	902	236	191	1,905	27.90	7.30	5.90	58.90	739	10E
101	05	SB	62.671	B	ZACA, JCT. RTE. 154 EAST	22,500	3,195	14.20	914	214	217	1,850	28.60	6.70	6.80	57.90	722	10E
101	05	SB	62.671	A	ZACA, JCT. RTE. 154 EAST	29,000	3,596	12.40	1,097	259	234	2,007	30.50	7.20	6.50	55.80	789	10E
101	05	SB	70.921	B	LOS ALAMOS, JCT. RTE. 135 NORTHWEST	29,000	3,770	13.00	1,195	260	230	2,085	31.70	6.90	6.10	55.30	819	10E
101	05	SB	70.921	A	LOS ALAMOS, JCT. RTE. 135 NORTHWEST	28,000	3,920	14.00	1,266	263	231	2,160	32.30	6.70	5.90	55.10	848	10E
101	05	SB	80.21	O	LAS FLORES BRIDGE	28,000	3,416	12.20	1,103	246	205	1,862	32.30	7.20	6.00	54.50	734	10E
101	05	SB	86.588	B	BETTERAVIA ROAD	43,000	3,870	9.00	1,033	550	178	2,109	26.70	14.20	4.60	54.50	841	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
101	05	SB	86.588	A	BETTERAVIA ROAD	57,000	4,332	7.60	1,191	611	199	2,331	27.50	14.10	4.60	53.80	931	10E
101	05	SB	90.749	B	JCT. RTE. 135 SOUTH	55,000	4,070	7.40	1,123	574	195	2,177	27.60	14.10	4.80	53.50	872	10E
101	05	SLO	0.813	B	JCT. RTE. 166 EAST	58,000	4,350	7.50	1,235	631	218	2,266	28.40	14.50	5.00	52.10	915	10E
101	05	SLO	0.813	A	JCT. RTE. 166 EAST	54,000	3,996	7.40	1,155	583	192	2,066	28.90	14.60	4.80	51.70	835	10E
101	05	SLO	13.173	B	ARROYO GRANDE, JCT. RTE. 227 NORTH, GRAND AVENUE	50,000	4,150	8.30	1,204	602	208	2,137	29.00	14.50	5.00	51.50	865	10E
101	05	SLO	13.173	A	ARROYO GRANDE, JCT. RTE. 227 NORTH, GRAND AVENUE	54,000	4,752	8.80	1,359	694	238	2,462	28.60	14.60	5.00	51.80	996	10E
101	05	SLO	17.756	B	PISMO BEACH, JCT. RTE. 1 SOUTH	58,000	5,104	8.80	1,450	750	260	2,644	28.40	14.70	5.10	51.80	1,070	10E
101	05	SLO	17.756	A	PISMO BEACH, JCT. RTE. 1 SOUTH	60,000	5,880	9.80	1,676	858	294	3,052	28.50	14.60	5.00	51.90	1,234	10E
101	05	SLO	R 24.296	B	SANTA FE	67,000	5,829	8.70	1,935	583	291	3,019	33.20	10.00	5.00	51.80	1,206	10E
101	05	SLO	R 24.296	A	SANTA FE	62,000	5,084	8.20	1,688	498	259	2,639	33.20	9.80	5.10	51.90	1,053	10E
101	05	SLO	28.088	B	SAN LUIS OBISPO, JCT. RTE. 227, MARCH STREET	60,000	4,926	8.21	1,645	478	246	2,557	33.40	9.70	5.00	51.90	1,020	10E
101	05	SLO	28.088	A	SAN LUIS OBISPO, JCT. RTE. 227, MARCH STREET	57,000	4,959	8.70	1,651	481	253	2,574	33.30	9.70	5.10	51.90	1,027	10E
101	05	SLO	29.067	A	SAN LUIS OBISPO, JCT. RTE. 1 NORTH	43,900	4,302	9.80	1,020	628	215	2,439	23.70	14.60	5.00	56.70	967	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
101	05	SLO	30.36	O	SAN LUIS OBISPO, NORTH CITY LIMITS	41,000	3,321	8.10	960	405	133	1,823	28.90	12.20	4.00	54.90	719	10E
101	05	SLO	37.863	B	JCT. RTE. 58 EAST, SANTA MARGARITA	41,000	3,239	7.90	972	204	123	1,940	30.00	6.30	3.80	59.90	740	10E
101	05	SLO	37.863	A	JCT. RTE. 58 EAST, SANTA MARGARITA	40,000	3,200	8.00	906	275	96	1,923	28.30	8.60	3.00	60.10	735	10E
101	05	SLO	45.572	B	ATASCADERO, JCT. RTE. 41	51,000	4,080	8.00	1,032	469	220	2,358	25.30	11.50	5.40	57.80	925	10E
101	05	SLO	45.572	A	ATASCADERO, JCT. RTE. 41	58,000	4,188	7.22	2,443	208	89	1,449	58.33	4.96	2.12	34.59	618	10E
101	05	SLO	54.116	B	JCT. RTE. 46 WEST	52,300	4,691	8.97	3,029	244	106	1,312	64.57	5.20	2.27	27.96	597	10E
101	05	SLO	54.116	A	JCT. RTE. 46 WEST	62,900	4,906	7.80	1,437	515	260	2,693	29.30	10.50	5.30	54.90	1,065	10E
101	05	SLO	57.92	B	PASO ROBLES, JCT. RTE. 46 EAST	32,000	3,616	11.30	1,088	195	127	2,206	30.10	5.40	3.50	61.00	836	10E
101	05	SLO	57.92	A	PASO ROBLES, JCT. RTE. 46 EAST	21,000	3,612	17.20	860	191	195	2,366	23.80	5.30	5.40	65.50	893	10E
101	05	MON	R 9.667	B	JOLON ROAD	15,600	2,902	18.60	786	116	133	1,866	27.10	4.00	4.60	64.30	702	03V
101	05	MON	R 9.667	A	JOLON ROAD	14,900	2,846	19.10	726	131	182	1,807	25.50	4.60	6.40	63.50	688	03V
101	05	MON	R 32.015	B	SAN LUCAS, JCT. RTE. 198	14,900	2,667	17.90	640	144	184	1,699	24.00	5.40	6.90	63.70	649	03E
101	05	MON	R 32.015	A	SAN LUCAS, JCT. RTE. 198	16,000	3,040	19.00	842	146	192	1,860	27.70	4.80	6.30	61.20	713	03E
101	05	MON	R 41.954	B	JOLON ROAD, NORTH JCT.	25,900	3,004	11.60	733	162	171	1,938	24.40	5.40	5.70	64.50	734	03E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
101	05	MON	R 41.954	A	JOLON ROAD, NORTH JCT.	25,900	1,515	5.85	551	70	38	856	36.36	4.61	2.53	56.51	327	10E
101	05	MON	61.583	B	JCT. RTE. 146 EAST	37,200	4,356	11.71	1,054	440	183	2,679	24.20	10.10	4.20	61.50	1,029	10E
101	05	MON	61.583	A	JCT. RTE. 146 EAST	36,000	5,436	15.10	1,517	593	201	3,126	27.90	10.90	3.70	57.50	1,216	03E
101	05	MON	66.398	B	SOLEDAD PRISON	37,100	5,565	15.00	1,953	479	323	2,810	35.10	8.60	5.80	50.50	1,129	03E
101	05	MON	72.605	B	NORTH GONZALES	39,400	7,013	17.80	1,978	666	540	3,829	28.20	9.50	7.70	54.60	1,531	03E
101	05	MON	85.624	A	SALINAS, AIRPORT BOULEVARD	49,100	9,034	18.40	5,908	407	307	2,412	65.40	4.50	3.40	26.70	1,121	05E
101	05	MON	101.316	B	MONTEREY/SAN BENITO COUNTY LINE	58,000	9,529	16.43	5,909	398	266	2,956	62.01	4.18	2.79	31.02	1,302	07E
101	05	SBT	2.998	B	JCT. RTE. 156 EAST	60,000	9,858	16.43	6,113	412	275	3,058	62.01	4.18	2.79	31.02	1,347	07E
101	05	SBT	2.998	A	JCT. RTE. 156 EAST	48,000	10,579	22.04	6,759	441	343	3,036	63.89	4.17	3.24	28.70	1,375	05E
101	05	SBT	R 4.898	A	JCT. RTE. 129 WEST	48,500	8,070	16.64	5,276	363	274	2,155	65.38	4.50	3.40	26.70	1,002	04E
101	04	SCL	3.16	B	JCT. RTE. 25 EAST	49,000	8,154	16.64	5,331	367	277	2,177	65.38	4.50	3.40	26.70	1,012	04E
101	04	SCL	3.16	A	JCT. RTE. 25 EAST	73,000	6,351	8.70	1,859	551	185	3,755	29.27	8.68	2.92	59.13	1,438	01V
101	04	SCL	R 6.08	A	GILROY, JCT. RTE. 152 EAST	88,000	7,040	8.00	2,223	547	206	4,066	31.57	7.77	2.92	57.75	1,561	01E
101	04	SCL	R 17.82	A	MORGAN HILL, COCHRAN ROAD	131,000	9,891	7.55	3,845	745	278	5,024	38.87	7.53	2.81	50.79	1,977	01V
101	04	SCL	R 26.78	B	San Jose, Jct. Rte. 85, Bernal Road Interchange	128,000	10,906	8.52	3,921	1,035	371	5,580	35.95	9.49	3.40	51.16	2,212	01V
101	04	SCL	R 28.609	B	SAN JOSE, JCT. RTE. 82 NORTH	120,000	12,348	10.29	4,453	998	503	6,394	36.06	8.08	4.07	51.78	2,528	01V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
101	04	SCL	R 28.609	A	SAN JOSE, JCT. RTE. 82 NORTH	149,000	11,786	7.91	5,003	1,003	437	5,344	42.45	8.51	3.71	45.34	2,175	01V
101	04	SCL	34.87	A	SAN JOSE, JCT. RTE. 280 WEST, JCT. RTE. 680 NORTH	191,000	11,460	6.00	5,711	1,540	311	3,899	49.83	13.44	2.71	34.02	1,732	01E
101	04	SCL	R 35.759	B	SAN JOSE, JCT. RTE. 130 EAST	191,000	9,531	4.99	4,946	1,031	253	3,302	51.89	10.82	2.65	34.64	1,444	01V
101	04	SCL	R 35.759	A	SAN JOSE, JCT. RTE. 130 EAST	154,000	10,210	6.63	5,005	1,286	291	3,628	49.02	12.60	2.85	35.53	1,588	01V
101	04	SCL	37.726	A	SAN JOSE, OAKLAND ROAD	175,000	9,503	5.43	4,453	999	389	3,662	46.86	10.51	4.09	38.54	1,568	01V
101	04	SCL	38.3	A	SAN JOSE, JCT. RTE. 880	130,000	6,500	5.00	3,504	829	241	1,926	53.91	12.76	3.70	29.63	899	01E
101	04	SCL	43.85	B	SUNNYVALE, LAWRENCE EXPRESSWAY	159,000	6,726	4.23	3,805	733	367	1,821	56.57	10.90	5.45	27.08	883	01V
101	04	SCL	46.134	B	SUNNYVALE, JCT. RTE. 237	135,000	5,211	3.86	3,031	534	183	1,463	58.17	10.24	3.52	28.07	687	01V
101	04	SCL	46.134	A	SUNNYVALE, JCT. RTE. 237	155,000	5,906	3.81	3,096	761	191	1,859	52.42	12.88	3.23	31.47	848	01V
101	04	SCL	48.103	B	MOUNTAIN VIEW, JCT. RTE. 85 SOUTH	154,000	7,053	4.58	2,789	595	200	3,468	39.55	8.43	2.84	49.17	1,378	01V
101	04	SCL	48.103	A	MOUNTAIN VIEW, JCT. RTE. 85 SOUTH	200,000	9,000	4.50	4,933	1,363	317	2,388	54.81	15.14	3.52	26.53	1,169	01E
101	04	SM	1.869	B	JCT. RTE. 114	188,000	7,952	4.23	4,840	646	363	2,103	60.86	8.13	4.56	26.45	1,008	01V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
101	04	SM	5.385	B	REDWOOD CITY, JCT. RTE. 84	201,000	9,045	4.50	5,237	925	288	2,594	57.90	10.23	3.18	28.68	1,206	01E
101	04	SM	5.385	A	REDWOOD CITY, JCT. RTE. 84	202,000	9,090	4.50	5,456	1,364	281	1,989	60.02	15.00	3.09	21.88	1,044	01E
101	04	SM	6.623	A	REDWOOD CITY, WHIPPLE AVENUE	214,000	10,465	4.89	6,408	1,241	495	2,321	61.23	11.86	4.73	22.18	1,212	01V
101	04	SM	11.895	B	SAN MATEO, JCT. RTE. 92	225,000	7,268	3.23	4,272	709	279	2,007	58.78	9.76	3.84	27.62	948	04V
101	04	SM	11.895	A	SAN MATEO, JCT. RTE. 92	250,000	8,725	3.49	5,011	958	177	2,579	57.43	10.98	2.03	29.56	1,179	04V
101	04	SM	13.461	B	SAN MATEO, THIRD AVENUE	248,000	9,449	3.81	5,818	827	463	2,341	61.57	8.75	4.90	24.78	1,155	01V
101	04	SM	13.461	A	SAN MATEO, THIRD AVENUE	247,000	10,917	4.42	6,462	1,019	584	2,852	59.19	9.33	5.35	26.12	1,390	01V
101	04	SM	17.947	B	MILLBRAE, MILLBRAE AVENUE	238,000	10,472	4.40	6,330	811	415	2,916	60.45	7.74	3.96	27.85	1,363	01V
101	04	SF	0.774	A	SAN FRANCISCO, THIRD STREET	217,000	10,025	4.62	5,282	1,649	262	2,832	52.69	16.45	2.61	28.25	1,352	01V
101	04	SF	1.976	B	SAN FRANCISCO, JCT. RTE. 280	225,000	8,550	3.80	4,367	1,402	221	2,558	51.08	16.40	2.59	29.92	1,197	04V
101	04	SF	1.976	A	SAN FRANCISCO, JCT. RTE. 280	220,000	5,412	2.46	2,940	613	143	1,716	54.33	11.32	2.64	31.70	772	04V
101	04	SF	4.241	B	SAN FRANCISCO, JCT. RTE. 80	207,000	3,188	1.54	1,829	354	95	911	57.36	11.10	2.97	28.57	425	01V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
101	04	SF	R 4.241	A	SAN FRANCISCO, JCT. RTE. 80	268,000	4,556	1.70	2,952	592	178	834	64.80	13.00	3.90	18.30	472	01E
101	04	SF	6.712	B	SAN FRANCISCO, LOMBARD STREET	40,500	883	2.18	658	102	12	111	74.52	11.55	1.36	12.57	72	04E
101	04	SF	9.4	B	SAN FRANCISCO, JCT. RTE. 1	78,000	881	1.13	690	53	22	117	78.29	5.99	2.46	13.26	73	04E
101	04	MRN	0	A	GOLDEN GATE BRIDGE	105,000	1,397	1.33	1,026	101	29	241	73.43	7.25	2.05	17.27	133	04V
101	04	MRN	0.318	A	SAUSALITO ROAD	102,000	1,683	1.65	1,266	106	59	252	75.22	6.28	3.53	14.96	150	01V
101	04	MRN	4.134	B	JCT. RTE. 1 WEST	129,000	2,670	2.07	2,026	284	51	308	75.88	10.65	1.91	11.55	211	01V
101	04	MRN	4.134	A	JCT. RTE. 1 WEST	127,000	3,467	2.73	2,525	377	80	484	72.84	10.88	2.32	13.96	302	01V
101	04	MRN	5.694	B	JCT. RTE. 131 EAST	126,000	2,331	1.85	1,804	239	49	238	77.40	10.27	2.10	10.23	174	01V
101	04	MRN	8.6	B	LARKSPUR, SIR FRANCIS DRAKE BOULEVARD	164,000	3,936	2.40	2,701	544	135	557	68.62	13.82	3.42	14.14	357	01V
101	04	MRN	8.6	A	LARKSPUR, SIR FRANCIS DRAKE BOULEVARD	139,000	3,864	2.78	2,692	535	132	505	69.67	13.85	3.42	13.06	337	01V
101	04	MRN	9.96	A	JCT. RTE. 580	183,000	6,240	3.41	3,615	643	236	1,746	57.94	10.30	3.78	27.98	823	01V
101	04	MRN	13.713	B	MANUEL FREITAS PARKWAY	176,000	7,744	4.40	4,151	1,022	225	2,346	53.60	13.20	2.90	30.30	1,082	01E
101	04	MRN	19.085	B	NOVATO, JCT. RTE. 37 EAST	156,000	6,380	4.09	3,577	849	212	1,742	56.06	13.30	3.33	27.30	835	01V
101	04	MRN	19.085	A	NOVATO, JCT. RTE. 37 EAST	129,000	5,702	4.42	3,074	567	318	1,743	53.91	9.94	5.58	30.57	808	01V
101	04	SON	2.925	B	SOUTH PETALUMA	80,000	3,768	4.71	1,538	448	190	1,593	40.81	11.88	5.04	42.27	673	01V
101	04	SON	2.925	A	SOUTH PETALUMA	76,000	4,841	6.37	1,799	459	146	2,437	37.17	9.48	3.01	50.34	967	01V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
101	04	SON	3.664	A	PETALUMA, SOUTH JCT. RTE. 116 EAST	88,000	4,400	5.00	1,769	521	139	1,970	40.20	11.84	3.17	44.78	810	01E
101	04	SON	7.651	B	PETALUMA, OLD REDWOOD HIGHWAY	87,000	4,968	5.71	1,779	661	164	2,365	35.80	13.30	3.30	47.60	963	01E
101	04	SON	7.651	A	PETALUMA, OLD REDWOOD HIGHWAY	92,000	5,161	5.61	2,004	676	154	2,328	38.83	13.09	2.98	45.11	958	01V
101	04	SON	12.682	B	COTATI, NORTH JCT. RTE. 116	83,000	5,569	6.71	2,296	582	338	2,353	41.23	10.45	6.07	42.25	995	01V
101	04	SON	12.682	A	COTATI, NORTH JCT. RTE. 116	90,000	5,139	5.71	2,055	594	270	2,220	39.99	11.56	5.25	43.19	932	01V
101	04	SON	19.646	B	SANTA ROSA, JCT. RTE. 12	133,000	6,783	5.10	2,925	937	459	2,462	43.12	13.81	6.77	36.30	1,105	01V
101	04	SON	19.646	A	SANTA ROSA, JCT. RTE. 12	117,000	7,020	6.00	3,728	976	267	2,050	53.10	13.90	3.80	29.20	967	01E
101	04	SON	20.74	B	SANTA ROSA, COLLEGE AVENUE	130,000	6,760	5.20	3,448	635	284	2,393	51.00	9.40	4.20	35.40	1,046	01E
101	04	SON	20.74	A	SANTA ROSA, COLLEGE AVENUE	121,000	6,292	5.20	2,701	883	259	2,449	42.92	14.03	4.11	38.93	1,059	01E
101	04	SON	27.618	A	SHILOH ROAD	62,000	3,677	5.93	1,700	334	83	1,560	46.24	9.07	2.27	42.42	641	01V
101	04	SON	34.551	B	SOUTH HEALDSBURG	46,000	3,344	7.27	1,304	388	51	1,601	39.01	11.59	1.53	47.88	641	01V
101	04	SON	R 38.558	B	LYTTON SPRINGS ROAD	28,500	2,420	8.49	590	361	23	1,446	24.38	14.91	0.96	59.75	556	01V
101	04	SON	R 41.43	B	SOUTH GEYSERVILLE	26,500	2,080	7.85	792	241	45	1,002	38.08	11.59	2.15	48.18	402	01V
101	04	SON	R 43.373	A	JCT. RTE. 128 EAST	22,400	1,938	8.65	569	198	155	1,016	29.37	10.23	8.00	52.40	411	01V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
101	04	SON	R 53.545	B	JCT. RTE. 128 WEST	14,000	1,586	11.33	560	177	121	728	35.29	11.18	7.65	45.88	305	06E
101	04	SON	R 54.201	A	JCT. RTE. 128 WEST	13,000	1,473	11.33	520	165	113	676	35.29	11.18	7.65	45.88	283	06E
101	01	MEN	10.89	B	HOPLAND, JCT. RTE. 175 EAST	14,600	1,654	11.33	584	185	127	759	35.29	11.18	7.65	45.88	318	06E
101	01	MEN	10.89	A	HOPLAND, JCT. RTE. 175 EAST	14,600	1,654	11.33	584	185	127	759	35.29	11.18	7.65	45.88	318	06E
101	01	MEN	R 21.59	A	JCT. RTE. 253 WEST	17,600	2,489	14.14	1,276	279	157	777	51.26	11.22	6.30	31.22	361	07V
101	01	MEN	R 23.45	A	UKIAH JCT 222 EAST	21,700	2,422	11.16	1,191	275	142	814	49.16	11.34	5.88	33.61	369	07E
101	01	MEN	30.833	B	JCT. RTE. 20 EAST	25,300	2,765	10.93	1,407	247	123	987	50.89	8.93	4.46	35.71	431	05E
101	01	MEN	30.833	A	JCT. RTE. 20 EAST	19,600	1,884	9.61	744	271	164	705	39.49	14.36	8.72	37.44	318	06E
101	01	MEN	46.363	B	WILLITS, JCT. RTE. 20 WEST	20,000	2,020	10.10	798	290	176	756	39.49	14.36	8.72	37.44	341	06E
101	01	MEN	46.363	A	WILLITS, JCT. RTE. 20 WEST	22,900	1,264	5.52	277	195	134	658	21.95	15.45	10.57	52.03	274	05E
101	01	MEN	59.308	B	JCT RTE 162 EAST	7,000	1,050	15.00	370	120	80	480	35.24	11.43	7.62	45.71	201	06E
101	01	MEN	59.308	A	JCT RTE 162 EAST	6,800	1,313	19.31	293	235	152	633	22.32	17.86	11.61	48.21	273	05E
101	01	MEN	69.49	B	LAYTONVILLE, BRANSCOMB ROAD	6,850	942	13.75	278	75	43	546	29.55	7.95	4.55	57.95	211	06E
101	01	MEN	69.49	A	LAYTONVILLE, BRANSCOMB ROAD	6,200	941	15.17	207	103	72	558	21.98	10.99	7.69	59.34	220	06E
101	01	MEN	T 91.245	A	LEGGETT, JCT. RTE. 1	6,100	925	15.17	203	102	71	549	21.98	10.99	7.69	59.34	216	06E
101	01	MEN	R103.818	A	JCT. RTE. 271	4,500	764	16.98	171	136	78	380	22.36	17.76	10.18	49.70	161	05E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
101	01	HUM	R 11.125	B	GARBERVILLE, SPROWEL CREEK ROAD	5,700	937	16.43	210	166	95	466	22.36	17.76	10.18	49.70	197	05E
101	01	HUM	R 11.125	A	GARBERVILLE, SPROWEL CREEK ROAD	3,800	828	21.78	185	147	84	412	22.36	17.76	10.18	49.70	174	05E
101	01	HUM	R 17.907	B	JCT. RTE. 254 NORTHEAST	6,700	969	14.47	281	134	26	528	29.00	13.80	2.70	54.50	208	05E
101	01	HUM	R 17.907	A	JCT. RTE. 254 NORTHEAST	5,900	984	16.67	295	138	30	522	30.00	14.00	3.00	53.00	208	05E
101	01	HUM	27.936	B	JCT. RTE. 254	5,000	887	17.74	257	124	35	471	29.00	14.00	3.90	53.10	188	05E
101	01	HUM	27.936	A	JCT. RTE. 254	5,400	928	17.19	253	132	46	496	27.30	14.20	5.00	53.50	199	05E
101	01	HUM	35.108	A	JCT. RTE. 254 SOUTH	5,400	1,190	22.03	320	171	58	640	26.90	14.40	4.90	53.80	256	05E
101	01	HUM	35.698	A	SOUTH FORK ROAD	5,600	1,064	19.00	284	153	54	572	26.70	14.40	5.10	53.80	229	05E
101	01	HUM	R 50.585	A	SOUTH SCOTIA ROAD	7,700	1,267	16.46	350	203	48	666	27.60	16.00	3.80	52.60	268	05E
101	01	HUM	57.69	B	JCT. RTE. 36 EAST	13,000	1,234	9.49	350	217	46	621	28.40	17.60	3.70	50.30	253	05E
101	01	HUM	57.69	A	JCT. RTE. 36 EAST	17,900	1,779	9.94	528	320	82	849	29.70	18.00	4.60	47.70	353	05E
101	01	HUM	64.29	B	JCT. RTE. 211, SINGELY ROAD	18,500	1,758	9.50	548	308	88	814	31.20	17.50	5.00	46.30	341	05E
101	01	HUM	64.29	A	JCT. RTE. 211, SINGELY ROAD	20,700	1,704	8.23	880	197	41	585	51.67	11.59	2.43	34.31	257	07V
101	01	HUM	65.947	A	LOLETA DRIVE	21,000	1,802	8.58	931	209	44	618	51.67	11.59	2.43	34.31	271	07E
101	01	HUM	81.14	O	EUREKA N CTY LIM	34,000	1,666	4.90	861	193	40	572	51.67	11.59	2.43	34.31	251	07E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
101	01	HUM	85.83	B	ARCATA, JCT. RTE. 255 SOUTH	37,000	1,691	4.57	874	196	41	580	51.67	11.59	2.43	34.31	255	07E
101	01	HUM	85.83	A	ARCATA, JCT. RTE. 255 SOUTH	37,000	2,494	6.74	1,361	436	76	621	54.59	17.47	3.06	24.89	313	05E
101	01	HUM	88.272	B	ARCATA, JCT. RTE. 299 EAST	42,500	2,495	5.87	1,362	436	76	621	54.59	17.47	3.06	24.89	313	05E
101	01	HUM	88.272	A	ARCATA, JCT. RTE. 299 EAST	32,500	1,931	5.94	1,251	40	70	570	64.77	2.07	3.63	29.53	254	05E
101	01	HUM	R 90.134	B	JCT. RTE. 200 EAST	33,500	2,087	6.23	1,352	43	76	616	64.77	2.07	3.63	29.53	275	05E
101	01	HUM	R 90.134	A	JCT. RTE. 200 EAST	18,700	1,010	5.40	472	169	78	292	46.70	16.70	7.70	28.90	144	05E
101	01	HUM	R 97.02	B	CRANNELL ROAD	10,700	1,951	18.23	1,460	165	73	253	74.81	8.48	3.74	12.97	164	06V
101	01	HUM	R 97.02	A	CRANNELL ROAD	10,600	2,234	21.08	1,631	268	93	241	73.03	11.99	4.17	10.80	179	07E
101	01	HUM	122.25	B	BALD HILLS ROAD	3,700	516	13.95	162	90	63	200	31.47	17.48	12.24	38.81	92	05E
101	01	HUM	122.25	A	BALD HILLS ROAD	3,700	504	13.62	159	88	62	196	31.47	17.48	12.24	38.81	90	05E
101	01	DN	R 4.638	B	KLAMATH, JCT. RTE. 169 SOUTHEAST	3,450	519	15.05	163	91	64	201	31.47	17.48	12.24	38.81	93	05E
101	01	DN	R 4.638	A	KLAMATH, JCT. RTE. 169 SOUTHEAST	3,800	483	12.71	152	84	59	187	31.47	17.48	12.24	38.81	86	05E
101	01	DN	24.41	B	SANDMINE ROAD	4,300	533	12.40	215	86	17	215	40.32	16.13	3.23	40.32	92	05E
101	01	DN	24.41	A	SANDMINE ROAD	6,300	558	8.86	225	90	18	225	40.32	16.13	3.23	40.32	96	05E
101	01	DN	27.01	B	CRESCENT CITY, NORTHCREST DRIVE	29,500	1,475	5.00	779	232	15	450	52.80	15.70	1.00	30.50	206	95E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
101	01	DN	27.01	A	CRESCENT CITY, NORTHCREST DRIVE	15,900	1,526	9.60	835	253	15	423	54.70	16.60	1.00	27.70	201	95E
101	01	DN	R 30.81	B	JCT. RTE. 199 NORTHEAST	10,900	739	6.78	275	141	77	246	37.17	19.05	10.45	33.33	119	99V
101	01	DN	R 30.81	A	JCT. RTE. 199 NORTHEAST	6,000	367	6.11	131	88	45	102	35.81	24.04	12.28	27.88	54	99V
101	01	DN	36.31	B	JCT. RTE. 197 SOUTHEAST	6,900	614	8.90	378	106	2	128	61.50	17.20	0.40	20.90	67	92E
101	01	DN	39.82	B	FRED HAIGHT DRIVE	6,500	389	5.99	140	70	46	133	36.01	18.00	11.71	34.27	64	99V
101	01	DN	46.492	B	OREGON STATE LINE	7,000	679	9.70	440	97	2	140	64.80	14.30	0.30	20.60	73	92E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
103	07	LA	0	A	NB OFF TO HENRY FORD BLVD AND LOS ANGELES, JCT. RTE. 47, TERMINAL ISLAND FREEWAY (BEGIN ROUTE 103)	13,800	7,556	54.75	341	2,900	93	4,222	4.51	38.38	1.23	55.88	1,749	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
104	03	SAC	0	A	JCT. RTE. 99	10,500	840	8.00	427	171	80	163	50.80	20.30	9.50	19.40	99	96E
104	10	AMA	R 5.766	B	IONE, JCT. RTE. 124 NORTH	8,700	653	7.51	99	189	27	338	15.10	29.00	4.10	51.80	141	96V
104	10	AMA	R 5.766	A	IONE, JCT. RTE. 124 NORTH	10,900	675	6.19	178	165	28	304	26.40	24.50	4.10	45.00	130	96V
104	10	AMA	R 5.96	A	IONE, JCT. RTE. 124 SOUTH	8,200	525	6.40	128	145	24	228	24.30	27.70	4.60	43.40	100	96V
104	10	AMA	R 8.201	B	JCT. RTE. 88	7,900	331	4.19	84	144	16	87	25.30	43.40	4.90	26.40	49	96V
104	10	AMA	8.386	A	JCT. RTE. 88	7,100	435	6.12	117	184	18	115	26.90	42.40	4.20	26.50	63	96V
104	10	AMA	10.072	B	SUTTER CREEK, JCT. RTE. 49	5,700	513	9.00	95	123	14	281	18.60	23.90	2.70	54.80	114	96V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
105	07	LA	R 2.106	B	LOS ANGELES, JCT. RTE. 405, SAN DIEGO FREEWAY INTERCHANGE	135,000	4,644	3.44	2,827	534	189	1,094	60.87	11.49	4.08	23.55	553	04V
105	07	LA	R 2.106	A	LOS ANGELES, JCT. RTE. 405, SAN DIEGO FREEWAY INTERCHANGE	199,000	11,323	5.69	6,918	1,303	510	2,592	61.10	11.51	4.50	22.89	1,331	04E
105	07	LA	R 5.234	O	HAWTHORNE, VAN NESS AVENUE	240,000	11,040	4.60	6,745	1,271	497	2,526	61.10	11.51	4.50	22.88	1,298	04V
105	07	LA	R 7.386	B	LOS ANGELES, JCT. RTE. 110, HARBOR FREEWAY INTERCHANGE	223,000	11,239	5.04	6,867	1,294	506	2,573	61.10	11.51	4.50	22.89	1,321	04E
105	07	LA	R 7.386	A	LOS ANGELES, JCT. RTE. 110, HARBOR FREEWAY INTERCHANGE	237,000	12,751	5.38	6,052	1,622	629	4,449	47.46	12.72	4.93	34.89	1,988	04E
105	07	LA	R 13.471	B	LYNWOOD, JCT. RTE. 710, LONG BEACH FREEWAY INTERCHANGE	230,000	14,628	6.36	6,942	1,861	721	5,104	47.46	12.72	4.93	34.89	2,281	04E
105	07	LA	R 13.471	A	LYNWOOD, JCT. RTE. 710, LONG BEACH FREEWAY INTERCHANGE	200,000	17,740	8.87	6,115	1,554	674	9,397	34.47	8.76	3.80	52.97	3,698	04E
105	07	LA	R 16.389	O	DOWNEY, ARDIS AVENUE	207,000	17,367	8.39	5,986	1,521	660	9,199	34.47	8.76	3.80	52.97	3,620	04V
105	07	LA	R 17.823	B	NORWALK, JCT. RTE. 605, SAN GABRIEL RIVER FREEWAY INTERCHANGE	202,000	17,877	8.85	6,162	1,566	679	9,469	34.47	8.76	3.80	52.97	3,726	04E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
107	07	LA	0	A	TORRANCE, JCT. RTE. 1, PACIFIC COAST HIGHWAY	43,500	835	1.92	698	82	32	23	83.55	9.85	3.89	2.71	45	06V
107	07	LA	4.696	B	TORRANCE, ARTESIA BOULEVARD	70,000	1,862	2.66	1,636	134	42	50	87.85	7.21	2.24	2.70	93	06E
107	07	LA	4.696	A	TORRANCE, ARTESIA BOULEVARD	52,000	1,128	2.17	991	81	25	30	87.85	7.21	2.24	2.70	56	06V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
108	10	STA	R 22.438	A	JCT. RTE. 132	9,300	297	3.19	225	40	7	26	75.70	13.30	2.40	8.60	22	92E
108	10	STA	L 22.836	A	MODESTO, K STREET AT NEEDHAM AVENUE	15,600	530	3.40	401	70	13	46	75.70	13.30	2.40	8.60	38	92E
108	10	STA	24.81	B	MODESTO, BRIGGSMORE AVENUE	30,100	1,023	3.40	774	136	25	88	75.70	13.30	2.40	8.60	74	92E
108	10	STA	27.618	B	JCT. RTE. 219 WEST	19,200	806	4.20	610	107	19	69	75.70	13.30	2.40	8.60	58	92V
108	10	STA	27.618	A	JCT. RTE. 219 WEST	21,000	1,470	7.00	176	265	206	823	12.00	18.00	14.00	56.00	345	01V
108	10	STA	38.236	B	OAKDALE, EAST JCT. RTE. 120	20,200	1,010	5.00	141	182	91	596	14.00	18.00	9.00	59.00	241	01E
108	10	TUO	L0	A	OAKDALE, EAST JCT. RTE. 120	15,200	1,064	7.00	181	202	117	564	17.00	19.00	11.00	53.00	237	98V
108	10	TUO	L 2.808	B	SONORA, JCT. RTE. 49	15,200	1,231	8.10	380	228	30	593	30.90	18.50	2.40	48.20	243	95V
108	10	TUO	R 0	A	SONORA, JCT. RTE. 49	18,100	1,358	7.50	422	280	38	618	31.10	20.60	2.80	45.50	259	95E
108	10	TUO	7.511	B	SOULSBYVILLE ROAD	11,000	220	2.00	40	70	29	81	18.00	32.00	13.00	37.00	40	01E
108	10	TUO	7.511	A	SOULSBYVILLE ROAD	7,900	237	3.00	38	90	24	85	16.00	38.00	10.00	36.00	42	01E
108	10	TUO	15.17	A	CHIEF FULLER ROAD	4,450	178	4.00	36	59	16	68	20.00	33.00	9.00	38.00	33	01V
108	10	TUO	30.164	B	MC COY SADDLE	4,750	143	3.00	34	40	20	49	24.00	28.00	14.00	34.00	25	01E
108	10	TUO	36.55	B	COW CREEK ROAD	1,850	56	3.00	12	16	7	21	22.00	28.00	13.00	37.00	10	01V
108	09	MNO	15.149	B	SONORA JUNCTION, JCT. RTE. 395	710	16	2.30	11	2	0	2	71.40	14.30	0.00	14.30	1	97V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
109	04	SM	1.87	B	MENLO PARK, JCT. RTE. 84	20,300	524	2.58	414	44	13	53	78.98	8.46	2.40	10.16	39	00V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
110	07	LA	R .931	B	LOS ANGELES, JCT. RTE. 47, VINCENT THOMAS BRIDGE INTERCHANGE	52,000	1,170	2.25	923	80	59	109	78.88	6.82	5.00	9.31	86	10E
110	07	LA	R .931	A	LOS ANGELES, JCT. RTE. 47, VINCENT THOMAS BRIDGE INTERCHANGE	71,000	2,300	3.24	769	372	80	1,079	33.44	16.19	3.46	46.90	445	10E
110	07	LA	4.061	B	LOS ANGELES, JCT. RTE. 1, PACIFIC COAST HIGHWAY INTERCHANGE	106,000	7,081	6.68	2,368	1,146	245	3,321	33.44	16.19	3.46	46.90	1,370	10E
110	07	LA	4.061	A	LOS ANGELES, JCT. RTE. 1, PACIFIC COAST HIGHWAY INTERCHANGE	144,000	8,611	5.98	2,880	1,394	298	4,039	33.44	16.19	3.46	46.90	1,666	10E
110	07	LA	6.144	O	228TH STREET	178,000	9,576	5.38	3,202	1,550	331	4,491	33.44	16.19	3.46	46.90	1,853	10V
110	07	LA	8.775	B	CARSON, JCT. RTE. 405, SAN DIEGO FREEWAY INTERCHANGE	218,000	10,529	4.83	3,521	1,705	364	4,938	33.44	16.19	3.46	46.90	2,037	10E
110	07	LA	9.87	B	LOS ANGELES, JCT. RTE. 91, GARDENA FREEWAY INTERCHANGE	263,000	21,198	8.06	6,915	2,010	799	11,477	32.62	9.48	3.77	54.14	4,504	10E
110	07	LA	9.87	A	LOS ANGELES, JCT. RTE. 91, GARDENA FREEWAY INTERCHANGE	234,000	15,912	6.80	8,009	2,019	700	5,184	50.33	12.69	4.40	32.58	2,357	10E
110	07	LA	11.891	A	LOS ANGELES, ROSECRANS AVENUE INTERCHANGE	251,000	15,336	6.11	7,719	1,946	675	4,996	50.33	12.69	4.40	32.58	2,272	10E
110	07	LA	13.82	B	LOS ANGELES, JCT. RTE. 105, GLENN ANDERSON FREEWAY INTERCHANGE	258,000	15,145	5.87	7,622	1,922	666	4,934	50.33	12.69	4.40	32.58	2,244	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
110	07	LA	13.82	A	LOS ANGELES, JCT. RTE. 105, GLENN ANDERSON FREEWAY INTERCHANGE	299,000	13,904	4.65	7,542	1,605	587	4,171	54.24	11.54	4.22	30.00	1,937	10E
110	07	LA	16.981	B	LOS ANGELES, FLORENCE AVENUE INTERCHANGE	318,000	13,547	4.26	7,348	1,563	572	4,064	54.24	11.54	4.22	30.00	1,887	10E
110	07	LA	21.444	B	LOS ANGELES, JCT. RTE. 10, SANTA MONICA FREEWAY INTERCHANGE	274,000	12,878	4.70	6,985	1,486	543	3,863	54.24	11.54	4.22	30.00	1,794	10E
110	07	LA	21.444	A	LOS ANGELES, JCT. RTE. 10, SANTA MONICA FREEWAY INTERCHANGE	269,000	7,478	2.78	4,750	960	233	1,536	63.52	12.84	3.11	20.54	819	10E
110	07	LA	22.556	O	LOS ANGELES, SEVENTH STREET	270,000	6,777	2.51	4,305	870	211	1,392	63.52	12.84	3.11	20.54	742	10E
110	07	LA	23.727	B	LOS ANGELES, JCT. RTE. 101, SANTA ANA/HOLLYWOOD FREEWAYS, FOUR LEVEL INTERCHANGE	271,000	6,314	2.33	4,011	811	196	1,297	63.52	12.84	3.11	20.54	691	10E
110	07	LA	23.727	A	LOS ANGELES, JCT. RTE. 101, SANTA ANA/HOLLYWOOD FREEWAYS, FOUR LEVEL INTERCHANGE	156,000	1,841	1.18	1,597	192	11	41	86.77	10.41	0.60	2.22	89	10E
110	07	LA	24.755	B	LOS ANGELES, STADIUM WAY OVERCROSSING	165,000	1,947	1.18	1,689	203	12	43	86.77	10.41	0.60	2.22	94	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
110	07	LA	25.751	B	LOS ANGELES, JCT. RTE. 5, GOLDEN STATE FREEWAY INTERCHANGE	182,000	1,747	0.96	1,516	182	10	39	86.77	10.41	0.60	2.22	85	10E
110	07	LA	25.751	A	LOS ANGELES, JCT. RTE. 5, GOLDEN STATE FREEWAY INTERCHANGE	122,000	988	0.81	968	20	0	0	97.96	2.04	0.00	0.00	36	10E
110	07	LA	31.912	B	PASADENA, GLENARM STREET	41,500	336	0.81	329	7	0	0	97.96	2.04	0.00	0.00	12	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
111	11	IMP	R 0	A	CALEXICO, SOUTH CITY LIMITS, AT MEXICAN BOUNDARY	26,500	954	3.60	531	169	19	235	55.70	17.70	2.00	24.60	118	78V
111	11	IMP	1.183	B	JCT. RTE. 98	31,000	1,488	4.80	1,004	137	49	298	67.50	9.20	3.30	20.00	158	78V
111	11	IMP	R 1.183	A	JCT. RTE. 98	27,000	2,160	8.00	1,192	225	32	711	55.20	10.40	1.50	32.90	312	78V
111	11	IMP	R 4.741	B	JCT. RTE. 86 WEST	30,000	2,400	8.00	1,325	250	36	790	55.20	10.40	1.50	32.90	347	78E
111	11	IMP	R 4.741	A	JCT. RTE. 86 WEST	29,500	2,065	7.00	1,088	310	99	568	52.70	15.00	4.80	27.50	277	81E
111	11	IMP	R 7.714	B	JCT. RTE. 8	29,000	2,030	7.00	1,070	305	97	558	52.70	15.00	4.80	27.50	272	81V
111	11	IMP	R 7.714	A	JCT. RTE. 8	21,700	2,691	12.40	1,262	258	40	1,130	46.90	9.60	1.50	42.00	464	78V
111	11	IMP	13.078	A	WORTHINGTON ROAD	10,200	2,580	25.29	2,221	11	17	332	86.07	0.43	0.64	12.85	196	07V
111	11	IMP	17.59	A	KEYSTONE ROAD	9,500	1,904	20.04	399	102	225	1,177	20.97	5.37	11.83	61.83	462	07E
111	11	IMP	22.139	B	JCT. RTE. 78	9,500	2,362	24.86	396	290	145	1,531	16.76	12.29	6.15	64.80	590	03E
111	11	IMP	22.14	A	JCT. RTE. 78	12,200	1,298	10.64	604	121	60	513	46.51	9.30	4.65	39.53	218	00E
111	11	IMP	26.67	B	RUTHERFORD ROAD	5,000	750	15.00	361	41	10	339	48.10	5.40	1.30	45.20	135	85E
111	11	IMP	26.67	A	RUTHERFORD ROAD	5,700	1,203	21.10	426	63	28	687	35.40	5.20	2.30	57.10	262	78V
111	11	IMP	32.513	B	JCT. RTE. 115 EAST	5,600	1,182	21.10	418	61	27	675	35.40	5.20	2.30	57.10	257	78E
111	11	IMP	32.513	A	JCT. RTE. 115 EAST	4,850	781	16.10	327	41	21	392	41.90	5.20	2.70	50.20	154	85V
111	11	IMP	39.82	B	NILAND AVENUE	4,050	745	18.40	312	39	20	374	41.90	5.20	2.70	50.20	146	85E
111	11	IMP	39.82	A	NILAND AVENUE	3,100	555	17.90	233	29	15	279	41.90	5.20	2.70	50.20	109	85E
111	11	IMP	65.395	B	IMPERIAL/RIVERSIDE COUNTY LINE	1,650	353	21.38	282	28	15	28	79.94	7.85	4.36	7.85	24	09V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
111	08	RIV	18.428	B	MECCA, JCT. RTE. 195 WEST	4,300	847	19.70	355	44	23	425	41.90	5.20	2.70	50.20	166	85E
111	08	RIV	18.428	A	MECCA, JCT. RTE. 195 WEST	7,500	1,313	17.50	506	66	54	688	38.50	5.00	4.10	52.40	269	85V
111	08	RIV	T 50.8	O	TAMARISK ROAD	18,000	1,998	11.10	1,650	174	38	136	82.60	8.70	1.90	6.80	126	92V
111	08	RIV	T 51.588	B	VISTA CHINO	19,300	2,162	11.20	1,786	188	41	147	82.60	8.70	1.90	6.80	137	91V
111	08	RIV	T 51.588	A	VISTA CHINO	29,000	2,233	7.70	2,030	145	18	40	90.90	6.50	0.80	1.80	101	91V
111	08	RIV	R 63.378	B	JCT. RTE. 10	13,200	713	5.40	515	51	19	128	72.30	7.20	2.60	17.90	70	90V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
112	04	ALA	R 0	A	SAN LEANDRO, JCT. RTE. 61	28,500	2,921	10.25	1,007	1,009	98	807	34.47	34.54	3.36	27.64	421	00V
112	04	ALA	0.602	A	JCT. RTE. 880	39,000	1,911	4.90	1,313	279	31	289	68.70	14.60	1.60	15.10	176	97E
112	04	ALA	1.782	B	SAN LEANDRO, JCT. RTE. 185	22,200	533	2.40	401	54	19	59	75.20	10.20	3.50	11.10	42	97E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
113	04	SOL	0	A	JCT. RTE. 12	3,900	279	7.15	35	16	5	222	12.54	5.79	1.93	79.74	80	04V
113	04	SOL	19.96	B	DIXON, NORTH ADAMS STREET	10,800	660	6.11	216	106	48	290	32.72	16.05	7.25	43.98	124	04V
113	04	SOL	21.24	B	DIXON, WEST JCT. RTE. 80	18,100	2,699	14.91	955	259	156	1,327	35.38	9.60	5.78	49.17	538	06E
113	04	SOL	R 21.772	A	EAST JCT. RTE. 80 NB	36,800	2,090	5.68	677	185	74	1,154	32.40	8.86	3.52	55.22	450	06E
113	03	YOL	R 1.082	B	DAVIS, RUSSELL BOULEVARD	37,500	2,018	5.38	654	180	71	1,114	32.40	8.90	3.50	55.20	434	06E
113	03	YOL	R 1.082	A	DAVIS, RUSSELL BOULEVARD	32,000	1,872	5.85	640	175	116	941	34.20	9.33	6.22	50.26	380	06E
113	03	YOL	R 4.105	A	COUNTY ROAD 29	24,200	1,868	7.72	639	174	116	939	34.20	9.33	6.22	50.26	379	06V
113	03	YOL	R 9.228	A	GIBSON ROAD	15,600	1,950	12.50	566	215	37	1,133	29.00	11.00	1.90	58.10	436	06E
113	03	YOL	R 10.218	B	WOODLAND, MAIN STREET	15,600	1,560	10.00	452	172	30	906	29.00	11.00	1.90	58.10	349	06E
113	03	YOL	R 10.218	A	WOODLAND, MAIN STREET	6,600	660	10.00	192	72	13	383	29.10	10.90	2.00	58.00	147	06E
113	03	YOL	12.33	A	COUNTY ROAD P18C	3,700	270	7.30	129	25	12	104	47.78	9.26	4.44	38.52	44	05E
113	03	YOL	21.9	B	KNIGHTS LANDING, JCT. RTE. 45 NORTH	8,300	581	7.00	191	202	56	132	32.90	34.80	9.60	22.70	79	96E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
114	04	SM	5	A	MENLO PARK, JCT. RTE. 101	36,500	2,154	5.90	1,514	227	68	345	70.28	10.52	3.18	16.02	203	94V
114	04	SM	5.926	B	JCT. RTE. 84	36,500	1,511	4.14	670	91	51	699	44.35	5.99	3.36	46.29	280	00V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
115	11	IMP	R 3.201	A	JCT. RTE. 8	1,050	392	37.30	98	27	14	253	24.90	7.00	3.50	64.60	95	78V
115	11	IMP	L 9.54	A	WALNUT AVENUE/5TH STREET	6,000	606	10.10	150	44	19	393	24.80	7.20	3.10	64.90	148	78E
115	11	IMP	21.17	B	JCT. RTE. 78	1,850	592	32.00	147	42	20	383	24.80	7.10	3.40	64.70	144	78E
115	11	IMP	21.18	A	JCT. RTE. 78	1,350	1,106	81.90	265	109	27	705	24.00	9.90	2.40	63.70	266	78E
115	11	IMP	35.235	B	CALIPATRIA, JCT. RTE. 111	3,850	1,159	30.10	278	116	29	736	24.00	10.00	2.50	63.50	279	78V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
116	04	SON	0	A	JCT. RTE. 1, JENNER, SOUTH	2,300	102	4.44	64	19	2	18	62.30	18.85	1.64	17.21	10	99V
116	04	SON	11.164	B	GUERNEWOOD PARK, HULBERT CREEK BRIDGE	8,350	205	2.46	149	20	5	31	72.78	9.79	2.45	14.98	18	99V
116	04	SON	14.05	B	SANTA NELLA WINERY/ODD FELLOWS ROAD	3,000	106	3.54	70	21	0	15	65.88	20.00	0.00	14.12	10	99V
116	04	SON	14.05	A	SANTA NELLA WINERY/ODD FELLOWS ROAD	2,700	103	3.81	73	18	0	12	70.71	17.17	0.00	12.12	8	99V
116	04	SON	21.8	B	GUERNEVILLE ROAD	11,400	457	4.01	262	66	7	121	57.26	14.52	1.64	26.58	58	99V
116	04	SON	26.51	B	SEBASTOPOL, MAIN STREET	20,900	878	4.20	644	123	26	84	73.40	14.00	3.00	9.60	67	96V
116	04	SON	R 26.733	B	SEBASTOPOL, JCT. RTE. 12 EAST, SEBASTOPOL/BODEGA AVENUE	25,800	619	2.40	504	58	3	53	81.50	9.40	0.50	8.60	42	96V
116	04	SON	R 26.733	A	SEBASTOPOL, JCT. RTE. 12 EAST, SEBASTOPOL/BODEGA AVENUE	23,600	802	3.40	547	151	10	94	68.20	18.80	1.30	11.70	67	96V
116	04	SON	27.3	A	SEBASTOPOL, PETALUMA AVENUE	23,400	889	3.80	735	95	14	44	82.70	10.70	1.60	5.00	52	96V
116	04	SON	33.61	A	STONY POINT ROAD EAST	14,800	928	6.27	512	188	31	198	55.15	20.21	3.31	21.34	108	02V
116	04	SON	35.03	B	PETALUMA, JCT. RTE. 101	22,100	2,601	11.77	1,083	314	152	1,052	41.63	12.09	5.83	40.46	452	99V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
116	04	SON	35.04	A	PETALUMA, JCT. RTE. 101	36,000	2,398	6.66	1,167	276	108	847	48.68	11.51	4.49	35.32	374	02V
116	04	SON	36.36	B	FRATES ROAD/CADER LANE	23,400	2,466	10.54	773	234	139	1,320	31.35	9.49	5.63	53.53	524	99V
116	04	SON	41.81	A	ADOBE ROAD	17,200	1,238	7.20	514	219	109	396	41.51	17.71	8.77	32.01	191	99V
116	04	SON	44.2	B	WATMAUGH ROAD	16,400	1,287	7.85	510	351	76	349	39.61	27.28	5.90	27.14	182	02V
116	04	SON	44.2	A	WATMAUGH ROAD	14,500	1,051	7.25	451	156	122	321	42.92	14.87	11.65	30.56	159	02V
116	04	SON	46.755	B	JCT. RTE. 121	16,500	896	5.43	413	134	102	247	46.06	14.96	11.42	27.56	127	02V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
118	07	VEN	0.516	A	VENTURA, JCT. RTE. 126, SANTA PAULA FREEWAY	38,000	3,960	10.42	1,405	599	261	1,695	35.48	15.13	6.59	42.80	727	07V
118	07	VEN	2.2	B	JCT. RTE. 232, VINEYARD AVENUE	37,500	4,425	11.80	1,444	579	276	2,126	32.64	13.08	6.24	48.04	878	07V
118	07	VEN	2.2	A	JCT. RTE. 232, VINEYARD AVENUE	22,200	2,595	11.69	799	496	242	1,057	30.80	19.11	9.34	40.75	474	07V
118	07	VEN	10.92	B	JCT. RTE. 34, SOMIS ROAD	10,700	2,751	25.71	705	452	214	1,380	25.64	16.43	7.77	50.16	574	08E
118	07	VEN	10.92	A	JCT. RTE. 34, SOMIS ROAD	17,000	1,933	11.37	396	266	120	1,152	20.48	13.74	6.19	59.58	453	08E
118	07	VEN	14.686	A	GRIMES CANYON ROAD	18,700	2,126	11.37	435	292	132	1,267	20.48	13.73	6.19	59.59	499	08V
118	07	VEN	17.494	B	MOORPARK, WEST JCT. RTE. 23, MOORPARK AVENUE	30,500	3,980	13.05	1,272	571	223	1,914	31.97	14.34	5.61	48.08	790	07V
118	07	VEN	R 17.905	B	MOORPARK, EAST JCT. RTE. 23, AT SPRING ROAD	34,500	4,502	13.05	1,439	646	253	2,165	31.97	14.34	5.61	48.08	894	07E
118	07	VEN	T 18.21	A	MOORPARK, JCT. RTE. 23, MOORPARK FREEWAY	77,000	3,496	4.54	1,380	556	230	1,330	39.48	15.90	6.58	38.04	592	10E
118	07	VEN	R 27.811	O	TAPO STREET	113,000	3,887	3.44	1,535	618	256	1,479	39.48	15.90	6.58	38.04	658	10V
118	07	LA	R 1.799	B	LOS ANGELES, JCT. RTE. 27, TOPANGA CANYON BOULEVARD INTERCHANGE	117,000	4,610	3.94	1,887	729	279	1,714	40.93	15.82	6.06	37.18	765	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
118	07	LA	R 1.799	A	LOS ANGELES, JCT. RTE. 27, TOPANGA CANYON BOULEVARD INTERCHANGE	127,000	5,334	4.20	2,240	841	304	1,950	41.99	15.76	5.69	36.56	873	10E
118	07	LA	R 9.805	B	LOS ANGELES, JCT. RTE. 405, SAN DIEGO FREEWAY INTERCHANGE	229,000	6,046	2.64	2,588	950	327	2,181	42.80	15.71	5.41	36.08	978	10V
118	07	LA	R 9.805	A	LOS ANGELES, JCT. RTE. 405, SAN DIEGO FREEWAY INTERCHANGE	220,000	11,022	5.01	4,173	1,938	878	4,033	37.86	17.58	7.97	36.59	1,845	10E
118	07	LA	R 11.447	A	LOS ANGELES, JCT. RTE. 5, GOLDEN STATE FREEWAY INTERCHANGE	149,000	2,533	1.70	1,590	283	136	525	62.76	11.16	5.35	20.73	283	10E
118	07	LA	R 14.08	B	LOS ANGELES, JCT. RTE. 210, FOOTHILL FREEWAY INTERCHANGE	104,000	2,454	2.36	1,540	274	131	509	62.76	11.16	5.35	20.73	274	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
119	06	KER	0	A	TAFT, JCT. RTE. 33	5,100	969	19.00	523	48	19	378	54.00	5.00	2.00	39.00	156	04E
119	06	KER	2.14	B	HARRISON STREET	5,000	1,100	22.00	605	110	55	330	55.00	10.00	5.00	30.00	153	04E
119	06	KER	2.14	A	HARRISON STREET	7,600	1,672	22.00	920	167	84	502	55.00	10.00	5.00	30.00	233	04E
119	06	KER	18.173	B	JCT. RTE. 43 NORTH	10,600	1,389	13.10	857	125	58	349	61.70	9.00	4.18	25.13	170	10V
119	06	KER	18.173	A	JCT. RTE. 43 NORTH	10,000	2,000	20.00	1,260	160	60	520	63.00	8.00	3.00	26.00	247	04E
119	06	KER	19.773	B	JCT. RTE. 5	10,000	1,988	19.88	1,473	220	92	204	74.09	11.05	4.61	10.25	156	08V
119	06	KER	19.773	A	JCT. RTE. 5	6,800	2,012	29.59	1,304	149	93	466	64.81	7.41	4.63	23.15	234	06E
119	06	KER	31.283	B	JCT. RTE. 99	12,500	2,625	21.00	1,680	131	53	761	64.00	5.00	2.00	29.00	341	04E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
120	10	SJ	R .493	A	MOSSDALE, JCT. RTE. 5	530	98	18.40	15	7	3	72	15.50	7.60	3.50	73.40	26	89V
120	10	SJ	T 6.87	B	SOUTH JCT. RTE. 99	72,000	4,320	6.00	691	734	518	2,376	16.00	17.00	12.00	55.00	988	01V
120	10	SJ	6.197	A	MANTECA, NORTH JCT. RTE. 99	14,100	2,073	14.70	346	386	54	1,287	16.70	18.60	2.60	62.10	500	97E
120	10	STA	3.16	B	VALLEY HOME ROAD	10,700	856	8.00	120	128	68	539	14.00	15.00	8.00	63.00	212	01V
120	10	STA	3.16	A	VALLEY HOME ROAD	24,300	3,810	15.68	457	610	76	2,667	12.00	16.00	2.00	70.00	1,003	01V
120	10	STA	5.116	B	OAKDALE, WEST JCT. RTE. 108	18,000	2,340	13.00	257	281	234	1,568	11.00	12.00	10.00	67.00	610	01E
120	10	STA	5.116	A	OAKDALE, WEST JCT. RTE. 108	25,700	1,799	7.00	270	234	126	1,169	15.00	13.00	7.00	65.00	453	01V
120	10	STA	T 18.168	O	STANISLAUS/TUOLUME COUNTY LINE	18,600	2,189	11.77	1,504	80	34	570	68.73	3.67	1.57	26.02	262	06V
120	10	TUO	R 0	O	STANISLAUS/TUOLUME COUNTY LINE	18,600	2,189	11.77	1,504	80	34	570	68.73	3.67	1.57	26.02	262	06V
120	10	TUO	12.077	B	EAST JCT. RTE. 108	15,500	1,511	9.75	1,042	57	26	385	68.98	3.80	1.75	25.47	178	07V
120	10	TUO	12.077	A	EAST JCT. RTE. 108	2,700	226	8.37	36	37	7	146	16.00	16.40	2.90	64.70	56	95V
120	10	TUO	15.516	A	CHINESE CAMP, NORTH JCT. RTE. 49	3,750	255	6.79	108	31	4	112	42.40	12.20	1.60	43.80	46	93E
120	10	TUO	R 23.897	A	SOUTH JCT. RTE. 49	3,900	195	5.00	39	66	20	70	20.00	34.00	10.00	36.00	35	01E
120	09	MNO	R 0	A	TUOLUMNE/MONO COUNTY LINE	2,870	83	2.90	67	0	16	0	81.08	0.00	18.92	0.00	5	07V
120	09	MNO	R 12	O	LEE VINING RANGER STATION	1,300	46	3.54	33	1	10	2	71.74	2.17	21.74	4.35	3	07V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
120	09	MNO	13.37	A	JCT. RTE. 395	420	57	13.46	2	5	2	49	3.00	8.00	3.00	86.00	18	03V
120	09	MNO	58.99	B	JCT. RTE. 6	400	21	5.29	13	1	6	1	61.11	5.56	27.78	5.56	2	01E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
121	04	SON	0	A	JCT. RTE. 37	14,900	1,073	7.20	665	176	62	170	61.99	16.38	5.81	15.82	107	02V
121	04	SON	6.692	B	JCT. RTE. 116 WEST	16,000	733	4.58	286	84	40	323	39.03	11.43	5.52	44.02	135	02V
121	04	SON	6.692	A	JCT. RTE. 116 WEST	17,000	1,076	6.33	469	141	104	363	43.57	13.09	9.63	33.71	170	99V
121	04	SON	R 7.438	B	JCT. RTE. 12 NORTH	16,300	1,281	7.86	597	191	102	391	46.62	14.89	8.00	30.49	188	02V
121	04	SON	7.442	A	JCT. RTE. 12 NORTH	14,200	1,116	7.86	481	181	76	378	43.06	16.25	6.83	33.86	175	02V
121	04	NAP	R 5.891	B	JCT. RTE. 221 SOUTH	21,300	562	2.64	352	121	10	78	62.72	21.57	1.86	13.85	52	02V
121	04	NAP	6.01	A	JCT. RTE. 221 SOUTH	29,500	1,159	3.93	718	190	67	183	61.99	16.38	5.81	15.82	116	02V
121	04	NAP	9.403	B	NAPA, TRANCAS STREET	11,700	462	3.95	249	111	59	42	53.90	24.09	12.82	9.19	42	99V
121	04	NAP	10.55	B	ATLAS PEAK ROAD	9,500	582	6.13	360	115	17	90	61.85	19.83	2.86	15.46	57	99V
121	04	NAP	10.68	B	VICHY AVENUE	4,750	166	3.49	105	48	6	7	63.02	29.17	3.65	4.17	11	99V
121	04	NAP	22.083	B	JCT. RTE. 128	2,200	64	2.90	49	9	0	7	76.10	13.40	0.00	10.50	5	96V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
123	04	ALA	0	A	OAKLAND, JCT. RTE. 580	26,000	429	1.65	312	56	11	50	72.73	13.07	2.65	11.55	35	03V
123	04	ALA	1.906	B	BERKELEY, JCT. RTE. 13	21,100	616	2.92	470	88	10	48	76.26	14.32	1.55	7.87	43	03V
123	04	ALA	1.906	A	BERKELEY, JCT. RTE. 13	22,300	466	2.09	365	58	8	35	78.41	12.39	1.77	7.43	31	03V
123	04	CC	2.1	B	CUTTING BOULEVARD	30,000	453	1.51	288	104	5	57	63.56	22.89	1.06	12.50	40	03V
123	04	CC	2.198	B	RICHMOND, JCT. RTE. 80	20,600	496	2.41	373	64	12	48	75.11	12.82	2.41	9.65	37	02V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
124	10	AMA	0	A	JCT. RTE. 88, IONE SOUTH	5,000	420	8.40	89	66	13	252	21.30	15.60	3.00	60.10	98	96V
124	10	AMA	2.291	B	IONE, WEST JCT RTE 104	6,000	528	8.80	106	104	22	296	20.00	19.70	4.20	56.10	119	96V
124	10	AMA	R 2.291	A	IONE, WEST JCT RTE 104	5,000	250	5.00	71	85	13	82	28.40	34.00	5.00	32.60	41	96V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
125	11	SD	12.967	A	EAST JCT. RTE. 94	160,000	7,040	4.40	4,147	1,000	275	1,619	58.90	14.20	3.90	23.00	836	96E
125	11	SD	R 15.409	B	JCT. RTE. 8	147,000	6,468	4.40	3,810	918	252	1,488	58.90	14.20	3.90	23.00	768	96E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
126	07	VEN	0	A	EB ON FROM MAIN ST and VENTURA, JCT. RTE. 101, VENTURA FREEWAY INTERCHANGE	47,500	2,047	4.31	507	278	154	1,108	24.78	13.56	7.51	54.15	448	10E
126	07	VEN	5.031	B	VENTURA, JCT. RTE. 118, WELLS ROAD INTERCHANGE	35,000	2,128	6.08	557	275	137	1,159	26.18	12.92	6.42	54.47	465	10E
126	07	VEN	R 5.031	A	VENTURA, JCT. RTE. 118, WELLS ROAD INTERCHANGE	48,000	2,208	4.60	609	271	118	1,210	27.59	12.29	5.33	54.79	481	10E
126	07	VEN	R 10.629	O	LAURIE LANE PED OC; E/O PECK RD	40,500	2,284	5.64	662	266	97	1,259	29.00	11.66	4.24	55.11	496	10V
126	07	VEN	R 12.042	B	SANTA PAULA, JCT. RTE. 150, 10TH STREET INTERCHANGE	36,500	2,237	6.13	608	242	87	1,299	27.18	10.82	3.91	58.09	504	10E
126	07	VEN	R 12.042	A	SANTA PAULA, JCT. RTE. 150, 10TH STREET INTERCHANGE	30,000	2,088	6.96	530	208	75	1,275	25.37	9.98	3.59	61.07	489	10E
126	07	VEN	21.137	B	FILLMORE, JCT. RTE. 23, A STREET	32,000	1,936	6.05	456	177	63	1,240	23.55	9.14	3.26	64.05	469	10E
126	07	VEN	21.137	A	FILLMORE, JCT. RTE. 23, A STREET	30,000	1,851	6.17	402	154	54	1,241	21.74	8.30	2.94	67.03	464	10E
126	07	VEN	R 30.8	O	PIRU	21,500	1,810	8.42	361	135	47	1,267	19.92	7.46	2.61	70.01	469	10E
126	07	LA	R 0	A	VENTURA/LOS ANGELES COUNTY LINE	22,500	1,775	7.89	354	132	46	1,243	19.92	7.46	2.61	70.01	460	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
126	07	LA	R 5.801	B	SANTA CLARITA, NORTH JCT. RTE. 5, GOLDEN STATE FREEWAY	40,000	3,592	8.98	643	473	246	2,230	17.89	13.17	6.85	62.08	872	10E
126	07	LA	R 5.85	A	SANTA CLARITA, SOUTH JCT. RTE. 5, GOLDEN STATE FREEWAY	24,500	777	3.17	341	179	86	172	43.85	22.99	11.02	22.14	100	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
127	08	SBD	L 0	A	JCT. RTE. 15	7,000	714	10.20	215	19	5	475	30.10	2.70	0.70	66.50	174	93E
127	08	SBD	29.708	A	SARATOGA SPRINGS ROAD	770	79	10.30	24	2	1	52	30.10	2.80	0.70	66.40	19	93E
127	09	INY	0	A	SAN BERNARDINO/INYO COUNTY LINE	750	103	13.79	10	10	5	77	10.00	10.00	5.00	75.00	29	07V
127	09	INY	14.749	B	SHOSHONE, SOUTH JCT. RTE. 178 EAST	950	110	11.58	23	12	10	65	20.91	10.91	9.09	59.09	26	08E
127	09	INY	41.99	B	SOUTH OF STATELINE ROAD	280	91	32.50	18	12	10	51	19.78	13.19	10.99	56.04	21	10V
127	09	INY	42.149	B	JCT. RTE. 190 WEST	1,170	251	21.43	17	13	13	208	6.70	5.30	5.30	82.70	75	07V
127	09	INY	42.149	A	JCT. RTE. 190 WEST	600	82	13.71	11	2	1	68	13.00	3.00	1.00	83.00	24	07V
127	09	INY	49.42	B	NEVADA STATE LINE	600	180	30.00	11	7	11	151	6.00	4.00	6.00	84.00	55	94V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
128	01	MEN	0	A	JCT. RTE. 1	1,700	303	17.81	138	106	32	27	45.61	35.00	10.53	8.77	29	06E
128	01	MEN	11.67	A	FLYNN CREEK ROAD	2,000	300	15.00	137	105	32	26	45.70	35.00	10.53	8.77	28	06E
128	01	MEN	29.576	B	JCT. RTE. 253 EAST	4,000	238	5.94	109	83	25	21	45.61	35.00	10.53	8.77	22	06E
128	01	MEN	29.576	A	JCT. RTE. 253 EAST	2,300	285	12.39	130	100	30	25	45.61	35.00	10.53	8.77	27	06E
128	04	SON	L 4.86	A	CLOVERDALE, NORTH JCT. RTE. 101	2,400	205	8.53	101	41	0	63	49.48	19.79	0.00	30.73	29	99V
128	04	SON	11.49	B	ALEXANDER VALLEY ROAD	2,700	131	4.84	66	30	1	34	50.00	22.83	1.09	26.09	17	99V
128	04	SON	11.49	A	ALEXANDER VALLEY ROAD	4,250	249	5.86	127	49	16	58	50.98	19.61	6.27	23.14	31	99V
128	04	NAP	2.66	B	TUBBS LANE	2,900	223	7.70	139	17	4	64	62.20	7.70	1.60	28.50	29	93E
128	04	NAP	4.55	B	CALISTOGA RTE. 29	10,100	379	3.75	182	76	27	94	47.91	20.16	7.07	24.87	50	99V
128	04	NAP	4.56	A	CALISTOGA RTE. 29	2,950	152	5.14	68	18	12	54	44.91	11.98	7.78	35.33	24	02V
128	04	NAP	15.79	A	LOWER CHILES VALLEY ROAD	1,000	282	28.20	164	47	12	59	58.00	16.60	4.40	21.00	32	93E
128	04	NAP	23.896	B	JCT. RTE. 121 SOUTH	3,500	336	9.60	197	75	4	60	58.70	22.30	1.10	17.90	35	93V
128	04	NAP	23.896	A	JCT. RTE. 121 SOUTH	1,000	90	9.00	43	21	4	22	48.00	22.90	4.70	24.40	12	93V
128	03	YOL	4.59	A	COUNTY ROAD 86	2,200	169	7.70	96	21	13	39	56.60	12.60	7.50	23.30	21	89E
128	03	YOL	8.77	B	WINTERS, RAILROAD STREET	9,200	322	3.50	127	63	4	129	39.30	19.50	1.10	40.10	55	89V
128	03	YOL	9.835	B	JCT. RTE. 505	11,200	849	7.58	118	307	265	159	13.90	36.16	31.21	18.73	126	05V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
129	05	SCR	L 0	A	JCT. RTE. 1	20,000	1,160	5.80	537	129	28	466	46.30	11.10	2.40	40.20	196	03E
129	05	SCR	0.54	B	WATSONVILLE, BLACKBURN STREET	20,700	2,443	11.80	1,295	132	110	906	53.00	5.40	4.50	37.10	386	03E
129	05	SCR	0.54	A	WATSONVILLE, BLACKBURN STREET	11,800	1,805	15.30	816	117	83	789	45.20	6.50	4.60	43.70	324	03E
129	05	SCR	7.2	B	ROGGE LANE	9,400	1,918	20.40	704	125	42	1,047	36.70	6.50	2.20	54.60	404	03E
129	05	SBT	R 2.644	B	JCT. RTE. 101	9,500	2,641	27.80	813	222	172	1,434	30.80	8.40	6.50	54.30	569	03E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
130	04	SCL	0	A	SAN JOSE, JCT. RTE. 101	29,000	682	2.35	582	71	0	30	85.34	10.34	0.00	4.33	37	04V
130	04	SCL	3.66	B	MOUNT HAMILTON ROAD	6,400	118	1.85	79	37	2	0	67.26	30.97	1.77	0.00	6	04V
130	04	SCL	3.66	A	MOUNT HAMILTON ROAD	2,150	63	2.95	45	16	2	0	70.77	26.15	3.08	0.00	3	04V
130	04	SCL	6.06	B	CLAYTON ROAD	770	35	4.50	29	6	0	0	82.40	17.60	0.00	0.00	2	98E
130	04	SCL	22.503	B	MOUNT HAMILTON	200	30	15.00	26	4	0	0	88.20	11.80	0.00	0.00	1	98E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
131	04	MRN	0	A	JCT. RTE. 101	28,000	708	2.53	533	132	22	21	75.31	18.71	3.04	2.93	41	05V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
132	10	SJ	0	A	JCT. RTE. 580	13,200	2,376	18.00	307	383	102	1,585	12.90	16.10	4.30	66.70	608	93E
132	10	SJ	3.24	B	JCT. RTE. 5	13,000	2,340	18.00	302	377	101	1,561	12.90	16.10	4.30	66.70	599	93E
132	10	SJ	3.24	A	JCT. RTE. 5	14,100	2,594	18.40	371	488	96	1,639	14.30	18.80	3.70	63.20	637	93E
132	10	SJ	R 5.86	A	VERNALIS, JCT. RTE. 33	15,500	2,465	15.90	550	407	27	1,481	22.30	16.50	1.10	60.10	572	93E
132	10	STA	14.732	B	MODESTO, JCT. RTE. 99	13,000	1,560	12.00	156	187	109	1,108	10.00	12.00	7.00	71.00	421	01E
132	10	STA	14.732	A	MODESTO, JCT. RTE. 99	11,500	1,357	11.80	357	208	22	771	26.30	15.30	1.60	56.80	301	93E
132	10	STA	17.14	A	EL VISTA AVENUE	19,200	1,882	9.80	664	327	41	849	35.30	17.40	2.20	45.10	352	85V
132	10	STA	28	B	HICKMAN ROAD/F STREET	6,500	787	12.10	330	90	65	303	41.90	11.40	8.20	38.50	134	89V
132	10	STA	28	A	HICKMAN ROAD/F STREET	5,600	526	9.40	235	92	37	162	44.60	17.50	7.10	30.80	78	93E
132	10	STA	35.98	A	ROBERTS FERRY ROAD	2,450	162	6.60	77	38	10	38	47.50	23.20	6.10	23.20	21	93E
132	10	MPA	18.746	B	COULTERVILLE, JCT. RTE. 49	830	33	4.00	16	10	2	5	49.60	29.70	4.80	15.90	3	93E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
133	12	ORA	0	A	LAGUNA BEACH, JCT. RTE. 1, PACIFIC COAST HIGHWAY	19,000	648	3.41	455	113	29	52	70.14	17.43	4.43	8.00	49	98E
133	12	ORA	3.416	B	LAGUNA BEACH, EL TORO ROAD	36,000	410	1.14	260	100	20	30	63.41	24.39	4.88	7.32	32	00E
133	12	ORA	3.416	A	LAGUNA BEACH, EL TORO ROAD	17,500	431	2.46	256	111	21	43	59.41	25.74	4.95	9.90	37	00E
133	12	ORA	8.376	B	JCT. RTE. 405, SAN DIEGO FREEWAY	34,500	1,297	3.76	885	243	79	89	68.26	18.76	6.10	6.88	96	00E
133	12	ORA	8.376	A	JCT. RTE. 405, SAN DIEGO FREEWAY	32,000	1,450	4.53	856	288	75	232	59.00	19.83	5.17	16.00	148	00E
133	12	ORA	11.897	B	IRVINE BOULEVARD	45,400	1,448	3.19	793	317	190	148	54.74	21.90	13.14	10.22	136	01E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
134	07	LA	0	A	LOS ANGELES, JCT. RTES. 101/170, VENTURA/HOLLYWOOD FREEWAYS INTERCHANGE	187,000	8,022	4.29	4,934	858	476	1,754	61.50	10.70	5.93	21.87	927	10E
134	07	LA	1.359	O	FORMAN AVENUE	212,000	8,120	3.83	4,994	869	482	1,776	61.50	10.70	5.93	21.87	938	10V
134	07	LA	R 5.47	B	LOS ANGELES, JCT. RTE. 5, GOLDEN STATE FREEWAY INTERCHANGE	192,000	7,795	4.06	4,794	834	462	1,705	61.50	10.70	5.93	21.87	901	10E
134	07	LA	R 5.47	A	LOS ANGELES, JCT. RTE. 5, GOLDEN STATE FREEWAY INTERCHANGE	227,000	7,922	3.49	3,963	732	442	2,785	50.03	9.24	5.58	35.15	1,232	10E
134	07	LA	R 8.963	B	GLENDALE, JCT. RTE. 2, GLENDALE FREEWAY INTERCHANGE	226,000	7,887	3.49	3,946	729	440	2,772	50.03	9.24	5.58	35.15	1,226	10E
134	07	LA	R 8.963	A	GLENDALE, JCT. RTE. 2, GLENDALE FREEWAY INTERCHANGE	203,000	5,014	2.47	2,175	782	256	1,801	43.37	15.60	5.10	35.92	807	10E
134	07	LA	R 12.36	B	PASADENA, SAN RAFAEL AVENUE INTERCHANGE	213,000	4,856	2.28	2,106	758	248	1,744	43.37	15.60	5.10	35.92	782	10V
134	07	LA	R 13.341	B	PASADENA, JCT. RTES. 210/710, FOOTHILL/LONG BEACH FREEWAYS INTERCHANGE	206,000	4,903	2.38	2,126	765	250	1,761	43.37	15.60	5.10	35.92	789	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
135	05	SB	0	A	LOS ALAMOS, JCT. RTE. 101	4,000	205	5.13	95	23	12	75	46.34	11.22	5.85	36.59	33	10E
135	05	SB	9.095	B	CABRILLO HIGHWAY, JUNCTION OLD ROUTE 1	1,700	173	10.20	57	31	15	70	32.90	18.10	8.40	40.60	31	10E
135	05	SB	M 11.722	B	SOUTH JCT. RTE. 1	3,100	207	6.67	98	21	12	76	47.27	10.00	5.91	36.82	33	10E
135	05	SB	R 9.1	A	ORCUTT, NORTH JCT. RTE. 1	13,000	309	2.38	113	47	63	86	36.57	15.21	20.39	27.83	47	10E
135	05	SB	15.772	B	SANTA MARIA, JCT. RTE. 166, MAIN STREET	24,000	960	4.00	578	122	50	210	60.20	12.70	5.20	21.90	111	10E
135	05	SB	15.772	A	SANTA MARIA, JCT. RTE. 166, MAIN STREET	20,900	836	4.00	503	106	43	184	60.20	12.70	5.10	22.00	97	10E
135	05	SB	17.806	B	SANTA MARIA, JCT. RTE. 101	19,900	836	4.20	498	110	43	186	59.60	13.10	5.10	22.20	98	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
136	09	INY	0	A	JCT. RTE. 395	600	14	2.40	6	6	0	2	43.80	43.70	0.00	12.50	1	97V
136	09	INY	17.73	B	JCT. RTE. 190	470	12	2.55	5	3	3	1	44.00	22.00	22.00	12.00	1	03V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
137	06	KIN	0	A	JCT. RTE. 43	2,600	249	9.58	102	54	19	74	40.96	21.69	7.63	29.72	37	08V
137	06	TUL	7.2	B	ROAD 228	3,050	309	10.13	150	44	22	93	48.54	14.24	7.12	30.10	45	08V
137	06	TUL	7.2	A	ROAD 228	2,100	156	7.43	79	23	12	42	50.64	14.74	7.69	26.92	21	08V
137	06	TUL	14.26	B	TULARE, SOUTH WEST STREET	5,000	357	7.14	164	73	26	94	45.94	20.45	7.28	26.33	49	08V
137	06	TUL	14.26	A	TULARE, SOUTH WEST STREET	6,700	1,139	17.00	1,002	34	23	80	88.00	3.00	2.00	7.00	69	04E
137	06	TUL	R 15.78	B	TULARE, M STREET	5,600	560	10.00	375	56	11	118	67.00	10.00	2.00	21.00	61	03E
137	06	TUL	16.628	B	TULARE, JCT. RTE. 99	25,000	3,000	12.00	1,740	150	60	1,050	58.00	5.00	2.00	35.00	446	01E
137	06	TUL	17.511	B	TULARE, JCT. RTE. 63 NORTH	15,000	1,800	12.00	990	126	18	666	55.00	7.00	1.00	37.00	279	01E
137	06	TUL	17.511	A	TULARE, JCT. RTE. 63 NORTH	10,500	2,205	21.00	1,499	110	66	529	68.00	5.00	3.00	24.00	255	04E
137	06	TUL	27.396	B	JCT. RTE. 65	10,100	2,121	21.00	1,442	106	64	509	68.00	5.00	3.00	24.00	245	01E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
138	07	LA	0	A	JCT. RTE. 5, GOLDEN STATE FREEWAY INTERCHANGE	3,600	741	20.57	50	40	17	633	6.78	5.42	2.35	85.45	226	03E
138	07	LA	36.874	B	JCT. RTE. 14 NORTH, ANTELOPE VALLEY FREEWAY	3,750	529	14.10	36	33	13	448	6.84	6.15	2.39	84.62	161	02V
138	07	LA	43.418	A	PALMDALE, JCT. RTE. 14 SOUTH, ANTELOPE VALLEY FREEWAY	31,000	1,671	5.39	902	319	107	343	53.96	19.11	6.39	20.54	195	03V
138	07	LA	48.59	B	PALMDALE, 47TH STREET EAST	19,900	884	4.44	365	147	109	263	41.25	16.58	12.38	29.79	133	03V
138	07	LA	51.41	B	PALMDALE, PEARLBLOSSOM HIGHWAY/AVENUE T	14,200	1,008	7.10	202	163	78	565	20.01	16.15	7.74	56.10	228	03V
138	07	LA	51.41	A	PALMDALE, PEARLBLOSSOM HIGHWAY/AVENUE T	16,500	1,541	9.34	716	378	150	297	46.45	24.50	9.76	19.29	184	02V
138	07	LA	69.3	B	JCT. RTE. 18, PALMDALE ROAD	13,200	1,266	9.59	451	169	121	526	35.61	13.31	9.57	41.51	231	02E
138	07	LA	69.3	A	JCT. RTE. 18, PALMDALE ROAD	9,100	866	9.52	314	116	74	362	36.30	13.36	8.56	41.78	157	02V
138	07	LA	74.973	O	LOS ANGELES/SAN BERNARDINO COUNTY LINE	9,900	942	9.52	342	126	81	394	36.30	13.36	8.56	41.78	171	02E
138	08	SBD	0	O	LOS ANGELES/SAN BERNARDINO COUNTY LINE	9,900	942	9.52	342	126	81	394	36.30	13.36	8.56	41.78	171	02E
138	08	SBD	6.662	B	JCT. RTE. 2 WEST	18,000	2,484	13.80	1,138	82	50	1,215	45.80	3.30	2.00	48.90	474	93E
138	08	SBD	R 15.203	B	JCT. RTE. 15	17,500	1,855	10.60	1,072	70	37	675	57.80	3.80	2.00	36.40	282	92V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
138	08	SBD	R 15.203	A	JCT. RTE. 15	4,400	568	12.90	500	56	11	0	88.10	9.90	2.00	0.00	24	88E
138	08	SBD	R 23.959	A	JCT. RTE. 173 EAST	1,650	210	12.70	176	21	9	4	83.70	10.20	4.10	2.00	11	88E
138	08	SBD	R 37.848	B	JCT. RTE. 18	7,500	413	5.50	391	8	8	6	94.60	2.00	1.90	1.50	18	88E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
139	02	LAS	0	A	SUSANVILLE, JCT. RTE. 36	6,700	88	1.31	17	38	7	26	19.02	43.48	8.15	29.35	14	10E
139	02	LAS	1.42	B	LASSEN COLLEGE	4,100	65	1.58	15	20	6	25	22.73	30.30	9.09	37.88	12	10E
139	02	LAS	2.34	B	SUSANVILLE DUMP	790	50	6.33	9	7	3	31	18.00	14.00	6.00	61.99	12	10V
139	02	LAS	2.34	A	SUSANVILLE DUMP	520	42	8.08	9	8	4	21	21.43	19.05	9.52	50.00	9	10V
139	02	LAS	61.46	B	COUNTY ROAD A-2	540	42	7.77	9	8	4	21	21.62	18.75	9.29	50.34	9	10V
139	02	LAS	61.46	A	COUNTY ROAD A-2	470	32	6.73	13	3	2	14	40.96	9.96	5.90	43.18	6	10E
139	02	MOD	0.23	B	ADIN, SOUTH JCT RTE 299	450	32	7.06	13	3	2	14	40.96	9.96	5.90	43.18	6	10E
139	02	MOD	17.35	A	LOOKOUT/HACKMORE ROADS	1,250	312	24.96	16	45	10	241	5.09	14.44	3.13	77.34	89	10E
139	02	MOD	44.505	B	NEWELL	2,100	376	17.91	42	48	21	265	11.17	12.66	5.71	70.47	100	10E
139	02	SIS	0	A	MODOC/SISKIYOU COUNTY LINE	2,300	411	17.89	46	52	23	290	11.17	12.66	5.71	70.47	110	10E
139	02	SIS	1.04	O	TULELAKE, EAST/WEST ROADS	2,600	472	18.14	50	47	18	357	10.54	9.89	3.87	75.70	132	10E
139	02	SIS	5.043	B	OREGON STATE LINE, JCT. RTE. 161 WEST	2,600	476	18.29	49	59	30	338	10.36	12.35	6.37	70.92	128	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
140	10	MER	0	A	JCT. RTE. 5	930	115	12.40	25	20	7	62	21.90	17.70	6.20	54.20	25	97E
140	10	MER	4.194	B	GUSTINE, WEST JCT. RTE. 33	1,600	200	12.50	44	34	12	110	21.90	17.10	6.00	55.00	44	97E
140	10	MER	4.353	A	GUSTINE, WEST JCT. RTE. 33	5,200	728	14.00	124	58	36	510	17.00	8.00	5.00	70.00	191	98V
140	10	MER	6.06	A	GUSTINE, EAST JCT. RTE. 33	3,250	387	11.90	94	57	22	215	24.20	14.60	5.60	55.60	86	97E
140	10	MER	16.22	B	JCT. RTE. 165	3,250	341	10.50	93	65	14	168	27.40	19.20	4.00	49.40	69	97E
140	10	MER	16.22	A	JCT. RTE. 165	3,100	360	11.60	50	70	10	230	13.80	19.40	2.80	64.00	89	97V
140	10	MER	35.78	B	MERCED, JCT. RTES. 99/59	14,400	576	4.00	86	132	109	248	15.00	23.00	19.00	43.00	117	98V
140	10	MER	35.79	A	MERCED, JCT. RTES. 99/59	14,700	882	6.00	194	247	168	273	22.00	28.00	19.00	31.00	148	98V
140	10	MER	37.4	B	MERCED, SANTA FE AVENUE	10,400	374	3.60	98	168	29	80	26.10	44.90	7.70	21.30	51	97V
140	10	MER	43.7	A	PLANADA ROAD	6,200	682	11.00	43	203	25	412	6.30	29.70	3.60	60.40	166	97V
140	10	MPA	9.5	B	HORNITOS ROAD	4,900	230	4.70	35	70	9	116	15.00	30.60	4.00	50.40	49	97V
140	10	MPA	21.224	B	MARIPOSA, SOUTH JCT. RTE. 49	5,000	139	2.78	46	49	8	36	33.30	35.00	5.70	26.00	20	97V
140	10	MPA	21.224	A	MARIPOSA, SOUTH JCT. RTE. 49	10,600	253	2.39	75	107	14	57	29.60	42.30	5.50	22.60	34	97V
140	10	MPA	22.001	B	MARIPOSA, JCT RTE 49 NORTH	8,300	323	3.89	84	106	20	113	26.10	32.70	6.30	34.90	55	97V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
140	10	MPA	22.001	A	MARIPOSA, JCT RTE 49 NORTH	4,700	212	4.50	52	94	16	50	24.40	44.40	7.70	23.50	30	97V
140	10	MPA	34.07	B	BRICEBURG STATION	1,250	139	11.10	20	35	2	81	14.60	25.30	1.70	58.40	32	97V
140	10	MPA	51.803	B	YOSEMITE NATIONAL PARK	1,400	71	5.10	12	36	2	21	17.50	50.00	3.30	29.20	11	97V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
142	12	ORA	R .753	A	JCT. RTE. 90, IMPERIAL HIGHWAY	10,500	977	9.30	591	132	106	149	60.50	13.50	10.80	15.20	100	79E
142	12	ORA	6.35	B	ORANGE/SAN BERNARDINO COUNTY LINE	14,700	118	0.80	101	17	0	0	85.90	14.10	0.00	0.00	5	79E
142	08	SBD	5.782	B	JCT. RTE. 71	37,000	3,330	9.00	2,764	233	63	270	83.00	7.00	1.90	8.10	221	77V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
144	05	SB	1.953	B	SANTA BARBARA, JCT. RTE. 192	3,300	33	1.00	30	1	0	1	91.50	4.30	0.00	4.20	1	03E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
145	06	FRE	0	A	JCT. RTES. 5 AND 33	2,650	663	25.00	259	20	13	371	39.00	3.00	2.00	56.00	141	04E
145	06	FRE	13.212	B	JCT. RTE. 269	3,350	955	28.51	300	118	76	461	31.41	12.36	7.96	48.27	192	10E
145	06	FRE	35.149	A	KERMAN, JCT. RTE. 180	9,400	1,410	15.00	832	56	28	494	59.00	4.00	2.00	35.00	209	04E
145	06	MAD	9.077	B	MADERA, JCT. RTE. 99	13,200	1,056	8.00	211	63	32	750	20.00	6.00	3.00	71.00	277	01E
145	06	MAD	11.02	B	MADERA, TOZER STREET	12,500	875	7.00	683	105	53	35	78.00	12.00	6.00	4.00	53	01E
145	06	MAD	11.02	A	MADERA, TOZER STREET	8,200	656	8.00	485	66	26	79	74.00	10.00	4.00	12.00	54	01E
145	06	MAD	25.459	B	JCT. RTE. 41	5,300	484	9.13	211	148	63	62	43.60	30.58	13.02	12.81	52	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
146	05	MON	3.48	B	METZ ROAD	3,000	450	15.00	158	149	0	143	35.10	33.10	0.00	31.80	69	03E
146	05	MON	3.48	A	METZ ROAD	260	9	3.64	9	0	0	0	100.00	0.00	0.00	0.00	0	03E
146	05	SBT	15.152	B	JCT. RTE. 25	250	6	2.50	4	2	0	0	66.70	33.30	0.00	0.00	0	03E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
147	02	PLU	0	A	CANYON DAM, JCT. RTE. 89	820	50	6.10	16	12	2	20	32.00	24.00	4.00	40.00	9	10V
147	02	PLU	7.37	B	BIG SPRINGS ROAD	1,200	50	4.17	11	9	2	28	22.00	18.00	4.00	56.00	11	10V
147	02	PLU	9.891	B	PLUMAS/LASSEN COUNTY LINE	1,400	140	10.00	38	32	4	66	27.00	23.00	3.00	47.00	28	10E
147	02	LAS	1.14	A	COUNTY ROAD A-21	820	50	6.10	11	9	2	28	22.00	18.00	4.00	56.00	11	10V
147	02	LAS	1.79	B	JCT. RTE. 36	820	50	6.10	11	9	2	28	22.00	18.00	4.00	56.00	11	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
149	03	BUT	0	A	JCT. RTE. 70	15,300	964	6.30	334	257	174	200	34.60	26.70	18.00	20.70	130	97V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
150	05	SB	R0	A	CARPINTERIA, JCT. RTE. 101	4,400	313	7.11	223	34	40	16	71.11	10.85	12.85	5.19	22	10V
150	05	SB	1.667	B	JCT. RTE. 192 WEST	3,100	279	9.00	193	54	17	15	69.20	19.30	6.20	5.30	19	10E
150	05	SB	1.667	A	JCT. RTE. 192 WEST	2,700	133	4.93	99	17	9	8	74.32	12.84	6.76	6.08	9	10E
150	05	SB	2.197	O	SANTA BARBARA/VENTURA COUNTY LINE	2,700	54	2.00	31	12	6	6	56.90	22.41	10.34	10.34	5	02V
150	07	VEN	0	O	SANTA BARBARA/VENTURA COUNTY LINE	2,700	54	2.00	31	12	6	6	56.90	22.41	10.34	10.34	5	02V
150	07	VEN	R 14.406	B	JCT. RTE. 33 SOUTH, VENTURA AVENUE	10,300	199	1.93	103	54	34	8	51.76	27.14	17.09	4.02	16	02V
150	07	VEN	R 14.406	A	JCT. RTE. 33 SOUTH, VENTURA AVENUE	20,100	376	1.87	144	61	23	148	38.18	16.31	6.14	39.37	65	03E
150	07	VEN	16.577	B	OJAI, JCT. RTE. 33 NORTH, MARICOPA HIGHWAY	18,400	403	2.19	154	66	25	159	38.18	16.31	6.14	39.37	70	03V
150	07	VEN	16.577	A	OJAI, JCT. RTE. 33 NORTH, MARICOPA HIGHWAY	22,600	719	3.18	333	193	156	37	46.34	26.83	21.74	5.09	65	03V
150	07	VEN	18.86	O	OJAI EAST CITY LIMITS	7,200	104	1.44	55	21	6	22	52.75	19.90	6.16	21.19	12	03V
150	07	VEN	31.95	O	SANTA PAULA, NORTH CITY LIMIT	3,750	143	3.81	54	27	24	38	38.10	18.62	16.70	26.58	21	03V
150	07	VEN	34.398	B	SANTA PAULA, JCT. RTE. 126, SANTA PAULA FREEWAY	15,600	451	2.89	183	109	64	95	40.55	24.10	14.29	21.06	59	03V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
151	02	SHA	0	A	SHASTA DAM	310	26	8.29	22	3	1	0	86.21	10.34	3.45	0.00	1	10E
151	02	SHA	3.781	A	LAKE BOULEVARD	1,800	53	2.94	33	3	2	15	62.26	5.66	3.77	28.30	7	10E
151	02	SHA	4.45	A	TOYON	2,500	145	5.78	50	22	17	56	34.62	15.38	11.54	38.46	26	10E
151	02	SHA	5.62	B	BEGIN COUPLET AT ASHBY ROAD	5,400	88	1.63	26	17	15	30	29.20	19.58	17.52	33.71	15	10E
151	02	SHA	5.993	A	ON SHASTA DAM BOULEVARD; DIVIDED HIGHWAY FACILITY	9,400	218	2.32	86	49	15	68	39.45	22.48	6.88	31.19	33	10E
151	02	SHA	R 6.924	B	JCT. RTE. 5, PROJECT CITY	13,200	218	1.65	86	49	15	68	39.45	22.48	6.88	31.19	33	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
152	05	SCR	T.31	A	WATSONVILLE, JCT. RTE. 1	27,000	945	3.50	758	143	2	43	80.20	15.10	0.20	4.50	55	03E
152	05	SCR	0.714	A	BECK AVENUE	15,000	510	3.40	433	58	5	14	84.90	11.40	0.90	2.80	26	03E
152	05	SCR	R 1.995	B	HOLOHAN/COLLEGE ROADS	15,000	705	4.70	627	47	6	25	88.90	6.60	0.90	3.60	36	03E
152	04	SCL	5.03	B	WATSONVILLE RD	6,100	262	4.30	220	17	6	19	83.90	6.60	2.30	7.20	17	98E
152	04	SCL	9.43	B	MONTEREY STREET	16,400	510	3.11	336	62	29	83	65.87	12.11	5.69	16.33	50	01V
152	04	SCL	M 10.277	B	GILROY, JCT. RTE. 101	36,500	2,526	6.92	1,551	265	159	551	61.39	10.51	6.30	21.80	292	01V
152	04	SCL	R 9.914	A	GILROY, JCT. RTE. 101	23,200	2,160	9.31	577	173	52	1,358	26.71	8.00	2.40	62.89	512	01V
152	04	SCL	12.81	B	FERGUSON ROAD	18,200	1,966	10.80	267	132	43	1,524	13.60	6.70	2.20	77.50	554	98E
152	04	SCL	12.81	A	FERGUSON ROAD	22,400	3,069	13.70	460	193	89	2,326	15.00	6.30	2.90	75.80	849	98E
152	04	SCL	R 21.977	B	JCT. RTE. 156 SOUTH	20,100	2,418	12.03	357	57	37	1,965	14.76	2.37	1.53	81.26	701	98V
152	04	SCL	R 21.977	A	JCT. RTE. 156 SOUTH	32,500	5,532	17.02	875	147	105	4,405	15.81	2.65	1.89	79.63	1,579	98V
152	04	SCL	R 26.77	O	PACHECO CREEK BRIDGE	33,500	5,327	15.90	810	298	176	4,043	15.20	5.60	3.30	75.90	1,476	96V
152	10	MER	13.848	A	JCT. RTE. 5	25,500	4,335	17.00	915	407	221	2,792	21.10	9.40	5.10	64.40	1,065	97E
152	10	MER	21.272	B	LOS BANOS, JCT. RTE. 165	26,500	2,639	9.96	844	157	69	1,570	31.97	5.95	2.60	59.48	596	03V
152	10	MER	21.272	A	LOS BANOS, JCT. RTE. 165	32,000	2,886	9.02	1,105	115	55	1,610	38.30	4.00	1.90	55.80	613	07V
152	10	MER	R 32.366	B	DOS PALOS WYE, EAST JCT. RTE. 33	17,500	2,730	15.60	620	289	55	1,766	22.70	10.60	2.00	64.70	666	95E
152	10	MER	R 32.366	A	DOS PALOS WYE, EAST JCT. RTE. 33	16,400	2,132	13.00	192	192	149	1,599	9.00	9.00	7.00	75.00	598	98V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
152	06	MAD	R 0	A	MERCED/MADERA COUNTY LINE	15,400	3,234	21.00	647	291	194	2,102	20.00	9.00	6.00	65.00	803	04E
152	06	MAD	10.799	B	JCT. RTE. 233 NORTHWEST	16,500	3,960	24.00	792	356	238	2,574	20.00	9.00	6.00	65.00	983	04E
152	06	MAD	10.799	A	JCT. RTE. 233 NORTHWEST	15,500	3,720	24.00	1,079	186	112	2,344	29.00	5.00	3.00	63.00	880	04E
152	06	MAD	15.634	B	CALIFA, JCT. RTE. 99	17,000	4,080	24.00	1,183	204	122	2,570	29.00	5.00	3.00	63.00	965	04E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
153	03	ED	0	A	JCT. RTE. 49	2,400	85	3.54	49	18	12	6	57.14	21.43	14.29	7.14	7	06E
153	03	ED	0.55	B	MARSHALL'S MONUMENT	110	4	3.54	2	1	1	0	57.14	21.43	14.29	7.14	0	06E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
154	05	SB	R 8.11	B	JCT. RTE. 246 WEST	6,100	433	7.10	273	68	13	78	63.00	15.80	3.10	18.10	45	10E
154	05	SB	R 8.11	A	JCT. RTE. 246 WEST	11,100	555	5.00	395	90	17	53	71.10	16.30	3.00	9.60	43	10E
154	05	SB	23.38	B	STAGECOACH ROAD	13,000	598	4.60	493	42	18	45	82.40	7.10	3.00	7.50	39	10E
154	05	SB	R 31.551	B	JCT. RTE. 192 EAST	16,000	496	3.10	400	48	12	36	80.60	9.70	2.50	7.20	33	10E
154	05	SB	R 31.551	A	JCT. RTE. 192 EAST	15,800	506	3.20	424	41	13	27	83.80	8.20	2.60	5.40	30	10E
154	05	SB	32.285	B	JCT. RTE. 101	15,800	823	5.21	414	131	114	164	50.30	15.97	13.83	19.90	100	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
155	06	KER	0	A	DELANO ON ELLINGTON STREET AT 9th AVENUE AND THE OFF/ON RAMPS FOR SOUTHBOUND ROUTE 99	5,300	265	5.00	130	24	13	98	49.00	9.00	5.00	37.00	42	04E
155	06	KER	R 0	A	DELANO, JCT. RTE. 99	11,500	805	7.00	636	24	8	137	79.00	3.00	1.00	17.00	73	06E
155	06	KER	R 10.99	B	JCT. RTE. 65	380	84	22.00	31	10	6	38	36.36	11.36	6.82	45.45	16	06V
155	06	KER	R 10.99	A	JCT. RTE. 65	180	45	25.00	17	6	5	18	36.67	13.33	10.00	40.00	8	06V
155	06	KER	30.313	A	JUNCTION OLD ROUTE 155 AT WOODY ROAD	180	43	23.75	37	2	2	1	86.84	5.26	5.26	2.63	2	06E
155	06	KER	38.25	A	GLENVILLE, GRANITE ROAD	260	126	48.33	109	7	4	7	86.21	5.17	3.45	5.17	7	06E
155	06	KER	R 60.637	B	WOFFORD BOULEVARD	1,900	86	4.50	63	13	6	4	73.33	15.56	6.67	4.44	6	06E
155	06	KER	R 60.637	A	WOFFORD BOULEVARD	6,300	654	10.38	425	102	79	47	65.06	15.66	12.05	7.23	52	06E
155	06	KER	R 70.991	B	JCT. RTE. 178	6,000	755	12.58	491	118	91	55	65.06	15.66	12.05	7.23	60	06E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
156	05	MON	R .167	A	JCT. RTE. 1	31,000	2,604	8.40	979	227	76	1,323	37.60	8.70	2.90	50.80	523	03E
156	05	MON	R 1.109	A	JCT. RTE. 183	29,600	2,368	8.00	947	225	76	1,120	40.00	9.50	3.20	47.30	451	03E
156	05	MON	T 5.185	B	SOUTH JCT. RTE. 101	28,000	2,380	8.50	957	221	81	1,121	40.20	9.30	3.40	47.10	452	03E
156	05	SBT	3.022	A	ALAMEDA STREET	23,300	3,309	14.20	1,046	268	169	1,827	31.60	8.10	5.10	55.20	716	97E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
158	09	MNO	0	A	JUNE LAKE JUNCTION, SOUTH JCT. RTE. 395	1,600	27	1.66	7	9	9	3	26.00	32.00	32.00	10.00	3	03V
158	09	MNO	3.81	O	SKI LIFT ROAD	1,700	26	1.50	17	2	0	7	66.70	8.30	0.00	25.00	3	97V
158	09	MNO	15.836	B	GRANT LAKE JUNCTION, NORTH JCT. RTE. 395	400	10	2.52	3	3	3	3	25.00	25.00	25.00	25.00	2	03V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
160	04	CC	0	A	ANTIOCH, JCT. RTE. 4 EAST	10,100	1,324	13.11	294	265	179	586	22.22	20.04	13.51	44.23	263	00V
160	04	CC	0.486	A	WILBUR AVENUE	12,300	802	6.52	280	89	34	399	34.86	11.12	4.20	49.81	161	00V
160	04	CC	1.327	B	CONTRA COSTA/SACRAMENTO COUNTY LINE	12,300	1,353	11.00	354	99	23	877	26.20	7.30	1.70	64.80	327	97E
160	03	SAC	L 10.783	B	JCT. RTE. 12	15,000	1,395	9.30	251	177	45	922	18.00	12.70	3.20	66.10	350	95V
160	03	SAC	R 0	A	JCT. RTE. 12	5,400	400	7.41	68	125	113	94	16.89	31.37	28.15	23.59	63	05E
160	03	SAC	5.95	B	SACRAMENTO RIVER, ISLETON BRIDGE	3,950	378	9.56	64	119	106	89	16.89	31.37	28.15	23.59	59	05E
160	03	SAC	5.95	A	SACRAMENTO RIVER, ISLETON BRIDGE	2,200	107	4.86	43	19	12	33	40.44	17.65	11.03	30.88	16	05V
160	03	SAC	11.46	B	RYDE, JCT. RTE. 220 WEST	2,150	135	6.30	34	26	5	70	25.00	19.40	4.00	51.60	28	95V
160	03	SAC	11.46	A	RYDE, JCT. RTE. 220 WEST	2,550	144	5.63	73	17	11	42	50.82	12.02	7.65	29.51	20	05V
160	03	SAC	14.16	B	WALNUT GROVE, WALNUT GROVE BRIDGE	3,100	226	7.30	43	46	10	127	18.90	20.20	4.60	56.30	51	95V
160	03	SAC	14.16	A	WALNUT GROVE, WALNUT GROVE BRIDGE	2,750	201	7.30	36	42	10	113	17.80	21.00	4.80	56.40	46	95V
160	03	SAC	16.92	B	LEARY ROAD	1,600	126	7.90	18	20	5	84	14.00	16.00	3.70	66.30	32	95V
160	03	SAC	16.92	A	LEARY ROAD	1,500	110	7.30	13	17	4	77	11.70	15.00	3.20	70.10	29	95V
160	03	SAC	34.07	A	FREEPORT BRIDGE ROAD	6,400	192	3.00	89	56	27	19	46.50	29.30	14.10	10.10	19	96E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
160	03	SAC	46.581	B	SACRAMENTO, JCT. RTE. 51	34,500	2,070	6.00	1,499	339	60	172	72.40	16.40	2.90	8.30	152	84E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
161	02	SIS	0.037	A	JCT. RTE. 97	570	201	35.25	6	6	2	187	3.17	3.17	0.76	92.91	66	10E
161	02	SIS	17.31	B	HILL ROAD	740	234	31.65	13	9	2	210	5.47	3.92	1.01	89.61	74	10E
161	02	SIS	19.361	B	JCT. RTE. 139	1,000	280	28.04	22	13	4	242	7.76	4.67	1.25	86.32	86	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
162	01	MEN	R 0	A	JCT. RTE. 101	850	113	13.33	57	19	9	28	50.00	16.67	8.33	25.00	15	06E
162	01	MEN	34.045	B	NEAR SHORT CREEK BRIDGE	400	48	12.00	34	6	0	8	71.00	12.90	0.00	16.10	5	91E
162	03	GLE	37.648	A	COUNTY ROAD 307	200	20	10.00	8	1	1	10	40.00	5.00	5.00	50.00	4	07E
162	03	GLE	65.523	B	WILLOWS, JCT. RTE. 5	8,800	390	4.43	226	50	31	82	58.06	12.90	8.06	20.97	45	00E
162	03	GLE	65.523	A	WILLOWS, JCT. RTE. 5	8,700	355	4.08	206	46	29	74	58.06	12.90	8.06	20.97	41	00E
162	03	GLE	67.106	A	WILLOWS, FIRST STREET	2,900	261	9.00	104	23	17	116	40.00	8.89	6.67	44.47	48	00E
162	03	GLE	76.27	B	JCT. RTE. 45	2,150	215	10.00	91	23	11	91	42.11	10.53	5.26	42.11	38	00E
162	03	GLE	76.28	A	JCT. RTE. 45	2,400	482	20.10	65	36	12	369	13.43	7.46	2.49	76.62	135	07E
162	03	BUT	6.66	B	RICHVALE SOUTH HIGHWAY	1,500	302	20.10	41	23	8	231	13.43	7.46	2.49	76.62	84	07E
162	03	BUT	6.66	A	RICHVALE SOUTH HIGHWAY	860	173	20.10	23	13	4	133	13.43	7.46	2.49	76.62	48	07E
162	03	BUT	9.726	B	JCT. RTE. 99	860	173	20.10	23	13	4	133	13.43	7.46	2.49	76.62	48	07E
162	03	BUT	R 9.726	A	JCT. RTE. 99	2,800	273	9.74	121	57	44	51	44.49	20.91	15.97	18.63	34	00E
162	03	BUT	15.831	B	OROVILLE, JCT. RTE. 70	13,200	1,209	9.16	247	432	370	160	20.41	35.71	30.61	13.27	158	00E
162	03	BUT	17.142	B	OROVILLE, LINCOLN STREET	32,000	3,200	10.00	1,920	704	64	512	60.00	22.00	2.00	16.00	318	83E
162	03	BUT	18.006	A	OROVILLE, LOWER WYANDOTE ROAD	20,900	857	4.10	434	212	37	175	50.60	24.70	4.30	20.40	101	85V
162	03	BUT	24.194	B	FORBESTOWN ROAD	4,550	455	10.00	273	100	9	73	60.00	22.00	2.00	16.00	45	83E
162	03	BUT	24.194	A	FORBESTOWN ROAD	1,850	185	10.00	111	39	7	28	60.00	21.10	3.80	15.10	18	83E
162	03	BUT	31.07	B	FOREMAN ROAD	1,500	150	10.00	90	31	6	23	60.00	20.70	4.00	15.30	15	83E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
163	11	SD	0.89	A	JCT. RTE. 5	110,000	3,300	3.00	2,389	409	69	432	72.40	12.40	2.10	13.10	280	86V
163	11	SD	3.742	B	SAN DIEGO, JCT. RTE. 8	161,000	4,830	3.00	3,497	599	101	633	72.40	12.40	2.10	13.10	411	86E
163	11	SD	3.742	A	SAN DIEGO, JCT. RTE. 8	151,000	5,587	3.70	3,598	860	140	989	64.40	15.40	2.50	17.70	567	86V
163	11	SD	7.043	B	SAN DIEGO, JCT. RTE. 805	163,000	6,031	3.70	3,884	929	151	1,067	64.40	15.40	2.50	17.70	612	86E
163	11	SD	7.043	A	SAN DIEGO, JCT. RTE. 805	140,000	7,140	5.10	3,941	1,100	243	1,856	55.20	15.40	3.40	26.00	915	86E
163	11	SD	8.01	A	SAN DIEGO, BALBOA AVENUE	139,000	3,934	2.83	2,041	650	380	863	51.89	16.51	9.67	21.93	485	04E
163	11	SD	R 10.837	B	SAN DIEGO, KEARNEY VILLA ROAD INTERCHANGE	135,619	4,380	3.23	3,158	392	196	633	72.11	8.95	4.48	14.46	394	10V
163	11	SD	R 11.662	B	JCT. RTE. 15	118,000	3,729	3.16	1,935	616	361	818	51.88	16.51	9.67	21.93	460	04E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
164	07	LA	3.341	B	JCT. RTE. 60, POMONA FREEWAY	25,500	1,627	6.38	932	235	46	415	57.26	14.44	2.81	25.49	204	06V
164	07	LA	3.341	A	JCT. RTE. 60, POMONA FREEWAY	45,000	3,411	7.58	2,501	314	115	480	73.33	9.22	3.37	14.08	299	06V
164	07	LA	5.599	B	EL MONTE, JCT. RTE. 10, SAN BERNARDINO FREEWAY	76,000	3,397	4.47	2,236	438	124	599	65.81	12.90	3.65	17.64	343	06V
164	07	LA	5.599	A	EL MONTE, JCT. RTE. 10, SAN BERNARDINO FREEWAY	52,000	1,742	3.35	1,339	183	55	165	76.87	10.49	3.17	9.47	129	06V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
165	10	MER	L0	A	JCT. RTE. 5	1,750	165	9.40	16	41	10	99	9.50	24.80	5.80	59.90	40	97V
165	10	MER	8.786	B	LOS BANOS, JCT. RTE. 152	12,000	948	7.90	91	129	21	707	9.60	13.60	2.20	74.60	262	97V
165	10	MER	8.786	A	LOS BANOS, JCT. RTE. 152	16,000	1,456	9.10	159	201	31	1,066	10.90	13.80	2.10	73.20	396	97V
165	10	MER	26.872	B	JCT. RTE. 140	5,300	413	7.79	50	65	14	284	12.00	15.80	3.40	68.80	108	97V
165	10	MER	26.872	A	JCT. RTE. 140	6,000	558	9.30	22	158	31	346	4.00	28.40	5.60	62.00	139	97V
165	10	STA	1.45	B	JCT. RTE. 99	18,800	921	4.90	86	133	20	682	9.30	14.40	2.20	74.10	253	97V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
166	05	SB	0	A	GUADALUPE, JCT. RTE. 1	9,300	986	10.60	396	65	40	485	40.16	6.59	4.06	49.19	193	10V
166	05	SB	6.87	B	SANTA MARIA, BLOSSER ROAD	8,700	957	11.00	416	123	41	376	43.50	12.90	4.30	39.30	162	10E
166	05	SB	6.87	A	SANTA MARIA, BLOSSER ROAD	15,300	1,025	6.70	483	160	36	346	47.10	15.60	3.50	33.80	156	10E
166	05	SB	7.87	A	SANTA MARIA, JCT. RTE. 135	22,000	1,430	6.50	435	194	63	738	30.40	13.60	4.40	51.60	297	10E
166	05	SB	8.927	B	SANTA MARIA, JCT. RTE. 101	22,000	748	3.40	198	71	56	423	26.42	9.43	7.55	56.60	168	10E
166	05	SLO	8.927	A	SANTA MARIA, JCT. RTE. 101	2,800	518	18.50	173	36	27	282	33.40	6.95	5.21	54.44	111	10V
166	05	SLO	13.511	A	SUEY ROAD	2,800	742	26.50	196	70	56	420	26.42	9.43	7.55	56.60	166	10E
166	05	SB	64.3	A	PERKINS ROAD	1,500	339	22.60	88	44	37	170	25.90	13.10	10.90	50.10	71	10E
166	05	SLO	74.718	B	MARICOPA, JCT. RTE. 33	3,300	792	24.00	165	31	9	587	20.83	3.94	1.16	74.07	212	06E
166	06	KER	0.01	A	MARICOPA, JCT. RTE. 33	2,500	600	24.00	125	24	7	444	20.83	3.94	1.16	74.07	161	06E
166	06	KER	2.96	A	PENTLAND ROAD	2,100	638	30.38	86	32	19	501	13.42	5.06	3.04	78.48	182	06E
166	06	KER	22.797	B	JCT. RTE. 5	2,000	467	23.33	93	33	20	320	20.00	7.14	4.29	68.57	120	06E
166	06	KER	24.62	B	METTLER, JCT. RTE. 99	3,000	462	15.41	37	18	11	397	8.02	3.82	2.29	85.88	142	06E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
167	09	MNO	0	A	JCT. RTE. 395	200	11	5.50	5	2	0	4	45.45	18.18	0.00	36.36	2	07V
167	09	MNO	21.331	B	NEVADA STATE LINE	130	7	5.00	2	0	0	5	25.00	0.00	0.00	75.00	2	07E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
168S	06	FRE	R .29	A	JCT RTE 180S, BEGIN FWY	73,000	2,416	3.31	1,680	290	122	324	69.53	11.99	5.07	13.41	215	04E
168S	06	FRE	R 4.258	A	SHAW AVENUE	56,000	2,856	5.10	1,046	636	451	723	36.62	22.28	15.80	25.30	411	10V
168S	06	FRE	R 8.042	B	FOWLER AVENUE	30,000	1,200	4.00	696	264	72	168	58.00	22.00	6.00	14.00	117	04V
168	06	FRE	15.47	B	ACADEMY AVENUE	6,000	600	10.00	516	42	24	18	86.00	7.00	4.00	3.00	32	04E
168	06	FRE	15.47	A	ACADEMY AVENUE	6,500	623	9.58	376	116	91	40	60.35	18.62	14.61	6.42	51	10V
168	06	FRE	R 36.179	B	AUBERRY ROAD	10,000	1,000	10.00	920	40	20	20	92.00	4.00	2.00	2.00	46	04E
168	06	FRE	R 36.179	A	AUBERRY ROAD	7,800	780	10.00	686	55	31	8	88.00	7.00	4.00	1.00	36	04E
168	06	FRE	49.66	B	HUNTINGTON LAKE ROAD	1,150	150	13.00	132	11	6	2	88.00	7.00	4.00	1.00	7	04E
168	06	FRE	49.66	A	HUNTINGTON LAKE ROAD	880	18	2.00	16	2	1	0	87.00	9.00	4.00	0.00	1	04E
168	06	FRE	65.84	B	FLORENCE LAKE ROAD	860	9	1.00	8	1	1	0	88.00	6.00	6.00	0.00	1	04E
168	09	INY	R0	A	LAKE SABRINA	400	4	1.00	3	1	0	0	75.00	25.00	0.00	0.00	0	07E
168	09	INY	R 3.278	B	SOUTH LAKE ROAD	400	10	2.50	5	5	0	0	50.00	50.00	0.00	0.00	1	07E
168	09	INY	R 3.278	A	SOUTH LAKE ROAD	550	13	2.33	9	1	3	0	68.75	6.25	25.00	0.00	1	07E
168	09	INY	14.74	B	OTEY ROAD	1,150	34	2.96	16	12	6	0	47.50	35.00	17.50	0.00	3	07V
168	09	INY	16.342	B	BROCKMAN LANE	6,400	254	3.97	191	36	8	19	75.00	14.10	3.30	7.60	18	07E
168	09	INY	16.342	A	BROCKMAN LANE	6,400	294	4.60	216	40	11	27	73.50	13.60	3.60	9.30	22	07V
168	09	INY	18.31	B	JCT. RTE. 395	8,200	440	5.36	344	57	18	22	78.11	13.00	4.00	4.89	28	07V
168	09	INY	18.32	A	JCT. RTE. 395	430	43	10.00	5	1	0	37	11.60	2.30	0.00	86.10	13	96V
168	09	MNO	1.45	B	OASIS, JCT. RTE. 266 NORTH	160	13	8.00	5	3	0	5	37.50	25.00	0.00	37.50	2	96E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
169	01	DN	R 0	A	KLAMATH, JCT. RTE. 101	1,900	162	8.50	49	57	3	54	30.00	35.30	1.60	33.10	26	91E
169	01	HUM	13.2	A	WAUTECK VILLAGE	200	40	20.00	32	5	0	3	79.55	13.64	0.00	6.82	3	91E
169	01	HUM	33.84	B	WEITCHPEC, JCT. RTE. 96	370	29	7.80	19	5	1	4	65.00	17.00	3.80	14.20	3	94V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
170	07	LA	4.5	B	LOS ANGELES, JCT. RTES. 101/134, VENTURA/HOLLYWOOD FREEWAYS INTERCHANGE	95,000	3,420	3.60	2,408	479	55	479	70.40	14.00	1.60	14.00	302	96E
170	07	LA	R 14.5	A	LOS ANGELES, JCT. RTES. 101/134, VENTURA/HOLLYWOOD FREEWAYS INTERCHANGE	169,000	5,712	3.38	3,809	727	187	989	66.69	12.73	3.28	17.31	569	10E
170	07	LA	R 17.62	O	S/O SHERMAN WAY; VAN OWEN ST	173,000	5,847	3.38	3,899	744	192	1,012	66.69	12.73	3.28	17.31	582	10V
170	07	LA	R 20.551	B	LOS ANGELES, JCT. RTE. 5, GOLDEN STATE FREEWAY INTERCHANGE	125,000	5,675	4.54	3,785	722	186	982	66.69	12.73	3.28	17.31	565	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
172	02	TEH	0	A	MINERAL, JCT. RTE. 36	150	3	1.76	2	1	0	0	66.67	33.33	0.00	0.00	0	10E
172	02	TEH	5.77	A	MILL CREEK	120	4	3.25	1	0	1	2	35.71	0.00	21.43	42.86	1	10E
172	02	TEH	8.917	B	MORGAN SPRINGS, JCT. RTE. 36	120	5	4.17	4	1	0	0	80.00	20.00	0.00	0.00	0	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
173	08	SBD	L 0	A	JCT. RTE. 138	1,050	43	4.10	28	8	6	2	64.00	18.00	14.00	4.00	3	85V
173	08	SBD	L 6.989	A	ARROWHEAD LAKE ROAD	130	52	40.00	52	0	0	0	100.00	0.00	0.00	0.00	2	79E
173	08	SBD	21.462	B	LAKE ARROWHEAD, JCT. RTE. 189 AT ARROWHEAD VILLAGE ROAD	9,000	540	6.00	474	46	0	20	87.80	8.50	0.00	3.70	28	89V
173	08	SBD	21.462	A	LAKE ARROWHEAD, JCT. RTE. 189 AT ARROWHEAD VILLAGE ROAD	4,300	430	10.00	347	41	0	41	80.80	9.60	0.00	9.60	30	86V
173	08	SBD	23.04	B	JCT. RTE. 18	5,400	216	4.00	169	27	7	13	78.30	12.30	3.30	6.10	14	86E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
174	03	PLA	0	A	COLFAX, JCT. RTE. 80	14,000	220	1.57	85	40	23	72	38.64	18.18	10.45	32.73	35	06E
174	03	PLA	2.883	O	PLACER/NEVADA COUNTY LINE	4,950	358	7.24	61	121	91	86	16.90	33.80	25.35	23.94	56	03E
174	03	NEV	0	O	PLACER/NEVADA COUNTY LINE	4,950	358	7.24	61	121	91	86	16.90	33.80	25.35	23.94	56	03E
174	03	NEV	10.17	B	GRASS VALLEY, JCT. RTE. 20	5,900	427	7.24	72	144	108	102	16.90	33.80	25.35	23.94	67	03E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
175	01	MEN	0	A	HOPLAND, JCT. RTE. 101	4,900	385	7.86	280	35	18	53	72.73	9.09	4.55	13.64	34	03E
175	01	LAK	R 8.193	B	JCT. RTE. 29	2,050	205	10.00	154	21	10	21	75.00	10.00	5.00	10.00	16	06E
175	01	LAK	8.254	A	JCT. RTE. 29	800	200	25.00	176	12	7	5	88.24	5.88	3.53	2.35	10	06E
175	01	LAK	19.62	A	COBB POST OFFICE	2,900	215	7.42	178	14	9	14	82.61	6.52	4.35	6.52	14	06E
175	01	LAK	28.038	B	JCT. RTE. 29	3,200	237	7.42	196	15	10	15	82.61	6.52	4.35	6.52	15	06E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
177	08	RIV	0	A	JCT. RTE. 10	3,500	263	7.50	126	0	11	126	48.00	0.00	4.00	48.00	49	78E
177	08	RIV	0.26	A	KAISER MINE ROAD	1,650	231	14.00	74	0	9	149	31.90	0.00	3.80	64.30	55	93V
177	08	RIV	27.024	B	JCT. RTE. 62	1,300	251	19.30	32	0	12	207	12.80	0.00	4.80	82.40	74	78E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
178S	06	KER	S 1.736	A	JCT RTE 178	4,000	120	3.00	73	11	6	30	61.00	9.00	5.00	25.00	15	03E
178S	06	KER	S 2.163	B	NORTH JCT RTE 204	3,350	168	5.00	102	15	10	40	61.00	9.00	6.00	24.00	20	03E
178	06	KER	0	A	JCT. RTES. 99/58	52,000	4,680	9.00	1,498	234	94	2,855	32.00	5.00	2.00	61.00	1,073	04E
178	06	KER	R 2.009	A	BAKERSFIELD, JCT. RTE. 204	67,000	4,020	6.00	2,613	844	241	322	65.00	21.00	6.00	8.00	316	04E
178	06	KER	R 5.641	B	BAKERSFIELD, OSWELL STREET	38,000	2,280	6.00	1,231	547	296	205	54.00	24.00	13.00	9.00	208	04E
178	06	KER	R 5.641	A	BAKERSFIELD, OSWELL STREET	26,000	2,080	8.00	1,165	270	125	520	56.00	13.00	6.00	25.00	263	03E
178	06	KER	T 9.614	B	JCT. RTE. 184	14,200	1,336	9.41	835	191	107	203	62.50	14.29	8.04	15.18	133	06E
178	06	KER	T 9.614	A	JCT. RTE. 184	13,400	1,206	9.00	1,110	36	24	36	92.00	3.00	2.00	3.00	58	04E
178	06	KER	R 42.941	B	JCT. RTE. 155	4,200	336	8.00	259	50	7	20	77.00	15.00	2.00	6.00	22	04E
178	06	KER	R 42.941	A	JCT. RTE. 155	4,200	378	9.00	295	53	4	26	78.00	14.00	1.00	7.00	25	04E
178	06	KER	57.076	A	KELSO VALLEY ROAD	2,700	136	5.02	92	7	3	34	68.00	5.00	2.00	25.00	16	04E
178	06	KER	88.26	B	JCT. RTE. 14	1,600	144	9.00	46	12	3	84	32.00	8.00	2.00	58.00	32	04E
178	06	KER	88.38	A	JCT. RTE. 14	2,900	276	9.50	94	22	17	144	34.00	8.00	6.00	52.00	57	04E
178	06	KER	R 93.237	B	JCT. RTE. 395	7,100	533	7.50	144	64	16	309	27.00	12.00	3.00	58.00	120	04E
178	06	KER	R 93.237	A	JCT. RTE. 395	7,500	563	7.50	203	101	34	225	36.00	18.00	6.00	40.00	99	04E
178	06	KER	102.616	B	RIDGECREST BOULEVARD	20,900	732	3.50	388	73	22	249	53.00	10.00	3.00	34.00	109	04E
178	06	KER	102.616	A	RIDGECREST BOULEVARD	13,100	393	3.00	197	35	12	149	50.00	9.00	3.00	38.00	63	04E
178	08	SBD	7.35	B	TRONA ROAD	2,200	176	8.00	26	18	7	125	15.00	10.00	4.00	71.00	47	91E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
178	08	SBD	7.35	A	TRONA ROAD	2,300	230	10.00	23	12	5	191	10.00	5.00	2.00	83.00	69	91E
178	08	SBD	14.778	B	TRONA ROAD	2,300	276	12.00	16	5	0	255	5.70	1.80	0.00	92.50	89	91V
178	09	INY	28	A	DEATH VALLEY MONUMENT, SOUTH BOUNDARY	250	15	6.07	11	0	4	0	75.00	0.00	25.00	0.00	1	07V
178	09	INY	42.92	B	JCT. RTE. 127	250	14	5.50	7	0	0	7	50.00	0.00	0.00	50.00	3	03V
178	09	INY	42.93	A	JCT. RTE. 127	850	77	9.10	40	11	3	22	52.20	14.50	4.40	28.90	10	94V
178	09	INY	62.186	B	NEVADA STATE LINE	850	76	8.90	39	12	2	23	51.50	15.20	3.00	30.30	11	94E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
180S	06	FRE	R 57.843	A	FRESNO, BLACKSTONE AVENUE	102,000	5,100	5.00	3,570	612	204	714	70.00	12.00	4.00	14.00	458	04E
180	06	FRE	34.59	B	JAMES ROAD	5,600	840	15.00	336	76	50	378	40.00	9.00	6.00	45.00	157	04E
180	06	FRE	34.59	A	JAMES ROAD	8,200	1,230	15.00	615	98	25	492	50.00	8.00	2.00	40.00	204	04E
180	06	FRE	40.11	A	SHASTA AVE	6,800	657	9.66	291	45	19	302	44.29	6.85	2.89	45.97	121	10V
180	06	FRE	42.639	B	KERMAN, JCT. RTE. 145	13,800	2,070	15.00	911	145	62	952	44.00	7.00	3.00	46.00	383	04E
180	06	FRE	42.639	A	KERMAN, JCT. RTE. 145	12,700	775	6.10	334	61	31	349	43.10	7.87	4.00	45.03	142	10V
180	06	FRE	71.61	B	ACADEMY AVENUE	12,300	861	7.00	560	60	26	215	65.00	7.00	3.00	25.00	103	04E
180	06	FRE	71.61	A	ACADEMY AVENUE	11,100	777	7.00	505	54	23	194	65.00	7.00	3.00	25.00	93	04E
180	06	FRE	74.95	B	CENTERVILLE, TRIMMER SPRINGS ROAD	12,600	1,638	13.00	1,032	115	49	442	63.00	7.00	3.00	27.00	206	04E
180	06	FRE	74.95	A	CENTERVILLE, TRIMMER SPRINGS ROAD	10,700	1,406	13.14	433	451	294	228	30.80	32.08	20.91	16.22	179	10E
180	06	FRE	87.706	B	JCT. RTE. 63 SOUTH	4,600	644	14.00	451	64	19	109	70.00	10.00	3.00	17.00	62	04E
180	06	FRE	87.706	A	JCT. RTE. 63 SOUTH	5,800	812	14.00	577	81	16	138	71.00	10.00	2.00	17.00	78	04E
180	06	FRE	108.128	B	JCT. RTE. 245 SOUTH	3,050	377	12.36	318	30	20	9	84.35	7.96	5.31	2.39	20	10E
180	06	TUL	110.829	B	NORTH BOUNDARY GENERAL GRANT GROVE, KINGS CANYON NATIONAL PARK	1,600	160	10.00	114	30	2	14	71.00	19.00	1.00	9.00	12	04E
180	06	FRE	112.09	A	NORTH BOUNDARY GENERAL GRANT GROVE, KINGS CANYON NATIONAL PARK	1,600	80	5.00	63	15	1	1	79.00	19.00	1.00	1.00	4	04E
180	06	FRE	116.85	A	HUME LAKE ROAD	880	35	4.00	28	7	0	0	80.00	20.00	0.00	0.00	2	04E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
182	09	MNO	0	A	BRIDGEPORT, JCT. RTE. 395	1,100	145	13.15	103	22	16	5	70.80	15.20	10.80	3.20	10	08V
182	09	MNO	12.651	B	NEVADA STATE LINE	250	38	15.34	12	9	16	1	32.00	24.00	42.00	2.00	4	08V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
183	05	MON	0	A	SALINAS, JCT. RTE. 101	35,700	3,106	8.70	2,184	311	34	578	70.30	10.00	1.10	18.60	309	03E
183	05	MON	1.821	B	SALINAS, WEST CITY LIMITS	16,000	1,920	12.00	697	300	58	866	36.30	15.60	3.00	45.10	359	03E
183	05	MON	9.006	B	CASTROVILLE, JCT. RTE. 156	22,400	3,472	15.50	1,458	406	104	1,503	42.00	11.70	3.00	43.30	622	03E
183	05	MON	9.98	B	NORTH, CASTROVILLE, JCT. RTE. 1	11,500	1,840	16.00	793	199	92	756	43.10	10.80	5.00	41.10	320	03E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
184	06	KER	L0	A	JCT. RTE. 223	4,000	857	21.42	317	37	20	484	36.96	4.28	2.33	56.42	184	06E
184	06	KER	7.937	B	JCT. RTE. 58	18,700	1,341	7.17	360	175	80	725	26.87	13.06	5.97	54.10	291	06E
184	06	KER	7.937	A	JCT. RTE. 58	18,000	875	4.86	417	188	146	125	47.62	21.43	16.67	14.29	96	06E
184	06	KER	9.6	B	BAKERSFIELD, NILES STREET	10,900	803	7.37	382	172	134	115	47.62	21.43	16.67	14.29	89	06E
184	06	KER	12.139	B	BAKERSFIELD, JCT. RTE. 178	5,700	930	16.32	625	110	74	121	67.19	11.86	7.91	13.04	85	06E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
185	04	ALA	1.992	B	JCT. RTE. 238	17,200	378	2.20	304	27	20	27	80.35	7.21	5.24	7.21	25	00V
185	04	ALA	5.728	B	JCT. RTE. 112 WEST	20,000	324	1.62	262	32	9	21	81.01	9.87	2.78	6.33	21	03V
185	04	ALA	5.728	A	JCT. RTE. 112 WEST	17,000	240	1.41	198	24	14	4	82.50	10.00	5.71	1.79	13	00V
185	04	ALA	10.37	B	OAKLAND, 44TH AVE/12TH STREET	24,400	595	2.44	472	61	6	56	79.35	10.18	0.99	9.48	42	02V
185	04	ALA	10.519	B	OAKLAND, HIGH/ 12TH STREETS	3,000	265	8.83	203	42	6	13	76.79	15.85	2.26	5.09	16	00V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
186	11	IMP	0	A	MEXICAN BOUNDARY	4,350	300	6.90	123	54	45	78	41.00	18.00	15.10	25.90	43	94E
186	11	IMP	2.07	B	JCT. RTE. 8	9,200	607	6.60	249	108	92	158	41.10	17.80	15.10	26.00	87	94E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
187	07	LA	3.5	A	LOS ANGELES, JCT. RTE. 1, LINCOLN BOULEVARD	39,500	1,307	3.31	1,103	128	40	36	84.40	9.83	3.03	2.74	69	06V
187	07	LA	5.832	B	LOS ANGELES, JCT. RTE. 405, SAN DIEGO FREEWAY	47,000	1,603	3.41	1,316	205	23	59	82.09	12.81	1.41	3.69	89	06V
187	07	LA	5.832	A	LOS ANGELES, JCT. RTE. 405, SAN DIEGO FREEWAY	69,000	1,746	2.53	1,476	168	29	73	84.54	9.60	1.67	4.19	97	06V
187	07	LA	8.802	B	LOS ANGELES, JCT. RTE. 10, SANTA MONICA FREEWAY	43,500	1,683	3.87	1,376	153	48	106	81.73	9.12	2.85	6.30	106	06V
187	07	LA	8.905	B	LOS ANGELES, CADILLAC AVENUE	54,000	1,723	3.19	1,406	188	40	89	81.58	10.93	2.31	5.18	103	06V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
188	11	SD	0	A	MEXICAN BOUNDARY	5,900	608	10.30	170	162	12	264	27.90	26.60	2.00	43.50	114	96E
188	11	SD	1.85	B	JCT. RTE. 94	5,600	577	10.30	161	153	12	251	27.90	26.60	2.00	43.50	108	96E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
189	08	SBD	0	A	JCT. RTE. 18	3,700	222	6.00	212	10	0	0	95.60	4.40	0.00	0.00	8	88V
189	08	SBD	5.565	B	JCT. RTE. 173	5,200	208	4.00	162	46	0	0	78.00	22.00	0.00	0.00	10	86V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
190	06	TUL	0	A	TIPTON, JCT. RTE. 99	3,700	916	24.76	383	77	44	412	41.81	8.41	4.80	44.98	169	10V
190	06	TUL	9.474	B	POPLAR, COUNTY ROAD 192	3,750	716	19.09	207	75	43	391	28.91	10.47	6.00	54.61	155	08E
190	06	TUL	9.474	A	POPLAR, COUNTY ROAD 192	5,650	904	16.00	316	54	81	452	35.00	6.00	9.00	50.00	184	03E
190	06	TUL	R 15.241	B	PORTERVILLE, JCT. RTE. 65	8,300	1,047	12.61	366	200	78	403	34.96	19.10	7.45	38.49	182	08V
190	06	TUL	R 15.241	A	PORTERVILLE, JCT. RTE. 65	23,100	4,158	18.00	2,620	416	166	956	63.00	10.00	4.00	23.00	484	03E
190	06	TUL	18.453	B	HOSPITAL ROAD	17,400	870	5.00	600	104	35	131	69.00	12.00	4.00	15.00	81	03E
190	06	TUL	18.453	A	HOSPITAL ROAD	10,100	606	6.00	394	127	55	30	65.00	21.00	9.00	5.00	44	03E
190	06	TUL	22.55	A	GOVERNMENT ROAD TO SUCCESS DAM	5,600	491	8.77	269	73	39	110	54.79	14.87	7.94	22.40	60	08V
190	06	TUL	R 32.704	B	BALCH PARK DRIVE	2,450	147	6.00	96	19	1	31	65.00	13.00	1.00	21.00	16	04E
190	06	TUL	R 32.704	A	BALCH PARK DRIVE	790	67	8.48	48	8	5	6	71.64	11.94	7.46	8.96	5	08V
190	06	TUL	47.98	B	CAMP NELSON ROAD	700	28	4.00	21	5	1	1	75.00	19.00	3.00	3.00	2	04E
190	06	TUL	47.98	A	CAMP NELSON ROAD	400	16	4.00	11	3	1	1	70.00	18.00	6.00	6.00	1	04E
190	06	TUL	56.567	B	QUAKING ASPEN CAMP	400	16	4.00	11	3	1	1	70.00	18.00	6.00	6.00	1	04E
190	09	INY	9.85	A	OLANCHA, JCT. RTE. 395	300	44	14.55	6	10	0	28	14.77	22.73	0.00	62.50	11	07V
190	09	INY	24.55	B	JCT. RTE. 136 NORTHWEST	250	4	1.67	4	0	0	0	100.00	0.00	0.00	0.00	0	07E
190	09	INY	24.55	A	JCT. RTE. 136 NORTHWEST	500	51	10.21	12	6	5	28	22.91	12.50	10.42	54.17	11	07V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
190	09	INY	110.72	A	FURNACE CREEK RANCH	1,050	41	3.90	36	3	0	2	87.00	7.00	0.00	6.00	2	07E
190	09	INY	140.692	B	DEATH VALLEY JUNCTION, JCT. RTE. 127	850	61	7.16	33	6	3	19	54.16	10.42	4.17	31.25	9	07V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
191	03	BUT	0	A	JCT. RTE. 70	5,100	335	6.57	80	120	95	40	23.88	35.82	28.36	11.94	42	03E
191	03	BUT	11.386	B	PARADISE, PEARSON ROAD	10,100	450	4.46	170	134	36	109	37.84	29.73	8.11	24.32	61	06E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
192	05	SB	R .019	A	JCT. RTE. 154	10,900	349	3.20	272	55	0	22	77.90	15.80	0.00	6.30	22	10E
192	05	SB	1.64	B	SANTA BARBARA, ONTARE ROAD	10,000	350	3.50	299	34	0	17	85.50	9.70	0.00	4.80	19	10E
192	05	SB	1.64	A	SANTA BARBARA, ONTARE ROAD	10,000	310	3.10	272	27	0	11	87.70	8.70	0.00	3.60	16	10E
192	05	SB	5.99	B	SANTA BARBARA, JCT. RTE. 144 SOUTH	3,200	237	7.41	147	38	29	24	61.88	16.03	12.10	9.99	21	10E
192	05	SB	8.28	B	HOT SPRINGS ROAD	3,900	108	2.77	102	6	0	0	94.30	5.70	0.00	0.00	4	10E
192	05	SB	8.28	A	HOT SPRINGS ROAD	7,300	146	2.00	121	21	4	1	82.60	14.20	2.60	0.60	7	10E
192	05	SB	8.82	A	SAN YSIDRO ROAD	7,700	185	2.40	179	6	0	0	96.90	3.10	0.00	0.00	7	10E
192	05	SB	21.07	B	JCT. RTE. 150	690	43	6.30	42	1	0	0	97.10	2.90	0.00	0.00	2	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
193	03	PLA	3	B	SIERRA COLLEGE BOULEVARD	9,700	910	9.38	197	76	30	607	21.67	8.33	3.33	66.67	228	06E
193	03	PLA	3	A	SIERRA COLLEGE BOULEVARD	6,400	600	9.38	130	50	20	400	21.67	8.33	3.33	66.67	150	06E
193	03	PLA	9.77	B	TAYLOR ROAD	5,100	301	5.90	110	83	47	61	36.60	27.60	15.60	20.20	39	97E
193	03	PLA	9.77	A	TAYLOR ROAD	10,000	890	8.90	476	173	123	118	53.50	19.40	13.80	13.30	91	97E
193	03	PLA	10.194	B	NEWCASTLE, JCT. RTE. 80	10,000	980	9.80	635	113	127	105	64.80	11.50	13.00	10.70	88	97E
193	03	ED	0	A	COOL, JCT. RTE. 49	5,800	348	6.00	218	73	5	52	62.60	21.10	1.30	15.00	33	89V
193	03	ED	12.699	B	GEORGETOWN, LOWER MAIN STREET	5,300	318	6.00	243	43	12	20	76.30	13.50	3.90	6.30	21	89E
193	03	ED	12.699	A	GEORGETOWN, LOWER MAIN STREET	3,550	213	6.00	133	20	2	57	62.40	9.60	1.10	26.90	26	89E
193	03	ED	26.95	B	JCT. RTE. 49	3,000	159	5.30	99	15	3	42	62.00	9.40	1.90	26.70	20	89E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
195	08	RIV	R 0	A	JCT RTE 86	1,000	50	5.00	25	6	5	14	50.00	12.00	10.00	28.00	7	94E
195	08	RIV	7.42	B	MECCA, JCT. RTE. 111	6,000	300	5.00	150	36	30	84	50.00	12.00	10.00	28.00	42	94E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
197	01	DN	R 0	A	JCT. RTE. 199	2,300	130	5.65	60	15	10	45	46.15	11.54	7.69	34.62	20	05E
197	01	DN	7.08	B	JCT. RTE. 101	1,800	222	12.33	102	36	22	62	45.95	16.22	9.91	27.93	32	07E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
198	05	MON	13.995	B	JCT. RTE. 25 NORTH	1,000	76	7.60	47	5	0	24	61.90	6.30	0.00	31.80	10	03E
198	05	MON	13.995	A	JCT. RTE. 25 NORTH	1,000	134	13.40	53	0	4	76	39.70	0.00	3.30	57.00	29	03E
198	06	FRE	12.33	B	PARKFIELD JUNCTION	1,200	204	17.00	129	14	14	47	63.00	7.00	7.00	23.00	24	04E
198	06	FRE	12.33	A	PARKFIELD JUNCTION	1,100	187	17.00	118	13	13	43	63.00	7.00	7.00	23.00	22	04E
198	06	FRE	21.19	B	FIRESTONE AVENUE	1,100	191	17.36	80	15	9	87	41.88	7.85	4.71	45.55	36	08V
198	06	FRE	22.65	B	JCT. RTE. 33	7,000	1,190	17.00	750	83	83	274	63.00	7.00	7.00	23.00	141	04E
198	06	FRE	22.66	A	JCT. RTE. 33	1,900	288	15.16	100	29	10	149	34.72	10.07	3.47	51.74	59	08V
198	06	FRE	26.814	B	JCT. RTE. 5	2,900	522	18.00	240	63	16	204	46.00	12.00	3.00	39.00	87	04E
198	06	FRE	26.814	A	JCT. RTE. 5	5,800	870	15.00	322	78	26	444	37.00	9.00	3.00	51.00	175	04E
198	06	FRE	34.66	A	JCT. RTE. 269	6,700	938	14.00	281	150	28	478	30.00	16.00	3.00	51.00	193	04E
198	06	KIN	4.992	B	AVENAL CUTOFF ROAD	17,500	1,400	8.00	406	224	70	700	29.00	16.00	5.00	50.00	287	04E
198	06	KIN	4.992	A	AVENAL CUTOFF ROAD	18,000	1,440	8.00	677	72	72	619	47.00	5.00	5.00	43.00	254	04E
198	06	KIN	8.897	B	JCT. RTE. 41	18,000	1,440	8.00	677	72	72	619	47.00	5.00	5.00	43.00	254	04E
198	06	KIN	R 8.897	A	JCT. RTE. 41	18,500	1,480	8.00	622	133	74	651	42.00	9.00	5.00	44.00	269	04E
198	06	KIN	R 15.745	B	HANFORD/ARMONA ROAD	31,000	2,905	9.37	1,875	164	99	767	64.53	5.66	3.42	26.40	360	08V
198	06	KIN	R 15.745	A	HANFORD/ARMONA ROAD	32,000	2,998	9.37	1,597	232	133	1,035	53.28	7.75	4.45	34.53	454	08E
198	06	KIN	R 17.912	B	HANFORD, 11TH AVENUE	27,500	2,475	9.00	1,114	173	99	1,089	45.00	7.00	4.00	44.00	445	04E
198	06	KIN	R 17.912	A	HANFORD, 11TH AVENUE	20,500	2,870	14.00	1,464	258	144	1,005	51.00	9.00	5.00	35.00	443	04E
198	06	KIN	R 20.975	B	JCT. RTE. 43	18,300	2,745	15.00	1,400	247	137	961	51.00	9.00	5.00	35.00	423	04E
198	06	KIN	R 20.975	A	JCT. RTE. 43	18,000	2,457	13.65	1,278	270	123	786	52.00	11.00	5.00	32.00	359	08E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
198	06	TUL	R 3.835	B	JCT. RTE. 99	38,000	4,613	12.14	2,402	300	192	1,720	52.06	6.50	4.16	37.28	733	10V
198	06	TUL	R 3.835	A	JCT. RTE. 99	30,000	3,300	11.00	1,815	264	165	1,056	55.00	8.00	5.00	32.00	476	02E
198	06	TUL	R 4.796	A	ALTA AVENUE; COUNTY ROAD 80	47,000	4,047	8.61	2,707	273	176	890	66.90	6.75	4.35	22.00	453	10E
198	06	TUL	R 8.753	B	VISALIA, JCT. RTE. 63 SOUTH	59,000	5,900	10.00	3,658	531	354	1,357	62.00	9.00	6.00	23.00	697	03E
198	06	TUL	R 8.753	A	VISALIA, JCT. RTE. 63 SOUTH	61,000	5,490	9.00	3,404	494	329	1,263	62.00	9.00	6.00	23.00	649	03E
198	06	TUL	R 9.967	A	VISALIA, JCT. RTE. 63 NORTH	48,500	4,365	9.00	2,706	393	262	1,004	62.00	9.00	6.00	23.00	516	00E
198	06	TUL	R 11.719	B	LOVERS LANE	38,000	3,420	9.00	1,607	205	68	1,539	47.00	6.00	2.00	45.00	616	03E
198	06	TUL	R 11.719	A	LOVERS LANE	29,000	2,900	10.00	1,537	174	145	1,044	53.00	6.00	5.00	36.00	451	00E
198	06	TUL	R 14.653	B	COUNTY ROAD 164	26,000	2,600	10.00	1,378	156	130	936	53.00	6.00	5.00	36.00	405	03E
198	06	TUL	R 14.653	A	COUNTY ROAD 164	21,000	2,310	11.00	1,016	162	92	1,040	44.00	7.00	4.00	45.00	423	03E
198	06	TUL	R 18.761	B	JCT. RTE. 65 SOUTH	19,000	2,987	15.72	2,295	152	121	419	76.83	5.09	4.05	14.03	257	10V
198	06	TUL	R 18.761	A	JCT. RTE. 65 SOUTH	11,600	2,088	18.00	940	167	63	919	45.00	8.00	3.00	44.00	375	08V
198	06	TUL	R 19.762	A	JCT. RTE. 245 NORTH	7,100	1,278	18.00	371	141	128	639	29.00	11.00	10.00	50.00	265	08V
198	06	TUL	27.96	B	JCT. RTE. 216 WEST	4,500	1,028	22.84	298	164	31	535	29.00	16.00	3.00	52.00	215	08E
198	06	TUL	27.96	A	JCT. RTE. 216 WEST	4,100	329	8.02	192	64	52	21	58.36	19.45	15.81	6.38	27	10V
198	06	TUL	38.49	B	THREE RIVERS, NORTH FORK DRIVE (COUNTY ROAD TO KAWEAH)	3,800	342	9.00	209	31	68	34	61.00	9.00	20.00	10.00	32	02E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
198	06	TUL	38.49	A	THREE RIVERS, NORTH FORK DRIVE (COUNTY ROAD TO KAWEAH)	3,600	324	9.00	198	29	65	32	61.00	9.00	20.00	10.00	30	02E
198	06	TUL	42.35	A	THREE RIVERS, MINERAL KING ROAD	1,650	77	4.67	54	14	5	4	70.13	18.18	6.49	5.19	5	08V
198	06	TUL	44.163	B	SEQUOIA NATIONAL PARK BOUNDARY	1,650	99	6.00	60	9	20	10	61.00	9.00	20.00	10.00	9	02E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
199	01	DN	T .506	A	JCT. RTE. 101	4,600	719	15.63	374	72	14	259	52.00	10.00	2.00	36.00	111	05E
199	01	DN	4.37	A	JCT. RTE. 197 NORTH	4,200	778	18.52	360	94	70	254	46.27	12.08	9.00	32.65	119	07E
199	01	DN	36.408	B	OREGON STATE LINE	3,100	554	17.86	288	55	11	199	52.00	10.00	2.00	36.00	85	05E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
200	01	HUM	R 0	A	JCT. RTE. 101	2,500	105	4.20	67	10	1	26	64.10	9.80	1.10	25.00	12	88V
200	01	HUM	R 2.681	B	JCT. RTE. 299	1,800	95	5.30	61	10	1	24	63.90	10.30	1.00	24.80	11	88E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
201	06	FRE	0	A	KINGSBURG, JCT. RTE. 99	17,600	2,464	14.00	1,774	197	148	345	72.00	8.00	6.00	14.00	221	00E
201	06	TUL	1.4	A	ROAD 28	5,400	461	8.54	224	102	40	95	48.59	22.13	8.68	20.61	56	08V
201	06	TUL	7.95	B	ALTA AVENUE	4,300	1,118	26.00	872	34	22	190	78.00	3.00	2.00	17.00	102	02V
201	06	TUL	7.95	A	ALTA AVENUE	2,800	728	26.00	575	22	15	116	79.00	3.00	2.00	16.00	64	03E
201	06	TUL	13.97	B	JCT. RTE. 63	2,800	81	2.89	39	14	8	20	48.15	17.28	9.88	24.69	11	08V
201	06	TUL	L 13.98	A	JCT. RTE. 63	4,350	510	11.72	186	68	44	212	36.47	13.33	8.63	41.57	92	08V
201	06	TUL	23.957	B	JCT. RTE. 245	1,500	136	9.07	90	15	10	21	66.18	11.03	7.35	15.44	13	08E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
202	06	KER	R 1.476	A	TEHACHAPI MENS PRISON	2,450	49	2.00	18	1	0	29	36.00	3.00	1.00	60.00	11	03E
202	06	KER	R 5.5	B	OLD TOWN ROAD	9,250	185	2.00	93	6	4	83	50.00	3.00	2.00	45.00	33	03E
202	06	KER	R 7.4	B	WOODFORD ROAD	9,450	189	2.00	95	9	8	77	50.00	5.00	4.00	41.00	32	03E
202	06	KER	12.008	B	JCT. RTE. 58	10,900	981	9.00	422	39	20	500	43.00	4.00	2.00	51.00	194	03E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
203	09	MNO	L 0	A	MINARET SUMMIT	620	11	1.70	9	1	0	2	78.90	5.30	0.00	15.80	1	93E
203	09	MNO	R 8.56	B	JCT. RTE. 395	7,950	1,055	13.27	615	214	178	48	58.34	20.28	16.87	4.51	84	09V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
204	06	KER	R 0	A	BAKERSFIELD, JCT. RTE. 58	43,000	5,160	12.00	2,425	568	258	1,909	47.00	11.00	5.00	37.00	834	03E
204	06	KER	3.087	B	BAKERSFIELD, CALIFORNIA AVENUE	35,000	3,850	11.00	1,810	462	193	1,386	47.00	12.00	5.00	36.00	612	03E
204	06	KER	3.087	A	BAKERSFIELD, CALIFORNIA AVENUE	34,000	3,060	9.00	1,438	367	153	1,102	47.00	12.00	5.00	36.00	487	03E
204	06	KER	4.057	A	BAKERSFIELD, 24TH STREET	13,000	1,170	9.00	550	140	59	421	47.00	12.00	5.00	36.00	186	03E
204	06	KER	4.235	B	BAKERSFIELD, JCT. RTE. 178	13,000	1,170	9.00	550	129	59	433	47.00	11.00	5.00	37.00	189	03E
204	06	KER	4.235	A	BAKERSFIELD, JCT. RTE. 178	30,000	2,700	9.00	1,269	324	135	972	47.00	12.00	5.00	36.00	429	03E
204	06	KER	6.752	B	BAKERSFIELD, JCT. RTE. 99	39,000	1,981	5.08	890	500	210	380	44.95	25.25	10.61	19.19	239	06E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
205	04	ALA	0.213	A	JCT. RTE. 580	116,000	13,920	12.00	4,026	587	342	8,964	28.92	4.22	2.46	64.40	3,338	06V
205	10	SJ	R 3.369	B	OLD ROUTE 50	97,000	11,640	12.00	3,436	744	348	7,112	29.52	6.39	2.99	61.10	2,694	04E
205	10	SJ	R 8.127	A	TRACY, MAC ARTHUR DRIVE	94,500	10,565	11.18	3,175	667	299	6,425	30.05	6.31	2.83	60.81	2,433	06V
205	10	SJ	R 12.686	B	JCT. RTE. 5	97,000	11,087	11.43	3,273	708	332	6,774	29.52	6.39	2.99	61.10	2,566	04V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
207	10	ALP	0	A	JCT. RTE. 4	750	45	6.00	1	20	5	19	2.00	45.00	10.00	43.00	9	98V
207	10	ALP	1.36	B	MT. REBA SKI RESORT	740	24	3.20	0	11	2	10	2.00	45.00	10.00	43.00	5	98E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
210U	08	SBD	15.767	B	SIERRA AVENUE	9,800	980	10.00	676	83	40	180	69.00	8.50	4.10	18.40	99	87E
210U	08	SBD	15.767	A	SIERRA AVENUE	12,000	1,200	10.00	629	164	72	335	52.40	13.70	6.00	27.90	163	87E
210U	08	SBD	19.521	B	RIALTO, RIVERSIDE AVENUE	19,000	2,926	15.40	1,088	301	20	1,516	37.20	10.30	0.70	51.80	592	89V
210U	08	SBD	19.521	A	RIALTO, RIVERSIDE AVENUE	27,500	1,898	6.90	1,234	199	85	380	65.00	10.50	4.50	20.00	205	87E
210U	08	SBD	21.68	B	CAJON BOULEVARD	28,000	1,904	6.80	1,245	171	36	451	65.40	9.00	1.90	23.70	220	92V
210U	08	SBD	R 23.095	B	NORTH JCT. RTE. 259	70,000	3,780	5.40	2,865	299	30	586	75.80	7.90	0.80	15.50	334	91E
210U	08	SBD	R 23.095	A	NORTH JCT. RTE. 259	130,000	6,240	4.80	4,599	524	212	905	73.70	8.40	3.40	14.50	553	91E
210U	08	SBD	R 24.215	B	SAN BERNARDINO, JCT. RTE. 18 NORTH	130,000	6,240	4.80	4,599	524	212	905	73.70	8.40	3.40	14.50	553	91E
210U	08	SBD	R 24.215	A	SAN BERNARDINO, JCT. RTE. 18 NORTH	105,000	7,350	7.00	6,468	368	74	441	88.00	5.00	1.00	6.00	423	83V
210U	08	SBD	R 28.664	B	SAN BERNARDINO, JCT. RTE. 330	70,000	4,900	7.00	4,312	245	44	299	88.00	5.00	0.90	6.10	283	83E
210U	08	SBD	R 28.664	A	SAN BERNARDINO, JCT. RTE. 330	70,000	4,109	5.87	2,039	507	161	1,400	49.62	12.33	3.92	34.06	625	03E
210U	08	SBD	R 30.232	B	HIGHLAND, FIFTH STREET	76,000	4,256	5.60	1,895	510	220	1,631	44.53	11.98	5.17	38.32	708	05E
210U	08	SBD	R 30.232	A	HIGHLAND, FIFTH STREET	92,000	5,078	5.52	2,261	608	263	1,946	44.53	11.98	5.17	38.32	845	05V
210U	08	SBD	R 33.18	B	JCT. RTE. 10	76,000	4,522	5.95	2,201	319	118	1,882	48.68	7.06	2.62	41.62	773	08V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
210	07	LA	R 0	A	LOS ANGELES, JCT. RTE. 5, GOLDEN STATE FREEWAY INTERCHANGE	76,000	5,822	7.66	982	526	225	4,089	16.87	9.04	3.86	70.23	1,527	10E
210	07	LA	R 3.57	O	E/O POLK ST; ASTORIA ST PED OC	83,000	6,125	7.38	1,033	554	236	4,302	16.87	9.04	3.86	70.23	1,606	10V
210	07	LA	R 5.911	B	LOS ANGELES, JCT. RTE. 118, RONALD REAGAN FREEWAY INTERCHANGE	120,000	6,192	5.16	1,045	560	239	4,349	16.87	9.04	3.86	70.23	1,624	10E
210	07	LA	R 5.911	A	LOS ANGELES, JCT. RTE. 118, RONALD REAGAN FREEWAY INTERCHANGE	117,000	9,524	8.14	2,405	1,153	422	5,544	25.25	12.11	4.43	58.21	2,165	10E
210	07	LA	R 18.872	B	LA CANADA-FLINTRIDGE, WEST JCT. RTE. 2, GLENDALE FREEWAY INTERCHANGE	168,000	9,290	5.53	2,346	1,125	412	5,408	25.25	12.11	4.43	58.21	2,112	10V
210	07	LA	R 18.872	A	LA CANADA-FLINTRIDGE, WEST JCT. RTE. 2, GLENDALE FREEWAY INTERCHANGE	119,000	9,877	8.30	2,729	547	234	6,366	27.63	5.54	2.37	64.45	2,377	10E
210	07	LA	R 19.881	A	LA CANADA-FLINTRIDGE, EAST JCT. RTE. 2, ANGELES CREST HIGHWAY INTERCHANGE	115,000	9,545	8.30	2,637	529	226	6,152	27.63	5.54	2.37	64.45	2,297	10E
210	07	LA	R 24.962	B	PASADENA, JCT. RTES. 134/710, VENTURA/LONG BEACH FREEWAYS INTERCHANGE	135,000	9,450	7.00	2,611	524	224	6,091	27.63	5.54	2.37	64.45	2,274	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
210	07	LA	R 24.962	A	PASADENA, JCT. RTES. 134/710, VENTURA/LONG BEACH FREEWAYS INTERCHANGE	295,000	13,246	4.49	4,059	1,427	633	7,128	30.64	10.77	4.78	53.81	2,826	10E
210	07	LA	R 26.326	A	PASADENA, LAKE AVENUE INTERCHANGE	294,000	13,201	4.49	4,045	1,422	631	7,103	30.64	10.77	4.78	53.81	2,816	10V
210	07	LA	L 29.795	B	PASADENA, ROSEMEAD BOULEVARD INTERCHANGE	265,000	15,503	5.85	4,932	1,490	867	8,213	31.81	9.61	5.59	52.98	3,271	10E
210	07	LA	R 29.486	A	PASADENA, ROSEMEAD BOULEVARD INTERCHANGE	258,000	16,280	6.31	5,179	1,565	910	8,625	31.81	9.61	5.59	52.98	3,435	10E
210	07	LA	R 36.41	B	DUARTE, JCT. RTE. 605, SAN GABRIEL RIVER FREEWAY INTERCHANGE	258,000	20,098	7.79	6,703	1,628	1,337	10,431	33.35	8.10	6.65	51.90	4,180	10E
210	07	LA	R 36.41	A	DUARTE, JCT. RTE. 605, SAN GABRIEL RIVER FREEWAY INTERCHANGE	265,000	17,914	6.76	5,684	1,139	425	10,668	31.73	6.36	2.37	59.55	4,047	10E
210	07	LA	R 41.594	A	GLENDORA, GRAND AVENUE INTERCHANGE	245,000	16,268	6.64	5,162	1,035	386	9,688	31.73	6.36	2.37	59.55	3,675	10V
210	07	LA	R 44.377	B	GLENDORA, JCT RTE 57, ORANGE FREEWAY INTERCHANGE	245,000	16,268	6.64	5,162	1,035	386	9,688	31.73	6.36	2.37	59.55	3,675	10E
210	07	LA	R 44.377	A	GLENDORA, JCT RTE 57, ORANGE FREEWAY INTERCHANGE	194,000	7,469	3.85	2,047	842	265	4,316	27.40	11.27	3.55	57.78	1,677	10E
210	07	LA	R 51.849	B	CLAREMONT, BASELINE ROAD INTERCHANGE	164,000	7,314	4.46	2,004	824	260	4,226	27.40	11.27	3.55	57.78	1,642	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
210	08	SBD	11.498	B	JCT RTE 15	158,000	7,394	4.68	2,056	900	291	4,148	27.80	12.17	3.93	56.10	1,629	05E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
211	01	HUM	73.2	A	FERNDALE, OCEAN AVENUE	6,100	590	9.67	387	112	41	51	65.52	18.97	6.90	8.62	47	02E
211	01	HUM	79.161	B	JCT. RTE. 101	5,100	822	16.11	539	156	57	71	65.52	18.97	6.90	8.62	66	02E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
213	07	LA	0	A	LOS ANGELES, 25TH STREET	27,000	462	1.71	375	58	24	5	81.19	12.56	5.25	1.00	24	06V
213	07	LA	5.085	B	LOS ANGELES, JCT. RTE. 1, PACIFIC COAST HIGHWAY	29,500	602	2.04	460	80	19	44	76.38	13.22	3.13	7.27	41	06V
213	07	LA	5.085	A	LOS ANGELES, JCT. RTE. 1, PACIFIC COAST HIGHWAY	20,800	620	2.98	491	69	16	45	79.16	11.07	2.52	7.25	41	06V
213	07	LA	7.983	B	CARSON STREET	30,000	1,140	3.80	913	144	29	54	80.09	12.63	2.54	4.74	68	06V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
215	08	RIV	R 8.998	A	MURRIETA, JCT. RTE. 15	85,000	6,120	7.20	3,039	810	335	1,937	49.65	13.24	5.47	31.65	898	05V
215	08	RIV	23.537	B	SOUTH JCT. RTE. 74	72,000	5,220	7.25	2,506	679	365	1,670	48.00	13.00	7.00	32.00	780	05E
215	08	RIV	23.537	A	SOUTH JCT. RTE. 74	88,000	10,384	11.80	5,317	1,526	602	2,939	51.20	14.70	5.80	28.30	1,429	84E
215	08	RIV	26.308	A	PERRIS, NORTH JCT. RTE. 74	82,000	10,824	13.20	5,044	1,266	628	3,886	46.60	11.70	5.80	35.90	1,726	84E
215	08	RIV	27.23	A	PERRIS, D STREET	99,000	11,880	12.00	4,514	1,307	475	5,584	38.00	11.00	4.00	47.00	2,275	86V
215	08	RIV	R 35.76	B	CACTUS AVENUE	120,000	12,240	10.20	4,884	1,236	612	5,508	39.90	10.10	5.00	45.00	2,275	84E
215	08	RIV	R 35.76	A	CACTUS AVENUE	126,000	11,340	9.00	4,627	1,123	567	5,024	40.80	9.90	5.00	44.30	2,082	84E
215	08	RIV	R 38.339	B	JCT. RTE. 60 EAST	119,000	17,255	14.50	7,506	1,087	449	8,213	43.50	6.30	2.60	47.60	3,262	96V
215	08	RIV	R 38.339	A	JCT. RTE. 60 EAST	168,000	18,312	10.90	7,691	989	330	9,302	42.00	5.40	1.80	50.80	3,618	96V
215	08	RIV	42.837	B	RIVERSIDE, SPRUCE STREET	157,000	11,461	7.30	4,493	768	424	5,776	39.20	6.70	3.70	50.40	2,283	84E
215	08	RIV	43.27	B	RIVERSIDE, JCT. RTES. 60/91, RIVERSIDE/ ESCONDIDO FREEWAY	157,000	10,205	6.50	4,041	653	367	5,143	39.60	6.40	3.60	50.40	2,030	84E
215	08	RIV	43.27	A	RIVERSIDE, JCT. RTES. 60/91, RIVERSIDE/ ESCONDIDO FREEWAY	155,000	9,455	6.10	3,952	700	416	4,387	41.80	7.40	4.40	46.40	1,777	84E
215	08	RIV	45.013	A	CENTER STREET	147,000	10,143	6.90	4,240	751	446	4,706	41.80	7.40	4.40	46.40	1,907	84E
215	08	SBD	0.402	A	IOWA AVENUE	153,000	10,863	7.10	4,671	826	424	4,943	43.00	7.60	3.90	45.50	2,007	84E
215	08	SBD	4.052	B	COLTON, JCT. RTE. 10	170,000	12,240	7.20	5,263	930	477	5,569	43.00	7.60	3.90	45.50	2,261	84E
215	08	SBD	4.052	A	COLTON, JCT. RTE. 10	155,000	14,880	9.60	6,994	1,979	551	5,357	47.00	13.30	3.70	36.00	2,356	84V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
215	08	SBD	6.06	A	SAN BERNARDINO, MILL STREET	136,000	8,432	6.20	3,634	1,180	320	3,297	43.10	14.00	3.80	39.10	1,420	84E
215	08	SBD	7.183	B	SAN BERNARDINO, JCT. RTE. 66 WEST	125,000	8,625	6.90	3,717	1,208	328	3,372	43.10	14.00	3.80	39.10	1,453	84E
215	08	SBD	7.183	A	SAN BERNARDINO, JCT. RTE. 66 WEST	125,000	8,375	6.70	3,618	1,164	327	3,266	43.20	13.90	3.90	39.00	1,409	84E
215	08	SBD	8.603	B	SAN BERNARDINO, JCT. RTE. 259 NORTH	115,000	8,510	7.40	3,676	1,183	332	3,319	43.20	13.90	3.90	39.00	1,431	84E
215	08	SBD	8.603	A	SAN BERNARDINO, JCT. RTE. 259 NORTH	65,000	7,865	12.10	1,573	1,400	417	4,475	20.00	17.80	5.30	56.90	1,789	84E
215	08	SBD	9.364	B	SAN BERNARDINO, HIGHLAND AVENUE	63,000	6,678	10.60	1,529	915	327	3,907	22.90	13.70	4.90	58.50	1,534	84E
215	08	SBD	9.364	A	SAN BERNARDINO, HIGHLAND AVENUE	58,000	6,148	10.60	2,035	510	203	3,400	33.10	8.30	3.30	55.30	1,321	84E
215	08	SBD	11.634	A	UNIVERSITY PARKWAY	53,000	4,839	9.13	1,975	333	154	2,375	40.82	6.89	3.19	49.09	942	04V
215	08	SBD	14.091	A	PALM AVENUE	53,000	4,839	9.13	1,975	333	154	2,375	40.82	6.89	3.19	49.09	942	04V
215	08	SBD	17.753	B	JCT. RTE. 15	48,000	4,406	9.18	1,483	258	97	2,569	33.65	5.85	2.20	58.30	976	04E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
216	06	TUL	R 0	A	VISALIA, JCT. RTE. 198	21,700	868	4.00	738	17	35	78	85.00	2.00	4.00	9.00	59	02E
216	06	TUL	R .99	B	LOVERS LANE	9,000	360	4.00	306	7	14	32	85.00	2.00	4.00	9.00	24	02E
216	06	TUL	1.96	A	LOVERS LANE	9,200	920	10.00	672	101	74	74	73.00	11.00	8.00	8.00	69	02E
216	06	TUL	2.46	A	MACAULIFF AVE,RD 144	4,600	256	5.57	169	35	26	26	66.02	13.67	10.16	10.16	22	08V
216	06	TUL	11.732	B	AVENUE 344	3,500	233	6.66	117	37	22	57	50.21	15.88	9.44	24.46	30	08E
216	06	TUL	11.732	A	AVENUE 344	4,900	637	13.00	490	32	19	96	77.00	5.00	3.00	15.00	56	02E
216	06	TUL	14.006	B	WOODLAKE, JCT. RTE. 245	5,800	1,143	19.71	299	409	300	135	26.16	35.78	26.25	11.81	139	08V
216	06	TUL	14.006	A	WOODLAKE, JCT. RTE. 245	5,400	1,064	19.70	278	381	279	126	26.16	35.78	26.25	11.81	129	08E
216	06	TUL	19.245	B	JCT. RTE. 198	1,250	208	16.64	78	21	13	96	37.50	10.10	6.25	46.15	40	08V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
217	05	SB	0.464	A	ENTRANCE, UNIVERSITY OF CALIFORNIA AT SANTA BARBARA	12,200	244	2.00	202	20	5	17	82.60	8.40	2.00	7.00	16	10E
217	05	SB	2.756	B	JCT. RTE. 101	23,000	690	3.00	570	57	13	50	82.60	8.30	1.90	7.20	44	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
218	05	MON	1.956	B	DEL REY OAKS, JCT. RTE. 68	12,800	1,024	8.00	744	106	40	133	72.70	10.40	3.90	13.00	88	03E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
219	10	STA	4.858	B	JCT. RTE. 108	14,200	1,278	9.00	281	243	102	652	22.00	19.00	8.00	51.00	272	01E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
220	04	SOL	0	A	JCT. RTE. 84	150	5	3.33	0	1	4	0	0.00	25.00	75.00	0.00	1	04E
220	03	SAC	3.114	B	RYDE, JCT. RTE. 160	780	49	6.30	29	7	3	10	58.50	14.10	6.00	21.40	6	95V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
221	04	NAP	0	A	JCT. RTE. 29	24,700	1,492	6.04	615	233	89	555	41.19	15.65	5.98	37.18	248	02V
221	04	NAP	2.682	B	JCT. RTE. 121	24,500	1,237	5.05	556	301	78	303	44.91	24.33	6.28	24.49	163	02V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
222	01	MEN	R 0	A	UKIAH, JCT. RTE. 101	8,000	280	3.50	158	74	0	48	56.50	26.30	0.00	17.20	29	88V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
223	06	KER	1.85	A	JCT. RTE. 5	1,200	228	19.00	73	9	11	135	32.00	4.00	5.00	59.00	52	03E
223	06	KER	R 10.536	B	JCT. RTE. 99	4,700	893	19.00	277	45	54	518	31.00	5.00	6.00	58.00	200	03E
223	06	KER	R 10.536	A	JCT. RTE. 99	6,900	1,435	20.80	276	193	138	828	19.23	13.46	9.62	57.69	333	03V
223	06	KER	R 16.014	B	JCT. RTE. 184 NORTH	6,600	1,848	28.00	739	314	111	684	40.00	17.00	6.00	37.00	307	03E
223	06	KER	R 16.014	A	JCT. RTE. 184 NORTH	7,000	1,750	25.00	858	158	105	630	49.00	9.00	6.00	36.00	277	03E
223	06	KER	R 20.15	B	ARVIN, COMANCHE DRIVE	7,200	936	13.00	365	103	19	449	39.00	11.00	2.00	48.00	180	03E
223	06	KER	20.15	A	ARVIN, COMANCHE DRIVE	10,000	1,000	10.00	400	70	20	510	40.00	7.00	2.00	51.00	199	03E
223	06	KER	31.92	B	JCT. RTE. 58	1,150	441	38.33	77	48	29	288	17.39	10.87	6.52	65.22	111	06V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
225	05	SB	0	A	SANTA BARBARA, JCT. RTE. 101	20,500	369	1.80	314	27	7	21	85.10	7.40	1.80	5.70	22	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
227	05	SLO	7.12	B	EDNA, PRICE CANYON ROAD	4,900	260	5.30	182	48	14	16	70.10	18.30	5.30	6.30	18	10E
227	05	SLO	7.12	A	EDNA, PRICE CANYON ROAD	10,600	774	7.30	458	122	33	160	59.20	15.80	4.30	20.70	87	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
229	05	SLO	0	A	JCT. RTE. 58	100	8	8.00	4	0	2	2	50.00	0.00	25.00	25.00	1	10E
229	05	SLO	9.16	B	JCT. RTE. 41	800	70	8.80	35	0	18	18	50.00	0.00	25.00	25.00	10	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
232	07	VEN	0	A	OXNARD, JCT. RTE. 1, OXNARD BOULEVARD	43,000	1,759	4.09	1,029	172	105	453	58.50	9.75	5.97	25.78	224	07E
232	07	VEN	0.441	A	OXNARD, JCT. RTE. 101, VENTURA FREEWAY	24,200	1,958	8.09	746	490	166	556	38.09	25.05	8.48	28.38	287	07E
232	07	VEN	R 4.11	B	JCT. RTE. 118, LOS ANGELES AVENUE	16,800	1,836	10.93	646	319	91	780	35.19	17.35	4.96	42.50	334	07V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
233	06	MAD	0.005	A	JCT. RTE. 152	3,600	439	12.19	212	116	47	64	48.29	26.42	10.71	14.58	47	10V
233	06	MAD	3.586	B	CHOWCHILLA, CHOWCHILLA AVENUE	11,300	904	8.00	389	45	36	434	43.00	5.00	4.00	48.00	173	04E
233	06	MAD	3.586	A	CHOWCHILLA, CHOWCHILLA AVENUE	11,300	904	8.00	389	45	36	434	43.00	5.00	4.00	48.00	173	04E
233	06	MAD	3.887	B	JCT. RTE. 99	11,000	880	8.00	378	44	35	422	43.00	5.00	4.00	48.00	168	04E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
236	05	SCR	0	A	BOULDER CREEK, JCT. RTE. 9	6,400	230	3.60	215	9	4	2	93.50	4.00	1.80	0.70	10	02E
236	05	SCR	17.721	B	JCT. RTE. 9, WATERMANS GAP	400	20	5.00	18	1	0	1	89.40	5.60	0.00	5.00	1	02E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
237	04	SCL	R 0	A	MOUNTAIN VIEW, JCT. RTE. 82	33,500	345	1.03	247	55	3	40	71.66	15.88	0.90	11.55	28	04V
237	04	SCL	R .375	B	MOUNTAIN VIEW, JCT. RTE. 85	33,500	1,005	3.00	609	204	21	171	60.60	20.30	2.10	17.00	102	98E
237	04	SCL	R .375	A	MOUNTAIN VIEW, JCT. RTE. 85	57,000	3,084	5.41	1,618	471	19	975	52.48	15.28	0.62	31.63	439	98V
237	04	SCL	2.48	B	SUNNYVALE, JCT. RTE. 101	67,000	2,928	4.37	887	426	76	1,539	30.31	14.55	2.60	52.55	612	01V
237	04	SCL	2.48	A	SUNNYVALE, JCT. RTE. 101	87,000	2,567	2.95	961	676	60	870	37.44	26.35	2.33	33.89	405	04V
237	04	SCL	9.335	B	JCT. RTE. 880, NIMITZ FREEWAY	133,000	8,326	6.26	4,468	1,294	296	2,269	53.66	15.54	3.55	27.25	1,102	98V
237	04	SCL	9.335	A	JCT. RTE. 880, NIMITZ FREEWAY	62,000	3,267	5.27	1,726	413	84	1,043	52.84	12.65	2.56	31.94	471	98V
237	04	SCL	T 10	B	MAIN STREET	62,000	2,480	4.00	1,252	370	159	699	50.50	14.90	6.40	28.20	342	98E
237	04	SCL	11.08	B	MILPITAS, JCT. RTE 680	66,000	2,640	4.00	1,061	275	150	1,154	40.20	10.40	5.70	43.70	483	98E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
238	04	ALA	0	A	FREMONT, JCT. RTE. 680, MISSION ROAD	29,000	870	3.00	540	81	21	228	62.10	9.30	2.40	26.20	108	94V
238	04	ALA	3.314	B	FREMONT, SOUTH JCT. RTE. 84 WEST	23,000	989	4.30	475	134	59	321	48.00	13.50	6.00	32.50	148	94V
238	04	ALA	3.314	A	FREMONT, SOUTH JCT. RTE. 84 WEST	33,000	1,947	5.90	870	275	156	646	44.70	14.10	8.00	33.20	302	94V
238	04	ALA	6.78	B	UNION CITY, DECOTO ROAD	25,500	893	3.50	436	157	37	263	48.80	17.60	4.10	29.50	126	97E
238	04	ALA	R 14.469	A	JCT. RTE. 580	123,000	16,359	13.30	3,566	1,309	474	11,010	21.80	8.00	2.90	67.30	4,113	94V
238	04	ALA	14.951	A	JCT. RTE. 185, MISSION BOULEVARD	121,000	14,278	11.80	2,998	957	286	10,037	21.00	6.70	2.00	70.30	3,698	94V
238	04	ALA	16.696	B	JCT. RTE. 880	74,000	5,624	7.60	1,355	546	186	3,537	24.10	9.70	3.30	62.90	1,345	94V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
241	12	ORA	17.768	A	ANTONIO PARKWAY	17,000	1,081	6.36	533	210	153	185	49.33	19.47	14.13	17.07	124	98E
241	12	ORA	20.077	A	LOS ALISOS BOULEVARD	37,000	629	1.70	312	148	57	112	49.67	23.50	9.09	17.74	72	98E
241	12	ORA	23.418	A	ALTON PARKWAY	40,300	1,241	3.08	792	207	79	163	63.83	16.69	6.34	13.14	115	98E
241	12	ORA	39.079	B	JCT RTE 91	43,000	714	1.66	443	123	31	117	62.07	17.24	4.31	16.38	72	01E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
242	04	CC	R 0	A	CONCORD, JCT. RTE. 680	90,000	4,500	5.00	1,926	554	158	1,863	42.80	12.30	3.50	41.40	784	00E
242	04	CC	R 3.398	B	CONCORD, JCT. RTE. 4	98,000	5,027	5.13	2,611	745	152	1,519	51.93	14.82	3.03	30.21	706	00V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
243	08	RIV	0	A	JCT. RTE. 74	3,400	136	4.00	123	12	0	2	90.10	8.60	0.00	1.30	6	79E
243	08	RIV	28.28	B	BANNING, SAN GORGONIO AVENUE	2,000	80	4.00	72	7	0	1	89.90	8.80	0.00	1.30	4	79E
243	08	RIV	29.659	B	BANNING, JCT. RTE. 10; 8TH STREET	7,000	280	4.00	254	21	0	5	90.70	7.60	0.00	1.70	13	79E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
244	03	SAC	0	A	SACRAMENTO, JCT. RTE. 80	8,900	1,335	15.00	534	134	134	534	40.00	10.00	10.00	40.00	235	83E
244	03	SAC	T 1.077	B	AUBURN BOULEVARD	32,000	4,800	15.00	1,920	480	480	1,920	40.00	10.00	10.00	40.00	844	83E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
245	06	TUL	0	A	JCT. RTE. 198	3,100	496	16.00	402	25	15	55	81.00	5.00	3.00	11.00	38	01V
245	06	TUL	7.066	B	JCT. RTE. 216	5,700	399	7.00	243	20	12	124	61.00	5.00	3.00	31.00	55	04E
245	06	TUL	7.066	A	JCT. RTE. 216	5,800	348	6.00	271	14	17	45	78.00	4.00	5.00	13.00	29	04E
245	06	TUL	11.999	B	JCT. RTE. 201 WEST	1,350	135	10.00	97	8	5	24	72.00	6.00	4.00	18.00	13	04E
245	06	TUL	11.999	A	JCT. RTE. 201 WEST	700	69	9.86	43	12	8	6	62.32	17.39	11.59	8.70	6	08E
245	06	TUL	19.293	B	OROSI ROAD/BOYD DRIVE	200	32	16.00	27	2	1	3	83.00	6.00	3.00	8.00	2	04E
245	06	FRE	8.972	B	JCT. RTE. 180	200	21	10.50	14	4	2	1	66.67	19.05	9.52	4.76	1	08V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
246	05	SB	8.302	A	LOMPOC, WEST CITY LIMITS	6,600	264	4.00	190	36	4	34	71.90	13.80	1.40	12.90	22	10E
246	05	SB	9.55	B	LOMPOC, JCT. RTE. 1	12,600	479	3.80	301	71	19	89	62.80	14.80	3.90	18.50	51	10E
246	05	SB	9.56	A	LOMPOC, JCT. RTE. 1	8,200	619	7.55	404	86	63	65	65.31	13.97	10.14	10.58	54	10V
246	05	SB	26.286	B	BUELLTON, JCT. RTE. 101	17,500	1,488	8.50	872	164	22	430	58.60	11.00	1.50	28.90	197	10E
246	05	SB	26.286	A	BUELLTON, JCT. RTE. 101	18,000	738	4.10	438	103	22	174	59.40	14.00	3.00	23.60	88	10E
246	05	SB	R 34.601	B	SANTA YNEZ, JCT. RTE. 154	8,200	532	6.49	445	37	33	16	83.70	7.00	6.29	3.01	29	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
247	08	SBD	0	A	YUCCA VALLEY, JCT. RTE. 62	12,000	1,068	8.90	641	106	108	214	60.00	9.90	10.10	20.00	122	89E
247	08	SBD	44.85	B	JCT. RTE. 18	3,000	450	15.00	330	32	8	81	73.30	7.10	1.70	17.90	44	89V
247	08	SBD	44.86	A	JCT. RTE. 18	1,900	247	13.00	75	16	21	135	30.30	6.40	8.50	54.80	54	88E
247	08	SBD	73.181	B	STODDARD WELLS ROAD	2,100	363	17.30	155	0	16	192	42.70	0.00	4.50	52.80	74	88V
247	08	SBD	73.181	A	STODDARD WELLS ROAD	1,700	294	17.30	132	3	12	147	44.90	0.90	4.20	50.00	57	88E
247	08	SBD	78.096	B	BARSTOW, JCT. RTE. 15	18,000	378	2.10	212	47	0	119	56.20	12.40	0.00	31.40	53	92V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
253	01	MEN	0	A	BOONVILLE, JCT. RTE. 128	2,000	284	14.21	158	32	11	84	55.56	11.11	3.70	29.63	39	06E
253	01	MEN	17.18	B	UKIAH, JCT. RTE. 101	2,600	281	10.80	156	31	10	83	55.56	11.11	3.70	29.63	38	06E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
254	01	HUM	0	A	JCT. RTE. 101	700	37	5.29	25	7	4	1	67.57	18.92	10.81	2.70	2	05E
254	01	HUM	12.327	B	JCT. RTE. 101	950	37	3.89	25	7	4	1	67.57	18.92	10.81	2.70	2	05E
254	01	HUM	12.327	A	JCT. RTE. 101	590	37	6.27	25	7	4	1	67.57	18.92	10.81	2.70	2	05V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
255	01	HUM	0	A	EUREKA, JCT. RTE. 101	9,500	830	8.74	415	87	22	306	50.00	10.53	2.63	36.84	131	03E
255	01	HUM	8.803	B	JCT. RTE. 101	15,500	953	6.15	377	139	40	397	39.58	14.58	4.17	41.67	169	03E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
259	08	SBD	R 0	A	SAN BERNARDINO, JCT. RTE. 215	67,000	2,948	4.40	2,429	215	44	259	82.40	7.30	1.50	8.80	201	84E
259	08	SBD	1.25	B	JCT. RTE. 30	64,000	2,816	4.40	2,320	206	42	248	82.40	7.30	1.50	8.80	192	84E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
260	04	ALA	R 1.924	B	OAKLAND, JCT. RTE. 880	44,600	1,070	2.40	763	102	19	186	71.30	9.50	1.80	17.40	103	94V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
262	04	ALA	R 0	A	FREMONT, JCT. RTE. 880	76,000	5,472	7.20	2,183	498	306	2,484	39.90	9.10	5.60	45.40	1,024	94V
262	04	ALA	R 1.07	B	FREMONT, JCT. RTE. 680	74,000	4,144	5.60	1,227	220	124	2,573	29.60	5.30	3.00	62.10	969	94V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
263	02	SIS	49.07	A	YREKA, JCT. RTE. 3	1,650	68	4.14	16	18	3	32	23.32	25.75	3.92	47.01	14	10E
263	02	SIS	50.63	B	HAWKINSVILLE, HUMBUG ROAD	1,550	62	3.99	17	13	2	30	27.64	21.14	2.44	48.78	12	10E
263	02	SIS	57.195	B	JCT. RTE. 96	990	40	4.03	9	9	1	21	23.15	22.22	2.78	51.85	9	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
265	02	SIS	19.801	A	WEED, JCT. RTE. 97	1,800	201	11.15	56	26	5	114	27.94	12.75	2.45	56.86	44	10E
265	02	SIS	20.328	B	WEED, JCT. RTE. 5	1,800	201	11.15	56	26	5	114	27.94	12.75	2.45	56.86	44	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
266	09	MNO	0	A	NEVADA STATE LINE (SOUTH)	200	12	6.00	2	2	3	5	14.30	14.30	28.50	42.90	2	07V
266	09	MNO	11.721	B	NEVADA STATE LINE (NORTH)	140	4	3.00	1	1	1	0	33.30	33.30	33.30	0.00	0	07E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
267	03	PLA	9.898	B	JCT. RTE. 28	9,300	298	3.20	135	67	24	72	45.16	22.58	8.06	24.19	39	06E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
269	06	KIN	0	A	JCT. RTE. 33	2,500	250	10.00	95	20	8	128	38.00	8.00	3.00	51.00	51	04E
269	06	FRE	0	A	KINGS/FRESNO COUNTY LINE	5,100	510	10.00	347	20	15	128	68.00	4.00	3.00	25.00	60	04E
269	06	FRE	0.427	A	JCT. RTE. 5	5,200	780	15.00	530	31	23	195	68.00	4.00	3.00	25.00	92	04E
269	06	FRE	12.746	B	JCT. RTE. 198	4,100	615	15.00	418	25	18	154	68.00	4.00	3.00	25.00	73	04E
269	06	FRE	12.746	A	JCT. RTE. 198	2,800	476	17.00	257	19	14	186	54.00	4.00	3.00	39.00	77	04E
269	06	FRE	24.764	B	JCT. RTE. 145	2,300	569	24.74	233	73	32	231	40.95	12.83	5.62	40.60	99	08V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
270	09	MNO	0	A	JCT. RTE. 395	480	27	5.65	21	3	2	0	78.90	12.90	6.94	1.26	1	08V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
271	01	MEN	0.02	A	JCT. RTE. 101	100	10	10.00	8	1	0	1	77.80	11.10	0.00	11.10	1	89E
271	01	MEN	5.601	B	JCT. RTE. 101, SCANDIA	450	41	9.00	33	6	0	2	80.90	14.90	0.00	4.20	2	89E
271	01	MEN	7.308	B	TEMPORARY JCT. RTE. 1	750	46	6.10	37	7	0	2	80.30	14.80	0.00	4.90	3	89V
271	01	MEN	R 17.048	A	JCT. RTE. 101, REYNOLDS	80	10	12.60	6	2	0	3	57.90	15.80	0.00	26.30	1	89V
271	01	MEN	19.459	A	JCT. RTE. 101, PIERCY	170	22	13.10	13	4	0	5	60.00	16.00	0.00	24.00	3	89E
271	01	HUM	T .306	B	TEMPORARY JCT. RTE. 101	130	34	26.00	20	8	0	7	58.10	22.60	0.00	19.40	4	89E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
273	02	SHA	3.812	A	JCT. RTE. 5	9,800	538	5.49	138	58	21	321	25.65	10.78	3.90	59.67	124	09V
273	02	SHA	4.44	B	ANDERSON, PINON AVENUE	9,800	718	7.33	94	111	18	495	13.16	15.40	2.54	68.90	187	09E
273	02	SHA	4.44	A	ANDERSON, PINON AVENUE	13,500	959	7.10	126	148	24	661	13.16	15.40	2.54	68.90	250	09E
273	02	SHA	5.206	B	ANDERSON, SOUTH STREET	13,500	922	6.83	129	160	25	608	13.97	17.39	2.70	65.94	233	09E
273	02	SHA	5.206	A	ANDERSON, SOUTH STREET	12,400	693	5.59	109	122	18	444	15.77	17.61	2.54	64.08	171	09E
273	02	SHA	5.438	A	ANDERSON, NORTH STREET	10,400	619	5.95	104	124	17	374	16.77	20.03	2.72	60.48	147	09E
273	02	SHA	6.387	B	ALEXANDER AVENUE	10,400	650	6.25	109	130	18	393	16.77	20.03	2.72	60.48	154	09E
273	02	SHA	6.387	A	ALEXANDER AVENUE	10,600	729	6.88	120	153	18	437	16.50	21.00	2.50	60.00	172	09E
273	02	SHA	6.9	A	OX YOKE ROAD	11,900	732	6.15	140	180	17	395	19.11	24.56	2.30	54.03	160	09E
273	02	SHA	7.24	A	CHAMPION/FRONTAGE ROADS	11,900	666	5.60	140	167	16	343	21.02	25.03	2.41	51.55	141	09E
273	02	SHA	7.54	A	HILL STREET	12,400	682	5.50	164	164	20	334	24.00	24.00	3.00	49.00	139	09E
273	02	SHA	9.99	A	HAPPY VALLEY ROAD	14,000	599	4.28	132	156	18	294	22.00	26.00	3.00	49.00	123	09E
273	02	SHA	11.1	A	CANYON ROAD	21,000	531	2.53	121	158	111	141	22.88	29.70	20.85	26.57	84	09V
273	02	SHA	11.83	A	REDDING, CLEAR CREEK ROAD	23,000	1,035	4.50	211	257	35	533	20.34	24.82	3.36	51.48	220	09E
273	02	SHA	12.27	A	REDDING, WESTWOOD AVENUE	22,700	1,101	4.85	264	319	44	473	24.00	29.00	4.00	43.00	208	09E
273	02	SHA	12.68	A	REDDING, CEDARS/SOUTH BONNEYVIEW ROADS	18,100	418	2.31	192	92	15	120	45.82	21.96	3.58	28.64	59	09V
273	02	SHA	16.833	A	NORTH JCT. RTE. 299 AND RTE 44	18,000	810	4.50	243	235	32	300	30.00	29.00	4.00	37.00	138	09V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
273	02	SHA	17.39	B	QUARTZ HILL/RIO	18,000	864	4.80	259	251	35	320	30.00	29.00	4.00	37.00	148	09E
273	02	SHA	17.39	A	QUARTZ HILL/RIO	21,400	910	4.25	273	264	36	337	30.00	29.00	4.00	37.00	155	09E
273	02	SHA	17.81	A	REDDING, BENTON DRIVE	25,000	1,025	4.10	308	297	41	379	30.00	29.00	4.00	37.00	175	09E
273	02	SHA	18.622	A	LAKE BOULEVARD	12,800	269	2.10	126	28	57	58	46.94	10.41	21.21	21.45	35	09V
273	02	SHA	18.92	A	TWINVIEW BOULEVARD	9,400	245	2.61	93	41	44	67	38.09	16.76	18.01	27.15	37	09E
273	02	SHA	20.033	B	JCT. RTE. 5	8,900	277	3.11	81	64	41	91	29.24	23.10	14.80	32.85	46	09V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
275	03	YOL	12.009	A	JCT. RTE. 50	9,300	391	4.20	318	35	5	33	81.30	8.90	1.30	8.50	26	86E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
280	04	SCL	R 0	A	SAN JOSE, JCT. RTES. 101/680	152,000	7,144	4.70	4,129	1,014	236	1,765	57.80	14.20	3.30	24.70	881	96V
280	04	SCL	R .366	A	MCLAUGHLIN AVENUE	238,000	7,973	3.35	4,307	1,017	302	2,346	54.02	12.76	3.79	29.43	1,098	00V
280	04	SCL	R 1.992	A	SAN JOSE, JCT. RTE. 82	232,000	6,032	2.60	3,873	736	205	1,218	64.20	12.20	3.40	20.20	654	96V
280	04	SCL	R 2.522	B	SAN JOSE, JCT. RTE. 87	232,000	5,800	2.50	3,428	696	238	1,438	59.10	12.00	4.10	24.80	715	96V
280	04	SCL	R 2.522	A	SAN JOSE, JCT. RTE. 87	196,000	2,999	1.53	1,979	220	91	708	65.99	7.35	3.05	23.60	347	00V
280	04	SCL	L 5.408	A	SAN JOSE, JCT. RTES. 17/880	179,000	5,549	3.10	2,658	966	266	1,659	47.90	17.40	4.80	29.90	793	96E
280	04	SCL	9.433	B	SARATOGA, SUNNYVALE/DE ANZA BOULEVARD	150,000	4,740	3.16	2,283	467	128	1,862	48.17	9.86	2.70	39.28	784	00V
280	04	SCL	9.433	A	SARATOGA, SUNNYVALE/DE ANZA BOULEVARD	138,000	4,099	2.97	1,671	508	107	1,813	40.76	12.39	2.62	44.23	746	05V
280	04	SCL	10.741	A	SUNNYVALE, JCT. RTE. 85	139,000	4,587	3.30	2,651	702	165	1,069	57.80	15.30	3.60	23.30	550	96E
280	04	SM	R 3.337	B	WOODSIDE, JCT. RTE. 84	103,000	3,317	3.22	1,906	391	56	964	57.46	11.78	1.70	29.06	443	08V
280	04	SM	R 3.337	A	WOODSIDE, JCT. RTE. 84	102,000	2,948	2.89	1,889	342	152	565	64.08	11.60	5.17	19.16	315	08V
280	04	SM	R 6.601	B	CANADA ROAD	102,000	2,254	2.21	1,374	244	46	591	60.95	10.82	2.03	26.21	281	02V
280	04	SM	10.866	B	JCT. RTE. 92	106,000	1,813	1.71	988	294	78	453	54.52	16.21	4.30	24.97	229	05V
280	04	SM	10.866	A	JCT. RTE. 92	105,000	1,764	1.68	1,020	196	55	493	57.82	11.10	3.14	27.93	232	05V
280	04	SM	R 19.278	B	SAN BRUNO, JCT. RTE. 35 NORTH	117,000	281	0.24	197	23	21	40	70.18	8.07	7.37	14.39	26	05V
280	04	SM	R 19.278	A	SAN BRUNO, JCT. RTE. 35 NORTH	102,000	449	0.44	288	38	56	67	64.19	8.52	12.45	14.85	45	05V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
280	04	SM	R 20.747	A	SAN BRUNO, SAN BRUNO AVENUE	104,000	2,465	2.37	1,674	286	65	440	67.92	11.61	2.63	17.84	246	00V
280	04	SM	R 22.62	A	SOUTH SAN FRANCISCO, WESTBOROUGH BOULEVARD	185,000	1,480	0.80	1,015	263	21	181	68.60	17.80	1.40	12.20	125	96E
280	04	SM	R 24.197	A	DALY CITY, HICKEY BOULEVARD	179,000	1,629	0.91	1,106	181	34	309	67.88	11.09	2.06	18.97	167	00V
280	04	SM	R 25.28	B	DALY CITY, JCT. RTE. 1 SOUTH	216,000	2,549	1.18	1,639	306	86	519	64.29	11.99	3.36	20.36	277	05V
280	04	SM	R 25.28	A	DALY CITY, JCT. RTE. 1 SOUTH	209,000	2,654	1.27	1,599	424	59	573	60.24	15.97	2.21	21.58	301	05V
280	04	SM	R 26.042	A	JUNIPERO SIERRA	226,000	2,757	1.22	1,867	286	77	527	67.72	10.36	2.81	19.11	285	05V
280	04	SM	M 27.165	B	DALY CITY, JCT. RTE. 1 NORTH	452,000	4,972	1.10	3,401	641	144	786	68.40	12.90	2.90	15.80	470	96V
280	04	SF	R .738	B	SAN FRANCISCO, JCT. RTE. 82, ALEMANY BOULEVARD/ SAN JOSE AVENUE	136,000	1,659	1.22	1,133	264	34	229	68.27	15.93	2.03	13.78	148	08V
280	04	SF	R .738	A	SAN FRANCISCO, JCT. RTE. 82, ALEMANY BOULEVARD/ SAN JOSE AVENUE	170,000	2,720	1.60	1,689	401	42	588	62.09	14.74	1.55	21.62	305	08V
280	04	SF	R 4.341	B	SAN FRANCISCO, JCT. RTE. 101	322,000	5,506	1.71	3,584	1,217	123	581	65.10	22.11	2.23	10.56	456	05V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
280	04	SF	R 6.05	A	INDIANA STREET/PENNSYLVANIA AVENUE	108,000	2,700	2.50	1,877	462	78	284	69.50	17.10	2.90	10.50	218	96V
280	04	SF	T 7.07	B	SAN FRANCISCO, 4TH STREET	99,000	723	0.73	468	91	6	159	64.76	12.52	0.77	21.95	80	02V
280	04	SF	T 7.543	B	SAN FRANCISCO, BRANNAN STREET	55,000	1,139	2.07	645	87	13	393	56.67	7.66	1.14	34.53	168	02V

RTE	DIST	CNTY	POST MILE	L E G	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
281	01	LAK	15.06	B	POINT LAKEVIEW ROAD	3,300	106	3.20	93	9	0	4	87.50	8.80	0.00	3.70	5	88E
281	01	LAK	17	B	JCT. RTE. 29	6,200	273	4.40	234	25	0	14	85.80	9.00	0.00	5.20	15	88V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
282	11	SD	0	A	JCT. RTE. 75	35,200	1,056	3.00	722	143	52	139	68.40	13.50	4.90	13.20	94	86V
282	11	SD	0.581	B	THIRD ST/ALAMEDA BLVD	29,600	888	3.00	603	130	44	112	67.90	14.60	4.90	12.60	78	86V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
283	01	HUM	0	A	JCT. RTE. 101, NORTH SCOTIA	2,150	75	3.50	51	13	0	11	68.20	17.80	0.00	14.00	7	88V
283	01	HUM	0.356	B	NORTH END OF EEL RIVER BRIDGE	2,150	75	3.50	51	13	0	11	68.20	17.80	0.00	14.00	7	88E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
284	02	PLU	0	A	JCT. RTE. 70	620	16	2.58	8	1	1	6	50.00	6.25	6.25	37.50	3	10V
284	02	PLU	8.302	B	FRENCHMAN RESERVOIR	320	8	2.50	3	2	0	3	37.50	25.00	0.00	37.50	1	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
299	01	HUM	0	A	ARCATA, JCT. RTE. 101	12,900	1,015	7.87	274	174	54	512	27.04	17.15	5.35	50.45	210	05E
299	01	HUM	R 1.802	B	JCT. RTE. 200 WEST	11,700	1,026	8.77	277	176	55	518	27.04	17.15	5.35	50.45	213	05E
299	01	HUM	R 1.802	A	JCT. RTE. 200 WEST	13,100	1,074	8.20	280	178	56	560	26.10	16.60	5.20	52.10	228	05E
299	01	HUM	R 5.451	A	BLUE LAKE ROAD	3,300	534	16.17	204	147	46	138	38.14	27.49	8.59	25.77	75	05E
299	01	HUM	38.833	B	WILLOW CREEK, JCT. RTE. 96 NORTH	3,200	517	16.17	197	142	44	133	38.14	27.49	8.59	25.77	72	05E
299	01	HUM	38.833	A	WILLOW CREEK, JCT. RTE. 96 NORTH	4,500	685	15.23	225	245	51	164	32.84	35.82	7.46	23.88	94	06V
299	01	HUM	43.035	B	HUMBOLT/TRINITY COUNTY LINE	3,800	730	19.22	234	255	64	176	32.08	34.97	8.82	24.13	102	09E
299	02	TRI	51.03	B	WEAVERVILLE, WEST CITY LIMITS	3,250	410	12.62	25	70	25	290	6.07	17.05	6.07	70.81	111	09E
299	02	TRI	51.03	A	WEAVERVILLE, WEST CITY LIMITS	3,250	273	8.40	48	43	12	170	17.58	15.75	4.40	62.27	66	09V
299	02	TRI	52.07	O	WEAVERVILLE, WASHINGTON STREET	11,600	360	3.10	27	66	21	246	7.44	18.41	5.73	68.41	95	09E
299	02	TRI	52.72	B	MARTIN/NUGGET ROADS	6,800	350	5.14	34	69	19	228	9.83	19.66	5.42	65.10	89	09E
299	02	TRI	52.72	A	MARTIN/NUGGET ROADS	6,300	376	5.97	38	78	19	240	10.22	20.84	5.01	63.93	94	09E
299	02	TRI	R 58.11	B	EAST JCT. RTE. 3	4,450	239	5.37	58	39	6	135	24.35	16.50	2.51	56.64	53	09V
299	02	TRI	R 58.11	A	EAST JCT. RTE. 3	4,050	442	10.91	76	76	12	278	17.13	17.12	2.75	63.00	107	09E
299	02	TRI	63.51	A	LEWISTON ROAD	3,500	521	14.88	51	102	26	342	9.80	19.61	4.90	65.69	133	09E
299	02	TRI	67.425	A	NEW LEWISTON ROAD	3,800	472	12.43	27	81	30	334	5.80	17.20	6.30	70.70	128	09E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
299	02	SHA	0	A	TRINITY/SHASTA COUNTY LINE	3,800	318	8.37	41	50	14	213	12.89	15.72	4.40	66.98	82	09V
299	02	SHA	8.648	B	FRENCH GULCH ROAD	3,800	318	8.37	41	50	14	213	12.89	15.72	4.40	66.98	82	09V
299	02	SHA	8.648	A	FRENCH GULCH ROAD	4,050	422	10.41	77	45	29	270	18.33	10.64	6.98	64.05	104	09V
299	02	SHA	16.47	A	KENNEDY DRIVE	5,400	562	10.40	103	60	39	360	18.33	10.64	6.98	64.05	139	09E
299	02	SHA	17.739	A	ROCK CREEK ROAD	9,200	471	5.12	86	101	12	272	18.30	21.35	2.62	57.73	108	09E
299	02	SHA	21.648	B	REDDING, WEST CITY LIMITS	10,000	286	2.86	69	48	9	161	23.97	16.78	3.08	56.16	64	09V
299	02	SHA	23.81	B	REDDING, COURT STREET	20,100	452	2.25	131	106	37	179	28.96	23.36	8.11	39.58	82	09E
299	02	SHA	23.81	A	REDDING, COURT STREET	19,800	537	2.71	156	125	42	213	29.04	23.35	7.90	39.71	97	09E
299	02	SHA	24.822	A	REDDING, JCT. RTE. 5	24,300	496	2.04	171	72	25	228	34.56	14.47	4.96	46.00	95	09V
299	02	SHA	25.54	A	HAWLEY ROAD	14,000	526	3.76	89	109	25	303	16.98	20.75	4.72	57.50	121	09E
299	02	SHA	27.239	A	OLD OREGON TRAIL	9,500	574	6.04	50	60	12	452	8.71	10.45	2.09	78.75	165	09V
299	02	SHA	60.05	B	BIG BEND ROAD	3,000	416	13.87	62	44	11	299	14.90	10.58	2.64	71.88	111	09V
299	02	SHA	72.64	O	HAYNES ROAD	2,850	377	13.23	48	49	8	272	12.62	12.97	2.16	72.25	101	08E
299	02	SHA	73.13	A	TAMARACK ROAD	3,100	389	12.56	40	60	7	283	10.34	15.36	1.68	72.63	106	09V
299	02	SHA	74.98	B	BURNEY, PLUMAS STREET	9,800	782	7.98	80	111	9	581	10.28	14.25	1.17	74.30	215	08E
299	02	SHA	76.181	A	BLACK RANCH ROAD	6,100	712	11.67	73	101	8	529	10.28	14.25	1.17	74.30	196	08E
299	02	SHA	80.085	B	FOUR CORNERS, JCT. RTE. 89	4,300	692	16.10	86	133	12	462	12.40	19.20	1.70	66.70	176	08V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
299	02	SHA	80.085	A	FOUR CORNERS, JCT. RTE. 89	3,000	167	5.57	14	37	3	113	8.24	22.35	1.76	67.65	43	09V
299	02	SHA	91.56	B	FALL RIVER MILLS, MAIN STREET	3,350	308	9.18	34	43	16	215	11.04	13.80	5.21	69.94	82	08E
299	02	SHA	91.56	A	FALL RIVER MILLS, MAIN STREET	4,500	302	6.72	40	42	13	206	13.29	13.92	4.43	68.35	78	08E
299	02	SHA	96.78	B	PITTVILLE ROAD	4,300	291	6.76	39	36	6	210	13.49	12.50	1.97	72.04	78	08E
299	02	SHA	96.78	A	PITTVILLE ROAD	2,900	282	9.72	38	35	5	204	13.48	12.41	1.77	72.34	76	08E
299	02	SHA	99.361	B	SHASTA/LASSEN COUNTY LINE	2,900	274	9.45	37	34	5	198	13.50	12.41	1.82	72.26	73	08E
299	02	LAS	10.407	O	CEMETERY ROAD	1,500	167	11.12	31	27	9	100	18.46	16.39	5.22	59.93	39	08V
299	02	MOD	0	A	LASSEN/MODOC COUNTY LINE	1,000	116	11.60	23	20	2	71	19.40	17.60	1.90	61.10	27	08V
299	02	MOD	0.332	B	ADIN, JCT. RTE. 139, SOUTH	1,000	116	11.64	23	20	2	71	19.44	17.59	1.85	61.11	27	08V
299	02	MOD	0.332	A	ADIN, JCT. RTE. 139, SOUTH	1,450	160	11.03	31	28	3	98	19.44	17.59	1.85	61.11	38	08E
299	02	MOD	21.749	B	JCT. RTE. 139 NORTH	770	140	18.13	26	19	8	87	18.62	13.79	5.52	62.07	34	08E
299	02	MOD	21.749	A	JCT. RTE. 139 NORTH	1,700	358	21.08	34	10	21	294	9.43	2.83	5.73	82.01	107	08V
299	02	MOD	40.276	B	ALTURAS, JUNIPER STREET	2,700	363	13.46	78	35	26	224	21.35	9.73	7.30	61.62	87	08E
299	02	MOD	40.276	A	ALTURAS, JUNIPER STREET	2,800	377	13.46	81	36	29	231	21.58	9.56	7.65	61.20	90	08E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
299	02	MOD	40.63	B	ALTURAS, JCT. RTE. 395	4,300	503	11.70	76	32	11	384	15.05	6.45	2.15	76.34	140	08V
299	02	MOD	40.64	A	ALTURAS, JCT. RTE. 395	760	60	7.95	15	4	2	39	25.76	6.06	3.03	65.15	15	08E
299	02	MOD	57.354	B	LAKE CITY ROAD	1,400	111	7.91	32	7	8	64	28.79	6.06	7.58	57.58	25	08E
299	02	MOD	57.354	A	LAKE CITY ROAD	300	32	10.65	24	1	2	5	75.76	3.03	6.06	15.15	3	08E
299	02	MOD	66.632	B	NEVADA STATE LINE	180	2	1.08	2	0	0	0	75.76	3.03	6.06	15.15	0	08E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
330	08	SBD	R 28.696	A	JCT. RTE. 30	9,000	225	2.50	133	27	9	56	59.10	12.00	4.00	24.90	28	85V
330	08	SBD	44.118	B	RUNNING SPRINGS, JCT. RTE. 18	10,000	400	4.00	344	16	4	36	86.00	4.00	1.10	8.90	27	79E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
371	08	RIV	56.395	A	JCT. RTE. 79	6,300	378	6.00	293	40	14	31	77.40	10.70	3.70	8.20	27	79E
371	08	RIV	77.148	B	JCT. RTE. 74	3,800	228	6.00	176	25	9	19	77.00	11.00	3.80	8.20	16	79E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
380	04	SM	T 4.703	A	SAN BRUNO, JCT. RTE. 280	139,000	2,989	2.15	1,682	500	27	781	56.26	16.72	0.90	26.12	378	07V
380	04	SM	6.373	B	SOUTH SAN FRANCISCO, JCT. RTE. 101	159,000	4,277	2.69	2,201	488	132	1,455	51.46	11.41	3.09	34.03	643	01V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
395	08	SBD	R 3.981	A	JCT. RTE. 15	24,000	5,280	22.00	1,119	164	69	3,928	21.20	3.10	1.30	74.40	1,420	90V
395	08	SBD	11.18	B	PALMDALE ROAD; JCT. RTE. 18	21,000	2,814	13.40	574	163	0	2,077	20.40	5.80	0.00	73.80	752	93V
395	08	SBD	11.18	A	PALMDALE ROAD; JCT. RTE. 18	18,000	3,114	17.30	504	159	0	2,451	16.20	5.10	0.00	78.70	878	93V
395	08	SBD	15.707	B	GEORGE AIR FORCE BASE ROAD	18,000	3,096	17.20	502	158	0	2,437	16.20	5.10	0.00	78.70	873	93E
395	08	SBD	15.707	A	GEORGE AIR FORCE BASE ROAD	15,000	2,700	18.00	437	138	0	2,125	16.20	5.10	0.00	78.70	761	98E
395	08	SBD	45.948	B	JCT. RTE. 58	7,000	1,260	18.00	204	64	0	992	16.20	5.10	0.00	78.70	355	98E
395	08	SBD	45.948	A	JCT. RTE. 58	4,100	492	12.00	80	25	0	387	16.20	5.10	0.00	78.70	139	98E
395	06	KER	R 1.152	B	REDROCK, RANDSBURG ROAD	4,200	672	16.00	141	74	54	403	21.00	11.00	8.00	60.00	159	04E
395	06	KER	R 1.152	A	REDROCK, RANDSBURG ROAD	4,200	588	14.00	123	24	24	417	21.00	4.00	4.00	71.00	154	03E
395	06	KER	R 23.48	B	JCT. RTE. 178	2,850	684	24.00	144	27	27	486	21.00	4.00	4.00	71.00	179	03E
395	06	KER	R 29.64	B	JCT. RTE. 14 SOUTH	2,750	643	23.37	80	126	111	327	12.41	19.54	17.26	50.78	144	08V
395	09	INY	34.674	B	JCT. RTE. 190 EAST	5,700	684	12.00	130	41	27	486	19.00	6.00	3.90	71.10	180	95E
395	09	INY	34.674	A	JCT. RTE. 190 EAST	5,900	513	8.70	48	15	6	444	9.30	3.00	1.10	86.60	157	98V
395	09	INY	55.827	B	JCT. RTE. 136 SOUTHEAST	6,050	666	11.00	153	47	26	440	23.00	7.00	3.90	66.10	165	95E
395	09	INY	55.827	A	JCT. RTE. 136 SOUTHEAST	6,950	1,154	16.60	178	72	14	891	15.40	6.20	1.20	77.20	322	97V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
395	09	INY	100.833	B	BIG PINE, JCT. RTE. 168 NORTHEAST	6,050	1,161	19.19	544	53	35	529	46.86	4.57	3.01	45.56	212	10V
395	09	INY	100.833	A	BIG PINE, JCT. RTE. 168 NORTHEAST	7,950	875	11.00	188	44	18	626	21.50	5.00	2.00	71.50	229	97E
395	09	INY	115.403	A	BISHOP, JCT. RTE. 168 WEST	15,500	930	6.00	279	93	9	549	30.00	10.00	1.00	59.00	209	97E
395	09	INY	116.25	B	JCT. RTE. 6 NORTH	16,150	485	3.00	170	92	5	218	35.00	19.00	1.10	44.90	90	97V
395	09	INY	116.25	A	JCT. RTE. 6 NORTH	13,450	728	5.41	361	53	20	294	49.65	7.23	2.78	40.33	122	01E
395	09	INY	120.95	A	ED POWERS ROAD	7,450	774	10.39	171	171	141	290	22.12	22.13	18.25	37.50	142	07V
395	09	MNO	R 25.75	B	JCT. RTE. 203 WEST	8,450	761	9.00	335	39	6	381	44.00	5.10	0.80	50.10	148	93E
395	09	MNO	R 25.75	A	JCT. RTE. 203 WEST	4,650	598	12.86	257	113	87	141	42.90	18.90	14.50	23.60	81	08V
395	09	MNO	40.336	A	SOUTH JCT. RTE. 158	4,200	467	11.11	63	46	16	342	13.51	9.95	3.32	73.22	127	98V
395	09	MNO	50.744	B	TIOGA PASS JUNCTION, NORTH JCT. RTE. 120 WEST	4,200	390	9.29	79	52	11	248	20.21	13.39	2.89	63.52	95	98V
395	09	MNO	50.744	A	TIOGA PASS JUNCTION, NORTH JCT. RTE. 120 WEST	4,550	541	11.90	89	44	7	400	16.50	8.20	1.30	74.00	146	94E
395	09	MNO	58.24	B	JCT. RTE. 167 EAST	3,200	357	11.17	102	30	4	221	28.45	8.50	1.10	61.95	83	07V
395	09	MNO	76.3	B	BRIDGEPORT, JCT. RTE. 182 NORTH	3,250	359	11.04	117	26	14	201	32.71	7.26	3.91	56.12	78	07V
395	09	MNO	76.3	A	BRIDGEPORT, JCT. RTE. 182 NORTH	3,700	273	7.39	55	21	17	180	20.08	7.79	6.15	65.98	68	98V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
395	09	MNO	93.7	A	JCT. RTE. 108 WEST	3,200	345	10.77	45	20	4	276	12.90	5.80	1.20	80.10	99	07V
395	09	MNO	116.965	B	JCT. RTE. 89	3,700	401	10.83	101	16	4	279	25.30	4.10	0.90	69.70	102	07V
395	09	MNO	120.49	B	NEVADA STATE LINE	3,650	395	10.83	100	16	4	275	25.30	4.10	0.90	69.70	100	07E
395	03	SIE	R 3.124	O	SIE/LAS CNTY LN	9,200	834	9.07	387	76	90	281	46.40	9.11	10.79	33.69	131	95E
395	02	LAS	R 4.615	B	JCT. RTE. 70 WEST	8,800	898	10.21	131	80	55	633	14.54	8.87	6.07	70.52	238	10E
395	02	LAS	R 4.615	A	JCT. RTE. 70 WEST	5,300	695	13.11	89	50	22	534	12.80	7.20	3.20	76.80	195	10E
395	02	LAS	29.84	A	GARNIER ROAD	4,150	664	16.00	65	54	36	509	9.79	8.13	5.42	76.66	188	10V
395	02	LAS	51.87	B	STANDISH ROAD	5,600	588	10.50	101	36	20	431	17.18	6.12	3.40	73.30	158	10E
395	02	LAS	51.87	A	STANDISH ROAD	5,600	573	10.23	96	37	26	414	16.75	6.46	4.54	72.25	153	10V
395	02	LAS	55.18	A	JANESVILLE ROAD	7,800	810	10.38	97	48	47	618	11.99	5.93	5.82	76.26	228	10E
395	02	LAS	R 61.094	B	JCT. RTE. 36 WEST	7,800	662	8.49	74	55	26	507	11.18	8.31	3.93	76.59	186	10V
395	02	LAS	R 61.094	A	JCT. RTE. 36 WEST	4,000	225	5.63	33	30	4	158	14.67	13.33	1.78	70.22	59	10V
395	02	LAS	70.12	A	STANDISH, COUNTY ROAD A 3	1,400	328	23.43	58	29	11	230	17.68	8.84	3.35	70.12	86	10V
395	02	LAS	72.943	A	LITCHFIELD, COUNTY ROAD A-27	1,100	264	24.00	25	18	8	213	9.47	6.82	3.03	80.68	77	10V
395	02	LAS	R 76.927	B	WENDEL ROAD	1,100	264	24.00	25	18	8	213	9.47	6.82	3.03	80.68	77	10V
395	02	LAS	R 76.927	A	WENDEL ROAD	1,000	265	26.50	27	16	7	215	10.19	6.04	2.64	81.13	78	10V
395	02	LAS	108.455	O	RAVENDALE	1,200	285	23.75	18	23	12	232	6.32	8.07	4.21	81.40	85	10V
395	02	LAS	138.979	O	LASSEN/MODOC COUNTY LINE	910	335	36.81	26	24	15	270	7.76	7.16	4.48	80.60	98	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
395	02	MOD	0.055	O	LASSEN/MODOC COUNTY LINE	910	335	36.81	26	24	15	270	7.76	7.16	4.48	80.60	98	10V
395	02	MOD	3.216	B	LIKELY, JESS VALLEY ROAD	980	270	27.55	38	18	9	205	14.03	6.75	3.38	75.84	75	10E
395	02	MOD	3.216	A	LIKELY, JESS VALLEY ROAD	1,200	288	24.03	17	6	28	236	6.04	2.25	9.88	81.83	87	10V
395	02	MOD	R 20.975	B	GLENN STREET	1,250	284	22.69	31	21	12	220	10.85	7.54	4.10	77.50	81	10E
395	02	MOD	R 20.975	A	GLENN STREET	1,950	293	15.00	64	19	12	198	21.96	6.39	4.19	67.47	74	10E
395	02	MOD	22.07	A	ALTURAS, FIRST STREET	7,000	306	4.37	67	20	13	206	22.02	6.58	4.12	67.28	77	10E
395	02	MOD	22.764	B	ALTURAS, JCT. RTE. 299 WEST	6,900	609	8.83	104	56	32	417	17.08	9.20	5.25	68.47	157	10E
395	02	MOD	22.764	A	ALTURAS, JCT. RTE. 299 WEST	4,800	341	7.10	59	40	19	223	17.36	11.75	5.51	65.38	85	10E
395	02	MOD	23.04	B	ALTURAS STATE HIGHWAY MAINTENANCE STATION	2,950	241	8.18	43	34	14	150	17.65	14.30	5.76	62.29	58	10E
395	02	MOD	28.285	B	JCT. RTE. 299 EAST	1,800	186	10.36	24	14	5	143	12.79	7.58	2.92	76.71	52	10E
395	02	MOD	28.285	A	JCT. RTE. 299 EAST	910	107	11.72	25	14	5	63	23.39	13.11	4.84	58.66	25	10E
395	02	MOD	61.563	B	OREGON STATE LINE	910	103	11.32	18	12	5	69	17.28	11.34	4.43	66.91	26	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
405	12	ORA	0.23	A	IRVINE, JCT. RTE. 5	192,000	9,600	5.00	4,426	1,152	421	3,600	46.10	12.00	4.39	37.50	1,565	82E
405	12	ORA	1.804	B	IRVINE, JCT. RTE. 133, LAGUNA FREEWAY	215,000	10,535	4.90	4,941	906	600	4,088	46.90	8.60	5.70	38.80	1,755	82E
405	12	ORA	1.804	A	IRVINE, JCT. RTE. 133, LAGUNA FREEWAY	248,000	12,896	5.20	6,422	1,199	683	4,591	49.80	9.30	5.30	35.60	2,019	82E
405	12	ORA	3.947	A	UNIVERSITY DRIVE	253,000	14,168	5.60	7,495	1,275	708	4,690	52.90	9.00	5.00	33.10	2,102	82V
405	12	ORA	7.803	B	IRVINE, MAC ARTHUR BOULEVARD	295,000	14,750	5.00	8,231	1,210	693	4,617	55.80	8.20	4.70	31.30	2,094	82E
405	12	ORA	7.803	A	IRVINE, MAC ARTHUR BOULEVARD	301,000	10,505	3.49	5,195	669	254	4,387	49.45	6.37	2.42	41.76	1,794	08E
405	12	ORA	8.74	A	COSTA MESA, JCT. RTE. 55, COSTA MESA FREEWAY	255,000	8,900	3.49	4,401	567	215	3,717	49.45	6.37	2.42	41.76	1,520	08E
405	12	ORA	16.544	B	HUNTINGTON BEACH, JCT. RTE. 39	271,000	9,458	3.49	4,677	602	229	3,950	49.45	6.37	2.42	41.76	1,615	08E
405	12	ORA	16.544	A	HUNTINGTON BEACH, JCT. RTE. 39	271,000	9,458	3.49	4,677	602	229	3,950	49.45	6.37	2.42	41.76	1,615	08E
405	12	ORA	20.751	B	JCT. RTE. 22 EAST, GARDEN GROVE FREEWAY	257,000	8,969	3.49	4,435	571	217	3,745	49.45	6.37	2.42	41.76	1,532	08V
405	12	ORA	20.751	A	JCT. RTE. 22 EAST, GARDEN GROVE FREEWAY	383,000	11,490	3.00	5,876	800	313	4,501	51.14	6.96	2.72	39.17	1,878	03E
405	12	ORA	24.044	B	SEAL BEACH, JCT. RTE. 605	374,000	11,220	3.00	5,738	781	305	4,395	51.14	6.96	2.72	39.17	1,834	03E
405	12	ORA	24.044	A	SEAL BEACH, JCT. RTE. 605	252,000	11,214	4.45	4,772	842	265	5,336	42.55	7.51	2.36	47.58	2,124	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
405	07	LA	3.324	A	LONG BEACH, LAKEWOOD BOULEVARD INTERCHANGE	291,000	12,950	4.45	5,510	973	306	6,162	42.55	7.51	2.36	47.58	2,453	10E
405	07	LA	7.596	B	LONG BEACH, JCT. RTE. 710, LONG BEACH FREEWAY INTERCHANGE	281,000	12,505	4.45	5,321	939	295	5,950	42.55	7.51	2.36	47.58	2,369	10E
405	07	LA	7.596	A	LONG BEACH, JCT. RTE. 710, LONG BEACH FREEWAY INTERCHANGE	279,000	12,555	4.50	5,922	1,031	491	5,111	47.17	8.21	3.91	40.71	2,138	10E
405	07	LA	12.97	B	CARSON, JCT. RTE. 110, HARBOR FREEWAY INTERCHANGE	261,000	11,745	4.50	5,540	964	459	4,781	47.17	8.21	3.91	40.71	2,000	10E
405	07	LA	12.97	A	CARSON, JCT. RTE. 110, HARBOR FREEWAY INTERCHANGE	258,000	9,572	3.71	4,791	732	361	3,687	50.05	7.65	3.77	38.52	1,560	10E
405	07	LA	17.589	B	LAWNDALE, HAWTHORNE BOULEVARD INTERCHANGE	247,000	9,164	3.71	4,587	701	345	3,530	50.05	7.65	3.77	38.52	1,494	10E
405	07	LA	R 21.175	B	LOS ANGELES, JCT. RTE 105, GLENN ANDERSON FREEWAY INTERCHANGE	240,000	8,904	3.71	4,456	681	336	3,430	50.05	7.65	3.77	38.52	1,451	10E
405	07	LA	R 21.175	A	LOS ANGELES, JCT. RTE 105, GLENN ANDERSON FREEWAY INTERCHANGE	318,000	9,635	3.03	4,362	790	365	4,118	45.27	8.20	3.79	42.74	1,700	10E
405	07	LA	25.947	B	CULVER CITY, JCT. RTE. 90, MARINA FREEWAY/JEFFERSON BOULEVARD INTERCHANGE	313,000	9,484	3.03	4,293	778	359	4,053	45.27	8.20	3.79	42.74	1,673	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
405	07	LA	25.947	A	CULVER CITY, JCT. RTE. 90, MARINA FREEWAY/JEFFERSON BOULEVARD INTERCHANGE	299,000	9,030	3.02	4,801	823	297	3,109	53.17	9.11	3.29	34.43	1,360	10E
405	07	LA	27.964	B	CULVER CITY, JCT. RTE. 187, VENICE BOULEVARD INTERCHANGE	300,000	9,060	3.02	4,817	825	298	3,119	53.17	9.11	3.29	34.43	1,364	10E
405	07	LA	29.538	B	LOS ANGELES, JCT. RTE. 10, SANTA MONICA FREEWAY INTERCHANGE	301,000	9,090	3.02	4,833	828	299	3,130	53.17	9.11	3.29	34.43	1,369	10E
405	07	LA	29.538	A	LOS ANGELES, JCT. RTE. 10, SANTA MONICA FREEWAY INTERCHANGE	280,000	9,744	3.48	4,862	1,197	286	3,400	49.90	12.28	2.94	34.89	1,495	10E
405	07	LA	30.856	A	LOS ANGELES, JCT. RTE. 2, SANTA MONICA BOULEVARD INTERCHANGE	287,000	9,988	3.48	4,984	1,227	294	3,485	49.90	12.28	2.94	34.89	1,533	10E
405	07	LA	39.432	B	LOS ANGELES, JCT. RTE. 101, VENTURA FREEWAY INTERCHANGE	284,000	9,883	3.48	4,932	1,214	291	3,448	49.90	12.28	2.94	34.89	1,517	10E
405	07	LA	39.432	A	LOS ANGELES, JCT. RTE. 101, VENTURA FREEWAY INTERCHANGE	217,000	7,053	3.25	3,197	813	237	2,806	45.33	11.53	3.36	39.79	1,190	10E
405	07	LA	42.9	A	N/O SHERMAN WAY; SATICOY ST	219,000	6,723	3.07	3,048	775	226	2,675	45.33	11.53	3.36	39.79	1,134	10V
405	07	LA	46.85	B	LOS ANGELES, JCT. RTE. 118, SIMI VALLEY FREEWAY INTERCHANGE	217,000	6,380	2.94	2,892	736	214	2,539	45.33	11.53	3.36	39.79	1,076	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
405	07	LA	46.85	A	LOS ANGELES, JCT. RTE. 118, SIMI VALLEY FREEWAY INTERCHANGE	145,000	5,829	4.02	2,680	639	241	2,269	45.98	10.97	4.13	38.92	971	10E
405	07	LA	47.754	B	LOS ANGELES, RINALDI STREET INTERCHANGE	137,000	5,507	4.02	2,532	604	227	2,143	45.98	10.97	4.13	38.92	917	10V
405	07	LA	48.643	B	LOS ANGELES, JCT. RTE. 5, GOLDEN STATE FREEWAY INTERCHANGE	137,000	5,507	4.02	2,532	604	227	2,143	45.98	10.97	4.13	38.92	917	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
505	04	SOL	R 0	A	VACAVILLE, JCT. RTE. 80	34,500	3,433	9.95	280	176	74	2,903	8.17	5.14	2.15	84.55	1,038	05E
505	04	SOL	R 10.626	B	SOLANO/YOLO COUNTY LINE	22,200	2,209	9.95	180	114	47	1,868	8.17	5.14	2.15	84.55	668	05E
505	03	YOL	0.396	B	JCT. RTE. 128 WEST	22,200	2,209	9.95	180	114	47	1,868	8.17	5.14	2.15	84.55	668	05E
505	03	YOL	0.396	A	JCT. RTE. 128 WEST	18,000	1,791	9.95	146	92	39	1,514	8.17	5.14	2.15	84.55	542	05E
505	03	YOL	10.623	B	JCT. RTE. 16	17,500	1,741	9.95	142	89	37	1,472	8.17	5.14	2.15	84.55	526	05E
505	03	YOL	10.623	A	JCT. RTE. 16	10,700	1,360	12.71	323	109	75	853	23.74	8.01	5.54	62.71	327	07E
505	03	YOL	R 22.356	B	JCT. RTE. 5	10,800	1,373	12.71	326	110	76	861	23.74	8.01	5.54	62.71	330	07V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
580	10	SJ	0	A	JCT. RTE. 5	21,000	3,381	16.10	850	113	53	2,365	25.13	3.34	1.56	69.96	864	06E
580	10	SJ	4.344	A	JCT. RTE. 132 EAST	30,000	5,331	17.77	1,338	184	84	3,725	25.10	3.45	1.58	69.87	1,361	07V
580	04	ALA	0.39	A	JCT. RTE. 205 EAST	153,000	19,125	12.50	2,352	516	402	15,855	12.30	2.70	2.10	82.90	5,659	96E
580	04	ALA	R 8.265	B	LIVERMORE, GREENVILLE ROAD	138,000	14,352	10.40	1,851	215	172	12,113	12.90	1.50	1.20	84.40	4,289	96E
580	04	ALA	R 8.265	A	LIVERMORE, GREENVILLE ROAD	137,000	11,412	8.33	2,205	580	301	8,327	19.32	5.08	2.64	72.97	3,048	07V
580	04	ALA	10.689	B	FIRST STREET	167,000	7,599	4.55	1,563	462	321	5,252	20.57	6.08	4.23	69.12	1,956	08V
580	04	ALA	10.689	A	FIRST STREET	160,000	19,520	12.20	3,572	605	410	14,933	18.30	3.10	2.10	76.50	5,393	96E
580	04	ALA	20.726	B	PLEASANTON, JCT. RTE. 680	177,000	11,983	6.77	2,971	802	473	7,739	24.79	6.69	3.95	64.58	2,917	00V
580	04	ALA	20.726	A	PLEASANTON, JCT. RTE. 680	174,000	15,991	9.19	3,945	1,292	531	10,225	24.67	8.08	3.32	63.94	3,863	00E
580	04	ALA	R 30.807	B	JCT. RTE. 238	166,000	9,545	5.75	2,255	468	274	6,547	23.63	4.90	2.87	68.59	2,421	05V
580	04	ALA	R 30.807	A	JCT. RTE. 238	137,000	8,453	6.17	2,206	558	274	5,415	26.10	6.60	3.24	64.06	2,037	05V
580	04	ALA	R 39.24	B	OAKLAND, JCT. RTE. 13 NORTH	163,000	831	0.51	782	25	0	23	94.15	3.05	0.00	2.80	38	00V
580	04	ALA	R 39.24	A	OAKLAND, JCT. RTE. 13 NORTH	140,000	1,540	1.10	1,277	89	3	171	82.90	5.80	0.20	11.10	112	96E
580	04	ALA	R 40.078	B	OAKLAND, HIGH STREET	133,000	559	0.42	519	6	8	26	92.90	0.99	1.49	4.62	29	05V
580	04	ALA	R 40.078	A	OAKLAND, HIGH STREET	147,000	588	0.40	545	7	8	28	92.61	1.26	1.42	4.72	31	05V
580	04	ALA	44.279	B	OAKLAND, OAKLAND AVENUE	184,000	1,067	0.58	891	82	16	78	83.52	7.69	1.52	7.27	68	05V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
580	04	ALA	44.279	A	OAKLAND, OAKLAND AVENUE	176,000	1,214	0.69	924	89	19	182	76.15	7.31	1.56	14.98	106	05V
580	04	ALA	45.151	A	OAKLAND, JCT. RTES. 24/980	222,000	2,464	1.11	1,595	304	37	527	64.74	12.34	1.52	21.39	271	05V
580	04	ALA	46.01	A	OAKLAND, JCT. RTE. 123	222,000	3,330	1.50	2,221	323	80	706	66.70	9.71	2.39	21.20	363	00V
580	04	ALA	46.46	B	OAKLAND, JCT. RTES. 80/880	222,000	2,664	1.20	1,852	220	58	535	69.51	8.25	2.17	20.07	278	00V
580	04	ALA	R 47.35	A	ALBANY, NORTH JCT. RTE. 80	87,000	5,342	6.14	1,871	621	173	2,677	35.02	11.63	3.24	50.11	1,072	05V
580	04	MRN	4.782	B	JCT. RTE. 101	50,000	3,450	6.90	1,542	428	193	1,287	44.70	12.40	5.60	37.30	566	96E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
605	12	ORA	3.092	A	SEAL BEACH, JCT RTE 22 BEGIN FREWAY	44,500	1,335	3.00	668	199	72	396	50.00	14.90	5.40	29.70	189	80E
605	12	ORA	R 0	A	JCT. RTE. 405	169,000	7,825	4.63	4,496	712	382	2,235	57.46	9.10	4.88	28.56	1,050	04E
605	07	LA	R 0	A	ORANGE/LOS ANGELES COUNTY LINE	178,000	8,793	4.94	5,360	738	392	2,303	60.96	8.39	4.46	26.19	1,108	10E
605	07	LA	R 1.74	A	LAKEWOOD, CARSON STREET INTERCHANGE	211,000	10,423	4.94	6,354	874	465	2,730	60.96	8.39	4.46	26.19	1,313	10E
605	07	LA	R 2.866	A	CERRITOS, DEL AMO BOULEVARD INTERCHANGE	223,000	11,016	4.94	6,715	924	491	2,885	60.96	8.39	4.46	26.19	1,388	10E
605	07	LA	R 5.046	B	CERRITOS, JCT. RTE. 91, ARTESIA FREEWAY INTERCHANGE	240,000	11,856	4.94	7,227	995	529	3,105	60.96	8.39	4.46	26.19	1,493	10E
605	07	LA	R 5.046	A	CERRITOS, JCT. RTE. 91, ARTESIA FREEWAY INTERCHANGE	301,000	16,916	5.62	8,744	1,818	787	5,567	51.69	10.75	4.65	32.91	2,510	10E
605	07	LA	R 7.653	B	NORWALK, JCT. RTE. 105, GLENN ANDERSON FREEWAY INTERCHANGE	302,000	16,972	5.62	8,773	1,824	789	5,585	51.69	10.75	4.65	32.91	2,518	10E
605	07	LA	R 7.653	A	NORWALK, JCT. RTE. 105, GLENN ANDERSON FREEWAY INTERCHANGE	299,000	23,561	7.88	9,759	1,868	982	10,951	41.42	7.93	4.17	46.48	4,436	10E
605	07	LA	R 9.612	A	SANTA FE SPRINGS, JCT. RTE. 5, SANTA ANA FREEWAY INTERCHANGE	263,000	28,588	10.87	10,981	2,719	1,401	13,488	38.41	9.51	4.90	47.18	5,494	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
605	07	LA	R 13.569	B	WHITTIER, JCT. RTE. 72, WHITTIER BOULEVARD INTERCHANGE	248,000	26,958	10.87	10,355	2,564	1,321	12,719	38.41	9.51	4.90	47.18	5,181	10E
605	07	LA	R 13.569	A	WHITTIER, JCT. RTE. 72, WHITTIER BOULEVARD INTERCHANGE	248,000	26,958	10.87	10,355	2,564	1,321	12,719	38.41	9.51	4.90	47.18	5,181	10E
605	07	LA	R 17.407	B	INDUSTRY, JCT. RTE. 60, POMONA FREEWAY INTERCHANGE	240,000	26,088	10.87	10,020	2,481	1,278	12,308	38.41	9.51	4.90	47.18	5,013	10E
605	07	LA	R 17.407	A	INDUSTRY, JCT. RTE. 60, POMONA FREEWAY INTERCHANGE	225,000	21,375	9.50	8,777	2,272	1,050	9,279	41.06	10.63	4.91	43.41	3,872	10E
605	07	LA	R 20.189	B	BALDWIN PARK, JCT. RTE. 10, SAN BERNARDINO FREEWAY INTERCHANGE	221,000	20,995	9.50	8,621	2,232	1,031	9,114	41.06	10.63	4.91	43.41	3,803	10E
605	07	LA	20.189	A	BALDWIN PARK, JCT. RTE. 10, SAN BERNARDINO FREEWAY INTERCHANGE	185,000	12,710	6.87	5,404	1,811	751	4,743	42.52	14.25	5.91	37.32	2,102	10E
605	07	LA	22.681	O	SAN GABRIEL RIVER BRIDGE	159,000	10,923	6.87	4,644	1,557	646	4,076	42.52	14.25	5.91	37.32	1,807	10E
605	07	LA	25.76	B	IRWINDALE, JCT. RTE. 210, FOOTHILL FREEWAY INTERCHANGE	149,000	10,236	6.87	4,352	1,459	605	3,820	42.52	14.25	5.91	37.32	1,693	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
680	04	SCL	M 0	A	SAN JOSE, JCT. RTES. 101/280	158,000	3,002	1.90	1,222	381	117	1,282	40.70	12.70	3.90	42.70	537	94E
680	04	SCL	M .385	B	SAN JOSE, KING ROAD	158,000	4,424	2.80	1,929	438	372	1,686	43.60	9.90	8.40	38.10	744	94E
680	04	SCL	M .385	A	SAN JOSE, KING ROAD	218,000	9,592	4.40	3,396	1,180	537	4,479	35.40	12.30	5.60	46.70	1,852	94V
680	04	SCL	M 1.74	B	SAN JOSE, JCT. RTE. 130	166,000	7,304	4.40	2,702	687	314	3,601	37.00	9.40	4.30	49.30	1,446	94V
680	04	SCL	M 1.74	A	SAN JOSE, JCT. RTE. 130	183,000	8,235	4.50	2,940	815	305	4,175	35.70	9.90	3.70	50.70	1,663	94V
680	04	SCL	M 5.068	B	SAN JOSE, CAPITOL AVENUE	145,000	7,830	5.40	2,654	861	493	3,821	33.90	11.00	6.30	48.80	1,563	94V
680	04	SCL	M 5.068	A	SAN JOSE, CAPITOL AVENUE	147,000	7,938	5.40	2,580	945	492	3,921	32.50	11.90	6.20	49.40	1,602	94V
680	04	SCL	M 7.647	B	MILPITAS, JCT. RTE. 237 WEST	137,000	6,302	4.60	2,174	460	214	3,453	34.50	7.30	3.40	54.80	1,341	94V
680	04	SCL	M 7.647	A	MILPITAS, JCT. RTE. 237 WEST	128,000	5,248	4.10	1,706	310	257	2,976	32.50	5.90	4.90	56.70	1,153	94V
680	04	ALA	M 2.382	B	FREMONT, JCT. RTE. 262 WEST	120,000	8,520	7.10	2,249	579	162	5,529	26.40	6.80	1.90	64.90	2,063	94V
680	04	ALA	M 2.382	A	FREMONT, JCT. RTE. 262 WEST	138,000	12,420	9.00	3,254	981	435	7,750	26.20	7.90	3.50	62.40	2,942	94V
680	04	ALA	R 6.396	B	FREMONT, JCT. RTE. 238 NORTH	140,000	10,360	7.40	2,714	756	186	6,703	26.20	7.30	1.80	64.70	2,504	94V
680	04	ALA	R 6.396	A	FREMONT, JCT. RTE. 238 NORTH	140,000	8,218	5.87	2,423	487	271	5,037	29.49	5.92	3.30	61.29	1,907	00V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
680	04	ALA	R 11.042	B	JCT. RTE. 84 WEST	139,000	10,564	7.60	3,064	909	518	6,074	29.00	8.60	4.90	57.50	2,363	94V
680	04	ALA	R 11.042	A	JCT. RTE. 84 WEST	140,000	11,200	8.00	3,226	1,086	952	5,936	28.80	9.70	8.50	53.00	2,401	94V
680	04	ALA	R 11.845	A	JCT. RTE. 84 EAST	116,000	10,672	9.20	3,074	1,035	907	5,656	28.80	9.70	8.50	53.00	2,287	94V
680	04	ALA	R 20.057	B	PLEASANTON, JCT. RTE. 580	144,000	9,360	6.50	3,033	440	281	5,607	32.40	4.70	3.00	59.90	2,122	94V
680	04	ALA	R 20.057	A	PLEASANTON, JCT. RTE. 580	163,000	12,388	7.60	3,927	1,226	211	7,024	31.70	9.90	1.70	56.70	2,705	94V
680	04	CC	R .01	A	SAN RAMON, ALCOSTA BOULEVARD	155,000	8,215	5.30	3,872	798	448	3,097	47.13	9.71	5.45	37.70	1,343	00V
680	04	CC	14.383	B	WALNUT CREEK, JCT. RTE. 24 WEST	150,000	9,570	6.38	4,420	826	464	3,859	46.19	8.63	4.85	40.32	1,630	00V
680	04	CC	14.383	A	WALNUT CREEK, JCT. RTE. 24 WEST	233,000	9,600	4.12	4,589	1,125	380	3,506	47.80	11.72	3.96	36.52	1,530	00V
680	04	CC	15.606	B	WALNUT CREEK, NORTH MAIN STREET	233,000	8,877	3.81	4,592	953	443	2,889	51.73	10.73	4.99	32.55	1,310	00V
680	04	CC	15.606	A	WALNUT CREEK, NORTH MAIN STREET	255,000	6,758	2.65	3,331	615	342	2,470	49.29	9.10	5.06	36.55	1,076	03V
680	04	CC	R 18.707	B	CONCORD, JCT. RTE. 242 NORTH	227,000	8,785	3.87	4,429	886	369	3,102	50.41	10.08	4.20	35.31	1,361	00V
680	04	CC	R 18.707	A	CONCORD, JCT. RTE. 242 NORTH	135,000	6,669	4.94	3,489	658	255	2,266	52.31	9.87	3.83	33.98	1,002	00V
680	04	CC	21.191	B	JCT. RTE. 4	127,000	3,429	2.70	1,778	511	121	1,019	51.84	14.91	3.53	29.73	479	00V
680	04	CC	21.191	A	JCT. RTE. 4	118,000	8,036	6.81	4,167	927	243	2,698	51.86	11.54	3.03	33.57	1,198	00V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
680	04	SOL	0.679	B	JCT. RTE. 780 NORTHWEST	102,000	5,814	5.70	1,128	814	215	3,657	19.40	14.00	3.70	62.90	1,408	95E
680	04	SOL	0.679	A	JCT. RTE. 780 NORTHWEST	56,000	2,968	5.30	1,097	188	192	1,491	36.95	6.35	6.46	50.24	598	03V
680	04	SOL	R 2.819	B	LAKE HERMAN ROAD	63,000	3,358	5.33	1,121	242	138	1,857	33.38	7.22	4.10	55.31	722	00V
680	04	SOL	R 2.819	A	LAKE HERMAN ROAD	63,000	3,377	5.36	1,213	290	123	1,751	35.93	8.60	3.64	51.84	691	00V
680	04	SOL	13.126	B	CORDELIA WYE, JCT. RTE. 80	62,000	3,230	5.21	1,134	282	266	1,548	35.10	8.72	8.25	47.93	639	00V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
710	07	LA	4.96	A	LONG BEACH, BEGIN ROUTE 710, LONG BEACH FREEWAY	57,000	15,059	26.42	916	3,671	81	10,392	6.08	24.38	0.54	69.01	3,967	10E
710	07	LA	6.881	B	LONG BEACH, JCT. RTE. 1, PACIFIC COAST HIGHWAY INTERCHANGE	130,000	17,953	13.81	2,196	4,316	298	11,143	12.23	24.04	1.66	62.07	4,362	10E
710	07	LA	6.881	A	LONG BEACH, JCT. RTE. 1, PACIFIC COAST HIGHWAY INTERCHANGE	150,000	20,715	13.81	2,533	4,980	344	12,858	12.23	24.04	1.66	62.07	5,033	10V
710	07	LA	9.41	B	LONG BEACH, JCT. RTE. 405, SAN DIEGO FREEWAY INTERCHANGE	165,000	21,236	12.87	2,597	5,105	353	13,181	12.23	24.04	1.66	62.07	5,160	10E
710	07	LA	9.41	A	LONG BEACH, JCT. RTE. 405, SAN DIEGO FREEWAY INTERCHANGE	179,000	25,508	14.25	5,221	3,413	365	16,509	20.47	13.38	1.43	64.72	6,246	10E
710	07	LA	10.823	A	LONG BEACH, DEL AMO BOULEVARD INTERCHANGE	183,000	26,041	14.23	5,331	3,484	372	16,854	20.47	13.38	1.43	64.72	6,376	10E
710	07	LA	12.97	B	LONG BEACH, JCT. RTE. 91, ARTESIA FREEWAY INTERCHANGE	191,000	26,549	13.90	5,435	3,552	380	17,183	20.47	13.38	1.43	64.72	6,501	10E
710	07	LA	12.97	A	LONG BEACH, JCT. RTE. 91, ARTESIA FREEWAY INTERCHANGE	214,000	18,832	8.80	5,384	2,582	584	10,284	28.59	13.71	3.10	54.61	4,060	10E
710	07	LA	R 15.692	B	LYNWOOD, JCT. RTE. 105, GLENN ANDERSON FREEWAY INTERCHANGE	219,000	19,031	8.69	5,441	2,609	590	10,393	28.59	13.71	3.10	54.61	4,103	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
710	07	LA	R 15.692	A	LYNWOOD, JCT. RTE. 105, GLENN ANDERSON FREEWAY INTERCHANGE	229,000	18,893	8.25	6,369	2,857	561	9,108	33.71	15.12	2.97	48.21	3,710	10E
710	07	LA	18.44	A	SOUTH GATE, FIRESTONE BOULEVARD INTERCHANGE	206,000	18,746	9.10	6,319	2,834	557	9,037	33.71	15.12	2.97	48.21	3,682	10V
710	07	LA	23.282	B	COMMERCE, JCT. RTE. 5, SANTA ANA FREEWAY INTERCHANGE	212,000	16,875	7.96	5,689	2,552	501	8,135	33.71	15.12	2.97	48.21	3,314	10E
710	07	LA	23.282	A	COMMERCE, JCT. RTE. 5, SANTA ANA FREEWAY INTERCHANGE	171,000	12,945	7.57	3,551	1,852	603	6,940	27.43	14.31	4.66	53.61	2,778	10E
710	07	LA	24.627	B	JCT. RTE. 60, POMONA FREEWAY INTERCHANGE	185,000	12,821	6.93	3,517	1,835	597	6,873	27.43	14.31	4.66	53.61	2,751	10E
710	07	LA	24.627	A	JCT. RTE. 60, POMONA FREEWAY INTERCHANGE	125,000	6,275	5.02	2,145	963	259	2,908	34.18	15.34	4.13	46.35	1,205	10V
710	07	LA	26.497	A	MONTEREY PARK, JCT. RTE. 10, SAN BERNARDINO FREEWAY INTERCHANGE	44,000	1,368	3.11	626	370	80	291	45.78	27.07	5.88	21.27	168	10E
710	07	LA	R 32.72	B	PASADENA, JCT. RTES. 134/210, VENTURA/FOOTHILL FREEWAYS INTERCHANGE	63,000	806	1.28	503	180	38	86	62.35	22.37	4.67	10.61	69	10E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
780	04	SOL	0.682	A	BENICIA, JCT. RTE. 680	54,000	2,797	5.18	1,361	287	58	1,091	48.66	10.26	2.08	39.00	459	01V
780	04	SOL	3.995	B	WEST BENICIA	54,000	2,371	4.39	1,130	213	90	937	47.68	8.99	3.80	39.53	396	04V
780	04	SOL	3.995	A	WEST BENICIA	57,000	2,747	4.82	1,425	274	71	977	51.89	9.97	2.60	35.55	423	01V
780	04	SOL	4.77	A	COLUMBUS PARKWAY	48,000	2,203	4.59	1,035	193	87	889	46.96	8.76	3.95	40.34	373	04V
780	04	SOL	7.44	B	LEMON STREET	26,000	1,050	4.04	624	78	44	303	59.45	7.46	4.23	28.86	140	04V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
805	11	SD	0.486	A	SAN DIEGO, JCT. RTE. 5	43,500	1,784	4.10	978	350	25	432	54.80	19.60	1.40	24.20	219	86E
805	11	SD	1.805	B	SAN DIEGO, JCT. RTE. 905	60,000	2,400	4.00	1,315	470	34	581	54.80	19.60	1.40	24.20	295	86V
805	11	SD	1.805	A	SAN DIEGO, JCT. RTE. 905	106,000	7,314	6.90	3,835	639	213	2,627	52.43	8.74	2.91	35.92	1,131	03E
805	11	SD	3.654	B	CHULA VISTA, AUTO PARKWAY DRIVE/MAIN STREET	143,000	10,010	7.00	5,248	875	291	3,596	52.43	8.74	2.91	35.92	1,548	03E
805	11	SD	3.654	A	CHULA VISTA, AUTO PARKWAY DRIVE/MAIN STREET	145,000	10,150	7.00	5,322	887	295	3,646	52.43	8.74	2.91	35.92	1,569	03E
805	11	SD	6.059	B	TELEGRAPH CANYON ROAD	150,000	10,980	7.32	5,586	973	284	4,137	50.87	8.86	2.59	37.68	1,754	04V
805	11	SD	8.854	B	JCT. RTE. 54, SWEETWATER ROAD	228,000	13,680	6.00	6,959	1,212	354	5,155	50.87	8.86	2.59	37.68	2,186	04V
805	11	SD	14.641	B	SAN DIEGO, JCT. RTE. 15	219,000	13,140	6.00	6,684	1,164	340	4,951	50.87	8.86	2.59	37.68	2,099	04E
805	11	SD	14.641	A	SAN DIEGO, JCT. RTE. 15	170,000	11,050	6.50	6,229	1,024	383	3,413	56.37	9.27	3.47	30.89	1,546	04E
805	11	SD	17.645	B	JCT. RTE. 8	192,000	12,480	6.50	7,035	1,157	433	3,855	56.37	9.27	3.47	30.89	1,746	04E
805	11	SD	17.645	A	JCT. RTE. 8	193,000	11,966	6.20	6,745	1,109	415	3,696	56.37	9.27	3.47	30.89	1,674	04E
805	11	SD	20.6	B	SAN DIEGO, JCT. RTE. 163	170,000	11,050	6.50	6,229	1,024	383	3,413	56.37	9.27	3.47	30.89	1,546	04E
805	11	SD	20.6	A	SAN DIEGO, JCT. RTE. 163	184,000	11,960	6.50	6,742	1,109	415	3,694	56.37	9.27	3.47	30.89	1,673	04E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
805	11	SD	23.651	B	JCT. RTE. 52	180,000	12,312	6.84	6,940	1,141	427	3,803	56.37	9.27	3.47	30.89	1,723	04V
805	11	SD	23.651	A	JCT. RTE. 52	196,000	10,858	5.54	5,966	1,003	350	3,540	54.95	9.24	3.22	32.60	1,574	07E
805	11	SD	28.502	B	JCT. RTE. 5	150,000	11,430	7.62	6,281	1,056	368	3,726	54.95	9.24	3.22	32.60	1,657	07V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
880	04	SCL	0	A	JCT. RTE. 280	157,000	4,443	2.83	2,530	682	223	1,008	56.95	15.34	5.02	22.69	532	00V
880	04	SCL	2.075	B	SAN JOSE, JCT. RTE. 82	155,000	4,588	2.96	2,660	672	153	1,103	57.98	14.64	3.33	24.05	558	00V
880	04	SCL	2.075	A	SAN JOSE, JCT. RTE. 82	156,000	4,961	3.18	2,907	793	155	1,106	58.59	15.98	3.12	22.30	579	00V
880	04	SCL	4.078	B	SAN JOSE, JCT. RTE. 101	160,000	6,704	4.19	3,652	960	140	1,952	54.47	14.32	2.09	29.12	910	00V
880	04	SCL	4.078	A	SAN JOSE, JCT. RTE. 101	176,000	7,568	4.30	3,481	1,370	250	2,467	46.00	18.10	3.30	32.60	1,136	96E
880	04	SCL	8.422	A	JCT. RTE. 237	200,000	11,400	5.70	5,027	2,109	513	3,751	44.10	18.50	4.50	32.90	1,739	96E
880	04	ALA	2.283	B	FREMONT, JCT. RTE. 262 EAST	189,000	8,316	4.40	3,667	832	299	3,518	44.10	10.00	3.60	42.30	1,463	96V
880	04	ALA	2.283	A	FREMONT, JCT. RTE. 262 EAST	174,000	8,352	4.80	4,001	902	535	2,915	47.90	10.80	6.40	34.90	1,307	96V
880	04	ALA	8.842	B	FREMONT, SOUTH JCT. RTE. 84	200,000	11,800	5.90	5,109	1,251	909	4,531	43.30	10.60	7.70	38.40	1,991	96E
880	04	ALA	8.842	A	FREMONT, SOUTH JCT. RTE. 84	200,000	13,200	6.60	5,333	2,072	1,056	4,739	40.40	15.70	8.00	35.90	2,167	96E
880	04	ALA	13.669	B	HAYWARD, WHIPPLE ROAD	197,000	10,835	5.50	3,929	1,098	545	5,263	36.26	10.13	5.03	48.57	2,134	00V
880	04	ALA	14.537	A	HAYWARD, INDUSTRIAL PARKWAY	208,000	12,272	5.90	4,909	1,546	749	5,068	40.00	12.60	6.10	41.30	2,173	96V
880	04	ALA	16.696	B	HAYWARD, JCT. RTE. 92	208,000	13,728	6.60	5,368	2,142	618	5,601	39.10	15.60	4.50	40.80	2,408	96E
880	04	ALA	16.696	A	HAYWARD, JCT. RTE. 92	235,000	16,450	7.00	6,498	2,517	806	6,629	39.50	15.30	4.90	40.30	2,864	96E
880	04	ALA	20.678	B	JCT. RTE. 238 EAST	217,000	18,445	8.50	7,157	3,154	830	7,304	38.80	17.10	4.50	39.60	3,183	96E
880	04	ALA	20.678	A	JCT. RTE. 238 EAST	212,000	17,808	8.40	3,615	3,259	712	10,222	20.30	18.30	4.00	57.40	4,058	96E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
880	04	ALA	23.644	B	RTE 112, DAVIS STREET	209,000	18,141	8.68	6,616	2,095	503	8,929	36.47	11.55	2.77	49.22	3,579	00V
880	04	ALA	23.644	A	RTE 112, DAVIS STREET	205,000	17,630	8.60	6,823	3,015	617	7,175	38.70	17.10	3.50	40.70	3,082	96E
880	04	ALA	25.497	A	OAKLAND, HEGENBERGER ROAD	202,000	15,433	7.64	5,369	1,539	531	7,993	34.79	9.97	3.44	51.79	3,165	02V
880	04	ALA	27.709	B	OAKLAND, JCT. RTE. 77	210,000	21,630	10.30	7,116	2,725	714	11,075	32.90	12.60	3.30	51.20	4,426	96E
880	04	ALA	27.709	A	OAKLAND, JCT. RTE. 77	211,000	20,256	9.60	6,360	2,573	790	10,533	31.40	12.70	3.90	52.00	4,209	96E
880	04	ALA	31.091	B	OAK/MADISON STREETS	216,000	23,112	10.70	7,350	3,005	832	11,926	31.80	13.00	3.60	51.60	4,770	96E

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
905	11	SD	3.19	A	SAN DIEGO, JCT. RTE. 5	18,800	1,504	8.00	779	235	47	444	51.80	15.60	3.10	29.50	209	87E
905	11	SD	3.818	B	SAN DIEGO, BEYER BOULEVARD	48,500	3,929	8.10	2,035	613	122	1,159	51.80	15.60	3.10	29.50	545	87E
905	11	SD	5.164	B	JCT. RTE. 805	54,000	4,374	8.10	2,266	682	136	1,290	51.80	15.60	3.10	29.50	607	87E
905	11	SD	T 6.434	B	SAN DIEGO, OTAY MESA ROAD	56,000	3,629	6.48	622	487	31	2,488	17.14	13.43	0.86	68.57	929	04E
905	11	SD	11.595	A	SIEMPRE VIVA ROAD	27,500	1,815	6.60	250	157	16	1,392	13.77	8.65	0.88	76.71	506	10V

RTE	DIST	CNTY	POST MILE	LEG	DESCRIPTION	VEHICLE AADT TOTAL	TRUCK AADT TOTAL	TRUCK % TOT VEH	TRUCK AADT TOTAL ---- By Axle ---- 2	3	4	5+	% TRUCK AADT ---- By Axle ---- 2	3	4	5+	EAL 2-WAY (1000)	YEAR VER/ EST
980	04	ALA	0.009	A	OAKLAND, JCT. RTE. 880	76,000	5,343	7.03	2,298	603	212	2,230	43.01	11.29	3.97	41.73	936	00V
980	04	ALA	0.702	A	OAKLAND, FOURTEENTH STREET	62,000	4,030	6.50	2,366	641	214	810	58.70	15.90	5.30	20.10	453	94E
980	04	ALA	2.036	B	OAKLAND, JCT. RTE. 580	115,000	3,324	2.89	2,044	551	119	610	61.49	16.58	3.57	18.35	350	00V