DIST.	COUNTY	ROUTE	MILE POST TOTAL PROJECT	SHEET NO.	TOTAL SHEETS

REGISTERED ENGINEER - CIVIL

PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER — No. Exp. CIVIL — STATE OF CALIFORNIA

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.



PLAN
1"=10'



STRUCTURE APPROACH - END STAGGER DETAIL
No Scale



DETAIL A
No Scale

APPROACH SLAB TRANSVERSE CONTACT JOINT		
STRUCTURE SKEW	AC APPROACH PAVEMENT	PCC APPROACH PAVEMENT
< 20°	Parallel to face of paving notch	Parallel to face of paving notch
20°- 45°	Parallel to face of P N use (Detail A)	Stagger lines 24' to 36' apart
> 45°	Parallel to face of P N use (Detail A)	Stagger at each lane line



MR > 2"



MR ≤ 2"

SEAT TYPE ABUTMENT
SECTION A-A
¾"=1'-0"

Note: Seat Type Abutment shown,for Diaphragm Type Abutment,see "Abutment Tie Details".



EDGE ANGLE DETAIL
½"=1'-0"



9" PAVING NOTCH



12" PAVING NOTCH



***(TO BE USED WITH TYPE 25 OR TYPE 27 CONCRETE BARRIER)**



***(TO BE USED WITH TYPE 732 OR TYPE 736 CONCRETE BARRIER)**

DETAIL B
1½"=1'-0"

DIAPHRAGM TYPE ABUTMENT
ABUTMENT TIE DETAILS
¾"=1'-0"



SECTION C-C
¾"=1'-0"

NOTES:

1. For details not noted or shown, see Structure Plans. Adjust bar reinforcement to clear a sawcut for sealed joint,when required.
2. For transverse contact joint with new PCC paving, refer to Standard Plan P10.
3. Longitudinal construction joints,when permitted by the Engineer,shall be located on lane lines.
4. End angle or plate at beginning of barrier transition, end of wing wall or end of structure approach as applicable.
5. At the contractor's option,approach slab transverse reinforcement may be placed parallel to paving notch. Spacing of transverse reinforcement is measured along ℄ roadway.
6. For drainage details,see Structure Plans.

STANDARD DRAWING

RELEASE DATE 3/14/05	DESIGN BY M.TRAFFALIS	CHECKED E.THORKILDSEN	RELEASED BY
FILE NO. xs3-150e	DETAILS BY R.YEE	CHECKED E.THORKILDSEN	OFFICE CHIEF
	SUBMITTED BY M.HA	DRAWING DATE 8/92	

STATE OF CALIFORNIA
DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

BRIDGE NO.

MILE POST

STRUCTURE APPROACH TYPE EQ(10)

DS OSD 2147A (ENGLISH) (REV. X/XX/XX)

ORIGINAL SCALE IN INCHES FOR REDUCED PLANS 0 1 2 3

CU
EA

DISREGARD PRINTS BEARING EARLIER REVISION DATES →

REVISION DATES (PRELIMINARY STAGE ONLY)

SHEET OF

DATE PLOTTED => 15-AUG-2008 TIME PLOTTED => 07:58

USERNAME => rwu

xs3-150e.dgn