

## PROJECT TITLE

[Median, Ramp & Connector Improvement]

Insert Location Map Below:



Project EA: 24670K

PPNO: 3550

Project Location: Downtown Los Angeles

Co/Rte/KP/PM:LA/110/KP35.4-37./PM22.0/23.2

Project Description: Median, Ramp & Connector Improvement

Project Scope: Surface improvements to concrete median barrier, asphalt median island, and connectors and exit ramps

Existing Funding: IIP: \$ 1,291,000  
RIP: \$0  
Other: \$0

Future Funding Need: \$ 0

Total Estimated Cost: \$ 1,291,000

Project Schedule: RTL 02/2006

## PROJECT INFORMATION

**Background:** In District 7, on Route 110 in the city of Los Angeles from Ninth Street to Third Street (KP 35.4/37.3; PM 22.0/23.2). This proposal to rejuvenate the freeway alongside the financial district in downtown Los Angeles consists of surface improvements to the concrete median barrier, an asphalt median island, and connectors and exit ramps.

**Project Need:** The median barrier is a conglomeration of several heights of barrier installed at different times, already shaded various colors from aging and grime. The median island near 4<sup>th</sup> Street has an asphaltic slurry covering that is patched and cracked. Long connectors and exit ramps may be confusing to new or infrequent users unfamiliar with the downtown area.

**Project Purpose:** This project will include sandblasting of the concrete median barrier to achieve uniform color. Pavers will be installed on the median island to improve its appearance. Colored, rubberized asphalt will be placed on the exit ramps and connectors to develop a color keyed navigation system.